Ross Draw Unit #055 - WPX Energy			Analytical Results - Envirotech Inc.						
Excavation Footprint/Sidewalls		Reported in mg/kg							
NM OCD Table 1 Thresholds (GW <50')		600	10	50		10	00		
Sample ID	Depth (ft)	Sampling Date	Chloride	Benzene	BTEX	GRO	DRO	ORO	Total TPH
SP1	3	7/24/2019	98.8	ND	ND	ND	53.8	ND	53.8
SP2	3	7/24/2019	333	ND	ND	ND	182	94.3	276.3
-	3.5	8/22/2019	-	-	-	-	ND	ND	ND
SP3	3	7/24/2019	183	ND	ND	ND	264	119.0	383
	3.5	8/22/2019	-	-	-	-	ND	ND	ND
SP4	3	7/24/2019	186	ND	ND	ND	127	87.5	214.5
-	3.5	8/22/2019	-	-	-	-	ND	ND	ND
SP5	3	7/24/2019	ND	ND	ND	ND	ND	ND	ND
SP6	3	7/24/2019	1010	ND	ND	ND	ND	ND	ND
-	3.5	8/22/2019	2630	-	-	-	-	-	-
-	4.0	9/10/2019	215	-	-	-	-	-	-
SP7	3	7/24/2019	761	ND	ND	ND	36.2	ND	36.2
-	3.5	8/22/2019	290	-	-	-	-	-	-
SP8	3	7/24/2019	498	ND	ND	ND	89.0	ND	89.0
SP9	3	7/24/2019	273	ND	ND	ND	ND	ND	ND
SP10	3	7/24/2019	68.1	ND	ND	ND	ND	ND	ND
SP11	3	7/24/2019	114	ND	ND	ND	68.0	ND	68.0
SP12	3	7/24/2019	43	ND	ND	ND	ND	ND	ND
SP13	3	7/24/2019	54.9	ND	ND	ND	139	62.7	201.7
-	3.5	8/22/2019	-	-	-	-	ND	ND	ND
SP14	3	7/24/2019	98.2	ND	ND	ND	76.2	ND	76.2
SP15	3	7/24/2019	62.2	ND	ND	ND	81.9	ND	81.9
SP16	3	7/24/2019	1070	ND	ND	ND	ND	ND	ND
-	3.5	8/22/2019	168	-	-	-	-	-	-
SP17	3	7/24/2019	59.6	ND	ND	ND	110	ND	110
-	3.5	8/22/2019	-	-	-		ND	ND	ND
SP18	3	7/24/2019	43.8	ND	ND	ND	130	50.6	180.6
-	3.5	8/22/2019	-	-	-	-	ND	ND	ND
SP19	3	7/24/2019	307	ND	ND	ND	46.1	ND	46.1
SP20	3	7/24/2019	56.7	ND	ND	ND	81.5	ND	81.5
SP21	3	7/24/2019	126	ND	ND	ND	61.6	ND	61.6
SP22	3	7/24/2019	25.8	ND	ND	ND	51.0	ND	51.0
SP23	3	7/24/2019	303	ND	ND	ND	39.6	ND	39.6

SP24		nolds (GW Sampling Date 7/24/2019 8/22/2019	600 Chloride 674	10 Benzene	50		10	Repo.	rted in mg/kg
Sample ID SP24 -	epth (ft) 3 3.5	Sampling Date 7/24/2019 8/22/2019	Chloride 674				10	00	
SP24	(ft) 3 3.5 3	Date 7/24/2019 8/22/2019	674	Benzene					
-	3.5	8/22/2019			BTEX	GRO	DRO	ORO	Total TPH
	3			ND	ND	ND	86.3	ND	86.3
SP25		7/24/2040	319	-	-	-	-	-	-
	2	7/24/2019	175	ND	ND	ND	ND	ND	ND
SP26		7/24/2019	489	ND	ND	ND	ND	ND	ND
SP27	2	7/24/2019	262	ND	ND	ND	ND	ND	ND
SP28	2	7/24/2019	893	ND	ND	ND	30.3	ND	30.3
-	3	8/22/2019	412	-	-	-	-	-	-
SP29	2	7/24/2019	255	ND	ND	ND	ND	ND	ND
SP30	2	7/24/2019	224	ND	ND	ND	206	104	310
-	3	8/22/2019	-	-	-	-	ND	ND	ND
SP31	2	7/24/2019	46.5	ND	ND	ND	ND	ND	ND
SP32	2	7/24/2019	ND	ND	ND	ND	ND	ND	ND
SP33	2	7/24/2019	688	ND	ND	ND	29.2	ND	29.2
-	3	8/22/2019	165	-	-	-	-	-	-
SP34	2	7/24/2019	38.0	ND	ND	ND	ND	ND	ND
-	2	7/24/2019	953	ND	ND	ND	ND	ND	ND
-	3	8/22/2019	7420	-	-	-	-	-	-
-	3.5	9/10/2019	226	-	-	-	-	-	-
SP36	2	7/24/2019	658	ND	ND	ND	ND	ND	ND
-	3	8/22/2019	475	-	-	-	-	-	-
SP37	2	7/24/2019	29.8	ND	ND	ND	ND	ND	ND
SP38	2	7/24/2019	503	ND	ND	ND	122	78.5	200.5
-	3	8/22/2019		-	-		ND	ND	ND
SP39	2	7/24/2019	223	ND	ND	ND	ND	ND	ND
SP40		7/24/2019	468	ND	ND	ND	69.5	ND	69.5
SP41	2	7/24/2019	35.3	ND	ND	ND	ND	ND	ND
SP42	2	7/24/2019	529	ND	ND	ND	55.4	ND	55.4
SP43	2	7/24/2019	39.1	ND	ND	ND	ND	ND	ND
SP44	2	7/24/2019	269	ND	ND	ND	ND	ND	ND
SP45	2	7/24/2019	23.8	ND	ND	ND	ND	ND	ND
SP46	2	7/24/2019	853	ND	ND	ND	ND	ND	ND
-	3	8/22/2019	336	-	-	-	-	-	-
SP47	2	7/24/2019	115	ND	ND	ND	68.7	ND	68.7
SP48	2	7/24/2019	84.2	ND	ND	ND	ND	ND	ND
SP49	2	7/24/2019	95.5	ND	ND	ND	ND	ND	ND
SP50	2	7/24/2019	172	ND	ND	ND	176	89.2	265.2
-	3	8/22/2019	-	-	-	-	ND	ND	ND
SP51	2	7/24/2019	95.6	ND	ND	ND	86.5	ND	86.5
SP52	2	7/24/2019	94.1	ND	ND	ND	35.0	ND	35.0

Ross Draw Ui	Analytical Results - Envirotech Inc.									
Excavation Footprint/Sidewalls			Reported in mg/kg							
NM OCD Table 1 Thresholds (GW <50')			600	10	50	100				
Sample ID	Depth (ft)	Sampling Date	Chloride	Benzene	BTEX	GRO	DRO	ORO	Total TPH	
SW1	Composite	7/24/2019	108	ND	ND	ND	46.0	ND	46.0	
SW2	Composite	7/24/2019	1180	ND	ND	ND	70.7	ND	70.7	
-	Composite	8/22/2019	198	-	-	-	-	-	-	
SW3	Composite	7/24/2019	470	ND	ND	ND	ND	ND	ND	
SW4	Composite	7/24/2019	1130	ND	ND	ND	68.2	ND	68.2	
-	Composite	8/22/2019	543	-	-	-	-	-	-	
SW5	Composite	7/24/2019	108	ND	ND	ND	ND	ND	ND	
SW6	Composite	7/24/2019	1340	ND	ND	ND	61.3	ND	61.3	
-	Composite	8/22/2019	258	-	-	-	-	-	-	
SW7	Composite	7/24/2019	168	ND	ND	ND	172	85.3	257.3	
-	Composite	8/22/2019	-	-	-	-	ND	ND	ND	
SW8	Composite	7/24/2019	473	ND	ND	ND	ND	ND	ND	
SW9	Composite	7/24/2019	339	ND	ND	ND	ND	ND	ND	
SW10	Composite	7/24/2019	306	ND	ND	ND	ND	ND	ND	
SW11	Composite	7/24/2019	568	ND	ND	ND	ND	ND	ND	
SW12	Composite	7/24/2019	306	ND	ND	ND	ND	ND	ND	
SW13	Composite	7/24/2019	511	ND	ND	ND	ND	ND	ND	
SW14	Composite	7/24/2019	23.6	ND	ND	ND	ND	ND	ND	
SW15	Composite	7/24/2019	ND	ND	ND	ND	ND	ND	ND	
SW16	Composite	7/24/2019	240	ND	ND	ND	36.3	ND	36.3	
SW17	Composite	7/24/2019	120	ND	ND	ND	ND	ND	ND	