


Form 3160-3
(April 2004)

OCD-ARTESIA

R-111-POTASH

FORM APPROVED
OMB No. 1004-0137
Expires March 31, 2007UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. 5H NMNM 086024 BH 19848	
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name TES 10/2/2012	
2. Name of Operator OXY USA Inc. 16696		7. If Unit or CA Agreement, Name and No.	
3a. Address P.O. Box 50250 Midland TX 79710		8. Lease Name and Well No. Com <39492> Express 33 Federal #5H	
3b. Phone No. (include area code) 432-685-5717		9. API Well No. 30-015-40768	
4. Location of Well (Report location clearly and in accordance with any State requirements *) At surface 453 FNL 803 FEL NENE (A) At proposed prod. zone 400 FSL 600 FEL SESE (P)		10. Field and Pool, or Exploratory Cedar Canyon, R3	
14. Distance in miles and direction from nearest town or post office* 6 miles northeast from Louisa, NM		11. Sec., T. R. M. or Blk. and Survey or Area Sec 33 T23S R29E	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 5-453' BH-400'	16. No. of acres in lease 640	17. Spacing Unit dedicated to this well 160	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 186'	19. Proposed Depth 12946' M 8803' U	20. BLM/BIA Bond No. on file ESB000226	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 2996.3' GL	22. Approximate date work will start* 7/1/12	23. Estimated duration 30 days	

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature	Name (Printed/Typed) David Stewart	Date 5/1/12
---------------	---	--------------------

Title **Regulatory Advisor**

Approved by (Signature)

Title **STATE DIRECTOR**

Name (Printed/Typed)

Office

NM STATE OFFICEDate **SEP 24 2012**

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on page 2)

Carlsbad Controlled Water BasinApproval Subject to General Requirements
& Special Stipulations Attached**SEE ATTACHED FOR
CONDITIONS OF APPROVAL**

District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Avenue, Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised October 12, 2005
Submit to Appropriate District Office
State Lease- 4 Copies
Fee Lease- 3 Copies

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-015-40768	Pool Code 11520	Pool Name Cedar Canyon; B.S.
Property Code 39492	Property Name CYPRESS 33 FEDERAL COM	Well Number 5H
OGRIID No. 16696	Operator Name OXY USA INC.	Elevation 3002.8'

Surface Location


UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
A	33	23 SOUTH	29 EAST, N.M.P.M.		453'	NORTH	803'	EAST	EDDY

Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	33	23 SOUTH	29 EAST, N.M.P.M.		400'	SOUTH	600'	EAST	EDDY

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.
160	N		

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

	<p>OPERATOR CERTIFICATION</p> <p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p><i>David Stewart-Reg. Adv.</i> 5/1/12 Signature Date</p> <p>David Stewart-Reg. Adv. Printed Name</p>
	<p>SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>SEPTEMBER 3, 2009 Date of Survey</p> <p>Signature and Seal of Professional Surveyor <i>Tommy J. Abel</i> 11/12/2009 Certificate Number 15079</p> <p>WFO# 090903WL-b (KA)</p>

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

OCD Alesia

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator OXY USA Inc. 16696

3a. Address
P.O. Box 50250 Midland, TX 797103b. Phone No. (include area code)
432-685-5717

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SL - 453 FNL 803 FEL NENE(A) Sec 33 T23S R29E
BH - 400 FSL 600 FEL SESE(P)

5. Lease Serial No.

NMNM086024

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

Cypress 33 Federal Com #5H

9. API Well No.

30-015-

40768

10. Field and Pool, or Exploratory Area

~~Wildcat 2nd Bone Spring~~

CEDAR CANYON

11. County or Parish, State

Eddy, NM

<11520>

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Well Name Change
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

OXY USA Inc. respectfully requests that the Cypress 33 Federal #5H be changed to the Cypress 33 Federal Com. #5H.

Accepted for record

NMOC

TES
10/2/201214. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

David Stewart

Title Regulatory Advisor

Signature



Date

6/28/12

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

/s/ JD Whitlock Jr

Title SPET

Date

7/4/12

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.


Office CFO

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

OPERATOR CERTIFICATION

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 12th day of May, 2012.



Name: Peter Lawrence
Position: Reservoir Management Team Leader
Address: 5 Greenway Plaza, Suite 110, Houston, TX 77046
Telephone: 713-215-7644
E-mail: (optional): peter_lawrence@oxy.com
Company: OXY USA Inc.
Field Representative (if not above signatory): Dusty Weaver
Address (If different from above): P.O. Box 50250 Midland, TX 79710
Telephone (if different from above): 432-685-5723
E-mail (if different from above): calvin_weaver@oxy.com

DRILLING PROGRAM

Operator Name/Number: OXY USA Inc. 16696
 Lease Name/Number: Cypress 33 Federal #5H Federal Lease No. NMNM086024
 Pool Name/Number: Wildcat 2nd Bone Spring
 Surface Location: 453 FNL 803 FEL NENE(A) Sec 33 T23S R29E
 Bottom Hole Location: 400 FSL 600 FEL SESE(P) Sec 33 T23S R29E

Proposed TD: 8803' TVD 12946' TMD Elevation: 3002.8' GR
 SL - Lat: 32.2672257 Long: 103.9832802 X= 608199.0 Y= 461110.9 NAD - 1927
 BH - Lat: 32.2550124 Long: 103.9824412 X= 608472.9 Y= 456668.9 NAD - 1927

1. Geologic Name of Surface Formation:

a. Permian

2. Estimated Tops of Geological Markers & Depths of Anticipated Fresh Water, Oil or Gas:

<u>Geological Marker</u>	<u>Depth</u>	<u>Type</u>
a. Rustler	263'	---
b. Top Salt	903'	---
c. Base Salt <i>CK</i>	<i>2670'</i>	---
d. Delaware	3128'	Oil
e. Bone Spring	6837'	Oil
f. 1st Bone Spring	7683'	Oil
g. 2nd Bone Spring	8048'	Oil
h. 2nd Bone Spring Sand	8543'	Oil

3. Casing Program:

<u>Hole Size</u>	<u>Interval</u>	<u>OD Csg</u>	<u>Weight</u>	<u>Collar</u>	<u>Grade</u>	<u>Condition</u>	<u>Collapse Design Factor</u>	<u>Burst Design Factor</u>	<u>Tension Design Factor</u>
17-1/2"	288'	13-3/8"	48	ST&C	H-40	New	5.59	1.26	23.29
				Hole filled with 8.9# Mud			770#	1730#	
12-1/4"	3180'	9-5/8"	40	LT&C	L-80	New	1.83	4.65	5.79
				Hole filled with 10.2# Mud			3090#	5750#	
8-3/4"	12946" M	5-1/2"	17	LT&C	L-80	New	1.46	2.26	1.54
	DVT @ 6000' - POST @ 3205'			Hole filled with 9.4# Mud			6290#	7740#	

Collapse and burst loads calculated using Stress Check with anticipated loads

4. Cement Program

*50' below previous casing shoe
per operator*

- a. 13-3/8" Surface Circulate cement to surface w/ 100sx PP cmt w/ 4% Bentonite + .25#/sx Poly-E-Flake + 2% CaCl₂, 13.5ppg 1.75 yield 985# 24hr CS 165% Excess followed by 300sx PP cmt w/ 2% CaCl₂, 14.8ppg 1.35 yield 1608# 24hr CS 165% Excess
- b. 9-5/8" Intermediate Circulate cement to surface w/ 815sx HES light PP cmt w/ 5% Salt + .125#/sx Poly-E-Flake + 3#/sx Kol Seal + 1% CaCl₂, 12.4ppg 2.13 yield 550# 24hr CS 105% Excess followed by 200sx PP cmt w/ 1% CaCl₂, 14.8ppg 1.34 yield 2525# 24hr CS 105% Excess

- c. 5-1/2" Production Cement 1st stage w/ 2040sx Super H w/ .5% Halad-344 + .4% CFR-3 + 2#/sx Kol Seal + .3% HR-800 + .125#/sx Poly-E-Flake, 13.2ppg 1.6 yield 1400# 24hr CS 85% Excess, Calc TOC-5950'
 Cement 2nd stage w/ 630sx HES light PP cmt w/ 3#/sx Salt + 3#/sx Kol Seal, 12.4ppg 2.10 yield 511# 24hr CS 125% Excess followed by 100sx PP cmt w/ 1% CaCl₂, 14.8ppg 1.34 yield 2125# 24hr CS 125% Excess, Calc TOC-3155'
 Cement 3rd stage w/ 510sx HES Light PP cmt w/ 3#/sx Salt, 12.4ppg 1.98 yield 511# 24hr CS 35% Excess followed by 100sx PP cmt w/ 2% CaCl₂, 14.8ppg 1.35 yield 2100# 24hr CS 35% Excess, Circ Surface

The above cement volumes could be revised pending the caliper measurement.

5. Pressure Control Equipment:

Surface None

Production 13-5/8" 10M two ram stack w/ 5M annular preventer, 10M Choke Manifold

All BOP's and associated equipment will be tested in accordance with Onshore Order #2 (250/5000 psi on rams for 10 minutes each and 250/3500 for 10 minutes for annular preventer, equal to 70% of working pressure) with a third party BOP testing service before drilling out the 13-3/8" casing shoe. Wellhead pressure rating will support this test and 13-3/8" casing will be protected from high pressure. Since the wellhead system is a multibowl design, this initial test will cover the requirements prior to drilling out the 9-5/8" casing shoe.

Pipe Rams will be operated and checked each 24-hour period and each time the drill pipe is out of the hole. These functional tests will be documented on the daily driller's log. A 2" kill line and 3" choke line will be accommodated on the drilling spool below the ram-type BOP. Other accessory BOP equipment will include a Kelly cock, floor safety valve, choke lines and choke manifold having a 5000 psi WP rating. OXY requests that the entire system be tested as a 5000psi WP rating.

OXY also requests a variance to connect the BOP outlet to the choke manifold using a co-flex hose that is manufactured by Contitech Rubber Industrial KFT. It is a 3" ID X 35' flexible hose rated to 10000psi working pressure. It has been tested to 15000psi and is built to API Spec 16C. Once the flex line is installed, it will be tied down with safety clamps, see attached for certifications.

6. Proposed Mud Circulation System

<u>Depth</u>	<u>Mud Wt.</u> <u>ppg</u>	<u>Visc</u> <u>sec</u>	<u>Fluid</u> <u>Loss</u>	<u>Type System</u>
0 - 288'	8.4-8.9	32-34	NC	Fresh Water/Spud Mud
288 - 3180'	9.8-10.2	28-29	NC	Brine Water
3180 - 6500'	8.4-8.8	28-29	NC	Fresh Water Mud
6500 - TD'	9.0-9.4	32-36	8-15	Duo Vis

Pump high viscosity sweeps as needed for hole cleaning. The mud system will be monitored visually/manually as well as with an electronic PVT. The necessary mud products for additional weight and fluid loss control will be on location at all times.

7. Auxiliary Well Control and Monitoring Equipment:

- A Kelly cock will be in the drill string at all times.
- A full opening drill pipe stabbing valve having the appropriate connections will be on the rig floor unobstructed and readily accessible at all times.
- Hydrogen Sulfide detection equipment will be in operation after drilling out the surface casing shoe until the production casing is cemented. Breathing equipment will be on location upon drilling the surface casing shoe until total depth is reached. If Hydrogen Sulfide is encountered, measured amounts and formations will be reported to the BLM.

8. Logging, Coring and Testing Program: *See CoA*

- a. Drill stem tests are not anticipated but if done will be based on geological sample shows.
- b. The open hole electrical logging program will consist of a GR from kick-off point to TD.
- c. No coring program is planned but if done will be sidewall rotary cores.
- d. No mudloggers are currently programmed for this well.

9. Potential Hazards:

No abnormal pressures, temperatures or H₂S gas are expected. The highest anticipated pressure gradient would be 0.488psi/ft or 4300psi. If H₂S is encountered the operator will comply with the provisions of Onshore Oil & Gas Order No.6. No lost circulation is expected to occur. All personnel will be familiar with all aspects of safe operation of equipment being used to drill this well. Adequate flare lines will be installed off the mud/gas separator where gas may be flared safely.


10. Anticipated Starting Date and Duration of Operations:

Road and location construction will begin after the BLM has approved the APD. Anticipated spud date will be as soon as possible after BLM approval and as soon as a rig will be available. Move in operations and drilling is expected to take 45 days. If production casing is run, then an additional 30 days will be needed to complete the well and construct surface facilities and/or lay flow lines in order to place well on production.

11. Spacing Unit:

The following wells are in the Cedar Canyon Bone Spring (11520) and completed in the 1st Bone Spring.

1. Cypress 33 Federal #1 – 30-015-36321 – TVD 7818'
2. Cypress 33 Federal #2 – 30-015-37308 – TVD 7649'
3. Cypress 33 Federal #3 – 30-015-36987 – TVD 7780'
4. Cypress 33 Federal #4 – 30-015-37368 – TVD 7702'



Scientific Drilling

OXY

Cypress

Cypress 33 Federal #5H

Cyp-33F#5H

Original Wellbore

Plan: Final Design

Standard Planning Report

18 November, 2011





Project: Cypress
Site: Cypress 33 Federal #5H
Well: Cyp- 33F#5H
Wellbore: Original Wellbore
Design: Final Design



PROJECT DETAILS: Cypress

Geodetic System US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone New Mexico East 3001
System Datum Mean Sea Level

SITE DETAILS: Cypress 33 Federal #5H

Sec 33, T23S, R29E, NMPM
Eddy Co., New Mexico
Northing 461110.90
Easting 608199.00
Elevation 3002.80
KB DFE @ 3027.80usft (DFE 25ft)

CASING DETAILS

TVD	MD	Size
270.00	270.00	13- 3/8
3155.00	3155.00	9- 5/8

FORMATION TOP DETAILS

TVD	MD	Formation
262.80	262.80	Rustler
902.80	902.80	Salado (Top of Salt)
1492.80	1492.80	Base of Salt
3077.80	3077.80	Base of Anhydrite
3127.80	3127.80	Top Delaware - Ramsey Sand
6837.80	6837.80	T Bone Spring Limestone
7682.80	7682.80	T BSPG1 Limestone
7747.80	7747.80	T BSPG1 1st Sand
8047.80	8047.80	T BSPG2 Limestone
8542.80	8581.18	T BSPG 2nd Sand
8802.80	9211.60	T BSPG 2nd Sand (Target)

SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	Vsect	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
8086.60	0.00	0.00	8086.60	0.00	0.00	0.00	0.00	
9211.60	90.00	176.47	8802.80	- 714.84	44.08	8.00	716.20	
12945.84	90.00	176.47	8802.80	- 4442.00	273.90	0.00	4450.44	Cyp33F#5H PBHL



DESIGN TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting	Shape
Cyp33F#5H PBHL	8802.80	- 4442.00	273.90	456668.90	608472.90	Point
- plan hits target center						



Azimuths to Grid North
True North: - 0.19°
Magnetic North: 7.54°

Magnetic Field
Strength 48557.7nT
Dip Angle 60.15°
Date: 2011/11/15
Model: IGRF2010



Database:	EDM-MPF	Local Co-ordinate Reference:	Well: Cyp-33F#5H
Company:	OXY	TVD Reference:	DFE @ 3027.80usft (DFE:25ft)
Project:	Cypress	MD Reference:	DFE @ 3027.80usft (DFE:25ft)
Site:	Cypress 33 Federal #5H	North Reference:	Grid
Well:	Cyp-33F#5H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Wellbore		
Design:	Final Design		

Project: Cypress, New Mexico	
Map System:	US State Plane 1927 (Exact solution)
Geo Datum:	NAD 1927 (NADCON CONUS)
Map Zone:	New Mexico East 3001
System Datum:	Mean Sea Level

Site						Cypress 33 Federal #5H, Sec.33, T23S, R29E, NMPM					
Site Position:		Northing:		461,110.90 usft		Latitude:		32° 16' 2.012 N			
From:		Map		Easting:		608,199.00 usft		Longitude:		103° 58' 59.809 W	
Position Uncertainty:		0.00 usft		Slot Radius:		0 "		Grid Convergence:		0.19 °	

Well:	Cyp-33F#5H					
Well Position	+N-S	0.00 usft	Northing:	461,110.90 usft	Latitude:	32° 16' 2.012 N
	+E-W	0.00 usft	Easting:	608,199.00 usft	Longitude:	103° 58' 59.809 W
Position Uncertainty		0.00 usft	Wellhead Elevation:		Ground Level:	3,002.80 usft

Wellbore	Original Wellbore				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	2011/11/15	7.73	60.15	48,558

Design:	Final Design			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD)	+N-S	+E-W	Direction
	(usft)	(usft)	(usft)	(°)
	0.00	0.00	0.00	176.47

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/S (usft)	+E/W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
8,086.60	0.00	0.00	8,086.60	0.00	0.00	0.00	0.00	0.00	0.00	
9,211.60	90.00	176.47	8,802.80	-714.84	44.08	8.00	8.00	0.00	176.47	
12,945.84	90.00	176.47	8,802.80	-4,442.00	273.90	0.00	0.00	0.00	0.00	Cyp33F#5H PBHL

Database:	EDM-MPF	Local Co-ordinate Reference:	Well Cyp-33F#5H
Company:	OXY	TVD Reference:	DFE @ 3027.80usft (DFE:25ft)
Project:	Cypress	MD Reference:	DFE @ 3027.80usft (DFE:25ft)
Site:	Cypress 33 Federal #5H	North Reference:	Grid
Well:	Cyp-33F#5H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Wellbore		
Design:	Final Design		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
262.80	0.00	0.00	262.80	0.00	0.00	0.00	0.00	0.00	0.00
Rustler									
270.00	0.00	0.00	270.00	0.00	0.00	0.00	0.00	0.00	0.00
13 3/8"									
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
902.80	0.00	0.00	902.80	0.00	0.00	0.00	0.00	0.00	0.00
Salado (Top of Salt)									
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,492.80	0.00	0.00	1,492.80	0.00	0.00	0.00	0.00	0.00	0.00
Base of Salt									
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,077.80	0.00	0.00	3,077.80	0.00	0.00	0.00	0.00	0.00	0.00
Base of Anhydrite									
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,127.80	0.00	0.00	3,127.80	0.00	0.00	0.00	0.00	0.00	0.00
Top Delaware - Ramsey Sand									
3,155.00	0.00	0.00	3,155.00	0.00	0.00	0.00	0.00	0.00	0.00
9 5/8"									
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00

Database:	EDM-MPF	Local Co-ordinate Reference:	Well Cyp-33F#5H
Company:	OXY	TVD Reference:	DFE @ 3027.80usft (DFE:25ft)
Project:	Cypress	MD Reference:	DFE @ 3027.80usft (DFE:25ft)
Site:	Cypress 33 Federal #5H	North Reference:	Grid
Well:	Cyp-33F#5H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Wellbore		
Design:	Final Design		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N-S (usft)	+E-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,100.00	0.00	0.00	4,100.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,200.00	0.00	0.00	4,200.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,300.00	0.00	0.00	4,300.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,400.00	0.00	0.00	4,400.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,500.00	0.00	0.00	4,500.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,600.00	0.00	0.00	4,600.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,700.00	0.00	0.00	4,700.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,800.00	0.00	0.00	4,800.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,900.00	0.00	0.00	4,900.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,000.00	0.00	0.00	5,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,100.00	0.00	0.00	5,100.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,200.00	0.00	0.00	5,200.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,300.00	0.00	0.00	5,300.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,400.00	0.00	0.00	5,400.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,500.00	0.00	0.00	5,500.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,600.00	0.00	0.00	5,600.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,700.00	0.00	0.00	5,700.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,800.00	0.00	0.00	5,800.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,900.00	0.00	0.00	5,900.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,000.00	0.00	0.00	6,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,100.00	0.00	0.00	6,100.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,200.00	0.00	0.00	6,200.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,300.00	0.00	0.00	6,300.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,400.00	0.00	0.00	6,400.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,500.00	0.00	0.00	6,500.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,600.00	0.00	0.00	6,600.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,700.00	0.00	0.00	6,700.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,800.00	0.00	0.00	6,800.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,837.80	0.00	0.00	6,837.80	0.00	0.00	0.00	0.00	0.00	0.00	
T. Bone Spring Limestone										
6,900.00	0.00	0.00	6,900.00	0.00	0.00	0.00	0.00	0.00	0.00	
7,000.00	0.00	0.00	7,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
7,100.00	0.00	0.00	7,100.00	0.00	0.00	0.00	0.00	0.00	0.00	
7,200.00	0.00	0.00	7,200.00	0.00	0.00	0.00	0.00	0.00	0.00	
7,300.00	0.00	0.00	7,300.00	0.00	0.00	0.00	0.00	0.00	0.00	
7,400.00	0.00	0.00	7,400.00	0.00	0.00	0.00	0.00	0.00	0.00	
7,500.00	0.00	0.00	7,500.00	0.00	0.00	0.00	0.00	0.00	0.00	
7,600.00	0.00	0.00	7,600.00	0.00	0.00	0.00	0.00	0.00	0.00	
7,682.80	0.00	0.00	7,682.80	0.00	0.00	0.00	0.00	0.00	0.00	
T. BSPG1 Limestone										
7,700.00	0.00	0.00	7,700.00	0.00	0.00	0.00	0.00	0.00	0.00	
7,747.80	0.00	0.00	7,747.80	0.00	0.00	0.00	0.00	0.00	0.00	
T. BSPG 1st Sand										
7,800.00	0.00	0.00	7,800.00	0.00	0.00	0.00	0.00	0.00	0.00	
7,900.00	0.00	0.00	7,900.00	0.00	0.00	0.00	0.00	0.00	0.00	
8,000.00	0.00	0.00	8,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
8,047.80	0.00	0.00	8,047.80	0.00	0.00	0.00	0.00	0.00	0.00	
T. BSPG2 Limestone										
8,086.60	0.00	0.00	8,086.60	0.00	0.00	0.00	0.00	0.00	0.00	
8087ft: KOP, 8°/100 DLS, 176° MTF										
8,100.00	1.07	176.47	8,100.00	-0.13	0.01	0.13	8.00	8.00	0.00	
8,200.00	9.07	176.47	8,199.53	-8.94	0.55	8.96	8.00	8.00	0.00	



Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
8,300.00	17.07	176.47	8,296.86	-31.50	1.94	31.56	8.00	8.00	0.00
8,400.00	25.07	176.47	8,390.09	-67.35	4.15	67.48	8.00	8.00	0.00
8,500.00	33.07	176.47	8,477.42	-115.81	7.14	116.03	8.00	8.00	0.00
8,581.18	39.57	176.47	8,542.80	-163.78	10.10	164.09	8.00	8.00	0.00
T. BSPG 2nd Sand									
8,600.00	41.07	176.47	8,557.15	-175.93	10.85	176.27	8.00	8.00	0.00
8,700.00	49.07	176.47	8,627.71	-246.54	15.20	247.01	8.00	8.00	0.00
8,800.00	57.07	176.47	8,687.74	-326.26	20.12	326.88	8.00	8.00	0.00
8,900.00	65.07	176.47	8,736.08	-413.55	25.50	414.33	8.00	8.00	0.00
9,000.00	73.07	176.47	8,771.77	-506.70	31.24	507.66	8.00	8.00	0.00
9,100.00	81.07	176.47	8,794.12	-603.90	37.24	605.05	8.00	8.00	0.00
9,200.00	89.07	176.47	8,802.71	-703.26	43.36	704.60	8.00	8.00	0.00
9,211.60	90.00	176.47	8,802.80	-714.84	44.08	716.20	8.00	8.00	0.00
9212ft: EOB, Hold 90° Inc, 176.5° Azi - T. BSPG 2nd Sand (Target)									
9,300.00	90.00	176.47	8,802.80	-803.07	49.52	804.59	0.00	0.00	0.00
9,400.00	90.00	176.47	8,802.80	-902.88	55.67	904.59	0.00	0.00	0.00
9,500.00	90.00	176.47	8,802.80	-1,002.69	61.83	1,004.59	0.00	0.00	0.00
9,600.00	90.00	176.47	8,802.80	-1,102.50	67.98	1,104.59	0.00	0.00	0.00
9,700.00	90.00	176.47	8,802.80	-1,202.31	74.14	1,204.59	0.00	0.00	0.00
9,800.00	90.00	176.47	8,802.80	-1,302.12	80.29	1,304.59	0.00	0.00	0.00
9,900.00	90.00	176.47	8,802.80	-1,401.93	86.45	1,404.59	0.00	0.00	0.00
10,000.00	90.00	176.47	8,802.80	-1,501.74	92.60	1,504.59	0.00	0.00	0.00
10,100.00	90.00	176.47	8,802.80	-1,601.55	98.75	1,604.59	0.00	0.00	0.00
10,200.00	90.00	176.47	8,802.80	-1,701.36	104.91	1,704.59	0.00	0.00	0.00
10,300.00	90.00	176.47	8,802.80	-1,801.17	111.06	1,804.59	0.00	0.00	0.00
10,400.00	90.00	176.47	8,802.80	-1,900.98	117.22	1,904.59	0.00	0.00	0.00
10,500.00	90.00	176.47	8,802.80	-2,000.79	123.37	2,004.59	0.00	0.00	0.00
10,600.00	90.00	176.47	8,802.80	-2,100.60	129.53	2,104.59	0.00	0.00	0.00
10,700.00	90.00	176.47	8,802.80	-2,200.42	135.68	2,204.59	0.00	0.00	0.00
10,800.00	90.00	176.47	8,802.80	-2,300.23	141.84	2,304.59	0.00	0.00	0.00
10,900.00	90.00	176.47	8,802.80	-2,400.04	147.99	2,404.59	0.00	0.00	0.00
11,000.00	90.00	176.47	8,802.80	-2,499.85	154.14	2,504.59	0.00	0.00	0.00
11,100.00	90.00	176.47	8,802.80	-2,599.66	160.30	2,604.59	0.00	0.00	0.00
11,200.00	90.00	176.47	8,802.80	-2,699.47	166.45	2,704.59	0.00	0.00	0.00
11,300.00	90.00	176.47	8,802.80	-2,799.28	172.61	2,804.59	0.00	0.00	0.00
11,400.00	90.00	176.47	8,802.80	-2,899.09	178.76	2,904.59	0.00	0.00	0.00
11,500.00	90.00	176.47	8,802.80	-2,998.90	184.92	3,004.59	0.00	0.00	0.00
11,600.00	90.00	176.47	8,802.80	-3,098.71	191.07	3,104.59	0.00	0.00	0.00
11,700.00	90.00	176.47	8,802.80	-3,198.52	197.23	3,204.59	0.00	0.00	0.00
11,800.00	90.00	176.47	8,802.80	-3,298.33	203.38	3,304.59	0.00	0.00	0.00
11,900.00	90.00	176.47	8,802.80	-3,398.14	209.53	3,404.59	0.00	0.00	0.00
12,000.00	90.00	176.47	8,802.80	-3,497.95	215.69	3,504.59	0.00	0.00	0.00
12,100.00	90.00	176.47	8,802.80	-3,597.76	221.84	3,604.59	0.00	0.00	0.00
12,200.00	90.00	176.47	8,802.80	-3,697.57	228.00	3,704.59	0.00	0.00	0.00
12,300.00	90.00	176.47	8,802.80	-3,797.38	234.15	3,804.59	0.00	0.00	0.00
12,400.00	90.00	176.47	8,802.80	-3,897.19	240.31	3,904.59	0.00	0.00	0.00
12,500.00	90.00	176.47	8,802.80	-3,997.00	246.46	4,004.59	0.00	0.00	0.00
12,600.00	90.00	176.47	8,802.80	-4,096.81	252.62	4,104.59	0.00	0.00	0.00
12,700.00	90.00	176.47	8,802.80	-4,196.62	258.77	4,204.59	0.00	0.00	0.00
12,800.00	90.00	176.47	8,802.80	-4,296.43	264.92	4,304.59	0.00	0.00	0.00
12,900.00	90.00	176.47	8,802.80	-4,396.24	271.08	4,404.59	0.00	0.00	0.00
12,945.84	90.00	176.47	8,802.80	-4,442.00	273.90	4,450.44	0.00	0.00	0.00
12946ft: TD									

Database:	EDM-MPF	Local Co-ordinate Reference:	Well Cyp-33F#5H
Company:	OXY	TVD Reference:	DFE @ 3027.80usft (DFE:25ft)
Project:	Cypress	MD Reference:	DFE @ 3027.80usft (DFE:25ft)
Site:	Cypress 33 Federal #5H	North Reference:	Grid
Well:	Cyp-33F#5H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Wellbore		
Design:	Final Design		

Design Targets									
Target Name	hit/miss target	Dip Angle	Dip Dir	TVD	+N/-S	+E/-W	Northing	Easting	
Shape		(°)	(°)	(usft)	(usft)	(usft)	(usft)	(usft)	Latitude Longitude
Cyp33F#5H PBHL		0.00	0.00	8,802.80	-4,442.00	273.90	456,668.90	608,472.90	32° 15' 18.045 N 103° 58' 56.788 W
- plan hits target center									
- Point									

Casing Points					
Measured Depth	Vertical Depth		Name	Casing Diameter	Hole Diameter
(usft)	(usft)			(")	(")
270.00	270.00	13 3/8"		13-3/8	17-1/2
3,155.00	3,155.00	9 5/8"		9-5/8	12-1/4

Formations						
Measured Depth	Vertical Depth		Name	Lithology	Dip	Dip Direction
(usft)	(usft)				(°)	(°)
262.80	262.80		Rustler		0.00	
902.80	902.80		Salado (Top of Salt)		0.00	
1,492.80	1,492.80		Base of Salt		0.00	
3,077.80	3,077.80		Base of Anhydrite		0.00	
3,127.80	3,127.80		Top Delaware - Ramsey Sand		0.00	
6,837.80	6,837.80		T. Bone Spring Limestone		0.00	
7,682.80	7,682.80		T. BSPG1 Limestone		0.00	
7,747.80	7,747.80		T. BSPG 1st Sand		0.00	
8,047.80	8,047.80		T. BSPG2 Limestone		0.00	
8,581.18	8,542.80		T. BSPG 2nd Sand		0.00	
9,211.60	8,802.80		T. BSPG 2nd Sand (Target)		0.00	



Scientific Drilling

OXY

Cypress

Cypress 33 Federal #5H

Cyp-33F#5H

Original Wellbore

Final Design

Anticollision Summary Report

18 November, 2011



Company:	OXY	Local Co-ordinate Reference:	Well Cyp-33F#5H
Project:	Cypress	TVD Reference:	DFE @ 3027.80usft (DFE:25ft)
Reference Site:	Cypress 33 Federal #5H	MD Reference:	DFE @ 3027.80usft (DFE:25ft)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Cyp-33F#5H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at:	2.00 sigma
Reference Wellbore:	Original Wellbore	Database:	EDM-MPF
Reference Design:	Final Design	Offset TVD Reference:	Offset Datum

Reference:	Final Design		
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria		
Interpolation Method:	Stations	Error Model:	ISCWSA
Depth Range:	Unlimited	Scan Method:	Closest Approach 3D
Results Limited by:	Maximum center-center distance of 9,999.98 usft	Error Surface:	Circular Conic
Warning Levels Evaluated at:	2 00 Sigma	Casing Method:	Not applied

Survey Tool Program		Date	2011/11/18		
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description	
0.00	3,100.00	Final Design (Original Wellbore)	SDI Standard Keeper 103	SDI Standard Wireline Keeper ver 1.0.3	
3,100.00	12,945.84	Final Design (Original Wellbore)	SDI MWD	SDI MWD - Standard ver 1.0.1	

Summary						
Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
Cypress 33 Federal #1H						
Cyp-33F#1H - Original Wellbore - As Drilled	12,695.51	7,944.00	1,066.48	961.24	10.134	CC
Cyp-33F#1H - Original Wellbore - As Drilled	12,700.00	7,944.00	1,066.49	961.16	10.125	ES
Cyp-33F#1H - Original Wellbore - As Drilled	12,900.00	7,944.00	1,085.90	976.67	9.941	SF
Cypress 33 Federal #2H						
Cyp-33F#2H - Original Wellbore - As Drilled	2,317.20	2,310.94	159.53	153.83	28.019	CC, ES
Cyp-33F#2H - Original Wellbore - As Drilled	7,100.00	7,076.27	295.37	275.87	15.144	SF
Cypress 33 Federal #3H						
Cyp-33F#3H - Original Wellbore - As Drilled	11,559.43	7,995.00	1,095.49	1,010.02	12.818	CC
Cyp-33F#3H - Original Wellbore - As Drilled	11,600.00	7,995.00	1,096.24	1,009.99	12.711	ES
Cyp-33F#3H - Original Wellbore - As Drilled	11,800.00	7,975.12	1,121.09	1,031.37	12.496	SF
Cypress 33 Federal #4H						
Cyp-33F#4H - Original Wellbore - Design #1	9,807.96	8,022.55	1,054.05	997.40	18.606	CC, ES
Cyp-33F#4H - Original Wellbore - Design #1	10,100.00	8,017.77	1,093.73	1,031.92	17.695	SF

Company:	OXY	Local Co-ordinate Reference:	Well Cyp-33F#5H
Project:	Cypress	TVD Reference:	DFE @ 3027.80usft (DFE:25ft)
Reference Site:	Cypress 33 Federal #5H	MD Reference:	DFE @ 3027.80usft (DFE:25ft)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Cyp-33F#5H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Original Wellbore	Database:	EDM-MPF
Reference Design:	Final Design	Offset TVD Reference:	Offset Datum

Reference Depths are relative to DFE @ 3027.80usft (DFE:25ft)


Offset Depths are relative to Offset Datum

Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: Cyp-33F#5H

Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 300


Grid Convergence at Surface is: 0.19°




Company:	OXY	Local Co-ordinate Reference:	Well Cyp-33F#5H
Project:	Cypress	TVD Reference:	DFE @ 3027.80usft (DFE:25ft)
Reference Site:	Cypress 33 Federal #5H	MD Reference:	DFE @ 3027.80usft (DFE:25ft)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Cyp-33F#5H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at:	2.00 sigma
Reference Wellbore:	Original Wellbore	Database:	EDM-MPF
Reference Design:	Final Design	Offset TVD Reference:	Offset Datum

Reference Depths are relative to DFE @ 3027.80usft (DFE:25ft)
 Offset Depths are relative to Offset Datum
 Central Meridian is 104° 20' 0.000 W


Coordinates are relative to: Cyp-33F#5H
 Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 300
 Grid Convergence at Surface is: 0.19°



12. BOP DIAGRAM



Choke
Manifold



ISSUED FOR
FABRICATION
MARCH 8, 2002
DRAFTSMAN
ENGINEER

PROPRIETARY
THIS DRAWING AND THE IDEAS AND INFORMATION INCLUDED
HEREIN ARE PROPRIETARY AND ARE NOT TO BE
REPRODUCED, COPIED, OR DISCLOSED IN ANY MANNER
WITHOUT THE PRIOR WRITTEN CONSENT OF A DULY AUTHORIZED
OFFICER OF HELMERICH & PAYNE INT'L DRILLING CO.

ENGINEERING APPROVAL		DATE	TITLE	
△			CHOKE MANIFOLD	
△			CUSTOMER: H&P	
△			PROJECT: FLEXING	
△			DRAWN: MTS	
△			DATE: 2-28-02	
△			DWG. NO.: 216-P1-05	
△			SCALE: 3/4"=1'	
△			SHEET: 1 OF 1	
REV	DATE	DESCRIPTION	BY	REV



Fluid Technology

Quality Document

CERTIFICATE OF CONFORMITY

Supplier : CONTITECH RUBBER INDUSTRIAL KFT.
Equipment : 6 pcs. Choke and Kill Hose with installed couplings
Type : 3" x 10,67 m WP: 10000 psi
Supplier File Number : 412638
Date of Shipment : April. 2008
Customer : Phoenix Beattie Co.
Customer P.o. : 002491
Referenced Standards
/ Codes / Specifications : API Spec 16 C
Serial No.: 52754,52755,52776,52777,52778,52782

STATEMENT OF CONFORMITY

We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.

COUNTRY OF ORIGIN HUNGARY/EU

Signed :

Position: Q.C. Manager

ContiTech Rubber
Industrial Kft.
Quality Control Dept.
(1)

Date: 04. April. 2008

[illegible]



Fluid Technology

Quality Document

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE				CERT. N°: 746	
PURCHASER: Phoenix Beattle Co.				P.O. N°: 002491	
CONTITECH ORDER N°: 412638		HOSE TYPE: 3" ID Choke and Kill Hose			
HOSE SERIAL N°: 52777		NOMINAL / ACTUAL LENGTH: 10,67 m			
W.P. 68,96 MPa 10000 psi		T.P. 103,4 MPa 15000 psi		Duration: 60 ~ min.	
Pressure test with water at ambient temperature <div style="text-align: center;">See attachment. (1 page)</div>					
↑ 10 mm = 10 Min. → 10 mm = 25 MPa					
COUPLINGS					
Type	Serial N°		Quality	Heat N°	
3" coupling with 4 1/16" Flange end	917	913	AISI 4130	T7998A	
			AISI 4130	26984	
INFOCHIP INSTALLED				API Spec 16 C Temperature rate: "B"	
All metal parts are flawless					
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.					
Date:	Inspector		Quality Control		
04. April. 2008			Contitech Rubber Industrial Kft. Quality Control Dept. (1)		


Phoenix Beattie Corp

11535 Brittonmoore Park Drive
Houston, TX 77041
Tel: (832) 327-0141
Fax: (832) 327-0148
E-mail mail@phoenixbeattie.com
www.phoenixbeattie.com

Delivery Note

Customer Order Number	370-369-001	Delivery Note Number	003078	Page	1
Customer / Invoice Address HELMERICH & PAYNE INT'L DRILLING CO 1437 SOUTH BOULDER TULSA, OK 74119		Delivery / Address HELMERICH & PAYNE IDC ATTN: JOE STEPHENSON - RIG 370 13609 INDUSTRIAL ROAD HOUSTON, TX 77015			

Customer Acc No	Phoenix Beattie Contract Manager	Phoenix Beattie Reference	Date
H01	JJL	006330	05/23/2008

Item No	Beattie Part Number / Description	Qty Ordered	Qty Sent	Qty To Follow
1	HP10CK3A-35-4F1 3" 10K 16G C&K HOSE x 35ft OAL CW 4.1/16" API SPEC FLANGE E/ End 1: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange End 2: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange c/w BX155 Standard ring groove at each end Suitable for H2S Service Working pressure: 10,000psi Test pressure: 15,000psi Standard: API 16C Full specification Armor Guarding: Included Fire Rating: Not Included Temperature rating: -20 Deg C to +100 Deg C	1	1	0
2	SECK3-HPF3 LIFTING & SAFETY EQUIPMENT TO SUIT HP10CK3-35-F1 2 x 160mm ID Safety Clamps 2 x 244mm ID Lifting Collars & element C's 2 x 7ft Stainless Steel wire rope 3/4" OD 4 x 7.75t Shackles	1	1	0
3	SC725-200CS SAFETY CLAMP 200MM 7.25T C/S GALVANISED	1	1	0

Continued...

All goods remain the property of Phoenix Beattie until paid for in full. Any damage or shortage on this delivery must be advised within 5 days.
Returns may be subject to a handling charge.

**Phoenix Beattie Corp**

11535 Brittain Park Drive
Houston, TX 77041
Tel: (832) 327-0141
Fax: (832) 327-0148
E-mail: mail@phoenixbeattie.com
www.phoenixbeattie.com

Delivery Note

Customer Order Number	370-369-001	Delivery Note Number	003078	Page	2
Customer / Invoice Address HELMERICH & PAYNE INT'L DRILLING CO 1437 SOUTH BOULDER TULSA, OK 74119		Delivery / Address HELMERICH & PAYNE IDC ATTN: JOE STEPHENSON - RIG 370 13609 INDUSTRIAL ROAD HOUSTON, TX 77015			

Customer Acc No	Phoenix Beattie Contract Manager	Phoenix Beattie Reference	Date
H01	JJL	006330	05/23/2008

Item No	Beattie Part Number / Description	Qty Ordered	Qty Sent	Qty To Follow
4	SC725-132CS SAFETY CLAMP 132MM 7.25T C/S GALVANIZED C/W BOLTS	1	1	0
5	00CERT-HYDRO HYDROSTATIC PRESSURE TEST CERTIFICATE	1	1	0
6	00CERT-LOAD LOAD TEST CERTIFICATES	1	1	0
7	00FREIGHT INBOUND / OUTBOUND FREIGHT PRE-PAY & ADD TO FINAL INVOICE NOTE: MATERIAL MUST BE ACCOMPANIED BY PAPERWORK INCLUDING THE PURCHASE ORDER, RIG NUMBER TO ENSURE PROPER PAYMENT	1	1	0

Phoenix Beattie Inspection Signature :

Received In Good Condition : Signature

Print Name


Date

All goods remain the property of Phoenix Beattie until paid for in full. Any damage or shortage on this delivery must be advised within 5 days.
Returns may be subject to a handling charge.




Permian Drilling Hydrogen Sulfide Drilling Operations Plan Cypress 33 Federal Com #5H

Open drill site. Satellite picture of the area below (Google Maps.) No homes or buildings are near the proposed location.



1. Escape

Personnel shall escape upwind of wellbore in the event of an emergency gas release.
Escape can take place through the lease road on the Southeast side of the location.
Personnel need to move to a safe distance and block the entrance to location.




SEC. 33 TWP. 23-S RGE. 29-E
SURVEY N.M.P.M.
COUNTY EDDY
DESCRIPTION 453' FNL & 803' FEL
ELEVATION 3002.8'
OPERATOR OXY USA INC.
LEASE CYPRESS 33 FED. #5H

SCALE: 1" = 2 MILES

Asel Surveying

P.O. BOX 393 - 310 W. TAYLOR
HOBBS, NEW MEXICO - 575-393-9146



DIRECTIONS BEGINNING AT THE INTERSECTION OF HWY. #128 AND HWY. #31, GO EAST ON HWY. #128 FOR 4.5 MILES, TURN SOUTH ON EDDY CO. ROAD #793 (RAWHIDE ROAD) FOR 4.1 MILES, TURN WEST ON LEASE ROAD FOR 3.5 MILES, TURN SOUTH FOR 1.9 MILES, TURN WEST FOR 0.3 MILES TO PROPOSED NEW ROAD AND GO NORTHWEST FOR 0.7 MILES TO LOCATION.



Permian Drilling Hydrogen Sulfide Drilling Operations Plan New Mexico

Scope

This contingency plan establishes guidelines for the public, all company employees, and contract employees who's work activities may involve exposure to hydrogen sulfide (H₂S) gas.

While drilling this well, it is possible to encounter H₂S bearing formations. At all times, the first barrier to control H₂S emissions will be the drilling fluid, which will have a density high enough to control influx.

Objective

1. Provide an immediate and predetermined response plan to any condition when H₂S is detected. All H₂S detections in excess of 10 parts per million (ppm) concentration are considered an Emergency.
2. Prevent any and all accidents, and prevent the uncontrolled release of hydrogen sulfide into the atmosphere.
3. Provide proper evacuation procedures to cope with emergencies.
4. Provide immediate and adequate medical attention should an injury occur.

Discussion

Implementation:	This plan with all details is to be fully implemented before drilling to <u>commence</u> .
Emergency response Procedure:	This section outlines the conditions and denotes steps to be taken in the event of an emergency.
Emergency equipment Procedure:	This section outlines the safety and emergency equipment that will be required for the drilling of this well.
Training provisions:	This section outlines the training provisions that must be adhered to prior to drilling.
Drilling emergency call lists:	Included are the telephone numbers of all persons to be contacted should an emergency exist.
Briefing:	This section deals with the briefing of all people involved in the drilling operation.
Public safety:	Public safety personnel will be made aware of any potential evacuation and any additional support needed.
Check lists:	Status check lists and procedural check lists have been included to insure adherence to the plan.
General information:	A general information section has been included to supply support information.

Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on the well:

1. The hazards and characteristics of H₂S.
2. Proper use and maintenance of personal protective equipment and life support systems.
3. H₂S detection.
4. Proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures and prevailing winds.
5. Proper techniques for first aid and rescue procedures.
6. Physical effects of hydrogen sulfide on the human body.
7. Toxicity of hydrogen sulfide and sulfur dioxide.
8. Use of SCBA and supplied air equipment.
9. First aid and artificial respiration.
10. Emergency rescue.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H₂S on metal components. If high tensile strength tubular is to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling a well, blowout prevention and well control procedures.
3. The contents and requirements of the H₂S Drilling Operations Plan.

H₂S training refresher must have been taken within one year prior to drilling the well. Specifics on the well to be drilled will be discussed during the pre-spud meeting. H₂S and well control (choke) drills will be performed while drilling the well, at least on a weekly basis. This plan shall be available in the well site. All personnel will be required to carry the documentation proving that the H₂S training has been taken.

Service company and visiting personnel

- A. Each service company that will be on this well will be notified if the zone contains H₂S.
- B. Each service company must provide for the training and equipment of their employees before they arrive at the well site.
- C. Each service company will be expected to attend a well site briefing

Emergency Equipment Requirements

1. Well control equipment

The well shall have hydraulic BOP equipment for the anticipated pressures. Equipment is to be tested on installation and follow Oxy Well Control standard, as well as BLM Onshore Order #2.

Special control equipment:

- A. Hydraulic BOP equipment with remote control on ground.
- B. Rotating head
- C. Gas buster equipment shall be installed before drilling out of surface pipe.

2. Protective equipment for personnel

- A. Four (4) 30-minute positive pressure air packs (2 at each briefing area) on location.
- B. Adequate fire extinguishers shall be located at strategic locations.
- C. Radio / cell telephone communication will be available at the rig.
 - Rig floor and trailers.
 - Vehicle.

3. Hydrogen sulfide sensors and alarms

- A. H₂S sensor with alarms will be located on the rig floor, at the bell nipple, and at the flow line. These monitors will be set to alarm at 10 ppm with strobe light, and audible alarm.
- B. Hand operated detectors with tubes.
- C. H₂S monitor tester (to be provided by contract Safety Company.)
- D. There shall be one combustible gas detector on location at all times.

4. Visual Warning Systems

- A. One sign located at each location entrance with the following language:

Caution – potential poison gas
Hydrogen sulfide
No admittance without authorization

Wind sock – wind streamers:

- A. One 36" (in length) wind sock located at protection center, at height visible from rig floor.
- B. One 36" (in length) wind sock located at height visible from pit areas.

Condition flags

- A. One each condition flag to be displayed to denote conditions.

green – normal conditions
yellow – potential danger
red – danger, H2S present

- B. Condition flag shall be posted at each location sign entrance.

5. Mud Program

The mud program is designed to minimize the risk of having H2S and other formation fluids at surface. Proper mud weight and safe drilling practices will be applied. H2S scavengers will be used to minimize the hazards while drilling. Below is a summary of the drilling program.

Mud inspection devices:

Garrett gas train or hatch tester for inspection of sulfide concentration in mud system.

6. Metallurgy

- A. Drill string, casing, tubing, wellhead, blowout preventers, drilling spools or adapters, kill lines, choke manifold, lines and valves shall be suitable for the H2S service.
- B. All the elastomers, packing, seals and ring gaskets shall be suitable for H2S service.

7. Well Testing

No drill stem test will be performed on this well.

8. Evacuation plan

Evacuation routes should be established prior to well spud for each well and discussed with all rig personnel.

9. Designated area

- A. Parking and visitor area: all vehicles are to be parked at a predetermined safe distance from the wellhead.
- B. There will be a designated smoking area.
- C. Two briefing areas on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds perpendicularly, or at a 45-degree angle if wind direction tends to shift in the area.

Emergency procedures

- A. In the event of any evidence of H₂S level above 10 ppm, take the following steps:
 - 1. The Driller will pick up off bottom, shut down the pumps, slow down the pipe rotation.
 - 2. Secure and don escape breathing equipment, report to the upwind designated safe briefing / muster area.
 - 3. All personnel on location will be accounted for and emergency search should begin for any missing, the Buddy System will be implemented.
 - 4. Order non-essential personnel to leave the well site, order all essential personnel out of the danger zone and upwind to the nearest designated safe briefing / muster area.
 - 5. Entrance to the location will be secured to a higher level than our usual "Meet and Greet" requirement, and the proper condition flag will be displayed at the entrance to the location.
 - 6. Take steps to determine if the H₂S level can be corrected or suppressed and, if so, proceed as required.
- B. If uncontrollable conditions occur:
 - 1. Take steps to protect and/or remove any public in the down-wind area from the rig – partial evacuation and isolation. Notify necessary public safety personnel and appropriate regulatory entities (i.e. BLM) of the situation.

2. Remove all personnel to the nearest upwind designated safe briefing / muster area or off location.
3. Notify public safety personnel of safe briefing / muster area.
4. An assigned crew member will blockade the entrance to the location. No unauthorized personnel will be allowed entry to the location.
5. Proceed with best plan (at the time) to regain control of the well. Maintain tight security and safety procedures.

C. Responsibility:

1. Designated personnel.
 - a. Shall be responsible for the total implementation of this plan.
 - b. Shall be in complete command during any emergency.
 - c. Shall designate a back-up.

All personnel:	<ol style="list-style-type: none"> 1. On alarm, don escape unit and report to the nearest upwind designated safe briefing / muster area upw 2. Check status of personnel (buddy system). 3. Secure breathing equipment. 4. Await orders from supervisor.
Drill site manager:	<ol style="list-style-type: none"> 1. Don escape unit if necessary and report to nearest upwind designated safe briefing / muster area. 2. Coordinate preparations of individuals to return to point of release with tool pusher and driller (using the buddy system). 3. Determine H2S concentrations. 4. Assess situation and take control measures.
Tool pusher:	<ol style="list-style-type: none"> 1. Don escape unit Report to up nearest upwind designated safe briefing / muster area. 2. Coordinate preparation of individuals to return to point of release with tool pusher drill site manager (using the buddy system). 3. Determine H2S concentration. 4. Assess situation and take control measures.
Driller:	<ol style="list-style-type: none"> 1. Don escape unit, shut down pumps, continue rotating DP.

2. Check monitor for point of release.
3. Report to nearest upwind designated safe briefing / muster area.
4. Check status of personnel (in an attempt to rescue, use the buddy system).
5. Assigns least essential person to notify Drill Site Manager and tool pusher by quickest means in case of their absence.
6. Assumes the responsibilities of the Drill Site Manager and tool pusher until they arrive should they be absent.

Derrick man
Floor man #1
Floor man #2

1. Will remain in briefing / muster area until instructed by supervisor.

Mud engineer:

1. Report to nearest upwind designated safe briefing / muster area.
2. When instructed, begin check of mud for ph and H2S level. (Garett gas train.)

Safety personnel:

1. Mask up and check status of all personnel and secure operations as instructed by drill site manager.

Taking a kick

When taking a kick during an H2S emergency, all personnel will follow standard Well control procedures after reporting to briefing area and masking up.

Open-hole logging

All unnecessary personnel off floor. Drill Site Manager and safety personnel should monitor condition, advise status and determine need for use of air equipment.

Running casing or plugging

Following the same “tripping” procedure as above. Drill Site Manager and safety personnel should determine if all personnel have access to protective equipment.

Ignition procedures

The decision to ignite the well is the responsibility of the operator (Oxy Drilling Management). The decision should be made only as a last resort and in a situation where it is clear that:

1. Human life and property are endangered.
2. There is no hope controlling the blowout under the prevailing conditions at the well.

Instructions for igniting the well

1. Two people are required for the actual igniting operation. They must wear self-contained breathing units and have a safety rope attached. One man (tool pusher or safety engineer) will check the atmosphere for explosive gases with the gas monitor. The other man is responsible for igniting the well.
2. Primary method to ignite: 25 mm flare gun with range of approximately 500 feet.
3. Ignite upwind and do not approach any closer than is warranted.
4. Select the ignition site best for protection, and which offers an easy escape route.
5. Before firing, check for presence of combustible gas.
6. After lighting, continue emergency action and procedure as before.
7. All unassigned personnel will remain in briefing area until instructed by supervisor or directed by the Drill Site Manager.

Remember: After well is ignited, burning hydrogen sulfide will convert to sulfur dioxide, which is also highly toxic. **Do not assume the area is safe after the well is ignited.**

Status check list

Note: All items on this list must be completed before drilling to production casing point.

1. H2S sign at location entrance.
2. Two (2) wind socks located as required.
3. Four (4) 30-minute positive pressure air packs (2 at each Briefing area) on location for all rig personnel and mud loggers.
4. Air packs inspected and ready for use.
5. Cascade system and hose line hook-up as needed.
6. Cascade system for refilling air bottles as needed.
7. Condition flag on location and ready for use.
8. H2S detection system hooked up and tested.
9. H2S alarm system hooked up and tested.
10. Hand operated H2S detector with tubes on location.
11. 1 – 100' length of nylon rope on location.
12. All rig crew and supervisors trained as required.
13. All outside service contractors advised of potential H2S hazard on well.
14. No smoking sign posted and a designated smoking area identified.
15. Calibration of all H2S equipment shall be noted on the IADC report.

Checked by: _____ Date: _____

Procedural check list during H2S events

Perform each tour:

1. Check fire extinguishers to see that they have the proper charge.
2. Check breathing equipment to ensure that it is in proper working order.
3. Make sure all the H2S detection system is operative.

Perform each week:

1. Check each piece of breathing equipment to make sure that demand or forced air regulator is working. This requires that the bottle be opened and the mask assembly be put on tight enough so that when you inhale, you receive air or feel air flow.
2. BOP skills (well control drills).
3. Check supply pressure on BOP accumulator stand by source.
4. Check breathing equipment mask assembly to see that straps are loosened and turned back, ready to put on.
5. Check pressure on breathing equipment air bottles to make sure they are charged to full volume. (Air quality checked for proper air grade "D" before bringing to location)
6. Confirm pressure on all supply air bottles.
7. Perform breathing equipment drills with on-site personnel.
8. Check the following supplies for availability.
 - A. Emergency telephone list.
 - B. Hand operated H2S detectors and tubes.

General evacuation plan

1. When the company approved supervisor (Drill Site Manager, consultant, rig pusher, or driller) determines the H₂S gas cannot be limited to the well location and the public will be involved, he will activate the evacuation plan.
2. Drill Site Manager or designee will notify local government agency that a hazardous condition exists and evacuation needs to be implemented.
3. Company or contractor safety personnel that have been trained in the use of H₂S detection equipment and self-contained breathing equipment will monitor H₂S concentrations, wind directions, and area of exposure. They will delineate the outer perimeter of the hazardous gas area. Extension to the evacuation area will be determined from information gathered.
4. Law enforcement personnel (state police, police dept., fire dept., and sheriff's dept.) Will be called to aid in setting up and maintaining road blocks. Also, they will aid in evacuation of the public if necessary.
5. After the discharge of gas has been controlled, company safety personnel will determine when the area is safe for re-entry.

Important: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

Emergency actions

Well blowout – if emergency

1. Evacuate all personnel to “Safe Briefing / Muster Areas” or off location if needed.
2. If sour gas – evacuate rig personnel.
3. If sour gas – evacuate public within 3000 ft radius of exposure.
4. Don SCBA and shut well in if possible using the buddy system.
5. Notify Drilling Superintendent and call 911 for emergency help (fire dept and ambulance) if needed.
6. Implement the Blowout Contingency Plan, and Drilling Emergency Action Plan.
6. Give first aid as needed.

Person down location/facility

1. If immediately possible, contact 911. Give location and wait for confirmation.
2. Don SCBA and perform rescue operation using buddy system.

Toxic effects of hydrogen sulfide

Hydrogen sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 ppm, which is .001% by volume. Hydrogen sulfide is heavier than air (specific gravity – 1.192) and colorless. It forms an explosive mixture with air between 4.3 and 46.0 percent by volume. Hydrogen sulfide is almost as toxic as hydrogen cyanide and is between five and six times more toxic than carbon monoxide. Toxicity data for hydrogen sulfide and various other gases are compared in table i. Physical effects at various hydrogen sulfide exposure levels are shown in table ii.

Table i
Toxicity of various gases

Common name	Chemical formula	Specific gravity (sc=1)	Threshold limit (1)	Hazardous limit (2)	Lethal concentration (3)
Hydrogen Cyanide	Hcn	0.94	10 ppm	150 ppm/hr	300 ppm
Hydrogen Sulfide	H2S	1.18	10 ppm	250 ppm/hr	600 ppm
Sulfur Dioxide	So2	2.21	5 ppm	-	1000 ppm
Chlorine	Cl2	2.45	1 ppm	4 ppm/hr	1000 ppm
Carbon Monoxide	Co	0.97	50 ppm	400 ppm/hr	1000 ppm
Carbon Dioxide	Co2	1.52	5000 ppm	5%	10%
Methane	Ch4	0.55	90,000 ppm	Combustible above 5% in air	

- 1) threshold limit – concentration at which it is believed that all workers may be repeatedly exposed day after day without adverse effects.
- 2) hazardous limit – concentration that will cause death with short-term exposure.
- 3) lethal concentration – concentration that will cause death with short-term exposure.

Toxic effects of hydrogen sulfide

Table ii
Physical effects of hydrogen sulfide

<u>Percent (%)</u>	<u>Ppm</u>	<u>Concentration</u> Grains 100 std. Ft3*	<u>Physical effects</u>
0.001	<10	00.65	Obvious and unpleasant odor.

0.002	10	01.30	Safe for 8 hours of exposure.
0.010	100	06.48	Kill smell in 3 – 15 minutes. May sting eyes and throat.
0.020	200	12.96	Kills smell shortly; stings eyes and throat.
0.050	500	32.96	Dizziness; breathing ceases in a few minutes; needs prompt artificial respiration.
0.070	700	45.36	Unconscious quickly; death will result if not rescued promptly.
0.100	1000	64.30	Unconscious at once; followed by death within minutes.

*at 15.00 psia and 60'f.

Use of self-contained breathing equipment (SCBA)

1. Written procedures shall be prepared covering safe use of SCBA's in dangerous atmosphere, which might be encountered in normal operations or in emergencies. Personnel shall be familiar with these procedures and the available SCBA.
2. SCBA's shall be inspected frequently at random to insure that they are properly used, cleaned, and maintained.
3. Anyone who may use the SCBA's shall be trained in how to insure proper face-piece to face seal. They shall wear SCBA's in normal air and then wear them in a test atmosphere. (note: such items as facial hair {beard or sideburns} and eyeglasses will not allow proper seal.) Anyone that may be reasonably expected to wear SCBA's should have these items removed before entering a toxic atmosphere. A special mask must be obtained for anyone who must wear eyeglasses or contact lenses.
4. Maintenance and care of SCBA's:
 - a. A program for maintenance and care of SCBA's shall include the following:
 1. Inspection for defects, including leak checks.
 2. Cleaning and disinfecting.
 3. Repair.
 4. Storage.
 - b. Inspection, self-contained breathing apparatus for emergency use shall be inspected monthly.
 1. Fully charged cylinders.
 2. Regulator and warning device operation.
 3. Condition of face piece and connections.
 4. Rubber parts shall be maintained to keep them pliable and prevent deterioration.
 - c. Routinely used SCBA's shall be collected, cleaned and disinfected as frequently as necessary to insure proper protection is provided.
5. Persons assigned tasks that requires use of self-contained breathing equipment shall be certified physically fit (medically cleared) for breathing equipment usage at least annually.
6. SCBA's should be worn when:
 - A. Any employee works near the top or on top of any tank unless test reveals less than 10 ppm of H₂S.

- B. When breaking out any line where H₂S can reasonably be expected.
- C. When sampling air in areas to determine if toxic concentrations of H₂S exists.
- D. When working in areas where over 10 ppm H₂S has been detected.
- E. At any time there is a doubt as to the H₂S level in the area to be entered.

Rescue
First aid for H₂S poisoning

Do not panic!

Remain calm – think!


1. Don SCBA breathing equipment.
2. Remove victim(s) utilizing buddy system to fresh air as quickly as possible. (go up-wind from source or at right angle to the wind. Not down wind.)
3. Briefly apply chest pressure – arm lift method of artificial respiration to clean the victim's lungs and to avoid inhaling any toxic gas directly from the victim's lungs.
4. Provide for prompt transportation to the hospital, and continue giving artificial respiration if needed.
5. Hospital(s) or medical facilities need to be informed, before-hand, of the possibility of H₂S gas poisoning – no matter how remote the possibility is.
6. Notify emergency room personnel that the victim(s) has been exposed to H₂S gas.

Besides basic first aid, everyone on location should have a good working knowledge of artificial respiration.

Revised CM 6/27/2012

Flex 3 Rig - Vdoor East
 OXY USA Inc.
 Cypress 33 Federal # 5H

Well site
 Facility layout



EQUIPMENT LIST

- 1EA. INDIRECT LINE HEATER
- 1EA. 3-PHASE TESTER
- 1EA. GAS SCRUBBER
- 1EA. FLARE STACK
- 1EA. METER RUN
- 1EA. VAPOR RECOVERY UNIT
- 2EA. 500 BBL STEEL TANKS
- 2EA. 500 BBL FIBERGLASS TANKS
- 1EA. TRANSFER PUMP

If road comes into the Southeast corner of pad Oxy will take up and re-seed 60' on west side and 50' on north side of pad

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	OXY USA INC.
LEASE NO.:	NM19848
WELL NAME & NO.:	5H-CYPRESS 33 FEDERAL COM
SURFACE HOLE FOOTAGE:	0453'/N. & 0803'/E.
BOTTOM HOLE FOOTAGE:	0400'/S. & 0600'/E.
LOCATION:	Section 33, T. 23 S., R. 29 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Pad construction**
 - Flowline ROW/sundry notice**
 - Cave/Karst
 - Communitization Agreement
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
 - R-111-P Potash
 - High Cave/Karst
 - Logging Requirements
 - Waste Material and Fluids
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**