

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals

SUBMIT IN TRIPLICATE

FORM APPROVED
OMB NO. 1004-0135
EXPIRES: NOVEMBER 30, 2000

1a. Type of Well ☒ Oil Well ☐ Gas Well ☐ Other _____

2. Name of Operator
DEVON LOUISIANA CORPORATION

3. Address and Telephone No.
20 North Broadway, Ste 1500, Oklahoma City, OK 73102 405-552-4615

4. Location of Well (Report location clearly and in accordance with Federal requirements)*
1980' FSL 1980 FEL J 22 18S 31E

5. Lease Serial No.
NMNM014103

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No.

8. Well Name and No.
Shugart 22 Fed 2

9. API Well No.
30-015-29907

10. Field and Pool, or Exploratory
SHUGART

12. County or Parish 13. State
EDDY NM

CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input checked="" type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work and approximate duration thereof. If the proposal deepens directionally or recompletes horizontally, give subsurface location and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirement, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection)

1. MIRU on 8/25/05. POOH with existing 2-7/8" production tubing and rod string.
2. Set CIBP @ 3330'. Spot 50' of cement on top to abandon Queen perms from 3350' to 3384'.
3. Displace hole with 9 ppg mud.
4. Pulled 5-1/2" casing to 197K, w/1/2" stretch. Cut 5-1/2" casing at 1625' with wireline. Work stuck casing with no luck.
5. Pressured up 5-1/2" casing to 1000 psi. No leak off.
6. Spot 25 sx cement plug at 1680'. WOC. Tagged TOC at 1466'.
7. Perfed 4 squeeze holes at 850'. Squeezed 40 sx cement to 500 psi. Tagged TOC at 684'. (8-5/8" casing shoe at 800')
8. Perfed 4 squeeze holes at 60'. Unable to pump in perforations. TIH to 63' and circulate cement to surface.
9. Well plugged and abandoned on 8/27/05.

RECEIVED
SEP 14 2005
ODD-ANTEOIA

Approved as to plugging of the well bore.
Liability under bond is retained until
surface restoration is completed.



14. I hereby certify that the foregoing is true and correct

Signed Ronnie Slack Name Ronnie Slack
Title Engineering Technician

Date SEP 7 2005

(This space for Federal or State Office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any: _____

Accepted for record - NM OCT 17 2005

DEVON ENERGY PRODUCTION COMPANY LP

Well Name: SHUGART 22 FED #2		Field: SHUGART	
Location: 1980' FSL & 1980' FEL; SEC 22-T18S-R31E		County: EDDY	State: NM
Elevation: 3669' KB; 3651' GR		Spud Date: 12/7/97	Compl Date: 2/6/98
API#: 30-015-29907	Prepared by: Ronnie Slack	Date: 8/29/05	Rev:

■ PLUGGED & ABANDONED - 8/27/05

12-1/4" Hole
8-5/8", 24#, K55, @ 800'
 Cmt'd w/395 sxs. Cmt circ to surf.

QUEEN

3350' - 3384' (6/18/04)
 6/23/04: acidized w/2500 gals 15% HCl
 7/17/04: Frac'd w/75K# 16/30

GRAYBURG

3972' - 3975' (6/16/04)
 6/17/05: acidized w/1000 gals, 15% NeFe
 6/17/05: swabbed dry. No show

TOC @ 5200' (cbl 1/5/98)


BRUSHY CANYON

6032' - 6042' (5/8/04)
 6070' - 6090' (5/6/04)
 5/7/04: acidized w/1500 gals, 7-1/2% Pentol
 5/9/04: swabbed all water

BONE SPRING

6490' - 6518' (1/6/98)

7-7/8" Hole
5-1/2", 15.5#, J55, @ 6650'
 Cmt'd w/2330 sxs. TOC @ 5200' (cbl 1/5/98)



1. Perf 4 sqz holes at 60'
 2. Could not pump in perms
 3. TIH to 63' and circulate cement to surface (8/27/05)

1. Perf 4 sqz holes at 850'
 2. Sqz 40 sx cement to 500 psi
 3. Tagged TOC at 684'. (8/27/05)

1. Pull 5-1/2" casing to 197K. 1/2" stretch
 2. Cut 5-1/2" casing at 1625' w/ wireline
 3. Work stuck casing w/ no luck
 4. Pressure up 5-1/2" to 1000 psi. No leak off
 5. Spot 25 sx cement plug at 1680'.
 6. Tagged TOC @ 1466' (8/27/05)

Spot 50' cement on top (8/26/05)
 Set CIBP @ 3300' (8/26/05)

31' cement on top. PBD @ 3839' (6/18/04)
 CIBP @ 3870' (6/18/04)

35' cement on top. PBD @ 5985' (5/10/04)
 CIBP @ 6020' (5/10/04)

35' cement on top. PBD @ 6415' (5/6/04)
 CIBP @ 6450' (5/6/04)

FC @ 6603'

TD @ 6650'