13-74

Form 3160-3
(April 2004)

OCD Artesia

FORM APPROVED
OMB No. 1004-0137
Expires March 31, 2007

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease Serial No.
NMLC-028784C

6. If Indian, Allotee or Tribe Name
N/A

TCS 1/15/2013

1a. Type of work: ☑ DRILL ☐ REENTER

7. If Unit or CA Agreement, Name and No.
NMNM-88525X; Burch Keely Unit

1b. Type of Well: ☑ Oil Well ☐ Gas Well ☐ Other ☐ Single Zone ☐ Multiple Zone

8. Lease Name and Well No. <308086>
Burch Keely Unit #933H

2. Name of Operator
COG Operating LLC <229137>

9. API Well No.
30-015- 40970

3a. Address
One Concho Center 600 W Illinois Ave
Midland, TX 79701

3b. Phone No. *(include area code)*
432-685-4384

10. Field and Pool, or Exploratory <97918>
Burch Keely; Glorieta-Upper Yeso

4. Location of Well *(Report location clearly and in accordance with any State requirements.*)*
At surface **2310' FNL & 330' FWL, Unit E**
At proposed prod. zone **2310' FNL & 330' FEL, Unit H**

11. Sec., T. R. M. or Blk. and Survey or Area
Sec 13 T17S R29E

14. Distance in miles and direction from nearest town or post office*
2 miles from Loco Hills, NM

12. County or Parish
EDDY

13. State
NM

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) **330'**

16. No. of acres in lease
1440

17. Spacing Unit dedicated to this well
160

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. **447'**

19. Proposed Depth
TVD: 4778' MD: 9267'

20. BLM/BIA Bond No. on file
NMB000740; NMB000215

21. Elevations (Show whether DF, KDB, RT, GL, etc.)
3625' GL

22. Approximate date work will start*
10/31/2012

23. Estimated duration
15 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature
Name *(Printed/Typed)* **Kelly J. Holly**
Date **08/29/2012**

Title **Permitting Tech**

Approved by *(Signature)* /s/ James A. Amos
Name *(Printed/Typed)*
Date JAN 8 2013

Title **FIELD MANAGER**
Office **CARLSBAD FIELD OFFICE**

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

Roswell Controlled Water Basin

Approval Subject to General Requirements & Special Stipulations Attached

RECEIVED
JAN 11 2013
NMOCD ARTESIA

SEE ATTACHED FOR CONDITIONS OF APPROVAL

DISTRICT I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
DISTRICT II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
DISTRICT III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
DISTRICT IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, New Mexico 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number	Pool Code	Pool Name
30-015- 40970	97918	Burch Keely; Glorieta Upper Yeso

Property Code	Property Name	Well Number
308086	BURCH KEELY UNIT	933H

OGRID No.	Operator Name	Elevation
229137	COG OPERATING, LLC	3625'

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
E	13	17-S	29-E		2310	NORTH	330	WEST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
H	13	17-S	29-E		2310	NORTH	330	EAST	EDDY

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.
160			

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION





CORNER COORDINATES TABLE

(A) - Y=668722.9 N, X=591219.1 E

(B) - Y=668735.8 N, X=596498.7 E

(C) - Y=667403.3 N, X=591222.1 E

(D) - Y=667417.1 N, X=596503.2 E

OPERATOR CERTIFICATION

I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Signature 8-8-12 Date

Kelly J. Holly
Printed Name

kholly@concho.com
E-mail Address

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

FEBRUARY 13, 2012
Date of Survey

Signature & Seal of Professional Surveyor:

RONALD J. EIDSON NEW MEXICO 3239 REGISTERED PROFESSIONAL SURVEYOR

Ronald J Eidson 08/03/2012

Certificate Number	Gary O. Eidson	12641
	Ronald J. Eidson	3239

DSR Rel.W.O.: 12.13.1105 WSC W.O.: 12.13.1385

I hereby certify that I, or persons under my direct supervision, have inspected the drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements make in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or COG Operating, LLC, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 7th day of March, 2012.

Signed: Carl Bird

Printed Name: Carl Bird

Position: Drilling Engineer

Address: One Concho Center, 600 W Illinois, Midland, Texas 79701

Telephone: (432) 683-7443

Field Representative (if not above signatory): Same

E-mail: cbird@conchoresources.com

ATTACHMENT TO FORM 3160-3
COG Operating, LLC
BURCH KEELY UNIT # 933H
SHL: 2310' FNL & 330' FWL, UNIT E
BHL: 2310' FNL & 330' FEL, Unit H
Sec 13, T17S, R29E
Eddy County, NM

1. Proration Unit Spacing: 160 Acres

2. Ground Elevation: 3625'

3. Proposed Depths: Horizontal: **EOC (end of curve) TVD=4850' MD= 5131'**
Toe (end of lateral) TVD=4778' MD 9267'

4. Estimated tops of geological markers:

Rustler	240'
Top of Salt	449'
Base of Salt	880'
Yates	1056'
Seven Rivers	1344'
Queen	1952'
Grayburg	2352'
San Andres	2657'
Glorieta	4054'
Paddock	4151'
Blinebry	4560'
Tubb	5728'

5. Possible mineral bearing formations:

Water Sand	110'	Fresh Water
Grayburg	2352'	
San Andres	2657'	
Glorieta	4054'	
Paddock	4151'	
Blinebry	4560'	
Tubb	5728	

No other formations are expected to give up oil, gas or fresh water in measurable quantities. Setting 13 3/8" casing to 265' (25' into Rustler) and circulating cement back to the surface will protect the surface fresh water sand. The Salt Section will be protected by setting 9 5/8" casing to 1100' and circulating cement back to surface in a single or multi-stage job and/or with an ECP. Any shallower zones above TD, which contain commercial quantities of oil and/or gas, will have cement circulated across them. This will be achieved by cementing 7" x 5 ½" tapered production casing from the TD to surface in two stages with DV Tool and ECP set at KOP. At KOP the production casing string will crossover from 7" to 5 ½". First stage will be from TD to KOP and second stage will be from KOP to surface. If wellbore conditions arise that require immediate action and/or a change to this program, COG Operating LLC personnel will always react to protect the wellbore and/or environment. See COA

6. Proposed Mud System

The well will be drilled to TD with a combination of fresh water, brine, cut brine and polymer mud systems. The applicable depths and properties of these systems are as follows:

DEPTH (MD)	TYPE	WEIGHT	VISCOSITY	WATERLOSS
0-265' 295'	Fresh Water	8.5	28	N.C.
295' 265'-1100'	Brine	10	30	N.C.
1100'-4373'	Cut Brine	8.7-9.2	30	N.C.
4373'-5131'	Cut Brine/polymer mud	8.7-9.2	30	N.C.
5131'-9267'	Cut Brine/polymer mud	8.7-9.2	30	N.C.

Sufficient mud materials will be kept at the well site to maintain mud properties and meet minimum lost circulation and weight increase requirements at all times.

See COA

6. Proposed Casing Program

Hole Size	Interval MD	OD Casing	Weight	Grade	Condition	Jt.	brst/clps/ten
17 ½"	0-265' 295	13 3/8"	48#	H-40/J-55 Hybrid	New	ST&C	6.52/6.58/29.1
12 ¼"	0 265'-1100'	9 5/8"	40#	J/K-55	New	ST&C	3.59/4.49/13.90
8 ¾"	0 1100'-4373'	7"	26#	L-80	New	LT&C	1.45/2.59/5.23
8 ¾"	4373'-5131'	5 ½"	17#	L-80	New	LT&C	1.55/2.64/4.65
7 7/8"	5131'-9267'	5 ½"	17#	L-80	New	LT&C	1.55/2.64/4.65

Production string will be a tapered string with 7" 26# L-80 LTC run from surface to kick off point (4373') and then crossed over to 5 ½" 17# L-80 LTC.

7. Proposed Cement Program See COA

13 3/8" SURFACE: (Circulate to Surface)

Lead: 0'-265' Excess 141%	400 sks	Class "C" w/2% CaCl2+ 0.25 pps CF	1.32 cf/sk	14.8 ppg

9 5/8" INTERMEDIATE:

Option #1: Single Stage (Circulate to Surface)

Lead: 0'-800' Excess 83%	200 sks	50:50:10 C:Poz:Gel w/ 5% Salt+ 0.25% CF +5 pps LCM	2.45 cf/sk	11.8 ppg
Tail: 800'-1100' Excess 164%	200 sks	Class C w/2% CaCl2	1.32 cf/sk	14.8 ppg

Option #2: Multi-stage w/ DV Tool @ +/-315'(DV Tool 50' below 13 3/8" csg. Shoe) (Circulate to Surface)

Stage #1: Lead: 315'-800' Excess 222%	200 sks	50:50:10 C:Poz:Gel w/5% Salt +5 pps LCM + 0.25 pps CF	2.45 cf/sk	11.8 ppg
Tail: 800'-1100' Excess 180%	200 sks	Class "C" w/2% CaCl2	1.32 cf/sk	14.8 ppg
Stage #2 0'-315' Excess 322%	200 sks	50:50:10 C:Poz:Gel w/5% salt+ 5 pps LCM + 0.25 pps CF	2.45 cf/sk	11.8 ppg

Note: Multi-stage tool to be set depending on hole conditions at approximately 315' (50' below the surface casing shoe). Cement volumes will be adjusted proportionately for depth changes of multi-stage tool.

7" X 5 ½" TAPERED PRODUCTION CASING:

Option #1: Single Stage (Cement cal to surface)

1st Lead: 0'-2900' Excess 81%	400 sks	35:65:6 C:Poz Gel w/5% salt+ 5 pps LCM+ 0.2 % SMS+ 0.3% FL-52A+ 0.125 pps CF	2.05 cf/sk	12.5 ppg
2nd Lead: 2900'-4373' Excess 143%	400 sks	50:50:2 C:Poz Gel w/5% salt+ 3 pps LCM+ 0.6 % SMS+ 0.125 pps CF+1% FL-25+ 1% BA-58	1.37 cf/sk	14.0 ppg
Tail: 4373'-9267' Excess 27%	725 sks	Class "H" SOLUCEM-H w/0.7% HR-601	2.62 cf/sk	15.0 ppg

Option #2:Multi-stage (2 Stages) w/DV Tool & ECP@ +/-4373'
(Cement calculated to surface)

Stage #1:

Tail: 4373'-9267' Excess 27%	725 sks	Class "H" SOLUCEM-H w/0.7% HR-601	2.62 cf/sk	15.0 ppg

Stage #2: 2nd DV Tool & ECP @ +/-4373'

Lead: 0'-2000' Excess 248%	525 sks	35:65:6 C:Poz Gel w/5% salt+ 5 pps LCM+ 0.2 % SMS+ 0.3% FL-52A+ 0.125 pps CF	2.05 cf/sk	12.5 ppg
Tail: 2000'-4373' Excess 33%	400 sks	50:50:2 C:Poz Gel w/5% salt+ 3 pps LCM+ 0.6 % SMS+ 0.125 pps CF+1% FL-25+ 1% BA-58	1.37 cf/sk	14.0 ppg

Note: 5 ½" casing will be run from KOP at 4373' thru curve and lateral to TD of 9267' MD. Productive intervals will be isolated by cement as described above..

Note: FL-52A is fluid loss additive, R-3 is retarder.

Note: Multi-stage tool & ECP to be set depending on hole conditions at approximately 4373.' Cement volumes will be adjusted proportionately for depth changes of multi-stage tool.

8. Pressure Control Equipment:

The blowout preventer equipment (BOP) shown in Exhibit #9 will consist of a double ram-type (2000 psi WP) preventer, and in some cases possibly a 2000 psi Hydril type annular preventer as provided for in Onshore Order #2. This unit will be hydraulically operated and the ram type preventer will be equipped with blind rams on top and 4 1/2" drill pipe rams on the bottom. A 13-5/8" BOP will be used during the drilling of the well. A 13 5/8" permanent casing head will be installed on the 13 3/8" casing. The BOP will be nippled up on the 13 5/8" permanent casing head and tested to 2000 psig. After setting 9-5/8", permanent "B section" well head will be installed and the BOP will then be nippled up on the permanent B . BOP and well head will be tested by a third party to 2000 psig and used continuously until total depth is reached. Pipe rams will be operationally checked each 24-hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve, choke lines and a choke manifold with a 2000 psi WP rating all of which will also be tested to working pressure by independent tester also.

9. Production Hole Drilling Summary:

Drill 8¾" hole to 4373'. Kick off at +/- 4373', building curve at 12°/100' over +/- 758' to horizontal at 5131' MD/4850'TVD. Reduce hole size and drill 7 7/8" lateral section in a easterly direction for +/4135' lateral to TD at +/-9267' MD, 4778' TVD. Run 7" x 5-1/2" production casing. 7" to be run from surface to kickoff point and then changed over to 5 ½". 5 ½" casing will be run from kickoff point to td and both strings will be isolated by either a single stage or multi-stage cement jobs Cement will be circulated to surface.

10. Auxiliary Well Control and Monitoring Equipment

A. Kelly cock will be kept in the drill string at all times.

B. A full opening drill pipe-stabbing valve with proper drill pipe connections will be on the rig floor at all times.

11. Logging, Testing and Coring Program: See COA

A. The following logs will be run in the vertical portion of the hole to KOP: SLB-PEX/HRLA,HNGS.

B. The mud logging program will consist of lagged 10' samples from KOP to TD in Horizontal hole.

C. Drill Stem test is not anticipated.

D. No conventional coring is anticipated.

E. Further testing procedures will be determined after the 7" x 5 ½" production casing has been cemented at TD based on drill shows and log evaluation.

12. Abnormal Conditions, Pressures, Temperatures and Potential Hazards:

No abnormal pressures or temperatures are anticipated. The estimated bottom hole temperature at TD is 90° Fahrenheit and estimated maximum bottom hole pressure is 2134 psi. Wells in the Empire area will penetrate formations that are known or could reasonably be expected to contain Hydrogen Sulfide. Measurable gas volumes or Hydrogen Sulfide levels have not been encountered during drilling operations in this area, However as per Onshore order No. 6 a H2S drilling operations plan is included with this APD. No major loss circulation zones have been reported in offsetting wells.

13. Anticipated Starting Date

Drilling operations will commence approximately on approximately December ***15, 2012*** with drilling and completion operations lasting approximately ***90*** days.

COG Operating LLC

Eddy County, NM
Burch Keely Unit 933H
Burch Keely Unit 933H

Wellbore #1

Plan: Plan #1

Standard Planning Report

20 August, 2012

Database:	Houston R5000 Database	**Local Co-ordinate Reference:**	Site Burch Keely Unit 933H
Company:	COG Operating LLC	**TVD Reference:**	WELL @ 3643.00ft (Silver Oak #8)
Project:	Eddy County, NM	**MD Reference:**	WELL @ 3643.00ft (Silver Oak #8)
Site:	Burch Keely Unit 933H	**North Reference:**	Grid
Well:	Burch Keely Unit 933H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #1		

Project	Eddy County, NM		
Map System:	US State Plane 1927 (Exact solution)	**System Datum:**	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site	Burch Keely Unit 933H				
Site Position:		**Northing:**	667,733.80 ft	**Latitude:**	32.835328
From:	Map	**Easting:**	591,551.30 ft	**Longitude:**	-104.035272
Position Uncertainty:	0.00 ft	**Slot Radius:**	13.200 in	**Grid Convergence:**	0.16 °

Well	Burch Keely Unit 933H					
Well Position	**+N/-S**	0.00 ft	**Northing:**	667,733.80 ft	**Latitude:**	32.835328
	+E/-W	0.00 ft	**Easting:**	591,551.30 ft	**Longitude:**	-104.035272
Position Uncertainty		0.00 ft	**Wellhead Elevation:**		**Ground Level:**	3,625.00 ft

Wellbore	Wellbore #1				
Magnetics	**Model Name**	**Sample Date**	**Declination (°)**	**Dip Angle (°)**	**Field Strength (nT)**
	IGRF2010	3/28/2012	7.75	60.65	48,853

Design	Plan #1				
Audit Notes:					
Version:		**Phase:**	PLAN	**Tie On Depth:**	0.00
Vertical Section:	**Depth From (TVD) (ft)**	**+N/-S (ft)**	**+E/-W (ft)**	**Direction (°)**	
	0.00	0.00	0.00	89.87	

Plan Sections

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,372.60	0.00	0.00	4,372.60	0.00	0.00	0.00	0.00	0.00	0.00	
5,130.94	91.00	89.87	4,850.00	1.11	485.80	12.00	12.00	0.00	89.87	
9,266.58	91.00	89.87	4,777.82	10.60	4,620.80	0.00	0.00	0.00	0.00	PBHL (Burch Keely U

Database:	Houston R5000 Database	**Local Co-ordinate Reference:**	Site Burch Keely Unit 933H
Company:	COG Operating LLC	**TVD Reference:**	WELL @ 3643.00ft (Silver Oak #8)
Project:	Eddy County, NM	**MD Reference:**	WELL @ 3643.00ft (Silver Oak #8)
Site:	Burch Keely Unit 933H	**North Reference:**	Grid
Well:	Burch Keely Unit 933H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,372.60	0.00	0.00	4,372.60	0.00	0.00	0.00	0.00	0.00	0.00
KOP - Start Build @ 12.00°/100'									
4,400.00	3.29	89.87	4,399.99	0.00	0.79	0.79	12.00	12.00	0.00
4,500.00	15.29	89.87	4,498.49	0.04	16.89	16.89	12.00	12.00	0.00
4,600.00	27.29	89.87	4,591.50	0.12	53.13	53.13	12.00	12.00	0.00
4,700.00	39.29	89.87	4,674.94	0.25	107.92	107.92	12.00	12.00	0.00
4,800.00	51.29	89.87	4,745.17	0.41	178.85	178.85	12.00	12.00	0.00
4,900.00	63.29	89.87	4,799.11	0.60	262.84	262.84	12.00	12.00	0.00
5,000.00	75.29	89.87	4,834.41	0.82	356.20	356.20	12.00	12.00	0.00
5,100.00	87.29	89.87	4,849.53	1.04	454.87	454.87	12.00	12.00	0.00
5,130.94	91.00	89.87	4,850.00	1.11	485.80	485.80	12.00	12.00	0.00
Landing Point - Hold @ 91.00° INC, 89.87° AZ									
5,200.00	91.00	89.87	4,848.79	1.27	554.85	554.85	0.00	0.00	0.00
5,300.00	91.00	89.87	4,847.05	1.50	654.83	654.83	0.00	0.00	0.00
5,400.00	91.00	89.87	4,845.30	1.73	754.82	754.82	0.00	0.00	0.00
5,500.00	91.00	89.87	4,843.56	1.96	854.80	854.80	0.00	0.00	0.00
5,600.00	91.00	89.87	4,841.81	2.19	954.79	954.79	0.00	0.00	0.00
5,700.00	91.00	89.87	4,840.07	2.42	1,054.77	1,054.77	0.00	0.00	0.00
5,800.00	91.00	89.87	4,838.32	2.65	1,154.75	1,154.76	0.00	0.00	0.00
5,900.00	91.00	89.87	4,836.58	2.88	1,254.74	1,254.74	0.00	0.00	0.00
6,000.00	91.00	89.87	4,834.83	3.11	1,354.72	1,354.73	0.00	0.00	0.00
6,100.00	91.00	89.87	4,833.08	3.34	1,454.71	1,454.71	0.00	0.00	0.00
6,200.00	91.00	89.87	4,831.34	3.57	1,554.69	1,554.70	0.00	0.00	0.00
6,300.00	91.00	89.87	4,829.59	3.80	1,654.68	1,654.68	0.00	0.00	0.00
6,400.00	91.00	89.87	4,827.85	4.03	1,754.66	1,754.67	0.00	0.00	0.00
6,500.00	91.00	89.87	4,826.10	4.25	1,854.65	1,854.65	0.00	0.00	0.00
6,600.00	91.00	89.87	4,824.36	4.48	1,954.63	1,954.64	0.00	0.00	0.00
6,700.00	91.00	89.87	4,822.61	4.71	2,054.62	2,054.62	0.00	0.00	0.00
6,800.00	91.00	89.87	4,820.87	4.94	2,154.60	2,154.61	0.00	0.00	0.00
6,900.00	91.00	89.87	4,819.12	5.17	2,254.58	2,254.59	0.00	0.00	0.00
7,000.00	91.00	89.87	4,817.38	5.40	2,354.57	2,354.57	0.00	0.00	0.00
7,100.00	91.00	89.87	4,815.63	5.63	2,454.55	2,454.56	0.00	0.00	0.00
7,200.00	91.00	89.87	4,813.89	5.86	2,554.54	2,554.54	0.00	0.00	0.00
7,300.00	91.00	89.87	4,812.14	6.09	2,654.52	2,654.53	0.00	0.00	0.00
7,400.00	91.00	89.87	4,810.40	6.32	2,754.51	2,754.51	0.00	0.00	0.00
7,500.00	91.00	89.87	4,808.65	6.55	2,854.49	2,854.50	0.00	0.00	0.00
7,600.00	91.00	89.87	4,806.91	6.78	2,954.48	2,954.48	0.00	0.00	0.00
7,700.00	91.00	89.87	4,805.16	7.01	3,054.46	3,054.47	0.00	0.00	0.00
7,800.00	91.00	89.87	4,803.42	7.24	3,154.44	3,154.45	0.00	0.00	0.00
7,900.00	91.00	89.87	4,801.67	7.47	3,254.43	3,254.44	0.00	0.00	0.00
8,000.00	91.00	89.87	4,799.93	7.69	3,354.41	3,354.42	0.00	0.00	0.00
8,100.00	91.00	89.87	4,798.18	7.92	3,454.40	3,454.41	0.00	0.00	0.00
8,200.00	91.00	89.87	4,796.43	8.15	3,554.38	3,554.39	0.00	0.00	0.00
8,300.00	91.00	89.87	4,794.69	8.38	3,654.37	3,654.38	0.00	0.00	0.00
8,400.00	91.00	89.87	4,792.94	8.61	3,754.35	3,754.36	0.00	0.00	0.00
8,500.00	91.00	89.87	4,791.20	8.84	3,854.34	3,854.35	0.00	0.00	0.00
8,600.00	91.00	89.87	4,789.45	9.07	3,954.32	3,954.33	0.00	0.00	0.00
8,700.00	91.00	89.87	4,787.71	9.30	4,054.31	4,054.32	0.00	0.00	0.00
8,800.00	91.00	89.87	4,785.96	9.53	4,154.29	4,154.30	0.00	0.00	0.00
8,900.00	91.00	89.87	4,784.22	9.76	4,254.27	4,254.29	0.00	0.00	0.00
9,000.00	91.00	89.87	4,782.47	9.99	4,354.26	4,354.27	0.00	0.00	0.00
9,100.00	91.00	89.87	4,780.73	10.22	4,454.24	4,454.26	0.00	0.00	0.00
9,200.00	91.00	89.87	4,778.98	10.45	4,554.23	4,554.24	0.00	0.00	0.00

Database:	Houston R5000 Database	**Local Co-ordinate Reference:**	Site Burch Keely Unit 933H
Company:	COG Operating LLC	**TVD Reference:**	WELL @ 3643.00ft (Silver Oak #8)
Project:	Eddy County, NM	**MD Reference:**	WELL @ 3643.00ft (Silver Oak #8)
Site:	Burch Keely Unit 933H	**North Reference:**	Grid
Well:	Burch Keely Unit 933H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
9,266.58	91.00	89.87	4,777.82	10.60	4,620.80	4,620.81	0.00	0.00	0.00

TD @ 9266.58' MD, 4777.82' TVD - PBHL (Burch Keely Unit 13 Federal 4H Plan 1)

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
PBHL (Burch Keely Unit - plan hits target center - Point	0.00	0.00	4,777.82	10.60	4,620.80	667,744.40	596,172.10	32.835320	-104.020228

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	Local Coordinates +E/-W (ft)	Comment
4,372.60	4,372.60	0.00	0.00	KOP - Start Build @ 12.00°/100'
5,130.94	4,850.00	1.11	485.80	Landing Point - Hold @ 91.00° INC, 89.87° AZ
9,266.58	4,777.82	10.60	4,620.80	TD @ 9266.58' MD, 4777.82' TVD

COG Operating LLC
Burch Keely Unit 933H
Eddy County, NM
Plan #1

Surface Location		Ground Elev: 3625.00 WELL @ 3643.00ft (Silver Oak #8)			
+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	667733.80	591551.30	32.835328	-104.035272

TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
PBHL (Burch Keely Unit 13 Federal 4H Plan 1)	4777.82	10.60	4620.80	667744.40	596172.10	32.835320	-104.020228



Azimuths to Grid North
True North: -0.16°
Magnetic North: 7.59°

Magnetic Field
Strength: 48852.8snT
Dip Angle: 60.65°
Date: 3/28/2012
Model: IGRF2010





SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Annotation
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2	4372.60	0.00	0.00	4372.60	0.00	0.00	0.00	0.00	0.00	KOP - Start Build @ 12.00°/100'
3	5130.94	91.00	89.87	4850.00	1.11	485.80	12.00	89.87	485.80	Landing Point - Hold @ 91.00° INC, 89.87° AZ
4	9266.58	91.00	89.87	4777.82	10.60	4620.80	0.00	0.00	4620.81	TD @ 9266.58' MD, 4777.82' TVD

13 5/8" 2K ANNULAR



COG Operating LLC

Exhibit #9

BOPE and Choke Schematic



Minimum 4" Nominal choke and kill lines

Choke Manifold Requirement (2000 psi WP)
No Annular Required



Adjustable Choke
(or Positive)

NOTES REGARDING THE BLOWOUT PREVENTERS
Master Drilling Plan
Eddy County, New Mexico

1. Drilling nipple to be so constructed that it can be removed without use of a welder through rotary table opening, with minimum I.D. equal to preventer bore.
2. Wear ring to be properly installed in head.
3. Blow out preventer and all fittings must be in good condition, 2000 psi WP minimum.
4. All fittings to be flanged.
5. Safety valve must be available on rig floor at all times with proper connections, valve to be full 2000 psi WP minimum.
6. All choke and fill lines to be securely anchored especially ends of choke lines.
7. Equipment through which bit must pass shall be at least as large as the diameter of the casing being drilled through.
8. Kelly cock on Kelly.
9. Extension wrenches and hands wheels to be properly installed.
10. Blow out preventer control to be located as close to driller's position as feasible.
11. Blow out preventer closing equipment to include minimum 40-gallon accumulator, two independent sources of pump power on each closing unit installation all API specifications.

COG Operating LLC

Closed Loop Equipment Diagram



COG Operating LLC

Hydrogen Sulfide Drilling Operation Plan

I. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards an characteristics of hydrogen sulfide (H2S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H2S detectors alarms warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H2S on metal components. If high tensile tubular are to be used, personnel well be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H2S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H2S zone (within 3 days or 500 feet) and weekly H2S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H2S Drilling Operations Plan and the Public Protection Plan. **The concentrations of H2S of wells in this area from surface to TD are low enough that a contingency plan is not required.**

II. H2S SAFETY EQUIPMENT AND SYSTEMS

Note: All H2S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonable expected to contain H2S.

1. **Well Control Equipment:**

   A. Flare line.

   B. Choke manifold.

   C. Closed Loop Blow Down Tank

   D. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.

   E. Auxiliary equipment may include if applicable: annular preventer & rotating head.

2. **Protective equipment for essential personnel:**

   A. SCBA (Self contained breathing apparatus) 30-minute units located in the doghouse and at briefing areas, as indicated on well site diagram.

3. **H2S detection and monitoring equipment:**

   A. Portable H2S monitors positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 PPM are reached.

4. **Visual warning systems:**

   A. Wind direction indicators as shown on well site diagram.

   B. Caution/Danger signs (Exhibit #7) shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.

5. **Mud program:**

   A. The mud program has been designed to minimize the volume of H2S circulated to surface. Proper mud weight, safe drilling practices, and the use of H2S scavengers will minimize hazards when penetrating H2S bearing zones.

6. **Metallurgy:**

   A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.

   B. All elastomers used for packing and seals shall be H2S trim.

7. **Communication:**

   A. Radio communications in company vehicles including cellular telephone and 2-way radio.

   B. Land line (telephone) communication at Office.

8. **Well testing:**

   A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safely and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H2S environment will use the closed chamber method of testing.

   B. There will be no drill stem testing.

EXHIBIT #7

WARNING

YOU ARE ENTERING AN H2S

AUTHORIZED PERSONNEL ONLY

1. **BEARDS OR CONTACT LENSES NOT ALLOWED**
2. **HARD HATS REQUIRED**
3. **SMOKING IN DESIGNATED AREAS ONLY**
4. **BE WIND CONSCIOUS AT ALL TIMES**
5. **CHECK WITH COG OPERATING FOREMAN AT**

COG OPERATING LLC
1-432-683-7443
1-575-746-2010

EDDY COUNTY EMERGENCY NUMBERS
ARTESIA FIRE DEPT. 575-746-5050
ARTESIA POLICE DEPT. 575-746-5000
EDDY CO. SHERIFF DEPT. 575-746-9888

LEA COUNTY EMERGENCY NUMBERS
HOBBS FIRE DEPT. 575-397-9308
HOBBS POLICE DEPT. 575-397-9285
LEA CO. SHERIFF DEPT. 575-396-1196

COG Operating LLC

Drilling Location - H2S Safety Equipment Diagram

EXHIBIT 8-
BKU 933H




320
60' will be reclaimed on motor side of pad
N
anchor
anchor
Stinger removed
Well Head
300
30' x30' Stinger
anchor
anchor
Road Access through existing lease road
This are will be reclaimed to the anchors on trailer side. This area will be reclaimed towards the wellhead.
Not To Scale
COG OPERATING LLC
Rig Layout Closed Loop
Interim reclamation plat

PECOS DISTRICT
CONDITIONS OF APPROVAL

OPERATOR'S NAME:	COG OPERATING, LLC
LEASE NO.:	LC028784C
WELL NAME & NO.:	933H-BURCH KEELY UNIT
SURFACE HOLE FOOTAGE:	2310'/N. & 330'/W.
BOTTOM HOLE FOOTAGE	2310'/N. & 330'/E.
LOCATION:	Section 13, T. 17 S., R. 29 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.