

ced Artesia

TES  
6/10/2013

FORM APPROVED  
OMB No. 1004-0137  
Expires July 31, 2010

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM-117806
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator LIME ROCK RESOURCES II-A, L.P.		7. If Unit or CA Agreement, Name and No.
3a. Address 1111 BAGBY ST., STE 4600 HOUSTON, TX 77002	3b. Phone No. (include area code) 713-292-9526	8. Lease Name and Well No. LOGAN 35 K FEDERAL 15
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface 1650' FSL & 2460' FWL At proposed prod. zone 1650' FSL & 2310' FWL		9. API Well No. 30-015-41434
14. Distance in miles and direction from nearest town or post office* 7 miles southeast of Artesia, NM		10. Field and Pool, or Exploratory RED LAKE; GLORIETA-YESO NE
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 306'	16. No. of acres in lease 160	11. Sec., T. R. M. or Blk. and Survey or Area UNIT K - SEC. 35 - T17S - R27E
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 159'	19. Proposed Depth MD 3920' TVD 3900'	12. County or Parish EDDY
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3626'	22. Approximate date work will start* 08/17/2013	13. State NM
23. Estimated duration 2-3 WEEKS		

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, must be attached to this form:

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification   |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM.             |

25. Signature <i>Lisa Barfield</i>	Name (Printed/Typed) LISA BARFIELD dba PETRO ENERGY GROUP	Date 4/22/2013
------------------------------------	--	-------------------

Title  
POA AGENT FOR LIME ROCK RESOURCES II-A, L.P.

Approved by (Signature) <i>/s/George MacDonell</i>	Name (Printed/Typed) <i>/s/George MacDonell</i>	Date JUN - 4 2013
Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

Roswell Controlled Water Basin

Approval Subject to General Requirements  
& Special Stipulations Attached

SEE ATTACHED FOR  
CONDITIONS OF APPROVAL

District I  
1625 N. French Dr., Hobbs, NM 88240  
District II  
1301 W. Grand Avenue, Artesia, NM 88210  
District III  
1000 Rio Brazos Rd., Aztec, NM 87410  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico  
Energy, Minerals & Natural Resources Department  
**OIL CONSERVATION DIVISION**  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Form C-102  
Revised October 15, 2009  
Submit one copy to appropriate  
District Office  
☐ AMENDED REPORT

**WELL LOCATION AND ACREAGE DEDICATION PLAT**

API Number <b>30-015-41434</b>	Pool Code <b>96836</b>	Pool Name <b>RED LAKE; GLORIETA-YESO NE</b>
Property Code <b>39943</b>	Property Name <b>LOGAN "35" K FEDERAL</b>	Well Number <b>15</b>
OGRID No. <b>277558</b>	Operator Name <b>LIME ROCK RESOURCES II A, LP</b>	Elevation <b>3625.9</b>

**10 Surface Location**

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
K	35	17 S	27 E		1650	SOUTH	2460	WEST	EDDY

**11 Bottom Hole Location If Different From Surface**


UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
K	35	17 S	27 E		1650	SOUTH	2310	WEST	EDDY

12 Dedicated Acres	13 Joint or Infill	14 Consolidation Code	15 Order No.
40			

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

<p>N89°00'58"W 2662.25 FT N89°02'08"W 2661.90 FT</p> <p>NW CORNER SEC. 35 LAT. = 32.7980625°N LONG. = 104.2575237°W</p> <p>N/4 CORNER SEC. 35 LAT. = 32.7979313°N LONG. = 104.2488634°W</p> <p>NE CORNER SEC. 35 LAT. = 32.7978019°N LONG. = 104.2402042°W</p> <p>NOTE: LATITUDE AND LONGITUDE COORDINATES ARE SHOWN USING THE NORTH AMERICAN DATUM OF 1927 (NAD27), AND ARE IN DECIMAL DEGREE FORMAT.</p> <p>W/4 CORNER SEC. 35 LAT. = 32.7906862°N LONG. = 104.2574077°W</p> <p>E/4 CORNER SEC. 35 LAT. = 32.7905650°N LONG. = 104.2401940°W</p> <p>SW CORNER SEC. 35 LAT. = 32.7833025°N LONG. = 104.2572947°W</p> <p>S/4 CORNER SEC. 35 LAT. = 32.7833129°N LONG. = 104.2487387°W</p> <p>SE CORNER SEC. 35 LAT. = 32.7833252°N LONG. = 104.2401842°W</p>			<p><b>17 OPERATOR CERTIFICATION</b> I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p><i>Lisa Barfield</i> 7/22/2012 Signature Date Printed Name <b>LISA BARFIELD</b></p> <p><b>18 SURVEYOR CERTIFICATION</b> I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>MARCH 24 2012 Date of Survey <i>[Signature]</i> Signature and Seal of Professional Surveyor Certificate Number <b>RAMON F. JARAMILLO, PLS 12797</b> SURVEY NO. 826</p>		
<p>500°48'08"E 2684.44 FT</p> <p>500°46'56"E 2687.16 FT</p> <p>500°07'08"W 2633.49 FT</p> <p>500°06'57"W 2634.57 FT</p> <p>500°52'25"E 2630.21 FT</p> <p>500°51'15"E 2629.71 FT</p> <p>2460' 2310'</p> <p>BOTTOM OF HOLE</p> <p>SURFACE LOCATION</p> <p>LOGAN "35" K FEDERAL #15 ELEV. = 3625.9' LAT. = 32.7878463°N (NAD27) LONG. = 104.2493608°W</p> <p>BOTTOM OF HOLE LAT. = 32.7878456°N LONG. = 104.2498489°W</p>					

SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
LOCATION VERIFICATION MAP



USGS QUAD MAP:  
RED LAKE  
SPRING LAKE

NOT TO SCALE


LIME ROCK RESOURCES II A, LP  
LOGAN "35" K FEDERAL #15  
LOCATED 1650 FT. FROM THE SOUTH LINE  
AND 2460 FT. FROM THE WEST LINE OF  
SECTION 35, TOWNSHIP 17 SOUTH,  
RANGE 27 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO

MARCH 24, 2012

SURVEY NO. 826

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO  
(575) 234-3341

SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
VICINITY MAP



NOT TO SCALE


LIME ROCK RESOURCES II A, LP  
LOGAN "35" K FEDERAL #15  
LOCATED 1650 FT. FROM THE SOUTH LINE  
AND 2460 FT. FROM THE WEST LINE OF  
SECTION 35, TOWNSHIP 17 SOUTH,  
RANGE 27 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO

MARCH 24, 2012

SURVEY NO. 826

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO  
(575) 234-3341

SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
AERIAL PHOTO



**NOT TO SCALE  
AERIAL PHOTO:  
GOOGLE EARTH  
JULY 2011**

**LIME ROCK RESOURCES II A, LP  
LOGAN "35" K FEDERAL #15  
LOCATED 1650 FT. FROM THE SOUTH LINE  
AND 2460 FT. FROM THE WEST LINE OF  
SECTION 35, TOWNSHIP 17 SOUTH,  
RANGE 27 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO**

**MARCH 24, 2012**


*SURVEY NO. 826*

**MADRON SURVEYING, INC.** 301 SOUTH CANAL CARLSBAD, NEW MEXICO  
(575) 234-3341

301 SOUTH CANA  
(575) 234-3341

**SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO**

NOTE: THE LATITUDE AND LONGITUDE COORDINATES ARE SHOWN USING THE NORTH AMERICAN DATUM OF 1927 (NAD27), AND ARE IN DECIMAL DEGREE FORMAT.



010 50 100 200

SCALE 1" = 100'

**DIRECTIONS TO LOCATION**

FROM PAVED CR. 225 (EMPIRE) AND PAVED CR. 228 (EVANS)  
GO NORTH-NORTHEAST ON CR. 225 265' TURN LEFT ON CALICHE  
ROAD AND GO NORTHWEST 369' AND LOCATION IS NORTHWEST 45'


**LIME ROCK RESOURCES II A, LP  
LOGAN "35" K FEDERAL #15  
LOCATED 1650 FT. FROM THE SOUTH LINE  
AND 2460 FT. FROM THE WEST LINE OF  
SECTION 35, TOWNSHIP 17 SOUTH,  
RANGE 27 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO**

MARCH 24, 2012

SURVEY NO. 826

**MADRON SURVEYING, INC.** 301 SOUTH CANAL (575) 234-3341 **CARLSBAD, NEW MEXICO**

**SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO**



Directions to location:

From paved County Rd 225 (Empire) and paved County Rd 226 (Evans), go North-Northeast on County 225 265'. Turn left on Caliche Road and go Northwest 369' and location is Northwest 45'.

NOT TO SCALE - ONE SQUARE ON THE MAP MEASURES 3 MILES X 3 MILES

**WELL COORDINATES:**

LAT. = 32.7878463N  
LONG. = 104.2493608 W  
(NAD 27- SEE NOTE)

NOTE: THE LATITUDE AND LONGITUDE COORDINATES ARE SHOWN USING THE NORTH AMERICAN DATUM OF 1927 (NAD 27) AND ARE IN DECIMAL DEGREE FORMAT.

**LEASE**

LOGAN "35" K FEDERAL #15

COUNTY/PARISH AND STATE  
EDDY COUNTY NEW MEXICO

SURVEY INFORMATION  
MADRON SURVEYING, INC.  
CARLSBAD, NEW MEXICO  
SURVEY NO. 826. 3/24/2012

Client

**Lime Rock Resources II-A, L.P.**

Title

**LOGAN "35" K FEDERAL #15**

LOCATED 1650 FT. FROM THE SOUTH LINE AND 2460 FT. FROM THE WEST LINE OF SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27 EAST, N.M.P.M. EDDY COUNTY, STATE OF NEW MEXICO


Petro Energy Group  
12777 Jones Road,  
Suite 385,  
Houston, TX 77070  
Tel. 281 890 1818

SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO

WELL COORDINATES:  
LAT. = 32.7878463° N  
LONG. = 104.2493608° W  
(NAD 27 - SEE NOTE)

NOTE: THE LATITUDE AND LONGITUDE  
COORDINATES ARE SHOWN USING THE  
NORTH AMERICAN DATUM OF 1927 (NAD27)  
AND ARE IN DECIMAL DEGREE FORMAT.



Directions to Location:

From paved County Road 225 (Empire) and paved County Road 226 (Evans), go North-Northeast on County 225 265 feet. Turn left on Caliche Road and go Northwest 369 feet and location is Northwest 45 feet.



12777 Jones Road,  
Suite 385,  
Houston TX 77070  
Tel. 281 890 1818  
www.peg-us.com

LEASE  
LOGAN "35" K FEDERAL #15  
COUNTY / PARISH AND STATE  
EDDY COUNTY NEW MEXICO

SURVEY INFORMATION  
MADRON SURVEYING, INC.  
CARLSBAD, NEW MEXICO  
SURVEY NO. 826. 3/24/2012  
DRAWING NO. AND REVISION  
2013-LR-L35K-15-004  
REV. 1

CLIENT

**Lime Rock Resources II-A, L.P.**

TITLE

**LOGAN "35" K FEDERAL #15**

LOCATED 1650 FT. FROM THE SOUTH LINE AND 2460 FT. FROM THE  
WEST LINE OF SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27  
EAST, N.M.P.M. EDDY COUNTY STATE OF NEW MEXICO


NOT TO SCALE

**SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27 EAST, N.M.P.M.**

**EDDY COUNTY, STATE OF NEW MEXICO**

WELL COORDINATES:  
LAT. = 32.7878463° N  
LONG. = 104.2493608° W  
(NAD 27 - SEE NOTE)

NOTE: THE LATITUDE AND LONGITUDE  
COORDINATES ARE SHOWN USING THE  
NORTH AMERICAN DATUM OF 1927 (NAD27)  
AND ARE IN DECIMAL DEGREE FORMAT.



**Directions to Location:**

From paved County Road 225 (Empire) and paved County Road 226 (Evans), go North-Northeast on County 225 265 feet. Turn left on Caliche Road and go Northwest 369 feet and location is Northwest 45 feet.



12777 Jones Road,  
Suite 385,  
Houston TX 77070  
Tel. 281 890 1818  
www.peg-us.com

LEASE  
LOGAN "35" K FEDERAL #15

COUNTY / PARISH AND STATE  
EDDY COUNTY NEW MEXICO

SURVEY INFORMATION  
MADRON SURVEYING, INC.  
CARLSBAD, NEW MEXICO  
SURVEY NO. 826. 3/24/2012

DRAWING NO. AND REVISION  
2013-LR-L35K-15-004  
REV. 2

CLIENT

**Lime Rock Resources II-A, L.P.**

TITLE

**LOGAN "35" K FEDERAL #15**

LOCATED 1650 FT. FROM THE SOUTH LINE AND 2460 FT. FROM THE  
WEST LINE OF SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27  
EAST, N.M.P.M. EDDY COUNTY STATE OF NEW MEXICO

NOT TO SCALE

# **LIME ROCK RESOURCES II- A, L.P**

## **APD DRILLING PLAN**

**OPERATOR:** LIME ROCK RESOURCES II- A, L.P

**WELL:** Logan 35 K Federal 15

**LOCATION:** Surface Location: 1650' FSL & 2460' FWL  
Bottom Hole Location: 1650' FSL & 2310' FWL

Unit K-Sec.35-T17S-R27E

Eddy County, NM

**LEASE NUMBER:** NMNM-117806

In attachment and accordance to BLM Form 3160-3, we respectfully submit the following information to drill the subject well as a "shallow S" deviated well with rotary tools to a total vertical depth of 3900', set production casing, and then move the rig off to use a workover rig to complete the well:

### **1. & 2. ESTIMATED TOPS OF GEOLOGIC FORMATIONS AND MARKERS:**

<b>Formation</b>	<b>MD</b>	<b>TVD</b>	<b>Formation Content</b>
Quaternary – Alluvium	Surface	Surface	
7 Rivers	365'	365'	
Queen	843'	843'	Oil/Gas
Grayburg	1328'	1328'	Oil/Gas
San Andres	1618'	1618'	Oil/Gas
Glorieta	3001'	2982'	Oil/Gas
Yeso	3105'	3086'	Oil/Gas
TD	3920'	3900'	Oil/Gas

The surface formation Geologic name is recent Permian with Quaternary Alluvium, which includes other surficial deposits. The elevation of the unprepared ground is 3626' Above Sea Level. The distance to the nearest Fresh Water Well is 0.5 miles, with usable water depth recorded to 250'. Usable water will be protected from salts, anhydrites along with oil and gas contamination with a surface casing string cemented to surface.

### **3. PRESSURE CONTROL:**

#### **(2000 psi BOPE SYSTEM WITH SCHEMATIC ATTACHED)**

The blowout preventer equipment (BOP) will consist of a 2000 psi rated, "XLT 11" type, National VARCO double ram preventer that will be tested to a maximum pressure of 2000 psi. The unit will be hydraulically operated and the ram type preventer will be equipped with blind rams on top and drill pipe rams on bottom. The 2M BOP will be installed on the 8 5/8" surface casing and utilized continuously until total depth is reached. All casing strings will be tested as per Onshore Order #2. This also includes a thirty-day (30) test, should the rig still be operating on the same well for thirty days.

Pipe rams will be operated and checked each 24-hour period and each time the drill pipe is out of the hole. These functional tests will be documented on the daily drilling logs.

The BOP equipment will consist of the following:

- Double ram with blind rams (top) and pipe rams (bottom),
- Drilling spool, or blowout preventer with 2 side outlets (choke side shall be a 2" minimum diameter, kill side will be at least 2 inch diameter),
- Kill line (2 inch minimum),
- A minimum of 2 choke line valves (2 inch minimum),
- 2 inch diameter choke line,

- 2 kill valves, one of which will be a check valve (2 inch minimum),
- 2 chokes, one of which will be capable of remote operation, pressure gauge on choke manifold,
- Upper Kelly cock valve with handle available,
- Safety valve and subs to fit all drill string connections in use,
- All BOPE connections subjected to well pressure will be flanged, welded, or clamped,
- A Fill-up line above the uppermost preventer.

#### 4. PROPOSED CASING ("CSG")

CASING TYPE	CASING DEPTH, FT	HOLE SIZE, IN.	CASING SIZE, IN.	CASING WEIGHT, LBS/FT	CASING GRADE	CASING THREAD	API, (Y) OR (N)	NEW (N) OR USED (U)
CONDUCTOR	80	26.000	20.000	91.5	B	WELDED	N	N
SURFACE	400	12.250	8.625	24.0	J-55	ST&C	Y	N
PRODUCTION	3920	7.875	5.500	17.0	J-55	LT&C	Y	N

All casing designed with a minimum of:

BURST SAFETY FACTOR

1.18

COLLAPSE SAFETY FACTOR

1.2

TENSION SAFETY FACTOR

2.0

#### 5. PROPOSED CEMENT ("CMT") PROGRAM

CASING TYPE	CASING DEPTH, FT	# SACKS CMT **	CMT TOP	CMT DENSIT Y, ppg	CMT YIELD, CU. FT. PER SACK	CMT EXCESS %	CMT BLEND *
CONDUCTOR	80	80	SURF	READY MIX			
SURFACE	400	350	SURF	14.8	1.4	200	1
PRODUCTION	3920	300	SURF	12.8	1.903	80	2
		440	1618	14.8	1.328	50	3

##### \* CMT BLENDS:

- (1) CI C Cmt +0.25 lbs/sk Cello Flake +2% CaCl<sub>2</sub>
- (2) Production casing lead slurry: (35:65)Poz/CI C Cmt + 5% NaCl +.25lb/sk Cello Flake+ 5lbs/sk LCM-1+ 0.2% R-3 +6% Gel
- (3) Production casing tail slurry: Class C w/ 0.6% R-3 and 1/4 pps cello flake

\*\* Cement volumes will be adjusted based on caliper log volumes and depths of casing.

\*\*\* A 13 3/8", 48#, H-40, ST&C, New, API contingency string will be set at 375' in a reamed 17 1/2" hole if circulation is lost in cave or karst (cave & karst potential to 350') and not regained. Contingency string will be cemented to the surface with 400 sacks (536 cubic feet) Class C + 1/4 pound per sack cello flake +2% CaCl<sub>2</sub> mixed to yield 1.34 cubic feet per sack and 14.8 pounds per gallon. Excess >100%

Upon the setting of a 13 3/8" contingency casing string, a 13 5/8" x 13 3/8" weld on wellhead will be installed. A 13 3/8" to 11" adapter flange will be installed and the 11" XLT 2000 psi NOV double ram BOP/BOPE (Schematic attached) will be installed. The BOP will be tested against the casing to 70% of

the internal yield pressure of the 13 3/8", 48#, H-40, ST&C (1211 psi) casing and held for 30 min before drilling out the 13 3/8" casing shoe. The formation will be drilled with a 10 3/4" bit +/- 50 ft past the 13 3/8" casing shoe into competent formation and 8 5/8" casing will be set and cemented with 200 sacks (268 cubic feet) Class C + 1/4 pound per sack cello flake +2% CaCl<sub>2</sub> mixed to yield 1.34 cubic feet per sack and 14.8 pounds per gallon. Excess >125%

#### 6. TYPE(S) AND CHARACTERISTIC(S) OF MUD SYSTEM:

An electronic/mechanical mud monitor with a minimum pit volume totalizer, stroke counter, and flow sensor will be used. All necessary mud products will be onsite to handle any abnormal hole conditions that could possibly be encountered during the drilling of this well.

Expected Drilling and Mud Properties			
Depth	0-400	400-3750	3750-3920
Mud Type	Fresh Water	Salt Water w/ Gel	Salt Water w/ Gel & Starch
Properties			
MW	8.5-9.2	9.9-10.2	9.9-10.2
pH	10	10-11.5	10-11.5
WL	NC	NC	15-20
Vis	28-34	30-32	32-35
MC	NC	NC	1
Solids	NC	<2%	<3%
Pump Rate	300-350gpm	350-400gpm	400-450gpm
Special	LCM as Req	Salt Gel, Acid & MF as req'd. Pmp Hi Vis sweeps to control Solids	Salt Gel, Acid & MF as req'd. Pmp Hi Vis sweeps to control Solids

#### 7. TESTING, CORING, and LOGGING PROCEDURES:

Testing Program: None

Electric Logging Program: Gamma Ray – Dual Laterlog – Compensated Neutron/Density Log from total depth to surface casing  
Surface casing to surface: Gamma Ray – Neutron log

Coring Program: None

#### 8. EXPECTED BOTTOM HOLE PRESSURE and TEMPERATURE:

Expected BHP: BHP 1716 PSI based on 0.44 x TD (3900')

Expected BHT: 125°F.

#### 9. ABNORMAL CONDITIONS:

**Lost Circulation-** Well to be drilled in a cave/karsts area, thus loss of circulation down to 350' is possible during the drilling phase. See contingency casing string in item 5.

**No Abnormal Temperature or Pressure Expected** during the drilling or completion stage.

**H<sub>2</sub>S is present in producing wells in the area.** H<sub>2</sub>S is not expected in the wellbore during the drilling of this well, but a H<sub>2</sub>S drilling plan will be in place and a summary of the plan is attached, and will be followed according to Onshore Oil and Gas Order No. 6. All personnel will be familiar with all aspects of the safe operation of equipment being used to drill this well.

#### Spud Date and Duration of Operations:

Anticipated spud date is after August 17, 2013. Move in operations and drilling is expected to take 10 days. An additional 14 days will be needed to complete the well and to construct surface facilities.

# Well Plan Details

## LIMEROCK

### WELLPATH ENERGY

AFE

Well: Logan 35K Federal #15 (3)

Job

Rig:

Eddy County, NM

Redlake

St. Plane - NAD27

4/1/2013

Well Information										
Rig:		Well: Logan 35K Federal #15 (3)		Map Details		Magnetics:				
Northing	650339.706	Northing	650339.710	System	2 - St. Plane	Decl., °	7.730			
Easting	525806.011	Easting	525806.010	Datum	1927 - NAD27	Dip, °	60.550			
Elevation	3639.300	Elevation	3639.300	Zone	3001 - New Mexico East	True N	0.000			
Latitude	32.787846	Latitude	32.787846	Scale. Fac	0.999910	Mag N	7.730			
Longitude	104.249361	Longitude	104.249361	Converg.	0.045474	Field, nT	48729.70			
Units	FEET	TVD Ref	MSL3625.9+KB13.4			Date	03/27/13			
Target Information										
Type	TVD	+N/S	+E/W	Latitude	Longitude	Northing	Easting	Description		
Radius:1	3900.00	-0.25	-150.00	32.787846	104.249849	650339.333	525656.011	PBHL		
Radius:1	3900.00	29.75	-180.00	32.787928	104.249947	650369.309	525625.987	Driller's Target		
4-Corners:1	3900.00	14.75	135.00	32.787887	104.248922	650354.559	525941.000	Driller's Box		
4-Corners:1	0.00	-0.25	-150.00	32.787846	104.249849	650339.333	525656.011	NO GO HARDLINE		
Radius:1	2350.00	20.00	-130.00	32.787901	104.249784	650359.603	525675.995	Southlake Unit #25		
Radius:1	5704.00	-41.00	-152.00	32.787734	104.249855	650298.586	525654.044	Well #15 Dry Hole		
Section Details: Logan 35K Federal #15 (3)										
MD	INC	AZI	TVD	NS	EW	VS279.38	BR	TR	DLS	Comments
0.00	0.00	0.00	0.00	0.00	0.00	0.00				SURFACE
365.00	0.00	360.00	365.00	0.00	0.00	0.00	0.00	0.00	0.00	7 Rivers
843.00	0.00	360.00	843.00	0.00	0.00	0.00	0.00	0.00	0.00	Queen
1328.00	0.00	360.00	1328.00	0.00	0.00	0.00	0.00	0.00	0.00	Grayburg
1618.00	0.00	360.00	1618.00	0.00	0.00	0.00	0.00	0.00	0.00	San Andres
1976.28	0.00	303.69	1976.28	0.00	0.00	0.00	0.00	-2.85	0.00	Build 3"/100'
2442.94	14.00	303.69	2438.31	31.47	-47.20	51.70	3.00	0.00	3.00	Hold
2506.52	14.00	303.69	2500.00	40.00	-60.00	65.72	0.00	0.00	0.00	2500' TVD: Drop 3.58"/100'
2731.10	14.00	270.00	2718.27	55.10	-109.85	117.36	0.88	-14.49	3.58	2718' TVD: Hold
2845.20	14.00	270.00	2828.97	55.10	-137.45	144.59	0.00	0.00	0.00	Drop 4"/100'
3001.10	7.76	270.00	2982.00	55.10	-166.87	173.62	-4.01	-0.01	4.01	Glorieta
3105.63	3.58	270.00	3086.00	55.10	-177.20	183.81	-4.00	0.00	4.00	Yeso
3195.19	0.00	270.00	3175.50	55.10	-180.00	186.57	-4.00	0.00	4.00	Hold
3919.69	0.00	270.00	3900.00	55.10	-180.00	186.58	0.00	0.00	0.00	PBHL



### Survey/Planning Report

<b>Operator</b>	LIMEROCK	<b>Northing</b>	650339.710	<b>Date</b>	1-Apr-13
<b>Dir. Co.</b>	WELLPATH ENERGY	<b>Easting</b>	525806.010	<b>System</b>	2 - St. Plane
<b>Well Name</b>	Logan 35K Federal #15 (3)	<b>Elevation</b>	3639.30	<b>Datum</b>	1927 - NAD27
<b>Location</b>	Eddy County, NM	<b>Latitude</b>	32.787846	<b>Zone</b>	3001 - New Mexico East
<b>Rig</b>		<b>Longitude</b>	104.249361	<b>Scale Fac.</b>	0.999910
<b>Job</b>		<b>Units</b>	FEET	<b>Converg.</b>	0.045474


MD	INC	AZI	TVD	+N/S-	+E/W-	VS@279.38°	BR	TR	DLS
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
0: SURFACE									
100.00	0.00	360.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	360.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	360.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
365.00	0.00	360.00	365.00	0.00	0.00	0.00	0.00	0.00	0.00
365: 7 Rivers									
400.00	0.00	360.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	360.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	360.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	360.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	360.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
843.00	0.00	360.00	843.00	0.00	0.00	0.00	0.00	0.00	0.00
843: Queen									
900.00	0.00	360.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1000.00	0.00	360.00	1000.00	0.00	0.00	0.00	0.00	0.00	0.00
1100.00	0.00	360.00	1100.00	0.00	0.00	0.00	0.00	0.00	0.00
1200.00	0.00	360.00	1200.00	0.00	0.00	0.00	0.00	0.00	0.00
1300.00	0.00	360.00	1300.00	0.00	0.00	0.00	0.00	0.00	0.00
1328.00	0.00	360.00	1328.00	0.00	0.00	0.00	0.00	0.00	0.00
1328: Grayburg									
1400.00	0.00	360.00	1400.00	0.00	0.00	0.00	0.00	0.00	0.00
1500.00	0.00	360.00	1500.00	0.00	0.00	0.00	0.00	0.00	0.00
1600.00	0.00	360.00	1600.00	0.00	0.00	0.00	0.00	0.00	0.00
1618.00	0.00	360.00	1618.00	0.00	0.00	0.00	0.00	0.00	0.00
1618: San Andres									
1700.00	0.00	360.00	1700.00	0.00	0.00	0.00	0.00	0.00	0.00
1800.00	0.00	360.00	1800.00	0.00	0.00	0.00	0.00	0.00	0.00
1900.00	0.00	360.00	1900.00	0.00	0.00	0.00	0.00	0.00	0.00
1976.28	0.00	303.69	1976.28	0.00	0.00	0.00	0.00	-2.85	0.00
1976.28: Build 3°/100'									
2000.00	0.71	303.69	2000.00	0.08	-0.12	0.13	3.00	0.00	3.00
2100.00	3.71	303.69	2099.91	2.22	-3.33	3.65	3.00	0.00	3.00
2200.00	6.71	303.69	2199.49	7.26	-10.89	11.93	3.00	0.00	3.00
2300.00	9.71	303.69	2298.45	15.18	-22.77	24.94	3.00	0.00	3.00
2400.00	12.71	303.69	2396.53	25.97	-38.95	42.66	3.00	0.00	3.00
2442.94	14.00	303.69	2438.31	31.47	-47.20	51.70	3.00	0.00	3.00
2442.94: Hold									
2500.00	14.00	303.69	2493.68	39.13	-58.69	64.28	0.00	0.00	0.00
2506.52	14.00	303.69	2500.00	40.00	-60.00	65.72	0.00	0.00	0.00
2506.52: 2500' TVD: Drop 3.58°/100'									
2543.95	13.68	298.25	2536.35	44.61	-67.67	74.03	-0.85	-14.54	3.58
2600.00	13.44	289.74	2590.84	49.95	-79.64	86.71	-0.43	-15.17	3.58
2700.00	13.73	274.51	2688.07	54.81	-102.41	109.97	0.29	-15.24	3.58
2731.10	14.00	270.00	2718.27	55.10	-109.85	117.36	0.88	-14.49	3.58
2731.1: 2718' TVD: Hold									
2800.00	14.00	270.00	2785.12	55.10	-126.52	133.81	0.00	0.00	0.00
2831.10	14.00	270.00	2815.30	55.10	-134.04	141.23	0.00	0.00	0.00
2845.20	14.00	270.00	2828.97	55.10	-137.45	144.59	0.00	0.00	0.00
2845.2: Drop 4°/100'									
2900.00	11.81	270.00	2882.39	55.10	-149.69	156.67	-4.00	0.00	4.00





Survey/Planning Report									
Operator	LIMEROCK			Northing	650339.710		Date	1-Apr-13	
Dir. Co.	WELLPATH ENERGY			Easting	525806.010		System	2 - St. Plane	
Well Name	Logan 35K Federal #15 (3)			Elevation	3639.30		Datum	1927 - NAD27	
Location	Eddy County, NM			Latitude	32.787846		Zone	3001 - New Mexico East	
Rig				Longitude	104.249361		Scale Fac.	0.999910	
Job				Units	FEET		Converg.	0.045474	
MD	INC	AZI	TVD	+N/S	+E/W	VS@279.38°	BR	TR	DLS
3000.00	7.81	270.00	2980.91	55.10	-166.72	173.47	-4.00	0.00	4.00
3001.10	7.76	270.00	2982.00	55.10	-166.87	173.62	-4.01	-0.01	4.01
3001.1: Glorieta									
3100.00	3.81	270.00	3080.38	55.10	-176.84	183.45	-4.00	0.00	4.00
3105.63	3.58	270.00	3086.00	55.10	-177.20	183.81	-4.00	0.00	4.00
3105.63: Yeso									
3195.19	0.00	270.00	3175.50	55.10	-180.00	186.57	-4.00	0.00	4.00
3195.19: Hold									
3200.00	0.00	270.00	3180.31	55.10	-180.00	186.57	0.00	0.00	0.00
3300.00	0.00	270.00	3280.31	55.10	-180.00	186.57	0.00	0.00	0.00
3400.00	0.00	270.00	3380.31	55.10	-180.00	186.57	0.00	0.00	0.00
3500.00	0.00	270.00	3480.31	55.10	-180.00	186.57	0.00	0.00	0.00
3600.00	0.00	270.00	3580.31	55.10	-180.00	186.57	0.00	0.00	0.00
3700.00	0.00	270.00	3680.31	55.10	-180.00	186.57	0.00	0.00	0.00
3800.00	0.00	270.00	3780.31	55.10	-180.00	186.57	0.00	0.00	0.00
3900.00	0.00	270.00	3880.31	55.10	-180.00	186.57	0.00	0.00	0.00
3919.69	0.00	270.00	3900.00	55.10	-180.00	186.58	0.00	0.00	0.00
3919.69: PBHL									





Note: all valves & lines on choke manifold are minimum of 2" unless otherwise noted. Exact manifold configuration may vary.

**11" Minimum 2000 psi BOP and  
Minimum 2000 psi BOPE System Schematic  
W/ Closed Loop System Equipment**

# **LIME ROCK RESOURCES II-A, L.P**

## **Design: Closed Loop System with roll-off steel bins (pits)**

**CRI/HOBBS** will supply (2) bins (100 bbl) volume, rails and transportation relating to the Close Loop System. Specification of the Closed Loop System is attached.

Contacts: Gary Wallace (432) 638-4076 Cell

(575) 393-1079 Office

## **Scomi Oil Tool: Supervisor – Armando Soto (432) 553-7979 Hobbs, NM**

Monitoring 24 Hour service

Equipment:

Centrifuges – Derrick Brand

Rig Shakers – Brandt Brand

D-watering Unit

Air pumps on location for immediate remediation process

Layout of Close Loop System with bins, centrifuges and shakers attached.

Cuttings and associated liquids will be hauled to a State regulated third party disposal site (CRI or Controlled Recovery, Inc.). The disposal site permit is DFP = #R9166.

2- (250 bbl) tanks to hold fluid

2-CRI bins with track system

2-500 bbl frac tanks with fresh water


2-500 bbl frac tanks for brine water

## **Operations:**

Closed Loop System equipment will be inspected daily by each tour and any necessary maintenance performed. Any leak in system will be repaired and/or contained immediately. OCD will be notified within 48 hours of any spill. Remediation process will start immediately.

## **Closure:**

During drilling operations all liquids, drilling fluids and cuttings will be hauled off via CRI equipment to DFP #R9166. Close Loop System. Specification of the Closed Loop System is attached.



This will be maintained by 24 hour solids control personnel that stay on location.

*TOMMY WILSON*



**CLOSED LOOP  
SPECIALTY**


Office: 575.746.1689

Cell: 575.748.6167

Lime Rock Resources II-A, L.P.

Location Layout

(Note: Not to Scale)





SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO

WELL COORDINATES:  
LAT. = 32.7878463° N  
LONG. = 104.2493608° W  
(NAD 27 - SEE NOTE)

NOTE: THE LATITUDE AND LONGITUDE  
COORDINATES ARE SHOWN USING THE  
NORTH AMERICAN DATUM OF 1927 (NAD27)  
AND ARE IN DECIMAL DEGREE FORMAT.



Directions to Location:

From paved County Road 225 (Empire) and paved County Road 226 (Evans), go North-Northeast on County 225 265 feet. Turn left on Caliche Road and go Northwest 369 feet and location is Northwest 45 feet.



12777 Jones Road,  
Suite 385,  
Houston TX 77070  
Tel. 281 890 1818  
www.peg-us.com

LEASE  
LOGAN "35" K FEDERAL #15  
COUNTY / PARISH AND STATE  
EDDY COUNTY NEW MEXICO  
SURVEY INFORMATION  
MADRON SURVEYING, INC.  
CARLSBAD, NEW MEXICO  
SURVEY NO. 826. 3/24/2012  
DRAWING NO. AND REVISION  
2013-LR-L35K-15-001  
REV. 1

CLIENT

Lime Rock Resources II-A, L.P.

TITLE

LOGAN "35" K FEDERAL #15

LOCATED 1650 FT. FROM THE SOUTH LINE AND 2460 FT. FROM THE  
WEST LINE OF SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27  
EAST, N.M.P.M. EDDY COUNTY STATE OF NEW MEXICO



SCALE AT LETTER PAPER SIZE 1 INCH = 100 FEET

## Hydrogen Sulfide Drilling Plan Summary

- A. All personnel shall receive proper H<sub>2</sub>S training in accordance with Onshore Order 6 III.C.3.a.
- B. Briefing Area: two perpendicular areas will be designated by signs and readily accessible.
- C. Required Emergency Equipment:

- Well control equipment

- a. Flare line 150' from wellhead to be ignited by flare gun.
- b. Choke manifold with a remotely operated choke.
- c. Mud/gas separator

- Protective equipment for essential personnel.

Breathing apparatus:

- a. Rescue Packs (SCBA) — 1 unit shall be placed at each breathing area, 2 shall be stored in the safety trailer.
- b. Work/Escapes packs — 4 packs shall be stored on the rig floor and contain sufficiently long air hoses as to not restrict work activity.
- c. Emergency Escape Packs — 4 packs shall be stored in the doghouse for emergency evacuation.

Auxiliary Rescue Equipment:

- a. Stretcher
- b. Two OSHA full body harness
- c. 100 ft 5/8 inch OSHA approved rope
- d. 1-20# class ABC fire extinguisher

- H<sub>2</sub>S detection and monitoring equipment:

The stationary detector with three sensors will be placed in the upper dog house if equipped, set to visually alarm @ 10 ppm and audible @ 14 ppm. Calibrate a minimum of every 30 days or as needed. The sensors will be placed in the following places: Rig floor / Bell nipple / End of flow line or where well bore fluid is being discharged.  
(Gas sample tubes will be stored in the safety trailer)

- Visual warning systems.

- a. One color code condition sign will be placed at the entrance to the site reflecting the possible conditions at the site.
- b. A colored condition flag will be on display, reflecting the current condition at the site at the time.
- c. Two wind socks will be placed in strategic locations, visible from all angles.

- Mud program:

The mud program has been designed to minimize the volume of H<sub>2</sub>S circulated to surface. The operator will have the necessary mud products to minimize hazards while drilling in H<sub>2</sub>S bearing zones.

- Metallurgy:

- a. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H<sub>2</sub>S service.
- b. All elastomers used for packing and seals shall be H<sub>2</sub>S trim.

■ **Communication:**

Communication will be via two way radio in emergency and company vehicles. Cell phones and land lines where available.

## H2S CONTINGENCY DRILLING PLAN EMERGENCY CONTACTS

**Company Offices -** Lime Rock Houston Office 713-292-9510  
Answering Service(After Hours) 713-292-9555  
Artesia, NM Office 575-748-9724  
Roswell, NM 575-623-8424

KEY PERSONNEL					
Name	Title	Location	Office #	Cell #	Home #
MIKE LOUDERMILK	OPERATIONS MANAGER	HOUSTON	713-292-9526	832-331-7367	SAME AS CELL
SPENCER COX	PRODUCTION ENGINEER	HOUSTON	713-292-9528	432-254-5140	SAME AS CELL
ERIC MCCLUSKY	PRODUCTION ENGINEER	HOUSTON	713-360-5714	405-821-0534	832-491-3079
JERRY SMITH	ASSISTANT PRODUCTION SUPERVISOR	ARTESIA	575-748-9724	505-918-0556	575-746-2478
MICHAEL BARRETT	PRODUCTION SUPERVISOR	ROSWELL	575-623-8424	505-353-2644	575-623-4707
DALE KENNARD	WELL SITE SUPERVISOR	ROTATES ON SITE	NA	575-420-1651	NA
GARY MCCELLAND	WELL SITE SUPERVISOR	ROTATES ON SITE	NA	903-503-8997	NA
BRAD TATE	WELL SITE SUPERVISOR	ROTATES ON SITE	NA	575-441-1966	NA
DAVE WILLIAMSON	WELL SITE SUPERVISOR	ROTATES ON SITE	NA	575-308-9980	NA

<b>Agency Call List</b>		
<b>City</b>	<b>Agency or Office</b>	<b>Telephone Number</b>
<b>Artesia</b>	<b>Ambulance</b>	<b>911</b>
<b>Artesia</b>	<b>State Police</b>	<b>575-746-2703</b>
<b>Artesia</b>	<b>Sheriff's Office</b>	<b>575-746-9888</b>
<b>Artesia</b>	<b>City Police</b>	<b>575-746-2703</b>
<b>Artesia</b>	<b>Fire Department</b>	<b>575-746-2701</b>
<b>Artesia</b>	<b>Local Emergency Planning Committee</b>	<b>575-746-2122</b>
<b>Artesia</b>	<b>New Mexico OCD District II</b>	<b>575-748-1283</b>
<b>Carlsbad</b>	<b>Ambulance</b>	<b>911</b>
<b>Carlsbad</b>	<b>State Police</b>	<b>575-885-3137</b>
<b>Carlsbad</b>	<b>Sheriff's Office</b>	<b>575-887-7551</b>
<b>Carlsbad</b>	<b>City Police</b>	<b>575-885-2111</b>
<b>Carlsbad</b>	<b>Fire Department</b>	<b>575-885-2111</b>
<b>Carlsbad</b>	<b>Local Emergency Planning Committee</b>	<b>575-887-3798</b>
<b>Carlsbad</b>	<b>US DOI Bureau of Land Management</b>	<b>575-887-6544</b>
<b>State Wide</b>	<b>New Mexico Emergency Response Commission ("NMERC")</b>	<b>505-476-9600</b>
<b>State Wide</b>	<b>NMERC 24 hour Number</b>	<b>505-827-9126</b>
<b>State Wide</b>	<b>New Mexico State Emergency Operations Center</b>	<b>505-476-9635</b>
<b>National</b>	<b>National Emergency Response Center (Washington, D.C.)</b>	<b>800-424-8802</b>

## H2S CONTINGENCY DRILLING PLAN EMERGENCY CONTACTS



Emergency Services				
Name	Service	Location	Telephone Number	Alternate Number
Boots & Coots International Well Control	Well Control	Houston / Odessa	1-800-256-9688	281-931-8884
Cudd Pressure Control	Well Control & Pumping	Odessa	915-699-0139	915-563-3356
Baker Hughes Inc.	Pumping Service	Artesia, Hobbs and Odessa	575-746-2757	SAME
Total Safety	Safety Equipment and Personnel	Artesia	575-746-2847	SAME
Cutter Oilfield Services	Drilling Systems Equipment	Midland	432-488-6707	SAME
Assurance Fire & Safety	Safety Equipment and Personnel	Artesia	575-396-9702	575-441-2224
Flight for Life	Emergency Helicopter Evacuation	Lubbock	806-743-9911	SAME
Aerocare	Emergency Helicopter Evacuation	Lubbock	806-747-8923	SAME
Med Flight Air Ambulance	Emergency Helicopter Evacuation	Albuquerque	505-842-4433	SAME
Artesia General Hospital	Emergency Medical Care	Artesia	575-748-3333	702 North 13 Street

SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO

WELL COORDINATES:  
LAT. = 32.7878463° N  
LONG. = 104.2493608° W  
(NAD 27 - SEE NOTE)

NOTE: THE LATITUDE AND LONGITUDE  
COORDINATES ARE SHOWN USING THE  
NORTH AMERICAN DATUM OF 1927 (NAD27)  
AND ARE IN DECIMAL DEGREE FORMAT.



Directions to Location:

From paved County Road 225 (Empire) and paved County Road 226 (Evans), go North-Northeast on County 225 265 feet. Turn left on Caliche Road and go Northwest 369 feet and location is Northwest 45 feet.



12777 Jones Road,  
Suite 385,  
Houston TX 77070  
Tel. 281 890 1818  
www.peg-us.com

LEASE  
LOGAN "35" K FEDERAL #15  
COUNTY / PARISH AND STATE  
EDDY COUNTY NEW MEXICO  
SURVEY INFORMATION  
MADRON SURVEYING, INC.  
CARLSBAD, NEW MEXICO  
SURVEY NO. 826. 3/24/2012  
DRAWING NO. AND REVISION  
2013-LR-L35K-15-002  
REV. 1


CLIENT

Lime Rock Resources II-A, L.P.

TITLE

LOGAN "35" K FEDERAL #15

LOCATED 1650 FT. FROM THE SOUTH LINE AND 2460 FT. FROM THE  
WEST LINE OF SECTION 35, TOWNSHIP 17 SOUTH, RANGE 27  
EAST, N.M.P.M. EDDY COUNTY STATE OF NEW MEXICO



## **MULTI POINT SURFACE USE AND OPERATIONS PLAN**

### **LIME ROCK RESOURCES II- A, L.P**

Logan 35 K Federal 15  
Unit K - Sec. 35-T17S-R27E  
Surface Location: 1650'FSL & 2460'FWL  
EDDY County, NM  
Lease No.: NM 064050 A

This plan is submitted with the Application for Permit to Drill the above described well. The purpose of this plan is to describe the location of the proposed well, the proposed construction activities and operations plan to be followed in rehabilitating the surface and environmental effects associated with the operations.

#### **1. EXISTING ROADS:**

- a. Existing roads are shown on the portion of a BLM topo map showing the location of the proposed well as staked. The well site location is approximately 7.17 road miles Southeast of Artesia, NM. Traveling East of Artesia on U.S. Hwy 82 there will be approximately 9.7 miles of existing highway .2 mile of County Rd. 225 and 227.
- b. Directions: From paved Cr 225 (Empire) and Paved Cr 226 (Evans) go North-Northeast on Cr. 225 265' turn left on Caliche Rd and go Northwest 369' and location is Northwest 45'.

#### **2. PLANNED ACCESS ROAD:**

- a. Length and Width: Access to the planned location is provided by existing caliche roads. The existing roads are color coded on the Vicinity Map.
- b. Construction: The existing access road will be upgraded, as needed, by grading, and topping with compacted caliche. The surface will be properly drained.
- c. Turnout: None will be required.
- d. Culverts: None.
- e. Cuts and Fills: None required
- f. Gates, Cattle guards: None will be required.
- g. Off Lease right of way: None required.

#### **3. LOCATION OF EXISITING WELLS**

- a. Locations of existing wells are shown on One Mile Radius Map.

**4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES:**

- a. Lime Rock Resources II A, L.P. has production facilities on the lease at this time
- b. If the well proves to be commercial, the necessary production facilities will be run parallel to the road and other flow lines to the Logan 35 Federal Tank Battery located in the adjacent section.
- c. A right-of-way will be applied for to transport fluids off lease.

**5. LOCATION AND TYPE OF WATER SUPPLY:**

- a. It is planned to drill the proposed well with fresh water that will be obtained from private or commercial sources and will be transported over the existing and proposed access roads.

**6. SOURCE OF CONSTRUCTION MATERIALS:**

- a. Caliche for surfacing the proposed access road and well site pad will be obtained from the approved private pit in the SW4/SW4 Sec. 32-T17S-R28E or a closer pit if available. No surface materials will be disturbed except those necessary to for grading and leveling the pad area and access road.

**7. METHODS OF HANDLING WASTE DISPOSAL**

- a. Drill cuttings and liquids will be stored in steel tanks of the closed loop mud system during the drilling operating and delivered to CRI, Permit No. R-9166, as needed, and at closure.
- b. There will be no mud pits to be fenced.
- c. Water produced during operations will be collected in tanks until hauled to an approved disposal system, or a separate disposal application will be submitted to the BLM for approval.
- d. Oil produced during operations will be stored in tanks until sold.

- e. Current laws and regulations pertaining to the disposal of human waste will be complied with.
- f. Trash, waste paper, garbage, and junk will be contained in trash bins to prevent scattering by the wind and will be removed for deposit in an approved sanitary landfill within 30 days after finishing drilling and/or completion operations.

**8. ANCILLARY FACILITIES:**

- a. None required.

**9. WELL SITE LAYOUT:**

- a. Refer to the plat that shows the relative location and dimension of the well pad, closed loop system, and major rig components. The pad and pit area has been staked and flagged, 240' X 200' with 30' X 30' stingers.
- b. Cut & Fill: The location will require approximately a 2' cut on the north with fill to the south.
- c. The surface will be topped with compacted caliche.

**10. PLANS FOR RESTORATION OF THE SURFACE:**

- a. After completion of drilling and/or completion operations, all equipment and other material not required for operations will be removed. The location will be cleaned of all trash and junk to leave the well site in an aesthetically pleasing a condition as possible.
- b. There will be no unguarded pits containing fluids.
- c. If the proposed well is found commercially viable, the location will be reduced to a square 170' by 180', with exception of road access centered at the well, allowing for environmental reclamation.
- d. If the proposed well is non-productive, all rehabilitation and/or vegetation requirements of the Bureau of Land Management will be complied with and will be accomplished as expeditiously as possible. Mud from the closed system will be disposed of as required.

**11. OTHER INFORMATION:**

- a. Topography: The proposed well site and access roads are located on an overall 2.0% slope to the south. The location has an elevation of 3626' GL..
- b. Soil: The topsoil at the well site is a tan loamy soil. The soil is part of the Reeves-Gypsum land complex.

- c.** Flora and Fauna: The location has a fair grass cover of grama, three-awn fluff grass alkali sacaton along with plant of mesquite, yucca, broomweed, cacti, and miscellaneous weeds and wildflowers. The wildlife consists of rabbits, coyotes, antelopes, deer, rattlesnakes, lizards, dove, quail, and other wildlife typical of the semi-arid desert land.
- d.** Ponds and Streams: None.
- e.** Residences and Other Structures: None in the immediate vicinity, except producing oil wells surrounding the location of the Logan 35 K Federal, Well No 15.
- f.** Land Use: Mostly oil production and possible cattle grazing.
- g.** Surface Ownership: The proposed well site and access road is on Federal surface and minerals.
- h.** There is no immediate evidence of an archaeological site on the location of the staked area. Archaeological Survey Consultants, P O Box 225, Roswell, NM 88202, is conducting an archaeological survey and their report will be submitted to the appropriate government agencies.

## **12. OPERATOR'S REPRESENTATIVE**

- a.** The field representative for assuring compliance with the approved use and operations plan is as follows:

Spencer Cox  
LIME ROCK RESOURCES II- A, L.P.  
Heritage Plaza  
1111 Bagby Street, Suite 4600  
Houston, TX 77002  
Office Phone: 713-292-9528  
Cell Phone: 432-254-5140

**CERTIFICATION:**

I hereby certify that I have inspected the proposed drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have knowledge of state and Federal laws applicable to this operation; that the statements made in the APD package are, to the best of my knowledge true and correct; and that the work associated with the operation proposed herein will be performed in the conformity with this APD package and the terms and conditions which it is approved. I also certify that I, or the company I represent, am/is responsible for the operations conducted under this application. These statements are subject to the provisions of 18U.S.C. 1001 for the filing of a false statement.

Executed this 4/5/2013

Lisa Barfield

Lisa Barfield

POA Agent for Lime Rock Resources IIA, L.P.

12777 Jones Rd., Ste 385

Houston, TX 77070

281-890-1818 (office)

## PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	LIME ROCK RESOURCES II-A
LEASE NO.:	NM117806
WELL NAME & NO.:	15-LOGAN 35 K FEDERAL
SURFACE HOLE FOOTAGE:	1650' FSL & 2460' FWL
BOTTOM HOLE FOOTAGE:	1650' FSL & 2310' FWL
LOCATION:	Section 35, T. 17 S., R 27 E., NMPM
COUNTY:	Eddy County, New Mexico

### TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
  - Cave/Karst**
- ☐ **Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
  - H2S requirements
  - High Cave Karst
  - Logging Requirements
  - Waste Material and Fluids
- ☒ **Production (Post Drilling)**
  - Well Structures & Facilities
  - Pipelines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## **V. SPECIAL REQUIREMENT(S)**

### **Cave and Karst**

\*\* Depending on location, additional Drilling, Casing, and Cementing procedures may be required by engineering to protect critical karst groundwater recharge areas.

#### **Cave/Karst Surface Mitigation**

The following stipulations will be applied to minimize impacts during construction, drilling and production.

##### **Construction:**

In the advent that any underground voids are opened up during construction activities, construction activities will be halted and the BLM will be notified immediately.

##### **No Blasting:**

No blasting will be utilized for pad construction. The pad will be constructed and leveled by adding the necessary fill and caliche.

##### **Pad Berming:**

The pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the pad. All sides will be bermed.

##### **Tank Battery Liners and Berms:**

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

##### **Leak Detection System:**

A method of detecting leaks is required. The method could incorporate gauges to measure loss, siting valves and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present. Leak detection plan will be submitted to BLM for approval.

##### **Automatic Shut-off Systems:**

Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

#### **Cave/Karst Subsurface Mitigation**

The following stipulations will be applied to protect cave/karst and ground water concerns:

##### **Rotary Drilling with Fresh Water:**

Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

**Directional Drilling:**

Kick off for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

**Lost Circulation:**

ALL lost circulation zones from the surface to the base of the cave occurrence zone will be logged and reported in the drilling report.

Regardless of the type of drilling machinery used, if a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cave-bearing zone, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

**Abandonment Cementing:**

Upon well abandonment in high cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

**Pressure Testing:**

Annual pressure monitoring will be performed by the operator on all casing annuli and reported in a sundry notice. If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall stockpile the topsoil in a low profile manner in order to prevent wind/water erosion of the topsoil. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be used for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### **D. FEDERAL MINERAL MATERIALS PIT**

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

### **F. EXCLOSURE FENCING (CELLARS & PITS)**

#### **Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For

examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

## **G. ON LEASE ACCESS ROADS**

### **Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

### **Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

### **Crowning**


Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

### **Ditching**

Ditching shall be required on both sides of the road.

### **Turnouts**

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:




## Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

### Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

### Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

## Culvert Installations

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

## Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.

## Fence Requirement


Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

## Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

**Figure 1 – Cross Sections and Plans For Typical Road Sections**



## VII. DRILLING

### A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

1. A Hydrogen Sulfide (H<sub>2</sub>S) Drilling Plan shall be activated 500 feet prior to drilling into the **Queen** formation. **As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. **The record of the drilling rate along with the GR/N well log run from TD to surface shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

### B. CASING

**Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).**

**Centralizers required on surface casing per Onshore Order 2.III.B.1.f.**

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

**HIGH CAVE/KARST – OPERATOR HAS PROPOSED A CONTINGENCY CASING IF LOST CIRCULATION OCCURS WHILE DRILLING THE SURFACE HOLE. IF LOST CIRCULATION OCCURS WHILE DRILLING THE 7-7/8” HOLE, THE CEMENT PROGRAM FOR THE 5-1/2” CASING WILL NEED TO BE MODIFIED AND THE BLM IS TO BE CONTACTED PRIOR TO RUNNING THE CASING. A MINIMUM OF TWO CASING STRINGS CEMENTED TO SURFACE IS REQUIRED IN HIGH CAVE/KARST AREAS. THE CEMENT MUST BE IN A SOLID SHEATH THEREFORE, ONE INCH OPERATIONS WILL NOT BE PERMITTED. A DV TOOL WILL BE REQUIRED**

**There is a potential for shallow oil production within the Yates and Seven Rivers Formations.**

**Possibility for water and brine flows in the Salado and Artesia Groups.**

**Possible lost circulation in the Grayburg and San Andres formations.**

**Contingency Surface Casing Plan:**

1. The 13-3/8 inch contingency surface casing shall be set at approximately 400 feet and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

**Casing Plan without Contingency:**

- 2. The **8-5/8** inch surface casing shall be set at approximately **400** feet and cemented to the surface. **(If contingency casing is used set 8-5/8" casing 50 feet below 13-3/8" shoe.)**
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 3. The minimum required fill of cement behind the **5-1/2** inch production casing is:
  - ☒ Cement to surface. If cement does not circulate, contact the appropriate BLM office.
- 4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

**C. PRESSURE CONTROL**

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi. Operator is approved to test against the casing for the contingency plan.

3. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**.
  - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock.
  - d. The results of the test shall be reported to the appropriate BLM office.
  - e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
  - f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure

#### **D. DRILL STEM TEST**

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

#### **E. WASTE MATERIAL AND FLUIDS**

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**CRW 060313**

## **VIII. PRODUCTION (POST DRILLING)**

### **A. WELL STRUCTURES & FACILITIES**

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

#### **Chemical and Fuel Secondary Containment and Exclosure Screening**

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

#### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the

largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

## **B. PIPELINES**

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. The holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
- b. Activities of other parties including, but not limited to:

- (1) Land clearing.
- (2) Earth-disturbing and earth-moving work.
- (3) Blasting.
- (4) Vandalism and sabotage.

c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.

6. All construction and maintenance activity will be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline must be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline must be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.

8. The holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline will be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines must be less than or equal to 4 inches and a working pressure below 125 psi.

## **IX. INTERIM RECLAMATION**

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

## **X. FINAL ABANDONMENT & RECLAMATION**

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

#### Seed Mixture 4, for Gypsum Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Alkali Sacaton ( <i>Sporobolus airoides</i> )	1.0
DWS Four-wing saltbush ( <i>Atriplex canescens</i> )	5.0
DWS: DeWinged Seed	

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed