


UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT



FORM APPROVED  
OMB No. 1004-0137  
Expires July 31, 2010

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM-090807
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name N/A
2. Name of Operator SM ENERGY COMPANY		7. If Unit or CA Agreement, Name and No. N/A
3a. Address 3300 N. A STREET, BLDG. 7-200 MIDLAND, TX 79705	3b. Phone No. (include area code) 432 688-1700	8. Lease Name and Well No. OSAGE 34 FEDERAL 6H Com?
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface 1700' FSL & 35' FEL At proposed prod. zone 1650' FSL & 330' FWL		9. API Well No. 30-015-41597
14. Distance in miles and direction from nearest town or post office* 17 AIR MILES NE OF CARLSBAD, NM		10. Field and Pool, or Exploratory PARKWAY; BONE SPRING
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 15'	16. No. of acres in lease 1,120	11. Sec., T. R. M. or Blk. and Survey or Area NESE 34-19S-29E NMPM
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 435' (Osage 34 Fed. 3H, in the 2nd Bone Spring)	19. Proposed Depth TVD=7001' MD=11833'	12. County or Parish EDDY
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3,332' UNGRADED	22. Approximate date work will start* 08/01/2013	13. State NM
20. BLM/BIA Bond No. on file NMB000805		
23. Estimated duration 3 MONTHS		

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification   |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM.             |

25. Signature	Name (Printed/Typed) BRIAN WOOD (505 466-8120)	Date 06/23/2013
---------------	---	--------------------

Title CONSULTANT (FAX 505 466-9682)

Approved by (Signature) /s/George MacDonell	Name (Printed/Typed)	Date AUG - 2 2013
---	----------------------	----------------------

Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE
---------------------	------------------------------

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

Capitan Controlled Water Basin

SEE ATTACHED FOR  
CONDITIONS OF APPROVAL

Approval Subject to General Requirements  
& Special Stipulations Attached

## DISTRICT I

1625 N. French Dr., Hobbs, NM 88240  
Phone (575) 393-6161 Fax: (575) 393-0720

## DISTRICT II

811 S. First St., Artesia, NM 88210  
Phone (575) 748-1283 Fax: (575) 748-9720

## DISTRICT III

1000 Rio Brazos Rd., Aztec, NM 87410  
Phone (505) 334-6178 Fax: (505) 334-6170

## DISTRICT IV

1220 S. St. Francis Dr., Santa Fe, NM 87505  
Phone (505) 478-3460 Fax: (505) 478-3462

State of New Mexico  
Energy, Minerals and Natural Resources Department

## OIL CONSERVATION DIVISION

1220 South St. Francis Dr.  
Santa Fe, New Mexico 87505

Form C-102

Revised August 1, 2011

Submit one copy to appropriate  
District Office

## WELL LOCATION AND ACREAGE DEDICATION PLAT

☐ AMENDED REPORT

API Number 30-015- 41597	Pool Code 49622	Pool Name PARKWAY; BONE SPRING
Property Code 38981 39397	Property Name OSAGE "34" FEDERAL	Well Number 6H
OGRID No. 154903	Operator Name SM ENERGY	Elevation 3332

## Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
I	34	19 S	29 E		1700	SOUTH	35	EAST	EDDY

## Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
L	34	19 S	29 E		1650	SOUTH	330	WEST	EDDY

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.
160			

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED  
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

<p><b>PROPOSED BOTTOM HOLE LOCATION</b> Lat - N 32°36'52.18" Long - W 104°04'13.06" NMSPCE- N 587384.6 E 622328.1 (NAD-83)</p>	<p><b>SURFACE LOCATION</b> Lat - N 32°36'52.47" Long - W 104°03'15.34" NMSPCE- N 587426.707 E 627264.280 (NAD-83)</p>	<p><b>OPERATOR CERTIFICATION</b> I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p><i>Brian Wood</i> 6-23-13 Signature Date BRIAN WOOD brian@permitswest.com Email Address</p>
<p>(This will be a first Bone Spring completion. Osage 34 Federal 3H was a second Bone Spring.)</p>		<p><b>SURVEYOR CERTIFICATION</b> I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p><i>Gary L. Jones</i> Date Surveyed Seal of Professional Surveyor 7977 Certificate No. Gary L. Jones 7977 BASIN SURVEYS 28487</p>

SM Energy Company  
Osage 34 Federal 6H  
SHL 1700' FSL & 35' FEL  
BHL 1650' FSL & 330' FWL  
Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 18

REPRESENTATION

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U. S. C. 1001 for the filing of false statements. Executed this 23rd day of June, 2013.



-----  
Brian Wood, Consultant

Permits West, Inc.

37 Verano Loop, Santa Fe, NM 87508

(505) 466-8120

FAX: (505) 466-9682

Cellular: (505) 699-2276

Field representative will be:

Malcolm Kintzing, Reservoir Engineer

SM Energy Company



3300 N. A Street, Building 7-200

Midland, TX 79705

Office: (432) 688-1700

FAX: (432) 688-1701

Osage 34 Federal 6H



TN MN

7.5°


02/10/13



SECTION 34, TOWNSHIP 19 SOUTH, RANGE 29 EAST, N.M.P.M.,  
EDDY COUNTY,

NEW MEXICO.

PAGE 21



SM ENERGY  
OSAGE "34" FEDERAL #6H  
ELEV. - 3332'  
SURFACE LOCATION  
Lat - N 32°36'52.47"  
Long - W 104°03'15.34"  
NMSPCE- N 587426.707  
E 627264.280  
(NAD-83)

200 0 200 400 FEET

SCALE: 1" = 200'

Directions to Location:

FROM THE JUNCTION OF HWY 62-180 AND CO. RD. 238, GO NORTHEAST ON CO. RD. 238 FOR 2.5 MILES TO LEASE ROAD, ON LEASE ROAD GO NORTH 4.0 MILES TO LEASE ROAD, GO EAST FOR 1.3 MILES TO WELL PAD AND PROPOSED LEASE ROAD.

**BASIN SURVEYS** P.O. BOX 1786 - HOBBS, NEW MEXICO

W.O. Number: 28487

Drawn By: J. SMALL

Date: 05-02-2013 Disk: DAJ 28487

**SM ENERGY**

REF: OSAGE "34" FEDERAL #6H / WELL PAD TOPO


THE OSAGE "34" FEDERAL #6H LOCATED 1700'

FROM THE SOUTH LINE AND 35' FROM THE EAST LINE OF  
SECTION 34, TOWNSHIP 19 SOUTH, RANGE 29 EAST,

N.M.P.M., EDDY COUNTY, NEW MEXICO.

Survey Date: 04-18-2013


Sheet 1 of 1 Sheets



SECTION 34, TOWNSHIP 19 SOUTH, RANGE 29 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO.

PAGE 23

OWNER: U.S.A.  
LESSEE: RICHARDSON CATTLE CO.




LEGAL DESCRIPTION

A TRACT OF LAND LOCATED IN SECTION 34, TOWNSHIP 19 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT WHICH LIES N0°01'00\"W, 1822.80 FEET AND S89°59'38\"W, 921.27 FEET FROM THE SOUTHEAST CORNER OF SAID SECTION 34; THENCE S.00°00'49\"W, 200.00 FEET; THENCE N89°59'20\"W, 175.00 FEET; THENCE N00°00'43\"E, 200.00 FEET; THENCE S89°59'13\"E, 200.00 FEET TO THE POINT OF BEGINNING. SAID TRACT OF LAND 0.8035 ACRES, MORE OR LESS.

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.



GARY L. JONES

No. 7977  
No. 5074

**BASIN SURVEYS**

P.O. BOX 1786 - HOBBS, NEW MEXICO


W.O. Number: 27883

Drawn By: K. GOAD

Date: 01-03-2013

Disk: KJG - 27883TRACT

1000 0 1000 2000 FEET



**SM ENERGY**

REF: PROPOSED EXTENSION OF THE 3H-1H OSAGE FRAC TRACT

A TRACT OF LAND IN  
SECTION 34, TOWNSHIP 19 SOUTH, RANGE 29 EAST,  
N.M.P.M., EDDY COUNTY, NEW MEXICO.

Survey Date: 12-28-2013

Sheet 1 of 1 Sheets



SM Energy Company  
Osage 34 Federal 6H  
SHL 1700' FSL & 35' FEL  
BHL 1650' FSL & 330' FWL  
Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 1

Drilling Program

1. ESTIMATED TOPS

<u>Name</u>	<u>Measured Depth from KB (18')</u>	<u>Elevation</u>
Quaternary	18'	+3,332'
Rustler	154'	+3,196'
Salt top	450'	+2,900'
Salt base	1,161'	+2,189'
Yates	1,345'	+2,005'
Capitan	1,738'	+1,612'
Queen	2,562'	788'
Delaware	3,370'	-20'
Brushy Canyon	4,034'	-684'
Bone Spring	5,726'	-2,376'
1 <sup>st</sup> Bone Spring sand	7,101'	-3,751'
Target	7,141'	-3,791'
BHL (TVD = 7,001')	11,833'	-3,652'

2. NOTABLE ZONES

<u>Gas or Oil Zones</u>	<u>Water Zone</u>	<u>Solid Mineral Zone</u>
Yates	Quaternary	Rustler
Cherry Canyon	(at ≈60')	Salt
Brushy Canyon		
Bone Spring		

Water zones will be protected with casing, cement, and weighted mud. Fresh water found while drilling will be recorded.

SM Energy Company  
Osage 34 Federal 6H  
SHL 1700' FSL & 35' FEL  
BHL 1650' FSL & 330' FWL  
Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 2

3. PRESSURE CONTROL (see PAGES 3 - 9)

SM Energy Company requests a variance from Onshore Order 2 to use a diverter system on the 20" surface casing.

A 2,000 psi annular system will be installed after running the 13-3/8" casing. A 3,000 psi double ram BOP and 3,000 psi annular system will be installed after running the 9-5/8" casing.

Pressure tests will be conducted before drilling out of the 13-3/8" casing. BOP controls will be installed before drilling out from under the surface casing and will remain in use until completion of drilling operations. BOPs will be inspected and operated as required by Onshore Order 2.

A Kelly cock valve and sub equipped with a full opening valve sized to fit the drill pipe and collars will be available on the rig floor and in the open position when the Kelly is not in use. A third party testing company will test the 11" BOPE to 3,000 psi and the annular to 1,500 psi before drilling below the surface casing shoe. The BOP/BOPE test will include a low-pressure test from 250 psi to 300 psi. The test will be held for a minimum of 10 minutes if the test is done with a test-plug. All BOPs and related equipment will comply with well control requirements in Onshore Order 2 and API RP 53 Section 17.

SM Energy Company requests a variance to Onshore Order 2 in order to use a 47' x 3" I. D. co-flex hose with 5,000-psi flanges between the BOPE and the choke manifold. The hose will be kept as straight as possible with minimal turns. Safety clamps will not be used since the ends will be flanged. Manufacturer is Midwest Hose & Specialty, Inc. Model details, serial numbers, and the test results are on Pages 6-9. Operator will test the line when the BOP is tested.

SM Energy Company  
 Osage 34 Federal 6H  
 SHL 1700' FSL & 35' FEL  
 BHL 1650' FSL & 330' FWL  
 Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 10

#### 4. CASING & CEMENT

Hole O. D. Inches	Casing O. D. Inches	Pounds per foot	Grade	Setting Interval	Collar	Age
26	20	94	J-55	0-350	BT&C	New
17.5	13.375	48	H-40	0-1200	ST&C	New
17.5	13.375	54.5	J-55	1200-1500	ST&C	New
12.25	9.625	36	J-55	0-3300	LT&C	New
8.75	7	26	P-110	0-7140	LT&C	New
6.125	4.5	11.6	P-110	6940-11853	LT&C	New

All casing designed with a minimum of:

Burst	Collapse	Tensile Strength
1.0	1.125	1.8

Surface casing will be set at approximately 350' in a competent bed below the Magenta Dolomite, a member of the Rustler. Surface casing will be cemented to the surface with >100% excess (920 sacks = 1,232 cubic feet) Class C + 2% CaCl<sub>2</sub> mixed to yield 1.34 cubic feet per sack and 14.8 pounds per gallon. Centralizers will be installed as required by Onshore Order 2.

Intermediate casing will be cemented to the surface with 65% excess (1,869 cubic feet). Lead with 785 sacks (1,601 cubic feet) 35:65 Class C with salt and LCM additives mixed to yield 2.04 cubic feet per sack and 12.5 pounds per gallon. Tail with 200 sacks (268 cubic feet) Class C with 2% CaCl<sub>2</sub> mixed to yield 1.34 cubic feet per sack and 14.8 pounds per gallon.

The deep intermediate casing will be cemented to the surface with 127% excess (1,829 cubic feet). Cement will be pumped in 2 stages using an ECP stage collar. It will be placed in the deepest competent formation, but not within 100' of the previous casing shoe. Position will be determined by a caliper survey or a rate of penetration log. Current collar estimate setting depth is ≈1,700'.

Stage 1 lead slurry will consist of 375 sacks (791 cubic feet) 35:65 poz fly ash Class C +5% bwoc NaCl +1/4 pound per sack cello flake + 10% bwoc bentonite

SM Energy Company  
Osage 34 Federal 6H  
SHL 1700' FSL & 35' FEL  
BHL 1650' FSL & 330' FWL  
Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 11

II + 151.7% fresh water mixed to yield 2.11 cubic feet per sack and 12.5 pounds per gallon. Tail with 185 sacks (247 cubic feet) Class C + 0.005 pounds per sack static free + 1% bwoc  $\text{CaCl}_2$  mixed to yield 1.34 cubic feet per sack and 14.8 pounds per gallon.

Second-stage slurry will consist of 375 sacks (791 cubic feet) 35:65 poz fly ash Class C + 5% bwow NaCl + 1/4 pound per sack cello flake + 10% bwoc bentonite II + 151.7% fresh water mixed to yield 2.11 cubic feet per sack and 12.5 pounds per gallon.

If packer placement changes, then the cement volumes will be adjusted proportionately as determined by the annulus volume above the packer. Cement will meet the 500-psi requirement before casing test and drill out.

Curve casing will be cemented to 1,620' (enough to cover the Capitan reef top at 1,626') with 110% excess (2,195 cubic feet). Lead with 750 sacks (1,957 cubic feet) Class C mixed to yield 2.61 cubic feet sack and 12.5 pounds per gallon. Tail with 200 sacks (238 cubic feet) Class H with 1% NaCl mixed to yield 1.19 cubic feet per sack and 15.6 pounds per gallon.

Production casing will include a sliding sleeve, frac port, and packer system with the 4-1/2" liner. No cement is planned.

##### 5. MUD PROGRAM

An electronic/mechanical mud monitor with a minimum pit volume totalizer, stroke counter, and flow sensor will be used. A mud monitoring system will be in place to record slow pump rate, pit gain or loss, mud weight, viscosity, gel strength, filtration, and pH. Circulation could be lost in every section of hole. Lost circulation material (e.g., cedar bark) will be on location. All necessary mud products will be on site to handle any abnormal hole conditions that could possibly be encountered during the drilling of the well.

SM Energy Company  
Osage 34 Federal 6H  
SHL 1700' FSL & 35' FEL  
BHL 1650' FSL & 330' FWL  
Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 12

1625

Interval	Type	Weight	Viscosity	Fluid loss
0 - 350	fresh water spud mud	8.6 - 9.4	32-34	no control
350 - 1500	brine	10	28-30	no control
1500 - 3300	fresh water	8.4	28-30	no control
3300 - 7140	cut brine	8.4 - 8.6	28-30	no control
7140 - TD	cut brine with polymer	8.4 - 8.6	32-40	no control

Aerated mud will be used in the Capitan Reef to assist in circulation if large losses occur. Estimated mud weight is 6 pounds per gallon. If a well control situation is encountered, then the emergency shut offs on the air units will be used and the rig pumps will be used to regain the 8.4 pounds per gallon mud weight.

#### 6. CORES, TESTS, & LOGS

No core or drill stem test is planned. Compensated neutron - GR CCL logs will be run in the vertical cased hole from KOP to surface. Mud log samples will be collected after drilling out from the 9-5/8" shoe. Samples will be collected every 20' until the Bone Spring and every 10' through the Bone Spring.

#### 7. DOWN HOLE CONDITIONS

No abnormal pressure or temperature is expected. Maximum expected bottom hole pressure is 4,512 psi.

No H<sub>2</sub>S is expected during the drilling phase. Nevertheless, H<sub>2</sub>S monitoring equipment will be on the rig floor and air packs will be available before drilling out of the surface casing. The mud logger will be warned to use a gas trap to detect H<sub>2</sub>S. If any H<sub>2</sub>S is detected, then the mud weight will be increased and H<sub>2</sub>S inhibitors will be added to control the gas. An H<sub>2</sub>S drilling operations contingency plan is attached.

Lost circulation is expected in the Capitan reef.

SM Energy Company  
Osage 34 Federal 6H  
SHL 1700' FSL & 35' FEL  
BHL 1650' FSL & 330' FWL  
Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 13

8. OTHER INFORMATION


The anticipated spud date is upon approval. It is expected it will take 3 months to drill and complete the well.

This will be a first Bone Spring completion. The Osage 34 Federal 3H is a second Bone Spring completion.


# SM ENERGY COMPANY

OSAGE 34 FEDERAL WELL #6H  
SECTION 34, T-19-S, R-29-E  
EDDY COUNTY, NEW MEXICO  
(05/09/13)

## HORIZONTAL PROJECTION



## VERTICAL PROJECTION





# **SM ENERGY COMPANY**

5/9/13

OSAGE 34 FEDERAL WELL #6H  
SECTION 34, T-19-S, R-29-E  
EDDY COUNTY, NEW MEXICO

RKB = 3349' AMSL Est. ( GL = 3331' )

SHL: X: 627,264.28' Y: 587,426.71'

Obj. =

S 89.51 W

NAD 83

Type	#	MD	ANG	Azimuth	DIR	CL	TVD	(+)North (-)South	(+)East (-)West	Vertical Section	Dogleg /100'
9-5/8" CASING	TI-IN	3550.00	0.00	269.51	S 89.51 W	---	3550.00	0.00	0.00	0.00	TI-IN
KOP	1	6567.34	0.00	269.51	S 89.51 W	3017	6567.34	0.00	0.00	0.00	0.00
	2	6599.34	3.20	269.51	S 89.51 W	32	6599.32	-0.01	-0.89	0.89	10.00
	3	6631.34	6.40	269.51	S 89.51 W	32	6631.20	-0.03	-3.57	3.57	10.00
	4	6663.34	9.60	269.51	S 89.51 W	32	6662.89	-0.07	-8.02	8.02	10.00
	5	6695.34	12.80	269.51	S 89.51 W	32	6694.27	-0.12	-14.24	14.24	10.00
	6	6727.34	16.00	269.51	S 89.51 W	32	6725.26	-0.19	-22.19	22.20	10.00
	7	6759.34	19.20	269.51	S 89.51 W	32	6755.76	-0.27	-31.87	31.87	10.00
	8	6791.34	22.40	269.51	S 89.51 W	32	6785.67	-0.37	-43.23	43.23	10.00
	9	6823.34	25.60	269.51	S 89.51 W	32	6814.90	-0.48	-56.24	56.25	10.00
	10	6855.34	28.80	269.51	S 89.51 W	32	6843.36	-0.60	-70.87	70.87	10.00
	11	6887.34	32.00	269.51	S 89.51 W	32	6870.96	-0.74	-87.06	87.06	10.00
	12	6919.34	35.20	269.51	S 89.51 W	32	6897.61	-0.89	-104.76	104.77	10.00
	13	6951.34	38.40	269.51	S 89.51 W	32	6923.23	-1.06	-123.93	123.93	10.00
	14	6983.34	41.60	269.51	S 89.51 W	32	6947.74	-1.23	-144.50	144.50	10.00
	15	7015.34	44.80	269.51	S 89.51 W	32	6971.06	-1.42	-166.40	166.40	10.00
	16	7047.34	48.00	269.51	S 89.51 W	32	6993.13	-1.62	-189.57	189.57	10.00
	17	7079.34	51.20	269.51	S 89.51 W	32	7013.86	-1.82	-213.93	213.94	10.00
	18	7111.34	54.40	269.51	S 89.51 W	32	7033.21	-2.04	-239.42	239.43	10.00
	19	7143.34	57.60	269.51	S 89.51 W	32	7051.10	-2.27	-265.94	265.95	10.00
	20	7175.34	60.80	269.51	S 89.51 W	32	7067.48	-2.50	-293.42	293.43	10.00
	21	7207.34	64.00	269.51	S 89.51 W	32	7082.31	-2.74	-321.78	321.79	10.00
	22	7239.34	67.20	269.51	S 89.51 W	32	7095.52	-2.99	-350.91	350.93	10.00
	23	7271.34	70.40	269.51	S 89.51 W	32	7107.09	-3.25	-380.74	380.76	10.00
	24	7303.34	73.60	269.51	S 89.51 W	32	7116.98	-3.51	-411.17	411.19	10.00
	25	7335.34	76.80	269.51	S 89.51 W	32	7125.15	-3.77	-442.11	442.12	10.00
	26	7367.34	80.00	269.51	S 89.51 W	32	7131.59	-4.04	-473.45	473.46	10.00
	27	7399.34	83.20	269.51	S 89.51 W	32	7136.26	-4.31	-505.10	505.12	10.00
	28	7431.34	86.40	269.51	S 89.51 W	32	7139.16	-4.58	-536.96	536.98	10.00
	29	7463.34	89.60	269.51	S 89.51 W	32	7140.28	-4.85	-568.94	568.96	10.00
LANDING	30	7485.66	91.83	269.51	S 89.51 W	22	7140.0000	-5.04	-591.25	591.27	10.00
	31	7517.66	91.83	269.51	S 89.51 W	32	7138.98	-5.32	-623.24	623.26	0.00
	32	8017.66	91.83	269.51	S 89.51 W	500	7122.99	-9.58	-1122.96	1123.00	0.00
	33	8517.66	91.83	269.51	S 89.51 W	500	7107.00	-13.84	-1622.69	1622.75	0.00
	34	9017.66	91.83	269.51	S 89.51 W	500	7091.02	-18.11	-2122.41	2122.49	0.00
	35	9517.66	91.83	269.51	S 89.51 W	500	7075.03	-22.37	-2622.14	2622.24	0.00
	36	10017.66	91.83	269.51	S 89.51 W	500	7059.04	-26.63	-3121.87	3121.98	0.00
	37	10517.66	91.83	269.51	S 89.51 W	500	7043.05	-30.89	-3621.59	3621.72	0.00
	38	11017.66	91.83	269.51	S 89.51 W	500	7027.07	-35.16	-4121.32	4121.47	0.00
	39	11517.66	91.83	269.51	S 89.51 W	500	7011.08	-39.42	-4621.04	4621.21	0.00
BHL	40	11832.97	91.83	269.51	S 89.51 W	315	7001.00	-42.11	-4936.18	4936.36	0.00
LATERAL		4347.31						-42.11	-4936.18	4936.36	





**SM ENERGY COMPANY**

OSAGE 34 FEDERAL WELL #6H  
SECTION 34, T-19-S, R-29-E  
EDDY COUNTY, NEW MEXICO

RKB = 3349' AMSL Est. ( GL = 3331' )

SHL: X: 627,264.28' Y: 587,426.71'

Type	#	MD	SURVEY			S	89.51	W	CL	TVD	NAD 83		Dogleg /100'
			ANG	Azimuth	DIR						(+)North (-)South	(+)East (-)West	
9-5/8" CASING	TI-IN	3550.00	0.00	269.51	S	89.51	W	---	---	3550.00	587,426.71	627,264.28	TI-IN
KOP	1	6567.34	0.00	269.51	S	89.51	W	3017	---	6567.34	587,426.71	627,264.28	0.00
	2	6599.34	3.20	269.51	S	89.51	W	32	---	6599.32	587,426.70	627,263.39	10.00
	3	6631.34	6.40	269.51	S	89.51	W	32	---	6631.20	587,426.68	627,260.71	10.00
	4	6663.34	9.60	269.51	S	89.51	W	32	---	6662.89	587,426.64	627,256.26	10.00
	5	6695.34	12.80	269.51	S	89.51	W	32	---	6694.27	587,426.59	627,250.04	10.00
	6	6727.34	16.00	269.51	S	89.51	W	32	---	6725.26	587,426.52	627,242.09	10.00
	7	6759.34	19.20	269.51	S	89.51	W	32	---	6755.76	587,426.44	627,232.41	10.00
	8	6791.34	22.40	269.51	S	89.51	W	32	---	6785.67	587,426.34	627,221.05	10.00
	9	6823.34	25.60	269.51	S	89.51	W	32	---	6814.90	587,426.23	627,208.04	10.00
	10	6855.34	28.80	269.51	S	89.51	W	32	---	6843.36	587,426.11	627,193.41	10.00
	11	6887.34	32.00	269.51	S	89.51	W	32	---	6870.96	587,425.97	627,177.22	10.00
	12	6919.34	35.20	269.51	S	89.51	W	32	---	6897.61	587,425.82	627,159.52	10.00
	13	6951.34	38.40	269.51	S	89.51	W	32	---	6923.23	587,425.65	627,140.35	10.00
	14	6983.34	41.60	269.51	S	89.51	W	32	---	6947.74	587,425.48	627,119.78	10.00
	15	7015.34	44.80	269.51	S	89.51	W	32	---	6971.06	587,425.29	627,097.88	10.00
	16	7047.34	48.00	269.51	S	89.51	W	32	---	6993.13	587,425.09	627,074.71	10.00
	17	7079.34	51.20	269.51	S	89.51	W	32	---	7013.86	587,424.89	627,050.35	10.00
	18	7111.34	54.40	269.51	S	89.51	W	32	---	7033.21	587,424.67	627,024.86	10.00
	19	7143.34	57.60	269.51	S	89.51	W	32	---	7051.10	587,424.44	626,998.34	10.00
	20	7175.34	60.80	269.51	S	89.51	W	32	---	7067.48	587,424.21	626,970.86	10.00
	21	7207.34	64.00	269.51	S	89.51	W	32	---	7082.31	587,423.97	626,942.50	10.00
	22	7239.34	67.20	269.51	S	89.51	W	32	---	7095.52	587,423.72	626,913.37	10.00
	23	7271.34	70.40	269.51	S	89.51	W	32	---	7107.09	587,423.46	626,883.54	10.00
	24	7303.34	73.60	269.51	S	89.51	W	32	---	7116.98	587,423.20	626,853.11	10.00
	25	7335.34	76.80	269.51	S	89.51	W	32	---	7125.15	587,422.94	626,822.17	10.00
	26	7367.34	80.00	269.51	S	89.51	W	32	---	7131.59	587,422.67	626,790.83	10.00
	27	7399.34	83.20	269.51	S	89.51	W	32	---	7136.26	587,422.40	626,759.18	10.00
	28	7431.34	86.40	269.51	S	89.51	W	32	---	7139.16	587,422.13	626,727.32	10.00
	29	7463.34	89.60	269.51	S	89.51	W	32	---	7140.28	587,421.86	626,695.34	10.00
LANDING	30	7485.66	91.83	269.51	S	89.51	W	22	---	7140.0000	587,421.67	626,673.03	10.00
	31	7517.66	91.83	269.51	S	89.51	W	32	---	7138.98	587,421.39	626,641.04	0.00
	32	8017.66	91.83	269.51	S	89.51	W	500	---	7122.99	587,417.13	626,141.32	0.00
	33	8517.66	91.83	269.51	S	89.51	W	500	---	7107.00	587,412.87	625,641.59	0.00
	34	9017.66	91.83	269.51	S	89.51	W	500	---	7091.02	587,408.60	625,141.87	0.00
	35	9517.66	91.83	269.51	S	89.51	W	500	---	7075.03	587,404.34	624,642.14	0.00
	36	10017.66	91.83	269.51	S	89.51	W	500	---	7059.04	587,400.08	624,142.41	0.00
	37	10517.66	91.83	269.51	S	89.51	W	500	---	7043.05	587,395.82	623,642.69	0.00
	38	11017.66	91.83	269.51	S	89.51	W	500	---	7027.07	587,391.55	623,142.96	0.00
	39	11517.66	91.83	269.51	S	89.51	W	500	---	7011.08	587,387.29	622,643.24	0.00
BHL	40	11832.97	91.83	269.51	S	89.51	W	315	---	7001.00	587,384.60	622,328.10	0.00
LATERAL			4347.31								587,384.60	622,328.10	

RAMCO DIRECTIONAL DRILLING INC

SM ENERGY OSAGE 35 WELL #6-H

## TARGETS

6/23/13


### Lease Line Calls

[illegible]


### Coordinates

[illegible]


## Diverter System




# BOP SCHEMATIC



# BOP SCHEMATIC



### Choke Manifold Schematic for Closed Loop System



**PACKING LIST**



# Midwest Hose & Specialty, Inc.

## Ship From

Midwest Hose & Specialty, Inc.  
3312 S I-35 Service Road  
Oklahoma City OK 73129  
USA

Ship To

Midwest Rose & Specialty, Inc - Alice  
3754 E Highway 44  
Alice TX 78332  
USA

Bill To

Midwest Hose & Specialty, Inc - Alice  
3754 E Highway 44  
Alice TX 78332  
USA

Payment Terms	NET 30 DAYS (NET30)
Ship Method	CNTRAN
Freight Terms	Prepaid
Customer Ship	ALICE
Cartons	1
Weight	1,718.00
Tracking Nbrs	

Shipping Notes:

Cust phone: (361) 661-1815

Written by: SGELISTA

Customer PO: 00132599

**Mark Number:**

Packing List #:00143913

Received By: \_\_\_\_\_

Date Received: \_\_\_\_\_

Print Name: \_\_\_\_\_

Work Phone #: \_\_\_\_\_

[illegible]

PAGE 7

Questions?

Phone: (800) 375-2358



Midwest Hose  
& Specialty, Inc.

## Internal Hydrostatic Test Graph

March 23, 2012

Customer: Alice


Pick Ticket #: 143913

### Hose Specifications

<u>Hose Type</u>	<u>Length</u>
0	47'
<u>I.D.</u>	<u>O.D.</u>
3"	4.49"
<u>Working Pressure</u>	<u>Burst Pressure</u>
5000 PSI	Standard Safety Multiplier Applies

### Verification

<u>Type of Fitting</u>	<u>Coupling Method</u>
41/L55K	Swage
<u>Min Size</u>	<u>Final O.D.</u>
5.12"	5.10"
<u>Hose Serial #</u>	<u>Hose Assembly Serial #</u>
7818	143913



Test Pressure  
5000 PSI

Time Held at Test Pressure  
1 2/4 Minutes

Actual Burst Pressure


Peak Pressure  
6679 PSI

**Comments:** Hose assembly pressure tested with water at ambient temperature.

**Tested By:** Donnie McEmore

**Approved By:** Kim Thomas






# Midwest Hose & Specialty, Inc.

## INTERNAL HYDROSTATIC TEST REPORT

Customer: ALICE		Customer P.O. Number: 132599
HOSE SPECIFICATIONS		
Type: Rotary / Vibrator Hose GRADE D / API 7K	Hose Length: 47 FEET	
I.D. 3 INCHES	O.D. 4.49 INCHES	
WORKING PRESSURE 5,000 PSI	TEST PRESSURE 5,000 PSI	BURST PRESSURE N/A PSI
COUPLINGS		
Part Number D3.5X64WB D3.5X64WB	Stem Lot Number 1Q11LOT1 1Q11LOT1	Ferrule Lot Number 1Q11LOT1 1Q11LOT1
Type of Coupling: Swage-It	Die Size: 5.12 INCHES	
PROCEDURE		
<u>Hose assembly pressure tested with water at ambient temperature.</u>		
TIME HELD AT TEST PRESSURE 1 1/2 MIN.		ACTUAL BURST PRESSURE: N/A PSI
Hose Assembly Serial Number: 143913		Hose Serial Number: 7818
Comments:		
Date: 2/23/2012	Tested: <i>D. H. [Signature]</i>	Approved: <i>James Thomas</i>

# **CLOSED-LOOP SYSTEM**

## **Design Plan:**




## **Operating and Maintenance Plan:**

During drilling operations, third party service companies will utilize solids control equipment to remove cuttings from the drilling fluid and collect it in haul-off bins. Equipment will be closely monitored at all times while drilling by the derrick man and the service company employees.

## **Closure Plan:**

During drilling operations, third party service companies will haul-off drill solids and fluids to an approved disposal facility as noted on the C-144 form. At the end of the well, all closed loop equipment will be removed from the location.



## Hydrogen Sulfide Drilling Operations Plan

1. Company and Contract personnel admitted on location should be trained by a qualified H<sub>2</sub>S safety instructor to the following:
  - A. Characteristics of H<sub>2</sub>S.
  - B. Physical Effects and Hazards.
  - C. Proper Use of Safety Equipment and Life Support Systems.
  - D. Principle and Operation of H<sub>2</sub>S Detectors, Warning System and Briefing.
  - E. Evacuation Procedure, Routes and First Aid.
  - F. Proper Use of 30 minute Pressure Demand Air Pack.
2. H<sub>2</sub>S Detection and Alarm Systems
  - A. H<sub>2</sub>S Detectors and Audio Alarm System to be Located at Bell Nipple, End of Blooie Line (mud pit) and on Derrick floor or doghouse.
3. Windsock and/or Wind Streamers
  - A. Windsock at Mud Pit Area Should be High Enough to be Visible.
  - B. Windsock at Briefing Area Should be High Enough to be Visible.
  - C. There Should be a Windsock at Entrance to Location.
4. Condition Flags and Signs
  - A. Warning Sign on Access Road to Location.
  - B. Flags to be Displayed on Sign at Entrance to Location.
    1. Green Flag, Normal Safe Condition.
    2. Yellow Flag, Indicates Potential Pressure and Danger.
    3. Red Flag, Danger H<sub>2</sub>S Present in Dangerous Concentration Only Emergency Personnel Admitted to Location.
5. Well Control Equipment
  - A. See Attached Diagram.
6. Communication
  - A. While Working Under Masks Chalkboards Will be Used for Communication.
  - B. Hand Signals will be Used Where Chalk Board is Inappropriate.
  - C. Two Way Radio or Cell Phone will be Used to Communicate off Location in Case of Available at Most Drilling Foreman's Trailer or Living Quarters.
7. Drillstem Testing
  - A. Exhausts will be Watered.
  - B. Flare Line will be Equipped with an Electric Igniter or a propane pilot light in case gas reaches the surface.
  - C. If Location is near any Dwelling a Closed DST will be Performed.
8. Drilling Contractor Supervisor will be Required to be Familiar with the Effects H<sub>2</sub>S has on tubular goods and other mechanical equipment.
9. If H<sub>2</sub>S Encountered, Mud system will be Altered if Necessary to Maintain Control of Formation. A Mud Gas Separator will be Brought into Service Along with H<sub>2</sub>S Scavengers if Necessary.



Company Contact List:

<u>New Mexico Operations:</u>	<u>Name:</u>	<u>Cellular:</u>	<u>Office:</u>
Drilling Superintendent	Howard Smith	903-262-0001	432-400-2395
Asst. Drilling Superintendent	Keith Pagett	806-317-5159	432-400-2395
Drilling Manager	Jonathan Nix	432-296-8956	432-688-3127
HSE Manager	David Carrillo	432-664-2095	432-688-3391
Project Manager	Malcolm Kintzing	432-212-2628	432-688-3125
Drilling Engineer	Michael Mataalii	432-271-2230	432-688-3392

<u>Lea County (Hobbs):</u>	<u>Contact Number:</u>
State Police	575-392-5588
City Police	575-397-9265
Sheriff's Office	575-393-2515
Ambulance	911
Fire Department	575-397-9308
Local Emergency Planning Committee	575-393-2870
NMOCD	575-393-6161
US Bureau of Land Management	575-393-3612

<u>Eddy County (Carlsbad)</u>	<u>Contact Number:</u>
State Police	575-885-3137
City Police	575-855-2111
Sheriff's Office	575-887-7551
Ambulance	911
Fire Department	575-885-2111
Local Emergency Planning Committee	575-887-3798
US Bureau of Land Management	575-887-6544

<u>Emergency Services</u>	<u>Contact Numbers:</u>
Boots & Coots IWC	1-800-256-9688 or 281-931-8884
Cudd Pressure Control	915-699-0139 or 915-563-3356
Halliburton	575-746-2757
B.J. Services	575-746-3569
Flight for Life Lubbock TX	806-743-9911
Aerocare Lubbock TX	806-747-8923
Med Flight Air Ambulance Albuquerque NM	575-842-4433
Lifeguard Air Med Albuquerque NM	575-272-3115


SM Energy Company  
Osage 34 Federal 6H  
SHL 1700' FSL & 15' FEL  
BHL 1650' FSL & 330' FWL  
Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 23

NORTH



1" = 75'




SM Energy Company  
Osage 34 Federal 6H  
SHL 1700' FSL & 35' FEL  
BHL 1650' FSL & 330' FWL  
Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 24


NORTH



1" = 75'



PAGE 25



FROM THE JUNCTION OF HWY 62-180 AND CO. RD.  
238, GO NORTHEAST ON CO. RD. 238 FOR 2.5  
MILES TO LEASE ROAD, ON LEASE ROAD GO NORTH  
4.0 MILES TO LEASE ROAD, GO EAST FOR 1.3 MILES  
TO WELL PAD AND PROPOSED LEASE ROAD.

**SM ENERGY**

REF: OSAGE "34" FEDERAL #6H / WELL PAD TOPO

THE OSAGE "34" FEDERAL #6H LOCATED 1700'

FROM THE SOUTH LINE AND 35' FROM THE EAST LINE OF

SECTION 34, TOWNSHIP 19 SOUTH, RANGE 29 EAST,

N.M.P.M., EDDY COUNTY, NEW MEXICO.

Survey Date: 04-18-2013      Sheet 1 of 1 Sheets



SM Energy Company  
Osage 34 Federal 6H  
SHL 1700' FSL & 35' FEL  
BHL 1650' FSL & 330' FWL  
Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 14

Surface Use Plan

1. ROAD DIRECTIONS & DESCRIPTIONS (See PAGES 19 - 21)

From the center of Carlsbad...

Go Northeast 14.3 miles on US 62 to the equivalent of Mile Post 49.4

Then turn left and go North 2.1 mile on paved County Road 238

Bear right and continue North & Northwest 4.1 miles on a dirt road

Turn right and go East 0.4 mile on a caliche road

Then turn right and go South 63.3 cross-country to the proposed pad

Roads will be maintained to a standard at least equal to or better than their present condition.

*This APD is also doubling as a plan of development for an accompanying BLM road and twin well pad right-of-way application totaling 2.47 acres. Application covers 20' x 63.3' (=0.03 acre) new road and 300' x 350' pad (=2.44 acres) in NESE Section 34 and NWSW Section 35, both 19s-29e. Application connects with existing road right-of-way NMNM-073084. APD for twin Parkway 35 Federal 6H will be filed in March.*

2. ROAD TO BE BUILT OR UPGRADED (See PAGES 19 - 21)

Approximately 63.3' of new road will be built. The new road will be crowned, have a 14' wide driving surface, and be surfaced with caliche. Maximum disturbed width = 20'. Maximum grade = 1%. Maximum cut or fill = 1'. No culvert, cattle guard, or turn out is needed. Padding will be placed across 8 surface poly lines. Upgrading of existing roads will consist of filling potholes with caliche.

SM Energy Company  
Osage 34 Federal 6H  
SHL 1700' FSL & 35' FEL  
BHL 1650' FSL & 330' FWL  
Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 15

### 3. EXISTING WELLS

Existing oil, gas, injection, disposal, water, and P & A wells within a mile radius are shown on Page 22.

### 4. PROPOSED PRODUCTION FACILITIES (PAGE 21)

Production facilities will be installed on the pad. All will be located in the Section 34 (on lease) side of the pad. Equipment and configuration will be determined after well completion. A Sundry will be submitted for approval before installation. SM will build a  $\approx 25'$  long power line from its existing overhead power line north of the pad south to the pad. DCP will lay a gas line and will be responsible for its right-of-way application.

### 5. WATER SUPPLY (PAGES 19-21 & 23)

SM has an existing frac pond that will be expanded (175' x 200') to the west. A temporary surface water pipeline will be laid east 900' along the south side of the existing road. The line will be 4" poly during drilling and 10" aluminum during completion. Existing supply pipeline and trucks from Carlsbad will be used to fill the expanded pond.

### 6. CONSTRUCTION MATERIALS & METHODS

NM One Call (1-800-321-ALERT) will be notified before construction starts. The top 6" of soil and brush will be stockpiled south of the pad. A closed loop drilling system will be used. Caliche will be bought and hauled from an existing approved caliche pit. Dirt contractor will be responsible for caliche.

SM Energy Company  
Osage 34 Federal 6H  
SHL 1700' FSL & 35' FEL  
BHL 1650' FSL & 330' FWL  
Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 16

#### 7. WASTE DISPOSAL

All trash will be placed in a portable trash cage. It will be hauled to a county landfill. There will be no trash burning. Contents of the mud tanks will be hauled to state approved disposal sites. Human waste will be disposed of in chemical toilets and hauled to an approved dump station.

#### 8. ANCILLARY FACILITIES

There will be no airstrip or camp. Camper trailers will be on location for the company man, tool pusher, or mud logger.

#### 9. WELL SITE LAYOUT

See Page 24 for depictions of the well pad, trash cage, access onto the location, parking, living facilities, and rig orientation.

#### 10. RECLAMATION (See PAGE 25)

Interim reclamation will consist of removing the caliche from at least a 50' x 300' strip on the west side of the pad. Depending on the production equipment, more of the pad may be reclaimed. Disturbed areas will be contoured to a natural shape and no steeper than 3:1. Soil and brush will be evenly spread over disturbed areas. Seeded areas will be ripped or harrowed. A BLM approved seed mix will be sown in a BLM approved manner. Enough stockpiled topsoil will be retained to cover the remainder of the pad when the well is plugged. Once the well is plugged, then the remainder of the pad will be similarly reclaimed. Noxious weeds will be controlled.

SM Energy Company  
Osage 34 Federal 6H  
SHL 1700' FSL & 35' FEL  
BHL 1650' FSL & 330' FWL  
Sec. 34, T. 19 S., R. 29 E., Eddy County, NM

PAGE 17

11. SURFACE OWNER

All construction will be on BLM.

12. OTHER INFORMATION

An on site inspection was held January 14, 2013 with Legion Brumley (BLM).

SNMAS has inspected the pad, road, pond, and water pipeline. See their reports SNMAS-12NM-4008/4009/4010 (Feb. 6, 2013) and SNMAS-13NM-4018 (Feb. 15, 2013).

## PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	SM ENERGY COMPANY
LEASE NO.:	NM90807
WELL NAME & NO.:	6H-OSAGE 34 FEDERAL
SURFACE HOLE FOOTAGE:	1700' FSL & 35' FEL
BOTTOM HOLE FOOTAGE:	1650' FSL & 330' FWL
LOCATION:	Section 34, T. 19 S., R 29 E., NMPM
COUNTY:	Eddy County, New Mexico

### TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
  - Cave/Karst
- ☐ **Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
  - Cement Requirements
  - H2S requirements
  - High Cave/Karst
  - Logging Requirements
  - Waste Material and Fluids
- ☐ **Production (Post Drilling)**
  - Well Structures & Facilities
  - Pipelines
  - Electric Lines (Overhead Electric lines)
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## **V. SPECIAL REQUIREMENT(S)**

### **Cave and Karst**

\*\* Depending on location, additional Drilling, Casing, and Cementing procedures may be required by engineering to protect critical karst groundwater recharge areas.

#### **Cave/Karst Surface Mitigation**

The following stipulations will be applied to minimize impacts during construction, drilling and production.

##### **Construction:**

In the advent that any underground voids are opened up during construction activities, construction activities will be halted and the BLM will be notified immediately.

##### **No Blasting:**

No blasting will be utilized for pad construction. The pad will be constructed and leveled by adding the necessary fill and caliche.

##### **Pad Berming:**

The pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the pad. All sides will be bermed.

##### **Tank Battery Liners and Berms:**

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

##### **Leak Detection System:**

A method of detecting leaks is required. The method could incorporate gauges to measure loss, situating valves and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present. Leak detection plan will be submitted to BLM for approval.

##### **Automatic Shut-off Systems:**

Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

#### **Cave/Karst Subsurface Mitigation**

The following stipulations will be applied to protect cave/karst and ground water concerns:

##### **Rotary Drilling with Fresh Water:**

Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

**Directional Drilling:**

Kick off for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

**Lost Circulation:**

ALL lost circulation zones from the surface to the base of the cave occurrence zone will be logged and reported in the drilling report.

Regardless of the type of drilling machinery used, if a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cave-bearing zone, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

**Abandonment Cementing:**

Upon well abandonment in high cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

**Pressure Testing:**

Annual pressure monitoring will be performed by the operator on all casing annuli and reported in a sundry notice. If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall stockpile the topsoil in a low profile manner in order to prevent wind/water erosion of the topsoil. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be used for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.



The operator shall properly dispose of drilling contents at an authorized disposal site.

#### **D. FEDERAL MINERAL MATERIALS PIT**

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

#### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

#### **F. EXCLOSURE FENCING (CELLARS & PITS)**

##### **Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

#### **G. ON LEASE ACCESS ROADS**

##### **Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

##### **Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road

deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

### Crowning


Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

### Ditching

Ditching shall be required on both sides of the road.

### Turnouts

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:




### Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill out sloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

### Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

#### **Formula for Spacing Interval of Lead-off Ditches**

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

#### **Culvert Installations**

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

#### **Cattleguards**

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.

#### **Fence Requirement**


Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

#### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

**Figure.1 – Cross Sections and Plans For Typical Road Sections**



## VII. DRILLING

### A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

1. A Hydrogen Sulfide (H<sub>2</sub>S) Drilling Plan shall be activated 500 feet prior to drilling into the **Delaware** formation. **As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The top and bottom of Salt are to be recorded on the Completion Report.**

### B. CASING

**Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#).**

**Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).**

**Centralizers required on surface casing per Onshore Order 2.III.B.1.f.**

**Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. IF OPERATOR DOES NOT HAVE THE WELL SPECIFIC CEMENT DETAILS ONSITE PRIOR TO PUMPING THE CEMENT FOR EACH CASING STRING, THE WOC WILL BE 30 HOURS. See individual casing strings for details regarding lead cement slurry requirements.**

**No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.**

**High cave/karst**

**Capitan Reef.**

**Possibility of water and brine flows in the Salado and Artesia Groups.**

**Possibility of lost circulation in the Artesia Group, Delaware, and Bone Springs.**

1. The **20 inch** surface casing shall be set at approximately **350 feet (in a competent bed below the Magenta Dolomite, a Member of the Rustler)** and cemented to the surface. **Freshwater mud to be used to setting depth.**
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

2. The minimum required fill of cement behind the **13-3/8 inch 1st intermediate casing** is: **(Ensure casing is set in the Seven Rivers formation at approximately 1625')**

☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.**

3. The minimum required fill of cement behind the **9-5/8 inch, second intermediate casing, which shall be set at the base of the Capitan Reef**, is:

**Operator has proposed DV tool at depth of 1700', but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range. If an ECP is used, it is to be set a minimum of 50' below the shoe to provide cement across the shoe. If it cannot be set below the shoe, a CBL shall be run to verify cement coverage.**

- a. First stage to DV tool:

☒ Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.

- b. Second stage above DV tool:

☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst and potash.**

**Centralizers shall be placed to obtain good cement placement around the 7" casing in the curve, must be type for directional service and a minimum of one every other joint.**

4. The minimum required fill of cement behind the **7 inch production casing** is:

☒ Cement should tie-back at least **50 feet above the Capitan Reef** (Top of Capitan Reef estimated at 1680'). Operator shall provide method of verification. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to Capitan Reef and cave/karst.**

5. The minimum required fill of cement behind the **4-1/2 inch production Liner** is:

☒ Cement not required – Packer/Port system to be used.

6. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a

larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

**C. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. **A variance is granted for the use of a diverter on the 20" surface casing.**
3. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).
4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 13-3/8" first intermediate casing shoe shall be **2000 (2M) psi.**
5. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **9-5/8** intermediate casing shoe shall be **3000 (3M) psi.**
6. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer.**



- c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock.
- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

#### **D. DRILL STEM TEST**

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

#### **E. DRILLING MUD**

Approved for aerated mud, but not air drilling, in the Capitan Reef.

#### **F. WASTE MATERIAL AND FLUIDS**

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**CRW 080213**

## **VIII. PRODUCTION (POST DRILLING)**

### **A. WELL STRUCTURES & FACILITIES**

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

#### **Chemical and Fuel Secondary Containment and Exclosure Screening**

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

#### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

## **B. PIPELINES**

### **Temporary Freshwater Pipelines (Drilling and Fracturing Operations) CONDITIONS OF APPROVAL**

#### **Must follow existing disturbance.**

Maintain a copy of your temporary permit and your approved route diagram on location. BLM personnel may request to see a copy of your permit during construction to ensure compliance with all conditions of approval.

Holder agrees to comply with the following conditions of approval to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this permit.

2. Standard Conditions of Approval:

- Temporary pipelines must be removed within 30-45 days from this route unless granted in writing by the authorized officer.
- Temporary pipelines flowing from the frac pond to the target well(s) will be laid along existing roadways unless an exception has been granted by the authorized officer.
- Pipe will be hand-carried and hand-laid along any cross country portion of the approved route.
- Areas impacted (disturbed greater than vegetation compaction) by your project may require full reclamation.
- Pipelines will be empty before disassembly. Flow water back to the pond whenever possible.
- Do not restrict traffic on existing roads. Place ramps where needed.
- Pipe will be placed not more than 2 feet off the edge of existing lease roads, 2-track roads, or buried pipeline corridors.

- All pumps will be placed on existing disturbance (pads, roads, etc.).
3. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer.

**C. Frac Pond**

**BLM LEASE NUMBER:**

**COMPANY NAME:**

**ASSOCIATED WELL NAME:**

**FRAC POND CONDITIONS OF APPROVAL**

A copy of the application (APD, Grant, or Sundry Notice) and attachments, including stipulations, survey plat and diagram, will be on location during construction. BLM personnel may request to see a copy of your permit during construction to ensure compliance with all conditions of approval.

Holder agrees to comply with the following conditions of approval to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this permit.

2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated.

3. Required Standard Conditions of Approval:

**a. Notification**

Contact the Supervisory Environmental Protection Specialist, Jim Amos, at 575-234-5909 at least 24 hours prior to starting construction.

**b. Freshwater Only**

The frac pond will only be authorized to contain freshwater and testing of water quality is required. Additives are not allowed without consent of the authorized officer in writing.

**c. Contamination**

If at any time the water in the frac pond becomes polluted with salts or other contaminants, use of the frac pond will cease and desist, and all liquids will be removed from the frac pond and disposed of properly. The operator will preclude releases of oil into open pits. The operator must remove any accumulation of oil, condensate, or contaminant in a pit within 48 hours of discovery.

**d. Authorized Disturbance**

Confine all construction and maintenance activity to the approved authorized area applied for in the application.

**e. Facilities**

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations. Grey-water, sewage, and trash shall be removed from the site and disposed of properly at a state approved facility.

**f. Escape Ramps**

The operator will construct and maintain frac ponds to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in frac ponds. Escape ramps must be installed at every corner of the frac pond and in the center of each side if that side exceeds 100 feet in length. Escape ramps must be in contact with the side of the frac pond, bottom of the frac pond, and the top of the frac pond berm. Escape ramps cannot be made of metal and cannot be steeper than a 3:1 slope (Horizontal Distance: Vertical Distance) or 30% slope. (*Examples of escape ramps: 12" wide wooden planks wrapped in matting, felt lining, etc.*)

**g. Frac Pond Pipelines**

Temporary pipelines flowing from the frac pond to the target well will be laid along existing roadways unless an exception has been granted by the authorized officer in writing.

**h. Mineral Material from Excavation**

Mineral materials extracted during construction of the frac pond will be stored on-location and/or used for constructing the frac pond.

**i. Frac Pond Liner**

The frac pond will be lined with at least a 30 mil. plastic liner. The plastic lining will be removed prior to final abandonment.

**j. Topsoil Stockpile**

The operator shall strip at least the top 6 inches of soil (root zone) from the entire frac pond area and stockpile the topsoil approximately 25 feet outside the bermed perimeter of the pond in a low profile manner, reasonably protected from wind and water erosion. Topsoil shall not be used for constructing the frac pond. The topsoil will be used for final reclamation purposes only.

**k. Frac Pond Fence**

The operator will install and maintain enclosure fencing on all sides of the frac pond to prevent access to public, livestock, and large forms of wildlife. The fence shall be installed at the base of the berm and never on top of the berm.

Construction of the fence shall consist of steel and/or wooden posts set firmly into natural ground. Hog panel or chain-link fencing must be used as the fence and tied securely to the fence posts. Barbed-wire fencing or electric fences shall not be used. The fence height shall not be shorter than six (6) feet. The erected fence shall be maintained in adequate condition until the frac pond is reclaimed.

**l. Erosion Prevention**

Install earthen erosion-control structures as are suitable for the specific terrain and soil conditions.

**m. Reclamation Start**

- I. Reclamation efforts will commence immediately after the frac pond is no longer needed for the purpose of completing wells.
- II. Within 3 months of completion of frac operations on associated wells, all earthwork and final reclamation must be completed. This includes reclaiming and/or removal of:
  - i. Any roads approved for use with the pond
  - ii. Surface water lines
  - iii. Tanks, pumps, fencing etc.

**Requirements for Operations and Final Reclamation:**

4. If, during any phase of the construction, operation, maintenance, or termination of the frac pond, any pollutant should be released from the contaminated frac pond, the control and total removal, disposal, and cleaning up of such pollutant, wherever found, shall be the responsibility of holder, regardless of fault.

Upon failure of holder to control, dispose of, or clean up such discharge, or to repair all damages resulting there-from, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to

proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

6. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

7. After all disturbed areas have been satisfactorily contoured and prepared for seeding the location needs to be revegetated with the seed mixture provided. Seeding may need to be repeated until revegetation is successful. Operators shall contact Jim Amos, Supervisor, Environmental Protection – (575)234-5909, **prior** to beginning surface reclamation operations.

8. Seeding is required: Use the following seed mix.

- |  |  |
|--|--|
| <input checked="" type="checkbox"/> (X) seed mixture 1 | <input type="checkbox"/> ( ) seed mixture 3      |
| <input type="checkbox"/> ( ) seed mixture 2            | <input type="checkbox"/> ( ) seed mixture 4      |
| <input type="checkbox"/> ( ) LPC mixture               | <input type="checkbox"/> ( ) Aplomado Falcon mix |

#### **D. ELECTRIC LINES**

##### **STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES**

**A copy of the approved application and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.**

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on

facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.

5. Power lines shall be constructed in accordance to standards outlined in "Suggested Practices for Raptor Protection on Power lines, " Raptor Research Foundation, Inc., 1981. The holder shall assume the burden and expense of proving that pole designs not shown in the above publication are "raptor safe." Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.



9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, cave passages, or voids are penetrated during construction and no further construction will be done until clearance has been issued by the Authorized Officer. Special restoration stipulations or realignment may be required.
- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes with native soil from the removed poles.

## **IX. INTERIM RECLAMATION**

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for

production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

## **X. FINAL ABANDONMENT & RECLAMATION**

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

### Seed Mixture 1, for Loamy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (small/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains lovegrass ( <i>Eragrostis intermedia</i> )	0.5
Sand dropseed ( <i>Sporobolus cryptandrus</i> )	1.0
Sideoats grama ( <i>Bouteloua curtipendula</i> )	5.0
Plains bristlegrass ( <i>Setaria macrostachya</i> )	2.0

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed