Form 3160-3 (March 2012) RECEIVED MARGERALDING

FORM APPROVED OMB No. 1004-0137 Expires October 31, 2014

UNITED STATES NMOCD ARTESIA
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

5. Lease Serial No.

APPLICATION FOR PERMIT TO	DRILL	OR REENTER		6. If Indian, Allotee	or Tribe	Name	
la. Type of work:  DRILL  REENTE	ER .			7. If Unit or CA Agn	eement, Na	ime and I	No.
lb. Type of Well: Oil Well Gas Well Other	<b></b> ✓	Single Zone Multip	ole Zone	8. Lease Name and LONGVIEW FEDE		1H <b>&lt;</b>	:386
2. Name of Operator, RKI EXPLORATION & PRODUCTION,	LLC.	-246289	97	9. API Well No	5-9	122	23.
3a. Address 210 PARK AVENUE, SUITE 900 OKLAHOMA CITY, OKLAHOMA 73102		e No. (include area code) 7-2138 (JOEL ACOST.	A) (	O Field and Pool, or UNDESIGNATED	ソルモノ	₽ PRING	
4. Location of Well (Report location clearly and in accordance with an	ny State requ	tirements.*)	,	11. Sec., T. R. M. or F	Blk. and Su	rvey or A	rea
At surface 780 FNL & 1880 FEL, SECTION 12				SHL: SECTION 12 BHL: SECTION 1,			
At proposed prod. zone 330 FNL & 2245 FEL, SECTION 1				12 C		12 6	
14. Distance in miles and direction from nearest town or post office*  5 MILES NORTHEAST OF LOVING, NM				12. County or Parish EDDY		13, Stat NM	e
15. Distance from proposed* SHL: 540' location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)	16. No. 800	of acres in lease 798.88	17. Spacin 199.79 A	g Unit dedicated to this	well		
18. Distance from proposed location* SHL: 25'	19. Prop	osed Depth	20. BLM/E	BIA Bond No. on file			
to nearest well, drilling, completed, BHL: 530' B.S. 65' DEL. applied for, on this lease, ft.	TVD: 7 MD: 13	3,013'		1B-000460			
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3022.6' GL	22. Approximate date work will start*			23. Estimated duration 25 DAYS	n		
·	24. A	ttachments		•			
The following, completed in accordance with the requirements of Onshor	re Oil and (	Gas Order No.1, must be at	tached to thi	s form:			
<ol> <li>Well plat certified by a registered surveyor.</li> <li>A Drilling Plan.</li> <li>A Surface Use Plan (if the location is on National Forest System SUPO must be filed with the appropriate Forest Service Office).</li> </ol>	Lands, the	Item 20 above). 5. Operator certific	ation	ns unless covered by an	·		,
25. Signature An W. A.		ame (Printed/Typed) ARRY W. HUNT			Date 9/	13/	/3
Title PERMIT AGENT FOR RKI EXPLORATION & PRODUC	CTION, L	LC.			•		
Approved by (Signature)  Title /S/ STEPHEN J. CAFFEY	Na	ame (Printed/Typed)			MAR	19	2014
Title /S/ STEP FEM AND STEP FIELD MANAGER	Of	Tice CARLSBAD FIE	LD OFF	CE			
Application approval does not warrant or certify that the applicant hold conduct operations thereon.  Conditions of approval, if any, are attached.	s legal or o	equitable title to those right	ts in the sub	ject lease which would on PROVAL FOR	entitle the a	ipplicant YEA	.RS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

Carlsbad Controlled Water Basin

Approval Subject to General Requirements & Special Stipulations Attached

SEE ATTACHED FOR CONDITIONS OF APPROVAL

#### CERTIFICATION

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct, and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or RKI Exploration and Production, LLC am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U. S. C. 1001 for the filing of false statements. Executed this 13th day of September 2013.

Signed:

Printed Name: Barry Hunt

Position: Agent for RKI Exploration & Production, LLC. Address: 1403 Springs Farm Place, Carlsbad, NM 88220

Telephone: (575) 361-4078

E-mail: specialtpermitting@gmail.com

## RKI Exploration & Production LLC

3817 NW Expressway, Suite 950, Oklahoma City, OK 73112 405-949-2221 Fax 405-949-2223

June 25th, 2012

To Whom It May Concern:

Please be advised that Mr. Barry Hunt has been retained by RKI Exploration & Production to sign as our agent on Application for Permit to Drill (APD) as well as Right of Way applications within the States of New Mexico and Texas.

If you have any questions or require additional information, please feel free to contact me at (405) 996-5771.

Sincerely,

Charles K. Ahn

EH&S/Regulatory Manager

a K. Ahn

DISTRICT I
1623 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-616 Fax: (575) 393-0720
DISTRICT II
811 S. Fren St., Artesia, NM 88210
Phone: (575) 748-1228 Fax: (575) 748-9720
DISTRICT III
1000 Rio Braros Rd., Artes, NM 87410
Phone: (595) 334-6178 Fax: (595) 334-6170
DISTRICT IV
1220 S. B. Frencis Dr., Santa Fs., NM 87505
Phone: (590) 3476-3460 Fax: (505) 476-3462

246289

Section

Township

UL or lot no.

# State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION 1220 South St. Francis Dr. Santa Fe, New Mexico 87505

Form C-102 Revised August 1, 2011 Submit one copy to appropriate District Office

☐ AMENDED REPORT

1H

Elevation

3022.6'

County

East/West line

WELL LOCATION AND ACREAGE DEDICATION PLAT

CALLEGRAL BIGGRATED BONE SPRING

LINDESIGNATED BONE SPRING

Property Name
LONGVIEW FEDERAL 12

Operator Name

**RKI EXPLORATION & PRODUCTION** 

**Surface Location** 

North/South line


Feet from the

Feet from the

Lot Idn

ј В	12	23 S	28 E		780	NORTH	1880	EAST	EDDY
			Bott	om Hole l	Location If D	Different From Surfa	ce .		
UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
2	1	23 S	28 E	•	330	NORTH	2245	EAST	EDDY
Dedicated Acres	Joint of	r Infill	Consolidated Co	de Orde	er No.	·		13	3013
	ill be assig	ned to this	s completion u	ntil all inte	rests have bee	en consolidated or a no	n-standard unit has	been approved by	y the
SW/- SW/- NWC NMSP- Y = . LAT.= N32 LONG.= W104  NWC NMSP- Y = . LAT.= N32 LONG.= W104  W/4 C NMSP- Y = . X = . X = . X = . X = . X = . X = . X = . X = . X = . X = . X = . X = . X = . X = . X = . X = . X = . X = . X = .	COR SEC 1 OR SEC 12 E (NAD 83) 482924.8 N 629059.3' E 19 38.33" 02' 57.81" OR SEC 12 E (NAD 83) 480295.8' N 629045.6' E	— . LA	LONGVIE  LONGVIE  LONGVIE  LATE  LAT	1L (3) N E 3"	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	NE COR SEC 1 NMSP-E (NAD 83) Y = 488299.7' N X = 634415.7' E LAT.= N32° 20' 31.37" LONG.= W104° 01' 55.01"  SE COR SEC 1 NE COR SEC 12 NMSP-E (NAD 83) Y = 483007.7' N X = 634422.4' E LAT.= N32° 19' 39.00" LONG.= W104° 01' 55.10"  E/4 COR SEC 12 NMSP-E (NAD 83) Y = 4803415.1' E LAT.= N32° 19' 12.63" LONG.= W104° 01' 55.27"	I hereby certify therein is true and knowledge and be either owns a wo mineral interest in proposed bottom is drill this well at construct with an working interest, agreement or a cheretofore entered.  Signande  E-mail Address  SURVEYO I hereby certify the plat was plotted from the made by me or un same is true and summer to the plat was plotted from the plat was plat	DRS CERTIFIC at the well location own field notes of ac dear my supervision, correct to the best of	contained st of my regarization leased y the my regarization leased of the my regarded from t
							Job No.: WTC48  JAMES E. TOMPKIN  Certificate Number		

## SITE LOCATION



SCALE: 1" = 100'

SECTION 12, T 23 S, R 28 E, N.M.P.M.

COUNTY: EDDY

STATE: NM

DESCRIPTION: 780' FNL & 1880' FEL

OPERATOR: RKI EXPLORATION & PRODUCTION

WELL NAME: LONGVIEW FEDERAL 12-1H



#### DRIVING DIRECTIONS:

From the intersection of New Mexico State Highway 31 and County Road 605. Go north on County Road 605 for 0.4 mile and the location is on your left  $\pm 0.1$  mile.




WEST TEXAS CONSULTANTS, INC. ENGINEERS PLANNERS SURVEYORS 405 S.W. 1st. STREET ANDREWS, TEXAS 79714 (432) 523-2181

**RKI** EXPLORATION & PRODUCTION

JOB No.: WTC48745

## **LOCATION VERIFICATION MAP**



SCALE: 1" = 2000'

SECTION 12, T 23 S, R 28 E, N.M.P.M.

COUNTY: EDDY

STATE: NM

DESCRIPTION: 780' FNL & 1880' FEL

OPERATOR: RKI EXPLORATION & PRODUCTION

WELL NAME: LONGVIEW FEDERAL 12-1H



#### **DRIVING DIRECTIONS:**

From the intersection of New Mexico State Highway 31 and County Road 605. Go north on County Road 605 for 0.4 mile and the location is on your left  $\pm 0.1$  mile.




WEST TEXAS CONSULTANTS, INC. ENGINEERS PLANNERS SURVEYORS 405 S.W. 1st. STREET -ANDREWS, TEXAS 79714 (432) 523-2181

**RKI** EXPLORATION & PRODUCTION

JOB No.: WTC48745

### **AERIAL MAP**



SCALE: 1" = 2000'

SECTION 12, T 23 S, R 28 E, N.M.P.M.

COUNTY: EDDY

STATE: NM

DESCRIPTION: 780' FNL & 1880' FEL

OPERATOR: RKI EXPLORATION & PRODUCTION

WELL NAME: LONGVIEW FEDERAL 12-1H



#### **DRIVING DIRECTIONS:**


From the intersection of New Mexico State Highway 31 and County Road 605. Go north on County Road 605 for 0.4 mile and the location is on your left ±0.1 mile.



WEST TEXAS CONSULTANTS, INC.
ENGINEERS PLANNERS SURVEYORS
405 S.W. 1st. STREET
ANDREWS, TEXAS 79714
(432) 523-2181

**RKI EXPLORATION & PRODUCTION** 

## **VICINITY MAP**



SECTION 12, T 23 S, R 28 E, N.M.P.M.

COUNTY: EDDY

STATE: NM

DESCRIPTION: 780' FNL & 1880' FEL

OPERATOR: RKI EXPLORATION & PRODUCTION

WELL NAME: LONGVIEW FEDERAL 12-1H



#### **DRIVING DIRECTIONS:**

From the intersection of New Mexico State Highway 31 and County Road 605. Go north on County Road 605 for 0.4 mile and the location is on your left  $\pm 0.1$  mile.





WEST TEXAS CONSULTANTS, INC. ENGINEERS PLANNERS SURVEYORS 405 S.W. 1st STREET ANDREWS, TEXAS 79714

(432) 523-2181

**RKI** EXPLORATION & PRODUCTION


JOB No.: WTC48745





## E-Line, Gas & Sw.D Lines Ex. E

## SITE LOCATION



SCALE: 1" = 100'

SECTION 12, T 23 S, R 28 E, N.M.P.M.

COUNTY: EDDY

STATE: NM

DESCRIPTION: 780' FNL & 1880' FEL

**OPERATOR: RKI EXPLORATION & PRODUCTION** 

WELL NAME: LONGVIEW FEDERAL 12-1H + 2 H



#### **DRIVING DIRECTIONS:**

From the intersection of New Mexico State Highway 31 and County Road 605. Go north on County Road 605 for 0.4 mile and the location is on your left ±0.1 mile.



WEST TEXAS CONSULTANTS, INC.

ENGINEERS PLANNERS SURVEYORS 405 S.W. 1st. STREET ANDREWS, TEXAS 79714 (432) 523-2181

RKI EXPLORATION & PRODUCTION

JOB No.: WTC48745

#### RKI Exploration & Production, LLC

#### **Brilling Plan**

Well

Longview Federal 12-1H

Location

Surface:

780 FNL

1.880 FEL

Section 12-23S-28E

Bottom Hole:

330 FNL

2,245 FEL

Section 1-23S-28E

'Eddy County

State

**New Mexico** 

- 1) The elevation of the unprepared ground is 3,023 feet above sea level.
- 2) The geologic name of the surface formation is Quaternary Alluvium.
- 3) A rotary rig will be utilized to drill the well to 13,562 feet and run casing and cement. This equipment will then be rigged down and the well will be completed with a workover rig.
- 4) Proposed depth is 13,562 feet MD

#### 5) Estimated tops:

•	TVD	MD	
Rustler	203	203	•
Salado	245 r	245	•
Top of Salt	512	512	
Base of Salt	2,555	2,555	BHP = .44 psi/ft x depth
Lamar Lime	2,735	2,735	1,203 psi
Base of Lime	2,774	2,774	1,221 psi
Delaware Top	2,820	2,820 Oil	1,241 psi
Bell Canyon Sand	2,820	2,820 Oil	<b>1,241</b> psi
Cherry Canyon Sand	3,681	3,681 Oil	1,620 psi
Brushy Canyon Sand	5,905	5,905 Oil	2,598 psi
Bone Spring	6,071	6,071 Oil	2,671 psi
KOP	6,907	6,967 Oil	3,039 psi
Bone Spring 1st Sand	7,332	7,389 Oil	3,226 psi
Landing Point	7,480	7,867 Oil	3,291 psi
TD	7,480	13,562	3,291 psi

Water anticipated at 150 feet.

180 degree F

#### 6) Pressure control equipment:

The blowout preventer equipment (BOP) shown in Exhibit #1 will consist of a double ram type (3,000 psi WP) preventer, a bag-type annular preventer (3,000 psi WP), and rotating head. Both units will be hydraulically operated and the ram type preventer will be equipped with blind rams on top and pipe rams (sized to accommodate the drill pipe size being utilized) on bottom. A 13 3/8" SOW x:13 5/8" 5M multi-bowl casing head will be installed on the 13 3/8" casing and utilized until total depth is reached. All BOP and associated equipment will be tested to 3,000 psi and the annular will be tested to 1,500 psi after initial installation. The 13 3/8" and 9 5/8" casing will be tested to .22 psi per ft of casing string length or 1,500 psi whichever is greater, but not to exceed 70% of the minimum yield.

The 9 5/8" casing will be hung in the casing multi-bowl head and the stack will not be nippled down at this point. The stack will not be isolated and tested after running the 9 5/8" casing, but will be tested along with the 9 5/8" casing. Pipe rams will be operated and checked each 24 hour period and each time the drill string is out of the hole.

These function test will be documented on the daily driller's log.

A drilling spool or blowout preventer with 2 side outlets (choke side shall be 3" minimum diameter, kill side shall be at least 2" diameter).

2 kill line valves, one of which will be a check valve.

2 chokes on the manifold along with a pressure gauge.

Upper kelly cock valve with handle available.

Safety valve and subs to fit all drill string connections in use.

All BOP equipment connections subjected to pressure will be flanged, welded, or clamped.

Fill up line above the upper most preventer.



#### 7) Casing program: ALL NEW CASING OD Csg Hole Top **Bottom** -Wt/Grade Connection Collapse Burst Tension Size Design Design . Design Factor Factor Factor 17 1/2" 0 13 3/8" 54.5#/J-55 ST&C 5.71 27.58 20.96 4,000 12 1/4" 0 9 5/8" 40#/J-55 LT&C 1.15 4.49 3.25 8 3/4" 0 7,867 7" 26#/P-110 LT&C 1.79 1.99 3.90 6 1/8" 6,867 13,562 4 1/2" 11.6#/HCP-110 **Buttress** 1.45 2.14 10.26 Collapse 1.125 Burst 1.0 Tension 2.0 8) Cement program:

17 1/2" hole **Surface** Pipe OD 13 3/8" \_450 ft Setting Depth 0.69462 cf/ft Annular Volume Excess 100 %

Lead 357 sx 1.75 cf/sk 13.5 ppg Tail 250 sx 1.34 cf/sk 14.8 ppg

Lead: "C" + 4% PF20 (gel) + 2% PF1 (CC) + .125 pps PF29 (CelloFlake) + .2% PF46 (antifoam)

Tail: "C" + 1% PF1 (CC)

Top of cement: Surface

12 1/4" hole Intermediate Pipe OD 9 5/8" 4,000 ft **Setting Depth** Annular Volume 0.31318 cf/ft

0.3627 cf/ft 50 % **Excess** 0.5

Lead 858 sx 1.92 cf/sk 12.9 ppg Tail 200 sx 1.33 cf/sk 14.8 ppg

Lead: 35/65 Poz "C" + 5% PF44 (salt) + 6% PF20 (gel) + 3 pps PF42 (KoalSeal) + .125 pps PF 29 (CelloFlake) + .2% PF46 (antifoam) + 1% PF1 (CC)

Tail: "C" + .2% PF13 (retarder)

Top of cement: Surface

8 3/4" hole Intermediate Pipe OD **Setting Depth** 7,867 ft

0.15033 cf/ft 0.1585 cf/ft 500 ft Annular Volume

0.35 Excess 35 %

DV Tool Depth 5,500 ft

Stage 1

325 sx 1.48 cf/sk 13.0 ppg Lead:

Lead: PVL + 2% PF174 (expanding agent) + .3% PF167 (Uniflac) + .1% PF65 (dispersant) + .2% PF13 (retarder) + .25 pps PF46 (antifloam)

Top of cement: DV tool

Stage 2

1.89 cf/sk Lead: 139 sx 12.9 ppg Tail: 100 sx 1.48 cf/sk 13.0 ppg

Lead: 35/65 Poz "C" + 5% PF44 (salt) + 6% PF20 (gel) + .125 pps PF29 (CelloFlake) + .2% PF13 (retarder) + .25 pps PF46 (antifoam)

Tail: PVL + 1.3% PF44 (salt) + 5% PF174 (expander) +.5% FP606 (gel suppressing agent) + .25 pps PF46 (antifoam) + .2% PF13 (reatarder)

Top of cement: 3,500 ft

6 1/8" hole Liner Pipe OD 4 1/2" 13,562 ft

Baker Frac Point System

**Setting Depth** 

#### 9) Mud program:

	Тор	Bottom	Mud Wt.	Vis	PV	ΥP	Fluid Loss	Type System
Dy	0 28	450-	8.5 to 8.9	32 to 36	1 - 6	1 - 6	NC	Fresh Water
COM	450	4,000	9.8 to 10.0	28 to 30	1 - 3	1 - 3 ·	NC	Brine
COH	4,000	13,562	8.9 to 9.1	28 to 36	1 - 3	1 - 3	NC	Fresh Water

The necessary mud products for weight addition and fluid loss control will be on location at all times. Electronic pit monitoring equipment will be utilized with a Pason system. Electronic mud monitoring and mud logging will be utilized below the 9 5/8" casing.

#### 10) Logging, coring, and testing program:

No drill stem test are planned KOP to intermediate: CNL, Caliper, GR, DLL, Intermediate to surface: CNL, GR No coring is planned

### 11) Potential hazards:

No abnormal pressure or temperature is expected. No H2S is known to exist in the area, although some form of H2S detection equipment will be utilized. If H2S is encountered the operator will comply with the provisions of Onshore Order No. 6. Lost circulation is not anticipated, but lost circulation material and weighting materials will be on location and readily available.

12) Anticipated start date ASAP
Duration 25 days

## **RKI Exploration & Production**

Eddy County (NM83E) Sec 12-T23S-R28E Longview Fed 12-1H

Wellbore #1


Plan: Prelim Plan #2

## **Standard Planning Report**

30 October, 2013

## RKI Exploration & Production

Project: Eddy County (NM83E) Site: Sec 12-T23S-R28E Well: Longview Fed 12-1H Wellbore: Wellbore #1 Design: Prelim Plan #2



Magnetic Field Strength: 48429.0snT Dip Angle: 60.15° Date: 09/06/2013 Model: IGRF2010





5400-

South(-)/North(+) (1200 ft/in) (200-3600-3600-3600-

2400

1800

Section Line

330 Hardline

Longview Fed 12-1H PBHL

BHL

330' FNL / 2245' FEL

TD at 13562.1



+N/-S +E/-W Northing 0.0 0.0 482198.60

375

Ground Level: 0.0
Easting Latittude Longitude
632541.20 32°19' 31.046 N 104°2' 17.052 W
SHL: 780' FNL / 1880' FEL of Sec 12
BHL: 330' FNL / 2245' FEL of Sec 1

#### SECTION DETAILS


+N/-S +E/-W DLeg TFace VSec Target 0.0 0.0 0.00 0.00 0.0 MD TVD Inc Azi 0.0 0.00 0.00 0.0 3419.9 0.00 0.00 3419.9 0.0 0.0 0.00 0.00 0.0 4019.9 12.00 215.37 4015.5 -36.2 2.00 215.37 -48.7 -51.0 -318.8 0.00 0.00 -428.5 -355.0 2.00 180.00 -477.2 Longview Fed 12-1H TGT 6367.0 12.00 215.37 6311.4 -449.0 6967.0 0.00 0.00 6907.0 -500.0 7867.0 90.00 360.00 7480.0 73.0 -355.0 10.00 360.00 94.7 13562.1 90.00 360.00 7480.0 5768.0 -355.4 0.00 0.00 5779.0 Longview Fed 12-1H PBHL

#### PROJECT TARGET DETAILS (MAP CO-ORDINATES)

Name +N/-S +E/-W Northing Easting Shape Longview Fed 12-1H TGT 6907.0 -500.0 -355.0 481697.62 632187.58 Point Longview Fed 12-1H PBHL7480.0 5768.0 -355.4 487965.60 632169.90 Point

1500

1875



Vertical Section at 356.47° (750 ft/in)

Planning Report

EDM-2003:21 Single User Db RKI Exploration & Production Eddy County Alexand Local Co-ordinate Reference: Well Longview Fed 12-1H Company: Project: Site: WELL @ 0.0ft (Original Well Elev) WELL @ 0.0ft (Original Well Elev) TVD Reference: Eddy County (NM83E) Sec 12-T235-R28E Longview Fed 12-1H MD Reference: True North Reference: Well: Minimum Curvature Survey Calculation Method: Wellbore: Wellbore #1 Prelim Plan #2 Design:

Sec 12-T23S-R28E 482,006.50ft Site Position: Northing: 32° 19' 29.227 N Latitude: Easting: 629,491.90ft 104° 2' 52.596 W From: Мар Longitude: 0.15° **Position Uncertainty:** 0.0 ft Slot Radius: **Grid Convergence:** 

Well: Longview Fed 12-1H 482,198.60 ft 32° 19' 31.046 N Well Position 183.7 ft Northing: Latitude: +N/-S 632,541.20 ft 104° 2' 17.052 W +E/-W 3,049.8 ft Easting: Longitude: Wellhead Elevation: ft **Ground Level:** 0.0ft **Position Uncertainty** 0.0 ft

Design 🐍 Prelim Plan #2 **Audit Notes:** Version: Phase: **PROTOTYPE** Tie On Depth: 0.0 Depth From (TVD) Direction (ft) 💈 (ft) (°); 0.0 0.0 0.0 356.47

Plan Sections									
Measured Depth In	clination		Vertical 🦑 🖟	+N/-S	+E/-W	Rate	Rate	Turn Rate /100ft)	TFO
0.0	0.00	0.00	0.0	(ft) 0.0	0.0	0.00	0.00	0.00	0.00
3,419.9	. 0.00	0.00	3,419.9	0.0	0.0	0.00	0.00	0.00	0.00
4,019.9 6,367.0	12.00 12.00	215.37 215.37	4,015.5 6,311.4	-51.0 <b>-44</b> 9.0	-36.2 -318.8	2.00 0.00	2.00 0.00	0.00 0.00	215.37 0.00
6,967.0	0.00	0.00	6,907.0	-500.0	-355.0	2.00	-2.00	0.00	180.00 Longview Fed 12-1
7,867.0 13,562.1	90.00 90.00	360.00 360.00	7,480.0 7,480.0	73.0 5,768.0	-355.0 -355.4	10.00 0.00	10.00 0.00	0.00 0.00	360.00 0.00 Longview Fed 12-1

Planning Report

Database: EDM'2003:21 Single User Db.
Company: RKI Exploration & Production
Project: Eddy County (NM83E)
Site: Sec 12:T23S R28E
Well: Longview Fed 12-1H
Wellbore: Wellbore #1

Eocal Co-ordinate Reference:
TVD Reference:
MD Reference:
North Reference:
Survey Calculation Method:

Well Longview Fed 12-1H.
WELL @ 0.0ft (Original Well Elev)
WELL @ 0.0ft (Original Well Elev)

Minimum Curvature

Wellbore: Wellbore #1
Design: Prelim Plan #2

Planned Survey				A MERCHANIA					
								1.4.54	
Measured Depth			Vertical	+N/-S		/ertical Section	Dogleg Rate	Build Rate	Turn Rate
	Inclination :		) (ff) / (f)	、TM/つ (ft)	(ft)	The state of the same and the same	STATE OF THE PARTY		(°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0 400.0	0.00 0.00	0.00 0.00	300.0 400.0	0.0 0.0	0.0 0.0	0.0 0.0	0.00 0.00	0.00 0.00	0.00 0.00
500.0 600.0	0.00 0.00	0.00 0.00	500.0 600.0	0.0 0.0	. 0.0 0.0	0.0 0.0	0.00 0.00	0.00 0.00	0.00 0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	. 0.00	0.00
1,000.0 1,100.0	0.00 0.00	0.00	1,000.0 1,100.0	0.0 0.0	0.0	0.0 0.0	0.00 0.00	0.00	0.00 0.00
1,100.0	0.00	0.00 0.00	1,100.0	0.0	0.0 0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0 1,700.0	0.00 0.00	0.00	1,600.0	0.0 0.0	0.0 0.0	0.0 0.0	0.00 0.00	0.00 0.00	0.00 0.00
1,800.0	0.00	0.00 0.00	1,700.0 1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00
2,200.0 2,300.0	0.00 0.00	0.00	2,200.0 2,300.0	0.0 - 0.0	.0.0 0.0	0.0 0.0	0.00 0.00	0.00 0.00	0.00 0.00
2,400.0	0.00	0.00 0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00
2,500.0	0.00	0.00	2,500.0	0.0	0.0	0.0	0.00	0.00	0.00
2,600.0	0.00	0.00	2,600.0	0.0	0.0	0.0	0.00	0.00	0.00
2,700.0	0.00	0.00	2,700.0	0.0	0.0	0.0	0.00	0.00	0.00
2,800.0 2,900.0	0.00 0.00	0.00 0.00	.2,800.0 2,900.0	0.0 0.0	0.0 0.0	. 0.0 0.0	0.00 0.00	0.00 0.00	0.00 0.00
3,000.0	0.00	0.00	3,000.0	0.0	0.0	0.0	0.00	0.00	0.00
3,100.0	0.00	0.00	3,100.0	0.0	0.0	0.0	0.00	0.00	0.00
3,200.0	0.00	0.00	3,200.0	0.0	0.0	0.0	0.00	0.00	0.00
3,300.0 3,400.0	0.00	0.00 0.00	3,300.0 3,400.0	0.0 0.0	0.0 0.0	0.0 0.0	0.00 0.00	0.00 0.00	0.00 0.00
			•				0.00	0.00	0.00
3,419.9 Bulld 2/100	0.00	0.00	3,419.9	0.0	0.0	0.0		0.00	0.00
3,500.0	1.60	215.37	3,500.0	-0.9	-0.6	-0.9	2.00	2.00	0.00
3,600.0	3.60	215.37	3,599.9	-4.6	-3.3	-4.4 10.6	2.00	2.00 <sup>-</sup>	0.00
3,700.0 3,800.0	5.60 7.60	215.37 215.37	3,699.6 3,798.9	-11.2 -20.5	-7.9 -14.6	-10.6 -19.6	2.00 2.00	2.00 2.00	0.00 0.00
3,900.0	9.60	215.37	3,897.8	-32.7	-23.2	-31.2	2.00	2.00	0.00
4,000.0	11.60	215.37	3,996.0	-32.1 -47.7	-33.9	-31.2 -45.6	2.00	2.00	0.00
4,019.9	12.00	215.37	4,015.5	-51.0	-36.2	-48.7	2.00	2.00	0.00
Begin Hold				646		61.7			
4,100.0 4,200.0	12.00 12.00	215.37 215.37	4,093.9 4,191.7	-64.6 -81.6	-45.9 -57.9	-61.7 -77.9	0.00 0.00	0.00 0.00	0.00 0.00
4,300.0	12.00	215.37	4,289.5	-98.5	-70.0	-94.0	0.00	0.00	0.00
4,400.0	12.00	215.37 215.37	4,289.5 4,387.3	-96.5 -115.5	-70.0 -82.0	- <del>94</del> .0 -110.2	0.00	0.00	0.00
4,500.0	12.00	215.37	4,485.1	-132.4	-94.0	-126.4	0.00	0.00	0.00
4,600.0	12.00	215.37	4,582.9	-149.4	-106.1	-142.6	0.00	0.00	0.00
4,700.0	12.00	215,37	4,680.8	-166.3	-118.1	-158.8	0.00	0.00	0.00
4,800.0 4,900.0	12.00 12.00	215.37 215.37	4,778.6 4,876.4	-183.3 -200.3	-130,1 -142,2	-174.9 -191.1	0.00 0.00	0.00 0.00	0.00 0.00
4,500.0	12.00	210,3/	4,070.4	-200.3	-174.4	-10/1,1	0.00	0.00	0.00

Planning Report

EDM 2003:21 Single User Db Database: Local Co-ordinate Reference: Well Longview Fed 12-1H Company: TVD Reference: MD Reference: North Reference: Survey Calculation Method: RKI Exploration & Production WELL @ 0.0ft (Original Well Elev) (Eddy County (NM83E) Project: WELL @ 0.0ft (Original Well Elev) Sec.12-T23S-R28E Longylew Fed.12-1H Wellbore #19 True Minimum Curvăture Site: Well: Well: Wellbore: Prelim Plan #2 Design:

Planned Survey		Prod. as to a				e and the second		The same of	
				the b					
Measured Depth			Vertical Depth			Vertical	Dögleg	Build	Turn
(ft)	Inclination (*)	د Azimuth ه د (۵)	(ft)	+N/-S. (ft)	+E/-W (ft)	Section (ft)	Rate (*/100ft)* *	Rate (°/100ft)	Rate (°/100ft)
5,000.0	12.00	215.37	4,974,2	-217.2	-154.2	-207.3	0.00	0.00	0.00
5,100.0	12.00	215.37	5,072.0	-234.2		-223.5	0.00	0.00	0.00
5,200.0	12.00	215.37	5,169.8	-251.1	-178.3	-239.7	0.00	0.00	0.00
5,300.0	12.00	215.37	5,267.6	-268.1	-190.3	-255.8	0.00	0.00	0.00
5,400.0 5,500.0	12.00 12.00	215.37 215.37	5,365.5 5,463.3	-285.0 -302.0	-202.4 -214.4	-272.0 -288.2	0.00 0.00	0.00	0.00
5,600.0	12.00	215.37	5,561.1	-318.9	-226.4	-304.4	0.00	0.00	0.00 0.00 -
5,700.0	12.00	215.37	5,658.9	-335.9	-238.5	-320.6	0.00	0.00	0.00
5,800.0	12.00	215.37	5,756.7	-352.8	-250.5	-336.8	0.00	0.00	0.00
5,900.0 6,000.0	12.00 12.00	215.37 215.37	5,854.5 5,952.4	-369.8 -386.7	-262.5 -274.6	-352.9 -369,1	0.00 0.00	0.00 0.00	0.00 0.00
6,100.0	12.00	215.37	6,050.2	-403.7	-286.6	-385.3	0.00	0.00	0.00
6,200.0	12.00	215.37	6,148.0	<b>-420</b> .6	-298.7	<del>-4</del> 01.5	0.00	0.00	0.00
6,300.0	12.00	215.37	6,245.8	-437.6	-310.7	-417.7	0.00	0.00	0.00
6,367.0 Drop 2/10	12.00	215.37	6,311.4	-449.0	-31 <b>8.8</b>	-428.5	0.00	0.00	0.00
6,400.0	11.34	215.37	6,343.7	-454.4	-322.6	<b>-433.7</b>	2.00	-2.00	0.00
6,500.0	9.34	215.37	6,442.0	-469.0	-333.0	<del>-44</del> 7.7	2.00	-2.00	0.00
6,600.0	7.34	215.37	6,541.0	-480.9	-341.4	-458.9	2.00	-2.00	0.00
6,700.0	5.34	215.37	6,640.3	-489.9	-347.8	-467.5	2.00	-2.00	0.00
6,800.0 6,900.0	3.34 1.34	215.37 215.37	6,740.0 6,840.0	-496.0 -499.4	-352.2 -354.5	-473.4 -476.6	2.00 2.00	-2.00 -2.00	0.00 0.00
6,967.0	0.00	0.00	6,907.0	-500.0	-355.0	-477.2	2.00	-2.00	0.00
KOP - 10/1	100 - Longview	Fed.12-1H.T							
7,000.0	3.30	360.00	6,939.9	-499.1	-355.0	-476.3	10.00	10.00	0.00
7,050.0 7,100.0	8.30 13.30	360.00 360.00	6,989.7 7,038.8	-494.0 -484.6	-355.0 -355.0	-471.2 -461.9	10.00 10.00	10.00 10.00	0.00 0.00
7,150.0	18.30	360.00	7,086.9	-471.0	-355.0		10.00	10.00	0.00
7,200.0 7,250.0	23.30 28.30	360.00 360.00	7,133.6 7,178.6	-453.3 -431.5	-355.0 -355.0	<b>-430.6</b>	10.00	10.00	0.00
7,300.0	33.30	360.00				-408.9	10.00	10.00	0.00
7,300.0	38.30 38.30	360.00	7,221.5 7,262.1	-405.9 -376.7	-355.0 -355.0	-383.3 -354.2	10.00 10.00	10.00 10.00	0.00 0.00
7,400.0	43.30	360.00	7.299.9	-344.1	-355.0	-321.6	10.00	10.00	0.00
7,450.0 7,500.0	48.30 53.30	360.00 360.00	7,334.8 7,366.4	-308.2 -269.5	-355.0 -355.0	-285.8 -247.1	10.00 10.00	10.00 10.00	0.00
7,550.0	58.30	360.00	7,394.5	-209.3	-355.0	-247.1	10.00	10.00	0.00
7,600.0	63.30	360.00	7,418.8	-184.5	-355.0 -355.0	-205.9 -162.3	10.00	10.00	0.00
7,650.0 7,700.0	68.30	360.00	7,439.3	-138.9	-355.0	-116.8	10.00	10.00	0.00
7,700.0	73.30 78.30	360.00 360.00	7,455.8 7,468.0	-91.7 -43.3	-355.0 -355.0	-69.7 -21.4	10.00 10.00	10.00 10.00	0.00 0.00
7,800.0	83.30	360.00	7.476.0	6.1	-355.0	27.9	10.00	10.00	0.00
7,850.0	. 88.30	360.00	7,479.7	55.9	-355.0	77.6	10.00	10.00	0.00
7,867.0	90.00 d to TD	360.00	7,480.0	73.0	-355.0	94.7	10.00	10.00	0.00
7,900.0	90.00	360.00	7,480.0	105.9	-355.0	127.5	0.00	0.00	0.00
8,000.0	90.00	360.00	7,480.0	205.9	-355.0	227.4	0.00	0.00	0.00
8,100.0	90.00	360.00	7,480.0	305.9	-355.1	327.2	0.00	0.00	0.00
8,200.0	90.00	360.00	7,480.0	405.9	-355.1	427.0	0.00	0.00	0.00
8,300.0 8,400.0	90.00 90.00	360.00. 360.00	7,480.0 7,480.0	505.9 605.9	-355.1 -355.1	526.8 626.6	0.00 0.00	0.00 0.00	0.00 0.00
8,500.0	90.00	360.00	7,480.0	705.9	-355.1	726.4	0.00	0.00	0.00
8,600.0	90.00	360.00	7,480.0	805.9	-355.1	826.2	0.00	0.00	0.00
8,700.0	90.00	360.00	7,480.0	905.9	-355.1	926.0	0.00	0.00	0.00

Planning Report

EDM 2003.21 Single User Db RKI Exploration & Production Database: Project: Eddy County (NM83E)

Prelim Plan #2

Site: Well: Sec 12-T23S-R28E Longview Fed 12-1H Wellbore #1 Wellbore:

Local Co-ordinate Reference: TVD Reference: MD Reference: North Reference: North Reference. Survey Calculation Method:

Well Longview Fed 12-1H WELL @ 0:0ft (Original Well Elev) WELL @ 0.0ft (Original Well Elev)

True Minimum Curvature

Plan		

Depth (ft)	Inclination					O 47	The same of the sa	D-4	D-4-
(m) (s. j.			Depth	+N/-S	+E/-W	Section	Rate	Rate	Rate
		14 (°) : 4 (§)	i. (ft)		(ft)	(ft)	(-/100π)	(°/100ft)	(°/100ft)
8,800.0	90.00	360.00	7,480.0	1,005.9	-355.1	1,025.8	0.00	0.00	0.00
8,900.0	90.00	360.00	7,480.0	1,105.9	-355.1	1,125.7	0.00	0.00	0.00
9,000.0	90.00	360.00	7,480.0	1,205.9	`-355.1	1,225.5	0.00	0.00	0.00
9,100.0	90.00	360.00	7,480.0	1,305.9	-355.1	1,325.3	0.00	0.00	0.00
9,200.0	90.00	360.00	7,480.0 7,480.0	1,405.9	-355.1	1,425.1	0.00	0.00	0.00
9,300.0	90.00	360.00	7,480.0	1,505.9	-355.1	1,524.9	0.00	0.00	0.00
9,400.0	90.00	360.00	7,480.0	1,605.9	-355.1	1,624.7	0.00	0.00	0.00
9,500.0	90.00	360.00	7,480.0	1,705.9	-355.1	1,724.5	0.00	0.00	0.00
·				•		·			0.00
9,600.0	90.00 90.00	360.00 360.00	7,480.0	1,805.9 1,905.9	-355.1 -355.2	1,824.3 1,924 <i>.</i> 1	0.00 0.00	0.00 0.00	0.00
9,700.0 9,800.0	90.00	360.00	7,480.0 7,480.0	2,005.9	-355.2 -355.2	2,024.0	0.00	0.00	0.00
9,800.0	90.00	360.00	7,480.0 7,480.0	2,005.9	-355.2 -355.2	2,024.0	0.00	0.00	0.00
10,000.0	90.00	360.00	7,480.0 7,480.0	2,105.9	-355.2	2,123.6	0.00	0.00	0.00
•				·					
10,100.0	90.00	360.00	7,480.0	2,305.9	-355.2	2,323.4	0.00	0.00	0.00
10,200.0	90.00	360.00	7,480.0	2,405.9	-355.2	2,423.2	0.00	0.00	0.00
10,300.0	90.00	360.00	7,480.0	2,505.9	-355.2	2,523.0	0.00	0.00	0.00
10,400.0	90.00	360.00	7,480.0	2,605.9	-355.2	2,622.8	0.00	0.00	0.00
10,500.0	90.00	360.00	7,480.0	2,705.9	-355.2	2,722.6	0.00	0.00	0.00
10,600.0	90.00	360.00	7,480.0	2,805.9	<i>-</i> 355.2	2,822.4	0.00	0.00	0.00
10,700.0	90.00	360.00	7,480.0	2,905.9	-355.2	2,922.3	0.00	0.00	0.00
10,800.0	90.00	360.00	7,480.0	3,005.9	-355.2	3,022.1	0.00	0.00	0.00
10,900.0	90.00	360.00	7,480.0	3,105.9	-355.2	3,121.9	0.00	0.00	0.00
11,000.0	90.00	360.00	7,480.0	3,205.9	-355.2	3,221.7	0.00	0.00	0.00
11,100.0	90.00	360.00	7,480.0	3,305.9	-355.2	3,321.5	0.00	0.00	0.00
11,200.0	90.00	360.00	7,480.0	3,405.9	-355.3	3,421.3	0.00	0.00	0.00
11,300.0	90.00	360.00	7,480.0	3,505.9	-355.3	3,521.1	0.00	0.00	0.00
11,400.0	90.00	360.00	7,480.0	3,605.9	-355.3	3,620.9	0.00	0.00	0.00
11,500.0	90.00	360.00	7,480.0	3,705.9	-355.3	3,720.7	0.00	0.00	0.00
11,600.0	90.00	360.00	7,480.0	3,805.9	-355.3	3,820.6	0.00	0.00	0.00
11,700.0	90.00	360.00	7,480.0	3,905.9	-355.3	3,920.4	0.00	0.00	0.00
11,800.0	90.00	360.00	7,480.0	4,005.9	-355.3	4,020.2	0.00	0.00	0.00
11,900.0	90.00	360.00	7,480.0	4,105.9	-355.3	4,120.0	0.00	0.00	0.00
12,000.0	90.00	360.00	7,480.0	4,205.9	-355.3	4,219.8	0.00	0.00	0.00
12,100.0	90.00	360.00	7,480.0	4,305.9	-355.3	4,319.6	0.00	0.00	0.00
12,200.0	90.00	360.00	7,480.0	4,405.9	-355.3	4,419.4	0.00	0.00	0.00
12,300.0	90.00	360.00	7,480.0	4,505.9	-355.3	4,519.2	0.00	0.00	0.00
12,400.0	90.00	360.00	7,480.0	4,605.9	-355.3	4,619.0	0.00	0.00	0.00
12,500.0	90.00	360.00	7,480.0	4,705.9	-355.3	4,718.9	0.00	0.00	0.00
12,600.0	90.00	360.00	7,480.0	4,805.9	-355.3	4,818.7	0.00	0.00	0.00
12,700.0	90.00	360.00	7,480.0	4,905.9	-355.4	4,918.5	0.00	0.00	0.00
12,800.0	90.00	360.00	7,480.0	5,005.9	-355.4	5,018.3	0.00	0.00	0.00
12,900.0	90.00	360.00	7,480.0	5,105.9	-355.4	5,118.1	0.00	0.00	0.00
13,000.0	90.00	360.00	7,480.0	5,205.9	-355.4	5,217.9	0.00	0.00	0.00
13,100.0	90.00	360.00	7,480.0	5,305.9	-355.4	5,317.7	0.00	0.00	0.00
13,200.0	90.00	360.00	7,480.0	5,405.9	-355.4	5,417.5	0.00	0.00	0.00
13,300.0	90.00	360.00	7,480.0	5,505.9	-355.4	5,517.3	0.00	0.00	0.00
13,400.0	90.00	360.00	7,480.0	5,605.9	-355.4	5,617.2	0.00	0.00	0.00
13,500.0	90.00	360.00	7,480.0	5,705.9	-355.4	5,717.0	0.00	0.00	0.00
13,562.1		360.00	7.480.0	5.768.0	i -355.4	5,779.0	0.00	0.00	0.00

## **RKI Exploration & Production**

Eddy County (NM83E) Sec 12-T23S-R28E Longview Fed 12-1H

Wellbore #1 Prelim Plan

## **Anticollision Report**

06 September, 2013

#### **Anticollision Report**

RKI Exploration & Production Well Longview Fed 12-1H Company: Local Co-ordinate Reference: Project: TVD Reference: WELL @ 0.0ft (Original Well Elev) Eddy County (NM83E) Sec 12-T23S-R28E WELL @ 0.0ft (Original Well Elev). Reference Site: MD Reference: True Minimum Curvature Site Error: 0.0ft North Reference: Reference Well: Longview Fed 12-1H Survey Calculation Method: 2.00 sigma 0.0ft Output errors are at Well Error: Database: EDM 2003.21 Single User Db Reference Wellbore Wellbore #1 Offset TVD Reference: Reference Design: Prelim Plan Offset Datum

Reference: Prelim Plan

Filter type: NO GLOBAL FILTER: Using user defined selection & filtering criteria

Interpolation Method: Stations Error Model: ISCWSA

 Depth Range:
 Unlimited
 Scan Method:
 Closest Approach 3D

 Results Limited by:
 Maximum center-center distance of 10,000.0ft
 Error Surface:
 Elliptical Conic

Warning Levels Evaluated at: 2.00 Sigma

9	Survey Tool Progra From (ft)	m To (ft)	Date Surve	2013/09/06 ý (Wellbore)	Tool Na	ime Descr	iption	
-	0.0	13,01	3.0 Prelim	Plan (Wellbore #1)	MWD	MWD	- Standard	and the state of t

Summary		Alexander Co				
			Commence of the Commence of th		The said of the sa	
	Reference Measured	Offset Measured E	Distance Between Be	1 100	paration	1162
Site Name	Depth	Depth	Centres El	lipses 🧎	Factor	V . %
Offset Well- Wellbore - Design	(ft)	(ft)	(ft).*	(ft): (//////	and the second s	
L Sec 12-T23S-R28E	Agent and the second		ر الله الماري الله الماري الله الماري . الماري الماري الماري الماري الماري الماري الماري الماري الماري الماري	n a ku i dhama.	The state of the s	البيني سأ
Longview Fed 12-2H - Wellbore #1 - Prelim Plan	6,907.0	6,907.0	24.7	-6.1	0.801 Level 1, CC	1
Longview Fed 12-2H - Wellbore #1 - Prelim Plan	6,950.0	6,950.0	24.8	-6.2	0.800 Level 1, ES, SF	

Offset D	)esign	Sec 12	2-T23S-R	28E - Long	view Fe	d 12-2H -	Wellbore #1	Prelim,F	lan 🤼			1373	Offset Site Error:	0.0 ft
Cumou Dec	aram O.M	WD *	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	w . A d' stops	1	N N W. S. 113	Carrier Barrer and Carrier Carr		Dista	2			Offset Well Error:	0.0 ft
Refer	rence		et 🦠	Semi Major	Axis 💨		Offset Wellboi	Sul Mark	Dista	nce				
Measured	Vertical	Measured N	Vertical	Reference	Offset 🐤	Highside	Offset Wellbo	e Centre	80	Between	Minimum	Separation	Warning	
Depth	Depth	Depth	Depth	1	and the same of th	Toolface	+N/-S (ff)	+E/-W	Centres	Ellipses	Separation (ft)	Factor		7 4
(ft)"	(ft)	(ft)	, (n), E	3 . (n) 3 %	·· (π) 🤏 🐧	\$ \V[2]\.	21 w (ft) 1 y 0 . 2 9 5	(ft); */: n	(m) · -	(ft):	e * (π) · · · ·	1 2 1	Marie Land	7
0.0	0.0	0.0	0.0	0.0	0.0	89.00	0.4	24.7	24.7					
100,0		100.0	100.0	0.1	0,1	89.00	0.4	24.7	24.7	24.5		109.915		
200.0		200.0	200.0	0.3	0.3	89.00	0.4	24.7	24.7	24.0		36.638		
300.0		300.0	300.0	0.6	0.6	89.00	0.4	24.7	24.7	23.6		21.983		
400.0		400.0	400.0	8.0	8.0	89.00	0.4	24.7	24.7	23.1		15.702		
500.0	500.0	500.0	500.0	1.0	1.0	89.00	0.4	24.7	24.7	22.7	2.02	12.213		
600.0	600.0	600.0	600.0	1,2	1.2	89.00	0.4	24,7	24.7	22.2	2.47	9.992		
700.0		700.0	700.0	1,5	1.5	89.00	0.4	24.7	24.7	21.8		8.455		
800.0		800.0	800.0	1.7	1.7	89.00	0.4	24.7	24.7	21.3		7.328		
900.0	900.0	900.0	900.0	1.9	1.9	89.00	0.4	24.7	24.7	20.9	3.82	6.466		
1,000.0	1,000.0	1,000.0	1,000.0	2.1	2.1	89.00	0.4	24.7	24.7	20.4	4.27	5.785		
1,100,0	1,100.0	1,100.0	1,100.0	2.4	2.4	89.00	0.4	24.7	24.7	20.0	4.72	5.234		
1,200.0	1,200.0	1,200.0	1,200.0	2.6	2.6	89.00	0.4	24.7	24.7	19.5	5.17	4.779		
1,300.0	1,300.0	1,300.0	1,300.0	2.8	2.8	89.00	0.4	24.7	24.7	19.1	5.62	4.397		
1,400.0	1,400.0	1,400.0	1,400,0	3.0	3.0	00,68	0.4	24.7	. 24.7	18.6	6,07	4,071		
1,500.0	1,500.0	1,500.0	1,500.0	3.3	3.3	89.00	0.4	24.7	24.7	18.2	6.52	3.790		
1,600.0	1,600.0	1,600.0	1,600.0	3.5	3.5	89.00	0.4	24.7	24.7	17.7	6.97	3.546		
1,700.0	1,700.0	1,700.0	1,700.0	3.7	3.7	89.00	0.4	24.7	24.7	17.3	7.42	3.331		
1,800.0	1,800.0	1,800.0	1,800.0	3.9	3.9	89.00	0.4	24.7	24.7	16.8	7,87	3.140		
1,900.0	1,900.0	1,900.0	1,900.0	4.2	4.2	89.00	0.4	24.7	24.7	· 16.4	8.32	2.971		
2,000.0	2,000.0	2,000.0	2,000.0	4.4	4.4	89.00	0.4	24.7	24.7	. 15.9	8.77	2.818		
2,100.0	2,100.0	2,100.0	2,100.0	4.6	4.6	89.00	0.4	24.7	24.7	15.5	9.22	2.681		
2,200.0	2,200.0	2,200.0	2,200.0	4.8	4.8	89.00	0.4	24.7	24.7	15.0	9.66	2.556		
2,300.0	2,300.0	2,300.0	2,300.0	5.1	5.1	89.00	0.4	24,7	24.7	14.6	10.11	2.443		
2,400,0	2,400.0	2,400.0	2,400.0	5.3	5.3	89.00	0.4	24.7	24.7	14.1	10.56	, 2.339		

#### **Anticollision Report**

Well Longview Fed 12-1H RKI Exploration & Production Company: Local Co-ordinate Reference Project: Reference Site: Site Error: Eddy County (NM83E) TVD Reference: WELL @ 0.0ft (Original Well Elev) Sec 12-T23S-R28E WELL @ 0.0ft (Original Well Elev) MD Reference: True Minimum Curvature 0:0ft North Reference: Longview Fed 12-1H Reference Well: Survey Calculation Method: Well Error: 0.0ft 2.00 sigma 📑 Output errors are at Database: Reference Wellbore Wellbore #1 EDM 2003.21 Single User Db Reference Design: Prelim Plan Offset TVD Reference: Offset Datum

Offset D	esign 💅	Sec 12	T23S-R	28E Longv	iew Fe	d 12-2H	Wellbore #1	Prelim P	lan		The market	Offset Site Error:	0.0 ft • 😼
Survey Pro	gram: 0 M	WD 🐇	£ 2. 21.	Semi Major A				Andreas Charles			1	Offset Well Error:	0.0ft 🏄
							Offset Wellbon	9-1-	& Distar	ICO:	X 2 2 2 2 3	The second secon	e s de
Measured Depth	Vertical	Measured ::	Vertical	Reference	)ffset ] ,a	Highside ** Toolface **	Offset Wellbon	e Centre +E/-W	Between E	Setween Filinses	Minimum;	Separation Warning Factor	
(ft).	் (ft) ஃ	(n)	₹ (ft) ₹ "	(ñ) ∢	(ft)	ૺૺ૽૾ૺૢ૿ૣૺૺૺ૿૽ૢ૽૾ૺ૽૽ૺ૽૽ૺ૱૽૽ૺૺ૱ૺૺૺૺૺૺૺ૽૽ૺૺૺૺૺૺૺૺ૽૽ૺૺૺૺૺૺૺૺ	, (n)	(ft) 3	🎉 (ft) 🐞	(ft) 3.5	3 (ft)		
2,500.0		2,500.0	2,500.0	5.5	5.5	89.00	0.4	24.7	24.7	13.7	11.01	2.243	1 1 1
2,600.0	2,600.0	2,600.0	2,600.0	5.7	5.7	89.00	0.4	24.7	24.7	13.2	11.46	2.155	
2,700.0	2,700.0	2,700.0	2,700.0	6.0	6.0	89.00	0.4	24.7	24.7	12.8	11.91	2.074	
2,800.0	2,800.0	2,800.0	2,800.0	6,2	6.2	89.00	0.4	24.7	24.7	12.3	12.36	1.998	
2,900.0	2,900.0	2,900.0	2,900.0	6.4	6.4	89.00	0.4	24.7	24.7	11.9	12.81	1,928	
3,000.0	3,000.0	3,000.0	3,000.0	6.6	6.6	89.00	0.4	24.7	24.7	11.4	13,26	1.863	
3,100.0	3,100.0	3,100.0	3,100.0	6.9	6.9	89.00	0.4	24.7	24.7	11.0	13.71	1.802	
3,200.0	3,200.0	3,200.0	3,200.0	7.1	7.1	89.00	0.4	24.7	24.7	10.5	14.16	1.745	
3,300.0	3,300.0	3,300.0	3,300.0	7.3	7.3	89.00	0.4	24.7	24.7	10,1	14.61	1.691	
3,400.0	3,400.0	3,400.0	3,400.0	7.5	7.5	89.00	0.4	24.7	24.7	9.6	15.06	1.641	
3,500.0	3,500.0	3,500.0	3,500.0	7.8	7.8	89.00	0.4	24.7	24.7	9.2	15.51	1.593	
3 600 0	2 600 0	9 600 0	3 600 0		9.0	90.00	0.4	24.7	247	0.7	45.00	4.540	
3,600.0 3,700.0	3,600.0 3,700.0	3,600.0 3,700.0	3,600.0 3,700.0	8.0 8.2	8.0 8.2	89,00 89.00	0.4 0.4	24.7 24.7	24.7 24.7	8.7 8.3	15.96 16,41	1.548 1,506	
3,800.0	3,800.0	3,800.0	3,800.0	8.4	8.4	89.00	0.4	24.7 24.7	24.7	7.8	16.86	1,466 Level 3	
3,900.0	3,900.0	3,900.0	3,900.0	8.7	8.7	89.00	0.4	24.7	24.7	7.4	17.31	1.427 Level 3	
4,000.0	4,000.0	4,000.0	4,000.0	8.9	8.9	89.00	0.4	24.7	24.7	6.9	17.76	1.391 Level 3	
1											•		
4,100.0	4,100.0	4,100.0	4,100.0	9.1	9.1	89.00	0.4	24.7	24.7	6.5	18.21	1.357 Level 3	
4,200.0	4,200.0	4,200.0	4,200.0	9.3	9.3	89.00	0.4	24.7	24.7	6.0	18,66	1,324 Level 3	
4,300.0	4,300.0	4,300.0	4,300.0	9.6	9.6	89.00	ນ 0.4	24.7		5.6	19.11	1.293 Level 3	
4,400.0 4,500.0	4,400.0 4,500.0	4,400.0 4,500.0	4,400.0 4,500.0	9.8 10.0	9.8 10.0	89.00 89.00	0.4 0.4	24.7 24.7	24.7 24.7	5.2 4.7	19.55 20.00	1.263 Level 3 1.235 Level 2	
4,300.0	4,300.0	4,300.0	4,500.0	10.0	10.0	05.00	0.4	24.1	. 24.1	4.7	20.00	1.233 Level 2	
4,600.0	4,600.0	4,600.0	4,600.0	10.2	10,2	89.00	0.4	24.7	24.7	4.3	20.45	1.208 Level 2	
4,700:0	4,700.0	4,700.0	4,700.0	10,5	10.5	89.00	0,4	24.7	24.7	3.8	20.90	1.182 Level 2	
4,800.0	4,800.0	4,800.0	4,800.0	10.7	10.7	89.00	0.4	24.7	24.7	3.4	21.35	1.157 Level 2	
4,900.0	4,900.0	4,900.0	4,900.0	10.9	10.9	89.00	0.4	24.7	24.7	2.9	21.80	1.133 Level 2	
5,000.0	5,000.0	5,000.0	5,000.0	11.1	11.1	89.00	0.4	24.7	24.7	2.5	22.25	1.110 Level 2	
5,100.0	5,100.0	5,100.0	5,100.0	11.4	11.4	89.00	0.4	24.7	24.7	2.0	22.70	1:088 Level 2	
5,200.0	5,200.0	5,200.0	5,200.0	11.6	11.6	89.00	0.4	24.7	24.7	1.6	23.15	1.067 Level 2	
5,300.0	5,300.0	5,300.0	5,300.0	11.8	11.8	89.00	0.4	24.7	24.7	1.1	23.60	1.047 Level 2	
5,400.0	5,400.0	5,400.0	5,400.0	12.0	12.0	89.00	.0.4	24.7	24.7	0.7	24.05	1.027 Level 2	
5,500.0	5,500.0	5,500.0	5,500.0	12.2	12.2	89.00	0.4	24.7	24.7	0.2	24.50	1.008 Level 2	
5,600.0	5,600.0	5,600.0	5,600.0	12.5	12.5	89.00	0.4	24.7	24.7	-0.2	24.95	0.990 Level 1	
5,700.0	5,700.0	5,700.0	5,700.0	12.7	12.7	89.00	0.4	24.7	24.7	-0.2	25.40	0.973 Level 1	
5,800.0	5,800.0	5,800.0	5,800.0	12.9	12.9	89.00	0.4	24.7	24.7	-1.1	25.85	0.956 Level 1	
5,900.0	5,900.0	5,900.0	5,900.0	13.1	13.1	89.00	0.4	24.7	24.7	-1.6	26,30	0.939 Level 1	
6,000.0	6,000.0	6,000.0	6,000.0	13.4	13.4	89.00	0.4	24.7	24.7	-2.0	26,75	0.924 Level 1	
6 400 0	C 400 C	C 100 0	6 400 0	40.0	40.0	90.00	0.4	04.7	017		07.00	0.008 Lovel 4	
6,100.0 6,200.0	6,100.0 6,200.0	6,100.0 - 6,200.0	6,100.0 6,200.0	13.6 13.8	13.6 13.8	89.00 89.00	0.4 0.4	24.7 24.7	24.7 24.7	-2.5 -2.9	27.20 27.65	0.908 Level 1 0.894 Level 1	
6,300.0	6,300.0	6,300.0	6,300.0	14.0	14.0	89.00	0.4	24.7 24.7	24.7 24.7	-2.9 -3.4	28,10	0.879 Level 1	
6,400.0	6,400.0	6,400.0	6,400.0	14.3	14.3	89.00	0.4	24.7	24.7	-3.8	28.55	0.865 Level 1	
6,500.0	6,500.0	6,500.0	6,500.0	14.5	14.5	89.00	0.4	24.7	24.7	-4.3	28.99	0.852 Level 1	
ŀ	·												
6,600.0	6,600.0	6,600.0	6,600.0	14.7	14.7	89.00	0.4	24.7	24.7	-4.7	29.44	0.839 Level 1	
6,700.0		6,700.0	6,700.0	14.9	14.9	89.00	0.4	24.7	24.7	-5.2	29.89	0.826 Level 1	
6,800.0	6,800.0	6,800.0	6,800.0	15.2	15.2	89.00	0.4	24.7	24.7	-5.6	30.34	0.814 Level 1	
6,907.0 6,950.0	6,907.0 6,950.0	6,907.0 6,950.0	6,907.0 6,950.0	15.4 15.5	15.4 15.5	89.00 96.22	0.4 0.4	24.7 24.7	24.7 24.8	-6.1 -6.2	30.82 31.02	0.801 Level 1, CC 0.800 Level 1, ES, SF	
0.000,0	บ.บธธ,บ	0,930.0	0,000.0	13.5	13.5	50.22	U.4	24.7	24.8	-6.2	31.02	0.000 Level 1, E3, 3F	
7,000.0	6,999.6	6,999.6	6,999.6	15.6	15.6	109.00	0.4	, 24.7	. 26.1	-5.1	31.20	0.838 Level 1	
7,050.0	7,048.5	7,048.5	7,048.5	15.7	15.7	126.48	0.4	24.7	31.0	-0.2	31,20	0.995 Level 1	
7,100.0	7,096.4	7,096.4	7,086.4	15.8	15.8	141.84	0.4	24.7	41.4	10.6	30.85	1.343 Level 3	•
7,150.0	7,142.8	7,142.8	7,142.8	16.0	15.9	152.42	0.4	24.7	57.4	27.2	30.25	1.898	
7,200.0	7,187.4	7,187.4	7,187.4	16.1	16.0	159.17	0.4	24.7	78.4	48.9	29.47	2.659	
7,250.0	7,229.9	7,229.9	7,229.9	16.2	16.1	163.48	0.4	24.7	103.7	75.1	28,55	3,632	
.,200,0	.,	.,	,,					.47.1	700,1	7 9.1	20,00		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

**Anticollision Report** 

Well-Longview Fed 12-1H WELL @ 0.0ft (Original Well Elev) RKI Exploration & Production Company: Local Co-ordinate Reference: TVD Reference: Eddy County (NM83E) Reference Site: Sec 12-T23S-R28E MD Reference: WELL @ 0.0ft (Original Well Elev) MD Reference: ATrue Minimum Curvature 0.0ft Longview Fed 12-1H Site Error: Reference Well: Survey Calculation Method: Output errors are at Well Error: 0.0ft 2.00 sigma Reference Wellbore Wellbore #1 Reference Design: Prelim Plan Database: 党 EDM 2003.21 Single User Db Offset TVD Reference: Offset Datum.

Offset D		Sec 12	2-T23S-R		gview F	ed 12-2H	- Wellböre #1 -	Prelim Pl	an 🔭	The same of the		1 1 1 1 1	Offset Site Error:	/ /0.0ft 5
Survey Pro		WD Offs		Semi Major	Α	4.90		colls.				7. 13.	Offset Well Error:	0.0 ft
		Measured				Highside:	Öffset Wellbor	e Centre	Dista Between	Between.	Minimum	Separation	Warning	
Depth	Depth	Depth	Depth	Control of the	100	Toolface	+N/-S	+E/-W (ft)	Centres	Ellipses	Separation	Factor	100	10,700
(ft)	(ft)	(ft)	(ft):	(m)	(ft)**-	(°).	(ft)	(ft) ,	/ (ft) "您	(ft)	, (tt) %	19 22 C	A STATE OF THE	小小 明山
7,300.0			7,269.9	16.3	16.2	166.28	0.4	24.7	133,0	105.4	27.52	4.831		
7,350.0 7,400.0	7,307.2 7,341.4	•	7,307.2 7,341.4	16.5 16.7	16.3 16.4	168.12 169.31	. 0.4	24.7	165.8	139.4	26.39	6.282		
7,450.0	7,341.4		7,341.4	16.7	16.5	169.99	0.4 0.4	24.7 24.7	201.9 240.9	176.7 217.0	25.20 23.97	8.012 10.050		
7,500.0	7,399.7		7,399.7	17.2	16,5	170.26	0.4	24.7	282.6	259.8	22.76	12.417		
7,550.0	7,423.3	7,423.3	7,423.3	17.4	16,6	170.08	0.4	24.7	326.5	304,9	21,61	15,105		
7,600.0	7,443.0	7,443.0	7,443.0	17.8	16.6	100.00	2.4	24.7	070.0		20.00	40.045		
7,650.0	7,458.6		7,458.6	18.1	16.6 16.7	169.36 167.72	0.4 0.4	24.7 24.7	372.3 419.7	351.7 399.7	20.63 19.97	18.043 21.017		
7,700.0	7,470.0		7,470.0	18.5	16.7	164,14	0.4	24.7	468.3	448,3	19.98	23.435		
7,750.0	7,477.2		7,477.2	19.0	16.7	154.35	0.4	24.7	517.7	495.5	22.20	23.316		
7,800.0	7,480.0	7,480.0	7,480.0	19.4	16.7	105.77	0.4	24.7	567.5	532.5	35.09	16.175		
7,807.0	7,480.0	7,480.0	7,480.0	19.5	16.7	90.00	0.4	24.7	574.6	538.4	36.19	15.877		
7,900.0	7,480.0		7,480.0	20,4	16.7	90.00	0.4	24.7 24.7	667.5	630,3	37.13	17.976		
8,000.0	7,480.0		7,480.0	21.6	16.7	90.00	0.4	24.7	767.4	729.1	38.25	20.062		
8,100.0	7,480.0	7,480.0	7,480.0	22.8	16.7	90,00	0.4	24.7	867.4	827.9	39.47	21.976		
8,200.0	7,480.0	9,115.2	8,400.0	24.1	25.3	173.2 <del>6</del>	961.3	49.7	926.4	903.6	22.81	40.613		
8,300.0	7,480.0	9,214.8	8,400.0	25.4	26.5	172,73	1,060.8	52.3	927.5	903.7	23.81	38.962		
8,400.0	7,480.0		8,400.0	26.9	27.8	172.19	1,160.4	54.9	928.7	903.8	24.88	37.322		
8,500.0	7,480.0	9,414.1	8,400.0	28.3	29.2	171.66	1,260.0	57.4	929.9	903.9	26.04	35.714		
8,600.0	7,480.0		8,400.0	29.9	30.6	171.13	1,359.6	60.0	931.2	903.9	27.27	34.153		
8,700.0	7,480.0	9,613.3	8,400.0	31.4	32.1	170.60	1,459.2	62.6	932.6	904.0	28.56	32.651		
8,800.0	7,480.0	9,712.9	8,400.0	33.0	33.6	170.08	1,558.8	65.2	934,1	904.2	29.93	31.213		
8,900.0	7,480.0		8,400.0	34.6	35.1	169.55	1,658.3	67,8	935.6	904.3	31.35	29.842		
9,000.0	7,480.0		8,400.0	36.2	36.6	169.03	1,757.9	70.4	937.3	904.4	32.84	28.542		
9,100.0	7,480.0		8,400.0	37.9	38.2	168.51	1,857.5	73.0	939.0	904.6	34.38	27.310		
9,200.0	7,480.0	10,111.4	8,400.0	39.6	39.8	167.99	1,957.1	75.6	940.8	904.8	35.98	26.145		
9,300.0	7,480.0	10,211.0	8,400.0	41.2	41.4	167.47	2,056.7	78.1	. 942.6	905.0	37.64	25.046		
9,400.0	7,480.0	10,310.6	8,400.0	42.9	43.0	166.95	2,156.3	80.7	944.6	905.2	39.34	24.009		
9,500.0	7,480.0		8,400.0	44.7	44.7	166.44	2,255.8	83.3	946.6	905.5	41.10	23.031		
9,600.0	7,480.0	10,509.9	8,400.0	46.4	46.3	165.93	2,355.4	85.9	948.7	905.8	42.91	22.110		
9,700.0	7,480.0	10,609.5	8,400.0	48,1	48.0	165.42	2,455.0	88.5	950.8	906,1	44.76	21.241		
9,800.0	7,480.0	10,709.1	8,400.0	49.9	49.6	164.91	2,554.6	91.1	953.1	906.4	46.67	20.423		
9,900.0	7,480.0	10,808.7	8,400.0	51.6	51.3	164.41	2,654.2	93.7	955.4	906.8	48.62	19.651		
10,000.0	7,480.0	10,908.3	8,400.0	53.4	53.0	163.91	2,753.8	96.3	957.8	907.2	50.62	18.922		
10,100.0	7,480.0 7,480.0	11,008.0 11,107.6	8,400.0 8,400.0	55.1 56.9	54.7 56.4	163,41 162,91	2,853.3 2,952.9	98.9 101.4	960.3 962.8	907.6 908.1	52.66 54.75	18,235 17,586		
			•	50.5			2,002.0	101.4	302.0	30a.1	J4.73	17,300		
10,300.0	7,480.0	11,207.2	8,400.0	58.7	58.1	162.42	3,052.5	104.0	965.4	908.6	56.88	16.973		
10,400.0	7,480.0	11,306.8	8,400.0 8,400.0	60.5	59.9	161.92	3,152.1	106.6	968.1	909.1	59.05	16.394	•	
10,500.0	7,480.0 7,480.0	11,406.4 . 11,506.0	8,400.0 8,400.0	62.2 64.0	61.6 63.3	161,44 160,95	3,251.7 3,351.3	109.2 111.8	970.9 973.7	909.6 910.2	61.27 63.53	15.845 15.326		
10,700.0	7,480.0	11,605.7	8,400.0	65.8	65.1	160.95	3,450.8	114.4	976.6	910.2	65.83	14.835		
10 000 0	7 400 0	44 705 0	9 400 0	07.0	00.0	450.00	2.550.4	447.0	670.0	n44 *				
10,800.0 10,900.0	7,480.0 7,480.0	11,705.3 11,804.9	8,400.0 8,400.0	67.6 69.4	66.8 68.5	159.99 159.51	3,550.4 3.650.0	117.0 <sup>,</sup> 119.6	979.6 982.6	911.4 912.1	68.17 70.56	14.369 13.927	•	
11,000.0	7,480.0	11,904.5	8,400.0	71.2	70.3	159.03	3,749.6	122.1	985.7	912.7	72.98	13.507		
11,100.0	7,480.0	12,004.1	8,400.0	73.0	72.0	158,56	3,849.2	124.7	988.9	913.4	75.44	13.109		
11,200.0	7,480.0	12,103.7	8,400.0	74.8	73.8	158.09	3,948.8	127.3	992.1	914.2	77.94	12.730		
11,300.0	7,480.0	12,203.4	8,400.0	76.6	75.5	157.09	V UVB 3	120.0	OUE 4	015.0	PU 47	17 270		
11,400.0	7,480.0 7,480.0	12,203.4	8,400.0 8,400.0	76.6 78.4	75.5 77.3	157.83 157.17	4,048.3 4,147.9	129.9 132.5	995.4 998.8	915.0 915.8	80.47 83,04	12.370 12.027		
11,500.0	7,480.0	12,402.6	8,400.0	80.2	79.1	156.71	4,247.5	135.1	1,002.2	916.6	85,65	11,701		
11,600.0	7,480.0	12,502.2	8,400.0	82.1	80.8	156.25	4,347.1	137.7	1,005.7	917.4	88.30	11.390		
11,700.0	7,480.0	12,601.8	8,400.0	83.9	82.6	155.80	4,446.7	140.3	1,009.3	918.3	90.98	11.094		
11,800,0	7,480:0	12,701.4	8,400,0	85.7	944	155,35	A 546 3	142.0	1,012.9	010.2	03.60	10.011	*	
11,000,0	1,400,0	14,701.4	0,400.0	65./	84.4	133,35	4,546.3	142.9	1,012.9	919.2	93.69	10.811		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: Project: Reference Site: RKI Exploration & Production Local Co-ordinate Reference: Well Longview Fed 12-1H Eddy County (NM83E) TVD Reference: WELL @:0.0ft (Original Well Elev) Sec 12-T23S-R28E MD Reference: WELL @ 0.0ft (Original Well Elev) True Minimum Curvature 0.0ft Longview Fed 12-1H Site Error: North Reference: Reference Well: Survey Calculation Method: 0.0ft 2.00 sigma Well Error: Output errors are at Wellbore #1 EDM 2003.21 Single User Db Reference Wellbore Database: Prelim Plan Offset TVD Reference: Offset Datum Reference Design:

Offset D	esian	Sec 12	-T23S-R	28E Lon	oview F	d 12-2H	Wellbore #1/-	Prelim Pl	an 📆	Charles Hall		100	Offset Site Error: 0.0 ft
	gram: 0-M	WD " ' " '			3			1,000				والمرابعة والمراجعة	Offset Well Error: 0.0 ft
Refer	ence 🤲								10 to 10 10 10 10 10 10 10 10 10 10 10 10 10				
Measured							Offset Wellbor	a 30 2.00				4 4 4 3 7 4	
		Depth	Depth			Toolface	二张军 22.500000000000000000000000000000000000				Separation	Factor	
( <mark>ti</mark> )	(t) (t)	(ft)	1(11)5	( <del>n</del> )	(n).	(3), (3), (3)	(ft)	(ft) ****	(ft)	(ft) + <sup>n</sup>	(ft) 🦠 🐪		
11,900.0	7,480.0	12,801.1	8,400.0	87.5	86.1	154.90	4,645.8	145.4	1,016.6	920.2	96.44	10.541	
12,000.0	7,480.0	12,900.7	8,400.0	89.3	87.9	154.46	4,745.4	148.0	1,020.4	921.1	99.22	10.284	
12,100.0	7,480.0	13,000.3	8,400.0	91.2	89.7	154.02	4,845.0	150.6	1,024.2	922.1	102.03	10.038	
12,200.0	7,480.0	13,099.9	8,400.0	93.0	91.5	153.58	4,944.6	153.2	1,028.0	923.2	104.88	9.802	
12,300.0	7,480.0	13,199.5	8,400.0	94.8	93.2	153.15	5,044.2	155.8	1,032.0	924.2	107.75	9,577	
12,400.0	7,480.0	13,299.2	8,400.0	96.6	95.0	152.72	5,143.8	158.4	1,036.0	925.3	110.66	9.362	
12,500.0	7,480.0	13,398.8	8,400.0	98.4	96.8	152.29	5,243.3	161.0	1,040.0	926.4	113.60	9.155	
12,600.0	7,480.0	13,498.4	8,400.0	100,3	98.6	151.87	5,342.9	163.6	1,044.1	927.6	116.56	8.958	
12,700.0	7,480.0	13,598.0	8,400.0	102.1	100.3	151.45	5,442,5	166.2	1,048.3	928.7	119.56	8.768	·
12,800.0	7,480.0	13,697.6	8,400.0	103.9	102.1	151.03	5,542.1	168.7	1,052.5	929.9	122.58	8.586	
12,900.0	7,480.0	13,797.2	8,400.0	105.8	103.9	150.62	5,641.7	171.3	1,056.8	931.1	125.63	8.412	
i													1
13,000.0		13,896.9	8,400.0	107.6	105.7	150.21	5,741.3	173.9	1,061.1		128.71	8.244	
13,013.0	7,480.0	13,909.8	8,400.0	107.8	105.9	150.16	5,754.2	174.3	1,061.7	932.6	129.11	8.223	


**Anticollision Report** 

RKI Exploration & Production Well Longview Fed 12-1H Company: Local Co-ordinate Reference: Project: Eddy County (NM83E) TVD Reference: WELL @ 0.0ft (Original Well Elev) Sec 12-1235-R28E MD Reference: Reference Site: WELL @ 0.0ft (Original Well Elev) 0.0ft Longview Fed 12-1H True Minimum Curvature Site Error: North Reference: Reference Well: Survey Calculation Method: Well Error: 0.0ft 2:00 sigma Output errors are at EDM 2003.21 Single User Db Reference Wellbore Wellbore #1 Database: Offset TVD Reference: Offset Datum Reference Design: Prelim Plan

Reference Depths are relative to WELL @ 0.0ft (Original Well Elev)
Offset Depths are relative to Offset Datum

Central Meridian is 104° 20' 0.000 W °

Coordinates are relative to: Longview Fed 12-1H Coordinate System is US State Plane 1983, New Mexico Eastern Zone Grid Convergence at Surface is: 0.16°



LEGEND

Longview Fed 12-2H, Wellbore #1, Prelim Plan VO

**Anticollision Report** 

RKI Exploration & Production Company: ¿ Local Co-ordinate Reference: Well Longview Fed 12-1H Eddy County (NM83E) 🙏 TVD Reference: Project: WELL @ 0.0ft (Original Well Elev) Sec 12-T23S-R28E 0.0ft Reference Site: MD Reference: WELL @ 0.0ft (Original Well Elev) True Minimum Curvature North Reference: Site Error: Reference Well: Longview Fed 12-1H Survey Calculation Method: 🎏 0.0ft Output errors are at Well Error: 2.00 sigma Reference Wellbore Wellbore #1 Database: EDM 2003.21 Single User Db Reference Design: Prelim Plan Offset TVD Reference: Offset Datum


Reference Depths are relative to WELL @ 0.0ft (Original Well Elev)


Offset Depths are relative to Offset Datum Central Meridian is 104° 20' 0.000 W °

Coordinates are relative to: Longview Fed 12-1H


Coordinate System is US State Plane 1983, New Mexico Eastern Zone


Grid Convergence at Surface is: 0.16°






## GE DILY Gas Multi-bowl Wellhead





#### **EXHIBIT D**


### Rig Plat Only LONGVIEW FEDERAL 12-1H & 12-2H V-DOOR WEST





#### **EXHIBIT C**

# Interim Reclamation & Production Facilities LONGVIEW FEDERAL 12-1H & 12-2H V-DOOR WEST



#### SURFACE USE PLAN

RKI Exploration & Production, LLC Longview Federal 12-1H Surface Hole: 780' FNL & 1880' FEL Section 12, T. 23 S., R. 28 E Bottom Hole: 330' FNL & 2245' FEL Section 1, T. 23 S., R. 28 E Eddy County, New Mexico


This plan is submitted with form 3160-3, Application for Permit to Drill, covering the above described well. The purpose of this plan is to describe the location of the proposed well, the proposed construction activities and operations plan, the magnitude of the surface disturbance involved and the procedures to be followed in rehabilitating the surface after completion of the operations, so that a complete appraisal can be made of the environmental effect associated with the operations.

#### 1. EXISTING ROADS:

- A. DIRECTIONS: Go east of Carlsbad, NM, on Highway 62/180, for 1.2 miles. Turn southeast onto the County Road 605 (Refinery Road) for 11.5 miles. The beginning point of proposed access road begins at this point. All existing roads are either paved or a caliche lease road.
- B. See attached plats and maps provided by WTC Surveys.
- C. The access routes from County Road 605 to the well location is depicted on **Exhibit A.** The route highlighted in red is all within the same lease and will not require a ROW permit.
- D. Existing roads on the access route will be improved and maintained to the standard set forth in Section 2 of this Surface Use Plan of Operations.

#### 2. NEW OR RECONSTRUCTED ACCESS ROADS:

- A. The new access road will begin at the northeast corner of the proposed well location and run east northeast for 290.7 ft. to the Old Refinery Road or County Road 605.
- B. The maximum width of the driving surface will be 14 feet. The road will be crowned and ditched with a 2% slope from the tip of the crown to the edge of the driving surface. The ditches will be 1 foot deep with 3:1 slopes. The driving surface will be made of 6" rolled and compacted caliche.



#### **Level Ground Section**

- C. Surface material will be native caliche. The average grade of the entire road will be approximately 3%.
- D. Fence Cuts: No E. Cattle guards: No
- F. Turnouts: No

- G. Culverts: No
- H. Cuts and Fills: Not significant
- I. Approximately 6 inches of topsoil (root zone) will be stripped from the proposed access road prior to any further construction activity. The topsoil that was stripped will be spread along the edge of the road and within the ditch. The topsoil will be seeded with the proper seed mix designated by the BLM.
- J. The access road will be constructed and maintained as necessary to prevent soil erosion and accommodate all-weather traffic. The road will be crowned and ditched with water turnouts installed as necessary to provide for proper drainage along the access road route.
- K. The access road and associated drainage structures will be constructed and maintained in accordance with road guidelines contained in the joint BLM/USFS publication: <u>Surface Operating Standards for Oil and Gas Exploration and Development, The Gold Book, Fourth Edition</u> and/or BLM Manual Section 9113 concerning road construction standards on projects subject to federal jurisdiction.

#### 3. LOCATION OF EXISTING WELLS:

See attached map (Exhibit B) showing all wells within a one-mile radius.

#### 4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES:

- A. In the event the well is found productive, a production facility (Tank Battery), will be installed on the north portion of the well pad (SEE EXHIBIT C). A 4" poly surface line (90 psi), a buried 6" steel gas pipeline (250 psi) and a 12.5 kv power line will be run to the existing utility corridor to the north (all within 50 ft.) SEE EXHIBIT E.
- B. All permanent (on site six months or longer) aboveground structures constructed or installed on location and not subject to safety requirements will be painted to BLM specifications.
- C. Containment berms will be constructed completely around production facilities designed to hold fluids. The containment berns will be constructed or compacted subsoil, be sufficiently impervious, hold 1 ½ times the capacity of the largest tank and away from cut or fill areas.

#### 5. LOCATION AND TYPE OF WATER SUPPLY:

The well will be drilled using a combination of water mud systems as outlined in the Drilling Program. The water will be obtained from commercial water stations in the area and hauled to the location by transport truck using the existing and proposed roads shown in the attached survey plats. If a commercial water well is nearby, a temporary, surface poly line, will be laid along existing roads or other ROW easements and the water pumped to the well. No water well will be drilled on the location.

#### 6. SOURCE OF CONSTRUCTION MATERIALS:

Any construction material that may be required for surfacing of the drill pad and access road will be from a contractor having a permitted source of materials within the general area. No construction materials will be removed from Federal lands without prior approval from the appropriate surface management agency. All roads will be constructed of 6" rolled and compacted caliche.

#### 7. METHODS OF HANDLING WASTE DISPOSAL:

- A. The well will be drilled utilizing a closed loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to an NMOCD approved disposal site.
- B. Drilling fluids will be contained in steel mud pits.
- C. Water produced from the well during completion will be held temporarily in steel tanks and then taken to an NMOCD approved commercial disposal facility.
- D. Oil produced during operations will be stored in tanks until sold.
- E. Portable, self-contained chemical toilets will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents thereof disposed of in an approved sewage disposal facility. All state and local laws and regulations pertaining to disposal of human and solid waste will be complied with. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete.
- F. All trash, junk, and other waste materials will be contained in trash cages or bins to prevent scattering and will be removed and deposited in an approved sanitary landfill. Immediately after drilling all debris and other waste materials on and around the well location, not contained in the trash cage will be cleaned up and removed from the location. No potentially adverse materials or substances will be left on the location.

#### 8. ANCILLARY FACILITIES:

No campsite, airstrip, or other facilities will be built as a result of the operation of this well. No staging areas are needed.

#### 9. WELL SITE LAYOUT:

- A. Exhibit D shows the dimensions of the proposed well pad.
- B. The proposed two well pad size will be 350' x 375' The two wells will be 25 ft. apart. The 1H will be west of the 2H (See Exhibit D). There will be no reserve pit due to the well being drilled utilizing a closed loop mud system. The closed loop system will meet the NMOCD requirements 19.15.17.
- C. The WTC Surveyor's plat, Site Location Plat, and **Exhibit D**, shows how the well will be turned to a V-Door West.
- D. A 600' x 600' area has been staked and flagged.
- E. All equipment and vehicles will be confined to the approved disturbed areas of this APD (i.e., access road, well pad, and topsoil storage areas)

#### 10. PLANS FOR SURFACE RECLAMATION:

- A. After concluding the drilling and/or completion operations, if the well is found non-commercial, all the equipment will be removed, the surface material, caliche, will be removed from the well pad and road and transported to the original caliche pit or used for other roads. The original stock piled top soil will be returned to the pad and contoured, as close as possible, to the original topography. The access road will have the caliche removed and the road ripped, barricaded and seeded as directed by the BLM.
- B. If the well is a producer, the portions of the location not essential to production facilities or space required for workover operations, will be reclaimed and seeded as per BLM requirements.

  (SEE EXHIBIT C FOR INTERIM RECLAMATION PLAT FOR THIS WELL)
- C. <u>Reclamation Performance Standards</u>
  The following reclamation performance standards will be met:

Interim Reclamation – Includes disturbed areas that may be redisturbed during operations and will be redisturbed at final reclamation to achieve restoration of the original landform and a natural vegetative community.

• Disturbed areas not needed for active, long-term production operations or vehicle travel will be recontoured, protected from erosion, and revegetated with a self-sustaining, vigorous, diverse, native (or as otherwise approved) plant community sufficient to minimize visual impacts, provide forage, stabilize soils, and impede the invasion of noxious, invasive, and non-native weeds.

Final Reclamation – Includes disturbed areas where the original landform and a natural vegetative community will be restored and it is anticipated the site will not be redisturbed for future development.

- The original landform will be restored for all disturbed areas including well pads, production facilities, roads, pipelines, and utility corridors.
- A self-sustaining, vigorous, diverse, native (or otherwise approved) plant community will be established on the site, with a density sufficient to control erosion and invasion by non-native plants and to re-establish wildlife habitat or forage production. At a minimum, the established plant community will consist of species included in the seed mix and/or desirable species occurring in the surrounding natural vegetation.
- Erosion features are equal to or less than surrounding area and erosion control is sufficient so that water naturally infiltrates into the soil and gullying, headcutting, slumping, and deep or excessive rills (greater than 3 inches) are not observed.
- The site will be free of State- or county-listed noxious weeds, oil field debris and equipment, and contaminated soil. Invasive and non-native weeds are controlled.

#### D. Reclamation Actions

Earthwork for interim and final reclamation will be completed within 6 months of well completion or plugging unless a delay is approved in writing by the BLM authorized officer.

The following minimum reclamation actions will be taken to ensure that the reclamation objectives and standards are met. It may be necessary to take additional reclamation actions beyond the minimum in order to achieve the Reclamation Standards.

#### Reclamation – General

#### Notification:

• The BLM will be notified at least 3 days prior to commencement of any reclamation operations.

#### Housekeeping:

- Within 30 days of well completion, the well location and surrounding areas(s) will be cleared of, and maintained free of, all debris, materials, trash, and equipment not required for production.
- No hazardous substances, trash, or litter will be buried or placed in pits.

# Topsoil Management:

- Operations will disturb the minimum amount of surface area necessary to conduct safe and efficient operations.
- Topsoil depth is defined as the top layer of soil that contains 80% of the roots. In areas to be heavily disturbed, the topsoil will be stripped and stockpiled around the perimeter of the well location and along the perimeter of the access road to control run-on and run-off, to keep topsoil viable, and to make redistribution of topsoil more efficient during interim reclamation. Stockpiled topsoil will include vegetative material. Topsoil will be clearly segregated and stored separately from subsoils.
- Salvaging and spreading topsoil will not be performed when the ground or topsoil is frozen or too wet to adequately support construction equipment or so dry that dust clouds greater than 30 feet tall are created. If such equipment creates ruts in excess of four (4) inches deep, the soil will be deemed too wet.
- No major depressions will be left that would trap water and cause ponding unless the intended purpose is to trap runoff and sediment.

### Seeding:

- Seedbed Preparation. Initial seedbed preparation will consist of recontouring to the appropriate interim or final reclamation standard. All compacted areas to be seeded will be ripped to a minimum depth of 18 inches with a minimum furrow spacing of 2 feet, followed by recontouring the surface and then evenly spreading the stockpiled topsoil. Prior to seeding, the seedbed will be scarified to a depth of no less than 4 6 inches. If the site is to be broadcast seeded, the surface will be left rough enough to trap seed and snow, control erosion, and increase water infiltration.
- If broadcast seeding is to be used and is delayed, final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to break the soil crust and create seed germination micro-sites.
- <u>Seed Application</u>. Seeding will be conducted no more than two weeks following completion of final seedbed preparation. A certified weed-free seed mix designed by the BLM to meet reclamation standards will be used.
- If the site is harrowed or dragged, seed will be covered by no more than 0.25 inch of soil.

### 11. SURFACE OWNERSHIP:

A. The surface is owned by the U. S. Government and is administered by the Bureau of Land Management. The surface is multiple use with the primary uses of the region for the grazing of livestock and the production of oil and gas.

### 12. OTHER INFORMATION:

- A. The area surrounding the well site is in a gentle sloped, shallow gravelly loam, rolling hills type area. The vegetation consists of Mesquite, Creosote, Whitethorn Acacia with three-awns and some dropseed species.
- B. There is no permanent or live water in the immediate area.
- C. There are no dwellings within 2 miles of this location.
- D. Sections 1 & 12 of T. 23 S., R. 28 E. has had an archaeological block survey done and a report filed with the BLM Carlsbad Field Office.



### 13. BOND COVERAGE:

Bond Coverage is Nationwide; Bond Number NMB-000460.

# **OPERATORS REPRESENTATIVE:**

The RKI Exploration and Production, LLC representatives responsible for ensuring compliance of the surface use plan are listed below:

# Surface:

Barry W. Hunt – Permitting Agent 1403 Springs Farm Place Carlsbad, NM 88220 (575) 885-1417 (Home) (575) 361-4078 (Cell)

Drilling & Production: Ken Fairchild – RKI Exploration and Production, LLC. 210 Park Avenue, Suite 900 Oklahoma City, Ok.73102 (405) 996-5764 (Office)

(469) 693-6051 (Cell)

ON-SITE PERFORMED ON 04/11/13 RESULTED IN PROPOSED LOCATION BEING LEFT WHERE STAKED. IT WAS AGREED TO TURN THE LOCATION TO A V-DOOR WEST, PLACE THE TOP SOIL TO THE EAST, TANK BATTERY TO THE NORTH AND INTERIM RECLAMATION TO BE ON THE SOUTH, EAST AND WEST PORTIONS OF THE PAD.

PRESENT AT ON-SITE:
BARRY HUNT – PERMIT AGENT FOR RKI EXPLORATION & PRODUCTION
AMANDA LYNCH – BLM
WTC SURVEYS

# PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:
LEASE NO.:
WELL NAME & NO.:
SURFACE HOLE FOOTAGE:
BOTTOM HOLE FOOTAGE
LOCATION:
COUNTY:
RKI Exploration & Production, LLC
NMNM-91078
Longview Federal 12-1H
0780' FNL & 1880' FEL
0330' FNL & 2245' FEL Sec. 01, T. 23 S., R 28 E.,
Section 12, T. 23 S., R 28 E., NMPM
Eddy County, New Mexico

# TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

	<b>General Provisions</b>
	Permit Expiration
	Archaeology, Paleontology, and Historical Sites
	Noxious Weeds
	Special Requirements
	Construction
	Notification
	Topsoil
	Closed Loop System
	Federal Mineral Material Pits
	Well Pads
	Roads
	Road Section Diagram
$\boxtimes$	Drilling
	Cement Requirements
	H2S Requirements
	Medium Cave/Karst
	Logging Requirements
	Waste Material and Fluids
$\boxtimes$	<b>Production (Post Drilling)</b>
	Well Structures & Facilities
	Pipelines
	Electric Lines
	Interim Reclamation
$\Gamma \supset$	Final Abandanment & Declaration

# I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

# II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

# III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

### IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

# V. CONSTRUCTION

# A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

# C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

# F. EXCLOSURE FENCING (CELLARS & PITS)

### **Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

### G. ON LEASE ACCESS ROADS

#### Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

### Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

### Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

#### Ditching

Ditching shall be required on both sides of the road.

### **Turnouts**


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

# **Drainage**

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

# Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

### Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope: 
$$\frac{400'}{4\%}$$
 + 100' = 200' lead-off ditch interval

#### **Culvert Installations**

Appropriately sized culverts shall be installed at deep waterway channel flow crossings through the road.

### **Cattleguards**

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings.

Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

# **Fence Requirement**

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

# **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

# **Construction Steps**

- 1. Salvage topsoil
- 3. Redistribute topsoil
- 2. Construct road
- 4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

### VI. DRILLING

# A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

# **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

- 1. Although Hydrogen Sulfide has not been reported in the area, it is always a potential hazard. If Hydrogen Sulfide is encountered, report measured amounts and formations to the BLM.
- 2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. If the drilling rig is removed without approval an Incident of Non-Compliance will be written and will be a "Major" violation.
- 3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
- 4. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

#### B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. IF OPERATOR DOES NOT HAVE THE WELL SPECIFIC CEMENT DETAILS ONSITE PRIOR TO PUMPING THE CEMENT FOR EACH CASING STRING, THE WOC WILL BE 30 HOURS. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Medium Cave/Karst Possibility of water flows in the Salado and Castile. Possibility of lost circulation in the Rustler and Delaware.

- 1. The 13-3/8 inch surface casing shall be set at approximately 225 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. If salt is encountered, set casing at least 25 feet above the salt.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
  - ⊠ Cement to surface. If cement does not circulate see B.1.a, c-d above.

If 75% or greater lost circulation occurs while drilling the intermediate casing hole, the cement on the production casing must come to surface.

# Centralizers required through the curve and a minimum of one every other joint.

3. The minimum required fill of cement behind the 7 inch production casing is:

Operator has proposed DV tool at depth of 5500'. Operator is to submit sundry if DV tool depth varies by more than 100' from approved depth.

- a. First stage to DV tool:
- □ Cement to circulate. If cement does not circulate, contact the appropriate
   □ BLM office before proceeding with second stage cement job. Operator should
   □ have plans as to how they will achieve approved top of cement on the next
   □ stage.
- b. Second stage above DV tool:
- Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification.
- 4. Cement not required on the 4-1/2" casing. Packer system being used.
- 5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

### C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Operator has proposed a multi-bowl wellhead assembly that has a weld on head with no o-ring seals. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 3000 (3M) psi.
  - a. Wellhead manufacturer is supplying the test plug/retrieval tool for the operator's third party tester to use during the BOP/BOPE test. Operator shall use the supplied test plug/retrieval tool.
  - b. Operator shall install the wear bushing required by the wellhead manufacturer. This wear bushing shall be installed by using the test plug/retrieval tool.

- c. Wellhead manufacturer representative shall be on location when the intermediate casing mandrel is landed. Operator shall submit copy of manufacturer's wellsite report with subsequent report.
- d. Operator shall perform the intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.
- e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- 3. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. The tests shall be done by an independent service company utilizing a test plug **not** a **cup** or **J-packer**.
  - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
  - d. The results of the test shall be reported to the appropriate BLM office.
  - e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
  - f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

### D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

# E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**JAM 031214** 

# VII. PRODUCTION (POST DRILLING)

### A. WELL STRUCTURES & FACILITIES

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

# **Chemical and Fuel Secondary Containment and Exclosure Screening**

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the

largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

# **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

### B. PIPELINES

#### **BURIED PIPELINE STIPULATIONS**

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- 1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
- 2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
- 3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C.6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
- 4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting

Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

- 5. All construction and maintenance activity will be confined to the authorized right-of-way.
- 6. The pipeline will be buried with a minimum cover of <u>36</u> inches between the top of the pipe and ground level.
- 7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:
  - Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed **20** feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
  - Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.)
  - The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (Compressing can be caused by vehicle tires, placement of equipment, etc.)
- 8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately \_\_\_6\_\_ inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.
- 9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
- 10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless

otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.

- 11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.
- 12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

( ) seed mixture 1	( ) seed mixture 3
(X) seed mixture 2 <sup>-</sup>	( ) seed mixture 4
( ) seed mixture 2/LPC	( ) Aplomado Falcon Mixture

- 13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" **Shale Green**, Munsell Soil Color No. 5Y 4/2.
- 14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.
- 15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.
- 16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.
- 17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist,

which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

- 18. <u>Escape Ramps</u> The operator will construct and maintain pipeline/utility trenches that are not otherwise fenced, screened, or netted to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:
  - a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
  - b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

### STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the application (Grant, Sundry Notice, APD) and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- 1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
- 2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
- 3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et

<u>seq.</u>) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

- 4. The holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:
  - a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
  - b. Activities of other parties including, but not limited to:
    - (1) Land clearing.
    - (2) Earth-disturbing and earth-moving work.
    - (3) Blasting.
    - (4) Vandalism and sabotage.
  - c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.

ight-of-					
d or					
n 10 feet					
from the edge of the road or buried pipeline right-of-way. If existing surface pipelines					
prevent this distance, the proposed surface pipeline must be installed immediately					
11					

adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.

- 7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.
- 8. The holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky of duney areas, the pipeline will be "snaked" around hummocks and dunes rather then suspended across these features.
- 9. The pipeline shall be buried with a minimum of <u>24</u> inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.
- 10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
- 11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.
- 12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.
- 13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.
- 14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.
- 15. Any cultural and/or paleontological resource (historic or prehistoric site or object)

discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

- 16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.
- 17. Surface pipelines must be less than or equal to 4 inches and a working pressure below 125 psi.

#### C. ELECTRIC LINES

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

- 1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
- 2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

- 3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
- 4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.
- 5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006. The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roasting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

- 6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
- 7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.
- 8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.
- 9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180

days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

# 11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes with native soil. .

### VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

### X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

# Seed Mixture 2, for Sandy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be <u>no</u> primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law (s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

Species	l <u>b/acre</u>
Sand dropseed (Sporobolus cryptandrus)	1.0
Sand love grass (Eragrostis trichodes)	. 1.0
Plains bristlegrass (Setaria macrostachya)	2.0

<sup>\*</sup>Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed