

Submit 1 Copy To Appropriate District Office
District I - (575) 393-6161
1625 N. French Dr., Hobbs, NM 88240
District II - (575) 748-1283
811 S. First St., Artesia, NM 88210
District III - (505) 334-6178
1000 Rio Brazos Rd., Aztec, NM 87410
District IV - (505) 476-3460
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources

Form C-103
Revised July 18, 2013

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

| |
|-----------------------------------------------------------------------------------------------------|
| WELL API NO. 30-005-60988 |
| 5. Indicate Type of Lease STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/> |
| 6. State Oil & Gas Lease No. LG-4354 |
| 7. Lease Name or Unit Agreement Name Cocklebur RD State |
| 8. Well Number 1 |
| 9. OGRID Number 025575 |
| 10. Pool name or Wildcat Pecos Slope; Abo |

| |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 4. Well Location Unit Letter <u>M</u> : <u>810</u> feet from the <u>South</u> line and <u>660</u> feet from the <u>West</u> line Section <u>17</u> Township <u>7S</u> Range <u>25E</u> NMPM <u>Chaves</u> County |
| 11. Elevation (Show whether DR, RKB, RT, GR, etc.) 3806'GR |

| | |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|
| SUNDRY NOTICES AND REPORTS ON WELLS (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.) 1. Type of Well: Oil Well <input type="checkbox"/> Gas Well <input checked="" type="checkbox"/> Other <input type="checkbox"/> 2. Name of Operator Yates Petroleum Corporation 3. Address of Operator 105 South Fourth Street, Artesia, NM 88210 | |
| 4. Well Location Unit Letter <u>M</u> : <u>810</u> feet from the <u>South</u> line and <u>660</u> feet from the <u>West</u> line Section <u>17</u> Township <u>7S</u> Range <u>25E</u> NMPM <u>Chaves</u> County | |
| 11. Elevation (Show whether DR, RKB, RT, GR, etc.) 3806'GR | |

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:

PERFORM REMEDIAL WORK ☐ PLUG AND ABANDON ☒
TEMPORARILY ABANDON ☐ CHANGE PLANS ☐
PULL OR ALTER CASING ☐ MULTIPLE COMPL ☐
DOWNHOLE COMMINGLE ☐
CLOSED-LOOP SYSTEM ☐
OTHER: ☐

SUBSEQUENT REPORT OF:

REMEDIAL WORK ☐ ALTERING CASING ☐
COMMENCE DRILLING OPNS. ☐ P AND A ☐
CASING/CEMENT JOB ☐
OTHER: ☐

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 19.15.7.14 NMAC. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

Yates Petroleum Corporation plans to plug and abandon this well as follows:

1. MIRU WSU. Rig up any safety equipment as needed. No casing recovery will be attempted. POOH with tubing.
2. Set a CIBP at 3682' and cap it with 35' cement. This puts a plug over Abo.
3. Perforate at 1477' and spot a 115 sx Class "C" cement plug from 1107'-1477'. This puts a 370' plug across intermediate casing shoe and top of the Glorieta, inside and outside casing. WOC and tag plug.
4. Perforate at 856' and spot a 25 sx Class "C" cement plug from 756'-856'. This puts a 100' plug across surface casing shoe, inside and outside casing. WOC and tag plug.
5. Perforate at 60' and spot a 15 sx Class "C" cement plug from 60' up to surface.
6. Remove all surface equipment, weld dry hole marker and clean location as per regulations.

Approved for plugging of well bore only.
Liability under bond is retained pending receipt of C-103 (Subsequent Report of Well Plugging) which may be found at OCD Web Page under Forms, www.emnrd.state.nm.us/oed.

Wellbore schematics attached
CONDITIONS OF APPROVAL ATTACHED

Approval Granted providing work is

Completed by

April 16, 2015

Rig Release Date:

RECEIVED

APR 15 2014

NMOC D ARTESIA

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Tina Huerta TITLE Regulatory Reporting Supervisor DATE April 14, 2014

Type or print name Tina Huerta E-mail address: tinah@yatespetroleum.com PHONE: 575-748-4168

For State Use Only

APPROVED BY: [Signature] TITLE Dist. Rep. Supervisor DATE 4-16-2014

Conditions of Approval (if any):

★ See Attached COA's

WELL NAME: Cockleburr RD St #1

FIELD: Pecos Slope Abo

LOCATION: 810' FSL & 660' FWL of Section 17-7S-25E

Chaves Co., NM

GL: 3806.2' GR

ZERO:

KB:

SPUD DATE: 6/30/81

COMPLETION DATE: 7/30/81


COMMENTS: API: 30-005-60988

CASING PROGRAM

| | |
|------------------------|--------|
| 13-3/8" 48# | 806' |
| 8-5/8" 24# K-55 ST&C | 1,157' |
| 4-1/2" 10.5# J-55 ST&C | 4,050' |
| | |

BEFORE

| | |
|------------|-------|
| Tops: | |
| San Andres | 464' |
| Glorieta | 1427' |
| Abo | 3508' |



Not to Scale
3/20/14
MMFH

WELL NAME: Cockleburrr RD St #1

FIELD: Pecos Slope Abo

LOCATION: 810' FSL & 660' FWL of Section 17-7S-25E

Chaves Co., NM

GL: 3806.2' GR

ZERO:

KB:

CASING PROGRAM

SPUD DATE: 6/30/81

COMPLETION DATE: 7/30/81

COMMENTS: API: 30-005-60988

| | |
|------------------------|--------|
| 13-3/8" 48# | 806' |
| 8-5/8" 24# K-55 ST&C | 1,157' |
| 4-1/2" 10.5# J-55 ST&C | 4,050' |
| | |

15 sxs, 60' surface cmt plug

AFTER

17 1/2" Hole

25 sxs cmt plug
756'-856'

12 1/4" Hole

13-3/8" @ 806'
w/ 800sx cmt (circ)

115Sxs, 370' cmt plug
1,107'-1,477'

8-5/8" @ 1157'
w/ 1150sx cmt
1" 309 sxs to surface

Tops:

| | |
|------------|-------|
| San Andres | 464' |
| Glorieta | 1427' |
| Abo | 3508' |

TOC @ 2,930' (CBL)

7 7/8" Hole

CIBP @ 3,682'+35' cmt

Abo perms: 3,732'-44' (8)

PBTD : 4,032'
TD : 4,050'

4-1/2" @ 4,050'
w/370 sx

Not to Scale
3/20/14
MMFH

NEW MEXICO OIL CONSERVATION DIVISION
DISTRICT 2 OFFICE
811 S. FIRST STREET
ARTESIA, NM 88210
(575)748-1283

CONDITIONS OF APPROVAL FOR PLUGGING & ABANDONMENT

Operator: Yates Petroleum

Well Name & Number: Cocklebur RD State #1

API #: 30-005-60988

1. Produced water **will not** be used during any part of the plugging & abandonment operation.
2. Notify NMOCD Dist. 2 office at least 24 hrs before beginning work.
3. Closed Loop System is to be used for entire plugging operation. Upon completion, contents of steel pit are to be hauled to a permitted disposal location.
4. Trucking companies being used to haul oilfield waste fluids to a disposal – commercial or private – shall have an approved NMOCD C-133 permit. A copy of this permit shall be available in each truck used to haul waste products. It is the responsibility of the operator, as well as the contractor, to verify that this permit is place prior to performing work. Drivers shall produce a copy upon request of NMOCD Field Inspectors.
5. A subsequent C-103 will serve as notification that the well bore has been plugged **ONLY**. A C-103 **FINAL** shall be filed before any bonding can be released on the well. Upon receipt of the Final, an inspection will be performed to verify that the location has been satisfactorily cleaned to NMOCD standards.
6. If work has not begun within 90 days of the approval of this procedure, an extension request must be filed, stating reason that well has not been plugged.
7. Every attempt must be made to clean the well bore out to below the perfs, before any plugs can be set, by whatever means possible.
8. **Cement Retainers may not be used.**

9. Squeeze pressures are not to exceed 500 PSI, unless approval is given by NMOCD.
10. Plugs may be combined after consulting with and getting approval from NMOCD.
11. Minimum WOC time for tag plugs will be 4 Hrs.

DATE: 7-16-2017

APPROVED BY: 

GUIDELINES FOR PLUGGING AND ABANDONMENT

DISTRICT II / ARTESIA

- All cement plugs will be a minimum of 100' in length or a minimum of 25 sacks of cement, whichever is greater.
- Mud laden fluids must be placed between all cement plugs.
- Mud laden fluids must be mixed at 25 sacks of gel per 100 bbls of water.
- A cement plug is required to be set 50' below and 50' above all casing shoes and casing stub plugs. These plugs must be tagged.
- A CIBP with 35' of cement on top may be set in lieu of 100' cement plug.
- A plug as indicated above must be placed within 100' of top perforation. This plug must be tagged.
- Plugs set below and above salt zones must be tagged.
- No more than 2000' is to be allowed between cement plugs in open hole and no more than 3000' in cased hole.
- DV tools are required to have a 100' cement plug set 50' above and below the tool and must be tagged.
- Formations to be isolated with plugs placed at the top of each formation are:
 - Fusselman
 - Devonian
 - Morrow
 - Wolfcamp
 - Bone Spring
 - Delaware
 - Any Salt Section (Plug at top and bottom)
 - Abo
 - Glorieta
 - Yates (this plug is usually at base of salt section)
- If cement does not exist behind casing strings at recommended formation depths, the casing must be cut and pulled with plugs set at these depths or casing must be perforated and cement squeezed behind casing at the formation depths.
- In the R-111-P area (Potash Mine area) a solid cement plug must be set across the salt section. Fluid used to mix the cement shall be saturated with the salts common to the section penetrated and in suitable proportions, but not more than a 3% calcium chloride by weight of cement will be considered the desired mixture whenever possible (50' below and 50' above).