Form 3160-3 (March 2012)

UNORTHODOX

**OCD Artesia** 

ATS-14-477

FORM APPROVED OMB No. 1004-0137 Expires October 31, 2014

5. Lease Serial No.

NMNM121474

| Ē     |                                      | JI N                     | BOKEAU (                                     | JF LAND N     | NANAGEMEN         | l                      |                   |             |              |                   |                                     |
|-------|--------------------------------------|--------------------------|--|---------------|-------------------|------------------------|-------------------|-------------|--------------|-------------------|-------------------------------------|
|       |                                      | APPLICA                  | TION FOR                                     | PERMIT        | TO DRILL O        | R REENTER              |                   |             | 6. If Indiar | n, Allotee or Tri | ibe Name                            |
| 1a.   | Type of Work:                        | ✓ DRILL                  |  | REEN          | TER .             |                        |                   |             | 7. If Unit o | r CA Agreeme      | nt, Name and No.                    |
|       |                                      |                          |  |               |                   |                        |                   |             | 8. Lease N   | lame and Well     | No. + 3/329                         |
| lb.   | Type of Well:                        | ✓ Oil Well               | Gas Well                                     | Other         |                   | Single Zone            | Multiple          | Zone        |              |                   | leral Com #1H                       |
| 2.    | Name of Opera                        | tor                      |  |               |                   | <u> </u>               | <u></u>           |             | 9. API Wel   | li No.            | , .                                 |
|       |                                      |                          | coc  | 3 Production  | LLC.              |                        |                   |             | -            | <u>30-015</u>     | - 42391                             |
| За.   | Address                              |                          |  | 3b. P         | hone No. (includ  | e area code)           |                   |             | 10/Piety au  | od Pool or Exp    | Isratory . A                        |
|       |                                      | 2208 West Main Str       |  |               |                   |                        |                   |             | DKO          | Wildcat, D        | etaware / Co = C                    |
|       |                                      | Artesia, NM 8821         |  |               |                   | 575-748-6940           | <del></del> -     |             | 44.5. T      | D. A.4. DII       | +8080                               |
| 4.    |                                      | (Report location clearly |  | •             | ,                 | •                      |                   |             | 11. Sec., 1. | R.M. or Bik and   | d Survey or Area                    |
|       | At surface                           |                          |  |               | (SWNE) Sec 31-    |                        |                   |             |              |                   |                                     |
|       | At proposed pro                      |                          |  |               |                   | Sec 30-T26S-R29        |                   |             | ļ            | Sec. 31 - T2      |                                     |
| 14.   | Distance in mile                     | es and direction from    | nearest town                                 | or post offic | e*                |                        |                   |             | 12. County   | or Parish         | 13. State                           |
|       |                                      |                          | Approximat                                   | ely 14 miles  | from Malaga       | ,                      |                   |             | 1            | Eddy              | NM                                  |
| 15.   | Distance from p                      | •                        |  |               |                   | 16. No. of acres in    | lease             | 17. Spaci   | ing Unit dec | licated to this v | well                                |
|       | location to near<br>property or leas |                          |  |               |                   | 51.8                   | 7                 | l           |              |                   |                                     |
|       |                                      | drig. Unit line, if any  | <i>(</i> )                                   | 200'          |                   | ] 31.8                 | ,                 | ľ           |              | 186.27            |                                     |
| 18.   | Distance from lo                     |                          | <u>′                                    </u> | SHL: 32       | 8'                | 19. Proposed Dept      | h                 | 20. BLM/    | BIA Bond N   |                   |                                     |
|       | to nearest well,                     | drilling, completed,     |  | BHL: 46       | 7'                |                        |                   | 1           |              |                   |                                     |
|       | applied for, on t                    | this lease, ft.          |  |               |                   | TVD: 6,330' N          | ИD: 11,828'       |             | NMB          | 000860 &NME       | 3000845                             |
| 21.   | Elevations (Sho                      | w whether DF, KDB, I     | RT, GL, etc.)                                |               |                   | 22. Approximate d      | ate work will st  | art*        |              | 23. Estimated     | duration                            |
|       |                                      | 29                       | 000.7' GL                                    | ,             |                   |                        | 5/1/2014          |             |              |                   | 30 days                             |
|       |                                      |                          |  |               | 24. /             | Attachments            |                   |             |              |                   |                                     |
| Γhe   | following, comp                      | leted in accordance v    | vith the requir                              | ements of O   | nshore Oil and G  | as Order No. 1, sha    | l be attached to  | this form   | 1:           |                   |                                     |
| 1.    | Well plat certific                   | ed by a registered su    | rveyor.                                      |               |                   | 4. Bond to cov         | er the operation  | ns unless o | covered by a | an existing bon   | d on file (see                      |
| 2.    | A Drilling Plan                      |                          | •  |               |                   | Item 20 abo            |                   |             | •            |                   | ,                                   |
| 3.    | A Surface Use P                      | lan (if the location is  | on National Fo                               | orest System  | Lands, the        | 5. Operator ce         | rtification       |             |              |                   |                                     |
|       | SUPO shall be fi                     | led with the appropr     | iate Forest Ser                              | vice Office). |                   | 6. Such other s        | •                 | rmation a   | nd/or plans  | as may be req     | uired by the                        |
|       | Cianatura                            | 1                        |  |               | Nama (Orinta      | authorized o           | oπicer.           |             |              | D-1-              |                                     |
| 25.   | Signature                            | all P                    | _  |               | Name (Printe      | и) гурей)              |                   |             |              | Date              |                                     |
|       | $\frac{\vee}{ }$                     | U/a L                    | 25p  |               |                   | Mayt                   | e Reyes           |             |              |                   | 2/5/2014                            |
| Title |                                      | · ·                      | b  |               |                   |                        |                   |             |              |                   |                                     |
|       | Regulatory                           | Analyst                  |  | <del></del>   | _                 |                        |                   |             |              |                   |                                     |
| App   | roved by <i>(Signati</i>             |                          |  |               | Name (Printe      | d/Typed)               |                   |             |              | Date APR 2        | 2 8 2014                            |
|       |                                      | Steve Ca                 | <b>iffey</b>                                 |               |                   |                        |                   |             |              | AFT 4             | 2 8 2014                            |
| Title |                                      | FIELD MAN                | AGER   |               | Office            |                        | CARLSBAD          | FIELD O     | FFICE        |                   |                                     |
| √pp   | lication approval                    | does not warrant or      | certify that th                              | e applicant h | nolds legan or eq | uitable title to those | rights in the su  | ubject leas | se which wo  | ould entitle the  | applicant to                        |
| con   | duct operations t                    | heron.                   |  |               |                   | •                      |                   | APPR(       | OVAL F       | OR TWO            | YEARS .                             |
| Con   | ditions of approv                    | al, if any, are attache  | 2d.  |               |                   |                        |                   |             | _ v · \nam 1 |                   | · · · · · · · · · · · · · · · · · · |
| ritle | 18 U.S.C. Sectio                     | n 1001 and Title 43 U    | J.S.C. Section 1                             |               | t a crime for any | person knowingly a     | nd willfully to n | nake to ar  | ıy departme  | ent or agency o   | of the United                       |

**UNITED STATES** 

**DEPARTMENT OF THE INTERIOR** 

(Continued on page 2)

\*(Instructions on page 2)

Carlsbad Controlled Water Basin

States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdie

MAY 06 2014

SEE ATTACHED FOR CONDITIONS OF APPROVAL

Approval Subject to General Requirements & Special Stipulations Attached

Surface Use Plan
COG Production LLC
Ridge None Endage Co

Ridge Nose Federal Com #1H SHL: 200' FSL & 2310' FEL

Lot #6

Section 31, T26S, R29E

BHL: 1650' FNL & 2310' FEL UL G

Section 30, T26S, R29E Eddy County, New Mexico

#### **OPERATOR CERTIFICATION**

I hereby certify that I, or persons under my direct supervision, have inspected the drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or COG Production, LLC, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this Application, 2014.

Signed:

Printed Name: Melanie J. Parker Position: Regulatory Coordinator

Address: 2208 W. Main Street, Artesia, NM 88210

Telephone: (575) 748-6940

Field Representative (if not above signatory): Rand French

E-mail: mparker@concho.com

Surface Use Plan Page 8

DISTRICT II 1301 W. GRAND AVENUE, ARTESIA. NM 88210 Phone: (575) 748-1283 Fex: (575) 748-9720

State of New Mexico DISTRICT I

1825 N. FRENCH DR., HOBBS, NM 88240
Phone: (678) 393-6161 Par: (676) 393-0720

Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION 11885 SOUTH ST. FRANCIS DR.

DISTRICT III 1000 RIO BRAZOS RD., AZTEC, NM 87410 Phone: (505) 334-6178 Fax: (505) 334-6170

Santa Fe, New Mexico 87505

Form C-102 Revised August 1, 2011 Submit one copy to appripriate

☐ AMENDED REPORT

DISTRICT IV 11885 S. ST. FRANCIS DR., SANTA FE, NM 87505 Phone: (505) 476-3460 Fax: (505) 476-3462

WELL LOCATION AND ACREAGE DEDICATION PLAT Phylood Name Ideat; Delaware Pool Code API Number 30-015-42391 8080 Property Co. . . Property Name Well Number 313299 RIDGE NOSE FEDERAL COM 1H Operator Name Elevation יסוזי שמוניס 217955 COG PRODUCTION, LLC 2900.7


#### Surface Location

| UL or lot No. | Section | Township | Range | Lot Idn | Feet from the | North/South line | Feet from the | East/West line | County |
|---------------|---------|----------|-------|---------|---------------|------------------|---------------|----------------|--------|
| 6             | .31     | 26-S     | 29-E  |         | 200           | SOUTH            | 2310          | EAST           | EDDY   |

#### Bottom Hole Location If Different From Surface

| UL or lot No.   | Section 30 | Township 26-S | Range<br>29-E | Lot Idn | Feet from the | North/South line | Feet from the | East/West line<br>EAST | County   |
|-----------------|------------|---------------|---------------|---------|---------------|------------------|---------------|------------------------|----------|
| Dedicated Acres | Joint o    | r Infill Co   | nsolidation ( | Code Or | der No.       |                  |               |                        | <u> </u> |

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



SECTION 31, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY NEW MEXICO 600' EXISTING COPPERHEAD 31 FEDERAL COM #2H 160' NORTH NW COR. NE COR. WELL PAD **OFFSET** WELL PAD 2907.4 2901.9 2901.2' ╼ RIDGE NOSE FEDERAL COM #1H 170' EAST 170' WEST **OFFSET** 0 **OFFSET** 2899.8' 2902.1' ELEV - 2900.7'  $LAT. = 32.000509^{\circ} N$ LONG. = 104.022282° W CALICHE SW COR. 160' SOUTH SE COR. WELL PAD OFFSET WELL PAD 2902.6 2900.7 2900.1' 20' CALICHE RD SECTION LINE "POLY"FL ALL FEATURES ARE EXISTING UNLESS OTHERWISE NOTED 600'


DIRECTIONS TO LOCATION

HEADING SOUTH ON HWY 285 TURN LEFT (EAST) ON CATFISH RD AND GO APPROX. 0.5 MILE AND PROPOSED WELL IS APPROX. 180 FEET NORTH.

#### HARCROW SURVEYING, LLC

1107 WATSON, ARTESIA, N.M. 88210 PH: (575) 513-2570 FAX: (575) 746-2158 chad\_harcrow77@yahoo.com






#### COG PRODUCTION, LLC

RIDGE NOSE FEDERAL COM #1H WELL LOCATED 200 FEET FROM THE SOUTH LINE AND 2310 FEET FROM THE EAST LINE OF SECTION 31, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO

| SURVEY DATE:    | 04/23/2013   | PAGE: 1  | OF 1  |
|-----------------|--------------|----------|-------|
| DRAFTING DATE:  | 04/25/2013   |          |       |
| APPROVED BY: CH | DRAWN BY: VD | FILE: 13 | 3-218 |

### EXHIBIT 2

### **LOCATION VERIFICATION MAP**




SEC. 31, TWP. 26S, RGE. 29E SURVEY: N.M.P.M COUNTY: EDDY STATE: NEW MEXICO DESCRIPTION: RIDGE NOSE FED COM #1H 200' FSL, 2310' FEL

ELEVATION: 2900.7'

OPERATOR: COG PRODUCTION LLC LEASE: RIDGE NOSE FED COM

W.O. # 13-218




HARCROW SURVEYING, LLC 1107 WATSON, ARTESIA N.M. 88210 PH: (575) 513-2570 FAX: (575) 746-2158 chad\_harcrow77@yahoo.com



MAP DATE: 4/26/2013

### **LOCATION VERIFICATION MAP**



SURVEY: N.M.P.M


COUNTY: EDDY STATE: NEW MEXICO DESCRIPTION: RIDGE NOSE FED COM #1H

200' FSL, 2310' FEL

ELEVATION: 2900.7'

OPERATOR: COG PRODUCTION LLC LEASE: RIDGE NOSE FED COM

W.O. # 13-218



HARCROW SURVEYING, LLC 1107 WATSON, ARTESIA N.M. 88210 PH: (575) 513-2570 FAX: (575) 746-2158 chad\_harcrow77@yahoo.com



MAP DATE: 4/26/2013

# **VICINITY MAP** 書き 23 2285 25S 28E 28 26 25S 29E 35 02 05 +10 .08 26S 28E = 26S 29E RIDGE NOSE FEDICOM #1H (35 NEW MEXICO Sources: Esri, Dellorme, NAVTEQ, USGS intermap, P.C. NRGAN, Esri Japan, METI, Esri Ghina (Hong Kong), Esri (Thailand), Tomitom, 2013.

SEC. 31, TWP. 26S, RGE. 29E

SURVEY: N.M.P.M

COUNTY: EDDY STATE: NEW MEXICO DESCRIPTION: RIDGE NOSE FED COM #1H

200' FSL, 2310' FEL

ELEVATION: 2900.7'

OPERATOR: COG PRODUCTION LLC LEASE: RIDGE NOSE FED COM

1 IN = 6,000 FT

0 0.5 MILES


● WELL
■ TOWNSHIP
■ SECTION

HARCROW SURVEYING, LLC 1107 WATSON, ARTESIA N.M. 88210 PH: (575) 513-2570 FAX: (575) 746-2158 chad\_harcrow77@yahoo.com



W.O. # 13-218

MAP DATE: 4/26/2013



#### **Melanie Parker**

From:

Melanie Parker

Sent:

Tuesday, March 04, 2014 1:43 PM

To:

'Ingram, Wesley W'; kmsimmon@blm.gov; jblakley@blm.gov Mayte Reyes; Tim Smith; Rand French (rfrench@concho.com)

Cc: Subject:

FW: RIDGE NOSE FEDERAL COM #1H - DEFICIENCY

Attachments:

Ridge Nose Federal Com #1H Deficiency Answer.pdf

Wesley,

The answer to the question on the deficiency letter is "Yes" per Tim Smith's email below.

Do we need to do anything further on this?

Thanks, Melanie

From: Tim Smith

Sent: Tuesday, March 04, 2014 1:33 PM

To: Melanie Parker

Cc: Mayte Reyes; Sheryl Baker

Subject: RE: RIDGE NOSE FEDERAL COM #1H - DEFICIENCY

Yes, we will test annular to full amount that was applied for in the drilling permit.

Thanks,

Tim D. Smith NM Drilling 432.741.5346

From: Melanie Parker

Sent: Tuesday, March 04, 2014 11:07 AM

To: Tim Smith

Cc: Mayte Reyes; Sheryl Baker

Subject: RIDGE NOSE FEDERAL COM #1H - DEFICIENCY

Hey Tim,

Please see the attached deficiency letter. If the answer is "Yes" we can send it in an email, but if not we can change it and send it in. Just let us know!

Thanks a bunch!

Melanie J. Parker Lead Regulatory Analyst

COG Operating LLC

2208 West Main Street Artesia NM 88210 Phone: 575-748-6952



# COG Production LLC DRILLING AND OPERATIONS PROGRAM

Ridge Nose Federal Com #1H

SHL: 200' FSL & 2310' FEL of Section 31 BHL: 1650' FNL & 2310' FEL of Section 30

Section 30 & 31 T26S R29E Eddy County, New Mexico

In conjunction with Form 3160-3, Application for Permit to Drill subject well, COG Production LLC submits the following eleven items of pertinent information in accordance with BLM requirements.

1. Geological surface formation: Permian

2. The estimated tops of geologic markers & estimated depths at which anticipated water, oil or gas formations are expected to be encountered are as follows:

| Fresh Water    | 51'     |     |
|----------------|---------|-----|
| Rustler        | 169'    |     |
| Top of Salt    | 963'    |     |
| Fletcher       | 2,499'  |     |
| Delaware/Lamar | 2,621'  | Oil |
| Bell Canyon    | 2,685'  | Oil |
| Cherry Canyon  | 3,529′  | Oil |
| Brushy Cnayon  | 4,759′  | Oil |
| Bone Springs   | 6,344'  | Oil |
| TD TVD         | 6,330'  |     |
| TD MD          | 11,828' |     |

No other formations are expected to give up oil, gas or fresh water in measurable quantities. The surface fresh water sands will be protected by setting 13-3/8" casing at 400' and circulating cement back to surface. All intervals will be isolated by setting 5 1/2" casing to total depth and tying back cement to a minimum of 500' into 9-5/8" csg.

#### 3. Proposed Casing Program: All casing is new and API approved

| Hole<br>Size | Depths       | Section                       | OD<br>Casing | New/<br>Used | Wt  | Collar | Grade | Collapse<br>Design<br>Factor | Burst<br>Design<br>Factor | Tension<br>Design<br>Factor |
|--------------|--------------|-------------------------------|--------------|--------------|-----|--------|-------|------------------------------|---------------------------|-----------------------------|
| 17 1/2"      | 0' - 400'    | Surface                       | 13 3/8"      | New          | 48# | STC    | H-40  | 1.125                        | 1.125                     | 1.6                         |
| 12 1/4"      | 0' - 2,600'  | Intrmd                        | 9 5/8"       | New          | 36# | LTC    | J-55  | 1.125                        | 1.125                     | 1.6                         |
| 7 7/8"       | 0' - 11,828' | Production<br>Curve & Lateral | 5 1/2"       | New          | 17# | LTC    | P-110 | 1.125                        | 1.125                     | 1.6                         |

• While running all casing strings, the pipe will be kept a minimum of 1/3 full at all times to avoid approaching the collapse pressure of casing.

#### 4. Proposed Cement Program

a. 13-3/8" Surface Cmt: 350 sx Class C + 2% CaCl<sub>2</sub>

(14.8 ppg / 1.34 cuft/sx/ 6.3 gal/sk)

\*\*Calculated w/50% excess on OH volumes

b. 9 5/8" Intermediate: Lead: 450 sx Class C + 4% Gel

(13.5 ppg /1.75 cuft/sx / 9.2 gal/sk)

Tail: 250 sx Class C

(14.8 ppg / 1.34 cuft/sx / 6.3 gal/sk)

\*\*Calculated w/35% excess on OH volumes

c. 5 1/2" Production: Lead: 350 sx 50:50:10 H Blend

(11.9 ppg / 2.51 cuft/sx / 14.1 gal/sk)

Tail: 1150 sx 50:50:2 H +Salt+GasStop +CFR-3

(14.4 ppg /1.24 cuft/sx / 6.4 gal/sk)

\*\*Calculated w/35% excess on OH volumes

• The above cement volumes could be revised pending the caliper measurement.

- The 9-5/8" intermediate string is designed to circulate cement to surface.
- The production string will tie back a minimum of 500' into 9-5/8" shoe

#### 5. Pressure Control:

Nipple up on 13 3/8 with annular preventer tested to 2000 psi by independent tester and the rest of the 2M system tested to 2000 psi.

Nipple up on 9 5/8 with 3M system tested to 3000 psi by independent tester.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. A 2" kill line and a minimum 3" choke line will be included in the drilling spool located below the ram-type BOP. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold with 3000 psi WP rating. A remotely operated choke will be installed before drilling out intermediate shoe. If H2S is monitored with 100 ppm in the gas stream while drilling intermediate, we will shut in and install a remote operated choke.

#### 6. Estimated BHP & BHT:

Lateral TD = 2,962 psi Lateral TD= 122° F

**7. Mud Program:** The applicable depths and properties of this system are as follows:

|                  |             | Mud       | Viscosity | Waterloss |
|------------------|-------------|-----------|-----------|-----------|
| Depth            | Type System | Weight    | (sec)     | (cc)      |
| 0' - 400'        | Fresh Water | 8.4 – 8.6 | 29        | N.C.      |
| 400′ – 2,600′    | Brine       | 10-10.2   | 29        | N.C.      |
| 2,600′ – 11,828′ | Cut Brine   | 8.8 – 9   | 29        | N.C.      |

- The necessary mud products for weight addition and fluid loss control will be on location at all times.
- A visual and electronic mud monitoring system will be rigged up prior to spud to detect changes in the volume of mud system. The electronic system consists of a pit volume total, stroke counter and flow sensor at flow line.
- If weight and/or viscosity are introduced to the mud system a daily mud check will be performed by mud contractor, along with tourly check by rig personnel.

• After setting intermediate casing, a third party gas unit detection system will be installed at the flow line.

#### 8. Auxiliary Well Control and Monitoring Equipment:

- a. A Kelly cock will be in the drill string at all times.
- b. A full opening drill pipe stabbing valve having the appropriate connections will be on the rig floor at all times.
- c. Hydrogen Sulfide detection equipment will be in operation after drilling out the 13 3/8" casing shoe until the 5 ½" casing is cemented. Breathing equipment will be on location upon drilling the 13 3/8" shoe until total depth is reached.

#### 9. Testing, Logging and Coring Program:

- a. Drill stem tests will be based on geological sample shows.
- b. If open hole electrical logging is performed, the program will be:
  - i. Total Depth to Intermediate Casing: Dual Laterolog-Micro Laterolog and Gamma Ray. Compensated Neutron Z Density log with Gamma Ray and Caliper.
  - ii. Total Depth to Surface: Compensated Neutron with Gamma Ray
  - iii. No coring program is planned
  - iv. Additional testing will be initiated subsequent to setting the 5 ½" production casing. Specific intervals will be targeted based on log evaluation, geological sample shows and drill stem tests.

#### 10. Potential Hazards:

a. No abnormal pressures or temperatures are expected. There is no known presence of H2S in this area. If H2S is encountered the operator will comply with the provisions of Onshore Oil and Gas Order No. 6. All personnel will be familiar with all aspects of safe operation of equipment being used to drill this well. No H2S is anticipated to be encountered.

#### 11. Anticipated starting date and Duration of Operations:

a. Road and location construction will begin after the BLM has approved the APD. Anticipated spud date will be as soon as possible after BLM approval and as soon as a riq will be available. Move in operations and drilling is expected to take 35 days.



COG PRODUCTION LLC

Eddy County, NM Section 31-26S-29E Ridge Nose Fed Com Ridge Nose Federal Com #1H

**Original Hole** 

Plan: Plan#1

# **Standard Planning Report**

28 October, 2013





#### Planning Report



EDM 5000-11 Single User Db COG Production ULC Eddy County, NM\* Database: Company: Project: Site:

Section: 31-26S-29E Ridge Nose Fed Com-

Well: Wellbore: Design:

Ridge Nose Federal Com.#1H/ Original Hole Plan#1

Local Co-ordinate Reference:

Survey Calculation Method:

TVD Reference: MD Reference: North Reference:

Well Ridge Nose Federal Com #1H

GL 2900 7 + 18 @ 2918 7usft (Silver Oak #) GL 2900 7 + 18 @ 2918 7usft (Silver Oak #) Grid Minimum Curvature

Project \* Eddy County NM States 2 2 2 2 2

Map System: Geo Datum: Map Zone:

US State Plane 1927 (Exact solution)

NAD 1927 (NADCON CONUS)

New Mexico East 3001

System Datum:

Mean Sea Level

Site Section 31-26S-29E Ridge Nose Fed Com

Site Position: From:

Мар

Northing: Easting:

364,051.30 usft

Latitude:

32° 0' 1.833 N

**Position Uncertainty:** 

0.0 usft Slot Radius: 596,423.90 usft

Longitude:

104° 1' 20.216 W

13-3/16 " **Grid Convergence:** 

0.16°

Well Ridge Nose Federal Com #1H THE PERSON OF TH The second of the second **Well Position** +N/-S 0.0 usft 364,051.30 usft Northing: Latitude: 32° 0' 1.833 N

+E/-W

0.0 usft

Easting:

596,423.90 usft

Longitude:

104° 1' 20.216 W

**Position Uncertainty** 0.0 usft Wellhead Elevation: **Ground Level:** 2,900.7 usft

Original Hole Wellbore Declination Field Strength Dip Angle IGRF2010 10/25/2013 7.49 59.84 48,200

Plan#1 **Audit Notes:** Version: **PROTOTYPE** Phase: Tie On Depth: 0.0 Vertical Section: Depth From (TVD) Direction (usft) (usft) 🕟 (usft) (°) 0.0 0.0 0.0 0.08

| Plan Sections | Mark Art  |         | e de la comp |         | 医骶髓线线  | Act as      | TACHAL T    | Granda de la composición dela composición de la composición dela composición de la c | Yavara e     | <b>化等的特别</b> "新工程 |
|---------------|-----------|---------|--------------|---------|--------|-------------|-------------|--|--------------|-------------------|
| Measured'     |           |         | Vertical     |         |        | ·Dogleg *   | Build       | Turn   |              | and the second    |
| Depth In      | clination | Azimuth | Depth        | +N/-S   | +E/-W  | Rate        | Rate        | Rate   | TFO          |                   |
| (usft)        | (°)       | (°)     | (usft)       | (usft)  | (usft) | (°/100usft) | (°/100usft) | (°/100usft)  | (°)          | Target            |
| 0.0           | 0.00      | 0.00    | 0.0          | 0.0     | 0.0    | 0.00        | 0.00        | 0.00   | 0.00         |                   |
| 5.832.6       | 0.00      | 0.00    | 5.832.6      | 0.0     | 0.0    | 0.00        | 0.00        | 0.00<br>0.00   | 0.00<br>0.00 |                   |
| 6,575.3       | 89.13     | 0.08    | 6.310.0      | 470.2   | 0.0    | 12.00       | 12.00       | 0.00   | 0.08         |                   |
| 11.828.0      | 89.13     | 0.08    | 6,390.0      | 5,722.3 | 8.4    | 0.00        | 0.00        | 0.00   |              | BHL Ridge Nose I  |



Planning Report



Database: Company: Project. Site:

EDM 5000 1 Single User Db COG Production LLC

Eddy County, NM

Section 31-26S-29E Ridge Nose Fed Com

Ridge Nose reue... Original Hole Ridge Nose Federal Com #1H

Well Wellbore: Design: Plan#1 Local Co-ordinate Reference:

TVD Reference:

North Reference:

Survey Calculation Method:

Well Ridge Nose Federal Com #1H

GL 2900.7 + 18 @ 2918 7usft (Silver Oak #) 'GL 2900.7 + 18 @ 2918.7usft (Silver Oak #)

Grid Minimum Curvature

|                | an#1         | 3, 3/3° 129 134 175 1       | E. Mr. Mr. L.    | A CONTRACTOR OF THE PARTY OF TH | THE RESERVE                              | ne.60 . 47 1 76 1 3 1 1 1 2 5 | 6-175-1-17-1-1 | 3 (49 75 ) 48   | 7 ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( |
|----------------|--------------|-----------------------------|------------------|--|--|-------------------------------|----------------|-----------------|---|
| Planned Survey |              |                             |                  |  |  |                               |                |                 |   |
|                |              |                             | CAN THE STATE OF | 10.00  | 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1 | 1                             | 100 B)         | 3 7 7 7         | 3 5 7 5 5 5 5 5 5                       |
| Measured       | 3 3          | But a state of the state of | Vertical         |  | v.                                       | ertical **                    | Dogleg         | Build           | Turn                                    |
|                |              | B. 180                      | Depth            |  |  |                               | Rate           | Rate *          | Rate                                    |
| Depth          | lination A   | zimutn                      | Depui            | +N/-S  |  | ection                        | rale y         | °/100usft). ↓ ( | Nate (*                                 |
| (usft)         | . ( ˇ)       | (i)                         | (usn)            | ·(usft)  | / (usft), (                              | usit)                         | (IUUUSII) (    | riodusit). I (  | (/Toousit)                              |
| 0.0            | 0.00         | 0.00                        | 0.0              | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 100.0          | 0.00         | 0.00                        | 100.0            | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 200.0          | 0.00         | 0.00                        | 200.0            | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 300.0          | 0.00         | 0.00                        | 300.0            | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 400.0          | 0.00         | 0.00                        | 400.0            | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
|                |              |                             |                  |  | 0.0                                      |                               |                |                 | 0.00                                    |
| 500.0          | 0.00         | 0.00                        | 500.0            | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 600.0          | 0.00         | 0.00                        | 600.0            | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00<br>0.00    | 0.00<br>0.00                            |
| 700.0<br>800.0 | 0.00<br>0.00 | 0.00<br>0.00                | 700.0<br>800.0   | 0.0<br>0.0   | 0.0<br>0.0                               | 0.0<br>0.0                    | 0.00<br>0.00   | 0.00            | 0.00                                    |
| 900.0          | 0.00         | 0.00                        | 900.0            | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
|                |              |                             |                  |  |  |                               |                |                 |   |
| 1,000.0        | 0.00         | 0.00                        | 1,000.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 1,100.0        | 0.00         | 0.00                        | 1,100.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 1,200.0        | 0.00         | 0.00                        | 1,200.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 1,300.0        | 0.00         | 0.00                        | 1,300.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 1,400.0        | 0.00         | 0.00                        | 1,400.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 1,500.0        | 0.00         | 0.00                        | 1,500.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 1,600.0        | 0.00         | 0.00                        | 1,600.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 1,700.0        | 0.00         | 0.00                        | 1,700.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 1,800.0        | 0.00         | 0.00                        | 1,800.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 1,900.0        | 0.00         | 0.00                        | 1,900.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
|                |              |                             |                  |  |  |                               |                |                 |   |
| 2,000.0        | 0.00         | 0.00                        | 2,000.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 2,100.0        | 0.00         | 0.00                        | 2,100.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 2,200.0        | 0.00         | 0.00                        | 2,200.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 2,300.0        | 0.00         | 0.00                        | 2,300.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 2,400.0        | 0.00         | 0.00                        | 2,400.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 2,500.0        | 0.00         | 0.00                        | 2,500.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 2,600.0        | 0.00         | 0.00                        | 2,600.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 2,700.0        | 0.00         | 0.00                        | 2,700.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 2,800.0        | 0.00         | 0.00                        | 2,800.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 2,900.0        | 0.00         | 0.00                        | 2,900.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 3,000.0        | 0.00         | 0.00                        | 3,000.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 3,100.0        | 0.00         | 0.00                        | 3,100.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 3,200.0        | 0.00         | 0.00                        | 3,200.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 3,300.0        | 0.00         | 0.00                        | 3,300.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 3,400.0        | 0.00         | 0.00                        | 3,400.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 3,500,0        |              |                             | 3,500.0          |  | 0.0                                      | 0.0                           |                |                 | ·                                       |
| 3,500.0        | 0.00<br>0.00 | 0.00<br>0.00                | 3,500.0          | 0.0<br>0.0   | 0.0                                      | 0.0                           | 0.00<br>0.00   | 0.00<br>0.00    | 0.00<br>0.00                            |
| 3,600.0        | 0.00         | 0.00                        | 3,700.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 3,700.0        | 0.00         | 0.00                        | 3,800.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 3,900.0        | 0.00         | 0.00                        | 3,900.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
|                |              |                             | •                |  |  |                               |                |                 |   |
| 4,000.0        | 0.00         | 0.00                        | 4,000.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 4,100.0        | 0.00         | 0.00                        | 4,100.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 4,200.0        | 0.00         | 0.00                        | 4,200.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 4,300.0        | 0.00         | 0.00                        | 4,300.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 4,400.0        | 0.00         | 0.00                        | 4,400.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 4,500.0        | 0.00         | 0.00                        | 4,500.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 4,600.0        | 0.00         | 0.00                        | 4,600.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 4,700.0        | 0.00         | 0.00                        | 4,700.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 4,800.0        | 0.00         | 0.00                        | 4,800.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 4,900.0        | 0.00         | 0.00                        | 4,900.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 5,000.0        | 0.00         | 0.00                        | 5,000.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 5,000.0        | 0.00         | 0.00                        | 5,000.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 5,200.0        | 0.00         | 0.00                        | 5,200.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 5,300.0        | 0.00         | 0.00                        | 5,300.0          | 0.0  | 0.0                                      | 0.0                           | 0.00           | 0.00            | 0.00                                    |
| 3,500.0        | 0.00         | 0.00                        | 0,000.0          | 0.0  | 3.0                                      |                               | 0.00           | 5.00            |   |



Planning Report



Database: Company: Project: Site: Well: Wellbore: Design:

EDM 5000:1 Single User Db COG Production L'LC Eddy County; NM Section 31-265-29E 'Ridge Nose Fed Com Ridge Nose Federal Com #1H Original Hole Plan#1

Original Hole

Local Co.ordinate Reference: TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well Ridge Nose Federal Com #1H GL 2900 7 + 18 @ 2918 7usft (Silver Oak #) GL 2900 7+18 @;2918 7usft (Silver Oak #) GL 2900 7+18 @ 2918 7usft (Silver Oak #) 'Grid! Minimum Curvature

| Design: Plan                       | n#1 <u>\$ 66</u> 5     | j,                   |                    | <u> </u>           |            |                    |                  | A 5 4 5 4             |                      |
|------------------------------------|------------------------|----------------------|--------------------|--------------------|------------|--------------------|------------------|-----------------------|----------------------|
| Planned Survey                     |                        |                      |                    | N. A.              |            |                    |                  |                       |                      |
|                                    |                        | ا<br>الراجع بيات إلى |                    |                    |            |                    |                  | 14146                 |                      |
| Measured.                          |                        |                      | /ertical           |                    |            | ertical 🌲 🦠        | Dogleg           | Build                 | Turn                 |
| Depth: Incli                       | nation Azim            | 1978 . ALM           |                    | +N/-S              |            | ection             | Rate             | Rate                  | Rate                 |
| (usft)                             | (°)                    |                      | (usft)             | (usft)             | (usft)     | (usft)             | (°/100usft) : (° | / ιυυusπ) 🛠 (         | //OUUSπ)             |
| 5,400.0                            | 0.00                   | 0.00                 | 5,400.0            | 0.0                | 0.0        | 0.0                | 0.00             | 0.00                  | 0.00                 |
| 5,500.0                            | 0.00                   | 0.00                 | 5,500.0            | 0.0                | 0.0        | 0.0                | 0.00             | 0.00                  | 0.00                 |
| 5,600.0                            | 0.00                   | 0.00                 | 5,600.0            | 0.0                | 0.0        | 0.0                | 0.00             | 0.00                  | 0.00                 |
| 5,700.0<br>5,800.0                 | 0.00<br>0.00           | 0.00<br>0.00         | 5,700.0<br>5,800.0 | 0.0<br>0.0         | 0.0<br>0.0 | 0.0<br>0.0         | 0.00<br>0.00     | 0.00<br>0.00          | 0.00<br>0.00         |
| 5,832.6                            | 0.00                   | 0.00                 | 5,832.6            | 0.0                | 0.0        | 0.0                | 0.00             | 0.00                  | 0.00                 |
| 5832.6 MD KOP                      |                        |                      |                    |                    |            |                    |                  | m. r-male man i mile. |                      |
| 5,850.0                            | 2.09                   | 0.08                 | 5,850.0            | 0.3                | 0.0        | 0.3                | 12.00            | 12.00                 | 0.00                 |
| 5,875.0                            | 5.09                   | 0.08                 | 5,874.9            | 1.9                | 0.0        | 1.9                | 12.00            | 12.00                 | 0.00                 |
| 5,900.0                            | 8.09                   | 80.0                 | 5,899.8            | 4.7                | 0.0        | 4.7                | 12.00            | 12.00                 | 0.00                 |
| 5,925.0<br>5,950.0                 | 11.09<br>14.09         | 0.08<br>0.08         | 5,924.4<br>5,948.8 | 8.9<br>14.4        | 0.0<br>0.0 | 8.9<br>14.4        | 12.00<br>12.00   | 12.00<br>12.00        | 0.00<br>0.00         |
| ,                                  |                        |                      | •                  |                    |            |                    |                  |                       |                      |
| 5,975.0<br>6,000.0                 | 17.09<br>20.09         | 0.08<br>0.08         | 5,972.9<br>5,996.6 | 21.1<br>29.0       | 0.0<br>0.0 | 21.1<br>29.0       | 12.00<br>12.00   | 12.00<br>12.00        | 0.00<br>0.00         |
| 6,025.0                            | 23.09                  | 0.08                 | 6,019.8            | 38.2               | 0.1        | 38.2               | 12.00            | 12.00                 | 0.00                 |
| 6,050.0                            | 26.09                  | 0.08                 | 6,042.6            | 48.6               | 0.1        | 48.6               | 12.00            | 12.00                 | 0.00                 |
| 6,075.0                            | 29.09                  | 0.08                 | 6,064.7            | 60.2               | 0.1        | 60.2               | 12.00            | 12.00                 | 0.00                 |
| 6,100.0                            | 32.09                  | 80.0                 | 6,086.2            | 72.9               | 0.1        | 72.9               | 12.00            | 12.00                 | 0.00                 |
| 6,125.0<br>6,150.0                 | 35.09<br>38.09         | 0.08<br>0.08         | 6,107.1<br>6,127.1 | 86.8<br>101.7      | 0.1<br>0.1 | 86.8<br>101.7      | 12.00<br>12.00   | 12.00<br>12.00        | 0.00<br>0.00         |
| 6,175.0                            | 41.09                  | 0.08                 | 6,146.4            | 117.6              | 0.2        | 117.6              | 12.00            | 12.00                 | 0.00                 |
| 6,200.0                            | 44.09                  | 0.08                 | 6,164.8            | 134.5              | 0.2        | 134.5              | 12.00            | 12.00                 | 0.00                 |
| 6,225.0                            | 47.09                  | 0.08                 | 6,182.3            | 152.4              | 0.2        | 152.4              | 12.00            | 12.00                 | 0.00                 |
| 6,250.0                            | 50.09                  | 0.08                 | 6,198.8            | 171.1              | 0.3        | 171.1              | 12.00            | 12.00                 | 0.00                 |
| 6,275.0<br>6,300.0                 | 53.09<br>56.09         | 0.08<br>0.08         | 6,214.4<br>6,228.8 | 190.7<br>211.1     | 0.3<br>0.3 | 190.7<br>211.1     | 12.00<br>12.00   | 12.00<br>12.00        | 0.00<br>0.00         |
| 6,325.0                            | 59.09                  | 0.08                 | 6,242.2            | 232.2              | 0.3        | 232.2              | 12.00            | 12.00                 | 0.00                 |
| 6,350.0                            | 62.09                  | 0.08                 | 6,254.5            | 254.0              | 0.4        | 254.0              | 12.00            | 12.00                 | 0.00                 |
| 6,375.0                            | 65.09                  | 0.08                 | 6,265.6            | 276.3              | 0.4        | 276.3              | 12.00            | 12.00                 | 0.00                 |
| 6,400.0                            | 68.09                  | 0.08                 | 6,275.6            | 299.3              | 0.4        | 299.3              | 12.00            | 12.00                 | 0.00                 |
| 6,425.0<br>6,450.0                 | 71.09<br>74.09         | 0.08<br>0.08         | 6,284.3<br>6,291.8 | 322.7<br>346.6     | 0.5<br>0.5 | 322.7<br>346.6     | 12.00<br>12.00   | 12.00<br>12.00        | 0.00<br>0.00         |
|                                    |                        |                      |                    |                    |            |                    |                  |                       |                      |
| 6,475.0<br>6,500.0                 | 77.09<br>80.09         | 80.0<br>80.0         | 6,298.0<br>6,302.9 | 370.8<br>395.3     | 0.5<br>0.6 | 370.8<br>395.3     | 12.00<br>12.00   | 12.00<br>12.00        | 0.00<br>0.00         |
| 6,525.0                            | 83.09                  | 0.08                 | 6,306.6            | 420.0              | 0.6        | 420.0              | 12.00            | 12.00                 | 0.00                 |
| 6,550.0                            | 86.09                  | 0.08                 | 6,309.0            | 444.9              | 0.7        | 444.9              | 12.00            | 12.00                 | 0.00                 |
| 6,575.3<br><b>6,575.3</b> MD: 6310 | 89.12                  | 0.08                 | 6,310.0            | 470.2              | 0.7        | 470.2              | 12.00            | 12.00                 | 0.00<br>7 * \$1 * \$ |
| The second second                  | . April Marie Dynnia . | 0.00                 | 0.040.4            | 404.0              |            | 4040               |                  | THE ALL AL            | SERVER TO SERVE      |
| 6,600.0<br>6,700.0                 | 89.13<br>89.13         | 0.08<br>0.08         | 6,310.4<br>6,311.9 | 494.9<br>594.9     | 0.7<br>0.9 | 494.9<br>594.9     | 0.01<br>0.00     | 0.01<br>0.00          | 0.00<br>0.00         |
| 6,800.0                            | 89.13                  | 0.08                 | 6,313.4            | 694.8              | 1.0        | 694.8              | 0.00             | 0.00                  | 0.00                 |
| 6,900.0                            | 89.13                  | 80.0                 | 6,315.0            | 794.8              | 1.2        | 794.8              | 0.00             | 0.00                  | 0.00                 |
| 7,000.0                            | 89.13                  | 0.08                 | 6,316.5            | 894.8              | 1.3        | 894.8              | 0.00             | 0.00                  | 0.00                 |
| 7,100.0                            | 89.13                  | 0.08                 | 6,318.0            | 994.8              | 1.5        | 994.8              | 0.00             | 0.00                  | 0.00                 |
| 7,200.0<br>7,300.0                 | 89.13<br>89.13         | 80.0<br>80.0         | 6,319.5<br>6,321.0 | 1,094.8<br>1,194.8 | 1.6<br>1.8 | 1,094.8<br>1,194.8 | 0.00<br>0.00     | 0.00<br>0.00          | 0.00<br>0.00         |
| 7,300.0                            | 89.13                  | 0.08                 | 6,321.0            | 1,194.8            | 1.6<br>1.9 | 1,194.8            | 0.00             | 0.00                  | 0.00                 |
| 7,500.0                            | 89.13                  | 0.08                 | 6,324.1            | 1,394.8            | 2.0        | 1,394.8            | 0.00             | 0.00                  | 0.00                 |
| 7,600.0                            | 89.13                  | 0.08                 | 6,325.6            | 1,494.7            | 2.2        | 1,494.7            | 0.00             | 0.00                  | 0.00                 |
| 7,700.0                            | 89.13                  | 80.0                 | 6,327.1            | 1,594.7            | 2.3        | 1,594.7            | 0.00             | 0.00                  | 0.00                 |
| 7,800.0                            | 89.13                  | 80.0                 | 6,328.7            | 1,694.7            | 2.5        | 1,694.7            | 0.00             | 0.00                  | 0.00                 |
| 7,900.0<br>8,000.0                 | 89.13<br>89.13         | 80.0<br>80.0         | 6,330.2<br>6,331.7 | 1,794.7<br>1,894.7 | 2.6<br>2.8 | 1,794.7<br>1,894.7 | 0.00<br>0.00     | 0.00<br>0.00          | 0.00<br>0.00         |
| 3,000.0                            |                        |                      | 0,001.7            | 1,001.1            | 2.0        | .,00 1.7           |                  |                       | 5.55                 |



Planning Report



Database: Company: Project: Site: Well: EDM 5000.1 Single User Db

COG Prodiction LLC

Eddy County, NM Section 31-26S-29E, Ridge Nose Fed Com Ridge Nose Federal Com #1H

Original Hole Plan#1 Wellbore: Design

Local Co-ordinate Reference:

TVD Reference: MD Reference:

North Reference:

Survey Calculation Method:

Well Ridge Nose Federal Com #1H

GL 2900.7 + 18 @ 2918.7usft (Silver Oak #) GL 2900 7,++18 @ 2918 7usft (Silver Oak #)

Grid Minimum Curvature

| esign:        | Plan#1        |             | in the other process |           | <u> </u> |                                       | R. 12 4. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. | Land Chill Colored |                    |
|---------------|---------------|-------------|----------------------|-----------|----------|---------------------------------------|---|--------------------|--------------------|
| lanned Survey |               |             |                      | 7373      | 2.5      | Annahar State Marie Millian State and | 35.50   |                    |                    |
|               |               |             | Vertical             |           |          | Vertical                              |   |                    | Turn               |
| Measured ?    | Inclination   | Azimuth     | Doneh                | .+N/-S    | +E/-W    | C-24::                                | Dogleg<br>Rate                                  | Build Rate         | Date of the second |
| (usft)        | (°)           | (°)         | (usft)               | (usft)    |          | (usft)                                | , Rate<br>(°/100usft)                           | /100usft) (        | 1100usft)          |
| 8,100.0       | 89.13         | 0.08        | 6,333.2              | 1,994.7   | 2.9      | 1,994.7                               | 0.00  | 0.00               | 0.00               |
| 8,200.0       | 89.13         | 0.08        | 6,334.8              | 2,094.7   | 3.1      | 2,094.7                               | 0.00  | 0.00               | 0.00               |
| 8,300.0       | 89.13         | 0.08        | 6,336.3              | 2,194.7   | 3.2      | 2,194.7                               | 0.00  | 0.00               | 0.00               |
| 8,400.0       | 89.13         | 0.08        | 6,337.8              | 2,294.7   | 3.4      | 2,294.7                               | 0.00  | 0.00               | 0.00               |
| 8,500.0       | 89.13         | 0.08        | 6,339.3              | 2,394.6   | 3.5      | 2,394.6                               | 0.00  | 0.00               | 0.00               |
| 8,600.0       | 89.13         | 0.08        | 6,340.8              | 2,494.6   | 3.7      | 2,494.6                               | 0.00  | 0.00               | 0.00               |
| 8,700.0       | 89.13         | 0.08        | 6,342.4              | 2,594.6   | 3.8      | 2,594.6                               | 0.00  | 0.00               | 0.00               |
| 8,800.0       | 89:13         | 0.08        | 6,343.9              | 2,694.6   | 4.0      | 2,694.6                               | 0.00  | 0.00               | 0.00               |
| 8,900.0       | 89.13         | 0.08        | 6,345.4              | 2,794.6   | 4.1      | 2,794.6                               | 0.00  | 0.00               | 0.00               |
| 9,000.0       | 89.13         | 0.08        | 6,346.9              | 2,894.6   | 4.2      | 2,894.6                               | 0.00  | 0.00               | 0.00               |
| 9,100.0       | 89.13         | 0.08        | 6,348.5              | 2,994.6   | 4.4      | 2,994.6                               | 0.00  | 0.00               | 0.00               |
| 9,200.0       | 89.13         | 0.08        | 6,350.0              | 3,094.6   | 4.5      | 3,094.6                               | 0.00  | 0.00               | 0.00               |
| 9,300.0       | 89.13         | 0.08        | 6,351.5              | 3,194.5   | 4.7      | 3,194.5                               | 0.00  | 0.00               | 0.00               |
| 9,400.0       | 89.13         | 0.08        | 6,353.0              | 3,294.5   | 4.8      | 3,294.5                               | 0.00  | 0.00               | 0.00               |
| 9,500.0       | 89.13         | 0.08        | 6,354.5              | 3,394.5   | 5.0      | 3,394.5                               | 0.00  | 0.00               | 0.00               |
| 9,600.0       | 89.13         | 0.08        | 6,356.1              | 3,494.5   | 5.1      | 3,494.5                               | 0.00  | 0.00               | 0.00               |
| 9,700.0       | 89.13         | 0.08        | 6,357.6              | 3,594.5   | 5.3      | 3,594.5                               | 0.00  | 0.00               | 0.00               |
| 9,800.0       | 89.13         | 0.08        | 6,359.1              | 3,694.5   | 5.4      | 3,694.5                               | 0.00  | 0.00               | 0.00               |
| 9,900.0       | 89.13         | 0.08        | 6,360.6              | 3,794.5   | 5.6      | 3,794.5                               | 0.00  | 0.00               | 0.00               |
| 10,000.0      | 89.13         | 0.08        | 6,362.2              | 3,894.5   | 5.7      | 3,894.5                               | 0.00  | 0.00               | 0.00               |
| 10,100.0      | 89.13         | 0.08        | 6,363.7              | 3,994.5   | 5.9      | 3,994.5                               | 0.00  | 0.00               | 0.00               |
| 10,200.0      | 89.13         | 0.08        | 6,365.2              | 4,094.4   | 6.0      | 4,094.4                               | 0.00  | 0.00               | 0.00               |
| 10,300.0      | 89.13         | 0.08        | 6,366.7              | 4,194.4   | 6.2      | 4,194.4                               | 0.00  | 0.00               | 0.00               |
| 10,400.0      | 89.13         | 0.08        | 6,368.3              | 4,294.4   | 6.3      | 4,294.4                               | 0.00  | 0.00               | 0.00               |
| 10,500.0      | 89.13         | 0.08        | 6,369.8              | 4,394.4   | 6.5      | 4,394.4                               | 0.00  | 0.00               | 0.00               |
| 10,600.0      | 89.13         | 0.08        | 6,371.3              | 4,494.4   | 6.6      | 4,494.4                               | 0.00  | 0.00               | 0.00               |
| 10,700.0      | 89.13         | 0.08        | 6,372.8              | 4,594.4   | 6.7      | 4,594.4                               | 0.00  | 0.00               | 0.00               |
| 10,800.0      | 89.13         | 0.08        | 6,374.3              | 4,694.4   | 6.9      | 4,694.4                               | 0.00  | 0.00               | 0.00               |
| 10,900.0      | 89.13         | 0.08        | 6,375.9              | 4,794.4   | 7.0      | 4,794.4                               | 0.00  | 0.00               | 0.00               |
| 11,000.0      | 89.13         | 0.08        | 6,377.4              | 4,894.3   | 7.2      | 4,894.4                               | 0.00  | 0.00               | 0.00               |
| 11,100.0      | 89.13         | 0.08        | 6,378.9              | 4,994.3   | 7.3      | 4,994.3                               | 0.00  | 0.00               | 0.00               |
| 11,200.0      | 89.13         | 0.08        | 6,380.4              | 5,094.3   | 7.5      | 5,094.3                               | 0.00  | 0.00               | 0.00               |
| 11,300.0      | 89.13         | 0.08        | 6,382.0              | 5,194.3   | 7.6      | 5,194.3                               | 0.00  | 0.00               | 0.00               |
| 11,400.0      | 89.13         | 0.08        | 6,383.5              | 5,294.3   | 7.8      | 5,294.3                               | 0.00  | 0.00               | 0.00               |
| 11,500.0      | 89.13         | 0.08        | 6,385.0              | 5,394.3   | 7.9      | 5,394.3                               | 0.00  | 0.00               | 0.00               |
| 11,600.0      | 89.13         | 0.08        | 6,386.5              | 5,494.3   | 8.1      | 5,494.3                               | 0.00  | 0.00               | 0.00               |
| 11,700.0      | 89.13         | 0.08        | 6,388.0              | 5,594.3   | 8.2      | 5,594.3                               | 0.00  | 0.00               | 0.00               |
| 11,800.0      | 89.13         | 0.08        | 6,389.6              | 5,694.3   | 8.4      | 5,694.3                               | 0.00  | 0.00               | 0.00               |
| 11,828.0      | 89.13         | 0.08        | 6,390.0              | 5,722.3   | 8.4      | 5,722.3                               | 0.00  | 0.00               | 0.00               |
| 11828.1 MD    | , 6390' TVD E | OL - PBHL R | idge Nose Fe         | d Com #1H |          |                                       | 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1        |                    | ANT SAL            |

Design Targets Target Name Northing - hit/miss target 《Dip Angle》Dip Dir 🚷 TVD - Shape (usft) (usft) (usft) Latitude PBHL Ridge Nose Fe-0.00 0.01 6,390.0 5,722.3 8.4 369,773.60 596,432.30 32° 0' 58.464 N 104° 1' 19.927 W

- plan hits target center

- Point



COMPANY: COG PRODUCTION LLC
WELL: Ridge Nose Federal Com #1H
COUNTY: Eddy County, NM
DATUM: NAD 1927 (NADCON CONUS)
RIG: Silver Oak #
GRID CORRECTION: To convert a Magnetic Direction to a Grid Direction, Add 7.32°



GEODETIC ZONE: New Mexico East 3001 GL 2900.7 + 18 @ 2918.7usft (Silver Oak #) GROUND ELEVATION: 2900.7 +E/-W Northing Easting Latitude 0.0 364051.30 596423.90 32° 0' 1.833 N

+N/-S 0.0

Longitude 104° 1' 20.216 W


Slot


| PLAN SECTIONS |    |         |       |      |        |        |       |       |       |        |                             |
|---------------|----|---------|-------|------|--------|--------|-------|-------|-------|--------|-----------------------------|
| S             | ec | MD      | Inc   | Azi  | TVD    | +N/-S  | +E/-W | Dlea  | TFace | VSect  | Target                      |
|               | 1  | 0.0     | 0.00  | 0.00 | 0.0    | 0.0    | 0.0   | 0.00  | 0.00  | 0.0    | · ·                         |
|               | 2  | 5832.6  | 0.00  | 0.00 | 5832.6 | 0.0    | 0.0   | 0.00  | 0.00  | 0.0    |                             |
|               | 3  | 6575.3  | 89.13 | 0.08 | 6310.0 | 470.2  | 0.7   | 12.00 | 0.08  | 470.2  |                             |
|               | 4  | 11828.1 | 89.13 | 0.08 | 6390.0 | 5722.3 | 8.4   | 0.00  | 0.00  | 5722.3 | PBHL Ridge Nose Fed Com #1H |




Azimuths to Grid North True North: -0.17° Magnetic North: 7.32°

Magnetic Field Strength: 48200,0snT Dip Angle: 59,84° Date: 10/25/2013 Model: IGRF2010







# 2,000 psi BOP Schematic




# 3,000 psi BOP Schematic



### 2M Choke Manifold Equipment



### 3M Choke Manifold Equipment



•

Run Time:

07:58 AM

#### **DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT**

Run Date:

01/15/2014 Page 1 of 1

#### LLD ACREAGE REPORT

Admin State:

NM

Geo State:

NM

MTR:

23 0260S 0290E

Section:

031

| _NE | NW | SW | SE |
|-----|----|----|----|
|     |    |    |    |

|          |        |          | <u>NNSS NNSS NNSS NNSS</u> |          | Dup | Sub         |                |
|----------|--------|----------|----------------------------|----------|-----|-------------|----------------|
| Sur Type | Sur No | Lld Suff | EWWE EWWE EWWE             | Sur Note | Flg | <u>Surf</u> | <u>Acreage</u> |
| Α        |        |          | XX X                       |          | -   |             | 120.000        |
| L        | 1      |          | X                          |          |     |             | 40.000         |
| L        | 2      |          | X                          |          |     |             | 23.890         |
| L        | 3      |          | X                          |          |     |             | 23.750         |
| L        | 6      |          | X                          |          |     |             | 26.270         |
| L        | 7      |          | X                          |          |     |             | 25.600         |
| V        |        |          | XXXX XXXX                  |          |     |             |                |

Section 031 Total:

259.510

259.510

MTR Total Exluding Survey Notes C/D/R

and Sub Surf = Y

Grand Total Excluding Survey Notes C/D/R

259.510

and Sub Surf = Y:



# New Mexico Office of the State Engineer Water Column/Average Depth to Water

No records found.

PLSS Search:

Section(s): 31

Township: 26S

Range: 29E



# New Mexico Office of the State Engineer Water Column/Average Depth to Water

No records found.

PLSS Search:

Section(s): 30

Township: 26S

Range: 29E



# New Mexico Office of the State Engineer Water Column/Average Depth to Water

(A CLW##### in the POD suffix indicates the POD has been replaced & no longer serves a

(R=POD has been replaced, O=orphaned,

water right file.)

(quarters are 1=NW 2=NE 3=SW 4=SE) C=the file is

(quarters are smallest to largest) (NAD83 UTM in meters) closed)

(In feet)

|                | POD<br>Süb∋ |       |      | Q.  |       |     |     |        |          |     | Depth (C | Depth   | Water |
|----------------|-------------|-------|------|-----|-------|-----|-----|--------|----------|-----|----------|---------|-------|
| POD Number 200 | ode basin)  | Count | y 64 | 16  | 4 Sec | Tws | Rng | X      | Y        | 4.0 | Well V   | Vater C | olumn |
| C 01354 X-3    | С           | ED    | 2    | 1 3 | 3 23  | 26S | 29E | 598323 | 3543837  | 9   | 170      |         |       |
| C 02038        | С           | ED    | 3    | 2 4 | 26    | 26S | 29E | 599204 | 3541992* | (ر) | 200      |         |       |
| C 03507 POD1   | С           | ED    | 1    | 3 3 | 05    | 26S | 29E | 593064 | 3548313  | دو  | 140      | 78      | 62    |
| C 03508 POD1   | С           | ED    | 1    | 3 3 | 05    | 26S | 29E | 593063 | 3548361  | 9   | 140      | 75      | 65    |
| C 03605 POD1   | CUB         | ED    | 4    | 2 3 | 3 27  | 26S | 29E | 596990 | 3541983  | 9   | 45       | 0       | 45    |

Average Depth to Water:

51 feet

Minimum Depth:

0 feet

Maximum Depth:


78 feet

**Record Count:** 5

PLSS Search:

Township: 26S

Range: 29E



# COG PRODUCTION LLC HYDROGEN SULFIDE DRILLING OPERATIONS PLAN

#### 1. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

- a. The hazards and characteristics of hydrogen sulfide  $(H_2S)$ .
- b. The proper use and maintenance of personal protective equipment and life support systems.
- c. The proper use of H<sub>2</sub>S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
- d. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

- a. The effects of H2S on metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
- b. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
- c. The contents and requirements of the H<sub>2</sub>S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H2S zone (within 3 days or 500 feet) and weekly H2S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H2S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

#### 2. <u>H<sub>2</sub>S SAFETY EQUIPMENT AND SYSTEMS</u>

Note: All H<sub>2</sub>S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H<sub>2</sub>S. If H<sub>2</sub>S greater than 100 ppm is encountered in the gas stream we will shut in and install H<sub>2</sub>S equipment.

a. Well Control Equipment:

Flare line.

Choke manifold with remotely operated choke.

Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.

Auxiliary equipment to include: annular preventer, mud-gas separator, rotating head.

- b. Protective equipment for essential personnel:
  Mark II Surviveair 30-minute units located in the dog house and at briefing areas.
- c. H2S detection and monitoring equipment:
  2 portable H2S monitor positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 ppm are reached.
- d. Visual warning systems:

  Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.
- e. Mud Program:
  The mud program has been designed to minimize the volume of H2S circulated to the surface.
- f. Metallurgy:
  All drill strings, casings, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- g. Communication:Company vehicles equipped with cellular telephone.

COG PRODUCTION LLC has conducted a review to determine if an H2S contingency plan is required for the above referenced well. We were able to conclude that any potential hazardous volume would be minimal. H2S concentrations of wells in this area from surface to TD are low enough; therefore, we do not believe that an H2S contingency plan is necessary.

### WARNING

# YOU ARE ENTERING AN H<sub>2</sub>S AREA AUTHORIZED PERSONNEL ONLY

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED
- 2. HARD HATS REQUIRED
- 3. SMOKING IN DESIGNATED AREAS ONLY
- 4. BE WIND CONSCIOUS AT ALL TIMES
- 5. CK WITH COG OPERATING LLC FOREMAN AT MAIN OFFICE

COG PRODUCTION LLC

1-575-748-6940

## EMERGENCY CALL LIST


|                           | OFFICE       | MOBILE       |
|---------------------------|--------------|--------------|
| COG PRODUCTION LLC OFFICE | 575-748-6940 |              |
| SHERYL BAKER              | 575-748-6940 | 432-934-1873 |
| KENT GREENWAY             | 575-746-2010 | 432-557-1694 |
| SETH WILD                 | 432-683-7443 | 432-528-3633 |
| WALTER ROYE               | 575-748-6940 | 432-934-1886 |

## **EMERGENCY RESPONSE NUMBERS**

|  | <u>OFFICE</u>       |
|--|---------------------|
| STATE POLICE                                     | 575-748-9718        |
| EDDY COUNTY SHERIFF                              | 575-746-2701        |
| EMERGENCY MEDICAL SERVICES (AMBULANCE)           | 911 or 575-746-2701 |
| EDDY COUNTY EMERGENCY MANAGEMENT (HARRY BURGESS) | 575-887-9511        |
| STATE EMERGENCY RESPONSE CENTER (SERC)           | 575-476-9620        |
| CARLSBAD POLICE DEPARTMENT                       | 575-885-2111        |
| CARLSBAD FIRE DEPARTMENT                         | 575-885-3125        |
| NEW MEXICO OIL CONSERVATION DIVISION             | 575-748-1283        |
| INDIAN FIRE & SAFETY                             | 800-530-8693        |
| HALLIBURTON SERVICES                             | 800-844-8451        |

Well pad will be 340' X 340' with cellar in center of pad

COG Production LLC H<sub>2</sub>S Equipment Schematic Terrain: Shinnery sand hills.






COG Production LLC 2208 W. Main Street Artesia, NM 88210

# **Production Facility Layout**

Ridge Nose Federal Com #1H Section 31 - T26S - R29E

# Exhibit 3



Surface Use Plan **COG Production LLC** Ridge Nose Federal Com #1H

SHL: 200' FSL & 2310' FEL Lot #6 Section 31, T26S, R29E

BHL: 1650' FNL & 2310' FEL UL G Section 30, T26S, R29E

Eddy County, New Mexico

# Surface Use & Operating Plan

# Ridge Nose Federal Com #1H

- Surface Tenant: W. P. Ranches Family Partnership, Box 24, Cherokee, TX 76832
- New Road: No new Road
- Flow Line: On well pad
- Facilities: Will be constructed on well pad see Exhibit 3

#### **Well Site Information**

V Door: East

Topsoil: West

Interim Reclamation: West

#### Notes

Onsite: On-site was done by Jesse Rice (BLM); Rand French (COG) and Gerald Herrera (COG) on July 31, 2013.

Surface Use Plan Page 1 Surface Use Plan
COG Production LLC

Ridge Nose Federal Com #1H

SHL: 200' FSL & 2310' FEL

Lot #6

Section 31, T26S, R29E

BHL: 1650' FNL & 2310' FEL UL G

Section 30, T26S, R29E Eddy County, New Mexico

#### SURFACE USE AND OPERATING PLAN

#### 1. Existing & Proposed Access Roads

- A. The well site survey and elevation plat for the proposed well is attached with this application. It was staked by Harcrow Surveying, Artesia, NM.
- B. All roads to the location are shown on the Location Verification Map Exhibit 2. The existing lease roads are illustrated and are adequate for travel during drilling and production operations. Upgrading existing roads prior to drilling the well will be done where necessary. The road route to the well site is depicted in Exhibit #2. The road shown in Exhibit #2 will be used to access the well.
- C. Directions to location: See 600 x 600 plat
- D. Routine grading and maintenance of existing roads will be conducted as necessary to maintain their condition as long as any operations continue on this lease. Roads will be maintained according to specifications in section 2 of this Surface Use and Operating Plan.

#### 2. Proposed Access Road:

The Location Verification Map shows that no new access road will be required for this location. If any road is required it will be constructed as follows:

The maximum width of the running surface will be 14'. The road will be crowned, ditched and constructed of 6" rolled and compacted caliche. Ditches will be at 3:1 slope and 4 feet wide. Water will be diverted where necessary to avoid ponding, prevent erosion, maintain good drainage, and to be consistent with local drainage patterns.

- A. The average grade will be less than 1%.
- B. No turnouts are planned.
- C. There is a culvert as indicated on the Location Verification Map. No cattleguard, gates, low water crossings or fence cuts are necessary.
- D. Surfacing material will consist of native caliche. Caliche will be obtained from the actual well site if available. If not available onsite, caliche will be hauled from the nearest BLM approved caliche pit.

Surface Use Plan Page 2

Surface Use Plan COG Production LLC

Ridge Nose Federal Com #1H

SHL: 200' FSL & 2310' FEL

Lot #6

Section 31, T26S, R29E

BHL: 1650' FNL & 2310' FEL UL G

Section 30, T26S, R29E Eddy County, New Mexico

#### 3. Location of Existing Well:

The One-Mile Radius Map shows existing wells within a one-mile radius of surface hole location and the bottom hole location.

#### 4. Location of Existing and/or Proposed Facilities:

- A. COG Production LLC does not operate an oil production facility on this Lease.
- B. If the well is productive, contemplated facilities will be as follows:
  - 1) A tank battery and facilities will be constructed as shown on Exhibit 3.
  - 2) The tank battery and facilities including all flow lines and piping will be installed according to API specifications.
  - 3) Any additional caliche will be obtained from the actual well site. If caliche does not exist or is not plentiful from the well site, the caliche will be hauled from a BLM approved caliche pit. Any additional construction materials will be purchased from contractors.
  - 4) It will be necessary to run electric power if this well is productive. Power will be provided by Xcel Energy and they will submit a separate plan and ROW for service to the well location.
  - 5) If the well is productive, rehabilitation plans will include the following:
    - The original topsoil from the well site will be returned to the location, and the site will be re-contoured as close as possible to the original site.

#### 5. Location and Type of Water Supply:

The well will be drilled with combination brine and fresh water mud system as outlined in the drilling program. The water will be obtained from commercial water stations in the area and hauled to location by transport truck over the existing and proposed access roads shown in Exhibit #2. If a commercial fresh water source is nearby, fast line may be laid along existing road ROW's and fresh water pumped to the well. No water well will be drilled on the location.

Surface Use Plan Page 3

Surface Use Plan COG Production LLC

Ridge Nose Federal Com #1H

SHL: 200' FSL & 2310' FEL Lot #6

Section 31, T26S, R29E

BHL: 1650' FNL & 2310' FEL UL G

Section 30, T26S, R29E Eddy County, New Mexico

#### 6. Source of Construction Materials and Location "Turn-Over" Procedure:

Obtaining caliche: One primary way of obtaining caliche to build locations and roads will be by "turning over" the location. This means, caliche will be obtained from the actual well site. A caliche permit will be obtained from BLM prior to obtaining caliche. 2400 cubic yards is the maximum amount of caliche needed for pad and roads. Amount will vary for each pad. The procedure below has been approved by BLM personnel:

- A. The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.
- B. An approximate 160' X 160' area is used within the proposed well site to remove caliche.
- C. Subsoil is removed and stockpiled within the surveyed well pad.
- D. When caliche is found, material will be stock piled within the pad site to build the location and road.
- E. Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
- F. Once well is drilled, the stock piled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced.
- G. Neither caliche, nor subsoil will be stock piled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in the Well Site Layout or survey plat.

In the event that no caliche is found onsite, caliche will be hauled in from a BLM approved caliche pit or other established mineral pit. A BLM mineral material permit will be acquired prior to obtaining any mineral material from BLM pits or land.

#### 7. Methods of Handling Water Disposal:

- A. The well will be drilled utilizing a closed loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to an NMOCD approved disposal site.
- B. Drilling fluids will be contained in steel mud pits.
- C. Water produced from the well during completion will be held temporarily in steel tanks and then taken to an NMOCD approved commercial disposal facility.

Surface Use Plan COG Production LLC Ridge Nose Federal Com #1H

,

SHL: 200' FSL & 2310' FEL Lot #6

Section 31, T26S, R29E

BHL: 1650' FNL & 2310' FEL UL G

Section 30, T26S, R29E Eddy County, New Mexico

- D. Garbage and trash produced during drilling or completion operations will be collected in a trash bin and hauled to an approved landfill. No toxic waste or hazardous chemicals will be produced by this operation.
- E. Human waste and grey water will need to be properly contained and disposed of. Proper disposal and elimination of waste and grey water may include but are not limited to portable septic systems and/or portable waste gathering systems (i.e. portable toilets).
- F. After the rig is moved out and the well is either completed or abandoned, all waste materials will be cleaned up within 30 days. In the event of a dry hole only a dry hole marker will remain.

#### 8. Ancillary Facilities:

No airstrip, campsite or other facilities will be built as a result of the operation on this well.

#### 9. Well Site Layout:

- A. The drill pad layout, with elevations staked by Harcrow Surveying, is shown in the Elevation Plat. Dimensions of the pad and pits are shown on the Rig Layout. V door direction is East. Topsoil, if available, will be stockpiled per BLM specifications. Because the pad is almost level no major cuts will be required.
- B. The Rig Layout Closed-Loop exhibit shows the proposed orientation of closed loop system and access road. No permanent living facilities are planned, but a temporary foreman/toolpusher's trailer will be on location during the drilling operations.

#### 10. Plans for Restoration of the Surface:

A. Interim Reclamation will take place after the well has been completed. The pad will be downsized by reclaiming the areas not needed for production operations. The portions of the pad that are not needed for production operations will be re-contoured to its original state as much as possible. The caliche that is removed will be reused to either build another pad site or for road repairs within the lease. The stockpiled topsoil will then be spread out reclaimed area and reseeded with a BLM approved seed mixture. In the event that the well must be worked over or maintained, it may be necessary to drive, park, and/or operate machinery on reclaimed land. This area will be repaired or reclaimed after work is complete.

Surface Use Plan
COG Production LLC
Pidge Nove Federal C

Ridge Nose Federal Com #1H SHL: 200' FSL & 2310' FEL

Lot #6

Section 31, T26S, R29E

BHL: 1650' FNL & 2310' FEL UL G

Section 30, T26S, R29E Eddy County, New Mexico

B. Final Reclamation: Upon plugging and abandoning the well all caliche for well pad and lease road will be removed and surface will be recountoured to reflect its surroundings as much as possible. Caliche will be recycled for road repair or reused for another well pad within the lease. If any topsoil remains, it will be spread out and the area will be reseded with a BLM approved mixture and re-vegetated as per BLM orders.

#### 11. Surface Ownership:

- A. The surface is owned by the U.S. Government and is administered by the Bureau of Land Management. The surface is multiple uses with the primary uses of the region for grazing of livestock and the production of oil and gas.
- B. The surface tenant is W. P. Ranches Family Limited Partnership, Box 24, Cherokee, TX 76832.
- C. The proposed road routes and surface location will be restored as directed by the BLM.

#### 12. Other Information:

- A. The area around the well site is grassland and the topsoil is sandy. The vegetation is moderately sparse with native prairie grasses, some mesquite and shinnery oak. No wildlife was observed but it is likely that mule deer, rabbits, coyotes and rodents traverse the area.
- B. There is no permanent or live water in the immediate area.
- C. There are no dwellings within 2 miles of this location.
- D. If needed, a Cultural Resources Examination is being prepared by Boone Arch Services of NM, LLC., 2030 North Canal, Carlsbad, New Mexico, 88220, phone # 575-885-1352 and the results will be forwarded to your office in the near future. Otherwise, COG will be participating in the Permian Basin MOA Program.

#### 13. Bond Coverage:

Bond Coverage is Statewide Bonds # NMB000845 and NMB000860

Surface Use Plan COG Production LLC

Ridge Nose Federal Com #1H

SHL: 200' FSL & 2310' FEL

Lot #6

Section 31, T26S, R29E

BHL: 1650' FNL & 2310' FEL UL G

Section 30, T26S, R29E Eddy County, New Mexico

#### 14. Lessee's and Operator's Representative:

The COG Production LLC representative responsible for assuring compliance with the surface use plan is as follows:

Sheryl Baker

**Drilling Superintendent** 

COG Production LLC

2208 West Main Street

Artesia, NM 88210

Phone (575) 748-6940 (office)

(432) 934-1873 (cell)

Ray Peterson

**Drilling Manager** 

COG Production LLC

One Concho Center

600 W Illinois Ave

Midland, TX 79701

Phone (432) 685-4304 (office)

(432) 818-2254 (business)

# PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME: COG Production Company - Reyes, Mayte

LEASE NO.: NM121474

WELL NAME & NO.: Ridge Nose Federal Com - 1H

SURFACE HOLE FOOTAGE: [200] ' F [S] L [2310] ' F [E] L

BOTTOM HOLE FOOTAGE: [1650] ' F [N] L [2310] ' F [E] L

LOCATION: Section 031, T026. S., R 029 E., NMPM

5 8242 5 55

COUNTY: Eddy County, New Mexico

### TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

| General Provisions               | : v  |   |
|----------------------------------|--|---|
| Permit Expiration                | at from the  | V as as                                       |
| Archaeology, Paleontology, and 1 | Historical Sites   | ,   |
| Noxious Weeds                    | er hi  | ***   |
| Special Requirements             |  |   |
| Communitization Agreement        | •  |   |
| Construction                     | The second secon | 7. 150 A. |
| Notification                     |  | , E + 15%                                     |
| Topsoil                          | · ·  | i   |
| Closed Loop System               |  |   |
| Federal Mineral Material Pits    |  |   |
| Well Pads                        |  |   |
| Roads                            |  |   |
| ☐ Road Section Diagram           |  |   |
| ☑ Drilling                       |  |   |
| Medium Cave/Karst                |  |   |
| Logging Requirements             |  |   |
| Waste Material and Fluids        |  |   |
| Production (Post Drilling)       |  | -   |
| Well Structures & Facilities     |  |   |
| Pipelines                        |  |   |
| Electric Lines                   |  | •   |
| Interim Reclamation              |  |   |
| 🔲 Final Abandonment & Reclamat   | tion   |   |

#### I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

#### II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

#### III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

#### IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

# V. SPECIAL REQUIREMENT(S)

#### **Communitization Agreement**

A Communitization Agreement covering the acreage dedicated to this well must be filed for approval with the BLM. The effective date of the agreement shall be prior to any sales. In addition, the well sign shall include the surface and bottom hole lease numbers. If the Communitization Agreement number is known, it shall also be on the sign. If not, it shall be placed on the sign when the sign is replaced.

#### VI. CONSTRUCTION

#### A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

#### B. Carla TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

#### C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

#### D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

#### E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

#### F. EXCLOSURE FENCING (CELLARS & PITS)

#### **Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

#### G. ON LEASE ACCESS ROADS

#### Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet

#### Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of nótification.

#### Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

#### Ditching

Ditching shall be required on both sides of the road.

#### **Turnouts**

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

#### **Drainage**

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

#### Cross Section of a Typical Lead-off Ditch

All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

#### Formula for Spacing Interval of Lead-off Ditches

Example 4 On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope: 
$$\frac{400'}{494}$$
 + 100' = 200' lead-off ditch interval

#### Cattleguards

CHEST OF THE STATE OF THE STATE OF

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

#### Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

#### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

#### I. DRILLING

#### A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

#### **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

- 1. Although Hydrogen Sulfide has not been reported in the area, it is always a potential hazard. Operator has stated that they will have monitoring equipment in place prior to drilling out of the surface shoe. If Hydrogen Sulfide is encountered, report measured amounts and formations to the BLM.
- 2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. If the drilling rig is removed without approval an Incident of Non-Compliance will be written and will be a "Major" violation.
- 3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
- 4. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

#### B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

#### Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. IF OPERATOR DOES NOT HAVE THE WELL SPECIFIC CEMENT DETAILS ONSITE PRIOR TO PUMPING THE CEMENT FOR EACH CASING STRING, THE WOC WILL BE 30 HOURS. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Medium Cave/Karst

Possibility of water flows in the Salado and Castile.

Possibility of lost circulation in the Rustler and Delaware.

- 1. The 13-3/8 inch surface casing shall be set at approximately 400 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. If salt is encountered, set casing at least 25 feet above the salt.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
  - Cement to surface. If cement does not circulate see B.1.a, c-d above. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.

If 75% or greater lost circulation occurs while drilling the intermediate casing hole, the cement on the production casing must come to surface.

# Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

- 3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
  - Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification.
- 4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

#### C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
  - a. For surface casing only: If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.
- 3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for <u>drilling below</u> the 9-5/8 intermediate casing shoe shall be 3000 (3M) psi.
- 4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. The tests shall be done by an independent service company utilizing a test plug **not** a **cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (18 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- a. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- b. The results of the test shall be reported to the appropriate BLM office.
- c. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- d. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

#### D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

#### E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

#### JAM 042514

#### II. PRODUCTION (POST DRILLING)

#### A. WELL STRUCTURES & FACILITIES

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

#### Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

#### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

#### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES (Not Applied for in APD)

A State of the Contract of the

C. ELECTRIC LINES (Not Applied for in APD)

#### III. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

# X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

#### Seed Mixture 1, for Loamy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (small/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

| <u>Species</u>                             |                |
|--|----------------|
|  | <u>lb/acre</u> |
| Plains lovegrass (Eragrostis intermedia)   | 0.5            |
| Sand dropseed (Sporobolus cryptandrus)     | 1.0            |
| Sideoats grama (Bouteloua curtipendula)    | 5.0            |
| Plains bristlegrass (Setaria macrostachya) | 2.0            |

<sup>\*</sup>Pounds of pure live seed:

Pounds of seed  $\mathbf{x}$  percent purity  $\mathbf{x}$  percent germination = pounds pure live seed