

NM OIL CONSERVATION

ARTESIA DISTRICT

DEC 08 2014 OCD Artesia

FORM APPROVED
OMB No. 1004-0137
Expires October 31, 2014


UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
RECEIVED
APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		7. If Unit or CA Agreement, Name and No.	
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		8. Lease Name and Well No. <313961> Screech Owl Federal #3H	
2. Name of Operator COG Operating LLC.		9. API Well No. 30-015-42827	
3a. Address 2208 West Main Street Artesia, NM 88210	3b. Phone No. (include area code) 575-748-6940	10. Field and Pool, or Exploratory Welch; Bone Spring <64010>	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface 250' FSL & 2450' FEL Unit Letter O (SWSE) SHL Section 18-T26S-R27E At proposed prod. Zone 330' FSL & 1887' FEL Unit Letter O (SWSE) BHL Section 30-T26S-R27E		11. Sec., T.R.M. or Blk and Survey or Area Section 18 - T26S - R27E	
14. Distance in miles and direction from nearest town or post office* Approximately 12 miles from Malaga		12. County or Parish Eddy County	13. State NM
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. Unit line, if any) 250'	16. No. of acres in lease SHL: 760.24 BHL: 1280	17. Spacing Unit dedicated to this well 320	
18. Distance from location* to nearest well, drilling, completed, applied for, on this lease, ft. SHL: 818'	19. Proposed Depth TVD: 7,405' MD: 17,871'	20. BLM/BIA Bond No. on file NMB000740 & NMB00215	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3297.3' GL	22. Approximate date work will start* 7/1/2014	23. Estimated duration 30 days	

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature 	Name (Printed/Typed) Mayte Reyes	Date 6-4-14
Title Regulatory Analyst		
Approved by (Signature) James A. Amos	Name (Printed/Typed)	Date NOV 18 2014
Title FIELD MANAGER		
Office CARLSBAD FIELD OFFICE		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

Carlsbad Controlled Water Basin


Approval Subject to General Requirements
& Special Stipulations Attached

SEE ATTACHED FOR
CONDITIONS OF APPROVAL

Surface Use Plan
COG Operating LLC
Screech Owl Federal #3H
SHL: 250' FSL & 2450' FEL UL O
Section 18, T26S, R27E
BHL: 330' FSL & 1887' FEL UL O
Section 30, T26S, R27E
Eddy County, New Mexico

OPERATOR CERTIFICATION

I hereby certify that I, or persons under my direct supervision, have inspected the drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or COG Operating LLC, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 4th day of June, 2014.

Signed:  _____

Printed Name: Melanie J. Parker


Position: Regulatory Coordinator

Address: 2208 W. Main Street, Artesia, NM 88210

Telephone: (575) 748-6940

Field Representative (if not above signatory): Rand French


E-mail: mparker@concho.com

OPERATOR CERTIFICATION	
I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.	
<i>Melanie J Parker</i> Signature	5/12 Date
Melanie J Parker Printed Name	
mparker@concho.com E-mail Address	
SURVEYOR CERTIFICATION	
I hereby certify that the well location shown on this plot was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.	
FEBRUARY 7, 2014	
Date of Survey	
Signature & Seal of Professional Surveyor	
	
<i>Chad L. Harcrow</i> Certificate No. CHAD HARCROW 17777 W.O. # 14-371 DRAWN BY: SP	

SECTION 18, TOWNSHIP 26 SOUTH, RANGE 27 EAST, N.M.P.M.,


EDDY COUNTY

NEW MEXICO



DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF CR #724 (WHITES CITY RD.) AND CR #742 (JOHN D FOREHAND RD) GO APPROX. 2.3 MILES SOUTH ALONG CR #742; THEN TURN LEFT (NORTHEAST) AND GO APPROX. 0.8 MILE; THEN TURN RIGHT (SOUTH) AND GO APPROX. 0.2 MILE; THEN ROAD BECOMES A TWO TRACK RD, CONTINUE SOUTH ON TWO TRACK APPROX. 0.1 MILE; THEN TURN LEFT (EAST) AND GO APPROX. 0.1 MILE; THEN PROPOSED WELL IS APPROX. 180 FEET NORTH.



HARCROW SURVEYING, LLC

2314 W. MAIN ST, ARTESIA, N.M. 88210
PH: (575) 513-2570 FAX: (575) 746-2158
chad_harcrow77@yahoo.com



COG OPERATING, LLC

SCREECH OWL FED #3H WELL
LOCATED 250 FEET FROM THE SOUTH LINE
AND 2450 FEET FROM THE EAST LINE OF SECTION 18,
TOWNSHIP 26 SOUTH, RANGE 27 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO

SURVEY DATE: 02/07/2014


PAGE: 1 OF 1

DRAFTING DATE: 02/10/2014

APPROVED BY: CH

DRAWN BY: SP

FILE: 14-371




LEGEND

- WELL
- WELLPAD
- EXISTING RD.
- PROPOSED RD.
- TWO-TRACK RD.

SCREECH OWL FED #3H

SEC: 18 TWP: 26 S. RGE: 27 E. ELEVATION: 3297.3'
 STATE: NEW MEXICO COUNTY: EDDY 250' FSL & 2450' FEL
 W.O. # 14-371 LEASE: SCREECH OWL FED SURVEY: N.M.P.M




LOCATION MAP IMAGERY 02/10/2011 S.P.

CONCHO
 COG OPERATING, LLC

HARCROW SURVEYING, LLC
 1107 WATSON, ARTESIA N.M. 88210
 PH: (575) 513-2570 FAX: (575) 746-2158
 chad_harcrow77@yahoo.com



EXHIBIT 2



LEGEND


- WELL
- WELLPAD
- EXISTING RD.
- PROPOSED RD.
- TWO-TRACK RD.

SCREECH OWL FED #3H

SEC: 18 TWP: 26 S. RGE: 27 E. ELEVATION: 3297.3'

STATE: NEW MEXICO COUNTY: EDDY 250' FSL & 2450' FEL

W.O. # 14-371 LEASE: SCREECH OWL FED SURVEY: N.M.P.M



LOCATION MAP

TOPO

02/10/2011


SP






COG OPERATING, LLC

HARCROW SURVEYING, LLC
1107 WATSON, ARTESIA N.M. 88210
PH (575) 513-2570 FAX (575) 746-2158
chad_harcrow77@yahoo.com





<p>LEGEND</p> <ul style="list-style-type: none"> — FLOWLINE • BEND — EXISTING ROAD — PROPOSED ROAD — TWO-TRACK ROAD (TO BE UPGRADED) • WELL □ WELLPAD □ PRIVATE ■ STATE OF NM ■ US BLM 	<p align="center">SCREECH OWL FED FLOWLINE MAP</p> <p>SECTION: 18 TWP: 26 S. RGE: 27 E. LENGTH: 3460'</p> <p>STATE: NEW MEXICO COUNTY: EDDY SURVEY: N.M.P.M</p> <p>W.O. # 14-368 LEASE: SCREECH OWL FED</p> <div style="display: flex; justify-content: space-between;"> <div> <p>0 0.05 0.1 0.2 Miles</p> </div> <div> <p>0 2,500 FEET</p> </div> </div> <p align="right">1 IN = 1,000 FT</p> <p>FLOWLINE MAP IMAGERY 05/05/2011 SP</p>	<p align="center">  CONCHO COG OPERATING, LLC </p> <hr/> <p align="center">  HARCROW SURVEYING, LLC. 2314 W. MAIN ST, ARTESIA, NM 88210 PH: (575) 513-2570 FAX: (575) 746-2158 chad_harcrow77@yahoo.com </p>
---	--	--




LEGEND

- FLOWLINE
- BEND
- EXISTING ROAD
- PROPOSED ROAD
- TWO-TRACK ROAD (TO BE UPGRADED)
- WELL
- WELLPAD
- PRIVATE
- STATE OF NM
- US BLM

SCREECH OWL FIELD FLOWLINE MAP


SECTION: 18 TWP: 26 S. RGE: 27 E. LENGTH: 3460'
 STATE: NEW MEXICO COUNTY: EDDY SURVEY: N.M.P.M.
 W.O. # 14-368 LEASE: SCREECH OWL FED



FLOWLINE MAP LAND STATUS 05/05/2014 SP

CONCHO
 COG OPERATING, LLC

HARCROW
H HARCROW SURVEYING, LLC.
 2314 W. MAIN ST, ARTESIA, NM 88210
 PH: (575) 513-2570 FAX: (575) 746-2158
 chad_harcrow77@yahoo.com
 SURVEYING




LEGEND

- WELL
- WELLPAD
- EXISTING RD.
- PROPOSED RD.
- TWO-TRACK RD.

SCREECH OWL FED #3H

SEC: 18 TWP: 26 S. RGE: 27 E. ELEVATION: 3297.3'
 STATE: NEW MEXICO COUNTY: EDDY 250' FSL & 2450' FEL
 W.O. # 14-371 LEASE: SCREECH OWL FED SURVEY: N.M.P.M

0 2,500 5,000 7,500 10,000 12,500 15,000 FEET



0 0.4 0.8 1.6 Miles

1 IN = 6,000 FT

VICINITY MAP

02/10/2014


SIP



COG OPERATING, LLC

HARCROW SURVEYING, LLC
 1107 WATSON, ARTESIA NM 88210
 PH: (575) 313-2570 FAX: (575) 746-2138
 chad_harcrow@yahoo.com





DATA FOR "WELLS WITHIN 1 MI." IS TAKEN FROM THE NEW MEXICO EMNRD WEBSITE. THE DATA HAS BEEN UPDATED THROUGH DECEMBER 2013.


LEGEND

- WELL
- BOTTOMHOLE
- WELLS WITHIN 1 MI.
- 1 MI. BUFFER

SCREECH OWL FED #3H

SEC: 18 TWP: 26 S. RGE: 27 E. ELEVATION: 3297.3'
 STATE: NEW MEXICO COUNTY: EDDY 250' FSL & 2450' FEL
 W.O. # 14-371 LEASE: SCREECH OWL FED SURVEY: N.M.P.M

0 2,500 5,000 FEET



0 0.15 0.3 0.6 Miles

1 IN = 2,500 FT

1 MILE MAP

02/10/2014

SP

CONCHO
 COG OPERATING, LLC

HARCROW SURVEYING, LLC
 1107 WATSON, ARTESIA N.M. 88210
 PH: (575) 313-2570 FAX: (575) 746-2158
 chad_harcrow77@yahoo.com



FID	OPERATOR	WELL_NAME	LATITUDE	LONGITUDE	API	SECTION	TOWNSHIP	RANGE	FTG_NS	NS_CD	FTG_EW	EW_CD	TVD_DEPTH	COMPL_STAT
0	BUCK DRLG	V L GATES FED 001	32.011224	-104.209829	3001501162	29	26.0S	27E	1980 S		1980 E		0	Plugged
1	WEATHERFORD W	JP SIMMONS 001	32.017716	-104.215228	3001501163	29	26.0S	27E	990 N		1650 W		0	Plugged
2	WEATHERFORD W	JP SIMMONS 002	32.014087	-104.213021	3001501164	29	26.0S	27E	2310 N		2310 W		0	Plugged
3	JAKE L HAMON	OWL DRAW UT 1 001	32.040591	-104.231445	3001510730	18	26.0S	27E	1980 S		1980 W		0	Plugged
4	DYCHES & ADKISSON	CASTILE FED 001	32.01213	-104.21091	3001523071	29	26.0S	27E	2310 S		2310 E		0	Plugged
5	COG OPERATING LLC	OWL 20504 JV-P 001	32.04059	-104.23112	3001534749	18	26.0S	27E	1980 S		2080 W		5900	Active
6	COG OPERATING LLC	OWL 20504 JV-P 005	32.041486	-104.228253	3001535435	18	26.0S	27E	2310 S		2310 E		3800	New (Not drilled or compl)
7	BTA OIL PRODUCERS, LLC	OWL 20504 JV-P 004	32.037827	-104.22745	3001538339	18	26.0S	27E	980 S		2080 E		0	New (Not drilled or compl)
8	COG OPERATING LLC	BARN OWL FEDERAL 003H	32.036193	-104.231673	3001541283	18	26.0S	27E	380 S		1890 W		7520	New (Not drilled or compl)
9	BTA OIL PRODUCERS, LLC	OWL 20504 JV-P 002	32.044386	-104.235784	3001538340	18	26.0S	27E	1980 N		660 W		0	New (Not drilled or compl)
10	BTA OIL PRODUCERS, LLC	OWL 20504 JV-P 003	32.043799	-104.226182	3001538341	18	26.0S	27E	2180 N		1660 E		0	New (Not drilled or compl)

ATTACHMENT TO FORM 3160-3
COG Operating LLC
SCREECH OWL FEDERAL #3H
SHL: 250' FSL & 2450' FEL, Unit O
Sec. 18 T26S R27E
BHL: 330' FSL & 1887' FEL, Unit O
Sec 30, T26S, R27E
Eddy County, NM

1. Proration Unit Spacing: 320 Acres

2. Ground Elevation: 3297.3'

3. Proposed Depths:

Horizontal: KOP (Kick off Point) TVD = 6967' MD = 6967'
EOC (End of Curve) TVD = 7445' MD = 7719'
Toe (End of Lateral) TVD = 7405' MD = 17871'

4. Estimated tops of geological markers: (TVD)

Fresh Water	50'
Rustler	not present
Top of Salt	346'
BOS/Fletcher	1819'
Lamar/Top of Delaware	2002'
Bell Canyon	2042'
Cherry Canyon	2906'
Brushy Canyon	4023'
Bone Spring	5601'
Upper Avalon	5741'
Lower Avalon	6100'
1 st Bone Spring Sd	6538'
2 nd Bone Spring Sd	7242'
3 rd Bone Spring Sd	8353'

5. Possible mineral bearing formations:

Bell Canyon	2042'	Oil/Gas
Cherry Canyon	2906'	Oil/Gas
Brushy Canyon	4023'	Oil/Gas
Bone Spring	5601'	Oil/Gas
Upper Avalon	5741'	Oil/Gas
Lower Avalon	6100'	Oil/Gas
1 st Bone Spring Sd	6538'	Oil/Gas
2 nd Bone Spring Sd	7242'	Oil/Gas
3 rd Bone Spring Sd	8353'	Oil/gas

350'

No other formations are expected to give up oil, gas or fresh water in measurable quantities. Setting 13 3/8" casing at ~~521'~~ (25' above salt) and circulating cement back to the surface will protect the surface fresh water sand. The Salt Section will be isolated and protected by setting 9 5/8" casing at 2022' (20' into Lamar) and circulating cement back to surface. Any zones between 9 5/8" casing shoe and TD, which contain commercial quantities of oil and/or gas will have cement circulated across them. This will be achieved by cementing 5 1/2" production casing from the TD to surface.

ATTACHMENT TO FORM 3160-3
COG Operating LLC
SCREECH OWL FEDERAL #3H
Page 2 of 6

6. Proposed Mud System

The well will be drilled to TD with a combination of fresh water, brine, cut brine mud systems. The applicable depths and properties of these systems are as follows:

See COA

DEPTH (MD)	TYPE	WEIGHT	VISCOSITY	WATERLOSS
0-321' 350'	Fresh Water	8.3-8.5	28-40	N.C.
321'-2022'	Brine	9.8-10.1	28-32	N.C.
2022'-6968'	FW/Cut Brine	8.3-9.2	28-32	N.C.
6968'-17871'	Cut Brine	8.5-9.2	28-32	N.C.

Sufficient mud materials will be kept at the well site to maintain mud properties and meet minimum lost circulation and weight increase requirements at all times.

Visual or electronic mud monitoring equipment shall be in place to detect volume changes indicating loss or gain of circulating fluid volume.

The mud program has been designed to minimize the volume of H₂S circulated to surface. Proper mud weights, safe drilling practices and the use of H₂S scavengers will minimize

7. Proposed Casing Program

See COA

Hole Size	Interval MD	OD Casing	Weight	Grade	Condition	Jt.	brst/clps/ten
17 1/2"	0-321' 350'	13 3/8" 0-321'	48#	H-40	New	ST&C	5.39/5.22/24.01
12 1/4"	321'-2022'	9 5/8" 0-2022'	36#	J-55	New	LT&C	1.90/1.92/7.34
8 3/4"	2022'-17871'	5 1/2" 0-17871'	17#	P-110	New	BTC	1.33/2.12/5.26

ATTACHMENT TO FORM 3160-3
COG Operating LLC
SCREECH OWL FEDERAL #3H
Page 3 of 6

8. Proposed Cement Program

13 3/8" SURFACE: (Circulate to Surface)

		<u>Description</u>	<u>Yield</u>	<u>Density</u>	<u>Water Requirements</u>
Tail:	400 sks	Class C w/2% CaCl ₂	1.34 cf/sk	14.8 ppg	6.3 gal/sk.
0'-321'					
Excess 108%					

9 5/8" INTERMEDIATE CASING:

Single Stage: (Circulate to Surface)

Lead:	425 sks	Class "C"+ 4% Gel + 1% CaCl ₂	1.75 cf/sk	13.5 ppg	9.2 gal/sk.
0'-1500'					
Excess 52%					
Tail:	300 sks	Class C w/2% CaCl ₂	1.34 cf/sk	14.8 ppg	6.3 gal/sk.
1500'-2022'					
Excess 123%					
Combined Excess 71%					

5 1/2" PRODUCTION CASING:

Single Stage: (Cement calculated to surface. Minimum tie back 200' above 9 5/8" intermediate casing)

1st Lead:					
0'-2022'	235 sks	50:50:10 Class "H" w/8# salt+ 5# kolseal+ 0.5% Halad-322+ 0.3% HR-601+ 0.25 pps D-AIR 5000	2.51 cf/sk	11.9 ppg	14.1 gal/sk.
(min. tie back 200'					
Above 9 5/8" shoe)					
Excess 12%					

ATTACHMENT TO FORM 3160-3
COG Operating LLC
SCREECH OWL FEDERAL #3H
Page 4 of 6

		<u>Description</u>	<u>Yield</u>	<u>Density</u>	<u>Water Requirements</u>
2 nd Lead:					
2022'-6968'	600 sks	50:50:10 Class "H" w/8# salt+	2.51 cf/sk	11.9 ppg	14.1 gal/sk.
Excess 21%		5# kolseal + 0.5% Halad-322+			
		0.3% HR-601+ 0.25 pps D-AIR 5000			
Tail:					
6968'-17871'	2900 sks	50:50:2 Class "H" w/1% salt+	1.25 cf/sk	14.4ppg	5.7 gal/sk.
Excess 32%		0.4% GasStop + 0.3% CFR-3 +			
		0.1 % HR-601			

Combined Excess 26%

9. Pressure Control Equipment:

A 13 5/8" 2000 psi Hydril type annular preventer with mud cross, choke manifold, chokes, kill line, Kelly cock, safety valve and subs to fit all drill strings in use as provided for in Onshore Order #2 will be nipped up on the 13 3/8" x 2000 psi SOW X 13 5/8" x 2000 psi casing head (see attached BOPE drawings). This unit will be hydraulically operated and will be tested by independent tester using test plug to 250 psig/300 psig low and 1000 psig high. Choke line valve, chokes, upper Kelly cock valve, safety valve shall also be tested to 250 psig/300 psig low and 2000 psig high by independent tester.

After setting the 9 5/8" intermediate casing the following BOPE as provided for in Onshore Order #2 will be rigged up on the 9 5/8" intermediate casing spool (13 5/8" 2000 psi x 11" 3000 psi): 11" X 3000 psi annular, 11" X 3000 psi double ram type preventer with blind rams on top and 4 1/2" drill pipe rams on the bottom, choke, mud cross, choke manifold, 4" diameter choke line, 2" kill line, kelly cock, safety valve with proper subs for all drill string connections in use (see attached BOPE drawings). The BOPE including auxiliary equipment (chokes, choke manifold etc.) will be tested by independent tester.

Test plug will be used and all BOPE tested to 250 psig/ 300 psig low pressure and 3000 psig high pressure for 10 minutes. Annular preventer will be tested to 1500 psig. BOP stack will be used continuously until total depth is reached. Pipe rams will be operationally checked each 24-hour period.

Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Any time a component of the BOP stack or choke manifold is changed or installed BOPE will be re-tested as required.

All casing strings below the conductor shall be pressure tested to 0.22 psi per foot of casing string depth or 1500 psig, whichever is greater, but not to exceed 70 percent of casing's minimum internal yield. If pressure declines more than 10 percent in 30 minutes, corrective action will be taken.

ATTACHMENT TO FORM 3160-3
COG Operating LLC
SCREECH OWL FEDERAL #3H
Page 5 of 6

10. Production Hole Drilling Summary:

Drill 8 3/4" hole to 6968'. Kick off 8 3/4" hole at +/-6968', building curve at 12°/100' to 90.23° inclination AZ 165.00° at 7624' MD/7350' TVD. Turn 8 3/4" lateral at 3°/100' to az.177.17° at 8030' MD/7348' TVD. Continue 8 3/4" lateral section at 90.23° inc., az 177.71° for +/-9726' lateral to TD at +/-17871' MD/7310' TVD. Run 5-1/2" production casing. 5 1/2" casing will be isolated by a single stage cement job. Cement will be calculated to surface (min tie back is 200' above 9 5/8" csg shoe).

11. Auxiliary Well Control and Monitoring Equipment

- A. Kelly cock will be kept in the drill string at all times.
- B. A full opening drill pipe-stabbing valve with proper drill pipe connections will be on the rig floor at all times.

12. Logging, Testing and Coring Program:

- A. The following logs will be run in the vertical portion of the hole: Cased hole GR/CNL
- B. The mud logging program will consist of lagged 10' samples from 9 5/8" intermediate casing shoe to KOP and thru curve and lateral to TD.
- C. Drill Stem test is not anticipated
- D. No coring is anticipated
- E. Further testing procedures will be determined after the 5 1/2" production casing has been cemented at TD based on drill shows and log evaluation.

13. Abnormal Conditions, Pressures, Temperatures and Potential Hazards:

See COA

No abnormal pressures or temperatures are anticipated. The estimated bottom hole temperature is 102° Fahrenheit and estimated maximum bottom hole pressure is 3185 psi.. Wells in this area will penetrate formations that are known or could reasonably be expected to contain hydrogen sulfide. Therefore, a H₂S drilling operations plan is included with this APD. Hydrogen sulfide detection equipment will be operational and breathing equipment will be on location after drilling out the 13 3/8" casing shoe and until the 5 1/2" casing is cemented. If while drilling the intermediate hole section H₂S concentrations exceed 100 ppm the well will be shut-in and a remote operated choke installed. A remote operated choke will be installed as part of the 3000 psi BOP equipment rigged up after setting 9 5/8" casing and before drilling the casing shoe. COG will comply with Onshore Order #6. All BOPE testing companies used by COG have H₂S certified employees and will work on H₂S locations. No major loss circulation zones have been reported in offsetting wells.

ATTACHMENT TO FORM 3160-3
COG Operating LLC
SCREECH OWL FEDERAL #3H
Page 6 of 6

14. Anticipated Starting Date

Drilling operations will commence on approximately July 31, 2014 with drilling and completion operations lasting approximately 90 days.

Note: Feel free to make notes as necessary on any of the exhibits or drilling program.

GEG/4.25.14



COG Operating LLC

Eddy County, NM (NAD27 NME)

Screech Owl Federal

#3H

WB1/1410577

Plan: Plan #2 05-16-14

Standard Planning Report

16 May, 2014



PHOENIX
TECHNOLOGY SERVICES



Phoenix Technology Services
Planning Report



Database:	GCR DB	Local Co-ordinate Reference:	Well #3H.
Company:	COG Operating LLC	TVD Reference:	KB @ 3323.30usft (Scandriil Freedom)
Project:	Eddy County, NM (NAD27 NME)	MD Reference:	KB @ 3323.30usft (Scandriil Freedom)
Site:	Screech Owl Federal	North Reference:	Grid
Well:	#3H	Survey Calculation Method:	Minimum Curvature
Wellbore:	WB1/1410577		
Design:	Plan #2 05-16-14		

Project:	Eddy County, NM (NAD27 NME)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site:	Screech Owl Federal Com		
Site Position:		Northing:	376,447.40 usft
From:	Map	Easting:	530,415.40 usft
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "
		Latitude:	32° 2' 5.74965 N
		Longitude:	104° 14' 6.64890 W
		Grid Convergence:	0.05 °

Well:	#3H, 250' FSL & 2450' FEL		
Well Position	+N/-S	292.10 usft	Northing:
	+E/-W	2,196.20 usft	Easting:
Position Uncertainty	0.00 usft		Wellhead Elevation:
			Ground Level:

Wellbore:	WB1/1410577				
Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
			(°)	(°)	(nT)
	IGRF2010_14	05/16/14	7.51	59.83	48,140

Design:	Plan #2 05-16-14			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section	Depth From (TVD)	+N/-S	+E/-W	Direction
	(usft)	(usft)	(usft)	(°)
	0.00	0.00	0.00	176.40

Plan Sections										
Measured Depth	Inclination	Azimuth	Vertical Depth	+N/-S	+E/-W	Dogleg Rate	Build Rate	Turn Rate	TFO	Target
(usft)	(°)	(°)	(usft)	(usft)	(usft)	(%/100usft)	(%/100usft)	(%/100usft)	(°)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
6,967.50	0.00	0.00	6,967.50	0.00	0.00	0.00	0.00	0.00	0.00	
7,719.48	90.23	165.00	7,445.00	-463.08	124.08	12.00	12.00	0.00	165.00	
8,125.30	90.23	177.17	7,443.38	-863.25	186.84	3.00	0.00	3.00	90.00	
17,870.67	90.23	177.17	7,405.00	-10,596.70	667.20	0.00	0.00	0.00	0.00	PBHL-Screech Owl #:



Phoenix Technology Services
Planning Report



Database:	GCR DB	Local Co-ordinate Reference:	Well #3H
Company:	COG Operating LLC	TVD Reference:	KB @ 3323.30usft (Scandril Freedom)
Project:	Eddy County, NM (NAD27 NME)	MD Reference:	KB @ 3323.30usft (Scandril Freedom)
Site:	Screech Owl Federal	North Reference:	Grid
Well:	#3H	Survey Calculation Method:	Minimum Curvature
Wellbore:	WB1/1410577		
Design:	Plan #2 05-16-14		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
346.00	0.00	0.00	346.00	0.00	0.00	0.00	0.00	0.00	0.00	
TOS										
1,819.00	0.00	0.00	1,819.00	0.00	0.00	0.00	0.00	0.00	0.00	
BOS (Fletcher)										
2,002.00	0.00	0.00	2,002.00	0.00	0.00	0.00	0.00	0.00	0.00	
LMAR (Top Delaware)										
2,042.00	0.00	0.00	2,042.00	0.00	0.00	0.00	0.00	0.00	0.00	
BLCN										
2,906.00	0.00	0.00	2,906.00	0.00	0.00	0.00	0.00	0.00	0.00	
CYCN										
4,023.00	0.00	0.00	4,023.00	0.00	0.00	0.00	0.00	0.00	0.00	
BYCN										
5,601.00	0.00	0.00	5,601.00	0.00	0.00	0.00	0.00	0.00	0.00	
Bone Sprg (BSGL)										
5,741.00	0.00	0.00	5,741.00	0.00	0.00	0.00	0.00	0.00	0.00	
U Avalon Sh										
6,100.00	0.00	0.00	6,100.00	0.00	0.00	0.00	0.00	0.00	0.00	
L Avalon Sh										
6,538.00	0.00	0.00	6,538.00	0.00	0.00	0.00	0.00	0.00	0.00	
FBSG_sand										
6,967.50	0.00	0.00	6,967.50	0.00	0.00	0.00	0.00	0.00	0.00	
KOP, 12°/100' Build										
7,000.00	3.90	165.00	6,999.98	-1.07	0.29	1.08	12.00	12.00	0.00	
7,100.00	15.90	165.00	7,098.31	-17.64	4.73	17.91	12.00	12.00	0.00	
7,200.00	27.90	165.00	7,190.92	-53.60	14.36	54.40	12.00	12.00	0.00	
7,259.53	35.04	165.00	7,241.66	-83.60	22.40	84.84	12.00	12.00	0.00	
SBSG_sand										
7,300.00	39.90	165.00	7,273.77	-107.37	28.77	108.97	12.00	12.00	0.00	
7,400.00	51.90	165.00	7,343.24	-176.61	47.32	179.23	12.00	12.00	0.00	
7,500.00	63.89	165.00	7,396.29	-258.28	69.21	262.12	12.00	12.00	0.00	
7,600.00	75.89	165.00	7,430.61	-348.82	93.47	354.01	12.00	12.00	0.00	
7,700.00	87.89	165.00	7,444.68	-444.27	119.04	450.88	12.00	12.00	0.00	
7,719.48	90.23	165.00	7,445.00	-463.09	124.08	469.97	12.00	12.00	0.00	
LP, Begin 3°/100' Turn										
7,800.00	90.23	167.42	7,444.68	-541.28	143.28	549.21	3.00	0.00	3.00	
7,900.00	90.23	170.42	7,444.28	-639.40	162.50	648.35	3.00	0.00	3.00	
8,000.00	90.23	173.42	7,443.88	-738.40	176.56	748.03	3.00	0.00	3.00	
8,100.00	90.23	176.42	7,443.48	-837.99	185.42	847.99	3.00	0.00	3.00	
8,125.30	90.23	177.17	7,443.38	-863.25	186.84	873.28	3.00	0.00	3.00	
Hold 90.23° Inc, 177.17° Azm										
8,200.00	90.23	177.17	7,443.09	-937.86	190.52	947.98	0.00	0.00	0.00	
8,300.00	90.23	177.17	7,442.69	-1,037.74	195.45	1,047.97	0.00	0.00	0.00	
8,400.00	90.23	177.17	7,442.30	-1,137.61	200.38	1,147.96	0.00	0.00	0.00	
8,500.00	90.23	177.17	7,441.90	-1,237.49	205.31	1,247.95	0.00	0.00	0.00	
8,600.00	90.23	177.17	7,441.51	-1,337.37	210.24	1,347.94	0.00	0.00	0.00	
8,700.00	90.23	177.17	7,441.12	-1,437.25	215.17	1,447.93	0.00	0.00	0.00	
8,800.00	90.23	177.17	7,440.72	-1,537.12	220.09	1,547.92	0.00	0.00	0.00	
8,900.00	90.23	177.17	7,440.33	-1,637.00	225.02	1,647.91	0.00	0.00	0.00	
9,000.00	90.23	177.17	7,439.94	-1,736.88	229.95	1,747.90	0.00	0.00	0.00	
9,100.00	90.23	177.17	7,439.54	-1,836.76	234.88	1,847.89	0.00	0.00	0.00	
9,200.00	90.23	177.17	7,439.15	-1,936.64	239.81	1,947.88	0.00	0.00	0.00	
9,300.00	90.23	177.17	7,438.75	-2,036.51	244.74	2,047.87	0.00	0.00	0.00	



Phoenix Technology Services
Planning Report



Database:	GCR DB:	Local Co-ordinate Reference:	Well #3H
Company:	COG Operating LLC:	TVD Reference:	KB @ 3323.30usft (Scandriill Freedom)
Project:	Eddy County, NM (NAD27 NME)	MD Reference:	KB @ 3323.30usft (Scandriill-Freedom)
Site:	Screech Owl Federal	North Reference:	Grid
Well:	#3H	Survey Calculation Method:	Minimum Curvature
Wellbore:	WB1/1410577		
Design:	Plan #2 05-16-14		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,400.00	90.23	177.17	7,438.36	-2,136.39	249.67	2,147.86	0.00	0.00	0.00
9,500.00	90.23	177.17	7,437.97	-2,236.27	254.60	2,247.85	0.00	0.00	0.00
9,600.00	90.23	177.17	7,437.57	-2,336.15	259.53	2,347.84	0.00	0.00	0.00
9,700.00	90.23	177.17	7,437.18	-2,436.02	264.46	2,447.83	0.00	0.00	0.00
9,800.00	90.23	177.17	7,436.78	-2,535.90	269.39	2,547.82	0.00	0.00	0.00
9,900.00	90.23	177.17	7,436.39	-2,635.78	274.31	2,647.81	0.00	0.00	0.00
10,000.00	90.23	177.17	7,436.00	-2,735.66	279.24	2,747.80	0.00	0.00	0.00
10,100.00	90.23	177.17	7,435.60	-2,835.53	284.17	2,847.79	0.00	0.00	0.00
10,200.00	90.23	177.17	7,435.21	-2,935.41	289.10	2,947.78	0.00	0.00	0.00
10,300.00	90.23	177.17	7,434.82	-3,035.29	294.03	3,047.77	0.00	0.00	0.00
10,400.00	90.23	177.17	7,434.42	-3,135.17	298.96	3,147.76	0.00	0.00	0.00
10,500.00	90.23	177.17	7,434.03	-3,235.04	303.89	3,247.75	0.00	0.00	0.00
10,600.00	90.23	177.17	7,433.63	-3,334.92	308.82	3,347.74	0.00	0.00	0.00
10,700.00	90.23	177.17	7,433.24	-3,434.80	313.75	3,447.73	0.00	0.00	0.00
10,800.00	90.23	177.17	7,432.85	-3,534.68	318.68	3,547.72	0.00	0.00	0.00
10,900.00	90.23	177.17	7,432.45	-3,634.56	323.61	3,647.71	0.00	0.00	0.00
11,000.00	90.23	177.17	7,432.06	-3,734.43	328.54	3,747.70	0.00	0.00	0.00
11,100.00	90.23	177.17	7,431.67	-3,834.31	333.46	3,847.69	0.00	0.00	0.00
11,200.00	90.23	177.17	7,431.27	-3,934.19	338.39	3,947.68	0.00	0.00	0.00
11,300.00	90.23	177.17	7,430.88	-4,034.07	343.32	4,047.67	0.00	0.00	0.00
11,400.00	90.23	177.17	7,430.48	-4,133.94	348.25	4,147.66	0.00	0.00	0.00
11,500.00	90.23	177.17	7,430.09	-4,233.82	353.18	4,247.65	0.00	0.00	0.00
11,600.00	90.23	177.17	7,429.70	-4,333.70	358.11	4,347.64	0.00	0.00	0.00
11,700.00	90.23	177.17	7,429.30	-4,433.58	363.04	4,447.63	0.00	0.00	0.00
11,800.00	90.23	177.17	7,428.91	-4,533.45	367.97	4,547.62	0.00	0.00	0.00
11,900.00	90.23	177.17	7,428.51	-4,633.33	372.90	4,647.61	0.00	0.00	0.00
12,000.00	90.23	177.17	7,428.12	-4,733.21	377.83	4,747.60	0.00	0.00	0.00
12,100.00	90.23	177.17	7,427.73	-4,833.09	382.76	4,847.59	0.00	0.00	0.00
12,200.00	90.23	177.17	7,427.33	-4,932.97	387.69	4,947.58	0.00	0.00	0.00
12,300.00	90.23	177.17	7,426.94	-5,032.84	392.61	5,047.57	0.00	0.00	0.00
12,400.00	90.23	177.17	7,426.55	-5,132.72	397.54	5,147.56	0.00	0.00	0.00
12,500.00	90.23	177.17	7,426.15	-5,232.60	402.47	5,247.55	0.00	0.00	0.00
12,600.00	90.23	177.17	7,425.76	-5,332.48	407.40	5,347.54	0.00	0.00	0.00
12,700.00	90.23	177.17	7,425.36	-5,432.35	412.33	5,447.53	0.00	0.00	0.00
12,800.00	90.23	177.17	7,424.97	-5,532.23	417.26	5,547.52	0.00	0.00	0.00
12,900.00	90.23	177.17	7,424.58	-5,632.11	422.19	5,647.51	0.00	0.00	0.00
13,000.00	90.23	177.17	7,424.18	-5,731.99	427.12	5,747.50	0.00	0.00	0.00
13,100.00	90.23	177.17	7,423.79	-5,831.86	432.05	5,847.49	0.00	0.00	0.00
13,200.00	90.23	177.17	7,423.39	-5,931.74	436.98	5,947.48	0.00	0.00	0.00
13,300.00	90.23	177.17	7,423.00	-6,031.62	441.91	6,047.47	0.00	0.00	0.00
13,400.00	90.23	177.17	7,422.61	-6,131.50	446.83	6,147.46	0.00	0.00	0.00
13,500.00	90.23	177.17	7,422.21	-6,231.37	451.76	6,247.45	0.00	0.00	0.00
13,600.00	90.23	177.17	7,421.82	-6,331.25	456.69	6,347.44	0.00	0.00	0.00
13,700.00	90.23	177.17	7,421.43	-6,431.13	461.62	6,447.43	0.00	0.00	0.00
13,800.00	90.23	177.17	7,421.03	-6,531.01	466.55	6,547.42	0.00	0.00	0.00
13,900.00	90.23	177.17	7,420.64	-6,630.89	471.48	6,647.41	0.00	0.00	0.00
14,000.00	90.23	177.17	7,420.24	-6,730.76	476.41	6,747.40	0.00	0.00	0.00
14,100.00	90.23	177.17	7,419.85	-6,830.64	481.34	6,847.39	0.00	0.00	0.00
14,200.00	90.23	177.17	7,419.46	-6,930.52	486.27	6,947.38	0.00	0.00	0.00
14,300.00	90.23	177.17	7,419.06	-7,030.40	491.20	7,047.37	0.00	0.00	0.00
14,400.00	90.23	177.17	7,418.67	-7,130.27	496.13	7,147.36	0.00	0.00	0.00
14,500.00	90.23	177.17	7,418.27	-7,230.15	501.06	7,247.35	0.00	0.00	0.00
14,600.00	90.23	177.17	7,417.88	-7,330.03	505.98	7,347.34	0.00	0.00	0.00
14,700.00	90.23	177.17	7,417.49	-7,429.91	510.91	7,447.33	0.00	0.00	0.00



Phoenix Technology Services
Planning Report



Database:	GCR DB	Local Co-ordinate Reference:	Well #3H
Company:	COG Operating LLC	TVD Reference:	KB @ 3323.30usft (Scandriil Freedom)
Project:	Eddy County, NM (NAD27 NME)	MD Reference:	KB @ 3323.30usft (Scandriil Freedom)
Site:	Screech Owl Federal	North Reference:	Grid
Well:	#3H	Survey Calculation Method:	Minimum Curvature
Wellbore:	WB1/1410577		
Design:	Plan #2 05-16-14		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
14,800.00	90.23	177.17	7,417.09	-7,529.78	515.84	7,547.32	0.00	0.00	0.00	
14,900.00	90.23	177.17	7,416.70	-7,629.66	520.77	7,647.31	0.00	0.00	0.00	
15,000.00	90.23	177.17	7,416.31	-7,729.54	525.70	7,747.30	0.00	0.00	0.00	
15,100.00	90.23	177.17	7,415.91	-7,829.42	530.63	7,847.29	0.00	0.00	0.00	
15,200.00	90.23	177.17	7,415.52	-7,929.30	535.56	7,947.28	0.00	0.00	0.00	
15,300.00	90.23	177.17	7,415.12	-8,029.17	540.49	8,047.27	0.00	0.00	0.00	
15,400.00	90.23	177.17	7,414.73	-8,129.05	545.42	8,147.26	0.00	0.00	0.00	
15,500.00	90.23	177.17	7,414.34	-8,228.93	550.35	8,247.25	0.00	0.00	0.00	
15,600.00	90.23	177.17	7,413.94	-8,328.81	555.28	8,347.24	0.00	0.00	0.00	
15,700.00	90.23	177.17	7,413.55	-8,428.68	560.20	8,447.23	0.00	0.00	0.00	
15,800.00	90.23	177.17	7,413.16	-8,528.56	565.13	8,547.22	0.00	0.00	0.00	
15,900.00	90.23	177.17	7,412.76	-8,628.44	570.06	8,647.21	0.00	0.00	0.00	
16,000.00	90.23	177.17	7,412.37	-8,728.32	574.99	8,747.20	0.00	0.00	0.00	
16,100.00	90.23	177.17	7,411.97	-8,828.19	579.92	8,847.19	0.00	0.00	0.00	
16,200.00	90.23	177.17	7,411.58	-8,928.07	584.85	8,947.18	0.00	0.00	0.00	
16,300.00	90.23	177.17	7,411.19	-9,027.95	589.78	9,047.17	0.00	0.00	0.00	
16,400.00	90.23	177.17	7,410.79	-9,127.83	594.71	9,147.16	0.00	0.00	0.00	
16,500.00	90.23	177.17	7,410.40	-9,227.70	599.64	9,247.15	0.00	0.00	0.00	
16,600.00	90.23	177.17	7,410.00	-9,327.58	604.57	9,347.14	0.00	0.00	0.00	
16,700.00	90.23	177.17	7,409.61	-9,427.46	609.50	9,447.13	0.00	0.00	0.00	
16,800.00	90.23	177.17	7,409.22	-9,527.34	614.43	9,547.12	0.00	0.00	0.00	
16,900.00	90.23	177.17	7,408.82	-9,627.22	619.35	9,647.11	0.00	0.00	0.00	
17,000.00	90.23	177.17	7,408.43	-9,727.09	624.28	9,747.10	0.00	0.00	0.00	
17,100.00	90.23	177.17	7,408.04	-9,826.97	629.21	9,847.09	0.00	0.00	0.00	
17,200.00	90.23	177.17	7,407.64	-9,926.85	634.14	9,947.08	0.00	0.00	0.00	
17,300.00	90.23	177.17	7,407.25	-10,026.73	639.07	10,047.07	0.00	0.00	0.00	
17,400.00	90.23	177.17	7,406.85	-10,126.60	644.00	10,147.06	0.00	0.00	0.00	
17,500.00	90.23	177.17	7,406.46	-10,226.48	648.93	10,247.05	0.00	0.00	0.00	
17,600.00	90.23	177.17	7,406.07	-10,326.36	653.86	10,347.04	0.00	0.00	0.00	
17,700.00	90.23	177.17	7,405.67	-10,426.24	658.79	10,447.03	0.00	0.00	0.00	
17,800.00	90.23	177.17	7,405.28	-10,526.11	663.72	10,547.02	0.00	0.00	0.00	
17,870.67	90.23	177.17	7,405.00	-10,596.70	667.20	10,617.68	0.00	0.00	0.00	
TD at 17870.67 - PBHL-Screech Owl #3H										

Design Targets										
Target Name										
hit/miss target	Dip Angle	Dip Dir	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	
Shape	(°)	(°)	(usft)	(usft)	(usft)	(usft)	(usft)			
PBHL-Screech Owl #3H	0.00	0.00	7,405.00	-10,596.70	667.20	366,142.80	533,278.80	32° 0' 23.74129 N	104° 13' 33.50232 W	
- plan hits target center										
- Point										



Phoenix Technology Services
Planning Report



Database:	GCR DB	Local Co-ordinate Reference:	Well #3H
Company:	COG Operating LLC	TVD Reference:	KB @ 3323.30usft (Scandriill-Freedom)
Project:	Eddy County, NM (NAD27 NME)	MD Reference:	KB @ 3323.30usft (Scandriill Freedom)
Site:	Screech Owl Federal	North Reference:	Grid
Well:	#3H	Survey Calculation Method:	Minimum Curvature
Wellbore:	WB1/1410577		
Design:	Plan #2 05-16-14		

Formations						
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)	
346.00	346.00	TOS		-0.23	177.51	
1,819.00	1,819.00	BOS (Fletcher)		-0.23	177.51	
2,002.00	2,002.00	LMAR (Top Delaware)		-0.23	177.51	
2,042.00	2,042.00	BLCN		-0.23	177.51	
2,906.00	2,906.00	CYCN		-0.23	177.51	
4,023.00	4,023.00	BYCN		-0.23	177.51	
5,601.00	5,601.00	Bone Sprg (BSGL)		-0.23	177.51	
5,741.00	5,741.00	U Avalon Sh		-0.23	177.51	
6,100.00	6,100.00	L Avalon Sh		-0.23	177.51	
6,538.00	6,538.00	FBSG_sand		-0.23	177.51	
7,259.53	7,241.66	SBSG_sand		-0.23	177.51	

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
6,967.50	6,967.50	0.00	0.00	KOP, 12°/100' Build	
7,719.48	7,445.00	-463.09	124.08	LP, Begin 3°/100' Turn	
8,125.30	7,443.38	-863.25	186.84	Hold 90.23° Inc, 177.17° Azm	
17,870.67	7,405.00	-10,596.70	667.20	TD at 17870.67	



Project: Eddy County, NM (NAD27 NME)
Site: Screech Owl Federal Com
Well: #3H
Wellbore: WB1/1410577
Design: Plan #2 05-16-14
Rig: Scandril Freedom





PHOENIX
TECHNOLOGY SERVICES



Azimuths to Grid North
True North: -0.06°
Magnetic North: 7.48°

Magnetic Field
Strength: 48140.35nT
Dip Angle: 59.83°
Date: 05/16/2014
Model: IGRF2010_14





WELL DETAILS									
		Northings	Ground Level	Existing	Latitude	Longitude			
+N-S	+E-W	376739.50	3297.30	532611.60	32° 2' 8.62001 N	104° 13' 41.13126 W			
0.00	0.00								

SECTION DETAILS									
Sec	MD	Inc	Azi	TVD	+N-S	+E-W	Dleg	TFace	Vsect
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2	6967.50	0.00	0.00	6967.50	0.00	0.00	0.00	0.00	0.00
3	7719.45	90.23	155.00	7445.00	-463.08	124.08	12.00	165.00	469.97
4	8125.30	90.23	177.17	7443.38	-853.25	186.84	3.00	90.00	873.28
5	17670.67	90.23	177.17	7405.00	-10596.70	867.20	0.00	0.00	10617.68
PBHL-Screech Owl #3H									
KOP, 12°/100' Build									
LP, Begin 3°/100' Turn									
Hold 90.23° Inc. 177.17° Azm									
TD at 17870.67									


DESIGN TARGET DETAILS									
Name	TVD	+N-S	+E-W	Northings	Existing	Latitude	Longitude	Shape	
PBHL-Screech Owl #3H	7405.00	-10596.70	867.20	368142.80	533278.80	32° 0' 23.74129 N	104° 13' 33.50232 W	Point	
plan hits target center									

LEGEND	
---	#2H, WB1/1410578, Plan #2 05-16-14 VO
---	#4H, WB1, Plan #1 05-14-14 VO
---	Plan #2 05-16-14



Map System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone Name: New Mexico East 3001
Local Origin: Well #3H, Grid North
Latitude: 32° 2' 8.62001 N
Longitude: 104° 13' 41.13126 W
Grid East: 532611.60
Grid North: 376739.50
Scale Factor: 1.000
Geomagnetic Model: IGRF2010_14
Sample Date: 15 May-14
Magnetic Declination: 7.51°
Dip Angle from Horizontal: 59.83°
Magnetic Field Strength: 48140
To convert a Magnetic Direction to a Grid Direction, Add 7.48°
To convert a Magnetic Direction to a True Direction, Add 7.51° East
To convert a True Direction to a Grid Direction, Subtract 0.06°

FORMATION TOP DETAILS				
TVDPath	MDPath	Formation	DipAngle	DipDr
346.00	346.00	TOS	-0.23	177.51
1819.00	1819.00	BOS (Fletcher)	-0.23	177.51
2002.00	2002.00	LMAR (Top Delaware)	-0.23	177.51
2042.00	2042.00	BLCN	-0.23	177.51
2906.00	2906.00	CYCN	-0.23	177.51
4023.00	4023.00	BYCN	-0.23	177.51
5501.00	5501.00	Bone Sprg (BSGL)	-0.23	177.51
5741.00	5741.00	U Avalon Sh	-0.23	177.51
6100.00	6100.00	L Avalon Sh	-0.23	177.51
6538.00	6538.00	FBSG_sand	-0.23	177.51
7241.66	7259.53	SBSG_sand	-0.23	177.51





New Mexico Office of the State Engineer **Water Column/Average Depth to Water**

No records found.

PLSS Search:

Section(s): 30

Township: 26S

Range: 27E

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.



New Mexico Office of the State Engineer Water Column/Average Depth to Water

No records found.

PLSS Search:

Section(s): 19

Township: 26S

Range: 27E

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.

5/5/14 3:55 PM

Page 1 of 1

WATER COLUMN/ AVERAGE
DEPTH TO WATER



New Mexico Office of the State Engineer

Water Column/Average Depth to Water

No records found.

PLSS Search:

Section(s): 18

Township: 26S

Range: 27E

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.

5/5/14 3:55 PM

Page 1 of 1

WATER COLUMN/ AVERAGE
DEPTH TO WATER



New Mexico Office of the State Engineer

Water Column/Average Depth to Water

(A CLW##### in the
POD suffix indicates the
POD has been replaced
& no longer serves a
water right file.)

(R=POD has
been replaced,
O=orphaned,
C=the file is
closed)

(quarters are 1=NW 2=NE 3=SW 4=SE)

(quarters are smallest to largest)

(NAD83 UTM in meters)

(In feet)

POD Number	POD Sub Code	basin	County	Q 64	Q 16	Q 4	Sec	Tws	Rng	X	Y	Depth Well	Depth Water	Water Column
C 02218		CUB	ED	4	1	4	07	26S	27E	573039	3546725*	35		
C 02219		CUB	ED	4	4	4	05	26S	27E	575033	3547948*	35		
C 02474		CUB	ED		4	3	02	26S	27E	578964	3548029*	100		
C 02475		CUB	ED		2	4	13	26S	27E	581450	3545252*	100		
C 02476		CUB	ED		4	1	24	26S	27E	580653	3544032*	150		
C 02930		C	ED	2	3	4	22	26S	27E	577938	3543284*	100	50	50

Average Depth to Water: 50 feet

Minimum Depth: 50 feet

Maximum Depth: 50 feet

Record Count: 6

PLSS Search:


Township: 26S

Range: 27E


*UTM location was derived from PLSS - see Help

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.


2,000 psi BOP Schematic




3,000 psi BOP Schematic



2M Choke Manifold Equipment



3M Choke Manifold Equipment



COG Operating LLC

Rig Plat & Closed Loop Equipment Diagram

Well pad will be 340' X 340'
with cellar in center of pad





Exhibit 1

"I further certify that COG will comply with Rule 19.15.17
NMAC by using a Closed Loop System."

Well pad will be 400' X 400'
with cellar in center of pad

COG Operating LLC
H₂S Equipment Schematic
Terrain: Shinnery sand hills.



COG OPERATING LLC
HYDROGEN SULFIDE DRILLING OPERATIONS PLAN

1. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

- a. The hazards and characteristics of hydrogen sulfide (H₂S).
- b. The proper use and maintenance of personal protective equipment and life support systems.
- c. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
- d. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

- a. The effects of H₂S on metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
- b. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
- c. The contents and requirements of the H₂S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

2. H₂S SAFETY EQUIPMENT AND SYSTEMS

Note: All H₂S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H₂S. If H₂S greater than 100 ppm is encountered in the gas stream we will shut in and install H₂S equipment.

- a. Well Control Equipment:
 - Flare line.
 - Choke manifold with remotely operated choke.
 - Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
 - Auxiliary equipment to include: annular preventer, mud-gas separator, rotating head.

- b. Protective equipment for essential personnel:
Mark II Surviveair 30-minute units located in the dog house and at briefing areas.
- c. H2S detection and monitoring equipment:
2 - portable H2S monitor positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 ppm are reached.
- d. Visual warning systems:
Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.
- e. Mud Program:
The mud program has been designed to minimize the volume of H2S circulated to the surface.
- f. Metallurgy:
All drill strings, casings, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- g. Communication:
Company vehicles equipped with cellular telephone.

COG OPERATING LLC has conducted a review to determine if an H2S contingency plan is required for the above referenced well. We were able to conclude that any potential hazardous volume would be minimal. H2S concentrations of wells in this area from surface to TD are low enough; therefore, we do not believe that an H2S contingency plan is necessary.

WARNING

YOU ARE ENTERING AN H₂S AREA
AUTHORIZED PERSONNEL ONLY

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED*
- 2. HARD HATS REQUIRED*
- 3. SMOKING IN DESIGNATED AREAS ONLY*
- 4. BE WIND CONSCIOUS AT ALL TIMES*
- 5. CK WITH COG OPERATING LLC FOREMAN AT MAIN OFFICE*

COG OPERATING LLC

1-575-748-6940

EMERGENCY CALL LIST

	<u>OFFICE</u>	<u>MOBILE</u>
COG OPERATING LLC OFFICE	575-748-6940	
SHERYL BAKER	575-748-6940	432-934-1873
KENT GREENWAY	575-746-2010	432-557-1694
SETH WILD	432-683-7443	432-528-3633
WALTER ROYE	575-748-6940	432-934-1886

EMERGENCY RESPONSE NUMBERS

	<u>OFFICE</u>
STATE POLICE	575-748-9718
EDDY COUNTY SHERIFF	575-746-2701
EMERGENCY MEDICAL SERVICES (AMBULANCE)	911 or 575-746-2701
EDDY COUNTY EMERGENCY MANAGEMENT (HARRY BURGESS)	575-887-9511
STATE EMERGENCY RESPONSE CENTER (SERC)	575-476-9620
CARLSBAD POLICE DEPARTMENT	575-885-2111
CARLSBAD FIRE DEPARTMENT	575-885-3125
NEW MEXICO OIL CONSERVATION DIVISION	575-748-1283
INDIAN FIRE & SAFETY	800-530-8693
HALLIBURTON SERVICES	800-844-8451



COG Operating LLC
2208 West Main
Artesia, NM 88210

Production Facility Layout

Screech Owl Federal #3H
SHL: Section 18-T26S-R27E
BHL: Section 30-26S-27E




Exhibit 3

Surface Use & Operating Plan

Screech Owl Federal #3H

- Surface Tenant: Forehand Ranches, Inc., P O Box 5373, Carlsbad, NM 88220
- New Road: 1017'
- Flow Line: Will follow road to facility at the Screech Owl Federal #2H.
- Facilities: Will utilize facilities at the Screech Owl Federal #2H.

Well Site Information

V Door: East

Topsoil: North and West

Interim Reclamation: North, West and East.

Notes

Onsite: On-site was done by Tanner Nygren (BLM); Gerald Herrera (COG) on February 4, 2014.

SURFACE USE AND OPERATING PLAN

1. Existing & Proposed Access Roads

- A. The well site survey and elevation plat for the proposed well is attached with this application. It was staked by Harcrow Surveying, Artesia, NM.
- B. All roads to the location are shown on the Location Verification Map Exhibit 2. The existing lease roads are illustrated and are adequate for travel during drilling and production operations. Upgrading existing roads prior to drilling the well will be done where necessary. The road route to the well site is depicted in Exhibit #2. The road shown in Exhibit #2 will be used to access the well.
- C. Directions to location: See 600 x 600 plat
- D. Routine grading and maintenance of existing roads will be conducted as necessary to maintain their condition as long as any operations continue on this lease. Roads will be maintained according to specifications in section 2 of this Surface Use and Operating Plan.

2. Proposed Access Road:

The Location Verification Map shows that 1017' of new access road will be required for this location. If any road is required it will be constructed as follows:

The maximum width of the running surface will be 14'. The road will be crowned, ditched and constructed of 6" rolled and compacted caliche. Ditches will be at 3:1 slope and 4 feet wide. Water will be diverted where necessary to avoid ponding, prevent erosion, maintain good drainage, and to be consistent with local drainage patterns.

- A. The average grade will be less than 1%.
- B. No turnouts are planned.
- C. No culvert, cattleguard, gates, low water crossings or fence cuts are necessary.
- D. Surfacing material will consist of native caliche. Caliche will be obtained from the actual well site if available. If not available onsite, caliche will be hauled from the nearest BLM approved caliche pit.

3. Location of Existing Well:

The One-Mile Radius Map shows existing wells within a one-mile radius of the proposed wellbore.

4. Location of Existing and/or Proposed Facilities:

A. If the well is productive, contemplated facilities will be as follows:

- 1) A tank battery and facilities are proposed at the Screech Owl Federal #2H location.
- 2) Production will be sent to the Screech Owl Federal #2H facility. A surface flow line of approximately 1172' of 2 7/8" steel pipe carrying oil, gas and water under a maximum pressure of 125 psi will follow the access road to the Screech Owl Federal #2H. The flow line is be layed a safe distance, estimated at 5-10' from the road.
- 3) The tank battery and facilities including all flow lines and piping will be installed according to API specifications.
- 4) Any additional caliche will be obtained from the actual well site. If caliche does not exist or is not plentiful from the well site, the caliche will be hauled from a BLM approved caliche pit. Any additional construction materials will be purchased from contractors.
- 5) It will be necessary to run electric power if this well is productive. Power will be provided by Xcel Energy and they will submit a separate plan and ROW for service to the well location.
- 6) If the well is productive, rehabilitation plans will include the following:
 - The original topsoil from the well site will be returned to the location, and the site will be re-contoured as close as possible to the original site.

5. Location and Type of Water Supply:

The well will be drilled with combination brine and fresh water mud system as outlined in the drilling program. The water will be obtained from commercial water stations in the area and hauled to location by transport truck over the existing and proposed access roads shown in Exhibit #2. If a commercial fresh water source is nearby, fast line may be laid along existing road ROW's and fresh water pumped to the well. No water well will be drilled on the location.

6. Source of Construction Materials and Location "Turn-Over" Procedure:

Obtaining caliche: One primary way of obtaining caliche to build locations and roads will be by "turning over" the location. This means, caliche will be obtained from the actual well site. A caliche permit will be obtained from BLM prior to obtaining caliche. 2400 cubic yards is the maximum amount of caliche needed for pad and roads. Amount will vary for each pad. The procedure below has been approved by BLM personnel:

- A. The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.
- B. An approximate 160' X 160' area is used within the proposed well site to remove caliche.
- C. Subsoil is removed and stockpiled within the surveyed well pad.
- D. When caliche is found, material will be stock piled within the pad site to build the location and road.
- E. Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
- F. Once well is drilled, the stock piled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced.
- G. Neither caliche, nor subsoil will be stock piled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in the Well Site Layout or survey plat.

In the event that no caliche is found onsite, caliche will be hauled in from a BLM approved caliche pit or other established mineral pit. A BLM mineral material permit will be acquired prior to obtaining any mineral material from BLM pits or land.

7. Methods of Handling Water Disposal:

- A. The well will be drilled utilizing a closed loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to an NMOCD approved disposal site.
- B. Drilling fluids will be contained in steel mud pits.
- C. Water produced from the well during completion will be held temporarily in steel tanks and then taken to an NMOCD approved commercial disposal facility.

- D. Garbage and trash produced during drilling or completion operations will be collected in a trash bin and hauled to an approved landfill. No toxic waste or hazardous chemicals will be produced by this operation.
- E. Human waste and grey water will need to be properly contained and disposed of. Proper disposal and elimination of waste and grey water may include but are not limited to portable septic systems and/or portable waste gathering systems (i.e. portable toilets).
- F. After the rig is moved out and the well is either completed or abandoned, all waste materials will be cleaned up within 30 days. In the event of a dry hole only a dry hole marker will remain.

8. Ancillary Facilities:

No airstrip, campsite or other facilities will be built as a result of the operation on this well.

9. Well Site Layout:

- A. The drill pad layout, with elevations staked by Harcrow Surveying, is shown in the Elevation Plat. Dimensions of the pad and pits are shown on the Rig Layout. V door direction is East. Topsoil, if available, will be stockpiled per BLM specifications. Because the pad is almost level no major cuts will be required.
- B. The Rig Layout Closed-Loop exhibit shows the proposed orientation of closed loop system and access road. No permanent living facilities are planned, but a temporary foreman/toolpusher's trailer will be on location during the drilling operations.

10. Plans for Restoration of the Surface:

- A. COG Operating LLC proposes to delay interim reclamation until both the Asio Otus Federal #3H and the Screech Owl Federal #2H wells have been drilled and completed. The Asio Otus Federal #3H is scheduled to be drilled and completed less than six months prior to the drilling of the Screech Owl Federal #2H. The pad will be downsized by reclaiming the areas not needed for production operations. The portions of the pad that are not needed for production operations will be re-contoured to its original state as much as possible. The caliche that is removed will be reused to either build another pad site or for road repairs within the lease. The stockpiled topsoil will then be spread out reclaimed area and reseeded with a BLM approved seed mixture. In the event that the well must be worked over or maintained, it may be necessary to drive, park, and/or

operate machinery on reclaimed land. This area will be repaired or reclaimed after work is complete.

- B. Final Reclamation: Upon plugging and abandoning the well all caliche for well pad and lease road will be removed and surface will be recountoured to reflect its surroundings as much as possible. Caliche will be recycled for road repair or reused for another well pad within the lease. If any topsoil remains, it will be spread out and the area will be re-seeded with a BLM approved mixture and re-vegetated as per BLM orders.

11. Surface Ownership:

- A. The surface is owned by the U.S. Government and is administered by the Bureau of Land Management. The surface is multiple uses with the primary uses of the region for grazing of livestock and the production of oil and gas.
- B. The surface tenant is Forehand Ranches, Inc., P O Box 5373, Carlsbad, NM 88220.
- C. The proposed road routes and surface location will be restored as directed by the BLM.

12. Other Information:

- A. The area around the well site is grassland and the topsoil is sandy. The vegetation is moderately sparse with native prairie grasses, some mesquite and shinnery oak. No wildlife was observed but it is likely that mule deer, rabbits, coyotes and rodents traverse the area.
- B. There is no permanent or live water in the immediate area.
- C. There are no dwellings within 2 miles of this location.
- D. If needed, a Cultural Resources Examination is being prepared by Boone Arch Services of NM, LLC., 2030 North Canal, Carlsbad, New Mexico, 88220, phone # 575-885-1352 and the results will be forwarded to your office in the near future. Otherwise, **COG will be participating in the Permian Basin MOA Program.**

13. Bond Coverage:

Bond Coverage is Statewide Bonds # NMB000740 and NMB000215

Surface Use Plan
COG Operating LLC
Screech Owl Federal #3H
SHL: 250' FSL & 2450' FEL UL O
Section 18, T26S, R27E
BHL: 330' FSL & 1887' FEL UL O
Section 30, T26S, R27E
Eddy County, New Mexico

14. Lessee's and Operator's Representative:

The COG Operating LLC representative responsible for assuring compliance with the surface use plan is as follows:

Sheryl Baker
Drilling Superintendent
COG Operating LLC
2208 West Main Street
Artesia, NM 88210
Phone (575) 748-6940 (office)
(432) 934-1873 (cell)

Ray Peterson
Drilling Manager
COG Operating LLC
One Concho Center
600 W Illinois Ave
Midland, TX 79701
Phone (432) 685-4304 (office)
(432) 818-2254 (business)

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	COG Operating LLC
LEASE NO.:	NMNM-114970
WELL NAME & NO.:	Screech Owl Federal 3H
SURFACE HOLE FOOTAGE:	0250' FSL & 2450' FEL
BOTTOM HOLE FOOTAGE	0330' FSL & 1887' FEL Sec. 30, T. 26 S., R 27 E.
LOCATION:	Section 18, T. 26 S., R 27 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☐ **Special Requirements**
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
 - Cement Requirement
 - High Cave/Karst
 - Logging Requirements
 - Waste Material and Fluids
- ☒ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattleguards

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. **Although there are no measured amounts of Hydrogen Sulfide reported, it is always a potential hazard. Operator has stated that they will have monitoring equipment in place prior to drilling out the surface shoe. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. IF OPERATOR DOES NOT HAVE THE WELL SPECIFIC CEMENT DETAILS ONSITE PRIOR TO PUMPING THE CEMENT FOR EACH CASING STRING, THE WOC WILL BE 30 HOURS. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

High Cave/Karst

Possibility of water flows in the Salado and Castile.

Possibility of lost circulation in the Salado, Rustler, and Delaware.

A MINIMUM OF TWO CASING STRINGS CEMENTED TO SURFACE IS REQUIRED IN HIGH CAVE/KARST AREAS. THE CEMENT MUST BE IN A SOLID SHEATH. THEREFORE, ONE INCH OPERATIONS ARE NOT SUFFICIENT TO PROTECT CAVE KARST RESOURCES. A CASING DESIGN THAT HAS A ONE INCH JOB PERFORMED DOES NOT COUNT AS A SOLID SHEATH.

ON A THREE STRING DESIGN; IF THE PRIMARY CEMENT JOB ON THE SURFACE CASING DOES NOT CIRCULATE, THEN THE NEXT TWO CASING STRINGS MUST BE CEMENTED TO SURFACE.

1. The 13-3/8 inch surface casing shall be set at approximately 350 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing, which shall be set at approximately **2022** feet (Basal anhydrite of the Castile formation or Lamar Limestone), is:
- ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.**

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
- ☒ Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification.
4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
 - a. **For surface casing only:** If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.
- 3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 9-5/8 intermediate casing shoe shall be **3000 (3M)** psi.

4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (18 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
 - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - d. The results of the test shall be reported to the appropriate BLM office.
 - e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
 - f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 111814

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the

largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the application (Grant, Sundry Notice, APD) and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. The holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
- b. Activities of other parties including, but not limited to:
 - (1) Land clearing.
 - (2) Earth-disturbing and earth-moving work.
 - (3) Blasting.
 - (4) Vandalism and sabotage.
- c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.

6. All construction and maintenance activity will be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline must be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline must be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.

8. The holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline will be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation.

measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines must be less than or equal to 4 inches and a working pressure below 125 psi.

IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory

revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 1, for Loamy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (small/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

Species

lb/acre

Plains lovegrass (<i>Eragrostis intermedia</i>)	0.5
Sand dropseed (<i>Sporobolus cryptandrus</i>)	1.0
Sideoats grama (<i>Bouteloua curtipendula</i>)	5.0
Plains bristlegrass (<i>Setaria macrostachya</i>)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed