

15-770

NM OIL CONSERVATION

ARTESIA DISTRICT
OCD Artesia

DEC 03 2015

HIGH CAVE KARST

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

FORM APPROVED
OMB No. 1004-0137
Expires October 31, 2014

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work



DRILL



REENTER

1b. Type of Well



Oil Well



Gas Well



Other



Single Zone



Multiple Zone

2. Name of Operator

Cimarex Energy Co.

3a. Address

600 N. Marienfield St. Ste. 600 Midland Tx 79071

3b. Phone No. (include area code)

432-571-7800

4. Location of Well (Report location clearly and in accordance with any State requirements. *)

At Surface 330 FSL & 2200 FWL

At proposed prod. Zone 330 FSL & 2220 FWL

Bone Spring

14. Distance in miles and direction from nearest town or post office*

White City, NM is +/- miles northwesterly

9 miles

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drg. unit line if any)

266'

16. No of acres in lease

NMNM094842=159.02 acres
NMNM111530=478.86 acres

17. Spacing Unit dedicated to this well

160.00

18. Distance from proposed* location to nearest well, drilling, completed, applied for, on this lease, ft.

1986' to the
Gadwall 18
Federal Com
4H19. Proposed Depth
Pilot Hole TD: N/A
12,000 MD 7,270 TVD

20. BLM/BIA Bond No. on File

NMB01188

21. Elevations (Show whether DF, KDB, RT, GL, etc.)

3194 GR

22. Approximate date work will start*

7/30/15

23. Estimated duration

30 days

OCD
12/3/15

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor
- A Drilling Plan
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator Certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature

Hope Knauls

Name (Printed/Typed)

Hope Knauls

Date

6/9/15

Title

Regulatory Compliance

Approved By (Signature)

Steve Caley

Name (Printed/Typed)

CARLSBAD FIELD OFFICE

Date

DEC 3 2015

Title

FIELD MANAGER

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.S. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious, or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

Carlsbad Controlled Water Basin

Approval Subject to General Requirements
& Special Stipulations Attached.SEE ATTACHED FOR
CONDITIONS OF APPROVAL

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Uruzu Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

1 API Number 30-015- 43488	2 Pool Code 97494	3 Pool Name Cottonwood Draw, B.S.
4 Property Code 34114	5 Property Name GADWALL 18 FEDERAL Com	6 Well Number 5H
7 OGRID No. 162683	8 Operator Name CIMAREX ENERGY CO.	9 Elevation 3194.7'

"Surface Location


UT or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
C	18	25S	27E		266	NORTH	2594	WEST	EDDY

"Bottom Hole Location If Different From Surface

UT or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
N	18	25S	27E		330	SOUTH	1980	WEST	EDDY

11 Dedicated Acres 160	12 Joint or Infill	13 Consolidation Code	14 Order No.
---------------------------	--------------------	-----------------------	--------------

No allowbale will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



"OPERATOR
CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Hope Knauls 6/9/15
Signature Date

Hope Knauls
Printed Name
hknauls@cimarex.com
E-mail Address

"SURVEYOR
CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

April 17, 2015

Date of Survey
Signature and Seal of Professional Surveyor:

PROFESSIONAL SURVEYOR
NEW MEXICO
12446
Nelson J. Marshall
NELSON J. MARSHALL
APR 17 - 15

Certificate Number:

Operator Certification Statement

Gadwall 18 Federal Com 5H

Cimarex Energy Co.

UL: C, Sec. 18, 25S, 27E

Eddy Co., NM

Operator's Representative

Cimarex Energy Co. of Colorado

600 N. Marienfeld St., Ste. 600

Midland, TX 79701

Office Phone: (432) 571-7800

CERTIFICATION: I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

I am responsible under the terms and conditions of the lease to conduct lease operations in conjunction with the application. Bond coverage pursuant to 43, 25 or 36 CFR for lease activities is being provided by Cimarex Energy Co. under their (Lease, Statewide, Nationwide, Unit or Permit) Bond, BLM/BIA/FS Bond No. NMB01188.

Executed this 9 day of June, 2015

NAME: Hope Knauls

Hope Knauls


TITLE: Regulatory Compliance

ADDRESS: 600 N. Marienfeld St. Ste. 600 Midland Tx 79071

TELEPHONE: 432-571-7800

EMAIL: hknauls@cimarex.com

Field Representative: Same as above



LEGEND:

- EXISTING WELLS

CIMAREX ENERGY CO.

GADWALL 18 FEDERAL 5H
266' FNL 2594' FWL
NE 1/4, NW 1/4, SECTION 18, T25S, R27E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

DRAWN BY: B.D.

DATE DRAWN: 05-06-15

SCALE: 1" = 2000'

REVISED: 00-00-00


ONE MILE RADIUS PLAT

EXHIBIT A



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017





LEGEND:

○ PROPOSED LOCATION



CIMAREX ENERGY CO.

GADWALL 18 FEDERAL 5H
266' FNL 2594' FWL
NE 1/4, NW 1/4, SECTION 18, T25S, R27E, N.M.P.M.
EDDY COUNTY, NEW MEXICO




UELS, LLC
Corporate Office • 85 South 200 East
Vernal, UT 84078 • (435) 789-1017

DRAWN BY: B.D.
SCALE: 1:100,000

DATE DRAWN: 03-06-15
REVISED: 00-00-00

PUBLIC ACCESS ROAD MAP

EXHIBIT B



FINISHED GRADE ELEVATION = 3193.6'

NOTES:

- Contours shown at 2' intervals.
- Underground utilities shown on this sheet are for visualization purposes only, actual locations to be determined prior to construction.

CIMAREX ENERGY CO.

GADWALL 18 FEDERAL 5H

266' FNL 2594' FWL

NE 1/4 NW 1/4, SECTION 18, T25S, R27E, N.M.P.M.

EDDY COUNTY, NEW MEXICO




UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

DRAWN BY: T.E.	DATE DRAWN: 05-01-15
SCALE: 1" = 80'	REVISED: 00-00-00

LOCATION LAYOUT

EXHIBIT D



LINE TABLE		
LINE	DIRECTION	LENGTH
L1	S87°W	243'
L2	N74°W	264'
L3	N69°W	304'
L4	N39°W	108'
L5	N38°W	261'
L6	N08°E	388'

NOTES:


CIMAREX ENERGY CO.

GADWALL 18 FEDERAL 5H
 266' FNL 2594' FWL
 NE 1/4 NW 1/4, SECTION 18, T25S, R27E, N.M.P.M.
 EDDY COUNTY, NEW MEXICO



UELS, LLC
 Corporate Office * 85 South 200 East
 Vernal, UT 84078 * (435) 789-1017

DRAWN BY: T.E.	DATE DRAWN: 05-01-15
SCALE: 1" = 120'	REVISED: 00-00-00
ARCHAEOLOGICAL SURVEY BOUNDARY	EXHIBIT D



FLOW LINE RIGHT-OF-WAY DESCRIPTION

A 30' WIDE RIGHT-OF-WAY 15' ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE.

BEGINNING AT A POINT IN THE NE 1/4 NW 1/4 OF SECTION 18, T25S, R27E, N.M.P.M., WHICH BEARS S83°06'04"E 2409.09' FROM THE NORTHWEST CORNER OF SAID SECTION 18, THENCE S48°42'26"W 149.16'; THENCE N84°51'55"W 20.55'; THENCE N31°36'18"W 188.44'; THENCE N10°58'47"E 21.16'; THENCE N53°49'59"E 56.93' TO A POINT IN THE NE 1/4 NW 1/4 OF SAID SECTION 18, WHICH BEARS S85°34'24"E 2216.96' FROM THE NORTHWEST CORNER OF SAID SECTION 18. THE SIDE LINES OF SAID DESCRIBED RIGHT-OF-WAY BEING SHORTENED OR ELONGATED TO MEET THE GRANTOR'S PROPERTY LINES. BASIS OF BEARINGS IS A G.P.S. OBSERVATION. CONTAINS 0.300 ACRES MORE OR LESS.

BEGINNING OF FLOW LINE STA. 0+00 BEARS S83°06'04"E 2409.09' FROM THE NORTHWEST CORNER OF SECTION 18, T25S, R27E, N.M.P.M.

END OF FLOW LINE STA. 4+36.24 BEARS S85°34'24"E 2216.96' FROM THE NORTHWEST CORNER OF SECTION 18, T25S, R27E, N.M.P.M.



ACREAGE / LENGTH TABLE

	OWNERSHIP	FEET	RODS	ACRES
(SEC. 18 NW 1/4)	BLM	436.24	26.44	0.300

▲ = SECTION CORNERS LOCATED.

NOTES:

THIS IS TO CERTIFY THAT THE ABOVE MAP WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

CERTIFICATE OF PROFESSIONAL SURVEYOR

12448

REGISTERED LAND SURVEYOR
REGISTRATION NO. 12448
STATE OF NEW MEXICO

05-11-15

CIMAREX ENERGY CO.

GADWALL 18 FEDERAL 5H
SECTION 18, T25S, R27E, N.M.P.M.
EDDY COUNTY, NEW MEXICO


DRAWN BY: T.E. DATE DRAWN: 05-01-15
SCALE: 1" = 300' REVISED: 00-00-00

FLOW LINE R-O-W

EXHIBIT G-1



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017



ACREAGE / LENGTH TABLE				
	OWNERSHIP	FEET	RODS	ACRES
(SEC. 7 SW 1/4)	BLM	355.08	21.52	0.204
(SEC. 18 NW 1/4)	BLM	48.88	2.96	0.028
TOTAL		403.96	24.48	0.232

▲ = SECTION CORNERS LOCATED!

NOTES:

CERTIFICATE OF PROFESSIONAL SURVEYOR
THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM THE NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 12446
STATE OF NEW MEXICO
05-11-15

CIMAREX ENERGY CO.






GADWALL 18 FEDERAL 5H
SECTION 18, T25S, R27E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

DRAWN BY: T.E.	DATE DRAWN: 05-01-15
SCALE: 1" = 300'	REVISED: 00-00-00
POWER LINE R-O-W	EXHIBIT H



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

1" = 40'
X-Section
Scale
1" = 100'



APPROXIMATE EARTHWORK QUANTITIES	
(3") TOPSOIL STRIPPING	950 Cu. Yds.
REMAINING LOCATION	5,100 Cu. Yds.
TOTAL CUT	6,050 Cu. Yds.
FILL	8,590 Cu. Yds.
DEFICIT MATERIAL	<2,540> Cu. Yds.
TOPSOIL	950 Cu. Yds.
DEFICIT UNBALANCE (After Interim Rehabilitation)	<3,490> Cu. Yds.

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±2.331
30' WIDE FLOW LINE R-O-W DISTURBANCE	±436.24'	±0.300
25' WIDE POWER LINE R-O-W DISTURBANCE	±403.96'	±0.232
TOTAL SURFACE USE AREA		±2.863

NOTES:

- Fill quantity includes 5% for compaction.
- Obtain deficit material from approved borrow area.

CIMAREX ENERGY CO.

GADWALL 18 FEDERAL 5H
266' FNL 2594' FWL
NE 1/4 NW 1/4, SECTION 18, T25S, R27E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

DRAWN BY: T.E.	DATE DRAWN: 05-01-15
SCALE: AS SHOWN	REVISED: 00-00-00

TYPICAL CROSS SECTIONS **EXHIBIT D.**

BEGINNING AT THE INTERSECTION OF BLACK RIVER ROAD/ OLD CAVERN HIGHWAY PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 6.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 0.3 MILES TO THE EXISTING DA VINCI 7 FEDERAL COM 4H & GADWALL 18 FED COM #2 PAD AND THE PROPOSED LOCATION.

TOTAL DISTANCE FROM THE INTERSECTION OF BLACK RIVER ROAD/ OLD CAVERN HIGHWAY TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 6.7 MILES.

CIMAREX ENERGY CO.

GADWALL 18 FEDERAL 5H
266' FNL 2594' FWL
NE 1/4, NW 1/4, SECTION 18, T25S, R27E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017

DRAWN BY: B.D.

DATE DRAWN: 05-06-15

REVISED: 00-00-00

ROAD DESCRIPTION

EXHIBIT J

1. Geological Formations

TVD of target 7,270

Pilot Hole TD N/A

MD at TD 12,000

Deepest expected fresh water

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone	Hazards
QUATERNARY FILL		N/A	
RUSTLER		N/A	
SALADO (TOP SALT)	1125	N/A	H2S POSSIBLE
CASTILLE (BASE SALT)	1716	N/A	
BELL CANYON (DELAWARE GROUP)	1916	N/A	H2S POSSIBLE
CHERRY CANYON	2895	N/A	H2S POSSIBLE
BRUSHY CANYON	3930	N/A	
BRUSHY CANYON LOWER	4598	N/A	
BONESPRING	5400	N/A	
1ST BONE SPRING SS	6380	N/A	
2ND BONE SPRING SS	6380	N/A	
2ND BONE SPRING LS	6880	N/A	
2ND BS HORZ TARGET	7270	N/A	
3RD BONE SPRING LIMESTONE	7295	N/A	

2. Casing Program

Hole Size	Casing Depth From	Casing Depth To	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	471	13-3/8"	48.00	H-40/J-55 Hybrid	ST&C	3.43	8.03	14.24
12 1/4	0	1894	9-5/8"	36.00	J-55	LT&C	2.01	3.50	6.64
8 3/4	0	6757	5-1/2"	17.00	L-80	LT&C	1.95	2.39	2.73
8 3/4	6757	12000 12069	5-1/2"	17.00	L-80	BT&C	1.81	2.23	45.52
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	N
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	N
Is well within the designated 4 string boundary.	N
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	N
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	N
Is 2nd string set 100' to 600' below the base of salt?	N
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	N

3. Cementing Program

Casing	# Sks	Wt. lb/gal	Yld ft ³ /sack	H ₂ O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surface	104	13.50	1.72	9.15	15.5	Lead: Class C + Bentonite
	195	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Intermediate	356	12.90	1.88	9.65	12	Lead: 35:65 (Poz:C) + Salt + Bentonite
	111	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Production	677	10.80	2.35	9.60	17:43	Lead: Tuned Light I Class H
	1121	14.20	1.30	5.86	14:30	Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS

Casing String	TOC	% Excess
Surface	0	34
Intermediate	0	44
Production	1694	17

See
COTA

4. Pressure Control Equipment

A variance is requested for the use of a diverter on the surface casing. See attached for schematic.					
BOP installed and tested before drilling which hole?	Size	Min Required WP	Type		Tested To
12 1/4	13 5/8	2M	Annular	X	50% of working pressure
			Blind Ram	X	2M
			Pipe Ram		
			Double Ram	X	
			Other		
8 3/4	13 5/8	3M	Annular	X	50% of working pressure
			Blind Ram	X	
			Pipe Ram		3M
			Double Ram	X	
			Other		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.	
X	A variance is requested for the use of a <u>flexible choke line</u> from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.	
N	Are anchors required by manufacturer?	

See
COA

5. Mud Program

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0' to 471'	FW Spud Mud	8.30 - 8.80	28	N/C
471' to 1894'	Brine Water	9.70 - 10.20	30-32	N/C
1894' to 12000'	FW/Cut Brine	8.70 - 9.20	30-32	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing	
<input checked="" type="checkbox"/>	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
<input type="checkbox"/>	No logs are planned based on well control or offset log information.
<input type="checkbox"/>	Drill stem test?
<input type="checkbox"/>	Coring?

Additional Logs Planned	Interval
-------------------------	----------

7. Drilling Conditions

Condition	
BH Pressure at deepest TVD	3477 psi
Abnormal Temperature	No

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.


<input checked="" type="checkbox"/>	H ₂ S is present
<input checked="" type="checkbox"/>	H ₂ S plan is attached

8. Other Facets of Operation

Borehole:	Well:	Field:	Structure:
Original Borehole	Gadwall 18 Federal 5H	NM Eddy County (NAD 83)	TBD

Gravity & Magnetic Parameters	Surface Location	Miscellaneous
Model: HDGM 2014 Dip: 59.918° Date: 28-May-2015	NAD83 New Mexico State Plane, Eastern Zone, US Feet	Slot: Gadwall 18 TVD Ref: GL(3194.7ft above MSL)
MagDec: 7.654° FS: 48208.605nT Gravity FS: 958.447mgm (9.80665 Based)	Lat: N 32 8 11.49 Northing: 413419.231US Grid Conv: 0.0552°	Plan: Cimarex Gadwall 18 Federal 5H Rev0 OPB 28-May-15
	Lon: W 104 13 48.48 Easting: 573453.01ftUS Scale Fact: 0.99991027	

EW (ft) Scale = 1:1500ft



Critical Points								
Critical Point	MD	INCL	AZIM	TVD	VSEC	N(+)/S(-)	E(+)/W(-)	DLS
SHL Cimarex Gadwall 18 Federal 5H [2494' FWL, 330' FNL]	0.00	0.00	270.00	0.00	0.00	0.00	0.00	
KOP Build to 12 1/4 inch DLS	6809.04	0.00	270.00	6609.04	0.00	0.00	0.00	0.00
Build to 12 1/4 inch DLS	7082.37	56.80	270.00	7009.57	27.08	0.00	-216.02	12.00
Landing point	7832.35	90.00	180.00	7270.00	553.16	-477.44	-615.58	12.00
Cimarex Gadwall 18 Federal 5H - PBHL [1980' FWL, 330' FNL]	12068.35	80.00	180.00	7270.00	4753.50	-4713.44	-615.79	0.00

CONTROLLED	
Plan ref	Cimarex Gadwall 18 Federal 5H Rev0 OPB 28-May-15
Drawing ref	
Copy number	of 3
Date	28-May-2015

1	Client	
2	Client	
3	Office	
4	Office	

Copy number for

Cimarex Gadwall 18 Federal 5H Rev0 OPB 28-May-15 Proposal Geodetic

Report

(Non-Def Plan)

Report Date: May 28, 2015 - 05:33 PM
Client: Cimarex
Field: NM Eddy County (NAD 83)
Structure / Slot: Cimarex Gadwall 18 Federal 5H / Cimarex Gadwall 18 Federal 5H
Well: Gadwall 18 Federal 5H
Borehole: Original Borehole
UWI / API#: Unknown / Unknown
Survey Name: Cimarex Gadwall 18 Federal 5H Rev0 OPB 28-May-15
Survey Date: May 28, 2015
Tort / AHD / DDI / ERD Ratio: 146.797' / 5142.151 ft / 6.098' / 0.707
Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
Location Lat / Long: N 32° 8' 11.49257", W 104° 13' 46.47689"
Location Grid N/E Y/X: N 413419.230 ftUS, E 573453.010 ftUS
CRS Grid Convergence Angle: 0.0552°
Grid Scale Factor: 0.99991027
Version / Patch: 2.8.572.0

Survey / DLS Computation:
Vertical Section Azimuth: Minimum Curvature / Lubinski
Vertical Section Origin: 187.443° (Grid North)
TVD Reference Datum: 0.000 ft, 0.000 ft
Seabed / Ground Elevation: GL
Magnetic Declination: 3194.700 ft above MSL
Total Gravity Field Strength: 3194.700 ft above MSL
Gravity Model: 7.654°
Total Magnetic Field Strength: 998.446mgm (9.80665 Based)
Magnetic Dip Angle: GARM
Declination Date: 48208.605 nT
Magnetic Declination Model: 59.918°
North Reference: May 28, 2015
Grid Convergence Used: HDGM 2014
Total Corr Mag North->Grid North: Grid North
Local Coord Referenced To: 0.0552°
Structure Reference Point: 7.5984°

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
SHL Cimarex Gadwall 18 Federal 5H [2494' FWL, 330' FNL]	0.00	0.00	270.00	0.00	0.00	0.00	0.00	N/A	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
KOP Build to 12"/100' DLS Build to 12"/100' DLS	6609.04	0.00	270.00	6609.04	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
Landing point	7082.37	56.80	270.00	7008.57	27.98	0.00	-216.02	12.00	413419.23	573237.01	N 32 8 11.49	W 104 13 48.99
Cimarex Gadwall 18 Federal 5H - PBHL [11980' FWL, 330' FNL]	7832.35	90.00	180.00	7270.00	553.16	-477.44	-615.56	12.00	412941.83	572837.51	N 32 8 6.77	W 104 13 53.64
	12068.35	90.00	180.00	7270.00	4753.50	-4713.44	-615.79	0.00	408706.22	572837.28	N 32 7 24.86	W 104 13 53.69

Survey Type: Non-Def Plan

Survey Error Model: ISCWSA Rev 0 *** 3-D 95.000% Confidence 2.79555 sigma
Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size Casing Diameter (in)	Survey Tool Type	Borehole / Survey
-------------	------	-----------------	---------------	------------------	-----------------------------------	------------------	-------------------

Cimarex Gadwall 18 Federal 5H Rev0 OPB 28-May-15 Proposal Geodetic

Report

(Non-Def Plan)

Report Date: May 28, 2015 - 05:32 PM
Client: Cimarex
Field: NM Eddy County (NAD 83)
Structure / Slot: Cimarex Gadwall 18 Federal 5H / Cimarex Gadwall 18 Federal 5H
Well: Gadwall 18 Federal 5H
Borehole: Original Borehole
UWI / API#: Unknown / Unknown
Survey Name: Cimarex Gadwall 18 Federal 5H Rev0 OPB 28-May-15
Survey Date: May 28, 2015
Tort / AHD / DDI / ERD Ratio: 146.797' / 5142.151 ft / 6.098 / 0.707
Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
Location Lat / Long: N 32° 8' 11.49257", W 104° 13' 46.47689"
Location Grid N/E Y/X: N 413419.230 ftUS, E 573453.010 ftUS
CRS Grid Convergence Angle: 0.0552°
Grid Scale Factor: 0.99991027
Version / Patch: 2.8.572.0

Survey / DLS Computation:
Vertical Section Azimuth: Minimum Curvature / Lubinski
Vertical Section Origin: 187.443° (Grid North)
TVD Reference Datum: 0.000 ft, 0.000 ft
GL
TVD Reference Elevation: 3194.700 ft above MSL
Seabed / Ground Elevation: 3194.700 ft above MSL
Magnetic Declination: 7.854°
Total Gravity Field Strength: 998.446mgm (9.80665 Based)
Gravity Model: GARM
Total Magnetic Field Strength: 48208.605 nT
Magnetic Dip Angle: 59.918°
Declination Date: May 28, 2015
Magnetic Declination Model: HDGM 2014
North Reference: Grid North
Grid Convergence Used: 0.0552°
Total Corr Mag North->Grid
North: 7.5984°
Local Coord Referenced To: Structure Reference Point

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' '')	Longitude (E/W ° ' '')
SHL Cimarex Gadwall 18 Federal 5H [2494' FWL, 330' FNL]	0.00	0.00	270.00	0.00	0.00	0.00	0.00	N/A	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	100.00	0.00	270.00	100.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	200.00	0.00	270.00	200.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	300.00	0.00	270.00	300.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	400.00	0.00	270.00	400.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	500.00	0.00	270.00	500.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	600.00	0.00	270.00	600.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	700.00	0.00	270.00	700.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	800.00	0.00	270.00	800.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	900.00	0.00	270.00	900.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	1000.00	0.00	270.00	1000.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	1100.00	0.00	270.00	1100.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	1200.00	0.00	270.00	1200.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	1300.00	0.00	270.00	1300.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	1400.00	0.00	270.00	1400.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	1500.00	0.00	270.00	1500.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	1600.00	0.00	270.00	1600.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	1700.00	0.00	270.00	1700.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	1800.00	0.00	270.00	1800.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	1900.00	0.00	270.00	1900.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Eastings (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	2000.00	0.00	270.00	2000.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	2100.00	0.00	270.00	2100.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	2200.00	0.00	270.00	2200.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	2300.00	0.00	270.00	2300.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	2400.00	0.00	270.00	2400.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	2500.00	0.00	270.00	2500.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	2600.00	0.00	270.00	2600.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	2700.00	0.00	270.00	2700.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	2800.00	0.00	270.00	2800.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	2900.00	0.00	270.00	2900.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	3000.00	0.00	270.00	3000.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	3100.00	0.00	270.00	3100.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	3200.00	0.00	270.00	3200.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	3300.00	0.00	270.00	3300.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	3400.00	0.00	270.00	3400.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	3500.00	0.00	270.00	3500.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	3600.00	0.00	270.00	3600.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	3700.00	0.00	270.00	3700.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	3800.00	0.00	270.00	3800.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	3900.00	0.00	270.00	3900.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	4000.00	0.00	270.00	4000.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	4100.00	0.00	270.00	4100.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	4200.00	0.00	270.00	4200.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	4300.00	0.00	270.00	4300.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	4400.00	0.00	270.00	4400.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	4500.00	0.00	270.00	4500.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	4600.00	0.00	270.00	4600.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	4700.00	0.00	270.00	4700.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	4800.00	0.00	270.00	4800.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	4900.00	0.00	270.00	4900.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	5000.00	0.00	270.00	5000.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	5100.00	0.00	270.00	5100.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	5200.00	0.00	270.00	5200.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	5300.00	0.00	270.00	5300.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	5400.00	0.00	270.00	5400.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	5500.00	0.00	270.00	5500.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	5600.00	0.00	270.00	5600.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	5700.00	0.00	270.00	5700.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	5800.00	0.00	270.00	5800.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	5900.00	0.00	270.00	5900.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	6000.00	0.00	270.00	6000.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	6100.00	0.00	270.00	6100.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	6200.00	0.00	270.00	6200.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	6300.00	0.00	270.00	6300.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	6400.00	0.00	270.00	6400.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	6500.00	0.00	270.00	6500.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48
	6600.00	0.00	270.00	6600.00	0.00	0.00	0.00	0.00	413419.23	573453.01	N 32 8 11.49	W 104 13 46.48

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S °.′.″)	Longitude (E/W °.′.″)
	11000.00	90.00	180.00	7270.00	3594.14	-3645.09	-615.73	0.00	409774.47	572837.34	N 32 7 35.43	W 104 13 53.68
	11100.00	90.00	180.00	7270.00	3793.30	-3745.09	-615.73	0.00	409874.48	572837.33	N 32 7 34.44	W 104 13 53.69
	11200.00	90.00	180.00	7270.00	3892.46	-3845.09	-615.74	0.00	409974.49	572837.33	N 32 7 33.45	W 104 13 53.68
	11300.00	90.00	180.00	7270.00	3991.61	-3945.09	-615.74	0.00	409474.50	572837.32	N 32 7 32.46	W 104 13 53.68
	11400.00	90.00	180.00	7270.00	4090.77	-4045.09	-615.75	0.00	409374.51	572837.32	N 32 7 31.47	W 104 13 53.68
	11500.00	90.00	180.00	7270.00	4189.93	-4145.09	-615.75	0.00	409274.52	572837.31	N 32 7 30.48	W 104 13 53.68
	11600.00	90.00	180.00	7270.00	4289.09	-4245.09	-615.76	0.00	409174.53	572837.31	N 32 7 29.49	W 104 13 53.68
	11700.00	90.00	180.00	7270.00	4388.25	-4345.09	-615.77	0.00	409074.54	572837.30	N 32 7 28.50	W 104 13 53.69
	11800.00	90.00	180.00	7270.00	4487.41	-4445.09	-615.77	0.00	408974.55	572837.30	N 32 7 27.51	W 104 13 53.69
	11900.00	90.00	180.00	7270.00	4586.56	-4545.09	-615.78	0.00	408874.56	572837.29	N 32 7 26.52	W 104 13 53.69
	12000.00	90.00	180.00	7270.00	4685.72	-4645.09	-615.78	0.00	408774.56	572837.28	N 32 7 25.53	W 104 13 53.69
Cimarex Gadwall 18	12068.35	90.00	180.00	7270.00	4753.50	-4713.44	-615.79	0.00	408706.22	572837.28	N 32 7 24.86	W 104 13 53.69

Survey Type: Non-Def Plan

Survey Error Model: ISCWSA Rev 0 *** 3-D 95.000% Confidence 2.7955 sigma

Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size Casing Diameter (in)	Survey Tool Type	Borehole / Survey
	1	0.000	12068.351	1/100.000	30.000	SLB_MWD-STD	Original Borehole / Cimarex Gadwall 18 Federal 5H Rev0 OPB

Drilling 12-1/4" hole
below 13 3/8" Casing




Exhibit E-1 – 2000# BOP
Gadwall 18 Federal Com #5H
Cimarex Energy Co.
18-25S-27E
SHL 266 FNL & 2594 FWL
BHL 330 FSL & 1980 FWL
Eddy County, NM

Drilling 8-3/4" hole
below 9 -5/8"
Casing

Fill Line

Flowline

3000#
(3M) BOP

Annular Preventer

SRR & A

Pipe Rams

Blind Rams

2" Minimum Kill Line

Kill Line

2 Valves Minimum
(including 1 check valve)

3" minimum choke line

Choke Line

Drilling
Spool


2 Valves Minimum

Wellhead
Assembly

13-5/8" 3000 psi x 11" 5000 psi
Wellhead Assembly

13-5/8" 3000# psi x 13-3/8" SOW Casing Head

Exhibit E-1 – 3000# BOP
Gadwall 18 Federal Com #5H
Cimarex Energy Co.
18-25S-27E
SHL 266 FNL & 2594 FWL
BHL 330 FSL & 1980 FWL
Eddy County, NM



Choke Line:
 2M System: 2" Minimum
 3M System: 3" Minimum
 OPTIONAL: 4" Flex Hose may be used
 if approved in APD

2M: 1 Valve Minimum
 3M: 2 Valves Minimum
 HCR Valve is optional

REMOTELY
 OPERATED
 Adjustable
 Choke

Choke
 Isolation
 Valve

Exhibit E-1 – Choke Manifold Diagram
Gadwall 18 Federal Com #5H
 Cimarex Energy Co.
 18-25S-27E

SHL 266 FNL & 2594 FWL
 BHL 330 FSL & 1980 FWL
 Eddy County, NM

Drilling Operations **Choke Manifold** **2M/3M Service**

Exhibit F-1 – Co-Flex Hose Hydrostatic Test

Gadwall 18 Federal Com #5H

Cimarex Energy Co.

18-25S-27E

SHL 266 FNL & 2594 FWL

BHL 330 FSL & 1980 FWL

Eddy County, NM



Midwest Hose & Specialty, Inc.

INTERNAL HYDROSTATIC TEST REPORT		
Customer: Oderco Inc		P.O. Number: odyd-271
HOSE SPECIFICATIONS		
Type: Stainless Steel Armor Choke & Kill Hose		Hose Length: 45'ft.
I.D. 4 INCHES	O.D. 9 INCHES	
WORKING PRESSURE 10,000 PSI	TEST PRESSURE 15,000 PSI	BURST PRESSURE 0 PSI
COUPLINGS		
Stem Part No. OKC OKC		Ferrule No. OKC OKC
Type of Coupling: Swage-It		
PROCEDURE		
<u>Hose assembly pressure tested with water at ambient temperature.</u>		
TIME HELD AT TEST PRESSURE 15 MIN.		ACTUAL BURST PRESSURE: 0 PSI
Hose Assembly Serial Number: 79793		Hose Serial Number: OKC
Comments:		
Date: 3/8/2011	Tested: <i>A. Jimenez</i>	Approved: <i>[Signature]</i>

March 3, 2011

Internal Hydrostatic Test Graph


Customer: Houston

Pick Ticket #: 94260



Midwest Hose
& Specialty, Inc.

Hose Specifications		Verification	
Hose Type	Length	Time of Filling	Coupling Method
C&K	45'	4 1/16 10K	Swage
I.D.	O.D.	Die Size	Final O.D.
4"	6.05"	6.38"	6.75"
Working Pressure	Burst Pressure	Hose Serial #	Hose Assembly Serial #
10000 PSI	See attached Safety Data Sheet	5544	79793



Test Pressure	Time Held at Test Pressure	Actual Burst Pressure	Peak Pressure
15000 PSI	11 Minutes		15483 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Zac McConnell

Approved By: Kim Thomas

[Signature]

[Signature]

Exhibit F-2 - Co-Flex Hose
Gadwall 18 Federal Com #5H
Cimarex Energy Co.
18-25S-27E
SHL 266 FNL & 2594 FWL
BHL 330 FSL & 1980 FWL
Eddy County, NM



Midwest Hose & Specialty, Inc.

Certificate of Conformity

Customer:		PO
DEM		ODYD-271
SPECIFICATIONS		
Sales Order	Dated:	
79793	3/8/2011	
<p>We hereby certify that the material supplied for the referenced purchase order to be true according to the requirements of the purchase order and current industry standards</p> <p>Supplier: Midwest Hose & Specialty, Inc. 10640 Tanner Road Houston, Texas 77041</p>		
Comments:		
Approved:		Date:
<i>James Garcia</i>		3/8/2011



Midwest Hose
& Specialty, Inc.


Exhibit F-3- Co-Flex Hose
Gadwall 18 Federal Com #5H
Cimarex Energy Co.
18-25S-27E
SHL 266 FNL & 2594 FWL
BHL 330 FSL & 1980 FWL
Eddy County, NM


Specification Sheet Choke & Kill Hose

The Midwest Hose & Specialty Choke & Kill hose is manufactured with only premium components. The reinforcement cables, inner liner and cover are made of the highest quality material to handle the tough drilling applications of today's industry. The end connections are available with API flanges, API male threads, hubs, hammer unions or other special fittings upon request. Hose assembly is manufactured to API 7K. This assembly is wrapped with fire resistant vermiculite coated fiberglass insulation, rated at 2000 degrees with stainless steel armor cover.

Working Pressure:	5,000 or 10,000 psi working pressure
Test Pressure:	10,000 or 15,000 psi test pressure
Reinforcement:	Multiple steel cables
Cover:	Stainless Steel Armor
Inner Tube:	Petroleum resistant, Abrasion resistant
End Fitting:	API flanges, API male threads, threaded or butt weld hammer unions, unbolt and other special connections
Maximum Length:	110 Feet
ID:	2-1/2", 3", 3-1/2", 4"
Operating Temperature:	-22 deg F to +180 deg F (-30 deg C to +82 deg C)

Exhibit F – Co-Flex Hose
Gadwall 18 Federal Com #5H
Cimarex Energy Co.
18-25S-27E
SHL 266 FNL & 2594 FWL
BHL 330 FSL & 1980 FWL
Eddy County, NM





NOTES:

- Flare pit is to be located a min. of 160' from the wellhead.
- Contours shown at 2' intervals.


CIMAREX ENERGY CO.

GADWALL 18 FEDERAL 5H
266' FNL 2594' FWL
NE 1/4 NW 1/4, SECTION 18, T25S, R27E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



UELS, LLC
 Corporate Office * 85 South 200 East
 Vernal, UT 84078 * (435) 789-1017

DRAWN BY: T.E.	DATE DRAWN: 05-01-15
SCALE: 1" = 80'	REVISED: 00-00-00
TYPICAL RIG LAYOUT	EXHIBIT D.






-  Wind Direction Indicators
(wind sock or streamers)
-  • H2S Monitors
(alarms at bell nipple and shale shaker)
-  Briefing Areas



Exhibit D-1 – Rig Diagram
 Gadwall 18 Federal Com #5H
 Cimarex Energy Co.
 18-25S-27E
 SHL 266 FNL & 2594 FWL
 BHL 330 FSL & 1980 FWL
 Eddy County, NM

Hydrogen Sulfide Drilling Operations Plan
Gadwall 18 Federal Com 5H
Cimarex Energy Co.
UL: D, Sec.18, 25S, 27E
Eddy Co., NM

- 1 All Company and Contract personnel admitted on location must be trained by a qualified H₂S safety instructor to the following:
 - A. Characteristics of H₂S
 - B. Physical effects and hazards
 - C. Principal and operation of H₂S detectors, warning system and briefing areas.
 - D. Evacuation procedure, routes and first aid.
 - E. Proper use of safety equipment & life support systems
 - F. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30 minute pressure demand air packs.
- 2 H₂S Detection and Alarm Systems:
 - A. H₂S sensors/detectors to be located on the drilling rig floor, in the base of the sub structure/cellar area, on the mud pits in the shale shaker area. Additional H₂S detectors may be placed as deemed necessary.
 - B. An audio alarm system will be installed on the derrick floor and in the top doghouse.
- 3 Windsock and/or wind streamers:
 - A. Windsock at mudpit area should be high enough to be visible.
 - B. Windsock on the rig floor and / or top doghouse should be high enough to be visible.
- 4 Condition Flags and Signs
 - A. Warning sign on access road to location.
 - B. Flags to be displayed on sign at entrance to location. Green flag indicates normal safe condition. Yellow flag indicates potential pressure and danger. Red flag indicates danger (H₂S present in dangerous concentration). Only H₂S trained and certified personnel admitted to location.
- 5 Well control equipment:
 - A. See exhibit "E-1"
- 6 Communication:
 - A. While working under masks chalkboards will be used for communication.
 - B. Hand signals will be used where chalk board is inappropriate.
 - C. Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.
- 7 Drillstem Testing:

No DSTs or cores are planned at this time.
- 8 Drilling contractor supervisor will be required to be familiar with the effects H₂S has on tubular goods and other mechanical equipment.
- 9 If H₂S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H₂S scavengers if necessary.

H₂S Contingency Plan
Gadwall 18 Federal Com 5H
Cimarex Energy Co.
UL: D, Sec.18, 25S, 27E
Eddy Co., NM

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must:

- « Isolate the area and prevent entry by other persons into the 100 ppm ROE.
 - « Evacuate any public places encompassed by the 100 ppm ROE.
 - « Be equipped with H₂S monitors and air packs in order to control the release.
 - « Use the "buddy system" to ensure no injuries occur during the response.
 - « Take precautions to avoid personal injury during this operation.
 - « Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
-
- « Have received training in the:
 - Detection of H₂S, and
 - Measures for protection against the gas,
 - Equipment used for protection and emergency response.

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

Characteristics of H₂S and SO₂

Please see attached International Chemical Safety Cards.

Contacting Authorities

Cimarex Energy Co. of Colorado's personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. Cimarex Energy Co. of Colorado's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

H₂S Contingency Plan Emergency Contacts
Gadwall 18 Federal Com 5H
 Cimarex Energy Co.
 UL: D, Sec.18, 25S, 27E
 Eddy Co., NM

Company Office			
Cimarex Energy Co. of Colorado		800-969-4789	
Co. Office and After-Hours Menu			
Key Personnel			
Name	Title	Office	Mobile
Larry Seigrist	Drilling Manager	432-620-1934	580-243-8485
Doug McQuitty	Drilling Superintendent	432-620-1933	806-640-2605
Scott Lucas	Drilling Superintendent	432-620-1989	432-894-5572
Roy Shirley	Construction Superintendent		432-634-2136
Artesia			
Ambulance		911	
State Police		575-746-2703	
City Police		575-746-2703	
Sheriff's Office		575-746-9888	
Fire Department		575-746-2701	
Local Emergency Planning Committee		575-746-2122	
New Mexico Oil Conservation Division		575-748-1283	
Carlsbad			
Ambulance		911	
State Police		575-885-3137	
City Police		575-885-2111	
Sheriff's Office		575-887-7551	
Fire Department		575-887-3798	
Local Emergency Planning Committee		575-887-6544	
US Bureau of Land Management		575-887-6544	
Santa Fe			
New Mexico Emergency Response Commission (Santa Fe)		505-476-9600	
New Mexico Emergency Response Commission (Santa Fe) 24 Hrs		505-827-9126	
New Mexico State Emergency Operations Center		505-476-9635	
National			
National Emergency Response Center (Washington, D.C.)		800-424-8802	
Medical			
Flight for Life - 4000 24th St.; Lubbock, TX		806-743-9911	
Aerocare - R3, Box 49F; Lubbock, TX		806-747-8923	
Med Flight Air Amb - 2301 Yale Blvd S.E., #D3; Albuquerque, NM		505-842-4433	
SB Air Med Service - 2505 Clark Carr Loop S.E.; Albuquerque, NM		505-842-4949	
Other			
Boots & Coots IWC		800-256-9688	or 281-931-8884
Cudd Pressure Control		432-699-0139	or 432-563-3356
Halliburton		575-746-2757	
B.J. Services		575-746-3569	





Exhibit D-1
Interim Reclamation Diagram
Gadwall 18 Federal Com #5H
Cimarex Energy Co.
18-255-27E
SHL 266 FNL & 2594 FWL
BHL 330 FSL & 1980 FWL
Eddy County, NM

Gadwall 18 Federal Com 5H

Cimarex Energy Co.
UL: C, Sec. 18, 25S, 27E
Eddy Co., NM

The following surface use plan of operations will be followed and carried out once the APD is approved. No other disturbance will be created other than what is submitted in this surface use plan without approval. If any other disturbance is needed after the APD is approved, a BLM approved sundry notice or right of way application will be submitted for approval prior to any new surface disturbance.

1. Existing Roads:

- Please see Exhibit B and C-1 for existing access road planned to be used to access the proposed project.
- Cimarex Energy will improve or maintain existing roads in a condition the same as or better than before the operations began. Cimarex Energy will repair pot holes, etc. All existing structures on the entire access route such as cattleguards, other range improvement projects, culverts, etc. will be properly repaired or replaced if they are damaged or have deteriorated beyond practical use.
- Cimarex Energy will prevent and abate fugitive dust as needed, whether created by vehicular traffic, equipment operations, or other events.
- Cimarex Energy will obtain written BLM approval prior to the application of surfactants, binding agents, or other dust suppression chemicals on the roadways.
- The maximum width of the driving surface will be 14'. The road will be crowned and ditched with a 2% slope from the tip of the crown to the edge of the driving surface. The ditches will be 1' deep with 3:1 slopes. The driving surface will be made of 6" rolled and compacted caliche.
- Existing access road route to the proposed project is depicted on the public access point map if applicable. Improvements to the driving surface will be done where necessary. No new surface disturbance will be done, unless otherwise noted in the New or Reconstructed Access Roads section of the surface use plan.
Beginning at the intersection of Black River road/ Old Cavern highway proceed in a south direction approx 6.4 miles to the junction of this road and an existing road to the southeast; turn left and proceed in a southeasterly direction approx 0.3 miles to the existing Da Vinci 7 Fed Com 4H and Gadwall 18 Fed Com #2 pad and the proposed location.

2. New or Reconstructed Access Roads:

- No new access road planned.

3. Well Radius Map

Please see Exhibit A for wells within one mile of the proposed well SHL and BHL.

4. Proposed or Existing Production Facilities:

- If on completion this well is a producer, a tank battery will be used and the necessary production equipment will be installed and production will be sent to the Gadwall 18 Federal Com 2H.
- Allocation will be based on well test. Route is on lease, please see Exhibit G-1. Any changes to on lease route will be submitted via sundry notice. If route is off lease, a right of way will be submitted to the BLM for approval.

5. Gas Pipeline

- Cimarex plans to construct an on lease gas pipeline to service this battery location.
- No pipeline proposed.

6. Flowlines

- Cimarex Energy plans to construct on lease flowlines to service the well.
- Specifications of Polyline: 1 HP polyline for oil, gas, and water production. 1 HP polyline for gas lift.
- Both lines will be buried 10'-20' North of the access road.
- Length of Gas Lift Line: 1368.18'
- Length of Flowlines: 436.24'
- MAOP: 1500 psi.
- Anticipated working pressure: 200-300 psi.

7. Salt Water Disposal

- No pipeline proposed.

Gadwall 18 Federal Com 5H

Cimarex Energy Co.

UL: C, Sec. 18, 25S, 27E

Eddy Co., NM

8. Electric Lines

- Cimarex Energy plans to construct a new on lease electric line to service the well.
- Cimarex Energy plans to install an on lease overhead electric line from the proposed well to an existing overhead electric line at the Gadwall 18 Federal Com 2H. The proposed electric line will be 403.96' in length. 1-40' poles, 480 volt, 4 wire, 3 phase. The electric line will exit off the SW side of the well location and travel SW for 403.96' along the access road until it would intercept the existing electric line. The electric line will be routed on the south side of the access road and 25-35' from and parallel to the access road. Please see Exhibit H for proposed route information.

9. Water

Cimarex Energy plans to purchase fresh water from a 3rd party company. A local commercial source will truck water utilizing the access road. Please see Exhibit C-1 for access road route.

10. Construction Material

If possible, native caliche will be obtained from the excavation of drill site. The primary way of obtaining caliche will be by "turning over" the location. This means caliche will be obtained from the actual well site. A caliche permit will be obtained from BLM prior to pushing up any caliche. 2400 cu yds is the max amount of caliche needed for pad and roads. Amount will vary for each pad. The procedure below has been approved by BLM personnel:

- The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.
- An approximate 120' x 120' area is used within the proposed well site to remove caliche.
- Subsoil is removed and piled alongside the 120' by 120' area within the pad site.
- When caliche is found, material will be stockpiled within the pad site to build the location and road.
- Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
- Once well is drilled, the stockpiled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced. Neither caliche nor subsoil will be stockpiled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in Exhibit D – Rig Layout Diagram.

In the event that no caliche is found onsite, caliche will be hauled in from BLM-approved caliche pit.

11. Methods of Handling Waste

- Drilling fluids, produced oil, and water from the well during drilling and completion operations will be stored safely and disposed of properly in a NMOCD approved disposal facility.
- Garbage and trash produced during drilling and completion operations will be collected in a trash container and disposed of properly at a state approved disposal facility. All trash on and around well site will be collected for disposal.
- Human waste and grey water will be properly contained and disposed of properly at a state approved disposal site.
- After drilling and completion operations, trash, chemicals, salts, frac sand and other waste will be removed and disposed of properly at a state approved disposal site.
- The well will be drilled utilizing a closed loop system. Drill cuttings will be properly disposed of into steel tanks and taken to an NMOCD approved disposal facility.

12. Ancillary Facilities:

No camps or airstrips to be constructed.

13. Well Site Layout:

- Exhibit D: Rig Layout
- Exhibit D-2: Well Site layout plat
- Mud pits in the closed circulation system will be steel pits and the cuttings will be stored in steel containment pits.
- Cuttings will be stored in steel pits until they are hauled to a state-approved disposal facility.
- If the well is a producer, those areas of the location not essential to production facilities will be reclaimed and seeded per BLM requirements. Exhibit D-1: Interim Reclamation Diagram.

14. Interim and Final Reclamation

- Rehabilitation of the location will start in a timely manner after all drilling operations cease. The type of reclamation will depend on whether the well is a producer or a dry hole.
- In areas planned for interim and final reclamation, surfacing materials will be removed and returned to a mineral pit or recycled to repair or build roads and well pads.
- Drainage systems, if any, will be reshaped to the original configuration with provisions made to alleviate erosion. These may need to be modified in certain circumstances to prevent inundation of the location's pad and surface facilities. After the area has been shaped and contoured, topsoil from the spoil pile will be placed over the disturbed area to the extent possible. Revegetation procedures will comply with BLM standards.
- If the well is a dry hole, the pad and road area will be recountoured to match the existing terrain. Topsoil will be spread to the extent possible. Revegetation will comply with BLM standards.
- Should the well be a producer, those areas of the location not essential to production facilities and operations will be reclaimed and seeded per BLM requirements. Exhibit D-1 illustrates the proposed Interim Reclamation.

15. Surface Ownership:

- The wellsite is on surface owned by Bureau of Land Management, 620 E. Greene St. Carlsbad NM 88220, 575-234-5972.
- A copy of Surface Use Agreement has been given to the surface owner.
- The land is used mainly for farming, cattle ranching, recreational use, and oil and gas production.

16. Other Information:

- Topography consists of a sloping plane with loose tan sands. Vegetation is mainly yucca, mesquite and shin oak.
- Archeological survey will be conducted for the well pad/location and proposed road and the arch report will be filed with the BLM.
- There are no known dwellings within 1½ miles of this location.

17. On Site Notes and Information:

Onsite with Barry Hunt on 4/21/14 V-Door Southeast. Top soil southeast. Frac pad Northeast corner northwest (DaVinci pad). Interim reclaim: Southeast, southwest, northeast. E-line staked from #1 well line to northeast corner of 5H. Short gas lift/production line staked from northwest corner to #1 battery. No access required will utilize #1 access.

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Cimarex Energy Co
LEASE NO.:	NM111530
WELL NAME & NO.:	5H-Gadwall 18 Federal Com
SURFACE HOLE FOOTAGE:	266'/N & 2594'/W
BOTTOM HOLE FOOTAGE:	330'/S & 1980'/W
LOCATION:	Section 18, T. 25 S., R. 27 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Communitization Agreement
 - Lesser Prairie-Chicken Timing Stipulations
 - Ground-level Abandoned Well Marker
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
 - Cement Requirements
 - High Cave/Karst
 - Logging Requirements
 - Waste Material and Fluids
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattleguards

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. A Hydrogen Sulfide (H₂S) Drilling Plan shall be activated 500 feet prior to drilling into the **Delaware** formation. **As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Water Basin:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Possibility of water flows in the Salado and Castile.

Possibility of lost circulation in the Delaware.

HIGH CAVE/KARST

A MINIMUM OF TWO CASING STRINGS CEMENTED TO SURFACE IS REQUIRED IN HIGH CAVE/KARST AREAS. THE CEMENT MUST BE IN A SOLID SHEATH. THEREFORE, ONE INCH OPERATIONS ARE NOT SUFFICIENT TO PROTECT CAVE KARST RESOURCES. A CASING DESIGN THAT HAS A ONE INCH JOB PERFORMED DOES NOT COUNT AS A SOLID SHEATH. ON A THREE STRING DESIGN; IF THE PRIMARY CEMENT JOB ON THE SURFACE CASING DOES NOT CIRCULATE, THEN THE NEXT TWO CASING STRINGS MUST BE CEMENTED TO SURFACE.

1. The 13-3/8 inch surface casing shall be set at approximately 471 feet and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**

Excess calculates to 15% - Additional cement may be required.

- a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

- b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
- ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.**
3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
- ☒ Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification. **Excess calculates to 17% - Additional cement may be required.**
4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).

3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M) psi**.
 - a. **For surface casing only:** If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.
4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **9-5/8** intermediate casing shoe shall be **3000 (3M) psi**.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (18 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
 - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - d. The results of the test shall be reported to the appropriate BLM office.
 - e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**

- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

CRW 111015

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Enclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock enclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Enclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended enclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.