

HIGH CAVEKARST

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

JAN 11 2016


RECEIVED

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. SHL: Private, BHL: Unleased Sec 23 "UL C&F": NMNM012559	
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name	
2. Name of Operator COG Operating LLC.		7. If Unit or CA Agreement, Name and No.	
3a. Address 2208 West Main Street Artesia, NM 88210		8. Lease Name and Well No. Coachwhip Federal Com #1H	
3b. Phone No. (include area code) 575-748-6940		9. APL Well No. 30-015-43595	
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface 900' FSL & 2350' FWL Unit Letter N (SESW) Section 14 - T26S - R28E At proposed prod. Zone 330' FSL & 2210' FWL Unit Letter N (SESW) Section 23 - T26S - R28E		10. Field and Pool, or Exploratory Tecolote Peak ; Delaware	
14. Distance in miles and direction from nearest town or post office* Approximately 12 miles from Malaga		11. Sec.; T.R.M. or Blk and Survey or Area Section 14 - T26S - R28E	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. Unit line, if any) 330'		12. County or Parish Eddy County	
16. No. of acres in lease NMNM012559: 1400		13. State NM	
17. Spacing Unit dedicated to this well 160		18. Distance from location* to nearest well, drilling, completed, applied for, on this lease, ft. SHL: 4051' BHL: None	
19. Proposed Depth TVD: 6,233' MD: 11,931'		20. BLM/BIA Bond No. on file NMB000740 & NMB000215	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 2944.5' GL		22. Approximate date work will start* 12/1/2015	
23. Estimated duration 30 days			

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature 	Name (Printed/Typed) MAYTE REYES	Date 9-8-2015
---	--	-------------------------

Regulatory Analyst Approved by (Signature) Steve Caffey	Name (Printed/Typed) STEVE CAFFEY	Date JAN - 6 2016
Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

Carlsbad Controlled Water Basin

Approval Subject to General Requirements
& Special Stipulations Attached

SEE ATTACHED FOR
CONDITIONS OF APPROVAL

NM OIL CONSERVATION

ARTESIA DISTRICT

DISTRICT I
1625 N. FRENCH DR., HOBBBS, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720

DISTRICT II
811 S. FIRST ST., ARTESIA, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720

DISTRICT III
1000 RIO BRAZOS RD., AZTEC, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170

DISTRICT IV
1220 S. ST. FRANCIS DR., SANTA FE, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 SOUTH ST. FRANCIS DR.
Santa Fe, New Mexico 87505

RECEIVED

Form C-102
Revised August 1, 2011
Submit one copy to appropriate District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-015- 43595	Pool Code 59170	Pool Name Tecolote Peak; Delaware
Property Code 315786	Property Name COACHWHIP FED COM	Well Number 1H
OGRID No. 229137	Operator Name COG OPERATING, LLC	Elevation 2944.5

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
N	14	26-S	28-E		900	SOUTH	2350	WEST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
N	23	26-S	28-E		330	SOUTH	2210	WEST	EDDY
Dedicated Acres 160	Joint or Infill	Consolidation Code	Order No.						

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

<p>NAD 27 SURFACE LOCATION Y=377511.7 X=585106.8 LAT.=32.037597° N LONG.=104.058679° W</p> <p>NAD 27 PROPOSED BOTTOM HOLE LOCATION Y=371639.3 X=584922.3 LAT.=32.021455° N LONG.=104.059322° W</p> <p>Private</p> <p>PROJECT AREA PRODUCING AREA</p> <p>GRID AZ. 181°47'58" HORZ. DIST. 5875.3'</p> <p>NMNM012559</p> <p>Unleased</p> <p>SECTION 14 SECTION 23</p> <p>Y=376592.6 X=584076.9</p> <p>Y=376617.1 X=585405.3</p> <p>Y=371311.7 X=584034.3</p> <p>Y=371308.1 X=585358.7</p>	<p>OPERATOR CERTIFICATION</p> <p>I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p><i>Melanie J Wilson</i> 9/8/15 Signature Date Melanie J Wilson Printed Name mwilson@concho.com E-mail Address</p> <p>SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>OCTOBER 16, 2014 Date of Survey</p> <p>Signature & Seal of Professional Surveyor</p> <p><i>Chad L. Harcrow</i> 8/25/15 Certificate No. CHAD HARCROW 17777 W.O. # 14-875 DRAWN BY: AF</p>
--	--

Surface Use Plan
COG Operating LLC
Coachwhip Federal Com #1H
SL: 900' FSL & 2350' FWL UL N
Section 14, T26S, R28E
BHL: 330' FSL & 2210' FWL UL N
Section 23, T26S, R28E
Eddy County, New Mexico

OPERATOR CERTIFICATION

I hereby certify that I, or persons under my direct supervision, have inspected the drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or COG Operating LLC, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 8th day of September, 2015.

Signed: Melanie J. Wilson

Printed Name: Melanie J. Wilson


Position: Regulatory Coordinator

Address: 2208 W. Main Street, Artesia, NM 88210


Telephone: (575) 748-6940

Field Representative (if not above signatory): Rand French

E-mail: mwilson@concho.com




SECTION 14, TOWNSHIP 26 SOUTH, RANGE 28 EAST, N.M.P.M.,
EDDY COUNTY NEW MEXICO



DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF HWY 285 AND WHITEHORN RD. TURN LEFT (WEST) ONTO WHITEHORN ROAD (CR 725) AND GO APPROX. .2 MILES; THEN TURN RIGHT (SOUTH) AND GO APPROX. .3 MILES; THEN TURN RIGHT (SOUTHWEST) GO APPROX. .15; THEN TURN LEFT (SOUTH) AND GO APPROX. .2 MILES AND PROPOSED WELL IS APPROX. 300' LEFT (WEST).



HARCROW SURVEYING, LLC
2314 W. MAIN ST. ARTESIA, N.M. 88210
PH: (575) 746-2158 FAX: (575) 746-2158
c.harcrow@harcrowsurveying.com



COG OPERATING, LLC

COACHWHIP FED COM #1H WELL
LOCATED 900 FEET FROM THE SOUTH LINE
AND 2350 FEET FROM THE WEST LINE OF SECTION 14,
TOWNSHIP 26 SOUTH, RANGE 28 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO

SURVEY DATE: 10/16/2014


PAGE: 1 OF 1

DRAFTING DATE: 11/04/2014

APPROVED BY: CH

DRAWN BY: AF

FILE: 14-875



LEGEND

- WELL
- WELLPAD
- EXISTING ROAD
- PROPOSED ROAD

COACHWHIP FED COM #1H

SEC: 14 TWP: 26 S. RGE: 28 E. ELEVATION: 2944.5'

STATE: NEW MEXICO COUNTY: EDDY 900' FSL & 2350' FWL

W.O. # 14-875 LEASE: COACHWHIP FED COM SURVEY: N.M.P.M

0 2,500 FEET

0 0.1 0.2 0.4 Miles

1 IN = 1,500 FT

LOCATION MAP


TOPO ROAD

08/25/2015

A.F.

CONCHO
COG OPERATING, LLC

HARCROW SURVEYING, LLC.
2314 W. MAIN ST, ARTESIA, NM 88210
PH: (575) 746-2158 FAX: (575) 746-2158
c.harcrow@harcrowsurveying.com



T 26 S

R 28 E

R 29 E

07

18

19

LEGEND

WELL

WELLPAD

EXISTING ROAD

PROPOSED ROAD

COACHWHIP FED COM #1H

SEC: 14 TWP: 26 S. RGE: 28 E. ELEVATION: 2944.5'

STATE: NEW MEXICO COUNTY: EDDY 900' FSL & 2350' FWL

W.O. # 14-875 LEASE: COACHWHIP FED COM SURVEY: N.M.P.M

0 2,500 5,000 FEET

0 0.125 0.25 0.5 Miles 1 IN = 2,000 FT

LOCATION MAP


TOPO

03/25/2015

AP.

CONCHO
COG OPERATING, LLC

HARCROW SURVEYING, LLC.
2314 W. MAIN ST, ARTESIA, NM 88210
PH: (575) 746-2158 FAX: (575) 746-2158
c.harcrow@harcrowsurveying.com




T 26 S
R 28 E
R 29 E

LEGEND

- WELL
- WELLPAD
- EXISTING ROAD
- PROPOSED ROAD
- PRIVATE
- STATE OF NM
- US BLM

COACHWHIP FED COM #1H

SEC: 14 TWP: 26 S. RGE: 28 E. ELEVATION: 2944.5'
 STATE: NEW MEXICO COUNTY: EDDY 900' FSL & 2350' FWL
 W.O. # 14-875 LEASE: COACHWHIP FED COM SURVEY: N.M.P.M



LOCATION MAP LAND STATUS 03/25/2015 A.P.

CONCHO
 COG OPERATING, LLC

HARCROW SURVEYING, LLC.
 2314 W. MAIN ST. ARTESIA, NM 88210
 PH: (575) 746-2158 FAX: (575) 746-2158
 c.harcrow@harcrowsurveying.com

09

EXHIBIT 4

12

11

15 17 24 9

16 18

8 20

6

7

11

12

23

5

4

14

13

16

15

COACHWHIP
FED COM #1H

14

21

22

19

13

23

26S 28E

21

22

24

BHL: 330' FSL &
2210' FWL

0

1

10

26

25

28

27

DATA FOR "WELLS WITHIN 1 MI." IS TAKEN FROM THE NEW MEXICO EMNRD WEBSITE. THE DATA HAS BEEN UPDATED THROUGH JULY 12, 2015

LEGEND

- WELL
- BOTTOMHOLE
- WELLS WITHIN 1 MI.
- 1 MI. BUFFER

COACHWHIP FED COM #1H

SEC: 14 TWP: 26 S. RGE: 28 E. ELEVATION: 2944.5'

STATE: NEW MEXICO COUNTY: EDDY 900' FSL & 2350' FWL

W.O. # 14-875 LEASE: COACHWHIP FED COM SURVEY: N.M.P.M

0 2,500 5,000 FEET

0 0.125 0.25 0.5 Miles

1 IN = 2,000 FT

1 MILE MAP

08/25/2015

S.P.



 CONCHO

 COG OPERATING, LLC


 HARCROW SURVEYING, LLC.


 2314 W. MAIN ST, ARTESIA, NM 88210

 PH: (575) 746-2158 FAX: (575) 746-2158

 c.harcrow@harcrowsurveying.com

**COACHWHIP FED COM #1H ROAD
COG OPERATING, LLC.**

SURVEY OF A PROPOSED ROAD FROM AN EXISTING CALICHE ROAD TO THE COACHWHIP
FEDERAL COM #1H IN
SECTION 14, TOWNSHIP 26 SOUTH, RANGE 28 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.



DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE AND 118.2 FEET OR 7.16 RODS OR 0.022 MILES IN LENGTH CROSSING FEE LAND (DELAWARE RANCH INC.) IN SECTION 14, TOWNSHIP 26 SOUTH, RANGE 28 EAST, EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

BASIS OF BEARING:
BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983. DISTANCES ARE GRID VALUES.

HARCROW SURVEYING, LLC

2314 W. MAIN ST, ARTESIA, N.M. 88210
PH: (575) 746-2158 FAX: (575) 746-2158
c.harcrow@harcrowsurveying.com




CERTIFICATION

I, CHAD HARCROW, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.



Chad Harcrow
CHAD HARCROW N.M.P.S. NO. 17777

2/8/15
DATE



COG OPERATING, LLC

SURVEY OF A PROPOSED ROAD LOCATED IN
SECTION 14, TOWNSHIP 26 SOUTH, RANGE 28 EAST,
EDDY COUNTY, NMPM, NEW MEXICO

SURVEY DATE: OCTOBER 18, 2014

DRAFTING DATE: FEBRUARY 7, 2015

APPROVED BY: CH

DRAWN BY: SP

PAGE 1 OF 1

FILE: 15-138

FID	Shape *	OPERATOR	WELL_NAME	LATITUDE	LONGITUDE	API	SECTION	TOWNS	RANGE	FTG_NS_NS_CD	FTG_EW_EW_CD	TVD_DEPTH
0	Point	BENNETT J	Sinclair 001	32.019029	-104.064224	3E+09	26	26.0S	28E	660 N	660 W	0
1	Point	MAX WILSON INC	ATLANTIC 001	32.019417	-104.052255	3E+09	26	26.0S	28E	547 N	930 E	0
2	Point	POGO PRODUCTION CO	BRANTLEY FED 001	32.033712	-104.059545	3E+09	23	26.0S	28E	580 N	2130 W	0
3	Point	TXO PRODUCTION CORP	DELAWARE FEDERAL 001	32.02974	-104.043839	3E+09	24	26.0S	28E	2030 N	1650 W	0
4	Point	COG PRODUCTION, LLC	BABY BUDDAH 13 FEDERAL 001H	32.041757	-104.048589	3E+09	13	26.0S	28E	2350 S	190 W	8334
5	Point	MEWBOURNE OIL CO	DELAWARE RANCH 13 EH FED COM 001H	32.044044	-104.048909	3E+09	13	26.0S	28E	2100 N	95 W	9
6	Point	MEWBOURNE OIL CO	DELAWARE RANCH 14 FEE 002H	32.048922	-104.059287	3E+09	14	26.0S	28E	330 N	2260 W	0
7	Point	MEWBOURNE OIL CO	DELAWARE RANCH 14 B2BO FEE 001H	32.049355	-104.054758	3E+09	14	26.0S	28E	170 N	1700 E	8244
8	Point	MEWBOURNE OIL CO	DELAWARE RANCH 14 FEE 004	32.048922	-104.061262	3E+09	14	26.0S	28E	331 N	1651 W	0
9	Point	MEWBOURNE OIL CO	DELAWARE RANCH 11 NC FEE 001H	32.050736	-104.059291	3E+09	11	26.0S	28E	330 S	2260 W	8216
10	Point	COG PRODUCTION, LLC	COTTONMOUTH 24 FEDERAL COM 001H	32.021234	-104.0468	3E+09	24	26.0S	28E	105 S	745 W	0
11	Point	CHEVRON U S A INC	DELAWARE RANCH 11 FEDERAL COM 001H	32.049171	-104.050541	3E+09	14	26.0S	28E	235 N	400 E	0
12	Point	MEWBOURNE OIL CO	DELAWARE RANCH 13 FEDERAL COM 001H	32.04891	-104.048691	3E+09	13	26.0S	28E	330 N	170 W	0
13	Point	COG PRODUCTION, LLC	DIAMONDBACK 22 STATE COM 003H	32.033791	-104.068594	3E+09	22	26.0S	28E	550 N	660 E	10360
14	Point	COG PRODUCTION, LLC	COTTONMOUTH 23 FEDERAL COM 001H	32.035209	-104.058978	3E+09	23	26.0S	28E	35 N	2310 W	8148
15	Point	MEWBOURNE OIL CO	DELAWARE RANCH 11 FEE 006H	32.050741	-104.062746	3E+09	11	26.0S	28E	330 S	1195 W	0
16	Point	MEWBOURNE OIL CO	DELAWARE RANCH 11 W2MD FEE 004H	32.050741	-104.06294	3E+09	11	26.0S	28E	330 S	1135 W	0
17	Point	MEWBOURNE OIL CO	DELAWARE RANCH 11 FEE 005H	32.050739	-104.06127	3E+09	11	26.0S	28E	330 S	1650 W	0
18	Point	MEWBOURNE OIL CO	DELAWARE RANCH 14 FEE 005H	32.050375	-104.056967	3E+09	11	26.0S	28E	200 S	2380 E	0
19	Point	COG PRODUCTION, LLC	DIAMONDBACK 22 STATE COM 001H	32.033962	-104.072811	3E+09	22	26.0S	28E	480 N	1960 E	12365
20	Point	MEWBOURNE OIL CO	DELAWARE RANCH 14 CN FEE COM 001H	32.048924	-104.061265	3E+09	14	26.0S	28E	330 N	1650 W	10548
21	Point	COG PRODUCTION, LLC	DIAMONDBACK 22 STATE COM 005H	32.03483	-104.069675	3E+09	22	26.0S	28E	170 N	990 E	0

COG Operating, LLC – Coachwhip Federal Com 1H

1. Geologic Formations

TVD of target	6233'	Pilot hole depth	NA
MD at TD:	11,931'	Deepest expected fresh water:	120

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Quaternary Fill	Surface	Water	
Rustler	373	Water	
Top of Salt	766	Salt	
Base of Salt	2373	Salt	
Lamar	2567	Barren	
Bell Canyon	2613	Oil/Gas	
Cherry Canyon	3426	Oil/Gas	
Brushy Canyon	4729	Oil/Gas	
Brushy Canyon – B	5886	Oil/Gas	
Brushy Canyon – A	6044	Oil/Gas	
Brushy Canyon – 4	6105	Oil/Gas	
Brushy Canyon – 3	6136	Oil/Gas	
Brushy Canyon – 2	6181	Target Zone	
Bone Spring Lime	6273	Oil/Gas	

*H₂S, water flows, loss of circulation, abnormal pressures, etc.

2. Casing Program

See COA

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
	From	To							
17.5"	0	425 375'	13.375"	54.5	J55	STC	3.45	2.02	22.19
12.25"	0	2550 2570	9.625"	40	J55	LTC	1.49	1.126	4.93
8.75"	0	11,931	5.5"	17	P110	LTC	1.70	2.39	2.19
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y

COG Operating, LLC – Coachwhip Federal Com 1H

Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

3. Cementing Program

Casing	#/Sks	Wt. lb/gal	Yld ft ³ /sack	H ₂ O gal/s R	500# Comp. Strength (hours)	Slurry Description
Surf.	450	14.8	1.34	6.4	8	Tail: Class C + 2% CaCl ₂
Inter.	575	13.5	1.72	8.9	12	1 st stage Lead: Class C + 4% Gel + 1% CaCl
	250	14.8	1.34	6.4	8	1 st stage Tail: Class C + 1% CaCl
Prod.	610	11.9	2.50	14	60	1 st Lead: 50:50:10 Econocem H
	1125	14.4	1.25	5.7	20	1 st Tail: Versacem 50:50:2 Class H

See
COA

Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Casing/String	TOC	% Excess
Surface	0'	100%
Intermediate	0'	75%
Production	2050' 2000'	25% in Lateral – 40% OH in Vert - Tie In 500' Inside 9-5/8" Casing Shoe @ 2550' + 100 sx Lead

COG Operating, LLC – Coachwhip Federal Com 1H

4. Pressure Control Equipment

N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
---	--

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
12-1/4"	13-5/8"	2M	Annular	x	2000 psi
			Blind Ram		2M
			Pipe Ram		
			Double Ram		
			Other*		
8-3/4"	11"	3M	Annular	x	50% testing pressure
			Blind Ram	x	3M
			Pipe Ram	x	
			Double Ram		
			Other *		
			Annular		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other *		

*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
---	--

COG Operating, LLC – Coachwhip Federal Com 1H

N	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?
N	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	Surf. shoe	FW Gel	8.6-8.8	28-34	N/C
Surf csg	Int shoe	Saturated Brine	10.0-10.2	28-34	N/C
Int shoe	TD	Cut Brine	8.5-9.3	28-34	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing	
Y	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
N	No Logs are planned based on well control or offset log information.
N	Drill stem test? If yes, explain
N	Coring? If yes, explain

Additional logs planned		Interval
N	Resistivity	
N	Density	
Y	CBL	Production casing (If cement to circulated to surface)
Y	Mud log	Intermediate shoe to TD
N	PEX	

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	3127 psi at 6233' TVD

COG Operating, LLC – Coachwhip Federal Com 1H

Abnormal Temperature	NO
----------------------	----

Mitigation measure for abnormal conditions. Describe. Sufficient supplies of Paper/LCM for periodic sweeps to control seepage and losses will be maintained on location.

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

N	H ₂ S is present
Y	H ₂ S Plan attached

8. Other facets of operation

Is this a walking operation? NO If yes, describe.

Will be pre-setting casing? NO If yes, describe.

Attachments

- Directional Plan
- BOP & Choke Schematics
- C102 and supporting maps
- Rig plat
- H₂S schematic
- H₂S contingency plan
- Interim reclamation plat



NM OIL CONSERVATION
ARTESIA DISTRICT

JAN 11 2016

RECEIVED

NEW MEXICO BASIN

EDDY COUNTY, NM

DELAWARE

COACHWHIP FED COM #1H

OWB

Plan: PWP1

Standard Planning Report

25 August, 2015



COG Operating LLC

Planning Report

Database:	EDM_Users	Local Co-ordinate Reference:	Well COACHWHIP FED COM #1H
Company:	NEW MEXICO BASIN	TVD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Project:	EDDY COUNTY, NM	MD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Site:	DELAWARE	North Reference:	Grid
Well:	COACHWHIP FED COM #1H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OWB		
Design:	PWP1		

Project:	EDDY COUNTY, NM		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site	DELAWARE			
Site Position:	From:	Map	Northings:	376,544.50 usft
			Easting:	531,304.00 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "	Grid Convergence:
				0.05 "

Well	COACHWHIP FED COM #1H			
Well Position	+N/-S	967.2 usft	Northings:	377,511.70 usft
	+E/-W	53,802.8 usft	Easting:	585,106.80 usft
Position Uncertainty	3.0 usft	Wellhead Elevation:	0.0 usft	Ground Level:
				2,944.5 usft

Wellbore	OWB				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	WMM2015	8/25/2015	7.37	59.83	47,957

Design	PWP1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.0	0.0	0.0	181.80

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
5,775.5	0.00	0.00	5,775.5	0.0	0.0	0.00	0.00	0.00	0.00	
6,527.2	90.20	176.00	6,253.0	-478.0	33.4	12.00	12.00	0.00	176.00	
6,877.2	90.20	176.00	6,251.8	-827.1	57.8	0.00	0.00	0.00	0.00	
7,107.5	90.21	182.91	6,250.9	-1,057.2	60.0	3.00	0.01	3.00	89.88	
11,928.9	90.21	182.91	6,233.0	-5,872.4	-184.5	0.00	0.00	0.00	0.00	PBHL-Coachwhip Fed



COG Operating LLC
Planning Report

Database:	EDM_Users	Local Co-ordinate Reference:	Well COACHWHIP FED COM #1H
Company:	NEW MEXICO BASIN	TVD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Project:	EDDY COUNTY, NM	MD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Site:	DELAWARE	North Reference:	Grid
Well:	COACHWHIP FED COM #1H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OWB		
Design:	PWP1		


Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00	
5,775.5	0.00	0.00	5,775.5	0.0	0.0	0.0	0.00	0.00	0.00	
5775.5' MD KOP										
6,527.2	90.20	176.00	6,253.0	-478.0	33.4	476.7	12.00	12.00	0.00	
6253' TVD_EOC										
6,877.2	90.20	176.00	6,251.8	-827.1	57.8	824.9	0.00	0.00	0.00	
7,107.5	90.21	182.91	6,250.9	-1,057.3	60.0	1,054.9	3.00	0.01	3.00	
EOT										
11,928.9	90.21	182.91	6,233.0	-5,872.4	-184.5	5,875.3	0.00	0.00	0.00	

Design Targets										
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude	
- hit/miss target										
- Shape										
PBHL-Coachwhip Fed C	0.00	0.00	6,233.0	-5,872.4	-184.5	371,639.30	584,922.30	32° 1' 17.237 N	104° 3' 33.561 W	
- plan hits target center										
- Point										

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
5,775.5	5,775.5	0.0	0.0	5775.5' MD KOP	
6,527.2	6,253.0	-478.0	33.4	6253' TVD_EOC	
7,107.5	6,250.9	-1,057.3	60.0	EOT	





Project: EDDY COUNTY, NM
 Site: DELAWARE
 Well: COACHWHIP FED COM #1H
 Wellbore: OWB
 Design: PWP1



LEGEND

— COTTONMOUTH 23 FED COM #1H OWB ACTUAL WELLPATH V0
 — PWP1





NEW MEXICO BASIN

EDDY COUNTY, NM

DELAWARE

COACHWHIP FED COM #1H

OWB

PWP1

Anticollision Report

25 August, 2015



COG Operating LLC
Anticollision Report

Company:	NEW MEXICO BASIN	Local Co-ordinate Reference:	Well COACHWHIP FED COM #1H
Project:	EDDY COUNTY, NM	TVD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Reference Site:	DELAWARE	MD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	COACHWHIP FED COM #1H	Survey Calculation Method:	Minimum Curvature
Well Error:	3.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	OWB	Database:	EDM_Users
Reference Design:	PWP1	Offset TVD Reference:	Offset Datum

Reference	PWP1		
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria		
Interpolation Method:	MD interval 100.0usft	Error Model:	ISCWSA
Depth Range:	Unlimited	Scan Method:	Closest Approach 3D
Results Limited by:	Maximum center-center distance of 2,151.5 usft	Error Surface:	Circular Conic
Warning Levels Evaluated at:	2.00 Sigma	Casing Method:	Not applied

Survey Tool Program		Date 8/25/2015		
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description
0.0	11,928.9	PWP1 (OWB)	MWD	OWSG MWD - Standard

Summary						
Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
DELAWARE						
COTTONMOUTH 23 FED COM #1H - OWB - ACTUAL W	6,985.0	6,250.8	149.5	116.7	4.556	CC, ES, SF

Offset Design													DELAWARE - COTTONMOUTH 23 FED COM #1H - OWB - ACTUAL WELLPATH		Offset Site Error: 0.0 usft	
Survey Program: 100-Standard Keeper 104, 7541-MWD													Offset Well Error: 3.0 usft			
Reference		Offset		Semi Major Axis			Distance						Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor				
0.0	0.0	0.5	0.5	3.0	3.0	-177.09	-936.0	-47.5	937.2							
100.0	100.0	103.2	103.2	3.0	3.0	-177.13	-935.9	-47.0	937.0	931.0	6.00	156.084				
159.2	159.2	159.7	159.7	3.0	3.0	-177.16	-935.8	-46.3	937.0	930.9	6.02	155.523				
200.0	200.0	200.0	200.0	3.0	3.0	-177.19	-935.9	-45.9	937.0	930.9	6.05	154.926				
300.0	300.0	298.8	298.7	3.1	3.0	-177.27	-936.1	-44.7	937.2	931.0	6.14	152.686				
400.0	400.0	394.4	394.4	3.2	3.0	-177.35	-936.6	-43.4	937.6	931.3	6.27	149.526				
500.0	500.0	493.4	493.4	3.4	3.1	-177.44	-937.4	-41.9	938.3	931.9	6.44	145.649				
600.0	600.0	598.2	598.2	3.6	3.1	-177.52	-938.0	-40.5	938.8	932.2	6.65	141.159				
700.0	700.0	706.3	706.2	3.8	3.1	-177.59	-937.8	-39.5	938.6	931.8	6.89	136.295				
800.0	800.0	810.8	810.7	4.0	3.1	-177.62	-936.9	-39.0	937.8	930.7	7.14	131.389				
900.0	900.0	914.4	914.4	4.3	3.1	-177.60	-935.6	-39.2	936.5	929.1	7.40	126.606				
1,000.0	1,000.0	1,015.2	1,015.1	4.5	3.2	-177.55	-934.0	-39.9	934.9	927.3	7.67	121.953				
1,100.0	1,100.0	1,112.7	1,112.6	4.8	3.2	-177.46	-932.5	-41.3	933.5	925.6	7.95	117.478				
1,200.0	1,200.0	1,212.3	1,212.1	5.1	3.2	-177.32	-931.2	-43.6	932.3	924.0	8.24	113.177				
1,300.0	1,300.0	1,313.4	1,313.2	5.4	3.2	-177.15	-929.7	-46.3	930.9	922.4	8.54	108.995				
1,400.0	1,400.0	1,409.3	1,409.1	5.7	3.2	-177.01	-928.5	-48.5	929.8	920.9	8.86	104.685				
1,500.0	1,500.0	1,511.7	1,511.4	6.0	3.2	-176.88	-927.3	-50.6	928.8	919.6	9.19	101.115				
1,600.0	1,600.0	1,618.4	1,618.1	6.3	3.2	-176.76	-925.5	-52.3	927.2	917.8	9.53	97.278				
1,700.0	1,700.0	1,717.3	1,717.0	6.6	3.3	-176.68	-923.7	-53.5	925.4	915.5	9.89	93.592				
1,800.0	1,800.0	1,825.1	1,824.8	6.9	3.3	-176.65	-921.3	-54.0	923.2	912.9	10.26	89.989				
1,900.0	1,900.0	1,931.7	1,931.3	7.2	3.4	-176.72	-918.1	-52.6	920.1	909.4	10.64	86.490				
2,000.0	2,000.0	2,027.4	2,026.9	7.6	3.4	-176.93	-915.2	-49.2	918.8	905.8	11.01	83.244				
2,100.0	2,100.0	2,118.0	2,117.5	7.9	3.5	-177.09	-913.2	-46.5	914.6	903.2	11.39	80.290				
2,200.0	2,200.0	2,215.7	2,215.0	8.2	3.5	-177.33	-911.7	-42.6	912.8	901.1	11.77	77.537				
2,300.0	2,300.0	2,313.5	2,312.7	8.6	3.6	-177.66	-910.5	-37.2	911.3	899.2	12.16	74.970				
2,400.0	2,400.0	2,408.8	2,407.8	8.9	3.6	-177.93	-909.7	-32.8	910.3	897.7	12.54	72.574				

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



COG Operating LLC
Anticollision Report

Company:	NEW MEXICO BASIN	Local Co-ordinate Reference:	Well COACHWHIP FED COM #1H
Project:	EDDY COUNTY, NM	TVD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Reference Site:	DELAWARE	MD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	COACHWHIP FED COM #1H	Survey Calculation Method:	Minimum Curvature
Well Error:	3.0 usft	Output errors are at:	2.00 sigma
Reference Wellbore:	OWB	Database:	EDM_Users
Reference Design:	PWP1	Offset TVD Reference:	Offset Datum

Offset Design DELAWARE - COTTONMOUTH 23 FED COM #1H - OWB - ACTUAL WELLPATH														Offset Site Error:	0.0 usft
Survey Program: 100-Standard Keeper 104, 7541-MWD														Offset Well Error:	3.0 usft
Reference		Offset		Semi Major Axis		Distance									
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N-S (usft)	+E-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning		
2,500.0	2,500.0	2,505.8	2,504.9	9.3	3.7	-178.07	-909.1	-30.7	909.7	898.7	12.94	70.310			
2,600.0	2,600.0	2,608.2	2,607.3	9.6	3.8	-178.11	-908.6	-29.9	909.0	895.7	13.35	68.104			
2,700.0	2,700.0	2,706.0	2,705.1	9.9	3.8	-178.13	-907.9	-29.6	908.4	894.6	13.76	66.006			
2,800.0	2,800.0	2,806.9	2,805.9	10.3	3.9	-178.14	-907.4	-29.5	907.9	893.7	14.18	64.019			
2,900.0	2,900.0	2,907.3	2,906.4	10.6	4.0	-178.13	-906.7	-29.6	907.2	892.6	14.60	62.159			
3,000.0	3,000.0	3,007.4	3,006.4	11.0	4.0	-178.10	-906.1	-30.1	906.6	891.6	15.00	60.443			
3,100.0	3,100.0	3,106.7	3,105.7	11.3	4.1	-178.05	-905.4	-30.8	906.0	890.6	15.40	58.647			
3,200.0	3,200.0	3,205.5	3,204.5	11.7	4.1	-177.99	-904.9	-31.7	905.5	889.7	15.79	57.352			
3,300.0	3,300.0	3,306.5	3,305.5	12.0	4.2	-177.92	-904.3	-32.8	904.9	888.8	16.18	55.925			
3,400.0	3,400.0	3,401.9	3,401.0	12.3	4.2	-177.84	-904.0	-34.1	904.6	888.1	16.57	54.601			
3,443.9	3,443.9	3,445.4	3,444.4	12.5	4.2	-177.80	-904.0	-34.6	904.6	887.9	16.73	54.057			
3,500.0	3,500.0	3,500.9	3,499.9	12.7	4.3	-177.74	-903.9	-35.7	904.6	887.7	16.95	53.374			
3,600.0	3,600.0	3,603.5	3,602.5	13.0	4.3	-177.63	-903.8	-37.4	904.6	887.2	17.34	52.173			
3,700.0	3,700.0	3,701.9	3,700.9	13.4	4.3	-177.52	-903.6	-39.2	904.4	886.7	17.73	51.010			
3,800.0	3,800.0	3,802.4	3,801.4	13.7	4.4	-177.41	-903.4	-40.9	904.4	886.2	18.13	49.892			
3,900.0	3,900.0	3,903.4	3,902.3	14.1	4.4	-177.29	-903.2	-42.8	904.2	885.7	18.53	48.802			
4,000.0	4,000.0	4,003.5	4,002.4	14.4	4.5	-177.16	-902.9	-44.8	904.0	885.1	18.93	47.744			
4,056.8	4,056.8	4,056.4	4,057.3	14.6	4.5	-177.09	-902.8	-45.9	903.9	884.8	19.16	47.171			
4,100.0	4,100.0	4,100.0	4,098.9	14.8	4.5	-177.04	-902.8	-46.7	904.0	884.6	19.34	46.745			
4,200.0	4,200.0	4,194.1	4,193.0	15.1	4.6	-176.92	-903.1	-48.6	904.5	884.7	19.73	45.836			
4,300.0	4,300.0	4,293.6	4,292.4	15.5	4.6	-176.79	-903.9	-50.7	905.4	885.2	20.13	44.882			
4,400.0	4,400.0	4,394.0	4,392.8	15.8	4.7	-176.64	-904.6	-53.1	906.2	885.7	20.53	44.150			
4,500.0	4,500.0	4,490.7	4,489.5	16.2	4.7	-176.50	-905.5	-55.4	907.2	886.3	20.92	43.357			
4,600.0	4,600.0	4,595.7	4,594.4	16.6	4.8	-176.34	-906.4	-57.9	908.2	886.9	21.33	42.576			
4,700.0	4,700.0	4,689.2	4,688.0	16.9	4.8	-176.23	-907.2	-59.8	909.2	887.5	21.73	41.840			
4,800.0	4,800.0	4,790.4	4,789.1	17.3	4.9	-176.14	-908.5	-61.3	910.6	888.5	22.13	41.151			
4,900.0	4,900.0	4,888.7	4,887.4	17.6	4.9	-176.04	-909.6	-62.9	911.9	889.4	22.53	40.481			
5,000.0	5,000.0	4,987.0	4,985.6	18.0	5.0	-175.93	-911.0	-64.8	913.5	890.5	22.93	39.836			
5,100.0	5,100.0	5,085.0	5,083.6	18.3	5.0	-175.79	-912.6	-67.1	915.2	891.8	23.34	39.215			
5,200.0	5,200.0	5,185.0	5,183.6	18.7	5.1	-175.66	-914.3	-69.4	917.0	893.3	23.75	38.616			
5,300.0	5,300.0	5,284.5	5,283.1	19.0	5.1	-175.53	-916.0	-71.6	918.9	894.8	24.16	38.036			
5,400.0	5,400.0	5,379.7	5,378.2	19.4	5.2	-175.42	-917.8	-73.6	921.0	896.5	24.57	37.492			
5,500.0	5,500.0	5,477.4	5,475.8	19.7	5.2	-175.30	-920.2	-75.6	923.6	898.7	24.97	36.983			
5,600.0	5,600.0	5,575.0	5,573.4	20.1	5.3	-175.19	-922.8	-77.7	926.4	901.0	25.38	36.498			
5,700.0	5,700.0	5,676.3	5,674.6	20.4	5.3	-175.09	-925.5	-79.6	929.3	903.5	25.79	36.031			
5,800.0	5,800.0	5,779.9	5,778.2	20.8	5.4	9.01	-928.1	-81.2	931.3	905.1	26.20	35.545			
5,900.0	5,898.6	5,880.3	5,878.6	21.1	5.5	9.49	-930.3	-82.6	918.2	891.7	26.58	34.550			
6,000.0	5,991.8	5,976.5	5,974.8	21.4	5.5	10.70	-932.2	-83.6	885.0	858.1	26.93	32.860			
6,100.0	6,075.6	6,063.7	6,062.0	21.7	5.6	13.03	-933.8	-84.6	833.2	805.9	27.29	30.526			
6,200.0	6,148.3	6,135.7	6,133.9	22.0	5.6	17.31	-934.8	-85.4	765.1	737.4	27.68	27.644			
6,300.0	6,200.7	6,190.3	6,188.5	22.4	5.7	25.65	-935.7	-86.1	684.2	656.1	28.10	24.353			
6,400.0	6,236.6	6,226.4	6,224.8	22.9	5.7	43.24	-936.3	-86.7	594.5	565.9	28.57	20.808			
6,500.0	6,252.3	6,243.2	6,241.4	23.4	5.7	76.36	-936.6	-87.0	500.2	471.1	29.09	17.191			
6,600.0	6,252.7	6,245.3	6,243.5	24.0	5.7	86.83	-936.7	-87.0	406.1	376.4	29.68	13.683			
6,700.0	6,252.4	6,246.7	6,244.9	24.7	5.7	87.36	-936.7	-87.1	315.7	285.3	30.37	10.395			
6,800.0	6,252.0	6,248.1	6,246.3	25.4	5.7	87.89	-936.7	-87.1	233.1	202.0	31.15	7.484			
6,900.0	6,251.7	6,249.6	6,247.7	26.3	5.7	88.42	-936.8	-87.1	170.3	138.3	32.02	5.319			
6,985.0	6,251.4	6,250.8	6,249.0	27.1	5.7	88.90	-936.8	-87.1	149.5	116.7	32.81	4.556 CC, ES, SF			
7,000.0	6,251.3	6,251.1	6,249.2	27.2	5.7	88.99	-936.8	-87.2	150.2	117.2	32.95	4.558			
7,100.0	6,251.0	6,252.7	6,250.9	28.2	5.7	89.62	-936.8	-87.2	185.8	151.9	33.94	5.476			
7,200.0	6,250.6	6,254.4	6,252.5	29.2	5.7	90.25	-936.9	-87.2	256.1	221.2	34.96	7.326			
7,300.0	6,250.2	6,256.1	6,254.2	30.3	5.7	90.88	-936.9	-87.2	341.5	305.5	36.04	9.477			

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation



COG Operating LLC
Anticollision Report

Company:	NEW MEXICO BASIN	Local Co-ordinate Reference:	Well COACHWHIP FED COM #1H
Project:	EDDY COUNTY, NM	TVD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Reference Site:	DELAWARE	MD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	COACHWHIP FED COM #1H	Survey Calculation Method:	Minimum Curvature
Well Error:	3.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	OWB	Database:	EDM_Users
Reference Design:	PWP	Offset TVD Reference:	Offset Datum

Offset Design DELAWARE - COTTONMOUTH 23 FED COM #1H - OWB - ACTUAL WELLPATH														Offset Site Error:	0.0 usft
Survey Program: 100-Standard Keeper 104, 7541-MWD														Offset Well Error:	3.0 usft
Reference		Offset		Semi Major Axis			Distance								Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Tooface (")	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor			
7,400.0	6,249.9	6,257.8	6,255.9	31.5	5.7	91.53	-936.9	-87.3	433.2	396.1	37.17	11.856			
7,500.0	6,249.5	6,259.5	6,257.7	32.6	5.7	92.17	-937.0	-87.3	528.0	489.6	38.34	13.769			
7,600.0	6,249.1	6,261.3	6,259.4	33.8	5.7	92.83	-937.0	-87.3	624.3	584.8	39.56	15.783			
7,700.0	6,248.7	6,263.0	6,261.2	35.1	5.7	93.49	-937.0	-87.4	721.7	680.9	40.80	17.686			
7,800.0	6,248.4	6,264.8	6,263.0	36.4	5.7	94.16	-937.1	-87.4	818.7	777.6	42.08	19.477			
7,900.0	6,248.0	6,266.7	6,264.8	37.7	5.7	94.84	-937.1	-87.5	918.1	874.7	43.39	21.158			
8,000.0	6,247.6	6,268.5	6,266.7	39.0	5.7	95.52	-937.1	-87.5	1,018.8	972.1	44.73	22.734			
8,100.0	6,247.3	6,270.4	6,268.6	40.4	5.7	96.21	-937.2	-87.5	1,115.7	1,069.7	46.08	24.212			
8,200.0	6,246.9	6,272.3	6,270.4	41.7	5.7	96.90	-937.2	-87.6	1,214.9	1,167.4	47.48	25.598			
8,300.0	6,246.5	6,274.2	6,272.4	43.1	5.7	97.60	-937.3	-87.6	1,314.1	1,265.2	48.86	26.898			
8,400.0	6,246.1	6,276.1	6,274.3	44.5	5.7	98.31	-937.3	-87.7	1,413.5	1,363.2	50.27	28.118			
8,500.0	6,245.8	6,278.1	6,276.2	46.0	5.7	99.02	-937.3	-87.7	1,512.9	1,461.2	51.70	29.264			
8,600.0	6,245.4	6,280.1	6,278.2	47.4	5.7	99.74	-937.4	-87.7	1,612.4	1,559.2	53.14	30.342			
8,700.0	6,245.0	6,282.1	6,280.2	48.9	5.7	100.46	-937.4	-87.8	1,711.9	1,657.3	54.60	31.357			
8,800.0	6,244.6	6,284.1	6,282.3	50.3	5.7	101.19	-937.5	-87.8	1,811.5	1,755.5	56.06	32.313			
8,900.0	6,244.3	9,817.1	8,117.0	51.8	32.7	175.53	-2,869.5	-178.7	1,878.2	1,793.7	84.46	22.238			
8,997.2	6,243.9	9,892.0	8,116.8	53.2	33.9	175.70	-2,944.4	-176.7	1,877.5	1,790.4	87.13	21.550			
9,000.0	6,243.9	9,892.0	8,116.6	53.3	33.9	175.70	-2,944.4	-176.7	1,877.5	1,790.4	87.17	21.540			
9,100.0	6,243.5	9,988.0	8,117.2	54.8	35.5	175.96	-3,040.3	-173.3	1,877.9	1,787.6	90.23	20.811			
9,200.0	6,243.2	10,120.5	8,117.0	56.3	37.6	176.36	-3,172.7	-166.9	1,877.5	1,783.5	93.92	19.990			
9,300.0	6,242.8	10,214.7	8,116.1	57.8	39.2	176.68	-3,266.6	-160.8	1,876.1	1,779.1	96.99	19.344			
9,400.0	6,242.4	10,370.0	8,114.2	59.3	41.8	177.25	-3,421.5	-150.0	1,875.2	1,774.1	101.08	18.551			
9,500.0	6,242.0	10,432.2	8,112.5	60.8	42.8	177.45	-3,483.6	-146.5	1,872.2	1,768.6	103.64	18.065			
9,573.1	6,241.8	10,465.0	8,112.1	62.0	43.3	177.55	-3,516.4	-144.8	1,871.5	1,766.2	105.30	17.773			
9,600.0	6,241.7	10,488.0	8,112.1	62.4	43.7	177.62	-3,539.3	-143.8	1,871.5	1,765.4	106.10	17.640			
9,700.0	6,241.3	10,561.0	8,113.8	63.9	44.9	177.82	-3,612.3	-141.1	1,873.6	1,764.7	108.84	17.214			
9,800.0	6,240.9	10,637.2	8,116.5	65.4	46.2	178.01	-3,688.4	-138.8	1,877.0	1,765.4	111.65	16.812			
9,900.0	6,240.6	10,746.0	8,119.6	67.0	48.0	178.25	-3,797.2	-136.7	1,880.0	1,765.0	114.99	16.349			
10,000.0	6,240.2	10,819.8	8,122.0	68.5	49.2	178.37	-3,870.9	-136.4	1,883.5	1,765.7	117.78	15.995			
10,100.0	6,239.8	10,924.6	8,126.3	70.1	50.9	178.51	-3,975.6	-137.1	1,887.9	1,768.9	121.03	15.598			
10,200.0	6,239.4	11,049.8	8,130.1	71.7	53.0	178.62	-4,100.7	-140.1	1,891.2	1,766.6	124.64	15.173			
10,300.0	6,239.1	11,180.5	8,132.2	73.2	55.1	178.71	-4,231.3	-143.9	1,893.1	1,764.8	128.34	14.751			
10,400.0	6,238.7	11,291.5	8,132.4	74.8	56.9	178.81	-4,342.3	-146.3	1,893.6	1,761.9	131.73	14.375			
10,500.0	6,238.3	11,392.9	8,132.5	76.4	58.6	178.88	-4,443.7	-149.0	1,894.0	1,759.1	134.96	14.034			
10,600.0	6,237.9	11,487.2	8,132.6	77.9	60.1	178.98	-4,538.0	-150.3	1,894.5	1,756.4	138.08	13.720			
10,700.0	6,237.6	11,514.5	8,132.5	79.5	62.2	179.14	-4,655.2	-151.5	1,894.7	1,753.0	141.75	13.366			
10,800.0	6,237.2	11,739.1	8,130.4	81.1	64.3	179.28	-4,789.8	-153.4	1,893.4	1,748.0	145.38	13.024			
10,900.0	6,236.8	11,837.8	8,127.6	82.7	65.9	179.37	-4,888.5	-155.3	1,890.9	1,742.3	148.58	12.726			
10,998.8	6,236.5	11,897.0	8,126.7	84.2	66.9	179.43	-4,947.6	-156.3	1,889.8	1,738.7	151.09	12.508			
11,000.0	6,236.5	11,897.0	8,126.7	84.2	66.9	179.43	-4,947.6	-156.3	1,889.8	1,738.7	151.14	12.504			
11,100.0	6,236.1	11,969.4	8,126.9	85.8	68.1	179.50	-5,020.0	-157.8	1,890.5	1,736.6	153.92	12.283			
11,200.0	6,235.7	12,053.1	8,128.5	87.4	69.5	179.56	-5,103.7	-160.0	1,892.7	1,735.9	156.88	12.065			
11,300.0	6,235.3	12,148.5	8,130.7	89.0	71.0	179.65	-5,199.1	-161.8	1,895.4	1,735.3	160.04	11.843			
11,400.0	6,235.0	12,252.1	8,133.1	90.6	72.7	179.76	-5,302.5	-163.6	1,898.1	1,734.6	163.34	11.621			
11,500.0	6,234.6	12,369.4	8,135.2	92.2	74.7	179.90	-5,419.9	-164.9	1,900.2	1,733.4	166.87	11.388			
11,600.0	6,234.2	12,461.3	8,136.5	93.8	76.2	179.99	-5,511.7	-166.5	1,902.1	1,732.1	169.98	11.190			
11,700.0	6,233.9	12,565.0	8,137.8	95.4	77.9	-179.92	-5,616.4	-168.7	1,903.6	1,730.3	173.30	10.985			
11,800.0	6,233.5	12,630.1	8,139.0	97.0	79.0	-179.84	-5,680.5	-169.5	1,906.1	1,730.1	175.96	10.833			
11,900.0	6,233.1	12,696.0	8,141.9	98.6	80.1	-179.74	-5,746.3	-169.4	1,910.9	1,732.2	178.65	10.696			
11,928.9	6,233.0	12,719.7	8,143.2	99.0	80.5	-179.70	-5,769.9	-169.3	1,912.5	1,733.0	179.50	10.654			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



COG Operating LLC
Anticollision Report

Company:	NEW MEXICO BASIN	Local Co-ordinate Reference:	Well COACHWHIP FED COM #1H
Project:	EDDY COUNTY, NM	TVD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Reference Site:	DELAWARE	MD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	COACHWHIP FED COM #1H	Survey Calculation Method:	Minimum Curvature
Well Error:	3.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	OWB	Database:	EDM_Users
Reference Design:	PWP1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to RKB=2944.5+18 @ 2962.5usft (TBD)

Offset Depths are relative to Offset Datum


Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: COACHWHIP FED COM #1H

Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30

Grid Convergence at Surface is: 0.15°

Ladder Plot



LEGEND

COM#1H,OWB,ACTUALWELLPATHV0

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



COG Operating LLC
Anticollision Report

Company:	NEW MEXICO BASIN	Local Co-ordinate Reference:	Well COACHWHIP FED COM #1H
Project:	EDDY COUNTY, NM	TVD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Reference Site:	DELAWARE	MD Reference:	RKB=2944.5+18 @ 2962.5usft (TBD)
Site Error:	0.0 usft	North Reference:	Grid
Reference Well:	COACHWHIP FED COM #1H	Survey Calculation Method:	Minimum Curvature
Well Error:	3.0 usft	Output errors are at	2.00 sigma
Reference Wellbore	OWB	Database:	EDM_Users
Reference Design:	PWP1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to RKB=2944.5+18 @ 2962.5usft (TBD)

Offset Depths are relative to Offset Datum


Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: COACHWHIP FED COM #1H

Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30

Grid Convergence at Surface is: 0.15°

Separation Factor Plot



LEGEND

COM #1H, OWB, ACTUAL WELLPATH V0



New Mexico Office of the State Engineer Water Column/Average Depth to Water

(A CLW##### in the
POD suffix indicates the
POD has been replaced
& no longer serves a
water right file.)

(R=POD has
been replaced,
O=orphaned,
C=the file is
closed)

(quarters are 1=NW 2=NE 3=SW 4=SE)

(quarters are smallest to largest) (NAD83 UTM in meters)

(In feet)

POD Number	POD Sub-Code	basin	County	Q 64	Q 16	Q 4	Sec.	Tws.	Range	X	Y	Depth Well	Depth Water Column
C 02160		ED		4	1	2	14	26S	28E	589243	3546044*	300	120 180
C 02160 S		ED		1	1	2	14	26S	28E	589043	3546244*	300	120 180
C 02160 S2		ED		1	1	2	14	26S	28E	589043	3546244*	300	120 180
C 02160 S3		ED		2	2	1	14	26S	28E	588834	3546241*	300	120 180
C 02160 S4		ED		2	2	1	14	26S	28E	588834	3546241*	300	120 180
C 02160 S5		ED		1	1	1	14	26S	28E	588225	3546237*	300	120 180
C 02160 S6		ED		3	3	1	14	26S	28E	588232	3545635*	300	120 180
C 02481		CUB ED		1	1	14	26S	28E		588326	3546138*	200	

Average Depth to Water: 120 feet

Minimum Depth: 120 feet

Maximum Depth: 120 feet

Record Count: 8

PLSS Search:

Section(s): 14

Township: 26S

Range: 28E

*UTM location was derived from PLSS - see Help

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.



New Mexico Office of the State Engineer **Water Column/Average Depth to Water**

No records found.

PLSS Search:

Section(s): 23

Township: 26S

Range: 28E



New Mexico Office of the State Engineer

Water Column/Average Depth to Water

(A CLW##### in the
POD suffix indicates the
POD has been replaced
& no longer serves a
water right file.)

(R=POD has
been replaced,
O=orphaned,

C=the file is (quarters are 1=NW 2=NE 3=SW 4=SE)
closed) (quarters are smallest to largest)

(NAD83 UTM in meters)

(In feet)

POD Number	POD Sub	Code	basin	County	Q	Q	Q	Sec	Tws	Rng	X	Y	Depth Well	Depth Water	Water Column
C 01668				ED	3	3	12	26S	28E		589957	3546554*	250	100	150
C 02160				ED	4	1	2	14	26S	28E	589243	3546044*	300	120	180
C 02160 S				ED	1	1	2	14	26S	28E	589043	3546244*	300	120	180
C 02160 S2				ED	1	1	2	14	26S	28E	589043	3546244*	300	120	180
C 02160 S3				ED	2	2	1	14	26S	28E	588834	3546241*	300	120	180
C 02160 S4				ED	2	2	1	14	26S	28E	588834	3546241*	300	120	180
C 02160 S5				ED	1	1	1	14	26S	28E	588225	3546237*	300	120	180
C 02160 S6				ED	3	3	1	14	26S	28E	588232	3545635*	300	120	180
C 02160 S7				ED	3	3	1	22	26S	28E	586638	3543998*	300	120	180
C 02160 S8				ED	2	3	3	12	26S	28E	590056	3546653*	200	120	80
C 02160 S9				ED	3	3	2	02	26S	28E	589020	3548868*	300	120	180
C 02477		CUB		ED	1	1	03	26S	28E		586687	3549347*	150		
C 02478		CUB		ED	2	1	05	26S	28E		583848	3549325*	100		
C 02479		CUB		ED	4	4	10	26S	28E		587909	3546534*	200		
C 02480		CUB		ED	4	4	10	26S	28E		587909	3546534*	150		
C 02481		CUB		ED	1	1	14	26S	28E		588326	3546138*	200		
C 02894		C		ED	2	2	3	12	26S	28E	590458	3547061*	240		
C 02924		C		ED	1	3	2	11	26S	28E	589032	3547451*			

Average Depth to Water: 118 feet

Minimum Depth: 100 feet

Maximum Depth: 120 feet

Record Count: 18

PLSS Search:


Township: 26S

Range: 28E


*UTM location was derived from PLSS - see Help

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.


2,000 psi BOP Schematic




3,000 psi BOP Schematic



2M Choke Manifold Equipment



3M Choke Manifold Equipment



COG Operating LLC

Rig Plat & Closed Loop Equipment Diagram

Well pad will be 340' X 340' with cellar in center of pad

Flare Lines will be from both Choke Manifold & Separator to edge of location which is +/- 170'

North

Transfer Pump

Drig Separator

Choke Manifold

Pipe Racks

170'

170'

Cellar

Trailer

170'

Fluid Storage Tanks

Centrifuge or Solids Sep.

Roll Off Cutting Containers on Tracks

Shakers

Steel pits

Mud Pumps

170'

Water Tanks


Water Tanks

* I further certify that COG will comply with Rule 19.15.17 NMAC by using a Closed Loop System."


Well pad will be 340' X 340'
with cellar in center of pad

COG Operating LLC
H₂S Equipment Schematic
Terrain: Shinnery sand hills.

☐ Location Entry
Condition Sign



150' Buried Flare Line



Centrifuge or Solids Sep.





H₂S Sensor @ Flowline




Drig Separator

Flow line

Windstock on 20' pole



Choke Manifold



H₂S Sensors
1- on rig floor
1- under substructure




Windstock on 20' pole

H₂S Monitoring Panel

5 Escape Packs

Pipe Racks

☐ Briefing Area
w/SCBA



Prevailing Wind
Direction in SENM

Company Representative's Trailer

☐ Primary Briefing
Area w/SCBA


Secondary egress.

Production Facility Layout

Coachwhip Federal Com #1H

Section 14 - T26S - R28E

Exhibit 3



COG OPERATING LLC
HYDROGEN SULFIDE DRILLING OPERATIONS PLAN

1. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

- a. The hazards and characteristics of hydrogen sulfide (H₂S).
- b. The proper use and maintenance of personal protective equipment and life support systems.
- c. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
- d. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

- a. The effects of H₂S on metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
- b. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
- c. The contents and requirements of the H₂S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

2. H₂S SAFETY EQUIPMENT AND SYSTEMS

Note: All H₂S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H₂S. If H₂S greater than 100 ppm is encountered in the gas stream we will shut in and install H₂S equipment.

- a. Well Control Equipment:
 - Flare line.
 - Choke manifold with remotely operated choke.
 - Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
 - Auxiliary equipment to include: annular preventer, mud-gas separator, rotating head.

- b. Protective equipment for essential personnel:
Mark II Surviveair 30-minute units located in the dog house and at briefing areas.
- c. H2S detection and monitoring equipment:
2 - portable H2S monitor positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 ppm are reached.
- d. Visual warning systems:
Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.
- e. Mud Program:
The mud program has been designed to minimize the volume of H2S circulated to the surface.
- f. Metallurgy:
All drill strings, casings, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- g. Communication:
Company vehicles equipped with cellular telephone.

COG OPERATING LLC has conducted a review to determine if an H2S contingency plan is required for the above referenced well. We were able to conclude that any potential hazardous volume would be minimal. H2S concentrations of wells in this area from surface to TD are low enough; therefore, we do not believe that an H2S contingency plan is necessary.

W A R N I N G

**YOU ARE ENTERING AN H₂S AREA
AUTHORIZED PERSONNEL ONLY**

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED***
- 2. HARD HATS REQUIRED***
- 3. SMOKING IN DESIGNATED AREAS ONLY***
- 4. BE WIND CONSCIOUS AT ALL TIMES***
- 5. CK WITH COG OPERATING LLC FOREMAN AT MAIN OFFICE***

COG OPERATING LLC

1-575-748-6940

EMERGENCY CALL LIST

	<u>OFFICE</u>	<u>MOBILE</u>
COG OPERATING LLC OFFICE	575-748-6940	
SHERYL BAKER	575-748-6940	432-934-1873
KENT GREENWAY	575-746-2010	432-557-1694
SETH WILD	432-683-7443	432-528-3633
WALTER ROYE	575-748-6940	432-934-1886

EMERGENCY RESPONSE NUMBERS

	<u>OFFICE</u>
STATE POLICE	575-748-9718
EDDY COUNTY SHERIFF	575-746-2701
EMERGENCY MEDICAL SERVICES (AMBULANCE)	911 or 575-746-2701
EDDY COUNTY EMERGENCY MANAGEMENT (HARRY BURGESS)	575-887-9511
STATE EMERGENCY RESPONSE CENTER (SERC)	575-476-9620
CARLSBAD POLICE DEPARTMENT	575-885-2111
CARLSBAD FIRE DEPARTMENT	575-885-3125
NEW MEXICO OIL CONSERVATION DIVISION	575-748-1283
INDIAN FIRE & SAFETY	800-530-8693
HALLIBURTON SERVICES	800-844-8451

Surface Use & Operating Plan

Coachwhip Federal Com #1H

- Surface Owner: Draper Brantley, 706 Riverside Drive, Carlsbad, NM 88220. 575-706-3169
- New Road: 118'
- Flow Line: On well pad
- Facilities: Will be constructed on well pad – see Exhibit 3
- **Well Site Information**
 - V Door: East
 - Topsoil: East
 - Interim Reclamation: North and East

Notes

Onsite: On-site was done by Jesse Rice (BLM); Rand French (COG); Gerald Herrera (COG) on September 9th, 2014.

SURFACE USE AND OPERATING PLAN

1. Existing & Proposed Access Roads

- A. The well site survey and elevation plat for the proposed well is attached with this application. It was staked by Harcrow Surveying, Artesia, NM.
- B. All roads to the location are shown on the Location Verification Map Exhibit 2. The existing lease roads are illustrated and are adequate for travel during drilling and production operations. Upgrading existing roads prior to drilling the well will be done where necessary. The road route to the well site is depicted in Exhibit #2. The road shown in Exhibit #2 will be used to access the well.
- C. Directions to location: See 600 x 600 plat
- D. Based on current road maintenance performed on other roads serving existing wells, we anticipate maintaining the lease roads leading to the proposed well pad at least once a year on dry conditions and twice a year in wetter conditions.

2. Proposed Access Road:

The Location Verification Map shows that 118' of new access road will be required for this location. If any road is required it will be constructed as follows:

The maximum width of the running surface will be 14'. The road will be crowned, ditched and constructed of 6" rolled and compacted caliche. Ditches will be at 3:1 slope and 4 feet wide. Water will be diverted where necessary to avoid ponding, prevent erosion, maintain good drainage, and to be consistent with local drainage patterns.

- A. The average grade will be less than 1%.
- B. No turnouts are planned.
- C. No cattleguard, culvert, gates, low water crossings or fence cuts are necessary.
- D. Surfacing material will consist of native caliche. Caliche will be obtained from the actual well site if available. If not available onsite, caliche will be hauled from the nearest BLM approved caliche pit. Candidate source will be caliche pit from Draper Brantley Phone (575) 703-3169.

3. Location of Existing Well:

The One-Mile Radius Map Exhibit 4 shows existing wells within a one-mile radius of the proposed wellbore.

Location of Existing and/or Proposed Facilities:

- A. COG Operating LLC does not operate an oil production facility on this lease.
- B. If the well is productive, contemplated facilities will be as follows:
 - 1) A tank battery and facilities will be constructed as shown on Exhibit 3.
 - 2) The tank battery and facilities including all flow lines and piping will be installed according to API specifications.
 - 3) Any additional caliche will be obtained from the actual well site. If caliche does not exist or is not plentiful from the well site, the caliche will be hauled from a BLM approved caliche pit. Candidate source will be caliche pit from Draper Brantley phone (575) 703-3169. Any additional construction materials will be purchased from contractors.
 - 4) It will be necessary to run electric power if this well is productive. Power will be provided by Xcel Energy and they will submit a separate plan and ROW for service to the well location.
 - 5) If the well is productive, rehabilitation plans will include the following:
 - The original topsoil from the well site will be returned to the location, and the site will be re-contoured as close as possible to the original site.

4. Location and Type of Water Supply:

The well will be drilled with combination brine and fresh water mud system as outlined in the drilling program. The water will be obtained from a private source (Draper Brantley 575- 703-3169) or if necessary commercial water stations in the area and hauled to location by transport truck over the existing and proposed access roads shown in Exhibit #2. If a commercial fresh water source is nearby, fast line may be laid along existing road ROW's and fresh water pumped to the well. No water well will be drilled on the location.

5. Source of Construction Materials and Location "Turn-Over" Procedure:

Obtaining caliche: One primary way of obtaining caliche to build locations and roads will be by "turning over" the location. This means, caliche will be obtained from the actual well site. Amount will vary for each pad. The procedure below has been approved by BLM personnel:

- A. The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.
- B. An approximate 160' X 160' area is used within the proposed well site to remove caliche.
- C. Subsoil is removed and stockpiled within the surveyed well pad.
- D. When caliche is found, material will be stock piled within the pad site to build the location and road.
- E. Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
- F. Once well is drilled, the stock piled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced.
- G. Neither caliche, nor subsoil will be stock piled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in the Well Site Layout or survey plat.

In the event that no caliche is found onsite, caliche will be hauled in from a BLM approved caliche pit or other established mineral pit. Candidate source will be caliche pit from Draper Brantley Phone (575) 703-3169.

Methods of Handling Water Disposal:

- A. The well will be drilled utilizing a closed loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to R360's disposal site.
- B. Drilling fluids will be contained in steel mud pits.
- C. Water produced from the well during completion will be held temporarily in steel tanks and then taken to an NMOCD approved commercial disposal facility.
- D. Garbage and trash produced during drilling or completion operations will be collected in a trash bin and hauled to an approved landfill. No toxic waste or hazardous chemicals will be produced by this operation.

- E. Human waste and grey water will need to be properly contained and disposed of. Proper disposal and elimination of waste and grey water may include but are not limited to portable septic systems and/or portable waste gathering systems (i.e. portable toilets).
- F. After the rig is moved out and the well is either completed or abandoned, all waste materials will be cleaned up within 30 days. In the event of a dry hole only a dry hole marker will remain.

6. Ancillary Facilities:

No airstrip, campsite or other facilities will be built as a result of the operation on this well.

7. Well Site Layout:

- A. The drill pad layout, with elevations staked by Harcrow Surveying, is shown in the Elevation Plat. Dimensions of the pad and pits are shown on the Rig Layout. V door direction is East. Topsoil, if available, will be stockpiled per BLM specifications. Because the pad is almost level no major cuts will be required.
- B. The Rig Layout Closed-Loop exhibit shows the proposed orientation of closed loop system and access road. No permanent living facilities are planned, but a temporary foreman/toolpusher's trailer will be on location during the drilling operations.

8. Plans for Restoration of the Surface:

- A. Interim Reclamation will take place after the well has been completed. The pad will be downsized by reclaiming the areas not needed for production operations. The portions of the pad that are not needed for production operations will be re-contoured to its original state as much as possible. The caliche that is removed will be reused to either build another pad site or for road repairs within the lease. The stockpiled topsoil will then be spread out reclaimed area and reseeded with a BLM approved seed mixture. In the event that the well must be worked over or maintained, it may be necessary to drive, park, and/or operate machinery on reclaimed land. This area will be repaired or reclaimed after work is complete.

- B. Final Reclamation: Upon plugging and abandoning the well all caliche for well pad and lease road will be removed and surface will be recountoured to reflect its surroundings as much as possible. Caliche will be recycled for road repair or reused for another well pad within the lease. If any topsoil remains, it will be spread out and the area will be re-seeded with a BLM approved mixture and re-vegetated as per BLM orders. When required by BLM, the well pad site will be restored to match pre-construction grades.

9. Surface Ownership:

- A. The surface is owned by Draper Brantley, 706 Riverside Drive, Carlsbad, NM 88220, (575) 703-3169. The surface is multiple uses with the primary uses of the region for grazing of livestock and the production of oil and gas. The surface owner was notified before staking this well. COG Operating LLC is currently negotiating a Surface Use Agreement with the surface owner.
- B. The proposed road routes and surface location will be restored as directed by the BLM.

10. Other Information:

- A. The area around the well site is grassland and the topsoil is sandy. The vegetation is moderately sparse with native prairie grasses, some mesquite and shinnery oak. No wildlife was observed but it is likely that mule deer, rabbits, coyotes and rodents traverse the area.
- B. There is no permanent or live water in the immediate area.
- C. There are no dwellings within 2 miles of this location.
- D. If needed, a Cultural Resources Examination is being prepared by Boone Arch Services of NM, LLC., 2030 North Canal, Carlsbad, New Mexico, 88220, phone # 575-885-1352 and the results will be forwarded to your office in the near future. Otherwise, **COG will be participating in the Permian Basin MOA Program.**

11. Bond Coverage:

Bond Coverage is Statewide Bonds # NMB000740 and NMB000215

Surface Use Plan
COG Operating LLC
Coachwhip Federal Com #1H
SL: 900' FSL & 2350' FWL UL N
Section 14, T26S, R28E
BHL: 330' FSL & 2210' FWL UL N
Section 23, T26S, R28E
Eddy County, New Mexico

14. Lessee's and Operator's Representative:

The COG Operating LLC representative responsible for assuring compliance with the surface use plan is as follows:

Sheryl Baker
Drilling Superintendent
COG Operating LLC
2208 West Main Street
Artesia, NM 88210
Phone (575) 748-6940 (office)
(432) 934-1873 (cell)

Ray Peterson
Drilling Manager
COG Operating LLC
One Concho Center
600 W Illinois Ave
Midland, TX 79701
Phone (432) 685-4304 (office)
(432) 818-2254 (business)

JAN 11 2016

**PECOS DISTRICT
CONDITIONS OF APPROVAL**

RECEIVED

OPERATOR'S NAME:	COG Operating, LLC.
LEASE NO.:	NMNM-12559
WELL NAME & NO.:	Coachwhip Fed Com 1H
SURFACE HOLE FOOTAGE:	0900' FSL & 2210' FWL
BOTTOM HOLE FOOTAGE	0330' FSL & 2210' FWL Sec. 23, T. 26 S., R 28 E.
LOCATION:	Section 14, T. 26 S., R 28 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Communitization Agreement
 - Cave/Karst
 - Watershed
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
 - Cement Requirements
 - High Cave/Karst
 - Logging Requirements
 - Waste Material and Fluids
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Communitization Agreement

A Communitization Agreement covering the acreage dedicated to this well must be filed for approval with the BLM. The effective date of the agreement shall be prior to any sales. In addition, the well sign shall include the surface and bottom hole lease numbers. If the Communitization Agreement number is known, it shall also be on the sign. If not, it shall be placed on the sign when the sign is replaced.

Cave/Karst Surface Mitigation

The following stipulations will be applied to minimize impacts during construction, drilling and production.

Construction:

In the advent that any underground voids are opened up during construction activities, construction activities will be halted and the BLM will be notified immediately.

No Blasting:

No blasting will be utilized for pad construction. The pad will be constructed and leveled by adding the necessary fill and caliche.

Pad Berming:

The entire perimeter of the well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.

- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g. caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised. (Any access road crossing the berm cannot be lower than the berm height.)

Tank Battery Liners and Berms:

Tank battery locations and all facilities will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

Leak Detection System:

A method of detecting leaks is required. The method could incorporate gauges to measure loss, situating valves and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present. Leak detection plan will be submitted to BLM for approval.

Automatic Shut-off Systems:

Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

Cave/Karst Subsurface Mitigation

The following stipulations will be applied to protect cave/karst and ground water concerns:

Rotary Drilling with Fresh Water:

Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

Directional Drilling:

Kick off for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

Lost Circulation:

ALL lost circulation zones from the surface to the base of the cave occurrence zone will be logged and reported in the drilling report.

Regardless of the type of drilling machinery used, if a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cave-bearing zone, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

Abandonment Cementing:

Upon well abandonment in high cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

Pressure Testing:

Annual pressure monitoring will be performed by the operator on all casing annuli and reported in a sundry notice. If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

Watershed

- The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The berm shall be maintained through the life of the well and after interim reclamation has been completed.
- Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattleguards

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. **Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Water Basin:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

High Cave/Karst

Possibility of water flows in the Salado and Castile.

Possibility of lost circulation in the Rustler and Delaware.

A MINIMUM OF TWO CASING STRINGS CEMENTED TO SURFACE IS REQUIRED IN HIGH CAVE/KARST AREAS. THE CEMENT MUST BE IN A SOLID SHEATH. THEREFORE, ONE INCH OPERATIONS ARE NOT SUFFICIENT TO PROTECT CAVE KARST RESOURCES. A CASING DESIGN THAT HAS A ONE INCH JOB PERFORMED DOES NOT COUNT AS A SOLID SHEATH. IF THE PRIMARY CEMENT JOB ON THE SURFACE CASING DOES NOT CIRCULATE, THEN THE NEXT TWO CASING STRINGS MUST BE CEMENTED TO SURFACE.

1. The 13-3/8 inch surface casing shall be set at approximately 375 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing, which shall be set at approximately 2500 feet (**Lamar Limestone or basal anhydrite of the Castile formation**), is:

☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.**

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

3. The minimum required fill of cement behind the 5-1/2 inch production casing is:

☒ Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification. **Excess calculates to 16% - Additional cement may be required.**

4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M) psi (Installing 2M annular)**.
 - a. **For surface casing only:** If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.
3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 9-5/8 intermediate casing shoe shall be **3000 (3M) psi**.
4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin

after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 081915

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the

largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by

drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 1 for Loamy Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed shall be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed shall be planted using a drill equipped with a depth regulator to ensure proper depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture shall be evenly and uniformly planted over the disturbed area (small/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed shall be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre shall be doubled. The seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

Species	lb/acre
Plains lovegrass (<i>Eragrostis intermedia</i>)	0.5
Sand dropseed (<i>Sporobolus cryptandrus</i>)	1.0
Sideoats grama (<i>Bouteloua curtipendula</i>)	5.0
Plains bristlegrass (<i>Setaria macrostachya</i>)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed