

15-745

NM OIL CONSERVATION
ARTESIA DISTRICT

FEB 17 2016

FORM APPROVED
OMB No. 1004-0137
Expires October 31, 2014

Form 3160-3
(March 2012)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease Serial No. **LC054988B**
LC028793A, LC029342E, LC029342C

6. If Indian, Allottee or Tribe Name
N/A

7. If Unit or CA Agreement, Name and No.
N/A

8. Lease Name and Well No.
Jenkins B Federal Com #24H

9. API Well No.
30-015- **43643**

10. Field and Pool, or Exploratory
Loco Hills; Glorieta Yeso 96718

11. Sec., T. R. M. or Blk. and Survey or Area
Sec 19 & 20, T17S, R30E

12. County or Parish
EDDY

13. State
NM

1a. Type of work: ☒ DRILL ☐ REENTER

1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone

2. Name of Operator COG Operating LLC

3a. Address One Concho Center, 600 W. Illinois Ave
Midland, TX 79701

3b. Phone No. (include area code)
432-685-4384

4. Location of Well (Report location clearly and in accordance with any State requirements.)*

At surface SHL: 2391' FNL & 45' FEL, Sec 19, UL H

At proposed prod. zone BHL: 2311' FNL & 330' FEL, Sec 20, UL H

UNORTHODOX
LOCATION

14. Distance in miles and direction from nearest town or post office*
2.5 miles Northeast of Loco Hills, NM

15. Distance from proposed*
location to nearest
property or lease line, ft.
(Also to nearest drig. unit line, if any)
45'

16. No. of acres in lease
SL: 629.65;
Unit G: 80; BL: 120

17. Spacing Unit dedicated to this well
160

18. Distance from proposed location*
to nearest well, drilling, completed,
applied for, on this lease, ft.
315.6'

19. Proposed Depth
TVD: 5147' MD: 10003'
EOC: 5225' TVD

20. BLM/BIA Bond No. on file
NMB000740; NMB000215

21. Elevations (Show whether DF, KDB, RT, GL, etc.)
3630' GL


22. Approximate date work will start*
12/31/2015

23. Estimated duration
15 Days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, must be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM. |

25. Signature 	Name (Printed/Typed) Kelly J. Holly	Date 05/22/2015
---	--	--------------------

Title
Permitting Tech

Approved by (Signature) Steve Caffey	Name (Printed/Typed)	Date FEB - 8 2016
---	----------------------	-----------------------------

Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE
-------------------------------	--

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.


APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

Roswell Controlled Water Basin


2/18/16

Approval Subject to General Requirements
& Special Stipulations Attached

SEE ATTACHED FOR
CONDITIONS OF APPROVAL

Surface Use Plan
COG Operating, LLC
Jenkins B Federal Com 24H
SL: 2391' FNL & 45' FEL *UL H*
Section 19 T-17-S, R-30-E
BHL: 2311' FNL & 330' FEL *UL H*
Section 20, T-17-S, R-30-E
Eddy County, New Mexico

I hereby certify that I, or persons under my direct supervision, have inspected the drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or COG Operating, LLC, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 12th day of May, 2015.

Signed: Carl Bird

Printed Name: Carl Bird

Position: Sr. Drilling Engineer

Address: One Concho Center, 600 W. Illinois, Midland, Texas 79701

Telephone: (432) 683-7443

Field Representative (if not above signatory): Same

E-mail: cbird@concho.com

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505




Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT


WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-015-43643		² Pool Code 96718		³ Pool Name Loco Hills; Glorieta Yeso					
⁴ Property Code 315789		⁵ Property Name JENKINS B FED COM						⁶ Well Number 24H	
⁷ OGRID NO. 229137		⁸ Operator Name COG OPERATING, LLC						⁹ Elevation 3630'	
¹⁰ Surface Location									
UL or lot no. H	Section 19	Township 17S	Range R30E	Lot Idn	Feet from the 2391	North/South line NORTH	Feet From the 45	East/West line EAST	County EDDY
¹¹ Bottom Hole Location If Different From Surface									
UL or lot no. H	Section 20	Township 17S	Range 30E	Lot Idn	Feet from the 2311	North/South line NORTH	Feet from the 330	East/West line EAST	County EDDY
¹² Dedicated Acres 160		¹³ Joint or Infill		¹⁴ Consolidation Code		¹⁵ Order No.			

No allowable will be assigned to this completion until all interest have been consolidated or a non-standard unit has been approved by the division.

¹⁶ GEODETIC DATA NAD 27 GRID - NM EAST SURFACE LOCATION N 662406.2 - E 601668.8 LAT: 32.82060476° N LONG: 104.00238331° W BOTTOM HOLE N 662501.0 - E 606664.0		CORNER DATA NAD 27 GRID - NM EAST A: FOUND 2 1/2" STEEL PIPE N 659503.6 - E 596529.8 B: FOUND BRASS CAP "1914" N 662139.5 - E 596521.0 C: FOUND BRASS CAP "1914" N 664777.0 - E 596506.9 D: FOUND BRASS CAP "1997" N 664786.3 - E 599063.9 E: FOUND BRASS CAP "1916" N 664796.5 - E 601705.4 F: FOUND BRASS CAP "1916" N 664803.9 - E 604345.3 G: FOUND BRASS CAP "1916" N 664812.6 - E 606985.4		H: ALUM CAP STAMPED "1983" N 662172.0 - E 606994.4 I: ALUM CAP STAMPED "1983" N 659531.9 - E 607003.8 J: FOUND BRASS CAP "1916" N 659524.4 - E 604363.7 K: FOUND BRASS CAP "1916" N 659517.6 - E 601723.6 L: FOUND BRASS CAP "1916" N 659510.7 - E 599083.1 M: FOUND BRASS CAP "1990" N 662157.0 - E 601714.7 1: CALCULATED CORNER N 663476.7 - E 601710.1 2: CALCULATED CORNER N 663492.3 - E 606989.9		¹⁷ OPERATOR CERTIFICATION I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order as required by the division  Kelly J. Holly Printed Name kholly@concho.com E-mail Address	
						¹⁸ SURVEYOR CERTIFICATION I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief. 3-2-15 Date of Survey  Signature and Seal of Professional Surveyor 19680 Certificate Number	

COG OPERATING, LLC
JENKINS B FED COM #24H
(2391' FNL & 45' FEL)
SECTION 19, T17S, R30E
N. M. P. M., EDDY CO., NEW MEXICO



DIRECTIONS TO LOCATION

From the intersection of U. S. Hwy 82 and CR-217 (Hagerman Cutoff);
Go West on U. S. Hwy approx. 0.9 miles to lease road on right;
Turn right on lease road and go North approx. 0.1 miles;
Location is approx. 190 feet West of the lease road.

SCALE: 1" = 100'
0 50 100
BEARINGS ARE
NAD 27 GRID - NM EAST
DISTANCES ARE
GROUND.

Firm No.: TX 10193838 NM 4655451

Copyright 2015 - All Rights Reserved

NO.	REVISION	DATE
JOB NO.:	LS1501009	
DWG. NO.:	1501009PAD	


RRC

308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 100'
DATE: 3-2-15
SURVEYED BY: ML/BC
DRAWN BY: JC
APPROVED BY: RMH
SHEET : 1 OF 1

VICINITY MAP

NOT TO SCALE



SECTION 19, TWP. 17 SOUTH, RGE. 30 EAST,
N. M. P. M., EDDY CO., NEW MEXICO

OPERATOR: COG Operating, LLC
LEASE: Jenkins B Fed Com
WELL NO.: 24H

LOCATION: 2391' FNL & 45' FEL
ELEVATION: 3630'

Firm No.: TX 10193838 NM 4655451

Copyright 2015 - All Rights Reserved


NO.	REVISION	DATE
JOB NO.: LS1501009		
DWG. NO.: 1501009VM		

RRC

308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: NTS
DATE: 3-2-15
SURVEYED BY: ML/BC
DRAWN BY: JC
APPROVED BY: RMH
SHEET : 1 OF 1

LOCATION VERIFICATION MAP



SECTION 19, TWP. 17 SOUTH, RGE. 30 EAST,
N. M. P. M., EDDY CO., NEW MEXICO

OPERATOR: COG Operating, LLC
LEASE: Jenkins B Fed Com
WELL NO.: 24H
ELEVATION: 3630'

LOCATION: 2391' FNL & 45' FEL
CONTOUR INTERVAL: 10'
USGS TOPO. SOURCE MAP:
Red Lake SE, NM (1955)

Firm No.: TX 10193838 NM 4655451

Copyright 2015 - All Rights Reserved

NO.	REVISION	DATE
JOB NO.:	LS1501009	
DWG. NO.:	1501009LVM	

RRC

308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1"=1000'
DATE: 3-2-15
SURVEYED BY: ML/BC
DRAWN BY: JC
APPROVED BY: RMH
SHEET : 1 OF 1

Estimated Distance to Nearest
Wellbore 315.6 ft SW

Jenkins B Federal #24H

Estimated Distance to SHL to
BHL 4974.9 ft



SENM Shelf Area
Jenkins B Federal #24H

SEC. 19, T17S - R30E SHL 2391 FNL 45 FEL, UNIT H
SEC. 20, T17S - R30E SHL 2311 FNL 330 FEL, UNIT H

Author:
Idm

Date:
5 March, 2015

COG Operating LLC
Jenkins B Federal Com #24H

1. Geologic Formations

TVD of target	5225'	Pilot hole depth	NA
MD at TD:	10003'	Deepest expected fresh water:	100'

Back Reef

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target/Zone?	Hazards*
Quaternary Fill	Surface	Fresh Water	
Rustler	283'	Brackish Water	
Top of Salt	508'	Salt	
Tansill	995'	Barren	
Yates	1097'	Oil/Gas	
Seven Rivers	1394'	Oil/Gas	
Queen	2014'	Oil/Gas	
Grayburg	2400'	Oil/Gas	
San Andres	2740'	Oil/Gas	
Glorieta	4183'	Oil/Gas	
Paddock	4253'	Oil/Gas	
Blinberry	4780'	Target	
Tubb	5750'	Will not penetrate	

*H2S, water flows, loss of circulation, abnormal pressures, etc.

2. Casing Program *See COA*

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF	SF	SF
	From	To					Collapse	Burst	Tension
17.5"	0	308' 320	13.375"	48	H40/J55	STC	5.25	3.28	21.78
12.25"	0	1015' 1120	9.625"	40	J55	LTC	4.87	1.58	12.81
8.75"	0	4704'	7.0"	29	L80	LTC	3.17	1.33	2.60
8.75"	4704'	5531'	5.5"	17	L80	LTC	2.55	1.26	3.75
7.875"	5531'	10003'	5.5"	17	L80	LTC	2.55	1.26	7.71
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h BLM standard formulas where used on all SF calculations.
 Assumed 9.2 ppg MW equivalent pore pressure from 9 5/8" shoe to Deepest TVD in wellbore.

COG Operating LLC
Jenkins B Federal Com #24H

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	N
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

3. Cementing Program

Casing	# Sk	Wt. lb/gal	Yld ft ³ /sk	H ₂ O gal/sk	500 psi Comp. Strength (hours)	Slurry Description
Surf.	300	14.8	1.32	6.3	6	Tail: Class C + 2% Cacl ₂ + .25 pps Celloflake
Inter. Single stage	150	11.8	2.45	14.4	72	1 st stage Lead: 50:50:10 C: Poz:Gel w/ 5% Salt + 5 pps Lcm + 0.25 pps Cello flake
	150	14.8	1.32	6.3	6	1 st stage Tail: Class C w/ 2% Cacl ₂
IF DV Tool +/- 338 370						
Inter. Multi-Stage	75	11.8	2.45	14.4	72	1 st stage Lead: 50:50:10 C: Poz:Gel w/ 5% Salt + 5 pps Lcm + 0.25 pps Cello flake
	150	14.8	1.32	6.3	6	1 st stage Tail: Class C w/ 2% Cacl ₂
	150	11.8	2.45	14.4	72	2nd stage Lead: 50:50:10 C: Poz:Gel w/ 5% Salt + 5 pps Lcm + 0.25 pps Cello flake

COG Operating LLC
Jenkins B Federal Com #24H

Prod. Single Stage	500	12.5	2.01	11.4	22	1st stage Lead: 35:65:6 C:Poz Gel w/5% salt + 5 pps LCM + 0.2% SMS + 1% FL-25 + 1% Ba-58+0.3% FL-52A + 0.125 pps CF
	950	14	1.37	6.4	10	1st stage Tail: 50:50:2 C:Pox Gel w/5% salt+3 pps LCM + 0.6% SMS + 1% FL-25 +1% BA-58+ 0.125 pps CF
IF DV/ECP Tool +/- 2840'						
Prod Multi-Stage	425	12.5	2.01	11.4	22	2 nd Stage Lead: 35:65:6 C:Poz Gel w/5% salt+5 pps LCM+0.2% SMS + 1% FL-25+1% BA-58+0.3% FL-52A+ 0.125 pps CF
	150	16.8	.99	4.8	6	2 nd Stage Tail: Class"C" w/0.3% R-3 + 1.5% CD-32
	200	12.5	2.01	11.4	22	1 st stage Lead: 35:65:6 C: PozGel w/5% salt + 5 pp LCM + 0.2% SMS + 1% FL-25+ 1% BA-58 + 0.3% FL-52A + 0.125 pps CF
	950	14	1.37	6.4	10	1 st stage Tail: 50:50:2 C: PozGel w/5% salt + 3 pps LCM + 0.6% SMS + 1% FL-25 + 1% BA-58 + 0.125 pps CF

Casing String	TOC	% Excess
Surface	0'	50%
Intermediate	0'	50%
Production	0'	35%

4. Pressure Control Equipment * See attachment for further details*****

No	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
----	--

BOP installed and tested before drilling which hole?	Size?	Min Required WP	Type	✓	Tested for:
12-1/4"	13-5/8"	2M	Annular	X	2000 psi
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other*		
8-3/4" & 7 7/8"	13-5/8"	2M	Annular	X	2000 psi
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other*		

*Specify if additional ram is utilized.

COG Operating LLC
Jenkins B Federal Com #24H

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

NA	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.	
NA	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.	
	NA	Are anchors required by manufacturer?
NA	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. • Provide description here See attached schematic.	

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	Surf. shoe	FW Gel	8.6-8.8	28-34	N/C
Surf shoe	Int shoe	Saturated Brine	10.0-10.2	28-34	N/C
Int shoe	TD	FW-Cut Brine	8.5-9.2	28-34	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

COG Operating LLC
Jenkins B Federal Com #24H

6. Logging and Testing Procedures *See COA*

Logging, Coring and Testing	
X	Will run Cased hole GR/CNL from KOP to surface. Stated logs run will be in the Completion Report and submitted to the BLM.
No	Open hole logs are planned from KOP to Intermediate casing shoe.
No	Drill stem test? If yes, explain
No	Coring? If yes, explain

Additional logs planned	Interval
Resistivity	Int. shoe to KOP
Density	Int. shoe to KOP
CBL	Production casing
X Mud log	Intermediate shoe to TD
PEX/HRLA/HNGS	Intermediate shoe to KOP

7. Drilling Conditions *See COA*

Condition	Specify what type and where?
BH Pressure at deepest TVD	2300 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions.

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

No	H ₂ S is present <i>Yes</i>
Yes	H ₂ S Plan attached

See COA

8. Other facets of operation

Is this a walking operation? No.

Will be pre-setting casing? No

Attachments:

Directional Plan

Multi-stage Cement details

BOP description

**COG Operating LLC
Jenkins B Federal Com #24H**

Multi-stage Cement details:

Discussion of DV Tool cement options:

9 5/8" DV tool cement option is proposed for approval. This may become necessary if lost circulation occurs while drilling the 12 1/4" intermediate hole. DV tool depth will be based on hole conditions. Cement volumes will be adjusted proportionally. DV Tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe.

7" DV tool cement option is proposed for approval. This may become necessary if water flows in the San Andres are encountered. These water flows normally occur in areas where produced water disposal is happening. This dense cement is used to combat water flows. This cement recipe also has a right angle set time and is mixed a little under saturated so the water flow will be absorbed by cement. DV tool depth will be based on hole conditions. Cement volumes will be adjusted proportionally. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe.

Discussion of Pressure Control Equipment:

Does Not Apply, KBR

A 13 5/8" 3000 psi Double ram BOP or 13 5/8" 3000 psi Hydril type annular preventor will be used depending on the rig selected.

The majority of the rigs currently in use by COG have 13 5/8" 3000 psi BOPs (double ram or hydril type) but due to the vagaries of rig scheduling one of the few rigs with 11" BOPs might be used if the intermediate hole size is 11"; therefore, COG Operating LLC requests variance to the requirement of 13 5/8" BOPS on 13 3/8" casing. When the circumstance occurs that a 11" BOP is used on 13 3/8" casing a special flange will be utilized to allow testing the entire BOP with a test plug, without subjecting the casing to test pressure. The special flange also allows return to full-open capability if desired.

In every case COG Operating LLC will use BOP equipment which will meet or exceed well control requirements of Onshore Oil and Gas Order No. 2.

GEG 4/22/15



EXTRA COPY

COG Operating LLC

Eddy County, NM (NAD-27 2015)

Jenkins B Fed Com #24H

SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H

PP: 2311' FNL, 372' FWL, Sec 20, T17S, R30E, Unit E

BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H

Design #1

Anticollision Report

28 January, 2016



Company:	COG Operating LLC	Local Co-ordinate Reference:	Well SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H
Project:	Eddy County, NM (NAD-27 2015)	TVD Reference:	KB @ 3648.00usft (Silver Oak 3)
Reference Site:	Jenkins B Fed Com #24H	MD Reference:	KB @ 3648.00usft (Silver Oak 3)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at:	2.00 sigma
Reference Wellbore:	BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design W.D. McIntyre "C" #7 - W.D. McIntyre "C" #7 - OH - OH														Offset Site Error:	0.00 usft
Survey Program: 1465-MWD														Offset Well Error:	0.00 usft
Reference	Offset	Semi Major Axis	Distance	Measured Depth	Vertical Depth	Reference	Offset	Highside Toolface	Offset Wellbore Centre	Between Centres	Between Ellipses	Minimum Separation	Separation Factor	Warning	
(usft)	(usft)	(usft)	(usft)	(usft)	(usft)	(usft)	(usft)	(°)	N-S (usft)	E-W (usft)	(usft)	(usft)	(usft)		
2,200.00	2,200.00	1,918.69	1,918.38	4.81	0.95	88.86	97.26	4,883.44	4,892.40	4,886.67	5.73	853.203			
2,300.00	2,300.00	2,016.40	2,015.93	5.04	1.18	88.87	96.47	4,889.00	4,898.08	4,891.92	6.17	794.021			
2,400.00	2,400.00	2,114.00	2,113.37	5.26	1.39	88.87	96.40	4,894.65	4,903.86	4,897.27	6.59	743.948			
2,500.00	2,500.00	2,176.00	2,175.25	5.49	1.53	88.87	96.76	4,898.47	4,910.04	4,903.10	6.94	706.992			
2,600.00	2,600.00	2,265.49	2,264.53	5.71	1.75	88.86	97.95	4,904.51	4,916.81	4,909.45	7.36	667.777			
2,700.00	2,700.00	2,382.11	2,380.87	5.94	2.02	88.83	100.11	4,912.24	4,923.48	4,915.65	7.84	628.329			
2,800.00	2,800.00	2,440.98	2,439.60	6.16	2.16	88.83	100.47	4,916.22	4,930.29	4,922.11	8.18	602.448			
2,900.00	2,900.00	2,501.53	2,499.97	6.39	2.31	88.83	100.30	4,920.92	4,938.01	4,929.47	8.54	578.483			
3,000.00	3,000.00	2,644.38	2,642.36	6.61	2.66	88.87	97.50	4,931.83	4,945.60	4,936.53	9.07	545.165			
3,100.00	3,100.00	2,702.11	2,699.92	6.84	2.80	88.86	96.26	4,936.14	4,953.10	4,943.69	9.42	526.074			
3,200.00	3,200.00	2,764.00	2,761.57	7.06	2.95	88.88	96.36	4,941.62	4,961.79	4,952.02	9.77	507.939			
3,300.00	3,300.00	2,839.58	2,836.80	7.28	3.15	88.88	96.78	4,948.78	4,971.16	4,961.01	10.15	489.581			
3,400.00	3,400.00	2,952.33	2,949.08	7.51	3.43	88.89	95.98	4,959.08	4,980.28	4,969.66	10.62	468.884			
3,500.00	3,500.00	3,132.17	3,128.30	7.73	3.87	88.90	95.71	4,973.93	4,988.57	4,977.34	11.23	444.072			
3,600.00	3,600.00	3,618.78	3,614.30	7.96	4.93	88.93	93.61	4,994.00	4,994.90	4,982.40	12.50	399.672			
3,700.00	3,700.00	3,726.49	3,722.01	8.18	5.14	88.93	93.14	4,993.49	4,994.42	4,981.48	12.94	365.902			
3,800.00	3,800.00	3,827.50	3,823.02	8.41	5.32	88.93	93.04	4,992.93	4,993.86	4,980.49	13.37	373.432			
3,869.52	3,869.52	3,872.00	3,867.52	8.56	5.41	88.93	93.20	4,992.81	4,993.68	4,980.06	13.62	366.607			
3,900.00	3,900.00	3,896.17	3,891.68	8.63	5.45	88.93	93.32	4,992.83	4,993.70	4,979.96	13.74	363.465			
4,000.00	4,000.00	4,017.25	4,012.76	8.86	5.69	88.92	93.91	4,992.90	4,993.81	4,979.60	14.21	351.408			
4,100.00	4,100.00	4,170.32	4,165.82	9.08	5.98	88.91	94.61	4,991.38	4,992.74	4,977.99	14.75	338.485			
4,200.00	4,200.00	4,255.37	4,250.87	9.31	6.14	88.91	94.66	4,990.28	4,991.46	4,976.31	15.15	329.443			
4,300.00	4,300.00	4,333.00	4,329.49	9.53	6.29	88.91	95.22	4,989.50	4,990.50	4,974.97	15.54	321.224			
4,361.23	4,361.23	4,363.74	4,359.23	9.67	6.35	88.90	95.50	4,989.34	4,990.25	4,974.52	15.74	317.074			
4,400.00	4,400.00	4,395.00	4,390.49	9.76	6.41	88.90	95.62	4,989.50	4,990.42	4,974.53	15.89	314.059			
4,500.00	4,500.00	4,438.40	4,433.88	9.98	6.50	88.90	95.69	4,990.00	4,991.33	4,975.13	16.21	307.999			
4,600.00	4,600.00	4,532.67	4,528.15	10.21	6.69	88.90	95.82	4,991.37	4,992.78	4,976.15	16.63	300.306			
4,704.21	4,704.21	4,652.54	4,648.00	10.44	6.94	88.90	95.80	4,992.83	4,994.04	4,976.93	17.11	291.852			
4,750.00	4,749.94	4,700.62	4,696.09	10.54	7.04	9.99	95.77	4,993.33	4,992.54	4,975.23	17.31	288.406			
4,800.00	4,799.46	4,750.81	4,746.27	10.64	7.15	10.13	95.71	4,993.85	4,986.38	4,968.86	17.52	284.596			
4,850.00	4,848.10	4,799.81	4,795.26	10.75	7.25	10.37	95.61	4,994.36	4,975.57	4,957.84	17.73	280.626			
4,900.00	4,895.42	4,847.36	4,842.81	10.87	7.35	10.73	95.51	4,994.84	4,960.20	4,942.26	17.94	276.537			
4,950.00	4,940.98	4,900.32	4,895.78	11.00	7.45	11.24	95.40	4,995.36	4,940.40	4,922.25	18.15	272.133			
5,000.00	4,984.36	4,953.00	4,948.45	11.16	7.56	11.92	95.32	4,995.77	4,916.30	4,897.93	18.37	267.630			
5,050.00	5,025.15	4,987.74	4,983.19	11.36	7.64	12.78	95.27	4,996.03	4,888.18	4,869.64	18.54	263.600			
5,100.00	5,063.00	4,997.00	4,992.45	11.61	7.65	13.84	95.25	4,996.11	4,856.45	4,837.79	18.66	260.222			
5,150.00	5,097.54	4,997.00	4,992.45	11.92	7.65	15.19	95.25	4,996.11	4,821.52	4,802.77	18.76	257.027			
5,200.00	5,128.45	4,997.00	4,992.45	12.32	7.65	16.85	95.25	4,996.11	4,783.67	4,764.82	18.85	253.761			
5,250.00	5,155.47	4,997.00	4,992.45	12.81	7.65	19.32	95.25	4,996.11	4,743.17	4,724.24	18.94	250.439			
5,300.00	5,178.32	4,997.00	4,992.45	13.40	7.65	22.59	95.25	4,996.11	4,700.34	4,681.32	19.02	247.079			
5,350.00	5,196.81	4,997.00	4,992.45	14.08	7.65	27.29	95.25	4,996.11	4,655.51	4,636.41	19.10	243.700			
5,400.00	5,210.77	4,997.00	4,992.45	14.86	7.65	34.40	95.25	4,996.11	4,609.05	4,589.87	19.18	240.318			
5,450.00	5,220.06	4,997.00	4,992.45	15.71	7.65	45.73	95.25	4,996.11	4,561.32	4,542.07	19.25	236.951			
5,500.00	5,224.60	4,997.00	4,992.45	16.64	7.65	64.10	95.25	4,996.11	4,512.75	4,493.44	19.32	233.614			
5,531.48	5,225.00	4,997.00	4,992.45	17.24	7.65	79.91	95.25	4,996.11	4,481.93	4,462.57	19.36	231.524			
5,600.00	5,223.80	4,997.00	4,992.45	18.63	7.65	77.79	95.25	4,996.11	4,414.54	4,395.09	19.44	227.051			
5,700.00	5,222.05	4,997.00	4,992.45	20.81	7.65	72.44	95.25	4,996.11	4,315.54	4,295.98	19.56	220.667			
5,800.00	5,220.30	4,997.00	4,992.45	23.11	7.65	59.61	95.25	4,996.11	4,215.99	4,196.35	19.64	214.633			
5,900.00	5,218.56	4,997.00	4,992.45	25.49	7.65	15.43	95.25	4,996.11	4,116.13	4,096.45	19.69	209.074			


Company:	COG Operating LLC	Local Co-ordinate Reference:	Well SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H
Project:	Eddy County, NM (NAD-27 2015)	TVD Reference:	KB @ 3648.00usft (Silver Oak 3)
Reference Site:	Jenkins B Fed Com #24H	MD Reference:	KB @ 3648.00usft (Silver Oak 3)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore:	BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design W.D. McIntyre "C" #7 - W.D. McIntyre "C" #7 - OH - OH														Offset Site Error:
Survey Program: 1485-MWD														Offset Well Error: 0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Semi Major Axis (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
5,919.81	5,218.21	4,997.00	4,992.45	25.97	7.65	-0.17		95.25	4,996.11	4,096.34	4,076.64	19.69	208.032	
6,000.00	5,216.82	4,997.00	4,992.45	27.93	7.65	-0.17		95.25	4,996.11	4,016.20	3,996.50	19.70	203.874	
6,100.00	5,215.08	4,997.00	4,992.45	30.41	7.65	-0.17		95.25	4,996.11	3,916.28	3,896.57	19.71	198.686	
6,200.00	5,213.34	4,997.00	4,992.45	32.94	7.65	-0.17		95.25	4,996.11	3,816.36	3,796.63	19.72	193.495	
6,300.00	5,211.60	4,997.00	4,992.45	35.51	7.65	-0.17		95.25	4,996.11	3,716.44	3,696.70	19.74	188.301	
6,400.00	5,209.86	4,997.00	4,992.45	38.10	7.65	-0.17		95.25	4,996.11	3,616.52	3,596.77	19.75	183.106	
6,500.00	5,208.12	4,997.00	4,992.45	40.72	7.65	-0.17		95.25	4,996.11	3,516.62	3,496.85	19.77	177.908	
6,600.00	5,206.38	4,997.00	4,992.45	43.35	7.65	-0.17		95.25	4,996.11	3,416.71	3,396.93	19.78	172.710	
6,700.00	5,204.64	4,997.00	4,992.45	46.00	7.65	-0.17		95.25	4,996.11	3,316.82	3,297.01	19.80	167.511	
6,800.00	5,202.90	4,997.00	4,992.45	48.66	7.65	-0.17		95.25	4,996.11	3,216.92	3,197.11	19.82	162.312	
6,900.00	5,201.16	4,997.00	4,992.45	51.33	7.65	-0.17		95.25	4,996.11	3,117.04	3,097.20	19.84	157.112	
7,000.00	5,199.42	4,997.00	4,992.45	54.01	7.65	-0.17		95.25	4,996.11	3,017.16	2,997.30	19.86	151.913	
7,100.00	5,197.68	4,997.00	4,992.45	56.69	7.65	-0.17		95.25	4,996.11	2,917.30	2,897.41	19.88	146.715	
7,200.00	5,195.94	4,997.00	4,992.45	59.39	7.65	-0.17		95.25	4,996.11	2,817.44	2,797.53	19.91	141.518	
7,300.00	5,194.19	4,997.00	4,992.45	62.09	7.65	-0.17		95.25	4,996.11	2,717.59	2,697.66	19.94	136.323	
7,400.00	5,192.45	4,997.00	4,992.45	64.79	7.65	-0.17		95.25	4,996.11	2,617.75	2,597.79	19.96	131.129	
7,500.00	5,190.71	4,997.00	4,992.45	67.50	7.65	-0.17		95.25	4,996.11	2,517.93	2,497.94	19.99	125.937	
7,600.00	5,188.97	4,997.00	4,992.45	70.22	7.65	-0.17		95.25	4,996.11	2,418.12	2,398.10	20.03	120.748	
7,700.00	5,187.23	4,997.00	4,992.45	72.93	7.65	-0.17		95.25	4,996.11	2,318.33	2,298.27	20.06	115.561	
7,800.00	5,185.49	4,997.00	4,992.45	75.65	7.65	-0.17		95.25	4,996.11	2,218.56	2,198.46	20.10	110.378	
7,900.00	5,183.75	4,997.00	4,992.45	78.38	7.65	-0.17		95.25	4,996.11	2,118.80	2,098.66	20.14	105.197	
8,000.00	5,182.01	4,997.00	4,992.45	81.10	7.65	-0.17		95.25	4,996.11	2,019.08	1,998.89	20.19	100.020	
8,100.00	5,180.27	4,997.00	4,992.45	83.83	7.65	-0.17		95.25	4,996.11	1,919.38	1,899.14	20.24	94.845	
8,200.00	5,178.53	4,997.00	4,992.45	86.56	7.65	-0.17		95.25	4,996.11	1,819.71	1,799.42	20.29	89.674	
8,300.00	5,176.79	4,997.00	4,992.45	89.29	7.65	-0.17		95.25	4,996.11	1,720.08	1,699.73	20.35	84.507	
8,400.00	5,175.05	4,997.00	4,992.45	92.02	7.65	-0.17		95.25	4,996.11	1,620.50	1,600.08	20.42	79.342	
8,500.00	5,173.31	4,997.00	4,992.45	94.76	7.65	-0.17		95.25	4,996.11	1,520.98	1,500.47	20.50	74.181	
8,600.00	5,171.57	4,997.00	4,992.45	97.49	7.65	-0.17		95.25	4,996.11	1,421.51	1,400.92	20.59	69.022	
8,700.00	5,169.83	4,997.00	4,992.45	100.23	7.65	-0.17		95.25	4,996.11	1,322.14	1,301.43	20.70	63.866	
8,800.00	5,168.09	4,997.00	4,992.45	102.97	7.65	-0.17		95.25	4,996.11	1,222.86	1,202.03	20.83	58.712	
8,900.00	5,166.35	4,997.00	4,992.45	105.71	7.65	-0.17		95.25	4,996.11	1,123.71	1,102.73	20.98	53.560	
9,000.00	5,164.61	4,997.00	4,992.45	108.45	7.65	-0.17		95.25	4,996.11	1,024.72	1,003.56	21.17	48.408	
9,100.00	5,162.87	4,997.00	4,992.45	111.19	7.65	-0.17		95.25	4,996.11	925.96	904.55	21.40	43.259	
9,200.00	5,161.13	4,997.00	4,992.45	113.94	7.65	-0.17		95.25	4,996.11	827.49	805.78	21.71	38.113	
9,300.00	5,159.39	4,997.00	4,992.45	116.68	7.65	-0.17		95.25	4,996.11	729.44	707.31	22.12	32.974	
9,400.00	5,157.65	4,997.00	4,992.45	119.42	7.65	-0.17		95.25	4,996.11	631.99	609.30	22.69	27.852	
9,500.00	5,155.91	4,997.00	4,992.45	122.17	7.65	-0.17		95.25	4,996.11	535.50	511.98	23.52	22.771	
9,600.00	5,154.17	4,997.00	4,992.45	124.91	7.65	-0.17		95.25	4,996.11	440.56	415.79	24.77	17.783	
9,700.00	5,152.43	4,997.00	4,992.45	127.66	7.65	-0.17		95.25	4,996.11	348.47	321.68	26.79	13.006	
9,800.00	5,150.69	4,997.00	4,992.45	130.41	7.65	-0.17		95.25	4,996.11	262.25	232.09	30.15	8.698	
9,900.00	5,148.95	4,997.00	4,992.45	133.15	7.65	-0.17		95.25	4,996.11	190.03	154.80	35.23	5.394	
10,009.75	5,147.04	4,997.00	4,992.45	136.17	7.65	-0.17		95.25	4,996.11	152.60	114.08	38.52	3.962 CC, ES, SF	

Company:	COG Operating LLC	Local Co-ordinate Reference:	Well SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H
Project:	Eddy County, NM (NAD-27 2015)	TVD Reference:	KB @ 3648.00usft (Silver Oak 3)
Reference Site:	Jenkins B Fed Com #24H	MD Reference:	KB @ 3648.00usft (Silver Oak 3)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore:	BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to KB @ 3648.00usft (Silver Oak 3)
Offset Depths are relative to Offset Datum
Central Meridian is 104° 20' 0.000 W


Coordinates are relative to: SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H
Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30
Grid Convergence at Surface is: 0.18°



Company:	COG Operating LLC	Local Co-ordinate Reference:	Well SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H
Project:	Eddy County, NM (NAD-27 2015)	TVD Reference:	KB @ 3648.00usft (Silver Oak 3)
Reference Site:	Jenkins B Fed Com #24H	MD Reference:	KB @ 3648.00usft (Silver Oak 3)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at:	2.00 sigma
Reference Wellbore:	BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to KB @ 3648.00usft (Silver Oak 3)
Offset Depths are relative to Offset Datum
Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H
Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30
Grid Convergence at Surface is: 0.18°





COG Operating LLC

Eddy County, NM (NAD-27 2015)

Jenkins B Fed Com #24H

SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H

PP: 2311' FNL, 372' FWL, Sec 20, T17S, R30E, Unit E

BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H

Plan: Design #1

Standard Planning Report

28 January, 2016



Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H
Company:	COG Operating LLC	TVD Reference:	KB @ 3648.00usft (Silver Oak 3)
Project:	Eddy County, NM (NAD-27 2015)	MD Reference:	KB @ 3648.00usft (Silver Oak 3)
Site:	Jenkins B Fed Com #24H	North Reference:	Grid
Well:	SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H		
Design:	Design #1		

Project:	Eddy County, NM (NAD-27 2015)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site:	Jenkins B Fed Com #24H		
Site Position:		Northing:	662,406.20 usft
From:	Map	Easting:	601,668.80 usft
Position Uncertainty:	0.00 usft	Slot Radius:	13.20 in
		Latitude:	32° 49' 14.177 N
		Longitude:	104° 0' 8.580 W
		Grid Convergence:	0.18 °

Well:	SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H					
Well Position	+N/-S	0.00 usft	Northing:	662,406.20 usft	Latitude:	32° 49' 14.177 N
	+E/-W	0.00 usft	Easting:	601,668.80 usft	Longitude:	104° 0' 8.580 W
Position Uncertainty		0.00 usft	Wellhead Elevation:	0.00 usft	Ground Level:	3,630.00 usft

Wellbore:	BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H		
-----------	--	--	--

Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
			(°)	(°)	(nT)
	IGRF2015	1/27/2016	7.35	60.56	48,388

Design:	Design #1		
---------	-----------	--	--

Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00

Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction
	(usft)	(usft)	(usft)	(°)
	0.00	0.00	0.00	88.91

Plan Sections	Measured Depth	Inclination	Azimuth	Vertical Depth	+N/-S	+E/-W	Dogleg Rate	Build Rate	Turn Rate	TFO	Target
	(usft)	(°)	(°)	(usft)	(usft)	(usft)	(°/100usft)	(°/100usft)	(°/100usft)	(°)	
	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	4,704.21	0.00	0.00	4,704.21	0.00	0.00	0.00	0.00	0.00	0.00	
	5,531.48	91.00	78.94	5,225.00	101.67	520.12	11.00	11.00	0.00	78.94	
	5,919.81	91.00	90.59	5,218.21	137.03	906.10	3.00	0.00	3.00	89.91	
	10,009.75	91.00	90.59	5,147.04	94.80	4,995.20	0.00	0.00	0.00	0.00	PBHL (JBFC #24H/L1

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H
Company:	COG Operating LLC	TVD Reference:	KB @ 3648.00usft (Silver Oak 3)
Project:	Eddy County, NM (NAD-27 2015)	MD Reference:	KB @ 3648.00usft (Silver Oak 3)
Site:	Jenkins B Fed Com #24H	North Reference:	Grid
Well:	SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00
4,100.00	0.00	0.00	4,100.00	0.00	0.00	0.00	0.00	0.00	0.00
4,200.00	0.00	0.00	4,200.00	0.00	0.00	0.00	0.00	0.00	0.00
4,300.00	0.00	0.00	4,300.00	0.00	0.00	0.00	0.00	0.00	0.00
4,400.00	0.00	0.00	4,400.00	0.00	0.00	0.00	0.00	0.00	0.00
4,500.00	0.00	0.00	4,500.00	0.00	0.00	0.00	0.00	0.00	0.00
4,600.00	0.00	0.00	4,600.00	0.00	0.00	0.00	0.00	0.00	0.00
4,704.21	0.00	0.00	4,704.21	0.00	0.00	0.00	0.00	0.00	0.00
KOP - Start Build 11.00									
4,750.00	5.04	78.94	4,749.94	0.39	1.97	1.98	11.00	11.00	0.00
4,800.00	10.54	78.94	4,799.46	1.68	8.62	8.65	11.00	11.00	0.00

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H
Company:	COG Operating LLC	TVD Reference:	KB @ 3648.00usft (Silver Oak 3)
Project:	Eddy County, NM (NAD-27 2015)	MD Reference:	KB @ 3648.00usft (Silver Oak 3)
Site:	Jenkins B Fed Com #24H	North Reference:	Grid
Well:	SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H		
Design:	Design #1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	N-S (usft)	E-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,850.00	16.04	78.94	4,848.10	3.89	19.89	19.96	11.00	11.00	0.00
4,900.00	21.54	78.94	4,895.42	6.98	35.69	35.82	11.00	11.00	0.00
4,950.00	27.04	78.94	4,940.98	10.92	55.87	56.06	11.00	11.00	0.00
5,000.00	32.54	78.94	4,984.36	15.68	80.23	80.52	11.00	11.00	0.00
5,050.00	38.04	78.94	5,025.15	21.22	108.57	108.95	11.00	11.00	0.00
5,100.00	43.54	78.94	5,063.00	27.49	140.61	141.11	11.00	11.00	0.00
5,150.00	49.04	78.94	5,097.54	34.42	176.07	176.69	11.00	11.00	0.00
5,200.00	54.54	78.94	5,128.45	41.95	214.61	215.37	11.00	11.00	0.00
5,250.00	60.04	78.94	5,155.47	50.02	255.88	256.79	11.00	11.00	0.00
5,300.00	65.54	78.94	5,178.32	58.54	299.51	300.56	11.00	11.00	0.00
5,350.00	71.04	78.94	5,196.81	67.45	345.08	346.30	11.00	11.00	0.00
5,400.00	76.54	78.94	5,210.77	76.66	392.18	393.56	11.00	11.00	0.00
5,450.00	82.04	78.94	5,220.06	86.08	440.38	441.93	11.00	11.00	0.00
5,500.00	87.54	78.94	5,224.60	95.63	489.23	490.95	11.00	11.00	0.00
5,531.48	91.00	78.94	5,225.00	101.67	520.12	521.95	11.00	11.00	0.00
EOC/TURN - Start DLS 3.00 TFO 89.91									
5,600.00	91.00	81.00	5,223.80	113.60	587.57	589.62	3.00	0.00	3.00
5,700.00	91.00	84.00	5,222.05	126.66	686.69	688.97	3.00	0.00	3.00
5,800.00	91.00	87.00	5,220.30	134.51	786.36	788.77	3.00	0.00	3.00
5,900.00	91.00	90.00	5,218.56	137.13	886.29	888.74	3.00	0.00	3.00
5,919.81	91.00	90.59	5,218.21	137.03	906.10	908.54	3.00	-0.01	3.00
END TURN - Start 4089.93 hold at 5919.81 MD									
6,000.00	91.00	90.59	5,216.82	136.20	986.27	988.68	0.00	0.00	0.00
6,100.00	91.00	90.59	5,215.08	135.17	1,086.25	1,088.62	0.00	0.00	0.00
6,200.00	91.00	90.59	5,213.34	134.13	1,186.23	1,188.57	0.00	0.00	0.00
6,300.00	91.00	90.59	5,211.60	133.10	1,286.21	1,288.51	0.00	0.00	0.00
6,400.00	91.00	90.59	5,209.86	132.07	1,386.19	1,388.45	0.00	0.00	0.00
6,500.00	91.00	90.59	5,208.12	131.04	1,486.17	1,488.39	0.00	0.00	0.00
6,600.00	91.00	90.59	5,206.38	130.00	1,586.15	1,588.33	0.00	0.00	0.00
6,700.00	91.00	90.59	5,204.64	128.97	1,686.13	1,688.28	0.00	0.00	0.00
6,800.00	91.00	90.59	5,202.90	127.94	1,786.11	1,788.22	0.00	0.00	0.00
6,900.00	91.00	90.59	5,201.16	126.91	1,886.09	1,888.16	0.00	0.00	0.00
7,000.00	91.00	90.59	5,199.42	125.87	1,986.07	1,988.10	0.00	0.00	0.00
7,100.00	91.00	90.59	5,197.68	124.84	2,086.05	2,088.04	0.00	0.00	0.00
7,200.00	91.00	90.59	5,195.94	123.81	2,186.03	2,187.98	0.00	0.00	0.00
7,300.00	91.00	90.59	5,194.19	122.78	2,286.01	2,287.93	0.00	0.00	0.00
7,400.00	91.00	90.59	5,192.45	121.74	2,385.99	2,387.87	0.00	0.00	0.00
7,500.00	91.00	90.59	5,190.71	120.71	2,485.97	2,487.81	0.00	0.00	0.00
7,600.00	91.00	90.59	5,188.97	119.68	2,585.95	2,587.75	0.00	0.00	0.00
7,700.00	91.00	90.59	5,187.23	118.65	2,685.93	2,687.69	0.00	0.00	0.00
7,800.00	91.00	90.59	5,185.49	117.61	2,785.91	2,787.64	0.00	0.00	0.00
7,900.00	91.00	90.59	5,183.75	116.58	2,885.89	2,887.58	0.00	0.00	0.00
8,000.00	91.00	90.59	5,182.01	115.55	2,985.87	2,987.52	0.00	0.00	0.00
8,100.00	91.00	90.59	5,180.27	114.52	3,085.84	3,087.46	0.00	0.00	0.00
8,200.00	91.00	90.59	5,178.53	113.48	3,185.82	3,187.40	0.00	0.00	0.00
8,300.00	91.00	90.59	5,176.79	112.45	3,285.80	3,287.35	0.00	0.00	0.00
8,400.00	91.00	90.59	5,175.05	111.42	3,385.78	3,387.29	0.00	0.00	0.00
8,500.00	91.00	90.59	5,173.31	110.39	3,485.76	3,487.23	0.00	0.00	0.00
8,600.00	91.00	90.59	5,171.57	109.35	3,585.74	3,587.17	0.00	0.00	0.00
8,700.00	91.00	90.59	5,169.83	108.32	3,685.72	3,687.11	0.00	0.00	0.00
8,800.00	91.00	90.59	5,168.09	107.29	3,785.70	3,787.06	0.00	0.00	0.00

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H
Company:	COG Operating LLC	TVD Reference:	KB @ 3648.00usft (Silver Oak 3)
Project:	Eddy County, NM (NAD-27 2015)	MD Reference:	KB @ 3648.00usft (Silver Oak 3)
Site:	Jenkins B Fed Com #24H	North Reference:	Grid
Well:	SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H		
Design:	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
8,900.00	91.00	90.59	5,166.35	106.26	3,885.68	3,887.00	0.00	0.00	0.00	
9,000.00	91.00	90.59	5,164.61	105.22	3,985.66	3,986.94	0.00	0.00	0.00	
9,100.00	91.00	90.59	5,162.87	104.19	4,085.64	4,086.88	0.00	0.00	0.00	
9,200.00	91.00	90.59	5,161.13	103.16	4,185.62	4,186.82	0.00	0.00	0.00	
9,300.00	91.00	90.59	5,159.39	102.13	4,285.60	4,286.77	0.00	0.00	0.00	
9,400.00	91.00	90.59	5,157.65	101.10	4,385.58	4,386.71	0.00	0.00	0.00	
9,500.00	91.00	90.59	5,155.91	100.06	4,485.56	4,486.65	0.00	0.00	0.00	
9,600.00	91.00	90.59	5,154.17	99.03	4,585.54	4,586.59	0.00	0.00	0.00	
9,700.00	91.00	90.59	5,152.43	98.00	4,685.52	4,686.53	0.00	0.00	0.00	
9,800.00	91.00	90.59	5,150.69	96.97	4,785.50	4,786.48	0.00	0.00	0.00	
9,900.00	91.00	90.59	5,148.95	95.93	4,885.48	4,886.42	0.00	0.00	0.00	
10,009.75	91.00	90.59	5,147.04	94.80	4,995.20	4,996.10	0.00	0.00	0.00	
TD at 10009.75										

Design Targets										
Target Name	Dip Angle (°)	Dip Dir (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude	
KOP (JBFC #24H/L1 De - plan hits target center - Point	0.00	0.00	4,704.21	0.00	0.00	662,406.20	601,668.80	32° 49' 14.177 N	104° 0' 8.580 W	
PBHL (JBFC #24H/L1) - plan hits target center - Point	0.00	0.00	5,147.04	94.80	4,995.20	662,501.00	606,664.00	32° 49' 14.956 N	103° 59' 10.040 W	
PP (JBFC #24H/L1 Desi - plan hits target center - Point	0.00	0.00	5,216.15	81.50	416.94	662,487.70	602,085.74	32° 49' 14.970 N	104° 0' 3.691 W	
END OF TURN (JBFC # - plan hits target center - Point	0.00	0.00	5,218.21	137.03	906.10	662,543.23	602,574.90	32° 49' 15.504 N	103° 59' 57.957 W	
EOC (JBFC #24H/L1 De - plan hits target center - Point	0.00	0.00	5,225.00	101.67	520.12	662,507.87	602,188.92	32° 49' 15.167 N	104° 0' 2.481 W	

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
4,704.21	4,704.21	0.00	0.00	KOP - Start Build 11.00	
5,531.48	5,225.00	101.67	520.12	EOC/TURN - Start DLS 3.00 TFO 89.91	
5,919.81	5,218.21	137.03	906.10	END TURN - Start 4089.93 hold at 5919.81 MD	
10,009.75	5,147.04	94.80	4,995.20	TD at 10009.75	






COG Operating LLC
Project: Eddy County, NM (NAD-27 2015)
Site: Jenkins B Fed Com #24H

Well: SHL: 2391' FNL, 45' FEL, Sec 20, T17S, R30E, Unit H
Wellbore: BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H

Plan: Design #1 (SHL: 2391' FNL, 45' FEL, Sec 19, T17S, R30E, Unit H/BHL: 2311' FNL, 330' FEL, Sec 20, T17S, R30E, Unit H)

Section Details

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Target
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2	4704.21	0.00	0.00	4704.21	0.00	0.00	0.00	0.00	0.00	
3	5531.48	91.00	78.94	5225.00	101.67	520.12	11.00	78.94	521.95	
4	5919.81	91.00	90.59	5218.21	137.03	906.10	3.00	89.91	908.54	PBHL (JBFC #24H/L1)
5	10009.75	91.00	90.59	5147.04	94.80	4995.20	0.00	0.00	4996.10	PBHL (JBFC #24H/L1)



Ground Elevation: 3630.00
RKB Elevation: KB @ 3648.00usft (Silver Oak 3)

Northing 662406.20
Easting 601668.80
Latitude 32° 49' 14.177 N
Longitude 104° 0' 8.560 W

Vertical Section at 88.91° (200 usft/in)




Terra Directional Services LLC
3705 South County Road 1210, Midland, TX 79706
Phone: 432-618-1210

PROJECT DETAILS: Eddy County, NM (NAD-27 2015)
Geodetic System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone: New Mexico East 3001
System Datum: Mean Sea Level
Local North: Grid

Exhibit #10



(Choke Manifold Schematic same as Exhibit #9)



COG Operating LLC

Exhibit #9

BOPE and Choke Schematic



NOTES REGARDING THE BLOWOUT PREVENTERS
Master Drilling Plan
Eddy County, New Mexico

1. Drilling nipple to be so constructed that it can be removed without use of a welder through rotary table opening, with minimum I.D. equal to preventer bore.
2. Wear ring to be properly installed in head.
3. Blow out preventer and all fittings must be in good condition, 2000 psi WP minimum.
4. All fittings to be flanged.
5. Safety valve must be available on rig floor at all times with proper connections, valve to be full 2000 psi WP minimum.
6. All choke and fill lines to be securely anchored especially ends of choke lines.
7. Equipment through which bit must pass shall be at least as large as the diameter of the casing being drilled through.
8. Kelly cock on Kelly.
9. Extension wrenches and hands wheels to be properly installed.
10. Blow out preventer control to be located as close to driller's position as feasible.
11. Blow out preventer closing equipment to include minimum 40-gallon accumulator, two independent sources of pump power on each closing unit installation all API specifications.

Closed Loop Operation & Maintenance Procedure

All drilling fluid circulated over shaker(s) with cuttings discharged into roll off container.

Fluid and fines below shaker(s) are circulated with transfer pump through centrifuge(s) or solids separator with cuttings and fines discharged into roll off container.

Fluid is continuously re-circulated through equipment with polymer added to aid separation of cutting fines.

Roll off containers are lined and de-watered with fluids re-circulated into system.

Additional tank is used to capture unused drilling fluid or cement returns from casing jobs.

This equipment will be maintained 24 hrs./day by solids control personnel and or rig crews that stay on location.

Cuttings will be hauled to either:

CRI (permit number R9166)


or

GMI (permit number 711-019-001)

dependent upon which rig is available to drill this well.

COG Operating LLC

Closed Loop Equipment Diagram



COG Operating LLC

Hydrogen Sulfide Drilling Operation Plan

I. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H₂S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H₂S on metal components. If high tensile tubular are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H₂S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan. **The concentrations of H₂S of wells in this area from surface to TD are low enough that a contingency plan is not required.**

II. H2S SAFETY EQUIPMENT AND SYSTEMS

Note: All H2S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonable expected to contain H2S.

1. Well Control Equipment:

- A. Flare line.
- B. Choke manifold with minimum of one remotely operated choke.
- C. Closed Loop Blow Down Tank
- D. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
- E. Auxiliary equipment may include if applicable: mud-gas separator, annular preventer & rotating head.

2. Protective equipment for essential personnel:

- A. SCBA (Self contained breathing apparatus) 30-minute units located in the doghouse and at briefing areas, as indicated on well site diagram.

3. H2S detection and monitoring equipment:

- A. Portable H2S monitors positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 PPM are reached.

4. Visual warning systems:

- A. Wind direction indicators as shown on well site diagram.
- B. Caution/Danger signs (Exhibit #7) shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.

5. Mud program:

- A. The mud program has been designed to minimize the volume of H2S circulated to surface. Proper mud weight, safe drilling practices, and the use of H2S scavengers will minimize hazards when penetrating H2S bearing zones.
-

6. Metallurgy:

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H₂S service.
- B. All elastomers used for packing and seals shall be H₂S trim.

7. Communication:

- A. Radio communications in company vehicles including cellular telephone and 2-way radio.
- B. Land line (telephone) communication at Office.

8. Well testing:

- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safely and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H₂S environment will use the closed chamber method of testing.
- B. There will be no drill stem testing.

EXHIBIT #7

**WARNING
YOU ARE ENTERING AN H₂S
AUTHORIZED PERSONNEL ONLY**

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED
- 2. HARD HATS REQUIRED
- 3. SMOKING IN DESIGNATED AREAS ONLY
- 4. BE WIND CONSCIOUS AT ALL TIMES
- 5. CHECK WITH COG OPERATING FOREMAN AT

**COG OPERATING LLC
1-432-683-7443
1-575-746-2010**

EDDY COUNTY EMERGENCY NUMBERS

ARTESIA FIRE DEPT. 575-746-5050
ARTESIA POLICE DEPT. 575-746-5000
EDDY CO. SHERIFF DEPT. 575-746-9888

LEA COUNTY EMERGENCY NUMBERS

HOBBS FIRE DEPT. 575-397-9308
HOBBS POLICE DEPT. 575-397-9285
LEA CO. SHERIFF DEPT. 575-396-1196

COG Operating LLC

Drilling Location - H2S Safety Equipment Diagram

EXHIBIT 8-

Jenkins B

Fed Com
24H

Road Access
with H2S
sign

Fluid
Storage
Tanks

Roll Off Cutting
Containers on
Tracks

Mud House

Steel pits

Mud Pumps

Shakers

Centrifuge or
Solids Sep.

Flow line

Choke
Manifold *

Transfer Pump

2" Choke Line 150' f/ wellhead
(buried under Closed Loop Equipment)

*If necessary will
add a remote
operated choke

Water Tanks

Water Tanks

Substructure

Cellar

Dog House

Pipe
Racks

Steel Half Pit w/
mounted "Gas Buster"

2" choke
line to
gas
buster

Automatic Ignition

4" "Panic Line" to gas buster 150' f/wellhead
(buried under Closed Loop Equipment)

Secondary
Egress &
Briefing


N
Prevaling Wind
Direction

Wind Direction Indicators
H2S Monitor with alarm at
the bell nipple
Safe Briefing Area with
caution signs and
breathing equipment

Trailer

N
Pad Orientation

COG OPERATING, LLC
JENKINS B FED COM #24H
(2391' FNL & 45' FEL)
SECTION 19, T17S, R30E
N. M. P. M., EDDY CO., NEW MEXICO



DIRECTIONS TO LOCATION

From the intersection of U. S. Hwy 82 and CR-217 (Hagerman Cutoff);
Go West on U. S. Hwy approx. 0.9 miles to lease road on right;
Turn right on lease road and go North approx. 0.1 miles;
Location is approx. 190 feet West of the lease road.

SCALE: 1" = 100'
0 50 100
BEARINGS ARE
NAD 27 GRID - NM EAST
DISTANCES ARE
GROUND.

Firm No.: TX 1019J838 NM 4555451

Copyright 2015 - All Rights Reserved

NO.	REVISION	DATE
JOB NO.:	LS1501009	
DWG. NO.:	1501009REC	

RRC

308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 100'
DATE: 3-2-15
SURVEYED BY: ML/BC
DRAWN BY: JC
APPROVED BY: RMH
SHEET : 1 OF 1

Surface Use & Operating Plan

Jenkins B Federal Com 24H

- Surface Tenant: Bogle Farms, Lewis Derrick, P O Box 441, Artesia, NM 88211.
- New Road: approx. 68'
- Flow Line: approx. 1.2 mi
- Facilities: Northwest Central Production Facility

Well Site Information

V Door: South

Topsoil: North

Interim Reclamation: North/West

Notes

-N/A

Onsite: 7/24/2014

Indra Dahal (BLM), Caden Jameson (COG), Gary Box (RRC)

SURFACE USE AND OPERATING PLAN

1. Existing & Proposed Access Roads

- A. The well site survey and elevation plat for the proposed well is attached with this application. It was staked by Renewable Resource Consultants, LLC, Midland, TX.
- B. All roads to the location are shown in the Vicinity Map. The existing lease roads are illustrated and are adequate for travel during drilling and production operations. Upgrading existing roads prior to drilling the well will be done where necessary. The road route to the well site is depicted in Vicinity Map. The road highlighted in the Vicinity Map will be used to access the well.
- C. Directions to location: See Vicinity Map.
- D. Routine grading and maintenance of existing roads will be conducted as necessary to maintain their condition as long as any operations continue on this lease. Roads will be maintained according to specifications in section 2A of this Surface Use and Operating Plan.

2. Proposed Access Road:

The Elevation Plat shows that 68' of new access road will be required for this location. If any road is required it will be constructed as follows:

- A. The maximum width of the running surface will be 14'. The road will be crowned, ditched and constructed of 6" rolled and compacted caliche. Ditches will be at 3:1 slope and 4 feet wide. Water will be diverted where necessary to avoid ponding, prevent erosion, maintain good drainage, and to be consistent with local drainage patterns.
- B. The average grade will be less than 1%.
- C. No turnouts are planned.
- D. No culverts, cattleguard, gates, low water crossings or fence cuts are necessary.
- E. Surfacing material will consist of native caliche. Caliche will be obtained from the actual well site if available. If not available onsite, caliche will be hauled from the nearest BLM approved caliche pit.

3. Location of Existing Well:

The 1-mile Map shows all existing wells within a one-mile radius of this well.

As shown on this plat there are numerous wells producing from the San Andres and Yeso formations.

4. Location of Existing and/or Proposed Facilities:

- A. COG Operating LLC does operate a production facility on this lease.
- B. If the well is productive, contemplated facilities will be as follows:
 - 1) Production will be sent to the Northwest Central Production Facility located in section 17 in T17S R30E at 990' FSL & 2310' FWL. The facility location is shown in Exhibit #1.
 - 2) The tank battery and facilities including all flow lines and piping will be installed according to API specifications.
 - 3) Any additional caliche will be obtained from the actual well site. If caliche does not exist or is not plentiful from the well site, the caliche will be hauled from a BLM approved caliche pit. Any additional construction materials will be purchased from contractors.
 - 4) Proposed flow lines, will follow an archaeologically approved route to the Northwest Central Production Facility located in section 17 in T17S R30E at 990' FSL & 2310' FWL. The flowline will be SDR 7 3" poly line laid on the surface and will be approximately 1.2 mi in length. See Exhibit #1.
 - 5) It will be necessary to run electric power if this well is productive. Power will be provided by CVE and they will submit a separate plan and ROW for service to the well location.
 - 6) If the well is productive, rehabilitation plans will include the following:
 - The original topsoil from the well site will be returned to the location, and the site will be re-contoured as close as possible to the original site.

5. Location and Type of Water Supply:

The well will be drilled with combination brine and fresh water mud system as outlined in the drilling program. The water will be obtained from commercial water stations in the area and hauled to location by transport truck over the existing and proposed access roads shown in Vicinity Map. If a commercial fresh water source is nearby, fast line may be laid along existing road ROW's and fresh water pumped to the well. No water well will be drilled on the location.

6. Source of Construction Materials and Location "Turn-Over" Procedure:

Obtaining caliche: The primary way of obtaining caliche to build locations and roads will be by "turning over" the location. This means, caliche will be obtained from the actual well sight. A caliche permit will be obtained from BLM prior to pushing up any caliche. 2400 cu. Yards is max amount of caliche needed for pad and roads. Amount will vary for each pad. The procedure below has been approved by BLM personnel:

- A. The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.**
- B. An approximate 120' X 120' area is used within the proposed well site to remove caliche.**
- C. Subsoil is removed and piled alongside the 120' by 120' area within the pad site.**
- D. When caliche is found, material will be stock piled within the pad site to build the location and road.**
- E. Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.**
- F. Once well is drilled, the stock piled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced. Neither caliche nor subsoil will be stock piled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in attached plat.**
 - In the event that no caliche is found onsite, caliche will be hauled in from a BLM approved caliche pit.

7. Methods of Handling Water Disposal:

- A. The well will be drilled utilizing a closed loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to an NMOCD approved disposal site.
- B. Drilling fluids will be contained in steel mud pits.
- C. Water produced from the well during completion will be held temporarily in steel tanks and then taken to an NMOCD approved commercial disposal facility.
- D. Garbage and trash produced during drilling or completion operations will be collected in a trash bin and hauled to an approved landfill. No toxic waste or hazardous chemicals will be produced by this operation.
- E. Human waste and grey water will need to be properly contained and disposed of. Proper disposal and elimination of waste and grey water may include but are not limited to portable septic systems and/or portable waste gathering systems (i.e. portable toilets).
- F. After the rig is moved out and the well is either completed or abandoned, all waste materials will be cleaned up within 30 days. In the event of a dry hole only a dry hole marker will remain.

8. Ancillary Facilities:

No airstrip, campsite or other facilities will be built as a result of the operation on this well.

9. Well Site Layout:

- A. The drill pad layout, with elevations staked by Renewable Resource Consultants, LLC, Midland, TX, is shown in the Elevation Plat. Dimensions of the pad and pits are shown on the Rig Layout. V door direction is South. Topsoil, if available, will be stockpiled per BLM specifications. Because the pad is almost level no major cuts will be required.
- B. The Rig Layout Closed-Loop exhibit shows the proposed orientation of closed loop system and access road. No permanent living facilities are planned, but a temporary foreman/toolpusher's trailer will be on location during the drilling operations.

10. Plans for Restoration of the Surface:

- A. Interim Reclamation will take place after the well has been completed. The pad will be downsized by reclaiming the areas not needed for production operations. The portions of the pad that are not needed for production operations will be re-contoured to its original state as much as possible. The caliche that is removed will be reused to either build another pad site or for road repairs within the lease. The stockpiled topsoil will then be spread out reclaimed area and reseeded with a BLM approved seed mixture. In the event that the well must be worked over or maintained, it may be necessary to drive, park, and/or operate machinery on reclaimed land. This area will be repaired or reclaimed after work is complete.
- B. Final Reclamation: Upon plugging and abandoning the well all caliche for well pad and lease road will be removed and surface will be recountoured to reflect its surroundings as much as possible. Caliche will be recycled for road repair or reused for another well pad within the lease. If any topsoil remains, it will be spread out and the area will be reseeded with a BLM approved mixture and re-vegetated as per BLM orders.

11. Surface Ownership:

- A. The surface is owned by the U.S. Government and is administered by the Bureau of Land Management. The surface is multiple uses with the primary uses of the region for grazing of livestock and the production of oil and gas.
- B. The surface tenant is Bogle Farms, Lewis Derrick, P.O. Box 441, Artesia, NM 88211.
- C. The proposed road routes and surface location will be restored as directed by the BLM

12. Other Information:

- A. The area around the well site is grassland and the topsoil is sandy. The vegetation is moderately sparse with native prairie grasses, some mesquite and shinnery oak. No wildlife was observed but it is likely that mule deer, rabbits, coyotes and rodents traverse the area.
- B. There is no permanent or live water in the immediate area.
- C. There are no dwellings within 2 miles of this location.
- D. If needed, a Cultural Resources Examination is being prepared by Boone Arch Services of New Mexico, LLC. Carlsbad, NM, 88220. 506 E Chapman Rd. , phone # 575.887.7667 and the results will be forwarded to your office in the near future. Otherwise, **COG will be participating in the Permian Basin MOA Program.**

13. Bond Coverage:

Bond Coverage is Nationwide Bond # 000215

14. Lessee's and Operator's Representative:

The COG Operating LLC representative responsible for assuring compliance with the surface use plan is as follows:

Jim Evans	Ray Peterson
Drilling Superintendent	Drilling Manager
COG Operating LLC	COG Operating LLC
One Concho Center	One Concho Center
600 W. Illinois	600 W. Illinois
Midland, TX 79701	Midland, TX 79701
Phone (432) 685-4304 (office)	Phone (432) 685-4304 (office)
(432) 221-0346 (business)	(432) 818-2254 (business)

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	COG Operating
LEASE NO.:	LC029342C
WELL NAME & NO.:	24H-Jenkins B Federal Com
SURFACE HOLE FOOTAGE:	2391'N & 45'E
BOTTOM HOLE FOOTAGE	2311'N & 330'E
LOCATION:	Section 19, T. 17 S., R. 30 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Communitization Agreement
 - Lesser Prairie-Chicken Timing Stipulations
 - Below Ground-level Abandoned Well Marker
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
 - Cement Requirements
 - H2S Requirements
 - Logging Requirements
 - Pressure Control Requirements
 - Waste Material and Fluids
- ☒ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Communitization Agreement:

1. The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
2. If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
3. In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattleguards

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Lea County**

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240,
(575) 393-3612

1. A Hydrogen Sulfide (H₂S) Drilling Plan shall be activated **500** feet prior to drilling into the **Yates** formation. **As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Water Basin:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE.

Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Risks:

Possibility of Water Flows in the Salado and in the Artesia Group.

Possibility of Lost Circulation in the Rustler, in the San Andres, in the Red Beds and in the Artesia Group.

1. The 13 3/8 inch surface casing shall be set at approximately 320 feet (**into the top of the Rustler, and if salt is encountered, set casing at least 25 feet above the salt**) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

2. The minimum required fill of cement behind the 9 5/8 inch intermediate casing which shall be set at approximately at 1120 feet (to avoid setting in the base of the salt) is:

Option 1:

- ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above.

Option 2:

Operator has proposed DV tool at depth of 370 feet, but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50 feet below previous shoe and a minimum of 200 feet above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range.

- a. First stage to DV tool:

- ☒ Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.

- b. Second stage above DV tool:

- ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above.

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

3. The minimum required fill of cement behind the 7 X 5 1/2 inch production casing is:

Option 1:

- ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above.

Option 2:

Operator has proposed DV tool at depth of 2840 feet, but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50 feet below previous shoe and a minimum of 200 feet above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range.

- a. First stage to DV tool:

- ☒ Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.

- b. Second stage above DV tool:

- ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above.

4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
2. **In the case where the only BOP installed is an annular preventer, it shall be tested to a minimum of 2000 psi (which may require upgrading to 3M or 5M annular).**
3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M) psi**.
4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
 - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.

- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

KGR 01022016

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator

removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the Grant and attachments, including stipulations, survey plat(s) and/or map(s), shall be on location during construction. BLM personnel may request to review a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the

Authorized Officer:

1. Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, Holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC § 2601 *et seq.* (1982) with regard to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant (*see* 40 CFR, Part 702-799 and in particular, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193). Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. Holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. § 9601, *et seq.* or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, *et seq.*) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way Holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way Holder on the Right-of-Way. This provision applies without regard to whether a release is caused by Holder, its agent, or unrelated third parties.

4. Holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. Holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of Holder including, but not limited to: construction, operation, maintenance, and termination of the facility;
- b. Activities of other parties including, but not limited to:
 - (1) Land clearing
 - (2) Earth-disturbing and earth-moving work
 - (3) Blasting
 - (4) Vandalism and sabotage;

c. Acts of God:

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be

determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of Holder, regardless of fault. Upon failure of Holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he/she deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of Holder. Such action by the Authorized Officer shall not relieve Holder of any responsibility as provided herein.

6. All construction and maintenance activity shall be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline shall be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline shall be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity shall be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation shall be allowed unless approved in writing by the Authorized Officer.

8. Holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline shall be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines shall be less than or equal to 4 inches and a working pressure below 125 psi.

18. Special Stipulations:

- a. **Lesser Prairie-Chicken:** Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The

3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted.

- b. This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed