OCD Artesia

15-874

Form 3160-3
(March 2012)

SECRETARY'S POTASH

NM OIL CONSERVATION
ARTESIA DISTRICT
FEB 08 2016
RECEIVED

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0137
Expires October 31, 2014

5. Lease Serial No.
NMLC 0068408; BHL: NMNM 041557

6. If Indian, Allotee or Tribe Name

1a. Type of work: ☑ DRILL ☐ REENTER

7. If Unit or CA Agreement, Name and No.
Big Eddy Unit NM68294X

1b. Type of Well: ☑ Oil Well ☐ Gas Well ☐ Other ☑ Single Zone ☐ Multiple Zone

8. Lease Name and Well No.
Big Eddy Unit DI4B #274H

2. Name of Operator BOPCO, L.P.

9. API Well No.
30-015-43647

3a. Address P.O. Box 2760
Midland, TX 79702

3b. Phone No. *(include area code)*
432-683-2277

10. Field and Pool, or Exploratory
WC William Sink (Bone Spring)

4. Location of Well *(Report location clearly and in accordance with any State requirements.*)*

At surface SWSE, UL O, 720' FSL & 2065' FEL, Lat:N32.597211,Long:W103.889453

At proposed prod. zone 660' FSL & 330'FEL,Sec 4, T20S-R31E,Lat:N32.5961,Long:W103.8677

11. Sec., T. R. M. or Blk. and Survey or Area
Section 5, T20S-R31E

14. Distance in miles and direction from nearest town or post office*
23 miles northeast of Carlsbad, NM

12. County or Parish
Eddy County

13. State
NM

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 330'	16. No. of acres in lease 1,880.68	17. Spacing Unit dedicated to this well 240 acres
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 40'	19. Proposed Depth 15,784' MD / 9,184' TVD	20. BLM/BIA Bond No. on file COB 000050
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3,464 GL	22. Approximate date work will start* 09/01/2015	23. Estimated duration 35 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the BLM.

25. Signature Whitney B McKee	Name *(Printed/Typed)* Whitney McKee	Date 7/7/15

Title
Engineering Assistant

Approved by *(Signature)* /S/ JEANETTE MARTINEZ	Name *(Printed/Typed)*	Date JAN 29 2016
Title FIELD MANAGER	Office BLM-CARLSBAD FIELD OFFICE	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

2/19/16

APPROVAL SUBJECT TO GENERAL REQUIREMENTS AND SPECIAL STIPULATIONS ATTACHED

SEE ATTACHED FOR CONDITIONS OF APPROVAL

Capitan Controlled Water Basin

Witness Surface & Intermediate Casing

OPERATOR'S CERTIFICATION

APPLICATION FOR PERMIT TO DRILL
BIG EDDY UNIT DI4B #274H
720' FSL, 2065' FEL, Sec. 5, T20S, R31E, Eddy County, NM

In reference to the above captioned well, I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in the APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Executed this 7th day of July, 2015.

If you have any questions regarding the accuracy of the plan provided herein, please do not hesitate to contact me at (432) 683-2277.

Whitney McKee
Engineering Assistant

DISTRICT I
1625 N. French Dr., Hobbs, NM 88240
Phone (575) 393-6161 Fax: (575) 393-0720
DISTRICT II
811 S. First St., Artesia, NM 88210
Phone (575) 748-1283 Fax: (575) 748-9720
DISTRICT III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone (505) 334-6178 Fax: (505) 334-6170
DISTRICT IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources Department

OIL CONSERVATION DIVISION

1220 South St. Francis Dr.
Santa Fe, New Mexico 87505

Form C-102
Revised August 1, 2011

Submit one copy to appropriate District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number	Pool Code	Pool Name
30-015-43647	97650	WC WILLIAM SINK (BONE SPRING)

Property Code	Property Name	Well Number
~~305860~~ 315998	BIG EDDY UNIT DI4B	274H

OGRID No.	Operator Name	Elevation
260737	BOPCO, L.P.	3464

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
O	5	20 S	31 E		720	SOUTH	2065	EAST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	4	20 S	31 E		660	SOUTH	330	EAST	EDDY

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.
240			

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



SURFACE LOCATION
Lat – N 32°35'49.49"
Long – W 103°53'20.20"
NMSPCE– N 581215.3
E 636858.4
(NAD-27)



PROPOSED BOTTOM HOLE LOCATION
Lat – N 32°35'48.75"
Long – W 103°51'58.13"
NMSPCE– N 581170.9
E 643879.4
(NAD-27)

OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Whitney McKee 7/7/15
Signature Date

Whitney McKee
Printed Name

wbmckee@basspet.com
Email Address

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervison, and that the same is true and correct to the best of my belief.

SEPTEMBER 26, 2014
Date Surveyed

Signature & Seal of Professional Surveyor

GARY L. JONES NEW MEXICO 7977 REGISTERED PROFESSIONAL LAND SURVEYOR

Certificate No. Gary L. Jones 7977
BASIN SURVEYS

0' 1000' 2000' 3000' 4000'
SCALE: 1" = 2000'
WO Num.: 31011

SECTION 5, TOWNSHIP 20 SOUTH, RANGE 31 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.



100 0 100 200 FEET

SCALE: 1" = 100'

BOPCO, L.P.

REF: BIG EDDY UNIT DI4B 274H / WELL PAD TOPO

THE BIG EDDY UNIT DI4B 274H LOCATED 720' FROM THE SOUTH LINE AND 2065' FROM THE EAST LINE OF SECTION 5, TOWNSHIP 20 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

Basin Surveys
focused on excellence in the oilfield
P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

W.O. Number: 31011	Drawn By: K. NORRIS	Date: 10-01-2014	Survey Date: 09-24-2014	Sheet 1 of 1 Sheets



BIG EDDY UNIT DI4B 274H

Located 720' FSL and 2065' FEL
Section 5, Township 20 South, Range 31 East,
N.M.P.M., Eddy County, New Mexico.

Basin Surveys
focused on excellence in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 – Office
(575) 392-2206 – Fax
basinsurveys.com

0 1 MI 2 MI 3 MI 4 MI
SCALE: 1" = 2 MILES

W.O. Number: KAN 31011

Survey Date: 09-24-2014

YELLOW TINT – USA LAND
BLUE TINT – STATE LAND
NATURAL COLOR – FEE LAND

N

BOPCO, L.P.



BIG EDDY UNIT DI4B 274H

Located 720' FSL and 2065' FEL

Section 5, Township 20 South, Range 31 East, N.M.P.M., Eddy County, New Mexico.

basin Surveys
focused on excellence in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

0' 1000' 2000' 3000' 4000'

SCALE: 1" = 2000'

W.O. Number: KAN 31011

Survey Date: 09-24-2014

YELLOW TINT - USA LAND
BLUE TINT - STATE LAND
NATURAL COLOR - FEE LAND

N

BOPCO, L.P.



BIG EDDY UNIT DI4B 274H BOTTOM HOLE LOCATION

Located 660' FSL and 330' FEL

Section 6, Township 20 South, Range 31 East, N.M.P.M., Eddy County, New Mexico.

Basin Surveys
focused on excellence in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

0' 1000' 2000' 3000' 4000'

SCALE: 1" = 2000'

W.O. Number: KAN 31011

Survey Date: 09-24-2014

YELLOW TINT - USA LAND
BLUE TINT - STATE LAND
NATURAL COLOR - FEE LAND

N

BOPCO, L.P.



BIG EDDY UNIT DI4B 274H
Located 720' FSL and 2065' FEL
Section 5, Township 20 South, Range 31 East, N.M.P.M., Eddy County, New Mexico.

basin Surveys
focused on excellence in the oilfield
P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

0' 1000' 2000' 3000' 4000'
SCALE: 1" = 2000'

W.O. Number: KAN 31011

Survey Date: 09-24-2014

YELLOW TINT - USA LAND
BLUE TINT - STATE LAND
NATURAL COLOR - FEE LAND

N

BOPCO, L.P.



BIG EDDY UNIT DI4B 274H BOTTOM HOLE LOCATION

Located 660' FSL and 330' FEL
Section 6, Township 20 South, Range 31 East,
N.M.P.M., Eddy County, New Mexico.

Basin Surveys
focused on excellence in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

0' 1000' 2000' 3000' 4000'
SCALE: 1" = 2000'

W.O. Number: KAN 31011

Survey Date: 09-24-2014

YELLOW TINT - USA LAND
BLUE TINT - STATE LAND
NATURAL COLOR - FEE LAND

N

BOPCO, L.P.

EXHIBIT "D"

RIG LAYOUT SCHEMATIC
INCLUSIVE OF CLOSED-LOOP DESIGN PLAN

SOLIDS CONTROL EQUIPMENT LEGEND

1) ROLL OFF BIN
2) STEEL TANK
3) MUD CLEANER
4) SHAKER
5) CENTRIFUGE
6) DEWATERING UNIT
7) CATCH TANK
8) CHOKE MANIFOLD
A) BLEED LINE FROM CHOKE MANIFOLD



BIG EDDY UNIT DI4B 274H
Located 720' FSL and 2065' FEL
Section 5, Township 20 South, Range 31 East, N.M.P.M., Eddy County, New Mexico.

Basin Surveys
focused on excellence in the oilfield
P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

SCALE: NONE

W.O. Number: KAN 31011

Survey Date: 09-24-2014

N

BOPCO, L.P.

Flowline Route Diagram 4



Access Road Diagram



BOPCO, L.P., Big Eddy Unit DI4B #274H

1. Geologic Formations

TVD of target	9184	Pilot hole depth	NA
MD at TD:	15784	Deepest expected fresh water:	135

The Surface hole location is nonstandard, and inside the Big Eddy Unit.

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Quaternary Fill	Surface	Water	
Top Rustler	564	Water	
Top Salado	699	Salt	
Base Salt	804	Salt	
Top Yates	2569	Oil	
Top Reef	2899	Water	Loss of circulation
Top Lamar	4074	Barren	
Top Bone Spring Lime	6974	Oil/Gas	
Top 2nd BS Sand	9046	Target Zone	
Top Wolfcamp	10244	Oil/Gas	

*H2S, water flows, loss of circulation, abnormal pressures, etc.

2. Casing Program

Hole Size	Casing Interval From	To	Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
18.125"	0	650	16"	84	J55	BTC	4.48	1.95	28.25
14.75"	0	2849	13.375"	68	HCL80 Ultra Flush Joint	STC	1.85	3.16	9.51
12.25"	0	4125	9.625"	40	J55	LTC	1.20	1.72	4.43
8.75"	0	15784	5.5"	17	HCP110	LTC	1.92	4.37	4.12
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y

Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	N
Is well located within Capitan Reef?	Y
If yes, does production casing cement tie back a minimum of 50' above the Reef?	Y
Is well within the designated 4 string boundary.	Y
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	N
Is well located in R-111-P and SOPA?	Y
If yes, are the first three strings cemented to surface?	Y
Is 2nd string set 100' to 600' below the base of salt?	Y
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	N

3. Cementing Program

Casing	# Sks	Wt. lb/ gal	Yld ft3/ sack	H_20 gal/sk	500# Comp. Strength (hours)	Slurry Description
Surf.	230	13.5	1.75	8.69	14	Lead: Class C +2% CACL + 4% Bentonite + 0.25 LB/SK Cello Flake + 3 lb/sk LCM-1
	140	14.8	1.35	6.35	8	Tail: Class C + 2% CACL + 0.25 LB/Sk CF + 3 LB/Sk LCM-1
Inter.	490	12.9	1.85	9.32	14	Lead: EconoCEM HLC + 5% CaCl + 5#/sk Gilsonite
	220	14.8	1.33	6.34	6	Tail: Class C neat
2nd Inter.	360	13.5	1.75	8.69	14	1st primary: HalCem C 4% bentonite + 0.6% Halad(R)-9 **DV Tool and ECP @ 2899'**
2nd Inter.	480 180	12.9 14.8	1.85 1.33	9.83 6.34	14 6	2nd Lead: EconoCem HLC + NaCL 2nd Tail: Class C neat
Prod.	670	11	2.64	14.87	11	1st Lead: Tuned Light + 0.125 pps Poly – E- Flake
	1360	12	2.03	11.41	14	1st Tail: Class H + 0.5% Halad-344 + 0.25% CFR-3 + 0.5% Econolite
	DV Tool 5000'					
	300	11	2.35	11.7	11	2nd stage Primary: Tuned Light + 0.125 pps Poly – E-Flake

DV tool depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. DV tool will be set a minimum of 50 feet below previous casing and a minimum

of 200 feet above current shoe.

Casing String	TOC	%Excess
Surface	0'	100%
Intermediate	0'	30%
2nd Intermediate	0'	50%
Production	~~2899~~' 2849'	50%

4. Pressure Control Equipment

X	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.

BOP installed and tested before drilling which hole?	Size?	System Rated WP	Type	✓	Tested to:
14-3/4"	13-5/8"	3M	Annular	x	50% of working pressure
			Blind Ram	x	3000
			Pipe Ram	x	
			Double Ram		
			Other*		
12-1/4"	13-5/8"	3M	Annular	x	50% of working pressure
			Blind Ram	x	3000
			Pipe Ram	x	
			Double Ram		
			Other*		
8-3/4"	13-5/8"	3M	Annular	x	50% of working pressure
			Blind Ram	x	3000
			Pipe Ram	x	
			Double Ram		
			Other*		

*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
X	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
	N Are anchors required by manufacturer?
	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. See attached schematic.

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	Surf. shoe	FW Gel	8 -9.2	38-70	N/C
Surf csg	Int shoe	Saturated Brine	9.8-10.2	28-30	N/C
Int. shoe	Prod. Shoe	FW/Gel	8.7-9.0	28-36	N/C
Prod. casing shoe	TD	FW/Gel/Starch	8.7-9.0	28-36	<100

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	Pason/Visual Monitoring

6. Logging and Testing Procedures

Logging, Coring and Testing.	
	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
X	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned		Interval
	Resistivity	Int. shoe to KOP
	Density	Int. shoe to KOP

	CBL	Production casing
	Mud log	Intermediate shoe to TD
	PEX	

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	4299 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. Standard LCM will be on location to use when needed.

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

	H2S is present
X	H2S Plan attached

8. Other facets of operation

Is this a walking operation? No

Will be pre-setting casing? No

Attachments
_X_ Directional Plan
___ Other, describe

WTD - West Texas Division

Location: Eddy County, NM
Field: Big Eddy Unit
Facility: Drilling Island 4 - B

Slot: No.274H SHL
Well: No.274H
Wellbore: No.274H PWB

BOPCO, L.P.



Well Profile Data

Design Comment	MD (ft)	Inc (°)	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)	VS (ft)
Tie On	20.00	0.000	90.362	20.00	0.00	0.00	0.00	0.00
Est KOP	8420.00	0.000	90.362	8420.00	0.00	0.00	0.00	0.00
70° Curve	9120.00	70.000	90.362	8958.40	-2.38	376.99	10.00	376.99
200' Tangent	9320.00	70.000	90.362	9026.81	-3.57	564.92	0.00	564.93
EOC	9636.30	89.068	90.365	9084.00	-5.53	874.52	6.03	874.54
TL	9636.44	89.068	90.362	9084.00	-5.53	874.66	2.00	874.67
No.274H PBHL	15784.22	89.068	90.362	9184.00	-44.40	7021.50	0.00	7021.64

Wellpath Comments

MD (ft)	X (ft)	Y (ft)	TVD (ft)	Inclination (°)	Azimuth (°)	VS (ft)	Comment
564.00	0.00	0.00	564.00	0.000	90.362	0.00	Top Rustler
699.00	0.00	0.00	699.00	0.000	90.362	0.00	Top Salado
804.00	0.00	0.00	804.00	0.000	90.362	0.00	Base Salt
2569.00	0.00	0.00	2569.00	0.000	90.362	0.00	Top Yates
2899.00	0.00	0.00	2899.00	0.000	90.362	0.00	Top Reel
4074.00	0.00	0.00	4074.00	0.000	90.362	0.00	Top Lamar
6974.00	0.00	0.00	6974.00	0.000	90.362	0.00	Top Bone Spring Lime
9381.65	623.49	-3.94	9046.00	73.716	90.363	623.51	Top 2nd BS Sand
9420.00	660.51	-4.17	9056.01	76.028	90.363	660.53	FTP

Plot reference wellpath is B-1	
True vertical depths are referenced to Rig on No.274H SHL (KB)	Grid System: NAD27 / TM New Mexico SP, Eastern Zone (3001), US feet
Measured depths are referenced to Rig on No.274H SHL (KB)	North Reference: Grid north
Rig on No.274H SHL (KB) to Mean Sea Level: 3484 feet	Scale: True distance
Mean Sea Level to Mud line (At Slot: No.274H SHL): 0 feet	Depths are in feet
Coordinates are in feet referenced to Slot	Created by: BWGentry on 6/22/2015



IGRF (1900.0 to 2020.0)
Magnetic North is 7.34 degrees East of True North (at 6/18/2015)
Grid North is 0.24 degrees East of True North
To correct azimuth from True to Grid subtract 0.24 degrees
To correct azimuth from Magnetic to Grid add 7.10 degrees

Planned Wellpath Report

B-1

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	**WTD - West Texas Division**	Slot	**No.274H SHL**
Area	**Eddy County, NM**	Well	**No.274H**
Field	**Big Eddy Unit**	Wellbore	**No.274H PWB**
Facility	**Drilling Island 4 - B**		

REPORT SETUP INFORMATION			
Projection System	**NAD27 / TM New Mexico SP, Eastern Zone (3001), US feet**	Software System	**WellArchitect® 4.1.1**
North Reference	**Grid**	User	**BWGentry**
Scale	**0.999931**	Report Generated	**6/22/2015** at **9:32:04 AM**
Convergence at slot	**0.24° East**	Database/Source file	**WellArchitectDB/No.274H_PWB.xml**

WELLPATH LOCATION	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	**East[ft]**	**Easting[US ft]**	**Northing[US ft]**	**Latitude**	**Longitude**
Slot Location	-0.30	40.00	**636858.40**	**581215.30**	32°35'49.488"N	103°53'20.203"W
Facility Reference Pt			**636818.40**	**581215.60**	32°35'49.493"N	103°53'20.670"W
Field Reference Pt			**640125.10**	**530502.80**	32°27'27.522"N	103°52'44.545"W

WELLPATH DATUM			
Calculation method	**Minimum curvature**	Rig on No.274H SHL (KB) to Facility Vertical Datum	**3484.00ft**
Horizontal Reference Pt	**Slot**	Rig on No.274H SHL (KB) to Mean Sea Level	**3484.00ft**
Vertical Reference Pt	**Rig on No.274H SHL (KB)**	Rig on No.274H SHL (KB) to Mud Line at Slot (No.274H SHL)	**3484.00ft**
MD Reference Pt	**Rig on No.274H SHL (KB)**	Section Origin	**N 0.00, E 0.00 ft**
Field Vertical Reference	**Mean Sea Level**	Section Azimuth	**90.36°**

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

WELLPATH DATA (170 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
0.00†	0.000	90.362	0.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
20.00	0.000	90.362	20.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	Tie On
120.00†	0.000	90.362	120.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
220.00†	0.000	90.362	220.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
320.00†	0.000	90.362	320.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
420.00†	0.000	90.362	420.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
520.00†	0.000	90.362	520.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
564.00†	0.000	90.362	564.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	Top Rustler
620.00†	0.000	90.362	620.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
699.00†	0.000	90.362	699.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	Top Salado
720.00†	0.000	90.362	720.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
804.00†	0.000	90.362	804.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	Base Salt
820.00†	0.000	90.362	820.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
920.00†	0.000	90.362	920.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
1020.00†	0.000	90.362	1020.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
1120.00†	0.000	90.362	1120.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
1220.00†	0.000	90.362	1220.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
1320.00†	0.000	90.362	1320.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
1420.00†	0.000	90.362	1420.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
1520.00†	0.000	90.362	1520.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
1620.00†	0.000	90.362	1620.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
1720.00†	0.000	90.362	1720.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
1820.00†	0.000	90.362	1820.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
1920.00†	0.000	90.362	1920.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
2020.00†	0.000	90.362	2020.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
2120.00†	0.000	90.362	2120.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
2220.00†	0.000	90.362	2220.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
2320.00†	0.000	90.362	2320.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
2420.00†	0.000	90.362	2420.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
2520.00†	0.000	90.362	2520.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
2569.00†	0.000	90.362	2569.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	Top Yates
2620.00†	0.000	90.362	2620.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
2720.00†	0.000	90.362	2720.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
2820.00†	0.000	90.362	2820.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
2899.00†	0.000	90.362	2899.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	Top Reef
2920.00†	0.000	90.362	2920.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
3020.00†	0.000	90.362	3020.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
3120.00†	0.000	90.362	3120.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
3220.00†	0.000	90.362	3220.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
3320.00†	0.000	90.362	3320.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
3420.00†	0.000	90.362	3420.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
3520.00†	0.000	90.362	3520.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
3620.00†	0.000	90.362	3620.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
3720.00†	0.000	90.362	3720.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
3820.00†	0.000	90.362	3820.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

WELLPATH DATA (170 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
3920.00†	0.000	90.362	3920.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
4020.00†	0.000	90.362	4020.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
4074.00†	0.000	90.362	4074.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	Top Lamar
4120.00†	0.000	90.362	4120.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
4220.00†	0.000	90.362	4220.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
4320.00†	0.000	90.362	4320.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
4420.00†	0.000	90.362	4420.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
4520.00†	0.000	90.362	4520.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
4620.00†	0.000	90.362	4620.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
4720.00†	0.000	90.362	4720.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
4820.00†	0.000	90.362	4820.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
4920.00†	0.000	90.362	4920.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
5020.00†	0.000	90.362	5020.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
5120.00†	0.000	90.362	5120.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
5220.00†	0.000	90.362	5220.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
5320.00†	0.000	90.362	5320.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
5420.00†	0.000	90.362	5420.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
5520.00†	0.000	90.362	5520.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
5620.00†	0.000	90.362	5620.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
5720.00†	0.000	90.362	5720.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
5820.00†	0.000	90.362	5820.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
5920.00†	0.000	90.362	5920.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
6020.00†	0.000	90.362	6020.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
6120.00†	0.000	90.362	6120.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
6220.00†	0.000	90.362	6220.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
6320.00†	0.000	90.362	6320.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
6420.00†	0.000	90.362	6420.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
6520.00†	0.000	90.362	6520.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
6620.00†	0.000	90.362	6620.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
6720.00†	0.000	90.362	6720.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
6820.00†	0.000	90.362	6820.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
6920.00†	0.000	90.362	6920.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
6974.00†	0.000	90.362	6974.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	Top Bone Spring Lime
7020.00†	0.000	90.362	7020.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
7120.00†	0.000	90.362	7120.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
7220.00†	0.000	90.362	7220.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
7320.00†	0.000	90.362	7320.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
7420.00†	0.000	90.362	7420.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
7520.00†	0.000	90.362	7520.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
7620.00†	0.000	90.362	7620.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
7720.00†	0.000	90.362	7720.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
7820.00†	0.000	90.362	7820.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
7920.00†	0.000	90.362	7920.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
8020.00†	0.000	90.362	8020.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
8120.00†	0.000	90.362	8120.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	

Planned Wellpath Report

B-1

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

WELLPATH DATA (170 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
8220.00†	0.000	90.362	8220.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
8320.00†	0.000	90.362	8320.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	
8420.00	0.000	90.362	8420.00	0.00	0.00	0.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W	0.00	Est KOP
8520.00†	10.000	90.362	8519.49	8.70	-0.05	8.70	636867.10	581215.25	32°35'49.488"N	103°53'20.101"W	10.00	
8620.00†	20.000	90.362	8615.96	34.55	-0.22	34.55	636892.95	581215.08	32°35'49.485"N	103°53'19.799"W	10.00	
8720.00†	30.000	90.362	8706.48	76.76	-0.48	76.76	636935.15	581214.82	32°35'49.481"N	103°53'19.305"W	10.00	
8820.00†	40.000	90.362	8788.29	134.05	-0.85	134.04	636992.43	581214.45	32°35'49.475"N	103°53'18.636"W	10.00	
8920.00†	50.000	90.362	8858.91	204.67	-1.29	204.66	637063.05	581214.01	32°35'49.467"N	103°53'17.811"W	10.00	
9020.00†	60.000	90.362	8916.20	286.48	-1.81	286.47	637144.85	581213.49	32°35'49.459"N	103°53'16.854"W	10.00	
9120.00	70.000	90.362	8958.40	376.99	-2.38	376.99	637235.36	581212.92	32°35'49.449"N	103°53'15.796"W	10.00	70° Curve
9220.00†	70.000	90.362	8992.61	470.96	-2.98	470.95	637329.32	581212.32	32°35'49.440"N	103°53'14.698"W	0.00	
9320.00	70.000	90.362	9026.81	564.93	-3.57	564.92	637423.28	581211.73	32°35'49.430"N	103°53'13.600"W	0.00	200' Tangen
9381.65†	73.716	90.363	9046.00	623.51	-3.94	623.49	637481.85	581211.36	32°35'49.424"N	103°53'12.915"W	6.03	Top 2nd BS
9420.00†	76.028	90.363	9056.01	660.53	-4.17	660.51	637518.87	581211.13	32°35'49.420"N	103°53'12.483"W	6.03	FTP
9520.00†	82.057	90.364	9075.01	758.66	-4.80	758.64	637616.99	581210.50	32°35'49.410"N	103°53'11.336"W	6.03	
9620.00†	88.085	90.365	9083.60	858.24	-5.43	858.23	637716.56	581209.87	32°35'49.399"N	103°53'10.172"W	6.03	
9636.30	89.068	90.365	9084.00	874.54	-5.53	874.52	637732.86	581209.77	32°35'49.397"N	103°53'09.981"W	6.03	EOC
9636.44	89.068	90.362	9084.00	874.67	-5.53	874.66	637732.99	581209.77	32°35'49.397"N	103°53'09.980"W	2.00	TL
9720.00†	89.068	90.362	9085.36	958.23	-6.06	958.21	637816.54	581209.24	32°35'49.389"N	103°53'09.003"W	0.00	
9820.00†	89.068	90.362	9086.99	1058.21	-6.70	1058.19	637916.52	581208.61	32°35'49.378"N	103°53'07.835"W	0.00	
9920.00†	89.068	90.362	9088.61	1158.20	-7.33	1158.18	638016.49	581207.97	32°35'49.368"N	103°53'06.666"W	0.00	
10020.00†	89.068	90.362	9090.24	1258.19	-7.96	1258.16	638116.47	581207.34	32°35'49.357"N	103°53'05.497"W	0.00	
10120.00†	89.068	90.362	9091.87	1358.17	-8.59	1358.15	638216.45	581206.71	32°35'49.347"N	103°53'04.329"W	0.00	
10220.00†	89.068	90.362	9093.49	1458.16	-9.22	1458.13	638316.43	581206.08	32°35'49.337"N	103°53'03.160"W	0.00	
10320.00†	89.068	90.362	9095.12	1558.15	-9.86	1558.12	638416.40	581205.44	32°35'49.326"N	103°53'01.991"W	0.00	
10420.00†	89.068	90.362	9096.75	1658.13	-10.49	1658.10	638516.38	581204.81	32°35'49.316"N	103°53'00.823"W	0.00	
10520.00†	89.068	90.362	9098.37	1758.12	-11.12	1758.09	638616.36	581204.18	32°35'49.305"N	103°52'59.654"W	0.00	
10620.00†	89.068	90.362	9100.00	1858.11	-11.75	1858.07	638716.34	581203.55	32°35'49.295"N	103°52'58.486"W	0.00	
10720.00†	89.068	90.362	9101.63	1958.09	-12.39	1958.05	638816.32	581202.92	32°35'49.284"N	103°52'57.317"W	0.00	
10820.00†	89.068	90.362	9103.25	2058.08	-13.02	2058.04	638916.29	581202.28	32°35'49.274"N	103°52'56.148"W	0.00	
10920.00†	89.068	90.362	9104.88	2158.07	-13.65	2158.02	639016.27	581201.65	32°35'49.264"N	103°52'54.980"W	0.00	
11020.00†	89.068	90.362	9106.51	2258.05	-14.28	2258.01	639116.25	581201.02	32°35'49.253"N	103°52'53.811"W	0.00	
11120.00†	89.068	90.362	9108.13	2358.04	-14.91	2357.99	639216.23	581200.39	32°35'49.243"N	103°52'52.642"W	0.00	
11220.00†	89.068	90.362	9109.76	2458.03	-15.55	2457.98	639316.20	581199.75	32°35'49.232"N	103°52'51.474"W	0.00	
11320.00†	89.068	90.362	9111.39	2558.01	-16.18	2557.96	639416.18	581199.12	32°35'49.222"N	103°52'50.305"W	0.00	
11420.00†	89.068	90.362	9113.01	2658.00	-16.81	2657.95	639516.16	581198.49	32°35'49.211"N	103°52'49.137"W	0.00	
11520.00†	89.068	90.362	9114.64	2757.99	-17.44	2757.93	639616.14	581197.86	32°35'49.201"N	103°52'47.968"W	0.00	
11620.00†	89.068	90.362	9116.27	2857.98	-18.08	2857.92	639716.11	581197.23	32°35'49.190"N	103°52'46.799"W	0.00	
11720.00†	89.068	90.362	9117.89	2957.96	-18.71	2957.90	639816.09	581196.59	32°35'49.180"N	103°52'45.631"W	0.00	
11820.00†	89.068	90.362	9119.52	3057.95	-19.34	3057.89	639916.07	581195.96	32°35'49.169"N	103°52'44.462"W	0.00	
11920.00†	89.068	90.362	9121.15	3157.94	-19.97	3157.87	640016.05	581195.33	32°35'49.159"N	103°52'43.294"W	0.00	
12020.00†	89.068	90.362	9122.77	3257.92	-20.60	3257.86	640116.02	581194.70	32°35'49.148"N	103°52'42.125"W	0.00	
12120.00†	89.068	90.362	9124.40	3357.91	-21.24	3357.84	640216.00	581194.06	32°35'49.138"N	103°52'40.956"W	0.00	
12220.00†	89.068	90.362	9126.03	3457.90	-21.87	3457.83	640315.98	581193.43	32°35'49.127"N	103°52'39.788"W	0.00	
12320.00†	89.068	90.362	9127.65	3557.88	-22.50	3557.81	640415.96	581192.80	32°35'49.117"N	103°52'38.619"W	0.00	

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

WELLPATH DATA (170 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
12420.00†	89.068	90.362	9129.28	3657.87	-23.13	3657.80	640515.93	581192.17	32°35'49.106"N	103°52'37.450"W	0.00	
12520.00†	89.068	90.362	9130.91	3757.86	-23.77	3757.78	640615.91	581191.54	32°35'49.096"N	103°52'36.282"W	0.00	
12620.00†	89.068	90.362	9132.53	3857.84	-24.40	3857.77	640715.89	581190.90	32°35'49.085"N	103°52'35.113"W	0.00	
12720.00†	89.068	90.362	9134.16	3957.83	-25.03	3957.75	640815.87	581190.27	32°35'49.075"N	103°52'33.945"W	0.00	
12820.00†	89.068	90.362	9135.79	4057.82	-25.66	4057.74	640915.85	581189.64	32°35'49.064"N	103°52'32.776"W	0.00	
12920.00†	89.068	90.362	9137.41	4157.80	-26.29	4157.72	641015.82	581189.01	32°35'49.054"N	103°52'31.607"W	0.00	
13020.00†	89.068	90.362	9139.04	4257.79	-26.93	4257.70	641115.80	581188.38	32°35'49.043"N	103°52'30.439"W	0.00	
13120.00†	89.068	90.362	9140.66	4357.78	-27.56	4357.69	641215.78	581187.74	32°35'49.033"N	103°52'29.270"W	0.00	
13220.00†	89.068	90.362	9142.29	4457.76	-28.19	4457.67	641315.76	581187.11	32°35'49.022"N	103°52'28.102"W	0.00	
13320.00†	89.068	90.362	9143.92	4557.75	-28.82	4557.66	641415.73	581186.48	32°35'49.012"N	103°52'26.933"W	0.00	
13420.00†	89.068	90.362	9145.54	4657.74	-29.46	4657.64	641515.71	581185.85	32°35'49.001"N	103°52'25.764"W	0.00	
13520.00†	89.068	90.362	9147.17	4757.72	-30.09	4757.63	641615.69	581185.21	32°35'48.991"N	103°52'24.596"W	0.00	
13620.00†	89.068	90.362	9148.80	4857.71	-30.72	4857.61	641715.67	581184.58	32°35'48.980"N	103°52'23.427"W	0.00	
13720.00†	89.068	90.362	9150.42	4957.70	-31.35	4957.60	641815.64	581183.95	32°35'48.970"N	103°52'22.258"W	0.00	
13820.00†	89.068	90.362	9152.05	5057.68	-31.98	5057.58	641915.62	581183.32	32°35'48.959"N	103°52'21.090"W	0.00	
13920.00†	89.068	90.362	9153.68	5157.67	-32.62	5157.57	642015.60	581182.69	32°35'48.948"N	103°52'19.921"W	0.00	
14020.00†	89.068	90.362	9155.30	5257.66	-33.25	5257.55	642115.58	581182.05	32°35'48.938"N	103°52'18.753"W	0.00	
14120.00†	89.068	90.362	9156.93	5357.64	-33.88	5357.54	642215.55	581181.42	32°35'48.927"N	103°52'17.584"W	0.00	
14220.00†	89.068	90.362	9158.56	5457.63	-34.51	5457.52	642315.53	581180.79	32°35'48.917"N	103°52'16.415"W	0.00	
14320.00†	89.068	90.362	9160.18	5557.62	-35.15	5557.51	642415.51	581180.16	32°35'48.906"N	103°52'15.247"W	0.00	
14420.00†	89.068	90.362	9161.81	5657.60	-35.78	5657.49	642515.49	581179.52	32°35'48.896"N	103°52'14.078"W	0.00	
14520.00†	89.068	90.362	9163.44	5757.59	-36.41	5757.48	642615.46	581178.89	32°35'48.885"N	103°52'12.910"W	0.00	
14620.00†	89.068	90.362	9165.06	5857.58	-37.04	5857.46	642715.44	581178.26	32°35'48.875"N	103°52'11.741"W	0.00	
14720.00†	89.068	90.362	9166.69	5957.56	-37.67	5957.45	642815.42	581177.63	32°35'48.864"N	103°52'10.572"W	0.00	
14820.00†	89.068	90.362	9168.32	6057.55	-38.31	6057.43	642915.40	581177.00	32°35'48.853"N	103°52'09.404"W	0.00	
14920.00†	89.068	90.362	9169.94	6157.54	-38.94	6157.42	643015.38	581176.36	32°35'48.843"N	103°52'08.235"W	0.00	
15020.00†	89.068	90.362	9171.57	6257.53	-39.57	6257.40	643115.35	581175.73	32°35'48.832"N	103°52'07.066"W	0.00	
15120.00†	89.068	90.362	9173.20	6357.51	-40.20	6357.38	643215.33	581175.10	32°35'48.822"N	103°52'05.898"W	0.00	
15220.00†	89.068	90.362	9174.82	6457.50	-40.84	6457.37	643315.31	581174.47	32°35'48.811"N	103°52'04.729"W	0.00	
15320.00†	89.068	90.362	9176.45	6557.49	-41.47	6557.35	643415.29	581173.83	32°35'48.801"N	103°52'03.561"W	0.00	
15420.00†	89.068	90.362	9178.08	6657.47	-42.10	6657.34	643515.26	581173.20	32°35'48.790"N	103°52'02.392"W	0.00	
15520.00†	89.068	90.362	9179.70	6757.46	-42.73	6757.32	643615.24	581172.57	32°35'48.779"N	103°52'01.223"W	0.00	
15620.00†	89.068	90.362	9181.33	6857.45	-43.36	6857.31	643715.22	581171.94	32°35'48.769"N	103°52'00.055"W	0.00	
15720.00†	89.068	90.362	9182.96	6957.43	-44.00	6957.29	643815.20	581171.31	32°35'48.758"N	103°51'58.886"W	0.00	
15784.22	89.068	90.362	9184.00	7021.64	-44.40	7021.50	643879.40	581170.90	32°35'48.751"N	103°51'58.136"W	0.00	No.274H PB

TARGETS

Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	Shape
1) BEU No.274H BHL	15784.22	9184.00	-44.40	7021.50	**643879.40**	**581170.90**	32°35'48.751"N	103°51'58.136"W	point

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

SURVEY PROGRAM - Ref Wellbore: No.274H PWB Ref Wellpath: B-1

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
20.00	500.00	Generic gyro - northseeking (Standard)		No.274H PWB
500.00	15784.22	ISCWSA MWD, Rev. 3 (Standard)		No.274H PWB

Clearance Report

B-1

Closest Approach

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

REPORT SETUP INFORMATION			
Projection System	NAD27 / TM New Mexico SP, Eastern Zone (3001), US feet	Software System	WellArchitect® 4.1.1
North Reference	Grid	User	BWGentry
Scale	0.999931	Report Generated	1/27/2016 at 2:15:13 PM
Convergence at slot	0.24° East	Database/Source file	WellArchitectDB/No.274H_PWB_CR.xml

WELLPATH LOCATION

	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	East[ft]	Easting[US ft]	Northing[US ft]	Latitude	Longitude
Slot Location	-0.30	40.00	636858.40	581215.30	32°35'49.488"N	103°53'20.203"W
Facility Reference Pt			636818.40	581215.60	32°35'49.493"N	103°53'20.670"W
Field Reference Pt			640125.10	530502.80	32°27'27.522"N	103°52'44.545"W

WELLPATH DATUM

Calculation method	Minimum Curvature	Rig on No.274H SHL (KB) to Facility Vertical Datum	3484.00ft
Horizontal Reference Pt	Slot	Rig on No.274H SHL (KB) to Mean Sea Level	3484.00ft
Vertical Reference Pt	Rig on No.274H SHL (KB)	Rig on No.274H SHL (KB) to Mud Line at Slot (No.274H SHL)	3484.00ft
MD Reference Pt	Rig on No.274H SHL (KB)		
Field Vertical Reference	Mean Sea Level		

POSITIONAL UNCERTAINTY CALCULATION SETTINGS

Ellipse Confidence Limit	3.00 Std Dev	Ellipse Start MD	20.00ft	Surface Position Uncertainty	included
Declination	7.34° East of TN	Dip Angle	60.38°	Mag Field Strength	48332 nT
Slot Surface Uncertainty @1SD		Horizontal	0.100ft	Vertical	0.100ft
Facility Surface Uncertainty @1SD		Horizontal	1.000ft	Vertical	1.000ft

Positional Uncertainty values in the WELLPATH DATA table are the projection of the ellipsoid of uncertainty onto the vertical and horizontal planes

ANTI-COLLISION RULE

Rule Name	Separation Factor : R-type Closest Approach w/Hole&Csg Limit:1.0 StdDev:3.00 w/Surface Uncert R=(D-H&C)/PU	Rule Based On	Ratio
Plane of Rule	Closest Approach	Threshold Value	1.00
Subtract Casing & Hole Size	yes	Apply Cone of Safety	no

SURVEY PROGRAM - Ref Wellbore: No.274H PWB Ref Wellpath: B-1

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
20.00	500.00	Generic gyro - northseeking (Standard)		No.274H PWB
500.00	15784.22	ISCWSA MWD, Rev. 3 (Standard)		No.274H PWB

Clearance Report

B-1

Closest Approach

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

CALCULATION RANGE & CUTOFF		
From: **20.00ft MD**	To: **15784.22ft MD**	C-C Cutoff: **(none)**

OFFSET WELL CLEARANCE SUMMARY (2 Offset Wellpaths selected) Ratios are calculated in Closest Approach plane

Offset Facility	Offset Slot	Offset Well	Offset Wellbore	Offset Wellpath	C-C Clearance Distance			ACR Separation Ratio			
					Ref MD [ft]	Min C-C Clear Dist [ft]	Diverging from MD [ft]	Ref MD of Min Ratio [ft]	Min Ratio	Min Ratio Dvrg from [ft]	ACR Status
BEU No.33 (offest)	No.33 SHL	No.33	No.33 AWB	No.33 AWP	15395.31	20.09	15395.31	15395.31	0.03	15395.31	FAIL
Drilling Island 4 - B	No.273H SHL	No.273H	No.273H PWB	B-1	20.00	40.00	8320.00	8402.96	0.80	8402.96	FAIL

Clearance Report

B-1

Closest Approach

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

CLEARANCE DATA - Offset Wellbore: **No.33 AWB** Offset Wellpath: **No.33 AWP**

Facility: BEU No.33 (offest) **Slot: No.33 SHL** **Well: No.33** **Threshold Value=1.00** † = interpolated/extrapolated station

Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	ACR Status
20.00	20.00	0.00	0.00	19.00	20.00	-21.85	6632.77	90.19	6632.81	29.30	226.40	PASS
120.00†	120.00	0.00	0.00	119.00	120.00	-21.85	6632.77	90.19	6632.81	34.38	192.93	PASS
220.00†	220.00	0.00	0.00	219.00	220.00	-21.85	6632.77	90.19	6632.81	39.51	167.86	PASS
320.00†	320.00	0.00	0.00	319.00	320.00	-21.85	6632.77	90.19	6632.81	44.70	148.40	PASS
420.00†	420.00	0.00	0.00	419.00	420.00	-21.85	6632.77	90.19	6632.81	49.92	132.87	PASS
520.00†	520.00	0.00	0.00	519.00	520.00	-21.85	6632.77	90.19	6632.81	55.08	120.43	PASS
620.00†	620.00	0.00	0.00	619.00	620.00	-21.85	6632.77	90.19	6632.81	60.15	110.27	PASS
720.00†	720.00	0.00	0.00	719.00	720.00	-21.85	6632.77	90.19	6632.81	65.25	101.65	PASS
820.00†	820.00	0.00	0.00	819.00	820.00	-21.85	6632.77	90.19	6632.81	70.38	94.24	PASS
920.00†	920.00	0.00	0.00	919.00	920.00	-21.85	6632.77	90.19	6632.81	75.53	87.81	PASS
1020.00†	1020.00	0.00	0.00	1019.00	1020.00	-21.85	6632.77	90.19	6632.81	80.71	82.18	PASS
1120.00†	1120.00	0.00	0.00	1119.00	1120.00	-21.85	6632.77	90.19	6632.81	85.91	77.21	PASS
1220.00†	1220.00	0.00	0.00	1219.00	1220.00	-21.85	6632.77	90.19	6632.81	91.12	72.79	PASS
1320.00†	1320.00	0.00	0.00	1319.00	1320.00	-21.85	6632.77	90.19	6632.81	96.36	68.84	PASS
1420.00†	1420.00	0.00	0.00	1419.00	1420.00	-21.85	6632.77	90.19	6632.81	101.60	65.28	PASS
1520.00†	1520.00	0.00	0.00	1519.00	1520.00	-21.85	6632.77	90.19	6632.81	106.86	62.07	PASS
1620.00†	1620.00	0.00	0.00	1619.00	1620.00	-21.85	6632.77	90.19	6632.81	112.14	59.15	PASS
1720.00†	1720.00	0.00	0.00	1719.00	1720.00	-21.85	6632.77	90.19	6632.81	117.42	56.49	PASS
1820.00†	1820.00	0.00	0.00	1819.00	1820.00	-21.85	6632.77	90.19	6632.81	122.71	54.05	PASS
1920.00†	1920.00	0.00	0.00	1919.00	1920.00	-21.85	6632.77	90.19	6632.81	128.01	51.82	PASS
2020.00†	2020.00	0.00	0.00	2019.00	2020.00	-21.85	6632.77	90.19	6632.81	133.31	49.75	PASS
2120.00†	2120.00	0.00	0.00	2119.00	2120.00	-21.85	6632.77	90.19	6632.81	138.62	47.85	PASS
2220.00†	2220.00	0.00	0.00	2219.00	2220.00	-21.85	6632.77	90.19	6632.81	143.94	46.08	PASS
2320.00†	2320.00	0.00	0.00	2319.00	2320.00	-21.85	6632.77	90.19	6632.81	149.26	44.44	PASS
2420.00†	2420.00	0.00	0.00	2419.00	2420.00	-21.85	6632.77	90.19	6632.81	154.59	42.91	PASS
2520.00†	2520.00	0.00	0.00	2519.00	2520.00	-21.85	6632.77	90.19	6632.81	159.91	41.48	PASS
2620.00†	2620.00	0.00	0.00	2619.00	2620.00	-21.85	6632.77	90.19	6632.81	165.25	40.14	PASS
2720.00†	2720.00	0.00	0.00	2719.00	2720.00	-21.85	6632.77	90.19	6632.81	170.58	38.88	PASS
2820.00†	2820.00	0.00	0.00	2819.00	2820.00	-21.85	6632.77	90.19	6632.81	175.92	37.70	PASS
2920.00†	2920.00	0.00	0.00	2919.00	2920.00	-21.85	6632.77	90.19	6632.81	181.26	36.59	PASS
3020.00†	3020.00	0.00	0.00	3019.00	3020.00	-21.85	6632.77	90.19	6632.81	186.60	35.55	PASS
3120.00†	3120.00	0.00	0.00	3119.00	3120.00	-21.85	6632.77	90.19	6632.81	191.94	34.56	PASS
3220.00†	3220.00	0.00	0.00	3219.00	3220.00	-21.85	6632.77	90.19	6632.81	197.29	33.62	PASS
3320.00†	3320.00	0.00	0.00	3319.00	3320.00	-21.85	6632.77	90.19	6632.81	202.63	32.73	PASS
3420.00†	3420.00	0.00	0.00	3419.00	3420.00	-21.85	6632.77	90.19	6632.81	207.98	31.89	PASS
3520.00†	3520.00	0.00	0.00	3519.00	3520.00	-21.85	6632.77	90.19	6632.81	213.33	31.09	PASS
3620.00†	3620.00	0.00	0.00	3619.00	3620.00	-21.85	6632.77	90.19	6632.81	218.68	30.33	PASS
3720.00†	3720.00	0.00	0.00	3719.00	3720.00	-21.85	6632.77	90.19	6632.81	224.03	29.61	PASS
3820.00†	3820.00	0.00	0.00	3819.00	3820.00	-21.85	6632.77	90.19	6632.81	229.38	28.92	PASS
3920.00†	3920.00	0.00	0.00	3919.00	3920.00	-21.85	6632.77	90.19	6632.81	234.74	28.26	PASS
4020.00†	4020.00	0.00	0.00	4019.00	4020.00	-21.85	6632.77	90.19	6632.81	240.09	27.63	PASS
4120.00†	4120.00	0.00	0.00	4119.00	4120.00	-21.85	6632.77	90.19	6632.81	245.45	27.02	PASS
4220.00†	4220.00	0.00	0.00	4219.00	4220.00	-21.85	6632.77	90.19	6632.81	250.80	26.45	PASS
4320.00†	4320.00	0.00	0.00	4319.00	4320.00	-21.85	6632.77	90.19	6632.81	256.16	25.89	PASS
4420.00†	4420.00	0.00	0.00	4419.00	4420.00	-21.85	6632.77	90.19	6632.81	261.52	25.36	PASS

Clearance Report

B-1

Closest Approach

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

CLEARANCE DATA - Offset Wellbore: **No.33 AWB** Offset Wellpath: **No.33 AWP**

Facility: BEU No.33 (offest) **Slot: No.33 SHL** **Well: No.33** **Threshold Value=1.00** † = interpolated/extrapolated station

Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	ACR Status
4520.00†	4520.00	0.00	0.00	4519.00	4520.00	-21.85	6632.77	90.19	6632.81	266.87	24.85	PASS
4620.00†	4620.00	0.00	0.00	4619.00	4620.00	-21.85	6632.77	90.19	6632.81	272.23	24.36	PASS
4720.00†	4720.00	0.00	0.00	4719.00	4720.00	-21.85	6632.77	90.19	6632.81	277.59	23.89	PASS
4820.00†	4820.00	0.00	0.00	4819.00	4820.00	-21.85	6632.77	90.19	6632.81	282.95	23.44	PASS
4920.00†	4920.00	0.00	0.00	4919.00	4920.00	-21.85	6632.77	90.19	6632.81	288.31	23.01	PASS
5020.00†	5020.00	0.00	0.00	5019.00	5020.00	-21.85	6632.77	90.19	6632.81	293.67	22.59	PASS
5120.00†	5120.00	0.00	0.00	5119.00	5120.00	-21.85	6632.77	90.19	6632.81	299.03	22.18	PASS
5220.00†	5220.00	0.00	0.00	5219.00	5220.00	-21.85	6632.77	90.19	6632.81	304.39	21.79	PASS
5320.00†	5320.00	0.00	0.00	5319.00	5320.00	-21.85	6632.77	90.19	6632.81	309.75	21.41	PASS
5420.00†	5420.00	0.00	0.00	5419.00	5420.00	-21.85	6632.77	90.19	6632.81	315.11	21.05	PASS
5520.00†	5520.00	0.00	0.00	5519.00	5520.00	-21.85	6632.77	90.19	6632.81	320.48	20.70	PASS
5620.00†	5620.00	0.00	0.00	5619.00	5620.00	-21.85	6632.77	90.19	6632.81	325.84	20.36	PASS
5720.00†	5720.00	0.00	0.00	5719.00	5720.00	-21.85	6632.77	90.19	6632.81	331.20	20.03	PASS
5820.00†	5820.00	0.00	0.00	5819.00	5820.00	-21.85	6632.77	90.19	6632.81	336.56	19.71	PASS
5920.00†	5920.00	0.00	0.00	5919.00	5920.00	-21.85	6632.77	90.19	6632.81	341.93	19.40	PASS
6020.00†	6020.00	0.00	0.00	6019.00	6020.00	-21.85	6632.77	90.19	6632.81	347.29	19.10	PASS
6120.00†	6120.00	0.00	0.00	6119.00	6120.00	-21.85	6632.77	90.19	6632.81	352.65	18.81	PASS
6220.00†	6220.00	0.00	0.00	6219.00	6220.00	-21.85	6632.77	90.19	6632.81	358.02	18.53	PASS
6320.00†	6320.00	0.00	0.00	6319.00	6320.00	-21.85	6632.77	90.19	6632.81	363.38	18.25	PASS
6420.00†	6420.00	0.00	0.00	6419.00	6420.00	-21.85	6632.77	90.19	6632.81	368.74	17.99	PASS
6520.00†	6520.00	0.00	0.00	6519.00	6520.00	-21.85	6632.77	90.19	6632.81	374.11	17.73	PASS
6620.00†	6620.00	0.00	0.00	6619.00	6620.00	-21.85	6632.77	90.19	6632.81	379.47	17.48	PASS
6720.00†	6720.00	0.00	0.00	6719.00	6720.00	-21.85	6632.77	90.19	6632.81	384.84	17.24	PASS
6820.00†	6820.00	0.00	0.00	6819.00	6820.00	-21.85	6632.77	90.19	6632.81	390.20	17.00	PASS
6920.00†	6920.00	0.00	0.00	6919.00	6920.00	-21.85	6632.77	90.19	6632.81	395.56	16.77	PASS
7020.00†	7020.00	0.00	0.00	7019.00	7020.00	-21.85	6632.77	90.19	6632.81	400.93	16.54	PASS
7120.00†	7120.00	0.00	0.00	7119.00	7120.00	-21.85	6632.77	90.19	6632.81	406.29	16.33	PASS
7220.00†	7220.00	0.00	0.00	7219.00	7220.00	-21.85	6632.77	90.19	6632.81	411.66	16.11	PASS
7320.00†	7320.00	0.00	0.00	7319.00	7320.00	-21.85	6632.77	90.19	6632.81	417.03	15.91	PASS
7420.00†	7420.00	0.00	0.00	7419.00	7420.00	-21.85	6632.77	90.19	6632.81	422.39	15.70	PASS
7520.00†	7520.00	0.00	0.00	7519.00	7520.00	-21.85	6632.77	90.19	6632.81	427.76	15.51	PASS
7620.00†	7620.00	0.00	0.00	7619.00	7620.00	-21.85	6632.77	90.19	6632.81	433.12	15.31	PASS
7720.00†	7720.00	0.00	0.00	7719.00	7720.00	-21.85	6632.77	90.19	6632.81	438.49	15.13	PASS
7820.00†	7820.00	0.00	0.00	7819.00	7820.00	-21.85	6632.77	90.19	6632.81	443.85	14.94	PASS
7920.00†	7920.00	0.00	0.00	7919.00	7920.00	-21.85	6632.77	90.19	6632.81	449.22	14.77	PASS
8020.00†	8020.00	0.00	0.00	8019.00	8020.00	-21.85	6632.77	90.19	6632.81	454.59	14.59	PASS
8120.00†	8120.00	0.00	0.00	8119.00	8120.00	-21.85	6632.77	90.19	6632.81	459.95	14.42	PASS
8220.00†	8220.00	0.00	0.00	8219.00	8220.00	-21.85	6632.77	90.19	6632.81	465.32	14.25	PASS
8320.00†	8320.00	0.00	0.00	8319.00	8320.00	-21.85	6632.77	90.19	6632.81	470.68	14.09	PASS
8420.00	8420.00	0.00	0.00	8419.00	8420.00	-21.85	6632.77	90.19	6632.81	476.05	13.93	PASS
8520.00†	8519.49	-0.05	8.70	8518.49	8519.49	-21.85	6632.77	90.19	6624.11	481.39	13.76	PASS
8620.00†	8615.96	-0.22	34.55	8614.96	8615.96	-21.85	6632.77	90.19	6598.26	486.58	13.56	PASS
8720.00†	8706.48	-0.48	76.76	8705.48	8706.48	-21.85	6632.77	90.19	6556.05	491.45	13.34	PASS
8820.00†	8788.29	-0.85	134.04	8787.29	8788.29	-21.85	6632.77	90.19	6498.76	495.86	13.11	PASS
8920.00†	8858.91	-1.29	204.66	8857.91	8858.91	-21.85	6632.77	90.18	6428.14	499.66	12.86	PASS

Clearance Report

B-1

Closest Approach

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

CLEARANCE DATA - Offset Wellbore: **No.33 AWB** Offset Wellpath: **No.33 AWP**

Facility: BEU No.33 (offest) Slot: No.33 SHL Well: No.33 Threshold Value=1.00 † = interpolated/extrapolated statior

Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	ACR Status
9020.00†	8916.20	-1.81	286.47	8915.20	8916.20	-21.85	6632.77	90.18	6346.33	502.75	12.62	PASS
9120.00	8958.40	-2.38	376.99	8957.40	8958.40	-21.85	6632.77	90.18	6255.82	505.03	12.39	PASS
9220.00†	8992.61	-2.98	470.95	8991.61	8992.61	-21.85	6632.77	90.18	6161.85	506.87	12.16	PASS
9320.00	9026.81	-3.57	564.92	9025.81	9026.81	-21.85	6632.77	90.17	6067.88	508.70	11.93	PASS
9420.00†	9056.01	-4.17	660.51	9055.01	9056.01	-21.85	6632.77	90.17	5972.29	510.27	11.70	PASS
9520.00†	9075.01	-4.80	758.64	9074.01	9075.01	-21.85	6632.77	90.17	5874.16	511.31	11.49	PASS
9620.00†	9083.60	-5.43	858.23	9082.60	9083.60	-21.85	6632.77	90.16	5774.57	511.80	11.28	PASS
9636.30	9084.00	-5.53	874.52	9083.00	9084.00	-21.85	6632.77	90.16	5758.28	511.82	11.25	PASS
9636.44	9084.00	-5.53	874.66	9083.00	9084.00	-21.85	6632.77	90.16	5758.14	511.82	11.25	PASS
9720.00†	9085.36	-6.06	958.21	9084.36	9085.36	-21.85	6632.77	90.16	5674.59	511.92	11.08	PASS
9820.00†	9086.99	-6.70	1058.19	9085.99	9086.99	-21.85	6632.77	90.16	5574.60	512.04	10.89	PASS
9920.00†	9088.61	-7.33	1158.18	9087.61	9088.61	-21.85	6632.77	90.15	5474.62	512.16	10.69	PASS
10020.00†	9090.24	-7.96	1258.16	9089.24	9090.24	-21.85	6632.77	90.15	5374.63	512.28	10.49	PASS
10120.00†	9091.87	-8.59	1358.15	9090.87	9091.87	-21.85	6632.77	90.14	5274.64	512.41	10.29	PASS
10220.00†	9093.49	-9.22	1458.13	9092.49	9093.49	-21.85	6632.77	90.14	5174.66	512.53	10.10	PASS
10320.00†	9095.12	-9.86	1558.12	9094.12	9095.12	-21.85	6632.77	90.14	5074.67	512.66	9.90	PASS
10420.00†	9096.75	-10.49	1658.10	9095.75	9096.75	-21.85	6632.77	90.13	4974.69	512.80	9.70	PASS
10520.00†	9098.37	-11.12	1758.09	9097.37	9098.37	-21.85	6632.77	90.13	4874.70	512.93	9.50	PASS
10620.00†	9100.00	-11.75	1858.07	9099.00	9100.00	-21.85	6632.77	90.12	4774.71	513.07	9.31	PASS
10720.00†	9101.63	-12.39	1958.05	9100.63	9101.63	-21.85	6632.77	90.12	4674.73	513.21	9.11	PASS
10820.00†	9103.25	-13.02	2058.04	9102.25	9103.25	-21.85	6632.77	90.11	4574.74	513.36	8.91	PASS
10920.00†	9104.88	-13.65	2158.02	9103.88	9104.88	-21.85	6632.77	90.11	4474.76	513.50	8.71	PASS
11020.00†	9106.51	-14.28	2258.01	9105.51	9106.51	-21.85	6632.77	90.10	4374.77	513.65	8.52	PASS
11120.00†	9108.13	-14.91	2357.99	9107.13	9108.13	-21.85	6632.77	90.09	4274.79	513.80	8.32	PASS
11220.00†	9109.76	-15.55	2457.98	9108.76	9109.76	-21.85	6632.77	90.09	4174.80	513.95	8.12	PASS
11320.00†	9111.39	-16.18	2557.96	9110.39	9111.39	-21.85	6632.77	90.08	4074.81	514.11	7.93	PASS
11420.00†	9113.01	-16.81	2657.95	9112.01	9113.01	-21.85	6632.77	90.07	3974.83	514.27	7.73	PASS
11520.00†	9114.64	-17.44	2757.93	9113.64	9114.64	-21.85	6632.77	90.07	3874.84	514.43	7.53	PASS
11620.00†	9116.27	-18.08	2857.92	9115.27	9116.27	-21.85	6632.77	90.06	3774.86	514.59	7.34	PASS
11720.00†	9117.89	-18.71	2957.90	9116.89	9117.89	-21.85	6632.77	90.05	3674.87	514.76	7.14	PASS
11820.00†	9119.52	-19.34	3057.89	9118.52	9119.52	-21.85	6632.77	90.04	3574.89	514.93	6.94	PASS
11920.00†	9121.15	-19.97	3157.87	9120.15	9121.15	-21.85	6632.77	90.03	3474.90	515.10	6.75	PASS
12020.00†	9122.77	-20.60	3257.86	9121.77	9122.77	-21.85	6632.77	90.02	3374.92	515.27	6.55	PASS
12120.00†	9124.40	-21.24	3357.84	9123.40	9124.40	-21.85	6632.77	90.01	3274.93	515.45	6.35	PASS
12220.00†	9126.03	-21.87	3457.83	9125.03	9126.03	-21.85	6632.77	90.00	3174.95	515.63	6.16	PASS
12320.00†	9127.65	-22.50	3557.81	9126.65	9127.65	-21.85	6632.77	89.99	3074.96	515.81	5.96	PASS
12420.00†	9129.28	-23.13	3657.80	9128.28	9129.28	-21.85	6632.77	89.98	2974.98	515.99	5.77	PASS
12520.00†	9130.91	-23.77	3757.78	9129.91	9130.91	-21.85	6632.77	89.96	2874.99	516.18	5.57	PASS
12620.00†	9132.53	-24.40	3857.77	9131.53	9132.53	-21.85	6632.77	89.95	2775.01	516.36	5.37	PASS
12720.00†	9134.16	-25.03	3957.75	9133.16	9134.16	-21.85	6632.77	89.93	2675.03	516.55	5.18	PASS
12820.00†	9135.79	-25.66	4057.74	9134.79	9135.79	-21.85	6632.77	89.92	2575.04	516.75	4.98	PASS
12920.00†	9137.41	-26.29	4157.72	9136.41	9137.41	-21.85	6632.77	89.90	2475.06	516.94	4.79	PASS
13020.00†	9139.04	-26.93	4257.70	9138.04	9139.04	-21.85	6632.77	89.88	2375.07	517.14	4.59	PASS
13120.00†	9140.66	-27.56	4357.69	9139.66	9140.66	-21.85	6632.77	89.86	2275.09	517.34	4.40	PASS
13220.00†	9142.29	-28.19	4457.67	9141.29	9142.29	-21.85	6632.77	89.83	2175.11	517.55	4.20	PASS

Clearance Report

B-1

Closest Approach

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

CLEARANCE DATA - Offset Wellbore: **No.33 AWB** Offset Wellpath: **No.33 AWP**

Facility: BEU No.33 (offest) **Slot: No.33 SHL** **Well: No.33** **Threshold Value=1.00** **† = interpolated/extrapolated station**

Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	ACR Status
13320.00†	9143.92	-28.82	4557.66	9142.92	9143.92	-21.85	6632.77	89.81	2075.13	517.75	4.01	PASS
13420.00†	9145.54	-29.46	4657.64	9144.54	9145.54	-21.85	6632.77	89.78	1975.14	517.96	3.81	PASS
13520.00†	9147.17	-30.09	4757.63	9146.17	9147.17	-21.85	6632.77	89.75	1875.16	518.18	3.62	PASS
13620.00†	9148.80	-30.72	4857.61	9147.80	9148.80	-21.85	6632.77	89.71	1775.18	518.40	3.42	PASS
13720.00†	9150.42	-31.35	4957.60	9149.42	9150.42	-21.85	6632.77	89.68	1675.20	518.62	3.23	PASS
13820.00†	9152.05	-31.98	5057.58	9151.05	9152.05	-21.85	6632.77	89.63	1575.22	518.84	3.04	PASS
13920.00†	9153.68	-32.62	5157.57	9152.68	9153.68	-21.85	6632.77	89.58	1475.25	519.08	2.84	PASS
14020.00†	9155.30	-33.25	5257.55	9154.30	9155.30	-21.85	6632.77	89.53	1375.27	519.32	2.65	PASS
14120.00†	9156.93	-33.88	5357.54	9155.93	9156.93	-21.85	6632.77	89.46	1275.29	519.56	2.45	PASS
14220.00†	9158.56	-34.51	5457.52	9157.56	9158.56	-21.85	6632.77	89.38	1175.32	519.82	2.26	PASS
14320.00†	9160.18	-35.15	5557.51	9159.18	9160.18	-21.85	6632.77	89.29	1075.35	520.10	2.07	PASS
14420.00†	*9161.81*	*-35.78*	*5657.49*	*9160.81*	*9161.81*	*-21.85*	*6632.77*	*89.18*	*975.38*	*520.39*	*1.87*	*PASS*
14520.00†	9163.44	-36.41	5757.48	9162.44	9163.44	-21.85	6632.77	89.05	875.42	520.71	1.68	PASS
14620.00†	9165.06	-37.04	5857.46	9164.06	9165.06	-21.85	6632.77	88.88	775.46	521.08	1.49	PASS
14720.00†	9166.69	-37.67	5957.45	9165.69	9166.69	-21.85	6632.77	88.66	675.51	521.51	1.30	PASS
14820.00†	9168.32	-38.31	6057.43	9167.32	9168.32	-21.85	6632.77	88.36	575.58	522.07	1.10	PASS
14920.00†	9169.94	-38.94	6157.42	9168.94	9169.94	-21.85	6632.77	87.94	475.67	522.86	0.91	FAIL
15020.00†	9171.57	-39.57	6257.40	9170.57	9171.57	-21.85	6632.77	87.30	375.79	524.15	0.72	FAIL
15120.00†	9173.20	-40.20	6357.38	9172.20	9173.20	-21.85	6632.77	86.19	276.00	526.70	0.52	FAIL
15220.00†	9174.82	-40.84	6457.37	9173.82	9174.82	-21.85	6632.77	83.82	176.43	533.52	0.33	FAIL
15320.00†	9176.45	-41.47	6557.35	9175.45	9176.45	-21.85	6632.77	75.42	77.93	565.57	0.14	FAIL
15395.31†	9177.67	-41.94	6632.66	9176.68	9177.68	-21.85	6632.77	0.33	20.09	761.59	0.03	FAIL
15395.32†	9177.67	-41.94	6632.66	9176.67	9177.67	-21.85	6632.77	0.32	20.09	761.59	0.03	FAIL
15420.00†	9178.08	-42.10	6657.34	9177.08	9178.08	-21.85	6632.77	309.50	31.84	663.67	0.05	FAIL
15520.00†	9179.70	-42.73	6757.32	9178.70	9179.70	-21.85	6632.77	279.52	126.29	544.32	0.23	FAIL
15620.00†	9181.33	-43.36	6857.31	9180.33	9181.33	-21.85	6632.77	275.47	225.56	531.06	0.42	FAIL
15720.00†	9182.96	-44.00	6957.29	9181.96	9182.96	-21.85	6632.77	273.90	325.27	527.35	0.62	FAIL
15784.22	9184.00	-44.40	7021.50	9183.00	9184.00	-21.85	6632.77	273.32	389.38	526.31	0.74	FAIL

POSITIONAL UNCERTAINTY - **Offset Wellbore: No.33 AWB** **Offset Wellpath: No.33 AWP**

Slot Surface Uncertainty @1SD	Horizontal	2.000ft	Vertical	1.000ft
Facility Surface Uncertainty @1SD	Horizontal	8.200ft	Vertical	1.000ft

WELLPATH COMPOSITION - **Offset Wellbore: No.33 AWB** **Offset Wellpath: No.33 AWP**

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
0.00	12000.00	Unknown Tool (Standard)	Unknown <12000>	No.33 AWB

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

OFFSET WELLPATH MD REFERENCE - Offset Wellbore: No.33 AWB Offset Wellpath: No.33 AWP	
MD Reference: **Rig on No.33 SHL (RT)**	*Offset TVD & local coordinates use Reference Wellpath settings (See WELLPATH DATUM on page 1 of this report)*
Ellipse Start MD	**0.00ft**

Clearance Report

B-1

Closest Approach

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

CLEARANCE DATA - Offset Wellbore: **No.273H PWB** Offset Wellpath: **B-1**

Facility: Drilling Island 4 - B **Slot: No.273H SHL** **Well: No.273H** **Threshold Value=1.00** † = interpolated/extrapolated s

Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio
20.00	20.00	0.00	0.00	20.00	20.00	0.30	-40.00	270.43	40.00	0.60	66.67
120.00†	120.00	0.00	0.00	120.00	120.00	0.30	-40.00	270.43	40.00	1.00	39.84
220.00†	220.00	0.00	0.00	220.00	220.00	0.30	-40.00	270.43	40.00	1.72	23.28
320.00†	320.00	0.00	0.00	320.00	320.00	0.30	-40.00	270.43	40.00	2.49	16.07
420.00†	420.00	0.00	0.00	420.00	420.00	0.30	-40.00	270.43	40.00	3.28	12.21
520.00†	520.00	0.00	0.00	520.00	520.00	0.30	-40.00	270.43	40.00	3.68	10.88
620.00†	620.00	0.00	0.00	620.00	620.00	0.30	-40.00	270.43	40.00	3.75	10.68
720.00†	720.00	0.00	0.00	720.00	720.00	0.30	-40.00	270.43	40.00	3.92	10.21
820.00†	820.00	0.00	0.00	820.00	820.00	0.30	-40.00	270.43	40.00	4.18	9.57
920.00†	920.00	0.00	0.00	920.00	920.00	0.30	-40.00	270.43	40.00	4.51	8.86
1020.00†	1020.00	0.00	0.00	1020.00	1020.00	0.30	-40.00	270.43	40.00	4.91	8.15
1120.00†	1120.00	0.00	0.00	1120.00	1120.00	0.30	-40.00	270.43	40.00	5.34	7.49
1220.00†	1220.00	0.00	0.00	1220.00	1220.00	0.30	-40.00	270.43	40.00	5.82	6.88
1320.00†	1320.00	0.00	0.00	1320.00	1320.00	0.30	-40.00	270.43	40.00	6.32	6.33
1420.00†	1420.00	0.00	0.00	1420.00	1420.00	0.30	-40.00	270.43	40.00	6.84	5.85
1520.00†	1520.00	0.00	0.00	1520.00	1520.00	0.30	-40.00	270.43	40.00	7.37	5.42
1620.00†	1620.00	0.00	0.00	1620.00	1620.00	0.30	-40.00	270.43	40.00	7.93	5.05
1720.00†	1720.00	0.00	0.00	1720.00	1720.00	0.30	-40.00	270.43	40.00	8.49	4.71
1820.00†	1820.00	0.00	0.00	1820.00	1820.00	0.30	-40.00	270.43	40.00	9.06	4.42
1920.00†	1920.00	0.00	0.00	1920.00	1920.00	0.30	-40.00	270.43	40.00	9.63	4.15
2020.00†	2020.00	0.00	0.00	2020.00	2020.00	0.30	-40.00	270.43	40.00	10.22	3.91
2120.00†	2120.00	0.00	0.00	2120.00	2120.00	0.30	-40.00	270.43	40.00	10.81	3.70
2220.00†	2220.00	0.00	0.00	2220.00	2220.00	0.30	-40.00	270.43	40.00	11.40	3.51
2320.00†	2320.00	0.00	0.00	2320.00	2320.00	0.30	-40.00	270.43	40.00	12.00	3.33
2420.00†	2420.00	0.00	0.00	2420.00	2420.00	0.30	-40.00	270.43	40.00	12.60	3.18
2520.00†	2520.00	0.00	0.00	2520.00	2520.00	0.30	-40.00	270.43	40.00	13.20	3.03
2620.00†	2620.00	0.00	0.00	2620.00	2620.00	0.30	-40.00	270.43	40.00	13.80	2.90
2720.00†	2720.00	0.00	0.00	2720.00	2720.00	0.30	-40.00	270.43	40.00	14.41	2.78
2820.00†	2820.00	0.00	0.00	2820.00	2820.00	0.30	-40.00	270.43	40.00	15.02	2.66
2920.00†	2920.00	0.00	0.00	2920.00	2920.00	0.30	-40.00	270.43	40.00	15.63	2.56
3020.00†	3020.00	0.00	0.00	3020.00	3020.00	0.30	-40.00	270.43	40.00	16.24	2.46
3120.00†	3120.00	0.00	0.00	3120.00	3120.00	0.30	-40.00	270.43	40.00	16.85	2.37
3220.00†	3220.00	0.00	0.00	3220.00	3220.00	0.30	-40.00	270.43	40.00	17.47	2.29
3320.00†	3320.00	0.00	0.00	3320.00	3320.00	0.30	-40.00	270.43	40.00	18.08	2.21
3420.00†	3420.00	0.00	0.00	3420.00	3420.00	0.30	-40.00	270.43	40.00	18.70	2.14
3520.00†	3520.00	0.00	0.00	3520.00	3520.00	0.30	-40.00	270.43	40.00	19.31	2.07
3620.00†	3620.00	0.00	0.00	3620.00	3620.00	0.30	-40.00	270.43	40.00	19.93	2.01
3720.00†	3720.00	0.00	0.00	3720.00	3720.00	0.30	-40.00	270.43	40.00	20.55	1.95
3820.00†	3820.00	0.00	0.00	3820.00	3820.00	0.30	-40.00	270.43	40.00	21.17	1.89
3920.00†	3920.00	0.00	0.00	3920.00	3920.00	0.30	-40.00	270.43	40.00	21.79	1.84
4020.00†	4020.00	0.00	0.00	4020.00	4020.00	0.30	-40.00	270.43	40.00	22.40	1.79
4120.00†	4120.00	0.00	0.00	4120.00	4120.00	0.30	-40.00	270.43	40.00	23.02	1.74
4220.00†	4220.00	0.00	0.00	4220.00	4220.00	0.30	-40.00	270.43	40.00	23.65	1.69
4320.00†	4320.00	0.00	0.00	4320.00	4320.00	0.30	-40.00	270.43	40.00	24.27	1.65
4420.00†	4420.00	0.00	0.00	4420.00	4420.00	0.30	-40.00	270.43	40.00	24.89	1.61

Clearance Report

B-1

Closest Approach

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

CLEARANCE DATA - Offset Wellbore: **No.273H PWB** Offset Wellpath: **B-1**

Facility: Drilling Island 4 - B **Slot: No.273H SHL** **Well: No.273H** **Threshold Value=1.00** † = interpolated/extrapolated s

Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio
4520.00†	4520.00	0.00	0.00	4520.00	4520.00	0.30	-40.00	270.43	40.00	25.51	1.57
4620.00†	4620.00	0.00	0.00	4620.00	4620.00	0.30	-40.00	270.43	40.00	26.13	1.53
4720.00†	4720.00	0.00	0.00	4720.00	4720.00	0.30	-40.00	270.43	40.00	26.75	1.50
4820.00†	4820.00	0.00	0.00	4820.00	4820.00	0.30	-40.00	270.43	40.00	27.38	1.46
4920.00†	4920.00	0.00	0.00	4920.00	4920.00	0.30	-40.00	270.43	40.00	28.00	1.43
5020.00†	5020.00	0.00	0.00	5020.00	5020.00	0.30	-40.00	270.43	40.00	28.62	1.40
5120.00†	5120.00	0.00	0.00	5120.00	5120.00	0.30	-40.00	270.43	40.00	29.24	1.37
5220.00†	5220.00	0.00	0.00	5220.00	5220.00	0.30	-40.00	270.43	40.00	29.87	1.34
5320.00†	5320.00	0.00	0.00	5320.00	5320.00	0.30	-40.00	270.43	40.00	30.49	1.31
5420.00†	5420.00	0.00	0.00	5420.00	5420.00	0.30	-40.00	270.43	40.00	31.12	1.29
5520.00†	5520.00	0.00	0.00	5520.00	5520.00	0.30	-40.00	270.43	40.00	31.74	1.26
5620.00†	5620.00	0.00	0.00	5620.00	5620.00	0.30	-40.00	270.43	40.00	32.36	1.24
5720.00†	5720.00	0.00	0.00	5720.00	5720.00	0.30	-40.00	270.43	40.00	32.99	1.21
5820.00†	5820.00	0.00	0.00	5820.00	5820.00	0.30	-40.00	270.43	40.00	33.61	1.19
5920.00†	5920.00	0.00	0.00	5920.00	5920.00	0.30	-40.00	270.43	40.00	34.24	1.17
6020.00†	6020.00	0.00	0.00	6020.00	6020.00	0.30	-40.00	270.43	40.00	34.86	1.15
6120.00†	6120.00	0.00	0.00	6120.00	6120.00	0.30	-40.00	270.43	40.00	35.49	1.13
6220.00†	6220.00	0.00	0.00	6220.00	6220.00	0.30	-40.00	270.43	40.00	36.11	1.11
6320.00†	6320.00	0.00	0.00	6320.00	6320.00	0.30	-40.00	270.43	40.00	36.74	1.09
6420.00†	6420.00	0.00	0.00	6420.00	6420.00	0.30	-40.00	270.43	40.00	37.36	1.07
6520.00†	6520.00	0.00	0.00	6520.00	6520.00	0.30	-40.00	270.43	40.00	37.99	1.05
6620.00†	6620.00	0.00	0.00	6620.00	6620.00	0.30	-40.00	270.43	40.00	38.61	1.04
6720.00†	6720.00	0.00	0.00	6720.00	6720.00	0.30	-40.00	270.43	40.00	39.24	1.02
6820.00†	6820.00	0.00	0.00	6820.00	6820.00	0.30	-40.00	270.43	40.00	39.86	1.00
6920.00†	6920.00	0.00	0.00	6920.00	6920.00	0.30	-40.00	270.43	40.00	40.49	0.99
7020.00†	7020.00	0.00	0.00	7020.00	7020.00	0.30	-40.00	270.43	40.00	41.12	0.97
7120.00†	7120.00	0.00	0.00	7120.00	7120.00	0.30	-40.00	270.43	40.00	41.74	0.96
7220.00†	7220.00	0.00	0.00	7220.00	7220.00	0.30	-40.00	270.43	40.00	42.37	0.94
7320.00†	7320.00	0.00	0.00	7320.00	7320.00	0.30	-40.00	270.43	40.00	42.99	0.93
7420.00†	7420.00	0.00	0.00	7420.00	7420.00	0.30	-40.00	270.43	40.00	43.62	0.92
7520.00†	7520.00	0.00	0.00	7520.00	7520.00	0.30	-40.00	270.43	40.00	44.25	0.90
7620.00†	7620.00	0.00	0.00	7620.00	7620.00	0.30	-40.00	270.43	40.00	44.87	0.89
7720.00†	7720.00	0.00	0.00	7720.00	7720.00	0.30	-40.00	270.43	40.00	45.50	0.88
7820.00†	7820.00	0.00	0.00	7820.00	7820.00	0.30	-40.00	270.43	40.00	46.12	0.87
7920.00†	7920.00	0.00	0.00	7920.00	7920.00	0.30	-40.00	270.43	40.00	46.75	0.86
8020.00†	8020.00	0.00	0.00	8020.00	8020.00	0.30	-40.00	270.43	40.00	47.38	0.84
8120.00†	8120.00	0.00	0.00	8120.00	8120.00	0.30	-40.00	270.43	40.00	48.00	0.83
8220.00†	8220.00	0.00	0.00	8220.00	8220.00	0.30	-40.00	270.43	40.00	48.63	0.82
8320.00†	8320.00	0.00	0.00	8320.00	8320.00	0.30	-40.00	270.43	40.00	49.26	0.81
8402.96†	8402.96	0.00	0.00	8402.77	8402.77	0.30	-40.01	270.43	40.01	49.78	0.80
8420.00	8420.00	0.00	0.00	8418.69	8418.68	0.30	-40.31	270.42	40.33	49.87	0.81
8520.00†	8519.49	-0.05	8.70	8508.81	8508.15	0.18	-50.30	270.23	60.09	50.26	1.20
8620.00†	8615.96	-0.22	34.55	8584.45	8581.28	-0.03	-69.44	270.10	109.62	50.45	2.17
8720.00†	8706.48	-0.48	76.76	8639.59	8632.67	-0.26	-89.37	270.08	181.79	50.59	3.59
8820.00†	8788.29	-0.85	134.04	8674.66	8664.26	-0.43	-104.58	270.10	268.93	50.72	5.30

Clearance Report

B-1

Closest Approach

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

CLEARANCE DATA - Offset Wellbore: **No.273H PWB** Offset Wellpath: **B-1**

Facility: Drilling Island 4 - B **Slot: No.273H SHL** **Well: No.273H** **Threshold Value=1.00** † = interpolated/extrapolated s

Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio
8920.00†	8858.91	-1.29	204.66	8693.05	8680.44	-0.53	-113.32	270.14	364.65	50.84	7.17
9020.00†	8916.20	-1.81	286.47	8698.53	8685.21	-0.56	-116.03	270.18	464.07	51.01	9.10
9120.00	8958.40	-2.38	376.99	8694.28	8681.51	-0.53	-113.92	270.22	563.62	51.19	11.01
9220.00†	8992.61	-2.98	470.95	8686.68	8674.87	-0.49	-110.24	270.25	662.38	51.37	12.89
9320.00†	9026.81	-3.57	564.92	8680.21	8669.18	-0.46	-107.16	270.27	761.32	51.55	14.77
9420.00†	9056.01	-4.17	660.51	8672.56	8662.40	-0.42	-103.62	270.28	859.56	51.72	16.62
9520.00†	9075.01	-4.80	758.64	8662.05	8653.01	-0.36	-98.89	270.30	955.75	51.89	18.42
9620.00†	9083.60	-5.43	858.23	8649.24	8641.45	-0.30	-93.36	270.31	1049.30	52.03	20.17
9636.30	9084.00	-5.53	874.52	8646.96	8639.39	-0.29	-92.41	270.31	1064.26	52.05	20.45
9636.44	9084.00	-5.53	874.66	8646.95	8639.37	-0.29	-92.40	270.31	1064.39	52.05	20.45
9720.00†	9085.36	-6.06	958.21	8635.69	8629.10	-0.24	-87.80	270.32	1141.20	52.16	21.88
9820.00†	9086.99	-6.70	1058.19	8623.49	8617.86	-0.19	-83.04	270.33	1233.91	52.28	23.60
9920.00†	9088.61	-7.33	1158.18	8612.48	8607.64	-0.14	-78.95	270.33	1327.35	52.41	25.33
10020.00†	9090.24	-7.96	1258.16	8602.50	8598.31	-0.10	-75.42	270.34	1421.44	52.53	27.06
10120.00†	9091.87	-8.59	1358.15	8593.43	8589.78	-0.07	-72.34	270.34	1516.07	52.64	28.80
10220.00†	9093.49	-9.22	1458.13	8585.15	8581.94	-0.03	-69.66	270.35	1611.18	52.75	30.54
10320.00†	9095.12	-9.86	1558.12	8577.55	8574.73	-0.01	-67.29	270.35	1706.71	52.86	32.29
10420.00†	9096.75	-10.49	1658.10	8570.57	8568.06	0.02	-65.20	270.35	1802.61	52.96	34.04
10520.00†	9098.37	-11.12	1758.09	8564.13	8561.90	0.04	-63.35	270.35	1898.83	53.06	35.78
10620.00†	9100.00	-11.75	1858.07	8558.18	8556.18	0.06	-61.70	270.35	1995.34	53.16	37.53
10720.00†	9101.63	-12.39	1958.05	8552.66	8550.86	0.07	-60.22	270.35	2092.11	53.26	39.28
10820.00†	9103.25	-13.02	2058.04	8547.52	8545.90	0.09	-58.89	270.36	2189.11	53.35	41.03
10920.00†	9104.88	-13.65	2158.02	8542.74	8541.27	0.10	-57.69	270.36	2286.32	53.45	42.78
11020.00†	9106.51	-14.28	2258.01	8538.26	8536.93	0.11	-56.60	270.36	2383.71	53.54	44.52
11120.00†	9108.13	-14.91	2357.99	8534.08	8532.86	0.12	-55.62	270.36	2481.27	53.64	46.26
11220.00†	9109.76	-15.55	2457.98	8530.15	8529.04	0.13	-54.72	270.36	2578.98	53.73	48.00
11320.00†	9111.39	-16.18	2557.96	8526.46	8525.44	0.14	-53.90	270.36	2676.83	53.83	49.73
11420.00†	9113.01	-16.81	2657.95	8522.99	8522.04	0.15	-53.15	270.36	2774.81	53.92	51.46
11520.00†	9114.64	-17.44	2757.93	8519.71	8518.84	0.16	-52.46	270.36	2872.91	54.02	53.18
11620.00†	9116.27	-18.08	2857.92	8516.61	8515.81	0.17	-51.83	270.36	2971.11	54.12	54.90
11720.00†	9117.89	-18.71	2957.90	8513.69	8512.94	0.17	-51.24	270.36	3069.41	54.22	56.61
11820.00†	9119.52	-19.34	3057.89	8510.91	8510.22	0.18	-50.70	270.36	3167.80	54.32	58.32
11920.00†	9121.15	-19.97	3157.87	8508.28	8507.64	0.18	-50.20	270.36	3266.27	54.42	60.02
12020.00†	9122.77	-20.60	3257.86	8505.78	8505.18	0.19	-49.74	270.36	3364.82	54.52	61.72
12120.00†	9124.40	-21.24	3357.84	8503.40	8502.84	0.19	-49.31	270.36	3463.45	54.62	63.41
12220.00†	9126.03	-21.87	3457.83	8501.14	8500.61	0.20	-48.91	270.36	3562.13	54.73	65.09
12320.00†	9127.65	-22.50	3557.81	8498.98	8498.49	0.20	-48.53	270.36	3660.88	54.83	66.76
12420.00†	9129.28	-23.13	3657.80	8496.92	8496.45	0.21	-48.18	270.36	3759.69	54.94	68.43
12520.00†	9130.91	-23.77	3757.78	8494.95	8494.51	0.21	-47.85	270.36	3858.55	55.05	70.09
12620.00†	9132.53	-24.40	3857.77	8493.06	8492.66	0.21	-47.54	270.36	3957.46	55.16	71.74
12720.00†	9134.16	-25.03	3957.75	8491.26	8490.87	0.22	-47.25	270.36	4056.42	55.27	73.39
12820.00†	9135.79	-25.66	4057.74	8489.53	8489.17	0.22	-46.98	270.36	4155.42	55.39	75.03
12920.00†	9137.41	-26.29	4157.72	8487.88	8487.53	0.22	-46.73	270.36	4254.46	55.50	76.65
13020.00†	9139.04	-26.93	4257.70	8486.29	8485.96	0.23	-46.49	270.36	4353.54	55.62	78.27
13120.00†	9140.66	-27.56	4357.69	8484.76	8484.45	0.23	-46.26	270.36	4452.66	55.74	79.88

Clearance Report

B-1

Closest Approach

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

CLEARANCE DATA - Offset Wellbore: **No.273H PWB** Offset Wellpath: **B-1**

Facility: Drilling Island 4 - B **Slot: No.273H SHL** **Well: No.273H** **Threshold Value=1.00** † = interpolated/extrapolated s

Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio
13220.00†	9142.29	-28.19	4457.67	8483.30	8483.00	0.23	-46.05	270.36	4551.81	55.86	81.49
13320.00†	9143.92	-28.82	4557.66	8481.88	8481.60	0.23	-45.84	270.36	4650.99	55.98	83.08
13420.00†	9145.54	-29.46	4657.64	8480.52	8480.26	0.24	-45.65	270.36	4750.21	56.10	84.67
13520.00†	9147.17	-30.09	4757.63	8479.21	8478.96	0.24	-45.47	270.36	4849.45	56.23	86.24
13620.00†	9148.80	-30.72	4857.61	8477.95	8477.71	0.24	-45.30	270.36	4948.72	56.36	87.81
13720.00†	9150.42	-31.35	4957.60	8476.73	8476.50	0.24	-45.13	270.36	5048.02	56.49	89.37
13820.00†	9152.05	-31.98	5057.58	8475.56	8475.34	0.24	-44.98	270.36	5147.34	56.62	90.92
13920.00†	9153.68	-32.62	5157.57	8474.42	8474.21	0.25	-44.83	270.36	5246.68	56.75	92.46
14020.00†	9155.30	-33.25	5257.55	8473.32	8473.12	0.25	-44.69	270.36	5346.05	56.88	93.99
14120.00†	9156.93	-33.88	5357.54	8472.26	8472.07	0.25	-44.55	270.36	5445.44	57.02	95.51
14220.00†	9158.56	-34.51	5457.52	8471.24	8471.05	0.25	-44.43	270.36	5544.84	57.15	97.02
14320.00†	9160.18	-35.15	5557.51	8470.24	8470.06	0.25	-44.30	270.36	5644.27	57.29	98.52
14420.00†	9161.81	-35.78	5657.49	8469.28	8469.11	0.25	-44.19	270.36	5743.71	57.43	100.01
14520.00†	9163.44	-36.41	5757.48	8468.35	8468.18	0.25	-44.07	270.36	5843.18	57.57	101.49
14620.00†	9165.06	-37.04	5857.46	8467.44	8467.29	0.26	-43.97	270.36	5942.65	57.72	102.96
14720.00†	9166.69	-37.67	5957.45	8466.57	8466.42	0.26	-43.86	270.36	6042.15	57.86	104.43
14820.00†	9168.32	-38.31	6057.43	8465.71	8465.57	0.26	-43.77	270.36	6141.66	58.01	105.88
14920.00†	9169.94	-38.94	6157.42	8464.89	8464.75	0.26	-43.67	270.36	6241.18	58.15	107.32
15020.00†	9171.57	-39.57	6257.40	8464.08	8463.95	0.26	-43.58	270.36	6340.72	58.30	108.76
15120.00†	9173.20	-40.20	6357.38	8463.31	8463.18	0.26	-43.50	270.36	6440.27	58.45	110.18
15220.00†	9174.82	-40.84	6457.37	8462.55	8462.42	0.26	-43.41	270.36	6539.83	58.61	111.59
15320.00†	9176.45	-41.47	6557.35	8461.81	8461.69	0.26	-43.33	270.36	6639.41	58.76	112.99
15420.00†	9178.08	-42.10	6657.34	8461.09	8460.98	0.26	-43.26	270.36	6738.99	58.91	114.39
15520.00†	9179.70	-42.73	6757.32	8460.40	8460.29	0.26	-43.18	270.36	6838.59	59.07	115.77
15620.00†	9181.33	-43.36	6857.31	8459.72	8459.61	0.26	-43.11	270.36	6938.20	59.23	117.14
15720.00†	9182.96	-44.00	6957.29	8459.06	8458.95	0.27	-43.04	270.36	7037.82	59.39	118.51
15784.22	9184.00	-44.40	7021.50	8458.64	8458.54	0.27	-43.00	270.36	7101.79	59.49	119.38

POSITIONAL UNCERTAINTY - **Offset Wellbore: No.273H PWB** **Offset Wellpath: B-1**

Slot Surface Uncertainty @1SD	Horizontal	**0.100ft**	Vertical	**0.100ft**
Facility Surface Uncertainty @1SD	Horizontal	**1.000ft**	Vertical	**1.000ft**

SURVEY PROGRAM - **Offset Wellbore: No.273H PWB** **Offset Wellpath: B-1**

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
20.00	500.00	Generic gyro - northseeking (Standard)		No.273H PWB
500.00	16860.21	ISCWSA MWD, Rev. 3 (Standard)		No.273H PWB

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.274H SHL
Area	Eddy County, NM	Well	No.274H
Field	Big Eddy Unit	Wellbore	No.274H PWB
Facility	Drilling Island 4 - B		

OFFSET WELLPATH MD REFERENCE - Offset Wellbore: No.273H PWB Offset Wellpath: B-1	
MD Reference: Rig on No.273H SHL (KB)	*Offset TVD & local coordinates use Reference Wellpath settings (See WELLPATH DATUM on page 1 of this report)*
Ellipse Start MD	20.00ft



13-5/8" X 3-M BOPE (2 Rams and Rotating Head) & Closed Loop System Equipment Schematic
Diagram A

Note: all valves & lines on choke manifold are 3" unless otherwise noted. Exact manifold configuration may vary.



13-5/8" X 3-M BOPE (2 Rams and Rotating Head) & Closed Loop System Equipment Schematic
H2S contingency
Diagram B

Note: all valves & lines on choke manifold are 3" unless otherwise noted. Exact manifold configuration may vary.



Latshaw 4 closed loop system, with Latshaw 18 addition "clouded."

Latshaw 13-5/8" X 3-M BOPE (2 Rams and Rotating Head) & Closed Loop System Equipment Schematic Diagram C

Note: all valves & lines on choke manifold are 3" unless otherwise noted. Exact manifold configuration may vary.

Note: Dimensional information reflected on this drawing are estimated measurements only.



BOPBO, L.P.

CAMERON

Casing Design: 16" x 13.375" x 9.625" x 7"	Name: Jeanette	Date: 3-26-13	Drawing Number: # J-8968

BOPCO, L. P

20" 2,000 PSI Diverter

Diagram D



Note: Actual lengths of casing heads may vary. Always measure items prior to installing in order to ensure proper spacing.

TABLE OF CONTENTS

H_2S CONTINGENCY PLAN SECTION

Scope:

This contingency plan provides an organized plan of action for alerting and protecting the public within an area of exposure prior to an intentional release, or following the accidental release of a potentially hazardous volume of hydrogen sulfide. The plan establishes guidelines for all personnel whose work activity may involve exposure to Hydrogen Sulfide Gas (H_2S).

Objective:

Prevent any and all accidents, and prevent the uncontrolled release of H_2S into the atmosphere.

Provide proper evacuation procedures to cope with emergencies.

Provide immediate and adequate medical attention should an injury occur.

Discussion of Plan:

Suspected Problem Zones:

Implementation: This plan, with all details, is to be fully implemented 500' above or three days prior to drilling into the first known sour zone

Emergency Response and Public Protection Procedure: This section outlines the conditions and denotes steps to be taken in the event of an emergency.

Emergency Equipment and Procedure: This section outlines the safety and emergency equipment that will be required for the drilling of this well.

Training Provisions: This section outlines the training provisions that must be adhered to 500 feet above or three days prior to drilling into the first known sour zone.

Emergency call lists: Included are the telephone numbers of all persons that would need to be contacted should an H_2S emergency occur.

Briefing: This section deals with the briefing of all persons involved with the drilling of this well.

Public Safety: Public Safety Personnel will be made aware of the drilling of this well.

EMERGENCY PROCEDURES AND PUBLIC PROTECTION SECTION

I. In the event of any evidence of H_2S levels above 10 ppm, take the following steps immediately:

A. Secure breathing apparatus.

B. Order non-essential personnel out of the danger zone.

C. Take steps to determine if the H_2S level can be corrected or suppressed, and if so, proceed with normal operations.

II. If uncontrollable conditions occur, proceed with the following:

A. Take steps to protect and/or remove any public downwind of the rig, including partial evacuation or isolation. Notify necessary public safety personnel and the New Mexico Oil & Gas of the situation.

B. Isolate area and prevent entry by unauthorized persons into the 100 ppm ROE.

C. Remove all personnel to the Safe Briefing Area.

D. Notify public safety personnel for help with maintaining roadblocks and implementing evacuation. Phone number list attached.

E. Determine and proceed with the best possible plan to regain control of the well. Maintain tight security and safety measures.

III. Responsibility:

A. The Company Approved Supervisor shall be responsible for the total implementation of the plan.

B. The Company Approved Supervisor shall be in complete command during any emergency.

C. The Company Approved Supervisor shall designate a back up Supervisor in the event that he/she is not available.

EMERGENCY PROCEDURE IMPLEMENTATION

I. Drilling or Tripping

A. All Personnel

1. When alarm sounds, don escape unit and report to upwind Safe Briefing Area.
2. Check status of other personnel (buddy system).
3. Secure breathing apparatus.
4. Wait for orders from supervisor.

B. Drilling Foreman

1. Report to the upwind Safe Briefing Area.
2. Don Breathing Apparatus and return to the point of release with the Tool Pusher or Driller (buddy system).
3. Determine the concentration of H_2S.
4. Assess the situation and take appropriate control measures.

C. Tool Pusher

1. Report to the upwind Safe Briefing Area.
2. Don breathing apparatus and return to the point of release with the Drilling Foreman or the Driller (buddy system).
3. Determine the concentration.
4. Assess the situation and take appropriate control measures.

D. Driller

1. Check the status of other personnel (in a rescue attempt, always use the buddy system).
2. Assign the least essential person to notify the Drilling Foreman and Tool Pusher, in the event of their absence.

3. Assume the responsibility of the Drilling Foreman and the Tool Pusher until they arrive, in the event of their absence.

E. Derrick Man and Floor Hands

1. Remain in the upwind Safe Briefing Area until otherwise instructed by a supervisor.

F. Mud Engineer

1. Report to the upwind Safe Briefing Area.

2. When instructed, begin check of mud for pH level and H_2S level.

G. On-site Safety Personnel

1. Don Breathing Apparatus.

2. Check status of all personnel.

3. Wait for instructions from Drilling Foreman or Tool Pusher.

II. Taking a Kick

A. All personnel report to the upwind Safe Briefing Area.

B. Follow standard BOP procedures.

III. Open Hole Logging

A. All unnecessary personnel should leave the rig floor.

B. Drilling Foreman and Safety Personnel should monitor the conditions and make necessary safety equipment recommendations.

IV. Running Casing or Plugging

A. Follow "Drilling or Tripping" procedures.

B. Assure that all personnel have access to protective equipment.

SIMULATED BLOWOUT CONTROL DRILLS

All drills will be initiated by activating alarm devices (air horn). Use one long blast on the air horn for ACTUAL and SIMULATED Blowout Control Drills. This operation will be performed by the Drilling Foreman or Tool Pusher at least one time per week for each of the following conditions, with each crew:

Drill # 1 Bottom Drilling

Drill # 2 Tripping Drill Pipe

In each of these drills, the initial reaction time to shutting in the well shall be timed as well as the total time for the crew to complete its entire pit drill assignment. The times must be recorded on the IADC Driller's Log as "Blowout Control Drill".

Drill No.:		
Reaction Time to Shut-In:	minutes,	seconds.
Total Time to Complete Assignment:	minutes,	seconds.

I. Drill Overviews

A. Drill No. 1- Bottom Drilling

1. Sound the alarm immediately.
2. Stop the rotary and hoist kelly joint above the rotary table.
3. Stop the circulatory pump.
4. Close the drill pipe rams.
5. Record casing and drill pipe shut-in pressures and pit volume increases.

B. Drill No. 2 – Tripping Drill Pipe

1. Sound the alarm immediately.
2. Position the upper tool joint just above the rotary table and set the slips.

3. Install a full opening valve or inside blowout preventor tool in order to close the drill pipe.

4. Close the drill pipe rams.

5. Record the shut-in annular pressure.

II. Crew Assignments

A. Drill No. 1 – Bottom Drilling

1. Driller

   a) Stop the rotary and hoist kelly joint above the rotary table.

   b) Stop the circulatory pump.

   c) Check flow.

   d) If flowing, sound the alarm immediately.

   e) Record the shut-in drill pipe pressure.

   f) Determine the mud weight increase needed or other courses of action.

2. Derrickman

   a) Open choke line valve at BOP.

   b) Signal Floor Man # 1 at accumulator that choke line is open.

   c) Close choke and upstream valve after pipe tams have been closed.

   d) Read the shut-in annular pressure and report readings to Driller.

3. Floor Man # 1

   a) Close the pipe rams after receiving the signal from the Derrickman.

   b) Report to Driller for further instructions.

4. Floor Man # 2

   a) Notify the Tool Pusher and Operator Representative of the H_2S alarms.

   b) Check for open fires and, if safe to do so, extinguish them.

   c) Stop all welding operations.

   d) Turn-off all non-explosion proof lights and instruments.

   e) Report to Driller for further instructions.

5. Tool Pusher

   a) Report to the rig floor.

   b) Have a meeting with all crews.

   c) Compile and summarize all information.

   d) Calculate the proper kill weight.

   e) Ensure that proper well procedures are put into action.

6. Operator Representative

   a) Notify the Drilling Superintendent.

   b) Determine if an emergency exists and if so, activate the contingency plan.

B. Drill No. 2 – Tripping Pipe

1. Driller

   a) Sound the alarm immediately when mud volume increase has been detected.

   b) Position the upper tool joint just above the rotary table and set slips.

   c) Install a full opening valve or inside blowout preventor tool to close the drill pipe.

   d) Check flow.

e) Record all data reported by the crew.

f) Determine the course of action.

2. Derrickman

a) Come down out of derrick.

b) Notify Tool Pusher and Operator Representative.

c) Check for open fires and, if safe to do so, extinguish them.

d) Stop all welding operations.

e) Report to Driller for further instructions.

3. Floor Man # 1

a) Pick up full opening valve or inside blowout preventor tool and stab into tool joint above rotary table (with Floor Man # 2).

b) Tighten valve with back-up tongs.

c) Close pipe rams after signal from Floor Man # 2.

d) Read accumulator pressure and check for possible high pressure fluid leaks in valves or piping.

e) Report to Driller for further instructions.

4. Floor Man # 2

a) Pick-up full opening valve or inside blowout preventor tool and stab into tool joint above rotary table (with Floor Man # 1).

b) Position back-up tongs on drill pipe.

c) Open choke line valve at BOP.

d) Signal Floor Man # 1 at accumulator that choke line is open.

e) Close choke and upstream valve after pipe rams have been closed.

f) Check for leaks on BOP stack and choke manifold.

g) Read annular pressure.

h) Report readings to the Driller.

5. Tool Pusher

a) Report to the rig floor.

b) Have a meeting with all of the crews.

c) Compile and summarize all information.

d) See that proper well kill procedures are put into action.

6. Operator Representative

a) Notify Drilling Superintendent

b) Determine if an emergency exists, and if so, activate the contingency plan.

IGNITION PROCEDURES

Responsibility:

The decision to ignite the well is the responsibility of the DRILLING FOREMAN in concurrence with the STATE POLICE. The State Police shall be the Incident Command on the scene of any major release. Intentional ignition must be coordinated with the NMOCD and local officials. In the event the Drilling Foreman is incapacitated, it becomes the responsibility of the RIG TOOL PUSHER. This decision should be made only as a last resort and in a situation where it is clear that:

1. Human life and property are endangered.

2. There is no hope of controlling the blowout under the prevailing conditions.

If time permits, notify the main office, but do not delay if human life is in danger. Initiate the first phase of the evacuation plan.

Instructions for Igniting the Well:

1. Two people are required for the actual igniting operation. Both men must wear self-contained breathing apparatus and must use a full body harness and attach a retrievable safety line to the D-Ring in the back. One man must monitor the atmosphere for explosive gases with the LEL monitor, while the Drilling Foreman is responsible for igniting the well.

2. The primary method to ignite is a 25mm flare gun with a range of approximately 500 feet.

3. Ignite from upwind and do not approach any closer than is warranted.

4. Select the ignition site best suited for protection and which offers an easy escape route.

5. Before igniting, check for the presence of combustible gases.

6. After igniting, continue emergency actions and procedures as before.

7. All unassigned personnel will limit their actions to those directed by the Drilling Foreman.

NOTE: After the well is ignited, burning Hydrogen Sulfide will convert to Sulfur Dioxide (SO_2), which is also highly toxic. Do not assume the area is safe after the well is ignited.

TRAINING REQUIREMENTS

When working in an area where Hydrogen Sulfide (H_2S) might be encountered, definite training requirements must be carried out. The Company Supervisor will ensure that all personnel at the well site, whether regularly assigned, contracted, or employed on an unscheduled basis, have had adequate training by a qualified instructor in the following:

1. Hazards and Characteristics of Hydrogen Sulfide and Sulfur Dioxide.
2. Physicals effects of Hydrogen Sulfide on the human body.
3. Toxicity of Hydrogen Sulfide and Sulfur Dioxide.
4. H_2S detection, emergency alarm and sensor location.
5. Emergency rescue.
6. First aid and artificial resuscitation.
7. The effects of Hydrogen Sulfide on metals.
8. Location safety.

In addition, Supervisory Personnel will be trained in the following areas:

1. If high tensile tubular are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well as well as blowout prevention and well control procedures.
3. The contents and requirements of the H_2S Drilling Operations Contingency Plan and the Public Protection Plan.

Service company personnel and visiting personnel must be notified if the zone contains H_2S, and each service company must provide adequate training and equipment for their employees before they arrive at the well site.

EMERGENCY EQUIPMENT

As stated in the BLM Onshore Order 6, for wells located in a known H_2S areas, H_2S equipment will be rigged up after setting surface casing. For wells located inside known H_2S areas, the flare pit will be located 150' from the location and for wells located outside known H_2S areas, the flare pit will be located 100' away from the location. (See page 6 of Survey plat package and diagram B or C.)

It is not anticipated that any H_2S is in the area, however in the event that H_2S is encountered, the attached H_2S Contingency Plan will be implemented. (Please refer to diagrams B or C for choke manifold and closed loop system layout.) See H_2S location layout diagram for location of all H_2S equipment on location.

All H_2S safety equipment and systems will be installed, tested and be operational when drilling reaches a depth of 500' above, or three days prior to penetrating a known formation containing H_2S.

Lease Entrance Sign:

Caution signs should be located at all roads providing direct access to the location. Signs shall have a yellow background with black lettering and contain the words "CAUTION" and "POISON GAS" that is legible from a distance of at least 50 feet.

LEASE NAME
CAUTION – POTENTIAL POISON GAS
HYDROGEN SULFIDE
NO ADMITTANCE WITHOUT AUTHORIZATION

Windsocks or Wind Streamers:

- A minimum of two 10" windsocks located at strategic locations so that they may be seen from any point on location.
- Wind streamers (if preferred) should be placed at various locations on the well site to ensure wind consciousness at all times. (Corners of location)

Hydrogen Sulfide Detector and Alarms:

- H_2S monitors with alarms will be located on the rig floor, at the cellar, and at the mud pits. These monitors will be set to alarm at 10 PPM with a red light and to alarm at 15 PPM with a red light and audible alarm.

Well Condition Flags:

The Well Condition flags should be located at all roads providing direct access to the location. It should have three (3) color coded flags (green, yellow and red) that will be used to denote the following location conditions:

GREEN – Normal Operating Conditions
YELLOW – Potential Danger
RED – Danger, H_2S Gas Present

Respiratory Equipment:

- Fresh air breathing equipment should be placed at the company supervision trailer and the safe briefing areas and should include the following:
  - A minimum of two SCBA's at each briefing area and the supervisor company supervision trailer.
  - Enough air line units to operate safely, anytime the H_2S concentration reaches the IDLH level (100 PPM).
  - Cascade system with enough breathing air hose and manifolds to reach the rig floor, the derrickman and the other operation areas.

Fire Extinguishers:

Adequate fire extinguishers shall be located at strategic locations.

Mud Program:

The mud program has been designed to minimize the volume of H_2S circulated to the surface. Proper mud weight, safe drilling practices and the use of H_2S scavengers will minimize hazards when penetrating H_2S bearing zones.

Metallurgy:

All drill strings, casing, tubing, wellhead; blowout preventer, drilling spools, kill lines, choke manifold and lines, and valves shall be suitable for H_2S service.

Well Control Equipment:

- Flare Line (See page 6 of survey plat package for flare line reference).
- Choke manifold (See diagram B or C and refer to H2S location diagram for location of important H2S safety items).
- Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing units.
- Auxiliary equipment may include, if applicable, annular preventer & rotating head.

Communication Equipment:

- Proper communication equipment such as cell phones or 2 – way radios should be available for communication between the company man's trailer, rig floor and tool pusher's trailer.

Well Testing:

- There will be no drill stem testing.

Evacuation Plan:

- Evacuation routes should be established prior to spudding the well.
- Should be discussed with all rig personnel.

Designated Areas:

Parking and Visitor area:

- All vehicles are to be parked at a pre-determined safe distance from the wellhead.
- A smoking area will be designated at a pre-determined safe distance from the wellhead and any other possible flammable areas.

Safe Briefing Areas:

- Two Safe Briefing Areas shall be designated on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds or they are at a 180 degree angle if wind directions tend to shift in the area.

- Personal protective equipment should be stored at both briefing areas or if a moveable cascade trailer is used, it should be kept upwind of existing winds. When wind is from the prevailing direction, both briefing areas should be accessible.

NOTE:

- Additional equipment will be available at Indian Fire and Safety in Hobbs, NM or at Total Safety in Hobbs, NM.

EVACUATION PLAN

General Plan

The direct lines of action to protect the public from hazardous gas situations are as follows:

1. When the company approved supervisor (Drilling Foremen, Tool Pusher or Driller) determine that Hydrogen Sulfide gas cannot be limited to the well location, and the public will be involved, he will activate the evacuation plan. Escape routes are noted on the Area Map.

2. Company safety personnel or designee will notify the appropriate local government agency that a hazardous condition exists and evacuation needs to be implemented.

3. Company approved safety personnel that have been trained in the use of the proper emergency equipment will be utilized.

4. Law enforcement personnel (State Police, Local Police Department, Fire Department, and the Sheriff's Department) will be called to aid in setting up and maintaining road blocks. Also, they will aid in evacuation of the public if necessary.

NOTE: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

5. After the discharge of gas has been controlled, Company approved safety personnel will determine when the area is safe for re-entry.

See Emergency Action Plan

Contacting Authorities

BOPCO L.P. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. (Operator Name)'s response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

H_2S CONTINGENCY PLAN EMERGENCY CONTACTS

BOPCO L.P. Midland Office 432-683-2277

Key Personnel

Name	Title	Cell Phone Number
Stephen Martinez	Drilling & Completions Manager	432-556-0262
Charles Warne	Division Engineer	432-312-4431
Don Wood	Division Drilling Specialist	432-266-2674
Leo Bojorquez	Area Drilling Superintendent	702-280-4424
Chris Giese	Engineer	432-661-7328
Chris Volek	Engineer	785-979-2643
Brian Braun	Engineer	210-683-9849
Jeremy Braden	Engineer	432-312-1113
Kevin Burns	Engineer	432-934-5499

Artesia

Ambulance	911
State Police	575-746-2703
City Police	575-746-2703
Sheriff's Office	575-746-9888
Fire Department	575-746-2701
Local Emergency Planning Committee	575-746-2122
New Mexico Oil Conservation Division	575-748-1283

Carlsbad

Ambulance	911
State Police	575-885-3137
City Police	575-885-2111
Sheriff's Office	575-887-7551
Fire Department	575-887-3798
Local Emergency Planning Committee	575-887-6544
US Bureau of Land Management	575-887-6544

New Mexico Emergency Response Commission (Santa Fe)	505-476-9600
24 Hour	505-827-9126
New Mexico State Emergency Operations Center	505-476-9635
National Emergency Response Center (Washington, DC)	800-424-8802

Other

Wild Well Control	432-550-6202 (Permian Basin)
Cudd PressureControl	432-580-3544 or 432-570-5300 (Permian Basin)
Flight For Life – 4000 24th St. Lubbock, Texas	806-743-9911
Aerocare – R3, Box 49F, Lubbock, Texas	806-747-8923
Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM	505-842-4433
S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM	505-842-4949
Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM	575-393-3093
Total Safety – 3229 Industrial Dr., Hobbs, NM	575-392-2973

TOXIC EFFECTS OF HYDROGEN SULFIDE

Hydrogen Sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 PPM, which is .001% by volume. Hydrogen Sulfide is heavier than air (specific gravity = 1.192) and colorless. It forms an explosive mixture with air between 4.3 and 46.0 percent by volume. Hydrogen sulfide is almost as toxic as hydrogen cyanide and is between five and six times more toxic than carbon monoxide. Toxicity data for hydrogen sulfide and various other gases are compared in Table I. Physical effects at various Hydrogen Sulfide exposure levels are shown in Table II.

Table I - TOXICITY OF VARIOUS GASES

Common Name	Chemical Formula	Specific Gravity (SC=1)	Threshold Limit (1)	Hazardous Limit (2)	Lethal Concentration (3)
Hydrogen Cyanide	HCN	0.94	10 PPM	150 PPM/HR	300 PPM
Hydrogen Sulfide	H2S	1.18	10 PPM	250 PPM/HR	600 PPM
Sulfur Dioxide	SO2	2.21	5 PPM	--	1000 PPM
Chlorine	CL2	2.45	1 PPM	4 PPM/HR	1000 PPM
Carbon Monoxide	CO	0.97	50 PPM	400 PPM/HR	1000 PPM
Carbon Dioxide	CO2	1.52	5000 PPM	5%	10%
Methane	CH4	0.55	90,000 PPM	Combustible in air	Above 5%

1) **Threshold Limit – Concentration at which it is believed that all *worker may be repeatedly exposed day after day without adverse* effects.**

2) **Hazardous Limit – Concentration that will cause death with short-term exposure.**

3) **Lethal Concentration – Concentration that will cause death with short-term exposure.**

Table II – PHYSICAL EFFECTS OF HYDROGEN SULFIDE

Percent (%)	PPM	Concentration Grains 100 STD. FT3*	Physical Effects
0.001	< 10	00.65	Obvious & unpleasant odor.
0.002	10	01.30	Safe for 8 hours of exposure.
0.010	100	06.48	Kills smell in 3-15 minutes. May sting eyes & throat.
0.020	200	12.96	Kills smell shortly; stings eyes & throat.
0.050	500	32.96	Dizziness; Breathing ceases in a few minutes. Needs prompt artificial respiration.
0.070	700	45.36	Unconscious quickly; Death will result if not rescued promptly.
0.100	1000	64.30	Unconscious at once; Followed by death within minutes.

- At 15.00 PSIA and 60° F.

USE OF SELF-CONTAINED BREATHING APPARATUS

1. Anyone who uses an SCBA shall: Be approved by a physician or licensed health care practitioner; Pass a fit test; Be trained in donning and doffing, proper use, including how to ensure a proper face seal, conducting an inspection of the SCBA, and conduct proper maintenance.

2. Such items as facial hair (beard or sideburns) and eyeglasses will not allow a proper face mask seal.

3. *Anyone reasonably expected to wear SCBA's shall have these items* removed before entering a toxic atmosphere.

4. A special mask with a mount for prescription glasses must be obtained for anyone who must wear eyeglasses in order to see while using an SCBA.

5. SCBA's should be worn in H_2S concentrations above 10 PPM.

RESCUE & FIRST AID FOR H_2S POISONING

DO NOT PANIC – REMAIN CALM – THINK

1. Hold your breath – do not inhale first.

2. Put on SCBA.

3. Remove victim(s) to fresh air as quickly as possible. Go upwind from source or at right angle to the wind. Do not go downwind.

4. Briefly apply chest pressure – using arm lift method of artificial respiration to clean victim's lungs and to avoid inhaling any toxic gas directly from victim's lungs.

5. Provide artificial respiration if needed.

6. Provide for prompt transportation to the hospital and continue giving artificial respiration if needed.

7. Inform hospital/medical facilities of the possibility of H2S gas poisoning before they treat.

Besides basic first aid, everyone on location should have a good working knowledge of artificial respiration and CPR, as well as first aid for eyes and skin *contact with liquid* H_2S.

Proposed H2S Safety Schematic

1) Location of windsocks.

2) Location of H2S alarms

3) Location of briefing areas.

4) Terrain of surrounding area (Please refer to page 2 of survey plat package also see point 11 of multi-surface use plan)

5) Location of flare line(s) and pit(s) (Please refer to diagram 2 choke manifold diagram and or page six of survey plat packet)

6) Location of caution and/or danger signs.

(7) Location of Breathing Equipment



Location On-Site Notes

Location on-site conducted by, Wes Hanna – BOPCO L.P., Jarrel Brooks – BOPCO L.P., Whitney McKee – BOPCO L.P. met on location with Robert Gomez – Basin Surveys and Amanda Lynch – BLM on September 24, 2014. The location was moved from the surface footage call of 660' FSL & 1980' FEL to a new surface footage call of 720' FSL & 2065' FEL to avoid an existing lease road. Location layout is as follows: v-door will face the east, frac pad extension to the north/northwest, access road will enter from the east/southeast, top soil will be stock piled on the north side of location.

MULTI-POINT SURFACE USE PLAN

NAME OF WELL: Big Eddy Unit DI4B #274H

LEGAL DESCRIPTION
SURFACE: 720' FSL, 2065' FEL, Section 5, T20S, R31E, Eddy County, NM.
BHL: 660' FSL, 330' FEL, Section 4, T20S, R31E, Eddy County, NM.

POINT 1: EXISTING ROADS

A) Proposed Well Site Location:

See Form C-102 (Survey Plat).

B) Existing Roads:

From hwy 360 and Co. Rd. 222 (Shugart), go east on Shugart for 4 miles. Then turn south and go about 1 mile on the existing lease road and go east about 0.8 mile to the proposed location on the north side.

C) Existing Road Maintenance or Improvement Plan:

Existing roads will be maintained and kept in the same or better condition than before operations began. See the Well Pad Layout and Topo Map of the survey plat (Sheet 1 and 2 of plat package)

POINT 2: NEW PLANNED ACCESS ROUTE

A) Route Location:

There will be no new road built. (See the Well Pad Layout of the survey plat (Sheet 1 of plat package).

B) Width

14' wide

C) Maximum Grade

Grade to match existing topography or as per BLM requirements.

D) Turnout Ditches

As required by BLM stipulations.

E) Culverts, Cattle Guards, and Surfacing Equipment

If required, culverts and cattle guards will be set per BLM Specs.

POINT 3: LOCATION OF EXISTING WELLS

The following wells are located within a one-mile radius of the location site. See the One-Mile Radius Map (Sheet 5 of the plat package).

Existing wells.....5 (One)
Water wells.....1 (One)

POINT 4: LOCATION OF EXISTING OR PROPOSED FACILITIES

A) New production facilities (to be referred to as BEU Drilling Island "DI" #4 Battery) have been constructed by BOPCO, L.P. and are located within one mile of the Big Eddy Unit DI4B #274H.

B) New Facilities the Event of Production:

New production facilities (to be referred to as BEU Drilling Island "DI" #4 Battery) have been built on the same pad north of the proposed wells located within Sec 5, T20S, R31E. A new 2-7/8" or 3-1/2" diameter steel flowline is to be run above ground approx 3.20 miles. The flowline is expected to carry oil, water and gas.

C) Rehabilitation of Disturbed Areas Unnecessary for Production:

Following the construction, those access areas required for continued production will be graded to provide drainage and minimize erosion. The areas unnecessary for use will be graded to blend in with the surrounding topography (see Point 10).

POINT 5: LOCATION AND TYPE OF WATER SUPPLY

A) Location and Type of Water Supply

Fresh water will be hauled from Johnson Station 50 miles east of Carlsbad, New Mexico or other commercial facilities. Brine water will be hauled from commercial facilities.

B) Water Transportation System

Water hauling to the location will be over the existing and proposed roads.

POINT 6: SOURCE OF CONSTRUCTION MATERIALS

A) Materials

On-site caliche will be used. If this is not sufficient, caliche will be hauled from a BLM approved pit.

B) Land Ownership

Federally Owned

C) Materials Foreign to the Site

No construction materials foreign to this area are anticipated for this drill site.

D) Access Roads

See the Well Pad Layout and Aerial Map of the survey plat (Sheet 1 and 4 of plat package).

POINT 7: METHODS FOR HANDLING WASTE MATERIAL

A) Cuttings

Cuttings will be contained in the roll off bins and disposed at R360 Environmental located in Lea County, NM.

B) Drilling Fluids

Drilling fluids will be contained in the steel pits, frac tanks and disposed at licensed disposal sites.

C) Produced Fluids

Water production will be contained in the steel pits.

Hydrocarbon fluid or other fluids that may be produced during testing will be retained in test tanks. Prior to cleanup operations, any hydrocarbon material in the reserve pit will be removed by skimming or burning as the situation would dictate.

D) Sewage

Current laws and regulations pertaining to the disposal of human waste will be complied with.

E) Garbage

Portable containers will be utilized for garbage disposal during the drilling of this well.

F) Cleanup of Well Site

Upon release of the drilling rig, the surface of the drilling pad will be graded to accommodate a completion rig if electric log analysis indicate potential productive zones. Reasonable cleanup will be performed prior to the final restoration of the site.

POINT 8: ANCILLARY FACILITIES

None required.

POINT 9: WELL SITE LAYOUT

A) Rig Orientation and Layout

The "Rig Layout Schematic" (Sheet 6 of plat package) shows the dimensions of the well pad, closed loop system, and the location of major rig components. Only minor leveling of the well site will be required. No significant cuts or fills will be necessary. **The top soil will be stockpiled on the north side of the location.**

B) Locations of Access Road

See the Well Pad Layout, Topo Map, and Vicinity Map of the survey plat (Sheet 1, 2, and 3 of plat package).

C) Lining of the Pits

No reserve pits - closed loop system.

POINT 10: PLANS FOR RESTORATION OF THE SURFACE

A) Reserve Pit Cleanup - Not applicable. Closed loop drilling fluid system will be used

B) Restoration Plans - Production Developed

BOPCO, L.P. has no plans for interim reclamation to allow for additional wells to be drilled on this pad

C) Restoration Plans - No Production Developed

BOPCO, L.P. has no plans for interim reclamation to allow for additional wells to be drilled on this pad

POINT 11: OTHER INFORMATION

A) On-Site

Location on-site conducted by, Wes Hanna – BOPCO L.P., Jarrel Brooks – BOPCO L.P., Whitney McKee – BOPCO L.P. met on location with Robert Gomez – Basin Surveys and Amanda Lynch – BLM on September 24, 2014. The location was moved from the surface footage call of 660' FSL & 1980' FEL to a new surface footage call of 720' FSL & 2065' FEL to avoid an existing lease road. Location layout is as follows: v-door will face the east, frac pad extension to the north/northwest, access road will enter from the east/southeast, top soil will be stock piled on the north side of location.

B) Soil

Caliche and sand.

C) Vegetation

Sparse, primarily grasses and mesquite with very little grass.

D) Surface Use

Primarily grazing.

E) Surface Water

There are no ponds, lakes, streams or rivers within several miles of the wellsite.

F) Water Wells

There is one water well located within a 1 mile radius of the proposed location.

G) Residences and Buildings

None in the immediate vicinity.

H) Historical Sites

None observed.

I) Archeological Resources

No independent archeological survey has been done. This well location is located in the area covered by Memorandum of Agreement – Permian Basin. A Payment for this project is included with the Big Eddy Unit DI4B #273H APD because it is a dual well pad. Any location or construction conflicts will be resolved before construction begins. Please see diagram 4 for flowline route.

J) Surface Ownership

The well site is on federally owned land. There will be no new road required for this location.

K) Well signs will be posted at the drilling site.

L) Open Pits

No open pits will be used for drilling or production. Any open top tanks will be netted.

M) Terrain

Slightly rolling hills.

POINT 12: OPERATOR'S FIELD REPRESENTATIVE

(Field personnel responsible for compliance with development plan for surface use).

DRILLING
Stephen Martinez
Box 2760
Midland, Texas 79702
(432) 683-2277

PRODUCTION
Gary Fletcher
3104 East Green Street
Carlsbad, New Mexico 88220
(575) 887-7329

Fritz Schoch
Box 2760
Midland, Texas 79702
(432) 683-2277

WBM

Form NM 8140-9
(March 2008)

United States Department of the Interior
Bureau of Land Management
New Mexico State Office

Permian Basin Cultural Resource Mitigation Fund

The company shown below has agreed to contribute funding to the Permian Basin Cultural Resource Fund in lieu of being required to conduct a Class III survey for cultural resources associated with their project. This form verifies that the company has elected to have the Bureau of Land Management (BLM) follow the procedures specified within the Memorandum of Agreement (MOA) concerning improved strategies for managing historic properties within the Permian Basin, New Mexico, for the undertaking rather than the Protocol to meet the agency's Section 106 obligations.

Company Name: BOPCO, L.P.

Address: P. O. Box 2760

Midland, Texas 79702

Project description: Big Eddy Unit DI4 #274H. PA covered on BEU DI4 #273H, dual pad.

T, 20S, R 31E, Section 5 NMPM, Eddy County, New Mexico

Amount of contribution: $ 0.00

Provisions of the MOA:

A. No new Class III inventories are required of industry within the Project Area for those projects where industry elects to contribute to the mitigation fund.

B. The amount of funds contributed was derived from the rate schedule established within Appendix B of the MOA. The amount of the funding contribution acknowledged on this form reflects those rates.

C. The BLM will utilize the funding to carry out a program of mitigation at high-priority sited whose study is needed to answer key questions identified within the Regional Research Design.

D. Donating to the fund is voluntary. Industry acknowledges that it is aware it has the right to pay for Class III survey rather than contributing to the mitigation fund, and that it must avoid or fund data recovery at those sites already recorded that are eligible for nomination to the National Register or whose eligibility is unknown and that any such payments are independent of the mitigation funds established by this MOA.

E. Previously recorded archeological sites determined eligible for nomination to the National Register or whose eligibility remains undetermined must be avoided or mitigated.

F. If any skeletal remains that might be human or funerary objects are discovered by any activities, the land-use applicant will cease activities in the area of discovery, protect the remains, and notify the BLM within 24 hours. The BLM will determine the appropriate treatment of the remains in consultation with culturally affiliated Indian Tribe(s) and lineal descendents. Applicants will be requited to pay for treatment of the cultural items independent and outside of the mitigation fund.

William B Meeker — 7/1/2015

Company-Authorized Officer — Date

BLM-Authorized Officer — Date

PECOS DISTRICT
CONDITIONS OF APPROVAL

OPERATOR'S NAME:	BOPCO, LP
LEASE NO.:	NMNM004557
WELL NAME & NO.:	Big Eddy Unit DI4B 274H
SURFACE HOLE FOOTAGE:	720'/S & 2065'/E
BOTTOM HOLE FOOTAGE	660'/S & 330'/E
LOCATION:	Section 5, T.20 S., R.31 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken: Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

Hackberry Lake OHV Area: Pipelines shall be buried a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. Power poles and associated ground structures (poles, guy wires) will not be placed within 20 feet of recreation trails. Guy wires must be equipped with a sleeve, tape or other industry approved apparatus that is highly visible during the day and reflective at night. Appropriate safety signage will be in place during all phases of the project. Upon completion of construction, the road shall be returned to pre-construction condition with no bumps or dips. All vehicle and equipment operators will observe speed limits and practice responsible defensive driving habits.

Commercial Well Determination

A commercial well determination shall be submitted after production has been established for at least six months.

Unit Wells

The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit designation, but will replace the unit number with the participating area number when the sign is replaced.

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope: $\frac{400'}{4\%} + 100' = 200'$ lead-off ditch interval

Cattleguards

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road
3. Redistribute topsoil
4. Revegetate slopes



Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

a. Spudding well (minimum of 24 hours)
b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**
Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

1. **Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**

2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a "Major" violation.**

3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.

4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the

approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Potash Areas:
After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Secretary's Potash
Capitan Reef
Possibility of water flows in the Tansill, Yates, Salado, and Seven Rivers.
Possibility of lost circulation in the Tansill, Yates, Seven Rivers, Rustler, Capitan Reef, and Cherry Canyon.

1. The **16** inch surface casing shall be set at approximately **650** feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**

    a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

    b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.

    c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
    d. If cement falls back, remedial cementing will be done prior to drilling out that string.

2. The minimum required fill of cement behind the **13-3/8** inch 1st intermediate casing, which shall be set at approximately **2849** feet (**Seven Rivers formation**), is:

☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to potash.**

3. The minimum required fill of cement behind the **9-5/8** inch 2nd intermediate casing is:

Operator has proposed DV tool at depth of 2899', but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range. If an ECP is used, it is to be set a minimum of 50' below the shoe to provide cement across the shoe. If it cannot be set below the shoe, a CBL shall be run to verify cement coverage.

a. First stage to DV tool:

☒ Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.

b. Second stage above DV tool:

☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to Capitan Reef and potash. Excess calculates to 16% - Additional cement may be required**

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

4. The minimum required fill of cement behind the **5-1/2** inch production casing is:

Operator has proposed DV tool at depth of 5000', but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range.

a. First stage to DV tool:

☒ Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.

b. Second stage above DV tool:

☒ Cement should tie-back at least **50 feet above the Capitan Reef** (Top of Capitan Reef estimated at 2899'). Operator shall provide method of verification.

5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.

2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).

3. **A variance is granted for the use of a diverter on the 16" surface casing.**

4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **13-3/8** 1st intermediate casing shoe shall be **3000 (3M)** psi.

5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.

    a. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.

    b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**.

c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.

d. The results of the test shall be reported to the appropriate BLM office.

e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**

f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

CLN 012616

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities
Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)
Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening
The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures
The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures
Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the

largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement
All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the Grant and attachments, including stipulations, survey plat(s) and/or map(s), shall be on location during construction. BLM personnel may request to review a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, Holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC § 2601 *et seq.* (1982) with regard to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant (*see* 40 CFR, Part 702-799 and in particular, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193). Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. Holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. § 9601, *et seq.* or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, *et seq.*) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way Holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way Holder on the Right-of-Way. This provision applies without regard to whether a release is caused by Holder, its agent, or unrelated third parties.

4. Holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. Holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

a. Activities of Holder including, but not limited to: construction, operation, maintenance, and termination of the facility;

b. Activities of other parties including, but not limited to:
   (1) Land clearing
   (2) Earth-disturbing and earth-moving work
   (3) Blasting
   (4) Vandalism and sabotage;

c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars ($1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of Holder, regardless of fault. Upon failure of Holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he/she deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of Holder. Such action by the Authorized Officer shall not relieve Holder of any responsibility as provided herein.

6. All construction and maintenance activity shall be confined to the authorized right-of-way width of **20** feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline shall be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline shall be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity shall be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation shall be allowed unless approved in writing by the Authorized Officer.

8. Holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky of duney areas, the pipeline shall be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of **24** inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will

be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines shall be less than or equal to 4 inches and a working pressure below 125 psi.

18. Special Stipulations:

a. **Lesser Prairie-Chicken:** Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted.

b. This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

IX. INTERIM RECLAMATION

A. GENERAL CONDITIONS

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.