

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018**SUNDRY NOTICES AND REPORTS ON WELLS**
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No. BHL:NMLC061873;SHL:LC061863A

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on page 2

7. If Unit of CA/Agreement, Name and/or No.

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

8. Well Name and No. Cotton Draw Unit 251H

2. Name of Operator Devon Energy Production Company L.P.

9. API Well No. 30-254-25900-42590

3a. Address 6488 Seven Rivers Highway Artesia, New Mexico 88210

3b. Phone No. (include area code)
(575) 748-187110. Field and Pool or Exploratory Area
Paduca; Delaware4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
Sec. 7, T25S, R32E; 125' FNL & 1650' FWL11. Country or Parish, State
Lea County, NM
Eddy

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

Expected start date as soon as possible after approval; project will take approximately 10 to 15 days.

This is a request to lay one additional 4 inch low pressure poly gas lift line buried within the existing easement from the Cotton Draw Unit 251H to the Cotton Draw Unit 7 DW Tank Battery.

The spacing for this line will be 30 feet wide by 793.8 feet (48.11 rods), containing 0.547 acres

Each poly line will carry approximately 1,000 mcf/day at 125 psi.

The lines will be in place for the life of the well or 30 years.

Devon Energy bond #CO-1104; NMB 000801

Reference APD submission for Cotton Draw Unit 251H; API: 30-254-25900

NM OIL CONSERVATION
ARTESIA DISTRICT

FEB 08 2016

OCD 2/16/16 RECEIVED
Accepted for record
NMOC

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)

Ray Vaz

Title Field Landman

Signature

Ray Vaz

Date

2/2/16

THE SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Steve Caffey

Title

FIELD MANAGER

Date

FEB - 3 2016


Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office CARLSBAD FIELD OFFICE

Title 18 U.S.C Section 1001 and Title 43 U.S.C Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

A 4" BURIED POLY FLOWLINE FROM THE CDU #251H TO THE CDU 7 DL CTB IN
SECTION 7, TOWNSHIP 25 SOUTH RANGE 32 EAST, N.M.P.M.,
LEA COUNTY, NEW MEXICO.



A STRIP OF LAND 30.0 FEET WIDE AND 793.8 FEET OR 48.11 RODS OR 0.150 MILES IN LENGTH CROSSING
USA LAND IN SECTION 7, TOWNSHIP 25 SOUTH, RANGE 32 EAST, LEA COUNTY, NEW MEXICO AND BEING
15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

1000 0 1000 2000 FEET

SCALE: 1"=1000'




Chad Harcrow
CHAD HARCROW N.M.P.S. NO. 17277 3/17/15
DATE

DEVON ENERGY PRODUCTION CO. LP.

SURVEY OF A PROPOSED FLOWLINE LOCATED IN
SECTION 7, TOWNSHIP 25 SOUTH, RANGE 32 EAST,
LEA COUNTY, NMPM, NEW MEXICO

SURVEY DATE: MARCH 7, 2015	LINE 2
DRAFTING DATE: MARCH 17, 2015	PAGE 1 OF 4
APPROVED BY: CH DRAWN BY: SP	FILE: 15-214

SECTION 7, TOWNSHIP 25 SOUTH, RANGE 32 EAST, N.M.P.M.
LEA COUNTY, STATE OF NEW MEXICO
LOCATION VERIFICATION MAP



USGS QUAD MAP:
PADUCA BREAKS NW

NOT TO SCALE


DEVON ENERGY PRODUCTION COMPANY, L.P.
COTTON DRAW UNIT 251H
LOCATED 125 FT. FROM THE NORTH LINE
AND 1650 FT. FROM THE WEST LINE OF
SECTION 7, TOWNSHIP 25 SOUTH,
RANGE 32 EAST, N.M.P.M.
LEA COUNTY, STATE OF NEW MEXICO

NOVEMBER 15, 2014

SURVEY NO. 2969A

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

SECTION 7, TOWNSHIP 25 SOUTH, RANGE 32 EAST, N.M.P.M.
LEA COUNTY, STATE OF NEW MEXICO
VICINITY MAP



DISTANCES IN MILES

NOT TO SCALE

DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF ORLA ROAD, CR 1 AND MONSANTO ROAD
GO WEST ON MONSANTO ROAD APPROX. 2.1 MILES, TURN RIGHT AT
ROAD INTERSECTION GO NORTH APPROX. 0.9 MILES ROAD TURNS LEFT
GO WEST APPROX. 2.0 MILES TURN RIGHT AT ROAD INTERSECTION GO
NORTH APPROX. 1.3 MILES TO CALICHE LEASE ROAD ON RIGHT GO
EAST 1.32 MILES TO A ROAD SURVEY ON LEFT (SOUTH) FOLLOW
FLAGS SOUTH 284' TO THE PROPOSED NORTHEAST PAD CORNER FOR
THIS LOCATION

DEVON ENERGY PRODUCTION COMPANY, L.P.
COTTON DRAW UNIT 251H

LOCATED 125 FT. FROM THE NORTH LINE
AND 1650 FT. FROM THE WEST LINE OF
SECTION 7, TOWNSHIP 25 SOUTH,
RANGE 32 EAST, N.M.P.M.
LEA COUNTY, STATE OF NEW MEXICO


NOVEMBER 15, 2014

SURVEY NO. 2969A

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(375) 234-3341

SECTION 7, TOWNSHIP 25 SOUTH, RANGE 32 EAST, N.M.P.M.
LEA COUNTY, STATE OF NEW MEXICO

AERIAL PHOTO



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
FEB. 2014

DEVON ENERGY PRODUCTION COMPANY, L.P.
COTTON DRAW UNIT 251H

LOCATED 125 FT. FROM THE NORTH LINE
AND 1650 FT. FROM THE WEST LINE OF
SECTION 7, TOWNSHIP 25 SOUTH,
RANGE 32 EAST, N.M.P.M.
LEA COUNTY, STATE OF NEW MEXICO

NOVEMBER 15, 2014

SURVEY NO. 2969A

MADRON SURVEYING, INC. 501 SOUTH CANAL CARLSBAD, NEW MEXICO
(505) 234-3341

SECTION 7, TOWNSHIP 25 SOUTH, RANGE 32 EAST, N.M.P.M.
LEA COUNTY, STATE OF NEW MEXICO
WELLS WITHIN 1-MILE DRILL PATH BOUNDARY

API	Well	Type	Status	ULSTR	Current Operator
1 30-025-35390	SPENCER 5 FEDERAL #001	Oil	Plugged	M-05-25S-32E	[20077] SAHARA OPERATING CO
2 30-025-39984	TRIONYX 6 FEDERAL #003H	Oil	New	7-08-25S-32E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
3 30-025-40105	TRIONYX 6 FEDERAL #003Y	Oil	Active	7-08-25S-32E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
4 30-025-39948	TRIONYX 6 FEDERAL #001	Oil	Active	7-08-25S-32E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
5 30-025-39949	TRIONYX 6 FEDERAL #002	Oil	Active	7-08-25S-32E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
6 30-025-40044	TRIONYX 6 FEDERAL #004H	Oil	Active	N-08-25S-32E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
7 30-025-40045	TRIONYX 6 FEDERAL #005H	Oil	Active	O-08-25S-32E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
8 30-025-40046	TRIONYX 6 FEDERAL #008H	Oil	Active	O-08-25S-32E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
9 30-025-40047	TRIONYX 6 FEDERAL #007H	Oil	Active	P-08-25S-32E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
10 30-025-40048	TRIONYX 6 FEDERAL #008H	Oil	Active	P-08-25S-32E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
11 30-025-35086	TEXACO COTTON DRAW UNIT #088	Gas	Plugged	K-07-25S-32E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
12 30-025-08200	PRE-ONGARD WELL #001	Oil	Plugged	B-18-25S-32E	[214263] PRE-ONGARD WELL OPERATOR
13 30-025-21726	COTTON DRAW UNIT #084	Gas	Plugged	C-18-25S-32E	[22351] TEXACO EXPLORATION & PRODUCTION INC
14 30-015-42425	COTTON DRAW UNIT #172H	Oil	New	O-01-25S-31E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
15 30-015-42515	COTTON DRAW UNIT #173H	Oil	New	P-01-25S-31E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
16 30-015-20272	COTTON DRAW #068	Gas	Active	F-12-25S-31E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP
17 30-015-20270	PRE-ONGARD WELL #068	Oil	Plugged	F-12-25S-31E	[214263] PRE-ONGARD WELL OPERATOR
18 30-015-29850	COTTON DRAW UNIT #086	Gas	Active	J-12-25S-31E	[8137] DEVON ENERGY PRODUCTION COMPANY, LP


DEVON ENERGY PRODUCTION COMPANY, L.P.
COTTON DRAW UNIT 251H
LOCATED 125 FT. FROM THE NORTH LINE
AND 1650 FT. FROM THE WEST LINE OF
SECTION 7, TOWNSHIP 25 SOUTH,
RANGE 32 EAST, N.M.P.M.
LEA COUNTY, STATE OF NEW MEXICO

NOVEMBER 15, 2014

SURVEY NO. 2969A

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(505) 734-3341

SECTION 7, TOWNSHIP 25 SOUTH, RANGE 32 EAST, N.M.P.M.
LEA COUNTY, STATE OF NEW MEXICO
AERIAL ACCESS ROUTE MAP



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
FEB. 2014


DEVON ENERGY PRODUCTION COMPANY, L.P.
COTTON DRAW UNIT 251H

LOCATED 125 FT. FROM THE NORTH LINE
AND 1650 FT. FROM THE WEST LINE OF
SECTION 7, TOWNSHIP 25 SOUTH,
RANGE 32 EAST, N.M.P.M.
LEA COUNTY, STATE OF NEW MEXICO

NOVEMBER 15, 2014

SURVEY NO. 2969A

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO



LEGEND PIPELINE WELL WELLPAD TANK BATTERY	CDU #251H FLOWLINE		 devon ENERGY PRODUCTION CO. L.P. HARCROW SURVEYING, LLC 2214 W. MAIN ST. ARTERIA, NM 88218 PH: (505) 746-2158 FAX: (505) 746-2158 c.harcrow@harcrowsurveying.com	
	SECTION: 7	TOWNSHIP: 25 S.		RANGE: 32 E.
	STATE: NEW MEXICO	COUNTY: LEA		SURVEY: N.M.P.M
	W.O. # 15-214	LEASE: COTTON DRAW UNIT		
	 0 0.15 0.3 0.6 Miles 1 IN = 2,500 FT			
	DRIVING DIRECTIONS	INACRY	SR	
	ORIG: 03/17/2015	PAGE: 2 OF 4		




LEGEND

- PIPELINE
- WELL
- WELLPAD
- ▨ TANK BATTERY

CDU #251H FLOWLINE

SECTION: 7 TOWNSHIP: 25 S. RANGE: 32 E.
 STATE: NEW MEXICO COUNTY: LEA SURVEY: N.M.P.M.
 W.O. # 15-214 LEASE: COTTON DRAW UNIT



PIPELINE OVERVIEW

IMAGERY

SR



devon


ENERGY PRODUCTION CO. L.P.



HARCROW SURVEYING, LLC
 2214 W. MAIN ST. ARTESIA, NM 88210
 PH: (575) 746-3158 FAX: (575) 746-3159
charcrow@harcrowsurveying.com

ORIG: 03/17/2015

PAGE: 3 OF 4



LEGEND PIPELINE WELL WELLPAD TANK BATTERY PRIVATE STATE OF NM US BLM	CDU #251H FLOWLINE		 devon ENERGY PRODUCTION CO. L.P. HARCROW SURVEYING, LLC 2114 W. MAIN ST. ALBUQUERQUE, NM 87102 PH: (505) 246-2158 FAX: (505) 246-2158 charcrow@harcrowsurveying.com
	SECTION: 7 TOWNSHIP: 25 S. RANGE: 32 E.		
	STATE: NEW MEXICO COUNTY: LEA SURVEY: N.M.P.M.		
	W.O. # 15-214 LEASE: COTTON DRAW UNIT		
	 0 0.05 0.1 0.2 Miles 1 IN = 1,000 FT		
PIPELINE OVERVIEW	LAND STATUS	SP	ORIG: 03/17/2015 PAGE: 4 OF 4

BLM LEASE NUMBER: SHL NMLC061863A BHLNMLC061873

COMPANY NAME: Devon Energy Production Company LP

ASSOCIATED WELL NAME: Cotton Draw Unit 251H

BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.
6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.
7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:
- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
 - Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
 - The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)
8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.
9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.
11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.
12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

- | | |
|--------------------------|-----------------------------|
| () seed mixture 1 | () seed mixture 3 |
| () seed mixture 2 | () seed mixture 4 |
| (X) seed mixture 2/LPC | () Aplomado Falcon Mixture |

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches that are not otherwise fenced, screened, or netted to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

19. Special Stipulations:

Will be buried within the existing easement from Cotton Draw Unit 251H pad to the Cotton draw Unit 7 DW Tank Battery.

Lesser Prairie-Chicken

Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.