

OCD Artesia
NM OIL CONSERVATION
ARTESIA DISTRICTFORM APPROVED
OMB No 1004-0137
Expires: January 31, 2018UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

JUN 10 2016


APPLICATION FOR PERMIT TO DRILL OR REENTER


1a. Type of work: ☒ DRILL ☐ REENTER		5. Lease Serial No. SESW:NM-115410, SHL & BHL: fee
1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other		6. If Indian, Allottee or Tribe Name N/A
1c. Type of Completion: ☐ Hydraulic Fracturing ☒ Single Zone ☐ Multiple Zone		7. If Unit or CA Agreement, Name and No. will comm. w/fee leases
2. Name of Operator MATADOR PRODUCTION COMPANY		8. Lease Name and Well No Dr. Scrivner Fed. Com #124H
3a. Address 5400 LBJ FREEWAY, STE 1500, DALLAS, TX 75240	3b. Phone No. (include area code) 972-371-5241	9. API Well No. 30-015- 43820
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface 661' FSL & 661' FEL At proposed prod. zone 660' FSL & 240' FWL		10. Field and Pool, or Exploratory CULEBRA BLUFF; BONE SPRINGS, S
14. Distance in miles and direction from nearest town or post office* 2-1/2 AIR MILES NE OF MALAGA, NM		11. Sec., T. R. M. or Blk. and Survey or Area SESE 1-24-28E NMPM
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) SHL: 569' (comm. line) BHL: 240' (comm. line)	16. No of acres in lease lease= 40 ac, comm=160 ac	17. Spacing Unit dedicated to this well S2S2 1-24S-28E
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 330' (P&A)	19. Proposed Depth TVD: 8,429' MD: 13,354'	20. BLM/BIA Bond No. in file BLM NMB-001079
21. Elevations (Show whether DF, KDB, RT, GL., etc.) 2,984' UNGRADED	22. Approximate date work will start* 02/21/2016	23. Estimated duration 3 MONTHS

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM. |

25. Signature 	Name (Printed/Typed) SAM PRYOR (PHONE: 972-371-5241)	Date 04/07/2016
--	---	--------------------

Title SR. Staff Landman		
Approved by (Signature) 	Name (Printed/Typed) James A. Amos	Date JUN 1 - 2016
Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Carlsbad Controlled Water Basin

NSL must be in place prior to placing well
on productionApproval Subject to General Requirements
& Special Stipulations AttachedSEE ATTACHED FOR
CONDITIONS OF APPROVAL

(Continued on page 2)

*(Instructions on page 2)

Matador Production Company

SURFACE PLAN PAGE 5

Dr. Scrivner Fed. 01-24S-28E RB 124H


SHL 661' FSL & 661' FEL Sec. 1, T. 24 S., R. 28 E.

BHL 660' FSL & 240' FWL Sec. 1, T. 24 S., R. 28 E.

Eddy County, NM

CERTIFICATION

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U. S. C. 1001 for the filing of false statements. Executed this 8th day of January, 2016.



Brian Wood, Consultant

Permits West, Inc.

37 Verano Loop, Santa Fe, NM 87508

(505) 466-8120

FAX: (505) 466-9682

Cellular: (505) 699-2276

Field representative will be:

Sam Pryor, Senior Staff Landman

Matador Production Company

5400 LBJ Freeway, Suite 1500

Dallas TX 75240

Phone: (972) 371-5241


FAX: (214) 866-4841

January 8, 2016

To Who it May Concern:

Matador Resources Company has a private surface owner agreement with Johnson Enterprises (P. O. Box 1713, Roswell NM 88202) for the Dr. Scrivner Fed. 01-24S-28E RB 124H well site, battery, pipeline, power line, and road in Section 1, T. 24 S., R. 28 E. Eddy County, NM.

Matador Resources Company has a private surface owner agreement with John Draper Brantley, Jr. and Henry McDonald (706 W. Riverside Dr., Carlsbad NM 88220) for the Dr. Scrivner Fed. 01-24S-28E RB 123H pipeline and power line in Section 6, T. 24 S., R. 29 E. Eddy County, NM.

A handwritten signature in black ink, appearing to read "B. Wood". The signature is fluid and cursive, with a large initial "B" and a stylized "Wood".

Brian Wood

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Sante Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources
Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Sante Fe, NM 87505

FORM C-102

Revised August 1, 2011

Submit one copy to appropriate

District Office

☐ AMENDED REPORT

*2nd Bone Spring sand is goal

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-015- 43020	² Pool Code 15011	³ Pool Name CULEBRA BLUFF; BONE SPRING*, SOUTH
⁴ Property Code 316327	⁵ Property Name DR. SCRIVNER FEDERAL 01-24S-28E RB	⁶ Well Number #124H
⁷ OGRID No. 228937	⁸ Operator Name MATADOR PRODUCTION COMPANY	⁹ Elevation 2984'

¹⁰Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	1	24-S	28-E	-	661'	SOUTH	661'	EAST	EDDY


UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	1	24-S	28-E	-	660'	SOUTH	240'	WEST	EDDY

¹² Dedicated Acres	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
160		C	

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

BOTTOM HOLE LOCATION NEW MEXICO EAST NAD 1927 X=588131 Y=451632 LAT.: N 32.2413318 LONG.: W 104.0482847 NAD 1983 X=629315 Y=451691 LAT.: N 32.24145349 LONG.: W 104.0487765 LAST PERFORATION POINT NEW MEXICO EAST NAD 1927 X=588221 Y=451632 LAT.: N 32.2413322 LONG.: W 104.0479936 NAD 1983 X=629405 Y=451691 LAT.: N 32.24145396 LONG.: W 104.0484854 SURFACE LOCATION NEW MEXICO EAST NAD 1927 X=592590 Y=451653 LAT.: N 32.2407520 LONG.: W 104.0338648 NAD 1983 X=633744 Y=451712 LAT.: N 32.24147864 LONG.: W 104.0344516 FIRST PERFORATION POINT NEW MEXICO EAST NAD 1927 X=592892 Y=451654 LAT.: N 32.2413554 LONG.: W 104.0328885 NAD 1983 X=634075 Y=451712 LAT.: N 32.24147739 LONG.: W 104.0333797	¹⁷OPERATOR CERTIFICATION I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division. <i>Brian Wood</i> Signature Date 1-8-16 BRIAN WOOD Printed Name brian@permitswest.com E-mail Address ¹⁸SURVEYOR CERTIFICATION I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true to the best of my belief. 11/19/2015 Date of Survey Signature and Seal of Professional Surveyor <i>Michael B. Brown</i> MICHAEL B. BROWN NEW MEXICO 18329 PROFESSIONAL SURVEYOR Certificate Number
--	---


LOCATION & ELEVATION VERIFICATION MAP



SCALE: 1" = 1000'
0' 500' 1000'



SECTION 1, TOWNSHIP 24-S, RANGE 28-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO



LEASE NAME & WELL NO.: DR. SCRIVNER FEDERAL 01-24S-28E RB #124H


SECTION 1 TWP 24-S RGE 28-E SURVEY N.M.P.M.
COUNTY EDDY STATE NM
DESCRIPTION 661' FSL & 661' FEL

DISTANCE & DIRECTION

FROM INT. OF US-285 S. & HWY. 720 GO EAST (RIGHT) ON DUARTE RD.
±0.8 MILES, THENCE GO NORTH (LEFT) ON HARROUN RD. ±2.6 MILES.
THENCE GO SOUTH (RIGHT) ON LEASE RD. ±0.1 MILES, THENCE WEST
(RIGHT) ON LEASE RD. ±67 FEET TO A POINT ±300 FEET NORTHEAST
OF THE LOCATION.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID
BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE OF THE
NORTH AMERICAN DATUM 1927, U.S. SURVEY FEET

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND
UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF
SURVEY, AND DATA PROVIDED BY MATADOR PRODUCTION COMPANY. THIS CERTIFICATION IS MADE
AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS
NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.




Michael Blake Brown, P.S. No. 18329
NOVEMBER 30, 2015




1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM


104.11667° W 104.10000° W 104.08333° W 104.06667° W 104.05000° W 104.03333° W 104.01667° W 104.00000° W 103.98333° W WGS84 103.95000° W



7.5°

12/18/15






SCALE: 1" = 1000'

0' 500' 1000'

SECTION 1, TOWNSHIP 24-S, RANGE 28-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO
PROPOSED 3.55 ACRE SITE


MAP 4



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

Michael Blake Brown, P.S. No. 18329
NOVEMBER 30, 2015






MAP 5

SECTION 1, TOWNSHIP 24-S, RANGE 28-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

DETAIL VIEW
SCALE: 1" = 100'



LEASE NAME & WELL NO.: DR. SCRIVNER FEDERAL 01-24S-28E RB #124H

LEGEND

#124H LATITUDE N 32.2413567 #124H LONGITUDE W 104.0339603

--- PROPOSED ROAD
--- ARCH SITE

SCALE: 1" = 100'
0' 50' 100'

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID
BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE OF THE
NORTH AMERICAN DATUM 1927, U.S. SURVEY FEET

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER
MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY,
AND DATA PROVIDED BY MATADOR PRODUCTION COMPANY. THIS CERTIFICATION IS MADE AND
LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS
NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY


1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

ORIGINAL DOCUMENT SIZE: 8.5" X 11"

SCALE: 1" = 1000'

SECTION 1, TOWNSHIP 24-S, RANGE 28-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO
PROPOSED 2.81 ACRE SITE

MAP 6



LINE	BEARING	DISTANCE
1	S 67°16'37" W	350.00'
2	N 22°43'23" W	350.00'
3	N 67°16'37" E	350.00'
4	S 22°43'23" E	350.00'

DR. SCRIVNER 01-24S-28E RB
TANK BATTERY SITE

Metes and Bounds Description of the Proposed 2.81 Acre Tank Battery Site located in Section 1, Township 24-S, Range 28-E, N.M.P.M., in Eddy County, New Mexico.

BEGINNING at 1/2" iron rod at the Southeast corner of the site, from thence bearing S 67°16'37" W, a distance of 1333.66 feet;

Thence S 67°16'37" W, a distance of 350.00 feet to 1/2" iron rod at the Southeast corner of the site;

Thence N 22°43'23" W, a distance of 350.00 feet to 1/2" iron rod at the Northwest corner of the site;


Thence N 67°16'37" E, a distance of 350.00 feet to 1/2" iron rod at the Northeast corner of the site;

Thence S 22°43'23" E, a distance of 350.00 feet to the Point of Beginning.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM



Michael B. Brown, P.S. No. 18329
NOVEMBER 25, 2015

NOTES:

1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927.
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR PRODUCTION COMPANY, ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJACENT TO THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
4. P.O.B. = POINT OF BEGINNING


DR. SCRIVNER 01-24S-28E RB TANK BATTERY SITE	REVISION:
DATE: 08/21/2015	A.V.F. 11/25/2015
FILE: 00 DR SCRIVNER FEDERAL 01-24S-28E RB TANK BATTERY SITE REV1	
DRAWN BY: GCU	
SHEET: 1 OF 1	



MAP 7

SECTION 1, TOWNSHIP 24-S, RANGE 28-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

DETAIL VIEW
SCALE: 1" = 100'



LEGEND

PROPOSED 2.81 ACRE TANK BATTERY SITE

- ARCH SITE
- == ROAD WAY

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE OF THE NORTH AMERICAN DATUM 1927, U.S. SURVEY FEET

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY MATADOR PRODUCTION COMPANY. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

SCALE: 1" = 100'
0' 50' 100'



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY


1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

ORIGINAL DOCUMENT SIZE: 8.5" X 11"

SCALE: 1" = 1000'
0' 500' 1000'

SECTION 1, TOWNSHIP 24-S, RANGE 28-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

MAP 8




Being a proposed gas line easement being 30 feet in width, 15 feet left, and 15 feet right of the above platted centerline total line footage containing 793.22 feet or 48 07 rods, containing 0.55 acres more or less.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140
 TELEPHONE: (817) 744-7512 • FAX (817) 744-7548
 2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
 TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
 WWW.TOPOGRAPHIC.COM



Michael Blake Brown, P.S. No. 18329
 NOVEMBER 30, 2015

DR. SCRIVNER GAS LINE TO
ENTERPRISE
INTERCONNECT

REVISION:

NOTES:

1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927.
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR PRODUCTION COMPANY. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
4. B.O.L. = BEGINNING OF LINE
5. P.O.E. = END OF LINE/POINT OF EXIT

DATE: 11/30/2015

FILE: DR. SCRIVNER GAS LINE TO ENTERPRISE INTERCONNECT.DWG

DRAWN BY: MML


SHEET: 1 OF 1

SCALE: 1" = 1000'

0' 500' 1000'


SECTION 6, TOWNSHIP 24-S, RANGE 29-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

MAP 9



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM



Michael Blake Brown, P.S. No. 18329

NOVEMBER 30, 2015

DR. SCRIVNER GAS LINE
TO ENTERPRISE
INTERCONNECT

REVISION:

INT DATE

DATE: 11/30/15

FILE: DR. SCRIVNER GAS LINE TO ENTERPRISE INTERCONNECT.DWG

DRAWN BY: GLH

SHEET: 1 OF 1


NOTES:

1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927.
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR PRODUCTION CO. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
4. P.O.B. = POINT OF BEGINNING
5. E.O.L. = END OF LINE
6. ADJOINER INFORMATION SHOWN FOR INFORMATIONAL PURPOSES ONLY.

SCALE: 1" = 1000'

SECTION 1, TOWNSHIP 24-S, RANGE 28-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

MAP 10




Being a proposed electrical easement being 15 feet in width, 7.5 feet left, and 7.5 feet right of the above platted centerline total line footage containing 1639.04 feet or 99.34 rods, containing 0.56 acres more or less.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1853 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

Michael Blake Brown, P.S. No. 18329
NOVEMBER 30, 2015



DR. SCRIVNER TO XCEL
ELECTRICAL EASEMENT

REVISION:

DATE: 11/30/2015

FILE: DR. SCRIVNER TO XCEL ELECTRICAL EASEMENT 01-24S-28E SE1-4

DRAWN BY: MML

SHEET: 1 OF 1

NOTES:


1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927.
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR PRODUCTION COMPANY. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
4. P.O.B./B.O.L. = POINT OF BEGINNING/BEGINNING OF LINE
5. E.O.L. = END OF LINE

SCALE: 1" = 1000'

0' 500' 1000'

SECTION 6, TOWNSHIP 24-S, RANGE 29-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

MAP 11




DR. SCRIVNER TO XCEL
ELECTRICAL EASEMENT

Being a proposed electrical easement being 15 feet in width, 7.5 feet left, and 7.5 feet right of the above platted centerline total line footage containing 2056.27 feet or 124.62 rods, containing 0.71 acres more or less.



TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX: (817) 744-7548
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 787-1653 • FAX: (432) 682-1743
WWW.TOPOGRAPHIC.COM



Michael Blake Brown, P.S. No. 18329
NOVEMBER 30, 2015

DR. SCRIVNER TO XCEL
ELECTRICAL EASEMENT

REVISION:

INT DATE

DATE: 11/30/15

FILE: EP DR SCRIVNER TO XCEL ELECTRICAL EASEMENT 06-24S-29E-W1-2

DRAWN BY: GLH

SHEET: 1 OF 1

NOTES.

1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927.
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR PRODUCTION CO. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
4. P.O.B. = POINT OF BEGINNING
5. E.O.L. = END OF LINE
6. ADJOINER INFORMATION SHOWN FOR INFORMATIONAL PURPOSES ONLY.



Well: 124H
Wellbore: OH / Job 1514200
Design: Preliminary Plan 1
Rig: Patterson 297



Magnetic Field
Strength: 48312.4nT
Dip Angle: 60.10°
Date: 8/26/2015
Model: HDGM

WELL DETAILS




	Ground Level	2984.00
+N-S	0.00	
+E-W	0.00	
Northing	451653.00	
Latitude	32° 14' 28.88339 N	
Longitude	104° 2' 28.075 W	

DESIGN TARGET DETAILS

Name	TVD	+N-S	+E-W	Northing	Easting	Latitude	Longitude
BHL Dr. Scraper 124H	8428.96	-21.00	-4429.00	451632.00	58831.00	32° 14' 28.79482 N	104° 2' 52.80717 W
LPP Dr. Scraper 124H	8428.96	-21.00	-4339.00	451632.00	588221.00	32° 14' 28.79246 N	104° 2' 52.78279 W
FPP Dr. Scraper 124H	8514.00	1.00	332.00	451654.00	592892.00	32° 14' 28.88411 N	104° 1' 58.38506 W

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N-S	+E-W	Dip	TFace	VSect	Target	Annotation
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		Start Build 1.5°/100'
2	1000.00	0.00	0.00	1000.00	0.00	0.00	0.00	0.00	0.00		Hold 4° Inc at 89.81° Azm
3	1268.67	4.00	88.81	1268.65	0.03	9.30	1.50	88.81	-9.30		Start Build 1.5°/100'
4	2750.00	10.00	89.81	2746.17	0.37	112.78	0.00	0.00	-112.78		Hold 10° Inc
5	3150.00	10.00	89.81	3143.04	0.53	161.51	1.50	0.01	-161.51		Start Drop 1.5°/100'
6	5410.01	10.00	89.81	5368.58	1.81	553.96	0.00	0.00	-553.97		Hold Vertical
7	6076.71	0.00	0.00	6032.00	2.00	612.00	1.50	180.00	-612.00		KOP: Start Build 10°/100'
8	7986.75	91.10	269.74	8514.85	-0.56	28.01	10.00	269.74	-28.01		LP: 91.1° Inc at 269.74° Azm
9	8887.75	91.10	269.74	8428.96	-21.00	-4429.00	0.00	4429.05			TD at 13355.63
10	13355.63	91.10	269.74	8428.96	-21.00	-4429.00	0.00	4429.05			



Map System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone Name: New Mexico East 3001
Local Origin: Well 124H, Grid North
Latitude: 32° 14' 28.8839 N
Longitude: 104° 2' 2.26075 W
Grid East: 592560.00
Grid North: 451653.00
Scale Factor: 1.000
Geometric Model: HDGM
Sample Date: 26-Aug-15
Magnetic Declination: 7.42°
Dip Angle from Horizontal: 60.10°
Magnetic Field Strength: 48312


To convert a Magnetic Direction to a Grid Direction, Add 7.26°
To convert a Magnetic Direction to a True Direction, Add 7.42° East
To convert a True Direction to a Grid Direction, Subtract 0.16°

FORMATION TOP DETAILS

No formation data is available

CASING DETAILS

TVD	MD	Name	Size
800.00	600.00	13 3/8"	13-3/8
2646.41	2650.00	9 5/8"	9-5/8



Matador Production Company

DRILL PLAN PAGE 1

Dr. Scrivner Fed. 01-24S-28E RB 124H

SHL 661' FSL & 661' FEL Sec. 1, T. 24 S., R. 28 E.

BHL 660' FSL & 240' FWL Sec. 1, T. 24 S., R. 28 E.

Eddy County, NM

Drilling Program

1. ESTIMATED TOPS

Formation Name	TVD	Bearing
Quaternary	GL	Water
Eroded Salado/Rustler	500	Water/Salt
Castille	790	Salt
Base of Salt/Top of Anhydrite	2215	Barren
Lamar	2662	Barren
Bell Canyon	2692	Hydrocarbon
Cherry Canyon	3578	Hydrocarbon
Brushy Canyon	4783	Hydrocarbon
Bone Spring Lime	6565	Hydrocarbon
1st Bone Spring Sand	7416	Hydrocarbon
2nd Bone Spring Carbonate	7688	Hydrocarbon
2nd Bone Spring Sand	8189	Hydrocarbon (& Target Formation)
TVD (2nd Bone Spring Sand)	8429	Hydrocarbon
MD (2nd Bone Spring Sand)	13356	Hydrocarbon

2. NOTABLE ZONES

Closest water well (C 02184) is 2,364' to the northwest. Depth to water in that 87' deep well is 60'.

3. PRESSURE CONTROL

A BOP stack consisting of 3 rams with 2 pipe rams, 1 blind ram and one annular preventer will be installed. The BOP will be used below surface casing to TD. See attachments for BOP and choke manifold diagrams.

Matador Production Company

DRILL PLAN PAGE 2

Dr. Scrivner Fed. 01-24S-28E RB 124H

SHL 661' FSL & 661' FEL Sec. 1, T. 24 S., R. 28 E.

BHL 660' FSL & 240' FWL Sec. 1, T. 24 S., R. 28 E.

Eddy County, NM

An accumulator that meets the requirements of Onshore Order 2 for the pressure rating of the BOP stack will be present. A rotating head will be installed as needed.

Pressure tests will be conducted before drilling out under all casing strings. BOP will be inspected and operated as recommended in Onshore Order 2. A Kelly cock and sub equipped with a full opening valve sized to fit the drill pipe and collars will be available on the rig floor in the open position.

A third party company will test the BOPs. Test pressures will be as follows: After surface casing is set and the BOP is nipped up, the BOP pressure tests will be made to 250 psi low and 2000 psi high. On the intermediate #1, pressure tests will be made to 250 psi low and 3000 psi high. On the intermediate #2, pressure tests will be made to 250 psi low and 7500 psi high. The annular preventer will be tested to 250 psi low and 1000 psi high on the surface casing, and 250 psi low and 1500 psi high on the intermediate #1 and #2 casing. In the case of running a speed head with landing mandrel for 9-5/8" and 7" casing the initial, after surface casing is set, BOP test pressures will be 250 psi low and 3000 psi high with wellhead seals tested to 5000 psi once the 9-5/8" casing has been landed and cemented. The BOP will then be lifted to install the 'C-section' of the wellhead. Matador will nipple the BOP back up and the pressure tests will be made to 250 psi low and 7500 psi high and the annular will be tested to 250 psi low and 1500 psi high.

See COA Matador requests a variance to drill this well using a co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used.

4. CASING & CEMENT

Hole will extend west of the drilling window to allow for pump installation. All perforations will be $\geq 330'$ from the dedication perimeter.

Matador Production Company

DRILL PLAN PAGE 3

Dr. Scrivner Fed. 01-24S-28E RB 124H

SHL 661' FSL & 661' FEL Sec. 1, T. 24 S., R. 28 E.

BHL 660' FSL & 240' FWL Sec. 1, T. 24 S., R. 28 E.

Eddy County, NM

See COA

Hole O. D.	Set @ (MD)	Casing O. D.	Age	Weight (lb/ft)	Grade	Thread Collar	Collapse	Burst	Tension
17.5"	610' 360'	13.375"	New	54.5	J-55	BTC	1.125	1.125	1.8
12.25"	2700'	9.625"	New	40	J-55	BTC	1.125	1.125	1.8
8.75"	13354'	5.5"	New	20	P-110	BTC/TXP	1.125	1.125	1.8

Name	Type	Sacks	Yield	Cubic Feet	Weight	Blend & Centralizers
Surface	Lead	240	1.82	436.8	12.8	Class C + bentonite + 2% CaCl ₂ + 3% NaCl + LCM
	Tail	350	1.38	483	14.8	Class C + 5% NaCl + LCM
TOC = 0'		100% Excess			Centralizers per Onshore Order 2.III.B.1f	
Intermediate	Lead	550	2.13	1171.5	12.6	Class C + bentonite + 1% CaCl ₂ + 8% NaCl + LCM
	Tail	270	1.38	372.6	14.8	Class C + 5% NaCl + LCM
TOC = 0'		100% Excess			2 on btm jt, 1 on 2nd jt, 1 every 4th jt to surface	
Production	Lead	830	2.35	1950.5	11.5	TXI + Fluid Loss + Dispersant + Retarder + LCM
	Tail	1400	1.39	1946	13.2	TXI + Fluid Loss + Dispersant + Retarder + LCM
TOC = 1500'		35% Excess			2 on btm jt, 1 on 2nd jt, 1 every other jt to top of tail cement (500' above TOC)	

5. MUD PROGRAM

Mud monitoring system will be an electronic Pason system satisfying the requirements of Onshore Order 1. All necessary mud products for weight

Matador Production Company

DRILL PLAN PAGE 4

Dr. Scrivner Fed. 01-24S-28E RB 124H

SHL 661' FSL & 661' FEL Sec. 1, T. 24 S., R. 28 E.

BHL 660' FSL & 240' FWL Sec. 1, T. 24 S., R. 28 E.

Eddy County, NM

addition and fluid loss control will be on location at all times. Mud program is subject to change due to the hole condition.

Name	Hole Size	Mud Weight	Visc	Fluid Loss	Type Mud
Surface	17-1/2"	8.30	28	NC	FW Spud Mud
Intermediate	12-1/4"	10.00	30-32	NC	Brine Water
Production	8-3/4"	9.00	30-32	NC	FW/Cut Brine

6. CORES, TESTS, & LOGS

No core or drill stem test is planned.

A 2-person mud-logging program will be used from 5600' to TD.

No electric logs are planned. GR will be collected through the MWD tools from intermediate casing to TD. CBL with CCL will be run as far as gravity will let it fall to TOC. See COA

7. DOWN HOLE CONDITIONS

No abnormal pressure or temperature is expected. Maximum expected bottom hole pressure is ≈ 4500 psi. Expected bottom hole temperature is $\approx 145^\circ$ F.

In accordance with Onshore Order 6, Matador does not anticipate that there will be enough H_2S from the surface to the Bone Spring to meet the BLM's minimum requirements for the submission of an " H_2S Drilling Operation Plan" or "Public Protection Plan" for the drilling and completion of this well. Since Matador has an H_2S safety package on all wells, attached is an " H_2S Drilling Operations Plan". Adequate flare lines will be installed off the mud/gas separator where gas may be flared safely. All personnel will be familiar with all aspects of safe operation of equipment being used.

Matador Production Company

DRILL PLAN PAGE 5

Dr. Scrivner Fed. 01-24S-28E RB 124H

SHL 661' FSL & 661' FEL Sec. 1, T. 24 S., R. 28 E.

BHL 660' FSL & 240' FWL Sec. 1, T. 24 S., R. 28 E.

Eddy County, NM

8. OTHER INFORMATION

The anticipated spud date is upon approval. It is expected it will take 2-1/2 months to drill and complete the well.



Phoenix Technology Services Planning Report



Database:	Compass 5000 GCR	Local Co-ordinate Reference:	Well 124H
Company:	Matador Resources	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Project:	Eddy County, NM (NAD27 NME)	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site:	Dr. Scrivner Federal 01-24S-28E RB	North Reference:	Grid
Well:	124H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH / Job 1514200		
Design:	Preliminary Plan 1		

Project	Eddy County, NM (NAD27 NME)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site	Dr. Scrivner Federal 01-24S-28E RB			
Site Position:		Northing:	451,653.00 usft	Latitude: 32° 14' 28.88339 N
From:	Map	Easting:	592,560.00 usft	Longitude: 104° 2' 2.26075 W
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "	Grid Convergence: 0.16 °

Well	124H			
Well Position	+N/-S	0.00 usft	Northing:	451,653.00 usft
	+E/-W	0.00 usft	Easting:	592,560.00 usft
Position Uncertainty	0.00 usft	Wellhead Elevation:	0.00 usft	Ground Level: 2,984.00 usft

Wellbore	OH / Job 1514200			
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)
	HDGM	8/26/2015	7.42	60.10
				Field Strength (nT) 48,312

Design	Preliminary Plan 1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction
	(usft)	(usft)	(usft)	(°)
	0.00	0.00	0.00	269.74

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,266.67	4.00	89.81	1,266.45	0.03	9.30	1.50	1.50	0.00	89.81	
2,750.00	4.00	89.81	2,746.17	0.37	112.78	0.00	0.00	0.00	0.00	
3,150.03	10.00	89.81	3,143.04	0.53	161.51	1.50	1.50	0.00	0.01	
5,410.01	10.00	89.81	5,368.68	1.81	553.96	0.00	0.00	0.00	0.00	
6,076.71	0.00	0.00	6,032.00	2.00	612.00	1.50	-1.50	0.00	180.00	
7,986.71	0.00	0.00	7,942.00	2.00	612.00	0.00	0.00	0.00	0.00	
8,897.75	91.10	269.74	8,514.85	-0.66	28.01	10.00	10.00	-9.91	269.74	
13,355.63	91.10	269.74	8,428.96	-21.00	-4,429.00	0.00	0.00	0.00	0.00	BHL Dr. Scrivner 124I



Phoenix Technology Services Planning Report



Database:	Compass 5000 GCR	Local Co-ordinate Reference:	Well 124H
Company:	Matador Resources	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Project:	Eddy County, NM (NAD27 NME)	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site:	Dr. Scrivner Federal 01-24S-28E RB	North Reference:	Grid
Well:	124H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH / Job 1514200		
Design:	Preliminary Plan 1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N-S (usft)	+E-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
13 3/8"									
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 1.5°/100'									
1,100.00	1.50	89.81	1,099.99	0.00	1.31	-1.31	1.50	1.50	0.00
1,200.00	3.00	89.81	1,199.91	0.02	5.23	-5.23	1.50	1.50	0.00
1,266.67	4.00	89.81	1,266.45	0.03	9.30	-9.30	1.50	1.50	0.00
Hold 4° Inc at 89.81° Azm									
1,300.00	4.00	89.81	1,299.70	0.04	11.63	-11.63	0.00	0.00	0.00
1,400.00	4.00	89.81	1,399.46	0.06	18.61	-18.61	0.00	0.00	0.00
1,500.00	4.00	89.81	1,499.22	0.08	25.58	-25.58	0.00	0.00	0.00
1,600.00	4.00	89.81	1,598.97	0.11	32.56	-32.56	0.00	0.00	0.00
1,700.00	4.00	89.81	1,698.73	0.13	39.53	-39.53	0.00	0.00	0.00
1,800.00	4.00	89.81	1,798.48	0.15	46.51	-46.51	0.00	0.00	0.00
1,900.00	4.00	89.81	1,898.24	0.18	53.48	-53.48	0.00	0.00	0.00
2,000.00	4.00	89.81	1,998.00	0.20	60.46	-60.46	0.00	0.00	0.00
2,100.00	4.00	89.81	2,097.75	0.22	67.43	-67.43	0.00	0.00	0.00
2,200.00	4.00	89.81	2,197.51	0.25	74.41	-74.41	0.00	0.00	0.00
2,300.00	4.00	89.81	2,297.27	0.27	81.39	-81.39	0.00	0.00	0.00
2,400.00	4.00	89.81	2,397.02	0.29	88.36	-88.36	0.00	0.00	0.00
2,500.00	4.00	89.81	2,496.78	0.32	95.34	-95.34	0.00	0.00	0.00
2,600.00	4.00	89.81	2,596.54	0.34	102.31	-102.31	0.00	0.00	0.00
2,650.00	4.00	89.81	2,646.41	0.35	105.80	-105.80	0.00	0.00	0.00
9 5/8"									
2,700.00	4.00	89.81	2,696.29	0.36	109.29	-109.29	0.00	0.00	0.00
2,750.00	4.00	89.81	2,746.17	0.37	112.78	-112.78	0.00	0.00	0.00
Start Build 1.5°/100'									
2,800.00	4.75	89.81	2,796.02	0.39	116.59	-116.59	1.50	1.50	0.00
2,900.00	6.25	89.81	2,895.56	0.42	126.17	-126.18	1.50	1.50	0.00
3,000.00	7.75	89.81	2,994.81	0.46	138.36	-138.36	1.50	1.50	0.00
3,100.00	9.25	89.81	3,093.71	0.51	153.14	-153.14	1.50	1.50	0.00
3,150.03	10.00	89.81	3,143.04	0.53	161.51	-161.51	1.50	1.50	0.00
Hold 10° Inc									
3,200.00	10.00	89.81	3,192.25	0.56	170.18	-170.18	0.00	0.00	0.00
3,300.00	10.00	89.81	3,290.73	0.62	187.55	-187.55	0.00	0.00	0.00
3,400.00	10.00	89.81	3,389.21	0.67	204.92	-204.92	0.00	0.00	0.00
3,500.00	10.00	89.81	3,487.69	0.73	222.28	-222.28	0.00	0.00	0.00
3,600.00	10.00	89.81	3,586.17	0.79	239.65	-239.65	0.00	0.00	0.00
3,700.00	10.00	89.81	3,684.65	0.84	257.01	-257.01	0.00	0.00	0.00
3,800.00	10.00	89.81	3,783.13	0.90	274.38	-274.38	0.00	0.00	0.00
3,900.00	10.00	89.81	3,881.61	0.96	291.74	-291.74	0.00	0.00	0.00
4,000.00	10.00	89.81	3,980.09	1.01	309.11	-309.11	0.00	0.00	0.00
4,100.00	10.00	89.81	4,078.57	1.07	326.47	-326.48	0.00	0.00	0.00
4,200.00	10.00	89.81	4,177.05	1.13	343.84	-343.84	0.00	0.00	0.00



Phoenix Technology Services Planning Report



Database: Compass 5000 GCR
Company: Matador Resources
Project: Eddy County, NM (NAD27 NME)
Site: Dr. Scrivner Federal 01-24S-28E RB
Well: 124H
Wellbore: OH / Job 1514200
Design: Preliminary Plan 1

Local Co-ordinate Reference:
TVD Reference:
MD Reference:
North Reference:
Survey Calculation Method:
Well 124H
RKB @ 3011.50usft (Patterson 297)
RKB @ 3011.50usft (Patterson 297)
Grid
Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,300.00	10.00	89.81	4,275.53	1.18	361.21	-361.21	0.00	0.00	0.00
4,400.00	10.00	89.81	4,374.02	1.24	378.57	-378.57	0.00	0.00	0.00
4,500.00	10.00	89.81	4,472.50	1.30	395.94	-395.94	0.00	0.00	0.00
4,600.00	10.00	89.81	4,570.98	1.35	413.30	-413.30	0.00	0.00	0.00
4,700.00	10.00	89.81	4,669.46	1.41	430.67	-430.67	0.00	0.00	0.00
4,800.00	10.00	89.81	4,767.94	1.47	448.03	-448.03	0.00	0.00	0.00
4,900.00	10.00	89.81	4,866.42	1.52	465.40	-465.40	0.00	0.00	0.00
5,000.00	10.00	89.81	4,964.90	1.58	482.76	-482.77	0.00	0.00	0.00
5,100.00	10.00	89.81	5,063.38	1.64	500.13	-500.13	0.00	0.00	0.00
5,200.00	10.00	89.81	5,161.86	1.69	517.49	-517.50	0.00	0.00	0.00
5,300.00	10.00	89.81	5,260.34	1.75	534.86	-534.86	0.00	0.00	0.00
5,400.00	10.00	89.81	5,358.82	1.81	552.23	-552.23	0.00	0.00	0.00
5,410.01	10.00	89.81	5,368.68	1.81	553.96	-553.97	0.00	0.00	0.00
Start Drop 1.5°/100'									
5,500.00	8.65	89.81	5,457.48	1.86	568.55	-568.55	1.50	-1.50	0.00
5,600.00	7.15	89.81	5,556.53	1.90	582.29	-582.29	1.50	-1.50	0.00
5,700.00	5.65	89.81	5,655.90	1.94	593.44	-593.44	1.50	-1.50	0.00
5,800.00	4.15	89.81	5,755.53	1.97	601.98	-601.98	1.50	-1.50	0.00
5,900.00	2.65	89.81	5,855.35	1.99	607.91	-607.92	1.50	-1.50	0.00
6,000.00	1.15	89.81	5,955.29	2.00	611.23	-611.23	1.50	-1.50	0.00
6,076.71	0.00	0.00	6,032.00	2.00	612.00	-612.00	1.50	-1.50	0.00
Hold Vertical									
6,100.00	0.00	0.00	6,055.29	2.00	612.00	-612.00	0.00	0.00	0.00
6,200.00	0.00	0.00	6,155.29	2.00	612.00	-612.00	0.00	0.00	0.00
6,300.00	0.00	0.00	6,255.29	2.00	612.00	-612.00	0.00	0.00	0.00
6,400.00	0.00	0.00	6,355.29	2.00	612.00	-612.00	0.00	0.00	0.00
6,500.00	0.00	0.00	6,455.29	2.00	612.00	-612.00	0.00	0.00	0.00
6,600.00	0.00	0.00	6,555.29	2.00	612.00	-612.00	0.00	0.00	0.00
6,700.00	0.00	0.00	6,655.29	2.00	612.00	-612.00	0.00	0.00	0.00
6,800.00	0.00	0.00	6,755.29	2.00	612.00	-612.00	0.00	0.00	0.00
6,900.00	0.00	0.00	6,855.29	2.00	612.00	-612.00	0.00	0.00	0.00
7,000.00	0.00	0.00	6,955.29	2.00	612.00	-612.00	0.00	0.00	0.00
7,100.00	0.00	0.00	7,055.29	2.00	612.00	-612.00	0.00	0.00	0.00
7,200.00	0.00	0.00	7,155.29	2.00	612.00	-612.00	0.00	0.00	0.00
7,300.00	0.00	0.00	7,255.29	2.00	612.00	-612.00	0.00	0.00	0.00
7,400.00	0.00	0.00	7,355.29	2.00	612.00	-612.00	0.00	0.00	0.00
7,500.00	0.00	0.00	7,455.29	2.00	612.00	-612.00	0.00	0.00	0.00
7,600.00	0.00	0.00	7,555.29	2.00	612.00	-612.00	0.00	0.00	0.00
7,700.00	0.00	0.00	7,655.29	2.00	612.00	-612.00	0.00	0.00	0.00
7,800.00	0.00	0.00	7,755.29	2.00	612.00	-612.00	0.00	0.00	0.00
7,900.00	0.00	0.00	7,855.29	2.00	612.00	-612.00	0.00	0.00	0.00
7,986.71	0.00	0.00	7,942.00	2.00	612.00	-612.00	0.00	0.00	0.00
KOP: Start Build 10°/100'									
8,000.00	1.33	269.74	7,955.29	2.00	611.85	-611.85	10.00	10.00	0.00
8,050.00	6.33	269.74	8,005.16	1.98	608.51	-608.51	10.00	10.00	0.00
8,100.00	11.33	269.74	8,054.55	1.95	600.84	-600.84	10.00	10.00	0.00
8,150.00	16.33	269.74	8,103.09	1.89	588.89	-588.89	10.00	10.00	0.00
8,200.00	21.33	269.74	8,150.40	1.82	572.76	-572.76	10.00	10.00	0.00
8,250.00	26.33	269.74	8,196.12	1.73	552.56	-552.57	10.00	10.00	0.00
8,300.00	31.33	269.74	8,239.91	1.62	528.46	-528.46	10.00	10.00	0.00
8,350.00	36.33	269.74	8,281.43	1.49	500.63	-500.64	10.00	10.00	0.00
8,400.00	41.33	269.74	8,320.37	1.35	469.30	-469.30	10.00	10.00	0.00
8,450.00	46.33	269.74	8,356.43	1.19	434.68	-434.68	10.00	10.00	0.00



Phoenix Technology Services Planning Report



Database: Compass 5000 GCR
Company: Matador Resources
Project: Eddy County, NM (NAD27 NME)
Site: Dr. Scrivner Federal 01-24S-28E RB
Well: 124H
Wellbore: OH / Job 1514200
Design: Preliminary Plan 1

Local Co-ordinate Reference: Well 124H
TVD Reference: RKB @ 3011.50usft (Patterson 297)
MD Reference: RKB @ 3011.50usft (Patterson 297)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
8,500.00	51.33	269.74	8,389.33	1.02	397.06	-397.06	10.00	10.00	0.00
8,550.00	56.33	269.74	8,418.84	0.84	356.71	-356.71	10.00	10.00	0.00
8,600.00	61.33	269.74	8,444.71	0.64	313.94	-313.94	10.00	10.00	0.00
8,650.00	66.33	269.74	8,466.75	0.44	269.08	-269.08	10.00	10.00	0.00
8,700.00	71.33	269.74	8,484.80	0.22	222.47	-222.47	10.00	10.00	0.00
8,750.00	76.33	269.74	8,498.73	0.00	174.46	-174.46	10.00	10.00	0.00
8,800.00	81.33	269.74	8,508.41	-0.22	125.43	-125.43	10.00	10.00	0.00
8,850.00	86.33	269.74	8,513.78	-0.45	75.73	-75.73	10.00	10.00	0.00
8,897.75	91.10	269.74	8,514.85	-0.66	28.01	-28.01	10.00	10.00	0.00
LP: 91.1° Inc at 269.74° Azm									
8,900.00	91.10	269.74	8,514.81	-0.67	25.76	-25.76	0.00	0.00	0.00
9,000.00	91.10	269.74	8,512.88	-1.13	-74.22	74.22	0.00	0.00	0.00
9,100.00	91.10	269.74	8,510.95	-1.59	-174.20	174.21	0.00	0.00	0.00
9,200.00	91.10	269.74	8,509.03	-2.04	-274.18	274.19	0.00	0.00	0.00
9,300.00	91.10	269.74	8,507.10	-2.50	-374.16	374.17	0.00	0.00	0.00
9,400.00	91.10	269.74	8,505.17	-2.96	-474.14	474.15	0.00	0.00	0.00
9,500.00	91.10	269.74	8,503.25	-3.41	-574.12	574.13	0.00	0.00	0.00
9,600.00	91.10	269.74	8,501.32	-3.87	-674.10	674.11	0.00	0.00	0.00
9,700.00	91.10	269.74	8,499.39	-4.32	-774.08	774.09	0.00	0.00	0.00
9,800.00	91.10	269.74	8,497.47	-4.78	-874.06	874.08	0.00	0.00	0.00
9,900.00	91.10	269.74	8,495.54	-5.24	-974.04	974.06	0.00	0.00	0.00
10,000.00	91.10	269.74	8,493.61	-5.69	-1,074.02	1,074.04	0.00	0.00	0.00
10,100.00	91.10	269.74	8,491.69	-6.15	-1,174.00	1,174.02	0.00	0.00	0.00
10,200.00	91.10	269.74	8,489.76	-6.60	-1,273.99	1,274.00	0.00	0.00	0.00
10,300.00	91.10	269.74	8,487.83	-7.06	-1,373.97	1,373.98	0.00	0.00	0.00
10,400.00	91.10	269.74	8,485.91	-7.52	-1,473.95	1,473.96	0.00	0.00	0.00
10,500.00	91.10	269.74	8,483.98	-7.97	-1,573.93	1,573.95	0.00	0.00	0.00
10,600.00	91.10	269.74	8,482.05	-8.43	-1,673.91	1,673.93	0.00	0.00	0.00
10,700.00	91.10	269.74	8,480.13	-8.89	-1,773.89	1,773.91	0.00	0.00	0.00
10,800.00	91.10	269.74	8,478.20	-9.34	-1,873.87	1,873.89	0.00	0.00	0.00
10,900.00	91.10	269.74	8,476.27	-9.80	-1,973.85	1,973.87	0.00	0.00	0.00
11,000.00	91.10	269.74	8,474.35	-10.25	-2,073.83	2,073.85	0.00	0.00	0.00
11,100.00	91.10	269.74	8,472.42	-10.71	-2,173.81	2,173.83	0.00	0.00	0.00
11,200.00	91.10	269.74	8,470.49	-11.17	-2,273.79	2,273.82	0.00	0.00	0.00
11,300.00	91.10	269.74	8,468.57	-11.62	-2,373.77	2,373.80	0.00	0.00	0.00
11,400.00	91.10	269.74	8,466.64	-12.08	-2,473.75	2,473.78	0.00	0.00	0.00
11,500.00	91.10	269.74	8,464.71	-12.54	-2,573.73	2,573.76	0.00	0.00	0.00
11,600.00	91.10	269.74	8,462.79	-12.99	-2,673.71	2,673.74	0.00	0.00	0.00
11,700.00	91.10	269.74	8,460.86	-13.45	-2,773.69	2,773.72	0.00	0.00	0.00
11,800.00	91.10	269.74	8,458.93	-13.90	-2,873.67	2,873.70	0.00	0.00	0.00
11,900.00	91.10	269.74	8,457.00	-14.36	-2,973.65	2,973.69	0.00	0.00	0.00
12,000.00	91.10	269.74	8,455.08	-14.82	-3,073.63	3,073.67	0.00	0.00	0.00
12,100.00	91.10	269.74	8,453.15	-15.27	-3,173.61	3,173.65	0.00	0.00	0.00
12,200.00	91.10	269.74	8,451.22	-15.73	-3,273.59	3,273.63	0.00	0.00	0.00
12,300.00	91.10	269.74	8,449.30	-16.18	-3,373.57	3,373.61	0.00	0.00	0.00
12,400.00	91.10	269.74	8,447.37	-16.64	-3,473.55	3,473.59	0.00	0.00	0.00
12,500.00	91.10	269.74	8,445.44	-17.10	-3,573.53	3,573.57	0.00	0.00	0.00
12,600.00	91.10	269.74	8,443.52	-17.55	-3,673.51	3,673.56	0.00	0.00	0.00
12,700.00	91.10	269.74	8,441.59	-18.01	-3,773.49	3,773.54	0.00	0.00	0.00
12,800.00	91.10	269.74	8,439.66	-18.47	-3,873.48	3,873.52	0.00	0.00	0.00
12,900.00	91.10	269.74	8,437.74	-18.92	-3,973.46	3,973.50	0.00	0.00	0.00
13,000.00	91.10	269.74	8,435.81	-19.38	-4,073.44	4,073.48	0.00	0.00	0.00
13,100.00	91.10	269.74	8,433.88	-19.83	-4,173.42	4,173.46	0.00	0.00	0.00
13,200.00	91.10	269.74	8,431.96	-20.29	-4,273.40	4,273.45	0.00	0.00	0.00



Phoenix Technology Services Planning Report



Database:	Compass 5000 GCR	Local Co-ordinate Reference:	Well 124H
Company:	Matador Resources	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Project:	Eddy County, NM (NAD27 NME)	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site:	Dr. Scrivner Federal 01-24S-28E RB	North Reference:	Grid
Well:	124H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH / Job 1514200		
Design:	Preliminary Plan 1		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
13,300.00	91.10	269.74	8,430.03	-20.75	-4,373.38	4,373.43	0.00	0.00	0.00
13,355.63	91.10	269.74	8,428.96	-21.00	-4,429.00	4,429.05	0.00	0.00	0.00
TD at 13355.63									

Design Targets									
Target Name	hit/miss target	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude Longitude
BHL Dr. Scrivner 124H	- plan hits target center - Point	0.00	0.00	8,428.96	-21.00	-4,429.00	451,632.00	588,131.00	32° 14' 28.79482 N 104° 2' 53.83071 W
LPP Dr. Scrivner 124H	- plan misses target center by 1.78usft at 13265.65usft MD (8430.69 TVD, -20.59 N, -4339.04 E) - Point	0.00	0.00	8,428.96	-21.00	-4,339.00	451,632.00	588,221.00	32° 14' 28.79246 N 104° 2' 52.78279 W
FPP Dr. Scrivner 124H	- plan misses target center by 69.71usft at 8614.36usft MD (8451.44 TVD, 0.58 N, 301.26 E) - Point	0.00	0.00	8,514.00	1.00	332.00	451,654.00	592,892.00	32° 14' 28.88411 N 104° 1' 58.39507 W

Casing Points					
Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (")	Hole Diameter (")	
600.00	600.00	13 3/8"	13-3/8	17-1/2	
2,650.00	2,646.41	9 5/8"	9-5/8	12-1/4	

Plan Annotations				
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
1,000.00	1,000.00	+N/-S (usft)	+E/-W (usft)	Start Build 1.5°/100'
1,266.67	1,266.45	0.03	9.30	Hold 4° Inc at 89.81° Azm
2,750.00	2,746.17	0.37	112.78	Start Build 1.5°/100'
3,150.03	3,143.04	0.53	161.51	Hold 10° Inc
5,410.01	5,368.68	1.81	553.96	Start Drop 1.5°/100'
6,076.71	6,032.00	2.00	612.00	Hold Vertical
7,986.71	7,942.00	2.00	612.00	KOP: Start Build 10°/100'
8,897.75	8,514.85	-0.66	28.01	LP: 91.1° Inc at 269.74° Azm
13,355.63	8,428.96	-21.00	-4,429.00	TD at 13355.63



Matador Resources

Eddy County, NM (NAD27 NME)
Dr. Scrivner Federal 01-24S-28E RB
124H

OH / Job 1514200
Preliminary Plan 1

Anticollision Report

07 April, 2016





Phoenix Technology Services

Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Reference	Preliminary Plan 1		
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria		
Interpolation Method:	MD Interval 100.00usft	Error Model:	ISCWSA
Depth Range:	Unlimited	Scan Method:	Closest Approach 3D
Results Limited by:	Maximum center-center distance of 4,000.00 usft	Error Surface:	Elliptical Conic
Warning Levels Evaluated at:	2.00 Sigma	Casing Method:	Not applied

Survey Tool Program	Date 4/7/2016			
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description
0.00	13,355.56	Preliminary Plan 1 (OH / Job 1514200)	PHX+MWD+HDGM	PHX+OWSG MWD + HDGM

Summary						
Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
Dr. Scrivner Federal 01-24S-28E RB						
204H - OH - Preliminary Plan 1	1,000.00	1,000.00	30.00	23.29	4.469	CC
204H - OH - Preliminary Plan 1	1,100.00	1,099.81	30.31	22.89	4.088	ES
204H - OH - Preliminary Plan 1	2,800.00	2,799.14	57.42	37.75	2.919	SF
208H - OH - Preliminary Plan 1	1,000.00	1,000.00	30.00	23.29	4.469	CC
208H - OH - Preliminary Plan 1	1,100.00	1,099.81	30.31	22.91	4.091	ES
208H - OH - Preliminary Plan 1	2,800.00	2,799.13	58.19	38.57	2.966	SF
224H - OH / Job 1514201 - Preliminary Plan 1	1,000.00	1,000.00	60.00	53.29	8.939	CC
224H - OH / Job 1514201 - Preliminary Plan 1	1,100.00	1,099.36	60.52	53.11	8.164	ES
224H - OH / Job 1514201 - Preliminary Plan 1	2,900.00	2,896.21	111.35	90.94	5.456	SF
228H - OH / Job 1514202 - Preliminary Plan 1	1,000.00	1,000.00	60.00	53.29	8.939	CC
228H - OH / Job 1514202 - Preliminary Plan 1	1,100.00	1,099.35	60.55	53.14	8.175	ES
228H - OH / Job 1514202 - Preliminary Plan 1	8,200.00	8,197.70	329.98	270.29	5.528	SF
Phillips Federal						
1 - OH - Surveys	11,587.20	8,414.64	181.52	69.96	1.627	CC, ES
1 - OH - Surveys	11,600.00	8,414.39	181.97	70.07	1.626	SF

Offset Design											
Dr. Scrivner Federal 01-24S-28E RB - 204H - OH - Preliminary Plan 1											
Survey Program: Q-PHX+MWD+HDGM											
Offset Site Error: 0.00 usft											
Offset Well Error: 0.00 usft											
Reference	Offset	Semi-Major Axis		Distance				Separation		Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	30.00	0.00	30.00		
100.00	100.00	100.00	100.00	0.13	0.13	0.00	30.00	0.00	30.00	29.74	0.26
200.00	200.00	200.00	200.00	0.49	0.49	0.00	30.00	0.00	30.00	29.02	0.98
300.00	300.00	300.00	300.00	0.85	0.85	0.00	30.00	0.00	30.00	28.31	1.69
400.00	400.00	400.00	400.00	1.21	1.21	0.00	30.00	0.00	30.00	27.59	2.41
500.00	500.00	500.00	500.00	1.56	1.56	0.00	30.00	0.00	30.00	26.87	3.13
600.00	600.00	600.00	600.00	1.92	1.92	0.00	30.00	0.00	30.00	26.16	3.84
700.00	700.00	700.00	700.00	2.28	2.28	0.00	30.00	0.00	30.00	25.44	4.56
800.00	800.00	800.00	800.00	2.64	2.64	0.00	30.00	0.00	30.00	24.72	5.28
900.00	900.00	900.00	900.00	3.00	3.00	0.00	30.00	0.00	30.00	24.00	6.00
1,000.00	1,000.00	1,000.00	1,000.00	3.36	3.36	0.00	30.00	0.00	30.00	23.29	6.71
1,100.00	1,099.99	1,099.81	1,099.80	3.71	3.71	-89.88	30.31	1.27	30.31	22.89	7.41

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Phoenix Technology Services

Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MO Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design														Dr. Scrivner Federal 01-24S-28E RB - 204H - OH - Preliminary Plan 1		Offset Site Error: 0.00 usft	
Survey Program: 0-PHX+MWD+HDGM																Offset Well Error: 0.00 usft	
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning				
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)							
1,200.00	1,199.91	1,199.82	1,189.53	4.05	4.06	-90.08	31.24	5.07	31.22	23.12	8.11	3.852					
1,300.00	1,299.70	1,299.48	1,299.18	4.40	4.41	-90.39	32.76	11.26	32.72	23.92	8.81	3.716					
1,400.00	1,399.46	1,399.47	1,398.93	4.75	4.76	-90.70	34.41	18.04	34.36	24.85	9.51	3.612					
1,500.00	1,499.22	1,499.45	1,498.67	5.11	5.12	-90.97	36.07	24.81	36.00	25.78	10.22	3.521					
1,600.00	1,598.97	1,599.44	1,598.41	5.46	5.48	-91.23	37.73	31.59	37.64	26.70	10.94	3.441					
1,700.00	1,698.73	1,699.43	1,698.16	5.82	5.84	-91.46	39.39	38.36	39.28	27.62	11.66	3.369					
1,800.00	1,798.48	1,799.41	1,797.90	6.18	6.20	-91.67	41.04	45.14	40.92	28.54	12.38	3.306					
1,900.00	1,898.24	1,899.40	1,897.64	6.54	6.56	-91.87	42.70	51.91	42.56	29.46	13.10	3.249					
2,000.00	1,998.00	1,999.38	1,997.38	6.91	6.92	-92.05	44.36	58.69	44.20	30.37	13.83	3.197					
2,100.00	2,097.75	2,099.37	2,097.13	7.27	7.28	-92.22	46.02	65.46	45.84	31.29	14.55	3.150					
2,200.00	2,197.51	2,199.36	2,196.87	7.63	7.65	-92.38	47.68	72.23	47.48	32.20	15.28	3.107					
2,300.00	2,297.27	2,299.34	2,296.61	8.00	8.01	-92.52	49.33	79.01	49.13	33.12	16.01	3.069					
2,400.00	2,397.02	2,399.33	2,396.36	8.36	8.38	-92.66	50.99	85.78	50.77	34.03	16.74	3.033					
2,500.00	2,496.78	2,499.32	2,496.10	8.73	8.75	-92.79	52.65	92.56	52.41	34.94	17.47	3.000					
2,600.00	2,596.54	2,599.30	2,595.84	9.09	9.11	-92.91	54.31	99.33	54.05	35.85	18.20	2.970					
2,700.00	2,696.29	2,699.29	2,695.58	9.46	9.48	-93.02	55.96	106.11	55.70	36.76	18.93	2.942					
2,800.00	2,796.02	2,799.14	2,795.17	9.83	9.84	-93.13	57.70	113.18	57.42	37.75	19.67	2.919 SF					
2,900.00	2,895.56	2,898.84	2,894.41	10.20	10.22	-93.26	59.96	122.44	59.67	39.26	20.41	2.923					
3,000.00	2,994.81	2,998.52	2,993.35	10.58	10.59	-93.41	62.84	134.20	62.54	41.37	21.17	2.954					
3,100.00	3,093.71	3,098.17	3,091.91	10.97	10.98	-93.57	66.33	148.47	66.01	44.07	21.94	3.009					
3,200.00	3,192.25	3,197.94	3,190.22	11.36	11.37	-93.74	70.37	164.96	70.03	47.30	22.73	3.081					
3,300.00	3,290.73	3,297.85	3,288.61	11.76	11.77	-93.90	74.49	181.82	74.12	50.60	23.52	3.151					
3,400.00	3,389.21	3,397.77	3,387.01	12.16	12.17	-94.05	78.61	198.67	78.22	53.90	24.32	3.216					
3,500.00	3,487.89	3,497.69	3,485.41	12.57	12.57	-94.18	82.74	215.53	82.32	57.19	25.13	3.276					
3,600.00	3,586.17	3,597.60	3,583.81	12.97	12.98	-94.30	86.86	232.38	86.41	60.48	25.93	3.332					
3,700.00	3,684.65	3,697.52	3,682.20	13.38	13.38	-94.40	90.99	249.24	90.51	63.77	26.75	3.384					
3,800.00	3,783.13	3,797.43	3,780.60	13.79	13.79	-94.50	95.11	266.09	94.61	67.05	27.56	3.433					
3,900.00	3,881.61	3,897.35	3,879.00	14.20	14.20	-94.59	99.24	282.95	98.71	70.33	28.38	3.478					
4,000.00	3,980.09	3,997.26	3,977.40	14.61	14.61	-94.67	103.36	299.80	102.80	73.60	29.20	3.521					
4,100.00	4,078.57	4,097.18	4,075.79	15.03	15.02	-94.75	107.49	316.66	106.90	76.88	30.02	3.561					
4,200.00	4,177.05	4,197.10	4,174.19	15.44	15.43	-94.82	111.61	333.51	111.00	80.15	30.85	3.598					
4,300.00	4,275.53	4,297.01	4,272.59	15.86	15.85	-94.88	115.73	350.37	115.10	83.42	31.68	3.633					
4,400.00	4,374.02	4,396.93	4,370.99	16.27	16.26	-94.95	119.86	367.22	119.20	86.69	32.51	3.667					
4,500.00	4,472.50	4,496.84	4,469.38	16.69	16.68	-95.00	123.98	384.08	123.30	89.96	33.34	3.698					
4,600.00	4,570.98	4,596.76	4,567.78	17.11	17.09	-95.06	128.11	400.93	127.40	93.22	34.17	3.728					
4,700.00	4,669.46	4,696.68	4,666.18	17.53	17.51	-95.11	132.23	417.79	131.60	96.49	35.01	3.756					
4,800.00	4,767.94	4,796.59	4,764.58	17.95	17.93	-95.15	136.36	434.65	135.60	99.75	35.84	3.783					
4,900.00	4,866.42	4,896.51	4,862.97	18.37	18.35	-95.20	140.48	451.50	139.69	103.01	36.68	3.808					
5,000.00	4,964.90	4,996.42	4,961.37	18.79	18.77	-95.24	144.61	468.36	143.79	106.27	37.52	3.832					
5,100.00	5,063.38	5,096.34	5,059.77	19.21	19.19	-95.28	148.73	485.21	147.89	109.53	38.36	3.855					
5,200.00	5,161.86	5,196.26	5,158.17	19.64	19.61	-95.32	152.85	502.07	151.99	112.79	39.20	3.877					
5,300.00	5,260.34	5,296.17	5,256.56	20.06	20.03	-95.35	156.98	518.92	156.09	116.05	40.05	3.898					
5,400.00	5,358.82	5,396.09	5,354.86	20.48	20.45	-95.38	161.10	535.78	160.19	119.30	40.89	3.918					
5,500.00	5,457.48	5,496.00	5,453.36	20.90	20.87	-95.40	165.23	552.63	164.19	122.46	41.73	3.935					
5,600.00	5,556.53	5,596.41	5,552.37	21.31	21.29	-94.20	169.19	569.83	167.88	125.32	42.56	3.945					
5,700.00	5,655.90	5,697.08	5,652.03	21.70	21.70	-93.30	172.56	586.60	171.01	127.65	43.36	3.944					
5,800.00	5,755.53	5,797.85	5,752.13	22.07	22.09	-92.42	175.31	593.82	173.57	129.44	44.12	3.934					
5,900.00	5,855.35	5,898.72	5,852.60	22.43	22.47	-91.54	177.43	602.48	175.55	130.68	44.86	3.913					
6,000.00	5,955.29	5,999.67	5,953.36	22.78	22.84	-90.66	178.92	608.57	176.95	131.38	45.57	3.883					
6,100.00	6,055.29	6,100.72	6,054.34	23.11	23.19	0.02	179.77	612.07	177.77	134.24	43.54	4.083					
6,200.00	6,155.29	6,201.67	6,155.29	23.43	23.52	0.32	180.00	613.00	178.00	133.78	44.23	4.025					
6,300.00	6,255.29	6,301.67	6,255.29	23.75	23.85	0.32	180.00	613.00	178.00	133.10	44.90	3.964					

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Phoenix Technology Services
Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design											Offset Site Error: 0.00 usft		
Dr. Scrivner Federal 01-24S-28E RB - 204H - OH - Preliminary Plan 1											Offset Well Error: 0.00 usft		
Survey Program: O-PHX+MWD+HDGM													
Reference		Offset		Semi Major Axis		Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)		Separation Factor
6,400.00	6,355.29	6,401.67	6,355.29	24.08	24.17	0.32	180.00	613.00	178.00	132.42	45.58	3.905	
6,500.00	6,455.29	6,501.67	6,455.29	24.40	24.50	0.32	180.00	613.00	178.00	131.74	46.26	3.848	
6,600.00	6,555.29	6,601.67	6,555.29	24.73	24.83	0.32	180.00	613.00	178.00	131.06	46.94	3.792	
6,700.00	6,655.29	6,701.67	6,655.29	25.06	25.16	0.32	180.00	613.00	178.00	130.38	47.62	3.738	
6,800.00	6,755.29	6,801.67	6,755.29	25.38	25.49	0.32	180.00	613.00	178.00	129.70	48.31	3.685	
6,900.00	6,855.29	6,901.67	6,855.29	25.71	25.82	0.32	180.00	613.00	178.00	129.01	48.99	3.634	
7,000.00	6,955.29	7,001.67	6,955.29	26.04	26.15	0.32	180.00	613.00	178.00	128.33	49.67	3.583	
7,100.00	7,055.29	7,101.67	7,055.29	26.37	26.48	0.32	180.00	613.00	178.00	127.64	50.36	3.535	
7,200.00	7,155.29	7,201.67	7,155.29	26.70	26.81	0.32	180.00	613.00	178.00	126.96	51.05	3.487	
7,300.00	7,255.29	7,301.67	7,255.29	27.04	27.14	0.32	180.00	613.00	178.00	126.27	51.73	3.441	
7,400.00	7,355.29	7,401.67	7,355.29	27.37	27.48	0.32	180.00	613.00	178.00	125.58	52.42	3.396	
7,500.00	7,455.29	7,501.67	7,455.29	27.70	27.81	0.32	180.00	613.00	178.00	124.89	53.11	3.352	
7,600.00	7,555.29	7,601.67	7,555.29	28.04	28.15	0.32	180.00	613.00	178.00	124.20	53.80	3.309	
7,700.00	7,655.29	7,701.67	7,655.29	28.37	28.48	0.32	180.00	613.00	178.00	123.51	54.49	3.267	
7,800.00	7,755.29	7,801.67	7,755.29	28.71	28.82	0.32	180.00	613.00	178.00	122.82	55.18	3.226	
7,900.00	7,855.29	7,901.67	7,855.29	29.04	29.15	0.32	180.00	613.00	178.00	122.13	55.87	3.186	
7,961.79	7,917.07	7,963.46	7,917.07	29.25	29.36	90.73	180.00	613.00	178.01	119.44	58.57	3.039	
8,000.00	7,955.29	8,001.67	7,955.29	29.38	29.49	90.63	180.00	613.00	178.00	119.18	58.83	3.026	
8,100.00	8,054.55	8,100.94	8,054.55	29.67	29.83	94.09	180.00	613.00	178.47	119.05	58.41	3.004	
8,200.00	8,150.40	8,196.78	8,150.40	29.92	30.15	102.13	180.00	613.00	182.67	123.02	59.65	3.062	
8,300.00	8,239.91	8,286.29	8,239.91	30.17	30.45	112.27	180.00	613.00	197.40	138.55	58.85	3.354	
8,400.00	8,320.37	8,366.76	8,320.37	30.42	30.73	121.37	180.00	613.00	229.28	172.68	56.60	4.051	
8,500.00	8,389.33	8,435.72	8,389.33	30.74	30.96	127.27	180.00	613.00	280.47	226.83	53.65	5.228	
8,600.00	8,444.71	8,491.09	8,444.71	31.17	31.15	128.95	180.00	613.00	348.72	297.02	51.70	6.745	
8,700.00	8,484.80	8,531.19	8,484.80	31.77	31.28	125.14	180.00	613.00	429.92	376.90	53.03	8.108	
8,800.00	8,508.41	8,554.79	8,508.41	32.56	31.36	112.47	180.00	613.00	519.81	460.51	59.30	8.766	
8,900.00	8,514.81	8,561.19	8,514.81	33.53	31.39	86.36	180.00	613.00	614.41	549.60	64.80	9.481	
9,000.00	8,512.88	8,559.27	8,512.88	34.68	31.38	85.74	180.00	613.00	710.69	644.78	65.91	10.783	
9,100.00	8,510.95	8,557.34	8,510.95	36.02	31.37	85.12	180.00	613.00	807.87	740.67	67.20	12.022	
9,200.00	8,509.03	8,555.41	8,509.03	37.53	31.37	84.51	180.00	613.00	905.67	837.02	68.64	13.194	
9,300.00	8,507.10	8,553.48	8,507.10	39.19	31.36	83.90	180.00	613.00	1,003.89	933.66	70.22	14.295	
9,400.00	8,505.17	8,551.56	8,505.17	40.98	31.35	83.28	180.00	613.00	1,102.43	1,030.50	71.92	15.327	
9,500.00	8,503.25	8,549.63	8,503.25	42.88	31.35	82.67	180.00	613.00	1,201.21	1,127.48	73.73	16.293	
9,600.00	8,501.32	8,547.70	8,501.32	44.88	31.34	82.06	180.00	613.00	1,300.17	1,224.56	75.61	17.195	
9,700.00	8,499.39	10,995.54	9,767.67	46.96	50.74	165.43	325.29	-799.92	1,310.66	1,272.40	38.27	34.252	
9,800.00	8,497.47	11,095.54	9,765.75	49.13	52.79	165.43	324.84	-899.90	1,310.67	1,270.91	39.77	32.958	
9,900.00	8,495.54	11,195.54	9,763.83	51.35	54.91	165.43	324.39	-999.88	1,310.68	1,269.36	41.32	31.721	
10,000.00	8,493.61	11,295.54	9,761.91	53.64	57.09	165.43	323.94	-1,099.86	1,310.69	1,267.77	42.92	30.541	
10,100.00	8,491.69	11,395.54	9,759.99	55.97	59.33	165.43	323.49	-1,199.84	1,310.70	1,266.15	44.55	29.420	
10,200.00	8,489.76	11,495.54	9,758.07	58.36	61.61	165.43	323.04	-1,299.82	1,310.71	1,264.48	46.22	28.356	
10,300.00	8,487.83	11,595.54	9,756.15	60.77	63.94	165.43	322.59	-1,399.80	1,310.71	1,262.79	47.93	27.349	
10,400.00	8,485.91	11,695.54	9,754.23	63.23	66.31	165.43	322.15	-1,499.78	1,310.72	1,261.07	49.66	26.395	
10,500.00	8,483.98	11,795.54	9,752.31	65.71	68.71	165.43	321.70	-1,599.75	1,310.73	1,259.32	51.42	25.493	
10,600.00	8,482.05	11,895.54	9,750.39	68.23	71.15	165.43	321.25	-1,699.74	1,310.74	1,257.54	53.20	24.640	
10,700.00	8,480.13	11,995.54	9,748.47	70.77	73.61	165.43	320.80	-1,799.72	1,310.75	1,255.75	55.00	23.833	
10,800.00	8,478.20	12,095.54	9,746.55	73.32	76.10	165.43	320.35	-1,899.70	1,310.76	1,253.94	56.82	23.070	
10,900.00	8,476.27	12,195.54	9,744.63	75.90	78.61	165.43	319.90	-1,999.68	1,310.77	1,252.11	58.66	22.347	
11,000.00	8,474.35	12,295.54	9,742.71	78.50	81.15	165.43	319.45	-2,099.67	1,310.77	1,250.27	60.51	21.663	
11,100.00	8,472.42	12,395.54	9,740.79	81.11	83.70	165.43	319.00	-2,199.65	1,310.78	1,248.41	62.38	21.014	
11,200.00	8,470.49	12,495.54	9,738.87	83.74	86.27	165.43	318.55	-2,299.63	1,310.79	1,246.53	64.26	20.399	
11,300.00	8,468.57	12,595.54	9,736.95	86.38	88.86	165.43	318.11	-2,399.61	1,310.80	1,244.65	66.15	19.816	
11,400.00	8,466.64	12,695.54	9,735.03	89.04	91.46	165.43	317.66	-2,499.59	1,310.81	1,242.76	68.05	19.262	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Phoenix Technology Services
Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design														Offset Site Error: 0.00 usft	
Dr. Scrivner Federal 01-24S-28E RB - 204H - OH - Preliminary Plan 1														Offset Well Error: 0.00 usft	
Survey Program: O-PHX+MWD+HDGM															
Reference		Offset		Semi Major Axis		Distance									
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning		
11,500.00	8,464.71	12,795.54	9,733.11	91.70	94.08	165.43	317.21	-2,599.57	1,310.82	1,240.85	69.96	18.735			
11,600.00	8,462.79	12,895.54	9,731.19	94.38	96.71	165.42	316.76	-2,699.55	1,310.82	1,238.94	71.89	18.234			
11,700.00	8,460.86	12,995.54	9,729.27	97.06	99.35	165.42	316.31	-2,799.53	1,310.83	1,237.01	73.82	17.758			
11,800.00	8,458.93	13,095.54	9,727.35	99.75	102.00	165.42	315.86	-2,899.51	1,310.84	1,235.08	75.76	17.303			
11,900.00	8,457.00	13,195.54	9,725.43	102.45	104.66	165.42	315.41	-2,999.49	1,310.85	1,233.15	77.70	16.870			
12,000.00	8,455.08	13,295.54	9,723.51	105.16	107.33	165.42	314.96	-3,099.47	1,310.86	1,231.20	79.66	16.456			
12,100.00	8,453.15	13,395.54	9,721.59	107.88	110.01	165.42	314.52	-3,199.45	1,310.87	1,229.25	81.62	16.061			
12,200.00	8,451.22	13,495.54	9,719.67	110.60	112.69	165.42	314.07	-3,299.43	1,310.87	1,227.29	83.58	15.684			
12,300.00	8,449.30	13,595.54	9,717.75	113.32	115.38	165.42	313.62	-3,399.41	1,310.88	1,225.33	85.55	15.323			
12,400.00	8,447.37	13,695.54	9,715.83	116.05	118.08	165.42	313.17	-3,499.39	1,310.89	1,223.37	87.53	14.977			
12,500.00	8,445.44	13,795.54	9,713.91	118.79	120.79	165.42	312.72	-3,599.37	1,310.90	1,221.39	89.51	14.646			
12,600.00	8,443.52	13,895.54	9,711.99	121.53	123.50	165.42	312.27	-3,699.35	1,310.91	1,219.42	91.49	14.328			
12,700.00	8,441.59	13,995.54	9,710.07	124.28	126.22	165.42	311.82	-3,799.34	1,310.92	1,217.44	93.48	14.023			
12,800.00	8,439.66	14,095.54	9,708.15	127.03	128.94	165.42	311.37	-3,899.32	1,310.93	1,215.45	95.47	13.731			
12,900.00	8,437.74	14,195.54	9,706.23	129.78	131.66	165.42	310.92	-3,999.30	1,310.93	1,213.46	97.47	13.450			
13,000.00	8,435.81	14,295.54	9,704.31	132.54	134.40	165.42	310.48	-4,099.28	1,310.94	1,211.47	99.47	13.179			
13,100.00	8,433.88	14,395.54	9,702.39	135.30	137.13	165.42	310.03	-4,199.26	1,310.95	1,209.48	101.47	12.919			
13,200.00	8,431.96	14,495.54	9,700.47	138.06	139.87	165.42	309.58	-4,299.24	1,310.96	1,207.48	103.48	12.669			
13,300.00	8,430.03	14,595.54	9,698.55	140.83	142.61	165.42	309.13	-4,399.22	1,310.97	1,205.48	105.49	12.428			
13,314.60	8,429.75	14,610.14	9,698.27	141.23	143.01	165.42	309.06	-4,413.82	1,310.97	1,205.19	105.78	12.393			
13,355.63	8,428.96	14,624.96	9,697.99	142.37	143.42	165.42	309.00	-4,428.63	1,311.23	1,204.89	106.34	12.330			



Phoenix Technology Services

Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design													Offset Site Error:	0.00 usft
Dr. Scrivner Federal 01-24S-28E RB - 208H - OH - Preliminary Plan 1													Offset Well Error:	0.00 usft
Survey Program: D-PHX+MWD+HOGM														
Reference		Offset		Semi Major Axis		Distance		Warning						
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
0.00	0.00	0.00	0.00	0.00	0.00	180.00	-30.00	0.00	30.00					
100.00	100.00	100.00	100.00	0.13	0.13	180.00	-30.00	0.00	30.00	29.74	0.26	115.432		
200.00	200.00	200.00	200.00	0.49	0.49	180.00	-30.00	0.00	30.00	29.02	0.98	30.711		
300.00	300.00	300.00	300.00	0.85	0.85	180.00	-30.00	0.00	30.00	28.31	1.69	17.712		
400.00	400.00	400.00	400.00	1.21	1.21	180.00	-30.00	0.00	30.00	27.59	2.41	12.444		
500.00	500.00	500.00	500.00	1.56	1.56	180.00	-30.00	0.00	30.00	26.87	3.13	9.582		
600.00	600.00	600.00	600.00	1.92	1.92	180.00	-30.00	0.00	30.00	26.16	3.84	7.803		
700.00	700.00	700.00	700.00	2.28	2.28	180.00	-30.00	0.00	30.00	25.44	4.56	6.577		
800.00	800.00	800.00	800.00	2.64	2.64	180.00	-30.00	0.00	30.00	24.72	5.28	5.633		
900.00	900.00	900.00	900.00	3.00	3.00	180.00	-30.00	0.00	30.00	24.00	6.00	5.004		
1,000.00	1,000.00	1,000.00	1,000.00	3.36	3.36	180.00	-30.00	0.00	30.00	23.29	6.71	4.489 CC		
1,100.00	1,099.99	1,099.81	1,099.80	3.71	3.70	90.26	-30.31	1.27	30.31	22.91	7.41	4.091 ES		
1,200.00	1,199.91	1,199.62	1,199.53	4.05	4.04	90.46	-31.24	5.07	31.26	23.17	8.09	3.862		
1,300.00	1,299.70	1,299.48	1,299.18	4.40	4.39	90.77	-32.76	11.26	32.80	24.01	8.79	3.732		
1,400.00	1,399.46	1,399.46	1,398.92	4.75	4.74	91.07	-34.41	18.04	34.48	24.99	9.49	3.634		
1,500.00	1,498.22	1,498.45	1,498.67	5.11	5.09	91.35	-36.07	24.81	36.17	25.97	10.20	3.547		
1,600.00	1,598.97	1,599.44	1,598.41	5.46	5.45	91.60	-37.73	31.59	37.85	26.95	10.91	3.470		
1,700.00	1,698.73	1,699.42	1,698.15	5.82	5.80	91.83	-39.39	38.36	39.54	27.92	11.62	3.402		
1,800.00	1,798.48	1,799.41	1,797.89	6.18	6.16	92.04	-41.04	45.14	41.23	28.88	12.34	3.340		
1,900.00	1,898.24	1,899.39	1,897.63	6.54	6.52	92.23	-42.70	51.91	42.91	29.85	13.06	3.285		
2,000.00	1,998.00	1,999.38	1,997.38	6.91	6.89	92.41	-44.36	58.68	44.60	30.81	13.79	3.235		
2,100.00	2,097.75	2,099.36	2,097.12	7.27	7.25	92.57	-46.02	65.46	46.29	31.78	14.51	3.190		
2,200.00	2,197.51	2,199.35	2,196.86	7.63	7.61	92.73	-47.68	72.23	47.98	32.74	15.24	3.149		
2,300.00	2,297.27	2,299.34	2,296.60	8.00	7.97	92.87	-49.33	79.01	49.66	33.70	15.96	3.111		
2,400.00	2,397.02	2,399.32	2,396.35	8.36	8.34	93.01	-50.99	85.78	51.36	34.66	16.69	3.076		
2,500.00	2,496.78	2,499.31	2,496.09	8.73	8.70	93.13	-52.65	92.56	53.04	35.62	17.42	3.044		
2,600.00	2,596.54	2,599.29	2,595.83	9.09	9.07	93.25	-54.31	99.33	54.73	36.58	18.15	3.015		
2,700.00	2,696.29	2,699.28	2,695.57	9.46	9.43	93.36	-55.96	106.11	56.42	37.53	18.89	2.987		
2,800.00	2,796.02	2,799.13	2,795.15	9.83	9.80	93.47	-57.69	113.18	58.19	38.57	19.62	2.966 SF		
2,900.00	2,895.56	2,898.82	2,894.39	10.20	10.17	93.59	-59.36	122.43	60.50	40.14	20.36	2.971		
3,000.00	2,994.81	2,998.49	2,993.32	10.58	10.55	93.73	-62.84	134.20	63.45	42.33	21.12	3.004		
3,100.00	3,093.71	3,098.13	3,091.87	10.97	10.94	93.88	-66.33	148.46	67.02	45.13	21.89	3.061		
3,200.00	3,192.25	3,197.89	3,190.17	11.36	11.33	94.05	-70.36	164.95	71.15	48.47	22.68	3.137		
3,300.00	3,290.73	3,297.80	3,288.57	11.76	11.73	94.21	-74.49	181.80	75.36	51.88	23.48	3.210		
3,400.00	3,389.21	3,397.71	3,386.96	12.16	12.13	94.35	-78.61	198.65	79.56	55.28	24.28	3.277		
3,500.00	3,487.69	3,497.63	3,485.35	12.57	12.54	94.48	-82.73	215.50	83.77	58.69	25.08	3.340		
3,600.00	3,586.17	3,597.54	3,583.75	12.97	12.94	94.59	-86.86	232.36	87.98	62.09	25.89	3.398		
3,700.00	3,684.65	3,697.45	3,682.14	13.38	13.35	94.70	-90.98	249.21	92.19	65.48	26.71	3.452		
3,800.00	3,783.13	3,797.36	3,780.53	13.79	13.76	94.79	-95.10	266.06	96.40	68.87	27.53	3.502		
3,900.00	3,881.61	3,897.27	3,878.93	14.20	14.17	94.88	-99.23	282.91	100.61	72.26	28.35	3.549		
4,000.00	3,980.09	3,997.18	3,977.32	14.61	14.59	94.96	-103.35	299.76	104.82	75.65	29.17	3.594		
4,100.00	4,078.57	4,097.09	4,075.71	15.03	15.00	95.04	-107.47	316.61	109.03	79.03	29.99	3.635		
4,200.00	4,177.05	4,197.00	4,174.11	15.44	15.41	95.11	-111.60	333.46	113.24	82.42	30.82	3.674		
4,300.00	4,275.53	4,296.92	4,272.50	15.86	15.83	95.17	-115.72	350.31	117.45	85.80	31.65	3.711		
4,400.00	4,374.02	4,396.83	4,370.89	16.27	16.25	95.23	-119.84	367.16	121.66	89.18	32.49	3.745		
4,500.00	4,472.50	4,496.74	4,469.29	16.69	16.67	95.29	-123.97	384.01	125.87	92.55	33.32	3.778		
4,600.00	4,570.98	4,596.65	4,567.68	17.11	17.09	95.34	-128.09	400.87	130.08	95.93	34.16	3.809		
4,700.00	4,669.46	4,696.56	4,666.08	17.53	17.51	95.39	-132.21	417.72	134.29	99.30	34.99	3.838		
4,800.00	4,767.94	4,796.47	4,764.47	17.95	17.93	95.43	-136.34	434.57	138.50	102.67	35.83	3.865		
4,900.00	4,866.42	4,896.38	4,862.86	18.37	18.35	95.48	-140.46	451.42	142.71	106.04	36.67	3.892		
5,000.00	4,964.90	4,996.29	4,961.26	18.79	18.77	95.52	-144.58	468.27	146.93	109.41	37.51	3.917		
5,100.00	5,063.38	5,096.21	5,059.65	19.21	19.19	95.55	-148.71	485.12	151.14	112.78	38.36	3.940		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Phoenix Technology Services
Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design													Offset Site Error:	0.00 usft
Dr. Scrivner Federal 01-24S-28E RB - 208H - OH - Preliminary Plan 1													Offset Well Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM														
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (usft)	Separation Factor	Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Between Centres (usft)	Between Ellipses (usft)				Offset Well Error:	0.00 usft	Offset Site Error:
5,200.00	5,161.86	5,196.12	5,158.04	19.64	19.62	95.59	-152.83	501.97	155.35	116.15	39.20	3.963		
5,300.00	5,260.34	5,296.03	5,256.44	20.06	20.04	95.62	-156.95	518.82	159.56	119.51	40.05	3.984		
5,400.00	5,358.82	5,395.94	5,354.83	20.48	20.46	95.65	-161.08	535.67	163.77	122.88	40.89	4.005		
5,500.00	5,457.48	5,495.85	5,453.22	20.90	20.89	95.38	-165.20	552.52	167.88	126.15	41.73	4.023		
5,600.00	5,556.53	5,596.27	5,552.24	21.31	21.31	94.50	-169.17	568.74	171.68	129.11	42.55	4.034		
5,700.00	5,655.90	5,696.95	5,651.92	21.70	21.72	93.62	-172.54	582.52	174.87	131.53	43.34	4.035		
5,800.00	5,755.53	5,797.74	5,752.04	22.07	22.12	92.75	-175.29	593.76	177.48	133.38	44.10	4.024		
5,900.00	5,855.35	5,898.83	5,852.53	22.43	22.50	91.89	-177.42	602.44	179.51	134.68	44.83	4.004		
6,000.00	5,955.29	5,999.61	5,953.31	22.78	22.86	91.02	-178.91	608.54	180.94	135.41	45.53	3.974		
6,100.00	6,055.29	6,100.68	6,054.31	23.11	23.22	179.98	-179.77	612.06	181.77	136.23	43.55	4.174		
6,200.00	6,155.29	6,201.67	6,155.29	23.43	23.55	179.69	-180.00	613.00	182.00	137.77	44.23	4.115		
6,300.00	6,255.29	6,301.67	6,255.29	23.75	23.86	179.69	-180.00	613.00	182.00	137.10	44.90	4.053		
6,400.00	6,355.29	6,401.67	6,355.29	24.08	24.18	179.69	-180.00	613.00	182.00	136.43	45.57	3.994		
6,500.00	6,455.29	6,501.67	6,455.29	24.40	24.50	179.69	-180.00	613.00	182.00	135.76	46.25	3.935		
6,600.00	6,555.29	6,601.67	6,555.29	24.73	24.83	179.69	-180.00	613.00	182.00	135.08	46.92	3.879		
6,700.00	6,655.29	6,701.67	6,655.29	25.06	25.15	179.69	-180.00	613.00	182.00	134.41	47.60	3.824		
6,800.00	6,755.29	6,801.67	6,755.29	25.38	25.47	179.69	-180.00	613.00	182.00	133.73	48.27	3.770		
6,900.00	6,855.29	6,901.67	6,855.29	25.71	25.80	179.69	-180.00	613.00	182.00	133.05	48.95	3.718		
7,000.00	6,955.29	7,001.67	6,955.29	26.04	26.12	179.69	-180.00	613.00	182.00	132.37	49.63	3.667		
7,100.00	7,055.29	7,101.67	7,055.29	26.37	26.45	179.69	-180.00	613.00	182.00	131.69	50.31	3.618		
7,200.00	7,155.29	7,201.67	7,155.29	26.70	26.77	179.69	-180.00	613.00	182.00	131.01	50.99	3.569		
7,300.00	7,255.29	7,301.67	7,255.29	27.04	27.10	179.69	-180.00	613.00	182.00	130.33	51.67	3.522		
7,400.00	7,355.29	7,401.67	7,355.29	27.37	27.43	179.69	-180.00	613.00	182.00	129.65	52.36	3.476		
7,500.00	7,455.29	7,501.67	7,455.29	27.70	27.76	179.69	-180.00	613.00	182.00	128.96	53.04	3.431		
7,600.00	7,555.29	7,601.67	7,555.29	28.04	28.09	179.69	-180.00	613.00	182.00	128.28	53.72	3.388		
7,700.00	7,655.29	7,701.67	7,655.29	28.37	28.42	179.69	-180.00	613.00	182.00	127.59	54.41	3.345		
7,800.00	7,755.29	7,801.67	7,755.29	28.71	28.75	179.69	-180.00	613.00	182.00	126.91	55.10	3.303		
7,900.00	7,855.29	7,901.67	7,855.29	29.04	29.08	179.69	-180.00	613.00	182.00	126.22	55.78	3.263		
7,962.91	7,918.20	7,964.57	7,918.20	29.25	29.29	-90.20	-180.00	613.00	182.00	123.57	58.44	3.114		
8,000.00	7,955.29	8,001.66	7,955.29	29.38	29.42	-90.10	-180.00	613.00	182.00	123.32	58.69	3.101		
8,015.26	7,970.54	8,016.91	7,970.54	29.42	29.47	-90.28	-180.00	613.00	182.00	123.22	58.78	3.096		
8,100.00	8,054.55	8,100.93	8,054.55	29.67	29.75	-93.49	-180.00	613.00	182.36	123.11	59.25	3.078		
8,200.00	8,150.40	8,196.77	8,150.40	29.92	30.07	-101.40	-180.00	613.00	185.22	126.77	59.46	3.132		
8,300.00	8,239.91	8,286.29	8,239.91	30.17	30.37	-111.45	-180.00	613.00	200.33	141.64	58.69	3.413		
8,400.00	8,320.37	8,366.76	8,320.37	30.42	30.63	-120.52	-180.00	613.00	231.38	174.84	56.54	4.092		
8,500.00	8,389.33	8,435.71	8,389.33	30.74	30.87	-126.45	-180.00	613.00	281.76	228.05	53.73	5.245		
8,600.00	8,444.71	8,491.08	8,444.71	31.17	31.05	-128.17	-180.00	613.00	349.38	297.47	51.92	6.730		
8,700.00	8,484.80	8,531.18	8,484.80	31.77	31.19	-124.43	-180.00	613.00	430.11	376.81	53.30	8.070		
8,800.00	8,508.41	8,554.79	8,508.41	32.56	31.27	-111.96	-180.00	613.00	519.66	460.24	59.42	8.745		
8,900.00	8,514.81	8,561.18	8,514.81	33.53	31.29	-86.45	-180.00	613.00	614.01	549.38	64.63	9.501		
9,000.00	8,512.88	8,559.26	8,512.88	34.68	31.28	-85.84	-180.00	613.00	710.12	644.38	65.74	10.803		
9,100.00	8,510.95	8,557.33	8,510.95	36.02	31.27	-85.24	-180.00	613.00	807.17	740.14	67.02	12.043		
9,200.00	8,509.03	8,555.40	8,509.03	37.53	31.27	-84.64	-180.00	613.00	904.85	836.39	68.47	13.216		
9,300.00	8,507.10	8,553.48	8,507.10	39.19	31.26	-84.04	-180.00	613.00	1,002.99	932.84	70.05	14.319		
9,400.00	8,505.17	8,551.55	8,505.17	40.98	31.25	-83.44	-180.00	613.00	1,101.46	1,029.71	71.75	15.352		
9,500.00	8,503.25	8,549.62	8,503.25	42.88	31.25	-82.84	-180.00	613.00	1,200.18	1,126.63	73.55	16.317		
9,600.00	8,501.32	8,547.70	8,501.32	44.88	31.24	-82.25	-180.00	613.00	1,299.10	1,223.66	75.44	17.220		
9,700.00	8,499.39	10,992.72	9,767.25	46.96	50.01	-165.42	-334.22	-796.83	1,310.27	1,271.86	38.42	34.105		
9,800.00	8,497.47	11,092.72	9,765.34	48.13	52.06	-165.42	-334.68	-896.81	1,310.29	1,270.36	39.92	32.820		
9,900.00	8,495.54	11,192.72	9,763.43	51.35	54.17	-165.42	-335.15	-996.79	1,310.30	1,268.82	41.48	31.589		
10,000.00	8,493.61	11,292.72	9,761.51	53.64	56.35	-165.42	-335.61	-1,096.77	1,310.32	1,267.24	43.08	30.416		
10,100.00	8,491.69	11,392.72	9,759.60	55.97	58.58	-165.42	-336.07	-1,196.75	1,310.33	1,265.61	44.72	29.300		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Phoenix Technology Services
Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design														Offset Site Error: 0.00 usft	
Dr. Scrivner Federal 01-24S-28E RB - 208H - OH - Preliminary Plan 1														Offset Well Error: 0.00 usft	
Survey Program: 0-PHX+MWD+HDGM															
Reference		Offset		Semi Major Axis		Highside Toothface (°)	Distance		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)										
10,200.00	8,489.76	11,492.72	9,757.69	58.36	60.87	-165.42	-336.53	-1,296.73	1,310.35	1,263.95	46.40	28.241			
10,300.00	8,487.83	11,592.72	9,755.77	60.77	63.19	-165.42	-335.99	-1,396.71	1,310.36	1,262.25	48.11	27.238			
10,400.00	8,485.91	11,692.72	9,753.86	63.23	65.56	-165.42	-337.45	-1,496.69	1,310.37	1,260.53	49.85	26.289			
10,500.00	8,483.98	11,792.72	9,751.95	65.71	67.97	-165.42	-337.92	-1,596.67	1,310.39	1,258.78	51.61	25.391			
10,600.00	8,482.05	11,892.72	9,750.03	68.23	70.40	-165.42	-338.38	-1,696.65	1,310.40	1,257.01	53.40	24.541			
10,700.00	8,480.13	11,992.72	9,749.12	70.77	72.87	-165.42	-338.84	-1,796.63	1,310.42	1,255.21	55.21	23.737			
10,800.00	8,478.20	12,092.72	9,746.20	73.32	75.36	-165.42	-339.30	-1,896.61	1,310.43	1,253.40	57.03	22.977			
10,900.00	8,476.27	12,192.72	9,744.29	75.90	77.87	-165.42	-339.76	-1,996.59	1,310.44	1,251.57	58.88	22.257			
11,000.00	8,474.35	12,292.72	9,742.38	78.50	80.41	-165.42	-340.23	-2,096.57	1,310.46	1,249.72	60.74	21.575			
11,100.00	8,472.42	12,392.72	9,740.46	81.11	82.96	-165.42	-340.69	-2,196.55	1,310.47	1,247.86	62.62	20.929			
11,200.00	8,470.49	12,492.72	9,738.55	83.74	85.53	-165.42	-341.15	-2,296.53	1,310.49	1,245.98	64.50	20.316			
11,300.00	8,468.57	12,592.72	9,736.64	86.38	88.12	-165.42	-341.61	-2,396.52	1,310.50	1,244.10	66.40	19.735			
11,400.00	8,466.64	12,692.72	9,734.72	89.04	90.73	-165.42	-342.07	-2,496.50	1,310.52	1,242.20	68.32	19.183			
11,500.00	8,464.71	12,792.72	9,732.81	91.70	93.34	-165.42	-342.53	-2,596.48	1,310.53	1,240.29	70.24	18.658			
11,600.00	8,462.79	12,892.72	9,730.90	94.38	95.97	-165.42	-343.00	-2,696.46	1,310.54	1,238.37	72.17	18.159			
11,700.00	8,460.86	12,992.72	9,728.98	97.06	98.51	-165.42	-343.46	-2,796.44	1,310.56	1,236.45	74.11	17.684			
11,800.00	8,458.93	13,092.72	9,727.07	99.75	101.27	-165.42	-343.92	-2,896.42	1,310.57	1,234.51	76.06	17.231			
11,900.00	8,457.00	13,192.72	9,725.15	102.45	103.93	-165.42	-344.38	-2,996.40	1,310.59	1,232.57	78.01	16.800			
12,000.00	8,455.08	13,292.72	9,723.24	105.16	106.60	-165.42	-344.84	-3,096.38	1,310.60	1,230.63	79.97	16.388			
12,100.00	8,453.15	13,392.72	9,721.33	107.88	109.28	-165.42	-345.31	-3,196.36	1,310.61	1,228.67	81.94	15.994			
12,200.00	8,451.22	13,492.72	9,719.41	110.60	111.96	-165.42	-345.77	-3,296.34	1,310.63	1,226.71	83.92	15.618			
12,300.00	8,449.30	13,592.72	9,717.50	113.32	114.66	-165.42	-346.23	-3,396.32	1,310.64	1,224.75	85.90	15.258			
12,400.00	8,447.37	13,692.72	9,715.59	116.05	117.36	-165.42	-346.69	-3,496.30	1,310.66	1,222.77	87.88	14.914			
12,500.00	8,445.44	13,792.72	9,713.67	118.79	120.06	-165.42	-347.15	-3,596.28	1,310.67	1,220.80	89.87	14.584			
12,600.00	8,443.52	13,892.72	9,711.76	121.53	122.78	-165.42	-347.62	-3,696.26	1,310.69	1,218.82	91.87	14.267			
12,700.00	8,441.59	13,992.72	9,709.85	124.28	125.48	-165.42	-348.08	-3,796.24	1,310.70	1,216.84	93.86	13.964			
12,800.00	8,439.66	14,092.72	9,707.93	127.03	128.22	-165.42	-348.54	-3,896.22	1,310.71	1,214.85	95.87	13.672			
12,900.00	8,437.74	14,192.72	9,706.02	129.78	130.94	-165.42	-349.00	-3,996.21	1,310.73	1,212.85	97.87	13.392			
13,000.00	8,435.81	14,292.72	9,704.11	132.54	133.68	-165.42	-349.46	-4,096.19	1,310.74	1,210.86	99.88	13.123			
13,100.00	8,433.88	14,392.72	9,702.19	135.30	136.41	-165.42	-349.92	-4,196.17	1,310.76	1,208.86	101.90	12.864			
13,200.00	8,431.96	14,492.72	9,700.28	138.06	139.15	-165.42	-350.39	-4,296.15	1,310.77	1,206.86	103.91	12.614			
13,300.00	8,430.03	14,592.72	9,698.36	140.83	141.90	-165.42	-350.85	-4,396.13	1,310.78	1,204.85	105.93	12.374			
13,318.10	8,429.68	14,610.82	9,698.02	141.33	142.39	-165.42	-350.93	-4,414.22	1,310.79	1,204.49	106.30	12.332			
13,355.63	8,428.96	14,625.60	9,697.74	142.37	142.80	-165.42	-351.00	-4,429.00	1,310.99	1,204.16	106.83	12.272			



Phoenix Technology Services

Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design											Offset Site Error: 0.00 usft		
Dr. Scrivner Federal 01-24S-28E RB - 224H - OH / Job 1514201 - Preliminary Plan 1											Offset Well Error: 0.00 usft		
Survey Program: O-PHX+MWD+HDGM													
Reference		Offset		Semi Major Axis			Distance						
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
0.00	0.00	0.00	0.00	0.00	0.00	0.00	60.00	0.00	60.00				
100.00	100.00	100.00	100.00	0.13	0.13	0.00	60.00	0.00	60.00	58.74	0.26	230.865	
200.00	200.00	200.00	200.00	0.49	0.49	0.00	60.00	0.00	60.00	59.02	0.98	61.423	
300.00	300.00	300.00	300.00	0.85	0.85	0.00	60.00	0.00	60.00	58.31	1.69	35.424	
400.00	400.00	400.00	400.00	1.21	1.21	0.00	60.00	0.00	60.00	57.59	2.41	24.889	
500.00	500.00	500.00	500.00	1.56	1.56	0.00	60.00	0.00	60.00	56.87	3.13	19.184	
600.00	600.00	600.00	600.00	1.92	1.92	0.00	60.00	0.00	60.00	56.16	3.84	15.606	
700.00	700.00	700.00	700.00	2.28	2.28	0.00	60.00	0.00	60.00	55.44	4.56	13.153	
800.00	800.00	800.00	800.00	2.64	2.64	0.00	60.00	0.00	60.00	54.72	5.28	11.367	
900.00	900.00	900.00	900.00	3.00	3.00	0.00	60.00	0.00	60.00	54.00	6.00	10.006	
1,000.00	1,000.00	1,000.00	1,000.00	3.36	3.36	0.00	60.00	0.00	60.00	53.29	6.71	8.939 CC	
1,100.00	1,099.99	1,099.36	1,099.35	3.71	3.71	-89.92	60.53	1.18	60.52	53.11	7.41	8.164 ES	
1,200.00	1,199.91	1,198.71	1,198.62	4.05	4.06	-90.22	62.10	4.72	62.10	53.99	8.11	7.660	
1,300.00	1,299.70	1,298.23	1,297.94	4.40	4.41	-90.69	64.68	10.51	64.67	55.87	8.81	7.343	
1,400.00	1,399.46	1,398.19	1,397.65	4.75	4.76	-91.16	67.51	16.88	67.50	57.88	9.51	7.094	
1,500.00	1,499.22	1,498.15	1,497.37	5.11	5.12	-91.60	70.35	23.25	70.33	60.10	10.23	6.877	
1,600.00	1,598.97	1,598.11	1,597.08	5.46	5.48	-92.00	73.18	29.62	73.16	62.22	10.94	6.686	
1,700.00	1,698.73	1,698.06	1,696.80	5.82	5.84	-92.37	76.02	35.99	75.99	64.33	11.66	6.517	
1,800.00	1,798.48	1,798.02	1,796.51	6.18	6.20	-92.72	78.85	42.36	78.83	66.45	12.38	6.367	
1,900.00	1,898.24	1,897.98	1,896.23	6.54	6.56	-93.04	81.69	48.73	81.67	68.57	13.11	6.232	
2,000.00	1,998.00	1,997.94	1,995.94	6.91	6.93	-93.34	84.52	55.11	84.52	70.69	13.83	6.111	
2,100.00	2,097.75	2,097.90	2,095.66	7.27	7.29	-93.62	87.36	61.48	87.36	72.81	14.56	6.002	
2,200.00	2,197.51	2,197.86	2,195.37	7.63	7.66	-93.88	90.19	67.85	90.21	74.93	15.28	5.902	
2,300.00	2,297.27	2,297.82	2,295.09	8.00	8.02	-94.13	93.03	74.22	93.06	77.05	16.01	5.812	
2,400.00	2,397.02	2,397.77	2,394.80	8.36	8.39	-94.36	95.86	80.59	95.91	79.17	16.74	5.729	
2,500.00	2,496.78	2,497.73	2,494.52	8.73	8.75	-94.58	98.70	86.96	98.76	81.29	17.47	5.652	
2,600.00	2,596.54	2,597.68	2,594.23	9.09	9.12	-94.78	101.53	93.33	101.62	83.41	18.20	5.582	
2,700.00	2,696.29	2,697.65	2,693.95	9.46	9.48	-94.98	104.37	99.70	104.47	85.54	18.94	5.517	
2,800.00	2,796.02	2,797.18	2,793.22	9.83	9.85	-95.16	107.31	106.31	107.45	87.78	19.67	5.463	
2,900.00	2,895.56	2,896.21	2,891.79	10.20	10.22	-95.38	111.13	114.90	111.35	90.94	20.41	5.456 SF	
3,000.00	2,994.81	2,995.17	2,990.02	10.58	10.59	-95.64	115.99	125.82	116.31	95.15	21.16	5.497	
3,100.00	3,093.71	3,094.04	3,087.83	10.97	10.97	-95.92	121.88	139.04	122.33	100.40	21.92	5.580	
3,200.00	3,192.25	3,193.25	3,185.60	11.36	11.36	-96.22	128.72	154.41	129.30	106.59	22.71	5.694	
3,300.00	3,290.73	3,292.99	3,283.83	11.76	11.76	-96.51	135.76	170.23	136.42	112.93	23.50	5.806	
3,400.00	3,389.21	3,392.74	3,382.06	12.16	12.16	-96.77	142.80	186.06	143.55	119.26	24.29	5.910	
3,500.00	3,487.69	3,492.48	3,480.28	12.57	12.56	-97.00	149.85	201.88	150.69	125.60	25.09	6.006	
3,600.00	3,586.17	3,592.22	3,578.51	12.97	12.96	-97.22	156.89	217.70	157.82	131.93	25.89	6.095	
3,700.00	3,684.65	3,691.97	3,676.74	13.38	13.36	-97.41	163.93	233.53	164.96	138.26	26.70	6.178	
3,800.00	3,783.13	3,791.71	3,774.97	13.79	13.77	-97.59	170.98	249.35	172.10	144.59	27.51	6.256	
3,900.00	3,881.61	3,891.45	3,873.20	14.20	14.17	-97.76	178.02	265.17	179.24	150.92	28.32	6.328	
4,000.00	3,980.09	3,991.20	3,971.42	14.61	14.58	-97.91	185.06	281.00	186.38	157.24	29.14	6.396	
4,100.00	4,078.57	4,090.94	4,069.65	15.03	14.99	-98.05	192.10	296.82	193.53	163.57	29.96	6.460	
4,200.00	4,177.05	4,190.68	4,167.88	15.44	15.40	-98.18	199.15	312.64	200.67	169.89	30.78	6.520	
4,300.00	4,275.53	4,290.43	4,266.11	15.86	15.81	-98.31	206.19	328.47	207.82	175.22	31.60	6.576	
4,400.00	4,374.02	4,390.17	4,364.34	16.27	16.22	-98.42	213.23	344.29	214.96	182.54	32.43	6.629	
4,500.00	4,472.50	4,489.91	4,462.57	16.69	16.64	-98.53	220.28	360.11	222.11	188.86	33.25	6.680	
4,600.00	4,570.98	4,589.66	4,560.79	17.11	17.05	-98.63	227.32	375.94	229.26	195.18	34.08	6.727	
4,700.00	4,669.46	4,689.40	4,659.02	17.53	17.47	-98.72	234.36	391.76	235.41	201.50	34.91	6.772	
4,800.00	4,767.94	4,789.14	4,757.25	17.95	17.88	-98.81	241.40	407.58	243.56	207.82	35.74	6.815	
4,900.00	4,866.42	4,888.89	4,855.48	18.37	18.30	-98.89	248.45	423.41	250.71	214.14	36.57	6.855	
5,000.00	4,964.90	4,988.63	4,953.71	18.79	18.72	-98.97	255.49	439.23	257.86	220.45	37.41	6.893	
5,100.00	5,063.38	5,088.37	5,051.93	19.21	19.13	-99.05	262.53	455.05	265.01	226.77	38.24	6.930	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Phoenix Technology Services

Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design														Offset Site Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toothface (")	Distance		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)										
5,200.00	5,161.86	5,188.12	5,150.16	19.64	19.55	-99.12	269.58	470.88	272.16	233.08	39.08	6.965			
5,300.00	5,260.34	5,287.86	5,248.39	20.06	19.97	-99.19	276.62	486.70	279.31	239.40	39.91	6.998			
5,400.00	5,358.82	5,387.60	5,346.82	20.48	20.39	-99.25	283.66	502.52	286.47	245.71	40.75	7.029			
5,500.00	5,457.38	5,487.36	5,444.85	20.90	20.81	-99.20	290.71	518.35	293.45	251.85	41.59	7.056			
5,600.00	5,556.53	5,587.08	5,543.07	21.31	21.23	-98.67	297.75	534.17	300.03	257.62	42.42	7.074			
5,700.00	5,655.90	5,686.72	5,641.19	21.70	21.65	-97.67	304.78	549.97	306.30	263.07	43.23	7.086			
5,800.00	5,755.53	5,787.59	5,740.60	22.07	22.07	-96.30	311.74	565.60	312.26	268.24	44.02	7.094			
5,900.00	5,855.35	5,889.77	5,841.69	22.43	22.49	-94.89	317.79	579.21	317.40	272.61	44.79	7.087			
6,000.00	5,955.29	5,992.25	5,943.43	22.78	22.89	-93.49	322.76	590.37	321.66	276.13	45.53	7.065			
6,100.00	6,055.29	6,095.01	6,045.75	23.11	23.28	-92.28	326.63	599.06	325.03	281.34	46.69	7.440			
6,200.00	6,155.29	6,198.14	6,148.65	23.43	23.65	-91.18	329.38	605.24	327.52	283.11	44.41	7.376			
6,300.00	6,255.29	6,301.57	6,252.00	23.75	24.01	-90.54	331.01	608.90	329.04	283.92	45.12	7.293			
6,400.00	6,355.29	6,404.87	6,355.29	24.08	24.36	-90.35	331.50	610.00	329.51	283.69	45.81	7.192			
6,500.00	6,455.29	6,504.87	6,455.29	24.40	24.68	-90.35	331.50	610.00	329.51	283.01	46.49	7.087			
6,600.00	6,555.29	6,604.87	6,555.29	24.73	25.01	-90.35	331.50	610.00	329.51	282.34	47.17	6.985			
6,700.00	6,655.29	6,704.87	6,655.29	25.06	25.34	-90.35	331.50	610.00	329.51	281.66	47.85	6.886			
6,800.00	6,755.29	6,804.87	6,755.29	25.38	25.66	-90.35	331.50	610.00	329.51	280.97	48.53	6.789			
6,900.00	6,855.29	6,904.87	6,855.29	25.71	25.99	-90.35	331.50	610.00	329.51	280.29	49.21	6.685			
7,000.00	6,955.29	7,004.87	6,955.29	26.04	26.32	-90.35	331.50	610.00	329.51	279.61	49.90	6.604			
7,100.00	7,055.29	7,104.87	7,055.29	26.37	26.65	-90.35	331.50	610.00	329.51	278.92	50.58	6.514			
7,200.00	7,155.29	7,204.87	7,155.29	26.70	26.99	-90.35	331.50	610.00	329.51	278.24	51.27	6.427			
7,300.00	7,255.29	7,304.87	7,255.29	27.04	27.32	-90.35	331.50	610.00	329.51	277.55	51.95	6.342			
7,400.00	7,355.29	7,404.87	7,355.29	27.37	27.65	-90.35	331.50	610.00	329.51	276.87	52.64	6.260			
7,500.00	7,455.29	7,504.87	7,455.29	27.70	27.98	-90.35	331.50	610.00	329.51	276.18	53.33	6.179			
7,600.00	7,555.29	7,604.87	7,555.29	28.04	28.32	-90.35	331.50	610.00	329.51	275.49	54.01	6.100			
7,700.00	7,655.29	7,704.87	7,655.29	28.37	28.65	-90.35	331.50	610.00	329.51	274.80	54.70	6.023			
7,800.00	7,755.29	7,804.87	7,755.29	28.71	28.99	-90.35	331.50	610.00	329.51	274.11	55.39	5.948			
7,900.00	7,855.29	7,904.87	7,855.29	29.04	29.32	-90.35	331.50	610.00	329.51	273.42	56.08	5.875			
8,000.00	7,955.29	8,004.87	7,955.29	29.38	29.66	-89.94	331.50	610.00	329.51	272.61	56.89	5.895			
8,021.70	7,976.87	8,026.55	7,976.87	29.44	29.73	-90.10	331.50	610.00	329.51	270.48	59.03	5.582			
8,100.00	8,054.55	8,104.13	8,054.55	29.67	29.99	-91.82	331.50	610.00	329.68	270.19	59.49	5.542			
8,200.00	8,150.40	8,199.98	8,150.40	29.92	30.32	-96.25	331.50	610.00	331.78	271.85	59.92	5.537			
8,300.00	8,239.91	8,289.49	8,239.91	30.17	30.62	-102.15	331.50	610.00	339.81	279.84	59.96	5.687			
8,400.00	8,320.37	8,369.95	8,320.37	30.42	30.89	-107.96	331.50	610.00	358.88	299.49	59.40	6.042			
8,500.00	8,389.33	8,438.91	8,389.33	30.74	31.12	-112.13	331.50	610.00	393.14	334.68	58.46	6.725			
8,600.00	8,444.71	8,494.29	8,444.71	31.17	31.31	-113.43	331.50	610.00	443.88	385.95	58.03	7.650			
8,700.00	8,484.80	8,534.38	8,484.80	31.77	31.45	-110.71	331.50	610.00	509.83	450.59	59.24	8.607			
8,800.00	8,508.41	8,557.99	8,508.41	32.56	31.53	-102.54	331.50	610.00	587.24	524.89	62.35	9.418			
8,900.00	8,514.81	8,564.39	8,514.81	33.53	31.55	-88.04	331.50	610.00	672.07	607.12	64.95	10.348			
9,000.00	8,512.88	8,562.46	8,512.88	34.68	31.54	-87.70	331.50	610.00	760.79	694.70	66.09	11.512			
9,100.00	8,510.95	8,560.53	8,510.95	36.02	31.54	-87.37	331.50	610.00	852.01	784.60	67.41	12.639			
9,200.00	8,509.03	8,558.61	8,509.03	37.53	31.53	-87.04	331.50	610.00	945.00	876.10	68.90	13.715			
9,300.00	8,507.10	8,556.68	8,507.10	39.19	31.52	-86.70	331.50	610.00	1,039.29	968.76	70.54	14.734			
9,400.00	8,505.17	8,554.75	8,505.17	40.98	31.52	-86.37	331.50	610.00	1,134.56	1,062.26	72.30	15.693			
9,500.00	8,503.25	8,552.83	8,503.25	42.88	31.51	-86.03	331.50	610.00	1,230.57	1,156.41	74.17	16.592			
9,600.00	8,501.32	8,550.90	8,501.32	44.88	31.50	-85.70	331.50	610.00	1,327.17	1,251.04	75.13	17.432			
9,700.00	8,499.39	8,548.97	8,499.39	46.96	31.50	-85.37	331.50	610.00	1,424.24	1,346.06	76.18	18.217			
9,800.00	8,497.47	8,547.05	8,497.47	49.13	31.49	-85.04	331.50	610.00	1,521.69	1,441.38	77.30	18.950			
9,900.00	8,495.54	8,545.12	8,495.54	51.35	31.48	-84.70	331.50	610.00	1,619.44	1,536.96	78.48	19.634			
10,000.00	8,493.61	8,543.19	8,493.61	53.64	31.48	-84.37	331.50	610.00	1,717.45	1,632.74	79.71	20.273			
10,100.00	8,491.69	8,541.27	8,491.69	55.97	31.47	-84.04	331.50	610.00	1,815.68	1,728.68	80.99	20.871			
10,200.00	8,489.76	8,539.34	8,489.76	58.36	31.46	-83.71	331.50	610.00	1,914.08	1,824.77	82.31	21.432			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Phoenix Technology Services
Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design													Offset Site Error:
Dr. Scrivner Federal 01-24S-28E RB - 224H - OH / Job 1514201 - Preliminary Plan 1													0.00 usft
Survey Program: D-PHX+MWD+HDGM													Offset Well Error:
													0.00 usft
Reference		Offset		Semi Major Axis		Distance							
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
10,300.00	8,487.83	8,537.41	8,487.83	60.77	31.46	83.38	331.50	610.00	2,012.65	1,920.98	91.66	21.957	
10,400.00	8,485.91	12,491.17	10,545.14	63.23	67.77	170.91	321.98	-1,515.12	2,086.82	2,041.87	44.95	46.422	
10,500.00	8,483.98	12,691.17	10,544.21	65.71	70.12	170.91	321.54	-1,615.10	2,086.82	2,040.41	46.41	44.962	
10,600.00	8,482.05	12,691.17	10,542.29	68.23	72.51	170.91	321.09	-1,715.08	2,086.83	2,038.93	47.89	43.571	
10,700.00	8,480.13	12,791.17	10,540.36	70.77	74.93	170.91	320.65	-1,815.06	2,086.83	2,037.43	49.40	42.246	
10,800.00	8,478.20	12,891.17	10,538.43	73.32	77.38	170.91	320.20	-1,915.04	2,086.83	2,035.91	50.92	40.985	
10,900.00	8,476.27	12,991.17	10,536.51	75.90	79.85	170.91	319.76	-2,015.02	2,086.83	2,034.38	52.45	39.785	
11,000.00	8,474.35	13,091.17	10,534.58	78.50	82.35	170.91	319.31	-2,115.00	2,086.83	2,032.83	54.00	38.642	
11,100.00	8,472.42	13,191.17	10,532.65	81.11	84.87	170.91	318.86	-2,214.98	2,086.83	2,031.26	55.57	37.554	
11,200.00	8,470.49	13,291.17	10,530.73	83.74	87.41	170.91	318.42	-2,314.97	2,086.84	2,029.69	57.15	36.517	
11,300.00	8,468.57	13,391.17	10,528.80	86.38	89.96	170.91	317.97	-2,414.95	2,086.84	2,028.10	58.74	35.528	
11,400.00	8,466.64	13,491.17	10,526.87	89.04	92.53	170.91	317.53	-2,514.93	2,086.84	2,026.50	60.34	34.586	
11,500.00	8,464.71	13,591.17	10,524.94	91.70	95.12	170.91	317.08	-2,614.91	2,086.84	2,024.89	61.95	33.686	
11,600.00	8,462.79	13,691.17	10,523.02	94.38	97.72	170.91	316.64	-2,714.89	2,086.84	2,023.27	63.57	32.823	
11,700.00	8,460.86	13,791.17	10,521.09	97.06	100.33	170.91	316.19	-2,814.87	2,086.84	2,021.64	65.20	32.008	
11,800.00	8,458.93	13,891.17	10,519.16	99.75	102.96	170.91	315.74	-2,914.85	2,086.84	2,020.01	66.83	31.224	
11,900.00	8,457.00	13,991.17	10,517.24	102.45	105.59	170.91	315.30	-3,014.83	2,086.85	2,018.37	68.48	30.474	
12,000.00	8,455.08	14,091.17	10,515.31	105.16	108.24	170.91	314.85	-3,114.81	2,086.85	2,016.72	70.13	29.757	
12,100.00	8,453.15	14,191.17	10,513.38	107.88	110.89	170.91	314.41	-3,214.79	2,086.85	2,015.06	71.79	29.070	
12,200.00	8,451.22	14,291.17	10,511.46	110.60	113.56	170.90	313.96	-3,314.77	2,086.85	2,013.40	73.45	28.411	
12,300.00	8,449.30	14,391.17	10,509.53	113.32	116.23	170.90	313.52	-3,414.75	2,086.85	2,011.73	75.12	27.780	
12,400.00	8,447.37	14,491.17	10,507.60	116.05	118.91	170.90	313.07	-3,514.73	2,086.85	2,010.06	76.79	27.175	
12,500.00	8,445.44	14,591.17	10,505.67	118.79	121.60	170.90	312.62	-3,614.71	2,086.85	2,008.38	78.47	26.593	
12,600.00	8,443.52	14,691.17	10,503.75	121.53	124.29	170.90	312.18	-3,714.69	2,086.86	2,006.70	80.16	26.034	
12,700.00	8,441.59	14,791.17	10,501.82	124.28	126.99	170.90	311.73	-3,814.67	2,086.86	2,005.01	81.85	25.497	
12,800.00	8,439.66	14,891.17	10,499.89	127.03	129.69	170.90	311.29	-3,914.65	2,086.86	2,003.32	83.54	24.981	
12,900.00	8,437.74	14,991.17	10,497.97	129.78	132.40	170.90	310.84	-4,014.63	2,086.86	2,001.63	85.23	24.484	
13,000.00	8,435.81	15,091.17	10,496.04	132.54	135.12	170.90	310.40	-4,114.61	2,086.86	1,999.93	86.93	24.005	
13,100.00	8,433.88	15,191.17	10,494.11	135.30	137.84	170.90	309.95	-4,214.59	2,086.86	1,998.23	88.64	23.544	
13,200.00	8,431.96	15,291.17	10,492.19	138.06	140.56	170.90	309.51	-4,314.57	2,086.87	1,996.52	90.34	23.099	
13,300.00	8,430.03	15,391.17	10,490.26	140.83	143.29	170.90	309.06	-4,414.55	2,086.87	1,994.81	92.05	22.670	
13,355.63	8,428.96	15,404.62	10,490.00	142.37	143.66	170.90	309.00	-4,428.00	2,087.29	1,994.64	92.65	22.529	



Phoenix Technology Services
Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MO Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design													Offset Site Error:	0.00 usft
Dr. Scrivner Federal 01-24S-28E RB - 228H - OH / Job 1514202 - Preliminary Plan 1													Offset Well Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM														
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance				Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
0.00	0.00	0.00	0.00	0.00	0.00	180.00	-60.00	0.00	60.00					
100.00	100.00	100.00	100.00	0.13	0.13	180.00	-60.00	0.00	60.00	59.74	0.26	230.865		
200.00	200.00	200.00	200.00	0.49	0.49	180.00	-60.00	0.00	60.00	59.02	0.98	61.423		
300.00	300.00	300.00	300.00	0.85	0.85	180.00	-60.00	0.00	60.00	58.31	1.69	35.424		
400.00	400.00	400.00	400.00	1.21	1.21	180.00	-60.00	0.00	60.00	57.59	2.41	24.889		
500.00	500.00	500.00	500.00	1.56	1.56	180.00	-60.00	0.00	60.00	56.87	3.13	19.184		
600.00	600.00	600.00	600.00	1.92	1.92	180.00	-60.00	0.00	60.00	56.16	3.84	15.606		
700.00	700.00	700.00	700.00	2.28	2.28	180.00	-60.00	0.00	60.00	55.44	4.56	13.153		
800.00	800.00	800.00	800.00	2.64	2.64	180.00	-60.00	0.00	60.00	54.72	5.28	11.367		
900.00	900.00	900.00	900.00	3.00	3.00	180.00	-60.00	0.00	60.00	54.00	6.00	10.008		
1,000.00	1,000.00	1,000.00	1,000.00	3.36	3.36	180.00	-60.00	0.00	60.00	53.29	6.71	8.939 CC		
1,100.00	1,099.99	1,099.99	1,099.99	3.71	3.70	90.30	-60.54	1.17	60.55	53.14	7.41	8.175 ES		
1,200.00	1,199.91	1,199.91	1,199.91	4.05	4.04	90.62	-62.16	4.69	62.19	54.10	8.09	7.691		
1,300.00	1,299.70	1,299.70	1,299.70	4.40	4.38	91.12	-64.80	10.45	64.88	56.10	8.78	7.392		
1,400.00	1,399.46	1,399.46	1,399.46	4.75	4.72	91.61	-67.72	16.79	67.83	58.35	9.48	7.158		
1,500.00	1,499.22	1,499.22	1,499.22	5.11	5.07	92.07	-70.63	23.12	70.78	60.60	10.18	6.953		
1,600.00	1,598.97	1,598.97	1,598.97	5.46	5.43	92.49	-73.54	29.46	73.74	62.85	10.89	6.772		
1,700.00	1,598.73	1,598.73	1,598.73	5.82	5.78	92.88	-76.45	35.79	76.70	65.10	11.60	6.611		
1,800.00	1,798.48	1,797.95	1,796.44	6.18	6.14	93.23	-79.37	42.13	79.67	67.35	12.32	6.467		
1,900.00	1,898.24	1,897.91	1,896.15	6.54	6.50	93.57	-82.28	48.46	82.64	69.60	13.04	6.338		
2,000.00	1,998.00	1,997.86	1,995.86	6.91	6.86	93.87	-85.19	54.80	85.61	71.85	13.76	6.222		
2,100.00	2,097.75	2,097.82	2,095.57	7.27	7.22	94.16	-88.10	61.13	88.58	74.10	14.48	6.116		
2,200.00	2,197.51	2,197.77	2,195.29	7.63	7.59	94.43	-91.02	67.47	91.55	76.35	15.21	6.020		
2,300.00	2,297.27	2,297.72	2,295.00	8.00	7.95	94.69	-93.93	73.80	94.53	78.60	15.93	5.933		
2,400.00	2,397.02	2,397.68	2,394.71	8.36	8.31	94.92	-96.84	80.14	97.51	80.85	16.66	5.852		
2,500.00	2,496.78	2,497.63	2,494.42	8.73	8.68	95.15	-99.75	86.47	100.49	83.10	17.39	5.778		
2,600.00	2,596.54	2,597.59	2,594.13	9.09	9.04	95.36	-102.67	92.81	103.47	85.35	18.12	5.710		
2,700.00	2,696.29	2,697.54	2,693.84	9.45	9.41	95.56	-105.58	99.14	106.45	87.60	18.85	5.647		
2,800.00	2,796.02	2,797.06	2,793.09	9.83	9.77	95.74	-108.60	105.71	109.57	89.98	19.58	5.595		
2,900.00	2,895.56	2,896.04	2,891.62	10.20	10.14	95.96	-112.52	114.25	113.64	93.32	20.32	5.562		
3,000.00	2,994.81	2,994.94	2,989.80	10.58	10.52	96.22	-117.51	125.10	118.82	97.74	21.07	5.638		
3,100.00	3,093.71	3,093.75	3,087.54	10.97	10.90	96.50	-123.55	138.23	126.10	103.26	21.84	5.728		
3,200.00	3,192.25	3,192.91	3,185.26	11.35	11.29	96.80	-130.57	153.51	132.37	109.75	22.62	5.852		
3,300.00	3,290.73	3,292.63	3,283.47	11.76	11.69	97.09	-137.80	169.24	139.82	116.40	23.41	5.972		
3,400.00	3,389.21	3,392.35	3,381.67	12.16	12.09	97.35	-145.04	184.98	147.26	123.05	24.21	6.082		
3,500.00	3,487.69	3,492.07	3,478.88	12.57	12.50	97.59	-152.27	200.71	164.71	129.70	25.01	6.185		
3,600.00	3,586.17	3,591.79	3,578.08	12.97	12.90	97.80	-159.50	216.45	162.16	136.34	25.82	6.281		
3,700.00	3,684.65	3,691.51	3,676.29	13.38	13.31	98.00	-166.74	232.18	169.62	142.99	26.63	6.370		
3,800.00	3,783.13	3,791.23	3,774.49	13.79	13.72	98.18	-173.97	247.92	177.07	149.63	27.44	6.463		
3,900.00	3,881.61	3,890.95	3,872.70	14.20	14.13	98.34	-181.20	263.65	184.63	156.27	28.26	6.530		
4,000.00	3,980.09	3,990.67	3,970.90	14.61	14.54	98.49	-188.44	279.39	191.99	162.91	29.08	6.603		
4,100.00	4,078.57	4,090.39	4,069.11	15.03	14.95	98.63	-195.67	295.12	199.45	169.55	29.90	6.671		
4,200.00	4,177.05	4,190.11	4,167.31	15.44	15.37	98.77	-202.90	310.86	206.91	176.18	30.72	6.735		
4,300.00	4,275.53	4,289.83	4,265.52	15.86	15.78	98.89	-210.14	326.59	214.37	182.82	31.55	6.795		
4,400.00	4,374.02	4,389.55	4,363.72	16.27	16.20	99.00	-217.37	342.33	221.83	189.45	32.38	6.852		
4,500.00	4,472.50	4,489.27	4,461.93	16.69	16.62	99.11	-224.60	358.06	229.29	196.09	33.21	6.905		
4,600.00	4,570.98	4,588.99	4,560.13	17.11	17.04	99.20	-231.83	373.80	236.76	202.72	34.04	6.956		
4,700.00	4,669.46	4,688.71	4,658.34	17.53	17.46	99.30	-239.07	389.53	244.22	209.35	34.87	7.003		
4,800.00	4,767.94	4,788.43	4,756.54	17.95	17.88	99.39	-246.30	405.27	251.69	215.98	35.71	7.049		
4,900.00	4,866.42	4,888.15	4,854.75	18.37	18.30	99.47	-253.53	421.00	259.15	222.61	36.54	7.092		
5,000.00	4,964.90	4,987.87	4,952.95	18.79	18.72	99.55	-260.77	436.74	266.62	229.24	37.38	7.133		
5,100.00	5,063.38	5,087.59	5,051.16	19.21	19.14	99.62	-268.00	452.47	274.09	235.87	38.22	7.171		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation



Phoenix Technology Services

Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design													Offset Site Error:
Dr. Scrivner Federal 01-24S-28E RB - 228H - OH / Job 1514202 - Preliminary Plan 1													0.00 usft
Survey Program: 0-PHX+MWD+HDGM													Offset Well Error:
													0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Between Centres (usft)	Between Ellipses (usft)					
5,200.00	5,161.86	5,187.31	5,149.36	19.64	19.56	99.69	-275.23	468.21	281.55	242.50	39.06	7.208	
5,300.00	5,260.34	5,287.03	5,247.57	20.06	19.99	99.76	-282.47	483.94	289.02	249.12	39.90	7.244	
5,400.00	5,358.82	5,386.75	5,345.77	20.48	20.41	99.82	-289.70	499.68	296.49	255.75	40.74	7.277	
5,500.00	5,457.48	5,486.48	5,443.98	20.90	20.84	99.78	-296.93	515.42	303.78	262.19	41.58	7.305	
5,600.00	5,556.53	5,586.31	5,542.30	21.31	21.26	99.27	-304.17	531.17	310.64	268.23	42.41	7.325	
5,700.00	5,655.90	5,688.32	5,643.00	21.70	21.69	98.56	-310.95	545.90	316.74	273.53	43.21	7.330	
5,800.00	5,755.53	5,790.54	5,744.32	22.07	22.10	97.84	-316.61	558.22	321.76	277.77	43.99	7.314	
5,900.00	5,855.35	5,892.96	5,846.16	22.43	22.50	97.13	-321.14	568.08	325.70	280.96	44.74	7.280	
6,000.00	5,955.29	5,995.56	5,948.44	22.78	22.88	96.41	-324.54	575.47	328.56	283.10	45.46	7.228	
6,100.00	6,055.29	6,098.32	6,051.05	23.11	23.24	-174.50	-326.79	580.36	330.33	286.72	46.61	7.574	
6,200.00	6,155.29	6,201.25	6,153.95	23.43	23.60	-174.93	-327.88	582.75	331.18	286.86	46.32	7.473	
6,300.00	6,255.29	6,302.60	6,255.29	23.75	23.92	-174.98	-328.00	583.00	331.27	286.28	44.99	7.362	
6,400.00	6,355.29	6,402.60	6,355.29	24.08	24.24	-174.98	-328.00	583.00	331.27	285.61	45.66	7.255	
6,500.00	6,455.29	6,502.60	6,455.29	24.40	24.55	-174.98	-328.00	583.00	331.27	284.94	46.33	7.150	
6,600.00	6,555.29	6,602.60	6,555.29	24.73	24.87	-174.98	-328.00	583.00	331.27	284.27	47.00	7.048	
6,700.00	6,655.29	6,702.60	6,655.29	25.06	25.19	-174.98	-328.00	583.00	331.27	283.60	47.67	6.949	
6,800.00	6,755.29	6,802.60	6,755.29	25.38	25.51	-174.98	-328.00	583.00	331.27	282.93	48.34	6.852	
6,900.00	6,855.29	6,902.60	6,855.29	25.71	25.83	-174.98	-328.00	583.00	331.27	282.25	49.02	6.758	
7,000.00	6,955.29	7,002.60	6,955.29	26.04	26.15	-174.98	-328.00	583.00	331.27	281.58	49.69	6.666	
7,100.00	7,055.29	7,102.60	7,055.29	26.37	26.47	-174.98	-328.00	583.00	331.27	280.90	50.37	6.577	
7,200.00	7,155.29	7,202.60	7,155.29	26.70	26.80	-174.98	-328.00	583.00	331.27	280.23	51.05	6.490	
7,300.00	7,255.29	7,302.60	7,255.29	27.04	27.12	-174.98	-328.00	583.00	331.27	279.55	51.72	6.405	
7,400.00	7,355.29	7,402.60	7,355.29	27.37	27.45	-174.98	-328.00	583.00	331.27	278.87	52.40	6.321	
7,500.00	7,455.29	7,502.60	7,455.29	27.70	27.77	-174.98	-328.00	583.00	331.27	278.19	53.08	6.240	
7,600.00	7,555.29	7,602.60	7,555.29	28.04	28.10	-174.98	-328.00	583.00	331.27	277.51	53.77	6.161	
7,700.00	7,655.29	7,702.60	7,655.29	28.37	28.43	-174.98	-328.00	583.00	331.27	276.82	54.45	6.084	
7,800.00	7,755.29	7,802.60	7,755.29	28.71	28.75	-174.98	-328.00	583.00	331.27	276.14	55.13	6.009	
7,900.00	7,855.29	7,902.60	7,855.29	29.04	29.08	-174.98	-328.00	583.00	331.27	275.46	55.82	5.935	
8,000.00	7,955.29	8,002.60	7,955.29	29.38	29.41	-84.74	-328.00	583.00	331.26	272.64	58.62	5.651	
8,100.00	8,054.55	8,101.86	8,054.55	29.67	29.74	-86.71	-328.00	583.00	330.43	271.22	59.21	5.581	
8,174.52	8,126.46	8,173.77	8,126.46	29.86	29.98	-90.00	-328.00	583.00	329.86	270.28	59.58	5.536	
8,200.00	8,150.40	8,197.70	8,150.40	29.92	30.06	-91.41	-328.00	583.00	329.98	270.29	59.69	5.528 SF	
8,300.00	8,239.91	8,287.22	8,239.91	30.17	30.36	-97.82	-328.00	583.00	334.10	274.21	59.88	5.579	
8,400.00	8,320.37	8,367.68	8,320.37	30.42	30.62	-104.33	-328.00	583.00	348.42	288.88	59.55	5.851	
8,500.00	8,389.33	8,436.64	8,389.33	30.74	30.85	-109.26	-328.00	583.00	377.93	319.15	58.77	6.430	
8,600.00	8,444.71	8,492.01	8,444.71	31.17	31.04	-111.26	-328.00	583.00	424.73	366.37	58.36	7.277	
8,700.00	8,484.80	8,532.11	8,484.80	31.77	31.17	-109.21	-328.00	583.00	487.56	428.16	59.38	8.209	
8,800.00	8,508.41	8,555.72	8,508.41	32.56	31.25	-101.77	-328.00	583.00	562.86	500.68	62.18	9.052	
8,900.00	8,514.81	8,562.11	8,514.81	33.53	31.27	-88.14	-328.00	583.00	645.26	581.72	64.54	10.013	
9,000.00	8,512.88	8,560.19	8,512.88	34.68	31.26	-87.81	-328.00	583.00	734.02	668.33	65.68	11.175	
9,100.00	8,510.95	8,558.26	8,510.95	36.02	31.26	-87.47	-328.00	583.00	824.56	757.55	67.01	12.305	
9,200.00	8,509.03	8,556.33	8,509.03	37.53	31.25	-87.14	-328.00	583.00	917.06	848.57	68.50	13.388	
9,300.00	8,507.10	8,554.41	8,507.10	39.19	31.24	-86.80	-328.00	583.00	1,010.99	940.86	70.13	14.416	
9,400.00	8,505.17	8,552.48	8,505.17	40.98	31.24	-86.47	-328.00	583.00	1,105.99	1,034.09	71.89	15.384	
9,500.00	8,503.25	8,550.55	8,503.25	42.89	31.23	-86.14	-328.00	583.00	1,201.79	1,128.02	73.76	16.293	
9,600.00	8,501.32	8,548.63	8,501.32	44.89	31.23	-85.81	-328.00	583.00	1,298.22	1,222.49	75.73	17.143	
9,700.00	8,499.39	8,546.70	8,499.39	46.96	31.22	-85.47	-328.00	583.00	1,395.15	1,317.37	77.77	17.938	
9,800.00	8,497.47	8,544.77	8,497.47	49.13	31.21	-85.14	-328.00	583.00	1,492.48	1,412.59	79.89	18.681	
9,900.00	8,495.54	8,542.85	8,495.54	51.35	31.21	-84.81	-328.00	583.00	1,590.15	1,508.07	82.07	19.375	
10,000.00	8,493.61	8,540.92	8,493.61	53.64	31.20	-84.48	-328.00	583.00	1,688.08	1,603.77	84.30	20.023	
10,100.00	8,491.69	8,538.99	8,491.69	55.97	31.19	-84.15	-328.00	583.00	1,786.24	1,699.66	86.58	20.630	
10,200.00	8,489.76	8,537.07	8,489.76	58.36	31.19	-83.81	-328.00	583.00	1,884.59	1,795.69	88.90	21.199	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Phoenix Technology Services
Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design													Offset Site Error: 0.00 usft	
Dr. Scrivner Federal 01-24S-28E RB - 228H - OH / Job 1514202 - Preliminary Plan 1													Offset Well Error: 0.00 usft	
Survey Program: 0-PHX+MWD+HDGM														
Reference		Offset		Semi Major Axis			Distance							
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N-S (usft)	+E-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
10,300.00	8,487.83	8,535.14	8,487.83	60.77	31.18	-83.48	-328.00	583.00	1,983.11	1,891.86	91.25	21.732		
10,400.00	8,485.91	8,533.21	8,485.91	63.23	31.17	-83.15	-328.00	583.00	2,081.76	1,988.13	93.63	22.234		
10,500.00	8,483.98	12,557.70	10,543.95	65.71	69.31	-170.90	-338.05	-1,611.91	2,086.59	2,040.19	46.40	44.968		
10,600.00	8,482.05	12,657.70	10,542.03	68.23	71.70	-170.90	-338.51	-1,711.89	2,086.60	2,038.71	47.89	43.574		
10,700.00	8,480.13	12,757.70	10,540.11	70.77	74.12	-170.90	-338.97	-1,811.87	2,086.61	2,037.22	49.39	42.247		
10,800.00	8,478.20	12,857.70	10,538.19	73.32	76.57	-170.90	-339.43	-1,911.85	2,086.62	2,035.71	50.91	40.984		
10,900.00	8,476.27	12,957.70	10,536.28	75.90	79.04	-170.90	-339.89	-2,011.83	2,086.63	2,034.18	52.45	39.781		
11,000.00	8,474.35	13,057.70	10,534.36	78.50	81.54	-170.90	-340.35	-2,111.81	2,086.64	2,032.63	54.01	38.635		
11,100.00	8,472.42	13,157.70	10,532.44	81.11	84.06	-170.90	-340.81	-2,211.79	2,086.65	2,031.07	55.58	37.545		
11,200.00	8,470.49	13,257.70	10,530.53	83.74	86.60	-170.90	-341.27	-2,311.77	2,086.66	2,029.50	57.16	36.505		
11,300.00	8,468.57	13,357.70	10,528.61	86.38	89.15	-170.90	-341.73	-2,411.75	2,086.67	2,027.92	58.75	35.515		
11,400.00	8,466.64	13,457.70	10,526.69	89.04	91.73	-170.90	-342.19	-2,511.73	2,086.68	2,026.32	60.36	34.570		
11,500.00	8,464.71	13,557.70	10,524.77	91.70	94.32	-170.90	-342.65	-2,611.71	2,086.69	2,024.71	61.98	33.669		
11,600.00	8,462.79	13,657.70	10,522.86	94.38	96.92	-170.90	-343.11	-2,711.69	2,086.70	2,023.10	63.60	32.809		
11,700.00	8,460.86	13,757.70	10,520.94	97.06	99.53	-170.90	-343.57	-2,811.67	2,086.71	2,021.48	65.24	31.987		
11,800.00	8,458.93	13,857.70	10,519.02	99.75	102.16	-170.90	-344.03	-2,911.65	2,086.72	2,019.84	66.88	31.202		
11,900.00	8,457.00	13,957.70	10,517.11	102.45	104.79	-170.90	-344.49	-3,011.64	2,086.73	2,018.20	68.53	30.451		
12,000.00	8,455.08	14,057.70	10,515.19	105.16	107.44	-170.90	-344.95	-3,111.62	2,086.74	2,016.56	70.18	29.732		
12,100.00	8,453.15	14,157.70	10,513.27	107.88	110.10	-170.90	-345.41	-3,211.60	2,086.75	2,014.90	71.85	29.044		
12,200.00	8,451.22	14,257.70	10,511.36	110.60	112.76	-170.90	-345.87	-3,311.58	2,086.76	2,013.24	73.52	28.385		
12,300.00	8,449.30	14,357.70	10,509.44	113.32	115.44	-170.90	-346.32	-3,411.56	2,086.77	2,011.58	75.19	27.753		
12,400.00	8,447.37	14,457.70	10,507.52	116.05	118.12	-170.90	-346.78	-3,511.54	2,086.78	2,009.91	76.87	27.146		
12,500.00	8,445.44	14,557.70	10,505.60	118.79	120.81	-170.90	-347.24	-3,611.52	2,086.79	2,008.23	78.56	26.564		
12,600.00	8,443.52	14,657.70	10,503.69	121.53	123.50	-170.90	-347.70	-3,711.50	2,086.80	2,006.55	80.25	26.004		
12,700.00	8,441.59	14,757.70	10,501.77	124.28	126.20	-170.90	-348.16	-3,811.48	2,086.81	2,004.87	81.94	25.467		
12,800.00	8,439.66	14,857.70	10,499.85	127.03	128.91	-170.90	-348.62	-3,911.46	2,086.82	2,003.18	83.64	24.950		
12,900.00	8,437.74	14,957.70	10,497.94	129.78	131.62	-170.90	-349.08	-4,011.44	2,086.83	2,001.49	85.34	24.452		
13,000.00	8,435.81	15,057.70	10,496.02	132.54	134.33	-170.90	-349.54	-4,111.42	2,086.84	1,999.79	87.05	23.973		
13,100.00	8,433.88	15,157.70	10,494.10	135.30	137.06	-170.90	-350.00	-4,211.40	2,086.85	1,998.09	88.76	23.511		
13,200.00	8,431.96	15,257.70	10,492.19	138.06	139.78	-170.90	-350.46	-4,311.38	2,086.86	1,996.39	90.47	23.066		
13,300.00	8,430.03	15,357.70	10,490.27	140.83	142.51	-170.90	-350.92	-4,411.36	2,086.87	1,994.68	92.19	22.637		
13,355.63	8,428.96	15,375.34	10,489.93	142.37	142.99	-170.90	-351.00	-4,429.00	2,087.22	1,994.40	92.82	22.486		



Phoenix Technology Services
Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design Phillips Federal - 1 - OH - Surveys													Offset Site Error: 0.00 usft
Survey Program: 125-MWD													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
0.00	0.00	0.00	48.50	0.00	0.00	-90.05	-2.40	-2,661.70	2,662.14				
100.00	100.00	51.51	100.01	0.13	0.06	-90.05	-2.31	-2,661.70	2,661.70	2,661.51	0.19	N/A	
200.00	200.00	151.52	200.02	0.49	0.20	-90.03	-1.61	-2,661.70	2,661.70	2,661.01	0.69	3,862.525	
300.00	300.00	251.52	300.01	0.85	0.43	-90.01	-0.50	-2,661.70	2,661.70	2,660.43	1.27	2,091.487	
338.23	338.23	289.74	339.23	0.98	0.51	-90.00	0.00	-2,661.70	2,661.70	2,660.20	1.50	1,779.559	
400.00	400.00	351.50	399.99	1.21	0.65	-89.98	0.91	-2,661.70	2,661.70	2,659.84	1.86	1,433.994	
500.00	500.00	451.49	499.96	1.56	0.87	-89.94	2.59	-2,661.70	2,661.70	2,659.27	2.43	1,095.545	
600.00	600.00	551.48	599.94	1.92	1.07	-89.91	4.19	-2,661.70	2,661.70	2,658.71	2.99	890.388	
700.00	700.00	651.48	699.92	2.28	1.27	-89.88	5.63	-2,661.70	2,661.71	2,658.16	3.55	749.947	
800.00	800.00	751.46	799.89	2.64	1.48	-89.85	7.01	-2,661.70	2,661.71	2,657.60	4.11	647.239	
900.00	900.00	851.42	899.85	3.00	1.69	-89.81	8.65	-2,661.70	2,661.71	2,657.04	4.68	569.068	
1,000.00	1,000.00	951.38	999.78	3.36	1.90	-89.77	10.58	-2,661.70	2,661.72	2,656.48	5.24	507.748	
1,100.00	1,099.99	1,051.35	1,099.73	3.71	2.10	-179.54	12.69	-2,661.70	2,663.04	2,657.23	5.81	458.316	
1,200.00	1,199.91	1,151.28	1,199.64	4.05	2.31	-179.50	14.63	-2,661.70	2,666.97	2,660.61	6.36	419.234	
1,300.00	1,299.70	1,251.07	1,299.42	4.40	2.52	-179.46	16.39	-2,661.70	2,673.38	2,666.47	6.91	386.705	
1,400.00	1,399.46	1,350.86	1,399.19	4.75	2.73	-179.42	18.03	-2,661.70	2,680.37	2,672.90	7.47	358.843	
1,500.00	1,499.22	1,450.62	1,498.95	5.11	2.94	-179.40	19.40	-2,661.70	2,687.35	2,679.32	8.03	334.757	
1,600.00	1,598.97	1,550.34	1,598.65	5.46	3.15	-179.37	20.86	-2,661.70	2,694.34	2,685.75	8.59	313.742	
1,700.00	1,698.73	1,650.05	1,698.35	5.82	3.36	-179.33	22.49	-2,661.70	2,701.32	2,692.18	9.15	295.256	
1,800.00	1,798.48	1,749.84	1,798.13	6.18	3.57	-179.30	24.13	-2,661.70	2,708.31	2,698.60	9.71	278.867	
1,900.00	1,898.24	1,849.49	1,897.75	6.54	3.78	-179.27	25.61	-2,661.70	2,715.30	2,705.03	10.28	264.212	
2,000.00	1,998.00	1,948.84	1,997.08	6.91	4.00	-179.22	28.17	-2,661.70	2,722.30	2,711.46	10.84	251.029	
2,100.00	2,097.75	2,048.11	2,096.27	7.27	4.21	-179.14	32.09	-2,661.70	2,729.32	2,717.91	11.41	239.148	
2,200.00	2,197.51	2,147.54	2,195.58	7.63	4.43	-179.03	37.16	-2,661.70	2,736.36	2,724.37	11.99	228.256	
2,300.00	2,297.27	2,247.16	2,295.05	8.00	4.65	-178.93	42.38	-2,661.70	2,743.41	2,730.84	12.57	218.260	
2,400.00	2,397.02	2,346.24	2,393.97	8.36	4.88	-178.81	48.13	-2,661.70	2,750.48	2,737.32	13.15	209.087	
2,500.00	2,496.78	2,445.29	2,492.78	8.73	5.11	-178.67	54.95	-2,661.70	2,757.58	2,743.84	13.74	200.659	
2,600.00	2,596.54	2,545.26	2,592.50	9.09	5.34	-178.53	61.98	-2,661.70	2,764.70	2,750.37	14.33	192.956	
2,700.00	2,696.29	2,646.28	2,693.36	9.45	5.56	-178.41	67.69	-2,661.70	2,771.81	2,756.90	14.91	185.938	
2,800.00	2,796.02	2,746.25	2,793.25	9.83	5.78	-178.33	71.81	-2,661.70	2,779.21	2,763.74	15.47	179.673	
2,900.00	2,895.56	2,846.22	2,893.15	10.20	5.99	-178.25	75.44	-2,661.70	2,788.88	2,772.87	16.01	174.165	
3,000.00	2,994.81	2,945.89	2,992.78	10.58	6.20	-178.21	78.15	-2,661.70	2,801.14	2,784.59	16.55	169.278	
3,100.00	3,093.71	3,044.80	3,091.66	10.97	6.41	-178.16	80.73	-2,661.70	2,815.99	2,798.91	17.07	164.962	
3,200.00	3,192.25	3,143.43	3,190.26	11.36	6.62	-178.11	83.18	-2,661.70	2,833.09	2,815.48	17.61	160.853	
3,300.00	3,290.73	3,242.00	3,288.80	11.75	6.83	-178.08	85.48	-2,661.70	2,850.51	2,832.33	18.18	156.751	
3,400.00	3,389.21	3,340.56	3,387.34	12.15	7.04	-178.05	87.65	-2,661.70	2,867.83	2,849.18	18.75	152.900	
3,500.00	3,487.69	3,439.08	3,485.84	12.57	7.25	-178.02	89.73	-2,661.70	2,885.35	2,866.03	19.33	149.281	
3,600.00	3,586.17	3,537.61	3,584.35	12.97	7.45	-177.99	91.74	-2,661.70	2,902.77	2,882.87	19.90	145.865	
3,700.00	3,684.65	3,636.14	3,682.86	13.38	7.66	-177.96	93.68	-2,661.70	2,920.19	2,899.72	20.47	142.635	
3,800.00	3,783.13	3,734.68	3,781.38	13.79	7.87	-177.94	95.54	-2,661.70	2,937.60	2,916.56	21.05	139.577	
3,900.00	3,881.61	3,833.21	3,879.90	14.20	8.08	-177.91	97.33	-2,661.70	2,955.02	2,933.40	21.62	136.677	
4,000.00	3,980.09	3,931.71	3,978.38	14.61	8.28	-177.89	99.06	-2,661.70	2,972.43	2,950.23	22.19	133.923	
4,100.00	4,078.57	4,030.18	4,076.83	15.03	8.49	-177.87	100.78	-2,661.70	2,989.84	2,967.07	22.77	131.305	
4,200.00	4,177.05	4,128.65	4,175.28	15.44	8.70	-177.85	102.50	-2,661.70	3,007.25	2,983.90	23.35	128.813	
4,300.00	4,275.53	4,227.11	4,273.74	15.86	8.91	-177.83	104.21	-2,661.70	3,024.66	3,000.74	23.92	126.439	
4,400.00	4,374.02	4,325.58	4,372.19	16.27	9.12	-177.81	105.93	-2,661.70	3,042.07	3,017.57	24.50	124.174	
4,500.00	4,472.50	4,424.05	4,470.64	16.69	9.32	-177.79	107.65	-2,661.70	3,059.49	3,034.41	25.08	122.009	
4,600.00	4,570.98	4,522.51	4,569.09	17.11	9.53	-177.77	109.37	-2,661.70	3,076.90	3,051.25	25.65	119.941	
4,700.00	4,669.46	4,620.98	4,667.54	17.53	9.74	-177.75	111.09	-2,661.70	3,094.31	3,068.08	26.23	117.962	
4,800.00	4,767.94	4,719.45	4,765.99	17.95	9.95	-177.73	112.81	-2,661.70	3,111.73	3,084.92	26.81	116.067	
4,900.00	4,866.42	4,818.01	4,864.55	18.37	10.16	-177.71	114.50	-2,661.70	3,129.14	3,101.75	27.39	114.253	
5,000.00	4,964.90	4,916.65	4,963.17	18.79	10.36	-177.69	116.06	-2,661.70	3,146.55	3,118.58	27.97	112.514	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Phoenix Technology Services

Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design													Offset Site Error:	0.00 usft
Survey Program: 125-MWD													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance				Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
5,100.00	5,063.38	5,015.28	5,061.79	19.21	10.57	-177.68	117.48	-2,661.70	3,163.95	3,135.41	28.54	110.844		
5,200.00	5,161.86	5,113.90	5,160.40	19.64	10.78	-177.67	118.77	-2,661.70	3,181.35	3,152.23	29.12	109.243		
5,300.00	5,260.34	5,212.51	5,259.01	20.06	10.98	-177.66	119.94	-2,661.70	3,198.75	3,169.05	29.70	107.706		
5,400.00	5,358.82	5,311.13	5,357.62	20.48	11.19	-177.65	120.99	-2,661.70	3,216.14	3,185.85	30.28	106.226		
5,500.00	5,457.48	5,409.92	5,456.40	20.90	11.40	-177.66	121.94	-2,661.70	3,232.48	3,201.56	30.92	104.546		
5,600.00	5,556.53	5,509.09	5,555.57	21.31	11.60	-177.66	122.77	-2,661.70	3,248.24	3,214.69	31.55	102.891		
5,700.00	5,655.90	5,608.59	5,655.07	21.70	11.81	-177.66	123.50	-2,661.70	3,257.41	3,225.25	32.16	101.289		
5,800.00	5,755.53	5,708.35	5,754.83	22.07	12.02	-177.66	124.13	-2,661.70	3,265.97	3,233.22	32.75	99.739		
5,900.00	5,855.35	5,808.30	5,854.77	22.43	12.23	-177.66	124.65	-2,661.70	3,271.91	3,238.61	33.31	98.235		
6,000.00	5,955.29	5,908.22	5,954.70	22.78	12.44	-177.66	125.11	-2,661.70	3,275.24	3,241.40	33.84	96.780		
6,100.00	6,055.29	6,008.13	6,054.60	23.11	12.65	-87.84	125.63	-2,661.70	3,276.03	3,240.44	35.59	92.040		
6,200.00	6,155.29	6,108.04	6,154.51	23.43	12.85	-87.83	126.22	-2,661.70	3,276.06	3,239.93	36.13	90.687		
6,300.00	6,255.29	6,207.95	6,254.42	23.75	13.06	-87.82	126.88	-2,661.70	3,276.08	3,239.42	36.66	89.370		
6,400.00	6,355.29	6,307.86	6,354.33	24.08	13.27	-87.80	127.61	-2,661.70	3,276.11	3,238.92	37.19	88.089		
6,500.00	6,455.29	6,407.77	6,454.23	24.40	13.48	-87.79	128.41	-2,661.70	3,276.14	3,238.41	37.73	86.842		
6,600.00	6,555.29	6,507.45	6,553.91	24.73	13.69	-87.77	129.32	-2,661.70	3,276.18	3,237.92	38.26	85.629		
6,700.00	6,655.29	6,606.91	6,653.36	25.06	13.90	-87.75	130.60	-2,661.70	3,276.23	3,237.43	38.79	84.451		
6,800.00	6,755.29	6,706.36	6,752.79	25.38	14.10	-87.72	132.30	-2,661.70	3,276.29	3,236.96	39.33	83.303		
6,900.00	6,855.29	6,805.78	6,852.20	25.71	14.31	-87.68	134.42	-2,661.70	3,276.38	3,236.51	39.87	82.184		
7,000.00	6,955.29	6,905.37	6,951.76	26.04	14.52	-87.64	136.93	-2,661.70	3,276.48	3,236.08	40.40	81.092		
7,100.00	7,055.29	7,005.34	7,051.69	26.37	14.74	-87.59	139.55	-2,661.70	3,276.59	3,235.64	40.95	80.023		
7,200.00	7,155.29	7,105.31	7,151.62	26.70	14.95	-87.55	142.16	-2,661.70	3,276.70	3,235.21	41.49	78.981		
7,300.00	7,255.29	7,205.16	7,251.44	27.04	15.17	-87.50	144.79	-2,661.70	3,276.81	3,234.79	42.03	77.964		
7,400.00	7,355.29	7,304.78	7,351.02	27.37	15.38	-87.45	147.59	-2,661.70	3,276.94	3,234.37	42.57	76.972		
7,500.00	7,455.29	7,404.76	7,450.95	27.70	15.60	-87.40	150.58	-2,661.70	3,277.07	3,233.96	43.12	76.004		
7,600.00	7,555.29	7,505.14	7,551.30	28.04	15.81	-87.35	153.37	-2,661.70	3,277.20	3,233.54	43.66	75.058		
7,700.00	7,655.29	7,605.54	7,651.67	28.37	16.03	-87.31	155.88	-2,661.70	3,277.32	3,233.11	44.21	74.135		
7,800.00	7,755.29	7,705.94	7,752.04	28.71	16.24	-87.27	158.10	-2,661.70	3,277.42	3,232.67	44.75	73.233		
7,900.00	7,855.29	7,805.31	7,852.39	29.04	16.45	-87.24	160.06	-2,661.70	3,277.52	3,232.22	45.30	72.354		
8,000.00	7,955.29	7,906.70	7,952.76	29.38	16.66	3.06	161.78	-2,661.70	3,277.44	3,232.63	44.81	73.136		
8,100.00	8,054.55	8,006.35	8,052.41	29.67	16.87	3.15	163.23	-2,661.70	3,266.52	3,222.30	44.22	73.871		
8,200.00	8,150.40	8,102.22	8,148.27	29.92	17.07	3.37	164.48	-2,661.70	3,238.55	3,196.14	42.41	76.371		
8,300.00	8,239.91	8,191.72	8,237.76	30.17	17.26	3.75	165.66	-2,661.70	3,194.38	3,154.92	39.46	80.957		
8,400.00	8,320.37	8,272.17	8,318.21	30.42	17.43	4.37	166.71	-2,661.70	3,135.36	3,099.82	35.54	88.217		
8,500.00	8,389.33	8,341.13	8,387.15	30.74	17.58	5.39	167.61	-2,661.70	3,063.29	3,032.34	30.95	98.973		
8,600.00	8,444.71	8,396.49	8,442.51	31.17	17.69	7.23	168.34	-2,661.70	2,980.36	2,954.12	26.25	113.553		
8,700.00	8,484.80	8,420.00	8,466.02	31.77	17.74	10.92	168.64	-2,661.70	2,889.14	2,866.42	22.72	127.162		
8,800.00	8,508.41	8,420.00	8,466.02	32.56	17.74	21.46	168.64	-2,661.70	2,792.56	2,767.57	24.99	111.758		
8,900.00	8,514.81	8,420.00	8,466.02	33.53	17.74	90.94	168.64	-2,661.70	2,693.23	2,642.18	51.05	52.754		
9,000.00	8,512.88	8,420.00	8,466.02	34.68	17.74	90.94	168.64	-2,661.70	2,593.47	2,541.26	52.21	49.675		
9,100.00	8,510.95	8,420.00	8,466.02	36.02	17.74	90.94	168.64	-2,661.70	2,493.72	2,440.17	53.55	46.567		
9,200.00	8,509.03	8,420.00	8,466.02	37.53	17.74	90.94	168.64	-2,661.70	2,394.00	2,338.94	55.06	43.479		
9,300.00	8,507.10	8,420.00	8,466.02	39.19	17.74	90.94	168.64	-2,661.70	2,294.30	2,237.58	56.72	40.451		
9,400.00	8,505.17	8,420.00	8,466.02	40.98	17.74	90.94	168.64	-2,661.70	2,194.63	2,136.12	58.50	37.512		
9,500.00	8,503.25	8,420.00	8,466.02	42.88	17.74	90.94	168.64	-2,661.70	2,094.99	2,034.58	60.41	34.682		
9,600.00	8,501.32	8,420.00	8,466.02	44.88	17.74	90.94	168.64	-2,661.70	1,995.38	1,932.98	62.40	31.975		
9,700.00	8,499.39	8,420.00	8,466.02	46.96	17.74	90.94	168.64	-2,661.70	1,895.82	1,831.33	64.49	29.397		
9,800.00	8,497.47	8,420.00	8,466.02	49.13	17.74	90.94	168.64	-2,661.70	1,796.30	1,729.65	66.65	26.951		
9,900.00	8,495.54	8,420.00	8,466.02	51.35	17.74	90.94	168.64	-2,661.70	1,696.85	1,627.97	68.88	24.635		
10,000.00	8,493.61	8,420.00	8,466.02	53.64	17.74	90.94	168.64	-2,661.70	1,597.46	1,526.29	71.16	22.448		
10,100.00	8,491.69	8,420.00	8,466.02	55.97	17.74	90.94	168.64	-2,661.70	1,498.15	1,424.65	73.50	20.383		
10,200.00	8,489.76	8,420.00	8,466.02	58.36	17.74	90.94	168.64	-2,661.70	1,398.94	1,323.06	75.88	18.436		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Phoenix Technology Services
Anticollision Report



Company:	Matador Resources	Local Co-ordinate Reference:	Well 124H
Project:	Eddy County, NM (NAD27 NME)	TVD Reference:	RKB @ 3011.50usft (Patterson 297)
Reference Site:	Dr. Scrivner Federal 01-24S-28E RB	MD Reference:	RKB @ 3011.50usft (Patterson 297)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	124H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH / Job 1514200	Database:	Compass 5000 GCR
Reference Design:	Preliminary Plan 1	Offset TVD Reference:	Reference Datum

Offset Design Phillips Federal - 1 - OH - Surveys														Offset Site Error:	0.00 usft
Survey Program: 125-MWD														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
10,300.00	8,487.83	8,420.00	8,466.02	60.77	17.74	90.94	168.64	-2,661.70	1,299.85	1,221.55	78.30	16.601			
10,400.00	8,485.91	8,420.00	8,466.02	63.23	17.74	90.94	168.64	-2,661.70	1,200.91	1,120.15	80.75	14.871			
10,500.00	8,483.98	8,420.00	8,466.02	65.71	17.74	90.94	168.64	-2,661.70	1,102.17	1,018.93	83.24	13.241			
10,600.00	8,482.05	8,420.00	8,466.02	68.23	17.74	90.94	168.64	-2,661.70	1,003.67	917.92	85.75	11.704			
10,700.00	8,480.13	8,420.00	8,466.02	70.77	17.74	90.94	168.64	-2,661.70	905.50	817.21	88.29	10.256			
10,800.00	8,478.20	8,420.00	8,466.02	73.32	17.74	90.94	168.64	-2,661.70	807.78	716.93	90.85	8.892			
10,900.00	8,476.27	8,420.00	8,466.02	75.80	17.74	90.94	168.64	-2,661.70	710.69	617.27	93.43	7.607			
11,000.00	8,474.35	8,420.00	8,466.02	78.50	17.74	90.94	168.64	-2,661.70	614.55	518.52	96.02	6.400			
11,100.00	8,472.42	8,420.00	8,466.02	81.11	17.74	90.94	168.64	-2,661.70	519.85	421.22	98.64	5.270			
11,200.00	8,470.49	8,420.00	8,466.02	83.74	17.74	90.94	168.64	-2,661.70	427.58	326.32	101.26	4.222			
11,300.00	8,468.57	8,420.00	8,466.02	86.38	17.74	90.94	168.64	-2,661.70	339.72	235.81	103.90	3.269			
11,400.00	8,466.64	8,418.25	8,464.27	89.04	17.74	90.39	168.62	-2,661.70	260.74	154.17	106.57	2.447			
11,500.00	8,464.71	8,416.32	8,462.34	91.70	17.73	89.78	168.60	-2,661.70	201.38	92.14	109.24	1.843			
11,587.20	8,463.03	8,414.64	8,460.66	94.03	17.73	89.25	168.57	-2,661.70	181.52	69.96	111.56	1.627 CC, ES			
11,600.00	8,462.79	8,414.39	8,460.41	94.38	17.73	89.17	168.57	-2,661.70	181.97	70.07	111.90	1.626 SF			
11,700.00	8,460.86	8,412.46	8,458.48	97.06	17.73	88.66	168.55	-2,661.70	213.70	99.14	114.56	1.865			
11,800.00	8,458.93	8,410.52	8,456.54	99.75	17.72	87.95	168.52	-2,661.70	279.67	162.45	117.22	2.386			
11,900.00	8,457.00	8,408.59	8,454.61	102.45	17.72	87.34	168.49	-2,661.70	361.60	241.73	119.88	3.016			
12,000.00	8,455.08	8,406.66	8,452.68	105.16	17.71	86.73	168.47	-2,661.70	450.87	328.35	122.52	3.680			
12,100.00	8,453.15	8,404.73	8,450.75	107.88	17.71	86.13	168.44	-2,661.70	543.89	418.73	125.16	4.346			
12,200.00	8,451.22	8,402.79	8,448.81	110.60	17.71	85.52	168.42	-2,661.70	639.01	511.22	127.78	5.001			
12,300.00	8,449.30	8,400.86	8,446.88	113.32	17.70	84.91	168.39	-2,661.70	735.42	605.02	130.40	5.640			
12,400.00	8,447.37	8,398.93	8,444.95	116.05	17.70	84.31	168.37	-2,661.70	832.67	699.67	133.00	6.261			
12,500.00	8,445.44	8,397.00	8,443.02	118.79	17.69	83.70	168.34	-2,661.70	930.50	794.91	135.59	6.863			
12,600.00	8,443.52	8,395.06	8,441.08	121.53	17.69	83.10	168.32	-2,661.70	1,028.75	890.58	138.16	7.446			
12,700.00	8,441.59	8,393.13	8,439.15	124.28	17.69	82.49	168.29	-2,661.70	1,127.30	986.57	140.72	8.011			
12,800.00	8,439.66	8,391.20	8,437.22	127.03	17.68	81.89	168.27	-2,661.70	1,226.08	1,082.81	143.27	8.558			
12,900.00	8,437.74	8,389.26	8,435.29	129.78	17.68	81.29	168.24	-2,661.70	1,325.04	1,179.25	145.79	9.089			
13,000.00	8,435.81	8,387.33	8,433.35	132.54	17.67	80.70	168.22	-2,661.70	1,424.15	1,275.85	148.30	9.603			
13,100.00	8,433.88	8,385.40	8,431.42	135.30	17.67	80.10	168.19	-2,661.70	1,523.37	1,372.58	150.79	10.103			
13,200.00	8,431.96	8,383.47	8,429.49	138.06	17.66	79.51	168.17	-2,661.70	1,622.68	1,469.42	153.26	10.588			
13,300.00	8,430.03	8,381.53	8,427.56	140.83	17.66	78.92	168.14	-2,661.70	1,722.07	1,566.37	155.70	11.060			
13,355.63	8,428.96	8,380.45	8,426.48	142.37	17.66	78.59	168.13	-2,661.70	1,777.39	1,620.34	157.06	11.317			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

July 24 2015



Size: 5.500 in.
Wall: 0.361 in.
Weight: 20.00 lbs/ft
Grade: P110
Wall Thickness: 87.5 %





July 24 2015

Connection: TenarisXPTM BTC
 Casing/Tubing: CAS
 Coupling Option: REGULAR
 Size: 5.500 in.
 Wall: 0.361 in.
 Weight: 20.00 lbs/ft
 Grade: P110
 Min. Wall Thickness: 87.5 %

PIPE BODY DATA		
GEOMETRY		
Nominal OD	5.500 in.	Nominal Weight
Nominal ID	4.778 in.	Wall Thickness
Plain End Weight	19.83 lbs/ft	Standard Drift
		Diameter
PERFORMANCE		
Body Yield	641 x 1000 lbs	Internal Yield
Strength	12630 psi	SMYS
Collapse	11100 psi	


TENARISXPTM BTC CONNECTION DATA		
GEOMETRY		
Connection OD	6.100 in.	Coupling Length
Critical Section	5.828 sq. in.	Threads per in.
Area	5.828 sq. in.	Make-Up Loss
PERFORMANCE		
Tension Efficiency	100 %	Joint Yield Strength
Structural	100 %	Structural
Compression	100 %	Compression
Efficiency	100 %	Strength
External Pressure	11100 psi	Capacity
ESTIMATED MAKE-UP TORQUES ⁽²⁾		
Minimum	11270 ft-lbs	Optimum
Maximum	13770 ft-lbs	
OPERATIONAL LIMIT TORQUES		
Operating Torque	21500 ft-lbs	Yield Torque
		23900 ft-lbs

BLANKING DIMENSIONS	
Blanking Dimensions	


(1) Internal Pressure Capacity related to structural resistance only. Internal pressure leak resistance as per section 10.3 API 5C3 / ISO 10400 - 2007.

(2) Structural rating, pure bending to yield (i.e. no other loads applied)

(3) Torque values calculated for API Modified thread compounds with Friction Factor=1. For other thread compounds please contact us at licensees@oilfield.tenaris.com. Torque values may be further reviewed. For additional information, please contact us at contact-tenarishydril@tenaris.com



**PHOENIX
TECHNOLOGY SERVICES**








Azimuth to Grid North
 True North: -0.18°
 Magnetic North: 7.22°
 Magnetic Field
 Strength: 48280.2 nT
 Dip Angle: 60.10°
 Date: 12/14/2015
 Model: HDGM

	+N/-S	+E/-W	Northing	Easting	Ground Level	2004.00
	0.00	0.00	45453.00	50450.00		

DESIGN TARGET DETAILS

Name	TVD	+N+S	+E+W	Northing
Philips Federal 1	0 00	-2 40	-2661 70	451650 60
BHIL Dr. Scriener 124H	8428 96	-21 00	-4129 00	451632 00
LPP Dr. Scriener 124H	8428 96	-21 00	-4339 00	451632 00
LPP Dr. Scriener 124H	8514 00	1 00	337 00	451654 00

Sec	MD	Inc	Azi	TVD	+N/S	-E/W	Dipg	Tfacc	VScal
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2	1200.00	0.00	0.00	1020.00	0.00	0.00	0.00	0.00	0.00
3	1265.00	0.00	88.81	128.45	0.03	3.50	1.50	68.81	-9.30
4	1300.00	0.00	88.81	117.17	0.03	17.78	1.50	68.81	-9.30
5	3120.00	10.00	88.81	117.17	0.03	181.55	1.50	0.00	181.55
6	5410.00	10.00	88.81	5368.68	1.81	553.96	0.00	0.00	553.97
7	6786.71	0.00	0.00	6032.00	0.00	612.00	1.50	186.00	-812.00
8	7088.71	0.00	0.00	7842.00	2.00	872.00	0.00	0.00	872.00
9	13855.75	91.10	209.74	4514.85	-0.66	73.01	10.00	209.74	-73.01
10	13272.63	91.10	209.74	6424.95	0.00	-443.90	10.00	0.00	443.90



Map System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866

Local Origin	Well 124H, Grid North
Latitude	32° 14' 28.88339 N
Longitude	104° 2' 2.26075 W
Grid East	592560.00
Grid North	451653.00
Scale Factor	1.000

Geomagnetic Model HDGM
Sample Date 14-Dec-15
Magnetic Declination: 7.38°
Angle from Horizontal: 60.10°
Magnetic Field Strength 48280

To convert a Magnetic Direction to a Grid Direction, Add 7.22°
To convert a Magnetic Direction to a True Direction, Add 7.38° East
To convert a True Direction to a Grid Direction, Subtract 0.16°

FORMATION TOP DETAILS

CASING DETAILS		
	TVD	MD
	500.00	600.00
	2646.41	2650.00

MD	MD	MD
600 00	600 00	600 00
2646 41	2650 00	2650 00




PATTERSON-UTI

Well Control

RIG:

297



Made by Cameron
(Shaffer Spherical)
Clone Annular

PATTERSON-UTI # PS2-628

STYLE: New Shaffer Spherical

BORE 13 5/8" PRESSURE 5,000

HEIGHT: 48 1/2" WEIGHT: 13,800 lbs

PATTERSON-UTI # PC2-128

STYLE: New Cameron Type U

BORE 13 5/8" PRESSURE 10,000

RAMS: TOP 5" Pipe BTM Blinds

HEIGHT: 66 5/8" WEIGHT: 24,000 lbs

Length 40" Outlets 4" 10M

DSA 4" 10M x 2" 10M

PATTERSON-UTI # PC2-228

STYLE: New Cameron Type U

BORE 13 5/8" PRESSURE 10,000


RAMS: 5" Pipe

HEIGHT: 41 5/8" WEIGHT: 13,000 lbs


WING VALVES




2" Check Valve




2" Manual Valve




2" Manual Valve



4" Manual Valve



4" Hydraulic Valve



PATTERSON-UTI
DRILLING COMPANY LLC

CHOKE MANIFOLD

10M CHOKE ARRANGEMENT

RIG 297

DATE: R0297-D.001.LAY.09

COPYRIGHT 2014
PATTERSON-UTI
DRILLING COMPANY LLC

CONFIDENTIAL AND PROPRIETARY

NOT TO BE DISTRIBUTED

REV	DATE	DESCRIPTION	CHK	BY	APPROV	END
02	6-3-15	ISSUED FOR INFORMATION	CP	CEL		
01	7-9-15	ISSUED FOR INFORMATION	CEL	CEL		

WELDING NOTE & TOLERANCES UNLESS OTHERWISE SPECIFIED:

GENERAL WELDING NOTE:
ALL ACCESSIBLE CONTACT SURFACES
WELDED JOINTS SHALL BE WELDED TO
BE 1/8 INCH SMALLER THAN
THINNER MEMBER JOINED UP TO
SMALLER THAN THINNER MEMBER
JOINED UP TO 3/4 INCH THICKNESS
WELDMENT TOLERANCES: ±.015 INCH

MACHINING TOLERANCES
1 PLACE DECIMAL ±.1
2 PLACE DECIMAL ±.05
3 PLACE DECIMAL ±.015
FRACTIONAL TOLERANCES: 1/64
INDICE MACHINED CORNER RADIUS ±.01
ANGLE TOLERANCES: ±.01 DEGREE
MACHINED SURFACE FINISH: 125 RMS
ALL UNSPECIFIED DIMENSIONS ARE IN INCHES



Midwest Hose
& Specialty, Inc.

Internal Hydrostatic Test Graph

Customer: Patterson

Pick Ticket #: 284918

December 8, 2014

Hose Specifications

Hose Type

CK

I.D.

3"

Length

10'

O.D.

4.79"

Verification

Type of Fitting

4-1/16 10K

Die Size

5.37"

Coupling Method

Swage

Final O.D.

5.37"

Working Pressure

10000 PSI

Burst Pressure

Standard Safety Multiplier Applies


Hose Serial #

10490

Hose Assembly Serial #

284918-2

Pressure Test



Test Pressure
15000 PSI

Time Held at Test Pressure
15 2/4 Minutes

Actual Burst Pressure

Peak Pressure
15732 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Tyler Hill

Approved By: Ryan Adams



Midwest Hose
& Specialty, Inc.

Internal Hydrostatic Test Certificate

General Information		Hose Specifications	
Customer	PATTERSON B&E	Hose Assembly Type	Choke & Kill
MWH Sales Representative	AMY WHITE	Certification	API 7K
Date Assembled	12/8/2014	Hose Grade	MUD
Location Assembled	OKC	Hose Working Pressure	10000
Sales Order #	236404	Hose Lot # and Date Code	10490-01/13
Customer Purchase Order #	260471	Hose I.D. (Inches)	3"
Assembly Serial # (Pick Ticket #)	287918-2	Hose O.D. (Inches)	5.30"
Hose Assembly Length	10'	Aarmor (yes/no)	YES
Fittings			
End A		End B	
Stem (Part and Revision #)	R3.0X64WB	Stem (Part and Revision #)	R3.0X64WB
Stem (Heat #)	91996	Stem (Heat #)	91996
Ferrule (Part and Revision #)	RF3.0	Ferrule (Part and Revision #)	RF3.0
Ferrule (Heat #)	37DA5631	Ferrule (Heat #)	37DA5631
Connection (Part #)	4 1/16 10K	Connection (Part #)	4 1/16 10K
Connection (Heat #)		Connection (Heat #)	
Dies Used	5.37	Dies Used	5.37
Hydrostatic Test Requirements			
Test Pressure (psi)	15,000	Hose assembly was tested with ambient water temperature.	
Test Pressure Hold Time (minutes)	15 1/2		
Date Tested	Tested By		Approved By
12/8/2014			



Midwest Hose
& Specialty, Inc.

Certificate of Conformity

Customer: **PATTERSON B&E**

Customer P.O.# **260471**

Sales Order # **236404**

Date Assembled: **12/8/2014**

Specifications

Hose Assembly Type: **Choke & Kill**

Assembly Serial # **287918-2**

Hose Lot # and Date Code **10490-01/13**

Hose Working Pressure (psi) **10000**

Test Pressure (psi) **15000**

We hereby certify that the above material supplied for the referenced purchase order to be true according to the requirements of the purchase order and current industry standards.

Supplier:

Midwest Hose & Specialty, Inc.

3312 S I-35 Service Rd

Oklahoma City, OK 73129

Comments:

Approved By

Date

12/9/2014

December 9, 2014

Internal Hydrostatic Test Graph

Customer: Patterson

Pick Ticket #: 284918

Midwest Hose
& Specialty, Inc.

Hose Specifications


Hose Type
Ck
LD
3"
Working Pressure
10000 PSI

Length
20'
O.D.
4.77"

Verification

Type of Fitting
4-1/16 10K
Die Size
5.37"
Coupling Method
Swage
Final O.D.
5.40"
Hose Serial #
10490
Hose Assembly Serial #
284918-1

Pressure Test



Test Pressure
15000 PSI

Time Held at Test Pressure
15 2/4 Minutes

Actual Burst Pressure

Peak Pressure
15893 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Tyler Hill

Approved By: Ryan Adams



Midwest Hose
& Specialty, Inc.

Internal Hydrostatic Test Certificate

General Information		Hose Specifications	
Customer	PATTERSON B&E	Hose Assembly Type	Choke & Kill
MWH Sales Representative	AMY WHITE	Certification	API 7K
Date Assembled	12/8/2014	Hose Grade	MUD
Location Assembled	OKC	Hose Working Pressure	10000
Sales Order #	236404	Hose Lot # and Date Code	10490-01/13
Customer Purchase Order #	260471	Hose I.D. (Inches)	3"
Assembly Serial # (Pick Ticket #)	287918-1	Hose O.D. (Inches)	5.30"
Hose Assembly Length	20'	Armor (yes/no)	YES
Fittings			
End A		End B	
Stem (Part and Revision #)	R3.0X64WB	Stem (Part and Revision #)	R3.0X64WB
Stem (Heat #)	A141420	Stem (Heat #)	A141420
Ferrule (Part and Revision #)	RF3.0	Ferrule (Part and Revision #)	RF3.0
Ferrule (Heat #)	37DA5631	Ferrule (Heat #)	37DA5631
Connection (Part #)	4 1/16 10K	Connection (Part #)	4 1/16 10K
Connection (Heat #)	V3579	Connection (Heat #)	V3579
Dies Used	5.37	Dies Used	5.37
Hydrostatic Test Requirements			
Test Pressure (psi)	15,000	Hose assembly was tested with ambient water temperature.	
Test Pressure Hold Time (minutes)	15 1/2		
Date Tested	Tested By		Approved By
12/9/2014			



Midwest Hose
& Specialty, Inc.

Certificate of Conformity

Customer: **PATTERSON B&E**

Customer P.O.# **260471**

Sales Order # **236404**

Date Assembled: **12/8/2014**

Specifications

Hose Assembly Type: **Choke & Kill**

Assembly Serial # **287918-1**

Hose Lot # and Date Code **10490-01/13**

Hose Working Pressure (psi) **10000**

Test Pressure (psi) **15000**

We hereby certify that the above material supplied for the referenced purchase order to be true according to the requirements of the purchase order and current industry standards.

Supplier:

Midwest Hose & Specialty, Inc.

3312 S I-35 Service Rd

Oklahoma City, OK 73129

Comments:

Approved By

Date

12/9/2014

Internal Hydrostatic Test Graph

Customer: Patterson

Pick Ticket #: 284918



Midwest Hose
& Specialty, Inc.

Hose Specifications

Hose Type

Mud

I.D.

3"

Length

70'

O.D.

4.79"

Verification

Type of Fitting

4 1/16 10K

Die Size

5.37"

Coupling Method

Swage

Final O.D.

5.37"

Working Pressure

10000 PSI

Burst Pressure

Standard Safety Multiplier Applies


Hose Serial #

10490

Hose Assembly Serial #

284918-3

Pressure Test



Test Pressure
15000 PSI

Time Held at Test Pressure
16 3/4 Minutes

Actual Burst Pressure

Peak Pressure
15410 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Tyler Hill

Approved By: Ryan Adams

[Signature]

[Signature]



Midwest Hose
& Specialty, Inc.

Internal Hydrostatic Test Certificate

General Information		Hose Specifications	
Customer	PATTERSON B&E	Hose Assembly Type	Choke & Kill
MWH Sales Representative	AMY WHITE	Certification	API 7K
Date Assembled	12/8/2014	Hose Grade	MUD
Location Assembled	OKC	Hose Working Pressure	10000
Sales Order #	236404	Hose Lot # and Date Code	10490-01/13
Customer Purchase Order #	260471	Hose I.D. (Inches)	3"
Assembly Serial # (Pick Ticket #)	287918-3	Hose O.D. (Inches)	5.23"
Hose Assembly Length	70'	Armor (yes/no)	YES
Fittings			
End A		End B	
Stem (Part and Revision #)	R3.0X64WB	Stem (Part and Revision #)	R3.0X64WB
Stem (Heat #)	A141420	Stem (Heat #)	A141420
Ferrule (Part and Revision #)	RF3.0	Ferrule (Part and Revision #)	RF3.0
Ferrule (Heat #)	37DA5631	Ferrule (Heat #)	37DA5631
Connection (Part #)	4 1/16 10K	Connection (Part #)	4 1/16 10K
Connection (Heat #)		Connection (Heat #)	
Dies Used	5.37	Dies Used	5.37
Hydrostatic Test Requirements			
Test Pressure (psi)	15,000	Hose assembly was tested with ambient water temperature.	
Test Pressure Hold Time (minutes)	16 3/4		
Date Tested	Tested By	Approved By	
12/9/2014			



Midwest Hose
& Specialty, Inc.

Certificate of Conformity

Customer: **PATTERSON B&E**

Customer P.O.# **260471**

Sales Order # **236404**

Date Assembled: **12/8/2014**

Specifications

Hose Assembly Type: **Choke & Kill**

Assembly Serial # **287918-3**

Hose Lot # and Date Code **10490-01/13**

Hose Working Pressure (psi) **10000**

Test Pressure (psi) **15000**

We hereby certify that the above material supplied for the referenced purchase order to be true according to the requirements of the purchase order and current industry standards.

Supplier:

Midwest Hose & Specialty, Inc.

3312 S I-35 Service Rd

Oklahoma City, OK 73129


Comments:

Approved By

Date

12/9/2014

Closed-Loop System




Operating and Maintenance Plan:

During drilling operations, third party service companies will utilize solids control equipment to remove cuttings from the drilling fluids and collect it in haul-off bins. Equipment will be closely monitored at all times while drilling by the derrick man and the service company employees.

Closure Plan:


During drilling operations, third party service companies will haul off drill solids and fluids to an approved disposal facility. At the end of the well, all closed loop equipment will be removed from the location.




Schematic Closed Loop Drilling Rig*

1. Pipe Rack
2. Drill Rig
3. House Trailers/ Offices
4. Generator/Fuel/Storage
5. Overflow-Frac Tank
6. Skids
7. Roll Offs
8. Hopper or Centrifuge
9. Mud Tanks
10. Loop Drive
11. Generator (only for use with centrifuge)

*Not drawn to scale: Closed loop system requires at least 30 feet beyond mud tanks. Ideally 60 feet would be available




Above: Centrifugal Closed Loop System



Closed Loop Drilling System: Mud tanks to right (1)
Hopper in air to settle out solids (2)
Water return pipe (3)
Shaker between hopper and mud tanks (4)
Roll offs on skids (5)


Flow Chart for Drilling Fluids and Solids



Photos Courtesy of Gandy Corporation Oil
Field Service

PERMITS WEST .INC.
PROVIDING PERMITS for LAND USERS
17 Verano Loop, Santa Fe, New Mexico 87508 (505) 466-8120

Rig Diagram



Dr. Scrivner Fed. 01-24S-28E RB 124H
 Matador Production Company
 SHL 661' FSL & 661' FEL
 1-24S-28E, Eddy County, NM
 1" = 100'





Hydrogen Sulfide Drilling Operations Plan

Matador Production Company

1 H2S safety instructions to the following:

- Characteristics of H2S
- Physical effects and hazards
- Principal and operation of H2S detectors, warning system and briefing areas
- Evacuation procedures, routes and first aid
- Proper use of safety equipment & life support systems
- Essential personnel meeting medical evaluation criteria will receive additional training on the proper use of 30min pressure demand air packs

2 H2S Detection and Alarm Systems:

- H2S sensor/detectors to be located on the drilling rig floor, in the base of the sub structure / cellar area, on the mud pits in the shale shaker area. Additional H2S detectors may be placed as deemed necessary
- An audio alarm system will be installed on the derrick floor and in the doghouse

3 Windsocks and / Wind Streamers:

- Windsocks at mud pit area should be high enough to be visible
- Windsock on the rig floor and / top of doghouse should be high enough to be visible

4 Condition Flags and Signs:

- Warning sign on access road to location
- Flags to be displayed on sign at entrance to location
 - Green Flag – Normal Safe Operation Condition
 - Yellow Flag – Potential Pressure and Danger
 - Red Flag – Danger (H2S present in dangerous concentrations) Only H2S trained personnel admitted on location

5 Well Control Equipment:

- See APD

6 Communications:

- While working under masks, chalkboards will be used for communications
- Hand signals will be used where chalk board is inappropriate
- Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at drilling foreman's trailer or living quarters.



7 Drilling Stem Testing:

- No DST or cores are planned at this time

8 Drilling contractor supervisor will be required to be familiar with the effects H₂S has on tubulars good and other mechanical equipment

9 If H₂S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H₂S scavengers if necessary


11 Emergency Contacts

- See next page

H2S Contingency Plan Emergency Contacts
Matador Production Company
Sec. 1, 24S, 28E, Eddy County, NM

<u>Company Office</u>			
Matador Production Company	(972)-371-5200		
<u>Key Personnel</u>			
Name	Title	Office	Mobile
Billy Goodwin	Vice President Drilling	972-371-5210	817-522-2928
Gary Martin	Drilling Superintendent		601-669-1774
Dee Smith	Drilling Superintendent	972-371-5447	972-822-1010
Aaron Byrd	Drilling Engineer	972-371-5267	214-507-2333
	Construction Superintendent		
	Construction Superintendent		
<u>Artesia</u>			
Ambulance			911
State Police		575-746-2703	
City Police		575-746-2703	
Sheriff's Office		575-746-9888	
Fire Department		575-746-2701	
Local Emergency Planning Committee		575-746-2122	
New Mexico Oil Conservation Division		575-748-1283	
<u>Carlsbad</u>			
Ambulance			911
State Police		575-885-3137	
City Police		575-885-2111	
Sheriff's Office		575-887-7551	
Fire Department		575-887-3798	
Local Emergency Planning Committee		575-887-6544	
New Mexico Oil Conservation Division		575-887-6544	
<u>Santa Fe</u>			
New Mexico Emergency Response Commission (Santa Fe)		505-476-9600	
New Mexico Emergency Response Commission (Santa Fe) 24 hrs		505-827-9126	
New Mexico State Emergency Operations Center		505-476-9635	
<u>National</u>			
Carlsbad BLM		575-234-5972	
National Emergency Response Center (Washington, D.C.)		800-424-8802	
<u>Medical</u>			
Flight for Life- 4000 24th St.; Lubbock, TX		806-743-9911	
Aerocare- R3, Box 49F; Lubbock, TX		806-747-8923	
Med Flight Air Amb- 2301 Yale Blvd S.E., D3; Albuquerque, NM		505-842-4433	
SB Air Med Service- 2505 Clark Carr Loop S.E.; Albuquerque, NM		505-842-4949	
<u>Other</u>			
Boots & Coots IWC		800-256-9688	or 281-931-8884
Cudd Pressure Control		432-699-0139	or 432-563-3356
Haliburton		575-746-2757	
B.J. Services		575-746-3569	

H2S Diagram





Dr. Scrivner Fed. 01-24S-28E RB 124H
 Matador Production Company
 SHL 661' FSL & 661' FEL
 1-24S-28E, Eddy County, NM

Matador Production Company

Dr. Scribner Fed 01-24S-28E RB #124H
H-S Contingency Plan:
1 Mile Radius Map



Section 1, Township 24S, Range 28E
Eddy County, New Mexico



NAD 1927 New Mexico State Plane East
FIPS 3001 Feet

PERMITS UNIT


Prepared by Permits West, Inc., December 18, 2015
for Matador Production Company




Matador Production Company

Dr. Scribner Fed 01-24S-28E RB #124H
H&S Contingency Plan:
2 Mile Radius Map

Section 1, Township 24S, Range 28E
Eddy County, New Mexico





Surface Hole Location



NAD 1927 New Mexico State Plane East
FIPS 3001 Feet

PERMITS WEST

Prepared by Permits West, Inc. December 18, 2015
for Matador Production Company






SECTION 1, TOWNSHIP 24-S, RANGE 28-E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

DETAIL VIEW
SCALE: 1" = 100'

INTERIM RECLAMATION DIAGRAM

interim reclamation
1.78 acres



LEASE NAME & WELL NO.: DR. SCRIVNER FEDERAL 01-24S-28E RB #124H

#124H LATITUDE N 32.2413567 #124H LONGITUDE W 104.0339603

LEGEND

--- PROPOSED ROAD
--- ARCH SITE

SCALE: 1" = 100'
0' 50' 100'

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID
BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE OF THE
NORTH AMERICAN DATUM 1927, U.S. SURVEY FEET

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER
MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY,
AND DATA PROVIDED BY MATADOR PRODUCTION COMPANY. THIS CERTIFICATION IS MADE AND
LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS
NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY
1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743
WWW.TOPOGRAPHIC.COM

ORIGINAL DOCUMENT SIZE: 8.5" X 11"

Matador Production Company

SURFACE PLAN PAGE 1

Dr. Scrivner Fed. 01-24S-28E RB 124H

SHL 661' FSL & 661' FEL Sec. 1, T. 24 S., R. 28 E.

BHL 660' FSL & 240' FWL Sec. 1, T. 24 S., R. 28 E.

Eddy County, NM

Surface Use Plan

1. ROAD DIRECTIONS & DESCRIPTIONS (See MAPS 1 - 3 & 5)

From the Malaga Post Office...

Go East 0.85 miles on paved County Road 744 (aka, Duarte Road)

Then turn left and go North 1.0 mile on paved County Road 745

Then turn right and go East and Northeast 1.1 miles on paved Harroun Road

Then turn right and go South 200 yards on a caliche road

Then turn right and go West 67' cross-country to the proposed pad

Non-county roads will be maintained as needed to Gold Book standards. This includes pulling ditches, preserving the crown, and cleaning culverts. This will be done at least once a year, and more often as needed. Caliche will be hauled from existing caliche pits on private land in NWSE 1-24s-28e and NWSW 6-24s-29e.

2. ROAD TO BE BUILT OR UPGRADED (See MAPS 3, 5, & 7)

The 67' of new road to the well will be crowned, have a 14' wide driving surface, and be surfaced with caliche. Maximum disturbed width = 20'. Maximum grade = 1%. Maximum cut or fill = 1'. No upgrade, culvert, cattle guard, or vehicle turn out is needed.

Fifty feet of new road to the central tank battery (CTB) will be crowned, have a 14' wide driving surface, and be surfaced with caliche. Maximum disturbed width = 20'. Maximum grade = 1%. Maximum cut or fill = 3'. No upgrade, culvert, cattle guard, or vehicle turn out is needed.

Matador Production Company

SURFACE PLAN PAGE 2

Dr. Scrivner Fed. 01-24S-28E RB 124H

SHL 661' FSL & 661' FEL Sec. 1, T. 24 S., R. 28 E.

BHL 660' FSL & 240' FWL Sec. 1, T. 24 S., R. 28 E.

Eddy County, NM

3. EXISTING WELLS (See MAP 2)

Existing oil, gas, water, and P & A wells are within a mile. There are no injection or disposal wells within a mile radius.

4. PROPOSED PRODUCTION FACILITIES (See MAPS 2, 3, & 6-11)

The only production equipment on the pad will be the pump jack. A $\approx 6"$ O. D. steel buried flow line will be laid 230.54' north to Matador's proposed central tank battery (CTB). A 230.54' long overhead raptor safe 3-phase power line will be built south parallel to the flow line from the battery to the pad. Construction corridor for each line will be 15' wide.

A 350' x 350' central tank battery will be built between Matador's two proposed 5-well pads. Brush and the top 6" of soil will be piled west of the battery. A $\approx 6"$ O. D. steel buried gas line will be laid 3,452.91' northeast parallel to roads to an existing Enterprise meter. A 2,858.78' long overhead raptor safe 3-phase power line will be built northeast parallel to the gas line to an existing Xcel power line.

5. WATER SUPPLY (See MAPS 1 - 3)

Water will be trucked from an existing well (C 00464) on private land in NENW 13-24s-28e.

6. CONSTRUCTION MATERIALS & METHODS (see MAP 13)

NM One Call (811) will be notified before construction starts. A temporary fence will be built on the south side of the pad before construction starts to keep construction equipment off a slope. Top $\approx 6"$ of soil and brush will be stockpiled west of the pad. Pipe racks will be to the south. A closed loop drilling

Matador Production Company

SURFACE PLAN PAGE 3

Dr. Scrivner Fed. 01-24S-28E RB 124H

SHL 661' FSL & 661' FEL Sec. 1, T. 24 S., R. 28 E.

BHL 660' FSL & 240' FWL Sec. 1, T. 24 S., R. 28 E.

Eddy County, NM

system will be used. Caliche will be hauled from existing caliche pits on private land in NWSE 1-24s-28e and NWSW 6-24s-29e.

7. WASTE DISPOSAL

All trash will be placed in a portable trash cage. It will be hauled to the Eddy County landfill. There will be no trash burning. Contents (drill cuttings, mud, salts, and other chemicals) of the mud tanks will be hauled to CRI's state approved (NM-01-0006) disposal site. Human waste will be disposed of in chemical toilets and hauled to the Carlsbad wastewater treatment plant.

8. ANCILLARY FACILITIES

There will be no airstrip or camp. Camper trailers will be on location for the company man, tool pusher, or mud logger.

9. WELL SITE LAYOUT

See Rig Diagram for depictions of the well pad, trash cage, access onto the location, parking, living facilities, and rig orientation.

10. RECLAMATION

Interim reclamation will consist of shrinking the pad $\approx 51\%$ by removing caliche and reclaiming (1.78 acres) the north and west sides, leaving a 1.77 acre area around the pump jacks. Disturbed areas will be contoured to match pre-construction grades. Soil and brush will be evenly spread over disturbed areas. Disturbed areas will be seeded in accordance with the surface owner's requirements. Enough stockpiled topsoil will be retained to cover the remainder of the pad when the wells are plugged. Once the last well is plugged, then the

Matador Production Company

SURFACE PLAN PAGE 4

Dr. Scrivner Fed. 01-24S-28E RB 124H

SHL 661' FSL & 661' FEL Sec. 1, T. 24 S., R. 28 E.

BHL 660' FSL & 240' FWL Sec. 1, T. 24 S., R. 28 E.

Eddy County, NM

remainder of the pad will be similarly reclaimed. Noxious weeds will be controlled.

11. SURFACE OWNER

All construction will be on private surface. Matador has surface use agreements with the surface owners.

Johnson Enterprises (P. O. Box 1713, Roswell NM 88202) is the surface owner for the well site, battery, road, and those portions of the pipelines and power lines in Section 1, T. 24 S., R. 28 E. Eddy County, NM.

John Draper Brantley, Jr. and Henry McDonald (706 W. Riverside Dr., Carlsbad NM 88220) are the surface owners (together) for those portions of the pipeline and power line in Section 6, T. 24 S., R. 29 E. Eddy County, NM.

12. OTHER INFORMATION

On site inspection was held with Trish Bad Bear (BLM) on November 19, 2015.

Lone Mountain submitted archaeology report NMCRIS 134941 on December 23, 2015.

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Matador Production Company
LEASE NO.:	NMNM115410
WELL NAME & NO.:	124H-Dr Scrivner Fed 01 24S 28E RB.
SURFACE HOLE FOOTAGE:	661'/S & 661'/E
BOTTOM HOLE FOOTAGE:	660'/S & 240'/E
LOCATION:	Section 1, T.24 S., R.28 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Communitization Agreement
- ☒ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
 - Cement Requirements
 - Medium Cave/Karst
 - Logging Requirements
 - Waste Material and Fluids
- ☒ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

Lease Suspension

Well to be spudded within 120 days of the approval of the APD.

If the drilling operations have not commenced by this time, the lease suspension of Lease NMNM115410 will be removed and One month will be remaining in its primary term.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill out sloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattleguards

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. **Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Water Basin:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.

Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Medium Cave/Karst

Possibility of water flows in the Castile.

Possibility of lost circulation in the Salado, Rustler, and Delaware.

1. The 13-3/8 inch surface casing shall be set at approximately 360 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job is to include the

lead cement slurry.

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
- ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.**

If cement does not circulate to surface on the intermediate casing, the cement on the production casing must come to surface.

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
- ☒ Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification.
4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
- 2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the

field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).

3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi
4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **9-5/8** inch intermediate casing shoe shall be **3000 (3M)** psi.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
 - c. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
 - d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - e. The results of the test shall be reported to the appropriate BLM office.

- f. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

MHH051316

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.
5. All construction and maintenance activity will be confined to the authorized right-of-way.
6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.
7. The maximum allowable disturbance for construction in this right-of-way will be 15 feet:

- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. *(Blading is defined as the complete removal of brush and ground vegetation.)*
- Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 15 feet. The trench and bladed area are included in this area. *(Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.)*
- The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. *(Compressing can be caused by vehicle tires, placement of equipment, etc.)*

8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.

9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

- | | |
|--|--|
| ☒ seed mixture 1 | ☐ seed mixture 3 |
| ☐ seed mixture 2 | ☐ seed mixture 4 |
| ☐ seed mixture 2/LPC | ☐ Aplomado Falcon Mixture |

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches [that are not otherwise fenced, screened, or netted] to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the application (Grant, Sundry Notice, APD) and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
4. The holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:
 - a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
 - b. Activities of other parties including, but not limited to:
 - (1) Land clearing.

- (2) Earth-disturbing and earth-moving work.
- (3) Blasting.
- (4) Vandalism and sabotage.
- c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom; on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.

6. All construction and maintenance activity will be confined to the authorized right-of-way width of 15 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline must be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline must be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.

8. The holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline will be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines must be less than or equal to 4 inches and a working pressure below 125 psi.

C. ELECTRIC LINES

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.
5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The

holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.

Fill in any holes from the poles removed.

IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 1 for Loamy Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed shall be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed shall be planted using a drill equipped with a depth regulator to ensure proper depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture shall be evenly and uniformly planted over the disturbed area (small/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed shall be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre shall be doubled. The seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains lovegrass (<i>Eragrostis intermedia</i>)	0.5
Sand dropseed (<i>Sporobolus cryptandrus</i>)	1.0
Sideoats grama (<i>Bouteloua curtipendula</i>)	5.0
Plains bristlegrass (<i>Setaria macrostachya</i>)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

NMOCD CONDITION OF APPROVAL

The *New* Gas Capture Plan (GCP) notice is posted on the NMOCD website under Announcements. The Plan became effective May 1, 2016. A copy of the GCP form is included with the NOTICE and is also in our FORMS section under Unnumbered Forms. Please review filing dates for all applicable activities currently approved or pending and submit accordingly. Failure to file a GCP may jeopardize the operator's ability to obtain C-129 approval to flare gas after the initial 60-day completion period.