

**NM OIL CONSERVATION**  
ARTESIA DISTRICT

JUN 20 2016

FORM APPROVED  
OMB No. 1004-0137  
Expires October 31, 2014

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

RECEIVED

**APPLICATION FOR PERMIT TO DRILL OR REENTER**

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. SHL: NMNM130856, BHL: NMNM115409 Lot 15: NMNM115407	
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name	
2. Name of Operator COG Operating LLC.		7. If Unit or CA Agreement, Name and No.	
3a. Address 2208 West Main Street Artesia, NM 88210		8. Lease Name and Well No. Running Buffalo 1 Federal Com #2H	
3b. Phone No. (include area code) 575-748-6940		9. API Well No. 30 015 43031	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface 1650' FSL & 1980' FEL Unit Letter J (NWSE) Section 1 - T21S - R28E At proposed prod. Zone 330' FNL & 1980' FEL Unit Lot 2 (NWNE) Section 1 - T21S - R28E		10. Field and Pool, or Exploratory WC-015 G-05 S202935P; Bone Spring	
14. Distance in miles and direction from nearest town or post office* Approximately 10 miles from Malaga		11. Sec., T.R.M. or Blk and Survey or Area Sec. 1 - T21S - R28E	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. Unit line, if any) 330'		12. County or Parish Eddy County	
16. No. of acres in lease NMNM130856: 160 NMNM115409: 294.31 NMNM115407: 160		13. State NM	
17. Spacing Unit dedicated to this well 183.13		18. Distance from location* to nearest well, drilling, completed, applied for, on this lease, ft. SHL: 330' BHL: None on lease Closest to wellbore: 323'	
19. Proposed Depth TYD: 8,570' MD: 13,876'		20. BLM/BIA Bond No. on file NMB000740 & NMB000215	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3445.0' GL		22. Approximate date work will start* 6/1/2015	
23. Estimated duration 30 days			

**24. Attachments**

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- |   |  |
|---|--|
| 1. Well plat certified by a registered surveyor.  | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).    |
| 2. A Drilling Plan  | 5. Operator certification  |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature <i>Chris Walls</i>	Name (Printed/Typed) Chris Walls	Date 5-5-15
-------------------------------------	-------------------------------------	----------------

Regulatory Analyst	
Approved by (Signature) <i>/s/ Chris Walls</i>	Name (Printed/Typed) Chris Walls
Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

**APPROVAL FOR TWO YEARS**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

**Capitan Controlled Water Basin**

**Approval Subject to General Requirements  
& Special Stipulations Attached**

**SEE ATTACHED FOR  
CONDITIONS OF APPROVAL**

6-21-16 6-21-16

Surface Use Plan  
COG Operating LLC  
Running Buffalo 1 Federal Com #2H  
SHL: 1650' FSL & 1980' FEL UL J  
Section 1, T21S, R28E  
BHL: 330' FNL & 1980' FEL Lot 2  
Section 1, T21S, R28E  
Eddy County, New Mexico

---

### OPERATOR CERTIFICATION

I hereby certify that I, or persons under my direct supervision, have inspected the drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or COG Operating LLC, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 5th day of May, 2015.

Signed: Melanie J. Wilson

Printed Name: Melanie J. Wilson

Position: Regulatory Coordinator

Address: 2208 W. Main Street, Artesia, NM 88210

Telephone: (575) 748-6940

Field Representative (if not above signatory): Rand French

E-mail: [mwilson@concho.com](mailto:mwilson@concho.com)

DISTRICT I  
1625 N. FRENCH DR., HOBBS, NM 88240  
Phone: (570) 393-6181 Fax: (570) 393-0720

DISTRICT II  
811 S. FIRST ST., ARTESIA, NM 86210  
Phone: (575) 748-1285 Fax: (575) 748-0720

DISTRICT III  
1000 RIO BRAZOS RD., AZTEC, NM 87410  
Phone: (505) 334-6178 Fax: (505) 334-6170

DISTRICT IV  
1220 S. ST. FRANCIS DR., SANTA FE, NM 87505  
Phone: (505) 476-3480 Fax: (505) 476-3482

State of New Mexico  
Energy, Minerals & Natural Resources Department  
**OIL CONSERVATION DIVISION**  
1220 SOUTH ST. FRANCIS DR.  
Santa Fe, New Mexico 87505

Form C-102  
Revised August 1, 2011  
Submit one copy to appropriate  
District Office

☐ AMENDED REPORT

**WELL LOCATION AND ACREAGE DEDICATION PLAT**

API Number 30-015- <b>43831</b>	Pool Code 97995	Pool Name WC-015 G-05 S202935P; Bone Spring
Property Code 40010	Property Name RUNNING BUFFALO 1 FEDERAL COM	Well Number 2H
GRID No. 229137	Operator Name COG OPERATING, LLC	Elevation 3445.0

**Surface Location**


UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
J	1	21-S	28-E		1650'	SOUTH	1980'	EAST	EDDY

**Bottom Hole Location If Different From Surface**

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
2	1	21-S	28-E		330'	NORTH	1980'	EAST	EDDY

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.
187 <del>189</del> .13	{2, 7, 10, 15, 'J'}		

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED  
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



**OPERATOR CERTIFICATION**

I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

*Melanie J Wilson* 5/5/15  
Signature Date

Melanie J Wilson  
Printed Name  
mwilson@concho.com  
E-mail Address


**SURVEYOR CERTIFICATION**

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.


FEBRUARY 03, 2015

Date of Survey

Signature & Seal of Professional Surveyor




SECTION 1, TOWNSHIP 21 SOUTH, RANGE 28 EAST, N.M.P.M.,  
EDDY COUNTY NEW MEXICO



ALL FEATURES ARE EXISTING UNLESS OTHERWISE NOTED

**DIRECTIONS TO LOCATION**

HEADING NORTHEAST ON HWY 62/180 TURN RIGHT .5 PAST MM 47 ONTO A CALICHE ROAD; GO APPROX. .3 MILES AND TURN LEFT (SOUTHEAST) THEN GO APPROX. 0.8 MILE; THEN TURN LEFT (EAST) AND GO APPROX. 0.9 MILE; THEN TURN LEFT (NORTH) ONTO A TWO TRACK ROAD GO APPROX. 180 FEET AND PROPOSED WELL IS APPROX 184 FEET WEST.



**HARCROW SURVEYING, LLC**  
2314 W. MAIN ST, ARTESIA, N.M. 88210  
PH: (575) 746-2158 FAX: (575) 746-2158  
c.harcrow@harcrowsurveying.com



**COG OPERATING, LLC**

**RUNNING BUFFALO 1 FEDERAL COM #2H WELL**  
LOCATED 1850 FEET FROM THE SOUTH LINE  
AND 1980 FEET FROM THE EAST LINE OF SECTION 1,  
TOWNSHIP 21 SOUTH, RANGE 28 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO

SURVEY DATE: 02/03/2015


PAGE: 1 OF 1

DRAFTING DATE: 05/01/2015

APPROVED BY: CH

DRAWN BY: AF

FILE: 15-565



<b>LEGEND</b> • WELL WELLPAD EXISTING ROAD PROPOSED ROAD TWO-TRACK ROAD	<b>RUNNING BUFFALO 1 FEDERAL COM #2H</b>				 <b>CONCHO</b> COG OPERATING, LLC		
	SEC: 01    TWP: 21 S.    RGE: 28 E.    ELEVATION: 3445.0'						
	STATE: NEW MEXICO    COUNTY: EDDY    1650' FSL & 1980' FEL						
	W.O. # 15-565    LEASE: RUNNING BUFFALO 1 FED COM    SURVEY: N.M.P.M						
	<div style="display: flex; justify-content: space-between;"> <span>0</span> <span>2,500 FEET</span> </div> <div style="display: flex; justify-content: space-between;"> <span>0 0.05 0.1 0.2 Miles</span> <span>1 IN = 1,000 FT</span> </div>						
<b>LOCATION MAP</b>		<b>IMAGERY ROAD</b>		<b>05/01/2015</b>		<b>AP</b>	

**HARCROW SURVEYING, LLC.**  
 2314 W. MAIN ST, ARTESIA, NM 88210  
 PH: (575) 746-2158 FAX: (575) 746-2158  
 c.harcrow@harcrowsurveying.com

EXHIBIT 2

Section Two Tank

RUNNING BUFFALO 1 FEDERAL COM #1H

RUNNING BUFFALO 1 FEDERAL COM #2H

TO BE UPGRADED

3414T, 3422T, 3457T, 3485T, 3486T, 3488T, 3493T, 3408T, 3364T, 3415T

2-263

QUAHAD

3450, 3460, 3470, 3480, 3490

184', 180'


R25, R26, R27

2314 W. MAIN ST, ARTESIA, NM 88210  
PH: (575) 746-2158 FAX: (575) 746-2158  
c.harcrow@harcrowsurveying.com

# EXHIBIT 2A

## ACCESS ROAD PLAT COG OPERATING, LLC.

AN ACCESS ROAD FROM AN EXISTING ROAD TO THE RUNNING BUFFALO 1 FED COM #2H IN  
SECTION 1, TOWNSHIP 21 SOUTH, RANGE 28 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO.



### DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE AND 363.1 FEET OR 22.01 RODS OR 0.069 MILES IN LENGTH CROSSING USA LAND IN SECTION 1, TOWNSHIP 21 SOUTH, RANGE 28 EAST, EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

### BASIS OF BEARING:


BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983. DISTANCES ARE GRID VALUES.

### CERTIFICATION

I, CHAD HARCROW, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

### HARCROW SURVEYING, LLC

2314 W. MAIN ST. ARTESIA, N.M. 88210  
PH: (575) 746-2158 FAX: (575) 746-2158  
c.harcrow@harcrowsurveying.com



### COG OPERATING, LLC


SURVEY OF AN ACCESS EASEMENT LOCATED IN  
SECTION 1, TOWNSHIP 21 SOUTH, RANGE 28 EAST,  
EDDY COUNTY, NMPM, NEW MEXICO

SURVEY DATE: MARCH 11, 2015	
DRAFTING DATE: APRIL 20, 2015	PAGE 1 OF 1
APPROVED BY: CH	DRAWN BY: TC
	FILE: 15-317



*Chad Harcrow*  
CHAD HARCROW N.M.P.S. NO. 17777

4/26/15  
DATE



# LEGEND


- WELL
- WELLPAD
- EXISTING ROAD
- PROPOSED ROAD
- TWO-TRACK ROAD

**RUNNING BUFFALO 1 FEDERAL COM #2H**

SEC: 01 TWP: 21 S. RGE: 28 E. ELEVATION: 3445.0'

STATE: NEW MEXICO COUNTY: EDDY 1650' FSL & 1980' FEL

W.O. # 15-565 LEASE: RUNNING BUFFALO 1 FED COM SURVEY: N.M.P.M



1 IN = 1,750 FT

LOCATION MAP

INAGENCY

05/01/2015


AF

**CONCHO**  
COG OPERATING, LLC




HARCROW SURVEYING, LLC  
2314 W. MAIN ST, ARTESIA, NM 88210  
PH: (575) 746-2158 FAX: (575) 746-2159  
charcrow@harcrowsurveying.com





**HARCROW SURVEYING, LLC.**  
 2314 W. MAIN ST, ARTESIA, NM 88210  
 PH: (575) 746-2158 FAX: (575) 746-2158  
[charcrow@harcrowsurveying.com](mailto:charcrow@harcrowsurveying.com)



# LEGEND

WELL

WELLPAD

EXISTING ROAD

PROPOSED ROAD

TWO-TRACK ROAD

US BLM

## RUNNING BUFFALO 1 FEDERAL COM #2H

SEC: 01 TWP: 21 S. RGE: 28 E. ELEVATION: 3445.0'

STATE: NEW MEXICO COUNTY: EDDY 1650' FSL & 1980' FEL

W.O. # 15-565 LEASE: RUNNING BUFFALO 1 FED COM SURVEY: N.M.P.M

0 2,500 FEET

0 0.1 0.2 0.4 Miles

1 IN = 1,667 FT

LOCATION MAP

LANDSTATUS

05/01/2015

A.F.

**CONCHO**

COG OPERATING, LLC




HARCROW SURVEYING, LLC.

2314 W. MAIN ST, ARTESIA, NM 88210

PH: (575) 746-2158 FAX: (575) 746-2158

c.harcrow@harcrowsurveying.com

# EXHIBIT 2B




## LEGEND

- WELL
- WELLPAD
- FLOW LINE

## RUNNING BUFFALO 1 FED COM #2H FLOW LINE

SECTION: 1 TOWNSHIP: 21 S. RANGE: 28 E.  
 STATE: NEW MEXICO COUNTY: EDDY SURVEY: N.M.P.M  
 W.O. # 15-319 LEASE: RUNNING BUFFALO 1 FED COM



FLOW LINE OVERVIEW LAND STATUS 04/23/2015 S.P.


**CONCHO**  
 COG OPERATING, LLC

**HSI** HARCROW SURVEYING, LLC.  
 2310 W. MAIN ST, ARTESIA, NM 88210  
 PH: (575) 746-2158 FAX: (575) 746-2158  
 c.harcrow@harcrowsurveying.com

# EXHIBIT 2C

## FLOW LINE PLAT COG OPERATING, LLC.

A FLOW LINE FROM THE RUNNING BUFFALO 1 FED COM #2H TO THE RUNNING BUFFALO 1 FED COM #1H IN  
SECTION 1, TOWNSHIP 21 SOUTH, RANGE 28 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO.



### DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE AND 1410.4 FEET OR 85.48 RODS OR 0.267 MILES IN LENGTH CROSSING USA LAND IN SECTION 1, TOWNSHIP 21 SOUTH, RANGE 28 EAST, EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

### BASIS OF BEARING:


BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983. DISTANCES ARE GRID VALUES.

### CERTIFICATION

I, CHAD HARCROW, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

### HARCROW SURVEYING, LLC

2314 W. MAIN ST, ARTESIA, N.M. 88210  
PH: (575) 746-2158 FAX: (575) 746-2158  
c.harcrow@harcrowsurveying.com



### COG OPERATING, LLC


SURVEY OF A PROPOSED PIPELINE LOCATED IN SECTION 1, TOWNSHIP 21 SOUTH, RANGE 28 EAST, EDDY COUNTY, NMPM, NEW MEXICO

SURVEY DATE: MARCH 11, 2015	MAIN LINE
DRAFTING DATE: APRIL 20, 2015	PAGE 1 OF 1
APPROVED BY: CH	DRAWN BY: TG
	FILE: 15-319



Chad Harcrow  
CHAD HARCROW N.M.P.S. NO. 17777

4/26/15  
DATE




# LEGEND

- WELL
- WELLPAD
- FLOW LINE

## RUNNING BUFFALO 1 FED COM #2H FLOW LINE


SECTION: 1 TOWNSHIP: 21 S. RANGE: 28 E.  
 STATE: NEW MEXICO COUNTY: EDDY SURVEY: N.M.P.M  
 W.O. # 15-319 LEASE: RUNNING BUFFALO 1 FED COM



FLOW LINE OVERVIEW IMAGERY 04/23/2015 S.P.

**CONCHO**  
 COG OPERATING, LLC

**HARCROW SURVEYING, LLC.**  
 2314 W. MAIN ST, ARTESIA, NM 88210  
 PH: (575) 746-2158 FAX: (575) 746-2158  
 charcrow@harcrowsurveying.com




# LEGEND

- WELL
- WELLPAD
- FLOW LINE
- PRIVATE
- STATE OF NM
- US BLM

## RUNNING BUFFALO 1 FED COM #2H FLOW LINE


SECTION: 1 TOWNSHIP: 21 S. RANGE: 28 E.  
 STATE: NEW MEXICO COUNTY: EDDY SURVEY: N.M.P.M  
 W.O. # 15-319 LEASE: RUNNING BUFFALO 1 FED COM



FLOW LINE OVERVIEW LAND STATUS 04/23/2015 S.P.

**CONCHO**  
 COG OPERATING, LLC

**HARCROW SURVEYING, LLC.**  
 2314 W. MAIN ST. ARTESIA, NM 88210  
 PH: (575) 746-2158 FAX: (575) 746-2158  
 charcrow@harcrowsurveying.com



# LEGEND

- WELL
- WELLPAD
- EXISTING ROAD
- - - PROPOSED ROAD
- TWO-TRACK ROAD

## RUNNING BUFFALO 1 FEDERAL COM #2H

SEC: 01 TWP: 21 S. RGE: 28 E. ELEVATION: 3445.0'

STATE: NEW MEXICO COUNTY: EDDY 1650' FSL & 1980' FEL

W.O. # 15-565 LEASE: RUNNING BUFFALO 1 FED COM SURVEY: N.M.P.M

0 2,500 5,000 7,500 10,000 12,500 15,000 FEET

0 0.4 0.8 1.6 Miles

1 IN = 6,000 FT

VICINITY MAP

05/01/2015

AF

**CONCHO**

COG OPERATING, LLC




HARCROW SURVEYING, LLC.

2314 W. MAIN ST, ARTESIA, NM 88210

PH: (575) 746-2158 FAX: (575) 746-2158

c.harcrow@harcrowsurveying.com



DATA FOR "WELLS WITHIN 1 MI." IS TAKEN FROM THE NEW MEXICO EMNRD WEBSITE. THE DATA HAS BEEN UPDATED THROUGH JANUARY 12, 2015.

# **LEGEND**


- WELL
- BOTTOMHOLE
- WELLS WITHIN 1 MI.
- 1 MI. BUFFER

## **RUNNING BUFFALO 1 FEDERAL COM #2H**

SEC: 01 TWP: 21 S. RGE: 28 E. ELEVATION: 3445.0'

STATE: NEW MEXICO COUNTY: EDDY 1650' FSL & 1980' FEL

W.O. # 15-565 LEASE: RUNNING BUFFALO 1 FED COM SURVEY: N.M.P.M



1 MILE MAP

05/01/2015

A.F.

**CONCHO**

COG OPERATING, LLC

**HARCROW SURVEYING, LLC.**

2314 W. MAIN ST, ARTESIA, NM 88210

PH: (575) 746-2158 FAX: (575) 746-2158

c.harcrow@harcrowsurveying.com



FID	Shape *	OPERATOR	WELL_NAME	LATITUDE	LONGITUDE	API	SECTION	TOWNSHIP	RANGE	FTG_NS	NS_CD	FTG_EW	EW_CD	TVD_DEPTH	COMPL_STAT
0	Point	COX ROBERT G	Cowan 001	32.514718	-104.038024	3001507459	1	21.05	28E	4620 S		1980 E		0	Plugged
1	Point	SOTO OIL CO	ZACHARY 001	32.52806	-104.035135	3001503675	36	20.05	29E	1980 S		660 W		0	Plugged
2	Point	FREN OIL CO	ENZINGER 002	32.510292	-104.020821	3001503683	6	21.05	29E	3300 S		3300 W		0	Plugged
3	Point	PERRY R BASS	BID EDDY UNIT 001	32.492943	-104.033715	3001520866	12	21.05	28E	1980 S		660 E		0	Plugged
4	Point	MEADCO PROPERTIES	BELL FEDERAL 002	32.52172	-104.047847	3001520919	1	21.05	28E	330 N		330 W		0	Plugged
5	Point	ENRON OIL & GAS CO	GOLDEN LANE 36 FED 001	32.528331	-104.026261	3001522788	36	20.05	29E	2080 S		1880 E		0	Plugged
6	Point	PENROC OIL CORP	GOLDEN LANE 1 FEDERAL 001	32.51499	-104.036947	3001523846	1	21.05	28E	4720 S		1650 E		12650	Plugged
7	Point	FREN OIL CO	MAX ENZINGER #2 002M	32.510288	-104.026186	3001533015	6	21.05	29E	3300 S		3300 E		0	Plugged
8	Point	COG OPERATING LLC	LOTSAWHISKEY FEDERAL 001	32.524432	-104.035143	3001533212	36	20.05	29E	660 S		660 W		12600	Active
9	Point	COG OPERATING LLC	H-UNT FEDERAL 001	32.517859	-104.029413	3001533786	6	21.05	29E	1730 N		660 W		0	New (Not drilled or compl)
10	Point	YATES PETROLEUM CORPORATION	SOBER BEZ FEDERAL 001	32.528066	-104.043742	3001534334	35	20.05	29E	1980 S		1980 E		12500	Active
11	Point	YATES PETROLEUM CORPORATION	TEMPERATE BEC FEDERAL 001	32.511729	-104.029424	3001534339	6	21.05	29E	3960 N		660 W		12740	Plugged
12	Point	COG OPERATING LLC	MUCHO CERVEZA FEDERAL 001	32.529215	-104.034709	3001535032	36	20.05	29E	2400 S		790 W		0	New (Not drilled or compl)
13	Point	MEWBOURNE OIL CO	DOS HERMANOS 6 FEDERAL 001	32.520496	-104.025105	3001536402	6	21.05	29E	770 N		1980 W		12800	Active
14	Point	COG OPERATING LLC	RUNNING BUFFALO 1 FEDERAL COM 001H	32.507454	-104.035123	3001541538	1	21.05	28E	1980 S		1090 E		13617	New (Not drilled or compl)
15	Point	YATES PETROLEUM CORPORATION	SOBER BEZ FEDERAL 002H	32.523171	-104.039449	3001540943	35	20.05	29E	200 S		660 E		0	New (Not drilled or compl)
16	Point	YATES PETROLEUM CORPORATION	SOBER BEZ FEDERAL 004H	32.522851	-104.043359	3001542724	35	20.05	29E	10 S		1930 E		0	New (Not drilled or compl)
17	Point	YATES PETROLEUM CORPORATION	BOLSA BRF FEDERAL COM 001H	32.522568	-104.043552	3001542704	1	21.05	28E	20 N		1650 W		0	New (Not drilled or compl)

# COG Operating LLC – Running Buffalo 1 Federal Com 2H

## 1. Geologic Formations

TVD of target	8570'	Pilot hole depth	NA
MD at TD:	13,876'	Deepest expected fresh water:	100

### Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone?	Hazards
Quaternary Fill	Surface	Water	
Rustler	464	Water	
Top of Salt	892	Salt	
Base of Salt	1554	Salt	
Yates	1777	Oil/Gas	
Reef	1837	Brackish Water	Loss Circulation
Delaware	3214	Oil/Gas	
Bone Spring Lime	6576	Oil/Gas	
U. Avalon Shale	6702	Oil/Gas	
L. Avalon Shale	7221	Oil/Gas	
1 <sup>st</sup> Bone Spring Sand	7670	Oil/Gas	
2 <sup>nd</sup> Bone Spring Sand	8384	Oil/Gas Target Zone	
3 <sup>rd</sup> Bone Spring Sand	9419	Oil/Gas	

## 2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
	From	To							
26"	0	490 850'	20"	94	J55	STC	2.27	1.84	12.6
17.5"	0	1600 1700'	13.375"	54.5	J55	STC	1.68	1.59	5.89
12.25"	0	3300	9.625"	36	J55	LTC	1.18	1.1	3.81
8.75"	0	13,876'	5.5"	17	P110	LTC	1.93	2.39	2.33
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	Y
If yes, does production casing cement tie back a minimum of 50' above the Reef?	

## COG Operating LLC – Running Buffalo 1 Federal Com 2H

Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

### 3. Cementing Program

Casing	# Sk	Wt. lb/gal	Yld ft <sup>3</sup> /sack	H <sub>2</sub> O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surf.	500	13.5	1.75	9	12	Lead: Class C + 4% Gel + 2% CaCl <sub>2</sub>
	250	14.8	1.34	6.34	8	Tail: Class C + 2% CaCl <sub>2</sub>
1 <sup>st</sup> Inter.	700	12.7	2	10.6	12	Lead: Econocem HLC 65:35:6 + 5% Salt
2 <sup>nd</sup> Int	250	14.8	1.34	6.34	8	Tail: Class C + 2% CaCl
1 <sup>st</sup> Stage	300	12.7	1.98	10.6	16	1 <sup>st</sup> stage Lead: Econocem HLC 65:35:6 + 5% Salt
	250	14.8	1.34	6.34	8	1 <sup>st</sup> stage Tail: Class C + 2% CaCl
2 <sup>nd</sup> Int	400	13.5	1.75	9.11	12	2 <sup>nd</sup> stage Lead: Class C + 4% Gel (DV @ ~1800')
	100	14.8	1.34	6.34	8	2 <sup>nd</sup> stage Tail: Class C + 2% CaCl
5.5 Prod 1 Stage	875	11.9	2.51	14.6	24	Lead: 50:50:10 H Blend
	1650	14.4	1.24	5.7	19	Tail: Versacem 50:50:2 Class H + 1% Salt

Plan on DV Tool set above Reef at approximately 1750'.

Volumes Subject to Observed Hole Conditions and/or Fluid Caliper Results

Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Casing/String	TOC	% Excess
Surface	0'	50%
1 <sup>st</sup> Intermediate	0'	50% OH
2 <sup>nd</sup> Intermediate 1 <sup>st</sup> Stage	1750'	50%
2 <sup>nd</sup> Intermediate 2 <sup>nd</sup> Stage	0	50% OH
Production	1600'	35% OH

## COG Operating LLC – Running Buffalo 1 Federal Com 2H

### 4. Pressure Control Equipment

N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
---	--

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
17-1/2"	20"	2M	Annular	x	2000 psi
			Blind Ram		2M
			Pipe Ram		
			Double Ram		
			Other*		
12-1/4"	13-5/8"	2M	Annular	x	2000 psi
			Blind Ram		2M
			Pipe Ram		
			Double Ram		
			Other*		
8-3/4"	13-5/8"	3M	Annular	x	50% testing pressure
			Blind Ram	x	3M
			Pipe Ram	x	
			Double Ram		
			Other*		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
N	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?
N	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

## COG Operating LLC – Running Buffalo 1 Federal Com 2H

### 5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	Surf. Csg pt	FW Gel	8.6-8.8	28-34	N/C
Surf csg	13-3/8" csg pt	Saturated Brine	10.0-10.2	28-34	N/C
13-3/8"	9-5/8" csg pt	Fresh Water	8.4-8.6	28-34	N/C
9-5/8"	Lateral TD	Cut Brine	8.6 – 9.4	28-34	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

### 6. Logging and Testing Procedures

Logging, Coring and Testing	
Y	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
N	No Logs are planned based on well control or offset log information.
N	Drill stem test? If yes, explain
N	Coring? If yes, explain

Additional logs planned	Interval
N	Resistivity
N	Density
Y	CBL Production casing (If cement not circulated to surface)
Y	Mud log Intermediate shoe to TD
N	PEX

### 7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	4085 psi at 8570' TVD (EOC - Lateral)
Abnormal Temperature	NO

No abnormal pressure or temperature conditions are anticipated. Sufficient mud materials to maintain mud properties and weight increase requirements will be kept on location at all times. Sufficient supplies of Paper/LCM for periodic sweeps to control seepage and losses will be maintained on location.

Hydrogen Sulfide (H <sub>2</sub> S) monitors will be installed prior to drilling out the surface shoe. If H <sub>2</sub> S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
N	H <sub>2</sub> S is present
Y	H <sub>2</sub> S Plan attached





## **COG Operating LLC**

Eddy County, NM

Running Buffalo Federal Com

#2H

OH

Plan: Design #1

## **Standard Planning Report**

29 April, 2015



# Wellplanning Planning Report

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Running Buffalo Federal Com
Company:	COG Operating LLC	TVD Reference:	WELL @ 3461.2usft (Original Well Elev)
Project:	Eddy County, NM	MD Reference:	WELL @ 3461.2usft (Original Well Elev)
Site:	Running Buffalo Federal Com	North Reference:	Grid
Well:	#2H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Design #1		

Project	Eddy County, NM		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site	Running Buffalo Federal Com		
Site Position:	Northing:	548,081.60 usft	Latitude: 32° 30' 23.178 N
From: Map	Easting:	591,245.00 usft	Longitude: 104° 2' 14.466 W
Position Uncertainty:	0.0 usft	Slot Radius: 13-3/16 "	Grid Convergence: 0.16 °

Well	#2H		
Well Position	+N/-S	0.0 usft	Northing: 548,081.60 usft
	+E/-W	0.0 usft	Easting: 591,245.00 usft
Position Uncertainty	0.0 usft	Wellhead Elevation:	Ground Level: 3,443.2 usft

Wellbore	OH		
Magnetics	Model Name	Sample Date	Declination
			(°)
	IGRF2010	11/12/2014	7.40
			Dip Angle (°)
			60.28
			Field Strength (nT)
			48,394

Design	Design #1		
Audit Notes:			
Version:	Phase:	PLAN	Tie On Depth: 0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)
	0.0	0.0	0.0
			Direction (°)
			359.87

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
8,092.5	0.00	0.00	8,092.5	0.0	0.0	0.00	0.00	0.00	0.00	
8,842.6	90.00	359.87	8,570.0	477.5	-1.1	12.00	12.00	0.00	359.87	
13,876.0	90.00	359.87	8,570.0	5,510.9	-12.5	0.00	0.00	0.00	0.00	PBHL(RB1FC)





# Wellplanning Planning Report

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Running Buffalo Federal Com
Company:	COG Operating LLC	TVD Reference:	WELL @ 3461.2usft (Original Well Elev)
Project:	Eddy County, NM	MD Reference:	WELL @ 3461.2usft (Original Well Elev)
Site:	Running Buffalo Federal Com	North Reference:	Grid
Well:	#2H	Survey Calculation Method:	Minimum Curvature
Wallbore:	OH		
Design:	Design #1		

## Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00
2,400.0	0.00	0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00
2,500.0	0.00	0.00	2,500.0	0.0	0.0	0.0	0.00	0.00	0.00
2,600.0	0.00	0.00	2,600.0	0.0	0.0	0.0	0.00	0.00	0.00
2,700.0	0.00	0.00	2,700.0	0.0	0.0	0.0	0.00	0.00	0.00
2,800.0	0.00	0.00	2,800.0	0.0	0.0	0.0	0.00	0.00	0.00
2,900.0	0.00	0.00	2,900.0	0.0	0.0	0.0	0.00	0.00	0.00
3,000.0	0.00	0.00	3,000.0	0.0	0.0	0.0	0.00	0.00	0.00
3,100.0	0.00	0.00	3,100.0	0.0	0.0	0.0	0.00	0.00	0.00
3,200.0	0.00	0.00	3,200.0	0.0	0.0	0.0	0.00	0.00	0.00
3,300.0	0.00	0.00	3,300.0	0.0	0.0	0.0	0.00	0.00	0.00
3,400.0	0.00	0.00	3,400.0	0.0	0.0	0.0	0.00	0.00	0.00
3,500.0	0.00	0.00	3,500.0	0.0	0.0	0.0	0.00	0.00	0.00
3,600.0	0.00	0.00	3,600.0	0.0	0.0	0.0	0.00	0.00	0.00
3,700.0	0.00	0.00	3,700.0	0.0	0.0	0.0	0.00	0.00	0.00
3,800.0	0.00	0.00	3,800.0	0.0	0.0	0.0	0.00	0.00	0.00
3,900.0	0.00	0.00	3,900.0	0.0	0.0	0.0	0.00	0.00	0.00
4,000.0	0.00	0.00	4,000.0	0.0	0.0	0.0	0.00	0.00	0.00
4,100.0	0.00	0.00	4,100.0	0.0	0.0	0.0	0.00	0.00	0.00
4,200.0	0.00	0.00	4,200.0	0.0	0.0	0.0	0.00	0.00	0.00
4,300.0	0.00	0.00	4,300.0	0.0	0.0	0.0	0.00	0.00	0.00
4,400.0	0.00	0.00	4,400.0	0.0	0.0	0.0	0.00	0.00	0.00
4,500.0	0.00	0.00	4,500.0	0.0	0.0	0.0	0.00	0.00	0.00
4,600.0	0.00	0.00	4,600.0	0.0	0.0	0.0	0.00	0.00	0.00
4,700.0	0.00	0.00	4,700.0	0.0	0.0	0.0	0.00	0.00	0.00
4,800.0	0.00	0.00	4,800.0	0.0	0.0	0.0	0.00	0.00	0.00
4,900.0	0.00	0.00	4,900.0	0.0	0.0	0.0	0.00	0.00	0.00
5,000.0	0.00	0.00	5,000.0	0.0	0.0	0.0	0.00	0.00	0.00
5,100.0	0.00	0.00	5,100.0	0.0	0.0	0.0	0.00	0.00	0.00
5,200.0	0.00	0.00	5,200.0	0.0	0.0	0.0	0.00	0.00	0.00
5,300.0	0.00	0.00	5,300.0	0.0	0.0	0.0	0.00	0.00	0.00



# Wellplanning Planning Report

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Running Buffalo Federal Com
Company:	COG Operating LLC	TVD Reference:	WELL @ 3461.2usft (Original Well Elev)
Project:	Eddy County, NM	MD Reference:	WELL @ 3461.2usft (Original Well Elev)
Site:	Running Buffalo Federal Com	North Reference:	Grid
Well:	#2H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Design #1		

## Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,400.0	0.00	0.00	5,400.0	0.0	0.0	0.0	0.00	0.00	0.00
5,500.0	0.00	0.00	5,500.0	0.0	0.0	0.0	0.00	0.00	0.00
5,600.0	0.00	0.00	5,600.0	0.0	0.0	0.0	0.00	0.00	0.00
5,700.0	0.00	0.00	5,700.0	0.0	0.0	0.0	0.00	0.00	0.00
5,800.0	0.00	0.00	5,800.0	0.0	0.0	0.0	0.00	0.00	0.00
5,900.0	0.00	0.00	5,900.0	0.0	0.0	0.0	0.00	0.00	0.00
6,000.0	0.00	0.00	6,000.0	0.0	0.0	0.0	0.00	0.00	0.00
6,100.0	0.00	0.00	6,100.0	0.0	0.0	0.0	0.00	0.00	0.00
6,200.0	0.00	0.00	6,200.0	0.0	0.0	0.0	0.00	0.00	0.00
6,300.0	0.00	0.00	6,300.0	0.0	0.0	0.0	0.00	0.00	0.00
6,400.0	0.00	0.00	6,400.0	0.0	0.0	0.0	0.00	0.00	0.00
6,500.0	0.00	0.00	6,500.0	0.0	0.0	0.0	0.00	0.00	0.00
6,600.0	0.00	0.00	6,600.0	0.0	0.0	0.0	0.00	0.00	0.00
6,700.0	0.00	0.00	6,700.0	0.0	0.0	0.0	0.00	0.00	0.00
6,800.0	0.00	0.00	6,800.0	0.0	0.0	0.0	0.00	0.00	0.00
6,900.0	0.00	0.00	6,900.0	0.0	0.0	0.0	0.00	0.00	0.00
7,000.0	0.00	0.00	7,000.0	0.0	0.0	0.0	0.00	0.00	0.00
7,100.0	0.00	0.00	7,100.0	0.0	0.0	0.0	0.00	0.00	0.00
7,200.0	0.00	0.00	7,200.0	0.0	0.0	0.0	0.00	0.00	0.00
7,300.0	0.00	0.00	7,300.0	0.0	0.0	0.0	0.00	0.00	0.00
7,400.0	0.00	0.00	7,400.0	0.0	0.0	0.0	0.00	0.00	0.00
7,500.0	0.00	0.00	7,500.0	0.0	0.0	0.0	0.00	0.00	0.00
7,600.0	0.00	0.00	7,600.0	0.0	0.0	0.0	0.00	0.00	0.00
7,700.0	0.00	0.00	7,700.0	0.0	0.0	0.0	0.00	0.00	0.00
7,800.0	0.00	0.00	7,800.0	0.0	0.0	0.0	0.00	0.00	0.00
7,900.0	0.00	0.00	7,900.0	0.0	0.0	0.0	0.00	0.00	0.00
8,000.0	0.00	0.00	8,000.0	0.0	0.0	0.0	0.00	0.00	0.00
8,092.5	0.00	0.00	8,092.5	0.0	0.0	0.0	0.00	0.00	0.00
KOP - 8092.5 'MD, 0.00° INC, 0.00° AZI									
8,100.0	0.90	359.87	8,100.0	0.1	0.0	0.1	12.00	12.00	0.00
8,125.0	3.90	359.87	8,125.0	1.1	0.0	1.1	12.00	12.00	0.00
8,150.0	6.90	359.87	8,149.9	3.5	0.0	3.5	12.00	12.00	0.00
8,175.0	9.90	359.87	8,174.6	7.1	0.0	7.1	12.00	12.00	0.00
8,200.0	12.90	359.87	8,199.1	12.0	0.0	12.0	12.00	12.00	0.00
8,225.0	15.90	359.87	8,223.3	18.3	0.0	18.3	12.00	12.00	0.00
8,250.0	18.90	359.87	8,247.2	25.7	-0.1	25.7	12.00	12.00	0.00
8,275.0	21.90	359.87	8,270.6	34.5	-0.1	34.5	12.00	12.00	0.00
8,300.0	24.90	359.87	8,293.5	44.4	-0.1	44.4	12.00	12.00	0.00
8,325.0	27.90	359.87	8,315.9	55.5	-0.1	55.5	12.00	12.00	0.00
8,350.0	30.90	359.87	8,337.7	67.8	-0.2	67.8	12.00	12.00	0.00
8,375.0	33.90	359.87	8,358.8	81.2	-0.2	81.2	12.00	12.00	0.00
8,400.0	36.90	359.87	8,379.2	95.6	-0.2	95.6	12.00	12.00	0.00
8,425.0	39.90	359.87	8,398.8	111.2	-0.3	111.2	12.00	12.00	0.00
8,450.0	42.90	359.87	8,417.5	127.7	-0.3	127.7	12.00	12.00	0.00
8,475.0	45.90	359.87	8,435.4	145.2	-0.3	145.2	12.00	12.00	0.00
8,500.0	48.90	359.87	8,452.3	163.6	-0.4	163.6	12.00	12.00	0.00
8,525.0	51.90	359.87	8,468.2	182.8	-0.4	182.8	12.00	12.00	0.00
8,550.0	54.90	359.87	8,483.1	202.9	-0.5	202.9	12.00	12.00	0.00
8,575.0	57.90	359.87	8,497.0	223.7	-0.5	223.7	12.00	12.00	0.00
8,600.0	60.90	359.87	8,509.7	245.2	-0.6	245.2	12.00	12.00	0.00
8,625.0	63.90	359.87	8,521.3	267.4	-0.6	267.4	12.00	12.00	0.00
8,650.0	66.90	359.87	8,531.7	290.1	-0.7	290.1	12.00	12.00	0.00
8,675.0	69.89	359.87	8,540.9	313.4	-0.7	313.4	12.00	12.00	0.00



# Wellplanning Planning Report

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Running Buffalo Federal Com
Company:	COG Operating LLC	TVD Reference:	WELL @ 3461.2usft (Original Well Elev)
Project:	Eddy County, NM	MD Reference:	WELL @ 3461.2usft (Original Well Elev)
Site:	Running Buffalo Federal Com	North Reference:	Grid
Well:	#2H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
8,700.0	72.89	359.87	8,548.9	337.1	-0.8	337.1	12.00	12.00	0.00	
8,725.0	75.89	359.87	8,555.6	361.1	-0.8	361.1	12.00	12.00	0.00	
8,750.0	78.89	359.87	8,561.1	385.5	-0.9	385.5	12.00	12.00	0.00	
8,775.0	81.89	359.87	8,565.2	410.2	-0.9	410.2	12.00	12.00	0.00	
8,800.0	84.89	359.87	8,568.1	435.0	-1.0	435.0	12.00	12.00	0.00	
8,825.0	87.89	359.87	8,569.7	459.9	-1.0	459.9	12.00	12.00	0.00	
8,842.6	90.00	359.87	8,570.0	477.5	-1.1	477.5	12.00	12.00	0.00	
EOC- 8842.6 'MD, 90.00° INC, 359.87° AZI										
8,900.0	90.00	359.87	8,570.0	534.9	-1.2	534.9	0.00	0.00	0.00	
9,000.0	90.00	359.87	8,570.0	634.9	-1.4	634.9	0.00	0.00	0.00	
9,100.0	90.00	359.87	8,570.0	734.9	-1.7	734.9	0.00	0.00	0.00	
9,200.0	90.00	359.87	8,570.0	834.9	-1.9	834.9	0.00	0.00	0.00	
9,300.0	90.00	359.87	8,570.0	934.9	-2.1	934.9	0.00	0.00	0.00	
9,400.0	90.00	359.87	8,570.0	1,034.9	-2.3	1,034.9	0.00	0.00	0.00	
9,500.0	90.00	359.87	8,570.0	1,134.9	-2.6	1,134.9	0.00	0.00	0.00	
9,600.0	90.00	359.87	8,570.0	1,234.9	-2.8	1,234.9	0.00	0.00	0.00	
9,700.0	90.00	359.87	8,570.0	1,334.9	-3.0	1,334.9	0.00	0.00	0.00	
9,800.0	90.00	359.87	8,570.0	1,434.9	-3.3	1,434.9	0.00	0.00	0.00	
9,900.0	90.00	359.87	8,570.0	1,534.9	-3.5	1,534.9	0.00	0.00	0.00	
10,000.0	90.00	359.87	8,570.0	1,634.9	-3.7	1,634.9	0.00	0.00	0.00	
10,100.0	90.00	359.87	8,570.0	1,734.9	-3.9	1,734.9	0.00	0.00	0.00	
10,200.0	90.00	359.87	8,570.0	1,834.9	-4.2	1,834.9	0.00	0.00	0.00	
10,300.0	90.00	359.87	8,570.0	1,934.9	-4.4	1,934.9	0.00	0.00	0.00	
10,400.0	90.00	359.87	8,570.0	2,034.9	-4.6	2,034.9	0.00	0.00	0.00	
10,500.0	90.00	359.87	8,570.0	2,134.9	-4.8	2,134.9	0.00	0.00	0.00	
10,600.0	90.00	359.87	8,570.0	2,234.9	-5.1	2,234.9	0.00	0.00	0.00	
10,700.0	90.00	359.87	8,570.0	2,334.9	-5.3	2,334.9	0.00	0.00	0.00	
10,800.0	90.00	359.87	8,570.0	2,434.9	-5.5	2,434.9	0.00	0.00	0.00	
10,900.0	90.00	359.87	8,570.0	2,534.9	-5.8	2,534.9	0.00	0.00	0.00	
11,000.0	90.00	359.87	8,570.0	2,634.9	-6.0	2,634.9	0.00	0.00	0.00	
11,100.0	90.00	359.87	8,570.0	2,734.9	-6.2	2,734.9	0.00	0.00	0.00	
11,200.0	90.00	359.87	8,570.0	2,834.9	-6.4	2,834.9	0.00	0.00	0.00	
11,300.0	90.00	359.87	8,570.0	2,934.9	-6.7	2,934.9	0.00	0.00	0.00	
11,400.0	90.00	359.87	8,570.0	3,034.9	-6.9	3,034.9	0.00	0.00	0.00	
11,500.0	90.00	359.87	8,570.0	3,134.9	-7.1	3,134.9	0.00	0.00	0.00	
11,600.0	90.00	359.87	8,570.0	3,234.9	-7.3	3,234.9	0.00	0.00	0.00	
11,700.0	90.00	359.87	8,570.0	3,334.9	-7.6	3,334.9	0.00	0.00	0.00	
11,800.0	90.00	359.87	8,570.0	3,434.9	-7.8	3,434.9	0.00	0.00	0.00	
11,900.0	90.00	359.87	8,570.0	3,534.9	-8.0	3,534.9	0.00	0.00	0.00	
12,000.0	90.00	359.87	8,570.0	3,634.9	-8.2	3,634.9	0.00	0.00	0.00	
12,100.0	90.00	359.87	8,570.0	3,734.9	-8.5	3,734.9	0.00	0.00	0.00	
12,200.0	90.00	359.87	8,570.0	3,834.9	-8.7	3,834.9	0.00	0.00	0.00	
12,300.0	90.00	359.87	8,570.0	3,934.9	-8.9	3,934.9	0.00	0.00	0.00	
12,400.0	90.00	359.87	8,570.0	4,034.9	-9.2	4,034.9	0.00	0.00	0.00	
12,500.0	90.00	359.87	8,570.0	4,134.9	-9.4	4,134.9	0.00	0.00	0.00	
12,600.0	90.00	359.87	8,570.0	4,234.9	-9.6	4,234.9	0.00	0.00	0.00	
12,700.0	90.00	359.87	8,570.0	4,334.9	-9.8	4,334.9	0.00	0.00	0.00	
12,800.0	90.00	359.87	8,570.0	4,434.9	-10.1	4,434.9	0.00	0.00	0.00	
12,900.0	90.00	359.87	8,570.0	4,534.9	-10.3	4,534.9	0.00	0.00	0.00	
13,000.0	90.00	359.87	8,570.0	4,634.9	-10.5	4,634.9	0.00	0.00	0.00	
13,100.0	90.00	359.87	8,570.0	4,734.9	-10.7	4,734.9	0.00	0.00	0.00	
13,200.0	90.00	359.87	8,570.0	4,834.9	-11.0	4,834.9	0.00	0.00	0.00	
13,300.0	90.00	359.87	8,570.0	4,934.9	-11.2	4,934.9	0.00	0.00	0.00	
13,400.0	90.00	359.87	8,570.0	5,034.9	-11.4	5,034.9	0.00	0.00	0.00	



# Wellplanning Planning Report

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Running Buffalo Federal Com
Company:	COG Operating LLC	TVD Reference:	WELL @ 3461.2usft (Original Well Elev)
Project:	Eddy County, NM	MD Reference:	WELL @ 3461.2usft (Original Well Elev)
Site:	Running Buffalo Federal Com	North Reference:	Grid
Well:	#2H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Design #1		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
13,500.0	90.00	359.87	8,570.0	5,134.9	-11.7	5,134.9	0.00	0.00	0.00	
13,600.0	90.00	359.87	8,570.0	5,234.9	-11.9	5,234.9	0.00	0.00	0.00	
13,700.0	90.00	359.87	8,570.0	5,334.9	-12.1	5,334.9	0.00	0.00	0.00	
13,800.0	90.00	359.87	8,570.0	5,434.9	-12.3	5,434.9	0.00	0.00	0.00	
13,876.0	90.00	359.87	8,570.0	5,510.9	-12.5	5,510.9	0.00	0.00	0.00	
TD at 13876.0 - PBHL(RB1FC)										

Design Targets										
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude	
- hit/miss target										
- Shape										
PBHL(RB1FC)	0.00	0.00	8,570.0	5,510.9	-12.3	553,592.50	591,232.70	32° 31' 17.713 N	104° 2' 14.431 W	
- plan misses target center by 0.2usft at 13876.0usft MD (8570.0 TVD, 5510.9 N, -12.5 E)										
- Point										

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Comment	
8,092.5	8,092.5	0.0	0.0	KOP - 8092.5 'MD, 0.00° INC, 0.00° AZI	
8,842.6	8,570.0	477.5	-1.1	EOC- 8842.6 'MD, 90.00° INC, 359.87° AZI	
13,876.0	8,570.0	5,510.9	-12.5	TD at 13876.0	




COG Operating LLC  
Project: Eddy County, NM  
Site: Running Buffalo Federal Com  
Well: #2H

Plan: Design #1 (#2H/OH)

WELL DETAILS: #2H

Ground Elevation: 3443.2  
RKB Elevation: WELL @ 3461.2usft (Original Well Elev)  
Rig Name: Original Well Elev

Northing 548081.60  
Easting 591245.00  
Latitude 32° 30' 23.178 N  
Longitude 104° 2' 14.466 W





### Section Details

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSecl
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0
2	8092.5	0.00	0.00	8092.5	0.0	0.0	0.00	0.00	0.0
3	8842.6	90.00	359.87	8570.0	477.5	-1.1	12.00	359.87	477.5
4	13876.0	90.00	359.87	8570.0	5510.9	-12.5	0.00	0.00	5510.9

PBHL(RB1FC)

West(-)/East(+) (50 usft/in)



True Vertical Depth (200 usft/in)

0° KOP - 8092.5 MD, 0.00° INC, 0.00° AZI

EOC: 8842.6 MD, 90.00° INC, 359.87° AZI

TD at 13876.0

**NEXUS**  
DIRECTIONAL SOLUTIONS, L.P.

Vertical Section at 359.87° (200 usft/in)

Nexus Directional Solutions

PROJECT DETAILS: Eddy County, NM  
Geodetic System: US State Plane 1927 (Exact solution)  
Datum: NAD 1927 (NADCON CONUS)  
Ellipsoid: Clarke 1866  
Zone: New Mexico East 3001  
System Datum: Mean Sea Level  
Local North: Grid

# **COG Operating LLC**

Eddy County, NM

Running Buffalo Federal Com

#2H

OH

Plan #2

## **Anticollision Report**

27 April, 2016

## Integrity Directional Services, LLC

### Anticollision Report

<b>Company:</b>	COG Operating LLC	<b>Local Co-ordinate Reference:</b>	Well #2H
<b>Project:</b>	Eddy County, NM	<b>TVD Reference:</b>	WELL @ 3461.2usft (Original Well Elev)
<b>Reference Site:</b>	Running Buffalo Federal Com	<b>MD Reference:</b>	WELL @ 3461.2usft (Original Well Elev)
<b>Site Error:</b>	0.0 usft	<b>North Reference:</b>	Grid
<b>Reference Well:</b>	#2H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.0 usft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	OH	<b>Database:</b>	EDM 5000.1 Multi User Db
<b>Reference Design:</b>	Plan #2	<b>Offset TVD Reference:</b>	Offset Datum

Reference	Plan #2		
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria		
Interpolation Method:	MD Interval 100.0usft	Error Model:	ISCWSA
Depth Range:	0.0 to 100,000.0usft	Scan Method:	Closest Approach 3D
Results Limited by:	Maximum center-center distance of 10,000.0 us	Error Surface:	Elliptical Conic
Warning Levels Evaluated at:	2.00 Sigma	Casing Method:	Not applied

Survey Tool Program		Date	4/27/2016	
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description
0.0	13,885.7	Plan #2 (OH)	MWD	MWD - Standard

Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
Running Buffalo Federal Com						
Golden Lane 1 Fed 1 - Wellbore #1 - Wellbore #1	11,436.1	8,815.8	159.2	-11,661.1	0.013	Level 1, CC, ES, SF

Offset Design												Running Buffalo Federal Com - Golden Lane 1 Fed 1 - Wellbore #1 - Wellbore #1		Offset Site Error: 0.0 usft	
Survey Program: 12540-BLIND												Offset Well Error: 0.0 usft			
Reference		Offset		Semi Major Axis		Highside Tooface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
0.0	0.0	245.8	245.8	0.0	327.9	0.00	3,070.0	0.0	3,070.0						
100.0	100.0	345.8	345.8	0.1	461.4	0.00	3,070.0	0.0	3,070.0	2,608.5	461.46	6.653			
200.0	200.0	445.8	445.8	0.3	594.8	0.00	3,070.0	0.0	3,070.0	2,474.9	595.10	5.159			
300.0	300.0	545.8	545.8	0.5	728.2	0.00	3,070.0	0.0	3,070.0	2,341.3	728.75	4.213			
400.0	400.0	645.8	645.8	0.8	861.6	0.00	3,070.0	0.0	3,070.0	2,207.6	862.39	3.560			
500.0	500.0	745.8	745.8	1.0	995.0	0.00	3,070.0	0.0	3,070.0	2,074.0	996.04	3.082			
600.0	600.0	845.8	845.8	1.2	1,128.5	0.00	3,070.0	0.0	3,070.0	1,940.3	1,129.68	2.718			
700.0	700.0	945.8	945.8	1.4	1,261.9	0.00	3,070.0	0.0	3,070.0	1,806.7	1,263.33	2.430			
800.0	800.0	1,045.8	1,045.8	1.7	1,395.3	0.00	3,070.0	0.0	3,070.0	1,673.0	1,396.97	2.198			
900.0	900.0	1,145.8	1,145.8	1.9	1,528.7	0.00	3,070.0	0.0	3,070.0	1,539.4	1,530.62	2.006			
1,000.0	1,000.0	1,245.8	1,245.8	2.1	1,662.1	0.00	3,070.0	0.0	3,070.0	1,405.7	1,664.26	1.845			
1,100.0	1,100.0	1,345.8	1,345.8	2.3	1,795.6	0.00	3,070.0	0.0	3,070.0	1,272.1	1,797.91	1.708			
1,200.0	1,200.0	1,445.8	1,445.8	2.6	1,929.0	0.00	3,070.0	0.0	3,070.0	1,138.4	1,931.55	1.589			
1,300.0	1,300.0	1,545.8	1,545.8	2.8	2,062.4	0.00	3,070.0	0.0	3,070.0	1,004.8	2,065.19	1.487	Level 3		
1,400.0	1,400.0	1,645.8	1,645.8	3.0	2,195.8	0.00	3,070.0	0.0	3,070.0	871.2	2,198.84	1.396	Level 3		
1,500.0	1,500.0	1,745.8	1,745.8	3.2	2,329.2	0.00	3,070.0	0.0	3,070.0	737.5	2,332.48	1.316	Level 3		
1,600.0	1,600.0	1,845.8	1,845.8	3.5	2,462.7	0.00	3,070.0	0.0	3,070.0	603.9	2,466.13	1.245	Level 2		
1,700.0	1,700.0	1,945.8	1,945.8	3.7	2,596.1	0.00	3,070.0	0.0	3,070.0	470.2	2,599.77	1.181	Level 2		
1,800.0	1,800.0	2,045.8	2,045.8	3.9	2,729.5	0.00	3,070.0	0.0	3,070.0	336.6	2,733.42	1.123	Level 2		
1,900.0	1,900.0	2,145.8	2,145.8	4.1	2,862.9	0.00	3,070.0	0.0	3,070.0	202.9	2,867.06	1.071	Level 2		
2,000.0	2,000.0	2,245.8	2,245.8	4.4	2,996.3	0.00	3,070.0	0.0	3,070.0	69.3	3,000.71	1.023	Level 2		
2,100.0	2,100.0	2,345.8	2,345.8	4.6	3,129.8	0.00	3,070.0	0.0	3,070.0	-64.4	3,134.35	0.979	Level 1		
2,200.0	2,200.0	2,445.8	2,445.8	4.8	3,263.2	0.00	3,070.0	0.0	3,070.0	-198.0	3,268.00	0.939	Level 1		
2,300.0	2,300.0	2,545.8	2,545.8	5.0	3,396.6	0.00	3,070.0	0.0	3,070.0	-331.6	3,401.64	0.903	Level 1		
2,400.0	2,400.0	2,645.8	2,645.8	5.3	3,530.0	0.00	3,070.0	0.0	3,070.0	-465.3	3,535.29	0.868	Level 1		
2,500.0	2,500.0	2,745.8	2,745.8	5.5	3,663.4	0.00	3,070.0	0.0	3,070.0	-598.9	3,668.93	0.837	Level 1		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

# Integrity Directional Services, LLC

## Anticollision Report

<b>Company:</b>	COG Operating LLC	<b>Local Co-ordinate Reference:</b>	Well #2H
<b>Project:</b>	Eddy County, NM	<b>TVD Reference:</b>	WELL @ 3461.2usft (Original Well Elev)
<b>Reference Site:</b>	Running Buffalo Federal Com	<b>MD Reference:</b>	WELL @ 3461.2usft (Original Well Elev)
<b>Site Error:</b>	0.0 usft	<b>North Reference:</b>	Grid
<b>Reference Well:</b>	#2H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.0 usft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	OH	<b>Database:</b>	EDM 5000.1 Multi User Db
<b>Reference Design:</b>	Plan #2	<b>Offset TVD Reference:</b>	Offset Datum

<b>Offset Design:</b> Running Buffalo Federal Com - Golden Lane 1 Fed 1 - Wellbore #1 - Wellbore #1													<b>Offset Site Error:</b> 0.0 usft
<b>Survey Program:</b> 12540-BLIND													<b>Offset Well Error:</b> 0.0 usft
Reference	Offset	Semi Major Axis		Distance		Minimum Separation		Warning					
Measured Vertical Depth (usft)	Vertical Depth (usft)	Measured Vertical Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
2,600.0	2,600.0	2,845.8	2,845.8	5.7	3,796.9	0.00	3,070.0	0.0	3,070.0	-732.6	3,802.58	0.807	Level 1
2,700.0	2,700.0	2,945.8	2,945.8	5.9	3,930.3	0.00	3,070.0	0.0	3,070.0	-866.2	3,936.22	0.780	Level 1
2,800.0	2,800.0	3,045.8	3,045.8	6.2	4,063.7	0.00	3,070.0	0.0	3,070.0	-999.9	4,069.87	0.754	Level 1
2,900.0	2,900.0	3,145.8	3,145.8	6.4	4,197.1	0.00	3,070.0	0.0	3,070.0	-1,133.5	4,203.51	0.730	Level 1
3,000.0	3,000.0	3,245.8	3,245.8	6.6	4,330.5	0.00	3,070.0	0.0	3,070.0	-1,267.2	4,337.15	0.708	Level 1
3,100.0	3,100.0	3,345.8	3,345.8	6.8	4,464.0	0.00	3,070.0	0.0	3,070.0	-1,400.8	4,470.80	0.687	Level 1
3,200.0	3,200.0	3,445.8	3,445.8	7.1	4,597.4	0.00	3,070.0	0.0	3,070.0	-1,534.4	4,604.44	0.667	Level 1
3,300.0	3,300.0	3,545.8	3,545.8	7.3	4,730.8	0.00	3,070.0	0.0	3,070.0	-1,668.1	4,738.09	0.648	Level 1
3,400.0	3,400.0	3,645.8	3,645.8	7.5	4,864.2	0.00	3,070.0	0.0	3,070.0	-1,801.7	4,871.73	0.630	Level 1
3,500.0	3,500.0	3,745.8	3,745.8	7.7	4,997.6	0.00	3,070.0	0.0	3,070.0	-1,935.4	5,005.38	0.613	Level 1
3,600.0	3,600.0	3,845.8	3,845.8	8.0	5,131.1	0.00	3,070.0	0.0	3,070.0	-2,069.0	5,139.02	0.597	Level 1
3,700.0	3,700.0	3,945.8	3,945.8	8.2	5,264.5	0.00	3,070.0	0.0	3,070.0	-2,202.7	5,272.67	0.582	Level 1
3,800.0	3,800.0	4,045.8	4,045.8	8.4	5,397.9	0.00	3,070.0	0.0	3,070.0	-2,336.3	5,406.31	0.568	Level 1
3,900.0	3,900.0	4,145.8	4,145.8	8.6	5,531.3	0.00	3,070.0	0.0	3,070.0	-2,470.0	5,539.96	0.554	Level 1
4,000.0	4,000.0	4,245.8	4,245.8	8.9	5,664.7	0.00	3,070.0	0.0	3,070.0	-2,603.6	5,673.60	0.541	Level 1
4,100.0	4,100.0	4,345.8	4,345.8	9.1	5,798.2	0.00	3,070.0	0.0	3,070.0	-2,737.2	5,807.25	0.529	Level 1
4,200.0	4,200.0	4,445.8	4,445.8	9.3	5,931.6	0.00	3,070.0	0.0	3,070.0	-2,870.9	5,940.89	0.517	Level 1
4,300.0	4,300.0	4,545.8	4,545.8	9.5	6,065.0	0.00	3,070.0	0.0	3,070.0	-3,004.5	6,074.54	0.505	Level 1
4,400.0	4,400.0	4,645.8	4,645.8	9.8	6,198.4	0.00	3,070.0	0.0	3,070.0	-3,138.2	6,208.18	0.495	Level 1
4,500.0	4,500.0	4,745.8	4,745.8	10.0	6,331.8	0.00	3,070.0	0.0	3,070.0	-3,271.8	6,341.83	0.484	Level 1
4,600.0	4,600.0	4,845.8	4,845.8	10.2	6,465.3	0.00	3,070.0	0.0	3,070.0	-3,405.5	6,475.47	0.474	Level 1
4,700.0	4,700.0	4,945.8	4,945.8	10.4	6,598.7	0.00	3,070.0	0.0	3,070.0	-3,539.1	6,609.11	0.465	Level 1
4,800.0	4,800.0	5,045.8	5,045.8	10.7	6,732.1	0.00	3,070.0	0.0	3,070.0	-3,672.8	6,742.76	0.455	Level 1
4,900.0	4,900.0	5,145.8	5,145.8	10.9	6,865.5	0.00	3,070.0	0.0	3,070.0	-3,806.4	6,876.40	0.446	Level 1
5,000.0	5,000.0	5,245.8	5,245.8	11.1	6,998.9	0.00	3,070.0	0.0	3,070.0	-3,940.0	7,010.05	0.438	Level 1
5,100.0	5,100.0	5,345.8	5,345.8	11.3	7,132.4	0.00	3,070.0	0.0	3,070.0	-4,073.7	7,143.69	0.430	Level 1
5,200.0	5,200.0	5,445.8	5,445.8	11.6	7,265.8	0.00	3,070.0	0.0	3,070.0	-4,207.3	7,277.34	0.422	Level 1
5,300.0	5,300.0	5,545.8	5,545.8	11.8	7,399.2	0.00	3,070.0	0.0	3,070.0	-4,341.0	7,410.98	0.414	Level 1
5,400.0	5,400.0	5,645.8	5,645.8	12.0	7,532.6	0.00	3,070.0	0.0	3,070.0	-4,474.6	7,544.63	0.407	Level 1
5,500.0	5,500.0	5,745.8	5,745.8	12.2	7,666.0	0.00	3,070.0	0.0	3,070.0	-4,608.3	7,678.27	0.400	Level 1
5,600.0	5,600.0	5,845.8	5,845.8	12.5	7,799.5	0.00	3,070.0	0.0	3,070.0	-4,741.9	7,811.92	0.393	Level 1
5,700.0	5,700.0	5,945.8	5,945.8	12.7	7,932.9	0.00	3,070.0	0.0	3,070.0	-4,875.8	7,945.56	0.386	Level 1
5,800.0	5,800.0	6,045.8	6,045.8	12.9	8,066.3	0.00	3,070.0	0.0	3,070.0	-5,009.2	8,079.21	0.380	Level 1
5,900.0	5,900.0	6,145.8	6,145.8	13.1	8,199.7	0.00	3,070.0	0.0	3,070.0	-5,142.9	8,212.85	0.374	Level 1
6,000.0	6,000.0	6,245.8	6,245.8	13.4	8,333.1	0.00	3,070.0	0.0	3,070.0	-5,276.5	8,346.50	0.368	Level 1
6,100.0	6,100.0	6,345.8	6,345.8	13.6	8,466.6	0.00	3,070.0	0.0	3,070.0	-5,410.1	8,480.14	0.362	Level 1
6,200.0	6,200.0	6,445.8	6,445.8	13.8	8,600.0	0.00	3,070.0	0.0	3,070.0	-5,543.8	8,613.79	0.356	Level 1
6,300.0	6,300.0	6,545.8	6,545.8	14.0	8,733.4	0.00	3,070.0	0.0	3,070.0	-5,677.4	8,747.43	0.351	Level 1
6,400.0	6,400.0	6,645.8	6,645.8	14.3	8,866.8	0.00	3,070.0	0.0	3,070.0	-5,811.1	8,881.07	0.346	Level 1
6,500.0	6,500.0	6,745.8	6,745.8	14.5	9,000.2	0.00	3,070.0	0.0	3,070.0	-5,944.7	9,014.72	0.341	Level 1
6,600.0	6,600.0	6,845.8	6,845.8	14.7	9,133.7	0.00	3,070.0	0.0	3,070.0	-6,078.4	9,148.36	0.336	Level 1
6,700.0	6,700.0	6,945.8	6,945.8	14.9	9,267.1	0.00	3,070.0	0.0	3,070.0	-6,212.0	9,282.01	0.331	Level 1
6,800.0	6,800.0	7,045.8	7,045.8	15.2	9,400.5	0.00	3,070.0	0.0	3,070.0	-6,345.7	9,415.65	0.326	Level 1
6,900.0	6,900.0	7,145.8	7,145.8	15.4	9,533.9	0.00	3,070.0	0.0	3,070.0	-6,479.3	9,549.30	0.321	Level 1
7,000.0	7,000.0	7,245.8	7,245.8	15.6	9,667.3	0.00	3,070.0	0.0	3,070.0	-6,612.9	9,682.94	0.317	Level 1
7,100.0	7,100.0	7,345.8	7,345.8	15.8	9,800.8	0.00	3,070.0	0.0	3,070.0	-6,746.6	9,816.59	0.313	Level 1
7,200.0	7,200.0	7,445.8	7,445.8	16.1	9,934.2	0.00	3,070.0	0.0	3,070.0	-6,880.2	9,950.23	0.309	Level 1
7,300.0	7,300.0	7,545.8	7,545.8	16.3	10,067.6	0.00	3,070.0	0.0	3,070.0	-7,013.9	10,083.88	0.304	Level 1
7,400.0	7,400.0	7,645.8	7,645.8	16.5	10,201.0	0.00	3,070.0	0.0	3,070.0	-7,147.5	10,217.52	0.300	Level 1
7,500.0	7,500.0	7,745.8	7,745.8	16.7	10,334.4	0.00	3,070.0	0.0	3,070.0	-7,281.2	10,351.17	0.297	Level 1
7,600.0	7,600.0	7,845.8	7,845.8	16.9	10,467.9	0.00	3,070.0	0.0	3,070.0	-7,414.8	10,484.81	0.293	Level 1
7,700.0	7,700.0	7,945.8	7,945.8	17.2	10,601.3	0.00	3,070.0	0.0	3,070.0	-7,548.5	10,618.46	0.289	Level 1

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Integrity Directional Services, LLC

## Anticollision Report

<b>Company:</b>	COG Operating LLC	<b>Local Co-ordinate Reference:</b>	Well #2H
<b>Project:</b>	Eddy County, NM	<b>TVD Reference:</b>	WELL @ 3461.2usft (Original Well Elev)
<b>Reference Site:</b>	Running Buffalo Federal Com	<b>MD Reference:</b>	WELL @ 3461.2usft (Original Well Elev)
<b>Site Error:</b>	0.0 usft	<b>North Reference:</b>	Grid
<b>Reference Well:</b>	#2H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.0 usft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	OH	<b>Database:</b>	EDM 5000.1 Multi User Db
<b>Reference Design:</b>	Plan #2	<b>Offset TVD Reference:</b>	Offset Datum

<b>Offset Design:</b> Running Buffalo Federal Com - Golden Lane 1 Fed 1 - Wellbore #1 - Wellbore #1												<b>Offset Site Error:</b> 0.0 usft
<b>Survey Program:</b> 12540-BLIND												<b>Offset Well Error:</b> 0.0 usft
Reference	Offset	Semi Major Axis		Distance		Minimum Separation		Warning				
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference	Offset	Highside Toolface (°)	Offset Wellbore Centre +N-S (usft)	+E-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor
7,800.0	7,800.0	8,045.8	8,045.8	17.4	10,734.7	0.00	3,070.0	0.0	3,070.0	-7,682.1	10,752.10	0.286 Level 1
7,900.0	7,900.0	8,145.8	8,145.8	17.6	10,868.1	0.00	3,070.0	0.0	3,070.0	-7,815.7	10,885.74	0.282 Level 1
8,000.0	8,000.0	8,245.8	8,245.8	17.8	11,001.5	0.00	3,070.0	0.0	3,070.0	-7,949.4	11,019.39	0.279 Level 1
8,100.0	8,100.0	8,345.8	8,345.8	18.1	11,135.0	-3.00	3,070.0	0.0	3,069.9	-8,081.7	11,151.66	0.275 Level 1
8,200.0	8,199.1	8,444.9	8,444.9	18.3	11,267.2	-3.09	3,070.0	0.0	3,058.0	-7,943.6	11,001.57	0.278 Level 1
8,300.0	8,293.5	8,539.3	8,539.3	18.5	11,393.2	-3.36	3,070.0	0.0	3,025.7	-7,329.4	10,355.07	0.292 Level 1
8,400.0	8,379.2	8,625.0	8,625.0	18.7	11,507.4	-3.87	3,070.0	0.0	2,974.5	-6,255.4	9,229.93	0.322 Level 1
8,500.0	8,452.3	8,698.1	8,698.1	19.0	11,605.0	-4.81	3,070.0	0.0	2,906.7	-4,771.4	7,678.03	0.379 Level 1
8,600.0	8,509.7	8,755.5	8,755.5	19.4	11,681.6	-6.68	3,070.0	0.0	2,825.1	-2,990.7	5,815.83	0.486 Level 1
8,700.0	8,548.9	8,794.7	8,794.7	19.9	11,733.9	-11.32	3,070.0	0.0	2,733.5	-1,369.5	4,102.93	0.666 Level 1
8,800.0	8,568.1	8,813.9	8,813.9	20.5	11,759.5	-34.46	3,070.0	0.0	2,635.7	-4,086.5	6,722.22	0.392 Level 1
8,900.0	8,570.0	8,815.8	8,815.8	21.2	11,762.0	-90.00	3,070.0	0.0	2,535.9	-9,247.3	11,783.24	0.215 Level 1
9,000.0	8,570.0	8,815.8	8,815.8	22.0	11,762.0	-90.00	3,070.0	0.0	2,436.2	-9,347.9	11,784.08	0.207 Level 1
9,100.0	8,570.0	8,815.8	8,815.8	23.0	11,762.0	-90.00	3,070.0	0.0	2,336.4	-9,448.7	11,785.04	0.198 Level 1
9,200.0	8,570.0	8,815.8	8,815.8	24.1	11,762.0	-90.00	3,070.0	0.0	2,236.6	-9,549.5	11,786.10	0.190 Level 1
9,300.0	8,570.0	8,815.8	8,815.8	25.2	11,762.0	-90.00	3,070.0	0.0	2,136.9	-9,650.3	11,787.24	0.181 Level 1
9,400.0	8,570.0	8,815.8	8,815.8	26.4	11,762.0	-90.00	3,070.0	0.0	2,037.2	-9,751.3	11,788.46	0.173 Level 1
9,500.0	8,570.0	8,815.8	8,815.8	27.7	11,762.0	-90.00	3,070.0	0.0	1,937.5	-9,852.2	11,789.75	0.164 Level 1
9,600.0	8,570.0	8,815.8	8,815.8	29.1	11,762.0	-90.00	3,070.0	0.0	1,837.9	-9,953.2	11,791.09	0.156 Level 1
9,700.0	8,570.0	8,815.8	8,815.8	30.4	11,762.0	-90.00	3,070.0	0.0	1,738.3	-10,054.2	11,792.48	0.147 Level 1
9,800.0	8,570.0	8,815.8	8,815.8	31.9	11,762.0	-90.00	3,070.0	0.0	1,638.7	-10,155.2	11,793.91	0.139 Level 1
9,900.0	8,570.0	8,815.8	8,815.8	33.4	11,762.0	-90.00	3,070.0	0.0	1,539.3	-10,256.1	11,795.38	0.130 Level 1
10,000.0	8,570.0	8,815.8	8,815.8	34.9	11,762.0	-90.00	3,070.0	0.0	1,439.8	-10,357.0	11,796.89	0.122 Level 1
10,100.0	8,570.0	8,815.8	8,815.8	36.4	11,762.0	-90.00	3,070.0	0.0	1,340.5	-10,457.9	11,798.42	0.114 Level 1
10,200.0	8,570.0	8,815.8	8,815.8	37.9	11,762.0	-90.00	3,070.0	0.0	1,241.3	-10,558.7	11,799.98	0.105 Level 1
10,300.0	8,570.0	8,815.8	8,815.8	39.5	11,762.0	-90.00	3,070.0	0.0	1,142.2	-10,659.4	11,801.56	0.097 Level 1
10,400.0	8,570.0	8,815.8	8,815.8	41.1	11,762.0	-90.00	3,070.0	0.0	1,043.3	-10,759.9	11,803.16	0.088 Level 1
10,500.0	8,570.0	8,815.8	8,815.8	42.7	11,762.0	-90.00	3,070.0	0.0	944.6	-10,860.2	11,804.77	0.080 Level 1
10,600.0	8,570.0	8,815.8	8,815.8	44.4	11,762.0	-90.00	3,070.0	0.0	846.2	-10,960.2	11,806.41	0.072 Level 1
10,700.0	8,570.0	8,815.8	8,815.8	46.0	11,762.0	-90.00	3,070.0	0.0	748.3	-11,059.8	11,808.05	0.063 Level 1
10,800.0	8,570.0	8,815.8	8,815.8	47.7	11,762.0	-90.00	3,070.0	0.0	651.0	-11,158.7	11,809.71	0.055 Level 1
10,900.0	8,570.0	8,815.8	8,815.8	49.3	11,762.0	-90.00	3,070.0	0.0	554.6	-11,256.7	11,811.38	0.047 Level 1
11,000.0	8,570.0	8,815.8	8,815.8	51.0	11,762.0	-90.00	3,070.0	0.0	459.8	-11,353.2	11,813.06	0.039 Level 1
11,100.0	8,570.0	8,815.8	8,815.8	52.7	11,762.0	-90.00	3,070.0	0.0	367.8	-11,446.9	11,814.75	0.031 Level 1
11,200.0	8,570.0	8,815.8	8,815.8	54.4	11,762.0	-90.00	3,070.0	0.0	281.3	-11,535.2	11,816.44	0.024 Level 1
11,300.0	8,570.0	8,815.8	8,815.8	56.1	11,762.0	-90.00	3,070.0	0.0	207.2	-11,610.9	11,818.15	0.018 Level 1
11,400.0	8,570.0	8,815.8	8,815.8	57.8	11,762.0	-90.00	3,070.0	0.0	163.0	-11,656.8	11,819.80	0.014 Level 1
11,436.1	8,570.0	8,815.8	8,815.8	58.3	11,762.0	-90.00	3,070.0	0.0	159.2	-11,661.1	11,820.35	0.013 Level 1, CC, ES, SF
11,500.0	8,570.0	8,815.8	8,815.8	59.3	11,762.0	-90.00	3,070.0	0.0	170.9	-11,650.4	11,821.30	0.014 Level 1
11,600.0	8,570.0	8,815.8	8,815.8	60.9	11,762.0	-90.00	3,070.0	0.0	225.2	-11,597.5	11,822.75	0.019 Level 1
11,700.0	8,570.0	8,815.8	8,815.8	62.5	11,762.0	-90.00	3,070.0	0.0	301.8	-11,522.3	11,824.15	0.026 Level 1
11,800.0	8,570.0	8,815.8	8,815.8	64.2	11,762.0	-90.00	3,070.0	0.0	388.3	-11,437.5	11,825.81	0.033 Level 1
11,900.0	8,570.0	8,815.8	8,815.8	65.9	11,762.0	-90.00	3,070.0	0.0	480.1	-11,347.5	11,827.57	0.041 Level 1
12,000.0	8,570.0	8,815.8	8,815.8	67.7	11,762.0	-90.00	3,070.0	0.0	574.6	-11,254.7	11,829.33	0.049 Level 1
12,100.0	8,570.0	8,815.8	8,815.8	69.4	11,762.0	-90.00	3,070.0	0.0	670.7	-11,160.4	11,831.10	0.057 Level 1
12,200.0	8,570.0	8,815.8	8,815.8	71.2	11,762.0	-90.00	3,070.0	0.0	767.8	-11,065.1	11,832.87	0.065 Level 1
12,300.0	8,570.0	8,815.8	8,815.8	73.0	11,762.0	-90.00	3,070.0	0.0	865.6	-10,969.1	11,834.65	0.073 Level 1
12,400.0	8,570.0	8,815.8	8,815.8	74.7	11,762.0	-90.00	3,070.0	0.0	963.8	-10,872.6	11,836.43	0.081 Level 1
12,500.0	8,570.0	8,815.8	8,815.8	76.5	11,762.0	-90.00	3,070.0	0.0	1,062.3	-10,775.9	11,838.21	0.090 Level 1
12,600.0	8,570.0	8,815.8	8,815.8	78.3	11,762.0	-90.00	3,070.0	0.0	1,161.1	-10,678.9	11,840.00	0.098 Level 1
12,700.0	8,570.0	8,815.8	8,815.8	80.1	11,762.0	-90.00	3,070.0	0.0	1,260.1	-10,581.7	11,841.79	0.106 Level 1
12,800.0	8,570.0	8,815.8	8,815.8	81.9	11,762.0	-90.00	3,070.0	0.0	1,359.3	-10,484.3	11,843.58	0.115 Level 1

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

# Integrity Directional Services, LLC

## Anticollision Report

<b>Company:</b>	COG Operating LLC	<b>Local Co-ordinate Reference:</b>	Well #2H
<b>Project:</b>	Eddy County, NM	<b>TVD Reference:</b>	WELL @ 3461.2usft (Original Well Elev)
<b>Reference Site:</b>	Running Buffalo Federal Com	<b>MD Reference:</b>	WELL @ 3461.2usft (Original Well Elev)
<b>Site Error:</b>	0.0 usft	<b>North Reference:</b>	Grid
<b>Reference Well:</b>	#2H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.0 usft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	OH	<b>Database:</b>	EDM 5000.1 Multi User Db
<b>Reference Design:</b>	Plan #2	<b>Offset TVD Reference:</b>	Offset Datum

<b>Offset Design:</b> Running Buffalo Federal Com - Golden Lane 1 Fed 1 - Wellbore #1 - Wellbore #1													<b>Offset Site Error:</b> 0.0 usft
Survey Program: 12540-BLIND													<b>Offset Well Error:</b> 0.0 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning:
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N-S (usft)	+E-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
12,900.0	8,570.0	8,815.8	8,815.8	83.7	11,762.0	-90.00	3,070.0	0.0	1,458.5	-10,386.9	11,845.38	0.123	Level 1
13,000.0	8,570.0	8,815.8	8,815.8	85.4	11,762.0	-90.00	3,070.0	0.0	1,557.9	-10,289.3	11,847.18	0.131	Level 1
13,100.0	8,570.0	8,815.8	8,815.8	87.2	11,762.0	-90.00	3,070.0	0.0	1,657.3	-10,191.7	11,848.98	0.140	Level 1
13,200.0	8,570.0	8,815.8	8,815.8	89.0	11,762.0	-90.00	3,070.0	0.0	1,756.8	-10,094.0	11,850.78	0.148	Level 1
13,300.0	8,570.0	8,815.8	8,815.8	90.8	11,762.0	-90.00	3,070.0	0.0	1,856.4	-9,996.2	11,852.59	0.157	Level 1
13,400.0	8,570.0	8,815.8	8,815.8	92.6	11,762.0	-90.00	3,070.0	0.0	1,955.9	-9,898.5	11,854.40	0.165	Level 1
13,500.0	8,570.0	8,815.8	8,815.8	94.4	11,762.0	-90.00	3,070.0	0.0	2,055.6	-9,800.6	11,856.21	0.173	Level 1
13,600.0	8,570.0	8,815.8	8,815.8	96.3	11,762.0	-90.00	3,070.0	0.0	2,155.2	-9,702.8	11,858.02	0.182	Level 1
13,700.0	8,570.0	8,815.8	8,815.8	98.1	11,762.0	-90.00	3,070.0	0.0	2,254.9	-9,604.9	11,859.84	0.190	Level 1
13,800.0	8,570.0	8,815.8	8,815.8	99.9	11,762.0	-90.00	3,070.0	0.0	2,354.7	-9,507.0	11,861.65	0.199	Level 1

CC - Min centre to center distance or convergent point, SF,- min separation factor, ES - min ellipse separation


# Integrity Directional Services, LLC

## Anticollision Report

<b>Company:</b>	COG Operating LLC	<b>Local Co-ordinate Reference:</b>	Well #2H
<b>Project:</b>	Eddy County, NM	<b>TVD Reference:</b>	WELL @ 3461.2usft (Original Well Elev)
<b>Reference Site:</b>	Running Buffalo Federal Com	<b>MD Reference:</b>	WELL @ 3461.2usft (Original Well Elev)
<b>Site Error:</b>	0.0 usft	<b>North Reference:</b>	Grid
<b>Reference Well:</b>	#2H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.0 usft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	OH	<b>Database:</b>	EDM 5000.1 Multi User Db
<b>Reference Design:</b>	Plan #2	<b>Offset TVD Reference:</b>	Offset Datum

Reference Depths are relative to WELL @ 3461.2usft (Original Well Elev)  
 Offset Depths are relative to Offset Datum  
 Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: #2H  
 Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30  
 Grid Convergence at Surface is: 0.16°




# Integrity Directional Services, LLC

## Anticollision Report

<b>Company:</b>	COG Operating LLC	<b>Local Co-ordinate Reference:</b>	Well #2H
<b>Project:</b>	Eddy County, NM	<b>TVD Reference:</b>	WELL @ 3461.2usft (Original Well Elev)
<b>Reference Site:</b>	Running Buffalo Federal Com	<b>MD Reference:</b>	WELL @ 3461.2usft (Original Well Elev)
<b>Site Error:</b>	0.0 usft	<b>North Reference:</b>	Grid
<b>Reference Well:</b>	#2H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.0 usft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	OH	<b>Database:</b>	EDM 5000.1 Multi User Db
<b>Reference Design:</b>	Plan #2	<b>Offset TVD Reference:</b>	Offset Datum

Reference Depths are relative to WELL @ 3461.2usft (Original Well Elev) Coordinates are relative to: #2H  
Offset Depths are relative to Offset Datum Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30  
Central Meridian is 104° 20' 0.000 W Grid Convergence at Surface is: 0.16°

### Separation Factor Plot



### LEGEND

Golden Lane 1 Fed 1, Wellbore #1, Wellbore #1 V0

Run Time: 08:52 AM

DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENTRun Date: 01/08/2015  
Page 1 of 1

## LLD ACREAGE REPORT

Admin State: NM

Geo State: NM

MTR: 23 0210S 0280E

Section: 001

Sur Type	Sur No	Lld Suff	NE	NW	SW	SE	Sur Note	Dup Flg	Sub Surf	Acreage
			NNSS	NNSS	NNSS	NNSS				
A			----	----	XXXX	XXXX				320.000
L	1		X----	----	----	----	X			27.180
L	10		-X--	----	----	----				40.000
L	11		----	X--	----	----				40.000
L	12		----	-X--	----	----				40.000
L	13		----	--X-	----	----				40.000
L	14		----	---X	----	----				40.000
L	15		--X-	----	----	----				40.000
L	16		--- <td>----</td> <td>----</td> <td>----</td> <td></td> <td></td> <td></td> <td>40.000</td>	----	----	----				40.000
L	2		-X--	----	----	----	X			27.130
L	3		----	X--	----	----	X			27.070
L	4		----	-X--	----	----	X			27.020
L	5		----	-X--	----	----	X			40.000
L	6		----	X--	----	----	X			40.000
L	7		-X--	----	----	----	X			40.000
L	8		X----	----	----	----	X			40.000
L	9		X----	----	----	----				40.000

Section	001	Total:	908.400
---------	-----	--------	---------

MTR Total Excluding Survey Notes C/D/R and Sub Surf = Y	908.400
--	---------

Grand Total Excluding Survey Notes C/D/R and Sub Surf = Y:	908.400
---	---------



# New Mexico Office of the State Engineer Water Column/Average Depth to Water

(A CLW##### in the  
POD suffix indicates the  
POD has been replaced  
& no longer serves a  
water right file.)

(R=POD has  
been replaced,  
O=orphaned,  
C=the file is  
closed)

(quarters are 1=NW 2=NE 3=SW 4=SE)

(quarters are smallest to largest) (NAD83 UTM in meters)

(In feet)

POD Number	POD Sub-Code	basin	County	Q 64	Q 16	Q 4	Sec	Tws	Rng	X	Y	Depth Well	Depth Water	Water Column
C 03266 POD1	CUB	ED		3	4	4	04	21S	28E	585844	3596555*	260	80	180
C 03267 POD1	CUB	ED		4	3	3	04	21S	28E	584833	3596541*	52	40	12
C 03272 POD1	CUB	ED		4	3	1	18	21S	28E	581632	3594114*	22	9	13
CP 00516		ED		4	4	4	12	21S	28E	590901	3594984*	275	205	70
CP 00527		XX		3	2	3	17	21S	28E	583446	3593715*	100		
CP 00529		LE		1	2	3	17	21S	28E	583446	3593915*	100		
CP 00569		ED			4	3	17	21S	28E	583549	3593414*	71	50	21
CP 00576		ED		1	4	3	17	21S	28E	583448	3593513*	295	32	263
CP 00627		ED			2	3	17	21S	28E	583547	3593816*	154	30	124
CP 00627 POD2		ED		1	2	3	17	21S	28E	583360	3593982	175		
CP 00650		ED				3	17	21S	28E	583347	3593612*	155	35	120
CP 01016 POD1		LE		2	2	4	30	21S	28E	679417	3591905	150		
CP 01171 POD1		ED			1	4	35	21S	28E	588814	3588862	70		
CP 01171 POD2		ED			1	4	35	21S	28E	588866	3588862	110		
CP 01171 POD3		ED			1	4	35	21S	28E	588814	3588862	115		

Average Depth to Water: 60 feet

Minimum Depth: 9 feet

Maximum Depth: 205 feet

Record Count: 15

PLSS Search:

Township: 21S

Range: 28E

\*UTM location was derived from PLSS - see Help

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.



# *New Mexico Office of the State Engineer* **Water Column/Average Depth to Water**

No records found.

**PLSS Search:**


**Section(s): 1**

**Township: 21S**

**Range: 28E**


The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.

# 2,000 psi BOP Schematic







# 2,000 psi BOP Schematic




# 3,000 psi BOP Schematic



# 2M Choke Manifold Equipment (WITH MGS + CLOSED LOOP)



### 3M Choke Manifold Equipment (WITH MGS + CLOSED LOOP)



# COG Operating LLC

## Rig Plat & Closed Loop Equipment Diagram

Well pad will be 340' X 340'  
with cellar in center of pad

Flare Lines will be from both Choke  
Manifold & Separator to edge of  
location.

NORTH

170'

170'

170'

170'








Exhibit 1


"I further certify that COG will comply with Rule 19.15.17  
NMAC by using a Closed Loop System."

COG Operating LLC  
H<sub>2</sub>S Equipment Schematic  
Terrain: Shinnery sand hills.

Well pad will be 340' X 340'  
with cellar in center of pad

Secondary egress.

170'



☐ Briefing Area  
w/SCBA

☐ Location Entry  
Condition Sign

Company Representative's Trailer

☐ Primary Briefing  
Area w/SCBA

Prevailing Wind  
Direction in SENM

**COG OPERATING LLC**  
**HYDROGEN SULFIDE DRILLING OPERATIONS PLAN**

**1. HYDROGEN SULFIDE TRAINING**

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

- a. The hazards and characteristics of hydrogen sulfide (H<sub>2</sub>S).
- b. The proper use and maintenance of personal protective equipment and life support systems.
- c. The proper use of H<sub>2</sub>S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
- d. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

- a. The effects of H<sub>2</sub>S on metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
- b. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
- c. The contents and requirements of the H<sub>2</sub>S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H<sub>2</sub>S zone (within 3 days or 500 feet) and weekly H<sub>2</sub>S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H<sub>2</sub>S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

**2. H<sub>2</sub>S SAFETY EQUIPMENT AND SYSTEMS**

Note: All H<sub>2</sub>S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H<sub>2</sub>S. If H<sub>2</sub>S greater than 100 ppm is encountered in the gas stream we will shut in and install H<sub>2</sub>S equipment.

- a. Well Control Equipment:
  - Flare line.
  - Choke manifold with remotely operated choke.
  - Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
  - Auxiliary equipment to include: annular preventer, mud-gas separator, rotating head.

- b. Protective equipment for essential personnel:  
Mark II Surviveair 30-minute units located in the dog house and at briefing areas.
- c. H2S detection and monitoring equipment:  
2 - portable H2S monitor positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 ppm are reached.
- d. Visual warning systems:  
Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.
- e. Mud Program:  
The mud program has been designed to minimize the volume of H2S circulated to the surface.
- f. Metallurgy:  
All drill strings, casings, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- g. Communication:  
Company vehicles equipped with cellular telephone.

COG OPERATING LLC has conducted a review to determine if an H2S contingency plan is required for the above referenced well. We were able to conclude that any potential hazardous volume would be minimal. H2S concentrations of wells in this area from surface to TD are low enough; therefore, we do not believe that an H2S contingency plan is necessary.



# **W A R N I N G**

**YOU ARE ENTERING AN H<sub>2</sub>S AREA  
AUTHORIZED PERSONNEL ONLY**

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED***
- 2. HARD HATS REQUIRED***
- 3. SMOKING IN DESIGNATED AREAS ONLY***
- 4. BE WIND CONSCIOUS AT ALL TIMES***
- 5. CK WITH COG OPERATING LLC FOREMAN AT MAIN OFFICE***

**COG OPERATING LLC**

**1-575-748-6940**

## **EMERGENCY CALL LIST**


	<b><u>OFFICE</u></b>	<b><u>MOBILE</u></b>
COG OPERATING LLC OFFICE	575-748-6940	
SHERYL BAKER	575-748-6940	432-934-1873
KENT GREENWAY	575-746-2010	432-557-1694
SETH WILD	432-683-7443	432-528-3633
WALTER ROYE	575-748-6940	432-934-1886

## **EMERGENCY RESPONSE NUMBERS**

	<b><u>OFFICE</u></b>
STATE POLICE	575-748-9718
EDDY COUNTY SHERIFF	575-746-2701
EMERGENCY MEDICAL SERVICES (AMBULANCE)	911 or 575-746-2701
EDDY COUNTY EMERGENCY MANAGEMENT (HARRY BURGESS)	575-887-9511
STATE EMERGENCY RESPONSE CENTER (SERC)	575-476-9620
CARLSBAD POLICE DEPARTMENT	575-885-2111
CARLSBAD FIRE DEPARTMENT	575-885-3125
NEW MEXICO OIL CONSERVATION DIVISION	575-748-1283
INDIAN FIRE & SAFETY	800-530-8693
HALLIBURTON SERVICES	800-844-8451

Production Facility Layout  
Running Buffalo 1 Federal Com #2H  
Section 1 - T21S - R28E

# Exhibit 3



# Surface Use Plan of Operations

## Introduction

The following surface use plan of operations will be followed and carried out once the APD is approved. No other disturbance will be created other than what was submitted in this surface use plan. If any other surface disturbance is needed after the APD is approved, a BLM approved sundry notice or right of way application will be acquired prior to any new surface disturbance.

Before any surface disturbance is created, stakes or flagging will be installed to mark boundaries of permitted areas of disturbance, including soils storage areas. As necessary, slope, grade, and other construction control stakes will be placed to ensure construction in accordance with the surface use plan. All boundary markers will be maintained in place until final construction cleanup is completed. If disturbance boundary markers are disturbed or knocked down, they will be replaced before construction proceeds.


If terms and conditions are attached to the approved APD and amend any of the proposed actions in this surface use plan, we will adhere to the terms and conditions.

## 1. Existing Roads

- a. The existing access road route to the proposed project is depicted on Exhibit 2, Exhibit 2A. Improvements to the driving surface will be done where necessary. No new surface disturbance will be done, unless otherwise noted in the New or Reconstructed Access Roads section of this surface use plan.
- b. The existing access road route to the proposed project does cross lease boundaries and a BLM road right-of-way will be acquired from the BLM prior to construction activities.
- c. The operator will improve or maintain existing roads in a condition the same as or better than before operations begin. The operator will repair pot holes, clear ditches, repair the crown, etc. All existing structures on the entire access route such as cattleguards, other range improvement projects, culverts, etc. will be properly repaired or replaced if they are damaged or have deteriorated beyond practical use.
- d. We will prevent and abate fugitive dust as needed, whether created by vehicular traffic, equipment operations, or wind events. BLM written approval will be acquired before application of surfactants, binding agents, or other dust suppression chemicals on roadways.

## 2. New or Reconstructed Access Roads

- a. An access road will be needed for this proposed project. See the survey plat for the location of the access road.
- b. The length of access road needed to be constructed for this proposed project is about 364 feet.
- c. The maximum driving width of the access road will be 14 feet. The maximum width of surface disturbance when constructing the access road will not exceed 25 feet. All areas outside of the driving surface will be revegetated.
- d. The access road will be constructed with 6 inches of compacted Caliche.
- e. When the road travels on fairly level ground, the road will be crowned and ditched with a 2% slope from the tip of the road crown to the edge of the driving surface. The ditches will be 3 feet wide with 3:1 slopes. See Road Cross Section diagram below.



- f. The access road will be constructed with a ditch on each side of the road.
- g. The maximum grade for the access road will be 1 percent.
- h. No turnouts will be constructed on the proposed access road.
- i. No cattleguards will be installed for this proposed access road.
- j. Since the proposed access road crosses lease boundaries, a right-of-way will be required for this access road. A right-of-way grant will be applied for through the BLM. The access road will not be constructed until an approved BLM right-of-way grant is acquired.
- k. No culverts will be constructed for this proposed access road.
- l. No low water crossings will be constructed for the access road.
- m. Lead-off ditches will be constructed on the access road to divert water and prevent excessive erosion. Each lead-off ditch will be 6 inches deep and have a 6 inch berm above natural ground on the down hill slope. Each lead-off ditch will be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. Lead-off ditches will not extend more than 10 feet off the road edge.
- n. Newly constructed or reconstructed roads, on surface under the jurisdiction of the Bureau of Land Management, will be constructed as outlined in the BLM "Gold Book" and to meet the standards of the anticipated traffic flow and all anticipated weather requirements as needed. Construction will include ditching, draining, crowning and capping or sloping and dipping the roadbed as necessary to provide a well-constructed and safe road.

### 3. Location of Existing Wells

- a. Exhibit 4 of the APD depicts all known wells within a one mile radius of the proposed well.
- b. 1 mile well data

### 4. Location of Existing and/or Proposed Production Facilities

- a. All permanent, lasting more than 6 months, above ground structures including but not limited to pumpjacks, storage tanks, barrels, pipeline risers, meter housing, etc. that are not subject to safety requirements will be painted a non-reflective paint color, Shale Green, from the BLM Standard Environmental Colors chart, unless another color is required in the APD Conditions of Approval.
- b. If any type of production facilities are located on the well pad, they will be strategically placed to allow for maximum interim reclamation, recontouring, and revegetation of the well location.
- c. Production from the proposed well will be transported to the production facility located on the Running Buffalo 1 Federal Com #1H. The location of the well is as follows: 1980' FSL & 1090' FEL of Section 1. T21S. R28E..
- d. A pipeline to transport production will be installed from the proposed well to the existing production facility.

- i. We plan to install a 4 inch surface Poly pipeline from the proposed well to the production facility. The proposed length of the pipeline will be 1410 feet. The working pressure of the pipeline will be 125 psi or less. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline will be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline will be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.
- ii. Exhibit 2A and Exhibit 2B depicts the proposed production pipeline route from the well to the production facility.
- iii. Since the proposed pipeline crossess lease boundaries, a right of way grant will be acquired prior to installation of the proposed pipeline.

**If any plans change regarding the production facility or other infrastructure (pipeline, electric line, etc.), we will submit a sundry notice or right of way (if applicable) prior to installation or construction.**

#### **Additional Pipeline(s)**

We propose to install 1 additional pipeline(s):

1. Surface Gas Lift Gas pipeline:
  - a. We plan to install a 4 inch surface Poly pipeline from Running Buffalo 1 Federal Com #2H to Running Buffalo 1 Federal Com #1H. The proposed length of the pipeline will be 1410 feet. The working pressure of the pipeline will be 125 psi or less. The pipeline will transport Gas Lift Gas. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline will be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline will be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.
  - b. Exhibit 2B, and Exhibit 2C depicts the proposed Gas Lift Gas pipeline route.
  - c. Since the proposed pipeline crossess lease boundaries, a right of way grant will be acquired prior to installation of the proposed pipeline.

#### **Electric Line(s)**

- a. No electric line will be applied for with this APD.

### **5. Location and Types of Water**

- a. The location of the water well is as follows: Contractors water well.
- b. The operator will use established or constructed oil and gas roads to transport water to the well site. The operator will try to utilize the identified access route in the surface use plan.

### **6. Construction Material**

- a. Caliche from an approved Federal or State pit.

### **7. Methods for Handling Waste**

- a. Drilling fluids and produced oil and water from the well during drilling and completion operations will be stored safely and disposed of properly in an NMOCD approved disposal facility.

- b. Garbage and trash produced during drilling and completion operations will be collected in a trash container and disposed of properly at a state approved disposal facility. All trash on and around the well site will be collected for disposal.
- c. Human waste and grey water will be properly contained and disposed of properly at a state approved disposal facility.
- d. After drilling and completion operations, trash, chemicals, salts, frac sand and other waste material will be removed and disposed of properly at a state approved disposal facility.
- e. The well will be drilled utilizing a closed loop system. Drill cutting will be properly disposed of into steel tanks and taken to an NMOCD approved disposal facility.

## 8. Ancillary Facilities

- a. No ancillary facilities will be needed for this proposed project.

## 9. Well Site Layout

- a. The following information is presented in the well site survey plat or diagram:
  - i. reasonable scale (near 1":50')
  - ii. well pad dimensions
  - iii. well pad orientation
  - iv. drilling rig components
  - v. proposed access road
  - vi. elevations of all points
  - vii. topsoil stockpile
  - viii. reserve pit location/dimensions if applicable
  - ix. other disturbances needed (flare pit, stinger, frac farm pad, etc.)
  - x. existing structures within the 600' x 600' archaeological surveyed area (pipelines, electric lines, well pads, etc)
- b. The proposed drilling pad was staked and surveyed by a professional surveyor. The attached survey plat of the well site depicts the drilling pad layout as staked.
- c. The submitted survey plat does depict all the necessary information required by Onshore Order No. 1.
- d. Topsoil Salvaging
  - i. Grass, forbs, and small woody vegetation, such as mesquite will be excavated as the topsoil is removed. Large woody vegetation will be stripped and stored separately and respread evenly on the site following topsoil resspreading. Topsoil depth is defined as the top layer of soil that contains 80% of the roots. In areas to be heavily disturbed, the top 6 inches of soil material, will be stripped and stockpiled on the perimeter of the well location and along the perimeter of the access road to control run-on and run-off, to keep topsoil viable, and to make redistribution of topsoil more efficient during interim reclamation. Stockpiled topsoil should include vegetative material. Topsoil will be clearly segregated and stored separately from subsoils. Contaminated soil will not be stockpiled, but properly treated and handled prior to topsoil salvaging.

## 10. Plans for Surface Reclamation

### Reclamation Objectives

- i. The objective of interim reclamation is to restore vegetative cover and a portion of the landform sufficient to maintain healthy, biologically active topsoil; control erosion; and minimize habitat and forage loss, visual impact, and weed infestation, during the life of the well or facilities.
- ii. The long-term objective of final reclamation is to return the land to a condition similar to what existed prior to disturbance. This includes restoration of the landform and natural vegetative community, hydrologic systems, visual resources, and wildlife habitats. To ensure that the long-term objective will be reached through human and natural processes, actions will be taken to ensure standards are met for site stability, visual quality, hydrological functioning, and vegetative productivity.
- iii. The BLM will be notified at least 3 days prior to commencement of any reclamation procedures.
- iv. If circumstances allow, interim reclamation and/or final reclamation actions will be completed no later than 6 months from when the final well on the location has been completed or plugged. We will gain written permission from the BLM if more time is needed.
- v. Interim reclamation will be performed on the well site after the well is drilled and completed. Exhibit 3 depicts the location and dimensions of the planned interim reclamation for the well site.

#### **Interim Reclamation Procedures (If performed)**

1. Within 30 days of well completion, the well location and surrounding areas will be cleared of, and maintained free of, all materials, trash, and equipment not required for production.
2. In areas planned for interim reclamation, all the surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads.
3. The areas planned for interim reclamation will then be recontoured to the original contour if feasible, or if not feasible, to an interim contour that blends with the surrounding topography as much as possible. Where applicable, the fill material of the well pad will be backfilled into the cut to bring the area back to the original contour. The interim cut and fill slopes prior to re-seeding will not be steeper than a 3:1 ratio, unless the adjacent native topography is steeper. Note: Constructed slopes may be much steeper during drilling, but will be recontoured to the above ratios during interim reclamation.
4. Topsoil will be evenly respread and aggressively revegetated over the entire disturbed area not needed for all-weather operations including cuts & fills. To seed the area, the proper BLM seed mixture, free of noxious weeds, will be used. Final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to break the soil crust and create seed germination micro-sites.
5. Proper erosion control methods will be used on the area to control erosion, runoff and siltation of the surrounding area.
6. The interim reclamation will be monitored periodically to ensure that vegetation has reestablished and that erosion is controlled.

#### **Final Reclamation (well pad, buried pipelines, etc.)**

1. Prior to final reclamation procedures, the well pad, road, and surrounding area will be cleared of material, trash, and equipment.
2. All surfacing material will be removed and returned to the original mineral pit or recycled to repair or build roads and well pads.



3. All disturbed areas, including roads, pipelines, pads, production facilities, and interim reclaimed areas will be recontoured to the contour existing prior to initial construction or a contour that blends indistinguishably with the surrounding landscape. Topsoil that was spread over the interim reclamation areas will be stockpiled prior to recontouring. The topsoil will be redistributed evenly over the entire disturbed site to ensure successful revegetation.
4. After all the disturbed areas have been properly prepared, the areas will be seeded with the proper BLM seed mixture, free of noxious weeds. Final seedbed preparation will consist of contour cultivating to a depth of 4 to 6 inches within 24 hours prior to seeding, dozer tracking, or other imprinting in order to break the soil crust and create seed germination micro-sites.
5. Proper erosion control methods will be used on the entire area to control erosion, runoff and siltation of the surrounding area.
6. All unused equipment and structures including pipelines, electric line poles, tanks, etc. that serviced the well will be removed.
7. All reclaimed areas will be monitored periodically to ensure that revegetation occurs, that the area is not redisturbed, and that erosion is controlled.

## 11. Surface Ownership

- a. The surface ownership of the proposed project is Federal.

## 12. Other Information

- a. A. The area around the well site is grassland and the topsoil is sandy. The vegetation is moderately sparse with native prairie grasses, some mesquite and shinnery oak. No wildlife was observed but it is likely that mule deer, rabbits, coyotes and rodents traverse the area.
- B. There is no permanent or live water in the immediate area.
- C. There are no dwellings within 2 miles of this location.
- D. If needed, a Cultural Resources Examination is being prepared by Boone Arch Services of NM, LLC., 2030 North Canal, Carlsbad, New Mexico, 88220, phone # 575-885-1352 and the results will be forwarded to your office in the near future. Otherwise, COG will be participating in the Permian Basin MOA Program.

## 13. Maps and Diagrams

- Exhibit 2, Exhibit 2A - Existing Road
- Exhibit 4 - Wells Within One Mile
- Exhibit 2B and Exhibit 2C - Production Pipeline
- Exhibit 2B, and Exhibit 2C - Gas Lift Gas Pipeline
- Exhibit 3 - Interim Reclamation

# PECOS DISTRICT CONDITIONS OF APPROVAL

<b>OPERATOR'S NAME:</b>	<b>COG Operating, LLC</b>
<b>LEASE NO.:</b>	<b>NMNM-115409</b>
<b>WELL NAME &amp; NO.:</b>	<b>Running Buffalo 1 Federal Com 2H</b>
<b>SURFACE HOLE FOOTAGE:</b>	<b>1650' FSL &amp; 1980' FEL</b>
<b>BOTTOM HOLE FOOTAGE</b>	<b>0330' FNL &amp; 1980' FEL</b>
<b>LOCATION:</b>	<b>Section 01, T. 21 S., R 28 E., NMPM</b>
<b>COUNTY:</b>	<b>Eddy County, New Mexico</b>

## TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
  - Communitization Agreement
  - Lesser Prairie-Chicken Timing Stipulations
  - Below Ground-level Abandoned Well Marker
  - Range
  - Watershed
  - Karst
- ☐ **Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
  - Capitan Reef
  - Medium Cave/Karst
  - Logging Requirements
  - Waste Material and Fluids
- ☒ **Production (Post Drilling)**
  - Well Structures & Facilities
  - Pipelines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## V. SPECIAL REQUIREMENT(S)

### **Communitization Agreement**

The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.

If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.

In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

### **Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:**

Oil and gas activities including 3-D geophysical exploration; and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

**Below Ground-level Abandoned Well Marker to avoid raptor perching:** Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

## **Karst**

### **Construction Mitigation**

In order to mitigate the impacts from construction activities on cave and karst resources, the following Conditions of Approval will apply to this APD:

- In the event that any underground voids are encountered during construction activities, construction activities will be halted and the BLM will be notified immediately.
- Pad Berming to minimize effects of any spilled contaminants.

### **Drilling Mitigation**

Federal regulations and standard Conditions of Approval applied to all APDs require that adequate measures are taken to prevent contamination to the environment. Due to the extreme sensitivity of the cave and karst resources in this project area, the following additional Conditions of Approval will be added to this APD.

To prevent cave and karst resource contamination the following will be required.

Closed Mud System Using Steel Tanks with All Fluids and Cuttings Hauled Off.

- Rotary drilling with fresh water where cave or karst features are expected to prevent contamination of freshwater aquifers.
- Directional Drilling allowed after at least 100 feet below the cave occurrence zone to prevent additional impacts resulting from directional drilling.
- Lost Circulation zones logged and reported in the drilling report so BLM can assess the situation and work with the operator on corrective actions.
- Additional drilling, casing, and cementing procedures to protect cave zones and fresh water aquifers. See Drilling COAs.

### **Production Mitigation**

In order to mitigate the impacts from production activities and due to the nature of karst terrain, the following Conditions of Approval will apply to this APD:

- Tank battery liners and berms to minimize the impact resulting from leaks.
- Leak detection system to provide an early alert to operators when a leak has occurred.
- Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of line failures used in production or drilling.

### **Residual and Cumulative Mitigation**

- Annual pressure monitoring will be performed by the operator. If the test results indicate a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

### **Plugging and Abandonment Mitigation**

**Abandonment Cementing:** Upon well abandonment in high cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

### **Watershed**

- **The entire well pad would be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. Topsoil would not be used to construct the berm. No water flow from the uphill side(s) of the pad would be allowed to enter the well pad. The berm would be maintained through the life of the well and after interim reclamation has been completed.**
- **Any water erosion that may occur due to the construction of the well pad during the life of the well would be quickly corrected and proper measures would be taken to prevent future erosion.**

### **Range**

Where entry is granted across a fence line, the fence must be braced and tied off on both sides of the passageway with H-braces prior to cutting. A wire gate would be installed in the fence opening during infrastructure installation to prevent livestock from crossing the fence. The gate would be in place during construction and activity. Once the work is completed, the fence will be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Where entry is granted across a fence line for an access road, the fence must be braced and tied off on both sides of the passageway with H-braces prior to cutting. Once the work is completed, the fence will be restored to its prior condition with an appropriately sized cattle guard sufficient to carry out the project. Any new or existing cattle guards on the access route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations. Once the road is abandoned, the fence would be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

The operator must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that provide water to livestock, or to any fence or other range improvement.

## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### **D. FEDERAL MINERAL MATERIALS PIT**

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

## **F. EXCLOSURE FENCING (CELLARS & PITS)**

### **Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

## **G. ON LEASE ACCESS ROADS**

### **Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

### **Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

### **Crowning**

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

### **Ditching**

Ditching shall be required on both sides of the road.

### **Turnouts**


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

### **Drainage**



Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

#### **Formula for Spacing Interval of Lead-off Ditches**

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

#### **Cattleguards**

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

#### **Fence Requirement**

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

#### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

## Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

## **VII. DRILLING**

### **A. DRILLING OPERATIONS REQUIREMENTS**

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

1. **Hydrogen Sulfide (H<sub>2</sub>S) monitors shall be installed prior to drilling out the surface shoe. If H<sub>2</sub>S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

### **B. CASING**

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

**Centralizers required on surface casing per Onshore Order 2.III.B.1.f.**

**Wait on cement (WOC) for Water Basin:**

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.

Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

### **Capitan Reef**

#### **Medium Cave/Karst**

**Possibility of water flows in the Artesia Group, Salado, and Capitan Reef.**

**Possibility of lost circulation in the Artesia Group, Red Beds, Salado, Rustler, Delaware, and Capitan Reef.**

1. The 20 inch surface casing shall be set at approximately 850 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt. Excess calculates to negative 14% - Additional cement will be required.**
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 13-3/8 inch 1<sup>st</sup> intermediate casing, which shall be set at approximately 1700 feet (**base of the Tansil**), is:
  - ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst. Excess calculates to 16% - Additional cement may be required.**

3. The minimum required fill of cement behind the 9-5/8 inch 2<sup>nd</sup> intermediate casing is:

**Operator has proposed DV tool at depth of 1750'. Operator is to submit sundry if DV tool depth varies by more than 100' from approved depth.**

- a. First stage to DV tool:

☒ Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.

- b. Second stage above DV tool:

☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to Capitan Reef.**

**Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.**

4. The minimum required fill of cement behind the 5-1/2 inch production casing is:

☒ Cement should tie-back at least **50 feet above the Capitan Reef** (Top of Capitan Reef estimated at 1770'). Operator shall provide method of verification.

5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. *If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.*

#### **C. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
2. **In the case where the only BOP installed is an annular preventer, it shall be tested to a minimum of 2000 psi (which may require upgrading to 3M or 5M annular).**
3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M) psi**.
4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 9-5/8 intermediate casing shoe shall be **3000 (3M) psi**.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after

installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**.
- c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

#### **D. DRILL STEM TEST**

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

#### **E. WASTE MATERIAL AND FLUIDS**

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**JAM 050416**

## **VIII. PRODUCTION (POST DRILLING)**

### **A. WELL STRUCTURES & FACILITIES**

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

#### **Chemical and Fuel Secondary Containment and Exclosure Screening**

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

#### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

## **B. PIPELINES**

### **STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES**

**A copy of the Grant and attachments, including stipulations, survey plat(s) and/or map(s), shall be on location during construction. BLM personnel may request to review a copy of your permit during construction to ensure compliance with all stipulations.**

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, Holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC § 2601 *et seq.* (1982) with regard to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant (*see* 40 CFR, Part 702-799 and in particular, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193). Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. Holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. § 9601, *et seq.* or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, *et seq.*) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way Holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way Holder on the Right-of-Way. This provision applies without regard to whether a release is caused by Holder, its agent, or unrelated third parties.
4. Holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. Holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused



or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of Holder including, but not limited to: construction, operation, maintenance, and termination of the facility;
- b. Activities of other parties including, but not limited to:
  - (1) Land clearing
  - (2) Earth-disturbing and earth-moving work
  - (3) Blasting
  - (4) Vandalism and sabotage;
- c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of Holder, regardless of fault. Upon failure of Holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he/she deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of Holder. Such action by the Authorized Officer shall not relieve Holder of any responsibility as provided herein.

6. All construction and maintenance activity shall be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline shall be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline shall be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity shall be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation shall be allowed unless approved in writing by the Authorized Officer.

8. Holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline shall be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land

affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines shall be less than or equal to 4 inches and a working pressure below 125 psi.

18. Special Stipulations:

- a. **Lesser Prairie-Chicken:** Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted.

## **IX. INTERIM RECLAMATION**

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

## **X. FINAL ABANDONMENT & RECLAMATION**

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

#### Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

Pounds of pure live seed: Pounds of seed x percent purity x percent germination = pounds pure live seed

## NMOCD CONDITION OF APPROVAL

The *New* Gas Capture Plan (GCP) notice is posted on the NMOCD website under Announcements. The Plan became effective May 1, 2016. A copy of the GCP form is included with the NOTICE and is also in our FORMS section under Unnumbered Forms. Please review filing dates for all applicable activities currently approved or pending and submit accordingly. Failure to file a GCP may jeopardize the operator's ability to obtain C-129 approval to flare gas after the initial 60-day completion period.