

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SECRETARY'S POTASH

APPLICATION FOR PERMIT TO DRILL OR REENTER

JUN 28 2016

RECEIVED

1a. Type of Work: ☒ DRILL ☐ REENTER1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone2. Name of Operator
OXY USA INCORPORATEDContact: DAVID STEWART
E-Mail: david_stewart@oxy.com3a. Address
5 GREENWAY PLAZA SUITE 110
HOUSTON, TX 77046-05213b. Phone No. (include area code)
Ph: 432.685.5717

4. Location of Well (Report location clearly and in accordance with any State requirements. *)

At surface NENE 150 305 100FNL 354FEL

At proposed prod. zone SESE 230FSL 354FEL 32.210576 N Lat, 103.809058 W Lon

14. Distance in miles and direction from nearest town or post office*
14 MILES SOUTHEAST FROM LOVING, NM15. Distance from proposed location to nearest property or
lease line, ft. (Also to nearest drig. unit line, if any)
150'16. No. of Acres in Lease
647.8818. Distance from proposed location to nearest well, drilling,
completed, applied for, on this lease, ft.
30'19. Proposed Depth
16227 MD PH 13,812'
11617 TVD21. Elevations (Show whether DF, KB, RT, GL, etc.)
3526 GL22. Approximate date work will start
08/01/20165. Lease Serial No.
NMNM89819

6. If Indian, Allottee or Tribe Name

7. If Unit or CA Agreement, Name and No.

8. Lease Name and Well No.
PATTON MDP1 18 FEDERAL 6H9. API Well No.
300154305410. Field and Pool, or Exploratory
UNKNOWN Wolfcamp
WC-015 (7-00-243118A)

11. Sec., T., R., M., or Blk. and Survey or Area

Sec 18 T24S R31E Mer NMP
SME: BLM12. County or Parish
EDDY13. State
NM17. Spacing Unit dedicated to this well
160.0020. BLM/BIA Bond No. on file
NMB00086223. Estimated duration
35DAYS

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature
(Electronic Submission)Name (Printed/Typed)
DAVID STEWART Ph: 432.685.5717Date
04/28/2016Title
REGULATORY ADVISORApproved by (Signature)
George MacDonell

Name (Printed/Typed)

JUN 21 2016

Title
FIELD MANAGEROffice
CARLSBAD FIELD OFFICEApplication approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Carlsbad Controlled Water Basin


Electronic Submission #337838 verified by the BLM Well Information System
For OXY USA INCORPORATED, sent to the Carlsbad
Committed to AFMSS for processing by JAMIE RHOADES on 05/04/2016 (16JLR0338AE)SEE ATTACHED FOR
CONDITIONS OF APPROVALApproval Subject to General Requirements
& Special Stipulations Attached

** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED **

65
2/7/16

OPERATOR CERTIFICATION

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 25th day of April, 2016.

Signature: 
Name: Omar Lisigurski
Position: Reservoir Management Team Leader
Address: 5 Greenway Plaza, Suite 110, Houston, TX 77046
Telephone: 713-215-7506
E-mail: (optional): omar_lisigurski@oxy.com
Company: Occidental Permian LP/OXY USA Inc./OXY USA WTP LP
Field Representative (if not above signatory): Jim Wilson
Address (If different from above): P.O. Box 50250 Midland, TX 79710
Telephone (if different from above): 575-631-2442
E-mail (if different from above): jim_wilson@oxy.com

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
111 E. First St., Arroyo, NM 88210
Phone: (575) 348-1283 Fax: (575) 348-9720
District III
1000 Rio Blanco Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87503
Phone: (505) 476-3480 Fax: (505) 476-3463

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-05-43054	Pool Code 98202	Pool Name WC-015 6-48 W. Locat Wolfcamp 524318A; WC
Property Code 316403	Property Name PATTON MDP1 "18" FEDERAL	Well Number 6H
OGRID No. 16696	Operator Name OXY USA INC.	Elevation 3525.7'

Surface Location

UL or lot no.	Section	Township	Range	Lot 1st	Feet from the	North/South line	Feet from the	East/West line	County
A	18	24 SOUTH	31 EAST, N.M.P.M.		150'	NORTH	505'	EAST	EDDY


Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot 1st	Feet from the	North/South line	Feet from the	East/West line	County
P	18	24 SOUTH	31 EAST, N.M.P.M.		230'	SOUTH	354'	EAST	EDDY

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.
160	N		

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.


GRID AZ = 71°43'41"
181.94'



Site Plan

OXY USA INC. PATTON MDP1 "18" FEDERAL #6H SITE PLAN

FAA PERMIT: NO




SURVEYORS CERTIFICATE

I, TERRY J. ASEL, NEW MEXICO PROFESSIONAL SURVEYOR NO. 15079, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND MEETS THE "MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO" AS ADOPTED BY THE NEW MEXICO STATE BOARD OF REGISTRATION FOR PROFESSIONAL ENGINEERS AND SURVEYORS.

Terry J. Asel 3/29/2016
Terry J. Asel, N.M. R.P.L.S. No. 15079


Asel Surveying

P.O. BOX 393 - 310 W. TAYLOR
HOBBS, NEW MEXICO - 575-393-9146



LEGEND

- DENOTES PROPOSED WELL PAD
- - - DENOTES PROPOSED ROAD
- ███ DENOTES STOCK PILE AREA
- * DENOTES EXISTING WELL




OXY USA INC.

PATTON MDP1 "18" FEDERAL #6H LOCATED
AT 150' FNL & 505' FEL IN SECTION 18,
TOWNSHIP 24 SOUTH, RANGE 31 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO

Survey Date: 10/15/15	Sheet 1 of 1 Sheets
W.O. Number: 151015WL-a	Drawn By: JR Rev:
Date: 02/29/15	151015WL-a Scale: 1"=200'

Location




A circular professional seal for Terry J. Aseel, a Registered Professional Land Surveyor in New Mexico. The seal features the name "TERRY J ASEEL" at the top, "NEW MEXICO" in the middle, and the license number "15079" in the center. The outer ring of the seal contains the text "REGISTERED PROFESSIONAL LAND SURVEYOR".

Terry J. Aase 3/29/2014
Terry J. Aase, M.D. R.P.L.S. No. 15070

Survey Date: 10/15/15	Sheet 1 of 1 Sheets	
W.O. Number: 151015WL-a	Drawn By: JR	Rev:
Date: 02/29/16	151015WL-a	Scale: 1"=1000'

VM

VICINITY MAP




SEC 18 TWP. 24-S RGE. 31-E
 SURVEY N.M.P.M.
 COUNTY EDDY
 DESCRIPTION 150' FNL & 505' FEL
 ELEVATION 3525.7'
 OPERATOR OXY USA INC.

SCALE: 1" = 2 MILES

Asel Surveying

P.O. BOX 393 - 310 W TAYLOR
 HOBBS, NEW MEXICO - 575-393-9146




LEASE PATTON MDP1 "18" FEDERAL #6H

DIRECTIONS BEGINNING AT THE INTERSECTION OF STATE HWY. #128 AND COUNTY ROAD #787 (TWIN WELLS ROAD). GO SOUTH ON COUNTY ROAD #787 FOR 5.2 MILES. TURN LEFT ON CALICHE ROAD AND GO EAST FOR 0.1 MILES. CONTINUE SOUTHEAST ON PROPOSED ROAD FOR 532.6 FEET TO LOCATION.

LUM

LOCATION VERIFICATION MAP



SCALE: 1" = 2000'

CONTOUR INTERVAL: 10'

SEC. 18 TWP. 24-S RGE. 31-E

SURVEY N.M.P.M.

COUNTY EDDY

DESCRIPTION 150' FNL & 505' FEL

ELEVATION 3525.7'


OPERATOR OXY USA INC.

LEASE PATTON MDP1 "18" FEDERAL #6H


U.S.G.S. TOPOGRAPHIC MAP
BIG SINKS, N.M.

Asel Surveying

P.O. BOX 393 - 310 W. TAYLOR
HOBBS, NEW MEXICO - 575-393-9146



AERIAL MAP




SCALE: NOT TO SCALE

SEC. 18 TWP. 24-S RGE. 31-ESURVEY N.M.P.M.COUNTY EDDYDESCRIPTION 150' FNL & 505' FELELEVATION 3525.7OPERATOR OXY USA INC.LEASE PATTON MDP1 18 FEDERAL #6H

Asel Surveying

P.O. BOX 393 - 310 W TAYLOR
HOBBS, NEW MEXICO - 575-393-9146



NORTH


VADR WEST

8' Diameter x 8' Deep Tinhorn
Cellar

FLEX 3 RIG DIAGRAM
Patton MDP1 18 Fed # 5H & 6H
EDDY COUNTY, NEW MEXICO


REVISION BLOCK		ENGINEERING RECORD			
NO.	DATE	DESCRIPTION	BY	CHK	APP
			BY	DATE	

Facility Layout



REVISION BLOCK		ENGINEERING RECORD				FACILITY LAYOUT DIAGRAM	
NO.	DATE	DESCRIPTION	BY	CHK	APP	BY	DATE
						Patton MDP1 18 Fed # 5H & 6H	
						EDDY COUNTY, NEW MEXICO	

Pipeline Survey



LINE TABLE

LINE	BEARING	DISTANCE
11	N00°06'30"W	45.0'
12	S07°52'21"E	205.1'
13	S49°30'06"E	209.9'
14	S85°11'27"E	430.3'
15	S05°30'57"E	1912.0'
16	S03°13'38"E	79.3'
17	S66°00'04"E	366.1'
18	S28°20'54"E	153.8'
19	N09°59'22"E	417.3'
20	N00°01'15"W	94.0'
21	S79°17'13"E	396.1'
22	N43°42'03"E	322.8'
23	S78°56'39"E	406.1'
24	S63°50'32"E	85.9'
25	S74°01'59"E	458.8'
26	S65°20'09"E	406.6'
27	S80°44'26"E	472.7'
28	S84°16'08"E	328.5'
29	N00°50'06"E	257.2'
30	N76°03'41"E	195.4'
31	S05°27'52"E	83.9'
32	S76°14'28"E	120.7'
33	N79°45'18"E	120.6'
34	S30°06'05"E	123.8'
35	N09°38'44"E	211.1'
36	N00°01'07"W	10.0'

LEGEND

⊙ DENOTES FOUND CORNER AS NOTED



OXY U.S.A. INC.

SURVEY FOR A PIPELINE FROM THE GILA 12 CTB TO THE PATTON RDPI 18 FEDERAL HIGH & HIGH CROSSING SECTION 12, TOWNSHIP 24 SOUTH, RANGE 30 EAST AND SECTIONS 7 & 18, TOWNSHIP 24 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO

Survey Date: 4/15/16 CAD Date: 4/22/16 Drawn By: LS
W.D. No. 16110249 Rev. Net. W.D. Sheet 1 of 1

NOTE

BEARINGS SHOWN HEREON ARE HORIZONTAL CURVE AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM. NEW MEXICO EAST ZONE. NORTH AMERICAN DATUM 1983. DISTANCES ARE SURFACE VALUES.

JOHN WEST SURVEYING COMPANY
412 N. DAL PASO HIGHWAY 114, ALBUQUERQUE, NM 87102
(505) 993-3117 www.jwsurvey.com

DESCRIPTION

SURVEY FOR A STRIP OF LAND 10.0 FEET WIDE AND 2670.6 FEET OR 1.453 MILES IN LENGTH CROSSING USA LAND IN SECTION 12, TOWNSHIP 24 SOUTH, RANGE 30 EAST AND SECTIONS 7 & 18, TOWNSHIP 24 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO, AND BEING 15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

RONALD J. EIDSON
NEW MEXICO
DATE: 4/22/2016

©2016 TMC Vermilion, LLC U.S.A. Inc. (Vermilion) 16110249 FROM THE GILA 12 BAIT TO PATTON RDPI 18 FED WELLS SEC 12 TOWN 24E

SURVEY OF A STRIP OF LAND 30.0 FEET WIDE AND 2537.6 FEET OR 0.481 MILES IN LENGTH CROSSING USA LAND IN SECTIONS 7 & 18, TOWNSHIP 24 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO, AND BEING 15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

1) BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983. DISTANCES ARE SURFACE VALUES.

2) LATITUDE AND LONGITUDE VALUES SHOWN HEREON ARE RELATIVE TO THE NORTH AMERICAN DATUM 1983 (NAD83)

I, RONALD J. EIDSON, NEW MEXICO PROFESSIONAL SURVEYOR No. 3239, DO HEREBY CERTIFY THAT THIS SURVEY PLAN AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

DATE: 4/20/2016

PROVIDING SURVEYING SERVICES
SINCE 1946

JOHN WEST SURVEYING COMPANY

412 N. DAL PASO HOBBS N.M. 88240

(575) 393-3117 www.b...

© DRAFTINGU crento\2016\Oxy USA Inc\Pipeline\USA\location.mxd 18 lect. mds 75h & 75h sec 7 24x 31x

© DENOTES FOUND CORNER AS NOTED



OXY U.S.A. INC.

**SURVEY FOR AN ELECTRIC LINE TO PATTON
MDPI 18 FEDERAL #5H & #6H
CROSSING SECTIONS 7 & 18,
TOWNSHIP 24 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, NEW MEXICO**

Survey Date: 3/31/16

CAD Date: 4/19/16

Drawn By: LSL


W.O. No : 16110210


Rev.

Ref. W.O.:

Sheet 1 of 1

Patton MDP1 18 Federal #6H - 1 Mile AOR





OXY USA Inc. - Patton MDP1 18 Federal 6H

OXY USA Inc. proposes to drill a pilot hole 50' into the Strawn formation, then plug back, sidetrack and drill a lateral wellbore into the Wolfcamp A formation.

- Drill 20" surface hole to 640' MD; run 16" casing and cement to surface.
- Drill 13-1/2" 1st intermediate hole to 4358' MD; run 10-3/4" casing and cement to surface.
- Drill 9-7/8" 2nd intermediate hole to $\pm 11,930'$ MD (approximately 400' into Wolfcamp formation); run 7-5/8" casing and cement to 500' into the 1st intermediate casing.
- Drill 6-3/4" pilot hole to 13,812' MD (50' into Strawn formation), log as per program and abandon with two cement plugs. See below for details.
- Sidetrack from whipstock set at $\pm 10,956'$ MD and drill 6-3/4" lateral to 16,227' MD targeting Wolfcamp A formation ($\sim 11,617'$ TVD).

The primary purpose of the Patton MDP1 18 Federal #6H is to drill a pilot hole into the Strawn formation in order to evaluate and appraise the Wolfcamp, Bone Spring and Avalon formations.

The logging plan for the pilot will be a Triple Combo from TD to intermediate casing shoe.


After the pilot has been drilled and logs have been acquired, the final objective will be to drill a ± 4500 ft lateral in the Wolfcamp. The top of the Wolfcamp is predicted at a depth of 11,519' TVD.

OXY proposes setting the 7-5/8" casing for this well at 11,930 MD ($\sim 400'$ into Wolfcamp formation and 150' into the Wolfcamp A Carb/Shale) in order to ensure a competent intermediate casing shoe that can withstand the expected pressure in the Strawn formation (12.5 – 13.5 ppg). When setting this casing at 11,930', the resulting kick tolerance to drill the pilot hole to 13,812' is 31.4 bbl (based on 15.5 ppg fracture gradient at 11,930' MD and 13.5 ppg max expected pore pressure at 13,812' MD).

The table below shows different mud weights and casing set depths from offset wells. This information supports our proposed 10.0 ppg or less MW to get into the Wolfcamp formation while drilling the second intermediate hole as well as our proposed casing depth $\sim 400'$ into the Wolfcamp formation.

Well	Wolfcamp				Strawn		
	Top	MW	Casing Depth	ft. into WC	Top	MW	Max. MW
Poker Lake 32 Sate 1	11,267	9.0	12,500	1,233	13,446	11.9	12.3
Sterling Silver 3-1	11,505	8.4	11,992	487	13,697	12.7	13.6
Patton 18 -1	11,486	8.5	11,770	284	N/A	N/A	N/A
Cal-Mon 2	11,634	9.1	11,860	226	13,762	10.3	12.5
State IG Com 1	11,950	9.4	12,060	110	14,154	10.9	12.0

OXY USA Inc. - Patton MDP1 18 Federal 6H



OXY USA Inc. - Patton MDP1 18 Federal 6H

1. Geologic Formations

TVD of target	11,617'	Pilot hole depth	13,812' MD
MD at TD:	16,227'	Deepest expected fresh water:	592'

Delaware Basin

Formation	TVD - RKB	Expected Fluids
T. Rustler	592	--
T. Salado	972	--
T. Castille	2,852	--
T. Delaware / Lamar / B. Anhydrite	4,310	Oil/Gas
T. Bell Canyon*	4,354	Water/Oil/Gas
T. Cherry Canyon*	5,126	Oil/Gas
T. Brushy Canyon*	6,449	Oil/Gas
T. BSPG	8,125	Oil/Gas
T. 2 nd BSPG	9,446	Oil/Gas
T. 3 rd BSPG	10,341	Oil/Gas
T. Wolfcamp	11,519	Oil/Gas
Target Wolfcamp A	11,617	Oil/Gas
T. Strawn	13,752	Oil/Gas

*H2S, water flows, loss of circulation, abnormal pressures, etc.

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
	From	To							
20.000"	0'	640' 700'	16"	84.0	J55	BTC	5.04	1.48	6.27
13.500"	0'	4,358' 4275'	10.75"	45.5	J55	BTC	1.41	2.17	2.66
9.875"	0'	11,930'	7.625"	29.7	L80	BTC	1.56	1.49	1.83
6.750"	0'	11,800'	5.5"	20	P-110	Ultra SF	1.54	1.25	2.21
6.750"	11,800'	16,227'	4.5"	13.5	P-110	DQX	1.48	1.23	2.83
BLM Minimum Safety Factor							1.125	1.00	1.6 Dry 1.8 Wet

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	Y
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	

OXY USA Inc. - Patton MDP1 18 Federal 6H

Is well located in SOPA but not in R-111-P?	Y
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	Y
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

3. Cementing Program

Casing	#Sks	Wt. lb/ gal	Yld ft3/ sack	H ₂ O gal/sk	500# Comp. Strength (hours)	Slurry Description
1 st Surf	560	14.8	1.36	6.55	6:30	Premium Plus Cement 2% Calcium Chloride (Accelerator)
1 st Int	1314	12.9	1.85	9.84	12:22	TUNED LIGHT (TM) SYSTEM 0.80% HR-601(Retarder), 3 lbm/sk Kol-Seal (Lost Circulation Additive), 0.125 lbm/sk Poly-E-Flake (Lost Circulation Additive)
	250	14.8	1.33	6.34	7:19	Super H Cement, 0.1% HR-800 (Retarder), 0.5% Halad(R)- 344 (Low Fluid Loss Control), 0.3% CFR-3 (Dispersant), 2 lbm Kol-Seal, 3 lbm Salt (Accelerator)
2 nd Int	1080	10.3	3.05	15.63	15:07	TUNED LIGHT (TM) SYSTEM 0.80% HR-601, 3 lbm/sk Kol-Seal, 0.125 lbm/sk Poly-E- Flake
	790	13.2	1.65	8.45	12:57	Super H Cement, 0.1 % HR-800, 0.5 % Halad(R)-344, 0.3 % CFR-3, 2 lbm Kol-Seal, 3 lbm Salt
Prod.	510	13.2	1.63	8.37	15:15	Super H Cement, 0.1 % HR-800, 0.5 % Halad(R)-344, 0.4 % CFR-3, 3 lbm Salt

Casing String	TOC	% Excess (Lead/Tail)
Surface	0'	50%
1 st Intermediate	0'	75%
2 nd Intermediate	3,858 3775	75% / 125%
Production	10,930	15%

OXY USA Inc. - Patton MDP1 18 Federal 6H

Include Pilot Hole Cementing specs:

Pilot hole depth: 13,812' MD

KOP 11,056' MD

WOC + tag plug →

Plug top	Plug Bottom	% Excess	No. Sacks	Wt. lb/gal	Yld ft ³ /sack	Water gal/sk	Slurry Description and Cement Type
13,561' MD	13,812' MD	40	70	14.4	1.246	5.73	VersaCem H, 50% Cement H, 50% Poz mix, 2% Bentonite (Light Weight Additive), 0.3% CFR-3 (friction reducer)
11,780' MD	12,030' MD	40	65	14.4	1.246	5.73	VersaCem H, 50% Cement H, 50% Poz mix, 2% Bentonite, 0.3% CFR-3

Note: The first plug is designed to be 250' in length to isolate the Strawn and bottom Wolfcamp from potential high pressure zones. The second one plug is designed to be 250' in length to isolate the 7-5/8" casing shoe from 12,030' to 11,780' (150' inside the shoe).

4. Pressure Control Equipment

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
13.500" Intermediate	13-5/8"	5M	Annular	✓	70% of working pressure
			Blind Ram	✓	250 / 5,000psi
			Upper Pipe Ram		
			Double Ram	✓	
			Lower Pipe Ram		
6.750" Pilot	13-5/8"	10M	Annular	✓	70% of working pressure
			Blind Ram	✓	250 / 10,000psi
			Upper Pipe Ram	✓	
			Double Ram		
			Lower Pipe Ram	✓	

*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

OXY USA Inc. - Patton MDP1 18 Federal 6H

See COA

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
X	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
Y	Are anchors required by manufacturer?
X	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. See attached schematic. We are proposing that we will run the wellhead through the rotary prior to cementing surface casing as discussed with the BLM on October 8, 2015.

5. Mud Program

*700'
4275'*

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	Surf. TD 640'	EnerSeal (MMH)	8.4-8.6	40-60	N/C
640'	1st Int. 4,358'	Brine	9.8-10.0	35-45	N/C
4,358'	Int. TD 11,930'	EnerSeal (MMH)	9.4-10.0	38-50	N/C
11,930'	Pilot TD 13,812'	Oil-Based Mud	10.0 - 13.5	35-50	N/C
10,956'	Prod. TD 16,227'	Oil-Based Mud	10.0-12.0	35-50	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

Oxy proposes to drill out the 16" surface casing shoe with a saturated brine system from 640' - 4,358', which is the 1st intermediate casing point. At this point we will drillout the 1st intermediate casing with a high viscosity mixed metal hydroxide system. We will drill with this system to the intermediate TD @ 11,930'.

What will be used to monitor the loss or gain of fluid?	PVT/MD Totco/Visual Monitoring
---	--------------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
Yes	Will run GR from TD to surface (vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
Yes	Logs are planned based on well control or offset log information.
No	Drill stem test? If yes, explain
No	Coring?

OXY USA Inc. - Patton MDP1 18 Federal 6H

Additional logs planned		Interval
No	Resistivity	-
No	Density	-
No	CBL	-
Yes	Mud log	Surface Shoe - TD
Yes	Pex	Pilot TD – 2 nd Intermediate Casing Shoe 2 nd Intermediate Casing Shoe – Avalon top

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	9,695 psi (pilot) / 7,250 psi (lateral)
Abnormal Temperature	No

Pump high viscosity sweeps as needed for hole cleaning. The mud system will be monitored visually/manually as well as with an electronic PVT. The necessary mud products for additional weight and fluid loss control will be on location at all times. Appropriately weighted mud will be used to isolate potential gas, oil, and water zones until such time as casing can be cemented into place for zonal isolation.

Hydrogen Sulfide (H₂S) monitors will be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

N	H ₂ S is present
Y	H ₂ S Plan attached

8. Other facets of operation

	Yes/No
Will the well be drilled with a walking/skidding operation? If yes, describe.	No
Will more than one drilling rig be used for drilling operations? If yes, describe.	No

Attachments

- ☒ Directional Plan
- ☒ H₂S Contingency Plan
- ☒ Flex III Attachments

COMPANY PERSONNEL:

<u>Name</u>	<u>Title</u>	<u>Office Phone</u>	<u>Mobile Phone</u>
Ludwing Franco	Drilling Engineer	(713)366-5174	(832) 523-6392
Miranda Hust	Drilling Engineer	(713)215-7576	(832) 390-0645
Diego Tellez	Drilling Engineering Team Lead	(713)350-4602	(713) 303-4932
Ryan Farrell	Drilling Engineer Supervisor	(713)366-5058	(832) 914-7443
Simon Benavides	Drilling Superintendent	(713)215-7403	(832) 528-3547
Daniel Holderman	Drilling Manager	(713)497-2006	(832) 525-9029

4 1/2 CS5 Spec

PERFORMANCE DATA

TMK UP DQX Technical Data Sheet

4.500 in

13.50 lbs/ft

P-110 HC

Tubular Parameters

Size	4.500	in	Minimum Yield	110,000	psi
Nominal Weight	13.50	lbs/ft	Minimum Tensile	125,000	psi
Grade	P-110 HC		Yield Load	422,000	lbs
PE Weight	13.04	lbs/ft	Tensile Load	479,000	lbs
Wall Thickness	0.290	in	Min. Internal Yield Pressure	12,400	psi
Nominal ID	3.920	in	Collapse Pressure	11,750	psi
Drift Diameter	3.795	in			
Nom. Pipe Body Area	3.836	in ²			

Connection Parameters

Connection OD	5.000	in
Connection ID	3.920	in
Make-Up Loss	3.772	in
Critical Section Area	3.836	in ²
Tension Efficiency	100.0	%
Compression Efficiency	100.0	%
Yield Load In Tension	422,000	lbs
Min. Internal Yield Pressure	12,400	psi
Collapse Pressure	11,750	psi


Make-Up Torques

Min. Make-Up Torque	6,000	ft-lbs
Opt. Make-Up Torque	6,700	ft-lbs
Max. Make-Up Torque	7,300	ft-lbs
Yield Torque	10,800	ft-lbs

Printed on: August-22-2014

NOTE

The content of this Technical Data Sheet is for general information only and does not guarantee performance or imply fitness for a particular purpose which only a competent drilling professional can determine considering the specific installation and operation parameters. Information that is printed or downloaded is no longer controlled by TMK IPSCO and might not be the latest information. Anyone using the information herein does so at their own risk. To verify that you have the latest TMK IPSCO technical information, please contact TMK IPSCO Technical Sales toll-free at 1-888-258-2000.



PERFORMANCE DATA

TMK UP ULTRA™ SF
Technical Data Sheet

5.500 in

20.00 lbs/ft

P-110

Tubular Parameters


Size	5.500	in	Minimum Yield	110,000	psi
Nominal Weight	20.00	lbs/ft	Minimum Tensile	125,000	psi
Grade	P-110		Yield Load	641,000	lbs
PE Weight	19.81	lbs/ft	Tensile Load	728,000	lbs
Wall Thickness	0.361	in	Min. Internal Yield Pressure	12,600	psi
Nominal ID	4.778	in	Collapse Pressure	11,100	psi
Drift Diameter	4.653	in			
Nom. Pipe Body Area	5.828	in ²			

Connection Parameters

Connection OD	5.646	in
Connection ID	4.734	in
Make-Up Loss	5.526	in
Critical Section Area	5.289	in ²
Tension Efficiency	90.5	%
Compression Efficiency	90.5	%
Yield Load In Tension	580,000	lbs
Min. Internal Yield Pressure	12,600	psi
Collapse Pressure	11,100	psi
Uniaxial Bending	83	°/100 ft

Make-Up Torques

Min. Make-Up Torque	10,200	ft-lbs
Opt. Make-Up Torque	11,200	ft-lbs
Max. Make-Up Torque	12,300	ft-lbs
Yield Torque	15,400	ft-lbs



Printed on: December-10-2014

NOTE

The content of this Technical Data Sheet is for general information only and does not guarantee performance or imply fitness for a particular purpose, which only a competent drilling professional can determine considering the specific installation and operation parameters. Information that is printed or downloaded is no longer controlled by TMK IPSCO and might not be the latest information. Anyone using the information herein does so at their own risk. To verify that you have the latest TMK IPSCO technical information, please contact TMK IPSCO Technical Sales toll-free at 1-888-258-2000.



DE-1

ST01 Oxy Patton MDP1 18 Fed 6H NM Eddy County (NAD 27) H&P 636

DP-2

Schumberger

Oxy Patton MDP1 18 Fed 6H Pilot Rev0 MMC 20Apr16 Proposal Geodetic Report (Non-Def Plan)



Report Date:	April 21, 2016 - 11:29 AM	Survey / DLS Computation:	Minimum Curvature / Lubinski
Client:	OXY	Vertical Section Azimuth:	177.940° (Grid North)
Field:	NM Eddy County (NAD 27)	Vertical Section Origin:	0 000 ft, 0 000 n
Structure / Slot:	Oxy Patton MDP1 18 Fed 6H / Oxy Patton MDP1 18 Fed 6H	TVD Reference Datum:	RKB
Well:	Oxy Patton MDP1 18 Fed 6H	TVD Reference Elevation:	3552.200 ft above MSL
Borehole:	Pilot - Original Hole	Sealed / Ground Elevation:	3525.700 ft above MSL
LWI / API#:	Unknown / Unknown	Magnetic Declination:	7.084°
Survey Name:	Oxy Patton MDP1 18 Fed 6H Pilot Rev0 MMC 20Apr16	Total Gravity Field Strength:	988.4287mgN (0.80665 Based)
Survey Date:	April 19, 2016	Gravity Model:	QARM
Ten / AHD / DOI / ERD Ratio:	20 010° / 161 045 N / 3 511 / 0 012	Total Magnetic Field Strength:	48247.196 nT
Coordinate Reference System:	NAD27 New Mexico State Plane, Eastern Zone US Feet	Magnetic Dip Angle:	80.028°
Location Lat / Long:	N 32° 13' 26.60589", W 103° 48' 34.34248"	Declination Date:	April 19, 2016
Location Grid N/E Y/X:	N 445625.840 NUS, E 661978.180 NUS	Magnetic Declination Model:	HOGM 2015
CRS Grid Convergence Angle:	0.2793°	North Reference:	Grid North
Grid Scale Factor:	0.99993014	Grid Convergence Used:	0.2793°
Version / Patch:	2.0.385.0	Total Corr Mag North-Grid North:	6.8946°

Local Coord Referenced To Structure Reference Point

Comments	MD (ft)	(in)	Azim Grid (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (ft/100ft)	Northing (NUS)	Easting (EUS)	Latitude (N/E)	Longitude (W/E)
S&L	0.00	0.00	71.73	0.00	3552.20	0.00	0.00	0.00	N/A	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	100.00	0.00	71.73	100.00	-3432.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	200.00	0.00	71.73	200.00	-3352.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	300.00	0.00	71.73	300.00	-3252.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	400.00	0.00	71.73	400.00	-3152.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	500.00	0.00	71.73	500.00	-3052.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
Rustler	582.00	0.00	71.73	582.00	-2960.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	600.00	0.00	71.73	600.00	-2952.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
18" Casmg	640.00	0.00	71.73	640.00	-2912.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	700.00	0.00	71.73	700.00	-2852.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	800.00	0.00	71.73	800.00	-2752.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	900.00	0.00	71.73	900.00	-2652.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
Salado	972.00	0.00	71.73	972.00	-2580.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	1000.00	0.00	71.73	1000.00	-2562.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	1100.00	0.00	71.73	1100.00	-2452.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	1200.00	0.00	71.73	1200.00	-2352.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	1300.00	0.00	71.73	1300.00	-2252.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	1400.00	0.00	71.73	1400.00	-2152.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	1500.00	0.00	71.73	1500.00	-2052.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	1600.00	0.00	71.73	1600.00	-1952.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	1700.00	0.00	71.73	1700.00	-1852.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	1800.00	0.00	71.73	1800.00	-1752.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	1900.00	0.00	71.73	1900.00	-1652.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	2000.00	0.00	71.73	2000.00	-1552.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	2100.00	0.00	71.73	2100.00	-1452.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	2200.00	0.00	71.73	2200.00	-1352.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	2300.00	0.00	71.73	2300.00	-1252.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	2400.00	0.00	71.73	2400.00	-1152.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	2500.00	0.00	71.73	2500.00	-1052.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	2600.00	0.00	71.73	2600.00	-952.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	2700.00	0.00	71.73	2700.00	-852.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	2800.00	0.00	71.73	2800.00	-752.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
Casfile	2852.00	0.00	71.73	2852.00	-700.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	2900.00	0.00	71.73	2900.00	-652.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	3000.00	0.00	71.73	3000.00	-552.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	3100.00	0.00	71.73	3100.00	-452.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	3200.00	0.00	71.73	3200.00	-352.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	3300.00	0.00	71.73	3300.00	-252.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	3400.00	0.00	71.73	3400.00	-152.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	3500.00	0.00	71.73	3500.00	-52.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	3600.00	0.00	71.73	3600.00	47.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	3700.00	0.00	71.73	3700.00	147.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	3800.00	0.00	71.73	3800.00	247.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	3900.00	0.00	71.73	3900.00	347.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	4000.00	0.00	71.73	4000.00	447.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	4100.00	0.00	71.73	4100.00	547.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	4200.00	0.00	71.73	4200.00	647.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	4300.00	0.00	71.73	4300.00	747.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
Delaware	4310.00	0.00	71.73	4310.00	757.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
Ball Canyon	4354.00	0.00	71.73	4354.00	801.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
10 3/4" Casmg	4358.00	0.00	71.73	4358.00	805.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	4400.00	0.00	71.73	4400.00	847.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	4500.00	0.00	71.73	4500.00	847.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	4600.00	0.00	71.73	4600.00	1047.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	4700.00	0.00	71.73	4700.00	1147.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	4800.00	0.00	71.73	4800.00	1247.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	4900.00	0.00	71.73	4900.00	1347.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	5000.00	0.00	71.73	5000.00	1447.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	5100.00	0.00	71.73	5100.00	1547.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
Cherry Canyon	5126.00	0.00	71.73	5126.00	1573.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	5200.00	0.00	71.73	5200.00	1647.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	5300.00	0.00	71.73	5300.00	1747.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	5400.00	0.00	71.73	5400.00	1847.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	5500.00	0.00	71.73	5500.00	1947.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	5600.00	0.00	71.73	5600.00	2047.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	5700.00	0.00	71.73	5700.00	2147.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"
	5800.00	0.00	71.73	5800.00	2247.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.61"	W 103° 48' 34.34"

DP-3

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	TVDSS (ft)	VSEC (s)	NS (ft)	EW (ft)	DLS (ft/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ° ' ")	Longitude (E/W ° ° ' ")	
Brushy Canyon	5900.00	0.00	71.73	5900.00	2347.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	6000.00	0.00	71.73	6000.00	2447.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	6100.00	0.00	71.73	6100.00	2547.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	6200.00	0.00	71.73	6200.00	2647.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	6300.00	0.00	71.73	6300.00	2747.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	6400.00	0.00	71.73	6400.00	2847.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	6449.00	0.00	71.73	6449.00	2896.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	6500.00	0.00	71.73	6500.00	2947.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	6600.00	0.00	71.73	6600.00	3047.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	6700.00	0.00	71.73	6700.00	3147.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	6800.00	0.00	71.73	6800.00	3247.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	6900.00	0.00	71.73	6900.00	3347.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	7000.00	0.00	71.73	7000.00	3447.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	7100.00	0.00	71.73	7100.00	3547.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	7200.00	0.00	71.73	7200.00	3647.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	7300.00	0.00	71.73	7300.00	3747.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	7400.00	0.00	71.73	7400.00	3847.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	7500.00	0.00	71.73	7500.00	3947.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	7600.00	0.00	71.73	7600.00	4047.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	7700.00	0.00	71.73	7700.00	4147.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	7800.00	0.00	71.73	7800.00	4247.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
7900.00	0.00	71.73	7900.00	4347.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34		
Pine Spring	8000.00	0.00	71.73	8000.00	4447.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	8100.00	0.00	71.73	8100.00	4547.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	8125.00	0.00	71.73	8125.00	4572.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	8200.00	0.00	71.73	8200.00	4647.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	8300.00	0.00	71.73	8300.00	4747.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	8400.00	0.00	71.73	8400.00	4847.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	8500.00	0.00	71.73	8500.00	4947.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	8600.00	0.00	71.73	8600.00	5047.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	8700.00	0.00	71.73	8700.00	5147.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	8800.00	0.00	71.73	8800.00	5247.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	8900.00	0.00	71.73	8900.00	5347.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	9000.00	0.00	71.73	9000.00	5447.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	9100.00	0.00	71.73	9100.00	5547.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	9200.00	0.00	71.73	9200.00	5647.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	9300.00	0.00	71.73	9300.00	5747.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34	
	Backbuild 2 7/100" DLS to 10" Inc	9380.50	0.00	71.73	9380.50	5826.30	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32 13 26.81	W 103 48 34.34
	Hold 10" Inc	9400.00	0.39	71.73	9400.00	5847.80	-0.02	0.02	0.06	2.00	445625.84	861978.24	N 32 13 26.81	W 103 48 34.34
		9500.00	2.39	71.73	9499.97	5947.77	-0.70	0.78	2.37	2.00	445626.02	861980.55	N 32 13 26.81	W 103 48 34.31
		9600.00	4.39	71.73	9599.79	6047.59	-2.25	2.84	7.98	2.00	445626.47	861986.18	N 32 13 26.83	W 103 48 34.25
		9700.00	8.39	71.73	9699.34	6147.14	-4.97	5.58	16.90	2.00	445631.42	861995.08	N 32 13 26.86	W 103 48 34.15
		9800.00	8.39	71.73	9798.50	6246.30	-8.58	9.81	29.11	2.00	445635.45	862007.29	N 32 13 26.79	W 103 48 34.00
9889.74		10.00	71.73	9878.20	6326.00	-12.18	13.88	41.37	2.00	445639.50	862019.55	N 32 13 26.74	W 103 48 33.88	
9900.00		10.00	71.73	9897.17	6444.97	-13.10	14.71	44.55	0.00	445640.58	862022.72	N 32 13 26.75	W 103 48 33.82	
10000.00		10.00	71.73	9995.65	6443.45	-17.05	20.15	61.04	0.00	445645.99	862039.22	N 32 13 26.80	W 103 48 33.83	
10100.00		10.00	71.73	10094.13	6541.93	-22.80	25.85	77.54	0.00	445651.44	862055.71	N 32 13 26.86	W 103 48 33.44	
10200.00		10.00	71.73	10192.61	6640.41	-27.85	31.05	94.04	0.00	445656.89	862072.21	N 32 13 26.91	W 103 48 33.25	
Drop 2 7/100" DLS to Vertical	10300.00	10.00	71.73	10291.09	6738.89	-32.50	36.49	110.53	0.00	445662.33	862088.71	N 32 13 26.96	W 103 48 33.05	
Hold Vertical	10311.39	10.00	71.73	10302.30	6780.10	-33.05	37.11	112.41	0.00	445662.55	862090.58	N 32 13 26.97	W 103 48 33.03	
	10400.00	8.23	71.73	10389.79	6837.59	-36.97	41.52	125.75	2.00	445667.35	862103.92	N 32 13 27.01	W 103 48 32.88	
	10500.00	8.23	71.73	10488.99	6936.79	-40.48	45.48	137.70	2.00	445671.30	862115.87	N 32 13 27.05	W 103 48 32.74	
	10600.00	4.23	71.73	10588.57	7036.37	-43.03	48.32	148.38	2.00	445674.16	862124.53	N 32 13 27.09	W 103 48 32.64	
	10700.00	2.23	71.73	10688.40	7135.20	-44.80	50.09	151.71	2.00	445675.93	862129.69	N 32 13 27.09	W 103 48 32.57	
	10800.00	0.23	71.73	10788.37	7234.17	-45.21	50.77	153.78	2.00	445676.61	862131.93	N 32 13 27.10	W 103 48 32.55	
	10811.63	0.00	71.73	10800.00	7247.80	-45.21	50.77	153.78	2.00	445676.61	862131.95	N 32 13 27.10	W 103 48 32.55	
	10900.00	0.00	71.73	10888.37	7338.17	-45.21	50.77	153.78	0.00	445676.61	862131.95	N 32 13 27.10	W 103 48 32.55	
	11000.00	0.00	71.73	10986.37	7438.17	-45.21	50.77	153.78	0.00	445676.61	862131.95	N 32 13 27.10	W 103 48 32.55	
	11100.00	0.00	71.73	11088.37	7538.17	-45.21	50.77	153.78	0.00	445676.61	862131.95	N 32 13 27.10	W 103 48 32.55	
Wattcamp	11200.00	0.00	71.73	11188.37	7638.17	-45.21	50.77	153.78	0.00	445676.61	862131.95	N 32 13 27.10	W 103 48 32.55	
	11300.00	0.00	71.73	11288.37	7738.17	-45.21	50.77	153.78	0.00	445676.61	862131.95	N 32 13 27.10	W 103 48 32.55	
	11400.00	0.00	71.73	11388.37	7838.17	-45.21	50.77	153.78	0.00	445676.61	862131.95	N 32 13 27.10	W 103 48 32.55	
	11500.00	0.00	71.73	11488.37	7938.17	-45.21	50.77	153.78	0.00	445676.61	862131.95	N 32 13 27.10	W 103 48 32.55	
	11530.63	0.00	71.73	11518.00	7968.80	-45.21	50.77	153.78	0.00	445676.61	8621			

DP-4

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (°)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' '')	Longitude (E/W ° ' '')
		1	0 000	28 500	1/100 000	30 000	30 000		NAL_MWD_HDGM-Depth Only	Pilot - Original Hole / Dry Patton MDP1 18 Fed 6H Pilot Rev0 MMC 20Apr16			
		1	28 500	13811 625	1/100 000	30 000	30 000		NAL_MWD_HDGM	Pilot - Original Hole / Dry Patton MDP1 18 Fed 6H Pilot Rev0 MMC			

Oxy Patton MDP1 18 Fed 6H ST01 Rev0 MMC 20Apr16 Proposal Geodetic Report

(Non-Def Plan)



DP-5

Report Date: Apr 21, 2016 - 11:32 AM
 Client: OXY
 Field: NM Eddy County (NAD 27)
 Structure / Slat: Oxy Patton MDP1 18 Fed 6H / Oxy Patton MDP1 18 Fed 6H
 Well: Oxy Patton MDP1 18 Fed 6H
 Borehole: ST01
 UWI / API#: Unknown / Unknown
 Survey Name: Oxy Patton MDP1 18 Fed 6H ST01 Rev0 MMC 20Apr16
 Survey Date: April 19, 2016
 Tilt / AHD / DDI / ERD Ratio: 110 010 ° / 5006 415 N / 5 896 / 0 431
 Coordinate Reference System: NAD27 New Mexico State Plane, Eastern Zone, US Feet
 Location Lat / Long: N 32° 13' 28.5058" W 103° 48' 34.3424"
 Location Grid N/E Y/X: N 445625 840 NUS, E 661978 180 NUS
 CRS Grid Convergence Angle: 0.2793 °
 Grid Scale Factor: 0.99993914
 Version / Patch: 2.9.365.0
 Survey / DLS Computation: Minimum Curvature / Lubinski
 Vertical Section Azimuth: 177.840 ° (Grid North)
 Vertical Section Origin: 0 000 N, 0 000 E
 TVD Reference Datum: RKB
 TVD Reference Elevation: 3552 200 ft above MSL
 Seabed / Ground Elevation: 3525 700 ft above MSL
 Magnetic Declination: 7.084 °
 Total Gravity Field Strength: 896 4287 mgn (g 80665 Based)
 Gravity Model: GARM
 Total Magnetic Field Strength: 46247 198 nT
 Magnetic Dip Angle: 66.038 °
 Declination Date: April 19, 2016
 Magnetic Declination Mode: HDGM 2015
 North Reference: Grid North
 Grid Convergence Used: 0.2793 °
 Total Cor Mag North -> Grid North: 8.6046 °
 Local Coord Referenced To: Structure Reference Point

Comments	MD (ft)	Incl (°)	Azin Grid (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (ft/100ft)	Northing (NUS)	Easting (EUS)	Latitude (N/E ° ' ")	Longitude (E/W ° ' ")
SRL	0.00	0.00	0.00	0.00	-3552.20	0.00	0.00	0.00	N/A	445625.84	661978.18	N 32 13 28.51	W 103 48 34.34
Rustler	582.00	0.00	71.73	582.00	-2960.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32 13 28.51	W 103 48 34.34
16" Casing	640.00	0.00	71.73	640.00	-2912.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32 13 28.51	W 103 48 34.34
Salado	872.00	0.00	71.73	872.00	-2580.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32 13 28.51	W 103 48 34.34
Castile	2832.00	0.00	71.73	2832.00	-700.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32 13 28.51	W 103 48 34.34
Delaware	4310.00	0.00	71.73	4310.00	757.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32 13 28.51	W 103 48 34.34
Dell Canyon	4354.00	0.00	71.73	4354.00	801.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32 13 28.51	W 103 48 34.34
10 3/4" Casing	4358.00	0.00	71.73	4358.00	805.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32 13 28.51	W 103 48 34.34
Cherry Canyon	5126.00	0.00	71.73	5126.00	1573.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32 13 28.51	W 103 48 34.34
Brushy Canyon	6449.00	0.00	71.73	6449.00	2696.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32 13 28.51	W 103 48 34.34
Bone Spring	8125.00	0.00	71.73	8125.00	4572.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32 13 28.51	W 103 48 34.34
Backbuild													
2 1/100" DLS to	9360.50	0.00	71.73	9360.50	5628.30	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32 13 28.51	W 103 48 34.34
10" Inc													
Hold 10" Inc	9880.74	10.00	71.73	9878.20	6328.00	-12.16	13.66	41.37	2.00	445639.50	662019.55	N 32 13 28.74	W 103 48 33.68
Drop 2 1/100"	10311.39	10.00	71.73	10302.30	6750.10	33.05	37.11	112.41	0.00	445662.95	662090.58	N 32 13 28.97	W 103 48 33.03
DLS to Vertical													
Hold Vertical	10811.63	0.00	71.73	10800.00	7247.80	-45.21	50.77	153.78	2.00	445676.81	662131.95	N 32 13 27.10	W 103 48 32.55
7 5/8" Casing	10911.63	0.00	71.73	10900.00	7247.80	-45.21	50.77	153.78	0.00	445676.81	662131.95	N 32 13 27.10	W 103 48 32.55
Fe Into Pilot													
Hole - Wingstock	10958.00	0.00	71.73	10944.37	7392.17	-45.21	50.77	153.78	0.00	445676.81	662131.95	N 32 13 27.10	W 103 48 32.55
	11000.00	0.00	71.73	10968.37	7436.17	-45.21	50.77	153.78	0.00	445676.81	662131.95	N 32 13 27.10	W 103 48 32.55
KOP - Built													
10 1/100" DLS to	11055.67	0.00	71.73	11044.04	7491.84	-45.21	50.77	153.78	0.00	445676.81	662131.95	N 32 13 27.10	W 103 48 32.55
Land													
	11100.00	4.43	179.78	11085.33	7536.13	-43.50	49.06	153.78	10.00	445674.00	662131.95	N 32 13 27.08	W 103 48 32.55
	11200.00	18.43	179.78	11186.85	7634.85	-27.14	32.89	153.85	10.00	445658.53	662132.02	N 32 13 26.92	W 103 48 32.55
	11300.00	24.43	179.78	11281.04	7728.84	6.07	-0.54	153.98	10.00	445625.30	662132.15	N 32 13 26.59	W 103 48 32.55
	11400.00	34.43	179.78	11368.02	7815.82	55.10	-49.62	154.17	10.00	445678.23	662132.34	N 32 13 26.11	W 103 48 32.55
	11500.00	44.43	179.78	11445.18	7892.96	116.53	-113.05	154.41	10.00	445652.72	662132.58	N 32 13 25.46	W 103 48 32.55
	11600.00	54.43	179.78	11510.11	7957.91	184.36	-188.92	154.70	10.00	445438.93	662132.87	N 32 13 24.73	W 103 48 32.55
Wolfcamp	11815.59	55.89	179.78	11518.00	7988.80	207.15	-201.72	154.75	10.00	445424.13	662132.92	N 32 13 24.60	W 103 48 32.55
	11700.00	64.43	179.78	11560.80	8008.70	280.31	-274.92	155.03	10.00	445350.94	662133.21	N 32 13 23.88	W 103 48 32.55
	11800.00	74.43	179.78	11595.98	8043.78	373.77	-386.42	155.40	10.00	445267.47	662133.57	N 32 13 22.95	W 103 48 32.55
	11900.00	84.43	179.78	11614.30	8082.10	471.90	-486.60	155.77	10.00	445190.27	662133.94	N 32 13 21.98	W 103 48 32.56
Landing Point @													
80" Inc	11955.87	90.00	179.78	11617.00	8084.80	527.45	-522.18	155.99	10.00	445103.89	662134.18	N 32 13 21.43	W 103 48 32.56
	12000.00	90.00	179.78	11617.00	8084.80	571.78	-566.51	156.16	0.00	445058.36	662134.33	N 32 13 20.99	W 103 48 32.56
	12100.00	90.00	179.78	11617.00	8084.80	617.71	-606.51	156.54	0.00	445058.36	662134.71	N 32 13 20.00	W 103 48 32.56
	12200.00	90.00	179.78	11617.00	8084.80	671.66	-666.51	156.83	0.00	445058.36	662135.10	N 32 13 19.01	W 103 48 32.56
	12300.00	90.00	179.78	11617.00	8084.80	731.61	-726.51	157.32	0.00	445058.36	662135.49	N 32 13 18.02	W 103 48 32.56
	12400.00	90.00	179.78	11617.00	8084.80	791.55	-786.51	157.70	0.00	445058.36	662135.87	N 32 13 17.03	W 103 48 32.56
	12500.00	90.00	179.78	11617.00	8084.80	851.50	-846.51	158.09	0.00	445058.36	662136.26	N 32 13 16.04	W 103 48 32.56
	12600.00	90.00	179.78	11617.00	8084.80	911.45	-906.51	158.47	0.00	445058.36	662136.64	N 32 13 15.05	W 103 48 32.56
	12700.00	90.00	179.78	11617.00	8084.80	971.40	-966.51	158.86	0.00	445058.36	662137.03	N 32 13 14.07	W 103 48 32.57
	12800.00	90.00	179.78	11617.00	8084.80	1031.35	-1026.51	159.24	0.00	445058.36	662137.41	N 32 13 13.08	W 103 48 32.57
	12900.00	90.00	179.78	11617.00	8084.80	1091.30	-1086.51	159.63	0.00	445058.36	662137.80	N 32 13 12.09	W 103 48 32.57
	13000.00	90.00	179.78	11617.00	8084.80	1151.25	-1146.51	160.01	0.00	445058.36	662138.18	N 32 13 11.10	W 103 48 32.57
	13100.00	90.00	179.78	11617.00	8084.80	1211.20	-1206.51	160.40	0.00	445058.36	662138.57	N 32 13 10.11	W 103 48 32.57
	13200.00	90.00	179.78	11617.00	8084.80	1271.15	-1266.51	160.78	0.00	445058.36	662138.95	N 32 13 9.12	W 103 48 32.57
	13300.00	90.00	179.78	11617.00	8084.80	1331.10	-1326.51	161.17	0.00	445058.36	662139.34	N 32 13 8.13	W 103 48 32.57
	13400.00	90.00	179.78	11617.00	8084.80	1391.05	-1386.51	161.55	0.00	445058.36	662139.72	N 32 13 7.14	W 103 48 32.57
	13500.00	90.00	179.78	11617.00	8084.80	1451.00	-1446.51	161.94	0.00	445058.36	662140.11	N 32 13 6.15	W 103 48 32.57
	13600.00	90.00	179.78	11617.00	8084.80	1510.95	-1506.51	162.33	0.00	445058.36	662140.50	N 32 13 5.16	W 103 48 32.58
	13700.00	90.00	179.78	11617.00	8084.80	1570.90	-1566.51	162.71	0.00	445058.36	662140.88	N 32 13 4.17	W 103 48 32.58
	13800.00	90.00	179.78	11617.00	8084.80	1630.85	-1626.51	163.10	0.00	445058.36	662141.27	N 32 13 3.18	W 103 48 32.58
	13900.00	90.00	179.78	11617.00	8084.80	1690.80	-1686.51	163.48	0.00	445058.36	662141.65	N 32 13 2.19	W 103 48 32.58
	14000.00	90.00	179.78	11617.00	8084.80	1750.75	-1746.51	163.87	0.00	445058.36	662142.04	N 32 13 1.20	W 103 48 32.58
	14100.00	90.00	179.78	11617.00	8084.80	1810.70	-1806.51	164.25	0.00	445058.36	662142.42	N 32 13 0.21	W 103 48 32.58
	14200.00	90.00	179.78	11617.00	8084.80	1870.65	-1866.51	164.64	0.00	445058.36	662142.81	N 32 12 59.22	W 103 48 32.58
	14300.00	90.00	179.78	11617.00	8084.80	1930.60	-1926.51	165.02	0.00	445058.36	662143.19	N 32 12 58.23	W 103 48 32.58
	14400.00	90.00	179.78	11617.00	8084.80	1990.55	-1986.51	165.41	0.00	445058.36	662143.58	N 32 12 57.24	W 103 48 32.59
	14500.00	90.00	179.78	11617.00	8084.80	2050.50	-2046.51	165.79	0.00	445058.36	662143.96	N 32 12 56.25	W 103 48 32.59
	14600.00	90.00	179.78	11617.00	8084.80	2110.45	-2106.51	166.18	0.00	445058.36	662144.35	N 32 12 55.26	W 103 48 32.59
	14700.00	90.00	179.78	11617.00	8084.80	2170.40	-2166.51	166.56	0.00	445058.36	662144.73	N 32 12 54.27	W 103 48 32.59
	14800.00	90.00	179.78	11617.00	8084.80	2230.35	-2226.51	166.95	0.00	445058.36	662145.12	N 32 12 53.28	W 103 48 32.59


DP-6

Comments	MD (ft)	Incl (°)	Asm Grid (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (NUS)	Easting (EUS)	Latitude (N/S ° °')	Longitude (E/W ° °')
	14900.00	90.00	179.78	11617.00	8064.80	3470.27	-3488.49	187.34	0.00	442159.57	882145.51	N 32 12 52.30	W 103 48 32.59
	15000.00	90.00	179.78	11617.00	8064.80	3570.21	-3588.49	187.72	0.00	442058.57	882145.89	N 32 12 51.31	W 103 48 32.59
	15100.00	90.00	179.78	11617.00	8064.80	3670.16	-3688.49	188.11	0.00	441958.58	882146.28	N 32 12 50.32	W 103 48 32.59
	15200.00	90.00	179.78	11617.00	8064.80	3770.11	-3788.49	188.49	0.00	441858.59	882146.66	N 32 12 49.33	W 103 48 32.60
	15300.00	90.00	179.78	11617.00	8064.80	3870.06	-3888.49	188.88	0.00	441759.59	882147.05	N 32 12 48.34	W 103 48 32.60
	15400.00	90.00	179.78	11617.00	8064.80	3970.01	-3988.49	189.26	0.00	441659.60	882147.43	N 32 12 47.35	W 103 48 32.60
	15500.00	90.00	179.78	11617.00	8064.80	4069.96	-4088.49	189.65	0.00	441559.61	882147.82	N 32 12 46.36	W 103 48 32.60
	15600.00	90.00	179.78	11617.00	8064.80	4169.91	-4188.49	170.03	0.00	441459.62	882148.20	N 32 12 45.37	W 103 48 32.60
	15700.00	90.00	179.78	11617.00	8064.80	4269.85	-4288.49	170.42	0.00	441359.62	882148.58	N 32 12 44.38	W 103 48 32.60
	15800.00	90.00	179.78	11617.00	8064.80	4369.80	-4388.49	170.80	0.00	441259.63	882148.97	N 32 12 43.39	W 103 48 32.60
	15900.00	90.00	179.78	11617.00	8064.80	4469.75	-4488.49	171.19	0.00	441159.64	882149.35	N 32 12 42.40	W 103 48 32.60
	16000.00	90.00	179.78	11617.00	8064.80	4569.70	-4588.49	171.58	0.00	441059.64	882149.74	N 32 12 41.41	W 103 48 32.60
	16100.00	90.00	179.78	11617.00	8064.80	4669.65	-4688.49	171.98	0.00	440959.65	882150.13	N 32 12 40.42	W 103 48 32.61
	16200.00	90.00	179.78	11617.00	8064.80	4769.60	-4788.49	172.35	0.00	440859.66	882150.52	N 32 12 39.43	W 103 48 32.61
Flat Bottom Perf	16227.18	90.00	179.78	11617.00	8064.80	4796.76	-4793.66	172.45	0.00	440832.48	882150.62	N 32 12 39.16	W 103 48 32.61

Survey Type: Non-Dal Plan

Survey Error Model: IECWSA Rev 0 *** 3-D 95 000% Confidence 2.7955 sigma
Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size Casing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey
	1	0.000	26.500	1/100.000	30.000	30.000	NAL_MWD_HDGM Depth Only	Pilot: Original Hole / Oxy Patton MDP1 18 Fed 6H Pilot Rev0 MMC 20Apr16
	1	26.500	10958.000	1/100.000	30.000	30.000	NAL_MWD_HDGM	Pilot: Original Hole / Oxy Patton MDP1 18 Fed 6H Pilot Rev0 MMC
	1	10958.000	16227.180	1/100.000	30.000	30.000	NAL_MWD_HDGM	ST01: Oxy Patton MDP1 18 Fed 6H ST01 Rev0 MMC 20Apr16

[illegible][illegible]

Oxy Patton MDP1 18 Fed 6H Pilot Rev0 MMC 20Apr16 Proposal Geodetic Report

(Non-Del Plan)



DP-2

Report Date:	April 21, 2016 - 11:29 AM	Survey / DLS Computation:	Minimum Curvature / Lubinski
Client:	OXY	Vertical Section Azimuth:	177.940° (Grid North)
Field:	NM Eddy County (NAD 27)	Vertical Section Origin:	0 000 ft, 0 000 ft
Structure / Blot:	Oxy Patton MDP1 18 Fed 6H / Oxy Patton MDP1 18 Fed 6H	TVD Reference Datum:	RKB
Well:	Oxy Patton MDP1 18 Fed 6H	TVD Reference Elevation:	3552.200 ft above MSL
Borehole:	Pilot - Original Hole	Sealed / Ground Elevation:	3525.700 ft above MSL
UWI / API#:	Unknown / Unknown	Magnetic Declination:	7.084°
Survey Name:	Oxy Patton MDP1 18 Fed 6H Pilot Rev0 MMC 20Apr16	Total Gravity Field Strength:	998.4267 mgn (9.80665 Based)
Survey Date:	April 19, 2016	Gravity Model:	GARM
Tort / AHD / DDI / ERD Ratio:	20 010° / 161 945 ft / 3 511 / 0 012	Total Magnetic Field Strength:	48247.196 nT
Coordinate Reference System:	NAD27 New Mexico State Plane, Eastern Zone US Feet	Magnetic Dip Angle:	60.036°
Location Lat / Long:	N 32° 13' 28.60589", W 103° 48' 34.34248"	Declination Date:	April 19, 2016
Location Grid N/E Y/X:	N 445625 840 NUS, E 861978 180 NUS	Magnetic Declination Model:	HOGM 2015
CRS Grid Convergence Angle:	0.2793°	North Reference:	Grid North
Grid Scale Factor:	0.999933916	Grid Convergence Used:	0.2793°
Varian / Patch:	2 0 385 D	Total Corr Mag North-Grid North:	6.8046°

Local Coord Referenced To Structure Reference Point

	Comments	MD (ft)	(in)	Azim (°)	TVD (ft)	TVD88 (ft)	VREC (ft)	H8 (ft)	EW (ft)	OLS (ft/100ft)	Northing (NUS)	Easting (EUS)	Latitude (N 27°)	Longitude (W 103°)
SHL		0.00	0.00	0.00	0.00	3552.20	0.00	0.00	0.00	N/A	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		100.00	0.00	71.73	100.00	3452.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		200.00	0.00	71.73	200.00	3352.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		300.00	0.00	71.73	300.00	3252.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		400.00	0.00	71.73	400.00	3152.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		500.00	0.00	71.73	500.00	3052.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		582.00	0.00	71.73	582.00	2980.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		600.00	0.00	71.73	600.00	2952.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		640.00	0.00	71.73	640.00	2912.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		700.00	0.00	71.73	700.00	2852.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
18" casing		800.00	0.00	71.73	800.00	2752.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		900.00	0.00	71.73	900.00	2652.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		872.00	0.00	71.73	872.00	2580.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		1000.00	0.00	71.73	1000.00	2552.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		1100.00	0.00	71.73	1100.00	2452.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		1200.00	0.00	71.73	1200.00	2352.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		1300.00	0.00	71.73	1300.00	2252.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		1400.00	0.00	71.73	1400.00	2152.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		1500.00	0.00	71.73	1500.00	2052.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		1600.00	0.00	71.73	1600.00	1952.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
Salado		1700.00	0.00	71.73	1700.00	1852.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		1800.00	0.00	71.73	1800.00	1752.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		1900.00	0.00	71.73	1900.00	1652.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		2000.00	0.00	71.73	2000.00	1552.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		2100.00	0.00	71.73	2100.00	1452.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		2200.00	0.00	71.73	2200.00	1352.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		2300.00	0.00	71.73	2300.00	1252.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		2400.00	0.00	71.73	2400.00	1152.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		2500.00	0.00	71.73	2500.00	1052.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		2600.00	0.00	71.73	2600.00	952.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
Castile		2700.00	0.00	71.73	2700.00	852.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		2800.00	0.00	71.73	2800.00	752.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		2852.00	0.00	71.73	2852.00	700.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		2900.00	0.00	71.73	2900.00	652.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		3000.00	0.00	71.73	3000.00	552.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		3100.00	0.00	71.73	3100.00	452.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		3200.00	0.00	71.73	3200.00	352.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		3300.00	0.00	71.73	3300.00	252.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		3400.00	0.00	71.73	3400.00	152.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		3500.00	0.00	71.73	3500.00	52.20	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
Delaware		3600.00	0.00	71.73	3600.00	47.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		3700.00	0.00	71.73	3700.00	147.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		3800.00	0.00	71.73	3800.00	247.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		3900.00	0.00	71.73	3900.00	347.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		4000.00	0.00	71.73	4000.00	447.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		4100.00	0.00	71.73	4100.00	547.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		4200.00	0.00	71.73	4200.00	647.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		4300.00	0.00	71.73	4300.00	747.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		4310.00	0.00	71.73	4310.00	757.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		4354.00	0.00	71.73	4354.00	801.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
10 3/4" casing		4358.00	0.00	71.73	4358.00	805.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		4400.00	0.00	71.73	4400.00	847.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		4500.00	0.00	71.73	4500.00	947.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		4600.00	0.00	71.73	4600.00	1047.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		4700.00	0.00	71.73	4700.00	1147.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		4800.00	0.00	71.73	4800.00	1247.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		4900.00	0.00	71.73	4900.00	1347.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		5000.00	0.00	71.73	5000.00	1447.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		5100.00	0.00	71.73	5100.00	1547.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		5126.00	0.00	71.73	5126.00	1573.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
Cherry Canyon		5200.00	0.00	71.73	5200.00	1647.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		5300.00	0.00	71.73	5300.00	1747.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		5400.00	0.00	71.73	5400.00	1847.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		5500.00	0.00	71.73	5500.00	1947.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		5600.00	0.00	71.73	5600.00	2047.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		5700.00	0.00	71.73	5700.00	2147.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"
		5800.00	0.00	71.73	5800.00	2247.80	0.00	0.00	0.00	0.00	445625.84	861978.18	N 32° 13' 28.61"	W 103° 48' 34.34"

DP-3

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	TVDSS (ft)	VSEC (s)	H3 (ft)	EW (ft)	DLB (ft/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N 11° 17' 11")	Longitude (W 103° 48' 34")
	5900.00	0.00	71.73	5900.00	2347.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	6000.00	0.00	71.73	6000.00	2447.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	6100.00	0.00	71.73	6100.00	2547.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	6200.00	0.00	71.73	6200.00	2647.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	6300.00	0.00	71.73	6300.00	2747.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	6400.00	0.00	71.73	6400.00	2847.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	6448.00	0.00	71.73	6448.00	2896.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	6500.00	0.00	71.73	6500.00	2947.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	6600.00	0.00	71.73	6600.00	3047.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	6700.00	0.00	71.73	6700.00	3147.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	6800.00	0.00	71.73	6800.00	3247.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	6900.00	0.00	71.73	6900.00	3347.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	7000.00	0.00	71.73	7000.00	3447.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	7100.00	0.00	71.73	7100.00	3547.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	7200.00	0.00	71.73	7200.00	3647.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	7300.00	0.00	71.73	7300.00	3747.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	7400.00	0.00	71.73	7400.00	3847.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	7500.00	0.00	71.73	7500.00	3947.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	7600.00	0.00	71.73	7600.00	4047.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	7700.00	0.00	71.73	7700.00	4147.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	7800.00	0.00	71.73	7800.00	4247.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	7900.00	0.00	71.73	7900.00	4347.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	8000.00	0.00	71.73	8000.00	4447.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	8100.00	0.00	71.73	8100.00	4547.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	8125.00	0.00	71.73	8125.00	4572.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	8200.00	0.00	71.73	8200.00	4647.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	8300.00	0.00	71.73	8300.00	4747.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	8400.00	0.00	71.73	8400.00	4847.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	8500.00	0.00	71.73	8500.00	4947.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	8600.00	0.00	71.73	8600.00	5047.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	8700.00	0.00	71.73	8700.00	5147.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	8800.00	0.00	71.73	8800.00	5247.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	8900.00	0.00	71.73	8900.00	5347.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	9000.00	0.00	71.73	9000.00	5447.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	9100.00	0.00	71.73	9100.00	5547.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	9200.00	0.00	71.73	9200.00	5647.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	9300.00	0.00	71.73	9300.00	5747.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
Backhaul 2" 100' DLS to 10" Inc	9380.50	0.00	71.73	9380.50	5826.30	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	9400.00	0.38	71.73	9400.00	5947.80	-0.02	0.02	0.08	2.80	445625.84	661978.18	N 32° 13' 26.81"	W 103° 48' 34.34"
	9500.00	2.38	71.73	9499.97	5947.77	-0.70	0.78	2.37	2.00	445625.82	661980.55	N 32° 13' 26.81"	W 103° 48' 34.31"
	9600.00	4.38	71.73	9599.79	5947.59	-2.35	2.84	7.98	2.00	445626.47	661988.16	N 32° 13' 26.83"	W 103° 48' 34.25"
	9700.00	8.38	71.73	9699.34	6147.14	-4.97	5.58	16.90	2.00	445631.42	661995.08	N 32° 13' 26.86"	W 103° 48' 34.15"
	9800.00	8.38	71.73	9798.50	6248.30	-8.58	9.61	28.11	2.00	445635.45	662007.29	N 32° 13' 26.70"	W 103° 48' 34.00"
	9880.74	10.00	71.73	9878.20	6328.00	-12.18	13.68	41.37	2.00	445639.50	662010.55	N 32° 13' 26.74"	W 103° 48' 33.88"
	9900.00	10.00	71.73	9897.17	6344.87	-13.10	14.71	44.55	0.00	445640.55	662022.72	N 32° 13' 26.75"	W 103° 48' 33.82"
	10000.00	10.00	71.73	9906.83	6443.45	-17.65	20.15	61.94	0.00	445645.99	662039.22	N 32° 13' 26.80"	W 103° 48' 33.63"
	10100.00	10.00	71.73	10094.13	6543.93	-22.80	25.63	77.54	0.00	445651.44	662055.71	N 32° 13' 26.86"	W 103° 48' 33.44"
	10200.00	10.00	71.73	10192.81	6640.41	-27.85	31.05	94.94	0.00	445656.89	662072.21	N 32° 13' 26.91"	W 103° 48' 33.25"
	10300.00	10.00	71.73	10291.09	6738.89	-32.50	36.49	110.53	0.00	445662.33	662088.71	N 32° 13' 26.96"	W 103° 48' 33.05"
Drop 2" 100' DLS to Vertical	10311.39	10.00	71.73	10302.30	6780.10	-33.95	37.11	112.41	0.00	445662.95	662090.59	N 32° 13' 26.97"	W 103° 48' 33.03"
	10400.00	8.23	71.73	10388.79	6837.59	-38.97	41.52	125.75	2.00	445667.38	662103.82	N 32° 13' 27.01"	W 103° 48' 32.89"
	10500.00	6.23	71.73	10488.99	6938.79	-40.48	45.48	137.70	2.00	445671.30	662115.87	N 32° 13' 27.05"	W 103° 48' 32.74"
	10600.00	4.23	71.73	10588.57	7036.37	-43.02	48.32	146.36	2.00	445674.18	662124.63	N 32° 13' 27.08"	W 103° 48' 32.64"
	10700.00	2.23	71.73	10688.46	7136.20	-44.80	50.09	151.71	2.00	445675.93	662129.69	N 32° 13' 27.09"	W 103° 48' 32.57"
	10800.00	0.23	71.73	10788.37	7236.17	-45.21	50.77	153.78	2.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	10811.63	0.00	71.73	10800.00	7247.80	-45.21	50.77	153.78	2.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	10900.00	0.00	71.73	10888.37	7336.17	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11000.00	0.00	71.73	10988.37	7436.17	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11100.00	0.00	71.73	11088.37	7536.17	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11200.00	0.00	71.73	11188.37	7636.17	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11300.00	0.00	71.73	11288.37	7736.17	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11400.00	0.00	71.73	11388.37	7836.17	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11500.00	0.00	71.73	11488.37	7936.17	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11530.63	0.00	71.73	11518.00	7968.80	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11600.00	0.00	71.73	11588.37	8036.17	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11700.00	0.00	71.73	11688.37	8136.17	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11780.63	0.00	71.73	11762.00	8216.80	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11800.00	0.00	71.73	11784.37	8236.17	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11900.00	0.00	71.73	11884.37	8336.17	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	11930.63	0.00	71.73	11918.00	8368.80	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"
	12000.00	0.00	71.73	11988.37	8436.17	-45.21	50.77	153.78	0.00	445676.61	662131.93	N 32° 13' 27.10"	W 103° 48' 32.53"

DP-4

Command	MJ (#)	Incl (°)	Azim Grid (°)	TYD (ft)	TYDSS (ft)	VSEC (ft)	NB (ft)	EW (ft)	DLS (°/100ft)	Northing (BUS)	Easting (BUS)	Latitude (N/S ° ' '')	Longitude (E/W ° ' '')
		1	0 000	28 500	1/100 000	30 000	30 800		NAL_MWD_HDGM: Depth Only	Pilot - Original Hole / Dry Pattern MDP1 18 Fed 6H Pilot Rev0 MMC 20Apr16			
		1	28 500	13811 625	1/100 000	30 000	30 000		NAL_MWD_HDGM	Pilot - Original Hole / Dry Pattern MDP1 18 Fed 6H Pilot Rev0 MMC			

Oxy Patton MDP1 18 Fed 6H ST01 Rev0 MMC 20Apr16 Proposal Geodetic Report

(Non-Def Plan)



Report Date: April 21, 2016 - 11:32 AM
 Client: OXY
 Field: NM Eddy County (NAD 27)
 Structure / Slet: Oxy Patton MDP1 18 Fed 6H / Oxy Patton MDP1 18 Fed 6H
 Well: Oxy Patton MDP1 18 Fed 6H
 Borehole: ST01
 UWI / API: Unknown / Unknown
 Survey Name: Oxy Patton MDP1 18 Fed 6H ST01 Rev0 MMC 20Apr16
 Survey Date: April 19, 2016
 Tort / AND / DDI / ERD Ratio: 110 010 * / 6006 415 N / 5 894 / 0 431
 Coordinate Reference System: NAD27 New Mexico State Plane, Eastern Zone, US Feet
 Location Lat / Long: N 32° 13' 28.80589" W 103° 48' 34.34248"
 Location Grid N/E Y/X: N 445625 840 NUS, E 661978 180 NUS
 CRB Grid Convergence Angle: 0.2703°
 Grid Scale Factor: 0.99993914
 Version / Patch: 2.9.385 D
 Survey / DLS Computation: Minimum Curvature / Lubinski
 Vertical Section on Azimuth: 177.840° (Grid North)
 Vertical Section Origin: 9 000 ft, 0 000 ft
 TVD Reference Datum: RKB
 TVD Reference Elevation: 3552 200 ft above MSL
 Seabed / Ground Elevation: 3525 700 ft above MSL
 Magnetic Declination: 7.084°
 Total Gravity Field Strength: 998.4287 mgn (P 80665 Based)
 Gravity Model: GARM
 Total Magnetic Field Strength: 46247.198 nT
 Magnetic Dip Angle: 60.038°
 Declination Date: April 19, 2016
 Magnetic Declination Mode: HDGM 2015
 North Reference: Grid North
 Grid Convergence Used: 0.2703°
 Total Corr Mag North-Grid North: 6.8046°
 Local Coord Referenced To: Structure Reference Point

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (ft/100ft)	Northing (NUS)	Easting (EUS)	Latitude (N/E/W)	Longitude (E/W)
Stk	0.00	0.00	0.00	0.00	-3552.20	0.00	0.00	0.00	N/A	445625.84	661978.18	N 32° 13' 28.81"	W 103° 48' 34.34"
Rustler	592.00	0.00	71.73	592.00	-2960.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 28.81"	W 103° 48' 34.34"
18" Casing	640.00	0.00	71.73	640.00	-2912.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 28.81"	W 103° 48' 34.34"
Salado	872.00	0.00	71.73	872.00	-2580.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 28.81"	W 103° 48' 34.34"
Castle	2632.00	0.00	71.73	2632.00	-700.20	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 28.81"	W 103° 48' 34.34"
Delaware	4310.00	0.00	71.73	4310.00	757.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 28.81"	W 103° 48' 34.34"
Ball Canyon	4354.00	0.00	71.73	4354.00	801.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 28.81"	W 103° 48' 34.34"
10 3/4" Casing	4358.00	0.00	71.73	4358.00	805.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 28.81"	W 103° 48' 34.34"
Cherry Canyon	5126.00	0.00	71.73	5126.00	1573.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 28.81"	W 103° 48' 34.34"
Brushy Canyon	6448.00	0.00	71.73	6448.00	2698.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 28.81"	W 103° 48' 34.34"
Bone Spring	8125.00	0.00	71.73	8125.00	4372.80	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 28.81"	W 103° 48' 34.34"
Backbuild 2"1100' DLS to 10" Inc	9360.50	0.00	71.73	9360.50	5626.30	0.00	0.00	0.00	0.00	445625.84	661978.18	N 32° 13' 28.81"	W 103° 48' 34.34"
Hold 10" Inc	9880.74	10.00	71.73	9878.20	6326.90	-12.18	13.66	41.37	2.00	445639.50	662019.55	N 32° 13' 28.74"	W 103° 48' 33.88"
Drop 2"1100' DLS to Vertical	10311.39	10.00	71.73	10302.30	6750.10	-33.05	37.11	12.41	0.00	445682.95	662090.88	N 32° 13' 28.97"	W 103° 48' 33.03"
Hold Vertical	10611.83	0.00	71.73	10600.00	7247.80	-45.21	50.77	152.78	2.00	445676.61	662131.05	N 32° 13' 27.10"	W 103° 48' 32.55"
7.5" Casing	10911.83	0.00	71.73	10900.00	7347.80	-45.21	50.77	152.78	0.00	445676.61	662131.05	N 32° 13' 27.10"	W 103° 48' 32.55"
Tie Into Pilot Hole - Whinstock	10958.00	0.00	71.73	10944.37	7392.17	-45.21	50.77	152.78	0.00	445676.61	662131.05	N 32° 13' 27.10"	W 103° 48' 32.55"
KOP - Build 10"1100' DLS to Land	11000.00	0.00	179.78	10968.37	7438.17	-45.21	50.77	152.78	0.00	445676.61	662131.05	N 32° 13' 27.10"	W 103° 48' 32.55"
	11055.67	0.00	179.78	11044.04	7491.84	-45.21	50.77	152.78	0.00	445676.61	662131.05	N 32° 13' 27.10"	W 103° 48' 32.55"
	11100.00	4.43	179.78	11089.33	7536.13	-43.50	49.06	152.79	10.00	445674.00	662131.08	N 32° 13' 27.08"	W 103° 48' 32.55"
	11200.00	14.43	179.78	11188.85	7634.65	-27.14	32.89	152.85	10.00	445658.53	662132.02	N 32° 13' 26.92"	W 103° 48' 32.55"
	11300.00	24.43	179.78	11281.04	7728.84	6.07	-0.54	152.98	10.00	445625.30	662132.15	N 32° 13' 26.59"	W 103° 48' 32.55"
	11400.00	34.43	179.78	11369.02	7815.82	55.13	-49.82	154.17	10.00	445578.23	662132.34	N 32° 13' 26.11"	W 103° 48' 32.55"
	11500.00	44.43	179.78	11445.18	7892.96	118.53	-113.05	154.41	10.00	445512.79	662132.58	N 32° 13' 25.49"	W 103° 48' 32.55"
	11600.00	54.43	179.78	11510.11	7957.91	184.36	-168.92	154.70	10.00	445436.03	662132.87	N 32° 13' 24.73"	W 103° 48' 32.55"
	11615.59	55.99	179.78	11518.00	7968.80	207.15	-201.72	154.75	10.00	445424.13	662132.82	N 32° 13' 24.60"	W 103° 48' 32.55"
	11700.00	64.43	179.78	11560.90	8008.70	260.31	-274.92	155.03	10.00	445350.90	662133.21	N 32° 13' 23.68"	W 103° 48' 32.55"
	11800.00	74.43	179.78	11595.98	8043.78	373.77	-388.42	155.40	10.00	445257.54	662133.57	N 32° 13' 22.95"	W 103° 48' 32.55"
	11900.00	84.43	179.78	11614.30	8082.10	471.80	-488.60	155.77	10.00	445190.27	662133.94	N 32° 13' 21.98"	W 103° 48' 32.56"
Landing Point @ 90" Inc	11959.87	90.00	179.78	11617.00	8084.80	527.45	-522.18	155.99	10.00	445103.89	662134.16	N 32° 13' 21.43"	W 103° 48' 32.56"
	12000.00	90.00	179.78	11617.00	8084.80	571.76	-566.51	156.16	0.00	445059.36	662134.33	N 32° 13' 20.89"	W 103° 48' 32.56"
	12100.00	90.00	179.78	11617.00	8084.80	617.71	-608.51	156.54	0.00	444950.37	662134.71	N 32° 13' 20.00"	W 103° 48' 32.56"
	12200.00	90.00	179.78	11617.00	8084.80	671.66	-658.51	156.93	0.00	444850.38	662135.10	N 32° 13' 19.01"	W 103° 48' 32.56"
	12300.00	90.00	179.78	11617.00	8084.80	717.61	-698.51	157.32	0.00	444750.38	662135.49	N 32° 13' 18.02"	W 103° 48' 32.56"
	12400.00	90.00	179.78	11617.00	8084.80	761.55	-738.51	157.70	0.00	444650.39	662135.87	N 32° 13' 17.03"	W 103° 48' 32.56"
	12500.00	90.00	179.78	11617.00	8084.80	801.50	-778.51	158.09	0.00	444550.40	662136.26	N 32° 13' 16.04"	W 103° 48' 32.56"
	12600.00	90.00	179.78	11617.00	8084.80	841.45	-818.51	158.47	0.00	444450.41	662136.64	N 32° 13' 15.05"	W 103° 48' 32.56"
	12700.00	90.00	179.78	11617.00	8084.80	881.40	-858.51	158.86	0.00	444350.41	662137.03	N 32° 13' 14.07"	W 103° 48' 32.57"
	12800.00	90.00	179.78	11617.00	8084.80	921.35	-898.51	159.24	0.00	444250.42	662137.41	N 32° 13' 13.08"	W 103° 48' 32.57"
	12900.00	90.00	179.78	11617.00	8084.80	961.30	-938.51	159.63	0.00	444150.43	662137.80	N 32° 13' 12.09"	W 103° 48' 32.57"
	13000.00	90.00	179.78	11617.00	8084.80	1001.25	-978.51	160.01	0.00	444050.43	662138.18	N 32° 13' 11.10"	W 103° 48' 32.57"
	13100.00	90.00	179.78	11617.00	8084.80	1041.19	-1018.50	160.40	0.00	443950.44	662138.57	N 32° 13' 10.11"	W 103° 48' 32.57"
	13200.00	90.00	179.78	11617.00	8084.80	1081.14	-1058.50	160.78	0.00	443850.45	662138.95	N 32° 13' 9.12"	W 103° 48' 32.57"
	13300.00	90.00	179.78	11617.00	8084.80	1121.09	-1098.50	161.17	0.00	443750.45	662139.34	N 32° 13' 8.13"	W 103° 48' 32.57"
	13400.00	90.00	179.78	11617.00	8084.80	1161.04	-1138.50	161.55	0.00	443650.46	662139.72	N 32° 13' 7.14"	W 103° 48' 32.57"
	13500.00	90.00	179.78	11617.00	8084.80	1200.99	-1178.50	161.94	0.00	443550.47	662140.11	N 32° 13' 6.15"	W 103° 48' 32.57"
	13600.00	90.00	179.78	11617.00	8084.80	1240.94	-1218.50	162.33	0.00	443450.48	662140.50	N 32° 13' 5.16"	W 103° 48' 32.58"
	13700.00	90.00	179.78	11617.00	8084.80	1280.89	-1258.50	162.71	0.00	443350.48	662140.88	N 32° 13' 4.17"	W 103° 48' 32.58"
	13800.00	90.00	179.78	11617.00	8084.80	1320.84	-1298.50	163.10	0.00	443250.49	662141.27	N 32° 13' 3.18"	W 103° 48' 32.58"
	13900.00	90.00	179.78	11617.00	8084.80	1360.79	-1338.50	163.48	0.00	443150.50	662141.65	N 32° 13' 2.19"	W 103° 48' 32.58"
	14000.00	90.00	179.78	11617.00	8084.80	1400.74	-1378.50	163.87	0.00	443050.50	662142.04	N 32° 13' 1.20"	W 103° 48' 32.58"
	14100.00	90.00	179.78	11617.00	8084.80	1440.69	-1418.50	164.25	0.00	442950.51	662142.42	N 32° 13' 0.21"	W 103° 48' 32.58"
	14200.00	90.00	179.78	11617.00	8084.80	1480.64	-1458.50	164.64	0.00	442850.52	662142.81	N 32° 12' 59.22"	W 103° 48' 32.58"
	14300.00	90.00	179.78	11617.00	8084.80	1520.59	-1498.50	165.02	0.00	442750.52	662143.19	N 32° 12' 58.23"	W 103° 48' 32.58"
	14400.00	90.00	179.78	11617.00	8084.80	1560.54	-1538.50	165.41	0.00	442650.53	662143.58	N 32° 12' 57.24"	W 103° 48' 32.59"
	14500.00	90.00	179.78	11617.00	8084.80	1600.49	-1578.50	165.79	0.00	442550.54	662143.96	N 32° 12' 56.25"	W 103° 48' 32.59"
	14600.00	90.00	179.78	11617.00	8084.80	1640.44	-1618.50	166.18	0.00	442450.55	662144.35	N 32° 12' 55.26"	W 103° 48' 32.59"
	14700.00	90.00	179.78	11617.00	8084.80	1680.39	-1658.50	166.56	0.00	442350.55	662144.73	N 32° 12' 54.27"	W 103° 48' 32.59"
	14800.00	90.00	179.78	11617.00	8084.80	1720.34	-1698.50	166.95	0.00	442250.56	662145.12	N 32° 12' 53.28"	W 103° 48' 32.59"

DP-6

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	TVDSS (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	14900.00	90.00	179.78	11617.00	8064.80	3470.27	-3468.49	167.34	0.00	442159.57	662143.51	N 32 12 52.30	W 103 48 32.59
	15000.00	90.00	179.78	11617.00	8064.80	3570.21	-3568.49	167.72	0.00	442059.57	662148.89	N 32 12 51.31	W 103 48 32.59
	15100.00	90.00	179.78	11617.00	8064.80	3670.16	-3668.49	168.11	0.00	441959.58	662146.28	N 32 12 50.32	W 103 48 32.59
	15200.00	90.00	179.78	11617.00	8064.80	3770.11	-3768.49	168.49	0.00	441859.59	662148.86	N 32 12 49.33	W 103 48 32.60
	15300.00	90.00	179.78	11617.00	8064.80	3870.06	-3868.49	168.88	0.00	441759.59	662147.05	N 32 12 48.34	W 103 48 32.60
	15400.00	90.00	179.78	11617.00	8064.80	3970.01	-3968.49	168.26	0.00	441659.60	662147.43	N 32 12 47.35	W 103 48 32.60
	15500.00	90.00	179.78	11617.00	8064.80	4069.96	-4068.49	168.65	0.00	441559.61	662147.82	N 32 12 46.36	W 103 48 32.60
	15600.00	90.00	179.78	11617.00	8064.80	4169.91	-4168.49	170.03	0.00	441459.62	662148.20	N 32 12 45.37	W 103 48 32.60
	15700.00	90.00	179.78	11617.00	8064.80	4269.85	-4268.49	170.42	0.00	441359.62	662148.59	N 32 12 44.38	W 103 48 32.60
	15800.00	90.00	179.78	11617.00	8064.80	4369.80	-4368.49	170.80	0.00	441259.63	662148.97	N 32 12 43.39	W 103 48 32.60
	15900.00	90.00	179.78	11617.00	8064.80	4469.75	-4468.49	171.19	0.00	441159.64	662149.39	N 32 12 42.40	W 103 48 32.60
	16000.00	90.00	179.78	11617.00	8064.80	4569.70	-4568.49	171.58	0.00	441059.64	662149.74	N 32 12 41.41	W 103 48 32.60
	16100.00	90.00	179.78	11617.00	8064.80	4669.65	-4668.49	171.98	0.00	440959.65	662150.13	N 32 12 40.42	W 103 48 32.61
	16200.00	90.00	179.78	11617.00	8064.80	4769.60	-4768.49	172.35	0.00	440859.66	662150.52	N 32 12 39.43	W 103 48 32.61
Plat Bottom Peri	16227.18	90.00	179.78	11617.00	8064.80	4796.76	-4793.06	172.43	0.00	440832.46	662150.62	N 32 12 39.18	W 103 48 32.61

Survey Type: Non-Del Plan

Survey Error Model: IECWSA Rev 0 *** 3-D 95.000% Confidence 2.7955 sigma
Survey Program:


Description	Part	MD From (ft)	MD To (ft)	EDU Freq (ft)	Hole Size Casing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey
	1	0.000	26.500	1/100.000	30.000	30.000	NAL_MWD_HDGM-Depth Only	Pilot - Original Hole / Dry Patton MDP1 18 Fed 6H Pilot Rev0 MMC 20Apr16
	1	26.500	10958.000	1/100.000	30.000	30.000	NAL_MWD_HDGM	Pilot - Original Hole / Dry Patton MDP1 18 Fed 6H Pilot Rev0 MMC
	1	10958.000	16227.180	1/100.000	30.000	30.000	NAL_MWD_HDGM	ST01 - Dry Patton MDP1 18 Fed 6H ST01 Rev0 MMC 20Apr16

10M BOP Stack

Mud Cross Valves:

5. 10M Check Valve
6. Outside 10M Kill Line Valve
7. Inside 10M Kill Line Valve
8. Outside 10M Kill Line Valve
9. 10M HCR Valve

*Minimum ID = 2-1/16" on Kill Line side and 3" minimum ID on choke line side




5M BOP Stack


Mud Cross Valves:

5. 5M Check Valve
6. Outside 5M Kill Line Valve
7. Inside 5M Kill Line Valve
8. Outside 5M Kill Line Valve
9. 5M HCR Valve

*Minimum ID = 2-1/16" on Kill Line side and 3" minimum ID on choke line side



BOP-3




Wofbone - Hybrid Design



Rev	Jeanette	Dep	9-19-14	Working Drawing	#	1175306
-----	----------	-----	---------	-----------------	---	---------

10M Choke Panel



1. Choke Manifold Valve
2. Choke Manifold Valve
3. Choke Manifold Valve
4. Choke Manifold Valve
5. Choke Manifold Valve
6. Choke Manifold Valve
7. Choke Manifold Valve
8. PC - Power Choke
9. Choke Manifold Valve
10. Choke Manifold Valve
11. Choke Manifold Valve
12. LMC - Lower Manual Choke
13. UMC - Upper manual choke
15. Choke Manifold Valve
16. Choke Manifold Valve
17. Choke Manifold Valve
18. Choke Manifold Valve
21. Vertical Choke Manifold Valve

*All Valves 3" minimum




5M Choke Panel

Green

Indicates Open

Red Indicates

Closed



1. 4" Choke Manifold Valve
2. 4" Choke Manifold Valve
3. 3" Choke Manifold Valve
4. 3" Choke Manifold Valve
5. 3" Choke Manifold Valve
6. 3" Choke Manifold Valve
7. 3" Choke Manifold Valve
8. PC - Power Choke
9. 3" Choke Manifold Valve
10. 3" Choke Manifold Valve
11. Choke Manifold Valve
12. MC - Manual Choke

18. Choke Manifold Valve


21. Vertical Choke Manifold Valve

*All Valves 3" minimum


CA-2




10M REMOTE KILL LINE SCHEMATIC



Choke Manifold – Gas Separator (Top View)




Choke Manifold – Gas Separator (Side View)




CM-5

Gas Separator Routing Flex III Rigs




Oxy Single Centrifuge Closed Loop System – New Mexico Flex III

May 28, 2013



CL-2

Oxy



Well Head

Oxy Single Centrifuge
Closed Loop System – New
Mexico Flex III
May 28, 2013



Fluid Technology

Quality Document

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE				CERT. N°: 746	
PURCHASER: Phoenix Beattie Co.				P.O. N°: 002491	
CONTITECH ORDER N°: 412638		HOSE TYPE: 3" ID Choke and Kill Hose			
HOSE SERIAL N°: 52777		NOMINAL / ACTUAL LENGTH: 10,67 m			
W.P. 68,96 MPa 10000 psi		T.P. 103,4 MPa 15000 psi		Duration: 60 ~ min.	
Pressure test with water at ambient temperature <p style="text-align: center;">See attachment. (1 page)</p>					
↑ 10 mm = 10 Min. → 10 mm = 25 MPa					
COUPLINGS					
Type		Serial N°		Quality	
3" coupling with 4 1/16" Flange end		917 913		AISI 4130 AISI 4130	
				Heat N° T7998A 26984	
INFOCHIP INSTALLED				API Spec 16 C Temperature rate: "B"	
All metal parts are flawless					
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.					
Date:		Inspector		Quality Control	
04. April. 2008				ContiTech Rubber Industrial Kit Quality Control Dept. (1)	

Coflex Hose Certification

Page: 1/1

15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100														
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100

ContiTech Rubber
Industrial Kft.
Quality Control Dept.
(2)

Coflex Hose Certification

Form No 100/12

**Phoenix Beattie Corp**

11535 Brittmoore Park Drive
Houston, TX 77041
Tel: (832) 327-0141
Fax: (832) 327-0148
E-mail: sales@phoenixbeattie.com
www.phoenixbeattie.com

Delivery Note

Customer Order Number	370-369-001	Delivery Note Number	003078	Page	1
Customer / Invoice Address HELMERICH & PAYNE INT'L DRILLING CO 1437 SOUTH BOULDER TULSA, OK 74119		Delivery / Address HELMERICH & PAYNE IDC ATTN: JOE STEPHENSON - RIG 370 13609 INDUSTRIAL ROAD HOUSTON, TX 77015			

Customer Acc No	Phoenix Beattie Contract Manager	Phoenix Beattie Reference	Date
H01	JJL	006330	05/23/2008

Item No	Beattie Part Number / Description	Qty Ordered	Qty Sent	Qty To Follow
1	HP10CK3A-35-4F1 3" 10K 16C C&K HOSE x 35ft OAL CW 4.1/16" API SPEC FLANGE E/ End 1: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange End 2: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange c/w BX155 Standard ring groove at each end Suitable for H2S Service Working pressure: 10,000psi Test pressure: 15,000psi Standard: API 16C Full specification Armor Guarding: Included Fire Rating: Not Included Temperature rating: -20 Deg C to +100 Deg C	1	1	0
2	SECK3-HPF3 LIFTING & SAFETY EQUIPMENT TO SUIT HP10CK3-35-F1 2 x 160mm ID Safety Clamps 2 x 244mm ID Lifting Collars & element C's 2 x 7ft Stainless Steel wire rope 3/4" OD 4 x 7.75t Shackles	1	1	0
3	SC725-200CS SAFETY CLAMP 200MM 7.25T C/S GALVANISED	1	1	0

Continued...

All goods remain the property of Phoenix Beattie until paid for in full. Any damage or shortage on this delivery must be advised within 5 days.
Returns may be subject to a handling charge.



Phoenix Beattie Corp

11535 Brittonmore Park Drive
Houston, TX 77041
Tel: (832) 327-0141
Fax: (832) 327-0148
E-mail: sales@phoenixbeattie.com
www.phoenixbeattie.com

Delivery Note

Customer Order Number	370-369-001	Delivery Note Number	003078	Page	2
Customer / Invoice Address HELMERICH & PAYNE INT'L DRILLING CO 1437 SOUTH BOULDER TULSA, OK 74119		Delivery / Address HELMERICH & PAYNE IDC ATTN: JOE STEPHENSON - RIG 370 13609 INDUSTRIAL ROAD HOUSTON, TX 77015			

Customer Acc No	Phoenix Beattie Contract Manager	Phoenix Beattie Reference	Date
H01	JJL	006330	05/23/2008

Item No	Beattie Part Number / Description	Qty Ordered	Qty Sent	Qty To Follow
4	SC725-132CS SAFETY CLAMP 132MM 7.25T C/S GALVANIZED C/W BOLTS	1	1	0
5	DOCERT-HYDRO HYDROSTATIC PRESSURE TEST CERTIFICATE	1	1	0
6	DOCERT-LOAD LOAD TEST CERTIFICATES	1	1	0
7	DOFREIGHT INBOUND / OUTBOUND FREIGHT PRE-PAY & ADD TO FINAL INVOICE NOTE: MATERIAL MUST BE ACCOMPANIED BY PAPERWORK INCLUDING THE PURCHASE ORDER, RIG NUMBER TO ENSURE PROPER PAYMENT	1	1	0

Phoenix Beattie Inspection Signature :

Received In Good Condition : Signature

Print Name

Date

All goods remain the property of Phoenix Beattie until paid for in full. Any damage or shortage on this delivery must be advised within 5 days.
Returns may be subject to a handling charge.

PHOENIX Beattie

Material Identification Certificate

[illegible]

We hereby certify that these goods have been inspected by our Quality Management System, and to the best of our knowledge are found to conform to relevant industry standards within the requirements of the purchase order as issued to Phoenix Beattie Corporation.

05/23/09.


CERTIFICATE OF CONFORMITY

Supplier : CONTITECH RUBBER INDUSTRIAL KFT.
Equipment : 6 pcs. Choke and Kill Hose with installed couplings
Type : 3" x 10,67 m WP: 10000 psi
Supplier File Number : 412638
Date of Shipment : April. 2008
Customer : Phoenix Beattie Co.
Customer P.o. : 002491
Referenced Standards
/ Codes / Specifications : API Spec 16 C
Serial No.: 52754,52755,52776,52777,52778,52782

STATEMENT OF CONFORMITY


We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.

COUNTRY OF ORIGIN HUNGARY/EU

Signed : 
Position: Q.C. Manager

ContiTech Rubber
Industrial Kft.
Quality Control Dept.
(3)

Date: 04. April. 2008



Permian Drilling Hydrogen Sulfide Drilling Operations Plan New Mexico

Scope

This contingency plan establishes guidelines for the public, all company employees, and contract employees who's work activities may involve exposure to hydrogen sulfide (H₂S) gas.

While drilling this well, it is possible to encounter H₂S bearing formations. At all times, the first barrier to control H₂S emissions will be the drilling fluid, which will have a density high enough to control influx.

Objective

1. Provide an immediate and predetermined response plan to any condition when H₂S is detected. All H₂S detections in excess of 10 parts per million (ppm) concentration are considered an Emergency.
2. Prevent any and all accidents, and prevent the uncontrolled release of hydrogen sulfide into the atmosphere.
3. Provide proper evacuation procedures to cope with emergencies.
4. Provide immediate and adequate medical attention should an injury occur.

Discussion

Implementation:	This plan with all details is to be fully implemented before drilling to <u>commence</u> .
Emergency response Procedure:	This section outlines the conditions and denotes steps to be taken in the event of an emergency.
Emergency equipment Procedure:	This section outlines the safety and emergency equipment that will be required for the drilling of this well.
Training provisions:	This section outlines the training provisions that must be adhered to prior to drilling.
Drilling emergency call lists:	Included are the telephone numbers of all persons to be contacted should an emergency exist.
Briefing:	This section deals with the briefing of all people involved in the drilling operation.
Public safety:	Public safety personnel will be made aware of any potential evacuation and any additional support needed.
Check lists:	Status check lists and procedural check lists have been included to insure adherence to the plan.
General information:	A general information section has been included to supply support information.

Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on the well:

1. The hazards and characteristics of H₂S.
2. Proper use and maintenance of personal protective equipment and life support systems.
3. H₂S detection.
4. Proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures and prevailing winds.
5. Proper techniques for first aid and rescue procedures.
6. Physical effects of hydrogen sulfide on the human body.
7. Toxicity of hydrogen sulfide and sulfur dioxide.
8. Use of SCBA and supplied air equipment.
9. First aid and artificial respiration.
10. Emergency rescue.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H₂S on metal components. If high tensile strength tubular is to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling a well, blowout prevention and well control procedures.
3. The contents and requirements of the H₂S Drilling Operations Plan.

H₂S training refresher must have been taken within one year prior to drilling the well. Specifics on the well to be drilled will be discussed during the pre-spud meeting. H₂S and well control (choke) drills will be performed while drilling the well, at least on a weekly basis. This plan shall be available in the well site. All personnel will be required to carry the documentation proving that the H₂S training has been taken.

Service company and visiting personnel

- A. Each service company that will be on this well will be notified if the zone contains H₂S.
- B. Each service company must provide for the training and equipment of their employees before they arrive at the well site.
- C. Each service company will be expected to attend a well site briefing

Emergency Equipment Requirements

1. Well control equipment

The well shall have hydraulic BOP equipment for the anticipated pressures. Equipment is to be tested on installation and follow Oxy Well Control standard, as well as BLM Onshore Order #2.

Special control equipment:

- A. Hydraulic BOP equipment with remote control on ground. Remotely operated choke.
- B. Rotating head
- C. Gas buster equipment shall be installed before drilling out of surface pipe.

2. Protective equipment for personnel

- A. Four (4) 30-minute positive pressure air packs (2 at each briefing area) on location.
- B. Adequate fire extinguishers shall be located at strategic locations.
- C. Radio / cell telephone communication will be available at the rig.
 - Rig floor and trailers.
 - Vehicle.

3. Hydrogen sulfide sensors and alarms

- A. H₂S sensor with alarms will be located on the rig floor, at the bell nipple, and at the flow line. These monitors will be set to alarm at 10 ppm with strobe light, and audible alarm.
- B. Hand operated detectors with tubes.
- C. H₂S monitor tester (to be provided by contract Safety Company.)
- D. There shall be one combustible gas detector on location at all times.

4. Visual Warning Systems

- A. One sign located at each location entrance with the following language:

**Caution – potential poison gas
Hydrogen sulfide
No admittance without authorization**

Wind sock – wind streamers:

- A. One 36" (in length) wind sock located at protection center, at height visible from rig floor.
- B. One 36" (in length) wind sock located at height visible from pit areas.

Condition flags

- A. One each condition flag to be displayed to denote conditions.

green – normal conditions
yellow – potential danger
red – danger, H₂S present

- B. Condition flag shall be posted at each location sign entrance.

5. Mud Program

The mud program is designed to minimize the risk of having H₂S and other formation fluids at surface. Proper mud weight and safe drilling practices will be applied. H₂S scavengers will be used to minimize the hazards while drilling. Below is a summary of the drilling program.

Mud inspection devices:

Garrett gas train or hatch tester for inspection of sulfide concentration in mud system.

6. Metallurgy

- A. Drill string, casing, tubing, wellhead, blowout preventers, drilling spools or adapters, kill lines, choke manifold, lines and valves shall be suitable for the H₂S service.
- B. All the elastomers, packing, seals and ring gaskets shall be suitable for H₂S service.

7. Well Testing

No drill stem test will be performed on this well.

8. Evacuation plan

Evacuation routes should be established prior to well spud for each well and discussed with all rig personnel.

9. Designated area

- A. Parking and visitor area: all vehicles are to be parked at a predetermined safe distance from the wellhead.
- B. There will be a designated smoking area.
- C. Two briefing areas on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds perpendicularly, or at a 45-degree angle if wind direction tends to shift in the area.

Emergency procedures

- A. In the event of any evidence of H₂S level above 10 ppm, take the following steps:
 - 1. The Driller will pick up off bottom, shut down the pumps, slow down the pipe rotation.
 - 2. Secure and don escape breathing equipment, report to the upwind designated safe briefing / muster area.
 - 3. All personnel on location will be accounted for and emergency search should begin for any missing, the Buddy System will be implemented.
 - 4. Order non-essential personnel to leave the well site, order all essential personnel out of the danger zone and upwind to the nearest designated safe briefing / muster area.
 - 5. Entrance to the location will be secured to a higher level than our usual "Meet and Greet" requirement, and the proper condition flag will be displayed at the entrance to the location.
 - 6. Take steps to determine if the H₂S level can be corrected or suppressed and, if so, proceed as required.
- B. If uncontrollable conditions occur:
 - 1. Take steps to protect and/or remove any public in the down-wind area from the rig – partial evacuation and isolation. Notify necessary public safety personnel and appropriate regulatory entities (i.e. BLM) of the situation.

2. Remove all personnel to the nearest upwind designated safe briefing / muster area or off location.
3. Notify public safety personnel of safe briefing / muster area.
4. An assigned crew member will blockade the entrance to the location. No unauthorized personnel will be allowed entry to the location.
5. Proceed with best plan (at the time) to regain control of the well. Maintain tight security and safety procedures.

C. Responsibility:

1. Designated personnel.

- a. Shall be responsible for the total implementation of this plan.
- b. Shall be in complete command during any emergency.
- c. Shall designate a back-up.

All personnel:

1. On alarm, don escape unit and report to the nearest upwind designated safe briefing / muster area upw
2. Check status of personnel (buddy system).
3. Secure breathing equipment.
4. Await orders from supervisor.

Drill site manager:

1. Don escape unit if necessary and report to nearest upwind designated safe briefing / muster area.
2. Coordinate preparations of individuals to return to point of release with tool pusher and driller (using the buddy system).
3. Determine H2S concentrations.
4. Assess situation and take control measures.

Tool pusher:

1. Don escape unit Report to up nearest upwind designated safe briefing / muster area.
2. Coordinate preparation of individuals to return to point of release with tool pusher drill site manager (using the buddy system).
3. Determine H2S concentration.
4. Assess situation and take control measures.

Driller:

1. Don escape unit, shut down pumps, continue

rotating DP.

2. Check monitor for point of release.
3. Report to nearest upwind designated safe briefing / muster area.
4. Check status of personnel (in an attempt to rescue, use the buddy system).
5. Assigns least essential person to notify Drill Site Manager and tool pusher by quickest means in case of their absence.
6. Assumes the responsibilities of the Drill Site Manager and tool pusher until they arrive should they be absent.

Derrick man
Floor man #1
Floor man #2

1. Will remain in briefing / muster area until instructed by supervisor.

Mud engineer:

1. Report to nearest upwind designated safe briefing / muster area.
2. When instructed, begin check of mud for pH and H₂S level. (Garett gas train.)

Safety personnel:

1. Mask up and check status of all personnel and secure operations as instructed by drill site manager.

Taking a kick

When taking a kick during an H₂S emergency, all personnel will follow standard Well control procedures after reporting to briefing area and masking up.

Open-hole logging

All unnecessary personnel off floor. Drill Site Manager and safety personnel should monitor condition, advise status and determine need for use of air equipment.

Running casing or plugging

Following the same "tripping" procedure as above. Drill Site Manager and safety personnel should determine if all personnel have access to protective equipment.

Ignition procedures

The decision to ignite the well is the responsibility of the operator (Oxy Drilling Management). The decision should be made only as a last resort and in a situation where it is clear that:

1. Human life and property are endangered.
2. There is no hope controlling the blowout under the prevailing conditions at the well.

Instructions for igniting the well

1. Two people are required for the actual igniting operation. They must wear self-contained breathing units and have a safety rope attached. One man (tool pusher or safety engineer) will check the atmosphere for explosive gases with the gas monitor. The other man is responsible for igniting the well.
2. Primary method to ignite: 25 mm flare gun with range of approximately 500 feet.
3. Ignite upwind and do not approach any closer than is warranted.
4. Select the ignition site best for protection, and which offers an easy escape route.
5. Before firing, check for presence of combustible gas.
6. After lighting, continue emergency action and procedure as before.
7. All unassigned personnel will remain in briefing area until instructed by supervisor or directed by the Drill Site Manager.

Remember: After well is ignited, burning hydrogen sulfide will convert to sulfur dioxide, which is also highly toxic. **Do not assume the area is safe after the well is ignited.**

Status check list

Note: All items on this list must be completed before drilling to production casing point.

1. H₂S sign at location entrance.
2. Two (2) wind socks located as required.
3. Four (4) 30-minute positive pressure air packs (2 at each Briefing area) on location for all rig personnel and mud loggers.
4. Air packs inspected and ready for use.
5. Cascade system and hose line hook-up as needed.
6. Cascade system for refilling air bottles as needed.
7. Condition flag on location and ready for use.
8. H₂S detection system hooked up and tested.
9. H₂S alarm system hooked up and tested.
10. Hand operated H₂S detector with tubes on location.
11. 1 – 100' length of nylon rope on location.
12. All rig crew and supervisors trained as required.
13. All outside service contractors advised of potential H₂S hazard on well.
14. No smoking sign posted and a designated smoking area identified.
15. Calibration of all H₂S equipment shall be noted on the IADC report.

Checked by: _____ Date: _____

Procedural check list during H₂S events**Perform each tour:**

1. Check fire extinguishers to see that they have the proper charge.
2. Check breathing equipment to ensure that it is in proper working order.
3. Make sure all the H₂S detection system is operative.

Perform each week:

1. Check each piece of breathing equipment to make sure that demand or forced air regulator is working. This requires that the bottle be opened and the mask assembly be put on tight enough so that when you inhale, you receive air or feel air flow.
2. BOP skills (well control drills).
3. Check supply pressure on BOP accumulator stand by source.
4. Check breathing equipment mask assembly to see that straps are loosened and turned back, ready to put on.
5. Check pressure on breathing equipment air bottles to make sure they are charged to full volume. (Air quality checked for proper air grade "D" before bringing to location)
6. Confirm pressure on all supply air bottles.
7. Perform breathing equipment drills with on-site personnel.
8. Check the following supplies for availability.
 - A. Emergency telephone list.
 - B. Hand operated H₂S detectors and tubes.

General evacuation plan

1. When the company approved supervisor (Drill Site Manager, consultant, rig pusher, or driller) determines the H₂S gas cannot be limited to the well location and the public will be involved, he will activate the evacuation plan.
2. Drill Site Manager or designee will notify local government agency that a hazardous condition exists and evacuation needs to be implemented.
3. Company or contractor safety personnel that have been trained in the use of H₂S detection equipment and self-contained breathing equipment will monitor H₂S concentrations, wind directions, and area of exposure. They will delineate the outer perimeter of the hazardous gas area. Extension to the evacuation area will be determined from information gathered.
4. Law enforcement personnel (state police, police dept., fire dept., and sheriff's dept.) Will be called to aid in setting up and maintaining road blocks. Also, they will aid in evacuation of the public if necessary.
5. After the discharge of gas has been controlled, company safety personnel will determine when the area is safe for re-entry.

Important: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

Emergency actions**Well blowout – if emergency**

1. Evacuate all personnel to “Safe Briefing / Muster Areas” or off location if needed.
2. If sour gas – evacuate rig personnel.
3. If sour gas – evacuate public within 3000 ft radius of exposure.
4. Don SCBA and shut well in if possible using the buddy system.
5. Notify Drilling Superintendent and call 911 for emergency help (fire dept and ambulance) if needed.
6. Implement the Blowout Contingency Plan, and Drilling Emergency Action Plan.
6. Give first aid as needed.

Person down location/facility

1. If immediately possible, contact 911. Give location and wait for confirmation.
2. Don SCBA and perform rescue operation using buddy system.

Toxic effects of hydrogen sulfide

Hydrogen sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 ppm, which is .001% by volume. Hydrogen sulfide is heavier than air (specific gravity – 1.192) and colorless. It forms an explosive mixture with air between 4.3 and 46.0 percent by volume. Hydrogen sulfide is almost as toxic as hydrogen cyanide and is between five and six times more toxic than carbon monoxide. Toxicity data for hydrogen sulfide and various other gases are compared in table i. Physical effects at various hydrogen sulfide exposure levels are shown in table ii.

Table i
Toxicity of various gases

Common name	Chemical formula	Specific gravity (sc=1)	Threshold limit (1)	Hazardous limit (2)	Lethal concentration (3)
Hydrogen Cyanide	Hcn	0.94	10 ppm	150 ppm/hr	300 ppm
Hydrogen Sulfide	H ₂ S	1.18	10 ppm	250 ppm/hr	600 ppm
Sulfur Dioxide	So ₂	2.21	5 ppm	-	1000 ppm
Chlorine	Cl ₂	2.45	1 ppm	4 ppm/hr	1000 ppm
Carbon Monoxide	Co	0.97	50 ppm	400 ppm/hr	1000 ppm
Carbon Dioxide	Co ₂	1.52	5000 ppm	5%	10%
Methane	Ch ₄	0.55	90,000 ppm	Combustible above 5% in air	

- 1) threshold limit – concentration at which it is believed that all workers may be repeatedly exposed day after day without adverse effects.
- 2) hazardous limit – concentration that will cause death with short-term exposure.
- 3) lethal concentration – concentration that will cause death with short-term exposure.

Toxic effects of hydrogen sulfide

Table ii
Physical effects of hydrogen sulfide

<u>Percent (%)</u>	<u>Ppm</u>	<u>Concentration</u> Grains 100 std. Ft3*	<u>Physical effects</u>
0.001	<10	00.65	Obvious and unpleasant odor.

0.002	10	01.30	Safe for 8 hours of exposure.
0.010	100	06.48	Kill smell in 3 - 15 minutes. May sting eyes and throat.
0.020	200	12.96	Kills smell shortly; stings eyes and throat.
0.050	500	32.96	Dizziness; breathing ceases in a few minutes; needs prompt artificial respiration.
0.070	700	45.36	Unconscious quickly; death will result if not rescued promptly.
0.100	1000	64.30	Unconscious at once; followed by death within minutes.

*at 15.00 psia and 60°f.

Use of self-contained breathing equipment (SCBA)

1. Written procedures shall be prepared covering safe use of SCBA's in dangerous atmosphere, which might be encountered in normal operations or in emergencies. Personnel shall be familiar with these procedures and the available SCBA.
2. SCBA's shall be inspected frequently at random to insure that they are properly used, cleaned, and maintained.
3. Anyone who may use the SCBA's shall be trained in how to insure proper face-piece to face seal. They shall wear SCBA's in normal air and then wear them in a test atmosphere. (note: such items as facial hair {beard or sideburns} and eyeglasses will not allow proper seal.) Anyone that may be reasonably expected to wear SCBA's should have these items removed before entering a toxic atmosphere. A special mask must be obtained for anyone who must wear eyeglasses or contact lenses.
4. Maintenance and care of SCBA's:
 - a. A program for maintenance and care of SCBA's shall include the following:
 1. Inspection for defects, including leak checks.
 2. Cleaning and disinfecting.
 3. Repair.
 4. Storage.
 - b. Inspection, self-contained breathing apparatus for emergency use shall be inspected monthly.
 1. Fully charged cylinders.
 2. Regulator and warning device operation.
 3. Condition of face piece and connections.
 4. Rubber parts shall be maintained to keep them pliable and prevent deterioration.
 - c. Routinely used SCBA's shall be collected, cleaned and disinfected as frequently as necessary to insure proper protection is provided.
5. Persons assigned tasks that requires use of self-contained breathing equipment shall be certified physically fit (medically cleared) for breathing equipment usage at least annually.
6. SCBA's should be worn when:
 - A. Any employee works near the top or on top of any tank unless test reveals less than 10 ppm of H₂S.

- B. When breaking out any line where H₂S can reasonably be expected.
- C. When sampling air in areas to determine if toxic concentrations of H₂S exists.
- D. When working in areas where over 10 ppm H₂S has been detected.
- E. At any time there is a doubt as to the H₂S level in the area to be entered.

Rescue
First aid for H₂S poisoning

Do not panic!


Remain calm – think!

1. Don SCBA breathing equipment.
2. Remove victim(s) utilizing buddy system to fresh air as quickly as possible. (go up-wind from source or at right angle to the wind. Not down wind.)
3. Briefly apply chest pressure – arm lift method of artificial respiration to clean the victim's lungs and to avoid inhaling any toxic gas directly from the victim's lungs.
4. Provide for prompt transportation to the hospital, and continue giving artificial respiration if needed.
5. Hospital(s) or medical facilities need to be informed, before-hand, of the possibility of H₂S gas poisoning – no matter how remote the possibility is.
6. Notify emergency room personnel that the victim(s) has been exposed to H₂S gas.

Besides basic first aid, everyone on location should have a good working knowledge of artificial respiration.


Revised CM 6/27/2012

H2S




Permian Drilling Hydrogen Sulfide Drilling Operations Plan Patton MDP1 18 Federal 6H

Open drill site. No homes or buildings are near the proposed location.



1. Escape

Personnel shall escape upwind of wellbore in the event of an emergency gas release. Escape can take place through the lease road on the Southeast side of the location. Personnel need to move to a safe distance and block the entrance to location. If the primary route is not an option due to the wind direction, then a secondary egress route should be taken.



SEC. 18 TWP. 24-S RGE 31-E

SCALE. 2 MILES

SURVEY N.M.P.M.

COUNTY EDDY


DESCRIPTION 150' ENL & 505' FEL

ELEVATION 3525.7'

OPERATOR OXY USA INC.

LEASE PATTON MDP1 18 FEDERAL #6H

Asel Surveying

P.O. BOX 393 - 310 N. TAYLOR
HOBBS, NEW MEXICO - 575 393 9146

DIRECTIONS BEGINNING AT THE INTERSECTION OF STATE HWY. #12E AND COUNTY ROAD #78Z (WYN WELLS ROAD). GO SOUTH ON COUNTY ROAD #78Z FOR 5.2 MILES. TURN LEFT ON CALICHE ROAD AND GO EAST FOR 0.1 MILES. CONTINUE SOUTHEAST ON PROPOSED ROAD FOR 532.6 FEET TO LOCATION.

- 3 -

OPERATOR NAME / NUMBER: OXY USA INC.

16696

LEASE NAME/NUMBER: Patton MDP1 18 Federal #6H

STATE: NM

COUNTY: Eddy

POOL NAME/NUMBER: Wildcat Wolfcamp

PROJECTED TD: 16227'M / 11617'V OBJECTIVE: Wolfcamp A

PROJECTED PILOT HOLE TD: 13812'M / 13800'V

SURFACE LOCATION: 150 FNL 505 FEL NENE (A) Sec 18 T24S R31E-NMNM089819
SL: LAT: 32.2240572N LONG:103.8095396W X:661978.18 Y:445625.84 NAD: 27

TOP PERFORATION: 340 FNL 351 FEL NENE (A) Sec 18 T24S R31E
TP: LAT: 32.2235350N LONG:103.8090423W X:662132.87 Y:445436.62 NAD: 27

BOTTOM PERFORATION: 340 FSL 354 FEL SESE (P) Sec 18 T24S R31E
BP: LAT: 32.2108785N LONG:103.8090576W X:662150.62 Y:440832.48 NAD: 27

BOTTOM HOLE LOCATION: 230 FSL 354 FEL SESE (P) Sec 18 T24S R31E
BHL: LAT: 32.2105761N LONG:103.8090579W X:662151.05 Y:440722.48 NAD: 27

APPROX GR ELEV: 3525.7'

EST KB ELEV: 3550.7' (25' KB-GL)

Surface Use Plan of Operations

Operator Name/Number: OXY USA Inc. – 16696
Lease Name/Number: Patton MDP1 18 Federal #6H
Pool Name/Number: Wildcat Wolfcamp
Surface Location: 150 FNL 505 FEL NESE (A) Sec 18 T24S R31E NMNM089819
Bottom Hole Location: 230 FSL 354 FEL SESE (P) Sec 18 T24S R31E

1. Existing Roads

- a. A copy of the USGS "Big Sinks, NM" quadrangle map is attached showing the proposed location. The well location is spotted on the map, which shows the existing road system.
- b. The well was staked by Terry J. Asel, Certificate No. 15079 on 10/15/15, certified 3/29/16.
- c. Directions to Location: From the intersection of USH 128 and CR 787 (Twin Wells Road), go south on CR 787 for 5.2 miles. Turn left on caliche road and go east for 0.1 miles, continue southeast on proposed road for 532.6 feet to location.

2. New or Reconstructed Access Roads:

- a. A new access road will be built. The access road will begin at an existing lease road and will go southeast approximately 532.6' through pasture to the northeast corner of pad.
- b. The maximum width of the road will be 15'. It will be crowned and made up of 6" of rolled and compacted caliche. Water will be deflected, as necessary, to avoid accumulation and prevent surface erosion.
- c. Surface material will be native caliche. This material will be obtained from a BLM approved pit nearest in proximity to the location. The average grade will be approximately 1%.
- d. No cattle guards, grates or fence cuts will be required. No turnouts are planned.
- e. Blade, water and repair existing caliche roads as needed.
- f. Water Bars will be incorporated every 200' during the construction of the road, see attached.

3. Location of Existing Wells:

Existing wells within a one mile radius of the proposed well are shown on attached plat.

4. Location of Existing and/or Proposed Facilities:

- a. In the event the well is found productive, the Gila 12 Federal #2 central tank battery would be utilized and the necessary production equipment will be installed at the well site. See proposed Production Facilities Layout diagram.
- b. All flow lines will adhere to API standards. They will consist of 2 – 4" composite flowlines operating < 75% MAWP, buried and 2 – 4" steel gas lift supply line operating ~1500 psig, buried, lines to follow surveyed route. Survey for a pipeline 30.0' wide and 7670.6' or 1.453 miles in length crossing Section 12, T24S R30E and Sections 7 & 18, T24S R31E, NMPM, Eddy County, NM, and being 15' left and 15' right of the center line survey, see attached.
- c. Electric line will follow a route approved by the BLM. Survey for an electric line 30' wide and 2537.6' or 0.481 miles in length crossing Sections 7 & 18, T24S R31E, NMPM, Eddy County, NM, and being 15' left and 15' right of the center line survey, see attached.

5. Location and types of Water Supply

This well will be drilled using a combination of water mud systems. It will be obtained from commercial water stations in the area and will be hauled to location by transport truck using existing and proposed roads.

6. Construction Materials:

Primary

All caliche utilized for the drilling pad and proposed access road will be obtained from an existing BLM/State/Fee approved pit or from prevailing deposits found on the location. Will use BLM recommended extra caliche from other locations close by for roads, if available.

Secondary

The secondary way of obtaining caliche to build locations and roads will be by "turning over" the location. This means, caliche will be obtained from the actual well site. A caliche permit will be obtained from BLM prior to pushing up any caliche. 2400 cubic yards is max amount of caliche needed for pad and roads. Amount will vary for each pad. The procedure below has been approved by BLM personnel:

- The top 6" of topsoil is pushed off and stockpiled along the side of the location.
- An approximate 120' X 120' area is used within the proposed well site to remove caliche.
- Subsoil is removed and piled alongside the 120' X 120' within the pad site.
- When caliche is found, material will be stockpiled within the pad site to build the location and road.
- Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
- Once the well is drilled the stockpiled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced. Neither caliche nor subsoil will be stockpiled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in the attached plat.

7. Methods of Handling Waste Material:

- A closed loop system will be utilized consisting of above ground steel tanks and haul-off bins. Disposal of liquids, drilling fluids and cuttings will be disposed of at an approved facility. Solids-CRI, Liquids-Laguna
- All trash, junk and other waste material will be contained in trash cages or bins to prevent scattering. When the job is completed, all contents will be removed and disposed of in an approved sanitary landfill.
- The supplier, including broken sacks, will pickup slats remaining after completion of well.
- A Porto-john will be provided for the rig crews. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete.
- Disposal of fluids to be transported will be by the following companies. TFH Ltd, Laguna SWD Facility

8. Ancillary Facilities: None needed.

9. Well Site Layout:

The proposed well site layout with dimensions of the pad layout and equipment location.

V-Door – West

CL Tanks – South

Pad – 330' X 440' – 2 well pad

10. Plans for Surface Reclamation:

- After concluding the drilling and/or completion operations, if the well is found non-commercial, the caliche will be removed from the pad and transported to the original caliche pit or used for other drilling locations. The road will be reclaimed as directed by the BLM. The original topsoil will again be returned to the pad and contoured, as close as

possible, to the original topography, and the area will be seeded with an approved BLM mixture to re-establish vegetation.

- b. If the well is deemed commercially productive, caliche from the areas of the pad site not required for operations will be reclaimed. The original topsoil will be returned to the area of the drill pad not necessary to operate the well. These unused areas of the drill pad will be contoured, as close as possible, to match the original topography, and the area will be seeded with an approved BLM mixture to re-establish vegetation.

11. Surface Ownership:

The surface is owned by the U.S. Government and is administered by the BLM. The surface is multiple use with the primary uses of the region for the grazing of livestock and the production of oil and gas. The surface is leased to: Richardson Cattle Co./J&R Engineering, P.O. Box 487, Carlsbad, NM 88221. They will be notified of our intention to drill prior to any activity.

12. Other Information:

- a. The vegetation cover is generally sparse consisting of mesquite, yucca, shinnery oak, sandsage and perennial native range grass. The topsoil is sandy in nature. Wildlife in the area is also sparse consisting of deer, coyotes, rabbits, rodents, reptiles, dove and quail.
- b. There is no permanent or live water in the general proximity of the location.
- c. There are no dwellings within one mile of the proposed well site.

- d. Cultural Resources Examination – This well is located in the Permian Basin MOA.

Pad + ¼ mile road	<u>\$1599.00</u>	\$.21/ft over ¼ mile	<u>\$0.00</u>	<u>\$1599.00</u>
Pipeline-up to 1 mile	<u>\$1476.00</u>	\$308 per ¼ mile	<u>\$616.00</u>	<u>\$2092.00</u>
Electric Line-up to 1 mile	<u>\$739.00</u>	\$.23/ft over 1 mile	<u>\$0.00</u>	<u>\$739.00</u>
Total	<u>\$3814.00</u>		<u>\$616.00</u>	<u>\$4430.00</u>

- e. This well is located in the MDP-1 and the EA was done by SWCA. Potash Stipulation R 3100-13 attached to lease. No lessees found within one mile of well location.

13. Bond Coverage:

Bond coverage is Individual-NMB000862, Nationwide-ESB00226.

14. Operators Representatives:

The OXY Permian representatives responsible for ensuring compliance of the surface use plan are listed below:

Victor Guadian
Production Coordinator
1502 West Commerce Dr.
Carlsbad, NM 88220
Office – 575-628-4006
Cellular – 575-291-9905

Charles Wagner
Manager Field Operations
1502 West Commerce Dr.
Carlsbad, NM 88220
Office – 575-628-4151
Cellular – 575-725-8306

Jim Wilson
Operation Specialist
P.O. Box 50250
Midland, TX 79710
Cellular – 575-631-2442

Omar Lisigurski
RMT Leader
P.O. Box 4294
Houston, TX 77210
Office – 713-215-7506
Cellular – 281-222-7248

New Mexico Staking Form

Date Staked: 10-15-15Lease/Well Name: Patton MDP 1 18 Fed #6HLegal Description: 150' FNL 50S' FEL Sec 18 T24S R31ELatitude: 32° 13' 27.04" Nad 83Longitude: -103° 48' 36.08"

More Information: _____

County: EddySurface Owner/Tenant: BLMNearest Residence: 2 miles

Nearest Water Well: _____

V-Door: WestRoad Description: Road into NE corner from North

New Road: _____

Upgrade Existing Road: _____

Interim Reclamation: 30' EAST 50' SOUTH

Source of Caliche: _____

Top Soil: EASTOnsite Date Performed: 1-12-16Onsite Attendees: Jesse Bassett, Brooke Wilson-BLM, Jim Wilson-Oxy
Michael Wilson-Oxy, Asel Surucy

Special Notes: _____

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Oxy USA, Inc.
LEASE NO.:	NMNM89819
WELL NAME & NO.:	6H-Patton MDP1 18 Federal
SURFACE HOLE FOOTAGE:	150'/N & 505'/E
BOTTOM HOLE FOOTAGE	230'/S & 354'/E
LOCATION:	Section 18, T.24 S., R.31 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Lesser Prairie-Chicken Timing Stipulations
 - Below Ground-level Abandoned Well Marker
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
 - Cement Requirements
 - High Pressure
 - Secretary's Potash
 - Logging Requirements
 - Waste Material and Fluids
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. **Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Potash Areas:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least **24 hours**. WOC time will be recorded in the driller's log.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Secretary's Potash

Possible water flows in the Castile, Salado, Delaware, and Bone Spring.

Possible lost circulation in the Rustler, Delaware, and Bone Spring.

Possible high pressure in the Wolfcamp and subsequent formations.

1. The 16 inch surface casing shall be set at approximately 700 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.** Additional cement may be required – excess calculates to 1%.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 10-3/4 inch 1st intermediate casing, which shall be set at approximately 4275 feet (**basal anhydrite of the Castile or the Lamar Limestone formation**), is:

- ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to potash.**

Formation below the 10-3/4" shoe to be tested according to Onshore Order

2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole. Report results to BLM office.

Intermediate casing shall be kept fluid filled while running into hole to meet BLM minimum collapse requirements.

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

3. The minimum required fill of cement behind the 7-5/8 inch 2nd intermediate casing is:
☒ Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification.

Formation below the 7-5/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe and the mud weight for the bottom of the hole. Report results to BLM office.

The pilot hole plugging procedure is approved as written. Tag plugs and note plug tops on subsequent drilling report.

4. The minimum required fill of cement behind the 5-1/2 x 4-1/2 inch production casing is:
☒ Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification.
5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).

3. **Operator has proposed a multi-bowl wellhead assembly.** This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi.**
- a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Operator shall perform the intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.

5M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.

4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 7-5/8" 2nd intermediate casing shoe shall be **10,000 (10M) psi. 10M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.**
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
- a. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer.**
 - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - d. The results of the test shall be reported to the appropriate BLM office.
 - e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**

- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the **Wolfcamp** formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

D. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the **Wolfcamp** formation, and shall be used until production casing is run and cemented.

E. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

F. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

CRW 062016

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator

removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.
5. All construction and maintenance activity will be confined to the authorized right-of-way.
6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.
7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:
 - Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
 - Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)

- The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)

8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.

9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

- | | |
|--|--|
| <input type="checkbox"/> seed mixture 1 | <input type="checkbox"/> seed mixture 3 |
| <input checked="" type="checkbox"/> seed mixture 2 | <input type="checkbox"/> seed mixture 4 |
| <input type="checkbox"/> seed mixture 2/LPC | <input type="checkbox"/> Aplomado Falcon Mixture |

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be

immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches [that are not otherwise fenced, screened, or netted] to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

19. Special Stipulations:

Lesser Prairie-Chicken

Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

C. ELECTRIC LINES

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.
5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes from the poles removed.

Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except

between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leaks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory

revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

NMOCD CONDITION OF APPROVAL

The *New* Gas Capture Plan (GCP) notice is posted on the NMOCD website under Announcements. The Plan became effective May 1, 2016. A copy of the GCP form is included with the NOTICE and is also in our FORMS section under Unnumbered Forms. Please review filing dates for all applicable activities currently approved or pending and submit accordingly. Failure to file a GCP may jeopardize the operator's ability to obtain C-129 approval to flare gas after the initial 60-day completion period.