

# Carlsbad Field Office

## OCD Artesia

Form 3160-3  
(August 2007)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

### APPLICATION FOR PERMIT TO DRILL OR REENTER


FORM APPROVED  
OMB No. 1004-0137  
Expires July 31, 2010

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. SHL: NMNM-121941 BHL: fee
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name N/A
2. Name of Operator MATADOR PRODUCTION COMPANY (228937)		7. If Unit or CA Agreement, Name and No. will comm. w/ fee lease
3a. Address 5400 LBJ FREEWAY, SUITE 1500 DALLAS, TX 75240	3b. Phone No. (include area code) 972-371-5241	8. Lease Name and Well No. Charlie Sweeney Fed Com #227H 316071
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface 190' FSL & 2160' FEL At proposed prod. zone 240' FNL & 1650' FEL		9. API Well No. 30-015- 44029
14. Distance in miles and direction from nearest town or post office* 2 AIR MILES SW OF LOVING, NM		10. Field and Pool, or Exploratory WILDCAT; WOLFCAMP B 96794
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) SHL: 190' BHL: 240'	16. No. of acres in lease BLM lease = 280 acres comm. area = 320 acres	11. Sec., T. R. M. or Blk. and Survey or Area SWSE 31-23S-28E NMPM
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. SHL: 30' (Sweeney 207) BHL: 660' (Sween. 223)	19. Proposed Depth TVD: 10300' MD: 15088'	12. County or Parish EDDY
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3111' UNGRADED	22. Approximate date work will start* 03/01/2017	13. State NM
17. Spacing Unit dedicated to this well E2 31-23S-28E		
20. BLM/BIA Bond No. on file BLM NMB-001079		
23. Estimated duration 3 MONTHS		

#### 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, must be attached to this form:


- |                                                                                                                                                |                                                                                                 |
|------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------|
| 1. Well plat certified by a registered surveyor.                                                                                               | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.                                                                                                                            | 5. Operator certification                                                                       |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM.             |

25. Signature 	Name (Printed/Typed) SAM PRYOR (PHONE: 972-371-5241)	Date 09/02/2016
------------------------------------------------------------------------------------------------------	---------------------------------------------------------	--------------------

Title

SENIOR STAFF LANDMAN

(FAX: 972-371-5201)

Approved by (Signature) 	Name (Printed/Typed) Cody R. Layman	Date 12/22/16
----------------------------------------------------------------------------------------------------------------	----------------------------------------	------------------

Title

FOR FIELD MANAGER

Office

CARLSBAD FIELD OFFICE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

APPROVAL FOR TWO YEARS

\*(Instructions on page 2)

NM OIL CONSERVATION  
ARTESIA DISTRICT

JAN 03 2017 REP 1-10-17

RECEIVED RB

SEE ATTACHED FOR  
CONDITIONS OF APPROVAL

Matador Production Company

SURFACE PLAN PAGE 5

Charlie Sweeney Fed Com 31-23S-28E 227H


SHL 190' FSL & 2160' FEL Sec. 31, T. 23 S., R. 28 E.

BHL 240' FNL & 1650' FEL Sec. 31, T. 23 S., R. 28 E.

Eddy County, NM

CERTIFICATION

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U. S. C. 1001 for the filing of false statements. Executed this 2nd day of July, 2016.



\_\_\_\_\_  
Brian Wood, Consultant

Permits West, Inc.

37 Verano Loop, Santa Fe, NM 87508

(505) 466-8120

FAX: (505) 466-9682

Cellular: (505) 699-2276

Field representative will be:

Sam Pryor, Senior Staff Landman

Matador Production Company

5400 LBJ Freeway, Suite 1500

Dallas TX 75240

Phone: (972) 371-5241

FAX: (214) 866-4841

# PECOS DISTRICT SURFACE USE CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Matador Operating Company
LEASE NO.:	NMNM121941
WELL NAME & NO.:	227H-Charlie Sweeney Fed Com
SURFACE HOLE FOOTAGE:	190'/S & 2061'/E
BOTTOM HOLE FOOTAGE:	240'/N & 1650'/E
LOCATION:	Section 31, T. 23 S., R. 28 E., NMPM
COUNTY:	Eddy County, New Mexico

## TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
  - Cave/Karst
- ☐ **Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- ☐ **Road Section Diagram**
- ☒ **Production (Post Drilling)**
  - Well Structures & Facilities
  - Pipelines
  - Electric Lines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

District I  
1625 N. French Dr., Hobbs, NM 88240  
Phone: (575) 393-6161 Fax: (575) 393-0720  
District II  
811 S. First St., Artesia, NM 88210  
Phone: (575) 748-1283 Fax: (575) 748-9720  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
Phone: (505) 334-6178 Fax: (505) 334-6170  
District IV  
1220 S. St. Francis Dr., Sante Fe, NM 87505  
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico  
Energy, Minerals & Natural Resources  
Department  
OIL CONSERVATION DIVISION  
1220 South St. Francis Dr.  
Sante Fe, NM 87505

FORM C-102  
Revised August 1, 2011  
Submit one copy to appropriate  
District Office  
☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

<sup>1</sup> API Number 30-015- <b>44029</b>	<sup>2</sup> Pool Code <b>96794</b>	<sup>3</sup> Pool Name WILDCAT; WOLFCAMP B
<sup>4</sup> Property Code <b>316071</b>	<sup>5</sup> Property Name CHARLIE SWEENEY FED COM	
<sup>10</sup> GRID No. 228937	<sup>8</sup> Operator Name MATADOR PRODUCTION COMPANY	
		<sup>6</sup> Well Number <b>#227H</b>
		<sup>9</sup> Elevation <b>3111'</b>


<sup>10</sup>Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
<b>0</b>	<b>31</b>	<b>23-S</b>	<b>28-E</b>	<b>-</b>	<b>190'</b>	<b>SOUTH</b>	<b>2160'</b>	<b>EAST</b>	<b>EDDY</b>

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
<b>B</b>	<b>31</b>	<b>23-S</b>	<b>28-E</b>	<b>-</b>	<b>240'</b>	<b>NORTH</b>	<b>1650'</b>	<b>EAST</b>	<b>EDDY</b>

<sup>12</sup> Dedicated Acres <b>320</b>	<sup>13</sup> Joint or Infill	<sup>14</sup> Consolidation Code <b>C</b>	<sup>15</sup> Order No.
---------------------------------------------	-------------------------------	----------------------------------------------	-------------------------


No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



[illegible]

SECTION 31 TWP 23-S RGE 28-E SURVEY N.M.P.M.  
COUNTY EDDY STATE NM ELEVATION 3111'  
DESCRIPTION 190' FSL & 2160' FEL

SCALE: 1" = 2000'



0' 1000' 2000'





1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
[WWW.TOPOGRAPHIC.COM](http://WWW.TOPOGRAPHIC.COM)



**Matador**  
PRODUCTION COMPANY

-N-






NATIONAL  
GEOGRAPHIC

0.0 0.5 1.0 1.5 2.0 2.5 3.0 miles  
0 1 2 3 4 5 km

TN-MN  
7.5°  
05/26/16







763

32.2653, -104.12624  
32.26502, -104.12621

3661.69' overhead  
power line

3750.25'  
surface water line

road already  
upgraded to  
valve station

32.2506, -104.1408  
32.25915, -104.13425

valve station  
(under  
construction)

upgrade 0.4 mile  
existing road

1082.28'  
new road

32.25666, -104.12597

32.25644, -104.1261

326.53' new road

32.25546, -104.12449  
32.25588, -104.12588

627.47' gas &  
saltwater lines

Charlie Sweeney Fed Com 227H

32.25445, -104.12588

existing Longwood  
Midstream pipelines

MAP 3


earth

1000 ft

SCALE: 1" = 1000'

SECTION 31, TOWNSHIP 23-S, RANGE 28-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

MAP 4




Being a proposed road easement being 30 feet in width, 15 feet left, and 15 feet right of the above platted centerline total line footage containing 5501.58 feet or 333.43 rods, containing 3.79 acres more or less.



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM



Michael Blake Brown, P.S. No. 18329

SEPTEMBER 1, 2016

CHARLIE SWEENEY FED ROAD EASEMENT	REVISION:	
	MML	06/30/16
	R.M.	08/24/16
DATE: 06/20/16	GJU	09/01/16
FILE: EP CHARLIE SWEENEY FED ROAD EASEMENT REV3		
DRAWN BY: MML		
SHEET: 1 OF 1		


NOTES:

1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY. MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR PRODUCTION CO. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
4. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
5. E.O.L. = END OF LINE
6. P.I. = POINT OF INTERSECTION
7. D.R.E.C.N.M. = DEED RECORDS EDDY COUNTY NEW MEXICO



MAP 5

SECTION 31, TOWNSHIP 23-S, RANGE 28-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO



LEGEND

LEASE NAME & WELL NO.: CHARLIE SWEENEY FED COM 31-23S-28E #227H

#227H LATITUDE N 32.2546332 #227H LONGITUDE W 104.1247363

SECTION LINE

SCALE: 1" = 100'

0' 50' 100'



TOPOGRAPHIC  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1853 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID  
BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE OF THE  
NORTH AMERICAN DATUM 1927, U.S. SURVEY FEET

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER  
MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY,  
AND DATA PROVIDED BY MATADOR PRODUCTION COMPANY. THIS CERTIFICATION IS MADE AND  
LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS  
NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ORIGINAL DOCUMENT SIZE: 8.5" X 11"

S:\SURVEY\MATADOR\_RESOURCES\CHARLIE\_SWEENEY\_FED\_COM\_31-23S-28E\_227H\FINAL\_PRODUCTS\LO\_CHARLIE\_SWEENEY\_FED\_COM\_31-23S-28E\_227H\_REV3.DWG 4/28/2016 8:04:15 AM jstovall

SCALE: 1" = 200'

0' 100' 200'




SECTION 31, TOWNSHIP 23-S, RANGE 28-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

MAP 6



TOP OF PAD ELEVATION: 3111.9429  
CUT SLOPE: 33.33% 3.00:1 18.43°  
FILL SLOPE: 33.33% 3.00:1 18.43°  
BALANCE TOLERANCE (C.Y.): 0.00  
CUT SWELL FACTOR: 1.00  
FILL SHRINK FACTOR: 1.00

PAD EARTHWORK VOLUMES  
CUT: 384,007.9 C.F., 14,222.51 C.Y.  
FILL: 384,008.1 C.F., 14,222.52 C.Y.  
BALANCE IMPORT: 0.2 C.F., 0.01 C.Y.  
AREA: 183694.3 SQ.FT., 4.217 ACRES




Horizontal Scale = 1:50  
Vertical Scale = 1:5



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548  
TEXAS FIRM REGISTRATION NO. 10042504  
WWW.TOPOGRAPHIC.COM



Michael Blake Brown, P.S. No. 18329

JANUARY 25, 2016

Field note description of even date accompanies this plat.

NOTES:

1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927.
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR RESOURCE COMPANY. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.

CHARLIE SWEENEY FED  
COM 31-23S-28E  
SURFACE PAD SITE PRO

REVISION:

INT DATE

DATE: 01/25/16

FILE: \\MATADOR\RESOURCES\CHARLIE\_SWEENEY\_FED\_COM\_31-23S-28E\_223H\_SURFACE\_PAD\_SITE\_FINAL\_PRODUCT\CID\_CHARLIE\_SWEENEY\_FED\_COM\_31-23S-28E\_223H\_SURFACE\_PAD\_SITE\_PRO\_REV1.DWG 4/27/2016 6:29:51 PM jstoval


DRAWN BY: GLH

SHEET: 1 OF 2

SCALE: 1" = 200'  
0' 100' 200'


SECTION 31, TOWNSHIP 23-S, RANGE 28-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

MAP 7



TOP OF PAD ELEVATION: 3111.9429  
CUT SLOPE: 33.33% 3.00:1 18.43°  
FILL SLOPE: 33.33% 3.00:1 18.43°  
BALANCE TOLERANCE (C.Y.): 0.00  
CUT SWELL FACTOR: 1.00  
FILL SHRINK FACTOR: 1.00

PAD EARTHWORK VOLUMES  
CUT: 384,007.9 C.F., 14,222.51 C.Y.  
FILL: 384,008.1 C.F., 14,222.52 C.Y.  
BALANCE IMPORT: 0.2 C.F., 0.01 C.Y.  
AREA: 183694.3 SQ.FT., 4.217 ACRES




Horizontal Scale = 1:50  
Vertical Scale = 1:5



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548  
TEXAS FIRM REGISTRATION NO. 10042504  
WWW.TOPOGRAPHIC.COM



Michael Blake Brown, P.S. No. 18329

JANUARY 25, 2016

Field note description of even date accompanies this plat.

CHARLIE SWEENEY FED  
COM 31-23S-28E  
SURFACE PAD SITE PRO

REVISION:

INT	DATE

DATE: 01/25/16

FILE: \\SURVEY\MATADOR\_RESOURCES\CHARLIE\_SWEENEY\_FED\_COM\_31-23S-28E\_223H\_SURFACE\_PAD\_SITE\FINAL\_PRODUCT\SCD\_CHARLIE\_SWEENEY\_FED\_COM\_31-23S-28E\_223H\_SURFACE\_PAD\_SITE\_PRO\_REV1.DWG 4/27/2016 6:29:52 PM jstoval

DRAWN BY: GLH

SHEET: 2 OF 2

NOTES:


1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927.
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR RESOURCE COMPANY. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.



SCALE: 1" = 1000'

SECTION 6, TOWNSHIP 24-S, RANGE 28-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

MAP 9




CHARLIE SWEENEY FEDERAL  
FLOWLINE EASEMENT

Being a proposed flowline easement being 30 feet in width, 15 feet left, and 15 feet right of the above platted centerline total line footage containing 48.27 feet or 2.93 rods, containing 0.03 acres more or less.



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY  
1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM




Michael Blake Brown, P.S. No. 18329  
JUNE 20, 2016

CHARLIE SWEENEY FEDERAL FLOWLINE EASEMENT		REVISION:	NOTES: 1. ORIGINAL DOCUMENT SIZE: 8.5" X 11" 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927. 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR PRODUCTION CO. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY. 4. P.O.B. = POINT OF BEGINNING 5. E.O.L. = END OF LINE 6. D.R.E.C.N.M. = DEED RECORDS EDDY COUNTY NEW MEXICO
DATE:	06/20/16		
FILE:	EP CHARLIE SWEENEY FEDERAL FLOWLINE EASEMENT SEC 6		
DRAWN BY:	GJU		
SHEET:	1 OF 1		

SECTION 31, TOWNSHIP 23-S, RANGE 28-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO


SCALE: 1" = 1000'  
0' 500' 1000'

MAP 10



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM



Michael Blake Brown, P.S. No. 18329  
JUNE 20, 2016


CHARLIE SWEENEY FEDERAL ELECTRIC EASEMENT		REVISION:	NOTES:
DATE:	06/20/16		
FILE:	EP CHARLIE SWEENEY FEDERAL ELECTRICAL LINE EASEMENT CONNALLY		1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
DRAWN BY:	GJU		2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927.
SHEET:	1 OF 1		3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR PRODUCTION CO. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
			4. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
			5. E.O.L. = END OF LINE
			6. P.I. = POINT OF INTERSECTION
			7. D.R.E.C.N.M. = DEED RECORDS EDDY COUNTY NEW MEXICO
			8. C.R.E.C.N.M. = COUNTY RECORDS EDDY COUNTY NEW MEXICO



SECTION 31, TOWNSHIP 23-S, RANGE 28-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

SCALE: 1" = 1000'

MAP 11




Being a proposed electric line easement being 15 feet in width, 7.5 feet left, and 7.5 feet right of the above platted centerline total line footage containing 69.92 feet or 4.24 rods, containing 0.02 acres more or less.



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140  
TELEPHONE (817) 744-7512 • FAX (817) 744-7548  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE (432) 682-1653 OR (800) 787-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM



Michael Blake Brown, P.S. No. 18329  
JUNE 20, 2016

CHARLIE SWEENEY FEDERAL ELECTRIC EASEMENT		REVISION:	NOTES:
DATE:	06/20/16		
FILE:	CP CHARLIE SWEENEY FEDERAL ELECTRICAL LINE EASEMENT MOORE		
DRAWN BY:	GJU		
SHEET:	1 OF 1		


NOTES:

1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927.
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR PRODUCTION CO. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
4. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
5. E.O.L. = END OF LINE
6. P.I. = POINT OF INTERSECTION
7. D.R.E.C.N.M. = DEED RECORDS EDDY COUNTY NEW MEXICO
8. C.R.E.C.N.M. = COUNTY RECORDS EDDY COUNTY NEW MEXICO

SCALE: 1" = 1000'

SECTION 31, TOWNSHIP 23-S, RANGE 28-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

MAP 12



LEGEND

- SURVEY/SECTION LINE
- BOUNDARY
- SURVEYED BASELINE
- CONTINUED BASELINE
- EDGE OF EASEMENT
- ROAD WAY
- X FENCE LINE
- OHE OVERHEAD ELECTRIC
- EXISTING PIPELINE
- W WATER LINE
- MONUMENT
- IRON ROD FOUND
- P.S. 18329 IRON ROD W/CAP

DETAIL VIEW

SCALE: 1" = 20'

LINE A

LINE	BEARING	DISTANCE
A1	S 00°23'16" W	1810.82'
A2	S 86°56'55" E	255.80'
A3	N 89°14'41" E	1120.81'
A4	S 76°10'02" E	213.38'
A5	S 89°02'56" E	1722.43'
A6	S 00°56'17" W	319.05'

LINE B

LINE	BEARING	DISTANCE
B1	S 00°05'30" E	349.44'


CHARLIE SWEENEY FEDERAL  
FAST LINE EASEMENT

Being a proposed fast line easement being 15 feet in width, 7.5 feet left, and 7.5 feet right of the above platted centerline total line footage containing 5791.73 feet or 351.01 rods, containing 1.99 acres more or less.



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM



Michael Blake Brown, P.S. No. 18329  
JUNE 20, 2016

CHARLIE SWEENEY  
FEDERAL FAST LINE  
EASEMENT

REVISION:

DATE: 06/20/16  
FILE: 07 CHARLIE SWEENEY FEDERAL FAST LINE EASEMENT CONNALLY  
DRAWN BY: MML  
SHEET: 1 OF 1


NOTES:

1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927.
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR PRODUCTION CO. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
4. B.O.L./P.O.B. = BEGINNING OF LINE/POINT OF BEGINNING
5. E.O.L. = END OF LINE
6. P.I. = POINT OF INTERSECTION
7. D.R.E.C.N.M. = DEED RECORDS EDDY COUNTY NEW MEXICO

SECTION 31, TOWNSHIP 23-S, RANGE 28-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

SCALE: 1" = 1000'

0' 500' 1000'




CHARLIE SWEENEY FEDERAL  
FAST LINE EASEMENT

Being a proposed fast line easement being 15 feet in width, 7.5 feet left, and 7.5 feet right of the above platted centerline total line footage containing 50.00 feet or 3.03 rods, containing 0.02 acres more or less.



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7548  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM



Michael Blake Brown, P.S. No. 18329  
JUNE 20, 2016

CHARLIE SWEENEY FEDERAL FAST LINE EASEMENT		REVISION:	NOTES:
DATE:	06/20/16		1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
FILE:	EP CHARLIE SWEENEY FEDERAL FAST LINE EASEMENT LONGWOOD		2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE, U.S. SURVEY FEET, NORTH AMERICAN DATUM 1927.
DRAWN BY:	MML		3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY MATADOR PRODUCTION CO. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
SHEET:	1 OF 1		4. B.O.L. = BEGINNING OF LINE
			5. P.O.E. = POINT OF EXIT
			6. D.R.E.C.N.M. = DEED RECORDS EDDY COUNTY NEW MEXICO

**Matador Production Company**  
**Charlie Sweeney Fed Com 227H**  
**SHL 190' FSL & 2160' FEL Sec. 31, T. 23 S., R. 28 E.**  
**BHL 240' FNL & 1650' FEL Sec. 31, T. 23 S., R. 28 E.**  
**Eddy County, NM**

**DRILL PLAN PAGE 1**

Drilling Program

**1. ESTIMATED TOPS**

<b>Formation Name</b>	<b>TVD</b>	<b>Bearing</b>
Quaternary	GL	Water
Eroded Salado/Rustler	460	Water/Salt
Castille	780	Salt
Base of Salt/Top of Anhydrite	2347	Barren
Lamar	2500	Barren
Bell Canyon	2533	Hydrocarbon
Cherry Canyon	3330	Hydrocarbon
Brushy Canyon	4524	Hydrocarbon
Bone Spring Lime	6067	Hydrocarbon
1st Bone Spring Sand	7012	Hydrocarbon
2nd Bone Spring Carbonate	7277	Hydrocarbon
2nd Bone Spring Sand	7657	Hydrocarbon
3 <sup>rd</sup> Bone Spring Carbonate	7947	Hydrocarbon
3 <sup>rd</sup> Bone Spring Sand	9032	Hydrocarbon
Wolfcamp	9487	Hydrocarbon
Wolfcamp B	10007	Hydrocarbon (& Target Formation)
TVD (Wolfcamp B)	10300	Hydrocarbon
MD (Wolfcamp B)	15088	Hydrocarbon

**2. NOTABLE ZONES**

Closest water well (C 02022/02955/03218) is ½ mile west-northwest. Depth of well and depth to water have not been reported to the State. Proposed depth was 190'. Closest (≈5,000' south) well (C 01244) with reported depths found water at 70'.

**3. PRESSURE CONTROL**

A BOP stack consisting of 3 rams with 2 pipe rams, 1 blind ram and 1 annular preventer will be installed. The BOP will be used below surface casing to TD. See attached BOP and choke manifold diagrams.

**Matador Production Company**  
**Charlie Sweeney Fed Com 227H**  
**SHL 190' FSL & 2160' FEL Sec. 31, T. 23 S., R. 28 E.**  
**BHL 240' FNL & 1650' FEL Sec. 31, T. 23 S., R. 28 E.**  
**Eddy County, NM**

**DRILL PLAN PAGE 2**

An accumulator that meets the requirements of Onshore Order 2 for the pressure rating of the BOP stack will be present. A rotating head will be installed as needed.

Pressure tests will be conducted before drilling out from under all casing strings. BOP will be inspected and operated as recommended in Onshore Order 2. A Kelly cock and sub equipped with a full opening valve sized to fit the drill pipe and collars will be available on the rig floor in the open position.

A third party company will test the BOPs. Test pressures will be as follows. After surface casing is set and the BOP is nipped up, the BOP pressure tests will be made to 250 psi low and 2000 psi high. On the intermediate #1, pressure tests will be made to 250 psi low and 3000 psi high. On the intermediate #2, pressure tests will be made to 250 psi low and 5000 psi high. The annular preventer will be tested to 250 psi low and 1000 psi high on the surface casing, and 250 psi low and 2500 psi high on the intermediate #1 and #2 casing. In the case of running a speed head with landing mandrel for 9-5/8" and 7" casing the initial, after surface casing is set, BOP test pressures will be 250 psi low and 3000 psi high with wellhead seals tested to 5000 psi once the 9-5/8" casing has been landed and cemented. The BOP will then be lifted to install the 'C-section' of the wellhead. Matador will nipple the BOP back up and the pressure tests will be made to 250 psi low and 5000 psi high and the annular will be tested to 250 psi low and 2500 psi high.

Matador requests a variance to drill the well using a co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used.

**4. CASING & CEMENT**

Hole will extend north of the drilling window to allow for pump installation. All perforations will be  $\geq 330'$  from the dedication perimeter.

Hole O. D.	Set @ (MD)	Casing O. D.	Age	Weight (lb/ft)	Grade	Thread Collar	Collapse	Burst	Tension
17.5"	550'	13.375"	New	54.5	J-55	BTC	1.125	1.125	1.8
12.25"	2600'	9.625"	New	40	J-55	BTC	1.125	1.125	1.8
8.75"	10470'	7"	New	29	P-110	BTC	1.125	1.125	1.8

**Matador Production Company**  
**Charlie Sweeney Fed Com 227H**  
**SHL 190' FSL & 2160' FEL Sec. 31, T. 23 S., R. 28 E.**  
**BHL 240' FNL & 1650' FEL Sec. 31, T. 23 S., R. 28 E.**  
**Eddy County, NM**

**DRILL PLAN PAGE 3**

6.125"	15090'	4.5"	New	13.5	P-110	BTC/TXP	1.125	1.125	1.8
--------	--------	------	-----	------	-------	---------	-------	-------	-----

Name	Type	Sacks	Yield	Cu. Ft.	Weight	Blend
Surface	Lead	240	1.82	436.8	12.8	Class C + Bentonite + 2% CaCl <sub>2</sub> + 3% NaCl + LCM
	Tail	350	1.38	483	14.8	Class C + 5% NaCl + LCM
TOC = GL		100% Excess			Centralizers per Onshore Order 2.III.B.1f	
Intermediate	Lead	550	2.13	1171.5	12.6	Class C + Bentonite + 1% CaCl <sub>2</sub> + 8% NaCl + LCM
	Tail	270	1.38	372.6	14.8	Class C + 5% NaCl + LCM
TOC = GL		100% Excess			2 on btm jt, 1 on 2nd jt, 1 every 4th jt to surface	
Intermediate 2	Lead	600	2.13	1278	12.6	TXI + Fluid Loss + Dispersant + Retarder + LCM
	Tail	310	1.38	427.8	14.8	TXI + Fluid Loss + Dispersant + Retarder + LCM
TOC = 1500'		35% Excess			2 on btm jt, 1 on 2nd jt, 1 every 4th jt to top of tail cement (500' above TOC)	
Production	Tail	500	1.17	585	15.8	Class H + Fluid Loss + Dispersant + Retarder + LCM
TOC = 9970'		25% Excess			2 on btm jt, 1 on 2nd jt, 1 every other jt to top of curve	

## 5. MUD PROGRAM

Mud monitoring system will be an electronic Pason system satisfying the requirements of Onshore Order 1. All necessary mud products for weight addition and fluid loss control will be on location at all times. Mud program is subject to change due to the hole condition.

Name	Hole Size	Mud Weight	Visc	Fluid Loss	Type Mud
Surface	17.5"	8.30	28	NC	FW Spud Mud
Intermediate	12.25"	10.00	30-32	NC	Brine Water
Intermediate 2	8.75"	8.00	30-31	NC	FW/Cut Brine
Production	6.125"	12.50	50-60	<10	OBM

**Matador Production Company  
Charlie Sweeney Fed Com 227H  
SHL 190' FSL & 2160' FEL Sec. 31, T. 23 S., R. 28 E.  
BHL 240' FNL & 1650' FEL Sec. 31, T. 23 S., R. 28 E.  
Eddy County, NM**

**DRILL PLAN PAGE 4**

#### **6. CORES, TESTS, & LOGS**

No core or drill stem test is planned.

A 2-person mud-logging program will be used from 10400' to TD.

No electric logs are planned. GR will be collected through the MWD tools from intermediate casing to TD. CBL with CCL will be run as far as gravity will let it fall to TOC.

#### **7. DOWN HOLE CONDITIONS**

No abnormal pressure or temperature is expected. Maximum expected bottom hole pressure is  $\approx 7150$  psi. Expected bottom hole temperature is  $\approx 170^{\circ}$  F.

In accordance with Onshore Order 6, Matador does not anticipate that there will be enough  $H_2S$  from the surface to the Bone Spring to meet the BLM's minimum requirements for the submission of an " $H_2S$  Drilling Operation Plan" or "Public Protection Plan" for the drilling and completion of this well. Since Matador has an  $H_2S$  safety package on all wells, attached is an " $H_2S$  Drilling Operations Plan". Adequate flare lines will be installed off the mud/gas separator where gas may be flared safely. All personnel will be familiar with all aspects of safe operation of equipment being used.

#### **8. OTHER INFORMATION**

The anticipated spud date is upon approval. It is expected it will take  $\approx 3$  months to drill and complete the well.



## **Matador Resources**

Eddy County, NM (NAD27 NME)  
Charlie Sweeney Federal 31-23S-28E  
227H

OH

Plan: Preliminary Plan 1

## **Standard Planning Report**

05 January, 2016







# Phoenix Technology Services

## Planning Report



**Database:** Compass 5000 GCR  
**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Site:** Charlie Sweeney Federal 31-23S-28E  
**Well:** 227H  
**Wellbore:** OH  
**Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature

<b>Project</b>	Eddy County, NM (NAD27 NME)		
<b>Map System:</b>	US State Plane 1927 (Exact solution)	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	NAD 1927 (NADCON CONUS)		
<b>Map Zone:</b>	New Mexico East 3001		

**Site** Charlie Sweeney Federal 31-23S-28E

<b>Site Position:</b>		<b>Northing:</b>	456,416.00 usft	<b>Latitude:</b>	32° 15' 16.67754 N
<b>From:</b>	Map	<b>Easting:</b>	564,425.00 usft	<b>Longitude:</b>	104° 7' 29.74586 W
<b>Position Uncertainty:</b>	0.00 usft	<b>Slot Radius:</b>	13-3/16 "	<b>Grid Convergence:</b>	0.11 °

<b>Well</b>	227H				
<b>Well Position</b>	<b>+N/-S</b>	0.00 usft	<b>Northing:</b>	456,416.00 usft	<b>Latitude:</b>
	<b>+E/-W</b>	60.00 usft	<b>Easting:</b>	564,485.00 usft	<b>Longitude:</b>
<b>Position Uncertainty</b>	0.00 usft		<b>Wellhead Elevation:</b>	0.00 usft	<b>Ground Level:</b>
					3,107.00 usft

**Wellbore** OH

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	HDGM	1/20/2016	7.50	60.10	48,251

**Design** Preliminary Plan 1

### Audit Notes:

<b>Version:</b>	<b>Phase:</b>	PROTOTYPE	<b>Tie On Depth:</b>	0.00
-----------------	---------------	-----------	----------------------	------

Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.00	0.00	0.00	0.48

### Plan Sections

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,300.00	4.50	105.17	1,299.69	-3.08	11.36	1.50	1.50	0.00	105.17	
2,750.00	4.50	105.17	2,745.22	-32.85	121.17	0.00	0.00	0.00	0.00	
3,116.50	10.00	105.17	3,108.65	-44.95	165.78	1.50	1.50	0.00	0.00	
4,830.79	10.00	105.17	4,796.91	-122.82	453.02	0.00	0.00	0.00	0.00	
5,497.28	0.00	0.00	5,460.03	-138.00	509.00	1.50	-1.50	0.00	180.00	
9,751.28	0.00	0.00	9,714.03	-138.00	509.00	0.00	0.00	0.00	0.00	
10,501.28	75.00	0.48	10,267.46	286.65	512.56	10.00	10.00	0.00	0.48	
10,751.29	90.00	0.48	10,300.00	533.80	514.63	6.00	6.00	0.00	0.00	
15,087.64	90.00	0.48	10,300.00	4,870.00	551.00	0.00	0.00	0.00	0.00	BHL Sweeney 227H



# Phoenix Technology Services

## Planning Report



**Database:** Compass 5000 GCR  
**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Site:** Charlie Sweeney Federal 31-23S-28E  
**Well:** 227H  
**Wellbore:** OH  
**Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature

### Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>13 3/8"</b>									
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Start Build 1.50°/100'</b>									
1,100.00	1.50	105.17	1,099.99	-0.34	1.26	-0.33	1.50	1.50	0.00
1,200.00	3.00	105.17	1,199.91	-1.37	5.05	-1.33	1.50	1.50	0.00
1,300.00	4.50	105.17	1,299.69	-3.08	11.36	-2.99	1.50	1.50	0.00
<b>Hold 4.5° Inc at 105.17° Azm</b>									
1,400.00	4.50	105.17	1,399.38	-5.13	18.94	-4.98	0.00	0.00	0.00
1,500.00	4.50	105.17	1,499.08	-7.19	26.51	-6.97	0.00	0.00	0.00
1,600.00	4.50	105.17	1,598.77	-9.24	34.08	-8.95	0.00	0.00	0.00
1,700.00	4.50	105.17	1,698.46	-11.29	41.65	-10.94	0.00	0.00	0.00
1,800.00	4.50	105.17	1,798.15	-13.35	49.23	-12.93	0.00	0.00	0.00
1,900.00	4.50	105.17	1,897.84	-15.40	56.80	-14.92	0.00	0.00	0.00
2,000.00	4.50	105.17	1,997.53	-17.45	64.37	-16.91	0.00	0.00	0.00
2,100.00	4.50	105.17	2,097.23	-19.51	71.94	-18.90	0.00	0.00	0.00
2,200.00	4.50	105.17	2,196.92	-21.56	79.52	-20.89	0.00	0.00	0.00
2,300.00	4.50	105.17	2,296.61	-23.61	87.09	-22.88	0.00	0.00	0.00
2,400.00	4.50	105.17	2,396.30	-25.67	94.66	-24.87	0.00	0.00	0.00
2,500.00	4.50	105.17	2,495.99	-27.72	102.23	-26.86	0.00	0.00	0.00
2,600.00	4.50	105.17	2,595.68	-29.77	109.81	-28.85	0.00	0.00	0.00
<b>9 5/8"</b>									
2,700.00	4.50	105.17	2,695.38	-31.83	117.38	-30.84	0.00	0.00	0.00
2,750.00	4.50	105.17	2,745.22	-32.85	121.17	-31.84	0.00	0.00	0.00
<b>Start Build 1.50°/100'</b>									
2,800.00	5.25	105.17	2,795.04	-33.96	125.27	-32.91	1.50	1.50	0.00
2,900.00	6.75	105.17	2,894.49	-36.70	135.36	-35.56	1.50	1.50	0.00
3,000.00	8.25	105.17	2,993.63	-40.11	147.95	-38.87	1.50	1.50	0.00
3,100.00	9.75	105.17	3,092.40	-44.21	163.05	-42.84	1.50	1.50	0.00
3,116.50	10.00	105.17	3,108.65	-44.95	165.78	-43.56	1.50	1.50	0.00
<b>Hold 10° Inc</b>									
3,200.00	10.00	105.17	3,190.89	-48.74	179.77	-47.23	0.00	0.00	0.00
3,300.00	10.00	105.17	3,289.37	-53.28	196.53	-51.64	0.00	0.00	0.00
3,400.00	10.00	105.17	3,387.85	-57.83	213.28	-56.04	0.00	0.00	0.00
3,500.00	10.00	105.17	3,486.33	-62.37	230.04	-60.44	0.00	0.00	0.00
3,600.00	10.00	105.17	3,584.81	-66.91	246.79	-64.84	0.00	0.00	0.00
3,700.00	10.00	105.17	3,683.29	-71.45	263.55	-69.24	0.00	0.00	0.00
3,800.00	10.00	105.17	3,781.77	-76.00	280.31	-73.65	0.00	0.00	0.00
3,900.00	10.00	105.17	3,880.26	-80.54	297.06	-78.05	0.00	0.00	0.00
4,000.00	10.00	105.17	3,978.74	-85.08	313.82	-82.45	0.00	0.00	0.00
4,100.00	10.00	105.17	4,077.22	-89.63	330.57	-86.85	0.00	0.00	0.00
4,200.00	10.00	105.17	4,175.70	-94.17	347.33	-91.26	0.00	0.00	0.00
4,300.00	10.00	105.17	4,274.18	-98.71	364.08	-95.66	0.00	0.00	0.00
4,400.00	10.00	105.17	4,372.66	-103.25	380.84	-100.06	0.00	0.00	0.00



# Phoenix Technology Services

## Planning Report



**Database:** Compass 5000 GCR  
**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Site:** Charlie Sweeney Federal 31-23S-28E  
**Well:** 227H  
**Wellbore:** OH  
**Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature

### Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,500.00	10.00	105.17	4,471.15	-107.80	397.59	-104.46	0.00	0.00	0.00
4,600.00	10.00	105.17	4,569.63	-112.34	414.35	-108.86	0.00	0.00	0.00
4,700.00	10.00	105.17	4,668.11	-116.88	431.11	-113.27	0.00	0.00	0.00
4,800.00	10.00	105.17	4,766.59	-121.42	447.86	-117.67	0.00	0.00	0.00
4,830.79	10.00	105.17	4,796.91	-122.82	453.02	-119.02	0.00	0.00	0.00
<b>Start Drop 1.50°/100'</b>									
4,900.00	8.96	105.17	4,865.18	-125.81	464.02	-121.91	1.50	-1.50	0.00
5,000.00	7.46	105.17	4,964.15	-129.54	477.80	-125.53	1.50	-1.50	0.00
5,100.00	5.96	105.17	5,063.46	-132.60	489.08	-128.50	1.50	-1.50	0.00
5,200.00	4.46	105.17	5,163.05	-134.97	497.84	-130.80	1.50	-1.50	0.00
5,300.00	2.96	105.17	5,262.83	-136.67	504.08	-132.44	1.50	-1.50	0.00
5,400.00	1.46	105.17	5,362.76	-137.68	507.80	-133.42	1.50	-1.50	0.00
5,497.28	0.00	0.00	5,460.03	-138.00	509.00	-133.73	1.50	-1.50	0.00
<b>Hold Vertical</b>									
5,500.00	0.00	0.00	5,462.75	-138.00	509.00	-133.73	0.00	0.00	0.00
5,600.00	0.00	0.00	5,562.75	-138.00	509.00	-133.73	0.00	0.00	0.00
5,700.00	0.00	0.00	5,662.75	-138.00	509.00	-133.73	0.00	0.00	0.00
5,800.00	0.00	0.00	5,762.75	-138.00	509.00	-133.73	0.00	0.00	0.00
5,900.00	0.00	0.00	5,862.75	-138.00	509.00	-133.73	0.00	0.00	0.00
6,000.00	0.00	0.00	5,962.75	-138.00	509.00	-133.73	0.00	0.00	0.00
6,100.00	0.00	0.00	6,062.75	-138.00	509.00	-133.73	0.00	0.00	0.00
6,200.00	0.00	0.00	6,162.75	-138.00	509.00	-133.73	0.00	0.00	0.00
6,300.00	0.00	0.00	6,262.75	-138.00	509.00	-133.73	0.00	0.00	0.00
6,400.00	0.00	0.00	6,362.75	-138.00	509.00	-133.73	0.00	0.00	0.00
6,500.00	0.00	0.00	6,462.75	-138.00	509.00	-133.73	0.00	0.00	0.00
6,600.00	0.00	0.00	6,562.75	-138.00	509.00	-133.73	0.00	0.00	0.00
6,700.00	0.00	0.00	6,662.75	-138.00	509.00	-133.73	0.00	0.00	0.00
6,800.00	0.00	0.00	6,762.75	-138.00	509.00	-133.73	0.00	0.00	0.00
6,900.00	0.00	0.00	6,862.75	-138.00	509.00	-133.73	0.00	0.00	0.00
7,000.00	0.00	0.00	6,962.75	-138.00	509.00	-133.73	0.00	0.00	0.00
7,100.00	0.00	0.00	7,062.75	-138.00	509.00	-133.73	0.00	0.00	0.00
7,200.00	0.00	0.00	7,162.75	-138.00	509.00	-133.73	0.00	0.00	0.00
7,300.00	0.00	0.00	7,262.75	-138.00	509.00	-133.73	0.00	0.00	0.00
7,400.00	0.00	0.00	7,362.75	-138.00	509.00	-133.73	0.00	0.00	0.00
7,500.00	0.00	0.00	7,462.75	-138.00	509.00	-133.73	0.00	0.00	0.00
7,600.00	0.00	0.00	7,562.75	-138.00	509.00	-133.73	0.00	0.00	0.00
7,700.00	0.00	0.00	7,662.75	-138.00	509.00	-133.73	0.00	0.00	0.00
7,800.00	0.00	0.00	7,762.75	-138.00	509.00	-133.73	0.00	0.00	0.00
7,900.00	0.00	0.00	7,862.75	-138.00	509.00	-133.73	0.00	0.00	0.00
8,000.00	0.00	0.00	7,962.75	-138.00	509.00	-133.73	0.00	0.00	0.00
8,100.00	0.00	0.00	8,062.75	-138.00	509.00	-133.73	0.00	0.00	0.00
8,200.00	0.00	0.00	8,162.75	-138.00	509.00	-133.73	0.00	0.00	0.00
8,300.00	0.00	0.00	8,262.75	-138.00	509.00	-133.73	0.00	0.00	0.00
8,400.00	0.00	0.00	8,362.75	-138.00	509.00	-133.73	0.00	0.00	0.00
8,500.00	0.00	0.00	8,462.75	-138.00	509.00	-133.73	0.00	0.00	0.00
8,600.00	0.00	0.00	8,562.75	-138.00	509.00	-133.73	0.00	0.00	0.00
8,700.00	0.00	0.00	8,662.75	-138.00	509.00	-133.73	0.00	0.00	0.00
8,800.00	0.00	0.00	8,762.75	-138.00	509.00	-133.73	0.00	0.00	0.00
8,900.00	0.00	0.00	8,862.75	-138.00	509.00	-133.73	0.00	0.00	0.00
9,000.00	0.00	0.00	8,962.75	-138.00	509.00	-133.73	0.00	0.00	0.00
9,100.00	0.00	0.00	9,062.75	-138.00	509.00	-133.73	0.00	0.00	0.00
9,200.00	0.00	0.00	9,162.75	-138.00	509.00	-133.73	0.00	0.00	0.00
9,300.00	0.00	0.00	9,262.75	-138.00	509.00	-133.73	0.00	0.00	0.00
9,400.00	0.00	0.00	9,362.75	-138.00	509.00	-133.73	0.00	0.00	0.00



# Phoenix Technology Services

## Planning Report



Database: Compass 5000 GCR  
Company: Matador Resources  
Project: Eddy County, NM (NAD27 NME)  
Site: Charlie Sweeney Federal 31-23S-28E  
Well: 227H  
Wellbore: OH  
Design: Preliminary Plan 1

Local Co-ordinate Reference: Well 227H  
TVD Reference: RKB @ 3134.50usft (Patterson 297)  
MD Reference: RKB @ 3134.50usft (Patterson 297)  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature

### Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,500.00	0.00	0.00	9,462.75	-138.00	509.00	-133.73	0.00	0.00	0.00
9,600.00	0.00	0.00	9,562.75	-138.00	509.00	-133.73	0.00	0.00	0.00
9,700.00	0.00	0.00	9,662.75	-138.00	509.00	-133.73	0.00	0.00	0.00
9,751.28	0.00	0.00	9,714.03	-138.00	509.00	-133.73	0.00	0.00	0.00
<b>KOP: Start Build 10°/100' to 75° Inc</b>									
9,800.00	4.87	0.48	9,762.69	-135.93	509.02	-131.66	10.00	10.00	0.00
9,850.00	9.87	0.48	9,812.26	-129.52	509.07	-125.25	10.00	10.00	0.00
9,900.00	14.87	0.48	9,861.08	-118.81	509.16	-114.54	10.00	10.00	0.00
9,950.00	19.87	0.48	9,908.79	-103.89	509.29	-99.62	10.00	10.00	0.00
10,000.00	24.87	0.48	9,955.01	-84.86	509.45	-80.59	10.00	10.00	0.00
10,050.00	29.87	0.48	9,999.40	-61.88	509.64	-57.61	10.00	10.00	0.00
10,100.00	34.87	0.48	10,041.61	-35.12	509.86	-30.85	10.00	10.00	0.00
10,150.00	39.87	0.48	10,081.34	-4.78	510.12	-0.51	10.00	10.00	0.00
10,200.00	44.87	0.48	10,118.26	28.90	510.40	33.18	10.00	10.00	0.00
10,250.00	49.87	0.48	10,152.11	65.68	510.71	69.95	10.00	10.00	0.00
10,300.00	54.87	0.48	10,182.63	105.26	511.04	109.54	10.00	10.00	0.00
10,350.00	59.87	0.48	10,209.58	147.36	511.39	151.64	10.00	10.00	0.00
10,400.00	64.87	0.48	10,232.76	191.64	511.76	195.92	10.00	10.00	0.00
10,450.00	69.87	0.48	10,251.99	237.78	512.15	242.06	10.00	10.00	0.00
10,501.28	75.00	0.48	10,267.46	286.65	512.56	290.93	10.00	10.00	0.00
<b>Start Build 6°/100' - 7°</b>									
10,550.00	77.92	0.48	10,278.87	334.01	512.95	338.29	6.00	6.00	0.00
10,600.00	80.92	0.48	10,288.04	383.15	513.37	387.44	6.00	6.00	0.00
10,650.00	83.92	0.48	10,294.64	432.70	513.78	436.99	6.00	6.00	0.00
10,700.00	86.92	0.48	10,298.63	482.54	514.20	486.83	6.00	6.00	0.00
10,751.29	90.00	0.48	10,300.00	533.80	514.63	538.09	6.00	6.00	0.00
<b>LP: 90° Inc at 0.48° Azm</b>									
10,800.00	90.00	0.48	10,300.00	582.51	515.04	586.80	0.00	0.00	0.00
10,900.00	90.00	0.48	10,300.00	682.51	515.88	686.80	0.00	0.00	0.00
11,000.00	90.00	0.48	10,300.00	782.50	516.72	786.80	0.00	0.00	0.00
11,100.00	90.00	0.48	10,300.00	882.50	517.55	886.80	0.00	0.00	0.00
11,200.00	90.00	0.48	10,300.00	982.50	518.39	986.80	0.00	0.00	0.00
11,300.00	90.00	0.48	10,300.00	1,082.49	519.23	1,086.80	0.00	0.00	0.00
11,400.00	90.00	0.48	10,300.00	1,182.49	520.07	1,186.80	0.00	0.00	0.00
11,500.00	90.00	0.48	10,300.00	1,282.49	520.91	1,286.80	0.00	0.00	0.00
11,600.00	90.00	0.48	10,300.00	1,382.48	521.75	1,386.80	0.00	0.00	0.00
11,700.00	90.00	0.48	10,300.00	1,482.48	522.59	1,486.80	0.00	0.00	0.00
11,800.00	90.00	0.48	10,300.00	1,582.47	523.43	1,586.80	0.00	0.00	0.00
11,900.00	90.00	0.48	10,300.00	1,682.47	524.26	1,686.80	0.00	0.00	0.00
12,000.00	90.00	0.48	10,300.00	1,782.47	525.10	1,786.80	0.00	0.00	0.00
12,100.00	90.00	0.48	10,300.00	1,882.46	525.94	1,886.80	0.00	0.00	0.00
12,200.00	90.00	0.48	10,300.00	1,982.46	526.78	1,986.80	0.00	0.00	0.00
12,300.00	90.00	0.48	10,300.00	2,082.46	527.62	2,086.80	0.00	0.00	0.00
12,400.00	90.00	0.48	10,300.00	2,182.45	528.46	2,186.80	0.00	0.00	0.00
12,500.00	90.00	0.48	10,300.00	2,282.45	529.30	2,286.80	0.00	0.00	0.00
12,600.00	90.00	0.48	10,300.00	2,382.45	530.14	2,386.80	0.00	0.00	0.00
12,700.00	90.00	0.48	10,300.00	2,482.44	530.97	2,486.80	0.00	0.00	0.00
12,800.00	90.00	0.48	10,300.00	2,582.44	531.81	2,586.80	0.00	0.00	0.00
12,900.00	90.00	0.48	10,300.00	2,682.44	532.65	2,686.80	0.00	0.00	0.00
13,000.00	90.00	0.48	10,300.00	2,782.43	533.49	2,786.80	0.00	0.00	0.00
13,100.00	90.00	0.48	10,300.00	2,882.43	534.33	2,886.80	0.00	0.00	0.00
13,200.00	90.00	0.48	10,300.00	2,982.43	535.17	2,986.80	0.00	0.00	0.00
13,300.00	90.00	0.48	10,300.00	3,082.42	536.01	3,086.80	0.00	0.00	0.00



# Phoenix Technology Services

## Planning Report



**Database:** Compass 5000 GCR  
**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Site:** Charlie Sweeney Federal 31-23S-28E  
**Well:** 227H  
**Wellbore:** OH  
**Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature

### Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
13,400.00	90.00	0.48	10,300.00	3,182.42	536.85	3,186.80	0.00	0.00	0.00
13,500.00	90.00	0.48	10,300.00	3,282.41	537.68	3,286.80	0.00	0.00	0.00
13,600.00	90.00	0.48	10,300.00	3,382.41	538.52	3,386.80	0.00	0.00	0.00
13,700.00	90.00	0.48	10,300.00	3,482.41	539.36	3,486.80	0.00	0.00	0.00
13,800.00	90.00	0.48	10,300.00	3,582.40	540.20	3,586.80	0.00	0.00	0.00
13,900.00	90.00	0.48	10,300.00	3,682.40	541.04	3,686.80	0.00	0.00	0.00
14,000.00	90.00	0.48	10,300.00	3,782.40	541.88	3,786.80	0.00	0.00	0.00
14,100.00	90.00	0.48	10,300.00	3,882.39	542.72	3,886.80	0.00	0.00	0.00
14,200.00	90.00	0.48	10,300.00	3,982.39	543.56	3,986.80	0.00	0.00	0.00
14,300.00	90.00	0.48	10,300.00	4,082.39	544.39	4,086.80	0.00	0.00	0.00
14,400.00	90.00	0.48	10,300.00	4,182.38	545.23	4,186.80	0.00	0.00	0.00
14,500.00	90.00	0.48	10,300.00	4,282.38	546.07	4,286.80	0.00	0.00	0.00
14,600.00	90.00	0.48	10,300.00	4,382.38	546.91	4,386.80	0.00	0.00	0.00
14,700.00	90.00	0.48	10,300.00	4,482.37	547.75	4,486.80	0.00	0.00	0.00
14,800.00	90.00	0.48	10,300.00	4,582.37	548.59	4,586.80	0.00	0.00	0.00
14,900.00	90.00	0.48	10,300.00	4,682.37	549.43	4,686.80	0.00	0.00	0.00
15,000.00	90.00	0.48	10,300.00	4,782.36	550.26	4,786.80	0.00	0.00	0.00
15,087.64	90.00	0.48	10,300.00	4,870.00	551.00	4,874.45	0.00	0.00	0.00

TD at 15087.64

### Design Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
- hit/miss target									
- Shape									
BHL Sweeney 227H	0.00	0.00	10,300.00	4,870.00	551.00	461,286.00	565,036.00	32° 16' 4.86052 N	104° 7' 22.51939 W
- plan hits target center									
- Point									
FPP Sweeney 227H	0.00	0.00	10,300.00	142.00	511.00	456,558.00	564,996.00	32° 15' 18.07179 N	104° 7' 23.09314 W
- plan misses target center by 82.18usft at 10387 19usft MD (10227 19 TVD, 180.11 N, 511.67 E)									
- Point									
LPP Sweeney 227H	0.00	0.00	10,300.00	4,780.00	551.00	461,196.00	565,036.00	32° 16' 3.96986 N	104° 7' 22.52145 W
- plan misses target center by 0.75usft at 14997.64usft MD (10300.00 TVD, 4780.01 N, 550.25 E)									
- Point									

### Casing Points

Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (")	Hole Diameter (")
600.00	600.00	13 3/8"	13-3/8	17-1/2
2,600.00	2,595.68	9 5/8"	9-5/8	12-1/4
10,501.28	10,267.46	7"	7	7-1/2



Phoenix Technology Services  
Planning Report





**Database:** Compass 5000 GCR  
**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Site:** Charlie Sweeney Federal 31-23S-28E  
**Well:** 227H  
**Wellbore:** OH  
**Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature

Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
1,000.00	1,000.00	0.00	0.00	Start Build 1.50°/100'
1,300.00	1,299.69	-3.08	11.36	Hold 4.5° Inc at 105.17° Azm
2,750.00	2,745.22	-32.85	121.17	Start Build 1.50°/100'
3,116.50	3,108.65	-44.95	165.78	Hold 10° Inc
4,830.79	4,796.91	-122.82	453.02	Start Drop 1.50°/100'
5,497.28	5,460.03	-138.00	509.00	Hold Vertical
9,751.28	9,714.03	-138.00	509.00	KOP: Start Build 10°/100' to 75° Inc
10,501.28	10,267.46	286.65	512.56	Start Build 6°/100'
10,751.29	10,300.00	533.80	514.63	LP: 90° Inc at 0.48° Azm
15,087.64	10,300.00	4,870.00	551.00	TD at 15087.64





## **Matador Resources**

**Eddy County, NM (NAD27 NME)  
Charlie Sweeney Federal 31-23S-28E  
227H**

**OH  
Preliminary Plan 1**

## **Anticollision Report**

**05 January, 2016**







# Phoenix Technology Services

## Anticollision Report



<b>Company:</b>	Matador Resources	<b>Local Co-ordinate Reference:</b>	Well 227H
<b>Project:</b>	Eddy County, NM (NAD27 NME)	<b>TVD Reference:</b>	RKB @ 3134.50usft (Patterson 297)
<b>Reference Site:</b>	Charlie Sweeney Federal 31-23S-28E	<b>MD Reference:</b>	RKB @ 3134.50usft (Patterson 297)
<b>Site Error:</b>	0.00 usft	<b>North Reference:</b>	Grid
<b>Reference Well:</b>	227H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.00 usft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	OH	<b>Database:</b>	Compass 5000 GCR
<b>Reference Design:</b>	Preliminary Plan 1	<b>Offset TVD Reference:</b>	Reference Datum

<b>Reference</b>	Preliminary Plan 1		
<b>Filter type:</b>	NO GLOBAL FILTER: Using user defined selection & filtering criteria		
<b>Interpolation Method:</b>	MD + Stations Interval 100.00usft	<b>Error Model:</b>	ISCWSA
<b>Depth Range:</b>	Unlimited	<b>Scan Method:</b>	Closest Approach 3D
<b>Results Limited by:</b>	Maximum center-center distance of 5,000.00 usft	<b>Error Surface:</b>	Elliptical Conic
<b>Warning Levels Evaluated at:</b>	2.00 Sigma	<b>Casing Method:</b>	Not applied

<b>Survey Tool Program</b>	<b>Date</b>	1/5/2016		
<b>From (usft)</b>	<b>To (usft)</b>	<b>Survey (Wellbore)</b>	<b>Tool Name</b>	<b>Description</b>
0.00	15,087.64	Preliminary Plan 1 (OH)	PHX+MWD+HDGM	PHX+OWSG MWD + HDGM

Summary						
Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
Charlie Sweeney Federal 31-23S-28E						
123H - OH - Preliminary Plan 1	1,009.83	1,010.97	60.00	53.21	8.844	CC
123H - OH - Preliminary Plan 1	1,200.00	1,203.75	60.44	52.35	7.473	ES
123H - OH - Preliminary Plan 1	3,000.00	3,008.25	92.84	71.92	4.438	SF
203H - OH - Preliminary Plan 1	1,000.89	1,001.91	90.00	83.28	13.389	CC
203H - OH - Preliminary Plan 1	1,100.00	1,102.07	90.66	83.26	12.240	ES
203H - OH - Preliminary Plan 1	9,200.00	9,136.10	535.40	471.23	8.344	SF
207H - OH - Preliminary Plan 1	1,073.86	1,075.42	29.99	22.76	4.148	CC
207H - OH - Preliminary Plan 1	1,300.00	1,302.97	30.25	21.48	3.451	ES
207H - OH - Preliminary Plan 1	9,147.63	9,137.99	136.85	72.81	2.137	SF
223H - OH - Preliminary Plan 1	965.28	969.28	120.00	113.52	18.525	CC
223H - OH - Preliminary Plan 1	1,000.00	1,003.97	120.00	113.27	17.841	ES
223H - OH - Preliminary Plan 1	15,087.64	15,059.17	660.02	500.89	4.148	SF

<b>Offset Design</b> Charlie Sweeney Federal 31-23S-28E - 123H - OH - Preliminary Plan 1												
Survey Program: 0-PHX+MWD+HDGM												
Reference Offset												
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor
0.00	0.00	1.00	0.00	0.00	0.00	-90.00	0.00	-60.00	60.00			
100.00	100.00	101.00	100.00	0.13	0.13	-90.00	0.00	-60.00	60.00	59.74	0.26	227.724
200.00	200.00	201.00	200.00	0.49	0.49	-90.00	0.00	-60.00	60.00	59.02	0.98	61.198
300.00	300.00	301.00	300.00	0.85	0.85	-90.00	0.00	-60.00	60.00	58.30	1.70	35.349
400.00	400.00	401.00	400.00	1.21	1.21	-90.00	0.00	-60.00	60.00	57.59	2.41	24.852
500.00	500.00	501.00	500.00	1.56	1.57	-90.00	0.00	-60.00	60.00	56.87	3.13	19.162
600.00	600.00	601.00	600.00	1.92	1.93	-90.00	0.00	-60.00	60.00	56.15	3.85	15.592
700.00	700.00	701.00	700.00	2.28	2.28	-90.00	0.00	-60.00	60.00	55.43	4.57	13.143
800.00	800.00	801.00	800.00	2.64	2.64	-90.00	0.00	-60.00	60.00	54.72	5.28	11.359
900.00	900.00	901.00	900.00	3.00	3.00	-90.00	0.00	-60.00	60.00	54.00	6.00	10.002
1,000.00	1,000.00	1,001.01	1,000.01	3.36	3.36	-90.00	0.00	-60.00	60.00	53.28	6.72	8.934
1,009.83	1,009.83	1,010.97	1,009.97	3.39	3.39	164.83	-0.01	-59.99	60.00	53.21	6.78	8.844 CC
1,100.00	1,099.99	1,102.39	1,101.38	3.70	3.71	164.50	-0.69	-58.81	60.09	52.68	7.41	8.108
1,200.00	1,199.91	1,203.75	1,202.66	4.04	4.05	163.55	-2.73	-55.31	60.44	52.35	8.09	7.473 ES
1,300.00	1,299.69	1,304.59	1,303.28	4.39	4.40	162.11	-6.01	-49.67	61.21	52.45	8.76	6.985
1,400.00	1,399.38	1,404.56	1,403.01	4.74	4.74	160.85	-9.52	-43.65	62.84	53.39	9.45	6.648

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation



# Phoenix Technology Services

## Anticollision Report



Company: Matador Resources  
Project: Eddy County, NM (NAD27 NME)  
Reference Site: Charlie Sweeney Federal 31-23S-28E  
Site Error: 0.00 usft  
Reference Well: 227H  
Well Error: 0.00 usft  
Reference Wellbore: OH  
Reference Design: Preliminary Plan 1

Local Co-ordinate Reference: Well 227H  
TVD Reference: RKB @ 3134.50usft (Patterson 297)  
MD Reference: RKB @ 3134.50usft (Patterson 297)  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Output errors are at 2.00 sigma  
Database: Compass 5000 GCR  
Offset TVD Reference: Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 123H - OH - Preliminary Plan 1											Offset Site Error: 0.00 usft		
Survey Program: 0-PHX+MWD+HDGM											Offset Well Error: 0.00 usft		
Reference		Offset		Semi Major Axis			Distance					Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)		Separation Factor
1,500.00	1,499.08	1,504.54	1,502.74	5.09	5.09	159.65	-13.03	-37.62	64.50	54.35	10.15	6.356	
1,600.00	1,598.77	1,604.52	1,602.48	5.45	5.45	158.52	-16.55	-31.60	66.19	55.34	10.85	6.101	
1,700.00	1,698.46	1,704.50	1,702.21	5.81	5.80	157.44	-20.06	-25.57	67.90	56.34	11.55	5.877	
1,800.00	1,798.15	1,804.47	1,801.95	6.17	6.16	156.41	-23.57	-19.54	69.63	57.37	12.26	5.679	
1,900.00	1,897.84	1,904.45	1,901.68	6.53	6.52	155.44	-27.08	-13.52	71.38	58.41	12.97	5.502	
2,000.00	1,997.53	2,004.43	2,001.41	6.89	6.88	154.51	-30.59	-7.49	73.16	59.47	13.69	5.345	
2,100.00	2,097.23	2,104.40	2,101.15	7.26	7.24	153.62	-34.10	-1.46	74.95	60.54	14.40	5.203	
2,200.00	2,196.92	2,204.38	2,200.88	7.62	7.60	152.78	-37.61	4.56	76.76	61.63	15.12	5.075	
2,300.00	2,296.61	2,304.36	2,300.62	7.99	7.96	151.98	-41.12	10.59	78.58	62.74	15.84	4.960	
2,400.00	2,396.30	2,404.34	2,400.35	8.36	8.33	151.21	-44.63	16.61	80.42	63.85	16.57	4.854	
2,500.00	2,495.99	2,504.31	2,500.08	8.73	8.69	150.48	-48.14	22.64	82.27	64.98	17.29	4.758	
2,600.00	2,595.68	2,604.29	2,599.82	9.09	9.06	149.78	-51.65	28.67	84.14	66.12	18.02	4.670	
2,700.00	2,695.38	2,704.27	2,699.55	9.46	9.42	149.11	-55.16	34.69	86.02	67.27	18.74	4.589	
2,750.00	2,745.22	2,754.33	2,749.49	9.65	9.61	148.78	-56.92	37.71	86.96	67.85	19.11	4.551	
2,800.00	2,795.04	2,805.12	2,800.12	9.83	9.79	148.38	-58.90	41.12	87.92	68.45	19.47	4.516	
2,900.00	2,894.49	2,906.69	2,901.21	10.21	10.17	147.33	-63.88	49.66	90.15	69.96	20.19	4.465	
3,000.00	2,993.63	3,008.25	3,001.98	10.59	10.56	145.98	-70.20	60.53	92.84	71.92	20.92	4.438 SF	
3,100.00	3,092.40	3,108.29	3,101.05	10.99	10.94	144.91	-77.20	72.54	96.72	75.09	21.64	4.470	
3,116.50	3,108.65	3,124.76	3,117.37	11.05	11.01	144.83	-78.36	74.52	97.57	75.82	21.75	4.485	
3,200.00	3,190.89	3,208.14	3,199.94	11.39	11.33	144.51	-84.19	84.55	102.01	79.62	22.39	4.556	
3,300.00	3,289.37	3,308.00	3,298.82	11.79	11.72	144.17	-91.18	96.55	107.34	84.19	23.15	4.636	
3,400.00	3,387.85	3,407.86	3,397.71	12.20	12.11	143.86	-98.17	108.55	112.67	88.75	23.92	4.710	
3,500.00	3,486.33	3,507.71	3,496.59	12.60	12.50	143.58	-105.16	120.55	118.00	93.31	24.69	4.780	
3,600.00	3,584.81	3,607.57	3,595.48	13.01	12.89	143.33	-112.15	132.55	123.33	97.88	25.46	4.844	
3,700.00	3,683.29	3,707.42	3,694.36	13.42	13.29	143.09	-119.15	144.56	128.67	102.44	26.23	4.905	
3,800.00	3,781.77	3,805.51	3,791.61	13.84	13.67	143.17	-125.58	155.60	134.56	107.57	26.99	4.985	
3,900.00	3,880.26	3,903.00	3,888.56	14.25	14.04	144.02	-130.74	164.47	142.02	114.29	27.73	5.121	
4,000.00	3,978.74	4,000.00	3,985.25	14.67	14.41	145.51	-134.64	171.16	151.16	122.71	28.45	5.313	
4,100.00	4,077.22	4,096.73	4,081.83	15.08	14.76	147.48	-137.30	175.73	162.09	132.93	29.15	5.560	
4,200.00	4,175.70	4,192.73	4,177.78	15.50	15.10	149.76	-138.72	178.16	174.95	145.11	29.83	5.865	
4,300.00	4,274.18	4,289.13	4,274.18	15.92	15.43	152.22	-138.99	178.63	189.78	159.28	30.49	6.224	
4,400.00	4,372.66	4,387.61	4,372.66	16.34	15.75	154.47	-138.99	178.63	205.34	174.19	31.16	6.591	
4,500.00	4,471.15	4,486.09	4,471.15	16.76	16.08	156.40	-138.99	178.63	221.18	189.35	31.83	6.949	
4,600.00	4,569.63	4,584.58	4,569.63	17.18	16.41	158.08	-138.99	178.63	237.22	204.72	32.50	7.298	
4,700.00	4,668.11	4,683.06	4,668.11	17.60	16.74	159.54	-138.99	178.63	253.44	220.26	33.18	7.637	
4,800.00	4,766.59	4,781.54	4,766.59	18.02	17.07	160.83	-138.99	178.63	269.80	235.94	33.87	7.966	
4,830.79	4,796.91	4,811.86	4,796.91	18.15	17.17	161.19	-138.99	178.63	274.87	240.79	34.08	8.065	
4,900.00	4,865.18	4,880.13	4,865.18	18.44	17.40	161.98	-138.99	178.63	285.69	251.09	34.60	8.256	
5,000.00	4,964.15	4,979.10	4,964.15	18.85	17.74	162.89	-138.99	178.63	299.32	263.97	35.35	8.467	
5,100.00	5,063.46	5,078.41	5,063.46	19.24	18.07	163.57	-138.99	178.63	310.51	274.43	36.08	8.606	
5,200.00	5,163.05	5,177.99	5,163.05	19.62	18.41	164.06	-138.99	178.63	319.24	282.45	36.79	8.678	
5,300.00	5,262.83	5,277.78	5,262.83	19.99	18.75	164.40	-138.99	178.63	325.46	287.99	37.48	8.685	
5,400.00	5,362.76	5,377.70	5,362.76	20.34	19.09	164.60	-138.99	178.63	329.18	291.04	38.14	8.631	
5,497.28	5,460.03	5,474.98	5,460.03	20.66	19.42	-90.17	-138.99	178.63	330.37	291.61	38.76	8.523	
5,500.00	5,462.75	5,477.69	5,462.75	20.67	19.43	-90.17	-138.99	178.63	330.37	291.59	38.78	8.519	
5,600.00	5,562.75	5,577.69	5,562.75	20.99	19.77	-90.17	-138.99	178.63	330.37	290.91	39.46	8.373	
5,700.00	5,662.75	5,677.69	5,662.75	21.31	20.12	-90.17	-138.99	178.63	330.37	290.23	40.14	8.231	
5,800.00	5,762.75	5,777.69	5,762.75	21.64	20.46	-90.17	-138.99	178.63	330.37	289.55	40.82	8.094	
5,900.00	5,862.75	5,877.69	5,862.75	21.96	20.80	-90.17	-138.99	178.63	330.37	288.87	41.50	7.961	
6,000.00	5,962.75	5,977.69	5,962.75	22.29	21.15	-90.17	-138.99	178.63	330.37	288.19	42.18	7.832	
6,100.00	6,062.75	6,077.69	6,062.75	22.61	21.49	-90.17	-138.99	178.63	330.37	287.50	42.87	7.707	
6,200.00	6,162.75	6,177.69	6,162.75	22.94	21.84	-90.17	-138.99	178.63	330.37	286.82	43.55	7.585	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



## Phoenix Technology Services

## Anticollision Report



Company: Matador Resources  
 Project: Eddy County, NM (NAD27 NME)  
 Reference Site: Charlie Sweeney Federal 31-23S-28E  
 Site Error: 0.00 usft  
 Reference Well: 227H  
 Well Error: 0.00 usft  
 Reference Wellbore: OH  
 Reference Design: Preliminary Plan 1

Local Co-ordinate Reference: Well 227H  
 TVD Reference: RKB @ 3134.50usft (Patterson 297)  
 MD Reference: RKB @ 3134.50usft (Patterson 297)  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature  
 Output errors are at: 2.00 sigma  
 Database: Compass 5000 GCR  
 Offset TVD Reference: Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 123H - OH - Preliminary Plan 1												Offset Site Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM												Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
6,300.00	6,262.75	6,277.69	6,262.75	23.27	22.18	-90.17	-138.99	178.63	330.37	286.13	44.24	7.468	
6,400.00	6,362.75	6,377.69	6,362.75	23.60	22.53	-90.17	-138.99	178.63	330.37	285.44	44.93	7.354	
6,500.00	6,462.75	6,477.69	6,462.75	23.93	22.88	-90.17	-138.99	178.63	330.37	284.76	45.61	7.243	
6,600.00	6,562.75	6,577.69	6,562.75	24.26	23.22	-90.17	-138.99	178.63	330.37	284.07	46.30	7.135	
6,700.00	6,662.75	6,677.69	6,662.75	24.59	23.57	-90.17	-138.99	178.63	330.37	283.38	46.99	7.030	
6,800.00	6,762.75	6,777.69	6,762.75	24.92	23.92	-90.17	-138.99	178.63	330.37	282.69	47.68	6.928	
6,900.00	6,862.75	6,877.69	6,862.75	25.26	24.26	-90.17	-138.99	178.63	330.37	282.00	48.38	6.829	
7,000.00	6,962.75	6,977.69	6,962.75	25.59	24.61	-90.17	-138.99	178.63	330.37	281.30	49.07	6.733	
7,100.00	7,062.75	7,077.69	7,062.75	25.93	24.96	-90.17	-138.99	178.63	330.37	280.61	49.76	6.639	
7,200.00	7,162.75	7,177.69	7,162.75	26.26	25.31	-90.17	-138.99	178.63	330.37	279.92	50.45	6.548	
7,300.00	7,262.75	7,277.69	7,262.75	26.60	25.66	-90.17	-138.99	178.63	330.37	279.22	51.15	6.459	
7,400.00	7,362.75	7,377.88	7,362.91	26.93	26.01	-89.99	-137.93	178.64	330.36	278.52	51.84	6.373	
7,431.03	7,393.78	7,408.87	7,393.78	27.04	26.11	-89.52	-135.21	178.66	330.35	278.30	52.05	6.347	
7,500.00	7,462.75	7,476.14	7,460.00	27.27	26.34	-87.50	-123.59	178.76	330.57	278.09	52.48	6.299	
7,600.00	7,562.75	7,567.08	7,546.46	27.61	26.62	-82.70	-95.72	179.00	333.10	280.04	53.06	6.278	
7,700.00	7,662.75	7,650.00	7,620.57	27.95	26.85	-76.47	-58.69	179.31	341.71	288.10	53.61	6.374	
7,800.00	7,762.75	7,716.70	7,675.81	28.28	27.01	-70.50	-21.38	179.62	360.06	305.92	54.14	6.650	
7,900.00	7,862.75	7,775.10	7,720.34	28.62	27.14	-64.87	16.37	179.94	390.37	335.70	54.67	7.141	
8,000.00	7,962.75	7,824.15	7,754.60	28.96	27.23	-60.05	51.44	180.24	432.77	377.60	55.18	7.843	
8,100.00	8,062.75	7,865.34	7,780.98	29.30	27.31	-56.06	83.07	180.51	485.97	430.31	55.67	8.730	
8,200.00	8,162.75	7,900.00	7,801.37	29.64	27.37	-52.81	111.09	180.74	548.08	491.95	56.13	9.764	
8,300.00	8,262.75	7,929.60	7,817.41	29.98	27.44	-50.13	135.97	180.96	617.25	560.66	56.58	10.909	
8,400.00	8,362.75	7,950.00	7,827.70	30.32	27.49	-48.36	153.57	181.10	691.95	634.95	57.00	12.140	
8,500.00	8,462.75	7,976.60	7,840.18	30.67	27.57	-46.13	177.06	181.30	770.87	713.43	57.43	13.422	
8,600.00	8,562.75	8,000.00	7,850.24	31.01	27.63	-44.25	198.19	181.48	853.20	795.35	57.85	14.748	
8,700.00	8,662.75	8,000.00	7,850.24	31.35	27.63	-44.25	198.19	181.48	938.33	880.12	58.20	16.122	
8,800.00	8,762.75	8,026.60	7,860.62	31.69	27.71	-42.22	222.67	181.69	1,025.21	966.59	58.62	17.489	
8,900.00	8,862.75	8,050.00	7,868.80	32.04	27.78	-40.53	244.59	181.87	1,114.14	1,055.10	59.04	18.871	
9,000.00	8,962.75	8,050.00	7,868.80	32.38	27.78	-40.53	244.59	181.87	1,204.20	1,144.82	59.39	20.277	
9,100.00	9,062.75	8,050.00	7,868.80	32.72	27.78	-40.53	244.59	181.87	1,295.72	1,235.98	59.74	21.691	
9,200.00	9,162.75	8,070.64	7,875.27	33.07	27.85	-39.11	264.19	182.04	1,387.89	1,327.76	60.14	23.079	
9,300.00	9,262.75	8,079.05	7,877.71	33.41	27.87	-38.55	272.25	182.11	1,481.05	1,420.54	60.51	24.478	
9,400.00	9,362.75	8,100.00	7,883.25	33.76	27.94	-37.20	292.44	182.28	1,575.10	1,514.20	60.90	25.862	
9,500.00	9,462.75	8,100.00	7,883.25	34.10	27.94	-37.20	292.44	182.28	1,669.38	1,608.13	61.25	27.254	
9,600.00	9,562.75	8,100.00	7,883.25	34.45	27.94	-37.20	292.44	182.28	1,764.30	1,702.69	61.60	28.640	
9,700.00	9,662.75	8,100.00	7,883.25	34.79	27.94	-37.20	292.44	182.28	1,859.74	1,797.79	61.95	30.019	
9,751.28	9,714.03	8,100.00	7,883.25	34.97	27.94	-37.20	292.44	182.28	1,908.87	1,846.74	62.13	30.723	
9,800.00	9,762.69	8,100.00	7,883.25	35.14	27.94	-29.51	292.44	182.28	1,955.14	1,893.03	62.11	31.480	
9,850.00	9,812.26	8,100.00	7,883.25	35.30	27.94	-23.95	292.44	182.28	2,001.48	1,939.77	61.71	32.432	
9,900.00	9,861.08	8,120.49	7,887.95	35.47	28.00	-19.74	312.38	182.45	2,045.95	1,985.02	60.93	33.578	
9,950.00	9,908.79	8,125.86	7,889.07	35.62	28.02	-17.00	317.64	182.49	2,088.96	2,029.24	59.71	34.982	
10,000.00	9,955.01	8,150.00	7,893.47	35.77	28.10	-14.79	341.37	182.69	2,130.35	2,072.23	58.12	36.656	
10,050.00	9,999.40	8,150.00	7,893.47	35.90	28.10	-13.31	341.37	182.69	2,168.97	2,112.85	56.12	38.651	
10,100.00	10,041.61	8,150.00	7,893.47	36.02	28.10	-12.15	341.37	182.69	2,205.29	2,151.53	53.76	41.019	
10,150.00	10,081.34	8,150.00	7,893.47	36.13	28.10	-11.21	341.37	182.69	2,239.15	2,188.06	51.09	43.831	
10,200.00	10,118.26	8,150.00	7,893.47	36.23	28.10	-10.46	341.37	182.69	2,270.40	2,222.28	48.13	47.177	
10,250.00	10,152.11	8,150.00	7,893.47	36.31	28.10	-9.85	341.37	182.69	2,298.93	2,254.00	44.93	51.166	
10,300.00	10,182.63	8,177.86	7,897.30	36.38	28.19	-9.29	368.96	182.93	2,323.78	2,282.17	41.60	55.858	
10,350.00	10,209.58	8,200.00	7,899.39	36.43	28.27	-8.86	391.00	183.11	2,346.09	2,307.91	38.18	61.456	
10,400.00	10,232.76	8,200.00	7,899.39	36.48	28.27	-8.55	391.00	183.11	2,364.83	2,330.11	34.72	68.121	
10,450.00	10,251.99	8,200.00	7,899.39	36.52	28.27	-8.31	391.00	183.11	2,380.44	2,349.06	31.38	75.852	
10,500.00	10,267.13	8,200.00	7,899.39	36.56	28.27	-8.13	391.00	183.11	2,392.88	2,364.54	28.35	84.408	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Phoenix Technology Services

## Anticollision Report



**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Reference Site:** Charlie Sweeney Federal 31-23S-28E  
**Site Error:** 0.00 usft  
**Reference Well:** 227H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at** 2.00 sigma  
**Database:** Compass 5000 GCR  
**Offset TVD Reference:** Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 123H - OH - Preliminary Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
10,501.28	10,267.46	8,200.00	7,899.39	36.56	28.27	-8.12	391.00	183.11	2,393.16	2,364.88	28.28	84.633		
10,550.00	10,278.87	8,224.13	7,900.69	36.64	28.35	-8.03	415.09	183.32	2,402.29	2,375.45	26.84	89.508		
10,600.00	10,289.04	8,242.99	7,901.00	36.76	28.41	-7.95	433.95	183.48	2,410.27	2,384.67	25.60	94.153		
10,650.00	10,294.64	8,244.54	7,901.00	36.89	28.42	-7.90	435.50	183.49	2,416.32	2,391.70	24.62	98.142		
10,700.00	10,298.63	8,294.38	7,901.00	37.04	28.60	-7.85	485.33	183.91	2,420.27	2,396.12	24.16	100.189		
10,751.29	10,300.00	8,345.64	7,901.00	37.20	28.81	-7.84	536.59	184.34	2,421.64	2,397.51	24.13	100.376		
10,800.00	10,300.00	8,394.35	7,901.00	37.37	29.01	-7.84	585.30	184.76	2,421.64	2,397.20	24.43	99.119		
10,900.00	10,300.00	8,494.35	7,901.00	37.74	29.48	-7.84	685.30	185.60	2,421.63	2,396.50	25.14	96.345		
11,000.00	10,300.00	8,594.35	7,901.00	38.16	30.02	-7.84	785.30	186.45	2,421.63	2,395.71	25.92	93.429		
11,100.00	10,300.00	8,694.35	7,901.00	38.63	30.61	-7.84	885.29	187.29	2,421.63	2,394.86	26.78	90.436		
11,200.00	10,300.00	8,794.35	7,901.00	39.15	31.27	-7.84	985.29	188.14	2,421.63	2,393.93	27.70	87.422		
11,300.00	10,300.00	8,894.35	7,901.00	39.71	31.97	-7.84	1,085.29	188.98	2,421.63	2,392.95	28.68	84.428		
11,400.00	10,300.00	8,994.35	7,901.00	40.32	32.72	-7.84	1,185.28	189.83	2,421.63	2,391.91	29.72	81.486		
11,500.00	10,300.00	9,094.35	7,901.00	40.97	33.52	-7.84	1,285.28	190.68	2,421.63	2,390.83	30.80	78.622		
11,600.00	10,300.00	9,194.35	7,901.00	41.65	34.36	-7.84	1,385.28	191.52	2,421.63	2,389.70	31.93	75.850		
11,700.00	10,300.00	9,294.35	7,901.00	42.38	35.24	-7.84	1,485.27	192.37	2,421.63	2,388.54	33.09	73.183		
11,800.00	10,300.00	9,394.35	7,901.00	43.14	36.16	-7.84	1,585.27	193.21	2,421.63	2,387.34	34.29	70.626		
11,900.00	10,300.00	9,494.35	7,901.00	43.94	37.11	-7.84	1,685.26	194.06	2,421.62	2,386.11	35.52	68.182		
12,000.00	10,300.00	9,594.35	7,901.00	44.77	38.10	-7.84	1,785.26	194.90	2,421.62	2,384.85	36.77	65.852		
12,100.00	10,300.00	9,694.35	7,901.00	45.63	39.11	-7.84	1,885.26	195.75	2,421.62	2,383.57	38.06	63.634		
12,200.00	10,300.00	9,794.35	7,901.00	46.52	40.15	-7.84	1,985.25	196.59	2,421.62	2,382.26	39.36	61.524		
12,300.00	10,300.00	9,894.35	7,901.00	47.43	41.21	-7.84	2,085.25	197.44	2,421.62	2,380.93	40.69	59.520		
12,400.00	10,300.00	9,994.35	7,901.00	48.38	42.30	-7.84	2,185.25	198.29	2,421.62	2,379.59	42.03	57.616		
12,500.00	10,300.00	10,094.35	7,901.00	49.34	43.41	-7.84	2,285.24	199.13	2,421.62	2,378.23	43.39	55.808		
12,600.00	10,300.00	10,194.35	7,901.00	50.33	44.54	-7.84	2,385.24	199.98	2,421.62	2,376.85	44.77	54.092		
12,700.00	10,300.00	10,294.35	7,901.00	51.35	45.69	-7.84	2,485.24	200.82	2,421.62	2,375.46	46.16	52.462		
12,800.00	10,300.00	10,394.35	7,901.00	52.38	46.85	-7.84	2,585.23	201.67	2,421.61	2,374.05	47.56	50.913		
12,900.00	10,300.00	10,494.35	7,901.00	53.43	48.03	-7.84	2,685.23	202.51	2,421.61	2,372.63	48.98	49.441		
13,000.00	10,300.00	10,594.35	7,901.00	54.50	49.22	-7.84	2,785.23	203.36	2,421.61	2,371.21	50.41	48.041		
13,100.00	10,300.00	10,694.35	7,901.00	55.59	50.43	-7.84	2,885.22	204.21	2,421.61	2,369.77	51.84	46.710		
13,200.00	10,300.00	10,794.35	7,901.00	56.70	51.65	-7.84	2,985.22	205.05	2,421.61	2,368.32	53.29	45.442		
13,300.00	10,300.00	10,894.35	7,901.00	57.82	52.88	-7.84	3,085.21	205.90	2,421.61	2,366.86	54.75	44.234		
13,400.00	10,300.00	10,994.35	7,901.00	58.95	54.13	-7.83	3,185.21	206.74	2,421.61	2,365.40	56.21	43.083		
13,500.00	10,300.00	11,094.35	7,901.00	60.10	55.38	-7.83	3,285.21	207.59	2,421.61	2,363.93	57.68	41.985		
13,600.00	10,300.00	11,194.35	7,901.00	61.26	56.64	-7.83	3,385.20	208.43	2,421.61	2,362.45	59.16	40.936		
13,700.00	10,300.00	11,294.35	7,901.00	62.43	57.91	-7.83	3,485.20	209.28	2,421.61	2,360.97	60.64	39.935		
13,800.00	10,300.00	11,394.35	7,901.00	63.62	59.20	-7.83	3,585.20	210.13	2,421.60	2,359.48	62.13	38.978		
13,900.00	10,300.00	11,494.35	7,901.00	64.81	60.48	-7.83	3,685.19	210.97	2,421.60	2,357.98	63.62	38.062		
14,000.00	10,300.00	11,594.35	7,901.00	66.02	61.78	-7.83	3,785.19	211.82	2,421.60	2,356.48	65.12	37.185		
14,100.00	10,300.00	11,694.35	7,901.00	67.24	63.08	-7.83	3,885.19	212.66	2,421.60	2,354.97	66.63	36.346		
14,200.00	10,300.00	11,794.35	7,901.00	68.46	64.39	-7.83	3,985.18	213.51	2,421.60	2,353.46	68.14	35.541		
14,300.00	10,300.00	11,894.35	7,901.00	69.69	65.70	-7.83	4,085.18	214.35	2,421.60	2,351.95	69.65	34.769		
14,400.00	10,300.00	11,994.35	7,901.00	70.94	67.02	-7.83	4,185.18	215.20	2,421.60	2,350.43	71.17	34.027		
14,500.00	10,300.00	12,094.35	7,901.00	72.19	68.35	-7.83	4,285.17	216.05	2,421.60	2,348.91	72.69	33.315		
14,600.00	10,300.00	12,194.35	7,901.00	73.44	69.68	-7.83	4,385.17	216.89	2,421.60	2,347.38	74.21	32.631		
14,700.00	10,300.00	12,294.35	7,901.00	74.71	71.02	-7.83	4,485.16	217.74	2,421.59	2,345.86	75.74	31.973		
14,800.00	10,300.00	12,394.35	7,901.00	75.98	72.36	-7.83	4,585.16	218.58	2,421.59	2,344.32	77.27	31.340		
14,900.00	10,300.00	12,494.35	7,901.00	77.26	73.70	-7.83	4,685.16	219.43	2,421.59	2,342.79	78.80	30.730		
15,000.00	10,300.00	12,594.35	7,901.00	78.54	75.05	-7.83	4,785.15	220.27	2,421.59	2,341.25	80.34	30.142		
15,063.50	10,300.00	12,657.85	7,901.00	79.36	75.91	-7.83	4,848.65	220.81	2,421.59	2,340.27	81.32	29.780		
15,087.64	10,300.00	12,680.20	7,901.00	79.67	76.21	-7.83	4,871.00	221.00	2,421.59	2,339.92	81.67	29.650		



# Phoenix Technology Services

## Anticollision Report



**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Reference Site:** Charlie Sweeney Federal 31-23S-28E  
**Site Error:** 0.00 usft  
**Reference Well:** 227H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at** 2.00 sigma  
**Database:** Compass 5000 GCR  
**Offset TVD Reference:** Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 203H - OH - Preliminary Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance							
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
0.00	0.00	1.00	0.00	0.00	0.00	-90.00	0.00	-90.00	90.00					
100.00	100.00	101.00	100.00	0.13	0.13	-90.00	0.00	-90.00	90.00	89.74	0.26	341.586		
200.00	200.00	201.00	200.00	0.49	0.49	-90.00	0.00	-90.00	90.00	89.02	0.98	91.797		
300.00	300.00	301.00	300.00	0.85	0.85	-90.00	0.00	-90.00	90.00	88.30	1.70	53.023		
400.00	400.00	401.00	400.00	1.21	1.21	-90.00	0.00	-90.00	90.00	87.59	2.41	37.278		
500.00	500.00	501.00	500.00	1.56	1.57	-90.00	0.00	-90.00	90.00	86.87	3.13	28.743		
600.00	600.00	601.00	600.00	1.92	1.93	-90.00	0.00	-90.00	90.00	86.15	3.85	23.388		
700.00	700.00	701.00	700.00	2.28	2.28	-90.00	0.00	-90.00	90.00	85.43	4.57	19.715		
800.00	800.00	801.00	800.00	2.64	2.64	-90.00	0.00	-90.00	90.00	84.72	5.28	17.039		
900.00	900.00	901.00	900.00	3.00	3.00	-90.00	0.00	-90.00	90.00	84.00	6.00	15.002		
1,000.00	1,000.00	1,001.01	1,000.01	3.36	3.36	-90.00	0.00	-90.00	90.00	83.28	6.72	13.401		
1,000.89	1,000.89	1,001.91	1,000.91	3.36	3.36	164.83	0.00	-90.00	90.00	83.28	6.72	13.389 CC		
1,100.00	1,099.99	1,102.07	1,101.05	3.70	3.70	164.28	-1.22	-89.39	90.66	83.26	7.41	12.240 ES		
1,200.00	1,199.91	1,203.05	1,201.95	4.04	4.04	162.69	-4.82	-87.58	92.72	84.64	8.07	11.483		
1,300.00	1,299.69	1,303.54	1,302.23	4.39	4.38	160.33	-10.62	-84.67	96.37	87.62	8.75	11.019		
1,400.00	1,399.38	1,403.35	1,401.80	4.74	4.72	158.16	-16.84	-81.55	101.19	91.76	9.43	10.731		
1,500.00	1,499.08	1,503.17	1,501.37	5.09	5.06	156.20	-23.07	-78.43	106.15	96.03	10.12	10.486		
1,600.00	1,598.77	1,602.98	1,600.94	5.45	5.41	154.41	-29.29	-75.30	111.23	100.41	10.82	10.278		
1,700.00	1,698.46	1,702.80	1,700.52	5.81	5.76	152.78	-35.52	-72.18	116.40	104.87	11.53	10.098		
1,800.00	1,798.15	1,802.61	1,800.09	6.17	6.11	151.29	-41.75	-69.05	121.66	109.42	12.24	9.943		
1,900.00	1,897.84	1,902.42	1,899.66	6.53	6.47	149.92	-47.97	-65.93	126.99	114.04	12.95	9.808		
2,000.00	1,997.53	2,002.24	1,999.23	6.89	6.83	148.67	-54.20	-62.81	132.39	118.73	13.66	9.689		
2,100.00	2,097.23	2,102.05	2,098.80	7.26	7.19	147.51	-60.42	-59.68	137.85	123.47	14.38	9.585		
2,200.00	2,196.92	2,201.86	2,198.37	7.62	7.55	146.44	-66.65	-56.56	143.36	128.26	15.10	9.492		
2,300.00	2,296.61	2,301.68	2,297.94	7.99	7.91	145.45	-72.88	-53.43	148.91	133.09	15.83	9.409		
2,400.00	2,396.30	2,401.49	2,397.51	8.36	8.27	144.53	-79.10	-50.31	154.51	137.96	16.55	9.335		
2,500.00	2,495.99	2,501.31	2,497.08	8.73	8.63	143.68	-85.33	-47.19	160.15	142.87	17.28	9.269		
2,600.00	2,595.68	2,601.12	2,596.65	9.09	9.00	142.88	-91.55	-44.06	165.81	147.81	18.00	9.209		
2,700.00	2,695.38	2,700.93	2,696.22	9.46	9.36	142.14	-97.78	-40.94	171.51	152.77	18.73	9.155		
2,750.00	2,745.22	2,750.84	2,746.00	9.65	9.54	141.79	-100.69	-39.38	174.37	155.27	19.10	9.130		
2,800.00	2,795.04	2,800.73	2,795.78	9.83	9.73	141.48	-104.01	-37.81	177.49	158.03	19.46	9.123		
2,900.00	2,894.49	2,900.43	2,895.23	10.21	10.09	141.27	-110.22	-34.69	185.27	165.10	20.16	9.188		
3,000.00	2,993.63	2,999.93	2,994.49	10.59	10.46	141.53	-116.43	-31.58	195.08	174.22	20.87	9.349		
3,100.00	3,092.40	3,099.19	3,093.50	10.99	10.82	142.19	-122.62	-28.47	206.96	185.40	21.56	9.600		
3,116.50	3,108.65	3,115.53	3,109.81	11.05	10.88	142.34	-123.64	-27.96	209.12	187.45	21.67	9.649		
3,200.00	3,190.89	3,198.24	3,192.32	11.39	11.18	143.13	-128.80	-25.37	220.22	197.93	22.29	9.882		
3,300.00	3,289.37	3,296.89	3,290.75	11.79	11.54	144.10	-134.53	-22.50	233.61	210.60	23.02	10.149		
3,400.00	3,387.85	3,395.01	3,388.79	12.20	11.90	145.50	-138.14	-20.69	247.37	223.63	23.74	10.421		
3,500.00	3,486.33	3,492.69	3,486.45	12.60	12.24	147.29	-139.50	-20.01	261.67	237.23	24.44	10.707		
3,600.00	3,584.81	3,591.05	3,584.81	13.01	12.57	149.22	-139.51	-20.00	276.50	251.37	25.13	11.003		
3,700.00	3,683.29	3,689.53	3,683.29	13.42	12.90	150.96	-139.51	-20.00	291.60	265.78	25.82	11.293		
3,800.00	3,781.77	3,788.01	3,781.77	13.84	13.23	152.53	-139.51	-20.00	306.95	280.44	26.51	11.577		
3,900.00	3,880.26	3,886.49	3,880.26	14.25	13.56	153.95	-139.51	-20.00	322.50	295.29	27.21	11.853		
4,000.00	3,978.74	3,984.97	3,978.74	14.67	13.90	155.24	-139.51	-20.00	338.22	310.32	27.90	12.121		
4,100.00	4,077.22	4,083.46	4,077.22	15.08	14.23	156.41	-139.51	-20.00	354.10	325.50	28.60	12.381		
4,200.00	4,175.70	4,181.94	4,175.70	15.50	14.57	157.49	-139.51	-20.00	370.12	340.82	29.30	12.632		
4,300.00	4,274.18	4,280.42	4,274.18	15.92	14.91	158.47	-139.51	-20.00	386.24	356.25	30.00	12.875		
4,400.00	4,372.66	4,378.90	4,372.66	16.34	15.24	159.38	-139.51	-20.00	402.48	371.78	30.70	13.110		
4,500.00	4,471.15	4,477.38	4,471.15	16.76	15.58	160.21	-139.51	-20.00	418.80	387.39	31.40	13.336		
4,600.00	4,569.63	4,575.86	4,569.63	17.18	15.92	160.98	-139.51	-20.00	435.20	403.09	32.11	13.555		
4,700.00	4,668.11	4,674.34	4,668.11	17.60	16.26	161.70	-139.51	-20.00	451.67	418.86	32.81	13.766		
4,800.00	4,766.59	4,772.83	4,766.59	18.02	16.60	162.37	-139.51	-20.00	468.21	434.69	33.52	13.969		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Phoenix Technology Services

## Anticollision Report



Company: Matador Resources  
 Project: Eddy County, NM (NAD27 NME)  
 Reference Site: Charlie Sweeney Federal 31-23S-28E  
 Site Error: 0.00 usft  
 Reference Well: 227H  
 Well Error: 0.00 usft  
 Reference Wellbore: OH  
 Reference Design: Preliminary Plan 1

Local Co-ordinate Reference: Well 227H  
 TVD Reference: RKB @ 3134.50usft (Patterson 297)  
 MD Reference: RKB @ 3134.50usft (Patterson 297)  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature  
 Output errors are at: 2.00 sigma  
 Database: Compass 5000 GCR  
 Offset TVD Reference: Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 203H - OH - Preliminary Plan 1													Offset Site Error: 0.00 usft
Survey Program: 0-PHX+MWD+HDGM													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
4,830.79	4,796.91	4,803.15	4,796.91	18.15	16.70	162.56	-139.51	-20.00	473.31	439.58	33.73	14.031	
4,900.00	4,865.18	4,871.41	4,865.18	18.44	16.94	163.01	-139.51	-20.00	484.21	449.93	34.28	14.125	
5,000.00	4,964.15	4,970.39	4,964.15	18.85	17.28	163.55	-139.51	-20.00	497.90	462.84	35.06	14.203	
5,100.00	5,063.46	5,069.70	5,063.46	19.24	17.63	163.97	-139.51	-20.00	509.12	473.31	35.81	14.217	
5,200.00	5,163.05	5,169.28	5,163.05	19.62	17.97	164.28	-139.51	-20.00	517.86	481.32	36.54	14.171	
5,300.00	5,262.83	5,269.07	5,262.83	19.99	18.32	164.50	-139.51	-20.00	524.09	486.84	37.25	14.068	
5,400.00	5,362.76	5,368.99	5,362.76	20.34	18.67	164.63	-139.51	-20.00	527.81	489.87	37.94	13.912	
5,497.28	5,460.03	5,466.27	5,460.03	20.66	19.01	-90.16	-139.51	-20.00	529.00	490.42	38.58	13.712	
5,500.00	5,462.75	5,468.98	5,462.75	20.67	19.02	-90.16	-139.51	-20.00	529.00	490.41	38.60	13.706	
5,600.00	5,562.75	5,568.98	5,562.75	20.99	19.36	-90.16	-139.51	-20.00	529.00	489.72	39.28	13.468	
5,700.00	5,662.75	5,668.98	5,662.75	21.31	19.71	-90.16	-139.51	-20.00	529.00	489.04	39.96	13.237	
5,800.00	5,762.75	5,768.98	5,762.75	21.64	20.06	-90.16	-139.51	-20.00	529.00	488.35	40.65	13.014	
5,900.00	5,862.75	5,868.98	5,862.75	21.96	20.41	-90.16	-139.51	-20.00	529.00	487.67	41.33	12.798	
6,000.00	5,962.75	5,968.98	5,962.75	22.29	20.76	-90.16	-139.51	-20.00	529.00	486.98	42.02	12.589	
6,100.00	6,062.75	6,068.98	6,062.75	22.61	21.11	-90.16	-139.51	-20.00	529.00	486.29	42.71	12.387	
6,200.00	6,162.75	6,168.98	6,162.75	22.94	21.46	-90.16	-139.51	-20.00	529.00	485.61	43.40	12.190	
6,300.00	6,262.75	6,268.98	6,262.75	23.27	21.81	-90.16	-139.51	-20.00	529.00	484.92	44.09	11.999	
6,400.00	6,362.75	6,368.98	6,362.75	23.60	22.17	-90.16	-139.51	-20.00	529.00	484.23	44.78	11.814	
6,500.00	6,462.75	6,468.98	6,462.75	23.93	22.52	-90.16	-139.51	-20.00	529.00	483.53	45.47	11.635	
6,600.00	6,562.75	6,568.98	6,562.75	24.26	22.87	-90.16	-139.51	-20.00	529.00	482.84	46.16	11.460	
6,700.00	6,662.75	6,668.98	6,662.75	24.59	23.22	-90.16	-139.51	-20.00	529.00	482.15	46.85	11.291	
6,800.00	6,762.75	6,768.98	6,762.75	24.92	23.57	-90.16	-139.51	-20.00	529.00	481.46	47.55	11.126	
6,900.00	6,862.75	6,868.98	6,862.75	25.26	23.92	-90.16	-139.51	-20.00	529.00	480.76	48.24	10.966	
7,000.00	6,962.75	6,968.98	6,962.75	25.59	24.28	-90.16	-139.51	-20.00	529.00	480.07	48.93	10.810	
7,100.00	7,062.75	7,068.98	7,062.75	25.93	24.63	-90.16	-139.51	-20.00	529.00	479.37	49.63	10.659	
7,200.00	7,162.75	7,168.98	7,162.75	26.26	24.98	-90.16	-139.51	-20.00	529.00	478.68	50.33	10.511	
7,300.00	7,262.75	7,268.98	7,262.75	26.60	25.34	-90.16	-139.51	-20.00	529.00	477.98	51.02	10.368	
7,400.00	7,362.75	7,368.98	7,362.75	26.93	25.69	-90.16	-139.51	-20.00	529.00	477.28	51.72	10.228	
7,500.00	7,462.75	7,468.98	7,462.75	27.27	26.04	-90.16	-139.51	-20.00	529.00	476.58	52.42	10.092	
7,600.00	7,562.75	7,568.98	7,562.75	27.61	26.40	-90.16	-139.51	-20.00	529.00	475.89	53.12	9.959	
7,700.00	7,662.75	7,668.98	7,662.75	27.95	26.75	-90.16	-139.51	-20.00	529.00	475.19	53.81	9.830	
7,800.00	7,762.75	7,768.98	7,762.75	28.28	27.10	-90.16	-139.51	-20.00	529.00	474.49	54.51	9.704	
7,900.00	7,862.75	7,868.98	7,862.75	28.62	27.46	-90.16	-139.51	-20.00	529.00	473.79	55.21	9.581	
8,000.00	7,962.75	7,968.98	7,962.75	28.96	27.81	-90.16	-139.51	-20.00	529.00	473.09	55.91	9.461	
8,100.00	8,062.75	8,068.98	8,062.75	29.30	28.16	-90.16	-139.51	-20.00	529.00	472.39	56.61	9.344	
8,200.00	8,162.75	8,168.98	8,162.75	29.64	28.52	-90.16	-139.51	-20.00	529.00	471.69	57.31	9.230	
8,300.00	8,262.75	8,268.98	8,262.75	29.98	28.87	-90.16	-139.51	-20.00	529.00	470.99	58.02	9.118	
8,400.00	8,362.75	8,368.98	8,362.75	30.32	29.23	-90.16	-139.51	-20.00	529.00	470.28	58.72	9.009	
8,500.00	8,462.75	8,468.98	8,462.75	30.67	29.58	-90.16	-139.51	-20.00	529.00	469.58	59.42	8.903	
8,600.00	8,562.75	8,568.98	8,562.75	31.01	29.94	-90.16	-139.51	-20.00	529.00	468.88	60.12	8.799	
8,700.00	8,662.75	8,668.98	8,662.75	31.35	30.29	-90.16	-139.51	-20.00	529.00	468.18	60.82	8.697	
8,800.00	8,762.75	8,768.98	8,762.75	31.69	30.64	-90.16	-139.51	-20.00	529.00	467.47	61.53	8.598	
8,900.00	8,862.75	8,868.98	8,862.75	32.04	31.00	-90.16	-139.51	-20.00	529.00	466.77	62.23	8.501	
8,959.50	8,922.25	8,928.48	8,922.25	32.24	31.21	-90.16	-139.51	-20.00	529.00	466.35	62.65	8.444	
9,000.00	8,962.75	8,968.98	8,962.75	32.38	31.35	-90.14	-139.30	-20.03	529.04	466.11	62.93	8.407	
9,100.00	9,062.75	9,053.72	9,048.94	32.72	31.65	-89.19	-130.48	-21.38	530.67	467.10	63.57	8.348	
9,200.00	9,162.75	9,136.10	9,126.68	33.07	31.92	-87.03	-110.29	-24.46	535.40	471.23	64.17	8.344 SF	
9,300.00	9,262.75	9,211.31	9,196.23	33.41	32.15	-84.07	-82.17	-28.75	544.72	479.99	64.73	8.415	
9,400.00	9,362.75	9,278.01	9,254.35	33.76	32.35	-80.78	-49.88	-33.68	560.38	495.12	65.26	8.587	
9,500.00	9,462.75	9,336.08	9,301.56	34.10	32.51	-77.49	-16.50	-38.78	583.79	518.03	65.76	8.878	
9,600.00	9,562.75	9,386.11	9,339.31	34.45	32.65	-74.44	15.93	-43.73	615.73	549.50	66.23	9.296	
9,700.00	9,662.75	9,429.04	9,369.33	34.79	32.77	-71.71	46.26	-48.36	656.28	589.58	66.69	9.840	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Phoenix Technology Services

## Anticollision Report



**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Reference Site:** Charlie Sweeney Federal 31-23S-28E  
**Site Error:** 0.00 usft  
**Reference Well:** 227H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at** 2.00 sigma  
**Database:** Compass 5000 GCR  
**Offset TVD Reference:** Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 203H - OH - Preliminary Plan 1											Offset Site Error: 0.00 usft	
Survey Program: 0-PHX+MWD+HDGM											Offset Well Error: 0.00 usft	
Reference		Offset		Semi Major Axis		Highside Toolface (")	Distance		Minimum Separation (usft)	Separation Factor	Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)				
9,751.28	9,714.03	9,450.00	9,383.13	34.97	32.82	-70.35	61.86	-50.74	680.26	613.33	66.92	10.165
9,800.00	9,762.69	9,466.75	9,393.74	35.14	32.87	-67.23	74.67	-52.70	704.28	637.24	67.04	10.505
9,850.00	9,812.26	9,485.75	9,405.30	35.30	32.92	-63.60	89.57	-54.97	729.22	662.17	67.04	10.877
9,900.00	9,861.08	9,500.00	9,413.64	35.47	32.96	-60.39	100.99	-56.72	754.14	687.28	66.86	11.279
9,950.00	9,908.79	9,524.73	9,427.43	35.62	33.03	-56.99	121.28	-59.81	778.64	712.18	66.46	11.717
10,000.00	9,955.01	9,550.00	9,440.59	35.77	33.10	-53.93	142.61	-63.07	802.58	736.81	65.77	12.202
10,050.00	9,999.40	9,564.73	9,447.82	35.90	33.14	-51.48	155.29	-65.01	825.60	760.80	64.80	12.740
10,100.00	10,041.61	9,585.01	9,457.23	36.02	33.20	-49.15	173.06	-67.72	847.61	784.06	63.54	13.339
10,150.00	10,081.34	9,600.00	9,463.77	36.13	33.24	-47.18	186.38	-69.75	868.43	806.40	62.03	14.000
10,200.00	10,118.26	9,626.04	9,474.29	36.23	33.32	-45.30	209.93	-73.35	887.83	827.55	60.28	14.729
10,250.00	10,152.11	9,650.00	9,483.00	36.31	33.39	-43.72	231.99	-76.71	905.78	847.42	58.36	15.520
10,300.00	10,182.63	9,667.50	9,488.77	36.38	33.44	-42.43	248.32	-79.21	922.12	865.77	56.35	16.364
10,350.00	10,209.58	9,701.27	9,498.46	36.43	33.55	-41.29	280.29	-84.09	936.99	882.67	54.33	17.247
10,400.00	10,232.76	9,701.27	9,498.46	36.48	33.55	-40.43	280.29	-84.09	949.78	897.44	52.34	18.146
10,450.00	10,251.99	9,738.80	9,507.46	36.52	33.66	-39.75	316.31	-89.59	960.51	909.89	50.62	18.975
10,500.00	10,267.13	9,766.07	9,513.10	36.56	33.75	-39.29	342.68	-93.61	969.16	919.98	49.19	19.704
10,501.28	10,267.46	9,766.77	9,513.24	36.56	33.76	-39.28	343.36	-93.72	969.35	920.20	49.15	19.721
10,550.00	10,278.87	9,800.00	9,519.05	36.64	33.87	-39.19	375.71	-98.66	976.28	927.64	48.64	20.070
10,600.00	10,288.04	9,820.65	9,522.08	36.76	33.94	-39.08	395.90	-101.74	982.45	934.25	48.20	20.384
10,650.00	10,294.64	9,850.00	9,525.64	36.89	34.04	-39.08	424.70	-106.13	987.78	939.80	47.98	20.586
10,700.00	10,298.63	9,875.19	9,527.97	37.04	34.14	-39.10	449.49	-109.92	992.23	944.30	47.93	20.704
10,751.29	10,300.00	9,900.00	9,529.63	37.20	34.23	-39.18	473.96	-113.65	995.89	947.84	48.05	20.726
10,800.00	10,300.00	9,929.77	9,530.76	37.37	34.34	-39.43	503.37	-118.14	999.46	951.02	48.44	20.632
10,900.00	10,300.00	10,042.29	9,531.00	37.74	34.82	-40.13	614.89	-132.98	1,008.44	958.83	49.61	20.329
11,000.00	10,300.00	10,194.25	9,531.00	38.16	35.53	-40.61	766.49	-142.70	1,013.14	962.29	50.85	19.925
11,100.00	10,300.00	10,315.84	9,531.00	38.63	36.16	-40.65	888.08	-142.69	1,013.57	961.81	51.76	19.582
11,200.00	10,300.00	10,415.84	9,531.00	39.15	36.73	-40.65	988.08	-141.85	1,013.56	960.93	52.63	19.259
11,300.00	10,300.00	10,515.84	9,531.00	39.71	37.35	-40.65	1,088.08	-141.00	1,013.56	959.98	53.58	18.918
11,400.00	10,300.00	10,615.84	9,531.00	40.32	38.02	-40.65	1,188.07	-140.16	1,013.55	958.95	54.60	18.563
11,500.00	10,300.00	10,715.84	9,531.00	40.97	38.73	-40.65	1,288.07	-139.31	1,013.55	957.86	55.69	18.198
11,600.00	10,300.00	10,815.84	9,531.00	41.65	39.48	-40.65	1,388.06	-138.47	1,013.55	956.69	56.86	17.827
11,700.00	10,300.00	10,915.84	9,531.00	42.38	40.26	-40.65	1,488.06	-137.62	1,013.54	955.46	58.08	17.451
11,800.00	10,300.00	11,015.84	9,531.00	43.14	41.09	-40.65	1,588.06	-136.77	1,013.54	954.18	59.36	17.074
11,900.00	10,300.00	11,115.84	9,531.00	43.94	41.95	-40.65	1,688.05	-135.93	1,013.53	952.83	60.70	16.698
12,000.00	10,300.00	11,215.84	9,531.00	44.77	42.84	-40.65	1,788.05	-135.08	1,013.53	951.44	62.09	16.324
12,100.00	10,300.00	11,315.84	9,531.00	45.63	43.76	-40.65	1,888.05	-134.24	1,013.52	950.00	63.53	15.955
12,200.00	10,300.00	11,415.84	9,531.00	46.52	44.71	-40.65	1,988.04	-133.39	1,013.52	948.51	65.01	15.591
12,300.00	10,300.00	11,515.84	9,531.00	47.43	45.68	-40.65	2,088.04	-132.55	1,013.51	946.98	66.53	15.233
12,400.00	10,300.00	11,615.84	9,531.00	48.38	46.68	-40.65	2,188.04	-131.70	1,013.51	945.41	68.10	14.884
12,500.00	10,300.00	11,715.84	9,531.00	49.34	47.71	-40.65	2,288.03	-130.85	1,013.50	943.81	69.70	14.542
12,600.00	10,300.00	11,815.84	9,531.00	50.33	48.75	-40.65	2,388.03	-130.01	1,013.50	942.17	71.33	14.209
12,700.00	10,300.00	11,915.84	9,531.00	51.35	49.82	-40.64	2,488.03	-129.16	1,013.50	940.50	73.00	13.884
12,800.00	10,300.00	12,015.84	9,531.00	52.38	50.90	-40.64	2,588.02	-128.32	1,013.49	938.80	74.69	13.569
12,900.00	10,300.00	12,115.84	9,531.00	53.43	52.00	-40.64	2,688.02	-127.47	1,013.49	937.07	76.42	13.263
13,000.00	10,300.00	12,215.84	9,531.00	54.50	53.12	-40.64	2,788.01	-126.63	1,013.48	935.32	78.16	12.966
13,100.00	10,300.00	12,315.84	9,531.00	55.59	54.26	-40.64	2,888.01	-125.78	1,013.48	933.54	79.94	12.678
13,200.00	10,300.00	12,415.84	9,531.00	56.70	55.41	-40.64	2,988.01	-124.93	1,013.47	931.74	81.73	12.400
13,300.00	10,300.00	12,515.84	9,531.00	57.82	56.58	-40.64	3,088.00	-124.09	1,013.47	929.92	83.55	12.130
13,400.00	10,300.00	12,615.84	9,531.00	58.95	57.75	-40.64	3,188.00	-123.24	1,013.46	928.07	85.39	11.869
13,500.00	10,300.00	12,715.84	9,531.00	60.10	58.94	-40.64	3,288.00	-122.40	1,013.46	926.21	87.24	11.616
13,600.00	10,300.00	12,815.84	9,531.00	61.26	60.14	-40.64	3,387.99	-121.55	1,013.45	924.34	89.12	11.372
13,700.00	10,300.00	12,915.84	9,531.00	62.43	61.36	-40.64	3,487.99	-120.71	1,013.45	922.44	91.01	11.136

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Phoenix Technology Services

## Anticollision Report



**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Reference Site:** Charlie Sweeney Federal 31-23S-28E  
**Site Error:** 0.00 usft  
**Reference Well:** 227H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at:** 2.00 sigma  
**Database:** Compass 5000 GCR  
**Offset TVD Reference:** Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 203H - OH - Preliminary Plan 1												Offset Site Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM												Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
13,800.00	10,300.00	13,015.84	9,531.00	63.62	62.58	-40.64	3,587.99	-119.86	1,013.45	920.53	92.91	10.908	
13,900.00	10,300.00	13,115.84	9,531.00	64.81	63.81	-40.64	3,687.98	-119.01	1,013.44	918.61	94.83	10.687	
14,000.00	10,300.00	13,215.84	9,531.00	66.02	65.05	-40.64	3,787.98	-118.17	1,013.44	916.67	96.76	10.473	
14,100.00	10,300.00	13,315.84	9,531.00	67.24	66.30	-40.64	3,887.98	-117.32	1,013.43	914.72	98.71	10.267	
14,200.00	10,300.00	13,415.84	9,531.00	68.46	67.56	-40.64	3,987.97	-116.48	1,013.43	912.76	100.67	10.067	
14,300.00	10,300.00	13,515.84	9,531.00	69.69	68.83	-40.64	4,087.97	-115.63	1,013.42	910.79	102.63	9.874	
14,400.00	10,300.00	13,615.84	9,531.00	70.94	70.10	-40.64	4,187.96	-114.79	1,013.42	908.80	104.61	9.687	
14,500.00	10,300.00	13,715.84	9,531.00	72.19	71.38	-40.64	4,287.96	-113.94	1,013.41	906.81	106.60	9.506	
14,600.00	10,300.00	13,815.84	9,531.00	73.44	72.67	-40.64	4,387.96	-113.09	1,013.41	904.81	108.60	9.331	
14,700.00	10,300.00	13,915.84	9,531.00	74.71	73.96	-40.64	4,487.95	-112.25	1,013.40	902.79	110.61	9.162	
14,800.00	10,300.00	14,015.84	9,531.00	75.98	75.26	-40.64	4,587.95	-111.40	1,013.40	900.77	112.63	8.998	
14,900.00	10,300.00	14,115.84	9,531.00	77.26	76.56	-40.64	4,687.95	-110.56	1,013.40	898.74	114.65	8.839	
15,000.00	10,300.00	14,215.84	9,531.00	78.54	77.87	-40.64	4,787.94	-109.71	1,013.39	896.71	116.68	8.685	
15,063.39	10,300.00	14,279.23	9,531.00	79.36	78.70	-40.64	4,851.33	-109.17	1,013.39	895.41	117.98	8.590	
15,087.64	10,300.00	14,300.90	9,531.00	79.67	78.99	-40.64	4,873.00	-108.99	1,013.39	894.95	118.44	8.556	





# Phoenix Technology Services

## Anticollision Report



**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Reference Site:** Charlie Sweeney Federal 31-23S-28E  
**Site Error:** 0.00 usft  
**Reference Well:** 227H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at** 2.00 sigma  
**Database:** Compass 5000 GCR  
**Offset TVD Reference:** Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 207H - OH - Preliminary Plan 1													Offset Site Error:
Survey Program: 0-PHX+MWD+HDGM													0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Tooface (")	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
0.00	0.00	1.00	0.00	0.00	0.00	-90.00	0.00	-30.00	30.00				
100.00	100.00	101.00	100.00	0.13	0.13	-90.00	0.00	-30.00	30.00	29.74	0.26	113.862	
200.00	200.00	201.00	200.00	0.49	0.49	-90.00	0.00	-30.00	30.00	29.02	0.98	30.599	
300.00	300.00	301.00	300.00	0.85	0.85	-90.00	0.00	-30.00	30.00	28.30	1.70	17.674	
400.00	400.00	401.00	400.00	1.21	1.21	-90.00	0.00	-30.00	30.00	27.59	2.41	12.426	
500.00	500.00	501.00	500.00	1.56	1.57	-90.00	0.00	-30.00	30.00	26.87	3.13	9.581	
600.00	600.00	601.00	600.00	1.92	1.93	-90.00	0.00	-30.00	30.00	26.15	3.85	7.796	
700.00	700.00	701.00	700.00	2.28	2.28	-90.00	0.00	-30.00	30.00	25.43	4.57	6.572	
800.00	800.00	801.00	800.00	2.64	2.64	-90.00	0.00	-30.00	30.00	24.72	5.28	5.680	
900.00	900.00	901.00	900.00	3.00	3.00	-90.00	0.00	-30.00	30.00	24.00	6.00	5.001	
1,000.00	1,000.00	1,001.01	1,000.01	3.36	3.36	-90.00	0.00	-30.00	30.00	23.28	6.72	4.467	
1,073.86	1,073.86	1,075.42	1,074.42	3.61	3.62	164.73	-0.24	-29.30	29.99	22.76	7.23	4.148 CC	
1,100.00	1,099.99	1,101.75	1,100.74	3.70	3.71	164.64	-0.44	-28.72	29.99	22.58	7.41	4.047	
1,200.00	1,199.91	1,202.50	1,201.41	4.04	4.05	164.12	-1.75	-24.93	30.02	21.93	8.09	3.712	
1,232.59	1,232.45	1,235.33	1,234.18	4.16	4.16	163.88	-2.36	-23.15	30.04	21.73	8.31	3.615	
1,300.00	1,299.69	1,302.97	1,301.67	4.39	4.40	163.39	-3.86	-18.81	30.25	21.48	8.76	3.451 ES	
1,400.00	1,399.38	1,402.97	1,401.42	4.74	4.75	163.03	-6.14	-12.22	31.24	21.78	9.45	3.304	
1,500.00	1,499.08	1,502.96	1,501.17	5.09	5.10	162.69	-8.41	-5.62	32.22	22.07	10.15	3.175	
1,600.00	1,598.77	1,602.96	1,600.92	5.45	5.45	162.37	-10.69	0.97	33.21	22.36	10.85	3.061	
1,700.00	1,698.46	1,702.95	1,700.67	5.81	5.81	162.07	-12.96	7.57	34.20	22.65	11.55	2.960	
1,800.00	1,798.15	1,802.95	1,800.43	6.17	6.17	161.79	-15.24	14.16	35.19	22.93	12.26	2.870	
1,900.00	1,897.84	1,902.94	1,900.18	6.53	6.53	161.52	-17.51	20.75	36.18	23.21	12.97	2.790	
2,000.00	1,997.53	2,002.94	1,999.93	6.89	6.89	161.27	-19.79	27.35	37.18	23.49	13.68	2.717	
2,100.00	2,097.23	2,102.93	2,099.68	7.26	7.25	161.03	-22.06	33.94	38.17	23.77	14.39	2.652	
2,200.00	2,196.92	2,202.93	2,199.43	7.62	7.61	160.80	-24.34	40.53	39.16	24.05	15.11	2.592	
2,300.00	2,296.61	2,302.92	2,299.18	7.99	7.98	160.58	-26.61	47.13	40.16	24.33	15.82	2.537	
2,400.00	2,396.30	2,402.92	2,398.93	8.36	8.34	160.37	-28.89	53.72	41.15	24.61	16.54	2.488	
2,500.00	2,495.99	2,502.91	2,498.68	8.73	8.71	160.18	-31.16	60.32	42.15	24.88	17.26	2.442	
2,600.00	2,595.68	2,602.91	2,598.44	9.09	9.07	159.99	-33.44	66.91	43.14	25.16	17.98	2.399	
2,700.00	2,695.38	2,702.90	2,698.19	9.46	9.44	159.81	-35.71	73.50	44.14	25.44	18.70	2.360	
2,750.00	2,745.22	2,752.93	2,748.09	9.65	9.62	159.72	-36.85	76.80	44.63	25.57	19.06	2.342	
2,800.00	2,795.04	2,803.47	2,798.48	9.83	9.81	159.59	-38.12	80.49	45.10	25.69	19.42	2.323	
2,900.00	2,894.49	2,904.56	2,899.10	10.21	10.18	159.16	-41.31	89.75	46.07	25.95	20.12	2.290	
3,000.00	2,993.63	3,005.67	2,999.44	10.59	10.57	158.54	-45.38	101.52	47.09	26.26	20.82	2.261	
3,100.00	3,092.40	3,105.78	3,098.56	10.99	10.96	158.27	-49.92	114.68	49.09	27.58	21.51	2.282	
3,116.50	3,108.65	3,122.26	3,114.89	11.05	11.02	158.33	-50.66	116.85	49.66	28.03	21.62	2.296	
3,200.00	3,190.89	3,205.71	3,197.53	11.39	11.34	158.72	-54.45	127.83	52.67	30.43	22.24	2.368	
3,300.00	3,289.37	3,305.64	3,296.49	11.79	11.73	159.13	-58.99	140.98	56.29	33.31	22.98	2.450	
3,400.00	3,387.85	3,405.58	3,395.45	12.20	12.12	159.49	-63.53	154.13	59.91	36.19	23.72	2.526	
3,500.00	3,486.33	3,505.51	3,494.41	12.60	12.51	159.80	-68.06	167.28	63.53	39.07	24.46	2.597	
3,600.00	3,584.81	3,605.45	3,593.37	13.01	12.90	160.09	-72.60	180.44	67.15	41.95	25.20	2.665	
3,700.00	3,683.29	3,705.38	3,692.33	13.42	13.30	160.34	-77.14	193.59	70.77	44.83	25.94	2.728	
3,800.00	3,781.77	3,805.31	3,791.29	13.84	13.69	160.57	-81.67	206.74	74.40	47.71	26.69	2.788	
3,900.00	3,880.26	3,905.25	3,890.25	14.25	14.09	160.78	-86.21	219.89	78.03	50.59	27.43	2.844	
4,000.00	3,978.74	4,005.18	3,989.21	14.67	14.48	160.97	-90.75	233.04	81.65	53.47	28.18	2.898	
4,100.00	4,077.22	4,105.12	4,088.17	15.08	14.88	161.14	-95.29	246.19	85.28	56.35	28.93	2.948	
4,200.00	4,175.70	4,205.05	4,187.13	15.50	15.28	161.30	-99.82	259.34	88.91	59.23	29.67	2.996	
4,300.00	4,274.18	4,304.98	4,286.10	15.92	15.67	161.45	-104.36	272.49	92.54	62.12	30.42	3.042	
4,400.00	4,372.66	4,404.92	4,385.06	16.34	16.07	161.59	-108.90	285.64	96.17	65.00	31.17	3.085	
4,500.00	4,471.15	4,504.85	4,484.02	16.76	16.47	161.71	-113.43	298.79	99.80	67.88	31.92	3.126	
4,600.00	4,569.63	4,604.78	4,582.98	17.18	16.87	161.83	-117.97	311.94	103.43	70.76	32.67	3.166	
4,700.00	4,668.11	4,704.72	4,681.94	17.60	17.27	161.94	-122.51	325.09	107.06	73.64	33.42	3.203	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Phoenix Technology Services

## Anticollision Report



**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Reference Site:** Charlie Sweeney Federal 31-23S-28E  
**Site Error:** 0.00 usft  
**Reference Well:** 227H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at** 2.00 sigma  
**Database:** Compass 5000 GCR  
**Offset TVD Reference:** Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 207H - OH - Preliminary Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Distance							Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
4,800.00	4,766.59	4,803.98	4,780.24	18.02	17.67	162.06	-126.99	338.08	110.77	76.60	34.17	3.242		
4,830.79	4,796.91	4,833.92	4,809.93	18.15	17.78	162.14	-128.24	341.72	112.19	77.79	34.40	3.262		
4,900.00	4,865.18	4,900.00	4,875.57	18.44	18.04	162.41	-130.75	348.99	115.61	80.67	34.94	3.309		
5,000.00	4,964.15	4,998.26	4,973.38	18.85	18.42	162.83	-133.79	357.81	120.43	84.72	35.71	3.373		
5,100.00	5,063.46	5,095.23	5,070.11	19.24	18.78	163.28	-135.99	364.17	125.13	88.69	36.44	3.434		
5,200.00	5,163.05	5,192.09	5,166.88	19.62	19.12	163.76	-137.38	368.21	129.71	92.56	37.14	3.492		
5,300.00	5,262.83	5,288.84	5,263.61	19.99	19.46	164.26	-137.98	369.93	134.16	96.35	37.81	3.548		
5,400.00	5,362.76	5,387.99	5,362.76	20.34	19.79	164.69	-138.00	370.00	137.80	99.36	38.45	3.584		
5,497.28	5,460.03	5,485.26	5,460.03	20.66	20.11	-90.00	-138.00	370.00	139.00	99.95	39.05	3.560		
5,500.00	5,462.75	5,487.98	5,462.75	20.67	20.11	-90.00	-138.00	370.00	139.00	99.93	39.07	3.558		
5,600.00	5,562.75	5,587.98	5,562.75	20.99	20.44	-90.00	-138.00	370.00	139.00	99.27	39.73	3.498		
5,700.00	5,662.75	5,687.98	5,662.75	21.31	20.77	-90.00	-138.00	370.00	139.00	98.59	40.41	3.440		
5,800.00	5,762.75	5,787.98	5,762.75	21.64	21.10	-90.00	-138.00	370.00	139.00	97.92	41.08	3.384		
5,900.00	5,862.75	5,887.98	5,862.75	21.96	21.44	-90.00	-138.00	370.00	139.00	97.25	41.75	3.329		
6,000.00	5,962.75	5,987.98	5,962.75	22.29	21.77	-90.00	-138.00	370.00	139.00	96.57	42.43	3.276		
6,100.00	6,062.75	6,087.98	6,062.75	22.61	22.10	-90.00	-138.00	370.00	139.00	95.89	43.11	3.225		
6,200.00	6,162.75	6,187.98	6,162.75	22.94	22.44	-90.00	-138.00	370.00	139.00	95.22	43.78	3.175		
6,300.00	6,262.75	6,287.98	6,262.75	23.27	22.77	-90.00	-138.00	370.00	139.00	94.54	44.46	3.126		
6,400.00	6,362.75	6,387.98	6,362.75	23.60	23.11	-90.00	-138.00	370.00	139.00	93.86	45.14	3.079		
6,500.00	6,462.75	6,487.98	6,462.75	23.93	23.44	-90.00	-138.00	370.00	139.00	93.17	45.83	3.033		
6,600.00	6,562.75	6,587.98	6,562.75	24.26	23.78	-90.00	-138.00	370.00	139.00	92.49	46.51	2.989		
6,700.00	6,662.75	6,687.98	6,662.75	24.59	24.12	-90.00	-138.00	370.00	139.00	91.81	47.19	2.945		
6,800.00	6,762.75	6,787.98	6,762.75	24.92	24.46	-90.00	-138.00	370.00	139.00	91.12	47.88	2.903		
6,900.00	6,862.75	6,887.98	6,862.75	25.26	24.79	-90.00	-138.00	370.00	139.00	90.44	48.56	2.862		
7,000.00	6,962.75	6,987.98	6,962.75	25.59	25.13	-90.00	-138.00	370.00	139.00	89.75	49.25	2.822		
7,100.00	7,062.75	7,087.98	7,062.75	25.93	25.47	-90.00	-138.00	370.00	139.00	89.06	49.94	2.783		
7,200.00	7,162.75	7,187.98	7,162.75	26.26	25.81	-90.00	-138.00	370.00	139.00	88.37	50.63	2.746		
7,300.00	7,262.75	7,287.98	7,262.75	26.60	26.15	-90.00	-138.00	370.00	139.00	87.68	51.32	2.709		
7,400.00	7,362.75	7,387.98	7,362.75	26.93	26.50	-90.00	-138.00	370.00	139.00	86.99	52.01	2.673		
7,500.00	7,462.75	7,487.98	7,462.75	27.27	26.84	-90.00	-138.00	370.00	139.00	86.30	52.70	2.638		
7,600.00	7,562.75	7,587.98	7,562.75	27.61	27.18	-90.00	-138.00	370.00	139.00	85.61	53.39	2.604		
7,700.00	7,662.75	7,687.98	7,662.75	27.95	27.52	-90.00	-138.00	370.00	139.00	84.92	54.08	2.570		
7,800.00	7,762.75	7,787.98	7,762.75	28.28	27.86	-90.00	-138.00	370.00	139.00	84.23	54.77	2.538		
7,900.00	7,862.75	7,887.98	7,862.75	28.62	28.21	-90.00	-138.00	370.00	139.00	83.54	55.46	2.506		
8,000.00	7,962.75	7,987.98	7,962.75	28.96	28.55	-90.00	-138.00	370.00	139.00	82.84	56.16	2.475		
8,100.00	8,062.75	8,087.98	8,062.75	29.30	28.90	-90.00	-138.00	370.00	139.00	82.15	56.85	2.445		
8,200.00	8,162.75	8,187.98	8,162.75	29.64	29.24	-90.00	-138.00	370.00	139.00	81.45	57.55	2.415		
8,300.00	8,262.75	8,287.98	8,262.75	29.98	29.58	-90.00	-138.00	370.00	139.00	80.76	58.24	2.387		
8,400.00	8,362.75	8,387.98	8,362.75	30.32	29.93	-90.00	-138.00	370.00	139.00	80.06	58.94	2.358		
8,500.00	8,462.75	8,487.98	8,462.75	30.67	30.28	-90.00	-138.00	370.00	139.00	79.36	59.64	2.331		
8,600.00	8,562.75	8,587.98	8,562.75	31.01	30.62	-90.00	-138.00	370.00	139.00	78.67	60.33	2.304		
8,700.00	8,662.75	8,687.98	8,662.75	31.35	30.97	-90.00	-138.00	370.00	139.00	77.97	61.03	2.278		
8,800.00	8,762.75	8,787.98	8,762.75	31.69	31.31	-90.00	-138.00	370.00	139.00	77.27	61.73	2.252		
8,900.00	8,862.75	8,887.98	8,862.75	32.04	31.66	-90.00	-138.00	370.00	139.00	76.57	62.43	2.227		
9,000.00	8,962.75	8,988.76	8,963.52	32.38	32.01	-89.88	-137.71	370.05	138.95	75.82	63.13	2.201		
9,100.00	9,062.75	9,091.37	9,065.24	32.72	32.36	-84.76	-125.45	372.24	137.36	75.60	63.76	2.154		
9,147.63	9,110.37	9,137.99	9,110.37	32.89	32.51	-79.90	-114.00	374.27	136.85	72.81	64.04	2.137 SF		
9,200.00	9,162.75	9,186.73	9,156.38	33.07	32.66	-73.22	-98.22	377.09	137.93	73.58	64.35	2.143		
9,300.00	9,262.75	9,271.04	9,232.18	33.41	32.91	-58.81	-62.05	383.53	149.82	84.77	65.05	2.303		
9,400.00	9,362.75	9,343.14	9,292.14	33.76	33.09	-45.78	-22.71	390.54	179.76	113.92	65.83	2.731		
9,500.00	9,462.75	9,400.00	9,335.59	34.10	33.21	-36.51	13.36	396.96	227.22	160.68	66.54	3.415		
9,600.00	9,562.75	9,450.00	9,370.64	34.45	33.31	-29.57	48.44	403.21	287.85	220.67	67.18	4.285		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation



# Phoenix Technology Services

## Anticollision Report



**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Reference Site:** Charlie Sweeney Federal 31-23S-28E  
**Site Error:** 0.00 usft  
**Reference Well:** 227H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at** 2.00 sigma  
**Database:** Compass 5000 GCR  
**Offset TVD Reference:** Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 207H - OH - Preliminary Plan 1													Offset Site Error:
Survey Program: 0-PHX+MWD+HDGM													Offset Well Error:
Reference		Offset		Semi Major Axis			Distance						Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
9,700.00	9,662.75	9,500.00	9,402.46	34.79	33.40	-23.81	86.40	409.97	357.65	289.87	67.77	5.277	
9,751.28	9,714.03	9,515.24	9,411.47	34.97	33.42	-22.28	98.49	412.13	396.05	328.03	68.02	5.823	
9,800.00	9,762.69	9,532.67	9,421.37	35.14	33.45	-19.27	112.61	414.64	432.64	364.64	67.99	6.363	
9,850.00	9,812.26	9,550.00	9,430.79	35.30	33.48	-16.51	126.94	417.19	468.76	401.21	67.54	6.940	
9,900.00	9,861.08	9,569.90	9,441.04	35.47	33.51	-14.18	143.73	420.18	503.26	436.62	66.65	7.551	
9,950.00	9,908.79	9,600.00	9,455.42	35.62	33.57	-11.93	169.76	424.82	536.24	470.91	65.34	8.207	
10,000.00	9,955.01	9,600.00	9,455.42	35.77	33.57	-11.14	169.76	424.82	567.08	503.55	63.53	8.926	
10,050.00	9,999.40	9,628.41	9,467.70	35.90	33.62	-9.61	194.98	429.31	595.93	534.56	61.37	9.711	
10,100.00	10,041.61	9,650.00	9,476.17	36.02	33.67	-8.53	214.53	432.80	622.89	564.07	58.82	10.590	
10,150.00	10,081.34	9,668.64	9,482.88	36.13	33.71	-7.69	231.65	435.84	647.74	591.83	55.91	11.585	
10,200.00	10,118.26	9,700.00	9,492.88	36.23	33.78	-6.72	260.91	441.06	670.63	617.90	52.73	12.719	
10,250.00	10,152.11	9,709.55	9,495.59	36.31	33.81	-6.29	269.92	442.66	690.91	641.65	49.27	14.024	
10,300.00	10,182.63	9,733.00	9,501.68	36.38	33.87	-5.67	292.22	446.63	709.08	663.44	45.65	15.534	
10,350.00	10,209.58	9,750.00	9,505.71	36.43	33.92	-5.24	308.48	449.53	724.72	682.80	41.92	17.288	
10,400.00	10,232.76	9,786.71	9,513.42	36.48	34.02	-4.57	343.81	455.82	737.39	699.15	38.24	19.282	
10,450.00	10,251.99	9,813.88	9,518.23	36.52	34.11	-4.11	370.13	460.51	747.40	712.68	34.72	21.529	
10,500.00	10,267.13	9,850.00	9,523.44	36.56	34.22	-3.57	405.32	466.78	754.68	723.12	31.57	23.907	
10,501.28	10,267.46	9,850.00	9,523.44	36.56	34.22	-3.57	405.32	466.78	754.82	723.33	31.49	23.969	
10,550.00	10,278.87	9,868.55	9,525.59	36.64	34.28	-3.31	423.46	470.01	759.78	729.83	29.96	25.361	
10,600.00	10,288.04	9,900.00	9,528.42	36.76	34.39	-2.89	454.30	475.50	763.89	735.19	28.70	26.620	
10,650.00	10,294.64	9,923.21	9,529.84	36.89	34.46	-2.59	477.11	479.57	766.84	739.08	27.76	27.624	
10,700.00	10,298.63	9,950.00	9,530.79	37.04	34.56	-2.25	503.46	484.26	768.71	741.48	27.23	28.230	
10,751.29	10,300.00	9,985.00	9,531.00	37.20	34.68	-1.81	537.93	490.34	769.39	742.23	27.17	28.319	
10,800.00	10,300.00	10,032.66	9,531.00	37.37	34.86	-1.29	585.01	497.75	769.20	741.70	27.50	27.969	
10,900.00	10,300.00	10,131.46	9,531.00	37.74	35.26	-0.49	683.11	509.36	769.03	740.79	28.24	27.235	
11,000.00	10,300.00	10,231.11	9,531.00	38.16	35.70	-0.06	782.53	515.91	769.00	739.99	29.01	26.510	
11,039.05	10,300.00	10,270.14	9,531.00	38.34	35.88	0.00	821.55	517.06	769.00	739.69	29.31	26.232	
11,100.00	10,300.00	10,331.10	9,531.00	38.63	36.18	0.01	882.50	517.68	769.00	739.21	29.79	25.814	
11,200.00	10,300.00	10,431.10	9,531.00	39.15	36.70	0.01	982.49	518.52	769.00	738.38	30.62	25.115	
11,300.00	10,300.00	10,531.10	9,531.00	39.71	37.27	0.01	1,082.49	519.35	769.00	737.50	31.50	24.409	
11,400.00	10,300.00	10,631.10	9,531.00	40.32	37.89	0.01	1,182.49	520.19	769.00	736.56	32.44	23.703	
11,500.00	10,300.00	10,731.10	9,531.00	40.97	38.56	0.01	1,282.48	521.02	769.00	735.57	33.43	23.005	
11,600.00	10,300.00	10,831.10	9,531.00	41.65	39.26	0.01	1,382.48	521.86	769.00	734.54	34.46	22.318	
11,700.00	10,300.00	10,931.10	9,531.00	42.38	40.01	0.01	1,482.48	522.69	769.00	733.48	35.52	21.648	
11,800.00	10,300.00	11,031.10	9,531.00	43.14	40.79	0.01	1,582.47	523.53	769.00	732.37	36.63	20.995	
11,900.00	10,300.00	11,131.10	9,531.00	43.94	41.61	0.01	1,682.47	524.36	769.00	731.24	37.76	20.363	
12,000.00	10,300.00	11,231.10	9,531.00	44.77	42.46	0.01	1,782.47	525.20	769.00	730.07	38.93	19.753	
12,100.00	10,300.00	11,331.10	9,531.00	45.63	43.34	0.01	1,882.46	526.04	769.00	728.88	40.12	19.165	
12,200.00	10,300.00	11,431.10	9,531.00	46.52	44.26	0.01	1,982.46	526.87	769.00	727.66	41.34	18.600	
12,300.00	10,300.00	11,531.10	9,531.00	47.43	45.20	0.01	2,082.46	527.71	769.00	726.41	42.59	18.058	
12,400.00	10,300.00	11,631.10	9,531.00	48.38	46.17	0.01	2,182.45	528.54	769.00	725.15	43.85	17.537	
12,500.00	10,300.00	11,731.10	9,531.00	49.34	47.16	0.01	2,282.45	529.38	769.00	723.87	45.13	17.039	
12,600.00	10,300.00	11,831.10	9,531.00	50.33	48.18	0.01	2,382.45	530.21	769.00	722.57	46.43	16.562	
12,700.00	10,300.00	11,931.10	9,531.00	51.35	49.22	0.01	2,482.44	531.05	769.00	721.25	47.75	16.106	
12,800.00	10,300.00	12,031.10	9,531.00	52.38	50.28	0.01	2,582.44	531.88	769.00	719.92	49.08	15.669	
12,900.00	10,300.00	12,131.10	9,531.00	53.43	51.36	0.01	2,682.43	532.72	769.00	718.58	50.42	15.251	
13,000.00	10,300.00	12,231.10	9,531.00	54.50	52.46	0.00	2,782.43	533.56	769.00	717.22	51.78	14.851	
13,100.00	10,300.00	12,331.10	9,531.00	55.59	53.57	0.00	2,882.43	534.39	769.00	715.85	53.15	14.469	
13,200.00	10,300.00	12,431.10	9,531.00	56.70	54.70	0.00	2,982.42	535.23	769.00	714.47	54.53	14.103	
13,300.00	10,300.00	12,531.10	9,531.00	57.82	55.84	0.00	3,082.42	536.06	769.00	713.08	55.92	13.752	
13,400.00	10,300.00	12,631.10	9,531.00	58.95	57.00	0.00	3,182.42	536.90	769.00	711.68	57.32	13.417	
13,500.00	10,300.00	12,731.10	9,531.00	60.10	58.17	0.00	3,282.41	537.73	769.00	710.28	58.72	13.095	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Phoenix Technology Services

## Anticollision Report



Company: Matador Resources  
Project: Eddy County, NM (NAD27 NME)  
Reference Site: Charlie Sweeney Federal 31-23S-28E  
Site Error: 0.00 usft  
Reference Well: 227H  
Well Error: 0.00 usft  
Reference Wellbore: OH  
Reference Design: Preliminary Plan 1

Local Co-ordinate Reference: Well 227H  
TVD Reference: RKB @ 3134.50usft (Patterson 297)  
MD Reference: RKB @ 3134.50usft (Patterson 297)  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Output errors are at: 2.00 sigma  
Database: Compass 5000 GCR  
Offset TVD Reference: Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 207H - OH - Preliminary Plan 1												Offset Site Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM												Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)					
13,600.00	10,300.00	12,831.10	9,531.00	61.26	59.36	0.00	3,382.41	538.57	769.00	708.86	60.14	12.787	
13,700.00	10,300.00	12,931.10	9,531.00	62.43	60.55	0.00	3,482.41	539.41	769.00	707.44	61.56	12.492	
13,800.00	10,300.00	13,031.10	9,531.00	63.62	61.76	0.00	3,582.40	540.24	769.00	706.01	62.99	12.208	
13,900.00	10,300.00	13,131.10	9,531.00	64.81	62.98	0.00	3,682.40	541.08	769.00	704.57	64.43	11.936	
14,000.00	10,300.00	13,231.10	9,531.00	66.02	64.21	0.00	3,782.40	541.91	769.00	703.13	65.87	11.674	
14,100.00	10,300.00	13,331.10	9,531.00	67.24	65.44	0.00	3,882.39	542.75	769.00	701.68	67.32	11.423	
14,200.00	10,300.00	13,431.10	9,531.00	68.46	66.69	0.00	3,982.39	543.58	769.00	700.23	68.77	11.182	
14,300.00	10,300.00	13,531.10	9,531.00	69.69	67.94	0.00	4,082.39	544.42	769.00	698.77	70.23	10.950	
14,400.00	10,300.00	13,631.10	9,531.00	70.94	69.20	0.00	4,182.38	545.25	769.00	697.31	71.69	10.726	
14,500.00	10,300.00	13,731.10	9,531.00	72.19	70.47	0.00	4,282.38	546.09	769.00	695.84	73.16	10.511	
14,600.00	10,300.00	13,831.10	9,531.00	73.44	71.75	0.00	4,382.38	546.93	769.00	694.37	74.63	10.304	
14,700.00	10,300.00	13,931.10	9,531.00	74.71	73.03	0.00	4,482.37	547.76	769.00	692.89	76.11	10.104	
14,800.00	10,300.00	14,031.10	9,531.00	75.98	74.32	0.00	4,582.37	548.60	769.00	691.41	77.59	9.911	
14,900.00	10,300.00	14,131.10	9,531.00	77.26	75.61	0.00	4,682.36	549.43	769.00	689.93	79.07	9.726	
15,000.00	10,300.00	14,231.10	9,531.00	78.54	76.91	0.00	4,782.36	550.27	769.00	688.44	80.56	9.546	
15,087.64	10,300.00	14,318.74	9,531.00	79.67	78.05	0.00	4,870.00	551.00	769.00	687.14	81.86	9.394	



# Phoenix Technology Services

## Anticollision Report



**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Reference Site:** Charlie Sweeney Federal 31-23S-28E  
**Site Error:** 0.00 usft  
**Reference Well:** 227H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at** 2.00 sigma  
**Database:** Compass 5000 GCR  
**Offset TVD Reference:** Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 223H - OH - Preliminary Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance							Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
0.00	0.00	4.00	0.00	0.00	0.01	-90.00	0.00	-120.00	120.00					
100.00	100.00	104.00	100.00	0.13	0.14	-90.00	0.00	-120.00	120.00	119.73	0.27	437.587		
200.00	200.00	204.00	200.00	0.49	0.50	-90.00	0.00	-120.00	120.00	119.01	0.99	121.069		
300.00	300.00	304.00	300.00	0.85	0.86	-90.00	0.00	-120.00	120.00	118.29	1.71	70.253		
400.00	400.00	404.00	400.00	1.21	1.22	-90.00	0.00	-120.00	120.00	117.57	2.43	49.483		
500.00	500.00	504.00	500.00	1.56	1.58	-90.00	0.00	-120.00	120.00	116.86	3.14	38.192		
600.00	600.00	604.00	600.00	1.92	1.94	-90.00	0.00	-120.00	120.00	116.14	3.86	31.097		
700.00	700.00	704.00	700.00	2.28	2.30	-90.00	0.00	-120.00	120.00	115.42	4.58	26.224		
800.00	800.00	804.00	800.00	2.64	2.65	-90.00	0.00	-120.00	120.00	114.71	5.29	22.672		
900.00	900.00	904.00	900.00	3.00	3.01	-90.00	0.00	-120.00	120.00	113.99	6.01	19.967		
965.28	965.28	969.28	965.28	3.23	3.25	-90.00	0.00	-120.00	120.00	113.52	6.48	18.525 CC		
1,000.00	1,000.00	1,003.97	999.97	3.36	3.37	-90.00	0.00	-120.00	120.00	113.27	6.73	17.841 ES		
1,100.00	1,099.99	1,103.26	1,099.25	3.70	3.71	164.34	-1.36	-120.30	121.57	114.16	7.41	16.406		
1,200.00	1,199.91	1,202.36	1,198.26	4.04	4.03	163.04	-5.23	-121.16	126.28	118.21	8.07	15.647		
1,300.00	1,299.69	1,301.40	1,297.10	4.39	4.37	161.17	-11.45	-122.53	134.19	125.45	8.74	15.360		
1,400.00	1,399.38	1,400.87	1,396.33	4.74	4.70	159.51	-18.22	-124.03	143.60	134.18	9.42	15.249		
1,500.00	1,499.08	1,500.35	1,495.56	5.09	5.04	158.05	-24.99	-125.53	153.12	143.02	10.10	15.153		
1,600.00	1,598.77	1,599.82	1,594.80	5.45	5.39	156.77	-31.75	-127.03	162.73	151.93	10.80	15.068		
1,700.00	1,698.46	1,699.30	1,694.03	5.81	5.74	155.63	-38.52	-128.53	172.41	160.91	11.50	14.994		
1,800.00	1,798.15	1,798.77	1,793.26	6.17	6.09	154.61	-45.29	-130.03	182.15	169.94	12.20	14.928		
1,900.00	1,897.84	1,898.25	1,892.50	6.53	6.44	153.69	-52.06	-131.53	191.94	179.03	12.91	14.869		
2,000.00	1,997.53	1,997.72	1,991.73	6.89	6.80	152.86	-58.83	-133.03	201.77	188.15	13.62	14.816		
2,100.00	2,097.23	2,097.20	2,090.96	7.26	7.16	152.11	-65.60	-134.53	211.64	197.31	14.33	14.769		
2,200.00	2,196.92	2,196.67	2,190.20	7.62	7.51	151.43	-72.37	-136.02	221.55	206.50	15.05	14.726		
2,300.00	2,296.61	2,296.15	2,289.43	7.99	7.87	150.80	-79.13	-137.52	231.48	215.72	15.76	14.687		
2,400.00	2,396.30	2,395.62	2,388.66	8.36	8.24	150.23	-85.90	-139.02	241.44	224.96	16.48	14.651		
2,500.00	2,495.99	2,495.10	2,487.90	8.73	8.60	149.70	-92.67	-140.52	251.42	234.23	17.20	14.619		
2,600.00	2,595.68	2,594.57	2,587.13	9.09	8.96	149.21	-99.44	-142.02	261.43	243.51	17.92	14.589		
2,700.00	2,695.38	2,694.05	2,686.36	9.46	9.32	148.76	-106.21	-143.52	271.44	252.80	18.64	14.562		
2,750.00	2,745.22	2,743.79	2,735.98	9.65	9.50	148.55	-109.59	-144.27	276.46	257.46	19.00	14.549		
2,800.00	2,795.04	2,793.50	2,785.57	9.83	9.69	148.33	-112.98	-145.02	281.75	262.40	19.35	14.561		
2,900.00	2,894.49	2,892.74	2,884.57	10.21	10.05	148.12	-119.73	-146.51	294.01	273.97	20.04	14.669		
3,000.00	2,993.63	2,991.68	2,983.27	10.59	10.41	148.15	-126.46	-148.00	308.47	287.74	20.73	14.884		
3,100.00	3,092.40	3,091.65	3,083.00	10.99	10.78	148.43	-133.11	-149.48	325.06	303.66	21.40	15.188		
3,116.50	3,108.65	3,108.57	3,099.89	11.05	10.84	148.53	-134.08	-149.69	327.94	306.42	21.51	15.243		
3,200.00	3,190.89	3,194.27	3,185.51	11.39	11.15	149.27	-137.86	-150.53	342.15	320.02	22.13	15.462		
3,300.00	3,289.37	3,297.03	3,288.25	11.79	11.51	150.44	-139.91	-150.98	358.14	335.28	22.86	15.667		
3,400.00	3,387.85	3,396.63	3,387.85	12.20	11.85	151.76	-140.00	-151.00	373.44	349.87	23.56	15.849		
3,500.00	3,486.33	3,495.12	3,486.33	12.60	12.18	152.96	-140.00	-151.00	388.87	364.61	24.26	16.029		
3,600.00	3,584.81	3,593.60	3,584.81	13.01	12.51	154.08	-140.00	-151.00	404.45	379.49	24.96	16.204		
3,700.00	3,683.29	3,692.08	3,683.29	13.42	12.84	155.11	-140.00	-151.00	420.18	394.52	25.66	16.375		
3,800.00	3,781.77	3,790.56	3,781.77	13.84	13.18	156.07	-140.00	-151.00	436.03	409.67	26.36	16.540		
3,900.00	3,880.26	3,889.04	3,880.26	14.25	13.51	156.96	-140.00	-151.00	451.99	424.92	27.06	16.700		
4,000.00	3,978.74	3,987.52	3,978.74	14.67	13.85	157.79	-140.00	-151.00	468.05	440.28	27.77	16.856		
4,100.00	4,077.22	4,086.01	4,077.22	15.08	14.18	158.56	-140.00	-151.00	484.20	455.73	28.47	17.006		
4,200.00	4,175.70	4,184.49	4,175.70	15.50	14.52	159.29	-140.00	-151.00	500.43	471.25	29.18	17.151		
4,300.00	4,274.18	4,282.97	4,274.18	15.92	14.86	159.97	-140.00	-151.00	516.74	486.85	29.88	17.291		
4,400.00	4,372.66	4,381.45	4,372.66	16.34	15.20	160.61	-140.00	-151.00	533.11	502.52	30.59	17.426		
4,500.00	4,471.15	4,479.93	4,471.15	16.76	15.54	161.21	-140.00	-151.00	549.54	518.24	31.30	17.557		
4,600.00	4,569.63	4,578.41	4,569.63	17.18	15.88	161.77	-140.00	-151.00	566.03	534.02	32.01	17.683		
4,700.00	4,668.11	4,676.90	4,668.11	17.60	16.22	162.30	-140.00	-151.00	582.56	549.85	32.72	17.805		
4,800.00	4,766.59	4,775.38	4,766.59	18.02	16.56	162.81	-140.00	-151.00	599.15	565.72	33.43	17.923		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Phoenix Technology Services

## Anticollision Report



**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Reference Site:** Charlie Sweeney Federal 31-23S-28E  
**Site Error:** 0.00 usft  
**Reference Well:** 227H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Gnd  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at** 2.00 sigma  
**Database:** Compass 5000 GCR  
**Offset TVD Reference:** Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 223H - OH - Preliminary Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance							Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
4,830.79	4,796.91	4,805.70	4,796.91	18.15	16.66	162.96	-140.00	-151.00	604.26	570.62	33.65	17.959		
4,900.00	4,865.18	4,873.96	4,865.18	18.44	16.90	163.32	-140.00	-151.00	615.18	580.98	34.20	17.986		
5,000.00	4,964.15	4,972.94	4,964.15	18.85	17.24	163.75	-140.00	-151.00	628.89	593.90	34.99	17.973		
5,100.00	5,063.46	5,072.25	5,063.46	19.24	17.59	164.09	-140.00	-151.00	640.12	604.36	35.76	17.902		
5,200.00	5,163.05	5,171.83	5,163.05	19.62	17.94	164.34	-140.00	-151.00	648.86	612.36	36.50	17.777		
5,300.00	5,262.83	5,271.62	5,262.83	19.99	18.28	164.52	-140.00	-151.00	655.09	617.87	37.22	17.600		
5,400.00	5,362.76	5,371.54	5,362.76	20.34	18.63	164.62	-140.00	-151.00	658.81	620.89	37.91	17.376		
5,497.28	5,460.03	5,468.82	5,460.03	20.66	18.97	-90.17	-140.00	-151.00	660.00	621.44	38.56	17.115		
5,500.00	5,462.75	5,471.53	5,462.75	20.67	18.98	-90.17	-140.00	-151.00	660.00	621.42	38.58	17.106		
5,600.00	5,562.75	5,571.53	5,562.75	20.99	19.33	-90.17	-140.00	-151.00	660.00	620.74	39.27	16.809		
5,700.00	5,662.75	5,671.53	5,662.75	21.31	19.68	-90.17	-140.00	-151.00	660.00	620.05	39.95	16.521		
5,800.00	5,762.75	5,771.53	5,762.75	21.64	20.03	-90.17	-140.00	-151.00	660.00	619.37	40.63	16.242		
5,900.00	5,862.75	5,871.53	5,862.75	21.96	20.38	-90.17	-140.00	-151.00	660.00	618.68	41.32	15.973		
6,000.00	5,962.75	5,971.53	5,962.75	22.29	20.73	-90.17	-140.00	-151.00	660.00	617.99	42.01	15.711		
6,100.00	6,062.75	6,071.53	6,062.75	22.61	21.08	-90.17	-140.00	-151.00	660.00	617.31	42.70	15.458		
6,200.00	6,162.75	6,171.53	6,162.75	22.94	21.43	-90.17	-140.00	-151.00	660.00	616.62	43.39	15.212		
6,300.00	6,262.75	6,271.53	6,262.75	23.27	21.78	-90.17	-140.00	-151.00	660.00	615.93	44.08	14.974		
6,400.00	6,362.75	6,371.53	6,362.75	23.60	22.14	-90.17	-140.00	-151.00	660.00	615.24	44.77	14.743		
6,500.00	6,462.75	6,471.53	6,462.75	23.93	22.49	-90.17	-140.00	-151.00	660.00	614.54	45.46	14.519		
6,600.00	6,562.75	6,571.53	6,562.75	24.26	22.84	-90.17	-140.00	-151.00	660.00	613.85	46.15	14.301		
6,700.00	6,662.75	6,671.53	6,662.75	24.59	23.19	-90.17	-140.00	-151.00	660.00	613.16	46.84	14.089		
6,800.00	6,762.75	6,771.53	6,762.75	24.92	23.54	-90.17	-140.00	-151.00	660.00	612.47	47.54	13.884		
6,900.00	6,862.75	6,871.53	6,862.75	25.26	23.90	-90.17	-140.00	-151.00	660.00	611.77	48.23	13.684		
7,000.00	6,962.75	6,971.53	6,962.75	25.59	24.25	-90.17	-140.00	-151.00	660.00	611.08	48.93	13.489		
7,100.00	7,062.75	7,071.53	7,062.75	25.93	24.60	-90.17	-140.00	-151.00	660.00	610.38	49.62	13.300		
7,200.00	7,162.75	7,171.53	7,162.75	26.26	24.96	-90.17	-140.00	-151.00	660.00	609.68	50.32	13.116		
7,300.00	7,262.75	7,271.53	7,262.75	26.60	25.31	-90.17	-140.00	-151.00	660.00	608.99	51.02	12.937		
7,400.00	7,362.75	7,371.53	7,362.75	26.93	25.66	-90.17	-140.00	-151.00	660.00	608.29	51.71	12.762		
7,500.00	7,462.75	7,471.53	7,462.75	27.27	26.02	-90.17	-140.00	-151.00	660.00	607.59	52.41	12.593		
7,600.00	7,562.75	7,571.53	7,562.75	27.61	26.37	-90.17	-140.00	-151.00	660.00	606.89	53.11	12.427		
7,700.00	7,662.75	7,671.53	7,662.75	27.95	26.72	-90.17	-140.00	-151.00	660.00	606.19	53.81	12.265		
7,800.00	7,762.75	7,771.53	7,762.75	28.28	27.08	-90.17	-140.00	-151.00	660.00	605.49	54.51	12.108		
7,900.00	7,862.75	7,871.53	7,862.75	28.62	27.43	-90.17	-140.00	-151.00	660.00	604.79	55.21	11.955		
8,000.00	7,962.75	7,971.53	7,962.75	28.96	27.79	-90.17	-140.00	-151.00	660.00	604.09	55.91	11.805		
8,100.00	8,062.75	8,071.53	8,062.75	29.30	28.14	-90.17	-140.00	-151.00	660.00	603.39	56.61	11.659		
8,200.00	8,162.75	8,171.53	8,162.75	29.64	28.50	-90.17	-140.00	-151.00	660.00	602.69	57.31	11.516		
8,300.00	8,262.75	8,271.53	8,262.75	29.98	28.85	-90.17	-140.00	-151.00	660.00	601.99	58.01	11.377		
8,400.00	8,362.75	8,371.53	8,362.75	30.32	29.20	-90.17	-140.00	-151.00	660.00	601.29	58.71	11.241		
8,500.00	8,462.75	8,471.53	8,462.75	30.67	29.56	-90.17	-140.00	-151.00	660.00	600.59	59.42	11.108		
8,600.00	8,562.75	8,571.53	8,562.75	31.01	29.91	-90.17	-140.00	-151.00	660.00	599.88	60.12	10.978		
8,700.00	8,662.75	8,671.53	8,662.75	31.35	30.27	-90.17	-140.00	-151.00	660.00	599.18	60.82	10.851		
8,800.00	8,762.75	8,771.53	8,762.75	31.69	30.62	-90.17	-140.00	-151.00	660.00	598.48	61.53	10.727		
8,900.00	8,862.75	8,871.53	8,862.75	32.04	30.98	-90.17	-140.00	-151.00	660.00	597.77	62.23	10.606		
9,000.00	8,962.75	8,971.53	8,962.75	32.38	31.33	-90.17	-140.00	-151.00	660.00	597.07	62.93	10.487		
9,100.00	9,062.75	9,071.53	9,062.75	32.72	31.69	-90.17	-140.00	-151.00	660.00	596.37	63.64	10.371		
9,200.00	9,162.75	9,171.53	9,162.75	33.07	32.04	-90.17	-140.00	-151.00	660.00	595.66	64.34	10.258		
9,300.00	9,262.75	9,271.53	9,262.75	33.41	32.40	-90.17	-140.00	-151.00	660.00	594.96	65.05	10.147		
9,400.00	9,362.75	9,371.53	9,362.75	33.76	32.76	-90.17	-140.00	-151.00	660.00	594.25	65.75	10.038		
9,500.00	9,462.75	9,471.53	9,462.75	34.10	33.11	-90.17	-140.00	-151.00	660.00	593.55	66.46	9.931		
9,600.00	9,562.75	9,571.53	9,562.75	34.45	33.47	-90.17	-140.00	-151.00	660.00	592.84	67.16	9.827		
9,700.00	9,662.75	9,671.53	9,662.75	34.79	33.82	-90.17	-140.00	-151.00	660.00	592.13	67.87	9.725		
9,751.28	9,714.03	9,722.87	9,714.08	34.97	34.00	-90.17	-139.99	-151.00	660.00	591.77	68.23	9.673		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Phoenix Technology Services

## Anticollision Report



**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Reference Site:** Charlie Sweeney Federal 31-23S-28E  
**Site Error:** 0.00 usft  
**Reference Well:** 227H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at** 2.00 sigma  
**Database:** Compass 5000 GCR  
**Offset TVD Reference:** Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 223H - OH - Preliminary Plan 1												Offset Site Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM												Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Distance							
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
9,800.00	9,762.69	9,772.22	9,763.35	35.14	34.18	-90.62	-137.51	-150.98	660.00	591.43	68.57	9.625	
9,850.00	9,812.26	9,822.83	9,813.47	35.30	34.35	-90.58	-130.59	-150.92	659.99	591.08	68.91	9.577	
9,900.00	9,861.08	9,873.39	9,862.74	35.47	34.52	-90.54	-119.28	-150.83	659.99	590.74	69.25	9.531	
9,950.00	9,908.79	9,923.92	9,910.78	35.62	34.68	-90.49	-103.68	-150.70	659.98	590.42	69.57	9.487	
10,000.00	9,955.01	9,974.39	9,957.21	35.77	34.84	-90.44	-83.94	-150.53	659.98	590.10	69.88	9.444	
10,050.00	9,999.40	10,024.81	10,001.68	35.90	34.99	-90.39	-60.22	-150.33	659.98	589.80	70.18	9.404	
10,100.00	10,041.61	10,075.17	10,043.85	36.02	35.13	-90.33	-32.71	-150.10	659.97	589.50	70.47	9.366	
10,150.00	10,081.34	10,125.47	10,083.39	36.13	35.27	-90.27	-1.65	-149.84	659.97	589.22	70.75	9.329	
10,200.00	10,118.26	10,175.71	10,120.02	36.23	35.41	-90.21	32.72	-149.55	659.96	588.95	71.02	9.293	
10,250.00	10,152.11	10,225.89	10,153.46	36.31	35.54	-90.15	70.11	-149.24	659.96	588.68	71.28	9.258	
10,300.00	10,182.63	10,276.01	10,183.46	36.38	35.68	-90.09	110.23	-148.90	659.96	588.42	71.54	9.225	
10,350.00	10,209.58	10,326.06	10,209.81	36.43	35.81	-90.02	152.76	-148.55	659.96	588.16	71.80	9.192	
10,367.22	10,218.00	10,343.27	10,218.00	36.45	35.85	-90.00	167.90	-148.42	659.96	588.07	71.89	9.181	
10,400.00	10,232.76	10,376.04	10,232.32	36.48	35.93	-89.96	197.37	-148.17	659.96	587.91	72.05	9.159	
10,450.00	10,251.99	10,425.96	10,250.84	36.52	36.06	-89.89	243.71	-147.79	659.96	587.65	72.31	9.127	
10,500.00	10,267.13	10,475.83	10,265.25	36.56	36.19	-89.83	291.43	-147.39	659.96	587.40	72.56	9.095	
10,501.26	10,267.46	10,477.11	10,265.58	36.56	36.20	-89.83	292.67	-147.38	659.96	587.40	72.57	9.095	
10,550.00	10,278.87	10,525.71	10,276.55	36.64	36.33	-89.79	340.01	-146.98	659.96	587.14	72.82	9.063	
10,600.00	10,288.04	10,575.58	10,285.28	36.76	36.46	-89.76	389.10	-146.57	659.97	586.87	73.09	9.029	
10,650.00	10,294.64	10,625.42	10,291.44	36.89	36.61	-89.72	438.55	-146.15	659.97	586.59	73.37	8.995	
10,700.00	10,298.63	10,675.24	10,295.01	37.04	36.76	-89.69	488.23	-145.74	659.97	586.30	73.67	8.959	
10,751.29	10,300.00	10,726.35	10,296.00	37.20	36.91	-89.65	539.33	-145.31	659.97	586.00	73.98	8.921	
10,800.00	10,300.00	10,775.06	10,296.00	37.37	37.08	-89.65	588.04	-144.90	659.97	585.68	74.30	8.883	
10,900.00	10,300.00	10,875.06	10,296.00	37.74	37.45	-89.65	688.04	-144.06	659.97	584.95	75.02	8.797	
11,000.00	10,300.00	10,975.06	10,296.00	38.16	37.87	-89.65	788.03	-143.22	659.98	584.12	75.86	8.700	
11,100.00	10,300.00	11,075.06	10,296.00	38.63	38.34	-89.65	888.03	-142.39	659.98	583.19	76.79	8.595	
11,200.00	10,300.00	11,175.06	10,296.00	39.15	38.86	-89.65	988.03	-141.55	659.98	582.16	77.82	8.481	
11,300.00	10,300.00	11,275.06	10,296.00	39.71	39.43	-89.65	1,088.02	-140.71	659.98	581.04	78.94	8.360	
11,400.00	10,300.00	11,375.06	10,296.00	40.32	40.04	-89.65	1,188.02	-139.87	659.98	579.82	80.16	8.234	
11,500.00	10,300.00	11,475.06	10,296.00	40.97	40.69	-89.65	1,288.02	-139.03	659.98	578.52	81.45	8.102	
11,600.00	10,300.00	11,575.06	10,296.00	41.65	41.39	-89.65	1,388.01	-138.20	659.98	577.15	82.83	7.967	
11,700.00	10,300.00	11,675.06	10,296.00	42.38	42.12	-89.65	1,488.01	-137.36	659.98	575.69	84.29	7.830	
11,800.00	10,300.00	11,775.06	10,296.00	43.14	42.89	-89.65	1,588.00	-136.52	659.98	574.16	85.82	7.690	
11,900.00	10,300.00	11,875.06	10,296.00	43.94	43.70	-89.65	1,688.00	-135.68	659.98	572.56	87.43	7.549	
12,000.00	10,300.00	11,975.06	10,296.00	44.77	44.54	-89.65	1,788.00	-134.84	659.98	570.89	89.09	7.408	
12,100.00	10,300.00	12,075.06	10,296.00	45.63	45.40	-89.65	1,887.99	-134.01	659.98	569.16	90.82	7.267	
12,200.00	10,300.00	12,175.06	10,296.00	46.52	46.30	-89.65	1,987.99	-133.17	659.98	567.37	92.61	7.126	
12,300.00	10,300.00	12,275.06	10,296.00	47.43	47.23	-89.65	2,087.99	-132.33	659.98	565.53	94.46	6.987	
12,400.00	10,300.00	12,375.06	10,296.00	48.38	48.18	-89.65	2,187.98	-131.49	659.99	563.63	96.35	6.850	
12,500.00	10,300.00	12,475.06	10,296.00	49.34	49.16	-89.65	2,287.98	-130.65	659.99	561.69	98.30	6.714	
12,600.00	10,300.00	12,575.06	10,296.00	50.33	50.16	-89.65	2,387.98	-129.82	659.99	559.70	100.29	6.581	
12,700.00	10,300.00	12,675.06	10,296.00	51.35	51.18	-89.65	2,487.97	-128.98	659.99	557.66	102.33	6.450	
12,800.00	10,300.00	12,775.06	10,296.00	52.38	52.22	-89.65	2,587.97	-128.14	659.99	555.58	104.40	6.321	
12,900.00	10,300.00	12,875.06	10,296.00	53.43	53.28	-89.65	2,687.97	-127.30	659.99	553.47	106.52	6.196	
13,000.00	10,300.00	12,975.06	10,296.00	54.50	54.36	-89.65	2,787.96	-126.46	659.99	551.32	108.67	6.073	
13,100.00	10,300.00	13,075.06	10,296.00	55.59	55.46	-89.65	2,887.96	-125.63	659.99	549.13	110.86	5.953	
13,200.00	10,300.00	13,175.06	10,296.00	56.70	56.57	-89.65	2,987.96	-124.79	659.99	546.91	113.08	5.837	
13,300.00	10,300.00	13,275.06	10,296.00	57.82	57.70	-89.65	3,087.95	-123.95	659.99	544.66	115.33	5.723	
13,400.00	10,300.00	13,375.06	10,296.00	58.95	58.84	-89.65	3,187.95	-123.11	659.99	542.39	117.61	5.612	
13,500.00	10,300.00	13,475.06	10,296.00	60.10	59.99	-89.65	3,287.95	-122.27	659.99	540.08	119.91	5.504	
13,600.00	10,300.00	13,575.06	10,296.00	61.26	61.16	-89.65	3,387.94	-121.44	659.99	537.75	122.24	5.399	
13,700.00	10,300.00	13,675.06	10,296.00	62.43	62.34	-89.65	3,487.94	-120.60	660.00	535.40	124.60	5.297	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Phoenix Technology Services

## Anticollision Report



**Company:** Matador Resources  
**Project:** Eddy County, NM (NAD27 NME)  
**Reference Site:** Charlie Sweeney Federal 31-23S-28E  
**Site Error:** 0.00 usft  
**Reference Well:** 227H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Preliminary Plan 1

**Local Co-ordinate Reference:** Well 227H  
**TVD Reference:** RKB @ 3134.50usft (Patterson 297)  
**MD Reference:** RKB @ 3134.50usft (Patterson 297)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at** 2.00 sigma  
**Database:** Compass 5000 GCR  
**Offset TVD Reference:** Reference Datum

Offset Design Charlie Sweeney Federal 31-23S-28E - 223H - OH - Preliminary Plan 1												Offset Site Error:	0.00 usft
Survey Program: 0-PHX+MWD+HDGM												Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (")	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
13,800.00	10,300.00	13,775.06	10,296.00	63.62	63.53	-89.65	3,587.93	-119.76	660.00	533.02	126.98	5.198	
13,900.00	10,300.00	13,875.06	10,296.00	64.81	64.73	-89.65	3,687.93	-118.92	660.00	530.62	129.38	5.101	
14,000.00	10,300.00	13,975.06	10,296.00	66.02	65.94	-89.65	3,787.93	-118.08	660.00	528.20	131.80	5.008	
14,100.00	10,300.00	14,075.06	10,296.00	67.24	67.17	-89.65	3,887.92	-117.25	660.00	525.76	134.24	4.917	
14,200.00	10,300.00	14,175.06	10,296.00	68.46	68.40	-89.65	3,987.92	-116.41	660.00	523.30	136.69	4.828	
14,300.00	10,300.00	14,275.06	10,296.00	69.69	69.64	-89.65	4,087.92	-115.57	660.00	520.83	139.17	4.742	
14,400.00	10,300.00	14,375.06	10,296.00	70.94	70.88	-89.65	4,187.91	-114.73	660.00	518.34	141.66	4.659	
14,500.00	10,300.00	14,475.06	10,296.00	72.19	72.14	-89.65	4,287.91	-113.89	660.00	515.83	144.17	4.578	
14,600.00	10,300.00	14,575.06	10,296.00	73.44	73.40	-89.65	4,387.91	-113.06	660.00	513.31	146.69	4.499	
14,700.00	10,300.00	14,675.06	10,296.00	74.71	74.67	-89.65	4,487.90	-112.22	660.00	510.78	149.22	4.423	
14,800.00	10,300.00	14,775.06	10,296.00	75.98	75.95	-89.65	4,587.90	-111.38	660.00	508.23	151.77	4.349	
14,900.00	10,300.00	14,875.06	10,296.00	77.26	77.23	-89.65	4,687.90	-110.54	660.00	505.67	154.34	4.276	
15,000.00	10,300.00	14,975.06	10,296.00	78.54	78.52	-89.65	4,787.89	-109.70	660.01	503.10	156.91	4.206	
15,051.58	10,300.00	15,026.64	10,296.00	79.21	79.18	-89.65	4,839.47	-109.27	660.01	501.76	158.24	4.171	
15,087.64	10,300.00	15,059.17	10,296.00	79.67	79.60	-89.65	4,872.00	-109.00	660.02	500.89	159.13	4.148 SF	






# PATTERSON-UTI

Well Control

297



Made by Cameron  
(Shaffer Spherical)  
Clone Annular

PATTERSON-UTI # PS2-628

STYLE: New Shaffer Spherical

BORE 13 5/8" PRESSURE 5,000

HEIGHT: 48 1/2" WEIGHT: 13,800 lbs

PATTERSON-UTI # PC2-128

STYLE: New Cameron Type U

BORE 13 5/8" PRESSURE 10,000

RAMS: TOP 5" Pipe BTM Blinds

HEIGHT: 66 5/8" WEIGHT: 24,000 lbs

Length 40" Outlets 4" 10M

DSA 4" 10M x 2" 10M

PATTERSON-UTI # PC2-228

STYLE: New Cameron Type U

BORE 13 5/8" PRESSURE 10,000

RAMS: 5" Pipe

HEIGHT: 41 5/8" WEIGHT: 13,000 lbs


## WING VALVES




2" Check Valve




2" Manual Valve



2" Manual Valve




4" Manual Valve



4" Hydraulic Valve

MATADOR  
15K 4-STRING  
MQ-94



NOTE:  
DIMENSIONS SHOWN ON THIS DRAWING ARE  
ESTIMATES ONLY AND CAN VARY SIGNIFICANTLY  
DEPENDING ON RAW MATERIAL LENGTHS.  
NO GUARANTEE OF STACKUP HEIGHT IS IMPLIED.  
DIMENSIONS SHOWN SHOULD BE CONSIDERED  
FOR REFERENCE PURPOSES ONLY.

RESTRICTED CONFIDENTIAL DOCUMENT


THIS DRAWING AND ALL INFORMATION SHOWN HEREON ARE THE  
EXCLUSIVE PROPERTY OF SEABOARD INTERNATIONAL, INC. AND ARE  
SUBMITTED ON A CONFIDENTIAL BASIS ONLY. THE RECIPIENT AGREES  
NOT TO REPRODUCE THE DRAWING, TO RETURN IT UPON REQUEST, AND  
THAT NO DISCLOSURE OF THE DRAWING OR THE INFORMATION SHOWN  
HEREON WILL BE MADE TO A THIRD PARTY WITHOUT PRIOR WRITTEN  
CONSENT OF SEABOARD INTERNATIONAL, INC.

**WEIR**

15,000 PSI WELLHEAD & TREE ASSEMBLY  
13-3/8 X 9-5/8 X 7 X 4-1/2 X 2-3/8

DRAWN BY:	RPL	SCALE:	1:10	DATE:	18JAN16	REV:	
CHECKED BY:		DRAWING NO.:					
APPROVED BY:							

P-20986



**PATTERSON-UTI**  
DRILLING COMPANY LLC

CHOKE MANIFOLD  
TOW DUCK ARRANGEMENT  
RIG 250

R0297-D.001.LAY.09

COPYRIGHT 2014  
PATTERSON-UTI  
DRILLING COMPANY LLC  
CONFIDENTIAL AND PROPRIETARY  
NOT TO BE DISTRIBUTED

ALL RIGHTS RESERVED BY PATTERSON-UTI

THIS DOCUMENT IS THE PROPERTY OF PATTERSON-UTI DRILLING COMPANY LLC. IT IS TO BE USED ONLY FOR THE PROJECT AND LOCATION SPECIFICALLY IDENTIFIED HEREIN. IT IS NOT TO BE REPRODUCED, COPIED, OR DISTRIBUTED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF PATTERSON-UTI DRILLING COMPANY LLC. PATTERSON-UTI DRILLING COMPANY LLC ASSUMES NO LIABILITY FOR ANY DAMAGE OR INJURY RESULTING FROM THE USE OF THIS DOCUMENT. THE INFORMATION CONTAINED HEREIN IS NOT TO BE USED FOR ANY OTHER PURPOSES.

REVISION

DATE

BY



Midwest Hose  
& Specialty, Inc.

## Internal Hydrostatic Test Graph

Customer: Patterson

Pick Ticket #: 284918

December 8, 2014

### Hose Specifications

Hose Type

Ck

I.D.

3"

Length

10'

O.D.

4.79"

### Verification

Type of Fitting

4-1/16 10K

Die Size

5.37"

Coupling Method

Swage

Final O.D.

5.37"

Working Pressure

10000 PSI

Burst Pressure

Standard Safety Multiplier Applies


Hose Serial #

10490

Hose Assembly Serial #

284918-2

## Pressure Test



Test Pressure  
15000 PSI

Time Held at Test Pressure  
15 2/4 Minutes

Actual Burst Pressure

Peak Pressure  
15732 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Tyler Hill

Approved By: Ryan Adams



Midwest Hose  
& Specialty, Inc.

### Internal Hydrostatic Test Certificate

General Information		Hose Specifications	
Customer	PATTERSON B&E	Hose Assembly Type	Choke & Kill
MWH Sales Representative	AMY WHITE	Certification	API 7K
Date Assembled	12/8/2014	Hose Grade	MUD
Location Assembled	OKC	Hose Working Pressure	10000
Sales Order #	236404	Hose Lot # and Date Code	10490-01/13
Customer Purchase Order #	260471	Hose I.D. (Inches)	3"
Assembly Serial # (Pick Ticket #)	287918-2	Hose O.D. (Inches)	5.30"
Hose Assembly Length	10'	Armor (yes/no)	YES
Fittings			
End A		End B	
Stem (Part and Revision #)	R3.0X64WB	Stem (Part and Revision #)	R3.0X64WB
Stem (Heat #)	91996	Stem (Heat #)	91996
Ferrule (Part and Revision #)	RF3.0	Ferrule (Part and Revision #)	RF3.0
Ferrule (Heat #)	37DA5631	Ferrule (Heat #)	37DA5631
Connection (Part #)	4 1/16 10K	Connection (Part #)	4 1/16 10K
Connection (Heat #)		Connection (Heat #)	
Dies Used	5.37	Dies Used	5.37
Hydrostatic Test Requirements			
Test Pressure (psi)	15,000	Hose assembly was tested with ambient water temperature.	
Test Pressure Hold Time (minutes)	15 1/2		
Date Tested	Tested By		Approved By
12/8/2014			



Midwest Hose  
& Specialty, Inc.

### Certificate of Conformity

Customer: **PATTERSON B&E**

Customer P.O.# **260471**

Sales Order # **236404**

Date Assembled: **12/8/2014**

### Specifications

Hose Assembly Type: **Choke & Kill**

Assembly Serial # **287918-2**

Hose Lot # and Date Code **10490-01/13**

Hose Working Pressure (psi) **10000**

Test Pressure (psi) **15000**

We hereby certify that the above material supplied for the referenced purchase order to be true according to the requirements of the purchase order and current industry standards.

Supplier:

**Midwest Hose & Specialty, Inc.**

**3312 S I-35 Service Rd**

**Oklahoma City, OK 73129**

Comments:

Approved By

Date

**12/9/2014**



Midwest Hose  
& Specialty, Inc.

## Internal Hydrostatic Test Graph

December 9, 2014

Customer: Patterson

Pick Ticket #: 284918


### Hose Specifications

Hose Type: CK  
Length: 20'  
I.D.: 3"  
O.D.: 4.77"  
Working Pressure: 10000 PSI  
Burst Pressure: Standard Safety Multiplier Applies

### Verification

Type of Fitting: 4-1/16 10K  
Coupling Method: Swage  
Die Size: 5.37"  
Final O.D.: 5.40"  
Hose Serial #: 10490  
Hose Assembly Serial #: 284918-1

### Pressure Test



Test Pressure  
15000 PSI

Time Held at Test Pressure  
15 2/4 Minutes

Actual Burst Pressure

Peak Pressure  
15893 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Tyler Hill

Approved By: Ryan Adams



Midwest Hose  
& Specialty, Inc.

### Internal Hydrostatic Test Certificate

General Information		Hose Specifications	
Customer	PATTERSON B&E	Hose Assembly Type	Choke & Kill
MWH Sales Representative	AMY WHITE	Certification	API 7K
Date Assembled	12/8/2014	Hose Grade	MUD
Location Assembled	OKC	Hose Working Pressure	10000
Sales Order #	236404	Hose Lot # and Date Code	10490-01/13
Customer Purchase Order #	260471	Hose I.D. (Inches)	3"
Assembly Serial # (Pick Ticket #)	287918-1	Hose O.D. (Inches)	5.30"
Hose Assembly Length	20'	Armor (yes/no)	YES
Fittings			
End A		End B	
Stem (Part and Revision #)	R3.0X64WB	Stem (Part and Revision #)	R3.0X64WB
Stem (Heat #)	A141420	Stem (Heat #)	A141420
Ferrule (Part and Revision #)	RF3.0	Ferrule (Part and Revision #)	RF3.0
Ferrule (Heat #)	37DA5631	Ferrule (Heat #)	37DA5631
Connection (Part #)	4 1/16 10K	Connection (Part #)	4 1/16 10K
Connection (Heat #)	V3579	Connection (Heat #)	V3579
Dies Used	5.37	Dies Used	5.37
Hydrostatic Test Requirements			
Test Pressure (psi)	15,000	Hose assembly was tested with ambient water temperature.	
Test Pressure Hold Time (minutes)	15 1/2		
Date Tested	Tested By		Approved By
12/9/2014			





Midwest Hose  
& Specialty, Inc.

### Certificate of Conformity

Customer: **PATTERSON B&E**

Customer P.O.# **260471**

Sales Order # **236404**

Date Assembled: **12/8/2014**

### Specifications

Hose Assembly Type: **Choke & Kill**

Assembly Serial # **287918-1**

Hose Lot # and Date Code **10490-01/13**

Hose Working Pressure (psi) **10000**

Test Pressure (psi) **15000**

*We hereby certify that the above material supplied for the referenced purchase order to be true according to the requirements of the purchase order and current industry standards.*

Supplier:

**Midwest Hose & Specialty, Inc.**

**3312 S I-35 Service Rd**

**Oklahoma City, OK 73129**

Comments:

Approved By

Date

**12/9/2014**

# Internal Hydrostatic Test Graph




Midwest Hose  
& Specialty, Inc.

Customer: Patterson

Pick Ticket #: 284918

Hose Specifications		Verification	
Hose Type	Length	Type of Fitting	Coupling Method
Mud	70'	4.1/16.10K	Swage
I.D.	O.D.	Die Size	Final O.D.
3"	4.79"	5.37"	5.37"
Working Pressure	Burst Pressure	Hose Serial #	Hose Assembly Serial #
10000 PSI	Standard Safety Multiplier Applies	10490	284918-3



Test Pressure	Time Held at Test Pressure	Actual Burst Pressure	Peak Pressure
15000 PSI	16 3/4 Minutes		15410 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Tyler Hill

Approved By: Ryan Adams

*[Signature]*

*[Signature]*



Midwest Hose  
& Specialty, Inc.

### Internal Hydrostatic Test Certificate

General Information		Hose Specifications	
Customer	PATTERSON B&E	Hose Assembly Type	Choke & Kill
MWH Sales Representative	AMY WHITE	Certification	API 7K
Date Assembled	12/8/2014	Hose Grade	MUD
Location Assembled	OKC	Hose Working Pressure	10000
Sales Order #	236404	Hose Lot # and Date Code	10490-01/13
Customer Purchase Order #	260471	Hose I.D. (Inches)	3"
Assembly Serial # (Pick Ticket #)	287918-3	Hose O.D. (Inches)	5.23"
Hose Assembly Length	70'	Armor (yes/no)	YES
Fittings			
End A		End B	
Stem (Part and Revision #)	R3.0X64WB	Stem (Part and Revision #)	R3.0X64WB
Stem (Heat #)	A141420	Stem (Heat #)	A141420
Ferrule (Part and Revision #)	RF3.0	Ferrule (Part and Revision #)	RF3.0
Ferrule (Heat #)	37DA5631	Ferrule (Heat #)	37DA5631
Connection (Part #)	4 1/16 10K	Connection (Part #)	4 1/16 10K
Connection (Heat #)		Connection (Heat #)	
Dies Used	5.37	Dies Used	5.37
Hydrostatic Test Requirements			
Test Pressure (psi)	15,000	Hose assembly was tested with ambient water temperature.	
Test Pressure Hold Time (minutes)	16 3/4		
Date Tested	Tested By	Approved By	
12/9/2014			



Midwest Hose  
& Specialty, Inc.

### Certificate of Conformity

Customer: **PATTERSON B&E**

Customer P.O.# **260471**

Sales Order # **236404**

Date Assembled: **12/8/2014**

### Specifications

Hose Assembly Type: **Choke & Kill**

Assembly Serial # **287918-3**

Hose Lot # and Date Code **10490-01/13**

Hose Working Pressure (psi) **10000**

Test Pressure (psi) **15000**

We hereby certify that the above material supplied for the referenced purchase order to be true according to the requirements of the purchase order and current industry standards.

Supplier:

**Midwest Hose & Specialty, Inc.**

**3312 S I-35 Service Rd**

**Oklahoma City, OK 73129**


Comments:

Approved By

Date

**12/9/2014**

## Closed-Loop System




### Operating and Maintenance Plan:

During drilling operations, third party service companies will utilize solids control equipment to remove cuttings from the drilling fluids and collect it in haul-off bins. Equipment will be closely monitored at all times while drilling by the derrick man and the service company employees.

### Closure Plan:


During drilling operations, third party service companies will haul off drill solids and fluids to an approved disposal facility. At the end of the well, all closed loop equipment will be removed from the location.



**Schematic Closed Loop Drilling Rig\***

1. Pipe Rack
2. Drill Rig
3. House Trailers/ Offices
4. Generator/Fuel/Storage
5. Overflow-Frac Tank
6. Skids
7. Roll Offs
8. Hopper or Centrifuge
9. Mud Tanks
10. Loop Drive
11. Generator (only for use with centrifuge)

\*Not drawn to scale: Closed loop system requires at least 30 feet beyond mud tanks. Ideally 60 feet would be available




**Above: Centrifugal Closed Loop System**



Closed Loop Drilling System: Mud tanks to right (1)  
 Hopper in air to settle out solids (2)  
 Water return pipe (3)  
 Shaker between hopper and mud tanks (4)  
 Roll offs on skids (5)

#### Flow Chart for Drilling Fluids and Solids



# Rig Diagram


Rig Diagram  
Charlie Sweeney Fed Com 227H  
31-23S-28E  
SHL 190' FSL & 2160' FEL  
Eddy County, NM

Wind Direction Indicator

H2S Monitors

Briefing Areas

Prevailing Winds  
NORTH







## Hydrogen Sulfide Drilling Operations Plan

Matador Production Company

### 1 H2S safety instructions to the following:

- Characteristics of H2S
- Physical effects and hazards
- Principal and operation of H2S detectors, warning system and briefing areas
- Evacuation procedures, routes and first aid
- Proper use of safety equipment & life support systems
- Essential personnel meeting medical evaluation criteria will receive additional training on the proper use of 30min pressure demand air packs

### 2 H2S Detection and Alarm Systems:

- H2S sensor/detectors to be located on the drilling rig floor, in the base of the sub structure / cellar area, on the mud pits in the shale shaker area. Additional H2S detectors may be placed as deemed necessary
- An audio alarm system will be installed on the derrick floor and in the doghouse

### 3 Windsocks and / Wind Streamers:

- Windsocks at mud pit area should be high enough to be visible
- Windsock on the rig floor and / top of doghouse should be high enough to be visible

### 4 Condition Flags and Signs:

- Warning sign on access road to location
- Flags to be displayed on sign at entrance to location
  - Green Flag – Normal Safe Operation Condition
  - Yellow Flag – Potential Pressure and Danger
  - Red Flag – Danger (H2S present in dangerous concentrations) Only H2S trained personnel admitted on location

### 5 Well Control Equipment:

- See APD

### 6 Communications:

- While working under masks, chalkboards will be used for communications
- Hand signals will be used where chalk board is inappropriate
- Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at drilling foreman's trailer or living quarters.



#### 7 Drilling Stem Testing:

- No DST or cores are planned at this time

8 Drilling contractor supervisor will be required to be familiar with the effects H<sub>2</sub>S has on tubulars good and other mechanical equipment

9 If H<sub>2</sub>S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H<sub>2</sub>S scavengers if necessary

#### 11 Emergency Contacts

- See next page

H2S Contingency Plan Emergency Contacts  
Matador Production Company  
Sec. 31, 23S, 28E, Eddy County, NM

<b><u>Company Office</u></b>			
Matador Production Company	(972)-371-5200		
<b><u>Key Personnel</u></b>			
<b>Name</b>	<b>Title</b>	<b>Office</b>	<b>Mobile</b>
Billy Goodwin	Vice President Drilling	972-371-5210	817-522-2928
Gary Martin	Drilling Superintendent		601-669-1774
Dee Smith	Drilling Superintendent	972-371-5447	972-822-1010
Aaron Byrd	Drilling Engineer	972-371-5267	214-507-2333
	Construction Superintendent		
	Construction Superintendent		
<b><u>Artesia</u></b>			
Ambulance		911	
State Police		575-746-2703	
City Police		575-746-2703	
Sheriff's Office		575-746-9888	
Fire Department		575-746-2701	
Local Emergency Planning Committee		575-746-2122	
New Mexico Oil Conservation Division		575-748-1283	
<b><u>Carlsbad</u></b>			
Ambulance		911	
State Police		575-885-3137	
City Police		575-885-2111	
Sheriff's Office		575-887-7551	
Fire Department		575-887-3798	
Local Emergency Planning Committee		575-887-6544	
New Mexico Oil Conservation Division		575-887-6544	
<b><u>Santa Fe</u></b>			
New Mexico Emergency Response Commission (Santa Fe)		505-476-9600	
New Mexico Emergency Response Commission (Santa Fe) 24 hrs		505-827-9126	
New Mexico State Emergency Operations Center		505-476-9635	
<b><u>National</u></b>			
Carlsbad BLM		575-234-5972	
National Emergency Response Center (Washington, D.C.)		800-424-8802	
<b><u>Medical</u></b>			
Flight for Life- 4000 24th St.; Lubbock, TX		806-743-9911	
Aerocare- R3, Box 49F; Lubbock, TX		806-747-8923	
Med Flight Air Amb- 2301 Yale Blvd S.E., D3; Albuquerque, NM		505-842-4433	
SB Air Med Service- 2505 Clark Carr Loop S.E.; Albuquerque, NM		505-842-4949	
<b><u>Other</u></b>			
Boots & Coots IWC		800-256-9688	or 281-931-8884
Cudd Pressure Control		432-699-0139	or 432-563-3356
Haliburton		575-746-2757	
B.J. Services		575-746-3569	

# H2S Rig Diagram


Rig Diagram  
Charlie Sweeney Fed Com 227H  
31-23S-28E  
SHL 190' FSL & 2160' FEL  
Eddy County, NM

Wind Direction Indicator

H2S Monitors

Briefing Areas



Prevailing Winds  
NORTH



# Matador Production Company

CHARLIE SWEENEY FED COM  
31-23S-28E #227H  
H&S Contingency Plan:  
1 Mile Radius Map



Section 31, Township 23S, Range 28E  
Eddy County, New Mexico



NAD 1927 New Mexico State Plane East  
FIPS 3001 Feet

PERMITS  
Produced by  
Permits West, Inc.


Prepared by Permits West, Inc., May 25, 2016  
for Matador Production Company




# Matador Production Company

CHARLIE SWEENEY FED COM  
31-23S-28E #227H  
H2S Contingency Plan:  
2 Mile Radius Map


Section 31, Township 23S, Range 28E  
Eddy County, New Mexico





Surface Hole Location



NAD 1927 New Mexico State Plane East  
FPS 3001 Feet



Prepared by Permits West, Inc., May 25, 2018  
for Matador Production Company



Matador Production Company

SURFACE PLAN PAGE 1

Charlie Sweeney Fed Com 227H

SHL 190' FSL & 2160' FEL Sec. 31, T. 23 S., R. 28 E.

BHL 240' FNL & 1650' FEL Sec. 31, T. 23 S., R. 28 E.

Eddy County, NM

### Surface Use Plan

#### 1. ROAD DIRECTIONS & DESCRIPTIONS (See MAPS 1 - 4)

From the gas stations in Loving, NM...

Go South 1.0 mile on US 285 to a substation

Then turn right onto paved County Road 716 and continue South 0.4 mile

Turn right at a transfer station and go West 2.05 mi. on paved County Rd. 763

Then turn left and go South & SE 0.35 mile on a caliche road to a valve station

Then turn left at the valve station and go Southeast 1082.28' cross-country

Then turn left and go East 0.4 mile on an existing road

Then turn right and go South 326.53' cross-country to the proposed pad

Non-county roads will be maintained as needed to Gold Book standards. This includes pulling ditches, preserving the crown, and cleaning culverts. This will be done at least once a year, and more often as needed. Caliche will be hauled from existing caliche pits on private land in NWSE 1-24s-28e and NWSW 6-24s-29e.

#### 2. ROAD TO BE BUILT OR UPGRADED (See MAPS 3 & 4)

Road from County Road 763 to the valve station is 2 lanes, crowned, and surfaced with caliche. No upgrade is needed.

All of the road (2/3 mile) from the valve station to the pad will be crowned, have a 14' wide driving surface, and be surfaced with caliche. Maximum disturbed width = 20'. Maximum grade = 2%. Maximum cut or fill = 1'. A cattle guard will be installed in the existing fence. No culvert or vehicle turn out is needed.

Matador Production Company

SURFACE PLAN PAGE 2

Charlie Sweeney Fed Com 31-23S-28E 227H

SHL 190' FSL & 2160' FEL Sec. 31, T. 23 S., R. 28 E.

BHL 240' FNL & 1650' FEL Sec. 31, T. 23 S., R. 28 E.

Eddy County, NM

### 3. EXISTING WELLS (See MAP 2)

Existing oil, gas, water, disposal, and P & A wells are within a mile. There are no injection wells within a mile radius.

### 4. PROPOSED PRODUCTION FACILITIES (See MAPS 3 & 8-11)

Oil tanks, water tanks, meter runs, separators, and a flare will be installed on the north side of the pad (see preceding diagram). A  $\approx 6$ " O. D. steel buried gas line and  $\approx 6$ " O. D. HDPE buried saltwater disposal line will be laid 627.47' east and then south in the same trench to Longwood Midstream's Black River Gathering System. A 3-phase raptor safe overhead power line will be built 3661.69' north the gas plant power line that is under construction.

### 5. WATER SUPPLY (See MAPS 3, 12, & 13)

Water will be piped 3750.25' via a  $\approx 10$ " O. D. surface "Fast Line" from an existing frac pond on private land in S2NW4 31-23s-28e.

### 6. CONSTRUCTION MATERIALS & METHODS (see MAPS 5-7)

NM One Call (811) will be notified before construction starts. A temporary fence will be built on the east side of the pad before construction starts to keep construction equipment out of an old canal. Top  $\approx 6$ " of soil and brush will be stockpiled north of the pad. Pipe racks will be to the west. A closed loop drilling system will be used. Caliche will be hauled from existing caliche pits on private land in NWSE 1-24s-28e and NWSW 6-24s-29e.



Matador Production Company

SURFACE PLAN PAGE 3

Charlie Sweeney Fed Com 31-23S-28E 227H

SHL 190' FSL & 2160' FEL Sec. 31, T. 23 S., R. 28 E.

BHL 240' FNL & 1650' FEL Sec. 31, T. 23 S., R. 28 E.

Eddy County, NM

#### 7. WASTE DISPOSAL

All trash will be placed in a portable trash cage. It will be hauled to the Eddy County landfill. There will be no trash burning. Contents (drill cuttings, mud, salts, and other chemicals) of the mud tanks will be hauled to CRI's state approved (NM-01-0006) disposal site. Human waste will be disposed of in chemical toilets and hauled to the Carlsbad wastewater treatment plant.

#### 8. ANCILLARY FACILITIES

There will be no airstrip or camp. Camper trailers will be on location for the company man, tool pusher, or mud logger.

#### 9. WELL SITE LAYOUT

See Rig Diagram for depictions of the well pad, trash cage, access onto the location, parking, living facilities, and rig orientation.

#### 10. RECLAMATION

Interim reclamation will be completed within 6 months of completing the last well on the pad. (A variance is requested for the intervening wells.) Interim reclamation will consist of shrinking the pad  $\approx 21\%$  by removing caliche and reclaiming the south (30') and east (125') sides. This will leave 2.87 acres for the production equipment, 5 pump jacks, and tractor-trailer turn around. Disturbed areas will be contoured to match pre-construction grades. Soil and brush will be evenly spread over disturbed areas. Disturbed areas will be seeded in accordance with the surface owner's requirements. Enough stockpiled topsoil will be retained to cover the remainder of the pad when the wells are plugged. Once the last well is plugged, then the remainder of the pad will be similarly reclaimed within 6 months of plugging. Noxious weeds will be controlled.

Matador Production Company

SURFACE PLAN PAGE 4

Charlie Sweeney Fed Com 31-23S-28E 227H

SHL 190' FSL & 2160' FEL Sec. 31, T. 23 S., R. 28 E.

BHL 240' FNL & 1650' FEL Sec. 31, T. 23 S., R. 28 E.

Eddy County, NM

## 11. SURFACE OWNER

All construction will be on private surface.

Matador Resources Company has a private surface owner agreement with Vickie Connally (R211 Ash Road, Loving NM 88256) for the well site, pipelines, power line, and road in NWSW, S2S2, NWSE, & SWSE Section 31, T. 23 S., R. 28 E. and pipelines in Lot 2 Section 6, T. 24 S., R. 28 E.; all Eddy County, NM.

Matador Resources Company has a private surface owner agreement with Jacob & Merrellee Moore (1011 Bounds Road, Loving NM 88256) for their portion (NWNE 31-23s-28e) of the power line.

Matador Resources Company has a private surface owner agreement with Longwood Midstream Delaware LLC (5400 LBJ Freeway, Suite 1500, Dallas TX 75240) for their portion (Lot 2 31-23s-28e) of the water (Fast Line) pipeline.


## 12. OTHER INFORMATION

On site inspection was held with Trish Bad Bear (BLM) on December 10, 2015.

Lone Mountain submitted archaeology report NMCRIS-135215 on February 29, 2016 for the well site and will file a report for the associated infrastructure.



SECTION 31, TOWNSHIP 23-S, RANGE 28-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO



PRODUCTION FACILITY & INTERIM RECLAMATION DIAGRAM

# LEGEND

SECTION LINE

LEASE NAME & WELL NO.: CHARLIE SWEENEY FED COM 31-23S-28E #227H

#227H LATITUDE N 32.2546332 #227H LONGITUDE W 104.1247363

SCALE: 1" = 100'

0' 50' 100'

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM, EAST ZONE OF THE NORTH AMERICAN DATUM 1927, U.S. SURVEY FEET

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY MATADOR PRODUCTION COMPANY. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ORIGINAL DOCUMENT SIZE: 8.5" X 11"

S:\SURVEY\MATADOR\_RESOURCES\CHARLIE\_SWEENEY\_FED\_COM\_31-23S-28E\_227H\FINAL\_PRODUCTS\LO\_CHARLIE\_SWEENEY\_FED\_COM\_31-23S-28E\_227H\_REV3.DWG 4/28/2016 8:04:15 AM jstovall



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 197 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX: (817) 744-7548  
2803 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX: (432) 682-1743  
WWW.TOPOGRAPHIC.COM

July 2, 2016

To Who it May Concern:

Matador Resources Company has a private surface owner agreement with Vickie Connally (R211 Ash Road, Loving NM 88256) for the Charlie Sweeney Fed Com 31-23s-28e 227H well site, pipelines, power line, and road in NWSW, S2S2, NWSE, & SWSE Section 31, T. 23 S., R. 28 E. and pipelines in Lot 2 Section 6, T. 24 S., R. 28 E.; all Eddy County, NM.

Matador Resources Company has a private surface owner agreement with Jacob & Merrellee Moore (1011 Bounds Road, Loving NM 88256) for their portion (NWNE 31-23s-28e) of the power line.

Matador Resources Company has a private surface owner agreement with Longwood Midstream Delaware LLC (5400 LBJ Freeway, Suite 1500, Dallas TX 75240) for their portion (Lot 2 31-23s-28e) of the water (Fast Line) pipeline.

A handwritten signature in black ink, appearing to read "B. Wood". The signature is stylized with a large, looped initial "B" and a cursive "Wood".

Brian Wood

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## **V. SPECIAL REQUIREMENT(S)**

### **Cave/Karst Surface Mitigation**

The following stipulations will be applied to minimize impacts during construction, drilling and production.

#### **Construction:**

In the advent that any underground voids are opened up during construction activities, construction activities will be halted and the BLM will be notified immediately.

#### **No Blasting:**

No blasting will be utilized for pad construction. The pad will be constructed and leveled by adding the necessary fill and caliche.

#### **Pad Berming:**

The entire perimeter of the well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.

- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g. caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised. (Any access road crossing the berm cannot be lower than the berm height.)

#### **Tank Battery Liners and Berms:**

Tank battery locations and all facilities will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

#### **Leak Detection System:**

A method of detecting leaks is required. The method could incorporate gauges to measure loss, situating valves and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present. Leak detection plan will be submitted to BLM for approval.

**Automatic Shut-off Systems:**

Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

**Cave/Karst Subsurface Mitigation**

The following stipulations will be applied to protect cave/karst and ground water concerns:

**Rotary Drilling with Fresh Water:**

Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

**Directional Drilling:**

Kick off for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

**Lost Circulation:**

ALL lost circulation zones from the surface to the base of the cave occurrence zone will be logged and reported in the drilling report.

Regardless of the type of drilling machinery used, if a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cave-bearing zone, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

**Abandonment Cementing:**

Upon well abandonment in high cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

**Pressure Testing:**

Annual pressure monitoring will be performed by the operator on all casing annuli and reported in a sundry notice. If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### **D. FEDERAL MINERAL MATERIALS PIT**

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

### **F. EXCLOSURE FENCING (CELLARS & PITS)**



**Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

**G. ON LEASE ACCESS ROADS****Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

**Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

**Crowning**

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

**Ditching**

Ditching shall be required on both sides of the road.

**Turnouts**


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

**Drainage**

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill out sloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

#### **Cross Section of a Typical Lead-off Ditch**



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

#### **Formula for Spacing Interval of Lead-off Ditches**

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

#### **Cattle guards**

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

#### **Fence Requirement**

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

#### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

### Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

## **VII. PRODUCTION (POST DRILLING)**

### **A. WELL STRUCTURES & FACILITIES**

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

#### **Chemical and Fuel Secondary Containment and Exclosure Screening**

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

#### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

#### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

### **B. PIPELINES**

#### **BURIED PIPELINE STIPULATIONS**

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of

the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.

6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.

7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:

- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
- Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
- The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)

8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.

9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

<input checked="" type="checkbox"/> ( X ) seed mixture 1	<input type="checkbox"/> ( ) seed mixture 3
<input type="checkbox"/> ( ) seed mixture 2	<input type="checkbox"/> ( ) seed mixture 4
<input type="checkbox"/> ( ) seed mixture 2/LPC	<input type="checkbox"/> ( ) Aplomado Falcon Mixture

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches [that are not otherwise fenced, screened, or netted] to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

#### STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

**A copy of the Grant and attachments, including stipulations, survey plat(s) and/or map(s), shall be on location during construction. BLM personnel may request to review a copy of your permit during construction to ensure compliance with all stipulations.**



Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, Holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC § 2601 *et seq.* (1982) with regard to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant (*see* 40 CFR, Part 702-799 and in particular, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193). Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. Holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. § 9601, *et seq.* or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, *et seq.*) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way Holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way Holder on the Right-of-Way. This provision applies without regard to whether a release is caused by Holder, its agent, or unrelated third parties.

4. Holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. Holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of Holder including, but not limited to: construction, operation, maintenance, and termination of the facility;
- b. Activities of other parties including, but not limited to:
  - (1) Land clearing
  - (2) Earth-disturbing and earth-moving work
  - (3) Blasting
  - (4) Vandalism and sabotage;

c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of Holder, regardless of fault. Upon failure of Holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he/she deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of Holder. Such action by the Authorized Officer shall not relieve Holder of any responsibility as provided herein.

6. All construction and maintenance activity shall be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline shall be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline shall be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity shall be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation shall be allowed unless approved in writing by the Authorized Officer.

8. Holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky of dune areas, the pipeline shall be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When

necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines shall be less than or equal to 4 inches and a working pressure below 125 psi.

### **C. ELECTRIC LINES**

## STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

**A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.**

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.
5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such

modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes from the poles removed.

## **VIII. INTERIM RECLAMATION**

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

## **IX. FINAL ABANDONMENT & RECLAMATION**

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

### **Seed Mixture 1 for Loamy Sites**

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed shall be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed shall be planted using a drill equipped with a depth regulator to ensure proper depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture shall be evenly and uniformly planted over the disturbed area (small/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed shall be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre shall be doubled. The seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains lovegrass ( <i>Eragrostis intermedia</i> )	0.5
Sand dropseed ( <i>Sporobolus cryptandrus</i> )	1.0
Sideoats grama ( <i>Bouteloua curtipendula</i> )	5.0
Plains bristlegrass ( <i>Setaria macrostachya</i> )	2.0

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

**PECOS DISTRICT  
DRILLING OPERATIONS  
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	Matador Operating Company
LEASE NO.:	NMNM121941
WELL NAME & NO.:	224H-Charlie Sweeney Fed Com
SURFACE HOLE FOOTAGE:	189'S & 665'E
BOTTOM HOLE FOOTAGE:	240'N & 990'E
LOCATION:	Section 31, T. 23 S., R. 28 E., NMPM
COUNTY:	Eddy County, New Mexico

**A. DRILLING OPERATIONS REQUIREMENTS**

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

1. **Although Hydrogen Sulfide has not been reported in the area, it is always a potential hazard. It is recommended that monitoring equipment be onsite for potential Hydrogen Sulfide. If H<sub>2</sub>S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, report measured amounts and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM**



office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

## **B. CASING**

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

**Centralizers required on surface casing per Onshore Order 2.III.B.1.f.**

### **Wait on cement (WOC) for Water Basin:**

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.

**Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.**

**No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.**

### **Medium Cave/Karst**

**Possibility of water flows in the Castile and Salado.**

**Possibility of lost circulation in the Red Beds, Rustler, and Delaware.**

**Abnormal pressures may be encountered upon penetrating the 3rd Bone Spring Sandstone and all subsequent formations.**

1. The 13-3/8 inch surface casing shall be set at approximately 350 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature

survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

- b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

**If cement does not circulate to surface on the intermediate casing, the cement on the production casing must come to surface.**

- 2. The minimum required fill of cement behind the **9-5/8** inch first intermediate casing, which shall be set at approximately **2450** feet, is:
  - ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.**
- 3. The minimum required fill of cement behind the **7** inch second intermediate casing, is:
  - ☒ Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification.

**Formation below the 7" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe and the mud weight for the bottom of the hole. Report results to BLM office.**

**Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.**

- 4. The minimum required fill of cement behind the **4-1/2** inch production casing is:
  - ☒ Cement as proposed by operator. Operator shall provide method of verification. **Excess calculates to 23% - Additional cement may be required.**

5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

### C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).
3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi
4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **9-5/8** inch first intermediate casing shoe shall be **3000 (3M)** psi.
5. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 7 inch second intermediate casing shoe shall be **5000 (5M)** psi.

**5M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.**

6. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before

cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the **Wolfcamp** formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

#### **D. DRILLING MUD**

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the **Wolfcamp** formation, and shall be used until production casing is run and cemented.

**E. DRILL STEM TEST**

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

**F. WASTE MATERIAL AND FLUIDS**


All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**G. SPECIAL REQUIREMENT (S)**

**Well Name:**

Operator must submit a sundry to remove 'Com' from the well name.



### NMOCD CONDITION OF APPROVAL

The *New!* Gas Capture Plan (GCP) notice is posted on the NMOCD website under Announcements. The Plan became effective May 1, 2016. A copy of the GCP form is included with the NOTICE and is also in our FORMS section under Unnumbered Forms. Please review filing dates for all applicable activities currently approved or pending and submit accordingly. Failure to file a GCP may jeopardize the operator's ability to obtain C-129 approval to flare gas after the initial 60-day completion period.