

APR 04 2017

FORM APPROVED  
OMB No. 1004-0137  
Expires October 31, 2014

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

RECEIVED

APPLICATION FOR PERMIT TO DRILL OR REENTER

|   |   |   |
|---|---|---|
| 1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER  |   | 5. Lease Serial No.<br>NMLC062300                                     |
| 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone  |   | 6. If Indian, Allottee or Tribe Name                                  |
| 2. Name of Operator<br>DEVON ENERGY PRODUCTION COMPANY LP   |   | 7. If Unit or CA Agreement, Name and No.<br>NMNM134249                |
| 3a. Address<br>333 West Sheridan Avenue Oklahoma City OK  |   | 8. Lease Name and Well No.<br>BIG SINKS DRAW 25-24 FED 424H           |
| 3b. Phone No. (include area code)<br>(405)552-6571  |   | 9. API Well No.<br>30-015-44123                                       |
| 4. Location of Well (Report location clearly and in accordance with any State requirements.)<br>At surface SENE / 2440 FNL / 610 FEL / LAT 32.1018386 / LONG -103.725024<br>At proposed prod. zone NENE / 330 FNL / 660 FEL / LAT 32.122156 / LONG -103.7251654 |   | 10. Field and Pool, or Exploratory<br>COTTON DRAW, SOUTH / DELAWARE   |
| 11. Sec., T. R. M. or Blk. and Survey or Area<br>SEC 25 / T25S / R31E / NMP   |   | 12. County or Parish<br>EDDY  |
| 13. State<br>NM   |   | 14. Distance in miles and direction from nearest town or post office* |
| 15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)<br>610 feet   | 16. No. of acres in lease<br>2479.82                | 17. Spacing Unit dedicated to this well<br>240                        |
| 18. Distance from proposed location* to nearest well, drilling, completed, 50 feet applied for, on this lease, ft.  | 19. Proposed Depth<br>8223 feet / 15379 feet        | 20. BLM/BIA Bond No. on file<br>FED: CO1104                           |
| 21. Elevations (Show whether DF, KDB, RT, GL, etc.)<br>3340 feet  | 22. Approximate date work will start*<br>10/07/2018 | 23. Estimated duration<br>45 days                                     |

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification   |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM.             |

|  |   |                    |
|--|---|--------------------|
| 25. Signature<br>(Electronic Submission)           | Name (Printed/Typed)<br>Linda Good / Ph: (405)552-6558  | Date<br>11/21/2016 |
| Title<br>Regulatory Compliance Professional        |   |                    |
| Approved by (Signature)<br>(Electronic Submission) | Name (Printed/Typed)<br>Cody Layton / Ph: (575)234-5959 | Date<br>03/24/2017 |
| Title<br>Supervisor Multiple Resources             |   |                    |

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

APPROVED WITH CONDITIONS

Ref 4/2/17

District I  
1625 N. French Dr., Hobbs, NM 88240  
Phone: (575) 393-6161 Fax: (575) 393-0720  
District II  
311 S. First St., Artesia, NM 88210  
Phone: (575) 748-1283 Fax: (575) 748-9720  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
Phone: (505) 334-6178 Fax: (505) 334-6170  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505  
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico  
Energy, Minerals & Natural Resources Department  
OIL CONSERVATION DIVISION  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Form C-102  
Revised August 1, 2011  
Submit one copy to appropriate  
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

|  |  |   |
|--|--|---|
| <sup>1</sup> API Number<br><b>30-015-44123</b> | <sup>2</sup> Pool Code<br><b>96757</b>                                     | <sup>3</sup> Pool Name<br><b>Cotton Draw; Delaware, South</b> |
| <sup>4</sup> Property Code<br><b>317584</b>    | <sup>5</sup> Property Name<br><b>BIG SINKS DRAW 25-24 FED COM</b>          |   |
| <sup>7</sup> OGRID No.<br><b>6137</b>          | <sup>8</sup> Operator Name<br><b>DEVON ENERGY PRODUCTION COMPANY, L.P.</b> | <sup>6</sup> Well Number<br><b>424H</b>                       |
|  |  | <sup>9</sup> Elevation<br><b>3339.6</b>                       |

<sup>10</sup> Surface Location

| UL or lot no. | Section   | Township    | Range       | Lot Idn | Feet from the | North/South line | Feet from the | East/West line | County      |
|---------------|-----------|-------------|-------------|---------|---------------|------------------|---------------|----------------|-------------|
| <b>H</b>      | <b>25</b> | <b>25 S</b> | <b>31 E</b> |         | <b>2440</b>   | <b>NORTH</b>     | <b>610</b>    | <b>EAST</b>    | <b>EDDY</b> |

<sup>11</sup> Bottom Hole Location If Different From Surface

| UL or lot no. | Section   | Township    | Range       | Lot Idn | Feet from the | North/South line | Feet from the | East/West line | County      |
|---------------|-----------|-------------|-------------|---------|---------------|------------------|---------------|----------------|-------------|
| <b>A</b>      | <b>24</b> | <b>25 S</b> | <b>31 E</b> |         | <b>330</b>    | <b>NORTH</b>     | <b>660</b>    | <b>EAST</b>    | <b>EDDY</b> |

|  |                               |                                  |                         |
|--|-------------------------------|----------------------------------|-------------------------|
| <sup>12</sup> Dedicated Acres<br><b>240.00</b> | <sup>13</sup> Joint or Infill | <sup>14</sup> Consolidation Code | <sup>15</sup> Order No. |
|--|-------------------------------|----------------------------------|-------------------------|

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

|   |  |  |  |  |  |
|---|--|--|--|--|--|
| <p>NW CORNER SEC. 24<br/>LAT. = 32.1230396°N<br/>LONG. = 103.7401298°W<br/>NMSP EAST (FT)<br/>N = 409003.35<br/>E = 724978.97</p> <p>W/4 CORNER SEC. 24<br/>LAT. = 32.1157841°N<br/>LONG. = 103.7401427°W<br/>NMSP EAST (FT)<br/>N = 408363.89<br/>E = 724989.50</p> <p>SECTION CORNER<br/>LAT. = 32.1085258°N<br/>LONG. = 103.7401774°W<br/>NMSP EAST (FT)<br/>N = 403723.39<br/>E = 724993.28</p> <p>W/4 CORNER SEC. 25<br/>LAT. = 32.1012691°N<br/>LONG. = 103.7401953°W<br/>NMSP EAST (FT)<br/>N = 401083.51<br/>E = 725002.28</p> <p>SW CORNER SEC. 25<br/>LAT. = 32.0940086°N<br/>LONG. = 103.7402111°W<br/>NMSP EAST (FT)<br/>N = 398442.24<br/>E = 725011.90</p>  |  | <p>N/4 CORNER SEC. 24<br/>LAT. = 32.1230698°N<br/>LONG. = 103.7316050°W<br/>NMSP EAST (FT)<br/>N = 409028.98<br/>E = 727618.03</p> <p>SECTION CORNER<br/>LAT. = 32.1085358°N<br/>LONG. = 103.7316143°W<br/>NMSP EAST (FT)<br/>N = 403741.74<br/>E = 727644.60</p> <p>S/4 CORNER SEC. 25<br/>LAT. = 32.0939992°N<br/>LONG. = 103.7316305°W<br/>NMSP EAST (FT)<br/>N = 398453.55<br/>E = 727669.16</p> |  | <p>NE CORNER SEC. 24<br/>LAT. = 32.1230606°N<br/>LONG. = 103.7230333°W<br/>NMSP EAST (FT)<br/>N = 409040.55<br/>E = 730271.66</p> <p>E/4 CORNER SEC. 24<br/>SCALED</p> <p>SECTION CORNER<br/>LAT. = 32.1085514°N<br/>LONG. = 103.7230430°W<br/>NMSP EAST (FT)<br/>N = 403762.33<br/>E = 730298.57</p> <p>E/4 CORNER SEC. 25<br/>LAT. = 32.1013031°N<br/>LONG. = 103.7230592°W<br/>NMSP EAST (FT)<br/>N = 401125.49<br/>E = 730309.71</p> <p>SE CORNER SEC. 25<br/>LAT. = 32.0940530°N<br/>LONG. = 103.7230584°W<br/>NMSP EAST (FT)<br/>N = 398488.02<br/>E = 730323.84</p> |  |
| <p><b>BIG SINKS DRAW 25-24 FED COM 424H</b><br/>ELEV. = 3339.6'<br/>LAT. = 32.1018386°N (NAD83)<br/>LONG. = 103.7250240°W<br/>NMSP EAST (FT)<br/>N = 401316.84<br/>E = 729698.95</p> <p><b>NOTE:</b> LATITUDE AND LONGITUDE COORDINATES ARE SHOWN USING THE NORTH AMERICAN DATUM OF 1983 (NAD83). LISTED NEW MEXICO STATE PLANE EAST COORDINATES ARE GRID (NAD83). BASIS OF BEARING AND DISTANCES USED ARE NEW MEXICO STATE PLANE EAST COORDINATES MODIFIED TO THE SURFACE. ELEVATION VALUES ARE NAVD 88.</p> <p><b>QUARTER CORNER</b><br/>LAT. = 32.1085358°N<br/>LONG. = 103.7316143°W<br/>NMSP EAST (FT)<br/>N = 403741.74<br/>E = 727644.60</p> <p><b>SURFACE LOCATION</b></p>                                |  |  |  |  |  |
| <p><b>17 OPERATOR CERTIFICATION</b><br/>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered into by this organization.</p> <p>Signature: <i>Linda Good</i> Date: <b>11/21/2016</b></p> <p>Printed Name: <b>Linda Good</b></p> <p>E-mail Address: <b>linda.good@dvn.com</b></p> |  |  |  |  |  |
| <p><b>18 SURVEYOR CERTIFICATION</b><br/>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p><b>JOHN F. JARAMILLO</b><br/>JUNE 20, 2016<br/>Date of Survey: <b>12797</b></p> <p>Signature: <i>[Signature]</i><br/>Certificate Number: <b>JOHN F. JARAMILLO, PLS 12797</b><br/>SURVEY NO. 4741</p>   |  |  |  |  |  |

**APD ID:** 10400008145

**Submission Date:** 11/21/2016

**Highlight**  
All Changes

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Federal/Indian APD:** FED

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Well Type:** OIL WELL

**Well Work Type:** Drill

### Application

#### Section 1 - General

**APD ID:** 10400008145

**Tie to previous NOS?**
**Submission Date:** 11/21/2016

**BLM Office:** CARLSBAD

**User:** Linda Good

**Title:** Regulatory Compliance  
Professional

**Federal/Indian APD:** FED

**Is the first lease penetrated for production Federal or Indian?** FED

**Lease number:** NMLC062300

**Lease Acres:** 2479.82

**Surface access agreement in place?**
**Allotted?**
**Reservation:**
**Agreement in place?** YES

**Federal or Indian agreement:** FEDERAL

**Agreement number:** NMNM134249

**Agreement name:**
**Keep application confidential?** YES

**Permitting Agent?** NO

**APD Operator:** DEVON ENERGY PRODUCTION COMPANY LP

**Operator letter of designation:**
**Keep application confidential?** YES

#### Operator Info

**Operator Organization Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Operator Address:** 333 West Sheridan Avenue

**Zip:** 73102

**Operator PO Box:**
**Operator City:** Oklahoma City **State:** OK

**Operator Phone:** (405)552-6571

**Operator Internet Address:** aletha.dewbre@dvn.com

#### Section 2 - Well Information

**Well in Master Development Plan?** NO

**Mater Development Plan name:**
**Well in Master SUPO?** NO

**Master SUPO name:**
**Well in Master Drilling Plan?** NO

**Master Drilling Plan name:**

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Well API Number:**

**Field/Pool or Exploratory?** Field and Pool

**Field Name:** COTTON DRAW,  
SOUTH

**Pool Name:** DELAWARE

**Is the proposed well in an area containing other mineral resources?** NATURAL GAS,OIL,POTASH

**Describe other minerals:**

**Is the proposed well in a Helium production area?** N

**Use Existing Well Pad?** NO

**New surface disturbance?**

**Type of Well Pad:** MULTIPLE WELL

**Multiple Well Pad Name:** BIG  
SINKS DRAW 25 FED COM/BIG  
SINKS 25-24 FED COM

**Number:** 4H/424H

**Well Class:** HORIZONTAL

**Number of Legs:**

**Well Work Type:** Drill

**Well Type:** OIL WELL

**Describe Well Type:**

**Well sub-Type:** INFILL

**Describe sub-type:**

**Distance to town:**

**Distance to nearest well:** 50 FT

**Distance to lease line:** 610 FT

**Reservoir well spacing assigned acres Measurement:** 240 Acres

**Well plat:** BSD 25-24 Fed Com 424H\_C-102\_signed\_11-21-2016.pdf

**Well work start Date:** 10/07/2018

**Duration:** 45 DAYS

### Section 3 - Well Location Table

**Survey Type:** RECTANGULAR

**Describe Survey Type:**

**Datum:** NAD83

**Vertical Datum:** NAVD88

**Survey number:** 4741

**STATE:** NEW MEXICO

**Meridian:** NEW MEXICO PRINCIPAL County: EDDY

**Latitude:** 32.1018386

**Longitude:** -103.725024

**SHL**

**Elevation:** 3340

**MD:** 0

**TVD:** 0

**Leg #: 1**

**Lease Type:** FEDERAL

**Lease #:** NMLC062300

**NS-Foot:** 2440

**NS Indicator:** FNL

**EW-Foot:** 610

**EW Indicator:** FEL

**Twsp:** 25S

**Range:** 31E

**Section:** 25

**Aliquot:** SENE

**Lot:**

**Tract:**

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

|          |                             |                                       |                     |
|----------|-----------------------------|---------------------------------------|---------------------|
|          | <b>STATE:</b> NEW MEXICO    | <b>Meridian:</b> NEW MEXICO PRINCIPAL | <b>County:</b> EDDY |
|          | <b>Latitude:</b> 32.1018386 | <b>Longitude:</b> -103.725024         |                     |
| KOP      | <b>Elevation:</b> -4320     | <b>MD:</b> 7660                       | <b>TVD:</b> 7660    |
| Leg #: 1 | <b>Lease Type:</b> FEDERAL  | <b>Lease #:</b> NMLC062300            |                     |
|          | <b>NS-Foot:</b> 2440        | <b>NS Indicator:</b> FNL              |                     |
|          | <b>EW-Foot:</b> 610         | <b>EW Indicator:</b> FEL              |                     |
|          | <b>Twsp:</b> 25S            | <b>Range:</b> 31E                     | <b>Section:</b> 25  |
|          | <b>Aliquot:</b> SENE        | <b>Lot:</b>                           | <b>Tract:</b>       |
|          | <b>STATE:</b> NEW MEXICO    | <b>Meridian:</b> NEW MEXICO PRINCIPAL | <b>County:</b> EDDY |
|          | <b>Latitude:</b> 32.1018386 | <b>Longitude:</b> -103.725024         |                     |
| PPP      | <b>Elevation:</b> 3340      | <b>MD:</b> 0                          | <b>TVD:</b> 0       |
| Leg #: 1 | <b>Lease Type:</b> FEDERAL  | <b>Lease #:</b> NMLC062300            |                     |
|          | <b>NS-Foot:</b> 2440        | <b>NS Indicator:</b> FNL              |                     |
|          | <b>EW-Foot:</b> 610         | <b>EW Indicator:</b> FEL              |                     |
|          | <b>Twsp:</b> 25S            | <b>Range:</b> 31E                     | <b>Section:</b> 25  |
|          | <b>Aliquot:</b> SENE        | <b>Lot:</b>                           | <b>Tract:</b>       |
|          | <b>STATE:</b> NEW MEXICO    | <b>Meridian:</b> NEW MEXICO PRINCIPAL | <b>County:</b> EDDY |
|          | <b>Latitude:</b> 32.122156  | <b>Longitude:</b> -103.7251654        |                     |
| EXIT     | <b>Elevation:</b> -4883     | <b>MD:</b> 15379                      | <b>TVD:</b> 8223    |
| Leg #: 1 | <b>Lease Type:</b> FEDERAL  | <b>Lease #:</b> NMLC061869            |                     |
|          | <b>NS-Foot:</b> 330         | <b>NS Indicator:</b> FNL              |                     |
|          | <b>EW-Foot:</b> 660         | <b>EW Indicator:</b> FEL              |                     |
|          | <b>Twsp:</b> 25S            | <b>Range:</b> 31E                     | <b>Section:</b> 24  |
|          | <b>Aliquot:</b> NENE        | <b>Lot:</b>                           | <b>Tract:</b>       |
|          | <b>STATE:</b> NEW MEXICO    | <b>Meridian:</b> NEW MEXICO PRINCIPAL | <b>County:</b> EDDY |
|          | <b>Latitude:</b> 32.122156  | <b>Longitude:</b> -103.7251654        |                     |
| BHL      | <b>Elevation:</b> -4883     | <b>MD:</b> 15379                      | <b>TVD:</b> 8223    |
| Leg #: 1 | <b>Lease Type:</b> FEDERAL  | <b>Lease #:</b> NMLC061869            |                     |
|          | <b>NS-Foot:</b> 330         | <b>NS Indicator:</b> FNL              |                     |
|          | <b>EW-Foot:</b> 660         | <b>EW Indicator:</b> FEL              |                     |

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Twsp:** 25S

**Range:** 31E

**Section:** 24

**Aliquot:** NENE

**Lot:**

**Tract:**

### Drilling Plan

#### Section 1 - Geologic Formations

**ID:** Surface formation

**Name:** UNKNOWN

**Lithology(ies):**

ALLUVIUM

**Elevation:** 3332

**True Vertical Depth:** 0

**Measured Depth:** 0

**Mineral Resource(s):**

NONE

**Is this a producing formation?** N

**ID:** Formation 1

**Name:** RUSTLER

**Lithology(ies):**

DOLOMITE

**Elevation:** 2688

**True Vertical Depth:** 652

**Measured Depth:** 652

**Mineral Resource(s):**

NONE

**Is this a producing formation?** N

**ID:** Formation 2

**Name:** SALADO

**Lithology(ies):**

SALT

**Elevation:** 2295

**True Vertical Depth:** 1045

**Measured Depth:** 1045

**Mineral Resource(s):**

NONE

**Is this a producing formation?** N

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**ID:** Formation 3

**Name:** BASE OF SALT

**Lithology(ies):**

SALT

**Elevation:** -773

**True Vertical Depth:** 4113

**Measured Depth:** 4113

**Mineral Resource(s):**

NONE

**Is this a producing formation?** N

**ID:** Formation 4

**Name:** DELAWARE

**Lithology(ies):**

SANDSTONE

**Elevation:** -1011

**True Vertical Depth:** 4351

**Measured Depth:** 4351

**Mineral Resource(s):**

NATURAL GAS

OIL

**Is this a producing formation?** Y

**ID:** Formation 5

**Name:** LAMAR

**Lithology(ies):**

SANDSTONE

**Elevation:** -1015

**True Vertical Depth:** 4355

**Measured Depth:** 4355

**Mineral Resource(s):**

NATURAL GAS

OIL

**Is this a producing formation?** N

**ID:** Formation 6

**Name:** BELL CANYON

**Lithology(ies):**

SANDSTONE

**Elevation:** -1031

**True Vertical Depth:** 4371

**Measured Depth:** 4371

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Mineral Resource(s):**

NATURAL GAS

OIL

**Is this a producing formation?** N

**ID:** Formation 7

**Name:** CHERRY CANYON

**Lithology(ies):**

SANDSTONE

**Elevation:** -1981

**True Vertical Depth:** 5321

**Measured Depth:** 5321

**Mineral Resource(s):**

NATURAL GAS

OIL

**Is this a producing formation?** N

**ID:** Formation 8

**Name:** BRUSHY CANYON

**Lithology(ies):**

SANDSTONE

**Elevation:** -3368

**True Vertical Depth:** 6700

**Measured Depth:** 6700

**Mineral Resource(s):**

NATURAL GAS

OIL

**Is this a producing formation?** N

**ID:** Formation 9

**Name:** BRUSHY CANYON

**Lithology(ies):**

SANDSTONE

**Elevation:** -4818

**True Vertical Depth:** 8150

**Measured Depth:** 8150

**Mineral Resource(s):**

NATURAL GAS

OIL

**Is this a producing formation?** Y



**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

## Section 2 - Blowout Prevention

---

**Pressure Rating (PSI):** 3M

**Rating Depth:** 8160

**Equipment:** BOP/BOPE will be installed per Onshore Oil & Gas Order #2 requirements prior to drilling below 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 3M will be installed on the wellhead system. BOP/BOPE will be tested by an independent service company per Onshore Oil & Gas Order #2 requirements and MASP (Maximum Anticipated Surface Pressure) calculations. If the system is upgraded, all the components installed will be functional and tested.

**Requesting Variance?** YES

**Variance request:** A variance is requested for the use of a flexible choke line from the BOP stack to the choke manifold. See attached for specs for hydrostatic test chart.

**Testing Procedure:** A multi-bowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

**Choke Diagram Attachment:**

BSD 25-24 Fed Com 424H\_3M BOPE

**BOP Diagram Attachment:**

BSD 25-24 Fed Com 424H\_3M BOPE

---

**Pressure Rating (PSI):** 3M

**Rating Depth:** 4150

**Equipment:** BOP/BOPE will be installed per Onshore Oil & Gas Order #2 requirements prior to drilling below 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 3M will be installed on the wellhead system. BOP/BOPE will be tested by an independent service company per Onshore Oil & Gas Order #2 requirements and MASP (Maximum Anticipated Surface Pressure) calculations. If the system is upgraded, all the components installed will be functional and tested.

**Requesting Variance?** YES

**Variance request:** A variance is requested for the use of a flexible choke line from the BOP stack to the choke manifold. See attached for specs for hydrostatic test chart.

**Testing Procedure:** A multi-bowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

**Choke Diagram Attachment:**

BSD 25-24 Fed Com 424H\_3M BOPE

**BOP Diagram Attachment:**

BSD 25-24 Fed Com 424H\_3M BOPE

---

## Section 3 - Casing

---

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**String Type:** SURFACE

**Other String Type:**

**Hole Size:** 17.5

**Top setting depth MD:** 0

**Top setting depth TVD:** 0

**Top setting depth MSL:** -4883

**Bottom setting depth MD:** 965

**Bottom setting depth TVD:** 965

**Bottom setting depth MSL:** -5848

**Calculated casing length MD:** 965

**Casing Size:** 13.375

**Other Size**

**Grade:** J-55

**Other Grade:**

**Weight:** 48

**Joint Type:** STC

**Other Joint Type:**

**Condition:** NEW

**Inspection Document:**

**Standard:** API

**Spec Document:**

**Tapered String?:** N

**Tapered String Spec:**

### **Safety Factors**

**Collapse Design Safety Factor:** 1.74

**Burst Design Safety Factor:** 2.45

**Joint Tensile Design Safety Factor type:** BUOYANT

**Joint Tensile Design Safety Factor:** 4.13

**Body Tensile Design Safety Factor type:** BUOYANT

**Body Tensile Design Safety Factor:** 4.13

**Casing Design Assumptions and Worksheet(s):**

BSD 25-24 Fed Com 424H\_SurfCsg Ass\_11-21-2016.pdf

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**String Type:** INTERMEDIATE

**Other String Type:**

**Hole Size:** 12.25

**Top setting depth MD:** 0

**Top setting depth TVD:** 0

**Top setting depth MSL:** -4883

**Bottom setting depth MD:** 4150

**Bottom setting depth TVD:** 4150

**Bottom setting depth MSL:** -9033

**Calculated casing length MD:** 4150

**Casing Size:** 9.625

**Other Size**

**Grade:** J-55

**Other Grade:**

**Weight:** 40

**Joint Type:** LTC

**Other Joint Type:**

**Condition:** NEW

**Inspection Document:**

**Standard:** API

**Spec Document:**

**Tapered String?:** N

**Tapered String Spec:**

### **Safety Factors**

**Collapse Design Safety Factor:** 1.19

**Burst Design Safety Factor:** 1.42

**Joint Tensile Design Safety Factor type:** BUOYANT

**Joint Tensile Design Safety Factor:** 3.98

**Body Tensile Design Safety Factor type:** BUOYANT

**Body Tensile Design Safety Factor:** 3.98

**Casing Design Assumptions and Worksheet(s):**

BSD 25-24 Fed Com 424H\_Int Csg Ass\_11-21-2016.pdf

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**String Type:** PRODUCTION

**Other String Type:**

**Hole Size:** 8.75

**Top setting depth MD:** 0

**Top setting depth TVD:** 0

**Top setting depth MSL:** -4883

**Bottom setting depth MD:** 15378

**Bottom setting depth TVD:** 8225

**Bottom setting depth MSL:** -13108

**Calculated casing length MD:** 15378

**Casing Size:** 5.5

**Other Size**

**Grade:** P-110

**Other Grade:**

**Weight:** 17

**Joint Type:** BUTT

**Other Joint Type:**

**Condition:** NEW

**Inspection Document:**

**Standard:** API

**Spec Document:**

**Tapered String?:** N

**Tapered String Spec:**

### **Safety Factors**

**Collapse Design Safety Factor:** 2.18

**Burst Design Safety Factor:** 2.7

**Joint Tensile Design Safety Factor type:** BUOYANT

**Joint Tensile Design Safety Factor:** 3.21

**Body Tensile Design Safety Factor type:** BUOYANT

**Body Tensile Design Safety Factor:** 3.21

**Casing Design Assumptions and Worksheet(s):**

BSD 25-24 Fed Com 424H\_ProdCsg Ass\_11-21-2016.pdf

---

### **Section 4 - Cement**

**Casing String Type:** SURFACE

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Stage Tool Depth:**

**Lead**

**Top MD of Segment:** 0

**Bottom MD Segment:** 965

**Cement Type:** C

**Additives:** 1% Calcium Chloride

**Quantity (sks):** 754

**Yield (cu.ff./sk):** 1.34

**Density:** 14.8

**Volume (cu.ft.):** 1010

**Percent Excess:** 50

**Casing String Type:** INTERMEDIATE

**Stage Tool Depth:**

**Lead**

**Top MD of Segment:** 0

**Bottom MD Segment:** 3150

**Cement Type:** C

**Additives:** Poz (Fly Ash): 6% BWOC  
Bentonite + 5% BWOW Sodium  
Chloride + 0.125 lbs/sks Poly-E-Flake

**Quantity (sks):** 695

**Yield (cu.ff./sk):** 1.85

**Density:** 12.9

**Volume (cu.ft.):** 1285

**Percent Excess:** 30

**Tail**

**Top MD of Segment:** 3150

**Bottom MD Segment:** 4150

**Cement Type:** H

**Quantity (sks):** 306

**Yield (cu.ff./sk):** 1.33

**Additives:** 0.125 lbs/sks Poly-R-Flake

**Volume (cu.ft.):** 407

**Percent Excess:** 30

**Density:** 14.8

**Casing String Type:** PRODUCTION

**Stage Tool Depth:**

**Lead**

**Top MD of Segment:** 3950

**Bottom MD Segment:** 8100

**Cement Type:** TUNED

**Additives:** N/A

**Quantity (sks):** 401

**Yield (cu.ff./sk):** 3.27

**Density:** 9

**Volume (cu.ft.):** 1310

**Percent Excess:** 25

**Tail**

**Top MD of Segment:** 8100

**Bottom MD Segment:** 15378

**Cement Type:** H

**Additives:** Poz (Fly Ash): 6% BWOC  
Bentonite + 5% BWOW Sodium  
Chloride + 0.125 lbs/sks Poly-E-Flake

**Quantity (sks):** 1915

**Yield (cu.ff./sk):** 1.2

**Density:** 14.5

**Volume (cu.ft.):** 2298

**Percent Excess:** 25

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

## Section 5 - Circulating Medium

**Mud System Type:** Closed

**Will an air or gas system be Used?** NO

**Description of the equipment for the circulating system in accordance with Onshore Order #2:**

**Diagram of the equipment for the circulating system in accordance with Onshore Order #2:**

**Describe what will be on location to control well or mitigate other conditions:** Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all time

**Describe the mud monitoring system utilized:** PVT/Pason/Visual Monitoring

### Circulating Medium Table

|                                    |                                       |
|------------------------------------|---------------------------------------|
| <b>Top Depth:</b> 965              | <b>Bottom Depth:</b> 4150             |
| <b>Mud Type:</b> SALT SATURATED    |                                       |
| <b>Min Weight (lbs./gal.):</b> 10  | <b>Max Weight (lbs./gal.):</b> 11     |
| <b>Density (lbs/cu.ft.):</b>       | <b>Gel Strength (lbs/100 sq.ft.):</b> |
| <b>PH:</b>                         | <b>Viscosity (CP):</b> 2              |
| <b>Filtration (cc):</b>            | <b>Salinity (ppm):</b>                |
| <b>Additional Characteristics:</b> |                                       |
| <b>Top Depth:</b> 4150             | <b>Bottom Depth:</b> 15378            |
| <b>Mud Type:</b> WATER-BASED MUD   |                                       |
| <b>Min Weight (lbs./gal.):</b> 8.5 | <b>Max Weight (lbs./gal.):</b> 9.3    |
| <b>Density (lbs/cu.ft.):</b>       | <b>Gel Strength (lbs/100 sq.ft.):</b> |
| <b>PH:</b>                         | <b>Viscosity (CP):</b> 12             |
| <b>Filtration (cc):</b>            | <b>Salinity (ppm):</b>                |
| <b>Additional Characteristics:</b> |                                       |

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Top Depth:** 0

**Bottom Depth:** 965

**Mud Type:** WATER-BASED MUD

**Min Weight (lbs./gal.):** 8.5

**Max Weight (lbs./gal.):** 9

**Density (lbs/cu.ft.):**

**Gel Strength (lbs/100 sq.ft.):**

**PH:**

**Viscosity (CP):** 2

**Filtration (cc):**

**Salinity (ppm):**

**Additional Characteristics:**

## Section 6 - Test, Logging, Coring

**List of production tests including testing procedures, equipment and safety measures:**

Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.

**List of open and cased hole logs run in the well:**

CALIPER,DS,GR,MWD,MUDLOG

**Coring operation description for the well:**

N/A

## Section 7 - Pressure

**Anticipated Bottom Hole Pressure:** 3700

**Anticipated Surface Pressure:** 1890.94

**Anticipated Bottom Hole Temperature(F):** 140

**Anticipated abnormal pressures, temperatures, or potential geologic hazards?** NO

**Describe:**

**Contingency Plans geohazards description:**

**Contingency Plans geohazards attachment:**

**Hydrogen Sulfide drilling operations plan required?** YES

**Hydrogen sulfide drilling operations plan:**

BSD 25-24 Fed Com 424H\_H2S Plan\_11-21-2016.pdf

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

## Section 8 - Other Information

**Proposed horizontal/directional/multi-lateral plan submission:**

BSD 25-24 Fed Com 424H\_Dir Plan\_11-21-2016.pdf

**Other proposed operations facets description:**

Multi-bowl Verbiage, Multi-bowl Wellhead, Closed Loop Design Plan, Production Cement Contingency

**Other proposed operations facets attachment:**

BSD 25-24 Fed Com 424H\_MB Verb\_11-21-2016.pdf

BSD 25-24 Fed Com 424H\_MB Wellhd\_11-21-2016.pdf

BSD 25-24 Fed Com 424H\_Closed Loop\_11-21-2016.pdf

BSD 25-24 Fed Com 424H\_ProdCmtContg\_11-21-2016.pdf

**Other Variance attachment:**

BSD 25-24 Fed Com 424H\_Co-flex\_11-21-2016.pdf

SUPD

## Section 1 - Existing Roads

**Will existing roads be used?** YES

**Existing Road Map:**

BSD 25-24 Fed Com 424H\_Ex AccessRd\_11-21-2016.pdf

BSD 25-24 Fed Com 424H\_Ex Lease Rd\_11-21-2016.pdf

**Existing Road Purpose:** ACCESS,FLUID TRANSPORT

**Row(s) Exist?** YES

**ROW ID(s)**

**ID:**

**Do the existing roads need to be improved?** YES

**Existing Road Improvement Description:** Improve road to accommodate Drilling and Completion operations.

**Existing Road Improvement Attachment:**

## Section 2 - New or Reconstructed Access Roads

**Will new roads be needed?** NO



**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

### Section 3 - Location of Existing Wells

**Existing Wells Map?** YES

**Attach Well map:**

BSD 25-24 Fed Com 424H\_1 Mile Map\_11-21-2016.pdf

**Existing Wells description:**

### Section 4 - Location of Existing and/or Proposed Production Facilities

**Submit or defer a Proposed Production Facilities plan?** DEFER

**Estimated Production Facilities description:** All flowlines will be buried going to the Big Sinks 25 CTB 2.

### Section 5 - Location and Types of Water Supply

#### Water Source Table

**Water source use type:** STIMULATION

**Water source type:** RECYCLED

**Describe type:**

**Source latitude:**

**Source longitude:**

**Source datum:**

**Water source permit type:** OTHER

**Source land ownership:** FEDERAL

**Water source transport method:** PIPELINE,TRUCKING

**Source transportation land ownership:** FEDERAL

**Water source volume (barrels):** 85000

**Source volume (acre-feet):** 10.955914

**Source volume (gal):** 3570000

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Water source and transportation map:**

BSD 25-24 Fed Com 424H\_Wtr Xfr Map\_11-21-2016.pdf

**Water source comments:** The attached Water Transfer Map is a proposal only and the final route and documentation will be provided by a Devon contractor prior to installation. When available Devon will always follow existing disturbance.

**New water well?** NO

## **New Water Well Info**

**Well latitude:**

**Well Longitude:**

**Well datum:**

**Well target aquifer:**

**Est. depth to top of aquifer(ft):**

**Est thickness of aquifer:**

**Aquifer comments:**

**Aquifer documentation:**

**Well depth (ft):**

**Well casing type:**

**Well casing outside diameter (in.):**

**Well casing inside diameter (in.):**

**New water well casing?**

**Used casing source:**

**Drilling method:**

**Drill material:**

**Grout material:**

**Grout depth:**

**Casing length (ft.):**

**Casing top depth (ft.):**

**Well Production type:**

**Completion Method:**

**Water well additional information:**

**State appropriation permit:**

**Additional information attachment:**

## **Section 6 - Construction Materials**

**Construction Materials description:** Dirt fill and caliche will be used to construct well pad.

**Construction Materials source location attachment:**

BSD 25-24 Fed Com 424H\_Caliche Pit\_01-19-2017.pdf

## **Section 7 - Methods for Handling Waste**

**Waste type:** DRILLING

**Waste content description:** Water based cuttings.

**Amount of waste:** 1650 barrels

**Waste disposal frequency :** Daily

**Safe containment description:** N/A

**Safe containmant attachment:**

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Waste disposal type:** HAUL TO COMMERCIAL FACILITY      **Disposal location ownership:** COMMERCIAL

**Disposal type description:**

**Disposal location description:** All cutting will be hauled to Sundance, R360, or equivalent.

**Waste type:** COMPLETIONS/STIMULATION

**Waste content description:** Flow back water during completion operations.

**Amount of waste:** 3000                  barrels

**Waste disposal frequency :** One Time Only

**Safe containment description:** N/A

**Safe containmant attachment:**

**Waste disposal type:** HAUL TO COMMERCIAL FACILITY      **Disposal location ownership:** COMMERCIAL

**Disposal type description:**

**Disposal location description:** Various disposal locations in Lea and Eddy counties.

**Waste type:** FLOWBACK

**Waste content description:** Produced water during flowback operations. This amount is a daily average during flowback (BWPD).

**Amount of waste:** 1500                  barrels

**Waste disposal frequency :** Daily

**Safe containment description:** N/A

**Safe containmant attachment:**

**Waste disposal type:** ON-LEASE INJECTION      **Disposal location ownership:** PRIVATE

**Disposal type description:**

**Disposal location description:** One of three company owned SWD facilities in the area: CDU 181, CDU 89, CDU 84.

**Waste type:** PRODUCED WATER

**Waste content description:** Produced water during production operations. This amount is a daily average during the first year of production (BWPD).

**Amount of waste:** 1000                  barrels

**Waste disposal frequency :** Daily

**Safe containment description:** N/A

**Safe containmant attachment:**

**Waste disposal type:** ON-LEASE INJECTION      **Disposal location ownership:** PRIVATE

**Disposal type description:**

**Disposal location description:** One of three company owned SWD facilities in the area: CDU 181, CDU 89, CDU 84.

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

### **Reserve Pit**

**Reserve Pit being used?** NO

**Temporary disposal of produced water into reserve pit?**

**Reserve pit length (ft.)**

**Reserve pit width (ft.)**

**Reserve pit depth (ft.)**

**Reserve pit volume (cu. yd.)**

**Is at least 50% of the reserve pit in cut?**

**Reserve pit liner**

**Reserve pit liner specifications and installation description**

### **Cuttings Area**

**Cuttings Area being used?** NO

**Are you storing cuttings on location?** NO

**Description of cuttings location**

**Cuttings area length (ft.)**

**Cuttings area width (ft.)**

**Cuttings area depth (ft.)**

**Cuttings area volume (cu. yd.)**

**Is at least 50% of the cuttings area in cut?**

**WCuttings area liner**

**Cuttings area liner specifications and installation description**

### **Section 8 - Ancillary Facilities**

**Are you requesting any Ancillary Facilities?:** NO

**Ancillary Facilities attachment:**

**Comments:**

### **Section 9 - Well Site Layout**

**Well Site Layout Diagram:**

BSD 25-24 Fed Com 424H\_Rig Layout\_11-21-2016.pdf

**Comments:**

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

## Section 10 - Plans for Surface Reclamation

**Type of disturbance:** NEW

**Recontouring attachment:**

**Drainage/Erosion control construction:** All areas disturbed shall be reclaimed as early and as nearly as practicable to their original condition or their final land use and shall be maintained to control dust and minimize erosion to the extent practicable.

**Drainage/Erosion control reclamation:** Topsoils and subsoils shall be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns. The disturbed area then shall be reseeded in the first favorable growing season.

**Wellpad long term disturbance (acres):** 2.191

**Wellpad short term disturbance (acres):** 3.778

**Access road long term disturbance (acres):** 0

**Access road short term disturbance (acres):** 0

**Pipeline long term disturbance (acres):** 3.1915014

**Pipeline short term disturbance (acres):** 5.319169

**Other long term disturbance (acres):** 0

**Other short term disturbance (acres):** 0

**Total long term disturbance:** 5.3825016

**Total short term disturbance:** 9.097169

**Reconstruction method:** Operator will use Best Management Practices "BMP" to mechanically recontour to obtain the desired outcome.

**Topsoil redistribution:** Topsoils shall be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns.

**Soil treatment:** Topsoils shall be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns.

**Existing Vegetation at the well pad:**

**Existing Vegetation at the well pad attachment:**

**Existing Vegetation Community at the road:**

**Existing Vegetation Community at the road attachment:**

**Existing Vegetation Community at the pipeline:**

**Existing Vegetation Community at the pipeline attachment:**

**Existing Vegetation Community at other disturbances:**

**Existing Vegetation Community at other disturbances attachment:**

**Non native seed used?** NO

**Non native seed description:**

**Seedling transplant description:**

**Will seedlings be transplanted for this project?** NO

**Seedling transplant description attachment:**

**Will seed be harvested for use in site reclamation?** NO

**Seed harvest description:**

**Seed harvest description attachment:**

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

## Seed Management

### Seed Table

**Seed type:**

**Seed source:**

**Seed name:**

**Source name:**

**Source address:**

**Source phone:**

**Seed cultivar:**

**Seed use location:**

**PLS pounds per acre:**

**Proposed seeding season:**

### Seed Summary

**Total pounds/Acre:**

| Seed Type | Pounds/Acre |
|-----------|-------------|
|-----------|-------------|

**Seed reclamation attachment:**

### Operator Contact/Responsible Official Contact Info

**First Name:** Mark

**Last Name:** Smith

**Phone:** (575)746-5559

**Email:** mark.smith@dvn.com

**Seedbed prep:**

**Seed BMP:**

**Seed method:**

**Existing invasive species?** NO

**Existing invasive species treatment description:**

**Existing invasive species treatment attachment:**

**Weed treatment plan description:** Maintain weeds on an as need basis.

**Weed treatment plan attachment:**

**Monitoring plan description:** Monitor as needed.

**Monitoring plan attachment:**

**Success standards:** N/A

**Pit closure description:** N/A

**Pit closure attachment:**

## Section 11 - Surface Ownership

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Disturbance type:** WELL PAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Disturbance type:** PIPELINE

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Disturbance type:** NEW ACCESS ROAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Disturbance type:** EXISTING ACCESS ROAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**



**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

## Section 12 - Other Information

**Right of Way needed?** NO

**Use APD as ROW?**

**ROW Type(s):**

### ROW Applications

**SUPO Additional Information:** Electric Survey, Flowline Survey

**Use a previously conducted onsite?** NO

**Previous Onsite information:**

### Other SUPO Attachment

BSD 25-24 Fed Com 424H\_Electric\_11-21-2016.PDF

BSD 25-24 Fed Com 424H\_Flowline\_11-21-2016.PDF

PWD

## Section 1 - General

**Would you like to address long-term produced water disposal?** NO

## Section 2 - Lined Pits

**Would you like to utilize Lined Pit PWD options?** NO

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Lined pit PWD on or off channel:**

**Lined pit PWD discharge volume (bbl/day):**

**Lined pit specifications:**

**Pit liner description:**

**Pit liner manufacturers information:**

**Precipitated solids disposal:**

**Describe precipitated solids disposal:**

**Precipitated solids disposal permit:**

**Lined pit precipitated solids disposal schedule:**

**Lined pit precipitated solids disposal schedule attachment:**

**Lined pit reclamation description:**

**Lined pit reclamation attachment:**

**Leak detection system description:**

**Leak detection system attachment:**

**Lined pit Monitor description:**

**Lined pit Monitor attachment:**

**Lined pit: do you have a reclamation bond for the pit?**

**Is the reclamation bond a rider under the BLM bond?**

**Lined pit bond number:**

**Lined pit bond amount:**

**Additional bond information attachment:**

### **Section 3 - Unlined Pits**

**Would you like to utilize Unlined Pit PWD options? NO**

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Unlined pit PWD on or off channel:**

**Unlined pit PWD discharge volume (bbl/day):**

**Unlined pit specifications:**

**Precipitated solids disposal:**

**Describe precipitated solids disposal:**

**Precipitated solids disposal permit:**

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Unlined pit precipitated solids disposal schedule:**

**Unlined pit precipitated solids disposal schedule attachment:**

**Unlined pit reclamation description:**

**Unlined pit reclamation attachment:**

**Unlined pit Monitor description:**

**Unlined pit Monitor attachment:**

**Do you propose to put the produced water to beneficial use?**

**Beneficial use user confirmation:**

**Estimated depth of the shallowest aquifer (feet):**

**Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?**

**TDS lab results:**

**Geologic and hydrologic evidence:**

**State authorization:**

**Unlined Produced Water Pit Estimated percolation:**

**Unlined pit: do you have a reclamation bond for the pit?**

**Is the reclamation bond a rider under the BLM bond?**

**Unlined pit bond number:**

**Unlined pit bond amount:**

**Additional bond information attachment:**

## **Section 4 - Injection**

**Would you like to utilize Injection PWD options? NO**

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Injection PWD discharge volume (bbl/day):**

**Injection well mineral owner:**

**Injection well type:**

**Injection well number:**

**Injection well name:**

**Assigned injection well API number?**

**Injection well API number:**

**Injection well new surface disturbance (acres):**

**Minerals protection information:**

**Mineral protection attachment:**

**Underground Injection Control (UIC) Permit?**

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**UIC Permit attachment:**

## **Section 5 - Surface Discharge**

**Would you like to utilize Surface Discharge PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Surface discharge PWD discharge volume (bbl/day):**

**Surface Discharge NPDES Permit?**

**Surface Discharge NPDES Permit attachment:**

**Surface Discharge site facilities information:**

**Surface discharge site facilities map:**

## **Section 6 - Other**

**Would you like to utilize Other PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Other PWD discharge volume (bbl/day):**

**Other PWD type description:**

**Other PWD type attachment:**

**Have other regulatory requirements been met?**

**Other regulatory requirements attachment:**

## **Bond Info**

### **Bond Information**

**Federal/Indian APD:** FED

**BLM Bond number:** CO1104

**BIA Bond number:**

**Do you have a reclamation bond?** NO

**Is the reclamation bond a rider under the BLM bond?**

**Is the reclamation bond BLM or Forest Service?**

**BLM reclamation bond number:**

**Forest Service reclamation bond number:**

**Forest Service reclamation bond attachment:**

**Reclamation bond number:**

**Operator Name:** DEVON ENERGY PRODUCTION COMPANY LP

**Well Name:** BIG SINKS DRAW 25-24 FED COM

**Well Number:** 424H

**Reclamation bond amount:**

**Reclamation bond rider amount:**

**Additional reclamation bond information attachment:**

### Operator Certification

#### Operator Certification

*I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.*

**NAME:** Linda Good

**Signed on:** 11/21/2016

**Title:** Regulatory Compliance Professional

**Street Address:** 333 West Sheridan Avenue

**City:** Oklahoma City

**State:** OK

**Zip:** 73102

**Phone:** (405)552-6558

**Email address:** Linda.Good@dvn.com

#### Field Representative

**Representative Name:** Ray Vaz

**Street Address:** 6488 Seven Rivers Hwy

**City:** Artesia

**State:** NM

**Zip:** 88210

**Phone:** (575)748-1871

**Email address:** ray.vaz@dvn.com

### Payment Info

#### Payment

**APD Fee Payment Method:** PAY.GOV


**pay.gov Tracking ID:** 25V4D60Q




# FLOWLINE PLAT (400672XYZ)

MULTI-USE ROW FOR 6" GAS LIFT & 6" POLY FIBER FLEX FLOWLINE FROM BIG SINKS DRAW "25" CTB TO  
BIG SINKS DRAW 25-24 FED COM 424H WITH LATERALS TO  
BIG SINKS DRAW 25-24 FED COM 421H, 422H, & 423H

DEVON ENERGY PRODUCTION COMPANY, L.P.  
CENTERLINE SURVEY OF A PIPELINE CROSSING  
SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
JUNE 28, 2016



SEE NEXT SHEET (2-4) FOR DESCRIPTION



## GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

## SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 29 DAY OF JUNE 2016

*Filimon F. Jaramillo*  
FILIMON F. JARAMILLO, PLS. 12797

MADRON SURVEYING, INC.  
301 SOUTH CANAL  
CARLSBAD, NEW MEXICO 88220  
Phone (575) 234-3341

SHEET: 1-4

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SURVEY NO. 4746

# FLOWLINE PLAT (400672XYZ)

MULTI-USE ROW FOR 6" GAS LIFT & 6" POLY FIBER FLEX FLOWLINE FROM BIG SINKS DRAW "25" CTB TO  
BIG SINKS DRAW 25-24 FED COM 424H WITH LATERALS TO  
BIG SINKS DRAW 25-24 FED COM 421H, 422H, & 423H

## DEVON ENERGY PRODUCTION COMPANY, L.P. CENTERLINE SURVEY OF A PIPELINE CROSSING SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. EDDY COUNTY, STATE OF NEW MEXICO JUNE 28, 2016

### DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

MAIN LINE TO BIG SINKS DRAW 25-24 FED COM 424H

BEGINNING AT A POINT WITHIN THE SW/4 NW/4 OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE WEST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S42°19'21"W, A DISTANCE OF 513.91 FEET; THENCE N00°00'03"W A DISTANCE OF 151.05 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED; THENCE N89°52'53"E A DISTANCE OF 4351.73 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED; THENCE S00°00'35"W A DISTANCE OF 131.28 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE EAST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S59°01'05"E, A DISTANCE OF 712.47 FEET;

SAID STRIP OF LAND BEING 4634.06 FEET OR 280.85 RODS IN LENGTH, CONTAINING 3.192 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

|           |              |            |             |
|-----------|--------------|------------|-------------|
| SW/4 NW/4 | 1130.62 L.F. | 68.52 RODS | 0.779 ACRES |
| SE/4 NW/4 | 1327.15 L.F. | 80.43 RODS | 0.914 ACRES |
| SW/4 NE/4 | 1327.42 L.F. | 80.45 RODS | 0.914 ACRES |
| SE/4 NE/4 | 848.87 L.F.  | 51.45 RODS | 0.585 ACRES |

LATERAL TO BIG SINKS DRAW 25-24 FED COM 421H

BEGINNING AT A POINT WITHIN THE SW/4 NW/4 OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE WEST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S67°37'10"W, A DISTANCE OF 1399.73 FEET; THENCE S00°00'24"W A DISTANCE OF 58.56 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE WEST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S69°52'14"W, A DISTANCE OF 1378.49 FEET;

SAID STRIP OF LAND BEING 58.56 FEET OR 3.55 RODS IN LENGTH, CONTAINING 0.040 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

|           |            |           |             |
|-----------|------------|-----------|-------------|
| SW/4 NW/4 | 58.56 L.F. | 3.55 RODS | 0.040 ACRES |
|-----------|------------|-----------|-------------|

LATERAL TO BIG SINKS DRAW 25-24 FED COM 422H

BEGINNING AT A POINT WITHIN THE SE/4 NW/4 OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE WEST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S68°22'12"W, A DISTANCE OF 1446.20 FEET; THENCE S00°00'49"W A DISTANCE OF 58.34 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE WEST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S70°32'59"W, A DISTANCE OF 1425.71 FEET;

SAID STRIP OF LAND BEING 58.34 FEET OR 3.54 RODS IN LENGTH, CONTAINING 0.040 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

|           |            |           |             |
|-----------|------------|-----------|-------------|
| SE/4 NW/4 | 58.34 L.F. | 3.54 RODS | 0.040 ACRES |
|-----------|------------|-----------|-------------|

LATERAL TO BIG SINKS DRAW 25-24 FED COM 423H

BEGINNING AT A POINT WITHIN THE SW/4 NE/4 OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE EAST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S75°36'44"E, A DISTANCE OF 1993.31 FEET; THENCE S00°00'44"W A DISTANCE OF 130.93 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE EAST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S79°18'47"E, A DISTANCE OF 1964.91 FEET;

SAID STRIP OF LAND BEING 130.93 FEET OR 7.93 RODS IN LENGTH, CONTAINING 0.090 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

|           |             |           |             |
|-----------|-------------|-----------|-------------|
| SW/4 NE/4 | 130.93 L.F. | 7.93 RODS | 0.090 ACRES |
|-----------|-------------|-----------|-------------|

### SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 29 DAY OF JUNE 2016

### GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING IS NMSP EAST MODIFIED TO SURFACE COORDINATES.

MADRON SURVEYING, INC.  
301 SOUTH CANAL  
CARLSBAD, NEW MEXICO 88220  
Phone (575) 234-3341  
FILMON F. JARAMILLO PLS. 12797  
SURVEY NO. 4746  
MADRON SURVEYING, INC. 301 SOUTH CANAL  
(575) 234-3341 CARLSBAD, NEW MEXICO

SHEET: 2-4




**FLOWLINE PLAT (400672XYZ)**

MULTI-USE ROW FOR 6" GAS LIFT & 6" POLY FIBER FLEX FLOWLINE FROM BIG SINKS DRAW "25" CTB TO  
BIG SINKS DRAW 25-24 FED COM 424H WITH LATERALS TO  
BIG SINKS DRAW 25-24 FED COM 421H, 422H, & 423H

DEVON ENERGY PRODUCTION COMPANY, L.P.  
CENTERLINE SURVEY OF A PIPELINE CROSSING  
SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
JUNE 28, 2016

SEC 25  
T.25S., R.31E.



**FLOWLINE PLAT (400672XYZ)**

MULTI-USE ROW FOR 6" GAS LIFT & 6" POLY FIBER FLEX FLOWLINE FROM BIG SINKS DRAW "25" CTB TO  
BIG SINKS DRAW 25-24 FED COM 424H WITH LATERALS TO  
BIG SINKS DRAW 25-24 FED COM 421H, 422H, & 423H

DEVON ENERGY PRODUCTION COMPANY, L.P.  
CENTERLINE SURVEY OF A PIPELINE CROSSING  
SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
JUNE 28, 2016





EXHIBIT "A"  
PAGE 1 of 4  
ELECTRIC LINE PLAT  
SECTION 25, T25S-R31E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO




30' EASEMENT AREA = 0.110 ACRE(S)  
160.14 FEET OR 9.71 RODS

SEE THE ATTACHED LEGAL DESCRIPTION


Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS #22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.



B.L. Laman PLS #22404  
Date Signed: 08-11-2016  
Horizonrow, LLC  
571 State Street Jasper, TX.  
(409) 202-5111 75951  
Employee of Horizonrow, LLC

LEGEND  
• POWER POLE



HORIZON ROW LLC

Drawn for:

devon

Drawn by:  
CHRIS MAAS

Date: 05/25/2016

DEVON ENERGY PRODUCTION COMPANY, L.P.  
BIG SINKS DRAW 25-24 FED COM  
421H & 422H PAD CONNECT  
ELECTRIC LINE  
PROPOSED 30' EASEMENT  
ON THE PROPERTY OF  
BUREAU OF LAND MANAGEMENT  
SECTION 25, T25S-R31E, N.M.P.M.

LINE NUMBER:  
EL7832  
WBS NUMBER:  
CC-112971.AL  
SCALE:  
1" = 1000'  
REVISIONS:  
7/28/16 CMAAS  
SHEET:  
1 OF 4

**SECTION 25, T25S-R31E, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO**

**ELECTRIC LINE PLAT**

**LEGAL DESCRIPTION**

**FOR**

**DEVON ENERGY PRODUCTION COMPANY, L.P.**

**BUREAU OF LAND MANAGEMENT**

**30' EASEMENT DESCRIPTION:**

**BEING** an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of the southwest quarter (SW ¼) and the northwest quarter (NW ¼) of Section 25, Township 25 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 2" iron pipe w/ BC 1939 for the southwest corner of Section 25, T25S-R31E, N.M.P.M., Eddy County, New Mexico;


Thence N 27°02'21" E a distance of 2886.04' to the **Point of Beginning** of this easement having coordinates of Northing=401012.79 feet, Easting=726323.64 feet and continuing the following course;

Thence N 00°24'00" W a distance of 160.14' to the **Point of Ending** having coordinates of Northing=401172.93 feet, Easting=726322.52 feet, from said point a 2" iron pipe w/ BC 1939 for the northwest corner of Section 25, T25S-R31E bears N 27°31'28" W a distance of 2876.24', covering **160.14' or 9.71 rods** and having an area of **0.110 acres**.

**NOTES:**

Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.


I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.

  
B.L. Laman      PLS 22404  
Date Signed: 08/11/2016  
Horizon Row, LLC  
571 State Street, Jasper, TX  
(402) 202-5111      75951  
Employee of Horizon Row, LLC



# EXHIBIT "A"

## PAGE 3 of 4



### QUAD MAP

SECTION 25, T25S-R31E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

**HORIZON ROW LLC**

DEVON ENERGY PRODUCTION CO., L.P.

PROPOSED 30' EASEMENT

Drawn by:  
CHRIS MAAS

Date: 05/25/2016

Drawn for:



LINE NUMBER:  
EL7832

WBS NUMBER:  
CC-112971.AL


SCALE:  
1" = 2000'

REVISIONS:  
7/28/16 CMAAS

SHEET:  
3 OF 4

# EXHIBIT "A"

## PAGE 4 of 4



### AERIAL MAP

SECTION 25, T25S-R31E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO


|                                   |                  |
|-----------------------------------|------------------|
| <b>HORIZON ROW LLC</b>            |                  |
| DEVON ENERGY PRODUCTION CO., L.P. |                  |
| PROPOSED 30' EASEMENT             |                  |
| Drawn by:<br>CHRIS MAAS           | Date: 05/25/2016 |

Drawn for:



|                             |
|-----------------------------|
| LINE NUMBER:<br>EL7832      |
| WBS NUMBER:<br>CC-112971.AL |
| SCALE:<br>1" = 2000'        |
| REVISIONS:<br>7/28/16 CMAAS |
| SHEET:<br>4 OF 4            |

SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
AERIAL ACCESS ROUTE MAP



NOT TO SCALE  
AERIAL PHOTO:  
GOOGLE EARTH  
NOV. 2015

DEVON ENERGY PRODUCTION COMPANY, L.P.  
**BIG SINKS DRAW 25-24 FED COM 424H**  
LOCATED 2440 FT. FROM THE NORTH LINE  
AND 610 FT. FROM THE EAST LINE OF  
SECTION 25, TOWNSHIP 25 SOUTH,  
RANGE 31 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO

JUNE 20, 2016


SURVEY NO. 4741

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

# ACCESS ROAD PLAT

AS-BUILT EXISTING LEASE ROAD TO BIG SINKS DRAW "25" FED COM 1H, 2H, & 3H  
AND PROPOSED BIG SINKS DRAW "25" FED COM 4H

DEVON ENERGY PRODUCTION COMPANY, L.P.  
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING  
SECTION 35, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
SEPTEMBER 30, 2015



SEE NEXT SHEET (2-8) FOR DESCRIPTION

## SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 1 DAY OF OCTOBER 2015

MADRON SURVEYING, INC.  
301 SOUTH CANAL  
CARLSBAD, NEW MEXICO 88220  
Phone (575) 234-3341

## GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING IS NMSP EAST MODIFIED TO SURFACE COORDINATES.

SHEET: 1-8

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SURVEY NO. 4247



## ACCESS ROAD PLAT

AS-BUILT EXISTING LEASE ROAD TO BIG SINKS DRAW "25" FED COM 1H, 2H, & 3H  
AND PROPOSED BIG SINKS DRAW "25" FED COM 4H

**DEVON ENERGY PRODUCTION COMPANY, L.P.**  
**CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING**  
**SECTION 35, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.**  
**EDDY COUNTY, STATE OF NEW MEXICO**  
**SEPTEMBER 30, 2015**

### DESCRIPTION

A STRIP OF LAND 20 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 35, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 10 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE NW/4 NW4 OF SAID SECTION 35, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE NORTHWEST CORNER OF SAID SECTION 35, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N02°14'32"W, A DISTANCE OF 867.34 FEET;  
THENCE N78°56'49"E A DISTANCE OF 302.60 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N89°46'01"E A DISTANCE OF 2722.52 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE S74°13'14"E A DISTANCE OF 303.74 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N82°58'50"E A DISTANCE OF 300.97 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N87°57'21"E A DISTANCE OF 909.00 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N89°34'58"E A DISTANCE OF 602.62 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N33°29'01"E A DISTANCE OF 301.49 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N00°17'43"W A DISTANCE OF 580.62 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE NORTHEAST CORNER OF SAID SECTION 35, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N89°47'30"E, A DISTANCE OF 15.42 FEET;


SAID STRIP OF LAND BEING 6023.56 FEET OR 365.06 RODS IN LENGTH, CONTAINING 2.766 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

|           |              |             |             |
|-----------|--------------|-------------|-------------|
| NW/4 NW/4 | 1308.72 L.F. | 79.32 RODS  | 0.601 ACRES |
| NE/4 NW/4 | 1332.87 L.F. | 80.78 RODS  | 0.612 ACRES |
| NW/4 NE/4 | 1347.49 L.F. | 81.67 RODS  | 0.619 ACRES |
| NE/4 NE/4 | 2034.48 L.F. | 123.30 RODS | 0.934 ACRES |

### SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,  
NEW MEXICO, THIS 1 DAY OF OCTOBER 2015

  
FILMON F. JARAMILLO, P.S. 12797

MADRON SURVEYING, INC.  
301 SOUTH CANAL  
CARLSBAD, NEW MEXICO 88220  
Phone (575) 234-3341

SURVEY NO. 4247

### GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING IS NMSP EAST MODIFIED TO SURFACE COORDINATES.


SHEET: 2-8

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

# ACCESS ROAD PLAT

AS-BUILT EXISTING LEASE ROAD TO BIG SINKS DRAW "25" FED COM 1H, 2H, & 3H  
AND PROPOSED BIG SINKS DRAW "25" FED COM 4H

DEVON ENERGY PRODUCTION COMPANY, L.P.  
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING  
SECTION 26, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
SEPTEMBER 30, 2015



SEE NEXT SHEET (4-8) FOR DESCRIPTION

## SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 15th DAY OF OCTOBER 2015


MADRON SURVEYING, INC.  
301 SOUTH CANAL  
CARLSBAD, NEW MEXICO 88220  
Phone (575) 234-3341

FILIMON F. JARAMILLO PLS. 12797

SURVEY NO. 4247

SHEET: 3-8

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO



## GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING IS NMSP EAST MODIFIED TO SURFACE COORDINATES.

### ACCESS ROAD PLAT

AS-BUILT EXISTING LEASE ROAD TO BIG SINKS DRAW "25" FED COM 1H, 2H, & 3H  
AND PROPOSED BIG SINKS DRAW "25" FED COM 4H

DEVON ENERGY PRODUCTION COMPANY, L.P.  
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING  
SECTION 26, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
SEPTEMBER 30, 2015

### DESCRIPTION

A STRIP OF LAND 20 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 26, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 10 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SE/4 SE/4 OF SAID SECTION 26, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHEAST CORNER OF SAID SECTION 26, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N89°47'30"E, A DISTANCE OF 15.42 FEET;  
THENCE N00°17'43"W A DISTANCE OF 2443.69 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N40°42'11"E A DISTANCE OF 29.19 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE EAST QUARTER CORNER OF SAID SECTION 26, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N00°12'31"W, A DISTANCE OF 176.09 FEET;

SAID STRIP OF LAND BEING 2472.87 FEET OR 149.87 RODS IN LENGTH, CONTAINING 1.135 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

|           |              |            |             |
|-----------|--------------|------------|-------------|
| SE/4 SE/4 | 1320.91 L.F. | 80.06 RODS | 0.606 ACRES |
| NE/4 SE/4 | 1151.96 L.F. | 69.82 RODS | 0.529 ACRES |

### SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 1 DAY OF OCTOBER 2015

### GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING IS NMSP EAST MODIFIED TO SURFACE COORDINATES.

SHEET: 4-8

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO


MADRON SURVEYING, INC.  
301 SOUTH CANAL  
CARLSBAD, NEW MEXICO 88220  
Phone (575) 234-3341

SURVEY NO. 4247


# ACCESS ROAD PLAT

AS-BUILT EXISTING LEASE ROAD TO BIG SINKS DRAW "25" FED COM 1H, 2H, & 3H  
AND PROPOSED BIG SINKS DRAW "25" FED COM 4H

DEVON ENERGY PRODUCTION COMPANY, L.P.  
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING  
SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
SEPTEMBER 30, 2015



SEE NEXT SHEET (6-8) FOR DESCRIPTION



## GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING IS NMSP EAST MODIFIED TO SURFACE COORDINATES.

## SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 1 DAY OF OCTOBER 2015

*[Signature]*  
FILMON F. JARAMILLO, 12797

MADRON SURVEYING, INC.  
301 SOUTH CANAL  
CARLSBAD, NEW MEXICO 88220  
Phone (575) 234-3341

SHEET: 5-8

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEY NO. 4247

## ACCESS ROAD PLAT

AS-BUILT EXISTING LEASE ROAD TO BIG SINKS DRAW "25" FED COM 1H, 2H, & 3H  
AND PROPOSED BIG SINKS DRAW "25" FED COM 4H

DEVON ENERGY PRODUCTION COMPANY, L.P.  
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING  
SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
SEPTEMBER 30, 2015

### DESCRIPTION

A STRIP OF LAND 20 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 10 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE NW/4 SW/4 OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE WEST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N00°12'31"W, A DISTANCE OF 176.09 FEET;  
THENCE N40°42'11"E A DISTANCE OF 272.59 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N87°58'56"E A DISTANCE OF 406.47 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE S86°26'44"E A DISTANCE OF 301.46 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N89°20'33"E A DISTANCE OF 880.61 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N89°25'13"E A DISTANCE OF 424.11 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N89°11'12"E A DISTANCE OF 928.72 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N89°44'23"E A DISTANCE OF 415.03 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;  
THENCE N89°08'07"E A DISTANCE OF 903.79 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE EAST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S88°12'19"E, A DISTANCE OF 871.49 FEET;

SAID STRIP OF LAND BEING 4532.77 FEET OR 274.71 RODS IN LENGTH, CONTAINING 2.081 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

|           |              |            |             |
|-----------|--------------|------------|-------------|
| NW/4 SW/4 | 233.88 L.F.  | 14.17 RODS | 0.107 ACRES |
| SW/4 NW/4 | 1188.80 L.F. | 72.05 RODS | 0.546 ACRES |
| SE/4 NW/4 | 1327.47 L.F. | 80.45 RODS | 0.609 ACRES |
| SW/4 NE/4 | 1327.48 L.F. | 80.45 RODS | 0.609 ACRES |
| SE/4 NE/4 | 455.15 L.F.  | 27.58 RODS | 0.209 ACRES |

### SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 1 DAY OF OCTOBER 2015

*Filimon F. Jaramillo*  
FILIMON F. JARAMILLO, PLS. 12797

MADRON SURVEYING, INC.  
301 SOUTH CANAL  
CARLSBAD, NEW MEXICO 88220  
Phone (575) 234-3341

### GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING IS NMSP EAST MODIFIED TO SURFACE COORDINATES.

SHEET: 6-8


MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO  
(575) 234-3341

SURVEY NO. 4247

# ACCESS ROAD PLAT

AS-BUILT EXISTING LEASE ROAD TO BIG SINKS DRAW "25" FED COM 1H, 2H, & 3H  
AND PROPOSED BIG SINKS DRAW "25" FED COM 4H

DEVON ENERGY PRODUCTION COMPANY, L.P.  
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING  
SECTIONS 35, 26, & 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
SEPTEMBER 30, 2015



SHEET: 7-8


MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO


SURVEY NO. 4247

**ACCESS ROAD PLAT**

AS-BUILT EXISTING LEASE ROAD TO BIG SINKS DRAW "25" FED COM 1H, 2H, & 3H  
AND PROPOSED BIG SINKS DRAW "25" FED COM 4H

DEVON ENERGY PRODUCTION COMPANY, L.P.  
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING  
SECTIONS 35, 26, & 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.  
EDDY COUNTY, STATE OF NEW MEXICO  
SEPTEMBER 30, 2015







# **DEVON ENERGY**

**Eddy County, NM (NAD-83)**

**Big Sinks Draw 25-24 Fed Com**

**424H**

**OH**

**Plan: Plan #1**

## **Standard Planning Report**

**11 November, 2016**

# LEAM Drilling Systems LLC

## Planning Report

**Database:** EDM 5000.1 Single User Db  
**Company:** DEVON ENERGY  
**Project:** Eddy County, NM (NAD-83)  
**Site:** Big Sinks Draw 25-24 Fed Com  
**Well:** 424H  
**Wellbore:** OH  
**Design:** Plan #1

**Local Co-ordinate Reference:** Well 424H  
**TVD Reference:** 3339.6' GE + 25' KB @ 3364.60usft  
**MD Reference:** 3339.6' GE + 25' KB @ 3364.60usft  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature

|                    |                           |                      |                |
|--------------------|---------------------------|----------------------|----------------|
| <b>Project</b>     | Eddy County, NM (NAD-83)  |                      |                |
| <b>Map System:</b> | US State Plane 1983       | <b>System Datum:</b> | Mean Sea Level |
| <b>Geo Datum:</b>  | North American Datum 1983 |                      |                |
| <b>Map Zone:</b>   | New Mexico Eastern Zone   |                      |                |

|                       |           |                              |                 |                   |                  |
|-----------------------|-----------|------------------------------|-----------------|-------------------|------------------|
| Site                  |           | Big Sinks Draw 25-24 Fed Com |                 |                   |                  |
| Site Position:        |           | Northing:                    | 401,293.75 usft | Latitude:         | 32° 6' 6.579 N   |
| From:                 | Map       | Easting:                     | 726,296.57 usft | Longitude:        | 103° 44' 9.643 W |
| Position Uncertainty: | 0.00 usft | Slot Radius:                 | 13-3/16 "       | Grid Convergence: | 0.32 °           |

|                      |           |               |                     |                 |               |                   |
|----------------------|-----------|---------------|---------------------|-----------------|---------------|-------------------|
| Well                 | 424H      |               |                     |                 |               |                   |
| Well Position        | +N/-S     | 23.09 usft    | Northing:           | 401,316.84 usft | Latitude:     | 32° 6' 6.619 N    |
|                      | +E/-W     | 3,402.38 usft | Easting:            | 729,698.95 usft | Longitude:    | 103° 43' 30.087 W |
| Position Uncertainty | 0.00 usft |               | Wellhead Elevation: | 3,364.60 usft   | Ground Level: | 3,339.60 usft     |

|                  |                   |                    |                        |                      |                            |
|------------------|-------------------|--------------------|------------------------|----------------------|----------------------------|
| <b>Wellbore</b>  | OH                |                    |                        |                      |                            |
| <b>Magnetics</b> | <b>Model Name</b> | <b>Sample Date</b> | <b>Declination (°)</b> | <b>Dip Angle (°)</b> | <b>Field Strength (nT)</b> |
|                  | HDGM              | 3/3/2016           | 6.98                   | 59.85                | 48,147                     |

|                   |                            |                 |                 |                  |
|-------------------|----------------------------|-----------------|-----------------|------------------|
| Design            | Plan #1                    |                 |                 |                  |
| Audit Notes:      |                            |                 |                 |                  |
| Version:          | Phase:                     | PLAN            | Tie On Depth:   | 0.00             |
| Vertical Section: | Depth From (TVD)<br>(usft) | +N/-S<br>(usft) | +E/-W<br>(usft) | Direction<br>(°) |
|                   | 0.00                       | 0.00            | 0.00            | 359.34           |

| Plan Sections         |                 |             |                       |              |              |                         |                        |                       |         |                |
|-----------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|------------------------|-----------------------|---------|----------------|
| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) | TFO (°) | Target         |
| 0.00                  | 0.00            | 0.00        | 0.00                  | 0.00         | 0.00         | 0.00                    | 0.00                   | 0.00                  | 0.00    |                |
| 7,659.56              | 0.00            | 0.00        | 7,659.56              | 0.00         | 0.00         | 0.00                    | 0.00                   | 0.00                  | 0.00    |                |
| 8,560.36              | 90.08           | 359.34      | 8,232.52              | 573.72       | -6.63        | 10.00                   | 10.00                  | 0.00                  | 359.34  |                |
| 15,378.02             | 90.08           | 359.34      | 8,223.00              | 7,390.91     | -85.47       | 0.00                    | 0.00                   | 0.00                  | 0.00    | PBHL (BS 424H) |

# LEAM Drilling Systems LLC

## Planning Report

Database: EDM 5000.1 Single User Db  
 Company: DEVON ENERGY  
 Project: Eddy County, NM (NAD-83)  
 Site: Big Sinks Draw 25-24 Fed Com  
 Well: 424H  
 Wellbore: OH  
 Design: Plan #1

Local Co-ordinate Reference: Well 424H  
 TVD Reference: 3339.6' GE + 25' KB @ 3364.60usft  
 MD Reference: 3339.6' GE + 25' KB @ 3364.60usft  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

### Planned Survey

| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Build Rate (°/100usft) | Turn Rate (°/100usft) |
|-----------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-------------------------|------------------------|-----------------------|
| 0.00                  | 0.00            | 0.00        | 0.00                  | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>SHL (BS 424H)</b>  |                 |             |                       |              |              |                         |                         |                        |                       |
| 100.00                | 0.00            | 0.00        | 100.00                | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 200.00                | 0.00            | 0.00        | 200.00                | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 300.00                | 0.00            | 0.00        | 300.00                | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 400.00                | 0.00            | 0.00        | 400.00                | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 500.00                | 0.00            | 0.00        | 500.00                | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 600.00                | 0.00            | 0.00        | 600.00                | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 700.00                | 0.00            | 0.00        | 700.00                | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 800.00                | 0.00            | 0.00        | 800.00                | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 900.00                | 0.00            | 0.00        | 900.00                | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 946.60                | 0.00            | 0.00        | 946.60                | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>Rustler</b>        |                 |             |                       |              |              |                         |                         |                        |                       |
| 1,000.00              | 0.00            | 0.00        | 1,000.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 1,046.60              | 0.00            | 0.00        | 1,046.60              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>Top of Salt</b>    |                 |             |                       |              |              |                         |                         |                        |                       |
| 1,100.00              | 0.00            | 0.00        | 1,100.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 1,200.00              | 0.00            | 0.00        | 1,200.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 1,300.00              | 0.00            | 0.00        | 1,300.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 1,400.00              | 0.00            | 0.00        | 1,400.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 1,500.00              | 0.00            | 0.00        | 1,500.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 1,600.00              | 0.00            | 0.00        | 1,600.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 1,700.00              | 0.00            | 0.00        | 1,700.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 1,800.00              | 0.00            | 0.00        | 1,800.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 1,900.00              | 0.00            | 0.00        | 1,900.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 2,000.00              | 0.00            | 0.00        | 2,000.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 2,100.00              | 0.00            | 0.00        | 2,100.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 2,200.00              | 0.00            | 0.00        | 2,200.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 2,300.00              | 0.00            | 0.00        | 2,300.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 2,400.00              | 0.00            | 0.00        | 2,400.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 2,500.00              | 0.00            | 0.00        | 2,500.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 2,600.00              | 0.00            | 0.00        | 2,600.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 2,700.00              | 0.00            | 0.00        | 2,700.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 2,800.00              | 0.00            | 0.00        | 2,800.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 2,900.00              | 0.00            | 0.00        | 2,900.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 3,000.00              | 0.00            | 0.00        | 3,000.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 3,100.00              | 0.00            | 0.00        | 3,100.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 3,200.00              | 0.00            | 0.00        | 3,200.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 3,300.00              | 0.00            | 0.00        | 3,300.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 3,400.00              | 0.00            | 0.00        | 3,400.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 3,500.00              | 0.00            | 0.00        | 3,500.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 3,600.00              | 0.00            | 0.00        | 3,600.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 3,700.00              | 0.00            | 0.00        | 3,700.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 3,800.00              | 0.00            | 0.00        | 3,800.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 3,900.00              | 0.00            | 0.00        | 3,900.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 4,000.00              | 0.00            | 0.00        | 4,000.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 4,100.00              | 0.00            | 0.00        | 4,100.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 4,171.60              | 0.00            | 0.00        | 4,171.60              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| <b>Base of Salt</b>   |                 |             |                       |              |              |                         |                         |                        |                       |
| 4,200.00              | 0.00            | 0.00        | 4,200.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 4,300.00              | 0.00            | 0.00        | 4,300.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 4,400.00              | 0.00            | 0.00        | 4,400.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |
| 4,429.60              | 0.00            | 0.00        | 4,429.60              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                   | 0.00                  |

Delaware

# LEAM Drilling Systems LLC

## Planning Report

**Database:** EDM 5000.1 Single User Db  
**Company:** DEVON ENERGY  
**Project:** Eddy County, NM (NAD-83)  
**Site:** Big Sinks Draw 25-24 Fed Com  
**Well:** 424H  
**Wellbore:** OH  
**Design:** Plan #1

**Local Co-ordinate Reference:** Well 424H  
**TVD Reference:** 3339.6' GE + 25' KB @ 3364.60usft  
**MD Reference:** 3339.6' GE + 25' KB @ 3364.60usft  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature

### Planned Survey

| Measured Depth (usft) | Inclination (°) | Azimuth (°) | Vertical Depth (usft) | +N/-S (usft) | +E/-W (usft) | Vertical Section (usft) | Dogleg Rate (°/100usft) | Buid Rate (°/100usft) | Turn Rate (°/100usft) |
|-----------------------|-----------------|-------------|-----------------------|--------------|--------------|-------------------------|-------------------------|-----------------------|-----------------------|
| 4,471.60              | 0.00            | 0.00        | 4,471.60              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| <b>Bell Canyon</b>    |                 |             |                       |              |              |                         |                         |                       |                       |
| 4,500.00              | 0.00            | 0.00        | 4,500.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 4,600.00              | 0.00            | 0.00        | 4,600.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 4,700.00              | 0.00            | 0.00        | 4,700.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 4,800.00              | 0.00            | 0.00        | 4,800.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 4,900.00              | 0.00            | 0.00        | 4,900.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 5,000.00              | 0.00            | 0.00        | 5,000.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 5,100.00              | 0.00            | 0.00        | 5,100.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 5,200.00              | 0.00            | 0.00        | 5,200.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 5,300.00              | 0.00            | 0.00        | 5,300.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 5,400.00              | 0.00            | 0.00        | 5,400.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 5,421.60              | 0.00            | 0.00        | 5,421.60              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| <b>Cherry Canyon</b>  |                 |             |                       |              |              |                         |                         |                       |                       |
| 5,500.00              | 0.00            | 0.00        | 5,500.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 5,600.00              | 0.00            | 0.00        | 5,600.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 5,700.00              | 0.00            | 0.00        | 5,700.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 5,800.00              | 0.00            | 0.00        | 5,800.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 5,900.00              | 0.00            | 0.00        | 5,900.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 6,000.00              | 0.00            | 0.00        | 6,000.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 6,100.00              | 0.00            | 0.00        | 6,100.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 6,200.00              | 0.00            | 0.00        | 6,200.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 6,300.00              | 0.00            | 0.00        | 6,300.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 6,400.00              | 0.00            | 0.00        | 6,400.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 6,500.00              | 0.00            | 0.00        | 6,500.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 6,600.00              | 0.00            | 0.00        | 6,600.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 6,700.00              | 0.00            | 0.00        | 6,700.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 6,761.60              | 0.00            | 0.00        | 6,761.60              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| <b>Brushy Canyon</b>  |                 |             |                       |              |              |                         |                         |                       |                       |
| 6,800.00              | 0.00            | 0.00        | 6,800.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 6,900.00              | 0.00            | 0.00        | 6,900.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 7,000.00              | 0.00            | 0.00        | 7,000.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 7,100.00              | 0.00            | 0.00        | 7,100.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 7,200.00              | 0.00            | 0.00        | 7,200.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 7,300.00              | 0.00            | 0.00        | 7,300.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 7,400.00              | 0.00            | 0.00        | 7,400.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 7,500.00              | 0.00            | 0.00        | 7,500.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 7,600.00              | 0.00            | 0.00        | 7,600.00              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 7,659.56              | 0.00            | 0.00        | 7,659.56              | 0.00         | 0.00         | 0.00                    | 0.00                    | 0.00                  | 0.00                  |
| 7,700.00              | 4.04            | 359.34      | 7,699.97              | 1.43         | -0.02        | 1.43                    | 10.00                   | 10.00                 | 0.00                  |
| 7,750.00              | 9.04            | 359.34      | 7,749.63              | 7.12         | -0.08        | 7.12                    | 10.00                   | 10.00                 | 0.00                  |
| 7,800.00              | 14.04           | 359.34      | 7,798.60              | 17.12        | -0.20        | 17.13                   | 10.00                   | 10.00                 | 0.00                  |
| 7,850.00              | 19.04           | 359.34      | 7,846.51              | 31.36        | -0.36        | 31.36                   | 10.00                   | 10.00                 | 0.00                  |
| 7,900.00              | 24.04           | 359.34      | 7,893.01              | 49.71        | -0.57        | 49.71                   | 10.00                   | 10.00                 | 0.00                  |
| 7,950.00              | 29.04           | 359.34      | 7,937.72              | 72.05        | -0.83        | 72.05                   | 10.00                   | 10.00                 | 0.00                  |
| 8,000.00              | 34.04           | 359.34      | 7,980.32              | 98.19        | -1.14        | 98.20                   | 10.00                   | 10.00                 | 0.00                  |
| 8,050.00              | 39.04           | 359.34      | 8,020.48              | 127.95       | -1.48        | 127.96                  | 10.00                   | 10.00                 | 0.00                  |
| 8,100.00              | 44.04           | 359.34      | 8,057.89              | 161.10       | -1.86        | 161.11                  | 10.00                   | 10.00                 | 0.00                  |
| 8,150.00              | 49.04           | 359.34      | 8,092.27              | 197.38       | -2.28        | 197.39                  | 10.00                   | 10.00                 | 0.00                  |
| 8,200.00              | 54.04           | 359.34      | 8,123.35              | 236.52       | -2.74        | 236.54                  | 10.00                   | 10.00                 | 0.00                  |
| 8,250.00              | 59.04           | 359.34      | 8,150.91              | 278.22       | -3.22        | 278.24                  | 10.00                   | 10.00                 | 0.00                  |
| 8,300.00              | 64.04           | 359.34      | 8,174.73              | 322.16       | -3.73        | 322.18                  | 10.00                   | 10.00                 | 0.00                  |
| 8,350.00              | 69.04           | 359.34      | 8,194.62              | 368.01       | -4.26        | 368.04                  | 10.00                   | 10.00                 | 0.00                  |

# LEAM Drilling Systems LLC

## Planning Report

Database: EDM 5000.1 Single User Db  
 Company: DEVON ENERGY  
 Project: Eddy County, NM (NAD-83)  
 Site: Big Sinks Draw 25-24 Fed Com  
 Well: 424H  
 Wellbore: OH  
 Design: Plan #1

Local Co-ordinate Reference: Well 424H  
 TVD Reference: 3339.6' GE + 25' KB @ 3364.60usft  
 MD Reference: 3339.6' GE + 25' KB @ 3364.60usft  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

### Planned Survey

| Measured<br>Depth<br>(usft) | Inclination<br>(°) | Azimuth<br>(°) | Vertical<br>Depth<br>(usft) | +N/-S<br>(usft) | +E/-W<br>(usft) | Vertical<br>Section<br>(usft) | Dogleg<br>Rate<br>(°/100usft) | Bulld<br>Rate<br>(°/100usft) | Turn<br>Rate<br>(°/100usft) |
|-----------------------------|--------------------|----------------|-----------------------------|-----------------|-----------------|-------------------------------|-------------------------------|------------------------------|-----------------------------|
| 8,368.82                    | 70.93              | 359.34         | 8,201.06                    | 385.69          | -4.46           | 385.72                        | 10.00                         | 10.00                        | 0.00                        |
| Lower Brushy Canyon         |                    |                |                             |                 |                 |                               |                               |                              |                             |
| 8,400.00                    | 74.04              | 359.34         | 8,210.45                    | 415.42          | -4.80           | 415.45                        | 10.00                         | 10.00                        | 0.00                        |
| 8,402.09                    | 74.25              | 359.34         | 8,211.02                    | 417.44          | -4.83           | 417.47                        | 10.00                         | 10.00                        | 0.00                        |
| LBRSHY D Sand               |                    |                |                             |                 |                 |                               |                               |                              |                             |
| 8,450.00                    | 79.04              | 359.34         | 8,222.08                    | 464.03          | -5.37           | 464.06                        | 10.00                         | 10.00                        | 0.00                        |
| 8,500.00                    | 84.04              | 359.34         | 8,229.43                    | 513.47          | -5.94           | 513.50                        | 10.00                         | 10.00                        | 0.00                        |
| 8,550.00                    | 89.04              | 359.34         | 8,232.44                    | 563.36          | -6.51           | 563.40                        | 10.00                         | 10.00                        | 0.00                        |
| 8,560.36                    | 90.08              | 359.34         | 8,232.52                    | 573.72          | -6.63           | 573.76                        | 10.00                         | 10.00                        | 0.00                        |
| 8,600.00                    | 90.08              | 359.34         | 8,232.46                    | 613.35          | -7.09           | 613.40                        | 0.00                          | 0.00                         | 0.00                        |
| 8,700.00                    | 90.08              | 359.34         | 8,232.32                    | 713.35          | -8.25           | 713.40                        | 0.00                          | 0.00                         | 0.00                        |
| 8,800.00                    | 90.08              | 359.34         | 8,232.18                    | 813.34          | -9.41           | 813.40                        | 0.00                          | 0.00                         | 0.00                        |
| 8,900.00                    | 90.08              | 359.34         | 8,232.05                    | 913.33          | -10.56          | 913.40                        | 0.00                          | 0.00                         | 0.00                        |
| 9,000.00                    | 90.08              | 359.34         | 8,231.91                    | 1,013.33        | -11.72          | 1,013.40                      | 0.00                          | 0.00                         | 0.00                        |
| 9,100.00                    | 90.08              | 359.34         | 8,231.77                    | 1,113.32        | -12.87          | 1,113.40                      | 0.00                          | 0.00                         | 0.00                        |
| 9,200.00                    | 90.08              | 359.34         | 8,231.63                    | 1,213.31        | -14.03          | 1,213.40                      | 0.00                          | 0.00                         | 0.00                        |
| 9,300.00                    | 90.08              | 359.34         | 8,231.49                    | 1,313.31        | -15.19          | 1,313.40                      | 0.00                          | 0.00                         | 0.00                        |
| 9,400.00                    | 90.08              | 359.34         | 8,231.35                    | 1,413.30        | -16.34          | 1,413.40                      | 0.00                          | 0.00                         | 0.00                        |
| 9,500.00                    | 90.08              | 359.34         | 8,231.21                    | 1,513.29        | -17.50          | 1,513.39                      | 0.00                          | 0.00                         | 0.00                        |
| 9,600.00                    | 90.08              | 359.34         | 8,231.07                    | 1,613.29        | -18.66          | 1,613.39                      | 0.00                          | 0.00                         | 0.00                        |
| 9,700.00                    | 90.08              | 359.34         | 8,230.93                    | 1,713.28        | -19.81          | 1,713.39                      | 0.00                          | 0.00                         | 0.00                        |
| 9,800.00                    | 90.08              | 359.34         | 8,230.79                    | 1,813.27        | -20.97          | 1,813.39                      | 0.00                          | 0.00                         | 0.00                        |
| 9,900.00                    | 90.08              | 359.34         | 8,230.65                    | 1,913.27        | -22.13          | 1,913.39                      | 0.00                          | 0.00                         | 0.00                        |
| 10,000.00                   | 90.08              | 359.34         | 8,230.51                    | 2,013.26        | -23.28          | 2,013.39                      | 0.00                          | 0.00                         | 0.00                        |
| 10,100.00                   | 90.08              | 359.34         | 8,230.37                    | 2,113.25        | -24.44          | 2,113.39                      | 0.00                          | 0.00                         | 0.00                        |
| 10,200.00                   | 90.08              | 359.34         | 8,230.23                    | 2,213.25        | -25.59          | 2,213.39                      | 0.00                          | 0.00                         | 0.00                        |
| 10,300.00                   | 90.08              | 359.34         | 8,230.09                    | 2,313.24        | -26.75          | 2,313.39                      | 0.00                          | 0.00                         | 0.00                        |
| 10,400.00                   | 90.08              | 359.34         | 8,229.95                    | 2,413.23        | -27.91          | 2,413.39                      | 0.00                          | 0.00                         | 0.00                        |
| 10,500.00                   | 90.08              | 359.34         | 8,229.81                    | 2,513.23        | -29.06          | 2,513.39                      | 0.00                          | 0.00                         | 0.00                        |
| 10,600.00                   | 90.08              | 359.34         | 8,229.67                    | 2,613.22        | -30.22          | 2,613.39                      | 0.00                          | 0.00                         | 0.00                        |
| 10,700.00                   | 90.08              | 359.34         | 8,229.53                    | 2,713.21        | -31.38          | 2,713.39                      | 0.00                          | 0.00                         | 0.00                        |
| 10,800.00                   | 90.08              | 359.34         | 8,229.39                    | 2,813.21        | -32.53          | 2,813.39                      | 0.00                          | 0.00                         | 0.00                        |
| 10,900.00                   | 90.08              | 359.34         | 8,229.25                    | 2,913.20        | -33.69          | 2,913.39                      | 0.00                          | 0.00                         | 0.00                        |
| 11,000.00                   | 90.08              | 359.34         | 8,229.11                    | 3,013.19        | -34.85          | 3,013.39                      | 0.00                          | 0.00                         | 0.00                        |
| 11,100.00                   | 90.08              | 359.34         | 8,228.97                    | 3,113.19        | -36.00          | 3,113.39                      | 0.00                          | 0.00                         | 0.00                        |
| 11,200.00                   | 90.08              | 359.34         | 8,228.83                    | 3,213.18        | -37.16          | 3,213.39                      | 0.00                          | 0.00                         | 0.00                        |
| 11,300.00                   | 90.08              | 359.34         | 8,228.69                    | 3,313.17        | -38.31          | 3,313.39                      | 0.00                          | 0.00                         | 0.00                        |
| 11,400.00                   | 90.08              | 359.34         | 8,228.55                    | 3,413.16        | -39.47          | 3,413.39                      | 0.00                          | 0.00                         | 0.00                        |
| 11,500.00                   | 90.08              | 359.34         | 8,228.41                    | 3,513.16        | -40.63          | 3,513.39                      | 0.00                          | 0.00                         | 0.00                        |
| 11,600.00                   | 90.08              | 359.34         | 8,228.28                    | 3,613.15        | -41.78          | 3,613.39                      | 0.00                          | 0.00                         | 0.00                        |
| 11,700.00                   | 90.08              | 359.34         | 8,228.14                    | 3,713.14        | -42.94          | 3,713.39                      | 0.00                          | 0.00                         | 0.00                        |
| 11,800.00                   | 90.08              | 359.34         | 8,228.00                    | 3,813.14        | -44.10          | 3,813.39                      | 0.00                          | 0.00                         | 0.00                        |
| 11,900.00                   | 90.08              | 359.34         | 8,227.86                    | 3,913.13        | -45.25          | 3,913.39                      | 0.00                          | 0.00                         | 0.00                        |
| 12,000.00                   | 90.08              | 359.34         | 8,227.72                    | 4,013.12        | -46.41          | 4,013.39                      | 0.00                          | 0.00                         | 0.00                        |
| 12,100.00                   | 90.08              | 359.34         | 8,227.58                    | 4,113.12        | -47.56          | 4,113.39                      | 0.00                          | 0.00                         | 0.00                        |
| 12,200.00                   | 90.08              | 359.34         | 8,227.44                    | 4,213.11        | -48.72          | 4,213.39                      | 0.00                          | 0.00                         | 0.00                        |
| 12,300.00                   | 90.08              | 359.34         | 8,227.30                    | 4,313.10        | -49.88          | 4,313.39                      | 0.00                          | 0.00                         | 0.00                        |
| 12,400.00                   | 90.08              | 359.34         | 8,227.16                    | 4,413.10        | -51.03          | 4,413.39                      | 0.00                          | 0.00                         | 0.00                        |
| 12,500.00                   | 90.08              | 359.34         | 8,227.02                    | 4,513.09        | -52.19          | 4,513.39                      | 0.00                          | 0.00                         | 0.00                        |
| 12,600.00                   | 90.08              | 359.34         | 8,226.88                    | 4,613.08        | -53.35          | 4,613.39                      | 0.00                          | 0.00                         | 0.00                        |
| 12,700.00                   | 90.08              | 359.34         | 8,226.74                    | 4,713.08        | -54.50          | 4,713.39                      | 0.00                          | 0.00                         | 0.00                        |
| 12,800.00                   | 90.08              | 359.34         | 8,226.60                    | 4,813.07        | -55.66          | 4,813.39                      | 0.00                          | 0.00                         | 0.00                        |
| 12,900.00                   | 90.08              | 359.34         | 8,226.46                    | 4,913.06        | -56.82          | 4,913.39                      | 0.00                          | 0.00                         | 0.00                        |

# LEAM Drilling Systems LLC

## Planning Report

Database: EDM 5000.1 Single User Db  
 Company: DEVON ENERGY  
 Project: Eddy County, NM (NAD-83)  
 Site: Big Sinks Draw 25-24 Fed Com  
 Well: 424H  
 Wellbore: OH  
 Design: Plan #1

Local Co-ordinate Reference: Well 424H  
 TVD Reference: 3339.6' GE + 25' KB @ 3364.60usft  
 MD Reference: 3339.6' GE + 25' KB @ 3364.60usft  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

### Planned Survey

| Measured<br>Depth<br>(usft) | Inclination<br>(°) | Azimuth<br>(°) | Vertical<br>Depth<br>(usft) | +N/-S<br>(usft) | +E/-W<br>(usft) | Vertical<br>Section<br>(usft) | Dogleg<br>Rate<br>(°/100usft) | Bulld<br>Rate<br>(°/100usft) | Turn<br>Rate<br>(°/100usft) |
|-----------------------------|--------------------|----------------|-----------------------------|-----------------|-----------------|-------------------------------|-------------------------------|------------------------------|-----------------------------|
| 13,000.00                   | 90.08              | 359.34         | 8,226.32                    | 5,013.06        | -57.97          | 5,013.39                      | 0.00                          | 0.00                         | 0.00                        |
| 13,100.00                   | 90.08              | 359.34         | 8,226.18                    | 5,113.05        | -59.13          | 5,113.39                      | 0.00                          | 0.00                         | 0.00                        |
| 13,200.00                   | 90.08              | 359.34         | 8,226.04                    | 5,213.04        | -60.28          | 5,213.39                      | 0.00                          | 0.00                         | 0.00                        |
| 13,300.00                   | 90.08              | 359.34         | 8,225.90                    | 5,313.04        | -61.44          | 5,313.39                      | 0.00                          | 0.00                         | 0.00                        |
| 13,400.00                   | 90.08              | 359.34         | 8,225.76                    | 5,413.03        | -62.60          | 5,413.39                      | 0.00                          | 0.00                         | 0.00                        |
| 13,500.00                   | 90.08              | 359.34         | 8,225.62                    | 5,513.02        | -63.75          | 5,513.39                      | 0.00                          | 0.00                         | 0.00                        |
| 13,600.00                   | 90.08              | 359.34         | 8,225.48                    | 5,613.02        | -64.91          | 5,613.39                      | 0.00                          | 0.00                         | 0.00                        |
| 13,700.00                   | 90.08              | 359.34         | 8,225.34                    | 5,713.01        | -66.07          | 5,713.39                      | 0.00                          | 0.00                         | 0.00                        |
| 13,800.00                   | 90.08              | 359.34         | 8,225.20                    | 5,813.00        | -67.22          | 5,813.39                      | 0.00                          | 0.00                         | 0.00                        |
| 13,900.00                   | 90.08              | 359.34         | 8,225.06                    | 5,913.00        | -68.38          | 5,913.39                      | 0.00                          | 0.00                         | 0.00                        |
| 14,000.00                   | 90.08              | 359.34         | 8,224.92                    | 6,012.99        | -69.54          | 6,013.39                      | 0.00                          | 0.00                         | 0.00                        |
| 14,100.00                   | 90.08              | 359.34         | 8,224.78                    | 6,112.98        | -70.69          | 6,113.39                      | 0.00                          | 0.00                         | 0.00                        |
| 14,200.00                   | 90.08              | 359.34         | 8,224.65                    | 6,212.98        | -71.85          | 6,213.39                      | 0.00                          | 0.00                         | 0.00                        |
| 14,300.00                   | 90.08              | 359.34         | 8,224.51                    | 6,312.97        | -73.00          | 6,313.39                      | 0.00                          | 0.00                         | 0.00                        |
| 14,400.00                   | 90.08              | 359.34         | 8,224.37                    | 6,412.96        | -74.16          | 6,413.39                      | 0.00                          | 0.00                         | 0.00                        |
| 14,500.00                   | 90.08              | 359.34         | 8,224.23                    | 6,512.95        | -75.32          | 6,513.39                      | 0.00                          | 0.00                         | 0.00                        |
| 14,600.00                   | 90.08              | 359.34         | 8,224.09                    | 6,612.95        | -76.47          | 6,613.39                      | 0.00                          | 0.00                         | 0.00                        |
| 14,700.00                   | 90.08              | 359.34         | 8,223.95                    | 6,712.94        | -77.63          | 6,713.39                      | 0.00                          | 0.00                         | 0.00                        |
| 14,800.00                   | 90.08              | 359.34         | 8,223.81                    | 6,812.93        | -78.79          | 6,813.39                      | 0.00                          | 0.00                         | 0.00                        |
| 14,900.00                   | 90.08              | 359.34         | 8,223.67                    | 6,912.93        | -79.94          | 6,913.39                      | 0.00                          | 0.00                         | 0.00                        |
| 15,000.00                   | 90.08              | 359.34         | 8,223.53                    | 7,012.92        | -81.10          | 7,013.39                      | 0.00                          | 0.00                         | 0.00                        |
| 15,100.00                   | 90.08              | 359.34         | 8,223.39                    | 7,112.91        | -82.26          | 7,113.39                      | 0.00                          | 0.00                         | 0.00                        |
| 15,200.00                   | 90.08              | 359.34         | 8,223.25                    | 7,212.91        | -83.41          | 7,213.39                      | 0.00                          | 0.00                         | 0.00                        |
| 15,300.00                   | 90.08              | 359.34         | 8,223.11                    | 7,312.90        | -84.57          | 7,313.39                      | 0.00                          | 0.00                         | 0.00                        |
| 15,378.02                   | 90.08              | 359.34         | 8,223.00                    | 7,390.91        | -85.47          | 7,391.40                      | 0.00                          | 0.00                         | 0.00                        |
| PBHL (BS 424H)              |                    |                |                             |                 |                 |                               |                               |                              |                             |

### Design Targets

| Target Name<br>- hit/miss target<br>- Shape            | Dip Angle<br>(°) | Dip Dir.<br>(°) | TVD<br>(usft) | +N/-S<br>(usft) | +E/-W<br>(usft) | Northing<br>(usft) | Easting<br>(usft) | Latitude        | Longitude         |
|--|------------------|-----------------|---------------|-----------------|-----------------|--------------------|-------------------|-----------------|-------------------|
| SHL (BS 424H)<br>- plan hits target center<br>- Point  | 0.00             | 0.00            | 0.00          | 0.00            | 0.00            | 401,316.84         | 729,698.95        | 32° 6' 6.619 N  | 103° 43' 30.087 W |
| PBHL (BS 424H)<br>- plan hits target center<br>- Point | 0.00             | 0.00            | 8,223.00      | 7,390.91        | -85.47          | 408,707.75         | 729,613.48        | 32° 7' 19.762 N | 103° 43' 30.595 W |

# LEAM Drilling Systems LLC


## Planning Report

**Database:** EDM 5000.1 Single User Db  
**Company:** DEVON ENERGY  
**Project:** Eddy County, NM (NAD-83)  
**Site:** Big Sinks Draw 25-24 Fed Com  
**Well:** 424H  
**Wellbore:** OH  
**Design:** Plan #1

**Local Co-ordinate Reference:** Well 424H  
**TVD Reference:** 3339.6' GE + 25' KB @ 3364.60usft  
**MD Reference:** 3339.6' GE + 25' KB @ 3364.60usft  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature


### Formations

| Measured<br>Depth<br>(usft) | Vertical<br>Depth<br>(usft) | Name                | Lithology | Dip<br>(°) | Dip<br>Direction<br>(°) |
|-----------------------------|-----------------------------|---------------------|-----------|------------|-------------------------|
| 946.60                      | 946.60                      | Rustler             |           | -0.08      | 359.34                  |
| 1,046.60                    | 1,046.60                    | Top of Salt         |           | -0.08      | 359.34                  |
| 4,171.60                    | 4,171.60                    | Base of Salt        |           | -0.08      | 359.34                  |
| 4,429.60                    | 4,429.60                    | Delaware            |           | -0.08      | 359.34                  |
| 4,471.60                    | 4,471.60                    | Bell Canyon         |           | -0.08      | 359.34                  |
| 5,421.60                    | 5,421.60                    | Cherry Canyon       |           | -0.08      | 359.34                  |
| 6,761.60                    | 6,761.60                    | Brushy Canyon       |           | -0.08      | 359.34                  |
| 8,368.82                    | 8,201.06                    | Lower Brushy Canyon |           | -0.08      | 359.34                  |
| 8,402.09                    | 8,211.02                    | LBRSHY D Sand       |           | -0.08      | 359.34                  |




Azimuths to Grid North  
 True North:  $-0.32^{\circ}$   
 Magnetic North:  $6.66^{\circ}$   
 Magnetic Field  
 Strength: 48147.4sn T  
 Dip Angle:  $59.85^{\circ}$   
 Date: 3/3/2016  
 Model: HDGM

Project: Eddy County, NM (NAD-83)  
 Site: Big Sinks Draw 25-24 Fed Com  
 Well: 424H  
 Wellbore: OH  
 Design: Plan #1







A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Devon proposes using a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 3000 (3M) psi.

- Wellhead will be installed by wellhead representatives.
- If the welding is performed by a third party, the wellhead representative will monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- Wellhead representative will install the test plug for the initial BOP test.
- Wellhead company will install a solid steel body pack-off to completely isolate the lower head after cementing intermediate casing. After installation of the pack-off, the pack-off and the lower flange will be tested to 3M, as shown on the attached schematic. Everything above the pack-off will not have been altered whatsoever from the initial nipple up. Therefore the BOP components will not be retested at that time.
- If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head will be cut and top out operations will be conducted.
- Devon will pressure test all seals above and below the mandrel (but still above the casing) to full working pressure rating.
- Devon will test the casing to 0.22 psi/ft or 1500 psi, whichever is greater, as per Onshore Order #2.

After running the 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 3M will be installed on the wellhead system and will undergo a 250 psi low pressure test followed by a 3,000 psi high pressure test. The 3,000 psi high and 250 psi low test will cover testing requirements a maximum of 30 days, as per Onshore Order #2. If the well is not complete within 30 days of this BOP test, another full BOP test will be conducted, as per Onshore Order #2.

After running the 9-5/8" intermediate casing with a mandrel hanger, the 13-5/8" BOP/BOPE system with a minimum rating of 3M will already be installed on the wellhead.

The pipe rams will be operated and checked each 24 hour period and each time the drill pipe is out of the hole. These tests will be logged in the daily driller's log. A 2" kill line and 3" choke line will be incorporated into the drilling spool below the ram BOP. In addition to the rams and annular preventer, additional BOP accessories include a kelly cock, floor safety valve, choke lines, and choke manifold rated at 3,000 psi WP.

Devon's proposed wellhead manufactures will be FMC Technologies, Cactus Wellhead, or Cameron.

## Casing Assumptions and Load Cases

### Surface

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

| Surface Casing Burst Design |                         |   |
|-----------------------------|-------------------------|---|
| Load Case                   | External Pressure       | Internal Pressure                                 |
| Pressure Test               | Formation Pore Pressure | Max mud weight of next hole-section plus Test psi |
| Drill Ahead                 | Formation Pore Pressure | Max mud weight of next hole section               |
| Displace to Gas             | Formation Pore Pressure | Dry gas from next casing point                    |

| Surface Casing Collapse Design |   |                   |
|--------------------------------|---|-------------------|
| Load Case                      | External Pressure                       | Internal Pressure |
| Full Evacuation                | Water gradient in cement, mud above TOC | None              |
| Cementing                      | Wet cement weight                       | Water (8.33ppg)   |

| Surface Casing Tension Design |             |
|-------------------------------|-------------|
| Load Case                     | Assumptions |
| Overpull                      | 100kips     |
| Runing in hole                | 3 ft/s      |
| Service Loads                 | N/A         |

## Casing Assumptions and Load Cases

### Intermediate

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

| Intermediate Casing Burst Design |                         |   |
|----------------------------------|-------------------------|---|
| Load Case                        | External Pressure       | Internal Pressure                                 |
| Pressure Test                    | Formation Pore Pressure | Max mud weight of next hole-section plus Test psi |
| Drill Ahead                      | Formation Pore Pressure | Max mud weight of next hole section               |
| Fracture @ Shoe                  | Formation Pore Pressure | Dry gas   |

| Intermediate Casing Collapse Design |   |                   |
|-------------------------------------|---|-------------------|
| Load Case                           | External Pressure                       | Internal Pressure |
| Full Evacuation                     | Water gradient in cement, mud above TOC | None              |
| Cementing                           | Wet cement weight                       | Water (8.33ppg)   |

| Intermediate Casing Tension Design |             |
|------------------------------------|-------------|
| Load Case                          | Assumptions |
| Overpull                           | 100kips     |
| Runing in hole                     | 2 ft/s      |
| Service Loads                      | N/A         |

## Casing Assumptions and Load Cases

### Production

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

| Production Casing Burst Design |                         |   |
|--------------------------------|-------------------------|---|
| Load Case                      | External Pressure       | Internal Pressure                                     |
| Pressure Test                  | Formation Pore Pressure | Fluid in hole (water or produced water) + test psi    |
| Tubing Leak                    | Formation Pore Pressure | Packer @ KOP, leak below surface 8.6 ppg packer fluid |
| Stimulation                    | Formation Pore Pressure | Max frac pressure with heaviest frac fluid            |

| Production Casing Collapse Design |  |                   |
|-----------------------------------|--|-------------------|
| Load Case                         | External Pressure                        | Internal Pressure |
| Full Evacuation                   | Water gradient in cement, mud above TOC. | None              |
| Cementing                         | Wet cement weight                        | Water (8.33ppg)   |

| Production Casing Tension Design |             |
|----------------------------------|-------------|
| Load Case                        | Assumptions |
| Overpull                         | 100kips     |
| Runing in hole                   | 2 ft/s      |
| Service Loads                    | N/A         |

| Production Cement Contingency |  |                 |                               |                |                   |
|-------------------------------|--|-----------------|-------------------------------|----------------|-------------------|
| Additional Info for String    |  | 3               | Additional String Description |                |                   |
| Stage Tool Depth              |  | 4200            |                               |                |                   |
| <i>Lead</i>                   |  |                 |                               |                |                   |
| Top MD of Segment             |  | 4000            | Btm MD of Segment             |                | 4100              |
|                               |  |                 | Cement Type                   |                | C                 |
| Additives                     | Enhancer 923 + 10% BWOC Bentonite +<br>0.05% BWOC SA-1015 + 0.3% BWOC HR-800<br>+ 0.2% BWOC FE-2 + 0.125 lb/sk Pol-E-Flake<br>+ 0.5 lb/sk D-Air 5000 |                 | Quantity (sks)                | 20             | Yield (cu.ft./sk) |
|                               |  |                 |                               |                | 3.31              |
| Density (lbs/gal)             | 10.9   | Volume (cu.ft.) | 66                            | Percent Excess | 25                |
| <i>Tail</i>                   |  |                 |                               |                |                   |
| Top MD of Segment             |  | 4100            | Top MD of Segment             |                | 4200              |
|                               |  |                 | Cement Type                   |                | H                 |
| Additives                     | 0.125 lbs/sack Poly-E-Flake  |                 | Quantity (sks)                | 30             | Yield (cu.ft./sk) |
|                               |  |                 |                               |                | 1.33              |
| Density (lbs/gal)             | 14.8   | Volume (cu.ft.) | 40                            | Percent Excess | 25                |

| Production Cement Contingency |  |                 |                               |                |                   |
|-------------------------------|--|-----------------|-------------------------------|----------------|-------------------|
| Additional Info for String    |  | 3               | Additional String Description |                |                   |
| Stage Tool Depth              |  | 4200            |                               |                |                   |
| <i>Lead</i>                   |  |                 |                               |                |                   |
| Top MD of Segment             |  | 4200            | Btm MD of Segment             |                | 8100              |
|                               |  |                 | Cement Type                   |                | C                 |
| Additives                     | Enhancer 923 + 10% BWOC Bentonite +<br>0.05% BWOC SA-1015 + 0.3% BWOC HR-800<br>+ 0.2% BWOC FE-2 + 0.125 lb/sk Pol-E-Flake<br>+ 0.5 lb/sk D-Air 5000 |                 | Quantity (sks)                | 371            | Yield (cu.ft./sk) |
|                               |  |                 |                               |                | 3.31              |
| Density (lbs/gal)             | 10.9   | Volume (cu.ft.) | 1228                          | Percent Excess | 25                |
| <i>Tail</i>                   |  |                 |                               |                |                   |
| Top MD of Segment             |  | 8100            | Top MD of Segment             |                | 15378             |
|                               |  |                 | Cement Type                   |                | H                 |
| Additives                     | Poz (Fly Ash) + 0.5% bwoc HALAD-344 +<br>0.4% bwoc CFR-3 + 0.2% BWOC HR-601 + 2%<br>bwoc Bentonite   |                 | Quantity (sks)                | 1915           | Yield (cu.ft./sk) |
|                               |  |                 |                               |                | 1.2               |
| Density (lbs/gal)             | 14.5   | Volume (cu.ft.) | 2298                          | Percent Excess | 25                |



Fluid Technology

ContiTech Beattie Corp.  
Website: [www.contitechbeattie.com](http://www.contitechbeattie.com)

Monday, June 14, 2010

RE: Drilling & Production Hoses  
Lifting & Safety Equipment

To Helmerich & Payne,

A Continental ContiTech hose assembly can perform as intended and suitable for the application regardless of whether the hose is secured or unsecured in its configuration. As a manufacturer of High Pressure Hose Assemblies for use in Drilling & Production, we do offer the corresponding lifting and safety equipment, this has the added benefit of easing the lifting and handling of each hose assembly whilst affording hose longevity by ensuring correct handling methods and procedures as well as securing the hose in the unlikely event of a failure; but in no way does the lifting and safety equipment affect the performance of the hoses providing the hoses have been handled and installed correctly. It is good practice to use lifting & safety equipment but not mandatory.


Should you have any questions or require any additional information/clarifications then please do not hesitate to contact us.

ContiTech Beattie is part of the Continental AG Corporation and can offer the full support resources associated with a global organization.

Best regards,

Robin Hodgson  
Sales Manager  
ContiTech Beattie Corp

ContiTech Beattie Corp,  
11535 Brittonmoore Park Drive,  
Houston, TX 77041  
Phone: +1 (832) 327-0141  
Fax: +1 (832) 327-0148  
[www.contitechbeattie.com](http://www.contitechbeattie.com)



RIG 212



## QUALITY DOCUMENT

PHOENIX RUBBER

INDUSTRIAL LTD.

6728 Szeged, Budapesti út 10. Hungary • H-6701 Szeged, P. O. Box 152  
 Phone: (3662) 556-737 • Fax: (3662) 556-738


SALES & MARKETING: H-1092 Budapest, Ráday u. 42-44. Hungary • H-1440 Budapest, P. O. Box 26  
 Phone: (361) 456-4200 • Fax: (361) 217-2972, 456-4273 • www.taurusemerge.hu

|   |                                      |  |         |
|---|--------------------------------------|--|---------|
| <b>QUALITY CONTROL<br/>INSPECTION AND TEST CERTIFICATE</b>  |                                      | CERT. N°: 552  |         |
| PURCHASER: Phoenix Beattie Co.  |                                      | P.O. N°: 1519FA-871  |         |
| PHOENIX RUBBER order N°: 170466   | HOSE TYPE: 3" ID Choke and Kill Hose |  |         |
| HOSE SERIAL N°: 34128   | NOMINAL / ACTUAL LENGTH: 11,43 m     |  |         |
| W.P. 68,96 MPa 10000 psi  | T.P. 103,4 MPa 15000 psi             | Duration: 60 min.  |         |
| Pressure test with water at ambient temperature<br><br><p style="text-align: center;">See attachment. (1 page)</p>                                    |                                      |  |         |
| ↑ 10 mm = 10 Min.<br>→ 10 mm = 25 MPa   |                                      |  |         |
| COUPLINGS   |                                      |  |         |
| Type  | Serial N°                            | Quality  | Heat N° |
| 3" coupling with<br>4 1/16" Flange end  | 720 719                              | AISI 4130  | C7626   |
|   |                                      | AISI 4130  | 47357   |
|   |                                      |  |         |
| API Spec 16 C<br>Temperature rate: "B"  |                                      |  |         |
| All metal parts are flawless  |                                      |  |         |
| WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT. |                                      |  |         |
| Date:   | Inspector                            | Quality Control  |         |
| 29. April. 2002.  |                                      | PHOENIX RUBBER<br>Industrial Ltd.<br>Hose Inspection and<br>Testing Dept.<br>PHOENIX RUBBER G.C. |         |



14094-65

40920-0-00015 N800C




*[Signature]*  
**PHOENIX RUBBER**  
 Industrial Ltd.  
 Hose Inspection and  
 Certification Dept.

VERIFIED TRUE CO.  
 PHOENIX RUBBER CO.



Commitment Runs Deep



Design Plan  
Operation and Maintenance Plan  
Closure Plan

SENM Closed Loop Systems  
June 2010

## **I. Design Plan**

Devon uses MI SWACO closed loop system (CLS). The MI SWACO CLS is designed to maintain drill solids at or below 5%. The equipment is arranged to progressively remove solids from the largest to the smallest size. Drilling fluids can thus be reused and savings is realized on mud and disposal costs. Dewatering may be required with the centrifuges to insure removal of ultra fine solids.

The drilling location is constructed to allow storm water to flow to a central sump normally the cellar. This insures no contamination leaves the drilling pad in the event of a spill. Storm water is reused in the mud system or stored in a reserve fluid tank farm until it can be reused. All lubricants, oils, or chemicals are removed immediately from the ground to prevent the contamination of storm water. An oil trap is normally installed on the sump if an oil spill occurs during a storm.

A tank farm is utilized to store drilling fluids including fresh water and brine fluids. The tank farm is constructed on a 20 ml plastic lined, bermed pad to prevent the contamination of the drilling site during a spill. Fluids from other sites may be stored in these tanks for processing by the solids control equipment and reused in the mud system. At the end of the well the fluids are transported from the tank farm to an adjoining well or to the next well for the rig.

Prior to installing a closed-loop system on site, the topsoil, if present, will be stripped and stockpiled for use as the final cover or fill at the time of closure.

Signs will be posted on the fence surrounding the closed-loop system unless the closed-loop system is located on a site where there is an existing well, that is operated by Devon.


## **II. Operations and Maintenance Plan**

*Primary Shakers:* The primary shakers make the first removal of drill solids from the drilling mud as it leaves the well bore. The shakers are sized to handle maximum drilling rate at optimal screen size. The shakers normally remove solids down to 74 microns.

**Mud Cleaner:** The Mud Cleaner cleans the fluid after it leaves the shakers. A set of hydrocyclones are sized to handle 1.25 to 1.5 times the maximum circulating rate. This ensures all the fluid is being processed to an average cut point of 25 microns. The wet discharged is dewatered on a shaker equipped with ultra fine mesh screens and generally cut at 40 microns.



Closed Loop Schematic



**Centrifuges:** The centrifuges can be one or two in number depending on the well geometry or depth of well. The centrifuges are sized to maintain low gravity solids at 5% or below. They may or may not need a dewatering system to enhance the removal rates. The centrifuges can make a cut point of 8-10 microns depending on bowl speed, feed rate, solids loading and other factors.

The centrifuge system is designed to work on the active system and be flexible to process incoming fluids from other locations. This set-up is also dependant on well factors.

**Dewatering System:** The dewatering system is a chemical mixing and dosing system designed to enhance the solids removal of the centrifuge. Not commonly used in shallow wells. It may contain pH adjustment, coagulant mixing and dosing, and polymer mixing and dosing. Chemical flocculation binds ultra fine solids into a mass that is within the centrifuge operating design. The

dewatering system improves the centrifuge cut point to infinity or allows for the return of clear water or brine fluid. This ability allows for the ultimate control of low gravity solids.

*Cuttings Boxes:* Cuttings boxes are utilized to capture drill solids that are discarded from the solids control equipment. These boxes are set upon a rail system that allows for the removal and replacement of a full box of cuttings with an empty one. They are equipped with a cover that insures no product is spilled into the environment during the transportation phase.

*Process Tank:* (Optional) The process tank allows for the holding and process of fluids that are being transferred into the mud system. Additionally, during times of lost circulation the process tank may hold active fluids that are removed for additional treatment. It can further be used as a mixing tank during well control conditions.

*Sump and Sump Pump:* The sump is used to collect storm water and the pump is used to transfer this fluid to the active system or to the tank for to hold in reserve. It can also be used to collect fluids that may escape during spills. The location contains drainage ditches that allow the location fluids to drain to the sump.

*Reserve Fluids (Tank Farm):* A series of frac tanks are used to replace the reserve pit. These are steel tanks that are equipped with a manifold system and a transfer pump. These tanks can contain any number of fluids used during the drilling process. These can include fresh water, cut brine, and saturated salt fluid. The fluid can be from the active well or reclaimed fluid from other locations. A 20 ml liner and berm system is employed to ensure the fluids do not migrate to the environment during a spill.

If a leak develops, the appropriate division district office will be notified within 48 hours of the discovery and the leak will be addressed. Spill prevention is accomplished by maintaining pump packing, hoses, and pipe fittings to insure no leaks are occurring. During an upset condition the source of the spill is isolated and repaired as soon as it is discovered. Free liquid is removed by a diaphragm pump and returned to the mud system. Loose topsoil may be used to stabilize the spill and the contaminated soil is excavated and placed in the cuttings boxes. After the well is finished and the rig has moved, the entire location is scrapped and testing will be performed to determine if a release has occurred.

All trash is kept in a wire mesh enclosure and removed to an approved landfill when full. All spent motor oils are kept in separate containers and they are removed and sent to an approved recycling center. Any spilled lubricants, pipe

dope, or regulated chemicals are removed from soil and sent to landfills approved for these products.

These operations are monitored by Mi Swaco service technicians. Daily logs are maintained to ensure optimal equipment operation and maintenance. Screen and chemical use is logged to maintain inventory control. Fluid properties are monitored and recorded and drilling mud volumes are accounted for in the mud storage farm. This data is kept for end of well review to insure performance goals are met. Lessons learned are logged and used to help with continuous improvement.

A MI SWACO field supervisor manages from 3-5 wells. They are responsible for training personnel, supervising installations, and inspecting sites for compliance of MI SWACO safety and operational policy.

### **III. Closure Plan**

A maximum 340' X 340' caliche pad is built per well. All of the trucks and steel tanks fit on this pad. All fluid cuttings go to the steel tanks to be hauled by various trucking companies to an agency approved disposal.

| Production Cement Contingency |  |                 |                               |                |                   |
|-------------------------------|--|-----------------|-------------------------------|----------------|-------------------|
| Additional Info for String    |  | 3               | Additional String Description |                |                   |
| Stage Tool Depth              |  | 4200            |                               |                |                   |
| <i>Lead</i>                   |  |                 |                               |                |                   |
| Top MD of Segment             |  | 4000            | Btm MD of Segment             |                | 4100              |
|                               |  |                 | Cement Type                   |                | C                 |
| Additives                     | Enhancer 923 + 10% BWOC Bentonite +<br>0.05% BWOC SA-1015 + 0.3% BWOC HR-800<br>+ 0.2% BWOC FE-2 + 0.125 lb/sk Pol-E-Flake<br>+ 0.5 lb/sk D-Air 5000 |                 | Quantity (sks)                | 20             | Yield (cu.ft./sk) |
|                               |  |                 |                               |                | 3.31              |
| Density (lbs/gal)             | 10.9   | Volume (cu.ft.) | 66                            | Percent Excess | 25                |
| <i>Tail</i>                   |  |                 |                               |                |                   |
| Top MD of Segment             |  | 4100            | Top MD of Segment             |                | 4200              |
|                               |  |                 | Cement Type                   |                | H                 |
| Additives                     | 0.125 lbs/sack Poly-E-Flake  |                 | Quantity (sks)                | 30             | Yield (cu.ft./sk) |
|                               |  |                 |                               |                | 1.33              |
| Density (lbs/gal)             | 14.8   | Volume (cu.ft.) | 40                            | Percent Excess | 25                |

| Production Cement Contingency |  |                 |                               |                |                   |
|-------------------------------|--|-----------------|-------------------------------|----------------|-------------------|
| Additional Info for String    |  | 3               | Additional String Description |                |                   |
| Stage Tool Depth              |  | 4200            |                               |                |                   |
| <i>Lead</i>                   |  |                 |                               |                |                   |
| Top MD of Segment             |  | 4200            | Btm MD of Segment             |                | 8100              |
|                               |  |                 | Cement Type                   |                | C                 |
| Additives                     | Enhancer 923 + 10% BWOC Bentonite +<br>0.05% BWOC SA-1015 + 0.3% BWOC HR-800<br>+ 0.2% BWOC FE-2 + 0.125 lb/sk Pol-E-Flake<br>+ 0.5 lb/sk D-Air 5000 |                 | Quantity (sks)                | 371            | Yield (cu.ft./sk) |
|                               |  |                 |                               |                | 3.31              |
| Density (lbs/gal)             | 10.9   | Volume (cu.ft.) | 1228                          | Percent Excess | 25                |
| <i>Tail</i>                   |  |                 |                               |                |                   |
| Top MD of Segment             |  | 8100            | Top MD of Segment             |                | 15378             |
|                               |  |                 | Cement Type                   |                | H                 |
| Additives                     | Poz (Fly Ash) + 0.5% bwoc HALAD-344 +<br>0.4% bwoc CFR-3 + 0.2% BWOC HR-601 + 2%<br>bwoc Bentonite   |                 | Quantity (sks)                | 1915           | Yield (cu.ft./sk) |
|                               |  |                 |                               |                | 1.2               |
| Density (lbs/gal)             | 14.5   | Volume (cu.ft.) | 2298                          | Percent Excess | 25                |



**Devon Energy Center  
333 West Sheridan Avenue  
Oklahoma City, Oklahoma 73102-5015**

# **Hydrogen Sulfide (H<sub>2</sub>S) Contingency Plan**

**For**

**Big Sinks Draw 25-24 Fed Com 424H**


**Sec-25 T-25S R-31E  
2440' FNL & 610' FEL  
LAT. = 32.1018386' N (NAD83)  
LONG = 103.7250240' W**

**Eddy County NM**




## Big Sinks Draw 25-24 Fed Com 424H

This is an open drilling site. H<sub>2</sub>S monitoring equipment and emergency response equipment will be used within 500' of zones known to contain H<sub>2</sub>S, including warning signs, wind indicators and H<sub>2</sub>S monitor.



6



Radius of Exposure (ROE) = 3000' (Radius of Exposure)

### Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated from the location entrance road. Crews should then block the entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE. There are no homes or buildings in or near the ROE.

**Assumed 100 ppm ROE = 3000'**

**100 ppm H<sub>2</sub>S concentration shall trigger activation of this plan.**

### **Emergency Procedures**

**In the event of a release of gas containing H<sub>2</sub>S, the first responder(s) must**

- **Isolate the area and prevent entry by other persons into the 100 ppm ROE.**
- **Evacuate any public places encompassed by the 100 ppm ROE.**
- **Be equipped with H<sub>2</sub>S monitors and air packs in order to control the release.**
- **Use the “buddy system” to ensure no injuries occur during the response**
- **Take precautions to avoid personal injury during this operation.**
- **Contact operator and/or local officials to aid in operation. See list of phone numbers attached.**
- **Have received training in the**
  - **Detection of H<sub>2</sub>S, and**
  - **Measures for protection against the gas,**
  - **Equipment used for protection and emergency response.**

### **Ignition of Gas Source**

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO<sub>2</sub>). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas

### **Characteristics of H<sub>2</sub>S and SO<sub>2</sub>**

| <b>Common Name</b>      | <b>Chemical Formula</b> | <b>Specific Gravity</b>  | <b>Threshold Limit</b> | <b>Hazardous Limit</b> | <b>Lethal Concentration</b> |
|-------------------------|-------------------------|--------------------------|------------------------|------------------------|-----------------------------|
| <b>Hydrogen Sulfide</b> | <b>H<sub>2</sub>S</b>   | <b>1.189<br/>Air = 1</b> | <b>10 ppm</b>          | <b>100 ppm/hr</b>      | <b>600 ppm</b>              |
| <b>Sulfur Dioxide</b>   | <b>SO<sub>2</sub></b>   | <b>2.21<br/>Air = 1</b>  | <b>2 ppm</b>           | <b>N/A</b>             | <b>1000 ppm</b>             |

### **Contacting Authorities**

Devon Energy Corp. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. Devon Energy Corp. Company response must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER)

## **Hydrogen Sulfide Drilling Operation Plan**

### **I. HYDROGEN SULFIDE (H<sub>2</sub>S) TRAINING**

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H<sub>2</sub>S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H<sub>2</sub>S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H<sub>2</sub>S metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H<sub>2</sub>S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H<sub>2</sub>S zone (within 3 days or 500 feet) and weekly H<sub>2</sub>S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H<sub>2</sub>S Drilling Operations Plan and the Public Protection Plan.

### **II. HYDROGEN SULFIDE TRAINING**

Note: All H<sub>2</sub>S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H<sub>2</sub>S.

## **1. Well Control Equipment**

- A. Flare line
- B. Choke manifold – Remotely Operated
- C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
- D. Auxiliary equipment may include if applicable: annular preventer and rotating head.
- E. Mud/Gas Separator

## **2. Protective equipment for essential personnel:**

30-minute SCBA units located at briefing areas, as indicated on well site diagram, with one escape unit available in the top doghouse. As it may be difficult to communicate audibly while wearing these units, hand signals shall be utilized.

## **3. H<sub>2</sub>S detection and monitoring equipment:**

Portable H<sub>2</sub>S monitors positioned on location for best coverage and response. These units have warning lights which activate when H<sub>2</sub>S levels reach 10 ppm and audible sirens which activate at 10 ppm. Sensor locations:

- Bell nipple
- Shale shaker
- Trip tank
- Suction pit
- Rig floor
- Cellar
- Choke manifold
- Living Quarters (usually the company man's trailer stairs.)

### **Visual warning systems:**

- A. Wind direction indicators as shown on well site diagram
- B. Caution/ Danger signs shall be posted on roads providing direct access to locations. Signs will be painted a high visibility yellow with black lettering of sufficient size to be reasonable distance from the immediate location. Bilingual signs will be used when appropriate.

#### **4. Mud program:**

The mud program has been designed to minimize the volume of H<sub>2</sub>S circulated to surface. Proper mud weight, safe drilling practices and the use of H<sub>2</sub>S scavengers will minimize hazards when penetrating H<sub>2</sub>S bearing zones.

#### **5. Metallurgy:**

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold lines, and valves shall be H<sub>2</sub>S trim.
- B. All elastomers used for packing and seals shall be H<sub>2</sub>S trim.

#### **6. Communication:**

- A. Company personnel have/use cellular telephones in the field.
- B. Land line (telephone) communications at Office

#### **7. Well testing:**


- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safety and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H<sub>2</sub>S environment will use the closed chamber method of testing.
- B. There will be no drill stem testing.

| <b><u>Devon Energy Corp. Company Call List</u></b> |   |                               |
|--|---|-------------------------------|
|  | Drilling Supervisor – Basin – Mark Kramer                               | 405-823-4796                  |
|  | Drilling Supervisor – Slope – Norman Naill                              | 405-760-7234                  |
|  | EHS Professional – Mark Hurst   | 575-513-9087                  |
| <b><u>Agency Call List</u></b>                     |   |                               |
| <b><u>Lea County (575)</u></b>                     | <b>Hobbs</b>  |                               |
|  | Lea County Communication Authority                                      | 393-3981                      |
|  | State Police  | 392-5588                      |
|  | City Police   | 397-9265                      |
|  | Sheriff's Office  | 393-2515                      |
|  | <b>Ambulance</b>  | <b>911</b>                    |
|  | Fire Department   | 397-9308                      |
|  | LEPC (Local Emergency Planning Committee)                               | 393-2870                      |
|  | NMOCD   | 393-6161                      |
|  | US Bureau of Land Management  | 393-3612                      |
|  |   |                               |
| <b><u>Eddy County (575)</u></b>                    | <b>Carlsbad</b>   |                               |
|  | State Police  | 885-3137                      |
|  | City Police   | 885-2111                      |
|  | Sheriff's Office  | 887-7551                      |
|  | <b>Ambulance</b>  | <b>911</b>                    |
|  | Fire Department   | 885-3125                      |
|  | LEPC (Local Emergency Planning Committee)                               | 887-3798                      |
|  | US Bureau of Land Management  | 887-6544                      |
|  | NM Emergency Response Commission (Santa Fe)                             | (505) 476-9600                |
|  | 24 HR   | (505) 827-9126                |
|  | National Emergency Response Center                                      | (800) 424-8802                |
|  | National Pollution Control Center: Direct                               | (703) 872-6000                |
|  | For Oil Spills  | (800) 280-7118                |
|  | <b>Emergency Services</b>   |                               |
|  | Wild Well Control   | (281) 784-4700                |
|  | Cudd Pressure Control   | (915) 699-0139 (915) 563-3356 |
|  | Halliburton   | (575) 746-2757                |
|  | B. J. Services  | (575) 746-3569                |
|  | <b>Give GPS position:</b>   |                               |
|  | Native Air – Emergency Helicopter – Hobbs                               | (575) 392-6429                |
|  | Flight For Life - Lubbock, TX   | (806) 743-9911                |
|  | Aerocare - Lubbock, TX  | (806) 747-8923                |
|  | Med Flight Air Amb - Albuquerque, NM                                    | (575) 842-4433                |
|  | Lifeguard Air Med Svc. Albuquerque, NM                                  | (800) 222-1222                |
|  | Poison Control (24/7)   | (575) 272-3115                |
|  | Oil & Gas Pipeline 24 Hour Service                                      | (800) 364-4366                |
|  | NOAA – Website - <a href="http://www.nhc.noaa.gov">www.nhc.noaa.gov</a> |                               |

Prepared in conjunction with  
Dave Small



# Devon Energy - Well Pad Rig Location Layout Safety Equipment Location








# Rig Location Layout

## 2 Well Pad

Big Sinks Draw 25-24 Fed Com 424H



This map is for illustrative purposes only and is not intended to be used as a legal record. Devon makes no warranty, representation or claim regarding this map.



WGS\_1984\_Web\_Mercator\_Auxiliary\_Sphere  
Prepared by: User  
Map is current as of: 03-Aug-2016



0 0.14 0.28 0.56 1.12, 457  
Miles

- Major Facility (DWH)
- Compressor Station
- Gas Processing Plant
- Waterbody
- Lake/Pond
- Playa
- Reservoir
- Swamp/Marsh
- Stream Area
- Canal/Ditch
- Inundation Area
- Water Areas
- Other Features
- Streams
- Artificial Path
- Canal/Ditch
- Coastline
- Connector
- Pipeline
- Stream/River
- Underground Conduit

-Duration: 30 days. Install 10 days prior to Completion.  
-Disturbance: Existing  
-Contents: Treated Water or back up will be Fresh Water  
-Size of Pipe: 10" or 12"  
-Length of Pipe: 20,421' TW & FW  
-Type of Pipe: Layflat


Devon will contact the BLM for additional time if needed.



- State pit 616 and 617 32- 23S- 32E



- Fed pit 25- 23S- 31E



- Private pit 26- 23S- 31E



**PECOS DISTRICT  
DRILLING OPERATIONS  
CONDITIONS OF APPROVAL**

|                       |                                    |
|-----------------------|------------------------------------|
| OPERATOR'S NAME:      | Devon Energy Production Co, L.P.   |
| LEASE NO.:            | NMLC062300                         |
| WELL NAME & NO.:      | 424H-Big Sinks Draw 25 24 Fed      |
| SURFACE HOLE FOOTAGE: | 2440'/N & 610'/E                   |
| BOTTOM HOLE FOOTAGE:  | 330'/N & 660'/E                    |
| LOCATION:             | Section 25, T.25 S., R.31 E., NMPM |
| COUNTY:               | Eddy County, New Mexico            |

**Communitization Agreement**

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

**A. DRILLING OPERATIONS REQUIREMENTS**

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

1. **Hydrogen Sulfide (H<sub>2</sub>S) monitors shall be installed prior to drilling out the surface shoe. If H<sub>2</sub>S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which**

**includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**

2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

## **B. CASING**

**Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.**

**Centralizers required on surface casing per Onshore Order 2.III.B.1.f.**

### **Wait on cement (WOC) for Water Basin:**

**After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.**

**No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.**

**Possibility of water flows in the Salado and Castile.**

**Possibility of lost circulation in the Red Beds, Rustler, and Delaware.**

A. The 13-3/8 inch surface casing shall be set at approximately 965 feet (in a competent bed below the Magenta Dolomite, which is a Member of the Rustler, and if salt is encountered, set casing at least 25 feet above the salt) and cemented to the surface.

1. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
2. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
3. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
4. If cement falls back, remedial cementing will be done prior to drilling out that string.

**Intermediate casing shall be kept fluid filled while running into hole to meet BLM minimum collapse requirements.**

B. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:

- ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above.  
**Additional cement maybe required. Excess cement calculates only 23%**

**Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.**

C. The minimum required fill of cement behind the 5-1/2 inch production casing is:

- ☒ Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification. **Additional cement maybe required. Excess cement calculates only 25%**

4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.



**C. PRESSURE CONTROL**

- A. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
- B. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).
- C. **Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 3000 (3M) psi.**
  - a. **Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.**
  - b. **If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.**
  - c. **Manufacturer representative shall install the test plug for the initial BOP test.**
  - d. **Operator shall perform the intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.**
  - e. **If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.**
- D. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - 1. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the

plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

2. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**.
3. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
4. The results of the test shall be reported to the appropriate BLM office.
5. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
6. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

#### **D. DRILL STEM TEST**

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

#### **E. WASTE MATERIAL AND FLUIDS**

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**CLN 03202017**

# PECOS DISTRICT SURFACE USE CONDITIONS OF APPROVAL

|                       |                                    |
|-----------------------|------------------------------------|
| OPERATOR'S NAME:      | Devon Energy Production Co, L.P.   |
| LEASE NO.:            | NMLC062300                         |
| WELL NAME & NO.:      | 424H-Big Sinks Draw 25 24 Fed      |
| SURFACE HOLE FOOTAGE: | 2440'/N & 610'/E                   |
| BOTTOM HOLE FOOTAGE:  | 330'/N & 660'/E                    |
| LOCATION:             | Section 25, T.25 S., R.31 E., NMPM |
| COUNTY:               | Eddy County, New Mexico            |

## TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
  - Lesser Prairie-Chicken Timing Stipulations
  - Ground-level Abandoned Well Marker
  - Range
- ☐ **Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- ☐ **Road Section Diagram**
- ☐ **Production (Post Drilling)**
  - Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## V. SPECIAL REQUIREMENT(S)

### **Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:**

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

**Ground-level Abandoned Well Marker to avoid raptor perching:** Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

**During construction, the proponent shall minimize disturbance to existing fences, water lines, troughs, windmills, and other improvements on public lands. The proponent is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the grazing permittee/allottee prior to disturbing any range improvement projects. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.**



## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### **D. FEDERAL MINERAL MATERIALS PIT**

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

### **F. EXCLOSURE FENCING (CELLARS & PITS)**

**Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

**G. ON LEASE ACCESS ROADS****Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

**Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

**Crowning**

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

**Ditching**

Ditching shall be required on both sides of the road.

**Turnouts**

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.


**Drainage**



Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

#### **Cross Section of a Typical Lead-off Ditch**



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

#### **Formula for Spacing Interval of Lead-off Ditches**

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

#### **Cattle guards**

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

#### **Fence Requirement**

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

#### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

### Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

## **VII. PRODUCTION (POST DRILLING)**

### **A. WELL STRUCTURES & FACILITIES**

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

#### **Chemical and Fuel Secondary Containment and Exclosure Screening**

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

#### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

#### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, Shale Green from the BLM Standard Environmental Color Chart (CC-001: June 2008).

### **VIII. INTERIM RECLAMATION**

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

### **IX. FINAL ABANDONMENT & RECLAMATION**

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory

revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at below ground level on a plate containing the pertinent information for the plugged well.

### Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

| Species             | lb/acre |
|---------------------|---------|
| Plains Bristlegrass | 5lbs/A  |
| Sand Bluestem       | 5lbs/A  |
| Little Bluestem     | 3lbs/A  |
| Big Bluestem        | 6lbs/A  |
| Plains Coreopsis    | 2lbs/A  |
| Sand Dropseed       | 1lbs/A  |

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed