

17-333

Form 3160-2
(March 2012)

OCD Artesia

FORM APPROVED
OMB No. 1004-0137
Expires October 31, 2014

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease Serial No. NMNM117122	
6. If Indian, Allottee or Tribe Name	
7. If Unit or CA Agreement, Name and No. NMNM133058	
8. Lease Name and Well No. HOBGOBLIN 7 FEDERAL COM 44H 313982	
9. API Well No. 30-015-44336	
1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER	10. Field and Pool, or Exploratory SQUARE LAKE / GRAYBURG-SAN AN
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone	11. Sec., T. R. M. or Blk. and Survey or Area SEC 7 / T17S / R30E / NMP
2. Name of Operator COG OPERATING LLC	12. County or Parish EDDY
3a. Address 600 West Illinois Ave Midland TX 79701	13. State NM
3b. Phone No. (include area code) (432)683-7443	14. Distance in miles and direction from nearest town or post office* 2.54 miles
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface SENE / 2310 FNL / 40 FEL / LAT 32.8499678 / LONG -104.002886 At proposed prod. zone LOT 2 / 2307 FNL / 220 FWL / LAT 32.8499334 / LONG -104.0789699	15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 40 feet
16. No. of acres in lease 240	17. Spacing Unit dedicated to this well 157.37
18. Distance from proposed location* to nearest well, drilling, completed, 110 feet applied for, on this lease, ft.	19. Proposed Depth 4049 feet / 8793 feet
20. BLM/BIA Bond No. on file FED: NMB000215	21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3669 feet
22. Approximate date work will start* 08/04/2017	23. Estimated duration 15 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM. |

25. Signature (Electronic Submission)	Name (Printed/Typed) Robyn Odom / Ph: (432)685-4385	Date 03/08/2017
Title Regulatory Analyst		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575)234-5959	Date 07/14/2017
Title Supervisor Multiple Resources		
Office CARLSBAD		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

APPROVED WITH CONDITIONS

NM OIL CONSERVATION
ARTESIA DISTRICT

JUL 24 2017

RECEIVED

Rup 7-25-17

APD ID: 10400012074

Submission Date: 03/08/2017

Highlight
All Changes

Operator Name: COG OPERATING LLC

Federal/Indian APD: FED

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Well Type: OIL WELL

Well Work Type: Drill

Application**Section 1 - General**

APD ID: 10400012074

Tie to previous NOS? 10400006385

Submission Date: 03/08/2017

BLM Office: CARLSBAD

User: Robyn Odom

Title: Regulatory Analyst

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM117122

Lease Acres: 240

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? YES

Federal or Indian agreement: FEDERAL

Agreement number: NMNM133058

Agreement name:

Keep application confidential? NO

Permitting Agent? NO

APD Operator: COG OPERATING LLC

Operator letter of designation:

Keep application confidential? NO

Operator Info

Operator Organization Name: COG OPERATING LLC

Operator Address: 600 West Illinois Ave

Zip: 79701

Operator PO Box:

Operator City: Midland

State: TX

Operator Phone: (432)683-7443

Operator Internet Address: RODOM@CONCHO.COM

Section 2 - Well Information

Well in Master Development Plan? NO

Mater Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: SQUARE LAKE

Pool Name: GRAYBURG-SAN ANDRES

Is the proposed well in an area containing other mineral resources? NATURAL GAS,OIL

Describe other minerals:

Is the proposed well in a Helium production area? N

Use Existing Well Pad? NO

New surface disturbance?

Type of Well Pad: SINGLE WELL

Multiple Well Pad Name:

Number:

Well Class: HORIZONTAL

Number of Legs:

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 2.54 Miles

Distance to nearest well: 110 FT

Distance to lease line: 40 FT

Reservoir well spacing assigned acres Measurement: 157.37 Acres

Well plat: Hobgoblin_7_Federal_Com_44H_C102_03-06-2017.pdf

Well work start Date: 08/04/2017

Duration: 15 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number:

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1	2310	FNL	40	FEL	17S	30E	7	Aliquot SENE	32.8499678	-104.002886	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 117122	3669	0	0
KOP Leg #1	2260	FNL	90	FEL	17S	30E	7	Aliquot SENE	32.850092	-104.003	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 117122	655	360	3604
PPP Leg #1	2260	FNL	330	FEL	17S	30E	7	Aliquot SENE	32.850075	-104.003947	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 117122	-3860	415	4055

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
EXIT Leg #1	2307	FNL	330	FWL	17S	30E	7	Lot 2	32.849925	-104.018608	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 025733	-380	8793	4049
BHL Leg #1	2307	FNL	220	FWL	17S	30E	7	Lot 2	32.849934	-104.0789699	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 025733	-380	8793	4049

Drilling Plan

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
17691	UNKNOWN	3669	0	0	ALLUVIUM	USEABLE WATER	No
17746	RUSTLER	3287	382	382	ANHYDRITE	OTHER : Brackish Water	No
17718	TOP SALT	3137	532	532	SALT	OTHER : Salt	No
17724	TANSILL	2562	1107	1107	DOLOMITE	NONE	No
17694	YATES	2458	1211	1211	SANDSTONE,DOL OMITE	NATURAL GAS,OIL	No
15319	SEVEN RIVERS	2167	1502	1502	SANDSTONE,DOL OMITE	NATURAL GAS,OIL	No
15318	QUEEN	1569	2100	2100	SANDSTONE	NATURAL GAS,OIL	No
17683	GRAYBURG	1154	2515	2515	SANDSTONE,DOL OMITE	NATURAL GAS,OIL	No
15314	SAN ANDRES	844	2825	2825	DOLOMITE,ANHY DRITE	NATURAL GAS,OIL	Yes
17701	GLORIETA	-605	4274	4274	SANDSTONE,SILT STONE	NATURAL GAS,OIL	No
17700	PADDOCK	-664	4333	4333	DOLOMITE	NATURAL GAS,OIL	No

Section 2 - Blowout Prevention

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Pressure Rating (PSI): 2M

Rating Depth: 9500

Equipment: All required equipment per Federal and State regulations to be in place prior to drilling out the Surface casing.

Requesting Variance? NO

Variance request:

Testing Procedure: BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure of 2000 psi per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure of 2000 psi. If the system is upgraded all the components installed will be functional and tested. Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold.

Choke Diagram Attachment:

2M Choke Schematic_12-21-2016.pdf

BOP Diagram Attachment:

2M ANNULAR BOP_12-21-2016.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	410	0	410			410	H-40	48	STC	4.91	2.91	DRY	18.99	DRY	18.99
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	1225	0	1225			1225	J-55	40	STC	4.62	1.58	DRY	11.31	DRY	11.31
3	PRODUCTION	8.75	7.0	NEW	API	N	0	3605	0	3605			3605	L-80	29	LTC	5.19	1.61	DRY	3.52	DRY	3.52
4	PRODUCTION	8.75	5.5	NEW	API	N	3605	4433	3605	4125			828	L-80	17	LTC	3.66	2.26	DRY	4.24	DRY	4.24
5	PRODUCTION	7.875	5.5	NEW	API	N	4433	8793	4125	4049			4360	L-80	17	LTC	3.66	2.26	DRY	8.18	DRY	8.18

Casing Attachments

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Casing Attachments

Casing ID: 1 **String Type:** SURFACE

Inspection Document:

Spec Document:

Taperd String Spec:

Casing Design Assumptions and Worksheet(s):

Casing_Design_Attachement_03-08-2017.pdf

Casing ID: 2 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Taperd String Spec:

Casing Design Assumptions and Worksheet(s):

Casing_Design_Attachement_03-08-2017.pdf

Casing ID: 3 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Taperd String Spec:

Casing Design Assumptions and Worksheet(s):

Casing_Design_Attachement_03-08-2017.pdf

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Casing Attachments

Casing ID: 4 String Type: PRODUCTION

Inspection Document:

Spec Document:

Taperd String Spec:

Casing Design Assumptions and Worksheet(s):

Casing_Design_Attachement_03-08-2017.pdf

Casing ID: 5 String Type: PRODUCTION

Inspection Document:

Spec Document:

Taperd String Spec:

Casing Design Assumptions and Worksheet(s):

Casing_Design_Attachement_03-08-2017.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	410	400	1.32	14.8	528	85	Class C	2% CaCl2+0.25 pps CF
INTERMEDIATE	Lead		0	1225	250	2.45	11.8	612.5	183	50:50:10 C:Poz:Gel	5% Salt+5pps LCM+0.25pps CF
INTERMEDIATE	Tail		0	1225	200	1.32	14.8	264	183	Class C	2% CaCl2
PRODUCTION	Lead		0	8793	400	2.01	12.5	804	91	35:65:6 C:Poz:Gel	5% salt + 5 pp LCM + 0.2% SMS + 1% FL-25+
PRODUCTION	Tail		0	8793	1400	1.37	14	1918	91	50:50:2 C:Poz:Gel	5% salt+3pps LCM+0.6%SMS+1%FL-

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
PRODUCTION	Lead		0	8793	400	2.01	12.5	804		35:65:6 C:Poz:Gel	5%Salt+5pps LCM+0.25pps CF
PRODUCTION	Tail		0	8793	1400	1.31	14	1918	91	50:50:2 C:Poz:Gel	5%salt+3pps LCM+0.6%SMS+1%FL-
PRODUCTION	Lead		0	8793	400	2.01	12.5	804		35:65:6 C:Poz:Gel	5% salt + 5 pp LCM + 0.2% SMS + 1% FL-25+
PRODUCTION	Tail		0	8793	1400	1.37	14	1918	91	50:50:2 C:Poz:Gel	5%salt+3pps LCM+0.6%SMS+1%FL-

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

Describe the mud monitoring system utilized: PVT/Pason/Visual Monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	4433	SALT SATURATED	10	10.2							
0	410	WATER-BASED MUD	8.6	8.8							
4433	8793	WATER-BASED MUD	8.5	9.2							

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Interval Perforating, Fracture stimulating, Flowback testing

List of open and cased hole logs run in the well:

CNL,MUDLOG

Coring operation description for the well:

N/A

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 1815

Anticipated Surface Pressure: 922.9

Anticipated Bottom Hole Temperature(F): 99

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

H2S Plan_12-21-2016.pdf

Hobgoblin_7_Fed_Com_44H_H2S_Schematic_03-06-2017.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Hobgoblin_7_Federal_Com_44H_Design_1_Rpt_03-06-2017.pdf

Hobgoblin_7_Federal_Com_44H_Design_1_AC_Rpt_03-06-2017.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:

Closed Loop Schematic_12-21-2016.pdf

Hobgoblin_7_Fed_Com_44H_Prod_Cement_Breakdown_03-08-2017.pdf

Contingent_Multi_Stage_Cement_Discussion_04-27-2017.pdf

Other Variance attachment:

52/10

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

Hobgoblin_7_Federal_Com_44H_Vicinity_Plat_03-07-2017.pdf

Existing Road Purpose: ACCESS,FLUID TRANSPORT

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? NO

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

Hobgoblin_7_Fed_Com_44H_1mileRadius_Map_03-07-2017.pdf

Existing Wells description:

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? DEFER

Estimated Production Facilities description: If the well is productive, contemplated facilities will be as follows: Two (2) proposed flowlines, will follow an archaeologically approved route to the Hobgoblin 7 Federal Com #4H Tank Battery located in Section 7 in T17S R30E. The flowlines will be SDR 7 3" poly line laid on the surface and will be approximately 700 feet in length. Normal working pressure of the flowlines will be below 70 psi and carry a mixture of produced oil, water, and gas. Flowlines will follow existing well-traveled or proposed roads. The tank battery and facilities including all flow lines and piping will be installed according to API specifications.

Section 5 - Location and Types of Water Supply

Water Source Table

Water source use type: INTERMEDIATE/PRODUCTION CASING,
SURFACE CASING

Water source type: GW WELL

Describe type:

Source latitude:

Source longitude:

Source datum:

Water source permit type: PRIVATE CONTRACT

Source land ownership: COMMERCIAL

Water source transport method: PIPELINE,TRUCKING

Source transportation land ownership: COMMERCIAL

Water source volume (barrels): 8000

Source volume (acre-feet): 1.0311447

Source volume (gal): 336000

Water source and transportation map:

Loco Hills Water Disposal Co Water Supply_12-21-2016.pdf

Caswell Ranch_Water Supply_12-21-2016.pdf

Water source comments: The well will be drilled with combination brine and fresh water mud system as outlined in the drilling program. Water will be obtained from commercial water stations in the area and hauled to location by transport truck over the existing and proposed access roads shown in Vicinity Map. A fresh water source is nearby and fast line may be laid along existing road ROW's and fresh water pumped to the well. Water will originate from private wells location described on the attached "Loco Hills Water Disposal Co" map attached to this APD. James R. Maloney, 575-677-2118. A secondary water source will be from 1 and/or all of the 3 private wells location depicted on the attached "Caswell Ranch Water Supply" Map. No water well will be drilled on the location.

New water well? NO

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method:

Drill material:

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Construction Materials description: Surfacing material will consist of native caliche. Caliche will be obtained from the actual well site if available. Secondary candidate source will be NMSLO Caliche Pit located in S2/SW4 of Sec 32, T16S, R30E. A third candidate source will be Caswell Ranch owned Caliche Pit located in NESE of Sec 9, T17S, R32E.

Construction Materials source location attachment:

Construction Turn-Over Procedure_12-21-2016.pdf

NMSLO Caliche Pit_12-21-2016.pdf

Caswell Ranch Caliche Pit_12-21-2016.pdf

Section 7 - Methods for Handling Waste

Waste type: DRILLING

Waste content description: Drill cuttings and Drilling fluids

Amount of waste: 100 barrels

Waste disposal frequency : Daily

Safe containment description: Closed Loop System

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** FEDERAL

Disposal type description:

Disposal location description: R360's Disposal site located at 3507 West Carlsbad Highway, Hobbs, NM 88240.

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Waste type: PRODUCED WATER

Waste content description: Produced water

Amount of waste: 100 barrels

Waste disposal frequency : Daily

Safe containment description: Steel tanks

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** STATE

Disposal type description:

Disposal location description: NMOCD approved commercial disposal facility. R360's disposal site located at 4507 West Carlsbad Highway, Hobbs, NM 88240.

Waste type: GARBAGE

Waste content description: Garbage and trash produced during drilling and completion operations.

Amount of waste: 100 pounds

Waste disposal frequency : Weekly

Safe containment description: Trash bin

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** STATE

Disposal type description:

Disposal location description: Garbage and trash to be collected in trash bin and hauled to Lea Landfill LLC. located at mile marker 64, Highway 62-180 East, PO Box 3247, Carlsbad, NM 88221. No toxic waste or hazardous chemicals will be produced by this operation.

Waste type: SEWAGE

Waste content description: Human waste and grey water

Amount of waste: 100 gallons

Waste disposal frequency : Weekly

Safe containment description: Portable septic system and/or portable waste gathering system.

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: Hauled to NMOCD approved waste disposal facility.

Reserve Pit

Reserve Pit being used? NO

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Temporary disposal of produced water into reserve pit?

Reserve pit length (ft.)

Reserve pit width (ft.)

Reserve pit depth (ft.)

Reserve pit volume (cu. yd.)

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? YES

Description of cuttings location Closed Loop Mud System: Roll-off style mud box.

Cuttings area length (ft.)

Cuttings area width (ft.)

Cuttings area depth (ft.)

Cuttings area volume (cu. yd.)

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: NO

Ancillary Facilities attachment:

Comments:

Section 9 - Well Site Layout

Well Site Layout Diagram:

Hobgoblin_7_Federal_Com_44H_Well_Site_Plat_03-06-2017.pdf

Hobgoblin_7_Federal_Com_44H_Interim_Reclamation_Plat_03-06-2017.pdf

Comments:

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Section 10 - Plans for Surface Reclamation

Type of disturbance: PAD EXPANSION

Recontouring attachment:

Drainage/Erosion control construction: No sedimentation or erosion control will be necessary on this location as it is generally flat with little to no slope or cut and fill.

Drainage/Erosion control reclamation: No sedimentation or erosion control will be necessary on this location as it is generally flat with little to no slope or cut and fill.

Wellpad long term disturbance (acres): 1.99

Wellpad short term disturbance (acres): 2.206

Access road long term disturbance (acres): 0

Access road short term disturbance (acres): 0

Pipeline long term disturbance (acres): 0.16069789

Pipeline short term disturbance (acres): 0.16069789

Other long term disturbance (acres): 0

Other short term disturbance (acres): 0

Total long term disturbance: 2.150698

Total short term disturbance: 2.3666978

Reconstruction method: After well is completed, the pad will be downsized by reclaiming the areas not needed for production operations. The portions of the pad that are not needed for production operations will be re-contoured to its original state as much as possible. The caliche that is removed will be reused to either build another pad site or for road repairs within the lease.

Topsoil redistribution: The stockpiled topsoil will be spread out on reclaimed area and reseeded with a BLM approved seed mixture.

Soil treatment: Interim reclamation as identified during on-site.

Existing Vegetation at the well pad: Grassland area with sandy topsoil. Vegetation is moderately sparse with Native prairie grasses, some mesquite and shinnery oak.

Existing Vegetation at the well pad attachment:

Existing Vegetation Community at the road: Grassland area with sandy topsoil. Vegetation is moderately sparse with Native prairie grasses, some mesquite and shinnery oak.

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline: Grassland area with sandy topsoil. Vegetation is moderately sparse with Native prairie grasses, some mesquite and shinnery oak.

Existing Vegetation Community at the pipeline attachment:

Existing Vegetation Community at other disturbances: Grassland area with sandy topsoil. Vegetation is moderately sparse with Native prairie grasses, some mesquite and shinnery oak.

Existing Vegetation Community at other disturbances attachment:

Non native seed used? NO

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? NO

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? NO

Seed harvest description:

Seed harvest description attachment:

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Seed Management

Seed Table

Seed type:

Seed source:

Seed name:

Source name:

Source address:

Source phone:

Seed cultivar:

Seed use location:

PLS pounds per acre:

Proposed seeding season:

Seed Summary

Total pounds/Acre:

Seed Type	Pounds/Acre
-----------	-------------

Seed reclamation attachment:

Operator Contact/Responsible Official Contact Info

First Name:

Last Name:

Phone:

Email:

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? NO

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: Approved EPA and BLM requirements and policies for weed control methods will be followed.

Weed treatment plan attachment:

Monitoring plan description: Evaluation of growth will be made after the completion of one full growing season after seeding. -OR- BLM representative will be contacted prior to commencing construction of well pad and road. BLM representative will also be contacted prior to commencing reclamation work.

Monitoring plan attachment:

Success standards: 80% coverage by 2nd growing season of native species with less than 5% invasive species.

Pit closure description: N/A

Pit closure attachment:

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Section 11 - Surface Ownership

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: PIPELINE

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

USFS Forest/Grassland:

USFS Ranger District:

Section 12 - Other Information

Right of Way needed? NO

Use APD as ROW?

ROW Type(s):

ROW Applications

SUPO Additional Information: 1. It will be necessary to run electric power if this well is productive. Power will be provided by CVE. There will be no necessary electric line construction for this well. CVE operates an existing primary line parallel to the well pad; therefor no poles will be set off the well pad disturbance. There is no permanent or live water in the immediate area. 2. There are no dwellings within 2 miles of this location. 3. If needed, a Cultural Resources Examination is being prepared by Boone Arch Services of New Mexico, LLC. Carlsbad, NM, 88220. 506 E Chapman Rd., phone # 575.887.7667 and the results will be forwarded to your office in the near future. Otherwise, COG will be participating in the Permian Basin MOA Program.

Use a previously conducted onsite? YES

Previous Onsite information: On-site performed on 12/12/2016 by Nick Franke(BLM), Curtis Griffin(COG), Jason Morgan(RRC), Cassandra Brooks(BLM).

Other SUPO Attachment

Hobgoblin_7_Fed_Com_Flowlines_Map_03-06-2017.pdf



Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Injection well name:

Assigned injection well API number?

Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

Other regulatory requirements attachment:

Bond Info

Bond Information

Federal/Indian APD: FED

BLM Bond number: NMB000215

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment:

Operator Certification

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Robyn Odom

Signed on: 03/08/2017

Title: Regulatory Analyst

Street Address: 600 W Illinois Ave

City: Midland

State: TX

Zip: 79701

Phone: (432)685-4385

Email address: rodom@concho.com

Field Representative

Representative Name:

Street Address:

Operator Name: COG OPERATING LLC

Well Name: HOBGOBLIN 7 FEDERAL COM

Well Number: 44H

City:

State:

Zip:

Phone:

Email address:

Payment


Payment

APD Fee Payment Method: PAY.GOV

pay.gov Tracking ID: 26152MLJ

VICINITY MAP

NOT TO SCALE



*SECTION 7, TWP. 17 SOUTH, RGE. 30 EAST,
N. M. P. M., EDDY COUNTY, NEW MEXICO*

OPERATOR: COG Operating, LLC
 LEASE: Hobgoblin 7 Federal Com
 WELL NO.: 44H

LOCATION: 2310' FNL & 40' FEL
 ELEVATION: 3669'

Firm No.: TX 10193838 NM 4655451

Copyright 2016 - All Rights Reserved


NO.	REVISION	DATE
JOB NO.: LS1611396		
DWG. NO.: 1611396VM		

RRC

308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: N. T. S.
DATE: 12-15-2016
SURVEYED BY: JM/HD
DRAWN BY: CMJ
APPROVED BY: RMH
SHEET: 1 OF 1

LOCATION VERIFICATION MAP



SECTION 7, TWP. 17 SOUTH, RGE. 30 EAST,
N. M. P. M., EDDY COUNTY, NEW MEXICO

OPERATOR: COG Operating, LLC
 LEASE: Hobgoblin 7 Federal Com
 WELL NO.: 44H
 ELEVATION: 3669'

LOCATION: 2310' FNL & 40' FEL
 CONTOUR INTERVAL: 10'
 USGS TOPO. SOURCE MAP:
Red Hills SE, NM (1955)

Firm No.: TX 10193838 NM 4655451

Copyright 2016 - All Rights Reserved


NO.	REVISION	DATE
JOB NO.: LS1609297		
DWG. NO.: 1609297LVM		




308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 1000'
DATE: 12-15-2016
SURVEYED BY: JM/HD
DRAWN BY: CMJ
APPROVED BY: RMH
SHEET: 1 OF 1

Loco Hills Water Disposal Co. Water Well Map



Caswell Ranch Water Supply Map




WELL SITE AND ROAD CONSTRUCTION

1. Source of Construction Materials and Location “Turn-Over” Procedure:


Obtaining caliche: The primary way of obtaining caliche to build locations and roads will be by “turning over” the location. This means, caliche will be obtained from the actual well sight. A caliche permit will be obtained from BLM prior to pushing up any caliche. 2400 cu. Yards is max amount of caliche needed for pad and roads. Amount will vary for each pad. The procedure below has been approved by BLM personnel:

- A. The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.**
- B. An approximate 120’ X 120’ area is used within the proposed well site to remove caliche.**
- C. Subsoil is removed and piled alongside the 120’ by 120’ area within the pad site.**
- D. When caliche is found, material will be stock piled within the pad site to build the location and road.**
- E. Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.**
- F. Once well is drilled, the stock piled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced. Neither caliche nor subsoil will be stock piled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in attached plat.**
 - In the event that no caliche is found onsite, caliche will be hauled in from a BLM approved caliche pit.

NMSLO Caliche Pit



Caswell Ranch Caliche Pit Map




COG OPERATING, LLC

HOBGOBLIN 7 FEDERAL COM #44H

(2310' FNL & 40' FEL)

SECTION 7, T17S, R30E

N. M. P. M., EDDY CO., NEW MEXICO



DIRECTIONS TO LOCATION

From the intersection of U.S. Hwy. 82 and CR-217 (Hagerman Cutoff Rd.);

Go North on CR-217 approx. 0.9 miles to a lease road on the left;

Turn left and go West approx. 0.8 miles to a lease road on the right;

Turn right and go North approx. 1.5 miles to a lease road on the right;


Turn right and go Southeast approx. 0.1 miles, to location.



THIS IS NOT A BOUNDARY SURVEY, APPARENT PROPERTY CORNERS AND PROPERTY LINES ARE SHOWN FOR INFORMATION ONLY. BOUNDARY DATA IS SHOWN FROM A PREVIOUS SURVEY REFERENCED HEREON.

I, R. M. Howett, a N. M. Professional Surveyor, hereby certify that I prepared this unclassified survey of a well location from an actual survey made on the ground under my direct supervision, said survey and plat meet the Min. Stats. for Land Surveying in the State of N. M. and are true and correct to the best of my knowledge and belief.

Robert M. Howett
Robert M. Howett NM PS 19680



SCALE: 1" = 100'
0 50 100

BEARINGS ARE
NAD 83 GRID - NM EAST
DISTANCES ARE
GROUND.

Firm No. TX 10193838 NM 4655451

Copyright 2016 - All Rights Reserved


NO.	REVISION	DATE
JOB NO.: LS1609297		
DWG. NO.: 1609297PAD		



308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 100'
DATE: 12-15-2016
SURVEYED BY: JM/HD
DRAWN BY: CMJ
APPROVED BY: RMH
SHEET: 1 OF 1

COG OPERATING, LLC
INTERIM RECLAMATION
HOBGOBLIN 7 FEDERAL COM #44H
(2310' FNL & 40' FEL)
SECTION 7, T17S, R30E
N. M. P. M., EDDY CO., NEW MEXICO



DIRECTIONS TO LOCATION

From the intersection of U.S. Hwy. 82 and CR-217 (Hagerman Cutoff Rd.);
 Go North on CR-217 approx. 0.9 miles to a lease road on the left;
 Turn left and go West approx. 0.8 miles to a lease road on the right;
 Turn right and go North approx. 1.5 miles to a lease road on the right;
 Turn right and go Southeast approx. 0.1 miles, to location.



SCALE: 1" = 100'
 0 50 100

BEARINGS ARE
 NAD 83 GRID - NM EAST
 DISTANCES ARE
 GROUND.

Firm No. TX 10193838 NM 4655451

Copyright 2016 - All Rights Reserved


NO.	REVISION	DATE
JOB NO.: LS1609297		
DWG. NO.: 1609297REC		



308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 100'
DATE: 12-15-2016
SURVEYED BY: JM/HD
DRAWN BY: CMJ
APPROVED BY: RMH
SHEET: 1 OF 1

Hobgoblin 7 Federal Com #44H Surface Flowlines Map



07

08

700' Flowlines

a) Battery

Hobgoblin Fed Com 4H Battery

Hobgoblin 7 Federal Com #44H

Casing Program

	Collapse SF	Burst SF	Tension SF
BLM Minimum Safety Factor	1.125	1	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Assumed 9.0ppg MW equivalent pore pressure from 9 5/8" shoe to deepest TVD in wellbore.

BLM standard formulas were used on all SF calculations.

Casing design does meet and/or exceed BLM's minimum standards.

The pipe will be kept at a minimum 1/3 fluid fill to avoid approaching the collapse pressure rating of the casing.

This well is not located within the Capitan Reef.

This well is not located in the SOPA or in the R-111-P.

This well is not located in a high or critical Cave/Karst area.

This is not a walking operation.

We will not be pre-setting casing.

All completion intervals are planned to be fracture stimulated.

Well: Hobgoblin 7 Fed Com #44H

Hole Volumes						
Hole	Hole Section (Length)	Casing	Capacity (ft ³ /Lin.ft)	Cu.Ft	Total Cu.Ft	% Excess
Prod	0-1225 (1225)	7"	0.1585	194.16	194.16	0
Prod	1225-3605 (2380)	7"	0.1503	357.7	1322.5	91.1
Prod	3605-4433 (828)	5.5"	0.2526	209.2		91.1
Prod	4433-8793 (4360)	5.5"	0.1733	755,6		91.1

Cement Volumes					
Blend	Cement Sacks	Yield	Weight	Volume	Total Volume
35:65:6	400	2.01	12.5	804	2722
50:50:02	1400	1.37	14	1918	

% Excess Calculation			
Total Volume	2722		2527.84
Cu.Ft	-194.16		/1322.5
	2527.84		91.1%excess

Contingent Multi-Stage Cement Discussion:

COG does not anticipate losing circulation or encountering water flows while drilling this well. If these situations arise, COG requests approval in this APD to set DV tools where necessary immediately without having to shut down the rig and wait for sundry approval.

Lost Circulation or Water flow Contingent DV Tool Cement Plans are as follows:

1. If lost circulation occurs while drilling the 12 ¼" intermediate hole, it may become necessary to set a DV tool in the 9 5/8" casing. The DV tool depth will be based on hole conditions and cement volumes will be adjusted proportionally. If the DV Tool is needed, it will be set a minimum of 50 feet below the previous casing and a minimum of 200 feet above the current shoe.
2. If water flows in the San Andres are encountered, it may become necessary to set a DV tool in the 7" casing. These water flows normally occur in areas where produced water disposal is happening. This dense cement is used to combat water flows. This cement recipe also has a right angle set time and is mixed a little under saturated so the water flow will be absorbed by cement. The DV tool depth will be based on hole conditions and cement volumes will be adjusted proportionally. If the DV tool is needed, it will be set a minimum of 50 feet below the previous casing and a minimum of 200 feet above the current shoe.



NM OIL CONSERVATION
ARTESIA DISTRICT

JUL 24 2017

RECEIVED

COG Operating LLC

Eddy County, NM (NAD-27 2015)

Hobgoblin 7 Federal Com #44H

SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H

PP: 2258' FNL, 330' FEL, Sec 7, T17S, R30E, Unit H

BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2

Plan: Design #1

Standard Planning Report

01 February, 2017





TDS
Planning Report



Database: EDM 5000.1 Single User Db
Company: COG Operating LLC
Project: Eddy County, NM (NAD-27 2015)
Site: Hobgoblin 7 Federal Com #44H
Well: SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Wellbore: BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2
Design: Design #1

Local Co-ordinate Reference: Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
TVD Reference: KB @ 3687.00usft (Silver Oak 3)
MD Reference: KB @ 3687.00usft (Silver Oak 3)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Project	Eddy County, NM (NAD-27 2015)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site Hobgoblin 7 Federal Com #44H

Site Position: **From:** Map
Position Uncertainty: 0.00 usft
Northing: 673,046.60 usft
Easting: 601,637.30 usft
Slot Radius: 13.20 in
Latitude: 32° 50' 59.467 N
Longitude: 104° 0' 8.559 W
Grid Convergence: 0.18 °

Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H

Well Position **+N/-S** 0.00 usft **Northing:** 673,046.60 usft **Latitude:** 32° 50' 59.467 N
+E/-W 0.00 usft **Easting:** 601,637.30 usft **Longitude:** 104° 0' 8.559 W
Position Uncertainty 0.00 usft **Wellhead Elevation:** 0.00 usft **Ground Level:** 3,669.00 usft

Wellbore BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2015	1/31/2017	7.24	60.57	48,300

Design Design #1

Audit Notes:

Version: **Phase:** PLAN **Tie On Depth:** 0.00

Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.00	0.00	0.00	269.68

Plan Sections

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,396.05	1.92	315.00	1,396.04	1.14	-1.14	2.00	2.00	0.00	315.00	
3,409.32	1.92	315.00	3,408.17	48.86	-48.86	0.00	0.00	0.00	0.00	
3,505.38	0.00	0.00	3,504.21	50.00	-50.00	2.00	-2.00	0.00	180.00	
3,605.38	0.00	0.00	3,604.21	50.00	-50.00	0.00	0.00	0.00	0.00	
4,432.65	91.00	270.00	4,125.00	50.00	-579.96	11.00	11.00	0.00	270.00	
4,832.65	91.00	270.00	4,118.02	50.00	-979.90	0.00	0.00	0.00	0.00	
4,870.20	91.00	268.87	4,117.37	49.63	-1,017.44	3.00	0.00	-3.00	-90.07	
8,793.41	91.00	268.87	4,049.00	-27.50	-4,939.30	0.00	0.00	0.00	0.00	PBHL (H7FC#44H/L1)



TDS
Planning Report



Database: EDM 5000.1 Single User Db
 Company: COG Operating LLC
 Project: Eddy County, NM (NAD-27 2015)
 Site: Hobgoblin 7 Federal Com #44H
 Well: SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
 Wellbore: BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2
 Design: Design #1

Local Co-ordinate Reference: Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
 TVD Reference: KB @ 3687.00usft (Silver Oak 3)
 MD Reference: KB @ 3687.00usft (Silver Oak 3)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00	
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00	
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00	
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00	
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00	
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00	
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00	
Start Build 2.00										
1,396.05	1.92	315.00	1,396.04	1.14	-1.14	1.13	2.00	2.00	0.00	
Start 2013.27 hold at 1396.05 MD										
1,400.00	1.92	315.00	1,399.98	1.23	-1.23	1.23	0.00	0.00	0.00	
1,500.00	1.92	315.00	1,499.92	3.60	-3.60	3.58	0.00	0.00	0.00	
1,600.00	1.92	315.00	1,599.87	5.97	-5.97	5.94	0.00	0.00	0.00	
1,700.00	1.92	315.00	1,699.81	8.34	-8.34	8.30	0.00	0.00	0.00	
1,800.00	1.92	315.00	1,799.76	10.71	-10.71	10.65	0.00	0.00	0.00	
1,900.00	1.92	315.00	1,899.70	13.08	-13.08	13.01	0.00	0.00	0.00	
2,000.00	1.92	315.00	1,999.64	15.45	-15.45	15.37	0.00	0.00	0.00	
2,100.00	1.92	315.00	2,099.59	17.83	-17.83	17.73	0.00	0.00	0.00	
2,200.00	1.92	315.00	2,199.53	20.20	-20.20	20.08	0.00	0.00	0.00	
2,300.00	1.92	315.00	2,299.47	22.57	-22.57	22.44	0.00	0.00	0.00	
2,400.00	1.92	315.00	2,399.42	24.94	-24.94	24.80	0.00	0.00	0.00	
2,500.00	1.92	315.00	2,499.36	27.31	-27.31	27.15	0.00	0.00	0.00	
2,600.00	1.92	315.00	2,599.31	29.68	-29.68	29.51	0.00	0.00	0.00	
2,700.00	1.92	315.00	2,699.25	32.05	-32.05	31.87	0.00	0.00	0.00	
2,800.00	1.92	315.00	2,799.19	34.42	-34.42	34.23	0.00	0.00	0.00	
2,900.00	1.92	315.00	2,899.14	36.79	-36.79	36.58	0.00	0.00	0.00	
3,000.00	1.92	315.00	2,999.08	39.16	-39.16	38.94	0.00	0.00	0.00	
3,100.00	1.92	315.00	3,099.02	41.53	-41.53	41.30	0.00	0.00	0.00	
3,200.00	1.92	315.00	3,198.97	43.90	-43.90	43.65	0.00	0.00	0.00	
3,300.00	1.92	315.00	3,298.91	46.27	-46.27	46.01	0.00	0.00	0.00	
3,409.32	1.92	315.00	3,408.17	48.66	-48.66	48.59	0.00	0.00	0.00	
Start Drop -2.00										
3,505.38	0.00	0.00	3,504.21	50.00	-50.00	49.72	2.00	-2.00	46.85	
Start 100.00 hold at 3505.38 MD										
3,605.38	0.00	0.00	3,604.21	50.00	-50.00	49.72	0.00	0.00	0.00	
Start Build 11.00										
3,650.00	4.91	270.00	3,648.78	50.00	-51.91	51.63	11.00	11.00	0.00	
3,700.00	10.41	270.00	3,698.31	50.00	-58.57	58.29	11.00	11.00	0.00	
3,750.00	15.91	270.00	3,746.98	50.00	-69.95	69.67	11.00	11.00	0.00	
3,800.00	21.41	270.00	3,794.34	50.00	-85.94	85.66	11.00	11.00	0.00	
3,850.00	26.91	270.00	3,839.94	50.00	-106.39	106.11	11.00	11.00	0.00	
3,900.00	32.41	270.00	3,883.37	50.00	-131.13	130.85	11.00	11.00	0.00	
3,950.00	37.91	270.00	3,924.23	50.00	-159.91	159.63	11.00	11.00	0.00	



TDS
Planning Report



Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Company:	COG Operating LLC	TVD Reference:	KB @ 3687.00usft (Silver Oak 3)
Project:	Eddy County, NM (NAD-27 2015)	MD Reference:	KB @ 3687.00usft (Silver Oak 3)
Site:	Hobgoblin 7 Federal Com #44H	North Reference:	Grid
Well:	SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,000.00	43.41	270.00	3,962.15	50.00	-192.47	192.19	11.00	11.00	0.00
4,050.00	48.91	270.00	3,996.77	50.00	-228.52	228.24	11.00	11.00	0.00
4,100.00	54.41	270.00	4,027.78	50.00	-267.72	267.44	11.00	11.00	0.00
4,150.00	59.91	270.00	4,054.88	50.00	-309.72	309.43	11.00	11.00	0.00
4,200.00	65.41	270.00	4,077.84	50.00	-354.11	353.83	11.00	11.00	0.00
4,250.00	70.91	270.00	4,096.43	50.00	-400.51	400.22	11.00	11.00	0.00
4,300.00	76.41	270.00	4,110.49	50.00	-448.47	448.18	11.00	11.00	0.00
4,350.00	81.91	270.00	4,119.90	50.00	-497.56	497.27	11.00	11.00	0.00
4,400.00	87.41	270.00	4,124.55	50.00	-547.32	547.03	11.00	11.00	0.00
4,432.65	91.00	270.00	4,125.00	50.00	-579.96	579.67	11.00	11.00	0.00
Start 400.00 hold at 4432.65 MD									
4,500.00	91.00	270.00	4,123.83	50.00	-647.30	647.01	0.00	0.00	0.00
4,600.00	91.00	270.00	4,122.08	50.00	-747.29	747.00	0.00	0.00	0.00
4,700.00	91.00	270.00	4,120.34	50.00	-847.27	846.98	0.00	0.00	0.00
4,800.00	91.00	270.00	4,118.59	50.00	-947.25	946.96	0.00	0.00	0.00
4,832.65	91.00	270.00	4,118.02	50.00	-979.90	979.61	0.00	0.00	0.00
Start DLS 3.00 TFO -90.07									
4,870.20	91.00	268.87	4,117.37	49.63	-1,017.44	1,017.15	3.00	0.00	-3.00
Start 3923.21 hold at 4870.20 MD									
4,900.00	91.00	268.87	4,116.85	49.05	-1,047.23	1,046.94	0.00	0.00	0.00
5,000.00	91.00	268.87	4,115.10	47.08	-1,147.20	1,146.92	0.00	0.00	0.00
5,100.00	91.00	268.87	4,113.36	45.11	-1,247.16	1,246.89	0.00	0.00	0.00
5,200.00	91.00	268.87	4,111.62	43.15	-1,347.13	1,346.87	0.00	0.00	0.00
5,300.00	91.00	268.87	4,109.88	41.18	-1,447.09	1,446.84	0.00	0.00	0.00
5,400.00	91.00	268.87	4,108.13	39.21	-1,547.06	1,546.82	0.00	0.00	0.00
5,500.00	91.00	268.87	4,106.39	37.25	-1,647.02	1,646.79	0.00	0.00	0.00
5,600.00	91.00	268.87	4,104.65	35.28	-1,746.99	1,746.77	0.00	0.00	0.00
5,700.00	91.00	268.87	4,102.91	33.32	-1,846.96	1,846.74	0.00	0.00	0.00
5,800.00	91.00	268.87	4,101.16	31.35	-1,946.92	1,946.72	0.00	0.00	0.00
5,900.00	91.00	268.87	4,099.42	29.38	-2,046.89	2,046.69	0.00	0.00	0.00
6,000.00	91.00	268.87	4,097.68	27.42	-2,146.85	2,146.67	0.00	0.00	0.00
6,100.00	91.00	268.87	4,095.94	25.45	-2,246.82	2,246.64	0.00	0.00	0.00
6,200.00	91.00	268.87	4,094.19	23.49	-2,346.78	2,346.62	0.00	0.00	0.00
6,300.00	91.00	268.87	4,092.45	21.52	-2,446.75	2,446.59	0.00	0.00	0.00
6,400.00	91.00	268.87	4,090.71	19.55	-2,546.71	2,546.57	0.00	0.00	0.00
6,500.00	91.00	268.87	4,088.96	17.59	-2,646.68	2,646.54	0.00	0.00	0.00
6,600.00	91.00	268.87	4,087.22	15.62	-2,746.64	2,746.52	0.00	0.00	0.00
6,700.00	91.00	268.87	4,085.48	13.66	-2,846.61	2,846.49	0.00	0.00	0.00
6,800.00	91.00	268.87	4,083.74	11.69	-2,946.58	2,946.47	0.00	0.00	0.00
6,900.00	91.00	268.87	4,081.99	9.72	-3,046.54	3,046.44	0.00	0.00	0.00
7,000.00	91.00	268.87	4,080.25	7.76	-3,146.51	3,146.41	0.00	0.00	0.00
7,100.00	91.00	268.87	4,078.51	5.79	-3,246.47	3,246.39	0.00	0.00	0.00
7,200.00	91.00	268.87	4,076.77	3.83	-3,346.44	3,346.36	0.00	0.00	0.00
7,300.00	91.00	268.87	4,075.02	1.86	-3,446.40	3,446.34	0.00	0.00	0.00
7,400.00	91.00	268.87	4,073.28	-0.11	-3,546.37	3,546.31	0.00	0.00	0.00
7,500.00	91.00	268.87	4,071.54	-2.07	-3,646.33	3,646.29	0.00	0.00	0.00
7,600.00	91.00	268.87	4,069.80	-4.04	-3,746.30	3,746.26	0.00	0.00	0.00
7,700.00	91.00	268.87	4,068.05	-6.00	-3,846.27	3,846.24	0.00	0.00	0.00
7,800.00	91.00	268.87	4,066.31	-7.97	-3,946.23	3,946.21	0.00	0.00	0.00
7,900.00	91.00	268.87	4,064.57	-9.94	-4,046.20	4,046.19	0.00	0.00	0.00
8,000.00	91.00	268.87	4,062.83	-11.90	-4,146.16	4,146.16	0.00	0.00	0.00



TDS
Planning Report



Database: EDM 5000.1 Single User Db
Company: COG Operating LLC
Project: Eddy County, NM (NAD-27 2015)
Site: Hobgoblin 7 Federal Com #44H
Well: SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Wellbore: BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2
Design: Design #1

Local Co-ordinate Reference: Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
TVD Reference: KB @ 3687.00usft (Silver Oak 3)
MD Reference: KB @ 3687.00usft (Silver Oak 3)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
8,100.00	91.00	268.87	4,061.08	-13.87	-4,246.13	4,246.14	0.00	0.00	0.00
8,200.00	91.00	268.87	4,059.34	-15.83	-4,346.09	4,346.11	0.00	0.00	0.00
8,300.00	91.00	268.87	4,057.60	-17.80	-4,446.06	4,446.09	0.00	0.00	0.00
8,400.00	91.00	268.87	4,055.86	-19.77	-4,546.02	4,546.06	0.00	0.00	0.00
8,500.00	91.00	268.87	4,054.11	-21.73	-4,645.99	4,646.04	0.00	0.00	0.00
8,600.00	91.00	268.87	4,052.37	-23.70	-4,745.95	4,746.01	0.00	0.00	0.00
8,700.00	91.00	268.87	4,050.63	-25.66	-4,845.92	4,845.99	0.00	0.00	0.00
8,793.41	91.00	268.87	4,049.00	-27.50	-4,939.30	4,939.38	0.00	0.00	0.00
TD at 8793.41									

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
39.54' Radius @ 4117.6' - plan misses target center by 949.82usft at 0.00usft MD (0.00 TVD, 0.00 N, 0.00 E) - Circle (radius 39.54)	0.00	0.01	0.00	-5.90	-949.80	673,040.70	600,687.50	32° 50' 59.438 N	104° 0' 19.693 W
KOP (H7FC#44H/L1) - plan hits target center - Point	0.00	0.00	3,604.21	50.00	-50.00	673,096.60	601,587.30	32° 50' 59.963 N	104° 0' 9.143 W
PP (H7FC#44H/L1) - plan hits target center - Point	0.00	0.00	4,042.96	50.00	-290.15	673,096.60	601,347.15	32° 50' 59.971 N	104° 0' 11.958 W
PBHL (H7FC#44H/L1) - plan hits target center - Point	0.00	0.00	4,049.00	-27.50	-4,939.30	673,019.10	596,698.00	32° 50' 59.344 N	104° 1' 6.460 W
END TURN (H7FC#44H) - plan hits target center - Point	0.00	0.00	4,117.37	49.63	-1,017.44	673,096.23	600,619.86	32° 50' 59.989 N	104° 0' 20.483 W
TURN (H7FC#44H/L1) - plan hits target center - Point	0.00	0.00	4,118.02	50.00	-979.90	673,096.60	600,657.40	32° 50' 59.992 N	104° 0' 20.043 W
EOC (H7FC#44H/L1) - plan hits target center - Point	0.00	0.00	4,125.00	50.00	-579.96	673,096.60	601,057.34	32° 50' 59.980 N	104° 0' 15.355 W



TDS
Planning Report






Database: EDM 5000.1 Single User Db
Company: COG Operating LLC
Project: Eddy County, NM (NAD-27 2015)
Site: Hobgoblin 7 Federal Com #44H
Well: SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Wellbore: BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2
Design: Design #1

Local Co-ordinate Reference: Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
TVD Reference: KB @ 3687.00usft (Silver Oak 3)
MD Reference: KB @ 3687.00usft (Silver Oak 3)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Plan Annotations





Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
1,300.00	1,300.00	0.00	0.00	Start Build 2.00
1,396.05	1,396.04	1.14	-1.14	Start 2013.27 hold at 1396.05 MD
3,409.32	3,408.17	48.86	-48.86	Start Drop -2.00
3,505.38	3,504.21	50.00	-50.00	Start 100.00 hold at 3505.38 MD
3,605.38	3,604.21	50.00	-50.00	Start Build 11.00
4,432.65	4,125.00	50.00	-579.96	Start 400.00 hold at 4432.65 MD
4,832.65	4,118.02	50.00	-979.90	Start DLS 3.00 TFO -90.07
4,870.20	4,117.37	49.63	-1,017.44	Start 3923.21 hold at 4870.20 MD
8,793.41	4,049.00	-27.50	-4,939.30	TD at 8793.41

COG Operating LLC
 Project: Eddy County, NM (NAD-27 2015)
 Site: Hobgoblin 7 Federal Com #44H
 Well: SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
 Wellbore: BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2
 Plan: Design #1 (SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H/BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2)



Section Details

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSec	Target
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2	1300.00	0.00	0.00	1300.00	0.00	0.00	0.00	0.00	0.00	0.00
3	1396.05	1.92	315.00	1396.04	1.14	-1.14	2.00	315.00	1.13	1.13
4	3409.32	1.92	315.00	3408.17	48.86	-48.86	0.00	0.00	48.59	48.59
5	3505.38	0.00	0.00	3504.21	50.00	-50.00	2.00	180.00	49.72	49.72
6	3605.38	0.00	0.00	3604.21	50.00	-50.00	0.00	0.00	49.72	49.72
7	4432.65	91.00	270.00	4125.00	50.00	-579.96	11.00	270.00	579.67	579.67
8	4832.65	91.00	270.00	4118.02	50.00	-979.90	0.00	0.00	979.61	979.61
9	4870.20	91.00	268.87	4117.37	49.63	-1017.44	3.00	-90.07	1017.15	1017.15
10	8793.41	91.00	268.87	4049.00	-27.50	-4939.30	0.00	0.00	4939.38	4939.38



PROJECT DETAILS: Eddy County, NM (NAD-27 2015)
 Geoid System: US State Plane 1927 (Exact solution)
 Datum: NAD 1927 (NADCON CONUS)
 Ellipsoid: Clarke 1866
 Zone: New Mexico East 3001
 System Datum: Mean Sea Level
 Local North: Grid

Ground Elevation: 3689.00
 RKB Elevation: KB @ 3687.00usft (Silver Oak 3)
 Northing: 673046.60
 Easting: 601637.30
 Latitude: 32° 50' 59.467" N
 Longitude: 104° 0' 8.559" W

Terra Directional Services LLC
 3705 South County Road 1210, Midland, TX 79706
 Phone: 432-618-1210



NM OIL CONSERVATION
ARTESIA DISTRICT

JUL 24 2017

COG Operating LLC

Eddy County, NM (NAD-27 2015)

Hobgoblin 7 Federal Com #44H

SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H

PP: 2258' FNL, 330' FEL, Sec 7, T17S, R30E, Unit H

BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2

Design #1

RECEIVED

Anticollision Report

01 February, 2017





TDS
Anticollision Report



Company:	COG Operating LLC	Local Co-ordinate Reference:	Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Project:	Eddy County, NM (NAD-27 2015)	TVD Reference:	KB @ 3687.00usft (Silver Oak 3)
Reference Site:	Hobgoblin 7 Federal Com #44H	MD Reference:	KB @ 3687.00usft (Silver Oak 3)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Reference	Design #1
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria
Interpolation Method:	Stations
Depth Range:	Unlimited
Results Limited by:	Maximum center-center distance of 9,999.98 usft
Warning Levels Evaluated at:	2.00 Sigma
Error Model:	ISCWSA
Scan Method:	Closest Approach 3D
Error Surface:	Elliptical Conic
Casing Method:	Not applied

From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description
0.00	8,793.41	Design #1 (BHL: 2307' FNL, 220' FWL, Se	MWD	MWD - Standard

Site Name	Reference		Offset		Distance		Separation Factor	Warning
	Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Between Centres (usft)	Between Ellipses (usft)		
Offset Well - Wellbore - Design								
Eddy County Offset Wells								
Brantley Federal #1 - OH - OH	4,800.00	4,121.99	16.54	-91.94	0.152	Level 1, SF		
Brantley Federal #1 - OH - OH	4,802.54	4,121.94	16.35	-90.18	0.153	Level 1, CC		
Brantley Federal #1 - OH - OH	4,832.65	4,121.42	34.26	-116.11	0.228	Level 1, ES		
Hobgoblin 7 Federal Com UBB #4H - OH - OH	3,810.21	3,802.12	49.26	34.26	3.283	CC, ES, SF		
Hobgoblin 7 Federal Com #14H								
SHL: 2260' FNL, 10' FEL, Sec 7, T17S, R30E, Unit H - B	1,782.54	1,779.31	56.57	48.85	7.327	CC		
SHL: 2260' FNL, 10' FEL, Sec 7, T17S, R30E, Unit H - B	2,000.00	1,996.64	57.04	48.34	6.560	ES		
SHL: 2260' FNL, 10' FEL, Sec 7, T17S, R30E, Unit H - B	3,605.38	3,601.21	79.70	63.85	5.029	SF		

Offset Design													Offset Site Error:	0.00 usft
Eddy County Offset Wells - Brantley Federal #1 - OH - OH													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Tooface (")	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
0.00	0.00	3.00	3.00	0.00	0.05	-90.36	-5.90	-949.80	949.82					
100.00	100.00	103.03	103.03	0.09	2.32	-90.34	-5.59	-949.80	949.82	947.40	2.41	393.448		
200.00	200.00	203.06	203.06	0.32	4.58	-90.28	-4.70	-949.80	949.81	944.92	4.89	194.116		
300.00	300.00	303.07	303.05	0.54	9.19	-90.20	-3.33	-949.80	949.81	940.08	9.73	97.644		
400.00	400.00	403.06	403.03	0.77	14.46	-90.10	-1.72	-949.80	949.80	934.58	15.22	62.393		
500.00	500.00	503.04	503.00	0.99	20.25	-90.00	0.03	-949.80	949.80	928.56	21.24	44.720		
503.26	503.26	506.30	506.26	1.00	20.44	-90.00	0.08	-949.80	949.80	928.36	21.44	44.309		
600.00	600.00	603.03	602.97	1.22	26.56	-89.89	1.80	-949.80	949.80	922.02	27.78	34.192		
700.00	700.00	702.99	702.91	1.44	33.68	-89.77	3.89	-949.80	949.81	914.68	35.12	27.041		
800.00	800.00	802.95	802.84	1.67	40.70	-89.62	6.36	-949.80	949.82	907.45	42.37	22.419		
900.00	900.00	902.97	902.83	1.89	47.13	-89.48	8.61	-949.80	949.84	900.81	49.02	19.375		
1,000.00	1,000.00	1,003.01	1,002.86	2.12	53.57	-89.38	10.31	-949.80	949.85	894.17	55.68	17.059		
1,100.00	1,100.00	1,103.01	1,102.85	2.34	58.46	-89.30	11.63	-949.80	949.87	889.08	60.79	15.625		
1,200.00	1,200.00	1,203.01	1,202.84	2.56	62.68	-89.22	12.93	-949.80	949.89	884.65	65.24	14.560		
1,300.00	1,300.00	1,303.05	1,302.87	2.79	65.83	-89.16	14.01	-949.80	949.90	881.29	68.61	13.845		
1,396.05	1,396.04	1,399.13	1,398.95	3.00	68.85	-44.19	14.75	-949.80	948.76	876.91	71.84	13.206		

CC - Min centre to center distance or convergent point. SF - min separation factor, ES - min ellipse separation



TDS
Anticollision Report



Company: COG Operating LLC
Project: Eddy County, NM (NAD-27 2015)
Reference Site: Hobgoblin 7 Federal Com #44H
Site Error: 0.00 usft
Reference Well: SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Well Error: 0.00 usft
Reference Wellbore: BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2
Reference Design: Design #1

Local Co-ordinate Reference: Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
TVD Reference: KB @ 3687.00usft (Silver Oak 3)
MD Reference: KB @ 3687.00usft (Silver Oak 3)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.1 Single User Db
Offset TVD Reference: Offset Datum

Offset Design Eddy County Offset Wells - Brantley Federal #1 - OH - OH													Offset Site Error:	0.00 usft
Survey Program: 225-INC													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
1,400.00	1,399.98	1,403.08	1,402.90	3.01	68.97	-44.20	14.77	-949.80	948.66	876.69	71.98	13.180		
1,500.00	1,499.92	1,503.04	1,502.86	3.23	72.00	-44.31	15.24	-949.80	946.27	871.05	75.22	12.580		
1,600.00	1,599.87	1,602.97	1,602.79	3.45	74.87	-44.41	16.03	-949.80	943.88	865.57	78.31	12.053		
1,700.00	1,699.81	1,702.94	1,702.75	3.67	77.93	-44.50	16.79	-949.80	941.49	859.90	81.59	11.539		
1,800.00	1,799.76	1,802.89	1,802.70	3.89	81.00	-44.60	17.53	-949.80	939.11	854.23	84.88	11.064		
1,900.00	1,899.70	1,902.84	1,902.65	4.12	84.10	-44.69	18.36	-949.80	936.73	848.52	88.21	10.620		
2,000.00	1,999.64	2,002.79	2,002.60	4.34	88.20	-44.77	19.40	-949.80	934.35	841.83	92.53	10.098		
2,100.00	2,099.59	2,102.75	2,102.55	4.57	92.50	-44.84	20.73	-949.80	931.98	834.93	97.05	9.603		
2,200.00	2,199.53	2,202.72	2,202.51	4.79	96.94	-44.91	22.00	-949.80	929.60	827.89	101.71	9.139		
2,300.00	2,299.47	2,302.69	2,302.47	5.02	100.79	-44.98	23.09	-949.80	927.23	821.44	105.79	8.765		
2,400.00	2,399.42	2,402.65	2,402.43	5.25	104.68	-45.07	24.02	-949.80	924.86	814.96	109.90	8.416		
2,500.00	2,499.36	2,502.62	2,502.39	5.48	108.63	-45.15	25.13	-949.80	922.49	808.42	114.07	8.087		
2,600.00	2,599.31	2,602.56	2,602.33	5.70	111.79	-45.24	26.03	-949.80	920.13	802.66	117.47	7.833		
2,700.00	2,699.25	2,702.51	2,702.27	5.93	114.19	-45.36	26.55	-949.80	917.77	797.68	120.08	7.643		
2,800.00	2,799.19	2,802.45	2,802.22	6.16	116.32	-45.49	26.92	-949.80	915.41	792.97	122.44	7.477		
2,900.00	2,899.14	2,902.41	2,902.17	6.39	118.22	-45.61	27.27	-949.80	913.06	788.49	124.57	7.330		
3,000.00	2,999.08	3,002.36	3,002.13	6.62	120.31	-45.74	27.64	-949.80	910.71	783.83	126.88	7.178		
3,100.00	3,099.02	3,102.33	3,102.09	6.85	122.51	-45.86	28.08	-949.80	908.37	779.07	129.30	7.025		
3,200.00	3,198.97	3,202.30	3,202.06	7.08	125.02	-45.98	28.61	-949.80	906.03	773.99	132.04	6.862		
3,300.00	3,298.91	3,302.30	3,302.06	7.30	127.94	-46.09	29.34	-949.80	903.69	768.51	135.17	6.685		
3,409.32	3,408.17	3,411.50	3,411.26	7.56	130.42	-46.21	30.08	-949.80	901.13	763.23	137.90	6.535		
3,505.38	3,504.21	3,507.46	3,507.21	7.75	132.53	-91.25	30.30	-949.80	900.01	759.81	140.20	6.420		
3,605.38	3,604.21	3,607.51	3,607.26	7.94	134.29	-91.25	30.43	-949.80	900.01	757.85	142.16	6.331		
3,650.00	3,648.78	3,652.10	3,651.85	8.04	135.07	-1.24	30.58	-949.80	898.10	755.06	143.03	6.279		
3,700.00	3,698.31	3,701.66	3,701.41	8.17	135.95	-1.25	30.80	-949.80	891.43	747.40	144.03	6.189		
3,750.00	3,746.98	3,750.33	3,750.09	8.30	137.28	-1.28	31.07	-949.80	880.05	734.58	145.47	6.050		
3,800.00	3,794.34	3,797.69	3,797.45	8.46	138.57	-1.33	31.34	-949.80	864.06	717.18	146.88	5.883		
3,850.00	3,839.94	3,843.30	3,843.05	8.64	139.81	-1.40	31.62	-949.80	843.60	695.36	148.24	5.691		
3,900.00	3,883.37	3,886.74	3,886.49	8.86	140.99	-1.50	31.89	-949.80	818.87	669.33	149.54	5.476		
3,950.00	3,924.23	3,927.61	3,927.36	9.14	142.10	-1.64	32.17	-949.80	790.09	639.32	150.77	5.240		
4,000.00	3,962.15	3,965.53	3,965.27	9.48	143.18	-1.83	32.43	-949.80	757.53	605.56	151.97	4.985		
4,050.00	3,996.77	4,000.15	3,999.90	9.91	144.28	-2.09	32.68	-949.80	721.48	568.31	153.18	4.710		
4,100.00	4,027.78	4,031.16	4,030.91	10.44	145.26	-2.47	32.91	-949.80	682.29	528.03	154.26	4.423		
4,150.00	4,054.88	4,058.27	4,058.02	11.07	146.13	-3.01	33.13	-949.80	640.30	485.10	155.21	4.125		
4,200.00	4,077.84	4,081.23	4,080.97	11.81	146.85	-3.85	33.31	-949.80	595.92	439.90	156.01	3.820		
4,250.00	4,096.43	4,099.82	4,099.57	12.65	147.44	-5.26	33.47	-949.80	549.54	392.87	156.67	3.508		
4,300.00	4,110.49	4,113.89	4,113.63	13.59	147.89	-7.94	33.58	-949.80	501.60	344.44	157.16	3.192		
4,350.00	4,119.90	4,123.29	4,123.04	14.60	148.19	-14.42	33.66	-949.80	452.54	295.05	157.49	2.874		
4,400.00	4,124.55	4,127.94	4,127.69	15.67	148.34	-42.06	33.70	-949.80	402.81	245.16	157.65	2.555		
4,432.65	4,125.00	4,128.40	4,128.14	16.39	148.35	-112.04	33.71	-949.80	370.19	212.54	157.66	2.348		
4,500.00	4,123.83	4,127.22	4,126.97	17.93	148.31	-108.39	33.70	-949.80	302.93	145.33	157.60	1.922		
4,600.00	4,122.08	4,125.48	4,125.22	20.31	148.26	-102.69	33.68	-949.80	203.17	45.69	157.47	1.290 Level 3		
4,700.00	4,120.34	4,123.73	4,123.48	22.78	148.20	-96.74	33.67	-949.80	103.82	-53.18	157.00	0.661 Level 1		
4,800.00	4,118.59	4,121.99	4,121.73	25.31	148.15	-90.65	33.65	-949.80	16.54	-91.94	108.49	0.152 Level 1, SF		
4,802.54	4,118.55	4,121.94	4,121.69	25.37	148.15	-90.49	33.65	-949.80	16.35	-90.18	106.53	0.153 Level 1, CC		
4,832.65	4,118.02	4,121.42	4,121.16	26.14	148.13	-88.65	33.65	-949.80	34.26	-116.11	150.37	0.228 Level 1, ES		
4,870.20	4,117.37	4,120.76	4,120.50	27.10	148.11	-86.57	33.64	-949.80	69.51	-86.58	156.09	0.445 Level 1		
4,900.00	4,116.85	4,120.23	4,119.98	27.87	148.09	-84.85	33.64	-949.80	98.65	-58.18	156.83	0.629 Level 1		
5,000.00	4,115.10	4,118.47	4,118.22	30.47	148.04	-79.16	33.62	-949.80	197.86	40.60	157.26	1.258 Level 3		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation



TDS
Anticollision Report



Company: COG Operating LLC
Project: Eddy County, NM (NAD-27 2015)
Reference Site: Hobgoblin 7 Federal Com #44H
Site Error: 0.00 usft
Reference Well: SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Well Error: 0.00 usft
Reference Wellbore: BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2
Reference Design: Design #1

Local Co-ordinate Reference: Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
TVD Reference: KB @ 3687.00usft (Silver Oak 3)
MD Reference: KB @ 3687.00usft (Silver Oak 3)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.1 Single User Db
Offset TVD Reference: Offset Datum

Offset Design Eddy County Offset Wells - Brantley Federal #1 - OH - OH														Offset Site Error:	0.00 usft
Survey Program: 225-INC														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance				Warning				
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning		
5,100.00	4,113.36	4,116.71	4,116.46	33.10	147.98	-73.68	33.61	-949.80	297.59	140.30	157.29	1.892			
5,200.00	4,111.62	4,114.95	4,114.70	35.74	147.92	-68.50	33.59	-949.80	397.45	240.18	157.26	2.527			
5,300.00	4,109.88	4,113.20	4,112.94	38.40	147.87	-63.68	33.58	-949.80	497.36	340.13	157.22	3.163			
5,400.00	4,108.13	4,111.44	4,111.18	41.07	147.81	-59.23	33.56	-949.80	597.29	440.11	157.17	3.800			
5,500.00	4,106.39	4,109.68	4,109.42	43.76	147.76	-55.17	33.55	-949.80	697.24	540.11	157.13	4.437			
5,600.00	4,104.65	4,107.92	4,107.66	46.45	147.70	-51.47	33.53	-949.80	797.20	640.12	157.08	5.075			
5,700.00	4,102.91	4,106.16	4,105.90	49.15	147.65	-48.13	33.52	-949.80	897.16	740.13	157.03	5.713			
5,800.00	4,101.16	4,104.40	4,104.14	51.85	147.59	-45.10	33.50	-949.80	997.13	840.14	156.98	6.352			
5,900.00	4,099.42	4,102.64	4,102.39	54.56	147.53	-42.37	33.49	-949.80	1,097.10	940.16	156.94	6.991			
6,000.00	4,097.68	4,100.88	4,100.63	57.27	147.48	-39.90	33.47	-949.80	1,197.07	1,040.18	156.89	7.630			
6,100.00	4,095.94	4,099.12	4,098.87	59.99	147.42	-37.67	33.46	-949.80	1,297.05	1,140.20	156.84	8.270			
6,200.00	4,094.19	4,097.36	4,097.11	62.71	147.37	-35.64	33.45	-949.80	1,397.02	1,240.23	156.80	8.910			
6,300.00	4,092.45	4,095.60	4,095.35	65.44	147.31	-33.80	33.43	-949.80	1,497.00	1,340.25	156.75	9.550			
6,400.00	4,090.71	4,093.85	4,093.59	68.16	147.25	-32.12	33.42	-949.80	1,596.98	1,440.27	156.71	10.191			
6,500.00	4,088.96	4,092.09	4,091.83	70.89	147.20	-30.59	33.40	-949.80	1,696.96	1,540.30	156.66	10.832			
6,600.00	4,087.22	4,090.33	4,090.07	73.62	147.14	-29.18	33.39	-949.80	1,796.94	1,640.32	156.62	11.473			
6,700.00	4,085.48	4,088.57	4,088.32	76.36	147.09	-27.90	33.37	-949.80	1,896.92	1,740.34	156.57	12.115			
6,800.00	4,083.74	4,086.81	4,086.56	79.09	147.03	-26.71	33.36	-949.80	1,996.90	1,840.37	156.53	12.757			
6,900.00	4,081.99	4,085.05	4,084.80	81.83	146.98	-25.62	33.34	-949.80	2,096.88	1,940.39	156.49	13.400			
7,000.00	4,080.25	4,083.29	4,083.04	84.56	146.92	-24.61	33.33	-949.80	2,196.86	2,040.41	156.45	14.042			
7,100.00	4,078.51	4,081.54	4,081.28	87.30	146.86	-23.67	33.31	-949.80	2,296.84	2,140.43	156.41	14.685			
7,200.00	4,076.77	4,079.78	4,079.52	90.04	146.81	-22.80	33.30	-949.80	2,396.82	2,240.46	156.37	15.328			
7,300.00	4,075.02	4,078.02	4,077.77	92.78	146.75	-21.99	33.29	-949.80	2,496.80	2,340.48	156.33	15.972			
7,400.00	4,073.28	4,076.26	4,076.01	95.52	146.70	-21.23	33.27	-949.80	2,596.79	2,440.50	156.29	16.616			
7,500.00	4,071.54	4,074.50	4,074.25	98.26	146.64	-20.52	33.26	-949.80	2,696.77	2,540.52	156.25	17.260			
7,600.00	4,069.80	4,072.75	4,072.49	101.01	146.58	-19.86	33.24	-949.80	2,796.75	2,640.54	156.21	17.904			
7,700.00	4,068.05	4,070.99	4,070.73	103.75	146.53	-19.24	33.23	-949.80	2,896.73	2,740.56	156.17	18.549			
7,800.00	4,066.31	4,069.23	4,068.98	106.49	146.47	-18.66	33.21	-949.80	2,996.72	2,840.58	156.13	19.193			
7,900.00	4,064.57	4,067.47	4,067.22	109.24	146.42	-18.11	33.20	-949.80	3,096.70	2,940.60	156.10	19.838			
8,000.00	4,062.83	4,065.71	4,065.46	111.98	146.36	-17.59	33.19	-949.80	3,196.68	3,040.62	156.06	20.484			
8,100.00	4,061.08	4,063.96	4,063.70	114.73	146.31	-17.10	33.17	-949.80	3,296.67	3,140.64	156.02	21.129			
8,200.00	4,059.34	4,062.20	4,061.95	117.47	146.25	-16.63	33.16	-949.80	3,396.65	3,240.66	155.99	21.775			
8,300.00	4,057.60	4,060.44	4,060.19	120.22	146.19	-16.19	33.14	-949.80	3,496.63	3,340.68	155.95	22.421			
8,400.00	4,055.86	4,058.68	4,058.43	122.97	146.14	-15.78	33.13	-949.80	3,596.62	3,440.70	155.92	23.067			
8,500.00	4,054.11	4,056.93	4,056.67	125.72	146.08	-15.38	33.12	-949.80	3,696.60	3,540.72	155.88	23.714			
8,600.00	4,052.37	4,055.17	4,054.92	128.46	146.03	-15.01	33.10	-949.80	3,796.58	3,640.73	155.85	24.360			
8,700.00	4,050.63	4,053.41	4,053.16	131.21	145.97	-14.65	33.09	-949.80	3,896.57	3,740.75	155.82	25.007			
8,793.41	4,049.00	4,051.77	4,051.52	133.78	145.92	-14.33	33.08	-949.80	3,989.96	3,834.18	155.79	25.612			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



TDS
Anticollision Report



Company: COG Operating LLC
Project: Eddy County, NM (NAD-27 2015)
Reference Site: Hobgoblin 7 Federal Com #44H
Site Error: 0.00 usft
Reference Well: SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Well Error: 0.00 usft
Reference Wellbore: BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2
Reference Design: Design #1

Local Co-ordinate Reference: Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
TVD Reference: KB @ 3687.00usft (Silver Oak 3)
MD Reference: KB @ 3687.00usft (Silver Oak 3)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: EDM 5000.1 Single User Db
Offset TVD Reference: Offset Datum

Offset Design														Offset Site Error:
Eddy County Offset Wells - Hobgoblin 7 Federal Com UBB #4H - OH - OH														0.00 usft
Survey Program: 100-VES-JSCWSA-GYRO-3. 4509-MWD														Offset Well Error:
														0.00 usft
Reference		Offset		Semi Major Axis		Highside		Offset Wellbore Centre		Distance		Minimum Separation		Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Tooface (")	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Ellipses (usft)	Separation (usft)	Factor		
0.00	0.00	0.00	0.00	0.00	0.00	-90.31	-0.60	-110.10	110.11					
100.00	100.00	98.28	98.28	0.09	0.08	-90.35	-0.68	-110.20	110.20	110.03	0.17	651.742		
200.00	200.00	197.82	197.82	0.32	0.26	-90.42	-0.82	-110.60	110.60	110.02	0.58	191.256		
300.00	300.00	298.21	298.21	0.54	0.44	-90.36	-0.69	-111.04	111.05	110.06	0.98	112.819		
400.00	400.00	398.58	398.57	0.77	0.62	-90.35	-0.68	-111.14	111.14	109.76	1.38	80.453		
500.00	500.00	498.27	499.27	0.99	0.78	-90.46	-0.88	-110.76	110.77	108.99	1.77	62.466		
600.00	600.00	599.29	599.29	1.22	0.95	-90.29	-0.55	-110.06	110.06	107.90	2.17	50.822		
700.00	700.00	698.62	698.61	1.44	1.12	-90.03	-0.06	-109.65	109.65	107.09	2.56	42.822		
800.00	800.00	799.58	799.57	1.67	1.30	-89.78	0.43	-109.11	109.12	106.16	2.96	36.617		
900.00	900.00	900.36	900.34	1.89	1.48	-89.58	0.80	-107.76	107.78	104.41	3.37	31.984		
1,000.00	1,000.00	1,000.03	1,000.00	2.12	1.66	-89.52	0.89	-106.20	106.22	102.45	3.77	28.164		
1,100.00	1,100.00	1,100.45	1,100.40	2.34	1.84	-89.35	1.19	-104.58	104.60	100.42	4.18	25.031		
1,200.00	1,200.00	1,200.94	1,200.87	2.56	2.02	-89.09	1.63	-102.49	102.53	97.95	4.59	22.348		
1,300.00	1,300.00	1,300.00	1,299.91	2.79	2.20	-88.97	1.80	-100.47	100.50	95.51	4.99	20.135		
1,396.05	1,396.04	1,395.38	1,395.28	3.00	2.38	-44.66	1.76	-99.27	98.13	92.76	5.38	18.249		
1,400.00	1,399.98	1,399.29	1,399.19	3.01	2.39	-44.72	1.76	-99.24	98.01	92.62	5.39	18.171		
1,500.00	1,499.92	1,499.24	1,499.14	3.23	2.57	-46.11	1.80	-98.51	94.92	89.13	5.80	16.379		
1,600.00	1,599.87	1,599.06	1,598.96	3.45	2.76	-47.55	1.93	-97.81	91.93	85.73	6.20	14.830		
1,700.00	1,699.81	1,699.04	1,698.93	3.67	2.94	-49.15	1.93	-97.14	89.03	82.42	6.60	13.480		
1,800.00	1,799.76	1,799.08	1,798.97	3.89	3.13	-50.93	1.86	-96.37	86.11	79.10	7.01	12.281		
1,900.00	1,899.70	1,898.69	1,898.57	4.12	3.31	-52.69	1.95	-95.74	83.40	75.98	7.42	11.243		
2,000.00	1,999.64	1,998.32	1,998.20	4.34	3.49	-54.31	2.35	-95.54	81.15	73.33	7.82	10.378		
2,100.00	2,099.59	2,098.48	2,098.37	4.57	3.67	-56.17	2.55	-95.35	79.02	70.80	8.22	9.611		
2,200.00	2,199.53	2,198.02	2,197.90	4.79	3.84	-58.39	2.35	-95.20	77.10	68.49	8.62	8.948		
2,300.00	2,299.47	2,297.88	2,297.76	5.02	4.00	-60.57	2.27	-95.42	75.63	66.63	9.00	8.402		
2,400.00	2,399.42	2,398.64	2,398.53	5.25	4.17	-62.84	2.37	-95.18	73.78	64.38	9.40	7.848		
2,500.00	2,499.36	2,498.33	2,498.21	5.48	4.35	-65.66	2.05	-94.35	71.64	61.84	9.81	7.305		
2,600.00	2,599.31	2,598.29	2,598.16	5.70	4.53	-68.78	1.53	-93.61	69.85	59.64	10.21	6.840		
2,700.00	2,699.25	2,697.76	2,697.63	5.93	4.70	-71.66	1.30	-93.31	68.55	57.94	10.61	6.462		
2,800.00	2,799.19	2,798.25	2,798.12	6.16	4.88	-74.29	1.49	-93.17	67.35	56.34	11.01	6.118		
2,900.00	2,899.14	2,897.90	2,897.77	6.39	5.06	-77.21	1.57	-92.70	66.08	54.67	11.41	5.790		
3,000.00	2,999.08	2,998.09	2,997.96	6.62	5.24	-80.58	1.32	-92.08	65.05	53.24	11.82	5.505		
3,100.00	3,099.02	3,097.62	3,097.49	6.85	5.41	-83.58	1.42	-91.82	64.32	52.11	12.22	5.265		
3,200.00	3,198.97	3,197.82	3,197.69	7.08	5.58	-86.70	1.40	-91.61	63.89	51.27	12.62	5.064		
3,258.03	3,256.97	3,255.56	3,255.42	7.21	5.68	-88.74	1.21	-91.32	63.73	50.88	12.85	4.961		
3,300.00	3,298.91	3,297.30	3,297.16	7.30	5.76	-90.15	1.03	-91.27	63.81	50.80	13.01	4.904		
3,409.32	3,408.17	3,407.10	3,406.97	7.56	5.95	-93.71	0.89	-91.01	63.86	50.41	13.45	4.748		
3,441.15	3,439.98	3,438.73	3,438.60	7.62	6.01	-94.58	0.91	-90.87	63.82	50.25	13.57	4.704		
3,505.38	3,504.21	3,502.63	3,502.49	7.75	6.12	-140.39	0.74	-90.77	63.94	50.14	13.80	4.632		
3,605.38	3,604.21	3,603.03	3,602.89	7.94	6.29	-140.41	0.71	-90.76	63.96	49.79	14.17	4.512		
3,650.00	3,648.78	3,647.62	3,647.48	8.04	6.37	-51.82	0.85	-90.72	62.62	48.27	14.35	4.363		
3,700.00	3,698.31	3,697.15	3,697.02	8.17	6.46	-57.30	0.98	-90.60	58.56	44.00	14.56	4.023		
3,750.00	3,746.98	3,745.55	3,745.41	8.30	6.55	-68.02	0.99	-90.50	53.14	38.39	14.76	3.601		
3,800.00	3,794.34	3,792.67	3,792.54	8.46	6.63	-84.93	0.81	-90.51	49.40	34.45	14.96	3.303		
3,810.21	3,803.80	3,802.12	3,801.99	8.49	6.64	-89.04	0.75	-90.52	49.26	34.26	15.00	3.283	CC, ES, SF	
3,850.00	3,839.94	3,838.45	3,838.31	8.64	6.70	-105.83	0.57	-90.61	51.89	36.73	15.16	3.423		
3,900.00	3,883.37	3,882.18	3,882.05	8.86	6.78	-124.59	0.48	-90.78	63.87	48.51	15.36	4.159		
3,950.00	3,924.23	3,923.24	3,923.10	9.14	6.84	-137.82	0.52	-90.98	84.85	69.30	15.55	5.458		
4,000.00	3,962.15	3,961.17	3,961.03	9.48	6.91	-146.23	0.58	-91.12	112.76	97.04	15.72	7.172		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



TDS
Anticollision Report



Company: COG Operating LLC
Project: Eddy County, NM (NAD-27 2015)
Reference Site: Hobgoblin 7 Federal Com #44H
Site Error: 0.00 usft
Reference Well: SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Well Error: 0.00 usft
Reference Wellbore: BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2
Reference Design: Design #1

Local Co-ordinate Reference: Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
TVD Reference: KB @ 3687.00usft (Silver Oak 3)
MD Reference: KB @ 3687.00usft (Silver Oak 3)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.1 Single User Db
Offset TVD Reference: Offset Datum

Offset Design Eddy County Offset Wells - Hobgoblin 7 Federal Com UBB #4H - OH - OH													Offset Site Error:	0.00 usft
Survey Program: 100-VES-ISCWSA-GYRO-3, 4509-MWD													Offset Well Error:	0.00 usft
Reference	Offset		Semi Major Axis		Highside		Offset Wellbore Centre		Distance		Minimum Separation	Separation Factor	Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Tooface (")	+N/-S (usft)	+E/-W (usft)	Centres (usft)	Between Ellipses (usft)	(usft)			
4,050.00	3,996.77	3,995.71	3,995.57	9.91	6.96	-151.40	0.66	-91.19	145.93	130.04	15.89	9.186		
4,100.00	4,027.78	4,026.64	4,026.50	10.44	7.02	-154.41	0.72	-91.22	183.25	167.21	16.04	11.425		
4,150.00	4,054.88	4,053.67	4,053.53	11.07	7.06	-155.81	0.73	-91.24	223.96	207.78	16.18	13.845		
4,200.00	4,077.84	4,076.55	4,076.42	11.81	7.10	-155.76	0.71	-91.26	267.43	251.14	16.29	16.413		
4,250.00	4,096.43	4,095.09	4,094.95	12.65	7.13	-154.01	0.67	-91.27	313.15	296.75	16.39	19.105		
4,300.00	4,110.49	4,109.54	4,109.40	13.59	7.16	-149.66	0.63	-91.28	360.58	344.12	16.47	21.898		
4,350.00	4,119.90	4,119.49	4,119.35	14.60	7.17	-139.65	0.61	-91.30	409.25	392.73	16.52	24.774		
4,400.00	4,124.55	4,124.55	4,124.41	15.67	7.18	-113.98	0.59	-91.32	458.67	442.13	16.55	27.719		
4,432.65	4,125.00	4,125.14	4,125.01	16.39	7.18	-81.91	0.59	-91.32	491.14	474.58	16.55	29.669		
4,500.00	4,123.83	4,124.13	4,123.99	17.93	7.18	-80.76	0.59	-91.32	558.18	541.63	16.55	33.720		
4,600.00	4,122.08	4,122.59	4,122.45	20.31	7.18	-79.03	0.60	-91.31	657.84	641.28	16.55	39.743		
4,700.00	4,120.34	4,121.01	4,120.87	22.78	7.17	-77.28	0.60	-91.31	757.58	741.03	16.55	45.772		
4,800.00	4,118.59	4,119.39	4,119.25	25.31	7.17	-75.50	0.61	-91.30	857.38	840.83	16.55	51.803		
4,832.65	4,118.02	4,118.86	4,118.72	26.14	7.17	-74.92	0.61	-91.30	889.97	873.42	16.55	53.772		
4,870.20	4,117.37	4,118.23	4,118.09	27.10	7.17	-78.33	0.61	-91.30	927.44	910.89	16.55	56.037		
4,900.00	4,116.85	4,117.74	4,117.60	27.87	7.17	-77.92	0.61	-91.30	957.16	940.61	16.55	57.834		
5,000.00	4,115.10	5,939.43	5,081.35	30.47	29.03	-179.06	30.58	-1,181.15	968.48	954.07	14.42	67.183		
5,100.00	4,113.36	6,041.31	5,077.97	33.10	31.72	-179.17	30.45	-1,282.97	966.88	951.02	15.86	60.964		
5,200.00	4,111.62	6,122.81	5,075.54	35.74	33.89	-179.19	29.20	-1,364.43	965.68	948.41	17.26	55.934		
5,203.36	4,111.56	6,125.43	5,075.49	35.83	33.96	-179.19	29.16	-1,367.04	965.68	948.36	17.31	55.783		
5,300.00	4,109.88	6,199.71	5,075.04	38.40	35.94	-179.18	27.41	-1,441.30	966.78	948.12	18.66	51.806		
5,400.00	4,108.13	6,290.48	5,076.38	41.07	38.36	-179.07	23.70	-1,531.98	969.99	949.89	20.10	48.251		
5,500.00	4,106.39	6,394.56	5,077.58	43.76	41.15	-178.91	19.04	-1,635.96	972.92	951.33	21.59	45.064		
5,600.00	4,104.65	6,512.04	5,078.11	46.45	44.31	-178.75	13.96	-1,753.31	975.22	952.09	23.12	42.176		
5,700.00	4,102.91	6,612.73	5,077.22	49.15	47.04	-178.77	12.25	-1,853.99	976.07	951.48	24.59	39.701		
5,800.00	4,101.16	6,716.00	5,076.33	51.85	49.84	-178.90	12.39	-1,957.25	976.91	950.87	26.04	37.517		
5,900.00	4,099.42	6,819.26	5,075.05	54.56	52.65	-179.03	12.54	-2,060.50	977.37	949.88	27.49	35.549		
6,000.00	4,097.68	6,919.76	5,073.65	57.27	55.39	-179.13	12.36	-2,160.99	977.69	948.74	28.94	33.778		
6,100.00	4,095.94	7,021.02	5,072.01	59.99	58.14	-179.22	11.81	-2,262.24	977.79	947.39	30.40	32.164		
6,200.00	4,094.19	7,116.46	5,070.81	62.71	60.74	-179.26	10.68	-2,357.66	978.26	946.41	31.85	30.718		
6,300.00	4,092.45	7,216.96	5,069.53	65.44	63.49	-179.30	9.25	-2,458.14	978.72	945.41	33.31	29.384		
6,400.00	4,090.71	7,312.13	5,068.70	68.16	66.08	-179.30	7.52	-2,553.30	979.59	944.84	34.76	28.184		
6,500.00	4,088.96	7,413.41	5,067.97	70.89	68.84	-179.28	5.07	-2,654.54	980.62	944.39	36.23	27.067		
6,600.00	4,087.22	7,517.16	5,066.91	73.62	71.68	-179.27	2.88	-2,758.26	981.34	943.63	37.71	26.026		
6,700.00	4,085.48	7,620.93	5,065.45	76.36	74.51	-179.24	0.36	-2,861.99	981.69	942.50	39.19	25.051		
6,800.00	4,083.74	7,720.27	5,063.82	79.09	77.23	-179.24	-1.61	-2,961.30	981.78	941.13	40.65	24.151		
6,900.00	4,081.99	7,811.94	5,062.72	81.83	79.74	-179.26	-3.07	-3,052.95	982.33	940.24	42.09	23.339		
7,000.00	4,080.25	7,907.16	5,062.46	84.56	82.34	-179.35	-3.46	-3,148.17	983.78	940.25	43.53	22.602		
7,100.00	4,078.51	8,033.02	5,061.09	87.30	85.80	-179.49	-3.58	-3,274.02	984.51	939.47	45.05	21.856		
7,200.00	4,076.77	8,143.30	5,057.33	90.04	88.82	-179.68	-2.43	-3,384.23	982.81	936.30	46.51	21.131		
7,300.00	4,075.02	8,243.80	5,053.47	92.78	91.58	-179.84	-1.70	-3,484.64	980.70	932.73	47.96	20.447		
7,400.00	4,073.28	8,345.73	5,049.32	95.52	94.37	-179.98	-1.17	-3,586.49	978.37	928.94	49.42	19.796		
7,500.00	4,071.54	8,445.16	5,045.38	98.26	97.10	179.87	-0.68	-3,685.84	976.15	925.26	50.88	19.184		
7,600.00	4,069.80	8,548.54	5,040.88	101.01	99.93	179.75	-0.70	-3,789.13	973.53	921.18	52.35	18.596		
7,700.00	4,068.05	8,650.45	5,036.46	103.75	102.73	179.65	-0.88	-3,890.94	970.95	917.13	53.82	18.040		
7,800.00	4,066.31	8,748.77	5,031.75	106.49	105.42	179.54	-1.05	-3,989.15	967.92	912.63	55.29	17.506		
7,900.00	4,064.57	8,830.90	5,028.69	109.24	107.68	179.45	-1.23	-4,071.21	965.98	909.25	56.73	17.028		
7,931.78	4,064.01	8,854.67	5,028.17	110.11	108.33	179.43	-1.33	-4,094.98	965.85	908.67	57.18	16.892		
8,000.00	4,062.83	8,910.99	5,027.66	111.98	109.88	179.39	-1.69	-4,151.29	966.40	908.25	58.15	16.820		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



TDS
Anticollision Report



Company:	COG Operating LLC	Local Co-ordinate Reference:	Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Project:	Eddy County, NM (NAD-27 2015)	TVD Reference:	KB @ 3687.00usft (Silver-Oak 3)
Reference Site:	Hobgoblin 7 Federal Com #44H	MD Reference:	KB @ 3687.00usft (Silver Oak 3)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Eddy County Offset Wells - Hobgoblin 7 Federal Com UBB #4H - OH - OH													Offset Site Error:	0.00 usft
Survey Program: 100-VES-ISCWSA-GYRO-3, 4509-MWD													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
8,100.00	4,061.08	9,010.97	5,027.14	114.73	112.62	179.31	-2.39	-4,251.27	967.63	908.01	59.62	16.229		
8,200.00	4,059.34	9,110.99	5,026.61	117.47	115.37	179.24	-3.12	-4,351.28	968.87	907.77	61.10	15.857		
8,300.00	4,057.60	9,209.82	5,026.12	120.22	118.08	179.21	-4.44	-4,450.11	970.12	907.55	62.57	15.505		
8,400.00	4,055.86	9,307.80	5,025.88	122.97	120.77	179.23	-6.78	-4,548.06	971.62	907.59	64.02	15.176		
8,500.00	4,054.11	9,406.27	5,025.75	125.72	123.47	179.27	-9.41	-4,646.49	973.21	907.73	65.48	14.863		
8,600.00	4,052.37	9,504.51	5,025.87	128.46	126.16	179.36	-12.71	-4,744.67	975.06	908.13	66.93	14.569		
8,700.00	4,050.63	9,529.00	5,025.91	131.21	126.83	179.38	-13.65	-4,769.15	979.87	911.96	67.91	14.429		
8,793.41	4,049.00	9,529.00	5,025.91	133.78	126.83	179.38	-13.65	-4,769.15	993.19	925.02	68.17	14.569		



TDS
Anticollision Report



Company: COG Operating LLC

Local Co-ordinate Reference:

Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H

Project: Eddy County, NM (NAD-27 2015)

TVD Reference:

KB @ 3687.00usft (Silver Oak 3)

Reference Site: Hobgoblin 7 Federal Com #44H

MD Reference:

KB @ 3687.00usft (Silver Oak 3)

Site Error: 0.00 usft

North Reference:

Grid

Reference Well: SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H

Survey Calculation Method:

Minimum Curvature

Well Error: 0.00 usft

Output errors are at

2.00 sigma

Reference Wellbore: BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2

Database:

EDM 5000.1 Single User Db

Reference Design: Design #1

Offset TVD Reference:

Offset Datum

Offset Design														Offset Site Error:
Survey Program: 0-MWD														Offset Well Error:
Reference														
Offset				Semi Major Axis			Distance							
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Tooface (")	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
0.00	0.00	0.00	0.00	0.00	0.00	30.56	50.30	29.70	58.49					
100.00	100.00	97.00	97.00	0.09	0.09	30.56	50.30	29.70	58.41	58.23	0.18	321.762		
200.00	200.00	197.00	197.00	0.32	0.31	30.56	50.30	29.70	58.41	57.79	0.63	93.150		
300.00	300.00	297.00	297.00	0.54	0.53	30.56	50.30	29.70	58.41	57.34	1.08	54.256		
400.00	400.00	397.00	397.00	0.77	0.76	30.56	50.30	29.70	58.41	56.89	1.53	38.275		
500.00	500.00	497.00	497.00	0.99	0.98	30.56	50.30	29.70	58.41	56.44	1.98	29.566		
600.00	600.00	597.00	597.00	1.22	1.21	30.56	50.30	29.70	58.41	55.99	2.43	24.086		
700.00	700.00	697.00	697.00	1.44	1.43	30.56	50.30	29.70	58.41	55.54	2.87	20.320		
800.00	800.00	797.00	797.00	1.67	1.66	30.56	50.30	29.70	58.41	55.09	3.32	17.572		
900.00	900.00	897.00	897.00	1.89	1.88	30.56	50.30	29.70	58.41	54.64	3.77	15.479		
1,000.00	1,000.00	997.00	997.00	2.12	2.11	30.56	50.30	29.70	58.41	54.19	4.22	13.831		
1,100.00	1,100.00	1,097.00	1,097.00	2.34	2.33	30.56	50.30	29.70	58.41	53.74	4.67	12.501		
1,200.00	1,200.00	1,197.00	1,197.00	2.56	2.56	30.56	50.30	29.70	58.41	53.29	5.12	11.404		
1,300.00	1,300.00	1,297.00	1,297.00	2.79	2.78	30.56	50.30	29.70	58.41	52.84	5.57	10.484		
1,396.05	1,396.04	1,393.04	1,393.04	3.00	3.00	77.11	50.30	29.70	58.03	52.03	6.00	9.672		
1,400.00	1,399.98	1,396.98	1,396.98	3.01	3.01	77.23	50.30	29.70	58.00	51.99	6.02	9.639		
1,500.00	1,499.92	1,496.92	1,496.92	3.23	3.23	80.50	50.30	29.70	57.36	50.90	6.46	8.878		
1,600.00	1,599.87	1,596.87	1,596.87	3.45	3.46	83.83	50.30	29.70	56.90	49.99	6.91	8.240		
1,700.00	1,699.81	1,696.81	1,696.81	3.67	3.68	87.20	50.30	29.70	56.64	49.28	7.35	7.704		
1,782.54	1,782.31	1,779.31	1,779.31	3.86	3.87	90.00	50.30	29.70	56.57	48.85	7.72	7.327	CC	
1,800.00	1,799.76	1,796.76	1,796.76	3.89	3.91	90.59	50.30	29.70	56.57	48.77	7.80	7.254		
1,900.00	1,899.70	1,896.70	1,896.70	4.12	4.13	93.98	50.30	29.70	56.71	48.46	8.25	6.876		
2,000.00	1,999.64	1,996.64	1,996.64	4.34	4.36	97.34	50.30	29.70	57.04	48.34	8.69	6.560	ES	
2,100.00	2,099.59	2,096.59	2,096.59	4.57	4.58	100.65	50.30	29.70	57.56	48.42	9.14	6.295		
2,200.00	2,199.53	2,196.53	2,196.53	4.79	4.80	103.89	50.30	29.70	58.27	48.68	9.59	6.075		
2,300.00	2,299.47	2,296.47	2,296.47	5.02	5.03	107.04	50.30	29.70	59.17	49.13	10.04	5.892		
2,400.00	2,399.42	2,396.42	2,396.42	5.25	5.25	110.09	50.30	29.70	60.24	49.75	10.49	5.742		
2,500.00	2,499.36	2,496.36	2,496.36	5.48	5.48	113.02	50.30	29.70	61.47	50.53	10.94	5.619		
2,600.00	2,599.31	2,596.31	2,596.31	5.70	5.70	115.83	50.30	29.70	62.86	51.47	11.39	5.519		
2,700.00	2,699.25	2,696.25	2,696.25	5.93	5.93	118.52	50.30	29.70	64.39	52.55	11.84	5.439		
2,800.00	2,799.19	2,796.19	2,796.19	6.16	6.15	121.07	50.30	29.70	66.06	53.77	12.29	5.376		
2,900.00	2,899.14	2,896.14	2,896.14	6.39	6.38	123.50	50.30	29.70	67.85	55.11	12.74	5.327		
3,000.00	2,999.08	2,996.08	2,996.08	6.62	6.60	125.79	50.30	29.70	69.75	56.57	13.18	5.291		
3,100.00	3,099.02	3,096.02	3,096.02	6.85	6.83	127.96	50.30	29.70	71.77	58.13	13.63	5.264		
3,200.00	3,198.97	3,195.97	3,195.97	7.08	7.05	130.01	50.30	29.70	73.88	59.80	14.08	5.246		
3,300.00	3,298.91	3,295.91	3,295.91	7.30	7.28	131.95	50.30	29.70	76.08	61.55	14.53	5.236		
3,409.32	3,408.17	3,405.17	3,405.17	7.56	7.52	133.93	50.30	29.70	78.57	63.55	15.02	5.231		
3,505.38	3,504.21	3,501.21	3,501.21	7.75	7.74	89.78	50.30	29.70	79.70	64.27	15.43	5.166		
3,605.38	3,604.21	3,601.21	3,601.21	7.94	7.96	89.78	50.30	29.70	79.70	63.85	15.85	5.029	SF	
3,650.00	3,648.78	3,645.78	3,645.78	8.04	8.06	179.79	50.30	29.70	81.61	65.56	16.05	5.086		
3,700.00	3,698.31	3,695.31	3,695.31	8.17	8.17	179.80	50.30	29.70	88.27	72.00	16.27	5.425		
3,750.00	3,746.98	3,743.98	3,743.98	8.30	8.28	179.82	50.30	29.70	99.65	83.15	16.50	6.040		
3,800.00	3,794.34	3,791.34	3,791.34	8.46	8.39	179.84	50.30	29.70	115.64	98.92	16.72	6.915		
3,850.00	3,839.94	3,836.94	3,836.94	8.64	8.49	179.86	50.30	29.70	136.09	119.15	16.95	8.030		
3,900.00	3,883.37	3,880.37	3,880.37	8.86	8.59	179.87	50.30	29.70	160.83	143.66	17.17	9.369		
3,950.00	3,924.23	3,921.23	3,921.23	9.14	8.68	179.89	50.30	29.70	189.61	172.23	17.38	10.912		
4,000.00	3,962.15	3,959.15	3,959.15	9.48	8.77	179.89	50.30	29.70	222.17	204.60	17.58	12.641		
4,050.00	3,996.77	3,993.77	3,993.77	9.91	8.84	179.90	50.30	29.70	258.22	240.46	17.76	14.538		
4,100.00	4,027.78	4,024.78	4,024.78	10.44	8.91	179.90	50.30	29.70	297.42	279.49	17.93	16.587		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



TDS
Anticollision Report



Company: COG Operating LLC
Project: Eddy County, NM (NAD-27 2015)
Reference Site: Hobgoblin 7 Federal Com #44H
Site Error: 0.00 usft
Reference Well: SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Well Error: 0.00 usft
Reference Wellbore: BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2
Reference Design: Design #1

Local Co-ordinate Reference: Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
TVD Reference: KB @ 3687.00usft (Silver Oak 3)
MD Reference: KB @ 3687.00usft (Silver Oak 3)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.1 Single User Db
Offset TVD Reference: Offset Datum

Offset Design													Offset Site Error:	0.00 usft		
Survey Program: 0-MWD													Offset Well Error:	0.00 usft		
Reference													Distance		Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor				
4,150.00	4,054.88	4,051.88	4,051.88	11.07	8.97	179.90	50.30	29.70	339.42	321.33	18.08	18.771				
4,200.00	4,077.84	4,131.99	4,131.70	11.81	9.14	179.94	50.21	23.90	382.27	364.05	18.22	20.979				
4,250.00	4,096.43	4,266.77	4,260.92	12.65	9.45	-179.92	49.62	-13.07	422.09	404.59	17.50	24.121				
4,300.00	4,110.49	4,520.15	4,460.45	13.59	10.74	-179.61	47.20	-165.15	452.61	439.33	13.28	34.079				
4,350.00	4,119.90	4,886.71	4,574.91	14.60	16.57	-178.96	41.80	-505.42	458.16	452.22	5.94	77.188				
4,400.00	4,124.55	4,936.38	4,574.04	15.67	17.67	-178.86	41.01	-555.08	452.65	446.04	6.61	68.431				
4,432.48	4,125.00	4,968.83	4,573.48	16.39	18.39	-178.79	40.49	-587.52	451.64	444.57	7.07	63.875				
4,432.65	4,125.00	4,969.00	4,573.47	16.39	18.40	-178.79	40.49	-587.69	451.64	444.57	7.07	63.853				
4,500.00	4,123.83	5,036.35	4,572.30	17.93	19.95	-178.66	39.42	-655.01	451.66	443.63	8.04	56.200				
4,600.00	4,122.08	5,136.33	4,570.55	20.31	22.33	-178.46	37.83	-754.97	451.70	442.22	9.49	47.619				
4,700.00	4,120.34	5,236.32	4,568.81	22.78	24.80	-178.26	36.24	-854.93	451.75	440.80	10.95	41.252				
4,800.00	4,118.59	5,336.31	4,567.06	25.31	27.32	-178.05	34.66	-954.89	451.80	439.37	12.43	36.349				
4,832.65	4,118.02	5,368.95	4,566.49	26.14	28.15	-177.99	34.14	-987.53	451.82	438.90	12.91	34.985				
4,870.20	4,117.37	5,406.50	4,565.84	27.10	29.11	-177.98	33.54	-1,025.07	451.82	438.36	13.47	33.551				
4,900.00	4,116.85	5,436.30	4,565.32	27.87	29.88	-177.99	33.07	-1,054.86	451.82	437.92	13.90	32.505				
5,000.00	4,115.10	5,536.30	4,563.57	30.47	32.47	-178.04	31.48	-1,154.83	451.80	436.45	15.35	29.425				
5,100.00	4,113.36	5,636.30	4,561.83	33.10	35.09	-178.09	29.89	-1,254.80	451.79	434.98	16.81	26.874				
5,200.00	4,111.62	5,736.30	4,560.08	35.74	37.73	-178.14	28.30	-1,354.77	451.77	433.50	18.27	24.728				
5,300.00	4,109.88	5,836.30	4,558.34	38.40	40.38	-178.18	26.72	-1,454.75	451.76	432.03	19.73	22.898				
5,400.00	4,108.13	5,936.30	4,556.59	41.07	43.05	-178.23	25.13	-1,554.72	451.74	430.55	21.19	21.320				
5,500.00	4,106.39	6,036.30	4,554.85	43.76	45.72	-178.28	23.54	-1,654.69	451.73	429.08	22.65	19.945				
5,600.00	4,104.65	6,136.30	4,553.10	46.45	48.41	-178.33	21.95	-1,754.66	451.72	427.61	24.11	18.736				
5,700.00	4,102.91	6,236.30	4,551.36	49.15	51.10	-178.38	20.36	-1,854.63	451.70	426.13	25.57	17.666				
5,800.00	4,101.16	6,336.30	4,549.61	51.85	53.80	-178.42	18.77	-1,954.60	451.69	424.66	27.03	16.711				
5,900.00	4,099.42	6,436.30	4,547.87	54.56	56.51	-178.47	17.18	-2,054.57	451.68	423.19	28.49	15.854				
6,000.00	4,097.68	6,536.29	4,546.12	57.27	59.22	-178.52	15.60	-2,154.55	451.66	421.71	29.95	15.081				
6,100.00	4,095.94	6,636.29	4,544.38	59.99	61.93	-178.57	14.01	-2,254.52	451.65	420.24	31.41	14.379				
6,200.00	4,094.19	6,736.29	4,542.63	62.71	64.65	-178.62	12.42	-2,354.49	451.64	418.77	32.87	13.740				
6,300.00	4,092.45	6,836.29	4,540.89	65.44	67.37	-178.66	10.83	-2,454.46	451.63	417.30	34.33	13.156				
6,400.00	4,090.71	6,936.29	4,539.14	68.16	70.09	-178.71	9.24	-2,554.43	451.62	415.83	35.79	12.619				
6,500.00	4,088.96	7,036.29	4,537.39	70.89	72.81	-178.76	7.65	-2,654.40	451.61	414.36	37.25	12.124				
6,600.00	4,087.22	7,136.29	4,535.65	73.62	75.54	-178.81	6.07	-2,754.37	451.59	412.89	38.71	11.667				
6,700.00	4,085.48	7,236.29	4,533.90	76.36	78.27	-178.85	4.48	-2,854.35	451.58	411.42	40.16	11.243				
6,800.00	4,083.74	7,336.29	4,532.16	79.09	81.00	-178.90	2.89	-2,954.32	451.57	409.95	41.62	10.849				
6,900.00	4,081.99	7,436.29	4,530.41	81.83	83.74	-178.95	1.30	-3,054.29	451.56	408.48	43.08	10.482				
7,000.00	4,080.25	7,536.29	4,528.67	84.56	86.47	-179.00	-0.29	-3,154.26	451.55	407.01	44.54	10.138				
7,100.00	4,078.51	7,636.29	4,526.92	87.30	89.20	-179.05	-1.88	-3,254.23	451.55	405.55	46.00	9.817				
7,200.00	4,076.77	7,736.29	4,525.18	90.04	91.94	-179.09	-3.46	-3,354.20	451.54	404.08	47.46	9.515				
7,300.00	4,075.02	7,836.29	4,523.43	92.78	94.68	-179.14	-5.05	-3,454.17	451.53	402.61	48.92	9.231				
7,400.00	4,073.28	7,936.28	4,521.69	95.52	97.42	-179.19	-6.64	-3,554.15	451.52	401.15	50.37	8.963				
7,500.00	4,071.54	8,036.28	4,519.94	98.26	100.16	-179.24	-8.23	-3,654.12	451.51	399.68	51.83	8.711				
7,600.00	4,069.80	8,136.28	4,518.20	101.01	102.90	-179.29	-9.82	-3,754.09	451.50	398.21	53.29	8.473				
7,700.00	4,068.05	8,236.28	4,516.45	103.75	105.64	-179.33	-11.41	-3,854.06	451.50	396.75	54.75	8.247				
7,800.00	4,066.31	8,336.28	4,514.71	106.49	108.38	-179.38	-12.99	-3,954.03	451.49	395.28	56.21	8.033				
7,900.00	4,064.57	8,436.28	4,512.96	109.24	111.12	-179.43	-14.58	-4,054.00	451.48	393.82	57.67	7.829				
8,000.00	4,062.83	8,536.28	4,511.22	111.98	113.87	-179.48	-16.17	-4,153.97	451.48	392.35	59.13	7.636				
8,100.00	4,061.08	8,636.28	4,509.47	114.73	116.61	-179.53	-17.76	-4,253.95	451.47	390.89	60.58	7.452				
8,200.00	4,059.34	8,736.28	4,507.73	117.47	119.35	-179.57	-19.35	-4,353.92	451.47	389.42	62.04	7.277				
8,300.00	4,057.60	8,836.28	4,505.98	120.22	122.10	-179.62	-20.94	-4,453.89	451.46	387.96	63.50	7.109				

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



TDS
Anticollision Report



Company:	COG Operating LLC	Local Co-ordinate Reference:	Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Project:	Eddy County, NM (NAD-27 2015)	TVD Reference:	KB @ 3687.00usft (Silver Oak 3)
Reference Site:	Hobgoblin 7 Federal Com #44H	MD Reference:	KB @ 3687.00usft (Silver Oak 3)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Offset Design Hobgoblin 7 Federal Com #14H - SHL: 2260' FNL, 10' FEL, Sec 7, T17S, R30E, Unit H - BHL: 2307' FN													Offset Site Error:	0.00 usft
Survey Program: 0-MWD													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
8,400.00	4,055.86	8,936.28	4,504.23	122.97	124.84	-179.67	-22.52	-4,553.86	451.46	386.49	64.96	6.949		
8,500.00	4,054.11	9,036.28	4,502.49	125.72	127.59	-179.72	-24.11	-4,653.83	451.45	385.03	66.43	6.796		
8,600.00	4,052.37	9,136.28	4,500.74	128.46	130.33	-179.77	-25.70	-4,753.80	451.45	383.56	67.89	6.650		
8,675.42	4,051.06	9,211.70	4,499.43	130.54	132.41	-179.80	-26.90	-4,829.20	451.44	382.45	68.99	6.544		
8,700.00	4,050.63	9,211.79	4,499.43	131.21	132.41	-179.80	-26.90	-4,829.30	452.11	382.79	69.32	6.522		
8,793.41	4,049.00	9,211.79	4,499.43	133.78	132.41	-179.80	-26.90	-4,829.30	466.58	397.67	68.91	6.771		




TDS
Anticollision Report



Company:	COG Operating LLC	Local Co-ordinate Reference:	Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Project:	Eddy County, NM (NAD-27 2015)	TVD Reference:	KB @ 3687.00usft (Silver Oak 3)
Reference Site:	Hobgoblin 7 Federal Com #44H	MD Reference:	KB @ 3687.00usft (Silver Oak 3)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to KB @ 3687.00usft (Silver Oak 3)	Coordinates are relative to: SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Offset Depths are relative to Offset Datum	Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30
Central Meridian is 104° 20' 0.000 W	Grid Convergence at Surface is: 0.18°






TDS
Anticollision Report



Company:	COG Operating LLC	Local Co-ordinate Reference:	Well SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Project:	Eddy County, NM (NAD-27 2015)	TVD Reference:	KB @ 3687.00usft (Silver Oak 3)
Reference Site:	Hobgoblin 7 Federal Com #44H	MD Reference:	KB @ 3687.00usft (Silver Oak 3)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	SHL: 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	BHL: 2307' FNL, 220' FWL, Sec 7, T17S, R30E, Lot 2	Database:	EDM 5000.1 Single User Db
Reference Design:	Design #1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to KB @ 3687.00usft (Silver Oak 3)
Offset Depths are relative to Offset Datum
Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: SHL, 2310' FNL, 40' FEL, Sec 7, T17S, R30E, Unit H
Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30
Grid Convergence at Surface is: 0.18°



LEGEND

BrantleyFederal#1, OH, OHV0


SHL:2260' F

COG Operating LLC

Exhibit #9

Choke Schematic

Choke Manifold Requirement (2000 psi WP)




NOTES REGARDING THE BLOWOUT PREVENTERS

Master Drilling Plan Eddy County, New Mexico

1. Drilling nipple to be so constructed that it can be removed without use of a welder through rotary table opening, with minimum I.D. equal to preventer bore.
2. Wear ring to be properly installed in head.
3. Blow out preventer and all fittings must be in good condition, 2000 psi WP minimum.
4. All fittings to be flanged.
5. Safety valve must be available on rig floor at all times with proper connections, valve to be full 2000 psi WP minimum.
6. All choke and fill lines to be securely anchored especially ends of choke lines.
7. Equipment through which bit must pass shall be at least as large as the diameter of the casing being drilled through.
8. Kelly cock on Kelly.
9. Extension wrenches and hands wheels to be properly installed.
10. Blow out preventer control to be located as close to driller's position as feasible.
11. Blow out preventer closing equipment to include minimum 40-gallon accumulator, two independent sources of pump power on each closing unit installation all API specifications.

Exhibit #10

13 5/8" 2K ANNULAR



COG Operating LLC

Hydrogen Sulfide Drilling Operation Plan

I. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H₂S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H₂S on metal components. If high tensile tubular are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H₂S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan. **The concentrations of H₂S of wells in this area from surface to TD are low enough that a contingency plan is not required.**

II. H2S SAFETY EQUIPMENT AND SYSTEMS

Note: All H2S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonable expected to contain H2S.

1. Well Control Equipment:

- A. Flare line.
- B. Choke manifold with minimum of one remotely operated choke.
- C. Closed Loop Blow Down Tank
- D. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
- E. Auxiliary equipment may include if applicable: mud-gas separator, annular preventer & rotating head.

2. Protective equipment for essential personnel:

- A. SCBA (Self contained breathing apparatus) 30-minute units located in the doghouse and at briefing areas, as indicated on well site diagram.

3. H2S detection and monitoring equipment:

- A. Portable H2S monitors positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 PPM are reached.

4. Visual warning systems:

- A. Wind direction indicators as shown on well site diagram.
- B. Caution/Danger signs (Exhibit #7) shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.

5. Mud program:

- A. The mud program has been designed to minimize the volume of H2S circulated to surface. Proper mud weight, safe drilling practices, and the use of H2S scavengers will minimize hazards when penetrating H2S bearing zones.
-

6. Metallurgy:

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- B. All elastomers used for packing and seals shall be H2S trim.

7. Communication:

- A. Radio communications in company vehicles including cellular telephone and 2-way radio.
- B. Land line (telephone) communication at Office.

8. Well testing:

- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safely and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H2S environment will use the closed chamber method of testing.
- B. There will be no drill stem testing.

EXHIBIT #7

WARNING

YOU ARE ENTERING AN H2S

AUTHORIZED PERSONNEL ONLY

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED
- 2. HARD HATS REQUIRED
- 3. SMOKING IN DESIGNATED AREAS ONLY
- 4. BE WIND CONSCIOUS AT ALL TIMES
- 5. CHECK WITH COG OPERATING FOREMAN AT

COG OPERATING LLC

1-432-683-7443

1-575-746-2010

EDDY COUNTY EMERGENCY NUMBERS


ARTESIA FIRE DEPT. 575-746-5050
ARTESIA POLICE DEPT. 575-746-5000
EDDY CO. SHERIFF DEPT. 575-746-9888

LEA COUNTY EMERGENCY NUMBERS

HOBBS FIRE DEPT. 575-397-9308
HOBBS POLICE DEPT. 575-397-9285
LEA CO. SHERIFF DEPT. 575-396-1196

COG Operating LLC

**Hobgoblin 7 Federal Com #44H - H2S Safety
Equipment Diagram**



Closed Loop Operation & Maintenance Procedure

All drilling fluid circulated over shaker(s) with cuttings discharged into roll off container.

Fluid and fines below shaker(s) are circulated with transfer pump through centrifuge(s) or solids separator with cuttings and fines discharged into roll off container.

Fluid is continuously re-circulated through equipment with polymer added to aid separation of cutting fines.

Roll off containers are lined and de-watered with fluids re-circulated into system.

Additional tank is used to capture unused drilling fluid or cement returns from casing jobs.

This equipment will be maintained 24 hrs./day by solids control personnel and or rig crews that stay on location.

Cuttings will be hauled to either:

CRI (permit number R9166)


or

GMI (permit number 711-019-001)

dependent upon which rig is available to drill this well.

COG Operating LLC

Closed Loop Equipment Diagram



**PECOS DISTRICT
DRILLING OPERATIONS
CONDITIONS OF APPROVAL**

**NM OIL CONSERVATION
ARTESIA DISTRICT**

JUL 24 2017

RECEIVED

OPERATOR'S NAME:	COG Operating, LLC
LEASE NO.:	NMNM117122
WELL NAME & NO.:	44H-Hobgoblin 7 Federal Com
SURFACE HOLE FOOTAGE:	2310'N & 40'E
BOTTOM HOLE FOOTAGE:	2307'N & 220'W
LOCATION:	Section 7, T.17 S., R.30 E., NMPM
COUNTY:	Eddy County, New Mexico

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. A Hydrogen Sulfide (H₂S) Drilling Plan shall be activated 500 feet prior to drilling into the **Grayburg** formation. **As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If**

available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Water Basin:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. **DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE.**

Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Risks:

Possibility of water flows in the Salado and in the Artesia Group.
Possibility of lost circulation in the San Andres and Grayburg.

1. The 13 3/8 inch surface casing shall be set at approximately 410 feet (**in the Rustler, and if salt is encountered, set casing at least 25 feet above the salt**) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run

to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

- b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9 5/8** inch intermediate casing which is:

Option 1:

- Cement to surface. If cement does not circulate see B.1.a, c-d above.

Option 2:

Operator has proposed DV tool and will adjust cement proportionately if moved. DV tool shall be set a minimum of 50 feet below previous shoe and a minimum of 200 feet above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range. If an ECP is used, it is to be set a minimum of 50' below the shoe to provide cement across the shoe. If it cannot be set below the shoe, a CBL shall be run to verify cement coverage.

- a. First stage to DV tool:
 - Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.
 - b. Second stage above DV tool:
 - Cement to surface. If cement does not circulate see B.1.a, c-d above.
3. The minimum required fill of cement behind the **7 X 5 1/2** inch production casing is:
- Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification.

4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
2. **In the case where the only BOP installed is an annular preventer, it shall be tested to a minimum of 2000 psi (which may require upgrading to 3M or 5M annular).**
3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M) psi (annular)**.
4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
 - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall

have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.

- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

F. SPECIAL REQUIREMENT(S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.

- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

Waste Minimization Plan (WMP)

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

MHH 06052017

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit Original
to Appropriate
District Office
NM OIL CONSERVATION
ARTESIA DISTRICT
JUL 24 2017

GAS CAPTURE PLAN

RECEIVED

Original

Date: 06/06/2017

Amended

Reason for Amendment: _____

This Gas Capture Plan outlines actions to be taken by the Operator to reduce well/production facility flaring/venting for new completion (new drill, recomplete to new zone, re-frac) activity.

Note: A C-129 must be submitted and approved prior to exceeding 60 days allowed by Rule 19.15.18.12.A

Well(s)/Production Facility – Name of facility

The well(s) that will be located at the production facility are shown in the table below.

Well Name	API	Well Location (ULSTR)	Footages	Expected MCF/D	Flared or Vented	Comments
Hobgoblin 7 Federal Com #44H	30-015-	UL H, Sec 07, T17S, R30E	2310 FNL 40 FEL	408	0	

Gathering System and Pipeline Notification

Well(s) will be connected to a production facility after flowback operations are complete, if gas transporter system is in place. The gas produced from production facility is dedicated to **DCP Midstream** and will be connected to **DCP's** low/high pressure gathering system located in **Eddy County**, New Mexico. **NO additional** pipeline to connect the facility to low/high pressure gathering system **because it will go to an existing meter**. **COG Operating LLC** provides (periodically) to **DCP** a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, **COG Operating LLC** and **DCP** have periodic conference calls to discuss changes to drilling and completion schedules. Gas from these wells will be processed at **DCP'S Linam** Processing Plant located in **Sec. 6, T19S, R37E, Lea County**, New Mexico. The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

Flowback Strategy

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on **DCP's** system at that time. Based on current information, it is COG Operating LLC belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

Alternatives to Reduce Flaring

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

- Power Generation – On lease
 - Only a portion of gas is consumed operating the generator, remainder of gas will be flared
- Compressed Natural Gas – On lease
 - Gas flared would be minimal, but might be uneconomical to operate when gas volume declines
- NGL Removal – On lease
 - Plants are expensive, residue gas is still flared, and uneconomical to operate when gas volume declines

JUL 24 2017

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

RECEIVED

OPERATOR'S NAME:	COG Operating, LLC
LEASE NO.:	NMNM117122
WELL NAME & NO.:	44H-Hobgoblin 7 Federal Com
SURFACE HOLE FOOTAGE:	2310'/N & 40'/E
BOTTOM HOLE FOOTAGE:	2307'/N & 220'/W
LOCATION:	Section 7, T.17 S., R.30 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
 - Lesser Prairie-Chicken Timing Stipulations
 - Below Ground-level Abandoned Well Marker
- Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- Road Section Diagram**
- Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
- Interim Reclamation**
- Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the Grant and attachments, including stipulations, survey plat(s) and/or map(s), shall be on location during construction. BLM personnel may request to review a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, Holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC § 2601 *et seq.* (1982) with regard to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant (*see* 40 CFR, Part 702-799 and in particular, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193). Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. Holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. § 9601, *et seq.* or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, *et seq.*) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way Holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way Holder on the Right-of-Way. This provision applies without regard to whether a release is caused by Holder, its agent, or unrelated third

parties.

4. Holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. Holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of Holder including, but not limited to: construction, operation, maintenance, and termination of the facility;
- b. Activities of other parties including, but not limited to:
 - (1) Land clearing
 - (2) Earth-disturbing and earth-moving work
 - (3) Blasting
 - (4) Vandalism and sabotage;

c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of Holder, regardless of fault. Upon failure of Holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he/she deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of Holder. Such action by the Authorized Officer shall not relieve Holder of any responsibility as provided herein.

6. All construction and maintenance activity shall be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline shall be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline shall be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity shall be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation shall be allowed unless approved in writing by the Authorized Officer.
8. Holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline shall be "snaked" around hummocks and dunes rather than suspended across these features.
9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.
10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.
12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.
13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.
14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.
15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed

is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines shall be less than or equal to 4 inches and a working pressure below 125 psi.

18. Special Stipulations:

- a. **Lesser Prairie-Chicken:** Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted.
- b. This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed