	N	IM OIL C	ONSERVATIO	N			
Form 3160 -3 (March 2012)	UNITED STATE DEPARTMENT OF THE BUREAU OF LAND MAI	artes S INTERIOR NAGEME NT		, initial of the second se	FORM OMB No Expires Oc 5. Lease Serial No. NMNM100558	APPROVED . 1004-0137 :tober 31, 2014	-
	APPLICATION FOR PERMIT TO	DRILL OF	REENTER		6. If Indian, Allotee	ur Tribe Name	
la. Type of work		°ER			7. If Unit or CA Agree	ment, Name and No.	_
lb. Type of Well:	Oil Well Gas Well 🖊 Other OT	н 🔽 Sin	ngle Zone 🔲 Multip	ole Zone	8. Lease Name and W TUCKER DRAW 9-4	/ell No. 4 FED COM 1H	319751
2. Name of Oper	ator RKI EXPLORATION & PRODUCTION		246289		9. API Well No. 30 - 013	5-44477	-
3a. Address 350	00 One Williams Center, MD 35 Tulsa OK 7	3b. Phone No (539)573-0	. (include area code) 212		10. Field and Pool, or E PURPLE-SAGE WC	xploratory DLFCAMP GAS / PL	-
 Location of W At surface N 	ell (Report location clearly and in accordance with a WNE / 250 FNL / 1463 FEL / LAT 32.0492	iny State requirem	ents.*) 03.882394	11. Sec., T. R. M. or Blk. and Survey or Area SEC 16 / T26S / R30E / NMP		-	
At proposed p	rod. zone NWSE / 2410 FSL / 2310 FEL / L	AT 32.07113	I / LONG -103.885	161	12 County or Parish	12 State	
 14. Distance in mil 16,4 miles 	es and direction from nearest town or post office*				EDDY	NM	_
15. Distance from location to near property or lear (Also to neares	proposed* rest 230 feet se line, ft. t drig. unit line, if any)	16. No. of a 960	cres in lease	17. Spacii 480	ng Unit dedicated to this w	ell	
18. Distance from p to nearest well, applied for, on	proposed location* drilling, completed, 25 feet this lease, ft.	19. Proposed 11116 fee	1 Depth t / 18781 feet	20. BLM FED: N	BIA Bond No. on file MB000396		_
21. Elevations (Sh 3089 feet	now whether DF, KDB, RT, GL, etc.)	22 Approxit 09/23/201	nate date work will sta 7	rt*	23. Estimated duration 30 days	· · · · · · · · · · · · · · · · · · ·	_
		24. Attac	chments				
 Well plat certifia A Drilling Plan. A Surface Use SUPO must be 	pleted in accordance with the requirements of Onsh ed by a registered surveyor. Plan (if the location is on National Forest Syster filed with the appropriate Forest Service Office).	ore Oil and Gas n Lands, the	 Order No.1, must be a Bond to cover t Item 20 above). Operator certific Such other site BLM. 	ttached to the he operation cation specific inf	ns form: ons unless covered by an o formation and/or plans as	existing bond on file (se may be required by the	e
25. Signature (E	lectronic Submission)	Name Justir	(Printed/Typed) Barmore / Ph: (53	9)573-26	51	Date 05/30/2017	=
Title	Specialist						
Approved by (Signa (Ele	uure) ectronic Submission)	Name Christ	(Printed/Typed) copher Walls / Ph: (575)234-	2234	Date 10/05/2017	_
Title Petroleum Engi	le Office etroleum Engineer CARL						_
Application approv conduct operations Conditions of approx	al does not warrant or certify that the applicant ho thereon. oval, if any, are attached.	lds legal or equi	table title to those righ	its in the su	bject lease which would en	ntitle the applicant to	_
Title 18 U.S.C. Sect States any false, fict	ion 1001 and Title 43 U.S.C. Section 1212, make it a itious or fraudulent statements or representations a	crime for any p s to any matter v	erson knowingly and within its jurisdiction.	willfully to	make to any department of	r agency of the United	
(Continued or	n page 2)		u conditi	ONS	*(lnstr	uctions on page 2)
	, nnDA	VED WI'	HUU		,		

APPROVED

NSP Required Rul. 10-19-17

PECOS DISTRICT DRILLING OPERATIONS CONDITIONS OF APPROVAL

OPERATOR'S NAME:	RKI Exploration and ProductionLLC
LEASE NO.:	NMNM-100558
WELL NAME & NO.:	Tucker Draw 9-4 Fed Com 1H
SURFACE HOLE FOOTAGE:	0250' FNL & 1463' FEL
BOTTOM HOLE FOOTAGE	2410' FSL & 2310' FEL
LOCATION:	Section 16, T. 26 S., R 30 E., NMPM
COUNTY:	County, New Mexico

Communitization Agreement

The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.

• If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.

• In addition, the well sign shall include the surface and bottom hole lease numbers. <u>When the Communitization Agreement number is known, it shall also be</u> <u>on the sign.</u>

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

A. Hydrogen Sulfide

- 1. Although there are no measured amounts of Hydrogen Sulfide reported, it is always a potential hazard. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.
- Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. If the drilling rig is removed without approval an Incident of Non-Compliance will be written and will be a "Major" violation.
- 3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
- 4. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Water Basin:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least <u>8 hours</u>. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.

Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Medium Cave/Karst

, ,

Possibility of water flows in the Salado and Delaware. Possibility of lost circulation in the Rustler, Red Beds, and Delaware.

- 1. The 13-3/8 inch surface casing shall be set at approximately 900 feet (in a competent bed <u>below the Magenta Dolomite</u>, which is a <u>Member of the Rustler</u>, and if salt is encountered, set casing at least 25 feet above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Formation below the 13-3/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe and the mud weight for the bottom of the hole. Report results to BLM office.

- 2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
 - ☐ Cement to surface. If cement does not circulate see B.1.a, c-d above. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst. Excess calculates to 13% - Additional cement may be required.

Formation below the 9-5/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole. Report results to BLM office.

Centralizers required through the curve and a minimum of one every other joint.

- 3. The minimum required fill of cement behind the 7 inch production casing is:
 - □ Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification. Excess calculates to 22% Additional cement may be required.

Formation below the 7" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe and the mud weight for the bottom of the hole. Report results to BLM office.

- 4. The minimum required fill of cement behind the 4-1/2 inch production Liner is:
 - Cement as proposed by operator. Operator shall provide method of verification. Excess calculates to 18% Additional cement may be required.
- 5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.

2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor. If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).

.

.

- 3. Operator has proposed a multi-bowl wellhead assembly that has a weld on head with no o-ring seals. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be psi.
 - a. Wellhead manufacturer is supplying the test plug/retrieval tool for the operator's third party tester to use during the BOP/BOPE test. Operator shall use the supplied test plug/retrieval tool.
 - b. Operator shall install the wear bushing required by the wellhead manufacturer. This wear bushing shall be installed by using the test plug/retrieval tool.
 - c. Wellhead manufacturer representative shall be on location when the intermediate casing mandrel is landed. Operator shall submit copy of manufacturer's wellsite report with subsequent report.
 - d. Operator shall perform the intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.

5M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.

- 4. The appropriate BLM office shall be notified a minimum of hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - a. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**.
 - b. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - c. The results of the test shall be reported to the appropriate BLM office.
 - d. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
 - e. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
 - f. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the **Wolfcamp** formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

D. DRILLING MUD

.

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the **Wolfcamp** formation, and shall be used until production casing is run and cemented.

E. DRILL STEM TEST

. .

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

F. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 091217

PECOS DISTRICT SURFACE USE CONDITIONS OF APPROVAL

OPERATOR'S NAME:	RKI Exploration & Production LLC
LEASE NO.:	NM100558
WELL NAME & NO.:	Tucker Draw 9-4 Fed Com – 1H
SURFACE HOLE FOOTAGE:	250'/N & 1463'/E
BOTTOM HOLE FOOTAGE	2410'/S & 2310'/E, sec. 4
LOCATION:	Section 16, T. 26 S., R. 30 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

General Provisions
Dormit Expiration

J	re	rmi	τĿΧĮ	Diration	
٦		_	_		

- Archaeology, Paleontology, and Historical Sites
- **Noxious Weeds**
- Special Requirements

Phantom Banks/Desert Heronry

Cave/Karst

Watersheds/Floodplain

Construction

Notification

Topsoil

Closed Loop System

Federal Mineral Material Pits

Well Pads

Roads

Road Section Diagram

Production (Post Drilling)

Well Structures & Facilities Pipelines

Electric Lines

Interim Reclamation

Final Abandonment & Reclamation

I. GENERAL PROVISIONS

.

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Phantom Banks/Desert Heronries ACEC

Surface disturbance will not be allowed within up to 200 meters of active heronries or by delaying activity for up to 120 days, or a combination of both.

Exhaust noise from engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

Cave and Karst Conditions of Approval for APDs

** Depending on location, additional Drilling, Casing, and Cementing procedures may be required by engineering to protect critical karst groundwater recharge areas.

Cave/Karst Surface Mitigation

The following stipulations will be applied to minimize impacts during construction, drilling and production.

Construction:

.

In the advent that any underground voids are opened up during construction activities, construction activities will be halted and the BLM will be notified immediately.

No Blasting:

No blasting will be utilized for pad construction. The pad will be constructed and leveled by adding the necessary fill and caliche.

Pad Berming:

The entire perimeter of the well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.

- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g. caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised. (Any access road crossing the berm cannot be lower than the berm height.)

:

Tank Battery Liners and Berms:

Tank battery locations and all facilities will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing, or equivalent, to prevent tears or punctures. Tank battery berms must be large enough to contain $1\frac{1}{2}$ times the content of the largest tank.

Leak Detection System:

A method of detecting leaks is required. The method could incorporate gauges to measure loss, situating values and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present. Leak detection plan will be submitted to BLM for approval.

Automatic Shut-off Systems:

Automatic shut off, check values, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

Cave/Karst Subsurface Mitigation

The following stipulations will be applied to protect cave/karst and ground water concerns:

Rotary Drilling with Fresh Water:

Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

Directional Drilling:

Kick off for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

Lost Circulation:

ALL lost circulation zones from the surface to the base of the cave occurrence zone will be logged and reported in the drilling report.

Regardless of the type of drilling machinery used, if a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cavebearing zone, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

Abandonment Cementing:

Upon well abandonment in high cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

Pressure Testing:

Annual pressure monitoring will be performed by the operator on all casing annuli and reported in a sundry notice. If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

Watersheds/Floodplain:

•

•

The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The berm shall be maintained through the life of the well and after interim reclamation has been completed.

Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion.

Surface disturbance will not be allowed within 180 meters of the 100-year floodplain for the Tucker Draw drainage that flows into Red Bluff Reservoir.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope: $\underline{400'}_{4\%}$ + 100' = 200' lead-off ditch interval

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.



Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, <u>Shale Green</u> from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 <u>et seq.</u> (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, <u>et seq</u>. or the Resource Conservation and Recovery Act, 42 U.S.C.6901, <u>et seq</u>.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of

the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

•

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-ofway.

6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.

7. The maximum allowable disturbance for construction in this right-of-way will be $\underline{30}$ feet:

- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed **20** feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
- Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed <u>30</u> feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
- The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)

9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

1

10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

(X) seed mixture 1	() seed mixture 3
() seed mixture 2	() seed mixture 4
() seed mixture 2/LPC	() Aplomado Falcon Mixture

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. <u>Escape Ramps</u> - The operator will construct and maintain pipeline/utility trenches [that are not otherwise fenced, screened, or netted] to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

C. ELECTRIC LINES

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations. Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, <u>et seq</u>. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, <u>et seq</u>.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.

5. Power lines shall be constructed and designed in accordance to-standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006. The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching

deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes from the poles removed.

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce

the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

1

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 1 for Loamy Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed shall be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed shall be planted using a drill equipped with a depth regulator to ensure proper depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture shall be evenly and uniformly planted over the disturbed area (small/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed shall be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre shall be doubled. The seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

Species	<u>lb/acre</u>
Plains lovegrass (Eragrostis intermedia)	0.5
Sand dropseed (Sporobolus cryptandrus)	1.0
Sideoats grama (Bouteloua curtipendula)	5.0
Plains bristlegrass (Setaria macrostachya)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT



Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C.

NAME: Justin Barmore		Signed on: 05/30/2017
Title: Regulatory Specialis	st	
Street Address: 3500 On	e Williams Center, MD 35	
City: Tulsa	State: OK	Zip: 74172
Phone: (539)573-2651		
Email address: justin.bar	more@wpxenergy.com	
Field Represe	ntative	
Representative Name:		
Street Address:		
City:	State:	Zip:
Phone:		

Email address:

TAFMSS

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT



APD ID: 10400013514

Operator Name: RKI EXPLORATION & PRODUCTION LLC Well Name: TUCKER DRAW 9-4 FED COM Well Type: OTHER

Submission Date: 05/30/2017

Well Number: 1H Well Work Type: Drill

. Land

> Highlighted data reflects the most recent changes <u>Show Final Text</u>

Section 1 - General

APD ID: 10400013514	Tie to previous NOS?	Submission Date: 05/30/2017			
BLM Office: CARLSBAD	User: Justin Barmore	Title: Regulatory Specialist			
Federal/Indian APD: FED	Is the first lease penetrated for	Is the first lease penetrated for production Federal or Indian? FED			
Lease number: NMNM100558	Lease Acres: 960				
Surface access agreement in place?	Allotted? Res	ervation:			
Agreement in place? NO	Federal or Indian agreement:	Federal or Indian agreement:			
Agreement number:					
Agreement name:					
Keep application confidential? YES					
Permitting Agent? NO	APD Operator: RKI EXPLORAT	TION & PRODUCTION LLC			
Operator letter of designation:					

Operator Info

Operator Organization Name: RKI E	XPLORATION & PRODUCTION LLC				
Operator Address: 3500 One Williams Center, MD 35					
Operator PO Box:	Διρ: 74172				
Operator City: Tulsa	State: OK				
Operator Phone: (539)573-0212					
Operator Internet Address:					

Section 2 - Well Information

Well in Master Development Plan? NO	Mater Development Plan name:			
Well in Master SUPO? NO	Master SUPO name:			
Well in Master Drilling Plan? NO	Master Drilling Plan name:			
Well Name: TUCKER DRAW 9-4 FED COM	Well Number: 1H	Well API Number:		
Field/Pool or Exploratory? Field and Pool	Field Name: PURPLE-SAGE WOLFCAMP GAS	Pool Name: PURPLE SAGE WOLFCAMP GAS		

Well Number: 1H

Is the proposed well in an area containing other mineral resources? USEABLE WATER, NATURAL GAS, OIL

Describe other minerals:					
Is the proposed well in a Helium produ	ction area? N	Use Existing Well Pad?	NO	New surface disturbance?	
Type of Well Pad: MULTIPLE WELL		Multiple Well Pad Name:		Number: 16-26S30E-B	
Well Class: HORIZONTAL		TUCKER DRAW FED COM Number of Legs: 1			
Well Work Type: Drill					
Well Type: OTHER					
Describe Well Type: Horizontal Gas Wel	I				
Well sub-Type: INFILL					
Describe sub-type:					
Distance to town: 16.4 Miles	Distance to nea	arest well: 25 FT	Distanc	e to lease line: 230 FT	
Reservoir well spacing assigned acres Measurement: 480 Acres					
Well plat: Well_Plat_04-18-2017.pdf					
Tucker_Draw_9_4_Federal	_Com_Pad_Plat	_05-24-2017.pdf			
Well work start Date: 09/23/2017		Duration: 30 DAYS			

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number:

NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	Ш	TVD
250	FNL	146	FEL	26S	30E	16		32.04921	-	EDD	NEW	NEW	s	STATE	308	0	0
		3					NWNE	1	103.8823	Y	MEXI	MEXI			9		
									94								
177	FNL	230	FEL	26S	30E	16		32.04942	-	EDD	NEW	NEW	s	STATE	-	106	105
		9					NWNE	1	103.8851	Y	MEXI	MEXI			746	11	54
									25						5		
330	FSL	231	FEL	26S	30E	9		32.05079	-	EDD	NEW	NEW	F	NMNM	-	113	110
		0					SWSE	7	103.8851	Y	MEXI	MEXI		100558	794	55	32
									28						3		

Operator Name: RKI EXPLORATION & PRODUCTION LLC

Well Name: TUCKER DRAW 9-4 FED COM

•

.

.

Well Number: 1H

NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
231	FSL	231	FEL	26S	30E	4		32.07085	-	EDD	NEW	NEW	F	NMNM	-	186	111
0		0					NWSE	6	103.8851	Y	MEXI	MEXI		119275	802	00	14
 									61						5		
241	FSL	231	FEL	26S	30E	4		32.07113	-	EDD	NEW	NEW	F	NMNM	-	187	111
0		0				1	NWSE	1	103.8851	Y	MEXI	MEXI		119275	802	81	16
									61						7		





U.S. Department of the Interior BUREAU OF LAND MANAGEMENT



APD ID: 10400013514 Operator Name: RKI EXPLORATION & PRODUCTION LLC	Submission Date: 05/30/2017	Highlighted data reflects the most
Well Name: TUCKER DRAW 9-4 FED COM	Well Number: 1H	recent changes Show Final Text
Well Type: OTHER	Well Work Type: Drill	

Section 1 - Geologic Formations

Formation			True Vertical	Measured			Producing
ID	Formation Name	Elevation	Depth	Depth	Lithologies	Mineral Resources	Formation
1	UNKNOWN	3089	0	0	ALLUVIUM,OTHER	USEABLE WATER	No
					: Quaternary		
2	BELL CANYON	-482	3571	3588	SHALE, SANDSTO	NATURAL GAS,OIL	No
					NE		
3	CHERRY CANYON	-1553	4642	4669	SHALE, SANDSTO	NATURAL GAS,OIL	No
					NE		
4	BRUSHY CANYON	-2621	5710	5747	SHALE, SANDSTO	NATURAL GAS,OIL	No
					NE		
5	AVALON SAND	-4404	7493	7547	SANDSTONE	NATURAL GAS,OIL	No
6	BONE SPRING 1ST	-5208	8297	8353	LIMESTONE, SHAL	NATURAL GAS,OIL	No
					E,SANDSTONE		
	· · · · · · · · · · · · · · · · · · ·						
7	BONE SPRING 2ND	-5933	9022	9078	LIMESTONE, SHAL	NATURAL GAS,OIL	No
					E,SANDSTONE		
	······································						
8	BONE SPRING 3RD	-7116	10205	10261	LIMESTONE, SHAL	NATURAL GAS,OIL	No
					E,SANDSTONE		
9	WOLFCAMP	-7490	10579	10635	LIMESTONE, SHAL	NATURAL GAS,OIL	Yes
					E,SANDSTONE		
		1	1			1	1

Section 2 - Blowout Prevention

Pressure Rating (PSI): 5M

Rating Depth: 18781

Equipment: The blowout preventer equipment (BOPE) will consist of 3 rams (10,000 psi WP) with 2 pipe rams (one of which may be variable), 1 blind ram and 1 annular preventer (5,000 psi WP) will be installed. The BOPE will be used below surface casing to TD. See attachments for BOP and choke manifold diagrams. A rotating head will be installed as needed. Units will be hydraulically operated. An accumulator that meets the requirements of Onshore Order 2 for the pressure rating of the BOP stack will be present. The following BOPE will be installed, tested and operational: • Drilling spool or blowout preventer with two (2) side outlets; Choke line side shall be 3" minimum diameter; Two (2) adjustable chokes with one (1) remotely controlled from the rig floor and pressure gauge. Kill side shall be at least 2" diameter; Two (2) manual valves and one (1) check valve. Auxiliary equipment is as follows: • Upper kelly cock valve with a handle available; • Lower kelly cock valve will be used in the drill string, either in a float sub or in the mud motor; • Safety valves and subs with a full opening sized to fit all drill strings and collars will be available on the rig floor in the open position. A mud gas

Operator Name: RKI EXPLORATION & PRODUCTION LLC

Well Name: TUCKER DRAW 9-4 FED COM

Well Number: 1H

separator (gas buster) will be in place during drilling.

Requesting Variance? YES

Variance request: RKI Exploration & Production, LLC. requests a variance to drill this well using a co-flex line between the BOP and the choke manifold. Certification for proposed co-flex hose is attached. The hose is required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used.

Testing Procedure: BOPE will be inspected and operated as stated in Onshore Order 2. A third party company will test the BOPE. After surface casing is set and the BOPE is nippled up, pressure tests will be conducted to 250 psi low and 5000 psi high (50% of WP) with the annular tested to 250 psi low and 2500 psi high (50% of WP).

Choke Diagram Attachment:

5MChokeManifold_04-18-2017.pdf

BOP Diagram Attachment:

BOP_Diagram_04-18-2017.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	900	0	900	-7465	-8365	900	J-55	54.5	STC	2.85	13.7 9	DRY	10.4 8	DRY	10.4 8
2	INTERMED IATE	12.2 5	9.625	NEW	API	N	0	3588	0	3571	-7465	- 11036	3588	J-55	40	LTC	1.64	5.03	DRY	3.62	DRY	3,62
3	INTERMED IATE	8.75	7.0	NEW	API	N	0	11355	0	11032	-7465	- 18497	11355	HCP -110	29	BUTT	1.9	4.62	DRY	2.9	DRY	2.9
4	LINER	6.12 5	4.5	NEW	NON API	N	10611	18781	10554	11116	- 18019	- 18581	8170	HCP -110	13.5	OTHER - CDC-HTC	2.18	5.07	DRY	1.75	DRY	1.75

Casing Attachments

Operator Name: RKI EXPLORATION & PRODUCTION LLC Well Name: TUCKER DRAW 9-4 FED COM

Well Number: 1H

Casing Attachments
Casing ID: 1 String Type: SURFACE
Inspection Document:
Spec Document:
Tapered String Spec:
Casing Design Assumptions and Worksheet(s):
Casing_Assumptions_05-23-2017.pdf
Casing ID: 2 String Type: INTERMEDIATE
Inspection Document:
Spec Document:
Tapered String Spec:
Casing Design Assumptions and Worksheet(s):
Casing_Assumptions_05-23-2017.pdf
Casing ID: 3 String Type:INTERMEDIATE Inspection Document:
Spec Document:
Tapered String Spec:
Casing Design Assumptions and Worksheet(s):
Casing_Assumptions_05-23-2017.pdf

Well Number: 1H

Casing Attachments

Casing ID: 4 String Type:LINER

Inspection Document:

Spec Document:

CDC_HTC_spec_sheet_05-23-2017.pdf

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Casing_Assumptions_05-23-2017.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	643	385	1.74	13.5	447	50	Class C	4% Gel + 2% CaCl + 0.4 pps Defoamer + 0.125 pps CelloFlake
SURFACE	Tail		643	900	200	1.34	14.8	134	50	Class C	2% Calcium
INTERMEDIATE	Lead		0	2914	564	1.92	12.9	957	20	Class C / Poz 35/65	5% Salt + 6% Gel + 0.5% Retarder + 3 pps LCM + 0.4 pps Defoamer + 0.125 pps CelloFlake
INTERMEDIATE	Tail		2914	3588	200	1.32	14.8	211	20	Class C	None
INTERMEDIATE	Lead		3088	1061 1	504	2.67	11.2	1135	20	TXI Lightweight	10% Gel + 8% Plex Crete + 0.9% Retarder + 0.7 pps FL + 3 pps LCM + 0.4 pps Defoamer + 0.125 pps CelloFlake
INTERMEDIATE	Tail		1061 1	1135 5	114	1.18	15.6	112	20	Class H	0.3% Retarder
LINER	Lead		1061 1	1878 1	483	1.89	13	772	20	Acid Soluble TXI	1.3% Salt + 30% CaCl + 5% Plexaid + 0.7% FL + 0.3% Retarder + 0.1%

Operator Name: RKI EXPLORATION & PRODUCTION LLC

Well Name: TUCKER DRAW 9-4 FED COM

Well Number: 1H



Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: An electronic mud monitoring system satisfying the requirements of Onshore Order 1 will be used. All necessary mud products for weight addition and fluid loss control will be on location at all times. Mud program is subject to change due to hole conditions.

Describe the mud monitoring system utilized: The following mud system monitoring equipment will be in place during drilling: • Visual pit markers • Pit volume totalizer (PVT) • Stroke counter • Gas detection • Mud-gas separator (gas buster) • Flow sensor

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (Ibs/gal)	Max Weight (Ibs/gal)	Density (Ibs/cu ft)	Gel Strength (lbs/100 sqft)	НА	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
3571	1103 2	OTHER : Cut Brine	8.9	9.4							
1103 2	1111 6	OIL-BASED MUD	10.5	12							
900	3571	OTHER : Brine	9.8	10							
0	900	WATER-BASED MUD	8.5	8.9							
Operator Name: RKI EXPLORATION & PRODUCTION LLC

Well Name: TUCKER DRAW 9-4 FED COM

Well Number: 1H

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures: A 2-person mud-logging program will be used from Int_1 9-5/8" casing point to TD.

List of open and cased hole logs run in the well: CBL,DS,MWD Coring operation description for the well:

None

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 6884

Anticipated Surface Pressure: 4438.47

Anticipated Bottom Hole Temperature(F): 200

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geoharzards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

RKI_H2S_Plan_Tucker_Draw_Fed_Com_26S_30E_B_3_30_17_04-18-2017.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Tucker_DF_9_4_1H_Plan__1_05-24-2017.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:

Tucker_Draw_Fed_COM_9_4_1H___BLM_Drilling_Plan__05_15_17__05-24-2017.pdf

Other Variance attachment:

5M Choke Manifold

. ·



· · · · · ·

Exhibit #1:

۰ **۱**



(USS) U. S. Steel Tubular Products

.

t, ;' Γ (Γ Γ 1 ł,

í.

.

4 1/2 13.50 lb (0.29) P110 HC

USS-CDC HTQ™

	PIPE	CONNECTIO	2N	
MECHANICAL PROPERTIES				
Minimum Yield Strength	110,000		,	psi
Maximum Yield Strength	140,000		,	psi
Minimum Tensile Strength	125,000		1	os i
DIMENSIONS				
Outside Diameter	4.500	5 250		in.
Wall Thickness	0.290			ìn.
Inside Diameter	3.920	3 920		in.
Drift API	3 795	3 795		in.
Nominal Linear Weight, T&C	13.50		lbs,	/ft
Plain End Weight	13.05		ibs,	/ft
SECTION AREA				
Cross Sectional Area Critical Area	3.836	3.836	sq.	in.
Joint Efficiency		100.0		%
PERFORMANCE				
Minimum Collapse Pressure	11,810	11,810	4	psi
External Pressure Leak Resistance		9,450	4	psi
Minimum Internal Yield Pressure	12,420	12,420	Å	psi
Minimum Pipe Body Yield Strength	422,000		1	lbs
Joint Strength		443,000	1	lbs
Compression Rating		266,000	1	lbs
Reference Length		21,877		ft
Maximum Uniaxial Bend Rating	Strange and stores and	70.5	deg/100) ft
MARE-UP DATA	Section of			
Make Up Loss		4,44		in.
Minimum Make Up Torque		7,000	ft-;	lbs
Maximum Make-Up Torque		10,000	ft l	lbs
Connection Yield Torque		12,400	ft l	lbs
Verfication of connection shoulder require	ed ™yokalishoù der (ange	4 500	6 500	16-2 16-2 1-1-1

Notes

Other than prophetary of lapse and connection values, performance properties have been calculated using standard equations defined by API pC3 and do tot incorporate any additional design or safety factors. Calculations assume nominal pipe OD, nominal wail thickness, and Specified Minimum Yield Strength (SMYS).

2) Uniaxial bending rating shown is structural only, and equal to compress on efficiency

3) Forques have been calculated assuming a thread compound friction factor of 10 and are recommended only. Field make-up torques may require adjustment based on actual field conditions (e.g. make-up speed, temperature, thread compound, etc.)

4) Reference, engines takes by joint strength divided by nominal 1&C we get with 1.5 safety factor

5) Connection external pressure resistance has been verified to 50% API cipe body to lapse pressure (API 505 Call) testing protocol)

Lega Nitroe USS-CDC HTQ¹⁴ High Till due Casing Dilling Climitection (is a trademark of UliS) Base — Lato — This product e a monited API Butvess threaded and dilling the connection designed for drilling with basing applications. All material contined in this bubilistion is for general intermal on one, This material shift of until therefore be used on end upon from any spectric accuration with the bender to order to the spectric accuration with a difference to order to any and all fability relimiting from such use. U. Site declamating and all oppressed or the diversities of fitness for any general or pendular application. U.S Steel declamating and all oppressed or the diversities of fitness for any general or pendular application.

U. S. Steel Tubular Products 1-877-893-9461 10343 Sam Houston Park Dr., #120 connections@uss.com Houston, TX 77064 www.usstubular.com

		4
	Certion	Casing Pro
		ogram:
(MD)	Тор	
(MD)	Bottom	

Safety FactorsCollapse1.125Burst1.000	1.600	Tension
Safety FactorsCollapse1.125	1,000	Burst
Safety Factors	1.125	Collapse
	Factors	Safety

.

1.75	5.07	2.18	Prod
2.90	4.62	1.90	Int_2
3.62	5,03	1.64	Int_1
10.48	13.79	2.85	Surf
Tension	Burst	Collapse	Section
	Factors	Design	

tortion		Тор	Bottom	Bottom		Weight		1
		(MD)	(MD)	(TVD)		(ppf)	Grade	Inreads
Surf	17-1/2"	0	006	006	13-3/8"	54.5	J-55	ST&C
Int_1	12-1/4"	0	3,588	3,571	9-5/8"	40.0	J-55	LT&C
Int_2	8-3/4"	0	11,355	11,032	7"	29.0	HCP-110	BT&C
Prod	6-1/8"	10,611	18,781	11,116	4-1/2"	13.5	HCP-110	CDC-HTC

Tucker Draw Fed Com 26S-30E-B



1. H2S Safety Training

When working in an area where Hydrogen Sulfide (H₂S) might be encountered, definite training requirements must be carried out. The Company Supervisor will ensure that all personnel, at the well site, have had adequate training in the following:

- Hazards and characteristics of Hydrogen Sulfide (H₂S).
- Physicals effects of Hydrogen Sulfide on the human body.
- Toxicity of Hydrogen Sulfide and Sulfur Dioxide.
- H₂S detection, Emergency alarm and sensor location.
- Emergency rescue.
- Resuscitators.
- First aid and artificial resuscitation.
- The effects of Hydrogen Sulfide on metals.
- Location safety.

Service company personnel and visiting personnel must be notified if the zone contains H₂S, and each service company must provide adequate training and equipment for their employees before they arrive at the well site.

2. H2S detection and Alarm Systems

- Four channel H₂S monitor with alarms.
- Three (3) sensors located as follows: #1 Rig Floor, #2 Shale Shaker, #3 Cellar.
- Gastec or Draeger pump with tubes.
- Sensor test gas.

3. Windsocks and / Wind Streamers

- A minimum of two 10" windsocks located at strategic locations so that they may be seen from any point on location.
- Wind streamers (if preferred) should be placed at various locations on the well site to ensure wind consciousness at all times. (Corners of location).

4. Condition Flags and Signs

The Well Condition Sign w/flags should be placed a minimum of 150' before you enter the location. It should have three (3) color coded flags (green, yellow and red) that will be used to denote the following location conditions:

- GREEN Normal Operating Conditions
- YELLOW Potential Danger
- RED Danger, H₂S Gas Present
- 5. Well Control Equipment

• See APD

- 6. Communications
 - Proper communication equipment such as cell phones or 2-way radios should be available at the rig.

- Radio communication shall be available for communication between the company man's trailer, rig floor and the tool pusher's trailer.
- Communication equipment shall be available on the vehicles.

7. Drilling Stem Testing

Not Applicable

8. Drilling Fluids

4

The primary control to avoid H₂S problems in a drilling operation is to keep it retained in the formation. A slight over balance in drilling fluid density is required. It must be enough to overcome any swabbing effects on connections and trips. Ample pit volume will be provided to contain an adequate supply of drilling mud.

- Drilling Fluid Monitoring On Any Hazardous H₂S gas well, the earlier the warning of danger the better chance to control operations. Mud Company will be in daily contact with a RKI Representative. The Mud Engineer will take samples of the mud, analyze these samples, and make necessary recommendations to prevent H₂S gas from the formation, the pH will be increased as necessary for corrosion control.
- pH Control For normal drilling, pH of 10.5 11.5. Would be sufficient for corrosion protection. If there is an influx of H₂S gas from the formation, the pH will be increased as necessary for corrosion control.
- H₂S Scavengers If necessary H₂S scavengers will be added to the drilling mud.
- Garret Gas Train or Hach Tester for inspection of Hydrogen Sulfide in the drilling mud system.

9. Emergency Contacts:

Local Contacts	
Operations Senior Foreman	
Danny Emerson	(505) 614-4867
Production Superintendent	
Justin Warren	(701) 421-7324
Production Foreman	
Kipper Folmar	(575) 644-2008
Gary Moreau	(575) 200-4278
Kurt Heckman	(505) 333-1809
Operation Foreman	
Filip Avila	(505) 692-5467
Completions Superintendent	
Kent Hejl	(575) 885-7539
Jim Auld	(539) 573-7508
Drilling Superintendent	
Lance Vaughn	(325) 647-8148
	(575) 200-4160
Deck Travis	(713) 805-6739
Environmental Specialist	
Karolina Blaney	(970) 589-0743

Safety Specialist	
Stephan Holloway	(361) 436-6290
EH&S Contractor	
Randali Moreland	(318) 458-1537
Regional Conta	acts
Production Manager	
Bobby Goodwin	(918) 642-3688
Drilling Engineer	
Preston Wray	(539) 573-7604
Completions Engineer	· · /
Jav Brenner	(918) 289-9252
Corporate Cont	acts
VP Asset Team	
Matt Hinson	(539) 573-0170
Drilling Manager	
leff Cutler	(539) 573-2772
FHS Manager	
Lucas Smith	(817) 727-9716
Legal Liaison	
Kevin Mathews	(918) 606-6356
RMID Liaison	
Scott Davennort	(018) 573-5917
Communications Liaison	(510) 575-5517
Communications Liaison	(918) 629-1037
Communications Liaison Kelly Swan	(918) 629-1037
Communications Liaison Kelly Swan Emergency Response Contacts	(918) 575-5517 (918) 629-1037 911 or
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service:	(918) 629-1037
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department	(918) 629-1037
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department Hospitals:	(918) 629-1037
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad)	(918) 629-1037
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso)	(918) 629-1037
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso) University Medical Center (Lubbock)	(918) 629-1037
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso) University Medical Center (Lubbock) Fire Department:	(918) 629-1037 911 or (575) 885-3125 (575) 557-4100 (915) 577-1200 (806) 775-8200
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso) University Medical Center (Lubbock) Fire Department: Carlsbad Fire Department	(918) 629-1037 <u>911 or</u> (575) 885-3125 (575) 557-4100 (915) 577-1200 (806) 775-8200 (575) 885-3125
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso) University Medical Center (Lubbock) Fire Department: Carlsbad Fire Department Pecos VFD	(918) 629-1037
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso) University Medical Center (Lubbock) Fire Department: Carlsbad Fire Department Pecos VFD Law Enforcement:	(918) 629-1037 911 or (575) 885-3125 (575) 557-4100 (915) 577-1200 (806) 775-8200 (575) 885-3125 (432) 445-3519
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso) University Medical Center (Lubbock) Fire Department: Carlsbad Fire Department Pecos VFD Law Enforcement: Carlsbad Police Department	(918) 629-1037 911 or (575) 885-3125 (575) 557-4100 (915) 577-1200 (806) 775-8200 (575) 885-3125 (432) 445-3519 (575) 885-6547
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso) University Medical Center (Lubbock) Fire Department: Carlsbad Fire Department Pecos VFD Law Enforcement: Carlsbad Police Department Pecos Police Department	(918) 629-1037 911 or (575) 885-3125 (575) 557-4100 (915) 577-1200 (806) 775-8200 (575) 885-3125 (432) 445-3519 (575) 885-6547 (432) 445-4911
Communications Liaison Kelly Swan <u>Emergency Response Contacts</u> Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso) University Medical Center (Lubbock) Fire Department: Carlsbad Fire Department Pecos VFD Law Enforcement: Carlsbad Police Department Pecos Police Department Eddy County Sherriff's Department	(918) 629-1037 911 or (575) 885-3125 (575) 557-4100 (915) 577-1200 (806) 775-8200 (575) 885-3125 (432) 445-3519 (575) 885-6547 (432) 445-4911 (575) 887-7551
Communications Liaison Kelly Swan <u>Emergency Response Contacts</u> Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso) University Medical Center (Lubbock) Fire Department: Carlsbad Fire Department Pecos VFD Law Enforcement: Carlsbad Police Department Pecos Police Department Pecos Police Department Eddy County Sherriff's Department Loving County Sherriff's Department	(918) 629-1037 911 or (575) 885-3125 (575) 557-4100 (915) 577-1200 (806) 775-8200 (575) 885-3125 (432) 445-3519 (575) 885-6547 (432) 445-4911 (575) 887-7551 (432) 337-2411
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso) University Medical Center (Lubbock) Fire Department: Carlsbad Fire Department Pecos VFD Law Enforcement: Carlsbad Police Department Pecos Police Department Pecos Police Department Eddy County Sherriff's Department Loving County Sherriff's Office	(918) 629-1037 911 or (575) 885-3125 (575) 557-4100 (915) 577-1200 (806) 775-8200 (575) 885-3125 (432) 445-3519 (575) 885-6547 (432) 445-4911 (575) 887-7551 (432) 337-2411 (432) 445-4901
Communications Liaison Kelly Swan <u>Emergency Response Contacts</u> Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso) University Medical Center (Lubbock) Fire Department: Carlsbad Fire Department Pecos VFD Law Enforcement: Carlsbad Police Department Pecos Police Department Pecos Police Department Eddy County Sherriff's Department Loving County Sherriff's Office New Mexico State Police – District 3	(918) 629-1037 911 or (575) 885-3125 (575) 557-4100 (915) 577-1200 (806) 775-8200 (575) 885-3125 (432) 445-3519 (575) 885-6547 (432) 445-4911 (575) 887-7551 (432) 337-2411 (432) 445-4901 (575) 885-3138
Communications Liaison Kelly Swan Emergency Response Contacts Ambulance Service: Carlsbad Fire Department Hospitals: Carlsbad Medical Center (Carlsbad) University Medical Center (El Paso) University Medical Center (Lubbock) Fire Department: Carlsbad Fire Department Pecos VFD Law Enforcement: Carlsbad Police Department Pecos Police Department Pecos Police Department Eddy County Sherriff's Department Loving County Sherriff's Office New Mexico State Police – District 3 Homeland Security (Federal)	(918) 629-1037 911 or (575) 885-3125 (575) 557-4100 (915) 577-1200 (806) 775-8200 (575) 885-3125 (432) 445-3519 (575) 885-6547 (432) 445-4911 (575) 887-7551 (432) 337-2411 (432) 445-4901 (575) 885-3138 (202) 282-8000

e 1

Regulatory Contacts

Local Emergency Planning Committee (LEPC)

• •

Eddy County, Carlsbad, NM	(575) 885-3581
Lea County, Lovington, NM	(575) 396-8607
Chaves County, Roswell, NM	(575) 624-6140
Reeves County, Pecos, TX	(432) 447-3542
Loving County, Mentone, TX	(915) 377-2362
Winkler County, Kermit, TX	(432) 586-6658
Wheeler County, Wheeler, TX	(806) 826-3777
Texas Railroad Commission – District 8	(432) 684-5581
New Mexico Oil Conservation Division	(505) 476-3440
New Mexico Occupational Safety and Health Bureau (NM OSHA)	(505) 476-8700
Federal OSHA: Lubbock area office	(806) 472-7681
US BLM: Carlsbad, NM field office	(575) 234-5972
Federal Environmental Protection Agency: National Response Center (NRC)	(800) 424-8802



WPX Energy

Eddy County, New Mexico NAD 83 Tucker Draw Fed 9-4 Pad Tucker Draw Fed 9-4 1H API: ??? Wellbore #1

Plan: Plan #1

Standard Planning Report

ne vez an arrante l'esta de la compañía de la compa

30 March, 2017

Scientific Drilling

www.scientificdrilling.com



Planning Report

Database: Company: Project: Site: Well: Well: Wellbore: Design:		Midlar WPX I Eddy (Tucke Tucke Wellbo Plan #	nd District Energy County, New r Draw Fed S r Draw Fed S ore #1	/ Mexico M 9-4 Pad 9-4 1H	NAD 83		Local Co-ordinate Reference:Well Tucker Draw Fed 9-4 1HTVD Reference:RKB @ 3112.00usft (Orion Aires)MD Reference:RKB @ 3112.00usft (Orion Aires)North Reference:GridSurvey Calculation Method:Minimum Curvature					95) 95)
Project		Eddy C	County, New	Mexico N	AD 83							
Map System: Geo Datum: Map Zone:	ן ה ו	JS State North An New Me	e Plane 1983 nerican Datu xico Eastern	m 1983 Zone			System Da	atum:	N	lean Sea Level		
Site		Tucker	Draw Fed 9	-4 Pad								
Site Position: Fram: Position Uncer	tainty:	Map	р ().00 usft	Northi Eastin Siot R	ng: g: adius:	38 68	1,932.50 usft 1,049.30 usft 13-3/16 "	Latitude: Longitude: Grid Conver	gence:		32° 2' 57.157 N 103° 52' 56.618 W 0.24 °
Well		Tucker	Draw Fed 9-	4 1H			1 A					
Well Position		+N/-S +E/-W		0.00 usft 0.00 usft	No Ea	rthing: sting:		381,932.5 681,049.3	0 usft La 0 usft Lo	titude: ngitude:		32° 2' 57.157 N 103° 52' 56.618 W
Position Uncer	tainty			0.00 usft	We	ellhead Eleva	tion:	0.0	0 usft Gr	ound Level:		3,089.00 usft
Wellbore		Wellbo	ore #1									
Magnetics		Mo	odel Name		Sample	e Date	Declin (°	ation)	Dip	Angle (°)	Field S (1	Strength nT)
			HDG	M		3/27/2017		6.93		59.78		48,030
Design Audit Notes:		Plan #1	1									
Version: Vertical Section	n:			Depth F {I	Phase from (TV usft) 0.00	e: (D)	PLAN +N/-S (usft) 0.00	+ (e On Depth: E/-W usft) 0.00	Dir (be 3	rection earing) 59.68	
Plan Sections							-					
Measured Depth (usft)	Inclin: (°	ation)	Azimuth (bearing)	Verti Dep (us	cal hth ft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00		0.00	0.0	0	0.00	0.00	0.00	0.00	0.0	0.00	0.00	
1,000.00		0.00	0.0	0 1,0	00.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,600.00		3.00	276.9	3 1,5	99.73	1.89	-15.59	0.50	0.50	0.00	276.93	
2,084.77		7.84	274.8	6 2,0	82.18	6.23	-61.17	1.00) 1.0	0 -0.43	-3.35	
7,663.79		7.84	274.8	6 7,6	09.00	70.73	-819.89	0.00) 0.01	0.00	0.00	
8,056.02		0.00	0.0	U 8,0	00.00	73.00	-846.60	2.00	-2.0	0.00	180.00	
10,610.56		0.00	0.0	U 10,5	54.54	73.00	-846.60	0.00	0.00	0.00	0.00	LUCKER DF 1H KOP
19,355.16		69.35 80.25	359.6	o 11,0 8 11 1	16.00	545.06 7 070 60	-849.24	12.00) 12.00	-0.04	80.855 0 00	Tucker DE 14 BHI
10,701.29		09.33	0.800	o II,1 	10.00	00.016,1	-090.70	U.UL	· U.UI		0.00	

¢

•

Planning Report

Database: Company:	Midland District WPX Energy	Local Co-ordinate Reference: TVD Reference:	Well Tucker Draw Fed 9-4 1H RKB @ 3112.00usft (Orion Aires)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	RKB @ 3112.00usft (Orion Aires)
Site:	Tucker Draw Fed 9-4 Pad	North Reference:	Grid
Well:	Tucker Draw Fed 9-4 1H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #1		

Planned Survey

.

÷

Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Section	Rate	Rate	Rate
(usft)	(°)	(bearing)	(usft)	(usft)	(usft)	(usft)	(°/100usft)	(°/100usft)	(°/100usft)
0.00	0,00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0
100.00	0,00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.0
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.0
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.0
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.0
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.0
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.0
600.00	0.00	0.00	000.00	0.00	0.00	0.00	0.00	0.00	0.0
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.0
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.0
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.1
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.
Start Build 0	.50 - 13 3/8"								
1,100.00	0.50	276.93	1,100.00	0.05	-0.43	0.06	0.50	0.50	0.
1,200.00	1.00	276.93	1,199.99	0.21	-1.73	0.22	0.50	0.50	0.
1,300.00	1.50	276.93	1,299.97	0.47	-3.90	0.50	0.50	0.50	0.
1,400.00	2.00	276.93	1,399.92	0.84	-6.93	0.88	0.50	0.50	0.
1 500 00	2 50	276.02	1 /00 8/	1 30	-10.83	1.20	0.50	0.50	0
1,500.00	2.50	276.93	1,499.64	1.32	-15.59	1.30	0.50	0.50	0.1
Start DI S 1	0.00	210.00	1,000.70	1.00	10.00	1.00	0.00	0.00	0.
1 700 00	4 00	276.00	1 600 54	2.58	-21.65	2 70	1.00	1.00	-0
1,700,00	4.00	270,09	1,099,04	2,00	-21.00	2.70	1.00	1.00	-0.
1,800.00	5.00	2/5.59	1,799.23	3.38	-29.40	3.54	1.00	1.00	-0.
1,900.00	6.00	2/5.25	1,898.77	4.28	-38.99	4.50	1.00	1.00	-0
2,000.00	7.00	275.01	1,998.12	5.29	-50.26	5.57	1.00	1.00	-0.
2,084.77	7.84	274.86	2,082.18	6.23	-61.17	6.57	1.00	1.00	-0.
2,087.57	7.84	274.86	2,084.96	6.26	-61.55	6.61	0.00	0.00	0.
Start 5575.1	hold at 2087.6 I	MD							
2,100.00	7.84	274,86	2,097.27	6.41	-63.24	6.76	0.00	0.00	0.
2,200.00	7.84	274.86	2,196.34	7.56	-76.84	7.99	0.00	0.00	0.
2,300.00	7.84	274.86	2,295.40	8.72	-90.44	9.22	0.00	0.00	0.
2,400.00	7.84	274.86	2.394.46	9.87	-104.04	10.46	0.00	0.00	0.
2 500 00	7 84	274 86	2 4 9 3 5 3	11.03	-117 64	11.69	0.00	0.00	0
2,000.00	7.04	274.00	2,400.00	12.10	-131.24	12.00	0.00	0.00	0.
2,800.00	7.84	274.80	2,592.59	13.34	-144 84	14.15	0.00	0.00	0.
2,700.00	7.01	27 1.00	2,001.00	14.50	450.44	15.00	0.00	0.00	
2,800.00	7.84	274.86	2,790.72	14.50	-158.44	15.38	0.00	0.00	0.
2,900.00	7.84	274.86	2,889.78	15.00	-1/2.04	10.02	0.00	0.00	0.
3,000.00	7.84	274.86	2,988.85	16.81	-185.64	17.85	0.00	0.00	0.
3,100.00	7.84	274.86	3,087.91	17.97	-199.24	19.08	0.00	0.00	0.
3,200,00	7.84	274.86	3,186.98	19.12	-212.84	20,31	0.00	0.00	0.
3,300.00	7.84	274.86	3,286.04	20.28	-226.44	21.54	0.00	0.00	0.
3,400.00	7.84	274.86	3,385.11	21.44	-240.04	22.78	0.00	0.00	0.
3,500.00	7.84	274.86	3,484.17	22.59	-253.64	24.01	0.00	0.00	0.
3,587.65	7.84	274.86	3,571.00	23.60	-265.56	25.09	0.00	0.00	0.
Bell Canyon	(Base of Salt) -	9 5/8"							
3,600.00	7.84	274.86	3,583.23	23.75	-267.24	25.24	0.00	0.00	0.
3,700.00	7 84	274 86	3,682 30	24 90	-280.83	26.47	0.00	0.00	0
3 800 00	7.07	274 86	3 781 36	26.06	-204 43	27 70	0.00	0.00	0. 0
3 900 00	7.04	274.00	3 880 13	20.00	-207.40	21.10	0.00	0.00	0. n
3,900.00	1.04	214.00	2,000.43	21.22	-300.03	20.54	0.00	0.00	0.
4,000.00	7.84 7 Q/	274.00 274.86	3,979.49 1 078 56	20.37 20.53	-321.03 _325.22	30.17	0.00	0.00	U. N
4,100.00	1.04	214.00	4,070.00	29.00	-333,23	51.40	0.00	0.00	0.
4,200.00	7.84	274.86	4,177.62	30.68	-348.83	32.63	0.00	0.00	0.
	7.84	274.86	4,276.68	31.84	-362.43	33.86	0.00	0.00	0.
4,300.00						0 E 1 0			~
4,300.00 4,400.00	7.84	274.86	4,375.75	33.00	-376.03	35.10	0.00	0.00	U.

Planning Report

Database:	Midland District	Local Co-ordinate Reference:	Well Tucker Draw Fed 9-4 1H
Company:	WPX Energy	TVD Reference:	RKB @ 3112.00usft (Orion Aires)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	RKB @ 3112.00usft (Orion Aires)
Site:	Tucker Draw Fed 9-4 Pad	North Reference:	Grid
Well:	Tucker Draw Fed 9-4 1H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #1		

Planned Survey

•

٠

Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Section	Rate	Rate	Rate
(usft)	(°)	(bearing)	(usft)	(usft)	(usft)	(usft)	(°/100usft)	(°/100usft)	(°/100usft)
4,668.77	7.84	274,86	4,642.00	36.10	-412.58	38.41	0.00	0.00	0.0
Cherry Cany	/on								
4,700.00	7.84	274.86	4,672.94	36.46	-416.83	38,79	0.00	0.00	0.0
4.800.00	7.84	274.86	4,772.00	37.62	-430.43	40.02	0.00	0.00	0.0
4,900.00	7.84	274.86	4.871.07	38.78	-444.03	41.26	0.00	0.00	0.0
5,000.00	7.84	274.86	4.970.13	39,93	-457.63	42,49	0.00	0.00	0.0
E 100 00	7 94	274.00	5 060 20	41.00	474 00	10 70	0.00	0.00	0.0
5,100.00	7.04	274.00	5,069.20	41.09	-471.23	43.72	0.00	0.00	0.0
5,200.00	7.04	274.00	5,100.20	42.20	-404.03	44.90	0.00	0.00	0.0
5,300.00	7.64	274.80	5,267.33	43.40	-496.43	40.18	0.00	0,00	0.0
5,400.00	7.84	274.80	5,366.39	44.56	-512.03	47.42	0.00	0.00	0.0
5,500.00	7.84	274.86	5,465.45	45.71	-525.62	48.65	0.00	0.00	0.0
5,600.00	7.84	274.86	5,564.52	46.87	-539.22	49.88	0.00	0.00	0.0
5,700.00	7.84	274.86	5,663.58	48.03	-552.82	51.11	0.00	0.00	0.0
5,746.86	7.84	274.86	5,710.00	48.57	-559.20	51.69	0.00	0.00	0.0
Brushy Can	yon								
5,800.00	7.84	274.86	5,762.65	49.18	-566.42	52.34	0.00	0.00	0.0
5,900.00	7.84	274.86	5,861.71	50.34	-580.02	53.58	0.00	0.00	0.0
e 000 00	7.04	274.00	E 000 78	E4 40	502.60	E1 01	0.00	0.00	
6,000.00	7.84	274.86	5,960.78	51.49	-593.62	54.81	0.00	0.00	0.0
6,100.00	7.84	274.86	6,059.84	52.65	-607.22	56.04	0.00	0.00	0.0
6,200.00	7.84	274.86	6,158.90	53.81	-620.82	57.27	0.00	0.00	0.0
6,300.00	7.84	274.86	6,257.97	54.96	-634.42	58.50	0.00	0.00	0.0
6,400.00	7.84	274.86	6,357.03	56.12	-648.02	59.74	0.00	0.00	0.0
6,500.00	7.84	274.86	6,456.10	57.27	-661.62	60.97	0.00	0.00	0.0
6,600.00	7.84	274,86	6,555,16	58.43	-675.22	62,20	0.00	0.00	0.0
6,700,00	7.84	274,86	6.654.22	59.59	-688,82	63,43	0.00	0.00	0.0
6,800,00	7.84	274.86	6.753.29	60.74	-702.42	64.66	0.00	0.00	0.0
6,900.00	7.84	274.86	6,852.35	61.90	-716.02	65.90	0.00	0.00	0.0
7,000.00	7.84	274.86	6,951,42	63,06	-729.62	67.13	0.00	0.00	0.0
7,100.00	7.84	274.86	7.050.48	64.21	-743.22	68.36	0.00	0.00	0.0
7.200.00	7.84	274.86	7 149 55	65.37	-756.81	69.59	0.00	0.00	0.0
7.300.00	7.84	274 86	7 248 61	66.52	-770.41	70.83	0.00	0.00	0.0
7,400.00	7.84	274.86	7,347.67	67.68	-784.01	72.06	0.00	0.00	0.0
7 422 54	7 84	274 86	7 370 00	67.94	-787.08	72 33	0.00	0.00	0.0
Rone Sprine	,	274.00	1,570.00	07.54	-707.00	72.00	0.00	0.00	0.0
7 500 00	7.94	274.96	7 446 74	60.04	707 61	73.20	0.00	0.00	0.1
7,500.00	7.04	274.00	7,440.74	60.04	-797.01	73.29	0.00	0.00	0.0
1,040.10	7.04	214.00	1,493.00	09.30	-000.90	13.00	0.00	0.00	0.0
7 600 00	704	274 00	7 645 00	60.00	041 04	74 50	0.00	0.00	~
7,000.00	7.64	274.00	7,545,80	09,99 70,70	-011.21	74,52	0.00	0.00	0.0
CO.200,1 Start Dron	7.04 200	214.00	1,007.87	10.12	-019.73	15.29	0.00	0.00	0.0
Start Drop -									
7,663.79	7.84	274.86	7,609.00	70.73	-819.89	75.31	0.00	0.00	0.0
7,700.00	7.12	274.86	7,644.90	71.13	-824.59	75.73	2.00	-2.00	0.0
7,800.00	5.12	274.86	7,744.32	72.03	-835.21	76.70	2.00	-2.00	0.0
7,900.00	3.12	274.86	7,844.06	72.64	-842.37	77.34	2.00	-2.00	0.0
8,000.00	1.12	274.86	7,943.99	72.95	-846.05	77.68	2.00	-2.00	0.0
8,056,02	0.00	0.00	8,000,00	73.00	-846.60	77,73	2.00	-2.00	0.0
8,056.44	0.00	0.00	8,000.42	73.00	-846.60	77.73	0.00	0.00	0.0
Start 2638 5	hold at 8056 4 M	MD OIL	_,						•
8 100 00	0.00	<u>-</u> 0.00	8 043 08	73.00	-846 60	77 72	0.00	0.00	0.0
8 200 00	0.00	0.00	8 1/3 08	73.00	-846 60	77 72	0.00	0.00	0.0
8,200.00	0.00	0.00	8 243 08	73.00	-846 60	77 73	0.00	0.00	0.0
0,000.00	0.00	0.00	0,240.00	75.00	040.00	11.13	0.00	0.00	0.0
8,353.02	0.00	0.00	8,297.00	73.00	-846.60	77.73	0.00	0.00	0.(
1st Bone Sp	ring Sand								

Planning Report

Database:	Midland District	Local Co-ordinate Reference:	Well Tucker Draw Fed 9-4 1H
Company:	WPX Energy	TVD Reference:	RKB @ 3112.00usft (Orion Aires)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	RKB @ 3112.00usft (Orion Aires)
Site:	Tucker Draw Fed 9-4 Pad	North Reference:	Grid
Well:	Tucker Draw Fed 9-4 1H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #1		

Planned Survey

•

,

Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth	Inclination	Azimuth	Depth	+N/_S	+F/-W	Section	Rate	Rate	Rate
(usft)	(°)	(bearing)	(usft)	(usft)	(usft)	(usft)	(°/100usft)	(°/100usft)	(°/100usft)
8,400.00	0.00	0.00	8,343.98	73,00	-846.60	77,73	0.00	0.00	0.00
8,500,00	0.00	0.00	8,443,98	73.00	-846.60	77.73	0.00	0.00	0.00
8,600,00	0.00	0.00	8,543,98	73.00	-846.60	77.73	0.00	0.00	0.00
8,700.00	0.00	0.00	8,643.98	73.00	-846.60	77.73	0.00	0.00	0.00
8,800.00	0.00	0.00	8,743.98	73.00	-846.60	77.73	0.00	0.00	0.00
8.900.00	0.00	0.00	8,843,98	73,00	-846,60	77,73	0,00	0.00	0.00
8,906.02	0.00	0.00	8,850.00	73.00	-846.60	77.73	0.00	0.00	0.00
2nd Bone Sp	oring Lime								
9,000.00	0.00	0.00	8,943.98	73.00	-846.60	77,73	0.00	0.00	0.00
9,078.02	0.00	0.00	9,022.00	73.00	-846.60	77.73	0.00	0.00	0.00
2nd Bone Sp	oring Sand								
9,100.00	0.00	0.00	9,043.98	73.00	-846.60	77.73	0.00	0.00	0.00
9.200.00	0.00	0.00	9,143,98	73.00	-846.60	77.73	0.00	0.00	0.00
9,300.00	0.00	0.00	9,243,98	73.00	-846.60	77.73	0.00	0.00	0.00
9 400 00	0.00	0.00	9 343 98	73.00	-846 60	77 73	0.00	0.00	0.00
9,500,00	0.00	0.00	9,443,98	73.00	-846,60	77,73	0.00	0.00	0.00
9 537 02	0.00	0.00	9 491 00	73.00	-846 60	77 73	0.00	0.00	0.00
3rd Bone Sn	ring Lime	0.00	5,401.00	/ 5.00	-040.00	11.15	0.00	0.00	0.00
9 600 00	0.00	0.00	9 543 98	73.00	-846 60	77 73	0.00	0.00	0.00
9,000.00	0.00	0.00	9 643 08	73.00	-846.60	77.73	0.00	0.00	0.00
9,700.00	0.00	0.00	9,043.90	73.00	-040.00	77.73	0.00	0.00	0.00
9,800.00	0.00	0.00	9,743.90	73.00	-846.60	77.73	0.00	0.00	0.00
9,900.00	0.00	0.00	9,043.90	70.00	-040.00	77.70	0.00	0.00	0.00
10,000.00	0.00	0.00	9,943.98	73.00	-846.60	77.73	0.00	0.00	0.00
10,100.00	0.00	0.00	10,043.98	73.00	-846.60	77.73	0.00	0.00	0.00
10,200.00	0.00	0.00	10,143.98	73.00	-846.60	77.73	0.00	0.00	0.00
10,261.02	0.00	0.00	10,205.00	73.00	-846.60	11.13	0.00	0.00	0.00
3rd Bone Sp	ring Sand					77.70			
10,300.00	0.00	0.00	10,243.98	73.00	-846.60	11.13	0.00	0.00	0.00
10,400.00	0.00	0.00	10,343.98	73.00	-846.60	77.73	0.00	0.00	0.00
10,500.00	0.00	0.00	10,443.98	73.00	-846.60	77.73	0.00	0.00	0.00
10,600.00	0.00	0.00	10,543.98	73.00	-846.60	77.73	0.00	0.00	0.00
10,610.56	0.00	0.00	10,554.54	73.00	-846.60	77.73	0.00	0.00	0.00
10,625.00	1.73	359.68	10,568.98	73.22	-846.60	77.95	12.00	12.00	0.00
10,635.03	2.94	359.68	10,579.00	73.63	-846.60	78.35	12.00	12.00	0.00
Wolfcamp To	ор								
10,650.00	4.73	359.68	10,593.94	74.63	-846.61	79.36	12.00	12.00	0.00
10,660.11	5.95	359,68	10,604.00	75.57	-846.61	80.30	12.00	12.00	0.00
Wolfcamp X	Sand								
10,675.00	7.73	359.68	10,618.79	77.34	- 846.62	82.07	12.00	12.00	0.00
10,694.98	10.13	359.68	10,638.52	80.44	-846.64	85.17	12.00	12.00	0.00
Start Build 1	2.00								
10,700.00	10.73	359.68	10,643.46	81.35	-846.65	86.08	12.00	12.00	0.00
10,725.00	13.73	359.68	10,667.89	86.65	-846.68	91.38	12.00	12.00	0.00
10,750.00	16.73	359.68	10,692.01	93.22	-846.71	97.94	12.00	12.00	0.00
10,757.32	17.61	359.68	10,699.00	95.38	-846.72	100.11	12.00	12.00	0.00
Wolfcamp Y	Sand								
10,775.00	19.73	359.68	10,715.75	101.04	-846.76	105.77	12.00	12.00	0.00
10,784.86	20.92	359.68	10,725.00	104.46	-846.78	109.19	12.00	12.00	0.00
Wolfcamp A									
10,800.00	22.73	359.68	10,739.05	110.09	-846.81	114.82	12.00	12.00	0.00
10,825.00	25.73	359.68	10,761.84	120.35	-846.86	125.08	12.00	12.00	0.00
10,850.00	28 73	359.68	10,784 07	131.79	-846.93	136.52	12.00	12.00	0.00
10,875.00	31.73	359.68	10,805.67	144.38	-847.00	149.10	12.00	12.00	0.00

Planning Report

Database: Company:	Midland District WPX Energy	Local Co-ordinate Reference: TVD Reference:	Well Tucker Draw Fed 9-4 1H RKB @ 3112.00usft (Orion Aires)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	RKB @ 3112.00usft (Orion Aires)
Site:	Tucker Draw Fed 9-4 Pad	North Reference:	Grid
Well:	Tucker Draw Fed 9-4 1H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #1		

Planned Survey

i

,

\$

Measured			Vertical			Vertical	Dogleg	Build	Turn
(usft)	Inclination (°)	Azimuth (bearing)	(usft)	+N/-5 (usft)	+E/-VV (usft)	(usft)	(°/100usft)	(°/100usft)	(°/100usft)
10.900.00	34,73	359.68	10.826.58	158.08	-847.08	162.80	12.00	12.00	0.00
10,925.00	37.73	359.68	10.846.74	172.85	-847.16	177.58	12.00	12.00	0.00
10,932,97	38.69	359.68	10,853.00	177 78	-847 19	182.51	12.00	12.00	0.00
Wolfcamp /	42	000.00	10,000.00	111.0	0.11.10	102.01	12.00	12.00	0100
10,950.00	40.73	359.68	10,866.10	188.66	-847.25	193.39	12.00	12.00	0.00
10,975.00	43.73	359.68	10,884.61	205.46	-847.34	210.19	12.00	12.00	0.00
11,000.00	46.73	359.68	10,902.21	223.21	-847.44	227.94	12.00	12.00	0.00
11,025.00	49,73	359.68	10,918.87	241.85	-847.54	246.58	12.00	12.00	0.00
11,050.00	52.73	359.68	10,934.52	261.34	-847.65	266.07	12.00	12.00	0.00
11,075,00	55.73	359.68	10.949.13	281.62	-847.76	286.36	12.00	12.00	0.00
11,100.00	58.73	359.68	10,962.66	302.64	-847.88	307.37	12.00	12.00	0.00
11 125.00	61.73	359.68	10.975.07	324.34	-848.00	329.07	12.00	12.00	0.00
11 150 00	64 73	359.68	10,986,33	346.66	-848.13	351.39	12.00	12.00	0.00
11 175 00	67.73	359.68	10,996,40	369 54	-848.26	374 27	12 00	12.00	0.00
11 200 00	70 73	359.68	11 005 26	392.91	-848.39	397 64	12.00	12 00	0.00
11 221 86	73.36	359.68	11,000.20	413 70	-848 50	418.43	12.00	12.00	0.00
Lower WFC	MP A Top Target	000.00	11,012.00	410.70	0 10.00	10.40	12.00	12.00	0.00
11 225 00	73 73	359.68	11 012 89	416 71	-848 52	421 45	12.00	12 00	0.00
11 250 00	76 73	359.68	11 019 26	440.89	-848.65	445.62	12.00	12.00	0.00
11 275 00	79.73	359.68	11 024 36	465.36	-848 79	470.09	12.00	12.00	0.00
11 300 00	82 73	359.68	11 028 17	490.06	-848.93	494 80	12.00	12.00	0.00
11,325,00	85.73	359.68	11 030 68	514 93	-849.07	519.67	12.00	12.00	0.00
11,020.00			11,000.00		0 10.01	0,0.07	.2.00	12.00	0.00
11,350.00	88.73	359.68	11,031.89	539.90	-849.21	544.63	12.00	12.00	0.00
11,354.79	89.31	359.68	11,031.97	544.69	-849.23	549.42	12.00	12.00	0.00
7"									
11,355.16	. 89.35	359,68	11,031.97	545.06	-849.24	549.79	12.00	12.00	0.00
11,357.43	89.35	359.68	11,032.00	547.33	-849.25	552.06	0.00	0.00	0.00
Lower WFC	MP A Landing Pf	t							
11,400.00	89.35	359.68	11,032.48	589.90	-849.49	594.63	0.00	0.00	0.00
11,444.98	89.35	359.68	11,032.99	634.87	-849.74	639.60	0.00	0.00	0.00
Start 7390.3	3 hold at 11445.0	MD							
11,500.00	89.35	359.68	11,033.61	689.89	-850.04	694.62	0.00	0.00	0.00
11,600.00	89.35	359.68	11,034.74	789.88	-850.60	794.62	0.00	0.00	0.00
11,700.00	89.35	359.68	11,035.88	889.87	-851.16	894.61	0.00	0.00	0.00
11,800.00	89.35	359.68	11,037.01	989.86	-851.72	9 9 4.61	0.00	0.00	0.00
11,900.00	89.35	359.68	11,038.14	1,089.86	-852.28	1,094.60	0.00	0.00	0.00
12,000.00	89.35	359.68	11,039.27	1,189.85	-852.84	1,194.59	0.00	0.00	0.00
12,100.00	89.35	359.68	11,040.40	1,289.84	-853,39	1,294.59	0.00	0.00	0.00
12,200.00	89.35	359.68	11,041.53	1,389.83	-853.95	1,394.58	0.00	0.00	0.00
12,300.00	89.35	359.68	11,042.67	1,489.82	-854.51	1,494.57	0.00	0.00	0.00
12,400.00	89.35	359.68	11,043.80	1,589.82	-855.07	1,594.57	0.00	0.00	0.00
12,500,00	89.35	359.68	11.044.93	1.689.81	-855.63	1,694,56	0.00	0.00	0.00
12,600.00	89.35	359.68	11.046.06	1,789,80	-856.19	1,794,55	0.00	0.00	0.00
12,700.00	89.35	359.68	11.047.19	1.889.79	-856.74	1.894.55	0.00	0.00	0.00
12,800.00	89.35	359.68	11,048.32	1,989.78	-857.30	1,994.54	0.00	0.00	0.00
12.900.00	89.35	359.68	11.049.45	2.089.78	-857.86	2,094,53	0.00	0.00	0.00
13 000 00	89.35	359.68	11.050 59	2,189 77	-858 42	2,194,53	0.00	0.00	0.00
13 100 00	89.35	359 68	11 051 72	2 289 76	-858 98	2 204 52	0.00	0.00	n nn
13 125 02	80.35	359 68	11 052 00	2 314 77	-859 12	2 319 5/	0,00 0,00	0.00	0.00
10,120.02	MD A Da To:	000.00	11,002.00	2,017.11	000,12	2,015.04	0.00	0.00	0.00
13,200.00	89.35	359.68	11,052.85	2,389.75	-859.54	2,394.52	0.00	0.00	0.00
13 300 00	80 35	350 68	11 053 99	2 489 74	-860 10	2 404 51	0.00	0.00	0.00
13 400 00	89.35	359.68	11.055 11	2,589 74	-860.65	2,594 50	0.00	0.00	0.00

Planning Report

Planned Survey

e •

	Measured			Vertical			Vertical	Dogleg	Build	Turn
	Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Section	Rate	Rate	Rate
	(usft)	(°)	(bearing)	(usft)	(usft)	(usft)	(usft)	(°/100usft)	(°/100usft)	(°/100usft)
1	13,500.00	89,35	359.68	11.056.24	2,689,73	-861,21	2,694.50	0.00	0.00	0.00
	13,600,00	89.35	359.68	11 057 37	2 789 72	-861 77	2 794 49	0.00	0.00	0.00
1	13 700 00	89.35	359.68	11 058 51	2 889 71	-862.33	2 894 48	0.00	0.00	0.00
	10,100.00	00.00	000.00	11,000.01	2,000.11	002.00	2,004.00	0.00	0.00	0.00
-	13,800.00	89.35	359.68	11,059.64	2,989.70	-862.89	2,994.48	0.00	0.00	0.00
	13,900.00	89.35	359.68	11,060.77	3,089.70	-863.45	3,094.47	0.00	0.00	0.00
	14,000.00	89.35	359.68	11,061.90	3,189.69	-864.00	3,194.46	0.00	0.00	0.00
	14,100.00	89,35	359,68	11,063.03	3,289.68	-864.56	3,294.46	0.00	0.00	0.00
I	14,200.00	89.35	359.68	11,064.16	3,389.67	-865.12	3,394.45	0.00	0.00	0.00
	44 200 00	90.25	250.09	44 065 30	0 400 66	965.09	2 404 45	0.00	0.00	0.00
	14,300.00	69.30	309.00	11,065.30	3,469.00	-000.00	3,494.45	0.00	0.00	0.00
	14,400.00	89.35	359.68	11,066.43	3,589.66	-866.24	3,594.44	0.00	0.00	0.00
1	14,500.00	89.35	359.68	11,067.56	3,689.65	-866.80	3,694.43	0.00	0.00	0.00
4	14,600.00	89.35	359.68	11,068.69	3,789.64	-867.35	3,794.43	0.00	0.00	0.00
1	14,700.00	89.35	359.68	11,069.82	3,889.63	-867.91	3,894.42	0.00	0.00	0.00
1	14.800.00	89.35	359.68	11.070.95	3.989.62	-868.47	3,994,41	0.00	0.00	0.00
1	14 900 00	89.35	359.68	11 072 08	4 089 62	-869.03	4 094 41	0.00	0.00	0.00
	15,000,00	89.35	359.68	11 073 22	1 189 61	-869.59	4 194 40	0.00	0.00	0.00
1	15,000.00	80.35	350.68	11 074 35	4,100,01	-870.15	4,104,40	0.00	0.00	0.00
	15,100.00	09.00	359.00	11.074.33	4,209.00	-070,10	4,294.39	0.00	0.00	0.00
	15,200.00	09.55	359.00	11,070,40	4,309.39	-070.70	4,394.35	0.00	0.00	0.00
	15,300.00	89.35	359.68	11,076.61	4,489.59	-871.26	4,494.38	0.00	0.00	0.00
	15,400.00	89.35	359.68	·11,077,74	4,589.58	-871,82	4,594.37	0.00	0.00	0.00
	15,500.00	89.35	359.68	11.078.87	4.689.57	-872.38	4,694,37	0.00	0.00	0.00
	15 600.00	89.35	359.68	11 080 00	4 789 56	-872 94	4 794 36	0.00	0.00	0.00
	15 700 00	89.35	359.68	11 081 14	4 889 55	-873 50	4 894 36	0.00	0.00	0.00
	10,700.00	00.00	000.00	11,001111	1,000.00	0.000	1,001100	0.00	0.00	0.00
	15,800.00	89.35	359.68	11,082.27	4,989.55	-874.05	4,994.35	0.00	0.00	0.00
	15,900.00	89.35	359.68	11,083.40	5,089.54	-874.61	5,094.34	0.00	0.00	0.00
	16,000.00	89,35	359.68	11,084.53	5,189.53	-875.17	5,194.34	0.00	0.00	0.00
	16,100.00	89.35	359.68	11,085.66	5,289.52	-875.73	5,294.33	0.00	0.00	0.00
	16,200.00	89.35	359.68	11,086.79	5,389.51	-876.29	5,3 9 4.32	0.00	0.00	0.00
i.	16.300.00	89.35	359.68	11.087.92	5.489.51	-876,85	5.494.32	0.00	0.00	0.00
	16 400 00	89.35	359.68	11 089 06	5 589 50	-877 40	5 594 31	0.00	0.00	0.00
	16 500 00	89.35	359.68	11 090 19	5 689 49	-877 96	5 694 30	0.00	0.00	0.00
	16,600,00	89.35	359.68	11 001 32	5 789 48	-878 52	5 794 30	0.00	0.00	0.00
	16 700 00	80.25	250.68	11,007.02	5 990 47	-070.32 970.09	5 804 20	0.00	0.00	0.00
	10,700.00	09.00	555.00	11,032,40	5,005.47	-07 9.00	5,054.25	0.00	0.00	0.00
	16,800.00	89.35	359.68	11,093.58	5,989.47	-879.64	5,994.29	0.00	0.00	0.00
	16,900.00	89.35	359.68	11,094.71	6,089.46	-880.20	6,094.28	0.00	0.00	0.00
	17,000.00	89.35	359.68	11,095.85	6,189.45	-880.75	6,194.27	0.00	0.00	0.00
	17,100.00	89,35	359.68	11,096.98	6,289.44	-881.31	6,294.27	0.00	0.00	0.00
	17,200.00	89.35	359.68	11,098.11	6,389.43	-881.87	6,394.26	0.00	0.00	0.00
	17.300.00	89.35	359.68	11.099.24	6.489.43	-882.43	6,494,25	0.00	0.00	0.00
	17 400 00	89.35	359.68	11 100 37	6 589 42	-882.99	6 594 25	0.00	0.00	0.00
	17 500 00	89.35	359.68	11,101.50	6 689 /1	-883.55	6 694 24	0.00	0.00	0.00
	17,000.00	80.35	350.68	11,107.50	6 780 40	-884 10	6 704 22	0.00	0.00	0.00
	17,000.00	80.35	359.68	11,102.03	6 990 20	-064.10	6 904 22	0.00	0.00	0.00
	17,700.00	09.33	359.00	11,103.77	0,005.35	-064.00	0,054.25	0.00	0.00	0.00
	17,800.00	89.35	359.68	11,104.90	6,989.39	-885.22	6,994.22	0.00	0.00	0.00
	17,900.00	89.35	359.68	11,106.03	7,089.38	-885.78	7,094.21	0.00	0.00	0.00
	18,000.00	89.35	359.68	11,107.16	7,189.37	-886.34	7,194.21	0.00	0.00	0.00
	18,100.00	89.35	359.68	11,108.29	7,289.36	-886.90	7,294.20	0.00	0.00	0.00
	18,200.00	89.35	359.68	11,109.42	7,389.35	-887.45	7,394.20	0.00	0.00	0.00
	18,300.00	89 35	359 68	11,110 55	7,489 35	-888.01	7,494 19	0.00	0.00	0.00
	18,400.00	89.35	359.68	11,111.69	7.589.34	-888.57	7,594.18	0.00	0.00	0.00
	18,500.00	89.35	359.68	11,112,82	7,689,33	-889.13	7.694.18	0.00	0.00	0.00
	18 600 00	89.35	359.68	11 113 95	7 789 32	-880 60	7 794 17	0.00 n nn	0.00 0.00	0.00 0.00
	18 700 00	89.35	359 68	11 115 08	7 889 31	-890.25	7 894 16	0.00	0.00	0.00
	10,700.00	00.00	000.00	11,110.00	7,000.01	000.20	7,007.10		0.00	0.00
	18,781.29	89,35	359.68	11,116.00	7,970.60	-890.70	7,975.45	0.00	0.00	0.00

Planning Report

Database: Company:	Midland District WPX Energy	Local Co-ordinate Reference: TVD Reference:	Well Tucker Draw Fed 9-4 1H RKB @ 3112.00usft (Orion Aires)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	RKB @ 3112.00usft (Orion Aires)
Site:	Tucker Draw Fed 9-4 Pad	North Reference:	Grid
Well:	Tucker Draw Fed 9-4 1H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #1		

Planned Survey

•

4

Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth (usft)	Inclination (°)	Azimuth (bearing)	Depth (usft)	+N/-S (usft)	+E/-W (usft)	Section (usft)	Rate (°/100usft)	Rate (°/100usft)	Rate (°/100usft)

Design Targets

Target Name

- hit/miss target - Shape	Dip Angle (°)	Dip Dir. (bearing	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Tucker DF 1H KOP - plan hits target cer - Point	0.00 hter	0.00	10,554.54	73.00	-846.60	382,005.50	680,202.70	32° 2' 57.915 N	103° 53' 6.451 W
Tucker DF 1H FTP - plan misses target - Point	0.00 center by 0.39	0.00 Jusft at 1138	11,031.97 34.38usft MD	574.28 (11032.30 TVI	-849.20 D, 574.28 N, -	382,506.78 849.40 E)	680,200.10	32° 3' 2.875 N	103° 53' 6.457 W
Tucker DF 1H LTP - plan misses target - Point	0.00 center by 0.98	0.00 Busft at 1868	11,113.90 31.27usft MD	7,870.60 (11114.87 TVI	-890.30 D, 7870.59 N,	389,803.10 -890.14 E)	680,159.00	32° 4' 15.081 N	103° 53' 6.583 W
Tucker DF 1H BHL - plan hits target cer - Point	0.00 nter	0.00	11,116.00	7,970.60	-890.70	389,903.10	680,158.60	32° 4' 16.071 N	103° 53' 6.582 W

Casing Points

Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter ('')	Hole Diameter ('')
1,000.00	1,000.00	13 3/8"	13-3/8	17-1/2
3,587.65	3,571.00	9 5/8"	9-5/8	12-1/4
11,354.79	11,031.97	7"	7	8-3/4
		the second se		

Planning Report

Database:	Midland District	Local Co-ordinate Reference:	Well Tucker Draw Fed 9-4 1H
Company:	WPX Energy	TVD Reference:	RKB @ 3112.00usft (Orion Aires)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	RKB @ 3112.00usft (Orion Aires)
Site:	Tucker Draw Fed 9-4 Pad	North Reference:	Grid
Well:	Tucker Draw Fed 9-4 1H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Plan #1		

Formations

.

.

Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (bearing)	
3,587.65	3,571.00	Bell Canyon (Base of Salt)				
4,668.77	4,642.00	Cherry Canyon				
5,746.86	5,710.00	Brushy Canyon				
7,422.54	7,370.00	Bone Spring				
7,546.70	7,493.00	Avalon				
8,353.02	8,297.00	1st Bone Spring Sand				
8,906.02	8,850.00	2nd Bone Spring Lime				
9,078.02	9,022.00	2nd Bone Spring Sand				
9,537.02	9,481.00	3rd Bone Spring Lime				
10,261.02	10,205.00	3rd Bone Spring Sand				
10,635.03	10,579.00	Wolfcamp Top				
10,660.11	10,604.00	Wolfcamp X Sand				
10,757.32	10,699.00	Wolfcamp Y Sand				
10,784.86	10,725.00	Wolfcamp A				
10,932.97	10,853.00	Wolfcamp A2				
11,221.86	11,012.00	Lower WFCMP A Top Target				
11,357.43	11,032.00	Lower WFCMP A Landing Pt				
13,125.02	11,052.00	Lower WFCMP A Base Target				

Plan Annotations

Measured	Vertical	Local Coor	dinates			
Depth (usft)	Depth (usft)	+N/-S (usft)	+E/-W (usft)	Comment		
1,000.00	1,000.00	0.00	0.00	Start Build 0.50		
1,600.00	1,599.73	1.89	-15.59	Start DLS 1.00 TFO 0.01		
2,087.57	2,084.96	6.26	-61.55	Start 5575.1 hold at 2087.6 MD		
7,662.65	7,607.87	70.72	-819.73	Start Drop -2.00		
8,056.44	8,000.42	73.00	-846.60	Start 2638.5 hold at 8056.4 MD		
10,694.98	10,638.52	80.44	-846.64	Start Build 12.00		
11,444.98	11,032.99	634.87	-849.74	Start 7390.3 hold at 11445.0 MD		
18,781.29	11,116.00	7,970.60	-890.70	TD at 18835.2		

WPX Energy

Eddy County, New Mexico NAD 83 Tucker Draw Fed 9-4 Pad Tucker Draw Fed 9-4 1H API: ??? Wellbore #1 Plan #1

Anticollision Report

30 March, 2017



Scientific Drilling

www.scientificdrilling.com

Azimuths to Grid North True North: -0.24° Magnetic North: 6.69° Magnetic Field Strength: 48029.7snT Dip Angle: 59.78° Date: 3/27/2017 Model: HDGM

,



Anticollision Report

Company:	WPX Energy	Local Co-ordinate Reference:	Well Tucker Draw Fed 9-4 1H
Project:	Eddy County, New Mexico NAD 83	TVD Reference:	RKB @ 3112.00usft (Orion Aires)
Reference Site:	Tucker Draw Fed 9-4 Pad	MD Reference:	RKB @ 3112.00usft (Orion Aires)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Tucker Draw Fed 9-4 1H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	Midland District
Reference Design:	Plan #1	Offset TVD Reference:	Offset Datum
Reference	Plan #1		
Filter type:	NO GLOBAL FILTER: Using user defined	selection & filtering criteria	
Interpolation Method:	MD Interval 100 00usft	Error Model:	ISCWSA

interpolation wetho	u. ND men	val 100.0003it	Life would.	1001107	
Depth Range:	Unlimited	1	Scan Method:	Closest Approach 3D	
Results Limited by:	Maximum	n center-center distance of 9,999.98 usft	Error Surface:	Elliptical Conic	
Warning Levels Eva	luated at:	2.00 Sigma	Casing Method:	Not applied	
Survey Tool Program	n	Date 3/30/2017			
From	То				
(usft)	(usft)	Survey (Wellbore)	Tool Name	Description	
0.00	18,781.29	Plan #1 (Wellbore #1)	MWD+HDGM	OWSG MWD + HDGM	

Summary

.

.

	Reference	Offset	Dista	nce		
	Measured	Measured	Between	Between	Separation	Warning
Site Name	Depth	Depth	Centres	Ellipses	Factor	
Offset Well - Wellbore - Design	(usft)	(usft)	(usft)	(usft)		
Tucker Draw Fed 9-4 Pad						
RDX 16-10H - Wellbore #1 - Actual	5,669.77	5,615.19	239.77	198.60	5.824 CC	
RDX 16-10H - Wellbore #1 - Actual	5,700.00	5,644.90	239.82	198.42	5.793 ES	
RDX 16-10H - Wellbore #1 - Actual	6,000.00	5,940.35	246.14	202.48	5.638 SF	
RDX 16-14H - Wellbore #1 - Actual	7,660.84	7,440.83	1,369.22	1,315.20	25.345 CC	
RDX 16-14H - Wellbore #1 - Actual	7,700.00	7,466.00	1,369.30	1,315.00	25.214 ES	
RDX 16-14H - Wellbore #1 - Actual	7,900.00	7,561.00	1,389.33	1,333.69	24.970 SF	
RDX 16-4 - Wellbore #1 - Actual	1,000.00	985.00	479.54	456.47	20.791 CC	
RDX 16-4 - Wellbore #1 - Actual	1,300.00	1,284.97	483.46	453.37	16.064 ES	
RDX 16-4 - Wellbore #1 - Actual	7,600.00	7,524.00	1,292,92	1,116.43	7.325 SF	
RDX 9-4H - Welibore #1 - Actual	7,641.42	7,550.00	1,164.53	984.19	6.458 CC,	ES
RDX 9-4H - Welibore #1 - Actual	7,700.00	7,550.00	1,165.98	985.40	6.457 SF	
Tucker Draw Fed 9-4 2H - Wellbore #1 - Plan #1	1,000.00	1,001.00	25.00	18.27	3.714 CC	
Tucker Draw Fed 9-4 2H - Wellbore #1 - Plan #1	1,100.00	1,101.00	25.43	17.99	3.418 ES	
Tucker Draw Fed 9-4 2H - Wellbore #1 - Plan #1	5,800.00	5,806.20	70.16	28.56	1.686 SF	
Tucker Draw Fed 9-4 3H - Wellbore #1 - Plan #1	1,000.00	1,002.00	50.00	43.26	7.423 CC	
Tucker Draw Fed 9-4 3H - Wellbore #1 - Plan #1	1,100.00	1,102.00	50.43	42.99	6.774 ES	
Tucker Draw Fed 9-4 3H - Wellbore #1 - Plan #1	18,781.29	18,779,30	660.07	417.42	2.720 SF	

Offset De	sign	Tucker	Draw Fed	9-4 Pad - F	RDX 16-1	0H - Wellbo	re #1 - Actual						Offset Site Error:	0.00 usft
Survey Prog	ram: 100	-MWD											Offset Well Error:	0.00 usft
Refer	ence	Offs	et	Semi Major	Axis				Dista	ance				
Measured	Vertical	Measured	Vertical	Reference	Offset	Highside	Offset Wellbo	re Centre	Between	Between	Minimum	Separation	Warning	
Depth	Depth	Depth	Depth			Toolface	+N/-S	+E/-W	Centres	Ellipses	Separation	Factor		
(usft)	(usft)	(usft)	(usft)	(usft)	(usft)	(")	(usft)	(usft)	(usft)	(usft)	(usft)			
0.00	0.00	0.00	0.00	0.00	0.00	-97.41	-84.09	-646.14	651.84					
100.00	100.00	78.26	78.26	0.14	0.14	-97.41	-84.11	-646.36	651.82	651.55	0.28	2,340.960		
200.00	200,00	176.98	176.98	0.50	0.46	-97.42	-84.22	-647.08	652.55	651.60	0,95	685.464		
300.00	300.00	279.35	279.34	0.85	0.82	-97.45	-84.64	-647.68	653,19	651.51	1,67	390.221		
400.00	400.00	383.46	383.45	1.21	1,18	-97.55	-85.80	-647.63	653,30	650,90	2.40	272.470		
500.00	500.00	485.55	485,52	1.57	1.54	-97.69	-87.36	-647.01	652.89	649.77	3.11	209.682		
600.00	600.00	586.67	586.63	1.93	1.90	-97,83	-88.84	-646.16	652.26	648.43	3.83	170.402		
700.00	700.00	688.87	688.81	2,29	2.26	-97.96	-90.23	-645.08	651.39	646.84	4.55	143.273		
800.00	800.00	795.22	795.14	2.65	2.64	-98.11	-91.65	-643.26	649.89	644.61	5.28	123.092		
900.00	900.00	897.61	897.49	3.01	3.00	-98.26	-92.97	-640,77	647.67	641.67	6.00	107.964		
1,000.00	1,000.00	989.81	989.66	3.36	3.33	-98.38	-94.07	-638.93	645.86	639.18	6.68	96.626		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WPX Energy	Loca
Project:	Eddy County, New Mexico NAD 83	TVD
Reference Site:	Tucker Draw Fed 9-4 Pad	MD F
Site Error:	0.00 usft	Nort
Reference Well:	Tucker Draw Fed 9-4 1H	Surv
Well Error:	0.00 usft	Outp
Reference Wellbore	Wellbore #1	Data
Reference Design:	Plan #1	Offs

Local Co-ordinate Reference: TVD Reference: MD Reference: North Reference: Survey Calculation Method: Output errors are at Database: Offset TVD Reference: Well Tucker Draw Fed 9-4 1H RKB @ 3112.00usft (Orion Aires) RKB @ 3112.00usft (Orion Aires) Grid Minimum Curvature 2.00 sigma Midland District Offset Datum

Reference Depths are relative to RKB @ 3112.00usft (Orion Aires) Offset Depths are relative to Offset Datum Central Meridian is 104° 20' 0.000 W Coordinates are relative to: Tucker Draw Fed 9-4 1H Coordinate System is US State Plane 1983, New Mexico Eastern Zone Grid Convergence at Surface is: 0.24°



CC - Min centre to center distance or covergent point, SF - min separation factor. ES - min ellipse separation

Anticollision Report

WPX Energy	Local Co-ordinate Reference:
Eddy County, New Mexico NAD 83	TVD Reference:
Tucker Draw Fed 9-4 Pad	MD Reference:
0.00 usft	North Reference:
Tucker Draw Fed 9-4 1H	Survey Calculation Method:
0.00 usft	Output errors are at
Wellbore #1	Database:
Plan #1	Offset TVD Reference:
	WPX Energy Eddy County, New Mexico NAD 83 Tucker Draw Fed 9-4 Pad 0.00 usft Tucker Draw Fed 9-4 1H 0.00 usft Wellbore #1 Plan #1

Well Tucker Draw Fed 9-4 1H RKB @ 3112.00usft (Orion Aires) RKB @ 3112.00usft (Orion Aires) Grid Minimum Curvature 2.00 sigma Midland District Offset Datum

Reference Depths are relative to RKB @ 3112.00usft (Orion Aires) Offset Depths are relative to Offset Datum Central Meridian is 104° 20' 0.000 W Coordinates are relative to: Tucker Draw Fed 9-4 1H Coordinate System is US State Plane 1983, New Mexico Eastern Zone Grid Convergence at Surface is: 0.24°



RKI Exploration & Production, LLC.

Drilling Plan

 Well
 Tucker Draw Fed COM 9-4 1H

 Location
 Surface: 250 FNL 1463 FEL, Sec 16

 Bottom Hole:
 2410 FSL 2310 FEL Sec 4

 County/State
 Eddy, NM

T26S R30E S16 T26S R30E S04

The elevation of the unprepared ground is

3,089 feet above sea level.

The geologic name of the surface formation is

Quaternary - Alluvium

A rotary rig will be utilized to drill the well to 18781' MD, then will be cased and cemented. This equipment will then be rigged down and the well will be completed with a workover rig.

Proposed depth is 18,781 feet MD.

1) Estimated Tops:

Formation Name	MD	TVD	Bearing	BHP (psi)	MASP (psi)
Quaternary - Alluvium	GL	GL	Water		
Bell Canyon Sand (Base Salt)	3,588	3,571	Oil/Gas		
Cherry Canyon Sand	4,669	4,642	Oil/Gas		
Brushy Canyon Sand	5,747	5,710	Oil/Gas		
1st Bone Spring Sand	8,353	8,297	Oil/Gas		
2nd Bone Spring Sand	9,078	9,022	Oil/Gas		
3rd Bone Spring Sand	10,261	10,205	Oil/Gas		
KOP	10,611	10,555			
Wolfcamp	10,635	10,579	Oil/Gas		
Landing Point (Wolfcamp)	11,355	11,032	Target Frm		
TD	18,781	11,116	Oil/Gas	6,884	4,438

2) Notable Formations:

Any usable fresh water zones encountered will be adequately protected and reported. All usable water zones, potential hydrocarbon zones, and valuable mineral zones will be isolated.

Useable water will be protected by surface casing set and cemented to surface.

3) Pressure Control Equipment:

The blowout preventer equipment (BOPE) will consist of 3 rams (10,000 psi WP) with 2 pipe rams (one of which may be variable), 1 blind ram and 1 annular preventer (5,000 psi WP) will be installed. The BOPE will be used below surface casing to TD. See attachments for BOP and choke manifold diagrams. A rotating head will be installed as needed. Units will be hydraulically operated.

An accumulator that meets the requirements of Onshore Order 2 for the pressure rating of the BOP stack will be present.

BOPE will be inspected and operated as recommended in Onshore Order 2. A third party company will test the BOPE. After surface casing is set and the BOPE is nippled up, pressure tests will be conducted to 250 psi low and 5000 psi high (50% of WP) with the annular tested to 250 psi low and 2500 psi high (50% of WP).

A 20" x 13-3/8" x 9-5/8" x 7" 10M multi-bowl wellhead w/ 9-5/8" and 7" mandrel hangers will be install after setting surface casing and utilized until total depth is reached. The 9-5/8" and 7" casings will be set using a mandrel in the casing head and the stack will not be retested at these casing points.

The following BOPE will be installed, tested and operational:

- Drilling spool or blowout preventer with two (2) side outlets;
 - · Choke line side shall be 3" minimum diameter;
 - Two (2) adjustable chokes with one (1) remotely controlled from the rig floor and pressure gauge.
 - · Kill side shall be at least 2" diameter;
 - Two (2) manual valves and one (1) check valve.

Auxiliary equipment is as follows:

- · Upper kelly cock valve with a handle available;
- Lower kelly cock valve with a handle available;
- A float valve will be used in the drill string, either in a float sub or in the mud motor;



• Safety valves and subs with a full opening sized to fit all drill strings and collars will be available on the rig floor in the open position.

RKI Exploration & Production, LLC. requests a variance to drill this well using a co-flex line between the BOP and the choke manifold. Certification for proposed co-flex hose is attached. The hose is required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be

4) Casing Program:

Section	Hole Size	Top (MD)	Bottom (MD)	Bottom (TVD)	Casing OD	Weight (ppf)	Grade	Threads
Surf	17-1/2"	0	900	900	13-3/8"	54.5	J-55	ST&C
Int_1	12-1/4"	Ō	3,588	3,571	9-5/8"	40.0	J-55	LT&C
Int_2	8-3/4"	0	11,355	11,032	7"	29.0	HCP-110	BT&C
Prod	6-1/8"	10,611	18,781	11,116	4-1/2"	13.5	HCP-110	CDC-HTC

Safety Factors				
Collapse	1.125			
Burst	1.000			
Tension	1.600			

Design Factors								
Section	Collapse	Burst	Tension					
Surf	2.85	13.79	10.48					
Int_1	1.64	5.03	3.62					
Int_2	1.90	4.62	2.90					
Prod	2.18	5.07	1.75					

Centralizers will be run as follows:

• One (1) centralizer on each of the bottom three jts of casing beginning with the shoe jt;

• One (1) centralizer every third jt from above bottom three jts to planned top of cement (TOC).

5) Cement Program:

Section	Hole Size	Casing OD	Cap _{Ann} (cuft/ft)					
Surf	17.50	13.375	0.6946					
Туре	Cmt Btm	Cmt Top	Cubic Feet	Yield	Excess	Sacks	Weight	Blend & Additives
Lead	643	0	447	1.74	50%	385	13.5	Class C + 4% Gel + 2% CaCl + 0.4 pps Defoamer + 0.125 pps CelloFlake
Tail	900	643	134	1.34	50%	200	14.8	Class C + 2% Calcium

Section	Hole Size	Casing OD	Cap _{Ann} (cuft/ft)	Prev Csg ID	Cap _{Csg-Csg} (cuft/ft)				
Int_1	12.25	9.625	0.3132	12.615	0.3627				
Туре	Cmt Btm	Cmt Top	Cubic Feet	Yield	Excess	Sacks	Weight	Blend & Additives	
Lood	900	0	326	1.00	326	0%	564	12.0	Class C/Poz 35/65 + 5% Salt + 6% Gel + 0.5% Retarder + 3 pps
Leau	2914	900	631	1.52	20%		12.5	LCM + 0.4 pps Defoamer + 0.125 pps CelloFlake	
Tail	3588	2914	211	1.32	20%	200	14.8	Class C	

Section	Hole Size	Casing OD	Cap _{Ann} (cuft/ft)	Prev Csg ID	Cap _{Csg-Csg} (cuft/ft)					
Int_2	8.75	7.00	0.1503	8.835	0.1585					
Туре	Cmt Btm	Cmt Top	Cubic Feet	Yield	Excess	Sacks	Weight	Blend & Additives		
Lead	3588	3088	79	0.07	2.67	2.67	0%	504	11.2	TXI Lightweight + 10% Gel + 8% Plex Crete + 0.9% Retarder + 0.7
Leau	10611	3588	1056	2.07	20%		11.2	pps FL + 3 pps LCM + 0.4 pps Defoamer + 0.125 pps CelloFlake		
Tail	11355	10611	112	1.18	20%	114	15.6	Class H + 0.3% Retarder		

Section Prod	Hole Size	Casing OD 4,50	Cap _{Ann} (cuft/ft) 0.0942	Prev Csg ID 6.184	Cap _{Csg-Csg} (cuft/ft) 0.0981			
Туре	Cmt Btm	Cmt Top	Cubic Feet	Yield	Excess	Sacks	Weight	Blend & Additives
Tail	11355	10611	73	1 80	0%	483	13.0	Acid Soluble TXI + 1,3% Sall + 30% CaCI + 5% Plexaid + 0,7% FL
1 811	18781	11355	699	1.09	20%	+03	13.0	+ 0.3% Retarder + 0.1% Antisettling + 0.4 pps Defoamer

6) Drilling Fluids Program:

,

An electronic mud monitoring system satisfying the requirements of Onshore Order 1 will be used. All necessary mud products for weight addition and fluid loss control will be on location at all times. Mud program is subject to change due to hole conditions.

Section	Hole Size	TMD	Mud Wt.	Vis	PV	YP	Fluid Loss	Туре
Surf	17-1/2"	900	8.5 to 8.9	32 to 36	1 - 6	1 - 6	NC	Fresh Wtr
Int_1	12-1/4"	3,588	9.8 to 10.0	28 to 30	1 - 3	1-3	NC	Brine
1nt_2	8-3/4"	11,355	8.9 to 9.4	28 to 36	1 - 3	1-3	NC	Cut Brine
Prod	6-1/8"	18,781	10.5 to 12.0	50 to 55	20-22	8 - 10	8 - 10	OBM

Mud checks will be performed every 24 hours.

The following mud system monitoring equipment will be in place during drilling:

· Visual pit markers

• Pit volume totalizer (PVT)

Stroke counter

Gas detection

• Mud-gas separator (gas buster)

· Flow sensor

A closed-loop system will be in place during all phases of drilling. Cuttings disposal will be at an off-site disposal facility.

7) Formation Evaluation Program:

No core or drill stem test is planned.

A 2-person mud-logging program will be used from Int_1 9-5/8" casing point to TD.

No electronic logs are planned.

8) Abnormal Conditions:

No abnormal pressure or temperature is expected.

Maximum expected bottom hole pressure is 6884 psi at 11116' TVD. Expected bottom hole temperature is <200°F.

In accordance with Onshore Order 6, RKI Exploration & Production, LLC does not anticipate that there will be enough H2S to meet the BLM's minimum requirements for the submission of an "H2S Drilling Operation Plan" or "Public Protection Plan" for the drilling and completion of this well. However, since RKI Exploration & Production, LLC has an H2S safety package on all wells, an "H2S Drilling Operations Plan" is attached.

Adequate flare lines will be installed off the mud/gas separator where gas may be flared safely.

All personnel will be familiar with all aspects of safe operation of equipment being used.

9) Other Information

The anticipated spud date is upon approval. Expected duration is 30 days to drill the well.





System Drawing

. .

INFORMATION CONTAINED HEREINIS THE FROPERTY OF CAOTOS VIELLHEAD, LLC, REFRODUCTION DISCUSSURE, OR USE THEREOFIC PERMISSIELE ONLY AS FROM DED BY CONTRACT OR AS EXPRESSLY AUTHOR ZED BY CAOTUS INFELHEAD, LLC



Bill of Materials

82

.

--

35

. •

.

= al

Page 2

WFORMATION CONTINNED HEREINIS THE PROPERTY OF CACTUS WELLHEAD LLC. REPRODUCTION DISCUSSURE, OF USE THERE DATIS FERMISSIELE ONLY AS PROVIDED BY CONTRACTOR AS EXPRESSIVAUTHOR, LED BY CACTUS WELL-FROM LC

١Ô

fur

<u>.</u>

•C3

er:

ł۳P

23

H6

Wellhead

NECELL	ATION CONT	NNEDHERE	IN IS THEFR	CFERTY OF	FQAOTUS VI	ELPENCIUS	REFROQUCTIO	N, ERSOLOGURE,
CR USE!	THEREOFIS	PERMELIE.	E CALMAS A	ROMDED	BY CONTRAC	OT OR AS EXP	RESSLYAUTHOR	CED BY CACTUS.
∆E∺E	AD IIC							

MBU-ST HOUSING ASSEMELY		MEL	AT -OUS NO ASSEMBLY		TU	ENG - EAD ASSEMBLY	
		Long Court	10 ° 20	179. IX	1 r	<u>_l</u> ;	uara, șt. s
41	5	Hereining and Marchan Tarker Might Sector and Write Distance (2017) - Michael Andreas Larger and Marchael Marchael Angel Amina Angel Radio (2017)	2 · 2 ·	 Being Hangen (AV, Merika A) Suint (1985); A Missler (1995); Use and the Annual State (1995); A merika better (1997); A 2014 (1996); Annual Complete (1997); Annual Complete (1996); 	7	•	Let a series of the series of
۵.	ï	NAC 22 DATE 1985 Sheep Natio Bridtan Kataliku	• ۋ-ھ	Palan var – Galar – Mr2 – An Marstan († 1955) – Karlina († 1981) Marstan († 1997) – Andrea († 1981)			en e
e.,		u – par un histoga – u+ChhaileM 2011 – presugari – Altas in Ma⊂ruta 2012 – presugari – Altas in Ma⊂ruta 2014 – particularita		- per lipit (* 500 mars) gangaran Gipangaran Gipangaran			N/W Proged in L. (44) opportune (1997) - EAS (46) opeople (1997) 2016/00/2011 2016/00/2011
4.5	1	n on an ann an Anna an Anna an Anna an		 Constant of the second s		2	All Netro Committe Control (C. M. 2 C. Mgu et 1912) A Muniter - Court Secure Ng Kalang Secure
ين الأ	ì	tkonstrutt in tatterant unvg. Konstraatienten		್ಯಾತ್ರಿ ಹೋಗಿ ಕಾರ್ಯ ಕ್ರಮಕ್ರಿ ಹೊಗ್ಗಳು ಕ್ರಮಕ್ರಿ ಮಾತ್ರಿ ಮಾತ್ರಿ ಕಾರ್ಯಕ್ರಿ ಕಾರ್ಯಕ್ರಿ	4		n dan ginapitetete van een naam fan Nei on angelekse op een al filler op dit
40	ĩ	Bodi, Malvin, Markinski, A. (1998) Budy, J. R. (1999) Structure and Alexic construction product data and the second and the second second second second and the second		(a) For the second s		4	eng casks the tatent The Statester
c.,		serie Fallefetti Late source source 2-13t		an a	a.	3•	సాహార్క్ కారణాలో 345 గాయాల రాజాల మార్లానికి సౌకర్యాల ఎగజ్ అంగాల
		SFM Tenged and the Anton Standors AACO-BE Th Page 2012 - AACO-BE Th Page 2013 - State Fage 441-00					laneste varie Mira rrichtich timeste varie Mira rrichtich timetettia
4.7	•	Algeria – Store Borne (Ma) Brigge Pistra fulfactor para Store Fat⊛n 1855			.	•	neessa on tao aga na tao Anton Na tao aga antona ang ang ang Na tao ang aga
<u>م.</u>	:	اف دراني الدينية المعلمين الي 1999 بروافع المراجعة الإيلام				•	na grivaakki privinsi 824 ti' DM Sistik prvin
÷.,)e	talan a shikaadarka Sreataba Marka biya battiriyag sa tam Karka a biya battiriyag sa tam			Ċ	••	S Laboration national data data data Pransi Sabisti a Suatri ingi Pransi Ni≣atri at
<u>م</u>	•	Pdar yr ymenod under Coar tiff 1911 - Afrig ar nwr Arst 1911 - F					
 7387247	625×27 0			Rent State Control State Stat	L L	1.182 (M. 1	er jäättessä aitoita soitaan soitaan soitaa soit
_y	<u>'C</u> w	actus :	201 х 13-3 Мал	AS1 x 9-5/81 x 71 10M MBU dret Hanger & CTH-DBLHF	-ST V/6 PS Tub	ellhe: Ing i	ad With 7° - IP 6487 Head - Page 3



• •

IP 6487 Page 3

INFORMATION CONTAINED HEREINIS THE PROPERTY OF CACTUS WELLHEAD LLC. REPRODUCTION, DISCUSSURE OR USE THEREOF IS PERMISSIELE ONLY AS FROM IDED BY CONTRACT OR AS EXPRESSLY AUTHOR ZED BY CACTUS WELLHEAD LLC.

.

DRILLING HOUSING ASSEMBLY	RECOMMENDED SERVICE TOOLS	RECOMMENDED SERVICE TOOLS		
here where the second second	ver hauth i feel calebra	terr rate - Lana pê un		
 The second and the seco	Schleit, R. L. Levin, J., Marchard, M. Housen, J. Mindukk, I. Skutter, S. Statulovic, J. Share, A. Hauda, J. Hauda, M. Harabar, S. 194, 2010, L. Base, Sec. Net. 199, 24, 111 (2014).	5. 11. 1. Weigen Breit C.W. Das rug Hanger Martulausterfühlsburger die 44-100 im 16 fahren Buter die seine Franzöhlter die seine Franzöhlter		
 Andreas Factorial and a second approximation of the second approximation	(c) Conduct Quarters Quarters (a) Conduct and APAC Conduct (c) APAC APAC Conduct (c) APAC Conduct (c) Conduct (c) APAC CONDUCT	(a) 1. The part is the response of the set 198-bit of the the set of the set Automotion of the set of the set of the set of the set of the set is the set of the set of the set of the set of the set of the set of the set of the set of the set of the set of the set of the set of the set of the set of the set of the set of the set of the s		
 Los partes 142 de la La Colla de Co	ರ್ಶನ್ 1 White ಬಿಡುಗಿದ್ದ ಗಳಲ್ಲಿ ಗಳಲ್ಲಿ ಕೆಗ ಗಳಲ್ಲಿ ಕೆಲ್ಲರ್ ಹಿಂಗಿ ಕೇಂದ್ರ ಮಂಗ್ರೆ ಕೊಟ್ಟರ್ ಅವರ 1 ಹಿಂದಿ ನಂಗ್ರೆ ಬಿಡುಗಳು ನಂಗ್ರೆ ಬಿಡುಗಳು	стенат Спр. 1 перии – П. Молистен 1345 г. и 4000 – Ст. – Сил 1540 г. и 4000 – Ст. – Сил		
 Construction of the construction of the construction	reserves reserves no de la serves de la serves de la serves	12 1 1 3364 Kg		
 Bola Program Bola Program Bola Program Bola Program Bola Program 	ಕೆ ಸಿಲ್ಲೆ ಸ್ಥಾನಗಳು ಸಂಘಟನೆಯಲ್ಲಿ ಸೇರಿಸಿದ್ ಕಾರ್ಯವರ್ಷ್ ಸಂಘಟನೆ ಸೇರಿಸಿಕೆ ಬಿಡಿದಿಗಳು ಸಂಪ ಗಳ ಭಾಗದಿಗಳು ಸಿತಿರಿಕೆ ಸಂಗ್ರಾಹಿ	 Marchard Landson, Carlo Carlo Control Marchard Landson, Carlo Carlos Antonesco Marchard Landson, Jack Karlov, Carlo Marchard Landson, Jack Karlov, Carlo Marchard Landson, Jack Carlo Marchard Landson, San Carlo Mar		
 E E Ergig gesterer versund man 112* 1121 - ab min tramelister e an #31 - unt 	5. F. Corpus Constant of Weinsteining here generation assessment for the constant resource of a processing of the British rule of the constant of the Statistical States.	ing the product of the sector of the production of the sector of the sector of the sector of the sector of the sector		
l a Prglakko(thr Nither U For≢bitti	in the second part of the second s	ార్ సినిమాలు సంగార్ సినిమాలు బిరియా సినిమాలు సంగా బిరిమాలు గ్రామాలు బిరిమాలు సినిమాలు		
 E. B. Hauds (2) through with Weillian Law beam weils Set Mining (2011) – big the register 	1. Construction of the contract of the second se	n an e succes ante 1 - Vera buento y dVa Modeste d dans trateste d'Estri Era Thistory a algunatio tariation		
 Build subscene strates in the part MM Explosite protots 	polini i Savanite Asian nego provo viste Monover vinne i tekste neevood	ስ ሽና ለማግኘት ይገኘ በላላ በራ ሽና ውስ ሽና የውስ ላይ		
 But and constants Mr. 4427, Add ST M. W. Constant State Agency (Constant) - add Agency (Constant) - add Agency (Constant) - add Agency (Consthor) - add Agenc	with TTLEOF 4 Math Aurea Louis the part of the Taurie AugUst Tauries sending with being block of the EATTLEOF	(a) The second secon		
	an Bartan ang ang ang ang Mangang ang ang ang Ting ang Suit ang ang ang ang ang ang Ting ang ang ang ang ang ang ang ang ang a	international destructions of the second construction of the second construction of the second construction of the second		
	2. B. M. Marta, Judda G. Martaka Alexandrov medical confection and the confection of a field of the confection and the confection of the confection of a field of the confection.	(1) The range of the shared the set up to the second range of the set of the time.		
	273 ಕೆ. ಬಹುಗೂ ಕೆಗ್ರೋ ಬಳಗ್ರ ಗಳು ಸಿಸಿ 1966 ಕೇವರಿ ಸಂಸರ್ಶಿತೆ, ನಿರಿತ ಮುಗೋಗಿಕ್ ಕೇವರಿ ಬರುಗಿ ಸಿರಿತಿಗಳು ಗಳು ಬರುವರು ಕ್ರೋಗಿಗೆ ದಿರಿಕ ಗ ಬರಗಳ ನಗರಗಾನ ಕೇವರಿಗಳು ಕಿರ್ದಾರ್ಶಕ ಕೇವರಿಗಳು ಸಿರ್ವಾ ಗೇವರಿ ಗೆಗಳು			

IP 0487 Page 4

. .

WPX Energy 20" x 13-3/6" x 5-5/6" x 7" 10M MBU-3T Weilhead With 7" Mandrei Hanger & CTH-DBLHP\$ Tubing Head



INFORMATION CONTAINED HERBINIS THE PROPERTY OF CAOTLIS WELLHEAD LLC. REPRODUCTION DISCLOSURE OR USE THEREOF IS PERMISSIBLE ONLY AS PROVIDED BY CONTRACT OR AS EXPRESSLY AUTHOR CED BY CAOTLIS WELLHEAD LLC

	EMERGENCY EQUIPMENT
··· -	une diterate sukarta
.4	naen gi Harigan (1997) Marian 12en tin jarahari Nera kanak ante Strana
£* ::.	 (a) - (b) (b) (b) (b) (b) (b) (b) (b) (b) (b)
,≃*4t	ان المراجع بين المراجع المراجع المراجع و المراجع و المراجع المراجع المراجع و المراجع و المراجع و المراجع و الم المراجع المراجع المراجع المراجع و المراجع
a*1.:	assure USA Morden sola Belabilitata prove estas 1016 Contrabilitata prove estas 1016 A solaritata estas estas anti- casa de solaritata estas activadas contrabilitata estas activadas contrabilitatas estas activadas contrabilitatas
<u>ب</u> ه، ع	- ಕಾಲ್ಯ ಭಾರ್ಶನ ನಿಂದು ಬಂದು ಬರುವಿದ್ದರು ಗಿಟ್ಟಾಡ 155 ಕೇಂದ್ರಿಸಿದ್ದು ಪ್ರತಿಕಾರಿದೆ. ನಿರ್ಣಾಭವ 365 ಕೇಂದ್ರಿಸಿ ನಾಗಾದ್ರನ್ನು ಕ್ಷಣ ಸ್ಥಾನ 15 ಕೆಂದು ಕೇಂದ್ರಿಸಿ ನಿರ್ಣ ನಿರ್ಣಾಭವಾಗಿ ಮಾಡಿದ್ದರು. ನೇಂದ್ರ ಮಾಡಿ 325 ನಿರ್ಧಾನಿ 25 ಕೆಂದು ನೇಂದ್ರ ಮಾಡಿ 325 ನಿರ್ಧಾನಿ 25 ಕೆಂದು ನೇಂದ್ರ ಮಾಡಿ 325

. .



WPX Energy 201 x 13-3/81 x 9-5/81 x 71 10M MBU-3T Wellhead With 71 Mandrei Hanger & CTH-D6LHPS Tubing Head

IP 0487 Page 5



Operating and Maintenance Plan:

During drilling operations, third party services companies will utilize solids control euipment to remove cuttings from drilling fluids and collect it in haul-off bins. Euipment will be closely monitored at all times while drilling by the derrick man and the service company empolyees.

Closure Plan:

During the drilling operations, third party service companies will haul off drill solids and fluids to an approved disposal facility. At the end of the well, all closed loop equipment will be removed from the location.



.

GATES E & S NORTH AMERICA, INC DU-TEX 134 44TH STREET CORPUS CHRISTI, TEXAS 78405
 PHONE:
 361-887-9807

 FAX:
 361-887-0812

 EMAIL:
 WEB:
 www.gates.com

.

10K CHOKE & KILL ASSEMBLY PRESSURE TEST CERTIFICATE

Castonier	URION DRILLING COMPANY	Test Date:	9/2/2014	
Customer Ref.	stomer Ref. PENEING		D-090214+4	
Invoice No.	2035(0)	Created By:	IDSTIN CROPPER	
r	handa'n an 'daar ar			
Product Description:		10X3 D25-00 < 1,)/1610×9LGE	/E	
Product Description:	4 1/36 'DK ELG	10X3 025.0F<1,1/1610<4LGE	/E	
Product Descriptions	4 1/16 :0K FLG	1083 025.00 < 1.1/1610×*LGE	/E 4 1/16 10K PLG	
Product Description:	4 1/16 :DK FLG 4773-4291	10X3 D25.0CK1,5/1630KFLGE End Fitting 7 Assembly Code	/E 4 1/16 10K PLG L33078040913D-090214-1	

Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agroyment/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 15,000 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

	<i>f </i>		. When the star of the same
Quolity Manager Date : 5 Induce	QUALITY 9/2/201477 10 10 10 10 10 10 10 10 10 10 10 10 10	Technical Supervice Octe Signician	Form PIC OI Bey, 0 i



Gates E&S North America 134 - 44th St. CORPUS CHRISTI, TEXAS 784DS PHONE : (361) 887-9807 FAX: (361) 887-0812

CERTIFICATE OF CONFORMANCE

This is to verify that all Parts and/or Materials included in this shipment have been manufactured and/or processed in Conformance with applicable drawings and specifications, and that Records of Required Tests are on file and subject to examination. The following items were assumbled at Gates E & S, Inc. (formerly Outex, Inc.), facilities in Corpus Christi, TX, USA. This has assembly was designed and manufactured to meet all the requirements of API Spec 7K.

CUSTOMER: ORION DRILLING COMPANY CUSTOMERS P.O.#: HERDING PART DESCRIPTION: 10<3.025.0CK4.3/1610KFLGE/E SALES ORDER #: 203508 QUANTITY: 1 SERIAL #: D-090214-4

Nino SIGNATURE: QUALITY/ TITLE: 9/2/2014 DATE:




.

(USS) (U. S. Stell, Tales at Products)

1. ×

1 1 1 - 11 Stells - 9,291 Photo HC

USS-CDC HTQ
กระหว่าสายเพ

		4-1-41.	たいうれいておけい	
	NECHANICAL FROM ATES			
	Manunum Yield Strength	110,000		ובע
	Musimum Y exit Strength	140,000		D St
	Modinarii Tizo di e Strength	125,000		
	EVINEENESICIALS			
	Outside Orameter	4.500	5.20C	•0
L	No Hickhes	J.290		эп.́
	or or 1 invotor	3 970	в ч. с	10
a	To P API	5 795	3 795	Ú.
	Nominal Unitar Weight, TAC	13.50		地址的
•	といれ名(にかい)また	13.05		100 F
	SECTION AREA			
į.	Crass Short Seal Area - Cotical Area	3.636	38.6	13 10
1	. < ∓1* γ		100 0	:
	PERFORMANCE			
	11 nim un aparié lesture	31 BJC	11 810	<u>ب</u> هم .
	wer of Period of Lee Reportance		¥ 458	,c i
	Mana ad Mala Poe	12,425	12 420	
	Molarium, Pipe Body Yield Streagth	122,000		1215
	22 Clarength		: 5.020	ibs.
	Taero kristi se Barling		N 331	101
	Refrier 100 gtor		71877	4
	Maximum response for all Batteric		70. 6	$\{\psi_{ij}\}_{i\in I} \in \mathcal{T}_{ij}$
,	MARE-UP DATA		같은 것	
	Make Collars		4,94	10
	Minimum Make Up Targ. :		7.030	÷ (cs
	Million an Afrika up Terera		13 002	*1 (too
	non-este i Milled Terigius		23.0	71 71
	the second se	E e e s	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	

2. The second protocol spectral protocol spectral protocol spectral protocol spectral action of the second protocol spectral protocol s

1. G. Street January Promotors	7.67 - 91 Set 1
10349 Sam Houston Park Or. #126	connections (J uss com
Lise 3.45 TX 770F4	weighten bis in afteration and i

GAS CAPTURE PLAN, Cont.

RKI Exploration and Production, LLC:

 Gas Capture Plan:
 DBM / ETC / Medallion / Enlink
 Processing Plant Information

 RKI Exploration and Production, LLC has the ability to deliver to the below listed Gas Processing Plants.
 Processing Plant Information

DBM / ETC / Medallion / Enlink

.

4

Block 58-T1-Section 36 Reeves County, Texas

L

1

⇒AFMSS SUPO Data Report U.S. Department of the Interior 10/05/2017 BUREAU OF LAND MANAGEMENT مجمعه فيسرد APD ID: 10400013514 Submission Date: 05/30/2017 Highlighted data reflects the most **Operator Name: RKI EXPLORATION & PRODUCTION LLC** recent changes Well Name: TUCKER DRAW 9-4 FED COM Well Number: 1H Show Final Text Well Type: OTHER Well Work Type: Drill

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

Road_Map_05-24-2017.pdf

Existing Road Purpose: ACCESS, FLUID TRANSPORT

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

Road_Map_05-24-2017.pdf

Existing Road Purpose:

ROW ID(s)

ID:

Do the existing roads need to be improved? Existing Road Improvement Description: Existing Road Improvement Attachment: Row(s) Exist? NO

Row(s) Exist?

Feet

Well Name: TUCKER DRAW 9-4 FED COM

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

Road_Map_05-24-2017.pdf

New road type: COLLECTOR

Length: 152.35

Width (ft.): 30

Max slope (%): 2

Max grade (%): 3

Army Corp of Engineers (ACOE) permit required? NO

ACOE Permit Number(s):

New road travel width: 14

New road access erosion control: The access road and associated drainage structures will be constructed and maintained in accordance with the road guidelines in the current BLM Gold Book standards and Surface Operating Standards for Oil and Gas Exploration and Development, Fourth Edition – Revised 2007. Continuous inspection will be performed and preventive maintenance measures will be taken as needed. These measures may include: grading, cleaning of drainage structures, erosion control and slope stabilization, and road closures during periods of excessive soil moisture. New road access plan or profile prepared? NO

New road access plan attachment:

Access road engineering design? NO

Access road engineering design attachment:

Access surfacing type: GRAVEL

Access topsoil source: ONSITE

Access surfacing type description:

Access onsite topsoil source depth: 6

Offsite topsoil source description:

Onsite topsoil removal process: Top 4-6 inches of topsoil will be removed and spread along the edge of the road and within the ditch.

Access other construction information:

Access miscellaneous information:

Number of access turnouts:

Access turnout map:

Drainage Control

New road drainage crossing: OTHER

Drainage Control comments: The access road and associated drainage structures will be constructed and maintained in accordance with the road guidelines in the current BLM Gold Book standards and Surface Operating Standards for Oil and Gas Exploration and Development, Fourth Edition – Revised 2007. Continuous inspection will be performed and preventive maintenance measures will be taken as needed. These measures may include: grading, cleaning of drainage structures,

Operator Name: RKI EXPLORATION & PRODUCTION LLC

Well Name: TUCKER DRAW 9-4 FED COM

Well Number: 1H

erosion control and slope stabilization, and road closures during periods of excessive soil moisture.

Road Drainage Control Structures (DCS) description: The road will be crowned and ditched with water turnouts installed as necessary to provide for proper drainage along the access road route. **Road Drainage Control Structures (DCS) attachment:**

Access Additional Attachments

Additional Attachment(s):

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES New Road Map: Road_Map_05-24-2017.pdf New road type: COLLECTOR Length: 1388.18 Feet Width (ft.): 40 Max slope (%): 2 Max grade (%): 3 Army Corp of Engineers (ACOE) permit required? NO ACOE Permit Number(s): New road travel width: 20 New road access erosion control: New road access plan or profile prepared? NO New road access plan attachment: Access road engineering design? NO Access road engineering design attachment: Access surfacing type: GRAVEL Access topsoil source: ONSITE Access surfacing type description: Access onsite topsoil source depth: Offsite topsoil source description: **Onsite topsoil removal process:** Access other construction information: Access miscellaneous information: Number of access turnouts: Access turnout map:

Drainage Control

Operator Name: RKI EXPLORATION & PRODUCTION LLC

Well Name: TUCKER DRAW 9-4 FED COM

Well Number: 1H

New road drainage crossing:

Drainage Control comments: The road will be crowned and ditched with water turnouts installed if necessary to provide for proper drainage along the access road route.

Road Drainage Control Structures (DCS) description:

Road Drainage Control Structures (DCS) attachment:

Access Additional Attachments

Additional Attachment(s):

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

Existing_Well_Map_05-26-2017.pdf

Existing Wells description:

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

Estimated Production Facilities description:

Production Facilities description:

Production Facilities map:

Tucker_Draw_9_4_Federal_Com_IR_Plat_05-24-2017.pdf

Section 5 - Location and Types of Water Supply

Water Source Table

Water source use type: INTERMEDIATE/PRODUCTION CASING, SURFACE CASING Describe type:	Water source type: GW WELL
Source latitude:	Source longitude:
Source datum:	
Water source permit type: WATER WELL	
Source land ownership: PRIVATE	
Water source transport method: TRUCKING	
Source transportation land ownership: PRIVATE	
Water source volume (barrels): 10000	Source volume (acre-feet): 1.288931

Well Number: 1H

Source volume (gal): 420000

Water source and transportation map:

Tucker_Draw_APD_plan_for_Waterlines_05-24-2017.pdf

Water source comments:

New water well? NO

New Water Well Info

Well latitude:	Well Longitude:	Well datum:
Well target aquifer:		
Est. depth to top of aquifer(ft):	Est thickness of aquifer:	:
Aquifer comments:		
Aquifer documentation:		
Well depth (ft):	Well casing type:	
Well casing outside diameter (in.):	Well casing inside diamete	er (in.):
New water well casing? •	Used casing source:	
Drilling method:	Drill material:	•
Grout material:	Grout depth:	
Casing length (ft.):	Casing top depth (ft.):	
Well Production type:	Completion Method:	
Water well additional information:		
State appropriation permit:		
Additional information attachment:		

Section 6 - Construction Materials

Construction Materials description: Caliche will be hauled from existing caliche pits located in Sec. 24 T26S R29E and Sec. 2 T26S R31E. The Bureau of Land Management is the surface management agency for the caliche pit located in Sec. 24 T26S R29E. The State of New Mexico is the surface management agency for the caliche pit located in Sec. 2 T26S R31E. No construction materials will be removed from Federal lands without prior approval form the appropriate surface management agency.

Construction Materials source location attachment:

Well Number: 1H

Section 7 - Methods for Handling Waste

Waste type: GARBAGE

Waste content description: Garbage produced on-site during drilling operations (not including materials used in the drilling process) including non-flammable solid waste materials.

Amount of waste: 100 gallons

Waste disposal frequency : Daily

Safe containment description: Will be contained in a portable trash cage.

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL Disposal location ownership: COMMERCIAL FACILITY Disposal type description:

Disposal location description: Accumulated trash will be hauled off to a local and state authorized disposal site. All debris and other waste materials not contained in the trash cage will be cleaned up and removed from the well location. No potentially adverse materials or substances will be left on the location. No burning will be allowed.

Waste type: SEWAGE

Waste content description: Sewage from trailers and outbuildings will be contained in portable self-contained chemical toilets provided for human waste disposal.

Amount of waste: 1000 gallons

Waste disposal frequency : Monthly

Safe containment description: Will be contained in portable self-contained chemical toilets provided for human waste disposal

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL Disposal location ownership: COMMERCIAL

FACILITY Disposal type description:

Disposal location description: Upon completion of operations, or as required, the toilet holdings will be pumped and hauled by a licensed contractor for disposal in an approved sewage disposal facility.

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit?

Reserve pit length (ft.) Reserve pit width (ft.)

Reserve pit depth (ft.)

Reserve pit volume (cu. yd.)

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Well Number: 1H

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? YES

Description of cuttings location Cuttings will be held in roll-off style mud boxes and taken to NMOCD approved disposal sites via third party contractors. Cuttings area length (ft.)

Cuttings area depth (ft.)

Cuttings area width (ft.)

Cuttings area volume (cu. yd.)

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: NO

Ancillary Facilities attachment:

Comments:

Section 9 - Well Site Layout

Well Site Layout Diagram:

Tucker_Draw_9_4_Federal_Com_Rig_Layout_05-24-2017.pdf

Comments:

Section 10 - Plans for Surface Reclamation

Type of disturbance: NEW

Recontouring attachment:

Drainage/Erosion control construction: Continuous inspection will be performed and preventive maintenance measures will be taken as needed. These measures may include: grading, cleaning of drainage structures, erosion control and slope stabilization, and road closures during periods of excessive soil moisture.

Drainage/Erosion control reclamation: The original stockpiled topsoil will be returned to the pad and re-contoured per original pad topography. The surface will be ripped, barricaded and seeded per NMSLO and BLM requirements Wellpad long term disturbance (acres): 7.72 Wellpad short term disturbance (acres): 10.3

Access road long term disturbance (acres): 0.05	Access road short term disturbance (acres): 0.1
Pipeline long term disturbance (acres): 0.18663912	Pipeline short term disturbance (acres): 0.3110652
Other long term disturbance (acres): 0	Other short term disturbance (acres): 0

Operator Name: RKI EXPLORATION & PRODUCTION LLC

Well Name: TUCKER DRAW 9-4 FED COM

Well Number: 1H

Total long term disturbance: 7.9566393

Total short term disturbance: 10.711065

Reconstruction method: The surface caliche will be removed from the well pad and road and will be transported to the original caliche pit or used for other roads. The original stockpiled topsoil will be returned to the pad and re-contoured per original pad topography. The pad and access road will be ripped, barricaded and seeded per NMSLO and BLM requirements. Noxious, invasive, and non-native weeds will be controlled.

Topsoil redistribution: The original stockpiled topsoil will be returned to the pad and re-contoured per original pad topography.

Soil treatment: The pad and access road will be ripped, barricaded and seeded per NMSLO and BLM requirements.

Existing Vegetation at the well pad:

Existing Vegetation at the well pad attachment:

Existing Vegetation Community at the road:

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline:

Existing Vegetation Community at the pipeline attachment:

Existing Vegetation Community at other disturbances:

Existing Vegetation Community at other disturbances attachment:

Non native seed used?

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project?

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation?

Seed harvest description:

Seed harvest description attachment:

Seed Management

Seed Table Seed type: Seed source: Seed name: Source name: Source address: Source phone: Seed cultivar: Seed use location: PLS pounds per acre: Proposed seeding season: Total pounds/Acre:

Seed Summary

Well Number: 1H

Seed Type Pounds/Acre

Seed reclamation attachment:

Operator Contact/Responsible Official Contact Info

First Name:

Last Name:

Email:

Phone:

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? NO

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: The pad and access road will be ripped, barricaded and seeded per NMSLO and BLM requirements. Noxious, invasive, and non-native weeds will be controlled. Weed treatment plan attachment:

Monitoring plan description: Noxious, invasive, and non-native weeds will be controlled. Periodic inspections will take place until full reclamation according to NMSLO and BLM standards is achieved. **Monitoring plan attachment:**

Success standards: RKI will reclaim all disturbed areas according to NMSLO and BLM standards.

Pit closure description: Not applicable

Pit closure attachment:

Section 11 - Surface Ownership

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: STATE GOVERNMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office: NEW MEXICO STATE LAND OFFICE

Military Local Office:

.

.

Well Number: 1H

USFWS Local Office:	
Other Local Office:	
USFS Region:	
USFS Forest/Grassland:	USFS Ranger District:

Disturbance type: PIPELINE	
Describe:	
Surface Owner: STATE GOVERNMENT	
Other surface owner description:	
BIA Local Office:	
BOR Local Office:	
COE Local Office:	
DOD Local Office:	
NPS Local Office:	
State Local Office: NEW MEXICO STATE LAND OFFICE	
Military Local Office:	
USFWS Local Office:	
Other Local Office:	
USFS Region:	
USFS Forest/Grassland:	USFS Ranger District:

Disturbance type: WELL PAD Describe: Surface Owner: STATE GOVERNMENT Other surface owner description: BIA Local Office: BOR Local Office: COE Local Office: DOD Local Office:

Well Number: 1H

NPS Local Office:	
State Local Office: NEW MEXICO STATE LAND OFFICE	
Military Local Office:	
USFWS Local Office:	
Other Local Office:	
USFS Region:	
USFS Forest/Grassland:	USFS Ranger District:

Section 12 - Other Information

Right of Way needed? NO ROW Type(s):

Use APD as ROW?

ROW Applications

SUPO Additional Information: A cultural resource survey was conducted in this project area on April 5, 2017.

Use a previously conducted onsite? YES

Previous Onsite information: Onsite was performed with BLM on February 21, 2017. New road east connecting to existing pad, V-door south, production facilities located on pad to east, and top soil stockpile south of pad. Three phase flow lines and gas lift injection tie-in to production facilities located on eastern pad. Right-of-way will be filed for this project with New Mexico State Land Office.

Other SUPO Attachment

BLM_SUPO_Tucker_Draw_9_4_Fed_Com_05-30-2017.pdf















SURFACE USE PLAN OF OPERATIONS

RKI EXPLORATION & PRODUCTION, LLC. Tucker Draw 9-4 Fed Com EDDY COUNTY, NEW MEXICO LEASE NO. NMNM 100558

1. Existing Roads

- a. Directions to location: From Malaga, NM: Head south on Highway 285 S for 12.5 miles. Turn left on Whitehorn Rd for 3.5 miles past a curve for an additional 0.6 miles. Turn left on Pipeline Rd and head east for 2.8 miles. Turn right on Tarbrush road and head south for 0.3 miles. Turn left on lease road and head east 0.5 miles. Turn right on lease road and head southeast for 0.6 miles. Turn left on lease road and head east for 0.7 miles. Stay left on lease road and continue east 2.8 miles. Turn right on lease road and south 0.1 miles. Location is to the east.
- b. All non-county roads used to access the wells will be maintained in their current condition or better than before operations began and will be maintained in accordance with current BLM Gold Book standards and Surface Operating Standards for Oil and Gas Exploration and Development, Fourth Edition Revised 2007. Continuous inspection will be performed and preventive maintenance measures will be taken as needed. These measures may include: grading, cleaning of drainage structures, erosion control and slope stabilization, and road closures during periods of excessive soil moisture.
- c. Please see attached exhibit for existing access road to be used for proposed project.

2. Planned Access Road

- a. Access Road: A new access road will need to be constructed for this pad and will be 152.35 feet long, 14 feet driving surface, have a maximum slope of 2%, and a maximum grade of 3%. Surfacing material will be caliche. There will be no cattle guards installed on this site.
- b. Please see attached exhibit for new access road to be used for proposed project.
- 3. Existing Wells

Please see attached exhibit showing the location of all existing wells within a one-mile radius of the proposed location.

- 4. Proposed Production Facilities
 - a. No production facilities will be constructed on this pad. Production facilities for these wells will be located on the new pad approximately 425 feet to the east. Please see attached exhibit for proposed production facilities layout.

2

.

- b. Pipelines: A 8-inch buried gas line 11.33' in length will be laid north from the eastern pad containing the production facilities to an existing tie-in. An 8-inch buried saltwater disposal line (SWD) 1.03' in length will be laid north from the eastern pad containing the production facilities to an existing tie-in. Three three-phase flow lines and three gas-lift injection lines will be laid from this pad to the production facilities located on the eastern pad. See attached exhibit for line routes and tie-in location.
- c. Electrical: Electric service will be installed to this pad from an existing overhead power pole located within the proposed disturbance on the northwest corner of the pad.
- 5. Location and Type of Water Supply

Water will be piped via a 10-inch O.D. temporary surface line from existing completion ponds located in the NWNW of Sec. 16 T26S R30E, SWSE of Sec. 17 T26S R30E, and the NWNE of Sec. 21 T26S R30E. See attached map for line route and completion pond locations.

- 6. <u>Source of Construction Materials</u>
 - a. NM One Call (811) will be notified before construction starts.
 - b. Top 4-6 inches of topsoil will be stockpiled along the side of location as shown in attached drawing.
 - c. Caliche will be hauled from existing caliche pits located in Sec. 24 T26S R29E and Sec. 2 T26S R31E. The Bureau of Land Management is the surface management agency for the caliche pit located in Sec. 24 T26S R29E. The State of New Mexico is the surface management agency for the caliche pit located in Sec. 2 T26S R31E. No construction materials will be removed from Federal lands without prior approval from the appropriate surface management agency
- 7. <u>Methods for Handling Waste Disposal</u>
 - a. Drilling: Drilling fluids, including cuttings and mud, will be self-contained and recycled via a closed loop system. Cuttings will be held in roll-off style mud boxes and taken to NMOCD approved disposal sites via third party contractors.
 - b. Sewage: Sewage from trailers and outbuildings will be contained in portable selfcontained chemical toilets provided for human waste disposal. Upon completion of operations, or as required, the toilet holdings will be pumped and hauled by a licensed contractor for disposal in an approved sewage disposal facility.

SURFACE USE PLAN OF OPERATIONS Tucker Draw 9-4 Fed Com Page 3

- c. Garbage: Garbage produced on-site during drilling operations (not including materials used in the drilling process) including non-flammable solid waste materials will be contained in a portable trash cage. Upon completion of operations, or as needed, the accumulated trash will be hauled off to a local and state authorized disposal site. All debris and other waste materials not contained in the trash cage will be cleaned up and removed from the well location. No potentially adverse materials or substances will be left on the location. No burning will be allowed.
- 8. Ancillary Facilities

No additional facilities will be utilized.

- 9. Wellsite Layout
 - d. Please see attached exhibits for proposed drilling and production facilities layout.
 - e. All equipment and vehicles will be confined to the access road, pad, and area specified in this APD.
- 10. Surface Reclamation Plan
 - a. Interim reclamation will be completed within 6 months of completing the last well on the pad. The surface caliche will be removed from the part of the well pad no longer in use and will be transported to the original caliche pit or used for other roads. Some of the original stockpiled topsoil will be returned to the pad and re-contoured per original pad topography. The surface will be ripped, barricaded and seeded per NMSLO and BLM requirements. Please see attached exhibit for proposed interim reclamation area.
 - b. Once the last well on the pad is plugged, all equipment will be removed and the remainder of the pad will be reclaimed within 6 months of plugging. The surface caliche will be removed from the well pad and road and will be transported to the original caliche pit or used for other roads. The original stockpiled topsoil will be returned to the pad and re-contoured per original pad topography. The pad and access road will be ripped, barricaded and seeded per NMSLO and BLM requirements. Noxious, invasive, and non-native weeds will be controlled.
- 11. Surface Ownership
 - a. The surface is administered by the New Mexico State Land Office.
 - b. The surface is multiple use with the primary uses of the region being grazing for livestock and production of oil and gas.

SURFACE USE PLAN OF OPERATIONS Tucker Draw 9-4 Fed Com Page 4

12. Other information

.

- c. Onsite was performed with BLM on February 21, 2017. New road east connecting to existing pad, V-door south, production facilities located on pad to east, and top soil stockpile south of pad. Three phase flow lines and gas lift injection tie-in to production facilities located on eastern pad. Right-of-way will be filed for this project with New Mexico State Land Office.
- d. A cultural resource survey was conducted in this project area on April 5, 2017.



AFMSS U.S. Department of the Interior BUREAU OF LAND MANAGEMENT



Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO Produced Water Disposal (PWD) Location: **PWD** surface owner: Lined pit PWD on or off channel: Lined pit PWD discharge volume (bbl/day): Lined pit specifications: **Pit liner description:** Pit liner manufacturers information: Precipitated solids disposal: Decribe precipitated solids disposal: Precipitated solids disposal permit: Lined pit precipitated solids disposal schedule: Lined pit precipitated solids disposal schedule attachment: Lined pit reclamation description: Lined pit reclamation attachment: Leak detection system description: Leak detection system attachment: Lined pit Monitor description: Lined pit Monitor attachment: Lined pit: do you have a reclamation bond for the pit? Is the reclamation bond a rider under the BLM bond? Lined pit bond number: Lined pit bond amount: Additional bond information attachment:

PWD disturbance (acres):

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Decribe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

PWD disturbance (acres):

PWD disturbance (acres):

Injection well type: Injection well number: Assigned injection well API number? Injection well new surface disturbance (acres): Minerals protection information: Mineral protection attachment: Underground Injection Control (UIC) Permit? NO UIC Permit attachment:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location: PWD surface owner: Surface discharge PWD discharge volume (bbl/day): Surface Discharge NPDES Permit? Surface Discharge NPDES Permit attachment: Surface Discharge site facilities information: Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location: PWD surface owner: Other PWD discharge volume (bbl/day): Other PWD type description: Other PWD type attachment: Have other regulatory requirements been met? Other regulatory requirements attachment: Injection well name: Injection well API number:

PWD disturbance (acres):

PWD disturbance (acres):

FMSS

U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

Bond Information

Federal/Indian APD: FED

BLM Bond number: NMB000396

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment:

