

RECEIVED  
Form 3160-3  
(March 2012)

MAY 16 2018

DISTRICT II-ARTESIA O.C.D.

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED  
OMB No. 1004-0137  
Expires October 31, 2014

5. Lease Serial No.  
NMNM116044

6. If Indian, Allottee or Tribe Name

7. If Unit or CA Agreement, Name and No.

8. Lease Name and Well No.  
DOUBLE DIAMOND FED COM 238H

9. API Well No.

10. Field and Pool, or Exploratory  
PURPLE SAGE WOLFCAMP

11. Sec., T. R. M. or Blk. and Survey or Area  
SEC 14 / T24S / R31E / NMP

12. County or Parish  
EDDY

13. State  
NM

1a. Type of work: ☒ DRILL ☐ REENTER

1b. Type of Well: ☐ Oil Well ☒ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone

2. Name of Operator  
TAP ROCK OPERATING LLC

3a. Address  
602 Park Point Drive Suite 200 Golden CO 80

3b. Phone No. (include area code)  
(720)460-3316

4. Location of Well (Report location clearly and in accordance with any State requirements.)\*

At surface SESE / 305 FSL / 860 FEL / LAT 32.2109581 / LONG -103.7428434

At proposed prod. zone NENE / 200 FNL / 330 FEL / LAT 32.2240899 / LONG -103.7411338

14. Distance in miles and direction from nearest town or post office\*  
19 miles

15. Distance from proposed\*  
location to nearest 305 feet  
property or lease line, ft.  
(Also to nearest drig. unit line, if any)

16. No. of acres in lease  
320

17. Spacing Unit dedicated to this well  
320

18. Distance from proposed location\*  
to nearest well, drilling, completed, 637 feet  
applied for, on this lease, ft.

19. Proposed Depth  
12894 feet / 17735 feet

20. BLM/BIA Bond No. on file  
FED: NMB001443

21. Elevations (Show whether DF, KDB, RT, GL, etc.)  
3586 feet

22. Approximate date work will start\*  
04/01/2018

23. Estimated duration  
90 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

1. Well plat certified by a registered surveyor.

2. A Drilling Plan.

3. A Surface Use Plan (if the location is on National Forest System Lands, the  
SUPO must be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see  
Item 20 above).

5. Operator certification

6. Such other site specific information and/or plans as may be required by the  
BLM.

25. Signature  
(Electronic Submission)

Name (Printed/Typed)  
Brian Wood / Ph: (505)466-8120

Date  
02/05/2018

Title

President

Approved by (Signature)  
(Electronic Submission)

Name (Printed/Typed)  
Cody Layton / Ph: (575)234-5959

Date  
04/27/2018

Title

Supervisor Multiple Resources

Office  
CARLSBAD

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to  
conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United  
States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

APPROVED WITH CONDITIONS  
Approval Date: 04/27/2018

R. Kline  
5-18-2018

## INSTRUCTIONS

**GENERAL:** This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

**ITEM 1:** If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

**ITEM 4:** Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

**ITEM 14:** Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

**ITEMS 15 AND 18:** If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

**ITEM 22:** Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

## NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

**AUTHORITY:** 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

**PRINCIPAL PURPOSES:** The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

**ROUTINE USE:** Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

**EFFECT OF NOT PROVIDING INFORMATION:** Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to allow evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

**BURDEN HOURS STATEMENT:** Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Collection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

(Continued on page 3)

(Form 3160-3, page 2)

Approval Date: 04/27/2018



## **Additional Operator Remarks**

### **Location of Well**

1. SHL: SESE / 305 FSL / 860 FEL / TWSP: 24S / RANGE: 31E / SECTION: 14 / LAT: 32.2109581 / LONG: -103.7428434 ( TVD: 0 feet, MD: 0 feet )  
PPP: SENE / 2640 FNL / 332 FEL / TWSP: 24S / RANGE: 31E / SECTION: 14 / LAT: 32.217352 / LONG: -103.741104 ( TVD: 12894 feet, MD: 16404 feet )  
PPP: SESE / 305 FSL / 860 FEL / TWSP: 24S / RANGE: 31E / SECTION: 14 / LAT: 32.2109581 / LONG: -103.7428434 ( TVD: 0 feet, MD: 0 feet )  
BHL: NENE / 200 FNL / 330 FEL / TWSP: 24S / RANGE: 31E / SECTION: 14 / LAT: 32.2240899 / LONG: -103.7411338 ( TVD: 12894 feet, MD: 17735 feet )

## **BLM Point of Contact**

Name: Judith Yeager

Title: Legal Instruments Examiner

Phone: 5752345936

Email: [jyeager@blm.gov](mailto:jyeager@blm.gov)

## **Review and Appeal Rights**

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

---

**Approval Date: 04/27/2018**

(Form 3160-3, page 4)

# PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

<b>OPERATOR'S NAME:</b>	<b>Tap Rock Operating LLC</b>
<b>LEASE NO.:</b>	<b>NMNM116044</b>
<b>WELL NAME &amp; NO.:</b>	<b>Double Diamond Fed Com 238H</b>
<b>SURFACE HOLE FOOTAGE:</b>	<b>305'/S &amp; 860'/E</b>
<b>BOTTOM HOLE FOOTAGE:</b>	<b>200'/N &amp; 330'/E</b>
<b>LOCATION:</b>	<b>Section 14, T.24 S., R.31 E., NMPM</b>
<b>COUNTY:</b>	<b>Eddy County, New Mexico</b>

COA

H2S	<input type="radio"/> Yes	<input checked="" type="radio"/> No	
Potash	<input type="radio"/> None	<input checked="" type="radio"/> Secretary	<input checked="" type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP

## A. Hydrogen Sulfide

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

## B. CASING

1. The 13-3/8 inch surface casing shall be set at approximately 1000 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **24 hours in the Potash Area** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement).



- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

**Operator shall filled 1/3<sup>rd</sup> casing with fluid while running 1<sup>st</sup> and 2<sup>nd</sup> intermediate casings to maintain collapse safety factor.**

- 2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
  - Cement to surface. If cement does not circulate see B.1.a, c-d above.

**Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**

**Variance for annular spacing between 7 5/8 x 9 5/8 inch casing is approved.**

- 3. The minimum required fill of cement behind the 7-5/8 inch production casing is:
  - Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification.

**Variance for annular spacing between 7 5/8 x 5 1/2 inch casing is approved.**

- 4. The minimum required fill of cement behind the 5-1/2 x 4 1/2 inch production casing is: Cement should tie-back 500' into the previous casing. Operator shall provide method of verification.

## **C. PRESSURE CONTROL**

- 1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
- 3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 9-5/8 intermediate casing shoe shall be **5000 (5M)** psi.
- 4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 7-5/8 intermediate casing shoe shall be **10,000 (10M)** psi.

## GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties

Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.  
During office hours call (575) 627-0272.  
After office hours call (575)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)  
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
    - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

#### A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.



7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

#### **B. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
  - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.

- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug. The results of the test shall be reported to the appropriate BLM office.
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

## C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

#### **D. WASTE MATERIAL AND FLUIDS**

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

#### **Waste Minimization Plan (WMP)**

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

**ZS 042418**



4/24/2018

DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT Double Diamond 5-1/2" TXP Casing Clearance Variance Request



Stevens, Zota <zstevens@blm.gov>

## [EXTERNAL] Double Diamond 5-1/2" TXP Casing Clearance Variance Request

1 message

Doug Sproul <dsproul@taprk.com>

Tue, Apr 24, 2018 at 9:37 AM

To: "zstevens@blm.gov" <zstevens@blm.gov>

Good Morning Zota;

Tap Rock is requesting a variance to be less than the 0.422" standoff regulation per Onshore Order No. 2 for the casing programs of the wells listed below for which we have applications processing. Specifically, we wish to run 5-1/2" 20# TXP inside 7-5/8" 29.7# BTC for our 4-string Wolfcamp wells.

Double Diamond 158H

Double Diamond 224H

Double Diamond 228H

Double Diamond 238H

Thank you!

**Doug Sproul**

Drilling Manager

Tap Rock Resources

602 Park Point DR

Suite 200

Golden, CO 80401

Cell: (303) 653-3518

[dsproul@taprk.com](mailto:dsproul@taprk.com)



4/24/2018

DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT Double Diamond Casing Variance Request



Stevens, Zota <zstevens@blm.gov>

---

## [EXTERNAL] Double Diamond Casing Variance Request

2 messages

Doug Sproul <dsproul@taprk.com>  
To: "zstevens@blm.gov" <zstevens@blm.gov>

Mon, Apr 23, 2018 at 8:57 PM

Hi Zota;

I'm sending you this e-mail as follow-up per our phone conversation last week regarding running 7-5/8" BTC inside 9-5/8" BTC, Tap Rock is requesting a variance to be less than the 0.422" standoff regulation per Onshore Order No. 2 for the casing programs of the wells listed below for which we have applications processing:

Double Diamond 158H

Double Diamond 224H

Double Diamond 228H

Double Diamond 238H

Please do let me know if any issues arise that need to be resolved, and thank you for your help.

**Doug Sproul**

Drilling Manager

Tap Rock Resources

602 Park Point DR

Suite 200

Golden, CO 80401

Cell: (303) 653-3518

dsproul@taprk.com



---

Stevens, Zota <zstevens@blm.gov>  
To: Doug Sproul <dsproul@taprk.com>

Tue, Apr 24, 2018 at 7:28 AM

4/24/2018

DEPARTMENT OF THE INTERIOR -- BUREAU OF LAND MANAGEMENT  
Blm-land-016-0000018 Double Diamond Casing Variance Request

Dear Doug,

Thanks for the the variance. Also i need a variance for the 5.5 x 7.625 because the spacing is 0.41 not .422.  
Thanks.

Zota Stevens  
Petroleum Engineer  
Bureau of Land Management  
620 E Greene St.  
Carlsbad, NM 88220  
E-mail: [zstevens@blm.gov](mailto:zstevens@blm.gov)  
Office: (575) 234-2228

Fax: (575) 234-5927

[Quoted text hidden]



**PECOS DISTRICT  
SURFACE USE  
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	Tap Rock Operating LLC
LEASE NO.:	NMNM116044
WELL NAME & NO.:	Double Diamond Fed Com 238H
SURFACE HOLE FOOTAGE:	305'/S & 860'/E
BOTTOM HOLE FOOTAGE:	200'/N & 330'/E
LOCATION:	Section 14, T.24 S., R.31 E., NMPM
COUNTY:	Eddy County, New Mexico

**TABLE OF CONTENTS**

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
  - Lesser Prairie-Chicken Timing Stipulations
  - Ground-level Abandoned Well Marker
  - Range
- ☐ **Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- ☐ **Road Section Diagram**
- ☐ **Production (Post Drilling)**
  - Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## **V. SPECIAL REQUIREMENT(S)**

### **Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:**

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

**Ground-level Abandoned Well Marker to avoid raptor perching:** Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

### **Cattle Guard Requirement**

Any new or existing cattle guards on the access route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations. Once the road is abandoned, the fence would be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

### **Livestock Watering Requirement**

Structures that provide water to livestock, such as windmills, pipelines, drinking troughs, and earthen reservoirs, will be avoided by moving the proposed action.

Any damage to fences, cattle guards, and pipelines or structures that provide water to livestock during construction, throughout the life of the project, and caused by its operation, must be immediately corrected by Tap Rock. Tap Rock must notify the grazing allottee or the private surface landowner and the BLM-CFO (575-234-5972) if any damage occurs to pipelines or structures that provide water to livestock.



## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### **D. FEDERAL MINERAL MATERIALS PIT**

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

### **F. EXCLOSURE FENCING (CELLARS & PITS)**

**Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

**G. ON LEASE ACCESS ROADS****Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

**Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

**Crowning**

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

**Ditching**

Ditching shall be required on both sides of the road.

**Turnouts**

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.


**Drainage**



Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

#### **Cross Section of a Typical Lead-off Ditch**



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

#### **Formula for Spacing Interval of Lead-off Ditches**

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

#### **Cattle guards**

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

#### **Fence Requirement**

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

#### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

### Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

## **VII. PRODUCTION (POST DRILLING)**

### **A. WELL STRUCTURES & FACILITIES**

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

#### **Chemical and Fuel Secondary Containment and Exclosure Screening**

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

#### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

#### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

### **VIII. INTERIM RECLAMATION**

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

### **IX. FINAL ABANDONMENT & RECLAMATION**

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory

revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

## Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



**PECOS DISTRICT  
SURFACE USE  
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	Tap Rock Operating LLC
LEASE NO.:	NMNM116044
WELL NAME & NO.:	Double Diamond Fed Com 238H
SURFACE HOLE FOOTAGE:	305'/S & 860'/E
BOTTOM HOLE FOOTAGE	200'/N & 330'/E
LOCATION:	Section 14, T.24 S., R.31 E., NMPM
COUNTY:	Eddy County, New Mexico

**TABLE OF CONTENTS**

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
  - Lesser Prairie-Chicken Timing Stipulations
  - Ground-level Abandoned Well Marker
  - Range
- ☐ **Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- ☐ **Road Section Diagram**
- ☐ **Production (Post Drilling)**
  - Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## **V. SPECIAL REQUIREMENT(S)**

### **Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:**

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

**Ground-level Abandoned Well Marker to avoid raptor perching:** Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

### **Cattle Guard Requirement**

Any new or existing cattle guards on the access route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations. Once the road is abandoned, the fence would be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

### **Livestock Watering Requirement**

Structures that provide water to livestock, such as windmills, pipelines, drinking troughs, and earthen reservoirs, will be avoided by moving the proposed action.

Any damage to fences, cattle guards, and pipelines or structures that provide water to livestock during construction, throughout the life of the project, and caused by its operation, must be immediately corrected by Tap Rock. Tap Rock must notify the grazing allottee or the private surface landowner and the BLM-CFO (575-234-5972) if any damage occurs to pipelines or structures that provide water to livestock.



## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### **D. FEDERAL MINERAL MATERIALS PIT**

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

### **F. EXCLOSURE FENCING (CELLARS & PITS)**

**Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

**G. ON LEASE ACCESS ROADS****Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

**Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

**Crowning**

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

**Ditching**

Ditching shall be required on both sides of the road.

**Turnouts**

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.


**Drainage**



Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

#### **Cross Section of a Typical Lead-off Ditch**



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

#### **Formula for Spacing Interval of Lead-off Ditches**

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

#### **Cattle guards**

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

#### **Fence Requirement**

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

#### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

### Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

## **VII. PRODUCTION (POST DRILLING)**

### **A. WELL STRUCTURES & FACILITIES**

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

#### **Chemical and Fuel Secondary Containment and Exclosure Screening**

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

#### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

#### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

### **VIII. INTERIM RECLAMATION**

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

### **IX. FINAL ABANDONMENT & RECLAMATION**

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory

revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.



## Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Operator Certification Data Report

05/01/2018

### Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

**NAME:** Brian Wood

**Signed on:** 02/05/2018

**Title:** President

**Street Address:** 37 Verano Loop

**City:** Santa Fe

**State:** NM

**Zip:** 87508

**Phone:** (505)466-8120

**Email address:** afmss@permitswest.com

### Field Representative

**Representative Name:**

**Street Address:**

**City:**

**State:**

**Zip:**

**Phone:**

**Email address:**



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Application Data Report

05/01/2018

**APD ID:** 10400026923

**Submission Date:** 02/05/2018

Highlighted data  
reflects the most  
recent changes

**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

[Show Final Text](#)

**Well Type:** CONVENTIONAL GAS WELL

**Well Work Type:** Drill

### Section 1 - General

**APD ID:** 10400026923

**Tie to previous NOS?**

**Submission Date:** 02/05/2018

**BLM Office:** CARLSBAD

**User:** Brian Wood

**Title:** President

**Federal/Indian APD:** FED

**Is the first lease penetrated for production Federal or Indian?** FED

**Lease number:** NMNM116044

**Lease Acres:** 320

**Surface access agreement in place?**

**Allotted?**

**Reservation:**

**Agreement in place?** NO

**Federal or Indian agreement:**

**Agreement number:**

**Agreement name:**

**Keep application confidential?** NO

**Permitting Agent?** YES

**APD Operator:** TAP ROCK OPERATING LLC

**Operator letter of designation:**

### Operator Info

**Operator Organization Name:** TAP ROCK OPERATING LLC

**Operator Address:** 602 Park Point Drive Suite 200

**Zip:** 80401

**Operator PO Box:**

**Operator City:** Golden

**State:** CO

**Operator Phone:** (720)460-3316

**Operator Internet Address:**

### Section 2 - Well Information

**Well in Master Development Plan?** NO

**Mater Development Plan name:**

**Well in Master SUPO?** NO

**Master SUPO name:**

**Well in Master Drilling Plan?** NO

**Master Drilling Plan name:**

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

**Well API Number:**

**Field/Pool or Exploratory?** Field and Pool

**Field Name:** PURPLE SAGE  
WOLFCAMP

**Pool Name:**

**Is the proposed well in an area containing other mineral resources?** POTASH

**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

**Describe other minerals:**

**Is the proposed well in a Helium production area?** N **Use Existing Well Pad?** NO

**New surface disturbance?**

**Type of Well Pad:** MULTIPLE WELL

**Multiple Well Pad Name:**

**Number:** 238H

DOUBLE DIAMOND

**Well Class:** HORIZONTAL

**Number of Legs:** 1

**Well Work Type:** Drill

**Well Type:** CONVENTIONAL GAS WELL

**Describe Well Type:**

**Well sub-Type:** INFILL

**Describe sub-type:**

**Distance to town:** 19 Miles

**Distance to nearest well:** 637 FT

**Distance to lease line:** 305 FT

**Reservoir well spacing assigned acres Measurement:** 320 Acres

**Well plat:** DD\_238H\_Plat\_20180205085300.pdf

**Well work start Date:** 04/01/2018

**Duration:** 90 DAYS

### Section 3 - Well Location Table

**Survey Type:** RECTANGULAR

**Describe Survey Type:**

**Datum:** NAD83

**Vertical Datum:** NAVD88

**Survey number:** 18329

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1	305	FSL	860	FEL	24S	31E	14	Aliquot SESE	32.21095 81	- 103.7428 434	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 116044	358 6	0	0
KOP Leg #1	305	FSL	860	FEL	24S	31E	14	Aliquot SESE	32.21095 81	- 103.7428 434	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 116044	- 874 2	123 52	123 28
PPP Leg #1	305	FSL	860	FEL	24S	31E	14	Aliquot SESE	32.21095 81	- 103.7428 434	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 116044	358 6	0	0

**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
PPP Leg #1	264 0	FNL	332	FEL	24S	31E	14	Aliquot SENE	32.21735 2	- 103.7411 04	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 111960	- 930 8	164 04	128 94
EXIT Leg #1	200	FNL	330	FEL	24S	31E	14	Aliquot NENE	32.22408 99	- 103.7411 338	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 111960	- 930 8	177 35	128 94
BHL Leg #1	200	FNL	330	FEL	24S	31E	14	Aliquot NENE	32.22408 99	- 103.7411 338	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 111960	- 930 8	177 35	128 94





U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Drilling Plan Data Report

05/01/2018

APD ID: 10400026923

Submission Date: 02/05/2018

Highlighted data  
reflects the most  
recent changes

Operator Name: TAP ROCK OPERATING LLC

Well Name: DOUBLE DIAMOND FED COM

Well Number: 238H

[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

### Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	---	3586	0	0	OTHER : Quaternary caliche	USEABLE WATER	No
2	RUSTLER ANHYDRITE	2855	731	731		NONE	No
3	SALADO	2519	1067	1067	SALT	NONE	No
4	BASE OF SALT	773	2813	2815		NONE	No
5	BELL CANYON	-1027	4613	4617	SANDSTONE	NATURAL GAS,CO2,OIL	No
6	BRUSHY CANYON	-3137	6723	6727	SANDSTONE	NATURAL GAS,CO2,OIL	No
7	BONE SPRING	-4857	8443	8477	LIMESTONE	NATURAL GAS,CO2,OIL	No
8	BONE SPRING 1ST	-5857	9443	9447	SANDSTONE	NATURAL GAS,CO2,OIL	No
9	BONE SPRING 2ND	-6497	10083	10089	SANDSTONE	NATURAL GAS,CO2,OIL	No
10	BONE SPRING 3RD	-7757	11343	11362	SANDSTONE	NATURAL GAS,CO2,OIL	No
11	WOLFCAMP	-8237	11823	11846	OTHER : A Carbonate	NATURAL GAS,CO2,OIL	No
12	WOLFCAMP	-8432	12018	12042	OTHER : A Fat Carbonate	NATURAL GAS,CO2,OIL	No
13	WOLFCAMP	-8622	12208	12232	OTHER : B Carbonate	NATURAL GAS,CO2,OIL	No
14	WOLFCAMP	-9117	12703	12759	OTHER : B2 Carbonate	NATURAL GAS,CO2,OIL	Yes

### Section 2 - Blowout Prevention

Operator Name: TAP ROCK OPERATING LLC

Well Name: DOUBLE DIAMOND FED COM

Well Number: 238H

Pressure Rating (PSI): 10M

Rating Depth: 13000

**Equipment:** A 13,000' 10,000-psi BOP stack consisting of 3 rams with 2 pipe rams, 1 blind ram, and 1 annular preventer will be used below surface casing to TD. An accumulator will be on site. It will comply with Onshore Order 2 requirements for the BOP stack pressure rating. Rotating head will be installed as needed.

**Requesting Variance?** YES

**Variance request:** Tap Rock requests a variance to use a co-flex hose between the BOP stack and choke manifold. Co-flex hose certification is attached. Manufacturer does not require the hose to be anchored. If the specific hose is not available, then one of equal or higher rating will be used.

**Testing Procedure:** Pressure tests will be conducted before drilling out from under all casing strings. BOP will be inspected and operated as required by Onshore Order 2. A top drive check valve and sub equipped with a full opening valve sized to fit the drill pipe and collars will be available on the rig floor in the open position. A third-party company will test the BOPs. Test pressures will be: After surface casing is set and the BOP is nipped up, pressure tests will be made to 250 psi low and 2000 psi high. Test intermediate 1 casing to 250 psi low and 3000 psi high. Test intermediate 2 casing to 250 psi low and 7500 psi high. Annular preventer will be tested to 250 psi low and 1000 psi high on the surface casing and 250 psi low and 1500 psi high on both intermediate strings. In the case of running a speed head with landing mandrel for the 1st and 2nd intermediate casing the initial, after surface casing is set, BOP test pressures will be 250 psi low and 3000 psi high with well head seals tested to 5000 psi once the first intermediate casing has been landed and cemented. BOP may then be lifted to install the C-section of the wellhead. Tap Rock will then nipple the BOP back up and pressure tests will be made to 250 psi low and 5000 psi high. Annular preventer will be tested to 250 psi low and 1500 psi high.

**Choke Diagram Attachment:**

DD\_238H\_Choke\_032918\_20180330164436.pdf

**BOP Diagram Attachment:**

DD\_238H\_BOP\_032918\_20180330164537.pdf

### Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	1000	0	1000	3586		1000	HCP-110	54.5	OTHER - BTC	1.3	1.15	DRY	1.51	DRY	1.51
2	INTERMEDIATE	8.75	7.625	NEW	API	Y	0	4000	0	3996	3586		4000	P-110	29.7	OTHER - BTC	1.3	1.15	DRY	1.51	DRY	1.51
3	INTERMEDIATE	12.25	9.625	NEW	API	N	0	4700	0	4696	3586		4700	J-55	40	OTHER - BTC	1.13	1.15	DRY	1.51	DRY	1.51
4	PRODUCTION	6.125	5.5	NEW	API	Y	0	12300	0	12276			12300	P-110	20	OTHER - BTC	1.3	1.115	DRY	1.51	DRY	1.51
5	INTERMEDIATE	8.75	7.625	NEW	API	Y	4000	12300	3996	12276			8300	P-110	29.7	OTHER - Flush	1.3	1.15	DRY	1.52	DRY	1.51
6	INTERMEDIATE	8.75	7.0	NEW	API	Y	12300	13100	12276	12882			800	P-110	29	OTHER - BTC	1.3	1.15	DRY	1.51	DRY	1.51



**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
7	PRODUCTI ON	6.12 5	4.5	NEW	API	Y	12300	17736	12276	12895			5436	P- 110	13.5	OTHER - BTC	1.3	1.15	DRY	1.51	DRY	1.51

#### Casing Attachments

**Casing ID:** 1      **String Type:** SURFACE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

DD\_238H\_Casing\_Design\_Assumptions\_20180205091752.pdf

**Casing ID:** 2      **String Type:** INTERMEDIATE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

DD\_238H\_7.625\_BTC\_Casing\_Spec\_20180205092451.PDF

**Casing Design Assumptions and Worksheet(s):**

DD\_238H\_Casing\_Design\_Assumptions\_20180205092723.pdf

**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

---

**Casing Attachments**

**Casing ID:** 3      **String Type:** INTERMEDIATE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

DD\_238H\_Casing\_Design\_Assumptions\_20180205091910.pdf

---

**Casing ID:** 4      **String Type:** INTERMEDIATE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

DD\_238H\_7.625\_P110\_Casing\_Spec\_20180205092627.pdf

**Casing Design Assumptions and Worksheet(s):**

DD\_238H\_Casing\_Design\_Assumptions\_20180205092711.pdf

---

**Casing ID:** 5      **String Type:** PRODUCTION

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

DD\_238H\_5.5in\_Casing\_Spec\_20180205100358.PDF

**Casing Design Assumptions and Worksheet(s):**

DD\_238H\_Casing\_Design\_Assumptions\_20180205093222.pdf

---

Operator Name: TAP ROCK OPERATING LLC

Well Name: DOUBLE DIAMOND FED COM

Well Number: 238H

#### Casing Attachments

Casing ID: 6 String Type: INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

DD\_238H\_7\_BTC\_Casing\_Spec\_20180205092906.PDF

Casing Design Assumptions and Worksheet(s):

DD\_238H\_Casing\_Design\_Assumptions\_20180205093207.pdf

Casing ID: 7 String Type: PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

DD\_238H\_4.5\_BTC\_Casing\_Spec\_20180205093323.PDF

Casing Design Assumptions and Worksheet(s):

DD\_238H\_Casing\_Design\_Assumptions\_20180205093358.pdf

#### Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	1000	1000	1.38	14.8	1380	100	Class C	5% NaCl + LCM

INTERMEDIATE	Lead		0	4000	660	2.35	11.5	1551	35	TXI	Fluid loss + dispersant + retarder + LCM
INTERMEDIATE	Tail		0	4000	120	1.39	13.2	166	35	TXI	fluid loss + dispersant + retarder + LCM
INTERMEDIATE	Lead		0	4700	1300	1.81	13.5	2353	100	Class C	Bentonite + 1% CaCl2 + 8% NaCl + LCM

**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
INTERMEDIATE	Tail		0	4700	427	1.38	14.8	589	100	Class C	5% NaCl + LCM
PRODUCTION	Lead		0	1230 0	550	1.17	15.8	643	10	Class H	fluid loss + dispersant + retarder + LCM
PRODUCTION	Tail		0	1230 0	550	1.17	15.8	643	10	Class H	fluid loss + dispersant + retarder + LCM
INTERMEDIATE	Lead		4000	1230 0	660	2.35	11.5	1551	35	TXI	fluid loss + dispersant + retarder + LCM
INTERMEDIATE	Tail		4000	1230 0	120	1.39	13.2	166	35	TXI	fluid loss + dispersant + retarder + LCM
INTERMEDIATE	Lead		1230 0	1310 0	120	1.39	13.2	166	35	TXI	fluid loss + dispersant + retarder + LCM

PRODUCTION	Lead		1230 0	1773 6	550	1.17	15.8	643	10	Class H	fluid loss + dispersant + retarder + LCM
PRODUCTION	Tail		1230 0	1773 6	550	1.17	15.8	643	10	Class H	fluid loss + dispersant + retarder + LCM

## Section 5 - Circulating Medium

**Mud System Type:** Closed

**Will an air or gas system be Used?** NO

**Description of the equipment for the circulating system in accordance with Onshore Order #2:**

**Diagram of the equipment for the circulating system in accordance with Onshore Order #2:**

**Describe what will be on location to control well or mitigate other conditions:** All necessary mud products (e. g., barite, cedar bark) for weight addition and fluid loss control will always be on site. Mud program is subject to change due to hole conditions.

**Describe the mud monitoring system utilized:** Electronic Pason mud monitor system complying with Onshore Order 1 will be used.

## Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
-----------	--------------	----------	----------------------	----------------------	---------------------	-----------------------------	----	----------------	----------------	-----------------	----------------------------

**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
1000	4700	OTHER : Brine water	10	10							
0	1000	OTHER : Fresh water spud	8.3	8.3							
4700	13100	OTHER : Fresh water & cut brine	9	9							
13100	17736	OIL-BASED MUD	12.5	12.5							

## Section 6 - Test, Logging, Coring

**List of production tests including testing procedures, equipment and safety measures:**

A 2-person mud logging program will be used from 4700' MD to TD. Triple combo logs (density, porosity, resistivity, GR) will be run in the pilot hole. GR will be collected through the MWD tools from intermediate casing to TD. CBL with CCL will be run as far as gravity will let it fall to TOC.

**List of open and cased hole logs run in the well:**

CBL,GR,MWD

**Coring operation description for the well:**

No core or drill stem test is planned.

## Section 7 - Pressure

**Anticipated Bottom Hole Pressure:** 8700

**Anticipated Surface Pressure:** 8700

**Anticipated Bottom Hole Temperature(F):** 180

**Anticipated abnormal pressures, temperatures, or potential geologic hazards?** NO

**Describe:**

**Contingency Plans geohazards description:**

**Contingency Plans geohazards attachment:**

**Hydrogen Sulfide drilling operations plan required?** YES

**Hydrogen sulfide drilling operations plan:**

DD\_238H\_H2S\_Plan\_20180205095049.pdf



**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

## Section 8 - Other Information

**Proposed horizontal/directional/multi-lateral plan submission:**

DD\_238H\_Horizontal\_Drill\_Plan\_20180205095141.pdf

**Other proposed operations facets description:**

Deficiency letter dated 3/29/18 requested:

- 1) Revised Choke/BOP to reflect 10M system - see revised attachments;
- 2) Indication that multibowl wellhead will be used - see revised Speedhead Specs diagram

Addressed 3/31/18


**Other proposed operations facets attachment:**

DD\_238H\_General\_Drill\_Plan\_20180205102351.pdf


DD\_228H\_Speedhead\_Specs\_033018\_20180330164052.pdf

**Other Variance attachment:**

**Choke Manifold – Gas Separator (Top View)**



**Choke Manifold – Gas Separator (Side View)**




10,000 psi BOP Stack

**Mud Cross Valves:**


- 5. 10M Check Valve
- 6. Outside 10M Kill Line Valve
- 7. Inside 10M Kill Line Valve
- 8. Outside 10M Kill Line Valve
- 9. 10M HCR Valve

\*Minimum ID = 2-1/16" on Kill Line side and 3" minimum ID on choke line side






**Choke Manifold – Gas Separator (Top View)**




**Choke Manifold – Gas Separator (Side View)**



# Hydrostatic Test Certificate



ContiTech

<b>Certificate Number</b> 938562	<b>COM Order Reference</b> 938562	<b>Customer Name &amp; Address</b> HELMERICH & PAYNE DRILLING CO 1434 SOUTH BOULDER AVE TULSA, OK 74119 USA
<b>Customer Purchase Order No:</b> 740043386		
<b>Project:</b> HOW		
<b>Test Center Address</b> ContiTech Oil & Marine Corp. 11535 Brittmoore Park Drive Houston, TX 77041 USA	<b>Accepted by COM Inspection</b> Signed:  Date: 3/13/17	<b>Accepted by Client Inspection</b>

We certify that the goods detailed hereon have been inspected as described below by our Quality Management System, and to the best of our knowledge are found to conform the requirements of the above referenced purchase order as issued to ContiTech Oil & Marine Corporation.

Item	Part No.	Description	Qty	Serial Number	Work. Press.	Test Press.	Test Time (minutes)
20		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	53631	10,000 psi	15,000 psi	60
30		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	54500	10,000 psi	15,000 psi	60
40		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	56838	10,000 psi	15,000 psi	60
50		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	56489	10,000 psi	15,000 psi	60
60		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	61475	10,000 psi	15,000 psi	60
80		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	60197	10,000 psi	15,000 psi	60
90		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	39474	10,000 psi	15,000 psi	60
100		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	60887	10,000 psi	15,000 psi	60

# Certificate of Conformity




ContiTech

<b>Certificate Number</b> 938562	<b>COM Order Reference</b> 938562	<b>Customer Name &amp; Address</b> HELMERICH & PAYNE DRILLING CO 1434 SOUTH BOULDER AVE TULSA, OK 74119 USA
<b>Customer Purchase Order No:</b>	740043386	
<b>Project:</b>	HOW	
<b>Test Center Address</b> ContiTech Oil & Marine Corp. 11535 Brittmoore Park Drive Houston, TX 77041 USA	<b>Accepted by COM Inspection</b> Signed: Roger Suarez Date: 6/13/17	<b>Accepted by Client Inspection</b>

We certify that the items detailed below meet the requirements of the customer's Purchase Order referenced above, and are in conformance with the specifications given below.

Item	Part No.	Description	Qty	Serial Number	Specifications
20		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	53631	ContiTech Standard
30		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	54500	ContiTech Standard
40		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	56838	ContiTech Standard
50		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	56489	ContiTech Standard
60		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	61475	ContiTech Standard
80		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	60197	ContiTech Standard
90		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	39474	ContiTech Standard
100		RECERTIFICATION - 3" ID 10K Choke and Kill Hose x 35 ft OAL	1	60887	ContiTech Standard





# Hose Inspection Report

ContiTech Oil & Marine

Customer	Customer Reference #	CBC Reference #	CBC Inspector	Date of Inspection
H&P Drilling	740043386	COM938562	A. Jaimes	03/06/2017

Hose Manufacturer	Contitech Rubber Industrial
-------------------	-----------------------------

Hose Serial #	53631	Date of Manufacture	08/2008
Hose I.D.	3"	Working Pressure	10000PSI
Hose Type	Choke and Kill	Test Pressure	15000PSI
Manufacturing Standard	API 16C		

## Connections

End A: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange	End B: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange
• No damage	• No damage
Material: Carbon Steel	Material: Carbon Steel
Seal Face: BX155	Seal Face: BX155
Length Before Hydro Test: 35'	Length After Hydro test: 35'


**Conclusion:** Hose #53631 passed the external inspection with minor damage to the hose armor. Internal borescope showed no damage to the liner. Hose #53631 passed the hydrostatic pressure test by holding a pressure of 15,000PSI for 60 minutes. Hose #53631 is suitable for continued service.

**Recommendations:** In general the hose should be inspected on a regular on-going basis. The frequency and degree of the inspection should as a minimum follow these guidelines:

Visual inspection: Every 3 to 6 months (or during installation/removal)  
 Annual: In-situ pressure test (in addition to the 3 to 6 monthly inspections)  
 Initial 5 years service: Major inspection  
 2nd Major inspection: Following subsequent 3 year life cycle  
 (Detailed description of test regime available upon request, QCP 206-1)

**\*\*NOTE:** There are a number of critical elements in the hose that cannot be thoroughly checked through standard inspection techniques. Away from dissecting the hose body, the best way to evaluate the condition of the hose is through review of the operating conditions recorded during the hose service life, in particular maximums and peak conditions.

External Damage Post – Hydro test	
Approx. Distance from End A	3'
Width	8"
Length	3"
Depth	To hose body
Notes	Broken armor



Issued By: Alejandro Jaimes  
 Date: 03/10/2017

Checked By: Gerson Mejia-Lazo  
 Date: 03/10/2017

Page 1 of 1  
 QF97

57580


JOE # 300420862  
PCC# 737362

TEST DESCRIPTION: 2" 10K CHOK + 1212X35'

CHART RECORDER: 15-0001937

CHART SETTINGS: 287110

DATE: 5 3 12



# Hose Inspection Report

ContiTech Oil & Marine

Customer	Customer Reference #	CBC Reference #	CBC Inspector	Date of Inspection
H&P Drilling	740043386	COM938562	A. Jaimes	03/03/2017

Hose Manufacturer	Contitech Rubber Industrial
-------------------	-----------------------------

Hose Serial #	54500	Date of Manufacture	01/2009
Hose I.D.	3"	Working Pressure	10000PSI
Hose Type	Choke and Kill	Test Pressure	15000PSI
Manufacturing Standard	API 16C		

## Connections

End A: 3.1/8" 5Kpsi API Spec 6A Type 6BX Flange	End B: 3.1/8" 5Kpsi API Spec 6A Type 6BX Flange
• No damage	• No damage
Material: Carbon Steel	Material: Carbon Steel
Seal Face: BX155	Seal Face: BX155
Length Before Hydro Test: 35'	Length After Hydro test: 35'

**Conclusion:** Hose #54500 passed the external inspection with no notable damages to the hose armor. Internal borescope of the hose showed no damage to the liner. Hose #54500 passed the hydrostatic pressure test by holding a pressure of 15,000PSI for 60 minutes. Hose #54500 is suitable for continued service.

**Recommendations:** In general the hose should be inspected on a regular on-going basis. The frequency and degree of the inspection should as a minimum follow these guidelines:

Visual inspection: Every 3 to 6 months (or during installation/removal)  
 Annual: In-situ pressure test (in addition to the 3 to 6 monthly inspections)  
 Initial 5 years service: Major inspection  
 2nd Major inspection: Following subsequent 3 year life cycle  
 (Detailed description of test regime available upon request, QCP 206-1)

**\*\*NOTE:** There are a number of critical elements in the hose that cannot be thoroughly checked through standard inspection techniques. Away from dissecting the hose body, the best way to evaluate the condition of the hose is through review of the operating conditions recorded during the hose service life, in particular maximums and peak conditions.

Issued By: Alejandro Jaimes  
 Date: 03/13/2017


Checked By: Gerson Mejia-Lazo  
 Date: 03/13/2017

Page 1 of 1  
 QF97



56838

JOB# 88800400883  
PBC# 938562  
HOSE DESCRIPTION: 3" 1016 CHOKE + KILL 35'  
TEST PRESSURE: 15000 PSI  
CHART RECORDER #: 24448  
CHART SETTING: 96 MIN  
CBC REPRESENTATIVE: P. J. JAMES  
DATE: 3-6-72





# Hose Inspection Report

ContiTech Oil & Marine

Customer	Customer Reference #	CBC Reference #	CBC Inspector	Date of Inspection
H&P Drilling	740043386	COM938562	A. Jaimes	03/06/2017

Hose Manufacturer	Contitech Rubber Industrial
-------------------	-----------------------------

Hose Serial #	56838	Date of Manufacture	11/2010
Hose I.D.	3"	Working Pressure	10000PSI
Hose Type	Choke and Kill	Test Pressure	15000PSI
Manufacturing Standard	API 16C		

## Connections


End A: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange	End B: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange
• No damage	• No damage
Material: Carbon Steel	Material: Carbon Steel
Seal Face: BX155	Seal Face: BX155
Length Before Hydro Test: 35'	Length After Hydro test: 35'

**Conclusion:** Hose #56838 passed the external inspection with no notable damage to the hose armor. Internal borescope of the hose showed no damage to the liner. Hose #56838 passed the hydrostatic pressure test by holding a pressure of 15,000PSI for 60 minutes. Hose #56838 is suitable for continued service.

**Recommendations:** In general the hose should be inspected on a regular on-going basis. The frequency and degree of the inspection should as a minimum follow these guidelines:

Visual inspection: Every 3 to 6 months (or during installation/removal)  
 Annual: In-situ pressure test (in addition to the 3 to 6 monthly inspections)  
 Initial 5 years service: Major inspection  
 2nd Major inspection: Following subsequent 3 year life cycle  
 (Detailed description of test regime available upon request, QCP 206-1)

**\*\*NOTE:** There are a number of critical elements in the hose that cannot be thoroughly checked through standard inspection techniques. Away from dissecting the hose body, the best way to evaluate the condition of the hose is through review of the operating conditions recorded during the hose service life, in particular maximums and peak conditions.





# Hose Inspection Report

ContiTech Oil & Marine

Customer	Customer Reference #	CBC Reference #	CBC Inspector	Date of Inspection
H&P Drilling	740043386	COM938562	A. Jaimes	03/01/2017

Hose Manufacturer	Contitech Rubber Industrial
-------------------	-----------------------------

Hose Serial #	56489	Date of Manufacture	08/2010
Hose I.D.	3"	Working Pressure	10000PSI
Hose Type	Choke and Kill	Test Pressure	15000PSI
Manufacturing Standard	API 16C		

## Connections

End A: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange	End B: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange
• No damage	• No damage
Material: Carbon Steel	Material: Carbon Steel
Seal Face: BX155	Seal Face: BX155
Length Before Hydro Test: 35'	Length After Hydro test: 35'

**Conclusion:** Hose #56489 passed the external inspection with no notable damage to the hose armor. Internal borescope of the hose showed no damage to the liner. Hose #56489 passed the hydrostatic pressure test by holding a pressure of 15,000PSI for 60 minutes. Hose #56489 is suitable for continued service.

**Recommendations:** In general the hose should be inspected on a regular on-going basis. The frequency and degree of the inspection should as a minimum follow these guidelines:

Visual inspection: Every 3 to 6 months (or during installation/removal)  
 Annual: In-situ pressure test (in addition to the 3 to 6 monthly inspections)  
 Initial 5 years service: Major inspection  
 2nd Major inspection: Following subsequent 3 year life cycle  
 (Detailed description of test regime available upon request, QCP 206-1)


**\*\*NOTE:** There are a number of critical elements in the hose that cannot be thoroughly checked through standard inspection techniques. Away from dissecting the hose body, the best way to evaluate the condition of the hose is through review of the operating conditions recorded during the hose service life, in particular maximums and peak conditions.

Issued By: Alejandro Jaimes  
 Date: 03/10/2017

Checked By: Gerson Mejia-Lazo  
 Date: 03/10/2017

Page 1 of 1  
 QF97







# Hose Inspection Report

ContiTech Oil & Marine

Customer	Customer Reference #	CBC Reference #	CBC Inspector	Date of Inspection
H&P Drilling	740043386	COM938562	A. Jaimes	03/01/2017

Hose Manufacturer	Contitech Rubber Industrial
-------------------	-----------------------------

Hose Serial #	61475	Date of Manufacture	01/2012
Hose I.D.	3"	Working Pressure	10000PSI
Hose Type	Choke and Kill	Test Pressure	15000PSI
Manufacturing Standard	API 16C		

## Connections

End A: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange	End B: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange
• No damage	• No damage
Material: Carbon Steel	Material: Carbon Steel
Seal Face: BX155	Seal Face: BX155
Length Before Hydro Test: 35'	Length After Hydro test: 35'

**Conclusion:** Hose #61475 passed the external inspection with no notable damage to the hose armor. Internal borescope of the hose showed no damage to the liner. Hose #61475 passed the hydrostatic pressure test by holding a pressure of 15,000PSI for 60 minutes. Hose #61475 is suitable for continued service.

**Recommendations:** In general the hose should be inspected on a regular on-going basis. The frequency and degree of the inspection should as a minimum follow these guidelines:

Visual inspection: Every 3 to 6 months (or during installation/removal)  
 Annual: In-situ pressure test (in addition to the 3 to 6 monthly inspections)  
 Initial 5 years service: Major inspection  
 2nd Major inspection: Following subsequent 3 year life cycle  
 (Detailed description of test regime available upon request, QCP 206-1)

**\*\*NOTE:** There are a number of critical elements in the hose that cannot be thoroughly checked through standard inspection techniques. Away from dissecting the hose body, the best way to evaluate the condition of the hose is through review of the operating conditions recorded during the hose service life, in particular maximums and peak conditions.

Issued By: Alejandro Jaimes  
 Date: 03/10/2017

Checked By: Gerson Mejia-Lazo  
 Date: 03/10/2017

Page 1 of 1  
 QF97

4 60197 5

JOB# 88300400887

PBG# 75852


HOSE DESCRIPTION: 3" 10K CHOKER + K102X 35'

TEST PRESSURE: 75000 PSI

CHART RECORDER #: 24448

CBG REPRESENTATIVE: J. J. J. J.

DATE: 3-9-17



# Hose Inspection Report

ContiTech Oil & Marine

Customer	Customer Reference #	CBC Reference #	CBC Inspector	Date of Inspection
H&P Drilling	740043386	COM938562	A. Jaimes	03/07/2017

Hose Manufacturer	Contitech Rubber Industrial
-------------------	-----------------------------

Hose Serial #	60197	Date of Manufacture	01/2011
Hose I.D.	3"	Working Pressure	10000PSI
Hose Type	Choke and Kill	Test Pressure	15000PSI
Manufacturing Standard	API 16C		

## Connections

End A: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange	End B: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange
• No damage	• No damage
Material: Carbon Steel	Material: Carbon Steel
Seal Face: BX155	Seal Face: BX155
Length Before Hydro Test: 35'	Length After Hydro test: 35'


**Conclusion:** Hose #60197 passed the external inspection with minor damage to the hose armor. Internal borescope showed no damage to the liner. Hose #60197 passed the hydrostatic pressure test by holding a pressure of 15,000PSI for 60 minutes. Hose #60197 is suitable for continued service.

**Recommendations:** In general the hose should be inspected on a regular on-going basis. The frequency and degree of the inspection should as a minimum follow these guidelines:

Visual inspection: Every 3 to 6 months (or during installation/removal)  
 Annual: In-situ pressure test (in addition to the 3 to 6 monthly inspections)  
 Initial 5 years service: Major inspection  
 2nd Major inspection: Following subsequent 3 year life cycle  
 (Detailed description of test regime available upon request, QCP 206-1)

**\*\*NOTE:** There are a number of critical elements in the hose that cannot be thoroughly checked through standard inspection techniques. Away from dissecting the hose body, the best way to evaluate the condition of the hose is through review of the operating conditions recorded during the hose service life, in particular maximums and peak conditions.

External Damage Post – Hydro test	
Approx. Distance from End A	6'
Width	1"
Length	1"
Depth	On armor
Notes	Crack on armor



Issued By: Alejandro Jaimes  
 Date: 03/10/2017

Checked By: Gerson Mejia-Lazo  
 Date: 03/10/2017

Page 1 of 2  
 QF97




## Hose Inspection Report

ContiTech Oil & Marine


Customer	Customer Reference #	CBC Reference #	CBC Inspector	Date of Inspection
H&P Drilling	740043386	COM938562	A. Jaimes	03/07/2017

External Damage Post – Hydro test	
Approx. Distance from End A	20'
Width	1"
Length	1"
Depth	On armor
Notes	Crack on armor



PASS





# Hose Inspection Report

ContiTech Oil & Marine

Customer	Customer Reference #	CBC Reference #	CBC Inspector	Date of Inspection
H&P Drilling	740043386	COM938562	A. Jaimes	03/02/2017

Hose Manufacturer	Contitech Rubber Industrial
-------------------	-----------------------------

Hose Serial #	39474	Date of Manufacture	08/2003
Hose I.D.	3"	Working Pressure	10000PSI
Hose Type	Choke and Kill	Test Pressure	15000PSI
Manufacturing Standard	API 16C		

## Connections

End A: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange	End B: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange
• No damage	• No damage
Material: Carbon Steel	Material: Carbon Steel
Seal Face: BX155	Seal Face: BX155
Length Before Hydro Test: 35'	Length After Hydro test: 35'


**Conclusion:** Hose #39474 passed the external inspection with minor damage to the hose armor. Internal borescope showed no damage to the liner. Hose #39474 passed the hydrostatic pressure test by holding a pressure of 15,000PSI for 60 minutes. Hose #39474 is suitable for continued service.

**Recommendations:** In general the hose should be inspected on a regular on-going basis. The frequency and degree of the inspection should as a minimum follow these guidelines:

Visual inspection: Every 3 to 6 months (or during installation/removal)  
 Annual: In-situ pressure test (in addition to the 3 to 6 monthly inspections)  
 Initial 5 years service: Major inspection  
 2nd Major inspection: Following subsequent 3 year life cycle  
 (Detailed description of test regime available upon request, QCP 206-1)

**\*\*NOTE:** There are a number of critical elements in the hose that cannot be thoroughly checked through standard inspection techniques. Away from dissecting the hose body, the best way to evaluate the condition of the hose is through review of the operating conditions recorded during the hose service life, in particular maximums and peak conditions.

External Damage Post – Hydro test	
Approx. Distance from End A	15'
Width	1"
Length	1"
Depth	To hose body
Notes	Cracked armor



Issued By: Alejandro Jaimes  
 Date: 03/10/2017

Checked By: Gerson Mejia-Lazo  
 Date: 03/10/2017

Page 1 of 1  
 QF97

5 60887 6 PM

JOB# 88300400 P89  
RBC# 738562  
HOSE DESCRIPTION: 5" 10K CHART # 1411X 35'  
TEST PRESSURE: 15,000 PSI  
CHART RECORDER #: 24448  
CHART SETTING: 25 PSI  
CBC REPRESENTATIVE: A Janner  
DATE: 3-7-12

CHART NO. MC MP-30000-ISO FX 50  
EQUIPMENT CATALOG  
METER  
CHART PUT ON  
LOCATION  
REMARKS  
TAKEN OFF

5 6 AM

NOON

MIDNIGHT



# Hose Inspection Report

ContiTech Oil & Marine

Customer	Customer Reference #	CBC Reference #	CBC Inspector	Date of Inspection
H&P Drilling	740043386	COM938562	A. Jaimes	03/07/2017

Hose Manufacturer	Contitech Rubber Industrial
-------------------	-----------------------------

Hose Serial #	60887	Date of Manufacture	10/2011
Hose I.D.	3"	Working Pressure	10000PSI
Hose Type	Choke and Kill	Test Pressure	15000PSI
Manufacturing Standard	API 16C		

## Connections

End A: 4.1/16" 5Kpsi API Spec 6A Type 6BX Flange	End B: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange
• No damage	• No damage
Material: Carbon Steel	Material: Carbon Steel
Seal Face: BX155	Seal Face: BX155
Length Before Hydro Test: 35'	Length After Hydro test: 35'


**Conclusion:** Hose #60887 passed the external inspection with minimal damage to the hose armor. Internal borescope showed no damage to the liner. Hose #60887 passed the hydrostatic pressure test by holding a pressure of 15,000PSI for 60 minutes. Hose #60887 is suitable for continued service.

**Recommendations:** In general the hose should be inspected on a regular on-going basis. The frequency and degree of the inspection should as a minimum follow these guidelines:

Visual inspection: Every 3 to 6 months (or during installation/removal)  
 Annual: In-situ pressure test (in addition to the 3 to 6 monthly inspections)  
 Initial 5 years service: Major inspection  
 2nd Major inspection: Following subsequent 3 year life cycle  
 (Detailed description of test regime available upon request, QCP 206-1)

**\*\*NOTE:** There are a number of critical elements in the hose that cannot be thoroughly checked through standard inspection techniques. Away from dissecting the hose body, the best way to evaluate the condition of the hose is through review of the operating conditions recorded during the hose service life, in particular maximums and peak conditions.

External Damage Post – Hydro test	
Approx. Distance from End A	10'
Width	1"
Length	1"
Depth	To hose body
Notes	Crack on armor



Issued By: Alejandro Jaimes  
 Date: 03/10/2017

Checked By: Gerson Mejia-Lazo  
 Date: 03/10/2017


Page 1 of 2  
 QF97

## Hose Inspection Report

ContiTech Oil & Marine

Customer	Customer Reference #	CBC Reference #	CBC Inspector	Date of Inspection
H&P Drilling	740043386	COM938562	A. Jaimes	03/07/2017

<b>External Damage</b> <b>Post – Hydro test</b>	
Approx. Distance from End A	4'
Width	4"
Length	4"
Depth	To hose body
Notes	Rubber exposed



PASS

Issued By: Alejandro Jaimes  
Date: 03/10/2017

Checked By: Gerson Mejia-Lazo  
Date: 03/10/2017

Page 2 of 2  
QF97

## Casing and Tubing Performance Data

### PIPE BODY DATA

#### GEOMETRY

Outside Diameter	7.625 in	Wall Thickness	0.375 in	API Drift Diameter	6.750 in
Nominal Weight	29.70 lbs/ft	Nominal ID	6.875 in	Alternative Drift Diameter	n.a.
Plain End Weight	29.06 lbs/ft	Nominal cross section	8.541 in		

#### PERFORMANCE

Steel Grade	P110	Minimum Yield	110,000 psi	Minimum Ultimate	125,000 psi
Tension Yield	940,000 in	Internal Pressure Yield	9,470 psi	Collapse Pressure	5,350 psi
Available Seamless	Yes	Available Welded	Yes		

### CONNECTION DATA

TYPE: BTC

#### GEOMETRY

Coupling Reg OD	8.500 in	Threads per in	5	Thread turns make up	1
-----------------	----------	----------------	---	----------------------	---

#### PERFORMANCE

Steel Grade	P110	Coupling Min Yield	110,000 psi	Coupling Min Ultimate	125,000 psi
Joint Strength	960,000 lbs			Internal Pressure Resistance	9,470 psi



## Wedge 513®

Printed on: 01/30/2018



Outside Diameter	7.625 in.	Min. Wall Thickness	87.5%	(*) Grade P110	
Wall Thickness	0.375 in.	Connection OD Option	REGULAR	COUPLING	PIPE BODY
Grade	P110*	Drift	API Standard	Body: White	1st Band: White
		Type	Casing	1st Band: -	2nd Band: -
				2nd Band: -	3rd Band: -
				3rd Band: -	4th Band: -



## GEOMETRY

Nominal OD	7.625 in.	Nominal Weight	29.70 lbs/ft	Drift	6.75 in.
Nominal ID	6.875 in.	Wall Thickness	0.375 in.	Plain End Weight	29.06 lbs/ft
OD Tolerance	API				

## PERFORMANCE

Body Yield Strength	940 x1000 lbs	Internal Yield	9470 psi	SMYS	110000 psi
Collapse	5350 psi				

## GEOMETRY

Connection OD	7.625 in.	Connection ID	6.800 in.	Make-up Loss	4.420 in.
Threads per in	3.29	Connection OD Option	REGULAR		

## PERFORMANCE

Tension Efficiency	60.0 %	Joint Yield Strength	564.000 x1000 lbs	Internal Pressure Capacity	9470.000 psi
Compression Efficiency	75.2 %	Compression Strength	706.880 x1000 lbs	Max. Allowable Bending	39.6 °/100 ft
External Pressure Capacity	5350.000 psi				

## MAKE-UP TORQUES

Minimum	9000 ft-lbs	Optimum	10800 ft-lbs	Maximum	15800 ft-lbs
---------	-------------	---------	--------------	---------	--------------

## OPERATION LIMIT TORQUES

Operating Torque	47000 ft-lbs	Yield Torque	70000 ft-lbs
------------------	--------------	--------------	--------------

## Notes

This connection is fully interchangeable with:

Wedge 523® - 7.625 in. - 29.7 lbs/ft

Connections with Dopeless® Technology are fully compatible with the same connection in its Standard version

For further information on concepts indicated in this datasheet, download the Datasheet Manual from [www.tenaris.com](http://www.tenaris.com)

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information -if any- provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or liability of any kind for any loss, damage or injury resulting from, or in connection with any information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Tenaris's products and services are subject to Tenaris's standard terms and conditions or otherwise to the terms resulting from the respective contracts of sale or services, as the case may be, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at [www.tenaris.com](http://www.tenaris.com) ©Tenaris 2017. All rights reserved.



## Casing and Tubing Performance Data

### PIPE BODY DATA

#### GEOMETRY

Outside Diameter	7.000 in	Wall Thickness	0.408 in	API Drift Diameter	6.059 in
Nominal Weight	29.00 lbs/ft	Nominal ID	6.184 in	Alternative Drift Diameter	6.125 in
Plain End Weight	28.75 lbs/ft	Nominal cross section	8.449 in		

#### PERFORMANCE

Steel Grade	P110	Minimum Yield	110,000 psi	Minimum Ultimate	125,000 psi
Tension Yield	929,000 in	Internal Pressure Yield	11,220 psi	Collapse Pressure	8,530 psi
Available Seamless	Yes	Available Welded	Yes		

### CONNECTION DATA

#### TYPE: BTC

#### GEOMETRY

Coupling Reg OD	7.656 in	Threads per in	5	Thread turns make up	1
-----------------	----------	----------------	---	----------------------	---

#### PERFORMANCE

Steel Grade	P110	Coupling Min Yield	110,000 psi	Coupling Min Ultimate	125,000 psi
Joint Strength	955,000 lbs			Internal Pressure Resistance	11,220 psi

5.5", 20#, P-110, TXP connection (modified buttress connection that provides a torque rating of nearly 24000ft-lbs)

TXP® BTC

SHARE EXPORT DATA PRINT



Outside Diameter	5.500 in	Min. Wall Thickness	87.5%	▼
		Drift	API Standard	▼
Wall Thickness	0.361 in	Type	Casing	▼
Grade	<a href="#">P110</a>	Connection OD Option	REGULAR	▼

Clear Filters

Compare

Request Info

CONNECTION INFORMATION

- > Blanking Dimensions
- > Connection's Page
- > Brochure
- > Datasheet Manual

PIPE BODY DATA

GEOMETRY

Nominal OD	5.500 in	Nominal Weight	20 lbs/ft	Drift	4.653 in
Nominal ID	4.778 in	Wall Thickness	0.361 in	Plain End Weight	19.83 lbs/ft
OD Tolerance	API				

PERFORMANCE

Body Yield Strength	641 x1000 lbs	Internal Yield	12640 psi	SMYS	110000 psi
Collapse	11100 psi				

CONNECTION DATA

GEOMETRY

Connection OD	6.100 in	Coupling Length	9.450 in	Connection ID	4.766 in
Make-up Loss	4.204 in	Threads per in	5	Connection OD Option	REGULAR

PERFORMANCE

Tension Efficiency	100.0 %	Joint Yield Strength	641,000 x1000 lbs	Internal Pressure Capacity (1)	12640,000 psi
Compression Efficiency	100 %	Compression Strength	641,000 x1000 lbs	Max Allowable Bending	92 x1000 ft
External Pressure Capacity	11100,000 psi				

MAKE-UP TORQUES

Minimum	11270 ft-lbs	Optimum	12520 ft-lbs	Maximum	13770 ft-lbs
---------	--------------	---------	--------------	---------	--------------

OPERATION LIMIT TORQUES

Operating Torque	21500 ft-lbs	Yield Torque	23900 ft-lbs
------------------	--------------	--------------	--------------

## Casing and Tubing Performance Data

### PIPE BODY DATA

#### GEOMETRY

Outside Diameter	4.500 in	Wall Thickness	0.290 in	API Drift Diameter	3.795 in
Nominal Weight	13.50 lbs/ft	Nominal ID	3.920 in	Alternative Drift Diameter	n.a.
Plain End Weight	13.05 lbs/ft	Nominal cross section	3.836 in		

#### PERFORMANCE

Steel Grade	P110	Minimum Yield	110,000 psi	Minimum Ultimate	125,000 psi
Tension Yield	422,000 in	Internal Pressure Yield	12,410 psi	Collapse Pressure	10,690 psi
Available Seamless	Yes	Available Welded	Yes		

### CONNECTION DATA

#### TYPE: BTC

#### GEOMETRY

Coupling Reg OD	5.000 in	Threads per in	5	Thread turns make up	0.5
-----------------	----------	----------------	---	----------------------	-----

#### PERFORMANCE

Steel Grade	P110	Coupling Min Yield	110,000 psi	Coupling Min Ultimate	125,000 psi
Joint Strength	443,000 lbs			Internal Pressure Resistance	12,410 psi

### **Casing Design Assumptions**

- Gas gravity 0.7
- Pore pressure gradient .468 psi/ft above the Wolfcamp, .676 psi/ft Wolfcamp and below
- .676 psi/ft fracture gradient above the Wolfcamp, .832 psi/ft Wolfcamp and below.
- 60°F average surface temperature and 1.5°/100ft temperature gradient
- Cementing loads based on slurries listed in Cement table, and post cement static loading
- Strings landed at neutral weight
- Gas kicks assumed at each casing shoe
- External pressure calculated with fluid gradients and pore pressure
- Production string load tested with completion fluid density and rate
- Tubing leak tested in production scenario

### **Casing Design Assumptions**

- Gas gravity 0.7
- Pore pressure gradient .468 psi/ft above the Wolfcamp, .676 psi/ft Wolfcamp and below
- .676 psi/ft fracture gradient above the Wolfcamp, .832 psi/ft Wolfcamp and below.
- 60°F average surface temperature and 1.5°/100ft temperature gradient
- Cementing loads based on slurries listed in Cement table, and post cement static loading
- Strings landed at neutral weight
- Gas kicks assumed at each casing shoe
- External pressure calculated with fluid gradients and pore pressure
- Production string load tested with completion fluid density and rate
- Tubing leak tested in production scenario

### **Casing Design Assumptions**

- Gas gravity 0.7
- Pore pressure gradient .468 psi/ft above the Wolfcamp, .676 psi/ft Wolfcamp and below
- .676 psi/ft fracture gradient above the Wolfcamp, .832 psi/ft Wolfcamp and below.
- 60°F average surface temperature and 1.5°/100ft temperature gradient
- Cementing loads based on slurries listed in Cement table, and post cement static loading
- Strings landed at neutral weight
- Gas kicks assumed at each casing shoe
- External pressure calculated with fluid gradients and pore pressure
- Production string load tested with completion fluid density and rate
- Tubing leak tested in production scenario

### **Casing Design Assumptions**

- Gas gravity 0.7
- Pore pressure gradient .468 psi/ft above the Wolfcamp, .676 psi/ft Wolfcamp and below
- .676 psi/ft fracture gradient above the Wolfcamp, .832 psi/ft Wolfcamp and below.
- 60°F average surface temperature and 1.5°/100ft temperature gradient
- Cementing loads based on slurries listed in Cement table, and post cement static loading
- Strings landed at neutral weight
- Gas kicks assumed at each casing shoe
- External pressure calculated with fluid gradients and pore pressure
- Production string load tested with completion fluid density and rate
- Tubing leak tested in production scenario



### **Casing Design Assumptions**

- Gas gravity 0.7
- Pore pressure gradient .468 psi/ft above the Wolfcamp, .676 psi/ft Wolfcamp and below
- .676 psi/ft fracture gradient above the Wolfcamp, .832 psi/ft Wolfcamp and below.
- 60°F average surface temperature and 1.5°/100ft temperature gradient
- Cementing loads based on slurries listed in Cement table, and post cement static loading
- Strings landed at neutral weight
- Gas kicks assumed at each casing shoe
- External pressure calculated with fluid gradients and pore pressure
- Production string load tested with completion fluid density and rate
- Tubing leak tested in production scenario

### **Casing Design Assumptions**

- Gas gravity 0.7
- Pore pressure gradient .468 psi/ft above the Wolfcamp, .676 psi/ft Wolfcamp and below
- .676 psi/ft fracture gradient above the Wolfcamp, .832 psi/ft Wolfcamp and below.
- 60°F average surface temperature and 1.5°/100ft temperature gradient
- Cementing loads based on slurries listed in Cement table, and post cement static loading
- Strings landed at neutral weight
- Gas kicks assumed at each casing shoe
- External pressure calculated with fluid gradients and pore pressure
- Production string load tested with completion fluid density and rate.
- Tubing leak tested in production scenario

### **Casing Design Assumptions**

- Gas gravity 0.7
- Pore pressure gradient .468 psi/ft above the Wolfcamp, .676 psi/ft Wolfcamp and below
- .676 psi/ft fracture gradient above the Wolfcamp, .832 psi/ft Wolfcamp and below.
- 60°F average surface temperature and 1.5°/100ft temperature gradient
- Cementing loads based on slurries listed in Cement table, and post cement static loading
- Strings landed at neutral weight
- Gas kicks assumed at each casing shoe
- External pressure calculated with fluid gradients and pore pressure
- Production string load tested with completion fluid density and rate
- Tubing leak tested in production scenario



## Hydrogen Sulfide Drilling

### Operations Plan

#### Tap Rock Resources

#### 1 H2S safety instructions to the following:

- Characteristics of H2S
- Physical effects and hazards
- Principal and operation of H2S detectors, warning system and briefing areas
- Evacuation procedures, routes and first aid
- Proper use of safety equipment & life support systems
- Essential personnel meeting medical evaluation criteria will receive additional training on the proper use of 30min pressure demand air packs

#### 2 H2S Detection and Alarm Systems:

- H2S sensor/detectors to be located on the drilling rig floor, in the base of the sub structure / cellar area, on the mud pits in the shale shaker area. Additional H2S detectors may be placed as deemed necessary
- An audio alarm system will be installed on the derrick floor and in the doghouse

#### 3 Windssocks and / Wind Streamers:

- Windssocks at mud pit area should be high enough to be visible
- Windssock on the rig floor and / top of doghouse should be high enough to be visible

#### 4 Condition Flags and Signs:

- Warning sign on access road to location
- Flags to be displayed on sign at entrance to location
  - Green Flag – Normal Safe Operation Condition
  - Yellow Flag – Potential Pressure and Danger
  - Red Flag – Danger (H2S present in dangerous concentrations) Only H2S trained personnel admitted on location

#### 5 Well Control Equipment:

- See Drilling Operations Plan Schematics

#### 6 Communication:

- While working under masks chalkboards will be used for communications
- Hand signals will be used where chalk board is inappropriate
- Two way radio will be used to communicate off location in case of emergency help is required.
- In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.



**7 Drilling Stem Testing:**

- No DST cores are planned at this time

8 Drilling contractor supervisor will be required to be familiar with the effects H<sub>2</sub>S has on tubulars good and other mechanical equipment

9 If H<sub>2</sub>S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H<sub>2</sub>S scavengers if necessary


**11 Emergency Contacts**

<b>Emergency Contacts</b>		
Carlsbad Police Department	575.887.7551	911
Carlsbad Medical Center	575.887.4100	911
Eddy County Fire Service	575.628.5450	911
Eddy County Sherriff	575.887.7551	911
Lea County Fire Service	575.391.2983	911
Lea County Sherriff	575.396.3611	911
Jal Police Department	575.395.2121	911
Jal Fire Department	575.395.2221	911
Tap Rock - Doug Sproul - Drilling	303-653-3518	



SECTION 14, TOWNSHIP 24-S, RANGE 31-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

DETAIL VIEW  
SCALE: 1" = 100'



LEASE NAME & WELL NO.: DOUBLE DIAMOND 24S21E1414 238H  
238H LATITUDE N 32.2109581 238H LONGITUDE W 103.7428434

SCALE: 1" = 100'  
0' 50' 100'

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY TAP ROCK OPERATING, L.L.C. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



TOPOGRAPHIC  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM




# Taprock Operating LLC

Double Diamond Fed Com  
24S31E #238H  
H<sub>2</sub>S Contingency Plan:  
2 Mile Radius Map

Sec. 14, Township 24S, Range 31E  
Eddy County, New Mexico



 Surface Hole Location



NAD 1983 New Mexico State Plane East  
FIPS 3001 Feet

PERMITS WEST

Prepared by Permits West, Inc., December 27, 2017  
for Taprock Operating, LLC










Project: Eddy County, New Mexico NAD83 NM east  
Site: Section 14-T24S-R31E  
Well: Double Diamond 24S 21E 1414 Well No. 238H  
Wellbore: Original Hole  
Design: rev1





## Planning Report

Database: DB\_Jul2216dt\_v14  
Company: Tap Rock Operating LLC  
Project: Eddy County, New Mexico NAD83 NM east  
Site: Section 14-T24S-R31E  
Well: Double Diamond 24S 21E 1414 Well No. 238H  
Wellbore: Original Hole  
Design: rev1

Local Co-ordinate Reference: Well Double Diamond 24S 21E 1414 Well No. 238H  
TVD Reference: RKB=3586+25 @ 3611.00ft  
MD Reference: RKB=3586+25 @ 3611.00ft  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature

Project	Eddy County, New Mexico NAD83 NM east		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Section 14-T24S-R31E				
Site Position:		Northing:	443,306.73 usft	Latitude:	32.21737448
From:	Map	Easting:	722,167.73 usft	Longitude:	-103.74860823
Position Uncertainty:	0.00 ft	Slot Radius:	13-3/16 "	Grid Convergence:	0.31 °

Well	Double Diamond 24S 21E 1414 Well No. 238H, Surf loc: 305 FSL 860 FEL Sec14-T24S-R31E					
Well Position	+N/-S	-2,324.73 ft	Northing:	440,982.00 usft	Latitude:	32.21095736
	+E/-W	1,795.27 ft	Easting:	723,963.00 usft	Longitude:	-103.74284469
Position Uncertainty	0.00 ft		Wellhead Elevation:		Ground Level:	3,586.00 ft

Wellbore	Original Hole				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2015	1/12/2018	6.97	60.02	47,852.21853548

Design	rev1			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	6.01

Plan Survey Tool Program	Date	1/28/2018		
Depth From (ft)	Depth To (ft)	Survey (Wellbore)	Tool Name	Remarks
1	0.00	9,500.00 rev1 (Original Hole)	GYRO-NS	
			OWSG Gyrocompass Gyro	
2	9,500.00	17,735.73 rev1 (Original Hole)	MWD	
			OWSG MWD - Standard	



## Planning Report

<b>Database:</b>	DB_Jul2216dt_v14	<b>Local Co-ordinate Reference:</b>	Well Double Diamond 24S 21E 1414 Well No. 238H
<b>Company:</b>	Tap Rock Operating LLC	<b>TVD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Project:</b>	Eddy County, New Mexico NAD83 NM east	<b>MD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Site:</b>	Section 14-T24S-R31E	<b>North Reference:</b>	Grid
<b>Well:</b>	Double Diamond 24S 21E 1414 Well No. 238H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Original Hole		
<b>Design:</b>	rev1		

### Plan Sections

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,500.00	3.00	163.00	1,499.86	-7.51	2.30	1.00	1.00	0.00	163.00	
4,300.00	3.00	163.00	4,296.03	-147.65	45.14	0.00	0.00	0.00	0.00	
4,600.00	0.00	163.00	4,595.89	-155.16	47.44	1.00	-1.00	0.00	180.00	
9,504.11	0.00	163.00	9,500.00	-155.16	47.44	0.00	0.00	0.00	163.00	
10,039.61	8.03	108.65	10,033.75	-167.14	82.94	1.50	1.50	-10.15	108.65	
11,688.29	8.03	108.65	11,666.25	-240.82	301.22	0.00	0.00	0.00	0.00	
12,223.79	0.00	0.00	12,200.00	-252.80	336.73	1.50	-1.50	0.00	180.00	Double Diamond Fed
12,352.29	0.00	0.00	12,328.50	-252.80	336.73	0.00	0.00	0.00	0.00	
12,402.29	5.00	14.35	12,378.44	-250.69	337.27	10.00	10.00	0.00	14.35	
13,052.29	70.00	14.35	12,866.90	112.43	430.17	10.00	10.00	0.00	0.00	
13,304.79	90.20	14.35	12,910.09	352.17	491.50	8.00	8.00	0.00	0.00	
13,598.50	90.20	359.66	12,909.06	642.88	527.23	5.00	0.00	-5.00	-89.97	
17,735.73	90.20	359.66	12,894.50	4,780.01	503.00	0.00	0.00	0.00	0.00	Double Diamond Fed





# Planning Report

Database: DB\_Jul2216dt\_v14  
 Company: Tap Rock Operating LLC  
 Project: Eddy County, New Mexico NAD83 NM east  
 Site: Section 14-T24S-R31E  
 Well: Double Diamond 24S 21E 1414 Well No. 238H  
 Wellbore: Original Hole  
 Design: rev1

Local Co-ordinate Reference: Well Double Diamond 24S 21E 1414 Well No. 238H  
 TVD Reference: RKB=3586+25 @ 3611.00ft  
 MD Reference: RKB=3586+25 @ 3611.00ft  
 North Reference: Grid  
 Survey Calculation Method: Minimum Curvature

## Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
KOP Begin 1°/100' build									
1,300.00	1.00	163.00	1,299.99	-0.83	0.26	-0.80	1.00	1.00	0.00
1,400.00	2.00	163.00	1,399.96	-3.34	1.02	-3.21	1.00	1.00	0.00
1,500.00	3.00	163.00	1,499.86	-7.51	2.30	-7.23	1.00	1.00	0.00
Begin 3.00° tangent									
1,600.00	3.00	163.00	1,599.73	-12.51	3.83	-12.04	0.00	0.00	0.00
1,700.00	3.00	163.00	1,699.59	-17.52	5.36	-16.86	0.00	0.00	0.00
1,800.00	3.00	163.00	1,799.45	-22.52	6.89	-21.68	0.00	0.00	0.00
1,900.00	3.00	163.00	1,899.31	-27.53	8.42	-26.50	0.00	0.00	0.00
2,000.00	3.00	163.00	1,999.18	-32.53	9.95	-31.31	0.00	0.00	0.00
2,100.00	3.00	163.00	2,099.04	-37.54	11.48	-36.13	0.00	0.00	0.00
2,200.00	3.00	163.00	2,198.90	-42.54	13.01	-40.95	0.00	0.00	0.00
2,300.00	3.00	163.00	2,298.77	-47.55	14.54	-45.77	0.00	0.00	0.00
2,400.00	3.00	163.00	2,398.63	-52.55	16.07	-50.58	0.00	0.00	0.00
2,500.00	3.00	163.00	2,498.49	-57.56	17.60	-55.40	0.00	0.00	0.00
2,600.00	3.00	163.00	2,598.36	-62.56	19.13	-60.22	0.00	0.00	0.00
2,700.00	3.00	163.00	2,698.22	-67.57	20.66	-65.04	0.00	0.00	0.00
2,800.00	3.00	163.00	2,798.08	-72.57	22.19	-69.85	0.00	0.00	0.00
2,900.00	3.00	163.00	2,897.94	-77.58	23.72	-74.67	0.00	0.00	0.00
3,000.00	3.00	163.00	2,997.81	-82.58	25.25	-79.49	0.00	0.00	0.00
3,100.00	3.00	163.00	3,097.67	-87.59	26.78	-84.30	0.00	0.00	0.00
3,200.00	3.00	163.00	3,197.53	-92.59	28.31	-89.12	0.00	0.00	0.00
3,300.00	3.00	163.00	3,297.40	-97.60	29.84	-93.94	0.00	0.00	0.00
3,400.00	3.00	163.00	3,397.26	-102.60	31.37	-98.76	0.00	0.00	0.00
3,500.00	3.00	163.00	3,497.12	-107.61	32.90	-103.57	0.00	0.00	0.00
3,600.00	3.00	163.00	3,596.99	-112.61	34.43	-108.39	0.00	0.00	0.00
3,700.00	3.00	163.00	3,696.85	-117.62	35.96	-113.21	0.00	0.00	0.00
3,800.00	3.00	163.00	3,796.71	-122.62	37.49	-118.03	0.00	0.00	0.00
3,900.00	3.00	163.00	3,896.57	-127.63	39.02	-122.84	0.00	0.00	0.00
4,000.00	3.00	163.00	3,996.44	-132.63	40.55	-127.66	0.00	0.00	0.00
4,100.00	3.00	163.00	4,096.30	-137.64	42.08	-132.48	0.00	0.00	0.00
4,200.00	3.00	163.00	4,196.16	-142.64	43.61	-137.30	0.00	0.00	0.00
4,300.00	3.00	163.00	4,296.03	-147.65	45.14	-142.11	0.00	0.00	0.00
Begin 1°/100' drop									
4,400.00	2.00	163.00	4,395.93	-151.82	46.42	-146.13	1.00	-1.00	0.00
4,500.00	1.00	163.00	4,495.89	-154.32	47.18	-148.54	1.00	-1.00	0.00
4,600.00	0.00	163.00	4,595.89	-155.16	47.44	-149.34	1.00	-1.00	0.00
Begin vertical hold									
4,700.00	0.00	0.00	4,695.89	-155.16	47.44	-149.34	0.00	0.00	0.00





# Planning Report

Database:	DB_Jul2216dt_v14	Local Co-ordinate Reference:	Well Double Diamond 24S 21E 1414 Well No. 238H
Company:	Tap Rock Operating LLC	TVD Reference:	RKB=3586+25 @ 3611.00ft
Project:	Eddy County, New Mexico NAD83 NM east	MD Reference:	RKB=3586+25 @ 3611.00ft
Site:	Section 14-T24S-R31E	North Reference:	Grid
Well:	Double Diamond 24S 21E 1414 Well No. 238H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev1		

## Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,800.00	0.00	0.00	4,795.89	-155.16	47.44	-149.34	0.00	0.00	0.00
4,900.00	0.00	0.00	4,895.89	-155.16	47.44	-149.34	0.00	0.00	0.00
5,000.00	0.00	0.00	4,995.89	-155.16	47.44	-149.34	0.00	0.00	0.00
5,100.00	0.00	0.00	5,095.89	-155.16	47.44	-149.34	0.00	0.00	0.00
5,200.00	0.00	0.00	5,195.89	-155.16	47.44	-149.34	0.00	0.00	0.00
5,300.00	0.00	0.00	5,295.89	-155.16	47.44	-149.34	0.00	0.00	0.00
5,400.00	0.00	0.00	5,395.89	-155.16	47.44	-149.34	0.00	0.00	0.00
5,500.00	0.00	0.00	5,495.89	-155.16	47.44	-149.34	0.00	0.00	0.00
5,600.00	0.00	0.00	5,595.89	-155.16	47.44	-149.34	0.00	0.00	0.00
5,700.00	0.00	0.00	5,695.89	-155.16	47.44	-149.34	0.00	0.00	0.00
5,800.00	0.00	0.00	5,795.89	-155.16	47.44	-149.34	0.00	0.00	0.00
5,900.00	0.00	0.00	5,895.89	-155.16	47.44	-149.34	0.00	0.00	0.00
6,000.00	0.00	0.00	5,995.89	-155.16	47.44	-149.34	0.00	0.00	0.00
6,100.00	0.00	0.00	6,095.89	-155.16	47.44	-149.34	0.00	0.00	0.00
6,200.00	0.00	0.00	6,195.89	-155.16	47.44	-149.34	0.00	0.00	0.00
6,300.00	0.00	0.00	6,295.89	-155.16	47.44	-149.34	0.00	0.00	0.00
6,400.00	0.00	163.00	6,395.89	-155.16	47.44	-149.34	0.00	0.00	0.00
6,500.00	0.00	0.00	6,495.89	-155.16	47.44	-149.34	0.00	0.00	0.00
6,600.00	0.00	0.00	6,595.89	-155.16	47.44	-149.34	0.00	0.00	0.00
6,700.00	0.00	0.00	6,695.89	-155.16	47.44	-149.34	0.00	0.00	0.00
6,800.00	0.00	163.00	6,795.89	-155.16	47.44	-149.34	0.00	0.00	0.00
6,900.00	0.00	0.00	6,895.89	-155.16	47.44	-149.34	0.00	0.00	0.00
7,000.00	0.00	0.00	6,995.89	-155.16	47.44	-149.34	0.00	0.00	0.00
7,100.00	0.00	0.00	7,095.89	-155.16	47.44	-149.34	0.00	0.00	0.00
7,200.00	0.00	0.00	7,195.89	-155.16	47.44	-149.34	0.00	0.00	0.00
7,300.00	0.00	0.00	7,295.89	-155.16	47.44	-149.34	0.00	0.00	0.00
7,400.00	0.00	0.00	7,395.89	-155.16	47.44	-149.34	0.00	0.00	0.00
7,500.00	0.00	0.00	7,495.89	-155.16	47.44	-149.34	0.00	0.00	0.00
7,600.00	0.00	0.00	7,595.89	-155.16	47.44	-149.34	0.00	0.00	0.00
7,700.00	0.00	0.00	7,695.89	-155.16	47.44	-149.34	0.00	0.00	0.00
7,800.00	0.00	0.00	7,795.89	-155.16	47.44	-149.34	0.00	0.00	0.00
7,900.00	0.00	0.00	7,895.89	-155.16	47.44	-149.34	0.00	0.00	0.00
8,000.00	0.00	0.00	7,995.89	-155.16	47.44	-149.34	0.00	0.00	0.00
8,100.00	0.00	0.00	8,095.89	-155.16	47.44	-149.34	0.00	0.00	0.00
8,200.00	0.00	0.00	8,195.89	-155.16	47.44	-149.34	0.00	0.00	0.00
8,300.00	0.00	0.00	8,295.89	-155.16	47.44	-149.34	0.00	0.00	0.00
8,400.00	0.00	0.00	8,395.89	-155.16	47.44	-149.34	0.00	0.00	0.00
8,500.00	0.00	0.00	8,495.89	-155.16	47.44	-149.34	0.00	0.00	0.00
8,600.00	0.00	0.00	8,595.89	-155.16	47.44	-149.34	0.00	0.00	0.00
8,700.00	0.00	0.00	8,695.89	-155.16	47.44	-149.34	0.00	0.00	0.00
8,800.00	0.00	0.00	8,795.89	-155.16	47.44	-149.34	0.00	0.00	0.00
8,900.00	0.00	0.00	8,895.89	-155.16	47.44	-149.34	0.00	0.00	0.00
9,000.00	0.00	0.00	8,995.89	-155.16	47.44	-149.34	0.00	0.00	0.00
9,100.00	0.00	0.00	9,095.89	-155.16	47.44	-149.34	0.00	0.00	0.00
9,200.00	0.00	0.00	9,195.89	-155.16	47.44	-149.34	0.00	0.00	0.00
9,300.00	0.00	0.00	9,295.89	-155.16	47.44	-149.34	0.00	0.00	0.00
9,400.00	0.00	0.00	9,395.89	-155.16	47.44	-149.34	0.00	0.00	0.00
9,500.00	0.00	0.00	9,495.89	-155.16	47.44	-149.34	0.00	0.00	0.00
9,504.11	0.00	0.00	9,500.00	-155.16	47.44	-149.34	0.00	0.00	0.00
Begin 1.5°/100' build									
9,600.00	1.44	108.65	9,595.88	-155.54	48.58	-149.60	1.50	1.50	0.00
9,700.00	2.94	108.65	9,695.80	-156.76	52.19	-150.44	1.50	1.50	0.00



# Planning Report

**Database:** DB\_Jul2216dt\_v14  
**Company:** Tap Rock Operating LLC  
**Project:** Eddy County, New Mexico NAD83 NM east  
**Site:** Section 14-T24S-R31E  
**Well:** Double Diamond 24S 21E 1414 Well No. 238H  
**Wellbore:** Original Hole  
**Design:** rev1

**Local Co-ordinate Reference:** Well Double Diamond 24S 21E 1414 Well No. 238H  
**TVD Reference:** RKB=3586+25 @ 3611.00ft  
**MD Reference:** RKB=3586+25 @ 3611.00ft  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature

## Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
9,800.00	4.44	108.65	9,795.59	-158.82	58.29	-151.85	1.50	1.50	0.00
9,900.00	5.94	108.65	9,895.18	-161.71	66.86	-153.83	1.50	1.50	0.00
10,000.00	7.44	108.65	9,994.50	-165.44	77.89	-156.38	1.50	1.50	0.00
10,039.61	8.03	108.65	10,033.75	-167.14	82.94	-157.54	1.50	1.50	0.00
Begin 8.03° tangent									
10,100.00	8.03	108.65	10,093.54	-169.84	90.94	-159.39	0.00	0.00	0.00
10,200.00	8.03	108.65	10,192.56	-174.31	104.18	-162.45	0.00	0.00	0.00
10,300.00	8.03	108.65	10,291.58	-178.78	117.42	-165.51	0.00	0.00	0.00
10,400.00	8.03	108.65	10,390.60	-183.25	130.66	-168.57	0.00	0.00	0.00
10,500.00	8.03	108.65	10,489.62	-187.71	143.90	-171.63	0.00	0.00	0.00
10,600.00	8.03	108.65	10,588.64	-192.18	157.14	-174.68	0.00	0.00	0.00
10,700.00	8.03	108.65	10,687.66	-196.65	170.38	-177.74	0.00	0.00	0.00
10,800.00	8.03	108.65	10,786.68	-201.12	183.62	-180.80	0.00	0.00	0.00
10,900.00	8.03	108.65	10,885.70	-205.59	196.86	-183.86	0.00	0.00	0.00
11,000.00	8.03	108.65	10,984.71	-210.06	210.10	-186.92	0.00	0.00	0.00
11,100.00	8.03	108.65	11,083.73	-214.53	223.34	-189.98	0.00	0.00	0.00
11,200.00	8.03	108.65	11,182.75	-219.00	236.58	-193.04	0.00	0.00	0.00
11,300.00	8.03	108.65	11,281.77	-223.46	249.81	-196.10	0.00	0.00	0.00
11,400.00	8.03	108.65	11,380.79	-227.93	263.05	-199.16	0.00	0.00	0.00
11,500.00	8.03	108.65	11,479.81	-232.40	276.29	-202.21	0.00	0.00	0.00
11,600.00	8.03	108.65	11,578.83	-236.87	289.53	-205.27	0.00	0.00	0.00
11,688.29	8.03	108.65	11,666.25	-240.82	301.22	-207.97	0.00	0.00	0.00
Begin 1.5°/100' drop									
11,700.00	7.86	108.65	11,677.85	-241.33	302.76	-208.33	1.50	-1.50	0.00
11,800.00	6.36	108.65	11,777.08	-245.29	314.48	-211.04	1.50	-1.50	0.00
11,900.00	4.86	108.65	11,876.60	-248.41	323.74	-213.17	1.50	-1.50	0.00
12,000.00	3.36	108.65	11,976.34	-250.70	330.52	-214.74	1.50	-1.50	0.00
12,100.00	1.86	108.65	12,076.23	-252.16	334.83	-215.74	1.50	-1.50	0.00
12,200.00	0.36	108.65	12,176.21	-252.78	336.66	-216.16	1.50	-1.50	0.00
12,223.79	0.00	0.00	12,200.00	-252.80	336.73	-216.18	1.50	-1.50	0.00
Begin vertical hold									
12,300.00	0.00	0.00	12,276.21	-252.80	336.73	-216.18	0.00	0.00	0.00
12,352.29	0.00	0.00	12,328.50	-252.80	336.73	-216.18	0.00	0.00	0.00
Begin 10°/100' build									
12,400.00	4.77	14.35	12,376.15	-250.88	337.22	-214.21	10.00	10.00	0.00
12,402.29	5.00	14.35	12,378.44	-250.69	337.27	-214.02	10.00	10.00	0.00
12,500.00	14.77	14.35	12,474.58	-234.46	341.42	-197.44	10.00	10.00	0.00
12,600.00	24.77	14.35	12,568.56	-201.73	349.80	-164.02	10.00	10.00	0.00
12,700.00	34.77	14.35	12,655.26	-153.68	362.09	-114.95	10.00	10.00	0.00
12,800.00	44.77	14.35	12,732.02	-91.79	377.92	-51.74	10.00	10.00	0.00
12,900.00	54.77	14.35	12,796.52	-17.92	396.82	23.71	10.00	10.00	0.00
13,000.00	64.77	14.35	12,846.80	65.68	418.21	109.08	10.00	10.00	0.00
13,052.29	70.00	14.35	12,866.90	112.43	430.17	156.83	10.00	10.00	0.00
Begin 8°/100' build									
13,100.00	73.82	14.35	12,881.72	156.36	441.40	201.69	8.00	8.00	0.00
13,200.00	81.82	14.35	12,902.80	250.98	465.61	298.32	8.00	8.00	0.00
13,300.00	89.82	14.35	12,910.09	347.52	490.31	396.92	8.00	8.00	0.00
13,304.79	90.20	14.35	12,910.09	352.16	491.50	401.66	8.00	8.00	0.00
Begin 5°/100' turn									
13,400.00	90.20	9.59	12,909.76	445.28	511.24	496.33	5.00	0.00	-5.00
13,500.00	90.20	4.59	12,909.40	544.48	523.57	596.28	5.00	0.00	-5.00





## Planning Report

Database:	DB_Jul2216dt_v14	Local Co-ordinate Reference:	Well Double Diamond 24S 21E 1414 Well No. 238H
Company:	Tap Rock Operating LLC	TVD Reference:	RKB=3586+25 @ 3611.00ft
Project:	Eddy County, New Mexico NAD83 NM east	MD Reference:	RKB=3586+25 @ 3611.00ft
Site:	Section 14-T24S-R31E	North Reference:	Grid
Well:	Double Diamond 24S 21E 1414 Well No. 238H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev1		

### Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
13,598.50	90.20	359.66	12,909.06	642.88	527.23	694.52	5.00	0.00	-5.00
Begin 90.20° lateral									
13,600.00	90.20	359.66	12,909.05	644.38	527.22	696.01	0.00	0.00	0.00
13,700.00	90.20	359.66	12,908.70	744.38	526.64	795.40	0.00	0.00	0.00
13,800.00	90.20	359.66	12,908.35	844.38	526.05	894.79	0.00	0.00	0.00
13,900.00	90.20	359.66	12,908.00	944.37	525.46	994.17	0.00	0.00	0.00
14,000.00	90.20	359.66	12,907.64	1,044.37	524.88	1,093.56	0.00	0.00	0.00
14,100.00	90.20	359.66	12,907.29	1,144.37	524.29	1,192.95	0.00	0.00	0.00
14,200.00	90.20	359.66	12,906.94	1,244.37	523.71	1,292.34	0.00	0.00	0.00
14,300.00	90.20	359.66	12,906.59	1,344.36	523.12	1,391.72	0.00	0.00	0.00
14,400.00	90.20	359.66	12,906.24	1,444.36	522.54	1,491.11	0.00	0.00	0.00
14,500.00	90.20	359.66	12,905.89	1,544.36	521.95	1,590.50	0.00	0.00	0.00
14,600.00	90.20	359.66	12,905.53	1,644.36	521.36	1,689.89	0.00	0.00	0.00
14,700.00	90.20	359.66	12,905.18	1,744.35	520.78	1,789.27	0.00	0.00	0.00
14,800.00	90.20	359.66	12,904.83	1,844.35	520.19	1,888.66	0.00	0.00	0.00
14,900.00	90.20	359.66	12,904.48	1,944.35	519.61	1,988.05	0.00	0.00	0.00
15,000.00	90.20	359.66	12,904.13	2,044.35	519.02	2,087.44	0.00	0.00	0.00
15,100.00	90.20	359.66	12,903.77	2,144.35	518.44	2,186.82	0.00	0.00	0.00
15,200.00	90.20	359.66	12,903.42	2,244.34	517.85	2,286.21	0.00	0.00	0.00
15,300.00	90.20	359.66	12,903.07	2,344.34	517.27	2,385.60	0.00	0.00	0.00
15,400.00	90.20	359.66	12,902.72	2,444.34	516.68	2,484.99	0.00	0.00	0.00
15,500.00	90.20	359.66	12,902.37	2,544.34	516.09	2,584.37	0.00	0.00	0.00
15,600.00	90.20	359.66	12,902.01	2,644.33	515.51	2,683.76	0.00	0.00	0.00
15,700.00	90.20	359.66	12,901.66	2,744.33	514.92	2,783.15	0.00	0.00	0.00
15,800.00	90.20	359.66	12,901.31	2,844.33	514.34	2,882.53	0.00	0.00	0.00
15,900.00	90.20	359.66	12,900.96	2,944.33	513.75	2,981.92	0.00	0.00	0.00
16,000.00	90.20	359.66	12,900.61	3,044.32	513.17	3,081.31	0.00	0.00	0.00
16,100.00	90.20	359.66	12,900.26	3,144.32	512.58	3,180.70	0.00	0.00	0.00
16,200.00	90.20	359.66	12,899.90	3,244.32	511.99	3,280.08	0.00	0.00	0.00
16,300.00	90.20	359.66	12,899.55	3,344.32	511.41	3,379.47	0.00	0.00	0.00
16,400.00	90.20	359.66	12,899.20	3,444.32	510.82	3,478.86	0.00	0.00	0.00
16,500.00	90.20	359.66	12,898.85	3,544.31	510.24	3,578.25	0.00	0.00	0.00
16,600.00	90.20	359.66	12,898.50	3,644.31	509.65	3,677.63	0.00	0.00	0.00
16,700.00	90.20	359.66	12,898.14	3,744.31	509.07	3,777.02	0.00	0.00	0.00
16,800.00	90.20	359.66	12,897.79	3,844.31	508.48	3,876.41	0.00	0.00	0.00
16,900.00	90.20	359.66	12,897.44	3,944.30	507.90	3,975.80	0.00	0.00	0.00
17,000.00	90.20	359.66	12,897.09	4,044.30	507.31	4,075.18	0.00	0.00	0.00
17,100.00	90.20	359.66	12,896.74	4,144.30	506.72	4,174.57	0.00	0.00	0.00
17,200.00	90.20	359.66	12,896.39	4,244.30	506.14	4,273.96	0.00	0.00	0.00
17,300.00	90.20	359.66	12,896.03	4,344.29	505.55	4,373.35	0.00	0.00	0.00
17,400.00	90.20	359.66	12,895.68	4,444.29	504.97	4,472.73	0.00	0.00	0.00
17,500.00	90.20	359.66	12,895.33	4,544.29	504.38	4,572.12	0.00	0.00	0.00
17,600.00	90.20	359.66	12,894.98	4,644.29	503.80	4,671.51	0.00	0.00	0.00
17,700.00	90.20	359.66	12,894.63	4,744.28	503.21	4,770.90	0.00	0.00	0.00
17,735.73	90.20	359.66	12,894.50	4,780.01	503.00	4,806.40	0.00	0.00	0.00

PBHL/TD 17735.73 MD/12894.50 TVD



## Planning Report

<b>Database:</b>	DB_Jul2216dt_v14	<b>Local Co-ordinate Reference:</b>	Well Double Diamond 24S 21E 1414 Well No. 238H
<b>Company:</b>	Tap Rock Operating LLC	<b>TVD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Project:</b>	Eddy County, New Mexico NAD83 NM east	<b>MD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Site:</b>	Section 14-T24S-R31E	<b>North Reference:</b>	Grid
<b>Well:</b>	Double Diamond 24S 21E 1414 Well No. 238H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Original Hole		
<b>Design:</b>	rev1		

### Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Double Diamond Fed 23 - plan hits target center - Point	0.00	0.00	12,200.00	-252.80	336.73	440,729.20	724,299.73	32.21025739	-103.74176047
Double Diamond Fed #2 - plan hits target center - Point	0.00	0.00	12,894.50	4,780.01	503.00	445,762.00	724,466.00	32.22408884	-103.74113323

### Casing Points

Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (")	Hole Diameter (")
1,000.00	1,000.00	13 3/8" Casing @ 1000 TVD	13-3/8	17-1/2
4,704.11	4,700.00	9 5/8" Casing @ 4700 TVD	9-5/8	12-1/4
13,104.53	12,882.97	7" Casing @ 13104.5 MD	7	8-3/4

### Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
1,200.00	1,200.00	0.00	0.00	KOP Begin 1°/100' build
1,500.00	1,499.86	-7.51	2.30	Begin 3.00° tangent
4,300.00	4,296.03	-147.65	45.14	Begin 1°/100' drop
4,600.00	4,595.89	-155.16	47.44	Begin vertical hold
9,504.11	9,500.00	-155.16	47.44	Begin 1.5°/100' build
10,039.61	10,033.75	-167.14	82.94	Begin 8.03° tangent
11,688.29	11,666.25	-240.82	301.22	Begin 1.5°/100' drop
12,223.79	12,200.00	-252.80	336.73	Begin vertical hold
12,352.29	12,328.50	-252.80	336.73	Begin 10°/100' build
13,052.29	12,866.90	-250.69	337.27	Begin 8°/100' build
13,304.79	12,910.09	112.43	430.17	Begin 5°/100' turn
13,598.50	12,909.06	352.17	491.50	Begin 90.20° lateral
17,735.73	12,894.50	642.88	527.23	PBHL/TD 17735.73 MD/12894.50 TVD



## Planning Report - Geographic

<b>Database:</b>	DB_Jul2216dt_v14	<b>Local Co-ordinate Reference:</b>	Well Double Diamond 24S 21E 1414 Well No. 238H
<b>Company:</b>	Tap Rock Operating LLC	<b>TVD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Project:</b>	Eddy County, New Mexico NAD83 NM east	<b>MD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Site:</b>	Section 14-T24S-R31E	<b>North Reference:</b>	Grid
<b>Well:</b>	Double Diamond 24S 21E 1414 Well No. 238H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Original Hole		
<b>Design:</b>	rev1		

<b>Project</b>	Eddy County, New Mexico NAD83 NM east		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	New Mexico Eastern Zone		

Site		Section 14-T24S-R31E			
Site Position:		Northing:	443,306.73 usft	Latitude:	32.21737448
From:	Map	Easting:	722,167.73 usft	Longitude:	-103.74860823
Position Uncertainty:	0.00 ft	Slot Radius:	13-3/16 "	Grid Convergence:	0.31 °

Well	Double Diamond 24S 21E 1414 Well No. 238H, Surf loc: 305 FSL 860 FEL Sec14-T24S-R31E					
Well Position	+N/-S	0.00 ft	Northing:	440,982.00 usft	Latitude:	32.21095736
	+E/-W	0.00 ft	Easting:	723,963.00 usft	Longitude:	-103.74284469
Position Uncertainty		0.00 ft	Wellhead Elevation:		Ground Level:	3,586.00 ft

<b>Wellbore</b>	Original Hole				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF2015	1/12/2018	6.97	60.02	47,852.21853548

**Design** rev1

### Audit Notes:

<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>	0.00
<b>Vertical Section:</b>	<b>Depth From (TVD) (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>
	0.00	0.00	0.00	6.01

**Plan Survey Tool Program** Date 1/28/2018

Depth From (ft)	Depth To (ft)	Survey (Wellbore)	Tool Name	Remarks
1	0.00	9,500.00 rev1 (Original Hole)	GYRO-NS OWSG Gyrocompass Gyro	
2	9,500.00	17,735.73 rev1 (Original Hole)	MWD OWSG MWD - Standard	





# Planning Report - Geographic

Database: DB\_Jul2216dt\_v14

Local Co-ordinate Reference:

Well Double Diamond 24S 21E 1414 Well No. 238H

Company: Tap Rock Operating LLC

TVD Reference:

RKB=3586+25 @ 3611.00ft

Project: Eddy County, New Mexico NAD83 NM east

MD Reference:

RKB=3586+25 @ 3611.00ft

Site: Section 14-T24S-R31E

North Reference:

Grid

Well: Double Diamond 24S 21E 1414 Well No. 238H

Survey Calculation Method:

Minimum Curvature

Wellbore: Original Hole

Design: rev1

## Plan Sections

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,500.00	3.00	163.00	1,499.86	-7.51	2.30	1.00	1.00	0.00	163.00	
4,300.00	3.00	163.00	4,296.03	-147.65	45.14	0.00	0.00	0.00	0.00	
4,600.00	0.00	163.00	4,595.89	-155.16	47.44	1.00	-1.00	0.00	180.00	
9,504.11	0.00	163.00	9,500.00	-155.16	47.44	0.00	0.00	0.00	163.00	
10,039.61	8.03	108.65	10,033.75	-167.14	82.94	1.50	1.50	-10.15	108.65	
11,688.29	8.03	108.65	11,666.25	-240.82	301.22	0.00	0.00	0.00	0.00	
12,223.79	0.00	0.00	12,200.00	-252.80	336.73	1.50	-1.50	0.00	180.00	Double Diamond Fed
12,352.29	0.00	0.00	12,328.50	-252.80	336.73	0.00	0.00	0.00	0.00	
12,402.29	5.00	14.35	12,378.44	-250.69	337.27	10.00	10.00	0.00	14.35	
13,052.29	70.00	14.35	12,866.90	112.43	430.17	10.00	10.00	0.00	0.00	
13,304.79	90.20	14.35	12,910.09	352.17	491.50	8.00	8.00	0.00	0.00	
13,598.50	90.20	359.66	12,909.06	642.88	527.23	5.00	0.00	-5.00	-89.97	
17,735.73	90.20	359.66	12,894.50	4,780.01	503.00	0.00	0.00	0.00	0.00	Double Diamond Fed



## Planning Report - Geographic

Database: DB\_Jul2216dt\_v14

Local Co-ordinate Reference:

Well Double Diamond 24S 21E 1414 Well No.  
238H

Company: Tap Rock Operating LLC

TVD Reference:

RKB=3586+25 @ 3611.00ft

Project: Eddy County, New Mexico NAD83 NM east

MD Reference:

RKB=3586+25 @ 3611.00ft

Site: Section 14-T24S-R31E

North Reference:

Grid

Well: Double Diamond 24S 21E 1414 Well No.  
238H

Survey Calculation Method:

Minimum Curvature

Wellbore: Original Hole

Design: rev1

## Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
100.00	0.00	0.00	100.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
200.00	0.00	0.00	200.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
300.00	0.00	0.00	300.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
400.00	0.00	0.00	400.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
500.00	0.00	0.00	500.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
600.00	0.00	0.00	600.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
700.00	0.00	0.00	700.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
800.00	0.00	0.00	800.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
900.00	0.00	0.00	900.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
1,000.00	0.00	0.00	1,000.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
1,100.00	0.00	0.00	1,100.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
1,200.00	0.00	0.00	1,200.00	0.00	0.00	440,982.00	723,963.00	32.21095736	-103.74284469
KOP Begin 1°/100' build									
1,300.00	1.00	163.00	1,299.99	-0.83	0.26	440,981.17	723,963.25	32.21095507	-103.74284388
1,400.00	2.00	163.00	1,399.96	-3.34	1.02	440,978.66	723,964.02	32.21094817	-103.74284145
1,500.00	3.00	163.00	1,499.86	-7.51	2.30	440,974.49	723,965.29	32.21093669	-103.74283740
Begin 3.00° tangent									
1,600.00	3.00	163.00	1,599.73	-12.51	3.83	440,969.49	723,966.82	32.21092291	-103.74283254
1,700.00	3.00	163.00	1,699.59	-17.52	5.36	440,964.48	723,968.35	32.21090913	-103.74282768
1,800.00	3.00	163.00	1,799.45	-22.52	6.89	440,959.48	723,969.88	32.21089535	-103.74282282
1,900.00	3.00	163.00	1,899.31	-27.53	8.42	440,954.47	723,971.41	32.21088157	-103.74281796
2,000.00	3.00	163.00	1,999.18	-32.53	9.95	440,949.47	723,972.94	32.21086779	-103.74281310
2,100.00	3.00	163.00	2,099.04	-37.54	11.48	440,944.46	723,974.47	32.21085401	-103.74280825
2,200.00	3.00	163.00	2,198.90	-42.54	13.01	440,939.46	723,976.00	32.21084023	-103.74280339
2,300.00	3.00	163.00	2,298.77	-47.55	14.54	440,934.45	723,977.53	32.21082645	-103.74279853
2,400.00	3.00	163.00	2,398.63	-52.55	16.07	440,929.45	723,979.06	32.21081267	-103.74279367
2,500.00	3.00	163.00	2,498.49	-57.56	17.60	440,924.44	723,980.59	32.21079888	-103.74278881
2,600.00	3.00	163.00	2,598.36	-62.56	19.13	440,919.44	723,982.12	32.21078510	-103.74278395
2,700.00	3.00	163.00	2,698.22	-67.57	20.66	440,914.43	723,983.65	32.21077132	-103.74277910
2,800.00	3.00	163.00	2,798.08	-72.57	22.19	440,909.43	723,985.18	32.21075754	-103.74277424
2,900.00	3.00	163.00	2,897.94	-77.58	23.72	440,904.42	723,986.71	32.21074376	-103.74276938
3,000.00	3.00	163.00	2,997.81	-82.58	25.25	440,899.42	723,988.24	32.21072998	-103.74276452
3,100.00	3.00	163.00	3,097.67	-87.59	26.78	440,894.41	723,989.77	32.21071620	-103.74275966
3,200.00	3.00	163.00	3,197.53	-92.59	28.31	440,889.41	723,991.30	32.21070242	-103.74275480
3,300.00	3.00	163.00	3,297.40	-97.60	29.84	440,884.40	723,992.83	32.21068864	-103.74274995
3,400.00	3.00	163.00	3,397.26	-102.60	31.37	440,879.40	723,994.36	32.21067486	-103.74274509
3,500.00	3.00	163.00	3,497.12	-107.61	32.90	440,874.39	723,995.89	32.21066108	-103.74274023
3,600.00	3.00	163.00	3,596.99	-112.61	34.43	440,869.39	723,997.43	32.21064730	-103.74273537
3,700.00	3.00	163.00	3,696.85	-117.62	35.96	440,864.38	723,998.96	32.21063352	-103.74273051
3,800.00	3.00	163.00	3,796.71	-122.62	37.49	440,859.38	724,000.49	32.21061974	-103.74272565
3,900.00	3.00	163.00	3,896.57	-127.63	39.02	440,854.37	724,002.02	32.21060596	-103.74272080
4,000.00	3.00	163.00	3,996.44	-132.63	40.55	440,849.37	724,003.55	32.21059218	-103.74271594
4,100.00	3.00	163.00	4,096.30	-137.64	42.08	440,844.36	724,005.08	32.21057840	-103.74271108
4,200.00	3.00	163.00	4,196.16	-142.64	43.61	440,839.36	724,006.61	32.21056462	-103.74270622
4,300.00	3.00	163.00	4,296.03	-147.65	45.14	440,834.35	724,008.14	32.21055084	-103.74270136
Begin 1°/100' drop									
4,400.00	2.00	163.00	4,395.93	-151.82	46.42	440,830.18	724,009.41	32.21053935	-103.74269731
4,500.00	1.00	163.00	4,495.89	-154.32	47.18	440,827.68	724,010.18	32.21053246	-103.74269488
4,600.00	0.00	163.00	4,595.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
Begin vertical hold									
4,700.00	0.00	0.00	4,695.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407





## Planning Report - Geographic

Database: DB\_Jul2216dt\_v14

Local Co-ordinate Reference:

Well Double Diamond 24S 21E 1414 Well No.  
238H

Company: Tap Rock Operating LLC

TVD Reference:

RKB=3586+25 @ 3611.00ft

Project: Eddy County, New Mexico NAD83 NM east

MD Reference:

RKB=3586+25 @ 3611.00ft

Site: Section 14-T24S-R31E

North Reference:

Grid

Well: Double Diamond 24S 21E 1414 Well No.  
238H

Survey Calculation Method:

Minimum Curvature

Wellbore: Original Hole

Design: rev1

## Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
4,800.00	0.00	0.00	4,795.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
4,900.00	0.00	0.00	4,895.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
5,000.00	0.00	0.00	4,995.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
5,100.00	0.00	0.00	5,095.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
5,200.00	0.00	0.00	5,195.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
5,300.00	0.00	0.00	5,295.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
5,400.00	0.00	0.00	5,395.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
5,500.00	0.00	0.00	5,495.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
5,600.00	0.00	0.00	5,595.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
5,700.00	0.00	0.00	5,695.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
5,800.00	0.00	0.00	5,795.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
5,900.00	0.00	0.00	5,895.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
6,000.00	0.00	0.00	5,995.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
6,100.00	0.00	0.00	6,095.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
6,200.00	0.00	0.00	6,195.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
6,300.00	0.00	0.00	6,295.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
6,400.00	0.00	163.00	6,395.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
6,500.00	0.00	0.00	6,495.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
6,600.00	0.00	0.00	6,595.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
6,700.00	0.00	0.00	6,695.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
6,800.00	0.00	163.00	6,795.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
6,900.00	0.00	0.00	6,895.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
7,000.00	0.00	0.00	6,995.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
7,100.00	0.00	0.00	7,095.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
7,200.00	0.00	0.00	7,195.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
7,300.00	0.00	0.00	7,295.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
7,400.00	0.00	0.00	7,395.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
7,500.00	0.00	0.00	7,495.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
7,600.00	0.00	0.00	7,595.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
7,700.00	0.00	0.00	7,695.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
7,800.00	0.00	0.00	7,795.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
7,900.00	0.00	0.00	7,895.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
8,000.00	0.00	0.00	7,995.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
8,100.00	0.00	0.00	8,095.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
8,200.00	0.00	0.00	8,195.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
8,300.00	0.00	0.00	8,295.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
8,400.00	0.00	0.00	8,395.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
8,500.00	0.00	0.00	8,495.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
8,600.00	0.00	0.00	8,595.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
8,700.00	0.00	0.00	8,695.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
8,800.00	0.00	0.00	8,795.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
8,900.00	0.00	0.00	8,895.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
9,000.00	0.00	0.00	8,995.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
9,100.00	0.00	0.00	9,095.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
9,200.00	0.00	0.00	9,195.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
9,300.00	0.00	0.00	9,295.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
9,400.00	0.00	0.00	9,395.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
9,500.00	0.00	0.00	9,495.89	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
9,504.11	0.00	0.00	9,500.00	-155.16	47.44	440,826.84	724,010.43	32.21053016	-103.74269407
Begin 1.5"/100' build									
9,600.00	1.44	108.65	9,595.88	-155.54	48.58	440,826.46	724,011.57	32.21052909	-103.74269039
9,700.00	2.94	108.65	9,695.80	-156.76	52.19	440,825.24	724,015.19	32.21052568	-103.74267872





# Planning Report - Geographic

Database:	DB_Jul2216dt_v14	Local Co-ordinate Reference:	Well Double Diamond 24S 21E 1414 Well No. 238H
Company:	Tap Rock Operating LLC	TVD Reference:	RKB=3586+25 @ 3611.00ft
Project:	Eddy County, New Mexico NAD83 NM east	MD Reference:	RKB=3586+25 @ 3611.00ft
Site:	Section 14-T24S-R31E	North Reference:	Grid
Well:	Double Diamond 24S 21E 1414 Well No. 238H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev1		

## Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
9,800.00	4.44	108.65	9,795.59	-158.82	58.29	440,823.18	724,021.28	32.21051993	-103.74265905
9,900.00	5.94	108.65	9,895.18	-161.71	66.86	440,820.29	724,029.85	32.21051185	-103.74263140
10,000.00	7.44	108.65	9,994.50	-165.44	77.89	440,816.56	724,040.89	32.21050145	-103.74259579
10,039.61	8.03	108.65	10,033.75	-167.14	82.94	440,814.86	724,045.94	32.21049668	-103.74257949
<b>Begin 8.03° tangent</b>									
10,100.00	8.03	108.65	10,093.54	-169.84	90.94	440,812.16	724,053.93	32.21048914	-103.74255368
10,200.00	8.03	108.65	10,192.56	-174.31	104.18	440,807.69	724,067.17	32.21047666	-103.74251096
10,300.00	8.03	108.65	10,291.58	-178.78	117.42	440,803.22	724,080.41	32.21046418	-103.74246823
10,400.00	8.03	108.65	10,390.60	-183.25	130.66	440,798.75	724,093.65	32.21045169	-103.74242550
10,500.00	8.03	108.65	10,489.62	-187.71	143.90	440,794.29	724,106.89	32.21043921	-103.74238278
10,600.00	8.03	108.65	10,588.64	-192.18	157.14	440,789.82	724,120.13	32.21042673	-103.74234005
10,700.00	8.03	108.65	10,687.66	-196.65	170.38	440,785.35	724,133.37	32.21041424	-103.74229732
10,800.00	8.03	108.65	10,786.68	-201.12	183.62	440,780.88	724,146.61	32.21040176	-103.74225460
10,900.00	8.03	108.65	10,885.70	-205.59	196.86	440,776.41	724,159.85	32.21038928	-103.74221187
11,000.00	8.03	108.65	10,984.71	-210.06	210.10	440,771.94	724,173.09	32.21037679	-103.74216914
11,100.00	8.03	108.65	11,083.73	-214.53	223.34	440,767.47	724,186.33	32.21036431	-103.74212642
11,200.00	8.03	108.65	11,182.75	-219.00	236.58	440,763.01	724,199.57	32.21035182	-103.74208369
11,300.00	8.03	108.65	11,281.77	-223.46	249.81	440,758.54	724,212.81	32.21033934	-103.74204097
11,400.00	8.03	108.65	11,380.79	-227.93	263.05	440,754.07	724,226.05	32.21032686	-103.74199824
11,500.00	8.03	108.65	11,479.81	-232.40	276.29	440,749.60	724,239.29	32.21031437	-103.74195551
11,600.00	8.03	108.65	11,578.83	-236.87	289.53	440,745.13	724,252.53	32.21030189	-103.74191279
11,688.29	8.03	108.65	11,666.25	-240.82	301.22	440,741.18	724,264.22	32.21029087	-103.74187506
<b>Begin 1.5°/100' drop</b>									
11,700.00	7.86	108.65	11,677.85	-241.33	302.76	440,740.67	724,265.75	32.21028942	-103.74187011
11,800.00	6.36	108.65	11,777.08	-245.29	314.48	440,736.71	724,277.47	32.21027837	-103.74183229
11,900.00	4.86	108.65	11,876.60	-248.41	323.74	440,733.59	724,286.73	32.21026964	-103.74180241
12,000.00	3.36	108.65	11,976.34	-250.70	330.52	440,731.30	724,293.52	32.21026324	-103.74178051
12,100.00	1.86	108.65	12,076.23	-252.16	334.83	440,729.84	724,297.83	32.21025918	-103.74176661
12,200.00	0.36	108.65	12,176.21	-252.78	336.66	440,729.22	724,299.66	32.21025745	-103.74176070
12,223.79	0.00	0.00	12,200.00	-252.80	336.73	440,729.20	724,299.73	32.21025739	-103.74176047
<b>Begin vertical hold</b>									
12,300.00	0.00	0.00	12,276.21	-252.80	336.73	440,729.20	724,299.73	32.21025739	-103.74176047
12,352.29	0.00	0.00	12,328.50	-252.80	336.73	440,729.20	724,299.73	32.21025739	-103.74176047
<b>Begin 10°/100' build</b>									
12,400.00	4.77	14.35	12,376.15	-250.88	337.22	440,731.12	724,300.22	32.21026267	-103.74175885
12,402.29	5.00	14.35	12,378.44	-250.69	337.27	440,731.31	724,300.27	32.21026318	-103.74175869
12,500.00	14.77	14.35	12,474.58	-234.46	341.42	440,747.54	724,304.42	32.21030774	-103.74174498
12,600.00	24.77	14.35	12,568.56	-201.73	349.80	440,780.27	724,312.79	32.21039758	-103.74171732
12,700.00	34.77	14.35	12,655.26	-153.68	362.09	440,828.32	724,325.08	32.21052945	-103.74167673
12,800.00	44.77	14.35	12,732.02	-91.79	377.92	440,890.21	724,340.92	32.21069935	-103.74162443
12,900.00	54.77	14.35	12,796.52	-17.92	396.82	440,964.08	724,359.82	32.21090212	-103.74156202
13,000.00	64.77	14.35	12,846.80	65.68	418.21	441,047.68	724,381.20	32.21113159	-103.74149138
13,052.29	70.00	14.35	12,866.90	112.43	430.17	441,094.43	724,393.16	32.21125990	-103.74145188
<b>Begin 8°/100' build</b>									
13,100.00	73.82	14.35	12,881.72	156.36	441.40	441,138.36	724,404.40	32.21138048	-103.74141476
13,200.00	81.82	14.35	12,902.80	250.98	465.61	441,232.98	724,428.61	32.21164021	-103.74133481
13,300.00	89.82	14.35	12,910.09	347.52	490.31	441,329.52	724,453.30	32.21190521	-103.74125324
13,304.79	90.20	14.35	12,910.09	352.16	491.50	441,334.16	724,454.49	32.21191795	-103.74124932
<b>Begin 5°/100' turn</b>									
13,400.00	90.20	9.59	12,909.76	445.28	511.24	441,427.28	724,474.23	32.21217359	-103.74118384
13,500.00	90.20	4.59	12,909.40	544.48	523.57	441,526.48	724,486.57	32.21244609	-103.74114218





# Planning Report - Geographic

<b>Database:</b>	DB_Jul2216dt_v14	<b>Local Co-ordinate Reference:</b>	Well Double Diamond 24S 21E 1414 Well No. 238H
<b>Company:</b>	Tap Rock Operating LLC	<b>TVD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Project:</b>	Eddy County, New Mexico NAD83 NM east	<b>MD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Site:</b>	Section 14-T24S-R31E	<b>North Reference:</b>	Grid
<b>Well:</b>	Double Diamond 24S 21E 1414 Well No. 238H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Original Hole		
<b>Design:</b>	rev1		

## Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
13,598.50	90.20	359.66	12,909.06	642.88	527.23	441,624.88	724,490.22	32.21271652	-103.74112861
<b>Begin 90.20° lateral</b>									
13,600.00	90.20	359.66	12,909.05	644.38	527.22	441,626.38	724,490.22	32.21272064	-103.74112861
13,700.00	90.20	359.66	12,908.70	744.38	526.64	441,726.38	724,489.63	32.21299552	-103.74112872
13,800.00	90.20	359.66	12,908.35	844.38	526.05	441,826.37	724,489.04	32.21327040	-103.74112883
13,900.00	90.20	359.66	12,908.00	944.37	525.46	441,926.37	724,488.46	32.21354527	-103.74112895
14,000.00	90.20	359.66	12,907.64	1,044.37	524.88	442,026.37	724,487.87	32.21382015	-103.74112906
14,100.00	90.20	359.66	12,907.29	1,144.37	524.29	442,126.37	724,487.29	32.21409503	-103.74112917
14,200.00	90.20	359.66	12,906.94	1,244.37	523.71	442,226.36	724,486.70	32.21436991	-103.74112928
14,300.00	90.20	359.66	12,906.59	1,344.36	523.12	442,326.36	724,486.12	32.21464479	-103.74112939
14,400.00	90.20	359.66	12,906.24	1,444.36	522.54	442,426.36	724,485.53	32.21491967	-103.74112950
14,500.00	90.20	359.66	12,905.89	1,544.36	521.95	442,526.36	724,484.95	32.21519454	-103.74112962
14,600.00	90.20	359.66	12,905.53	1,644.36	521.36	442,626.35	724,484.36	32.21546942	-103.74112973
14,700.00	90.20	359.66	12,905.18	1,744.35	520.78	442,726.35	724,483.77	32.21574430	-103.74112984
14,800.00	90.20	359.66	12,904.83	1,844.35	520.19	442,826.35	724,483.19	32.21601918	-103.74112995
14,900.00	90.20	359.66	12,904.48	1,944.35	519.61	442,926.35	724,482.60	32.21629406	-103.74113006
15,000.00	90.20	359.66	12,904.13	2,044.35	519.02	443,026.34	724,482.02	32.21656893	-103.74113018
15,100.00	90.20	359.66	12,903.77	2,144.35	518.44	443,126.34	724,481.43	32.21684381	-103.74113029
15,200.00	90.20	359.66	12,903.42	2,244.34	517.85	443,226.34	724,480.85	32.21711869	-103.74113040
15,300.00	90.20	359.66	12,903.07	2,344.34	517.27	443,326.34	724,480.26	32.21739357	-103.74113051
15,400.00	90.20	359.66	12,902.72	2,444.34	516.68	443,426.33	724,479.67	32.21766845	-103.74113062
15,500.00	90.20	359.66	12,902.37	2,544.34	516.09	443,526.33	724,479.09	32.21794333	-103.74113073
15,600.00	90.20	359.66	12,902.01	2,644.33	515.51	443,626.33	724,478.50	32.21821820	-103.74113085
15,700.00	90.20	359.66	12,901.66	2,744.33	514.92	443,726.33	724,477.92	32.21849308	-103.74113096
15,800.00	90.20	359.66	12,901.31	2,844.33	514.34	443,826.32	724,477.33	32.21876796	-103.74113107
15,900.00	90.20	359.66	12,900.96	2,944.33	513.75	443,926.32	724,476.75	32.21904284	-103.74113118
16,000.00	90.20	359.66	12,900.61	3,044.32	513.17	444,026.32	724,476.16	32.21931772	-103.74113129
16,100.00	90.20	359.66	12,900.26	3,144.32	512.58	444,126.32	724,475.58	32.21959259	-103.74113141
16,200.00	90.20	359.66	12,899.90	3,244.32	511.99	444,226.31	724,474.99	32.21986747	-103.74113152
16,300.00	90.20	359.66	12,899.55	3,344.32	511.41	444,326.31	724,474.40	32.22014235	-103.74113163
16,400.00	90.20	359.66	12,899.20	3,444.32	510.82	444,426.31	724,473.82	32.22041723	-103.74113174
16,500.00	90.20	359.66	12,898.85	3,544.31	510.24	444,526.31	724,473.23	32.22069211	-103.74113185
16,600.00	90.20	359.66	12,898.50	3,644.31	509.65	444,626.30	724,472.65	32.22096698	-103.74113196
16,700.00	90.20	359.66	12,898.14	3,744.31	509.07	444,726.30	724,472.06	32.22124186	-103.74113208
16,800.00	90.20	359.66	12,897.79	3,844.31	508.48	444,826.30	724,471.48	32.22151674	-103.74113219
16,900.00	90.20	359.66	12,897.44	3,944.30	507.90	444,926.30	724,470.89	32.22179162	-103.74113230
17,000.00	90.20	359.66	12,897.09	4,044.30	507.31	445,026.29	724,470.30	32.22206650	-103.74113241
17,100.00	90.20	359.66	12,896.74	4,144.30	506.72	445,126.29	724,469.72	32.22234137	-103.74113252
17,200.00	90.20	359.66	12,896.39	4,244.30	506.14	445,226.29	724,469.13	32.22261625	-103.74113263
17,300.00	90.20	359.66	12,896.03	4,344.29	505.55	445,326.29	724,468.55	32.22289113	-103.74113274
17,400.00	90.20	359.66	12,895.68	4,444.29	504.97	445,426.28	724,467.96	32.22316601	-103.74113286
17,500.00	90.20	359.66	12,895.33	4,544.29	504.38	445,526.28	724,467.38	32.22344089	-103.74113297
17,600.00	90.20	359.66	12,894.98	4,644.29	503.80	445,626.28	724,466.79	32.22371576	-103.74113308
17,700.00	90.20	359.66	12,894.63	4,744.28	503.21	445,726.28	724,466.21	32.22399064	-103.74113319
17,735.73	90.20	359.66	12,894.50	4,780.01	503.00	445,762.00	724,466.00	32.22408884	-103.74113323

PBHL/TD 17735.73 MD/12894.50 TVD





# Planning Report - Geographic

Database:	DB_Jul2216dt_v14	Local Co-ordinate Reference:	Well Double Diamond 24S 21E 1414 Well No. 238H
Company:	Tap Rock Operating LLC	TVD Reference:	RKB=3586+25 @ 3611.00ft
Project:	Eddy County, New Mexico NAD83 NM east	MD Reference:	RKB=3586+25 @ 3611.00ft
Site:	Section 14-T24S-R31E	North Reference:	Grid
Well:	Double Diamond 24S 21E 1414 Well No. 238H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Original Hole		
Design:	rev1		

## Design Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
- hit/miss target									
- Shape									
Double Diamond Fed 23	0.00	0.00	12,200.00	-252.80	336.73	440,729.20	724,299.73	32.21025739	-103.74176047
- plan hits target center									
- Point									
Double Diamond Fed #2	0.00	0.00	12,894.50	4,780.01	503.00	445,762.00	724,466.00	32.22408884	-103.74113323
- plan hits target center									
- Point									

## Casing Points

Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (")	Hole Diameter (")
1,000.00	1,000.00	13 3/8" Casing @ 1000 TVD	13-3/8	17-1/2
4,704.11	4,700.00	9 5/8" Casing @ 4700 TVD	9-5/8	12-1/4
13,104.53	12,882.97	7" Casing @ 13104.5 MD	7	8-3/4

## Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
1,200.00	1,200.00	0.00	0.00	KOP Begin 1°/100' build
1,500.00	1,499.86	-7.51	2.30	Begin 3.00° tangent
4,300.00	4,296.03	-147.65	45.14	Begin 1°/100' drop
4,600.00	4,595.89	-155.16	47.44	Begin vertical hold
9,504.11	9,500.00	-155.16	47.44	Begin 1.5°/100' build
10,039.61	10,033.75	-167.14	82.94	Begin 8.03° tangent
11,688.29	11,666.25	-240.82	301.22	Begin 1.5°/100' drop
12,223.79	12,200.00	-252.80	336.73	Begin vertical hold
12,352.29	12,328.50	-252.80	336.73	Begin 10°/100' build
13,052.29	12,866.90	-250.69	337.27	Begin 8°/100' build
13,304.79	12,910.09	112.43	430.17	Begin 5°/100' turn
13,598.50	12,909.06	352.17	491.50	Begin 90.20° lateral
17,735.73	12,894.50	642.88	527.23	PBHL/TD 17735.73 MD/12894.50 TVD



# Anticollision Report

**Company:** Tap Rock Operating LLC  
**Project:** Eddy County, New Mexico NAD83 NM east  
**Reference Site:** Section 14-T24S-R31E  
**Site Error:** 0.00 ft  
**Reference Well:** Double Diamond 24S 21E 1414 Well No. 238H  
**Well Error:** 0.00 ft  
**Reference Wellbore:** Original Hole  
**Reference Design:** rev1

**Local Co-ordinate Reference:** Well Double Diamond 24S 21E 1414 Well No. 238H  
**TVD Reference:** RKB=3586+25 @ 3611.00ft  
**MD Reference:** RKB=3586+25 @ 3611.00ft  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at** 2.00 sigma  
**Database:** DB\_Jul2216dt\_v14  
**Offset TVD Reference:** Offset Datum

<b>Reference</b>	rev1		
<b>Filter type:</b>	GLOBAL FILTER APPLIED: All wellpaths within 200'+ 100/1000 of reference		
<b>Interpolation Method:</b>	MD Interval 100.00ft	<b>Error Model:</b>	ISCWSA
<b>Depth Range:</b>	Unlimited	<b>Scan Method:</b>	Closest Approach 3D
<b>Results Limited by:</b>	Maximum center-center distance of 1,973.62 ft	<b>Error Surface:</b>	Ellipsoid Separation
<b>Warning Levels Evaluated at:</b>	2.00 Sigma	<b>Casing Method:</b>	Not applied

<b>Survey Tool Program</b>	<b>Date</b>	1/28/2018		
<b>From (ft)</b>	<b>To (ft)</b>	<b>Survey (Wellbore)</b>	<b>Tool Name</b>	<b>Description</b>
0.00	9,500.00	rev1 (Original Hole)	GYRO-NS	OWSG Gyrocompass Gyro
9,500.00	17,735.73	rev1 (Original Hole)	MWD	OWSG MWD - Standard

<b>Summary</b>							
<b>Site Name</b>	<b>Reference Measured Depth (ft)</b>	<b>Offset Measured Depth (ft)</b>	<b>Distance Between Centres (ft)</b>	<b>Distance Between Ellipses (ft)</b>	<b>Separation Factor</b>	<b>Warning</b>	
Offset Well - Wellbore - Design							
Section 14-T24S-R31E							
Double Diamond 24S 21E 1414 Well No. 158H - Original	1,200.00	1,200.00	75.00	67.06	9.444	CC	
Double Diamond 24S 21E 1414 Well No. 158H - Original	7,400.29	7,409.93	98.61	50.95	2.069	ES, SF	
Double Diamond 24S 21E 1414 Well No. 224H - Original	1,200.00	1,201.20	25.00	17.05	3.146	CC	
Double Diamond 24S 21E 1414 Well No. 224H - Original	1,300.00	1,301.03	25.59	16.95	2.961	ES	
Double Diamond 24S 21E 1414 Well No. 224H - Original	9,500.00	9,501.34	135.23	70.93	2.103	SF	
Double Diamond 24S 21E 1414 Well No. 228H - Original	1,200.00	1,200.10	50.00	42.06	6.296	CC	
Double Diamond 24S 21E 1414 Well No. 228H - Original	1,300.00	1,300.11	50.26	41.62	5.817	ES	
Double Diamond 24S 21E 1414 Well No. 228H - Original	12,107.38	12,126.44	197.16	130.49	2.957	SF	
Petrogulf BJT Federal Well No. 1H - Horizontal - Surveys	8,351.98	8,635.74	506.30	465.72	12.478	CC, ES, SF	
Petrogulf BJT Federal Well No. 2H - Original Hole - Surv	611.51	599.51	636.50	632.87	175.447	CC	
Petrogulf BJT Federal Well No. 2H - Original Hole - Surv	8,313.74	8,404.77	657.04	600.98	11.721	ES	
Petrogulf BJT Federal Well No. 2H - Original Hole - Surv	8,400.00	8,481.19	660.50	603.97	11.684	SF	

<b>Offset Design</b>	Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 158H - Original Hole - rev0										<b>Offset Site Error:</b>	0.00 ft
<b>Survey Program:</b>	G-GYRO-NS, 6100-MWD										<b>Offset Well Error:</b>	0.00 ft
<b>Reference</b>	<b>Offset</b>	<b>Semi Major Axis</b>		<b>Distance</b>		<b>Minimum Separation</b>		<b>Separation Factor</b>	<b>Warning</b>			
<b>Measured Depth (ft)</b>	<b>Vertical Depth (ft)</b>	<b>Measured Depth (ft)</b>	<b>Vertical Depth (ft)</b>	<b>Reference (ft)</b>	<b>Offset (ft)</b>	<b>Highside Toolface (°)</b>	<b>Offset Wellbore Centre +N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Between Centres (ft)</b>	<b>Between Ellipses (ft)</b>	<b>Minimum Separation (ft)</b>	
0.00	0.00	0.00	0.00	0.00	0.00	-90.00	0.00	-75.00	75.00			
100.00	100.00	100.00	100.00	0.13	0.13	-90.00	0.00	-75.00	75.00	74.74	0.26	286.479
200.00	200.00	200.00	200.00	0.48	0.48	-90.00	0.00	-75.00	75.00	74.04	0.96	78.131
300.00	300.00	300.00	300.00	0.83	0.83	-90.00	0.00	-75.00	75.00	73.34	1.66	45.234
400.00	400.00	400.00	400.00	1.18	1.18	-90.00	0.00	-75.00	75.00	72.64	2.36	31.831
500.00	500.00	500.00	500.00	1.53	1.53	-90.00	0.00	-75.00	75.00	71.95	3.05	24.555
600.00	600.00	600.00	600.00	1.88	1.88	-90.00	0.00	-75.00	75.00	71.25	3.75	19.987
700.00	700.00	700.00	700.00	2.24	2.24	-90.00	0.00	-75.00	75.00	70.55	4.45	16.852
800.00	800.00	800.00	800.00	2.59	2.59	-90.00	0.00	-75.00	75.00	69.85	5.15	14.567
900.00	900.00	900.00	900.00	2.94	2.94	-90.00	0.00	-75.00	75.00	69.15	5.85	12.827
1,000.00	1,000.00	1,000.00	1,000.00	3.29	3.29	-90.00	0.00	-75.00	75.00	68.46	6.54	11.459
1,100.00	1,100.00	1,100.00	1,100.00	3.64	3.64	-90.00	0.00	-75.00	75.00	67.76	7.24	10.355
1,200.00	1,200.00	1,200.00	1,200.00	3.99	3.99	-90.00	0.00	-75.00	75.00	67.06	7.94	9.444 CC

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation





# Anticollision Report

Company: Tap Rock Operating LLC

Local Co-ordinate Reference:

Well Double Diamond 24S 21E 1414 Well No. 238H

Project: Eddy County, New Mexico NAD83 NM east

TVD Reference:

RKB=3586+25 @ 3611.00ft

Reference Site: Section 14-T24S-R31E

MD Reference:

RKB=3586+25 @ 3611.00ft

Site Error: 0.00 ft

North Reference:

Grid

Reference Well: Double Diamond 24S 21E 1414 Well No. 238H

Survey Calculation Method:

Minimum Curvature

Well Error: 0.00 ft

Output errors are at

2.00 sigma

Reference Wellbore: Original Hole

Database:

DB\_Jul2216dt\_v14

Reference Design: rev1

Offset TVD Reference:

Offset Datum

Offset Design Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 158H - Original Hole - rev0													Offset Site Error:	0.00 ft
Survey Program: 0-GYRO-NS, 6100-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis			Distance							
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning	
1,300.00	1,299.99	1,300.01	1,299.99	4.34	4.34	107.63	0.00	-75.00	75.26	66.62	8.64	8.711		
1,400.00	1,399.96	1,400.04	1,399.96	4.68	4.69	109.50	0.00	-75.00	76.09	66.75	9.34	8.146		
1,500.00	1,499.86	1,500.14	1,499.86	5.03	5.04	112.52	0.00	-75.00	77.66	67.61	10.05	7.730		
1,600.00	1,599.73	1,600.27	1,599.73	5.39	5.39	115.99	0.00	-75.00	79.81	69.06	10.75	7.422		
1,700.00	1,699.59	1,700.41	1,699.59	5.75	5.74	119.27	0.00	-75.00	82.24	70.79	11.46	7.178		
1,800.00	1,799.45	1,800.55	1,799.45	6.11	6.09	122.34	0.00	-75.00	84.93	72.77	12.16	6.983		
1,900.00	1,899.31	1,900.69	1,899.31	6.46	6.45	125.23	0.00	-75.00	87.84	74.98	12.86	6.828		
2,000.00	1,999.18	2,000.82	1,999.18	6.82	6.80	127.92	0.00	-75.00	90.96	77.40	13.57	6.705		
2,100.00	2,099.04	2,100.96	2,099.04	7.17	7.15	130.43	0.00	-75.00	94.27	80.01	14.27	6.608		
2,200.00	2,198.90	2,201.10	2,198.90	7.53	7.50	132.76	0.00	-75.00	97.75	82.78	14.97	6.531		
2,300.00	2,298.77	2,301.23	2,298.77	7.88	7.85	134.93	0.00	-75.00	101.38	85.71	15.67	6.470		
2,400.00	2,398.63	2,401.37	2,398.63	8.23	8.20	136.95	0.00	-75.00	105.14	88.77	16.37	6.423		
2,500.00	2,498.49	2,501.51	2,498.49	8.59	8.55	138.83	0.00	-75.00	109.03	91.96	17.07	6.387		
2,600.00	2,598.36	2,601.64	2,598.36	8.94	8.90	140.57	0.00	-75.00	113.02	95.25	17.77	6.360		
2,700.00	2,698.22	2,701.78	2,698.22	9.29	9.25	142.20	0.00	-75.00	117.11	98.64	18.47	6.341		
2,800.00	2,798.08	2,801.92	2,798.08	9.64	9.61	143.71	0.00	-75.00	121.29	102.12	19.17	6.327		
2,900.00	2,897.94	2,902.06	2,897.94	10.00	9.96	145.13	0.00	-75.00	125.55	105.68	19.87	6.319		
3,000.00	2,997.81	3,002.19	2,997.81	10.35	10.31	146.44	0.00	-75.00	129.88	109.31	20.57	6.314		
3,100.00	3,097.67	3,102.33	3,097.67	10.70	10.66	147.68	0.00	-75.00	134.28	113.01	21.27	6.312		
3,200.00	3,197.53	3,202.47	3,197.53	11.05	11.01	148.83	0.00	-75.00	138.73	116.76	21.97	6.314		
3,300.00	3,297.40	3,302.60	3,297.40	11.40	11.36	149.92	0.00	-75.00	143.24	120.56	22.67	6.317		
3,400.00	3,397.26	3,402.74	3,397.26	11.75	11.71	150.93	0.00	-75.00	147.79	124.41	23.37	6.323		
3,500.00	3,497.12	3,502.88	3,497.12	12.11	12.06	151.89	0.00	-75.00	152.39	128.31	24.08	6.329		
3,600.00	3,596.99	3,603.02	3,596.99	12.46	12.41	152.79	0.00	-75.00	157.02	132.25	24.78	6.338		
3,700.00	3,696.85	3,703.15	3,696.85	12.81	12.77	153.64	0.00	-75.00	161.70	136.22	25.48	6.346		
3,800.00	3,796.71	3,803.29	3,796.71	13.16	13.12	154.44	0.00	-75.00	166.40	140.22	26.18	6.356		
3,900.00	3,896.57	3,903.43	3,896.57	13.51	13.47	155.19	0.00	-75.00	171.14	144.26	26.88	6.367		
4,000.00	3,996.44	4,003.56	3,996.44	13.86	13.82	155.91	0.00	-75.00	175.91	148.32	27.58	6.377		
4,100.00	4,096.30	4,103.70	4,096.30	14.21	14.17	156.59	0.00	-75.00	180.70	152.41	28.28	6.389		
4,200.00	4,196.16	4,203.84	4,196.16	14.56	14.52	157.23	0.00	-75.00	185.51	156.53	28.99	6.400		
4,300.00	4,296.03	4,303.97	4,296.03	14.91	14.87	157.84	0.00	-75.00	190.35	160.66	29.69	6.412		
4,400.00	4,395.93	4,404.07	4,395.93	15.26	15.22	158.34	0.00	-75.00	194.40	164.01	30.39	6.397		
4,500.00	4,495.89	4,504.11	4,495.89	15.61	15.57	158.63	0.00	-75.00	196.83	165.74	31.09	6.331		
4,600.00	4,595.89	4,604.11	4,595.89	15.95	15.92	-38.28	0.00	-75.00	197.65	165.86	31.79	6.218		
4,700.00	4,695.89	4,704.11	4,695.89	16.30	16.28	-38.28	0.00	-75.00	197.65	165.16	32.49	6.084		
4,800.00	4,795.89	4,804.11	4,795.89	16.65	16.63	-38.28	0.00	-75.00	197.65	164.46	33.19	5.956		
4,900.00	4,895.89	4,904.11	4,895.89	16.99	16.98	-38.28	0.00	-75.00	197.65	163.76	33.88	5.833		
5,000.00	4,995.89	5,004.11	4,995.89	17.34	17.33	-38.28	0.00	-75.00	197.65	163.06	34.58	5.715		
5,100.00	5,095.89	5,104.11	5,095.89	17.69	17.68	-38.28	0.00	-75.00	197.65	162.36	35.28	5.602		
5,200.00	5,195.89	5,204.11	5,195.89	18.03	18.03	-38.28	0.00	-75.00	197.65	161.66	35.98	5.493		
5,300.00	5,295.89	5,304.11	5,295.89	18.38	18.38	-38.28	0.00	-75.00	197.65	160.96	36.68	5.388		
5,400.00	5,395.89	5,404.11	5,395.89	18.73	18.73	-38.28	0.00	-75.00	197.65	160.27	37.38	5.287		
5,500.00	5,495.89	5,504.11	5,495.89	19.08	19.08	-38.28	0.00	-75.00	197.65	159.57	38.08	5.190		
5,600.00	5,595.89	5,604.11	5,595.89	19.42	19.43	-38.28	0.00	-75.00	197.65	158.87	38.78	5.097		
5,700.00	5,695.89	5,704.11	5,695.89	19.77	19.78	-38.28	0.00	-75.00	197.65	158.17	39.48	5.006		
5,800.00	5,795.89	5,804.11	5,795.89	20.12	20.13	-38.28	0.00	-75.00	197.65	157.47	40.18	4.919		
5,900.00	5,895.89	5,904.11	5,895.89	20.46	20.48	-38.28	0.00	-75.00	197.65	156.77	40.88	4.835		
6,000.00	5,995.89	6,004.11	5,995.89	20.81	20.83	-38.28	0.00	-75.00	197.65	156.07	41.58	4.754		
6,100.00	6,095.89	6,095.89	6,095.89	21.16	21.16	-38.28	0.00	-75.00	197.65	155.40	42.25	4.678		
6,200.00	6,195.89	6,200.28	6,200.27	21.51	21.35	-38.08	-0.45	-73.76	196.58	153.79	42.79	4.594		
6,300.00	6,295.89	6,304.71	6,304.61	21.85	21.35	-37.42	-1.88	-69.85	193.20	150.08	43.12	4.480		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Anticollision Report

Company: Tap Rock Operating LLC

Local Co-ordinate Reference:

Well Double Diamond 24S 21E 1414 Well No. 238H

Project: Eddy County, New Mexico NAD83 NM east

TVD Reference:

RKB=3586+25 @ 3611.00ft

Reference Site: Section 14-T24S-R31E

MD Reference:

RKB=3586+25 @ 3611.00ft

Site Error: 0.00 ft

North Reference:

Grid

Reference Well: Double Diamond 24S 21E 1414 Well No. 238H

Survey Calculation Method:

Minimum Curvature

Well Error: 0.00 ft

Output errors are at

2.00 sigma

Reference Wellbore: Original Hole

Database:

DB\_Jul2216dt\_v14

Reference Design: rev1

Offset TVD Reference:

Offset Datum

Offset Design Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 158H - Original Hole - rev0													Offset Site Error:	0.00 ft
Survey Program: 0-GYRO-NS, 6100-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis			Distance							
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning	
6,400.00	6,395.89	6,408.84	6,408.50	22.20	21.37	-36.27	-4.27	-63.27	187.57	144.13	43.45	4.317		
6,500.00	6,495.89	6,512.50	6,511.70	22.55	21.39	-34.53	-7.61	-54.09	179.80	136.04	43.76	4.109		
6,600.00	6,595.89	6,615.57	6,614.00	22.90	21.42	-32.08	-11.88	-42.35	170.05	125.99	44.07	3.859		
6,700.00	6,695.89	6,717.88	6,715.19	23.24	21.46	-28.69	-17.05	-28.14	158.61	114.23	44.38	3.574		
6,800.00	6,795.89	6,819.33	6,815.12	23.59	21.51	-24.20	-23.31	-11.82	145.83	101.11	44.72	3.261		
6,900.00	6,895.89	6,917.71	6,911.91	23.94	21.56	-18.99	-30.13	4.42	133.19	88.01	45.18	2.948		
7,000.00	6,995.89	7,016.10	7,008.71	24.29	21.63	-12.77	-36.95	20.65	121.88	76.22	45.67	2.869		
7,100.00	7,095.89	7,114.48	7,105.51	24.64	21.70	-5.41	-43.77	36.88	112.30	66.13	46.17	2.432		
7,200.00	7,195.89	7,212.87	7,202.30	24.98	21.79	3.11	-50.59	53.12	104.92	58.23	46.69	2.247		
7,300.00	7,295.89	7,311.25	7,299.10	25.33	21.88	12.64	-57.41	69.35	100.23	53.03	47.19	2.124		
7,400.00	7,395.89	7,409.64	7,395.90	25.68	21.99	22.76	-64.23	85.58	98.61	50.95	47.65	2.069		
7,400.29	7,396.18	7,409.93	7,396.18	25.68	21.99	22.79	-64.25	85.63	98.61	50.95	47.66	2.069 ES, SF		
7,500.00	7,495.89	7,508.02	7,492.70	26.03	22.10	32.88	-71.05	101.82	100.21	52.15	48.06	2.085		
7,600.00	7,595.89	7,606.41	7,589.49	26.38	22.22	42.42	-77.87	118.05	104.88	56.47	48.41	2.166		
7,700.00	7,695.89	7,704.80	7,686.29	26.73	22.35	50.94	-84.69	134.28	112.25	63.50	48.76	2.302		
7,800.00	7,795.89	7,803.18	7,783.09	27.07	22.49	58.31	-91.51	150.51	121.82	72.72	49.11	2.481		
7,900.00	7,895.89	7,901.57	7,879.88	27.42	22.64	64.53	-98.33	166.75	133.12	83.65	49.47	2.691		
8,000.00	7,995.89	7,999.95	7,976.68	27.77	22.79	69.75	-105.15	182.98	145.75	95.88	49.87	2.923		
8,100.00	8,095.89	8,101.66	8,073.48	28.12	22.96	74.12	-111.97	199.21	159.39	109.10	50.28	3.170		
8,200.00	8,195.89	8,196.72	8,170.28	28.47	23.13	77.79	-118.79	215.45	173.80	123.09	50.71	3.427		
8,300.00	8,295.89	8,304.89	8,267.07	28.82	23.33	80.89	-125.61	231.68	188.81	137.64	51.17	3.690		
8,400.00	8,395.89	8,406.51	8,363.87	29.17	23.52	83.53	-132.43	247.91	204.29	152.66	51.63	3.957		
8,500.00	8,495.89	8,508.12	8,460.67	29.52	23.72	85.80	-139.25	264.15	220.13	168.02	52.11	4.225		
8,600.00	8,595.89	8,609.73	8,557.46	29.87	23.93	87.77	-146.07	280.38	236.27	183.68	52.59	4.493		
8,700.00	8,695.89	8,688.65	8,654.26	30.22	24.10	89.48	-152.89	296.61	252.64	199.60	53.04	4.763		
8,800.00	8,795.89	8,787.04	8,751.06	30.57	24.31	90.98	-159.71	312.85	269.21	215.67	53.54	5.028		
8,900.00	8,895.89	8,885.42	8,847.86	30.92	24.53	92.31	-166.53	329.08	285.94	231.90	54.04	5.291		
9,000.00	8,995.89	8,983.81	8,944.65	31.27	24.76	93.49	-173.35	345.31	302.80	248.25	54.55	5.551		
9,100.00	9,095.89	9,082.19	9,041.45	31.62	24.99	94.55	-180.17	361.55	319.77	264.71	55.06	5.808		
9,200.00	9,195.89	9,180.58	9,138.25	31.97	25.23	95.50	-186.99	377.78	336.84	281.27	55.58	6.061		
9,300.00	9,295.89	9,278.96	9,235.04	32.32	25.48	96.36	-193.81	394.01	353.99	297.89	56.10	6.310		
9,400.00	9,395.89	9,377.35	9,331.84	32.67	25.73	97.14	-200.63	410.25	371.21	314.59	56.63	6.555		
9,500.00	9,495.89	9,475.74	9,428.64	32.85	25.98	97.86	-207.45	426.48	388.50	331.50	57.00	6.816		
9,600.00	9,595.88	9,574.33	9,525.64	32.86	26.25	-10.13	-214.28	442.75	404.67	347.46	57.21	7.074		
9,700.00	9,695.80	9,673.32	9,623.03	32.87	26.52	-9.59	-221.15	459.08	418.33	360.91	57.42	7.286		
9,800.00	9,795.59	9,773.19	9,721.29	32.88	26.79	-9.13	-228.07	475.55	429.45	371.80	57.65	7.450		
9,900.00	9,895.18	9,885.30	9,831.89	32.90	27.10	-8.77	-235.15	492.42	436.47	378.41	58.06	7.518		
10,000.00	9,994.50	9,997.84	9,943.42	32.92	27.39	-8.59	-241.00	508.34	438.05	379.61	58.44	7.495		
10,100.00	10,093.54	10,110.32	10,055.27	32.94	27.66	-8.55	-245.57	517.22	434.65	375.84	58.80	7.391		
10,200.00	10,192.56	10,222.47	10,167.10	32.97	27.92	-8.62	-248.86	525.04	428.17	369.04	59.13	7.241		
10,300.00	10,291.58	10,334.11	10,278.60	33.01	28.16	-8.78	-250.86	529.81	418.85	359.41	59.44	7.047		
10,400.00	10,390.60	10,445.04	10,389.51	33.05	28.38	-9.06	-251.60	531.58	406.71	347.00	59.71	6.811		
10,500.00	10,489.62	10,552.10	10,496.46	33.10	28.57	-9.90	-248.24	531.57	392.43	332.48	59.95	6.546		
10,600.00	10,588.64	10,657.76	10,599.85	33.15	28.73	-13.49	-227.20	531.45	376.12	315.90	60.22	6.246		
10,700.00	10,687.66	10,751.38	10,686.88	33.21	28.84	-19.40	-192.98	531.25	360.90	300.37	60.52	5.963		
10,800.00	10,786.68	10,830.84	10,755.56	33.28	28.91	-26.42	-153.14	531.02	352.08	291.38	60.70	5.800		
10,829.12	10,815.51	10,851.37	10,772.34	33.30	28.93	-28.50	-141.34	530.96	351.53	290.86	60.67	5.794		
10,900.00	10,885.70	10,896.74	10,807.89	33.35	28.95	-33.39	-113.15	530.79	355.12	294.78	60.34	5.885		
11,000.00	10,984.71	10,950.00	10,846.61	33.42	28.98	-39.50	-76.61	530.58	373.62	314.45	59.16	6.315		
11,100.00	11,083.73	11,000.00	10,879.72	33.50	29.00	-45.35	-39.17	530.37	408.22	350.63	57.58	7.089		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation





# Anticollision Report

Company:	Tap Rock Operating LLC	Local Co-ordinate Reference:	Well Double Diamond 24S 21E 1414 Well No. 238H
Project:	Eddy County, New Mexico NAD83 NM east	TVD Reference:	RKB=3586+25 @ 3611.00ft
Reference Site:	Section 14-T24S-R31E	MD Reference:	RKB=3586+25 @ 3611.00ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Double Diamond 24S 21E 1414 Well No. 238H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 ft	Output errors are at	2.00 sigma
Reference Wellbore	Original Hole	Database:	DB_Jul2216dt_v14
Reference Design:	rev1	Offset TVD Reference:	Offset Datum

Offset Design Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 158H - Original Hole - rev0													Offset Site Error: 0.00 ft	
Survey Program: 0-GYRO-NS, 5100-MWD													Offset Well Error: 0.00 ft	
Reference		Offset		Semi Major Axis			Distance							
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning	
11,200.00	11,182.75	11,032.47	10,899.42	33.59	29.01	-49.12	-13.37	530.22	456.93	401.32	55.61	8.217		
11,300.00	11,281.77	11,063.31	10,916.76	33.68	29.01	-52.58	12.14	530.07	516.99	463.01	53.99	9.577		
11,400.00	11,380.79	11,089.32	10,930.29	33.77	29.02	-55.40	34.34	529.94	585.63	532.92	52.71	11.111		
11,500.00	11,479.81	11,111.45	10,941.01	33.88	29.02	-57.71	53.71	529.83	660.64	608.87	51.77	12.761		
11,600.00	11,578.83	11,130.47	10,949.61	33.98	29.02	-59.62	70.67	529.73	740.40	689.28	51.12	14.484		
11,700.00	11,677.85	11,150.00	10,957.85	34.09	29.03	-61.74	88.37	529.63	823.75	773.01	50.74	16.235		
11,800.00	11,777.08	11,161.57	10,962.45	34.20	29.03	-65.10	98.98	529.57	910.17	859.73	50.44	18.045		
11,900.00	11,876.60	11,174.76	10,967.43	34.31	29.03	-68.93	111.20	529.50	999.12	948.80	50.33	19.853		
12,000.00	11,976.34	11,189.92	10,972.80	34.42	29.04	-73.20	125.38	529.42	1,089.99	1,039.64	50.35	21.647		
12,100.00	12,076.23	11,200.00	10,976.18	34.53	29.04	-77.36	134.87	529.37	1,182.26	1,131.85	50.41	23.454		
12,200.00	12,176.21	11,200.00	10,976.18	34.63	29.04	-81.24	134.87	529.37	1,275.72	1,225.28	50.45	25.289		
12,300.00	12,276.21	11,221.55	10,982.96	34.73	29.05	25.25	155.33	529.25	1,369.71	1,319.00	50.72	27.008		
12,400.00	12,376.15	11,232.07	10,986.05	34.83	29.05	8.34	165.38	529.19	1,463.74	1,412.82	50.91	28.749		
12,500.00	12,474.58	11,250.00	10,990.96	34.94	29.06	5.50	182.63	529.09	1,552.51	1,501.42	51.09	30.385		
12,600.00	12,568.56	11,250.00	10,990.96	35.04	29.06	4.32	182.63	529.09	1,633.62	1,582.49	51.12	31.954		
12,700.00	12,655.26	11,283.42	10,998.97	35.15	29.08	3.16	215.07	528.90	1,705.02	1,653.73	51.29	33.243		
12,800.00	12,732.02	11,300.00	11,002.37	35.26	29.09	2.58	231.30	528.81	1,766.02	1,714.67	51.35	34.392		
12,900.00	12,796.52	11,329.65	11,007.52	35.40	29.13	2.06	260.49	528.64	1,815.32	1,763.88	51.45	35.285		
13,000.00	12,846.80	11,350.00	11,010.36	35.60	29.16	1.74	280.64	528.53	1,852.27	1,800.75	51.52	35.951		
13,100.00	12,881.72	11,380.84	11,013.56	35.87	29.22	1.43	311.32	528.36	1,876.59	1,824.94	51.64	36.337		
13,200.00	12,902.80	11,400.00	11,014.88	36.22	29.27	1.25	330.43	528.25	1,890.63	1,838.85	51.78	36.511		
13,300.00	12,910.09	11,441.22	11,016.00	36.64	29.40	0.92	371.63	528.01	1,894.63	1,842.64	51.99	36.445		
13,400.00	12,909.76	11,511.53	11,015.87	37.11	29.67	0.51	441.93	527.61	1,893.96	1,841.71	52.25	36.246		
13,500.00	12,909.40	11,610.66	11,015.69	37.63	30.17	0.11	541.06	527.05	1,893.72	1,841.14	52.58	36.015		
13,600.00	12,909.05	11,710.54	11,015.51	38.18	30.76	-0.02	640.94	526.48	1,893.55	1,840.59	52.96	35.754		
13,700.00	12,908.70	11,810.54	11,015.33	38.77	31.43	-0.02	740.94	525.92	1,893.38	1,839.99	53.39	35.465		
13,800.00	12,908.35	11,910.54	11,015.14	39.43	32.18	-0.02	840.94	525.35	1,893.21	1,839.35	53.86	35.152		
13,900.00	12,908.00	12,010.54	11,014.96	40.14	32.99	-0.02	940.94	524.78	1,893.04	1,838.67	54.37	34.818		
14,000.00	12,907.64	12,110.54	11,014.78	40.91	33.86	-0.02	1,040.93	524.21	1,892.87	1,837.95	54.92	34.465		
14,100.00	12,907.29	12,210.54	11,014.60	41.72	34.78	-0.02	1,140.93	523.65	1,892.70	1,837.18	55.51	34.095		
14,200.00	12,906.94	12,310.54	11,014.42	42.59	35.76	-0.02	1,240.93	523.08	1,892.53	1,836.38	56.14	33.710		
14,300.00	12,906.59	12,410.54	11,014.24	43.50	36.78	-0.02	1,340.93	522.51	1,892.35	1,835.55	56.80	33.313		
14,400.00	12,906.24	12,510.54	11,014.06	44.46	37.85	-0.02	1,440.93	521.95	1,892.18	1,834.68	57.50	32.905		
14,500.00	12,905.89	12,610.54	11,013.87	45.45	38.96	-0.02	1,540.93	521.38	1,892.01	1,833.78	58.24	32.488		
14,600.00	12,905.53	12,710.54	11,013.69	46.48	40.10	-0.02	1,640.92	520.81	1,891.84	1,832.84	59.00	32.063		
14,700.00	12,905.18	12,810.54	11,013.51	47.55	41.28	-0.02	1,740.92	520.24	1,891.67	1,831.87	59.80	31.633		
14,800.00	12,904.83	12,910.54	11,013.33	48.65	42.49	-0.02	1,840.92	519.68	1,891.50	1,830.87	60.63	31.198		
14,900.00	12,904.48	13,010.54	11,013.15	49.78	43.73	-0.02	1,940.92	519.11	1,891.33	1,829.85	61.48	30.761		
15,000.00	12,904.13	13,110.54	11,012.97	50.94	45.00	-0.02	2,040.92	518.54	1,891.16	1,828.79	62.37	30.321		
15,100.00	12,903.77	13,210.54	11,012.79	52.12	46.29	-0.01	2,140.91	517.97	1,890.99	1,827.71	63.28	29.882		
15,200.00	12,903.42	13,310.54	11,012.61	53.33	47.60	-0.01	2,240.91	517.41	1,890.82	1,826.60	64.22	29.444		
15,300.00	12,903.07	13,410.54	11,012.42	54.57	48.93	-0.01	2,340.91	516.84	1,890.65	1,825.47	65.18	29.008		
15,400.00	12,902.72	13,510.54	11,012.24	55.82	50.28	-0.01	2,440.91	516.27	1,890.48	1,824.32	66.16	28.574		
15,500.00	12,902.37	13,610.54	11,012.06	57.10	51.65	-0.01	2,540.91	515.70	1,890.31	1,823.14	67.17	28.144		
15,600.00	12,902.01	13,710.54	11,011.88	58.39	53.03	-0.01	2,640.90	515.14	1,890.14	1,821.95	68.19	27.718		
15,700.00	12,901.66	13,810.54	11,011.70	59.71	54.43	-0.01	2,740.90	514.57	1,889.97	1,820.73	69.24	27.297		
15,800.00	12,901.31	13,910.54	11,011.52	61.04	55.84	-0.01	2,840.90	514.00	1,889.80	1,819.49	70.30	26.880		
15,900.00	12,900.96	14,010.54	11,011.34	62.38	57.27	-0.01	2,940.90	513.44	1,889.63	1,818.24	71.39	26.470		
16,000.00	12,900.61	14,110.54	11,011.15	63.74	58.71	-0.01	3,040.90	512.87	1,889.46	1,816.97	72.49	26.065		
16,100.00	12,900.26	14,210.54	11,010.97	65.11	60.16	-0.01	3,140.89	512.30	1,889.29	1,815.68	73.61	25.667		
16,200.00	12,899.90	14,310.54	11,010.79	66.50	61.61	-0.01	3,240.89	511.73	1,889.12	1,814.37	74.74	25.275		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation





# Anticollision Report

<b>Company:</b>	Tap Rock Operating LLC	<b>Local Co-ordinate Reference:</b>	Well Double Diamond 24S 21E 1414 Well No. 238H
<b>Project:</b>	Eddy County, New Mexico NAD83 NM east	<b>TVD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Reference Site:</b>	Section 14-T24S-R31E	<b>MD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Site Error:</b>	0.00 ft	<b>North Reference:</b>	Grid
<b>Reference Well:</b>	Double Diamond 24S 21E 1414 Well No. 238H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.00 ft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	Original Hole	<b>Database:</b>	DB_Jul2216dt_v14
<b>Reference Design:</b>	rev1	<b>Offset TVD Reference:</b>	Offset Datum

Offset Design      Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 158H - Original Hole - rev0													Offset Site Error:	0.00 ft
Survey Program:    0-GYRO-NS, 6100-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis			Distance							
Measured Depth	Vertical Depth	Measured Depth	Vertical Depth	Reference	Offset	Highside Toolface	Offset Wellbore Centre		Between Centres	Between Ellipses	Minimum Separation	Separation Factor	Warning	
(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(°)	+N/-S (ft)	+E/-W (ft)	(ft)	(ft)	(ft)			
16,300.00	12,899.55	14,410.54	11,010.61	67.89	63.08	-0.01	3,340.89	511.17	1,888.94	1,813.05	75.89	24.889		
16,400.00	12,899.20	14,510.54	11,010.43	69.30	64.56	-0.01	3,440.89	510.60	1,888.77	1,811.72	77.06	24.511		
16,500.00	12,898.85	14,610.54	11,010.25	70.72	66.04	-0.01	3,540.89	510.03	1,888.60	1,810.37	78.24	24.139		
16,600.00	12,898.50	14,710.54	11,010.07	72.15	67.54	-0.01	3,640.88	509.46	1,888.43	1,809.00	79.43	23.775		
16,700.00	12,898.14	14,810.54	11,009.88	73.59	69.04	-0.01	3,740.88	508.90	1,888.26	1,807.63	80.63	23.418		
16,800.00	12,897.79	14,910.54	11,009.70	75.04	70.54	-0.01	3,840.88	508.33	1,888.09	1,806.24	81.85	23.067		
16,900.00	12,897.44	15,010.54	11,009.52	76.49	72.06	0.00	3,940.88	507.76	1,887.92	1,804.84	83.08	22.724		
17,000.00	12,897.09	15,110.54	11,009.34	77.96	73.58	0.00	4,040.88	507.19	1,887.75	1,803.43	84.32	22.388		
17,100.00	12,896.74	15,210.54	11,009.16	79.43	75.10	0.00	4,140.88	506.63	1,887.58	1,802.01	85.57	22.059		
17,200.00	12,896.39	15,310.54	11,008.98	80.91	76.63	0.00	4,240.87	506.06	1,887.41	1,800.58	86.83	21.737		
17,300.00	12,896.03	15,410.54	11,008.80	82.39	78.17	0.00	4,340.87	505.49	1,887.24	1,799.14	88.10	21.421		
17,400.00	12,895.68	15,510.54	11,008.62	83.88	79.71	0.00	4,440.87	504.93	1,887.07	1,797.69	89.38	21.113		
17,500.00	12,895.33	15,610.54	11,008.43	85.38	81.25	0.00	4,540.87	504.36	1,886.90	1,796.23	90.67	20.810		
17,600.00	12,894.98	15,710.54	11,008.25	86.88	82.80	0.00	4,640.87	503.79	1,886.73	1,794.76	91.97	20.515		
17,700.00	12,894.63	15,810.54	11,008.07	88.39	84.35	0.00	4,740.86	503.22	1,886.56	1,793.28	93.27	20.226		
17,736.22	12,894.50	15,846.75	11,008.01	88.94	84.91	0.00	4,777.08	503.02	1,886.50	1,792.75	93.75	20.123		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Anticollision Report

Company: Tap Rock Operating LLC  
Project: Eddy County, New Mexico NAD83 NM east  
Reference Site: Section 14-T24S-R31E  
Site Error: 0.00 ft  
Reference Well: Double Diamond 24S 21E 1414 Well No. 238H  
Well Error: 0.00 ft  
Reference Wellbore: Original Hole  
Reference Design: rev1

Local Co-ordinate Reference: Well Double Diamond 24S 21E 1414 Well No. 238H  
TVD Reference: RKB=3586+25 @ 3611.00ft  
MD Reference: RKB=3586+25 @ 3611.00ft  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Output errors are at 2.00 sigma  
Database: DB\_Jul2216dt\_v14  
Offset TVD Reference: Offset Datum

Offset Design														Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 224H - Original Hole - rev1		Offset Site Error:		0.00 ft	
Survey Program: 0-GYRO-NS 9000-MWD																Offset Well Error:		0.00 ft	
Reference		Offset		Semi Major Axis			Distance							Warning					
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre		Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor							
							+N/-S (ft)	+E/-W (ft)											
0.00	0.00	1.20	1.20	0.00	0.00	-90.00	0.00	-25.00	25.00										
100.00	100.00	101.20	101.20	0.13	0.14	-90.00	0.00	-25.00	25.00	24.73	0.27	93.989							
200.00	200.00	201.20	201.20	0.48	0.49	-90.00	0.00	-25.00	25.00	24.04	0.96	25.930							
300.00	300.00	301.20	301.20	0.83	0.84	-90.00	0.00	-25.00	25.00	23.34	1.66	15.040							
400.00	400.00	401.20	401.20	1.18	1.19	-90.00	0.00	-25.00	25.00	22.64	2.36	10.592							
500.00	500.00	501.20	501.20	1.53	1.54	-90.00	0.00	-25.00	25.00	21.94	3.06	8.174							
600.00	600.00	601.20	601.20	1.88	1.89	-90.00	0.00	-25.00	25.00	21.24	3.76	6.655							
700.00	700.00	701.20	701.20	2.24	2.24	-90.00	0.00	-25.00	25.00	20.55	4.45	5.612							
800.00	800.00	801.20	801.20	2.59	2.59	-90.00	0.00	-25.00	25.00	19.85	5.15	4.852							
900.00	900.00	901.20	901.20	2.94	2.94	-90.00	0.00	-25.00	25.00	19.15	5.85	4.273							
1,000.00	1,000.00	1,001.20	1,001.20	3.29	3.29	-90.00	0.00	-25.00	25.00	18.45	6.55	3.817							
1,100.00	1,100.00	1,101.20	1,101.20	3.64	3.64	-90.00	0.00	-25.00	25.00	17.75	7.25	3.450							
1,200.00	1,200.00	1,201.20	1,201.20	3.99	3.99	-90.00	0.00	-25.00	25.00	17.05	7.95	3.146 CC							
1,300.00	1,299.99	1,301.03	1,301.03	4.34	4.34	107.01	-0.83	-25.33	25.59	16.95	8.64	2.961 ES							
1,400.00	1,399.96	1,400.84	1,400.80	4.68	4.69	107.12	-3.26	-26.32	27.34	18.00	9.35	2.926							
1,500.00	1,499.86	1,500.62	1,500.48	5.03	5.04	107.30	-7.31	-27.96	30.26	20.20	10.06	3.009							
1,600.00	1,599.73	1,600.56	1,600.28	5.39	5.39	107.53	-12.16	-29.92	33.75	22.98	10.77	3.133							
1,700.00	1,699.59	1,700.49	1,700.08	5.75	5.75	107.71	-17.01	-31.88	37.24	25.76	11.49	3.242							
1,800.00	1,799.45	1,800.43	1,799.88	6.11	6.11	107.86	-21.86	-33.84	40.74	28.54	12.20	3.339							
1,900.00	1,899.31	1,900.37	1,899.69	6.46	6.46	107.99	-26.70	-35.80	44.23	31.32	12.91	3.426							
2,000.00	1,999.18	2,000.31	1,999.49	6.82	6.82	108.10	-31.55	-37.76	47.73	34.11	13.62	3.504							
2,100.00	2,099.04	2,100.25	2,099.29	7.17	7.17	108.19	-36.40	-39.72	51.22	36.89	14.33	3.575							
2,200.00	2,198.90	2,200.19	2,199.09	7.53	7.53	108.28	-41.25	-41.68	54.71	39.68	15.04	3.639							
2,300.00	2,298.77	2,300.13	2,298.89	7.88	7.88	108.35	-46.10	-43.64	58.21	42.47	15.74	3.697							
2,400.00	2,398.63	2,400.07	2,398.70	8.23	8.23	108.41	-50.95	-45.61	61.70	45.25	16.45	3.751							
2,500.00	2,498.49	2,500.01	2,498.50	8.59	8.59	108.47	-55.80	-47.57	65.20	48.04	17.16	3.801							
2,600.00	2,598.36	2,600.06	2,598.30	8.94	8.94	108.52	-60.65	-49.53	68.69	50.83	17.86	3.846							
2,700.00	2,698.22	2,700.12	2,698.10	9.29	9.29	108.57	-65.50	-51.49	72.19	53.62	18.57	3.888							
2,800.00	2,798.08	2,800.18	2,797.90	9.64	9.65	108.61	-70.34	-53.45	75.68	56.41	19.27	3.927							
2,900.00	2,897.94	2,900.24	2,897.71	10.00	10.00	108.65	-75.19	-55.41	79.18	59.20	19.97	3.964							
3,000.00	2,997.81	3,000.30	2,997.51	10.35	10.35	108.69	-80.04	-57.37	82.67	61.99	20.68	3.998							
3,100.00	3,097.67	3,100.36	3,097.31	10.70	10.70	108.72	-84.89	-59.33	86.17	64.79	21.38	4.030							
3,200.00	3,197.53	3,200.42	3,197.11	11.05	11.05	108.75	-89.74	-61.29	89.66	67.58	22.09	4.060							
3,300.00	3,297.40	3,300.48	3,296.91	11.40	11.41	108.78	-94.59	-63.25	93.16	70.37	22.79	4.088							
3,400.00	3,397.26	3,400.54	3,396.72	11.75	11.76	108.80	-99.44	-65.22	96.65	73.16	23.49	4.114							
3,500.00	3,497.12	3,500.61	3,495.52	12.11	12.11	108.83	-104.29	-67.18	100.15	75.95	24.19	4.139							
3,600.00	3,596.99	3,600.67	3,596.32	12.46	12.46	108.85	-109.14	-69.14	103.64	78.75	24.90	4.163							
3,700.00	3,696.85	3,700.73	3,696.12	12.81	12.81	108.87	-113.98	-71.10	107.14	81.54	25.60	4.185							
3,800.00	3,796.71	3,800.79	3,795.92	13.16	13.16	108.89	-118.83	-73.06	110.63	84.33	26.30	4.206							
3,900.00	3,896.57	3,900.85	3,895.72	13.51	13.51	108.91	-123.68	-75.02	114.13	87.12	27.00	4.227							
4,000.00	3,996.44	4,000.91	3,995.53	13.86	13.86	108.92	-128.53	-76.98	117.62	89.92	27.70	4.246							
4,100.00	4,096.30	4,100.97	4,095.33	14.21	14.22	108.94	-133.38	-78.94	121.12	92.71	28.41	4.264							
4,200.00	4,196.16	4,201.03	4,195.13	14.56	14.57	108.95	-138.23	-80.90	124.61	95.50	29.11	4.281							
4,300.00	4,296.03	4,301.09	4,294.93	14.91	14.92	108.97	-143.08	-82.87	128.11	98.30	29.81	4.298							
4,400.00	4,395.93	4,398.85	4,394.74	15.26	15.26	108.65	-147.93	-84.83	131.32	100.82	30.50	4.305							
4,500.00	4,495.89	4,499.62	4,495.42	15.61	15.61	107.97	-152.01	-86.48	133.69	102.49	31.20	4.284							
4,600.00	4,595.89	4,600.46	4,596.22	15.95	15.96	-89.70	-154.46	-87.47	134.91	103.01	31.90	4.229							
4,700.00	4,695.89	4,701.35	4,697.10	16.30	16.31	-90.04	-155.26	-87.79	135.23	102.63	32.60	4.148							
4,707.93	4,703.82	4,709.35	4,705.11	16.33	16.34	-90.04	-155.25	-87.79	135.23	102.57	32.65	4.141							
4,800.00	4,795.89	4,801.34	4,797.09	16.65	16.66	-90.04	-155.26	-87.79	135.23	101.94	33.29	4.062							
4,900.00	4,895.89	4,901.34	4,897.09	16.99	17.00	-90.04	-155.26	-87.79	135.23	101.24	33.99	3.979							

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation





# Anticollision Report

Company: Tap Rock Operating LLC  
Project: Eddy County, New Mexico NAD83 NM east  
Reference Site: Section 14-T24S-R31E  
Site Error: 0.00 ft  
Reference Well: Double Diamond 24S 21E 1414 Well No. 238H  
Well Error: 0.00 ft  
Reference Wellbore: Original Hole  
Reference Design: rev1  
Local Co-ordinate Reference: Well Double Diamond 24S 21E 1414 Well No. 238H  
TVD Reference: RKB=3586+25 @ 3611.00ft  
MD Reference: RKB=3586+25 @ 3611.00ft  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Output errors are at 2.00 sigma  
Database: DB\_Jul2216dt\_v14  
Offset TVD Reference: Offset Datum

Offset Design Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 224H - Original Hole - rev1											Offset Site Error:		0.00 ft
Survey Program: 0-GYRO-NS, 9000-MWD											Offset Well Error:		0.00 ft
Reference		Offset		Semi Major Axis			Distance						Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	
5,000.00	4,995.89	5,001.34	4,997.09	17.34	17.35	-90.04	-155.26	-87.79	135.23	100.55	34.68	3.899	
5,100.00	5,095.89	5,101.34	5,097.09	17.69	17.70	-90.04	-155.26	-87.79	135.23	99.85	35.37	3.823	
5,200.00	5,195.89	5,201.34	5,197.09	18.03	18.04	-90.04	-155.26	-87.79	135.23	99.16	36.07	3.749	
5,300.00	5,295.89	5,301.34	5,297.09	18.38	18.39	-90.04	-155.26	-87.79	135.23	98.47	36.76	3.678	
5,400.00	5,395.89	5,401.34	5,397.09	18.73	18.74	-90.04	-155.26	-87.79	135.23	97.77	37.46	3.610	
5,500.00	5,495.89	5,501.34	5,497.09	19.08	19.08	-90.04	-155.26	-87.79	135.23	97.08	38.15	3.544	
5,600.00	5,595.89	5,601.34	5,597.09	19.42	19.43	-90.04	-155.26	-87.79	135.23	96.38	38.85	3.481	
5,700.00	5,695.89	5,701.34	5,697.09	19.77	19.78	-90.04	-155.26	-87.79	135.23	95.69	39.54	3.420	
5,800.00	5,795.89	5,801.34	5,797.09	20.12	20.13	-90.04	-155.26	-87.79	135.23	94.99	40.24	3.361	
5,900.00	5,895.89	5,901.34	5,897.09	20.46	20.47	-90.04	-155.26	-87.79	135.23	94.30	40.93	3.304	
6,000.00	5,995.89	6,001.34	5,997.09	20.81	20.82	-90.04	-155.26	-87.79	135.23	93.60	41.63	3.249	
6,100.00	6,095.89	6,101.34	6,097.09	21.16	21.17	-90.04	-155.26	-87.79	135.23	92.91	42.32	3.195	
6,200.00	6,195.89	6,201.34	6,197.09	21.51	21.52	-90.04	-155.26	-87.79	135.23	92.21	43.02	3.144	
6,300.00	6,295.89	6,301.34	6,297.09	21.85	21.86	-90.04	-155.26	-87.79	135.23	91.52	43.71	3.094	
6,400.00	6,395.89	6,401.34	6,397.09	22.20	22.21	-90.04	-155.26	-87.79	135.23	90.82	44.41	3.045	
6,500.00	6,495.89	6,501.34	6,497.09	22.55	22.56	-90.04	-155.26	-87.79	135.23	90.12	45.10	2.998	
6,600.00	6,595.89	6,601.34	6,597.09	22.90	22.91	-90.04	-155.26	-87.79	135.23	89.43	45.80	2.953	
6,700.00	6,695.89	6,701.34	6,697.09	23.24	23.25	-90.04	-155.26	-87.79	135.23	88.73	46.50	2.908	
6,800.00	6,795.89	6,801.34	6,797.09	23.59	23.60	-90.04	-155.26	-87.79	135.23	88.04	47.19	2.865	
6,900.00	6,895.89	6,901.34	6,897.09	23.94	23.95	-90.04	-155.26	-87.79	135.23	87.34	47.89	2.824	
7,000.00	6,995.89	7,001.34	6,997.09	24.29	24.30	-90.04	-155.26	-87.79	135.23	86.64	48.58	2.783	
7,100.00	7,095.89	7,101.34	7,097.09	24.64	24.64	-90.04	-155.26	-87.79	135.23	85.95	49.28	2.744	
7,200.00	7,195.89	7,201.34	7,197.09	24.98	24.99	-90.04	-155.26	-87.79	135.23	85.25	49.98	2.706	
7,300.00	7,295.89	7,301.34	7,297.09	25.33	25.34	-90.04	-155.26	-87.79	135.23	84.56	50.67	2.669	
7,400.00	7,395.89	7,401.34	7,397.09	25.68	25.69	-90.04	-155.26	-87.79	135.23	83.86	51.37	2.632	
7,500.00	7,495.89	7,501.34	7,497.09	26.03	26.04	-90.04	-155.26	-87.79	135.23	83.16	52.07	2.597	
7,600.00	7,595.89	7,601.34	7,597.09	26.38	26.39	-90.04	-155.26	-87.79	135.23	82.47	52.76	2.563	
7,700.00	7,695.89	7,701.34	7,697.09	26.73	26.73	-90.04	-155.26	-87.79	135.23	81.77	53.46	2.530	
7,800.00	7,795.89	7,801.34	7,797.09	27.07	27.08	-90.04	-155.26	-87.79	135.23	81.07	54.16	2.497	
7,900.00	7,895.89	7,901.34	7,897.09	27.42	27.43	-90.04	-155.26	-87.79	135.23	80.38	54.85	2.465	
8,000.00	7,995.89	8,001.34	7,997.09	27.77	27.78	-90.04	-155.26	-87.79	135.23	79.68	55.55	2.434	
8,100.00	8,095.89	8,101.34	8,097.09	28.12	28.13	-90.04	-155.26	-87.79	135.23	78.98	56.25	2.404	
8,200.00	8,195.89	8,201.34	8,197.09	28.47	28.48	-90.04	-155.26	-87.79	135.23	78.29	56.94	2.375	
8,300.00	8,295.89	8,301.34	8,297.09	28.82	28.83	-90.04	-155.26	-87.79	135.23	77.59	57.64	2.346	
8,400.00	8,395.89	8,401.34	8,397.09	29.17	29.18	-90.04	-155.26	-87.79	135.23	76.89	58.34	2.318	
8,500.00	8,495.89	8,501.34	8,497.09	29.52	29.53	-90.04	-155.26	-87.79	135.23	76.20	59.03	2.291	
8,600.00	8,595.89	8,601.34	8,597.09	29.87	29.88	-90.04	-155.26	-87.79	135.23	75.50	59.73	2.264	
8,700.00	8,695.89	8,701.34	8,697.09	30.22	30.23	-90.04	-155.26	-87.79	135.23	74.80	60.43	2.238	
8,800.00	8,795.89	8,801.34	8,797.09	30.57	30.58	-90.04	-155.26	-87.79	135.23	74.11	61.12	2.212	
8,900.00	8,895.89	8,901.34	8,897.09	30.92	30.93	-90.04	-155.26	-87.79	135.23	73.41	61.82	2.187	
9,000.00	8,995.89	9,001.34	8,997.09	31.27	31.28	-90.04	-155.26	-87.79	135.23	72.71	62.52	2.163	
9,100.00	9,095.89	9,101.34	9,097.09	31.62	31.45	-90.04	-155.26	-87.79	135.23	72.19	63.04	2.145	
9,200.00	9,195.89	9,201.34	9,197.09	31.97	31.46	-90.04	-155.26	-87.79	135.23	71.84	63.39	2.133	
9,300.00	9,295.89	9,301.34	9,297.09	32.32	31.46	-90.04	-155.26	-87.79	135.23	71.48	63.75	2.121	
9,400.00	9,395.89	9,401.34	9,397.09	32.67	31.48	-90.04	-155.26	-87.79	135.23	71.12	64.11	2.109	
9,500.00	9,495.89	9,501.34	9,497.09	32.85	31.49	-90.04	-155.26	-87.79	135.23	70.93	64.30	2.103 SF	
9,600.00	9,595.88	9,601.33	9,597.08	32.86	31.51	161.46	-155.26	-87.79	136.37	72.04	64.33	2.120	
9,700.00	9,695.80	9,701.25	9,697.00	32.87	31.54	161.94	-155.26	-87.79	139.99	75.63	64.36	2.175	
9,800.00	9,795.59	9,801.04	9,796.79	32.88	31.57	162.70	-155.26	-87.79	146.13	81.72	64.40	2.269	
9,900.00	9,895.18	9,900.63	9,896.38	32.90	31.60	163.65	-155.26	-87.79	154.78	90.33	64.45	2.402	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Anticollision Report

Company: Tap Rock Operating LLC

Local Co-ordinate Reference:

Well Double Diamond 24S 21E 1414 Well No. 238H

Project: Eddy County, New Mexico NAD83 NM east

TVD Reference:

RKB=3586+25 @ 3611.00ft

Reference Site: Section 14-T24S-R31E

MD Reference:

RKB=3586+25 @ 3611.00ft

Site Error: 0.00 ft

North Reference:

Grid

Reference Well: Double Diamond 24S 21E 1414 Well No. 238H

Survey Calculation Method:

Minimum Curvature

Well Error: 0.00 ft

Output errors are at

2.00 sigma

Reference Wellbore: Original Hole

Database:

DB\_Jul2216dt\_v14

Reference Design: rev1

Offset TVD Reference:

Offset Datum

Offset Design Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 224H - Original Hole - rev1													Offset Site Error:	0.00 ft
Survey Program: 0-GYRO-NS, 9000-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (ft)	Separation Factor	Warning			
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)						
10,000.00	9,994.50	9,999.95	9,995.70	32.92	31.63	164.74	-155.26	-87.79	166.00	101.49	64.51	2.573		
10,100.00	10,093.54	10,097.66	10,093.41	32.94	31.67	165.51	-156.32	-88.22	179.67	115.10	64.57	2.783		
10,200.00	10,192.56	10,195.13	10,190.81	32.97	31.72	165.50	-159.68	-89.58	194.33	129.69	64.64	3.006		
10,300.00	10,291.58	10,307.37	10,288.11	33.01	31.77	164.84	-165.31	-91.86	209.76	145.04	64.72	3.241		
10,400.00	10,390.60	10,408.66	10,386.58	33.05	31.83	164.07	-171.77	-94.47	225.48	160.67	64.82	3.479		
10,500.00	10,489.62	10,509.94	10,485.04	33.10	31.88	163.39	-178.23	-97.09	241.24	176.32	64.92	3.716		
10,600.00	10,588.64	10,588.77	10,583.51	33.15	31.93	162.80	-184.69	-99.70	257.02	192.01	65.01	3.953		
10,700.00	10,687.66	10,687.48	10,681.98	33.21	32.00	162.28	-191.15	-102.31	272.83	207.70	65.13	4.189		
10,800.00	10,786.68	10,786.20	10,780.45	33.28	32.06	161.82	-197.61	-104.93	288.66	223.41	65.25	4.424		
10,900.00	10,885.70	10,884.91	10,878.91	33.35	32.13	161.40	-204.07	-107.54	304.51	239.12	65.39	4.657		
11,000.00	10,984.71	10,983.62	10,977.38	33.42	32.21	161.02	-210.53	-110.16	320.37	254.84	65.53	4.889		
11,100.00	11,083.73	11,082.34	11,075.85	33.50	32.29	160.68	-216.99	-112.77	336.24	270.56	65.68	5.120		
11,200.00	11,182.75	11,181.05	11,174.32	33.59	32.37	160.37	-223.45	-115.38	352.12	286.28	65.83	5.349		
11,300.00	11,281.77	11,279.77	11,272.78	33.68	32.46	160.09	-229.91	-118.00	368.01	302.01	66.00	5.576		
11,400.00	11,380.79	11,378.48	11,371.25	33.77	32.56	159.83	-236.37	-120.61	383.91	317.73	66.17	5.801		
11,500.00	11,479.81	11,477.19	11,469.72	33.88	32.65	159.59	-242.83	-123.23	399.82	333.46	66.36	6.025		
11,600.00	11,578.83	11,577.65	11,569.94	33.98	32.76	159.39	-249.21	-125.81	415.65	349.10	66.55	6.246		
11,700.00	11,677.85	11,681.14	11,673.31	34.09	32.86	159.49	-253.69	-127.62	430.59	363.84	66.75	6.450		
11,800.00	11,777.08	11,785.08	11,777.23	34.20	32.97	159.90	-255.58	-128.38	442.98	376.03	66.95	6.616		
11,900.00	11,876.60	11,885.65	11,877.80	34.31	33.07	160.37	-255.64	-128.41	452.20	385.06	67.15	6.735		
12,000.00	11,976.34	11,985.46	11,977.55	34.42	33.17	160.97	-253.53	-128.42	458.95	391.61	67.34	6.815		
12,100.00	12,076.23	12,082.25	12,072.82	34.53	33.26	163.19	-237.14	-128.52	463.61	396.08	67.53	6.865		
12,200.00	12,176.21	12,171.22	12,156.84	34.63	33.35	166.82	-208.14	-128.68	467.93	400.24	67.70	6.912		
12,300.00	12,276.21	12,249.80	12,226.53	34.73	33.42	-80.15	-171.98	-128.89	475.32	407.57	67.75	7.016		
12,400.00	12,376.15	12,318.08	12,282.59	34.83	33.50	-89.23	-133.06	-129.12	490.24	422.65	67.99	7.253		
12,500.00	12,474.58	12,382.56	12,330.93	34.94	33.58	-83.16	-90.43	-129.36	513.19	445.96	67.23	7.634		
12,600.00	12,568.56	12,444.95	12,372.85	35.04	33.67	-77.34	-44.28	-129.63	541.67	474.91	66.77	8.113		
12,700.00	12,655.26	12,505.69	12,408.62	35.15	33.78	-72.04	4.78	-129.91	573.23	506.92	66.32	8.644		
12,800.00	12,732.02	12,565.16	12,438.42	35.26	33.91	-67.42	56.21	-130.21	605.81	539.84	65.97	9.183		
12,900.00	12,796.52	12,623.64	12,462.37	35.40	34.05	-63.56	109.54	-130.51	637.80	572.00	65.80	9.693		
13,000.00	12,846.80	12,685.33	12,482.01	35.60	34.23	-60.50	168.00	-130.85	667.75	601.87	65.88	10.136		
13,100.00	12,881.72	12,750.00	12,497.08	35.87	34.43	-58.51	230.86	-131.21	694.48	628.28	66.20	10.490		
13,200.00	12,902.80	12,809.96	12,505.95	36.22	34.66	-57.25	290.14	-131.55	718.74	652.04	66.70	10.775		
13,300.00	12,910.09	12,871.97	12,509.86	36.64	34.91	-56.42	352.00	-131.90	740.48	673.09	67.39	10.989		
13,400.00	12,909.76	12,960.22	12,509.76	37.11	35.32	-57.64	440.26	-132.40	758.46	690.22	68.24	11.115		
13,500.00	12,909.40	13,059.36	12,509.42	37.63	35.83	-58.46	539.39	-132.96	769.43	700.27	69.15	11.126		
13,600.00	12,909.05	13,159.24	12,509.08	38.18	36.42	-58.74	639.27	-133.53	773.02	702.92	70.10	11.028		
13,700.00	12,908.70	13,259.24	12,508.74	38.77	37.08	-58.74	739.26	-134.10	773.00	701.89	71.11	10.871		
13,800.00	12,908.35	13,359.24	12,508.40	39.43	37.79	-58.74	839.26	-134.67	772.97	700.75	72.22	10.703		
13,900.00	12,908.00	13,459.24	12,508.06	40.14	38.56	-58.74	939.26	-135.23	772.95	699.52	73.43	10.526		
14,000.00	12,907.64	13,559.24	12,507.72	40.91	39.39	-58.74	1,039.26	-135.80	772.93	698.19	74.74	10.342		
14,100.00	12,907.29	13,659.24	12,507.38	41.72	40.27	-58.74	1,139.26	-136.37	772.91	696.78	76.13	10.152		
14,200.00	12,906.94	13,759.24	12,507.04	42.59	41.19	-58.74	1,239.25	-136.93	772.89	695.28	77.61	9.959		
14,300.00	12,906.59	13,859.24	12,506.70	43.50	42.16	-58.74	1,339.25	-137.50	772.87	693.71	79.16	9.763		
14,400.00	12,906.24	13,959.24	12,506.36	44.46	43.17	-58.74	1,439.25	-138.07	772.84	692.06	80.79	9.566		
14,500.00	12,905.89	14,059.24	12,506.02	45.45	44.22	-58.74	1,539.25	-138.64	772.82	690.34	82.48	9.369		
14,600.00	12,905.53	14,159.24	12,505.68	46.48	45.31	-58.74	1,639.24	-139.20	772.80	688.56	84.24	9.173		
14,700.00	12,905.18	14,259.24	12,505.34	47.55	46.43	-58.74	1,739.24	-139.77	772.78	686.71	86.07	8.979		
14,800.00	12,904.83	14,359.24	12,505.00	48.65	47.58	-58.74	1,839.24	-140.34	772.76	684.82	87.94	8.787		
14,900.00	12,904.48	14,459.24	12,504.66	49.78	48.76	-58.74	1,939.24	-140.91	772.74	682.87	89.87	8.598		
15,000.00	12,904.13	14,559.24	12,504.32	50.94	49.96	-58.74	2,039.24	-141.47	772.72	680.87	91.85	8.413		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation





# Anticollision Report

Company: Tap Rock Operating LLC

Local Co-ordinate Reference:

Well Double Diamond 24S 21E 1414 Well No. 238H

Project: Eddy County, New Mexico NAD83 NM east

TVD Reference:

RKB=3586+25 @ 3611.00ft

Reference Site: Section 14-T24S-R31E

MD Reference:

RKB=3586+25 @ 3611.00ft

Site Error: 0.00 ft

North Reference:

Grid

Reference Well: Double Diamond 24S 21E 1414 Well No. 238H

Survey Calculation Method:

Minimum Curvature

Well Error: 0.00 ft

Output errors are at

2.00 sigma

Reference Wellbore: Original Hole

Database:

DB\_Jul2216dt\_v14

Reference Design: rev1

Offset TVD Reference:

Offset Datum

Offset Design Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 224H - Original Hole - rev1													Offset Site Error:	0.00 ft
Survey Program: 0-GYRO-NS, 9000-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis			Distance							Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Centre +E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor		
15,100.00	12,903.77	14,659.24	12,503.98	52.12	51.19	-58.74	2,139.23	-142.04	772.69	678.82	93.87	8.231		
15,200.00	12,903.42	14,759.24	12,503.64	53.33	52.45	-58.74	2,239.23	-142.61	772.67	676.73	95.94	8.054		
15,300.00	12,903.07	14,859.24	12,503.29	54.57	53.72	-58.74	2,339.23	-143.18	772.65	674.61	98.04	7.881		
15,400.00	12,902.72	14,959.24	12,502.95	55.82	55.02	-58.74	2,439.23	-143.74	772.63	672.44	100.18	7.712		
15,500.00	12,902.37	15,059.24	12,502.61	57.10	56.34	-58.74	2,539.22	-144.31	772.61	670.25	102.36	7.548		
15,600.00	12,902.01	15,159.24	12,502.27	58.39	57.67	-58.74	2,639.22	-144.88	772.59	668.02	104.57	7.388		
15,700.00	12,901.66	15,259.24	12,501.93	59.71	59.02	-58.74	2,739.22	-145.44	772.56	665.76	106.81	7.233		
15,800.00	12,901.31	15,359.24	12,501.59	61.04	60.38	-58.74	2,839.22	-146.01	772.54	663.47	109.07	7.083		
15,900.00	12,900.96	15,459.24	12,501.25	62.38	61.76	-58.74	2,939.22	-146.58	772.52	661.16	111.36	6.937		
16,000.00	12,900.61	15,559.24	12,500.91	63.74	63.15	-58.74	3,039.21	-147.15	772.50	658.82	113.68	6.796		
16,100.00	12,900.26	15,659.24	12,500.57	65.11	64.55	-58.74	3,139.21	-147.71	772.48	656.46	116.01	6.658		
16,200.00	12,899.90	15,759.24	12,500.23	66.50	65.97	-58.74	3,239.21	-148.28	772.46	654.08	118.37	6.526		
16,300.00	12,899.55	15,859.24	12,499.89	67.89	67.39	-58.74	3,339.21	-148.85	772.43	651.69	120.75	6.397		
16,400.00	12,899.20	15,959.24	12,499.55	69.30	68.83	-58.74	3,439.20	-149.42	772.41	649.27	123.15	6.272		
16,500.00	12,898.85	16,059.24	12,499.21	70.72	70.27	-58.74	3,539.20	-149.98	772.39	646.83	125.56	6.152		
16,600.00	12,898.50	16,159.24	12,498.87	72.15	71.73	-58.74	3,639.20	-150.55	772.37	644.39	127.99	6.035		
16,700.00	12,898.14	16,259.24	12,498.53	73.59	73.19	-58.74	3,739.20	-151.12	772.35	641.92	130.43	5.922		
16,800.00	12,897.79	16,359.24	12,498.19	75.04	74.66	-58.74	3,839.20	-151.69	772.33	639.44	132.88	5.812		
16,900.00	12,897.44	16,459.24	12,497.85	76.49	76.14	-58.74	3,939.19	-152.25	772.31	636.95	135.35	5.706		
17,000.00	12,897.09	16,559.24	12,497.51	77.96	77.62	-58.74	4,039.19	-152.82	772.28	634.45	137.83	5.603		
17,100.00	12,896.74	16,659.24	12,497.17	79.43	79.12	-58.74	4,139.19	-153.39	772.26	631.94	140.32	5.503		
17,200.00	12,896.39	16,759.24	12,496.83	80.91	80.62	-58.74	4,239.19	-153.95	772.24	629.42	142.83	5.407		
17,300.00	12,896.03	16,859.24	12,496.49	82.39	82.12	-58.74	4,339.19	-154.52	772.22	626.88	145.34	5.313		
17,400.00	12,895.68	16,959.24	12,496.15	83.88	83.63	-58.74	4,439.18	-155.09	772.20	624.34	147.86	5.223		
17,500.00	12,895.33	17,059.24	12,495.81	85.38	85.14	-58.74	4,539.18	-155.66	772.18	621.79	150.38	5.135		
17,600.00	12,894.98	17,159.24	12,495.47	86.88	86.66	-58.74	4,639.18	-156.22	772.15	619.23	152.92	5.049		
17,700.00	12,894.63	17,259.24	12,495.13	88.39	88.19	-58.74	4,739.18	-156.79	772.13	616.67	155.46	4.967		
17,735.22	12,894.50	17,295.45	12,495.00	88.94	88.74	-58.74	4,775.39	-157.00	772.12	615.74	156.38	4.937		



## Anticollision Report

Company: Tap Rock Operating LLC

Local Co-ordinate Reference:

Well Double Diamond 24S 21E 1414 Well No. 238H

Project: Eddy County, New Mexico NAD83 NM east

TVD Reference:

RKB=3586+25 @ 3611.00ft

Reference Site: Section 14-T24S-R31E

MD Reference:

RKB=3586+25 @ 3611.00ft

Site Error: 0.00 ft

North Reference:

Grid

Reference Well: Double Diamond 24S 21E 1414 Well No. 238H

Survey Calculation Method:

Minimum Curvature

Well Error: 0.00 ft

Output errors are at

2.00 sigma

Reference Wellbore: Original Hole

Database:

DB\_Jul2216dt\_v14

Reference Design: rev1

Offset TVD Reference:

Offset Datum

Offset Design Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 228H - Original Hole - rev1														Offset Site Error:	0.00 ft
Survey Program: 0-GYRO-NS, 8300-MWD														Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis			Distance								Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor			
0.00	0.00	0.10	-0.10	0.00	0.00	-90.00	0.00	-50.00	50.00						
100.00	100.00	100.10	99.90	0.13	0.13	-90.00	0.00	-50.00	50.00	49.74	0.26	190.732			
200.00	200.00	200.10	199.90	0.48	0.48	-90.00	0.00	-50.00	50.00	49.04	0.96	52.068			
300.00	300.00	300.10	299.90	0.83	0.83	-90.00	0.00	-50.00	50.00	48.34	1.66	30.149			
400.00	400.00	400.10	399.90	1.18	1.18	-90.00	0.00	-50.00	50.00	47.64	2.36	21.218			
500.00	500.00	500.10	499.90	1.53	1.53	-90.00	0.00	-50.00	50.00	46.95	3.05	16.368			
600.00	600.00	600.10	599.90	1.88	1.89	-90.00	0.00	-50.00	50.00	46.25	3.75	13.323			
700.00	700.00	700.10	699.90	2.24	2.24	-90.00	0.00	-50.00	50.00	45.55	4.45	11.234			
800.00	800.00	800.10	799.90	2.59	2.59	-90.00	0.00	-50.00	50.00	44.85	5.15	9.711			
900.00	900.00	900.10	899.90	2.94	2.94	-90.00	0.00	-50.00	50.00	44.15	5.85	8.551			
1,000.00	1,000.00	1,000.10	999.90	3.29	3.29	-90.00	0.00	-50.00	50.00	43.45	6.55	7.639			
1,100.00	1,100.00	1,100.10	1,099.90	3.64	3.64	-90.00	0.00	-50.00	50.00	42.76	7.24	6.903			
1,200.00	1,200.00	1,200.10	1,199.90	3.99	3.99	-90.00	0.00	-50.00	50.00	42.06	7.94	6.296 CC			
1,300.00	1,299.99	1,300.11	1,299.89	4.34	4.34	107.95	0.00	-50.00	50.26	41.62	8.64	5.817 ES			
1,400.00	1,399.96	1,400.14	1,399.86	4.68	4.69	110.73	0.00	-50.00	51.13	41.79	9.34	5.474			
1,500.00	1,499.86	1,499.76	1,499.76	5.03	5.04	115.14	0.00	-50.00	52.83	42.79	10.04	5.260			
1,600.00	1,599.73	1,600.47	1,600.47	5.39	5.39	120.53	0.23	-49.15	54.49	43.74	10.75	5.068			
1,700.00	1,699.59	1,701.12	1,701.08	5.75	5.75	126.57	0.91	-46.59	55.14	43.69	11.45	4.814			
1,800.00	1,799.45	1,801.66	1,801.52	6.11	6.10	133.58	2.05	-42.33	55.06	42.90	12.16	4.529			
1,832.57	1,831.97	1,834.13	1,833.94	6.22	6.22	136.04	2.49	-40.69	55.01	42.62	12.39	4.441			
1,900.00	1,899.31	1,901.38	1,901.11	6.46	6.46	141.12	3.41	-37.29	55.22	42.36	12.86	4.294			
2,000.00	1,999.18	2,001.12	2,000.71	6.82	6.81	148.48	4.76	-32.25	56.33	42.77	13.57	4.153			
2,100.00	2,099.04	2,100.86	2,100.31	7.17	7.17	155.45	6.11	-27.21	58.34	44.07	14.27	4.088			
2,200.00	2,198.90	2,200.59	2,199.91	7.53	7.52	161.87	7.46	-22.16	61.14	46.17	14.98	4.083			
2,300.00	2,298.77	2,300.33	2,299.50	7.88	7.88	167.67	8.81	-17.12	64.65	48.97	15.68	4.123			
2,400.00	2,398.63	2,400.06	2,399.10	8.23	8.23	172.82	10.16	-12.08	68.74	52.36	16.39	4.195			
2,500.00	2,498.49	2,500.20	2,498.70	8.59	8.58	177.37	11.51	-7.04	73.33	56.24	17.09	4.291			
2,600.00	2,598.36	2,600.47	2,598.30	8.94	8.94	-178.64	12.86	-2.00	78.33	60.53	17.80	4.401			
2,700.00	2,698.22	2,700.73	2,697.90	9.29	9.29	-175.15	14.21	3.05	83.66	65.15	18.50	4.521			
2,800.00	2,798.08	2,800.99	2,797.50	9.64	9.65	-172.08	15.56	8.09	89.26	70.05	19.21	4.647			
2,900.00	2,897.94	2,901.26	2,897.10	10.00	10.00	-169.38	16.92	13.13	95.09	75.18	19.91	4.775			
3,000.00	2,997.81	3,001.52	2,996.70	10.35	10.35	-166.99	18.27	18.17	101.10	80.48	20.62	4.904			
3,100.00	3,097.67	3,101.79	3,096.30	10.70	10.71	-164.88	19.62	23.21	107.27	85.95	21.32	5.031			
3,200.00	3,197.53	3,202.05	3,195.90	11.05	11.06	-162.99	20.97	28.25	113.57	91.55	22.03	5.156			
3,300.00	3,297.40	3,297.68	3,295.49	11.40	11.40	-161.31	22.32	33.30	119.98	97.27	22.71	5.282			
3,400.00	3,397.26	3,402.58	3,395.09	11.75	11.77	-159.80	23.67	38.34	126.48	103.05	23.43	5.397			
3,500.00	3,497.12	3,502.84	3,494.69	12.11	12.12	-158.44	25.02	43.38	133.06	108.92	24.14	5.513			
3,600.00	3,596.99	3,596.89	3,594.29	12.46	12.45	-157.20	26.37	48.42	139.71	114.89	24.82	5.629			
3,700.00	3,696.85	3,703.37	3,693.89	12.81	12.82	-156.08	27.72	53.46	146.42	120.87	25.55	5.732			
3,800.00	3,796.71	3,803.64	3,793.49	13.16	13.18	-155.06	29.07	58.51	153.18	126.93	26.25	5.836			
3,900.00	3,896.57	3,903.90	3,893.09	13.51	13.53	-154.12	30.43	63.55	159.98	133.03	26.95	5.936			
4,000.00	3,996.44	4,004.17	3,992.69	13.86	13.88	-153.26	31.78	68.59	166.82	139.17	27.66	6.032			
4,100.00	4,096.30	4,095.57	4,092.29	14.21	14.20	-152.47	33.13	73.63	173.70	145.37	28.33	6.132			
4,200.00	4,196.16	4,204.70	4,191.89	14.56	14.59	-151.74	34.48	78.67	180.61	151.54	29.06	6.214			
4,300.00	4,296.03	4,304.96	4,291.48	14.91	14.94	-151.06	35.83	83.72	187.54	157.77	29.77	6.301			
4,400.00	4,395.93	4,394.82	4,391.12	15.26	15.25	-150.33	37.18	88.76	193.74	163.31	30.43	6.366			
4,500.00	4,495.89	4,496.24	4,492.44	15.61	15.61	-149.58	38.35	93.11	198.09	166.95	31.14	6.361			
4,600.00	4,595.89	4,597.89	4,594.06	15.95	15.96	-148.96	39.05	95.73	200.12	168.27	31.85	6.283			
4,700.00	4,695.89	4,699.62	4,695.78	16.30	16.31	-148.19	39.28	96.61	200.56	168.00	32.56	6.160			
4,800.00	4,795.89	4,800.37	4,795.79	16.65	16.66	-147.19	39.28	96.61	200.56	167.31	33.25	6.031			
4,900.00	4,895.89	4,900.37	4,895.79	16.99	17.01	-146.19	39.28	96.61	200.56	166.61	33.95	5.908			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation





# Anticollision Report

Company: Tap Rock Operating LLC

Local Co-ordinate Reference:

Well Double Diamond 24S 21E 1414 Well No. 238H

Project: Eddy County, New Mexico NAD83 NM east

TVD Reference:

RKB=3586+25 @ 3611.00ft

Reference Site: Section 14-T24S-R31E

MD Reference:

RKB=3586+25 @ 3611.00ft

Site Error: 0.00 ft

North Reference:

Grid

Reference Well: Double Diamond 24S 21E 1414 Well No. 238H

Survey Calculation Method:

Minimum Curvature

Well Error: 0.00 ft

Output errors are at

2.00 sigma

Reference Wellbore: Original Hole

Database:

DB\_Jul2216dt\_v14

Reference Design: rev1

Offset TVD Reference:

Offset Datum

Offset Design Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 228H - Original Hole - rev1													Offset Site Error: 0.00 ft	
Survey Program: 0-GYRO-NS, 8300-MWD													Offset Well Error: 0.00 ft	
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth	Vertical Depth	Measured Depth	Vertical Depth	Reference	Offset	Highside Toolface	Offset Wellbore Centre	Between Centres	Between Ellipses	Minimum Separation	Separation Factor			
(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(°)	+N/-S (ft)	+E/-W (ft)	(ft)	(ft)	(ft)			
5,000.00	4,995.89	5,000.37	4,995.79	17.34	17.36	14.19	39.28	96.61	200.56	165.91	34.65	5.789		
5,100.00	5,095.89	5,100.37	5,095.79	17.69	17.70	14.19	39.28	96.61	200.56	165.22	35.34	5.675		
5,200.00	5,195.89	5,200.37	5,195.79	18.03	18.05	14.19	39.28	96.61	200.56	164.52	36.04	5.565		
5,300.00	5,295.89	5,300.37	5,295.79	18.38	18.40	14.19	39.28	96.61	200.56	163.83	36.73	5.460		
5,400.00	5,395.89	5,400.37	5,395.79	18.73	18.75	14.19	39.28	96.61	200.56	163.13	37.43	5.358		
5,500.00	5,495.89	5,500.37	5,495.79	19.08	19.09	14.19	39.28	96.61	200.56	162.43	38.13	5.260		
5,600.00	5,595.89	5,600.37	5,595.79	19.42	19.44	14.19	39.28	96.61	200.56	161.74	38.82	5.166		
5,700.00	5,695.89	5,700.37	5,695.79	19.77	19.79	14.19	39.28	96.61	200.56	161.04	39.52	5.075		
5,800.00	5,795.89	5,800.37	5,795.79	20.12	20.14	14.19	39.28	96.61	200.56	160.34	40.22	4.987		
5,900.00	5,895.89	5,900.37	5,895.79	20.46	20.48	14.19	39.28	96.61	200.56	159.65	40.91	4.902		
6,000.00	5,995.89	6,000.37	5,995.79	20.81	20.83	14.19	39.28	96.61	200.56	158.95	41.61	4.820		
6,100.00	6,095.89	6,100.37	6,095.79	21.16	21.18	14.19	39.28	96.61	200.56	158.25	42.31	4.741		
6,200.00	6,195.89	6,200.37	6,195.79	21.51	21.53	14.19	39.28	96.61	200.56	157.55	43.00	4.664		
6,300.00	6,295.89	6,300.37	6,295.79	21.85	21.88	14.19	39.28	96.61	200.56	156.86	43.70	4.589		
6,400.00	6,395.89	6,400.37	6,395.79	22.20	22.22	14.19	39.28	96.61	200.56	156.16	44.40	4.517		
6,500.00	6,495.89	6,500.37	6,495.79	22.55	22.57	14.19	39.28	96.61	200.56	155.46	45.10	4.447		
6,600.00	6,595.89	6,600.37	6,595.79	22.90	22.92	14.19	39.28	96.61	200.56	154.77	45.79	4.380		
6,700.00	6,695.89	6,700.37	6,695.79	23.24	23.27	14.19	39.28	96.61	200.56	154.07	46.49	4.314		
6,800.00	6,795.89	6,800.37	6,795.79	23.59	23.62	14.19	39.28	96.61	200.56	153.37	47.19	4.250		
6,900.00	6,895.89	6,900.37	6,895.79	23.94	23.97	14.19	39.28	96.61	200.56	152.67	47.89	4.188		
7,000.00	6,995.89	7,000.37	6,995.79	24.29	24.32	14.19	39.28	96.61	200.56	151.97	48.58	4.128		
7,100.00	7,095.89	7,100.37	7,095.79	24.64	24.67	14.19	39.28	96.61	200.56	151.28	49.28	4.070		
7,200.00	7,195.89	7,200.37	7,195.79	24.98	25.01	14.19	39.28	96.61	200.56	150.58	49.98	4.013		
7,300.00	7,295.89	7,300.37	7,295.79	25.33	25.36	14.19	39.28	96.61	200.56	149.88	50.68	3.958		
7,400.00	7,395.89	7,400.37	7,395.79	25.68	25.71	14.19	39.28	96.61	200.56	149.18	51.38	3.904		
7,500.00	7,495.89	7,500.37	7,495.79	26.03	26.06	14.19	39.28	96.61	200.56	148.49	52.07	3.851		
7,600.00	7,595.89	7,600.37	7,595.79	26.38	26.41	14.19	39.28	96.61	200.56	147.79	52.77	3.800		
7,700.00	7,695.89	7,700.37	7,695.79	26.73	26.76	14.19	39.28	96.61	200.56	147.09	53.47	3.751		
7,800.00	7,795.89	7,800.37	7,795.79	27.07	27.11	14.19	39.28	96.61	200.56	146.39	54.17	3.703		
7,900.00	7,895.89	7,900.37	7,895.79	27.42	27.46	14.19	39.28	96.61	200.56	145.69	54.87	3.655		
8,000.00	7,995.89	8,000.37	7,995.79	27.77	27.81	14.19	39.28	96.61	200.56	145.00	55.56	3.609		
8,100.00	8,095.89	8,100.37	8,095.79	28.12	28.16	14.19	39.28	96.61	200.56	144.30	56.26	3.565		
8,200.00	8,195.89	8,200.37	8,195.79	28.47	28.51	14.19	39.28	96.61	200.56	143.60	56.96	3.521		
8,300.00	8,295.89	8,299.63	8,295.79	28.82	28.68	14.19	39.28	96.61	200.56	143.08	57.48	3.489		
8,400.00	8,395.89	8,401.32	8,397.47	29.17	28.70	14.53	38.59	97.64	200.15	142.31	57.84	3.460		
8,500.00	8,495.89	8,502.95	8,499.02	29.52	28.71	15.60	36.40	100.92	198.91	140.71	58.20	3.418		
8,600.00	8,595.89	8,604.29	8,600.15	29.87	28.72	17.43	32.72	106.43	196.97	138.41	58.56	3.364		
8,700.00	8,695.89	8,705.22	8,700.64	30.22	28.74	20.05	27.58	114.13	194.59	135.66	58.92	3.302		
8,800.00	8,795.89	8,805.58	8,800.30	30.57	28.76	23.48	21.01	123.97	192.13	132.82	59.30	3.240		
8,900.00	8,895.89	8,905.26	8,898.94	30.92	28.80	27.74	13.04	135.90	190.07	130.38	59.69	3.184		
9,000.00	8,995.89	9,004.09	8,996.35	31.27	28.84	32.78	3.78	149.77	189.04	128.95	60.09	3.146		
9,018.19	9,014.08	9,022.00	9,013.98	31.34	28.84	33.73	2.03	152.39	189.01	128.85	60.16	3.142		
9,100.00	9,095.89	9,102.53	9,093.26	31.62	28.88	38.02	-5.84	164.18	189.56	129.08	60.48	3.134		
9,200.00	9,195.89	9,200.97	9,190.16	31.97	28.94	43.19	-15.46	178.59	191.70	130.83	60.87	3.149		
9,300.00	9,295.89	9,300.59	9,287.06	32.32	29.00	48.21	-25.08	192.99	195.41	134.16	61.25	3.190		
9,400.00	9,395.89	9,402.15	9,383.96	32.67	29.07	53.02	-34.70	207.40	200.60	138.97	61.63	3.255		
9,500.00	9,495.89	9,503.71	9,480.87	32.85	29.14	57.56	-44.32	221.81	207.15	145.32	61.83	3.350		
9,600.00	9,595.88	9,594.92	9,577.96	32.86	29.22	-47.00	-53.96	236.24	214.14	152.26	61.87	3.461		
9,700.00	9,695.80	9,705.06	9,675.43	32.87	29.32	-43.63	-63.63	250.73	220.23	158.29	61.94	3.556		
9,800.00	9,795.59	9,805.74	9,773.21	32.88	29.42	-40.89	-73.34	265.27	225.04	163.04	62.01	3.629		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Anticollision Report

Company: Tap Rock Operating LLC  
Project: Eddy County, New Mexico NAD83 NM east  
Reference Site: Section 14-T24S-R31E  
Site Error: 0.00 ft  
Reference Well: Double Diamond 24S 21E 1414 Well No. 238H  
Well Error: 0.00 ft  
Reference Wellbore: Original Hole  
Reference Design: rev1  
Local Co-ordinate Reference: Well Double Diamond 24S 21E 1414 Well No. 238H  
TVD Reference: RKB=3586+25 @ 3611.00ft  
MD Reference: RKB=3586+25 @ 3611.00ft  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Output errors are at 2.00 sigma  
Database: DB\_Jul2216dt\_v14  
Offset TVD Reference: Offset Datum

Offset Design Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 228H - Original Hole - rev1													Offset Site Error:	0.00 ft
Survey Program: 0-GYRO-NS. 8300-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (ft)	Separation Factor	Warning			
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Between Centres (ft)	Between Ellipses (ft)						
9,900.00	9,895.18	9,907.17	9,871.22	32.90	29.52	-38.68	-83.07	279.84	228.29	166.20	62.09	3.677		
10,000.00	9,994.50	10,007.42	9,969.41	32.92	29.63	-36.93	-92.82	294.44	229.76	167.58	62.19	3.695		
10,100.00	10,093.54	10,107.58	10,067.69	32.94	29.75	-35.53	-102.57	309.05	229.70	167.40	62.30	3.687		
10,200.00	10,192.56	10,207.73	10,165.98	32.97	29.87	-34.16	-112.33	323.66	229.60	167.18	62.42	3.678		
10,223.33	10,215.67	10,215.56	10,188.92	32.98	29.88	-33.84	-114.61	327.07	229.60	167.17	62.43	3.678		
10,300.00	10,291.58	10,307.89	10,264.27	33.01	30.00	-32.78	-122.09	338.28	229.64	167.09	62.55	3.671		
10,400.00	10,390.60	10,391.96	10,362.56	33.05	30.12	-31.41	-131.84	352.89	229.80	167.14	62.66	3.667		
10,500.00	10,489.62	10,491.81	10,460.85	33.10	30.26	-30.04	-141.60	367.50	230.10	167.30	62.81	3.664		
10,600.00	10,588.64	10,608.34	10,559.14	33.15	30.43	-28.68	-151.36	382.11	230.53	167.55	62.98	3.660		
10,700.00	10,687.66	10,691.51	10,657.43	33.21	30.56	-27.32	-161.12	396.73	231.10	167.98	63.12	3.661		
10,800.00	10,786.68	10,808.65	10,755.72	33.28	30.75	-25.97	-170.87	411.34	231.79	168.48	63.31	3.661		
10,900.00	10,885.70	10,908.80	10,854.01	33.35	30.92	-24.62	-180.63	425.95	232.61	169.12	63.49	3.664		
11,000.00	10,984.71	10,991.05	10,952.30	33.42	31.06	-23.29	-190.39	440.57	233.55	169.91	63.64	3.670		
11,100.00	11,083.73	11,109.10	11,050.59	33.50	31.27	-21.97	-200.15	455.18	234.63	170.77	63.86	3.674		
11,200.00	11,182.75	11,190.75	11,148.88	33.59	31.42	-20.66	-209.90	469.79	235.82	171.79	64.03	3.683		
11,300.00	11,281.77	11,291.66	11,248.23	33.68	31.62	-19.36	-219.73	484.51	237.10	172.84	64.26	3.690		
11,400.00	11,380.79	11,397.01	11,352.27	33.77	31.81	-18.27	-228.92	498.27	236.93	172.34	64.59	3.668		
11,500.00	11,479.81	11,502.40	11,456.77	33.88	32.00	-17.57	-236.51	509.64	234.51	169.59	64.92	3.613		
11,600.00	11,578.83	11,607.69	11,561.50	33.98	32.19	-17.23	-242.50	518.60	229.78	164.55	65.23	3.523		
11,700.00	11,677.85	11,712.71	11,666.22	34.09	32.36	-17.26	-246.86	525.15	222.76	157.22	65.54	3.399		
11,800.00	11,777.08	11,817.46	11,770.85	34.20	32.53	-17.54	-249.63	529.28	214.94	149.11	65.83	3.265		
11,900.00	11,876.60	11,922.01	11,875.38	34.31	32.68	-18.05	-250.80	531.04	207.32	141.21	66.11	3.136		
12,000.00	11,976.34	12,022.87	11,976.18	34.42	32.82	-19.21	-248.85	531.09	200.58	134.21	66.37	3.022		
12,100.00	12,076.23	12,119.57	12,071.41	34.53	32.92	-24.31	-232.71	531.00	197.18	130.53	66.65	2.958		
12,107.38	12,083.61	12,126.44	12,078.05	34.54	32.93	-24.84	-230.95	530.99	197.16	130.49	66.67	2.957 SF		
12,200.00	12,176.21	12,208.54	12,155.50	34.63	32.99	-32.76	-203.92	530.83	201.28	134.46	66.83	3.012		
12,300.00	12,276.21	12,287.19	12,225.34	34.73	33.04	66.35	-167.90	530.62	217.67	151.17	66.50	3.273		
12,400.00	12,376.15	12,355.57	12,281.57	34.83	33.07	42.19	-129.06	530.40	247.15	181.64	65.51	3.773		
12,500.00	12,474.58	12,420.15	12,330.08	34.94	33.09	33.52	-86.48	530.15	279.95	215.81	64.14	4.365		
12,600.00	12,568.56	12,482.62	12,372.15	35.04	33.09	26.93	-40.34	529.89	311.48	248.82	62.66	4.971		
12,700.00	12,655.26	12,543.45	12,408.06	35.15	33.10	21.86	8.72	529.61	339.84	278.65	61.20	5.553		
12,800.00	12,732.02	12,600.00	12,436.61	35.26	33.09	18.01	57.51	529.33	363.90	304.10	59.80	6.086		
12,900.00	12,796.52	12,661.56	12,462.05	35.40	33.08	14.64	113.53	529.00	382.82	324.07	58.75	6.516		
13,000.00	12,846.80	12,723.24	12,481.76	35.60	33.07	11.81	171.96	528.67	395.82	337.87	57.96	6.830		
13,100.00	12,881.72	12,785.77	12,496.51	35.87	33.06	9.35	232.70	528.32	402.11	344.67	57.44	7.000		
13,200.00	12,902.80	12,850.00	12,506.08	36.22	33.26	6.99	296.19	527.96	404.03	346.83	57.21	7.062		
13,300.00	12,910.09	12,910.05	12,509.85	36.64	33.46	4.86	356.11	527.63	401.97	344.72	57.25	7.021		
13,400.00	12,909.76	13,002.10	12,509.75	37.11	33.82	2.28	443.96	527.14	400.22	342.77	57.46	6.966		
13,500.00	12,909.40	13,102.96	12,509.41	37.63	34.29	0.45	543.09	526.59	399.91	342.18	57.73	6.928		
13,548.60	12,909.23	13,145.54	12,509.24	37.89	34.51	-0.01	591.59	526.32	399.90	342.02	57.88	6.910		
13,600.00	12,909.05	13,195.92	12,509.05	38.18	34.78	-0.17	642.97	526.03	399.90	341.85	58.05	6.889		
13,700.00	12,908.70	13,303.08	12,508.70	38.77	35.40	-0.17	742.96	525.47	399.90	341.47	58.44	6.843		
13,800.00	12,908.35	13,403.08	12,508.35	39.43	36.06	-0.16	842.96	524.92	399.90	341.05	58.85	6.795		
13,900.00	12,908.00	13,496.92	12,508.00	40.14	36.73	-0.16	942.96	524.36	399.90	340.61	59.29	6.745		
14,000.00	12,907.64	13,603.08	12,507.65	40.91	37.54	-0.16	1,042.96	523.80	399.90	340.10	59.80	6.688		
14,100.00	12,907.29	13,703.08	12,507.30	41.72	38.37	-0.15	1,142.96	523.25	399.90	339.58	60.32	6.629		
14,200.00	12,906.94	13,803.08	12,506.94	42.59	39.25	-0.15	1,242.95	522.69	399.90	339.01	60.89	6.568		
14,300.00	12,906.59	13,903.08	12,506.59	43.50	40.17	-0.14	1,342.95	522.13	399.90	338.42	61.49	6.504		
14,400.00	12,906.24	13,996.92	12,506.24	44.46	41.08	-0.14	1,442.95	521.58	399.90	337.80	62.10	6.440		
14,500.00	12,905.89	14,103.08	12,505.89	45.45	42.16	-0.13	1,542.95	521.02	399.90	337.12	62.78	6.370		
14,600.00	12,905.53	14,203.08	12,505.54	46.48	43.21	-0.13	1,642.95	520.46	399.90	336.42	63.48	6.300		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation





# Anticollision Report

<b>Company:</b>	Tap Rock Operating LLC	<b>Local Co-ordinate Reference:</b>	Well Double Diamond 24S 21E 1414 Well No. 238H
<b>Project:</b>	Eddy County, New Mexico NAD83 NM east	<b>TVD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Reference Site:</b>	Section 14-T24S-R31E	<b>MD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Site Error:</b>	0.00 ft	<b>North Reference:</b>	Grid
<b>Reference Well:</b>	Double Diamond 24S 21E 1414 Well No. 238H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.00 ft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	Original Hole	<b>Database:</b>	DB_Jul2216dt_v14
<b>Reference Design:</b>	rev1	<b>Offset TVD Reference:</b>	Offset Datum

Offset Design Section 14-T24S-R31E - Double Diamond 24S 21E 1414 Well No. 228H - Original Hole - rev1													Offset Site Error:	0.00 ft
Survey Program: 0-GYRO-NS, 8300-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (ft)	Separation Factor	Warning			
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)				Between Centres (ft)	Between Ellipses (ft)	
14,700.00	12,905.18	14,303.08	12,505.18	47.55	44.29	-0.13	1,742.94	519.91	399.90	335.70	6.229			
14,800.00	12,904.83	14,403.08	12,504.83	48.65	45.42	-0.12	1,842.94	519.35	399.90	334.94	6.156			
14,900.00	12,904.48	14,503.08	12,504.48	49.78	46.57	-0.12	1,942.94	518.79	399.90	334.15	6.083			
15,000.00	12,904.13	14,596.92	12,504.13	50.94	47.68	-0.11	2,042.94	518.24	399.90	333.37	6.011			
15,100.00	12,903.77	14,703.08	12,503.78	52.12	48.86	-0.11	2,142.93	517.68	399.90	332.50	5.934			
15,200.00	12,903.42	14,803.08	12,503.43	53.33	50.19	-0.11	2,242.93	517.12	399.90	331.64	5.858			
15,300.00	12,903.07	14,896.92	12,503.07	54.57	51.37	-0.10	2,342.93	516.57	399.90	330.78	5.785			
15,400.00	12,902.72	15,003.08	12,502.72	55.82	52.73	-0.10	2,442.93	516.01	399.90	329.84	5.708			
15,500.00	12,902.37	15,103.08	12,502.37	57.10	54.03	-0.09	2,542.93	515.45	399.90	328.90	5.632			
15,600.00	12,902.01	15,196.92	12,502.02	58.39	55.25	-0.09	2,642.92	514.90	399.90	327.97	5.560			
15,700.00	12,901.66	15,303.08	12,501.67	59.71	56.58	-0.08	2,742.92	514.34	399.90	326.96	5.483			
15,800.00	12,901.31	15,403.08	12,501.31	61.04	58.03	-0.08	2,842.92	513.78	399.90	325.96	5.409			
15,900.00	12,900.96	15,503.08	12,500.96	62.38	59.40	-0.08	2,942.92	513.23	399.90	324.94	5.335			
16,000.00	12,900.61	15,603.08	12,500.61	63.74	60.78	-0.07	3,042.92	512.67	399.90	323.91	5.262			
16,100.00	12,900.26	15,703.08	12,500.26	65.11	62.17	-0.07	3,142.91	512.11	399.90	322.85	5.190			
16,200.00	12,899.90	15,803.08	12,499.91	66.50	63.58	-0.06	3,242.91	511.56	399.90	321.78	5.119			
16,300.00	12,899.55	15,903.08	12,499.56	67.89	65.00	-0.06	3,342.91	511.00	399.90	320.69	5.049			
16,400.00	12,899.20	16,003.08	12,499.20	69.30	66.43	-0.06	3,442.91	510.44	399.90	319.59	4.979			
16,500.00	12,898.85	16,103.08	12,498.85	70.72	67.87	-0.05	3,542.90	509.89	399.90	318.47	4.911			
16,600.00	12,898.50	16,203.08	12,498.50	72.15	69.32	-0.05	3,642.90	509.33	399.90	317.33	4.843			
16,700.00	12,898.14	16,303.08	12,498.15	73.59	70.77	-0.04	3,742.90	508.77	399.90	316.18	4.777			
16,800.00	12,897.79	16,403.08	12,497.80	75.04	72.24	-0.04	3,842.90	508.22	399.90	315.02	4.711			
16,900.00	12,897.44	16,503.08	12,497.45	76.49	73.71	-0.03	3,942.90	507.66	399.90	313.85	4.647			
17,000.00	12,897.09	16,603.08	12,497.09	77.96	75.19	-0.03	4,042.89	507.10	399.90	312.66	4.584			
17,100.00	12,896.74	16,703.08	12,496.74	79.43	76.68	-0.03	4,142.89	506.55	399.90	311.46	4.522			
17,200.00	12,896.39	16,803.08	12,496.39	80.91	78.18	-0.02	4,242.89	505.99	399.90	310.25	4.461			
17,300.00	12,896.03	16,903.08	12,496.04	82.39	79.68	-0.02	4,342.89	505.43	399.90	309.03	4.401			
17,400.00	12,895.68	17,003.08	12,495.69	83.88	81.18	-0.01	4,442.88	504.88	399.90	307.80	4.342			
17,500.00	12,895.33	17,103.08	12,495.33	85.38	82.70	-0.01	4,542.88	504.32	399.90	306.55	4.284			
17,600.00	12,894.98	17,196.92	12,494.98	86.88	84.12	-0.01	4,642.88	503.76	399.90	305.34	4.229			
17,700.00	12,894.63	17,303.08	12,494.63	88.39	85.74	0.00	4,742.88	503.21	399.90	304.04	4.172			
17,736.22	12,894.50	17,333.14	12,494.50	88.94	86.20	0.00	4,779.09	503.01	399.90	303.62	4.154			



# Anticollision Report

Company: Tap Rock Operating LLC

Local Co-ordinate Reference:

Well Double Diamond 24S 21E 1414 Well No. 238H

Project: Eddy County, New Mexico NAD83 NM east

TVD Reference:

RKB=3586+25 @ 3611.00ft

Reference Site: Section 14-T24S-R31E

MD Reference:

RKB=3586+25 @ 3611.00ft

Site Error: 0.00 ft

North Reference:

Grid

Reference Well: Double Diamond 24S 21E 1414 Well No. 238H

Survey Calculation Method:

Minimum Curvature

Well Error: 0.00 ft

Output errors are at

2.00 sigma

Reference Wellbore Original Hole

Database:

DB\_Jul2216dt\_v14

Reference Design: rev1

Offset TVD Reference:

Offset Datum

Offset Design Section 14-T24S-R31E - Petrogulf BJT Federal Well No. 1H - Horizontal - Surveys Horizontal													Offset Site Error:	0.00 ft
Survey Program: 7833-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis			Distance							
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning	
5,900.00	5,895.89	7,700.00	7,699.24	20.46	0.00	45.44	348.55	558.97	1,943.32	1,932.08	11.24	172.954		
6,000.00	5,995.89	7,700.00	7,699.24	20.81	0.00	45.44	348.55	558.97	1,850.76	1,839.09	11.67	158.585		
6,100.00	6,095.89	7,700.00	7,699.24	21.16	0.00	45.44	348.55	558.97	1,759.02	1,746.88	12.14	144.897		
6,200.00	6,195.89	7,700.00	7,699.24	21.51	0.00	45.44	348.55	558.97	1,668.23	1,655.58	12.65	131.909		
6,300.00	6,295.89	7,700.00	7,699.24	21.85	0.00	45.44	348.55	558.97	1,578.55	1,565.35	13.20	119.593		
6,400.00	6,395.89	7,700.00	7,699.24	22.20	0.00	45.44	348.55	558.97	1,490.18	1,476.38	13.81	107.942		
6,500.00	6,495.89	7,700.00	7,699.24	22.55	0.00	45.44	348.55	558.97	1,403.38	1,388.91	14.47	96.965		
6,600.00	6,595.89	7,700.00	7,699.24	22.90	0.00	45.44	348.55	558.97	1,318.45	1,303.24	15.21	86.689		
6,700.00	6,695.89	7,700.00	7,699.24	23.24	0.00	45.44	348.55	558.97	1,235.77	1,219.75	16.03	77.113		
6,800.00	6,795.89	7,700.00	7,699.24	23.59	0.00	45.44	348.55	558.97	1,155.84	1,138.91	16.93	68.264		
6,900.00	6,895.89	7,700.00	7,699.24	23.94	0.00	45.44	348.55	558.97	1,079.25	1,061.32	17.93	60.178		
7,000.00	6,995.89	7,700.00	7,699.24	24.29	0.00	45.44	348.55	558.97	1,006.79	987.75	19.04	52.881		
7,100.00	7,095.89	7,700.00	7,699.24	24.64	0.00	45.44	348.55	558.97	939.39	919.15	20.24	46.410		
7,200.00	7,195.89	7,700.00	7,699.24	24.98	0.00	45.44	348.55	558.97	878.22	856.70	21.52	40.804		
7,300.00	7,295.89	7,700.00	7,699.24	25.33	0.00	45.44	348.55	558.97	824.69	801.84	22.84	36.102		
7,400.00	7,395.89	7,700.00	7,699.24	25.68	0.00	45.44	348.55	558.97	780.34	756.22	24.13	32.340		
7,500.00	7,495.89	7,700.00	7,699.24	26.03	0.00	45.44	348.55	558.97	746.84	721.56	25.28	29.542		
7,600.00	7,595.89	7,700.00	7,699.24	26.38	0.00	45.44	348.55	558.97	725.67	699.49	26.18	27.720		
7,700.00	7,695.89	7,700.00	7,699.24	26.73	0.00	45.44	348.55	558.97	717.93	691.21	26.72	26.868		
7,800.00	7,795.89	8,038.17	8,027.41	27.07	1.61	42.30	337.95	496.10	706.55	676.59	29.97	23.578		
7,900.00	7,895.89	8,173.76	8,141.46	27.42	2.85	37.09	342.11	423.32	670.90	639.90	31.00	21.643		
8,000.00	7,995.89	8,593.59	8,341.15	27.77	10.61	2.37	352.44	68.43	615.65	579.55	36.10	17.056		
8,100.00	8,095.89	8,610.13	8,342.89	28.12	10.99	0.51	351.81	51.99	565.06	527.35	37.71	14.986		
8,200.00	8,195.89	8,622.35	8,344.12	28.47	11.28	-0.86	351.28	39.84	528.44	489.28	39.17	13.492		
8,300.00	8,295.89	8,631.40	8,344.98	28.82	11.49	-1.88	350.89	30.83	508.94	468.70	40.24	12.649		
8,351.98	8,347.87	8,635.74	8,345.37	29.00	11.59	-2.37	350.71	26.52	506.30	465.72	40.58	12.478	CC, ES, SF	
8,400.00	8,395.89	8,639.54	8,345.71	29.17	11.68	-2.80	350.55	22.74	508.55	467.82	40.74	12.484		
8,500.00	8,495.89	8,646.88	8,346.33	29.52	11.85	-3.62	350.26	15.43	527.35	486.75	40.60	12.989		
8,600.00	8,595.89	8,652.85	8,346.81	29.87	11.99	-4.30	350.03	9.48	563.43	523.49	39.95	14.104		
8,700.00	8,695.89	8,657.48	8,347.15	30.22	12.09	-4.82	349.86	4.87	613.79	574.76	39.02	15.728		
8,800.00	8,795.89	8,661.27	8,347.39	30.57	12.18	-5.25	349.72	1.09	675.25	637.19	38.06	17.744		
8,900.00	8,895.89	8,664.43	8,347.58	30.92	12.26	-5.60	349.60	-2.07	745.08	707.90	37.18	20.041		
9,000.00	8,995.89	8,667.11	8,347.73	31.27	12.32	-5.90	349.51	-4.74	821.15	784.71	36.44	22.532		
9,100.00	9,095.89	8,669.41	8,347.84	31.62	12.37	-6.16	349.42	-7.03	901.89	866.03	35.86	25.147		
9,200.00	9,195.89	8,671.40	8,347.94	31.97	12.42	-6.38	349.35	-9.01	986.16	950.73	35.43	27.835		
9,300.00	9,295.89	8,681.00	8,348.30	32.32	12.64	-7.46	349.02	-18.61	1,073.20	1,038.03	35.16	30.520		
9,400.00	9,395.89	8,681.00	8,348.30	32.67	12.64	-7.46	349.02	-18.61	1,162.23	1,127.28	34.94	33.259		
9,500.00	9,495.89	8,681.00	8,348.30	32.85	12.64	-7.46	349.02	-18.61	1,252.91	1,218.17	34.74	36.062		
9,600.00	9,595.88	8,681.00	8,348.30	32.86	12.64	-112.99	349.02	-18.61	1,345.11	1,310.49	34.62	38.849		
9,700.00	9,695.80	8,681.00	8,348.30	32.87	12.64	-109.27	349.02	-18.61	1,438.70	1,404.12	34.59	41.597		
9,800.00	9,795.59	8,681.00	8,348.30	32.88	12.64	-105.05	349.02	-18.61	1,533.38	1,498.76	34.62	44.295		
9,900.00	9,895.18	8,681.00	8,348.30	32.90	12.64	-100.33	349.02	-18.61	1,628.88	1,594.19	34.70	46.943		
10,000.00	9,994.50	8,681.00	8,348.30	32.92	12.64	-95.13	349.02	-18.61	1,725.03	1,690.20	34.82	49.537		
10,100.00	10,093.54	8,681.00	8,348.30	32.94	12.64	-92.95	349.02	-18.61	1,821.64	1,786.66	34.98	52.075		
10,200.00	10,192.56	8,668.79	8,347.81	32.97	12.36	-91.51	349.45	-6.41	1,918.45	1,883.32	35.12	54.618		





# Anticollision Report

Company: Tap Rock Operating LLC

Local Co-ordinate Reference:

Well Double Diamond 24S 21E 1414 Well No. 238H

Project: Eddy County, New Mexico NAD83 NM east

TVD Reference:

RKB=3586+25 @ 3611.00ft

Reference Site: Section 14-T24S-R31E

MD Reference:

RKB=3586+25 @ 3611.00ft

Site Error: 0.00 ft

North Reference:

Grid

Reference Well: Double Diamond 24S 21E 1414 Well No. 238H

Survey Calculation Method:

Minimum Curvature

Well Error: 0.00 ft

Output errors are at

2.00 sigma

Reference Wellbore: Original Hole

Database:

DB\_Jul2216dt\_v14

Reference Design: rev1

Offset TVD Reference:

Offset Datum

Offset Design Section 14-T24S-R31E - Petrogulf BJT Federal Well No. 2H - Original Hole - Surveys Original Hole													Offset Site Error:	0.00 ft
Survey Program: 200-GYRO-NS, 7746-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (ft)	Separation Factor	Warning			
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)				Between Centres (ft)	Between Ellipses (ft)	
0.00	0.00	0.00	0.00	0.00	0.00	55.87	357.93	528.05	638.04					
100.00	100.00	89.24	89.24	0.13	0.14	55.87	357.88	527.98	637.85	0.27	2,358.578			
200.00	200.00	190.65	190.65	0.48	0.30	55.87	357.71	527.73	637.54	0.78	819.216			
300.00	300.00	290.33	290.33	0.83	0.63	55.88	357.42	527.44	637.14	1.46	436.766			
400.00	400.00	389.84	389.84	1.18	0.98	55.90	357.04	527.30	636.81	2.16	295.258			
500.00	500.00	488.99	488.99	1.53	1.32	55.91	356.77	527.21	636.58	2.85	223.172			
600.00	600.00	588.11	588.10	1.88	1.67	55.90	356.89	527.03	636.50	3.55	179.405			
611.51	611.51	599.51	599.51	1.93	1.71	55.89	356.92	527.00	636.50	3.63	175.447 CC			
700.00	700.00	686.87	686.87	2.24	2.01	55.87	357.19	526.92	636.58	4.24	150.098			
800.00	800.00	785.60	785.59	2.59	2.36	55.86	357.37	527.13	636.85	4.93	129.066			
900.00	900.00	886.43	886.42	2.94	2.71	55.88	357.39	527.52	637.19	5.64	113.089			
1,000.00	1,000.00	987.62	987.62	3.29	3.06	55.91	357.19	527.85	637.34	6.34	100.561			
1,100.00	1,100.00	1,089.09	1,089.08	3.64	3.42	55.95	356.85	528.01	637.29	7.04	90.501			
1,200.00	1,200.00	1,190.60	1,190.59	3.99	3.77	55.97	356.53	527.88	637.00	7.75	82.238			
1,244.56	1,244.56	1,234.02	1,234.01	4.14	3.92	-107.04	356.39	527.79	636.90	8.05	79.087			
1,300.00	1,299.99	1,287.45	1,287.44	4.34	4.11	-107.08	356.20	527.87	637.07	8.43	75.540			
1,400.00	1,399.96	1,383.82	1,383.80	4.68	4.45	-107.22	355.79	528.58	638.21	9.12	69.969			
1,500.00	1,499.86	1,483.04	1,483.02	5.03	4.79	-107.48	355.34	529.78	640.25	9.82	65.174			
1,600.00	1,599.73	1,582.82	1,582.79	5.39	5.14	-107.83	354.90	531.01	642.60	10.53	61.023			
1,700.00	1,699.59	1,680.61	1,680.57	5.75	5.49	-108.17	354.59	532.30	645.13	11.23	57.453			
1,800.00	1,799.45	1,777.96	1,777.91	6.11	5.83	-108.53	354.62	533.81	648.06	11.92	54.348			
1,900.00	1,899.31	1,873.29	1,873.22	6.46	6.16	-108.87	354.94	535.67	651.52	12.61	51.662			
2,000.00	1,999.18	1,958.00	1,957.89	6.82	6.50	-109.19	355.49	538.26	655.78	13.29	49.328			
2,100.00	2,099.04	2,064.83	2,064.66	7.17	6.84	-109.49	356.30	541.54	660.74	13.99	47.245			
2,200.00	2,198.90	2,162.72	2,162.49	7.53	7.19	-109.81	357.42	545.02	666.03	14.68	45.370			
2,300.00	2,298.77	2,264.41	2,264.10	7.88	7.55	-110.14	358.79	548.80	671.45	15.39	43.630			
2,400.00	2,398.63	2,368.48	2,368.12	8.23	7.92	-110.51	360.04	551.65	676.33	16.11	41.985			
2,500.00	2,498.49	2,474.92	2,474.53	8.59	8.29	-110.92	361.26	553.79	680.48	16.84	40.419			
2,600.00	2,598.36	2,582.31	2,581.91	8.94	8.67	-111.44	362.78	554.24	683.58	17.56	38.917			
2,700.00	2,698.22	2,683.71	2,683.30	9.29	9.02	-111.96	364.13	553.77	685.98	18.27	37.545			
2,800.00	2,798.08	2,784.03	2,783.62	9.64	9.37	-112.40	364.67	553.84	688.36	18.97	36.281			
2,900.00	2,897.94	2,883.61	2,883.19	10.00	9.71	-112.76	364.58	554.39	690.74	19.67	35.112			
3,000.00	2,997.81	2,983.07	2,982.65	10.35	10.06	-113.08	364.16	555.29	693.21	20.37	34.029			
3,100.00	3,097.67	3,084.95	3,084.52	10.70	10.41	-113.39	363.49	556.31	695.61	21.08	33.001			
3,200.00	3,197.53	3,187.31	3,186.88	11.05	10.77	-113.72	362.73	556.94	697.69	21.79	32.024			
3,300.00	3,297.40	3,284.67	3,284.23	11.40	11.11	-114.04	362.12	557.39	699.76	22.48	31.132			
3,400.00	3,397.26	3,381.28	3,380.84	11.75	11.45	-114.36	361.94	558.07	702.30	23.16	30.318			
3,500.00	3,497.12	3,480.28	3,479.84	12.11	11.79	-114.72	362.14	558.84	705.20	23.86	29.554			
3,600.00	3,596.99	3,579.83	3,579.39	12.46	12.14	-115.11	362.70	559.37	708.18	24.56	28.835			
3,700.00	3,696.85	3,678.19	3,677.74	12.81	12.48	-115.51	363.49	559.82	711.30	25.25	28.166			
3,800.00	3,796.71	3,776.24	3,775.79	13.16	12.82	-115.89	364.33	560.54	714.69	25.95	27.546			
3,900.00	3,896.57	3,874.38	3,873.92	13.51	13.17	-116.23	365.00	561.76	718.36	26.64	26.967			
4,000.00	3,996.44	3,972.61	3,972.12	13.86	13.51	-116.48	364.98	563.93	722.29	27.33	26.427			
4,100.00	4,096.30	4,080.45	4,079.92	14.21	13.89	-116.68	364.12	566.72	725.97	28.06	25.869			
4,200.00	4,196.16	4,192.06	4,191.51	14.56	14.28	-116.90	362.30	568.16	728.13	28.81	25.277			
4,300.00	4,296.03	4,288.37	4,287.80	14.91	14.61	-117.11	360.40	568.87	729.67	29.49	24.740			
4,400.00	4,395.93	4,383.52	4,382.92	15.26	14.94	-117.26	358.86	570.11	731.47	30.17	24.241			
4,500.00	4,495.89	4,478.30	4,477.68	15.61	15.28	-117.29	357.74	571.85	733.16	30.85	23.764			
4,600.00	4,595.89	4,573.00	4,572.35	15.95	15.61	-117.29	357.17	574.00	734.77	31.53	23.305			
4,700.00	4,695.89	4,673.15	4,672.47	16.30	15.96	-117.29	356.96	576.54	736.44	32.23	22.852			
4,800.00	4,795.89	4,775.50	4,774.79	16.65	16.32	-117.29	356.57	578.90	737.83	32.93	22.404			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



# Anticollision Report

Company: Tap Rock Operating LLC  
Project: Eddy County, New Mexico NAD83 NM east  
Reference Site: Section 14-T24S-R31E  
Site Error: 0.00 ft  
Reference Well: Double Diamond 24S 21E 1414 Well No. 238H  
Well Error: 0.00 ft  
Reference Wellbore: Original Hole  
Reference Design: rev1  
Local Co-ordinate Reference: Well Double Diamond 24S 21E 1414 Well No. 238H  
TVD Reference: RKB=3586+25 @ 3611.00ft  
MD Reference: RKB=3586+25 @ 3611.00ft  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Output errors are at 2.00 sigma  
Database: DB\_Jul2216dt\_v14  
Offset TVD Reference: Offset Datum

Offset Design Section 14-T24S-R31E - Petrogulf BJT Federal Well No. 2H - Original Hole - Surveys Original Hole													Offset Site Error:	0.00 ft
Survey Program: 200-GYRO-NS, 7746-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis			Distance							Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor		
4,900.00	4,895.89	4,880.73	4,880.00	16.99	16.68	46.24	355.80	580.98	738.75	705.10	33.65	21.954		
5,000.00	4,995.89	4,986.87	4,986.12	17.34	17.06	46.41	354.31	582.56	738.87	704.50	34.37	21.497		
5,100.00	5,095.89	5,087.75	5,086.98	17.69	17.41	46.55	352.66	583.57	738.46	703.39	35.07	21.057		
5,200.00	5,195.89	5,187.91	5,187.13	18.03	17.76	46.65	351.50	584.08	738.04	702.27	35.77	20.635		
5,300.00	5,295.89	5,290.37	5,289.58	18.38	18.12	46.71	350.45	584.25	737.45	700.98	36.47	20.221		
5,400.00	5,395.89	5,393.13	5,392.34	18.73	18.48	46.81	348.92	584.33	736.49	699.31	37.17	19.812		
5,500.00	5,495.89	5,490.13	5,489.32	19.08	18.82	46.89	347.50	584.37	735.52	697.66	37.86	19.427		
5,600.00	5,595.89	5,586.72	5,585.91	19.42	19.15	46.94	346.70	584.45	735.01	696.47	38.54	19.069		
5,700.00	5,695.89	5,685.59	5,684.78	19.77	19.50	46.96	346.35	584.54	734.84	695.60	39.24	18.728		
5,800.00	5,795.89	5,784.82	5,784.01	20.12	19.84	46.97	346.21	584.57	734.77	694.84	39.93	18.401		
5,900.00	5,895.89	5,885.84	5,885.03	20.46	20.20	46.97	346.20	584.49	734.70	694.07	40.63	18.082		
6,000.00	5,995.89	5,987.19	5,986.38	20.81	20.55	46.96	346.15	584.19	734.45	693.12	41.33	17.770		
6,100.00	6,095.89	6,087.56	6,086.74	21.16	20.90	46.94	346.05	583.77	734.08	692.05	42.03	17.466		
6,200.00	6,195.89	6,187.78	6,186.97	21.51	21.24	46.93	345.88	583.38	733.68	690.95	42.73	17.172		
6,300.00	6,295.89	6,287.57	6,286.76	21.85	21.59	46.92	345.70	582.99	733.27	689.85	43.42	16.887		
6,400.00	6,395.89	6,387.30	6,386.48	22.20	21.94	46.90	345.61	582.57	732.90	688.78	44.12	16.613		
6,500.00	6,495.89	6,488.86	6,488.04	22.55	22.29	46.88	345.49	582.06	732.45	687.63	44.82	16.343		
6,600.00	6,595.89	6,590.68	6,589.86	22.90	22.65	46.86	345.19	581.38	731.76	686.24	45.52	16.075		
6,700.00	6,695.89	6,689.15	6,688.33	23.24	22.99	46.84	344.87	580.68	731.03	684.81	46.21	15.819		
6,800.00	6,795.89	6,787.29	6,786.47	23.59	23.33	46.82	344.75	580.15	730.55	683.64	46.90	15.576		
6,900.00	6,895.89	6,887.14	6,886.32	23.94	23.68	46.80	344.74	579.71	730.22	682.62	47.60	15.341		
7,000.00	6,995.89	6,987.25	6,986.42	24.29	24.03	46.78	344.70	579.28	729.88	681.58	48.30	15.113		
7,100.00	7,095.89	7,096.57	7,095.74	24.64	24.41	46.75	344.29	578.30	728.97	679.95	49.02	14.870		
7,200.00	7,195.89	7,207.18	7,206.31	24.98	24.80	46.70	342.93	576.00	726.62	676.87	49.74	14.607		
7,300.00	7,295.89	7,306.30	7,305.39	25.33	25.14	46.65	341.38	573.41	723.64	673.20	50.44	14.347		
7,400.00	7,395.89	7,406.13	7,405.17	25.68	25.49	46.59	339.89	570.75	720.68	669.54	51.14	14.094		
7,500.00	7,495.89	7,504.83	7,503.83	26.03	25.84	46.55	338.34	568.32	717.82	665.99	51.83	13.850		
7,600.00	7,595.89	7,603.87	7,602.83	26.38	26.18	46.53	336.63	566.27	715.12	662.60	52.52	13.615		
7,700.00	7,695.89	7,709.90	7,708.81	26.73	26.56	46.57	334.07	564.20	712.05	658.81	53.23	13.376		
7,800.00	7,795.89	7,809.74	7,808.60	27.07	26.60	46.59	331.68	562.00	708.80	655.17	53.93	13.217		
7,900.00	7,895.89	7,903.76	7,902.55	27.42	26.61	46.50	330.37	559.08	705.60	651.61	53.99	13.068		
8,000.00	7,995.89	8,059.69	8,054.44	27.77	26.64	43.94	346.97	531.38	700.94	646.77	54.17	12.940		
8,100.00	8,095.89	8,258.85	8,218.78	28.12	26.79	35.06	393.28	432.29	683.44	629.38	54.06	12.642		
8,200.00	8,195.89	8,363.91	8,279.76	28.47	27.04	27.77	427.79	354.40	665.77	610.69	55.08	12.088		
8,300.00	8,295.89	8,401.70	8,295.38	28.82	27.19	24.82	441.21	323.23	657.17	601.18	55.99	11.736		
8,313.74	8,309.63	8,404.77	8,297.63	28.87	27.20	24.57	442.37	320.68	657.04	600.98	56.06	11.721 ES		
8,400.00	8,395.89	8,481.19	8,327.51	29.17	27.56	18.45	469.13	255.65	660.50	603.97	56.53	11.684 SF		
8,500.00	8,495.89	8,511.17	8,338.68	29.52	27.74	16.03	478.96	229.64	675.57	619.47	56.10	12.042		
8,600.00	8,595.89	8,538.88	8,348.62	29.87	27.91	13.80	488.34	205.53	703.15	648.14	55.01	12.782		
8,700.00	8,695.89	8,570.29	8,359.58	30.22	28.12	11.30	499.20	178.17	741.93	688.35	53.58	13.848		
8,800.00	8,795.89	8,598.98	8,369.34	30.57	28.33	9.04	509.11	153.08	790.10	738.16	51.94	15.213		
8,900.00	8,895.89	8,621.55	8,376.70	30.92	28.50	7.28	517.00	133.26	846.40	796.20	50.20	16.862		
9,000.00	8,995.89	8,639.06	8,381.98	31.27	28.64	5.92	523.10	117.71	909.55	861.07	48.48	18.761		
9,100.00	9,095.89	8,647.00	8,384.21	31.62	28.70	5.30	525.86	110.61	978.43	931.64	46.79	20.911		
9,200.00	9,195.89	8,663.20	8,388.38	31.97	28.84	4.04	531.43	95.98	1,051.95	1,006.52	45.43	23.153		
9,300.00	9,295.89	8,678.00	8,391.68	32.32	28.97	2.90	536.45	82.46	1,129.42	1,085.17	44.25	25.521		
9,400.00	9,395.89	8,678.00	8,391.68	32.67	28.97	2.90	536.45	82.46	1,209.97	1,165.89	43.09	28.081		
9,500.00	9,495.89	8,678.00	8,391.68	32.85	28.97	2.90	536.45	82.46	1,293.24	1,251.23	42.02	30.778		
9,600.00	9,595.88	8,690.11	8,394.00	32.86	29.08	-104.40	540.51	71.29	1,378.70	1,337.46	41.24	33.429		
9,700.00	9,695.80	8,693.70	8,394.63	32.87	29.12	-102.03	541.71	67.96	1,466.32	1,425.77	40.55	36.163		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation





# Anticollision Report

Company: Tap Rock Operating LLC  
Project: Eddy County, New Mexico NAD83 NM east  
Reference Site: Section 14-T24S-R31E  
Site Error: 0.00 ft  
Reference Well: Double Diamond 24S 21E 1414 Well No. 238H  
Well Error: 0.00 ft  
Reference Wellbore: Original Hole  
Reference Design: rev1

Local Co-ordinate Reference: Well Double Diamond 24S 21E 1414 Well No. 238H  
TVD Reference: RKB=3586+25 @ 3611.00ft  
MD Reference: RKB=3586+25 @ 3611.00ft  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature

Output errors are at 2.00 sigma  
Database: DB\_Jul2216dt\_v14  
Offset TVD Reference: Offset Datum

Offset Design Section 14-T24S-R31E - Petrogulf BJT Federal Well No. 2H - Original Hole - Surveys Original Hole													Offset Site Error:	0.00 ft
Survey Program: 200-GYRO-NS, 7746-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis			Distance							Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor		
9,800.00	9,795.59	8,696.25	8,395.05	32.88	29.14	-99.31	542.56	65.60	1,555.65	1,515.65	40.00	38.892		
9,900.00	9,895.18	8,709.00	8,396.93	32.90	29.26	-97.18	546.78	53.71	1,646.53	1,606.86	39.67	41.509		
10,000.00	9,994.50	8,709.00	8,396.93	32.92	29.26	-93.71	546.78	53.71	1,738.35	1,699.01	39.34	44.191		
10,100.00	10,093.54	8,709.00	8,396.93	32.94	29.26	-92.27	546.78	53.71	1,831.08	1,791.97	39.10	46.827		
10,200.00	10,192.56	8,709.00	8,396.93	32.97	29.26	-92.27	546.78	53.71	1,924.54	1,885.59	38.95	49.415		




## Anticollision Report

<b>Company:</b>	Tap Rock Operating LLC	<b>Local Co-ordinate Reference:</b>	Well Double Diamond 24S 21E 1414 Well No. 238H
<b>Project:</b>	Eddy County, New Mexico NAD83 NM east	<b>TVD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Reference Site:</b>	Section 14-T24S-R31E	<b>MD Reference:</b>	RKB=3586+25 @ 3611.00ft
<b>Site Error:</b>	0.00 ft	<b>North Reference:</b>	Grid
<b>Reference Well:</b>	Double Diamond 24S 21E 1414 Well No. 238H	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.00 ft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	Original Hole	<b>Database:</b>	DB_Jul2216dt_v14
<b>Reference Design:</b>	rev1	<b>Offset TVD Reference:</b>	Offset Datum

Reference Depths are relative to RKB=3586+25 @ 3611.00ft  
 Offset Depths are relative to Offset Datum  
 Central Meridian is -104.33333334

Coordinates are relative to: Double Diamond 24S 21E 1414 Well No. 238H  
 Coordinate System is US State Plane 1983, New Mexico Eastern Zone  
 Grid Convergence at Surface is: 0.31°

### Ladder Plot



### LEGEND

Double Diamond 24S 21E 1414 Well No. 158H Original Hole, rev0 V0	Petrogut BJT Federal Well No. 2H, Original Hole, Survey's Original Hole V0	Double Diamond 24S 21E 1414 Well No. 224H Original Hole, rev1 V1
Petrogut BJT Federal Well No. 2H, Horizontal Survey's Horizontal V0	Double Diamond 24S 21E 1414 Well No. 229H, Original Hole, rev1 V0	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



## Anticollision Report

Company: Tap Rock Operating LLC

Project: Eddy County, New Mexico NAD83 NM east

Reference Site: Section 14-T24S-R31E

Site Error: 0.00 ft

Reference Well: Double Diamond 24S 21E 1414 Well No. 238H

Well Error: 0.00 ft

Reference Wellbore: Original Hole

Reference Design: rev1

Local Co-ordinate Reference:

Well Double Diamond 24S 21E 1414 Well No. 238H

TVD Reference:

RKB=3586+25 @ 3611.00ft

MD Reference:

RKB=3586+25 @ 3611.00ft

North Reference:

Grid

Survey Calculation Method:

Minimum Curvature

Output errors are at

2.00 sigma

Database:

DB\_Jul2216dt\_v14

Offset TVD Reference:

Offset Datum

Reference Depths are relative to RKB=3586+25 @ 3611.00ft

Offset Depths are relative to Offset Datum


Central Meridian is -104.33333334

Coordinates are relative to: Double Diamond 24S 21E 1414 Well No. 238H

Coordinate System is US State Plane 1983, New Mexico Eastern Zone

Grid Convergence at Surface is: 0.31°

### Separation Factor Plot



#### LEGEND

Double Diamond 24S 21E 1414 Well No. 158H, Original Hole, rev0 V/D  
Petroleum BJT Federal Well No. 211, Horizontal Survey, Horizontal V/D

Petroleum BJT Federal Well No. 211, Original Hole, Survey's Original Hole V/D  
Double Diamond 24S 21E 1414 Well No. 228H, Original Hole, rev1 V/D

Double Diamond 24S 21E 1414 Well No. 224H, Original Hole, rev1 V/D

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Tap Rock Operating, LLC  
 Double Diamond Fed Com 238H  
 SHL 305' FSL & 860' FEL  
 BHL 200' FNL & 330' FEL  
 Sec. 14, T. 24 S., R. 31 E., Eddy County, NM

## DRILL PLAN PAGE 1

### Drilling Program

#### 1. ESTIMATED TOPS

Formation Name	TVD	MD	Bearing
Quaternary caliche	0'	0'	water
Rustler anhydrite	731'	731'	N/A
Salado salt	1067'	1067'	N/A
Base salt	2813'	2815'	N/A
Bell Canyon sandstone	4613'	4617'	hydrocarbons
Brushy Canyon sandstone	6723'	6727'	hydrocarbons
Bone Spring limestone	8443'	8447'	hydrocarbons
1 <sup>st</sup> Bone Spring sandstone	9443'	9447'	hydrocarbons
2nd Bone Spring sandstone	10083'	10089'	hydrocarbons
3 <sup>rd</sup> Bone Spring sandstone	11343'	11362'	hydrocarbons
Wolfcamp A carbonate	11823'	11846'	hydrocarbons
Wolfcamp A Fat carbonate	12018'	12042'	hydrocarbons
Wolfcamp B carbonate	12208'	12232'	hydrocarbons
(KOP	12328'	12352'	hydrocarbons)
Wolfcamp B2 carbonate (goal)	12703'	12759'	hydrocarbons
Horizontal TD	12895'	17736'	hydrocarbons
Pilot Hole TD ((Wolfcamp)	12910'	12930'	hydrocarbons

#### 2. NOTABLE ZONES

Wolfcamp B2 is the goal. Hole will extend north of the last perforation point to allow for pump installation. All perforations will be  $\geq 330'$  from the dedication perimeter. Closest water well (C 02440) in State Engineer records is 10,368' northwest. Well was drilled to 350'. No water was encountered.



Tap Rock Operating, LLC  
Double Diamond Fed Com 238H  
SHL 305' FSL & 860' FEL  
BHL 200' FNL & 330' FEL  
Sec. 14, T. 24 S., R. 31 E., Eddy County, NM

DRILL PLAN PAGE 2

### 3. PRESSURE CONTROL

A 13,000' 10,000-psi BOP stack consisting of 3 rams with 2 pipe rams, 1 blind ram, and 1 annular preventer will be used below surface casing to TD. BOP, choke manifold, co-flex hose, and speed head diagrams are attached.

An accumulator will be on site. It will comply with Onshore Order 2 requirements for the BOP stack pressure rating. Rotating head will be installed as needed.

Pressure tests will be conducted before drilling out from under all casing strings. BOP will be inspected and operated as required by Onshore Order 2. A top drive check valve and sub equipped with a full opening valve sized to fit the drill pipe and collars will be available on the rig floor in the open position.

A third-party company will test the BOPs. Test pressures will be:

After surface casing is set and the BOP is nipped up, pressure tests will be made to 250 psi low and 2000 psi high.

Test intermediate 1 casing to 250 psi low and 3000 psi high.

Test intermediate 2 casing to 250 psi low and 7500 psi high.

Annular preventer will be tested to 250 psi low and 1000 psi high on the surface casing and 250 psi low and 1500 psi high on both intermediate strings.

In the case of running a speed head with landing mandrel for the 1st and 2nd intermediate casing the initial, after surface casing is set, BOP test pressures will be 250 psi low and 3000 psi high with well head seals tested to 5000 psi once the first intermediate casing has been landed and cemented. BOP may then be lifted to install the C-section of the wellhead. Tap Rock will then nipple the BOP back up and pressure tests will be made to 250 psi low and 5000 psi high. Annular preventer will be tested to 250 psi low and 1500 psi high.

Tap Rock Operating, LLC  
Double Diamond Fed Com 238H  
SHL 305' FSL & 860' FEL  
BHL 200' FNL & 330' FEL  
Sec. 14, T. 24 S., R. 31 E., Eddy County, NM

## DRILL PLAN PAGE 3

Tap Rock requests a variance to use a co-flex hose between the BOP stack and choke manifold. Co-flex hose certification is attached. Manufacturer does not require the hose to be anchored. If the specific hose is not available, then one of equal or higher rating will be used.

### 4. CASING & CEMENT

All casing will be API and new. See attached casing assumption worksheet.

An 8.75" pilot hole will be drilled to 12,910 TVD (12,930' MD) and then plugged back to 12,300' MD. Plug will consist of 170 sacks (261 cubic feet) Class H + 35% BWOC silica flour + 33.5 lb/sack weighting additive + 0.75% BWOC dispersant mixed at 18 ppg and 1.54 ft<sup>3</sup> per sack. Excess >100%.

Hole O. D.	Set MD	Set TVD	Casing O. D.	Weight (lb/ft)	Grade	Joint	Collapse	Burst	Axial
17.5"	0' - 1000'	0' - 1000'	13.375" surface	54.5	J-55	BTC	1.3	1.15	1.51
12.25"	0' - 4700'	0' - 4696'	9.625" inter. 1	40.0	J-55	BTC	1.3	1.15	1.51
8.75"	0' - 4000'	0' - 3996'	7.625" inter. 2 top	29.7	P-110	BTC	1.3	1.15	1.51
8.75"	4000' - 12300'	3996' - 12276'	7.625" inter. 2 middle	29.7	P-110	flush	1.3	1.15	1.51
8.75"	12300' - 13100'	12276' - 12882'	7.0" inter. 2 bottom	29.0	P-110	BTC	1.3	1.15	1.51
6.125"	0' - 12300'	0' - 12276'	5.5" product. top	20.0	P-110	BTC	1.3	1.15	1.51
6.125"	12300' - 17736'	12276' - 12895'	4.5" product. bottom	13.5	P-110	BTC	1.3	1.15	1.51



Tap Rock Operating, LLC  
Double Diamond Fed Com 238H  
SHL 305' FSL & 860' FEL  
BHL 200' FNL & 330' FEL  
Sec. 14, T. 24 S., R. 31 E., Eddy County, NM

# DRILL PLAN PAGE 4

Name	Type	Sacks	Yield	Cu. Ft.	Weight	Blend
Surface	Tail	1000	1.38	1380	14.8	Class C + 5% NaCl + LCM
TOC = GL		100% Excess			Centralizers per Onshore Order 2 III. B. 1f	
Intermediate 1	Lead	1300	1.81	2353	13.5	Class C + bentonite + 1% CaCl <sub>2</sub> + 8% NaCl + LCM
	Tail	427	1.38	589	14.8	Class C + 5% NaCl + LCM
TOC = GL		100% Excess			2 on btm jt, 1 on 2nd jt, 1 every 4th jt to GL	
Intermediate 2	Lead	660	2.35	1551	11.5	TXI + fluid loss + dispersant + retarder + LCM
	Tail	120	1.39	166	13.2	TXI + fluid loss + dispersant + retarder + LCM
TOC = GL		35% Excess			2 on btm jt, 1 on 2nd jt, 1 every other jt to top of tail cement (500' above TOC)	
Production	Tail	550	1.17	643	15.8	Class H + fluid loss + dispersant + retarder + LCM
TOC = 12300'		10% Excess			2 on btm jt, 1 on 2nd jt, 1 every third jt to top of curve	

## 5. MUD PROGRAM

Electronic Pason mud monitor system complying with Onshore Order 1 will be used. All necessary mud products (e. g., barite, cedar bark) for weight addition and fluid loss control will always be on site. Mud program is subject to change due to hole conditions. A closed loop system will be used.

Type	Interval (MD)	lb/gal	Viscosity	Fluid Loss
fresh water spud	0' - 1000'	8.3	28	NC
brine water	1000' - 4700'	10.0	30 - 32	NC
fresh water & cut brine	4700' - 13100'	9.0	30 - 32	NC
OBM	13100' - 17736'	12.5	15 - 20	<10

Tap Rock Operating, LLC  
Double Diamond Fed Com 238H  
SHL 305' FSL & 860' FEL  
BHL 200' FNL & 330' FEL  
Sec. 14, T. 24 S., R. 31 E., Eddy County, NM

DRILL PLAN PAGE 5

#### 6. CORES, TESTS, & LOGS

No core or drill stem test is planned.

A 2-person mud logging program will be used from  $\approx 4700'$  MD to TD.

Triple combo logs (density, porosity, resistivity, GR) will be run in the pilot hole.

GR will be collected through the MWD tools from intermediate casing to TD. CBL with CCL will be run as far as gravity will let it fall to TOC.

#### 7. DOWN HOLE CONDITIONS


No abnormal pressure or temperature is expected. Maximum expected bottom hole pressure is  $\approx 8700$  psi. Expected bottom hole temperature is  $\approx 180^\circ$  F.

Tap Rock does not anticipate that there will be enough  $H_2S$  from the surface to the Bone Spring to meet the BLM's Onshore Order 6 requirements for the submission of an " $H_2S$  Drilling Operation Plan" or "Public Protection Plan" for drilling and completing this well. Tap Rock has an  $H_2S$  safety package on all wells and an " $H_2S$  Drilling Operations Plan" is attached. Adequate flare lines will be installed off the mud/gas separator where gas may be safely flared. All personnel will be familiar with all aspects of safe operation of equipment being used.

#### 8. OTHER INFORMATION

Anticipated spud date is upon approval. It is expected it will take  $\approx 3$  months to drill and complete the well.







# Tenaris

## Casing and Tubing Performance Data

Choose pipe size, wall thickness and steel grade to view API connection options and performance data.

Size  Wall  Grade  Connection  Unit

### Pipe Body Data

#### GEOMETRY

Nominal OD	13.375 in	Wall Thickness	0.380 in	API Drift Diameter	12.459 in
Nominal Weight	54.50 lbs/ft	Nominal ID	12.615 in	Alternate Drift Diameter	n.a.
Plain End Weight	52.79 lbs/ft	Nominal Cross Section	15.513 sq in		

#### PERFORMANCE

Steel Grade	J55	Minimum Yield	55,000 psi	Minimum Ultimate	75,000 psi
Body Yield Strength	853,000 lbs	Internal Yield Pressure	2,730 psi	Collapse Pressure	1,130 psi

### Connection Data

#### GEOMETRY

Regular OD	14.375 in	Threads Per Inch	5	Make-Up Thread Turns	1
------------	-----------	------------------	---	----------------------	---

#### PERFORMANCE

Steel Grade	J55	Minimum Yield	55,000 psi	Minimum Ultimate	75,000 psi
Joint Strength	909,000 lbs	Internal Pressure Resistance	2,730 psi		

[Tenaris Hydril Premium Connections](#)

Print

Contact Us

Ver 8.6





# Tenaris

## Casing and Tubing Performance Data

Choose pipe size, wall thickness and steel grade to view API connection options and performance data.

Size  Wall  Grade  Connection  Unit

### Pipe Body Data

#### GEOMETRY

Nominal OD	9.625 in	Wall Thickness	0.395 in	API Drift Diameter	8.679 in
Nominal Weight	40.00 lbs/ft	Nominal ID	8.835 in	Alternate Drift Diameter	8.75 in
Plain End Weight	38.97 lbs/ft	Nominal Cross Section	11.454 sq in		

#### PERFORMANCE

Steel Grade	J55	Minimum Yield	55,000 psi	Minimum Ultimate	75,000 psi
Body Yield Strength	630,000 lbs	Internal Yield Pressure	3,950 psi	Collapse Pressure	2,570 psi

### Connection Data

#### GEOMETRY

Regular OD	10.625 in	Threads Per Inch	5	Make-Up Thread Turns	1
------------	-----------	------------------	---	----------------------	---

#### PERFORMANCE

Steel Grade	J55	Minimum Yield	55,000 psi	Minimum Ultimate	75,000 psi
Joint Strength	714,000 lbs	Internal Pressure Resistance	3,950 psi		

[TenarisHydril Premium Connections](#)

[Print](#)

[Contact Us](#)

Ver 8.5



## Casing and Tubing Performance Data

### PIPE BODY DATA

#### GEOMETRY

Outside Diameter	7.625 in	Wall Thickness	0.375 in	API Drift Diameter	6.750 in
Nominal Weight	29.70 lbs/ft	Nominal ID	6.875 in	Alternative Drift Diameter	n.a.
Plain End Weight	29.06 lbs/ft	Nominal cross section	8.541 in		

#### PERFORMANCE

Steel Grade	P110	Minimum Yield	110,000 psi	Minimum Ultimate	125,000 psi
Tension Yield	940,000 in	Internal Pressure Yield	9,470 psi	Collapse Pressure	5,350 psi
Available Seamless	Yes	Available Welded	Yes		

### CONNECTION DATA

TYPE: BTC

#### GEOMETRY

Coupling Reg OD	8.500 in	Threads per in	5	Thread turns make up	1
-----------------	----------	----------------	---	----------------------	---

#### PERFORMANCE

Steel Grade	P110	Coupling Min Yield	110,000 psi	Coupling Min Ultimate	125,000 psi
Joint Strength	960,000 lbs			Internal Pressure Resistance	9,470 psi



## Wedge 513®

Printed on: 01/30/2018



Outside Diameter	7.625 in.	Min. Wall Thickness	87.5%	(*) Grade P110	
Wall Thickness	0.375 in.	Connection OD Option	REGULAR	COUPLING	PIPE BODY
Grade	P110*	Drift	API Standard	Body: White	1st Band: White
		Type	Casing	1st Band: -	2nd Band: -
				2nd Band: -	3rd Band: -
				3rd Band: -	4th Band: -

## GEOMETRY

Nominal OD	7.625 in.	Nominal Weight	29.70 lbs/ft	Drift	6.75 in.
Nominal ID	6.875 in.	Wall Thickness	0.375 in.	Plain End Weight	29.06 lbs/ft
OD Tolerance	API				

## PERFORMANCE

Body Yield Strength	940 x1000 lbs	Internal Yield	9470 psi	SMYS	110000 psi
Collapse	5350 psi				

## GEOMETRY

Connection OD	7.625 in.	Connection ID	6.800 in.	Make-up Loss	4.420 in.
Threads per in	3.29	Connection OD Option	REGULAR		

## PERFORMANCE

Tension Efficiency	60.0 %	Joint Yield Strength	564.000 x1000 lbs	Internal Pressure Capacity	9470.000 psi
Compression Efficiency	75.2 %	Compression Strength	706.880 x1000 lbs	Max. Allowable Bending	39.6 °/100 ft
External Pressure Capacity	5350.000 psi				

## MAKE-UP TORQUES

Minimum	9000 ft-lbs	Optimum	10800 ft-lbs	Maximum	15800 ft-lbs
---------	-------------	---------	--------------	---------	--------------

## OPERATION LIMIT TORQUES

Operating Torque	47000 ft-lbs	Yield Torque	70000 ft-lbs
------------------	--------------	--------------	--------------

## Notes

This connection is fully interchangeable with:

Wedge 523® - 7.625 in. - 29.7 lbs/ft

Connections with Dopeless® Technology are fully compatible with the same connection in its Standard version

For further information on concepts indicated in this datasheet, download the Datasheet Manual from [www.tenaris.com](http://www.tenaris.com)

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information –if any– provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or liability of any kind for any loss, damage or injury resulting from, or in connection with any Information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Tenaris's products and services are subject to Tenaris's standard terms and conditions or otherwise to the terms resulting from the respective contracts of sale or services, as the case may be, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at [www.tenaris.com](http://www.tenaris.com). ©Tenaris 2017 All rights reserved.



## Casing and Tubing Performance Data

### PIPE BODY DATA

#### GEOMETRY

Outside Diameter	7.000 in	Wall Thickness	0.408 in	API Drift Diameter	6.059 in
Nominal Weight	29.00 lbs/ft	Nominal ID	6.184 in	Alternative Drift Diameter	6.125 in
Plain End Weight	28.75 lbs/ft	Nominal cross section	8.449 in		

#### PERFORMANCE

Steel Grade	P110	Minimum Yield	110,000 psi	Minimum Ultimate	125,000 psi
Tension Yield	929,000 in	Internal Pressure Yield	11,220 psi	Collapse Pressure	8,530 psi
Available Seamless	Yes	Available Welded	Yes		

### CONNECTION DATA

TYPE: BTC

#### GEOMETRY

Coupling Reg OD	7.656 in	Threads per in	5	Thread turns make up	1
-----------------	----------	----------------	---	----------------------	---

#### PERFORMANCE

Steel Grade	P110	Coupling Min Yield	110,000 psi	Coupling Min Ultimate	125,000 psi
Joint Strength	955,000 lbs			Internal Pressure Resistance	11,220 psi

5.5", 20#, P-110, TXP connection (modified buttress connection that provides a torque rating of nearly 24000ft-lbs)

TXP® BTC

SHARE EXPORT DATA PRINT



Outside Diameter	5.500 in	Min. Wall Thickness	87.5%	▼	Clear Filters
Wall Thickness	0.361 in	Drift	API Standard	▼	Compare
Grade	P110	Type	Casing	▼	Request Info
		Connection OD Option	REGULAR	▼	CONNECTION INFORMATION
					<a href="#">Blanking Dimensions</a> <a href="#">Connection's Page</a> <a href="#">Brochure</a> <a href="#">Datasheet Manual</a>

#### PIPE BODY DATA

##### GEOMETRY

Nominal OD	5.500 in	Nominal Weight	20 lbs/ft	Drift	4.653 in.
Nominal ID	4.778 in	Wall Thickness	0.361 in	Plain End Weight	19.83 lbs/ft
OD Tolerance	API				

##### PERFORMANCE

Body Yield Strength	641 x1000 lbs	Internal Yield	12640 psi	SMYS	110000 psi
Collapse	11100 psi				

#### CONNECTION DATA

##### GEOMETRY

Connection OD	6.100 in	Coupling Length	9.450 in	Connection ID	4.766 in
Make-up Loss	4.204 in	Threads per in	5	Connection OD Option	REGULAR

##### PERFORMANCE

Tension Efficiency	100.0 %	Joint Yield Strength	641,000 x1000 lbs	Internal Pressure Capacity, <sup>(1)</sup>	12640,000 psi
Compression Efficiency	100 %	Compression Strength	641,000 x1000 lbs	Max. Allowable Bending	92 x100 ft
External Pressure Capacity	11100,000 psi				

##### MAKE-UP TORQUES

Minimum	11270 ft-lbs	Optimum	12520 ft-lbs	Maximum	13770 ft-lbs
---------	--------------	---------	--------------	---------	--------------

##### OPERATION LIMIT TORQUES

Operating Torque	21500 ft-lbs	Yield Torque	23900 ft-lbs		
------------------	--------------	--------------	--------------	--	--



## Casing and Tubing Performance Data

### PIPE BODY DATA

#### GEOMETRY

Outside Diameter	4.500 in	Wall Thickness	0.290 in	API Drift Diameter	3.795 in
Nominal Weight	13.50 lbs/ft	Nominal ID	3.920 in	Alternative Drift Diameter	n.a.
Plain End Weight	13.05 lbs/ft	Nominal cross section	3.836 in		

#### PERFORMANCE

Steel Grade	P110	Minimum Yield	110,000 psi	Minimum Ultimate	125,000 psi
Tension Yield	422,000 in	Internal Pressure Yield	12,410 psi	Collapse Pressure	10,690 psi
Available Seamless	Yes	Available Welded	Yes		

### CONNECTION DATA

TYPE: BTC

#### GEOMETRY

Coupling Reg OD	5.000 in	Threads per in	5	Thread turns make up	0.5
-----------------	----------	----------------	---	----------------------	-----

#### PERFORMANCE

Steel Grade	P110	Coupling Min Yield	110,000 psi	Coupling Min Ultimate	125,000 psi
Joint Strength	443,000 lbs			Internal Pressure Resistance	12,410 psi





APD ID: 10400026923

Submission Date: 02/05/2018

Highlighted data  
reflects the most  
recent changes

Operator Name: TAP ROCK OPERATING LLC

Well Name: DOUBLE DIAMOND FED COM

Well Number: 238H

[Show Final Text](#)

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

## Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

DD\_238H\_Road\_Map\_20180205095821.pdf

DD\_238H\_Road\_Plat\_033018\_20180330164307.PDF

Existing Road Purpose: ACCESS

Row(s) Exist? NO

**ROW ID(s)**

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

## Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

DD\_238H\_New\_Road\_Map\_20180205095847.pdf

DD\_238H\_Road\_Plat\_033018\_20180330164354.PDF

New road type: RESOURCE

Length: 227

Feet

Width (ft.): 30

Max slope (%): 0

Max grade (%): 1

Army Corp of Engineers (ACOE) permit required? NO

ACOE Permit Number(s):

New road travel width: 14

New road access erosion control: Crowned and ditched

New road access plan or profile prepared? NO

New road access plan attachment:

**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

**Access road engineering design?** NO

**Access road engineering design attachment:**

**Access surfacing type:** OTHER

**Access topsoil source:** ONSITE

**Access surfacing type description:** Caliche

**Access onsite topsoil source depth:** 6

**Offsite topsoil source description:**

**Onsite topsoil removal process:** Grader

**Access other construction information:**

**Access miscellaneous information:**

**Number of access turnouts:**

**Access turnout map:**

### **Drainage Control**

**New road drainage crossing:** OTHER

**Drainage Control comments:** Crowned and ditched

**Road Drainage Control Structures (DCS) description:** None

**Road Drainage Control Structures (DCS) attachment:**

### **Access Additional Attachments**

**Additional Attachment(s):**

### **Section 3 - Location of Existing Wells**

**Existing Wells Map?** YES

**Attach Well map:**

DD\_238H\_Well\_Map\_20180205100618.pdf

**Existing Wells description:**

### **Section 4 - Location of Existing and/or Proposed Production Facilities**

**Submit or defer a Proposed Production Facilities plan?** SUBMIT

**Production Facilities description:**

**Production Facilities map:**

DD\_238H\_Production\_Facilities\_20180205100858.pdf

**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

## Section 5 - Location and Types of Water Supply

### Water Source Table

**Water source use type:** DUST CONTROL,  
INTERMEDIATE/PRODUCTION CASING, STIMULATION, SURFACE  
CASING

**Water source type:** GW WELL

**Describe type:**

**Source longitude:**

**Source latitude:**

**Source datum:**

**Water source permit type:** PRIVATE CONTRACT

**Source land ownership:** FEDERAL

**Water source transport method:** TRUCKING

**Source transportation land ownership:** PRIVATE

**Water source volume (barrels):** 20000

**Source volume (acre-feet):** 2.577862

**Source volume (gal):** 840000

**Water source and transportation map:**

DD\_238H\_Water\_Source\_Map\_20180205101313.pdf

**Water source comments:**

**New water well?** NO

### New Water Well Info

**Well latitude:**

**Well Longitude:**

**Well datum:**

**Well target aquifer:**

**Est. depth to top of aquifer(ft):**

**Est thickness of aquifer:**

**Aquifer comments:**

**Aquifer documentation:**

**Well depth (ft):**

**Well casing type:**

**Well casing outside diameter (in.):**

**Well casing inside diameter (in.):**

**New water well casing?**

**Used casing source:**

**Drilling method:**

**Drill material:**

**Grout material:**

**Grout depth:**

**Casing length (ft.):**

**Casing top depth (ft.):**

**Well Production type:**

**Completion Method:**

**Water well additional information:**

**State appropriation permit:**

**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

**Additional information attachment:**

## Section 6 - Construction Materials

**Construction Materials description:** NM One Call (811) will be notified before construction starts. Top 6" of soil and brush will be stockpiled north of the pad. Pipe racks will be to the south. A closed loop drilling system will be used. Caliche will be hauled from existing pit on private land in NENE 7-23s-31e.

**Construction Materials source location attachment:**

DD\_238H\_Construction\_Methods\_20180205101422.pdf

## Section 7 - Methods for Handling Waste

**Waste type:** DRILLING

**Waste content description:** Drill cuttings, mud, salts, and other chemicals

**Amount of waste:** 2000 barrels

**Waste disposal frequency :** Daily

**Safe containment description:** Steel tanks

**Safe containmant attachment:**

**Waste disposal type:** HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** PRIVATE

**Disposal type description:**

**Disposal location description:** R360's state approved (NM1-6-0) disposal site at Halfway, NM

## Reserve Pit

**Reserve Pit being used?** NO

**Temporary disposal of produced water into reserve pit?**

**Reserve pit length (ft.)** **Reserve pit width (ft.)**

**Reserve pit depth (ft.)** **Reserve pit volume (cu. yd.)**

**Is at least 50% of the reserve pit in cut?**

**Reserve pit liner**

**Reserve pit liner specifications and installation description**

## Cuttings Area

**Cuttings Area being used?** NO

**Are you storing cuttings on location?** YES

**Description of cuttings location** Steel tanks on pad

**Cuttings area length (ft.)**

**Cuttings area width (ft.)**



**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

**Cuttings area depth (ft.)**

**Cuttings area volume (cu. yd.)**

**Is at least 50% of the cuttings area in cut?**

**WCuttings area liner**

**Cuttings area liner specifications and installation description**

## Section 8 - Ancillary Facilities

**Are you requesting any Ancillary Facilities?:** NO

**Ancillary Facilities attachment:**

**Comments:**

## Section 9 - Well Site Layout

**Well Site Layout Diagram:**

DD\_238H\_Well\_Site\_Layout\_20180205101612.pdf

**Comments:**

## Section 10 - Plans for Surface Reclamation

**Type of disturbance:** New Surface Disturbance

**Multiple Well Pad Name:** DOUBLE DIAMOND

**Multiple Well Pad Number:** 238H

**Recontouring attachment:**

DD\_238H\_Recontour\_Plant\_20180205101630.pdf

DD\_238H\_Interim\_Reclamation\_Diagram\_20180205101638.pdf

**Drainage/Erosion control construction:** Crowned and ditched

**Drainage/Erosion control reclamation:** Harrowed on the contour

**Well pad proposed disturbance (acres):** 5.11

**Road proposed disturbance (acres):** 0.16

**Powerline proposed disturbance (acres):** 0

**Pipeline proposed disturbance (acres):** 0

**Other proposed disturbance (acres):** 0

**Total proposed disturbance:** 5.27

**Well pad interim reclamation (acres):** 1.35

**Road interim reclamation (acres):** 0

**Powerline interim reclamation (acres):** 0

**Pipeline interim reclamation (acres):** 0

**Other interim reclamation (acres):** 0

**Total interim reclamation:** 1.35

**Well pad long term disturbance (acres):** 3.76

**Road long term disturbance (acres):** 0.16

**Powerline long term disturbance (acres):** 0

**Pipeline long term disturbance (acres):** 0

**Other long term disturbance (acres):** 0

**Total long term disturbance:** 3.92

**Reconstruction method:** Interim reclamation will shrink the well pad 26% by removing caliche and reclaiming the north 40' and west 100', leaving 3.76 acres for producing 5 wells and truck turn arounds.

**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

**Topsoil redistribution:** Enough stockpiled topsoil will be retained to cover the remainder of the pad when the wells are plugged. Once the last well is plugged, then the remainder of the pad and new road will be similarly reclaimed. Noxious weeds will be controlled.

**Soil treatment:** None

**Existing Vegetation at the well pad:**

**Existing Vegetation at the well pad attachment:**

**Existing Vegetation Community at the road:**

**Existing Vegetation Community at the road attachment:**

**Existing Vegetation Community at the pipeline:**

**Existing Vegetation Community at the pipeline attachment:**

**Existing Vegetation Community at other disturbances:**

**Existing Vegetation Community at other disturbances attachment:**

**Non native seed used?** NO

**Non native seed description:**

**Seedling transplant description:**

**Will seedlings be transplanted for this project?** NO

**Seedling transplant description attachment:**

**Will seed be harvested for use in site reclamation?** NO

**Seed harvest description:**

**Seed harvest description attachment:**

## **Seed Management**

### **Seed Table**

**Seed type:**

**Seed source:**

**Seed name:**

**Source name:**

**Source address:**

**Source phone:**

**Seed cultivar:**

**Seed use location:**

**PLS pounds per acre:**

**Proposed seeding season:**

**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

### Seed Summary

**Total pounds/Acre:**

**Seed Type**

**Pounds/Acre**

**Seed reclamation attachment:**

### Operator Contact/Responsible Official Contact Info

**First Name:**

**Last Name:**

**Phone:**

**Email:**

**Seedbed prep:**

**Seed BMP:**

**Seed method:**

**Existing invasive species?** NO

**Existing invasive species treatment description:**

**Existing invasive species treatment attachment:**

**Weed treatment plan description:** To BLM standards

**Weed treatment plan attachment:**

**Monitoring plan description:** To BLM standards

**Monitoring plan attachment:**

**Success standards:** To BLM satisfaction

**Pit closure description:** No pit

**Pit closure attachment:**

### Section 11 - Surface Ownership

**Disturbance type:** WELL PAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Disturbance type:** EXISTING ACCESS ROAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Disturbance type:** NEW ACCESS ROAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**



**Operator Name:** TAP ROCK OPERATING LLC

**Well Name:** DOUBLE DIAMOND FED COM

**Well Number:** 238H

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

## Section 12 - Other Information

**Right of Way needed?** NO

**Use APD as ROW?**

**ROW Type(s):**

## ROW Applications


**SUPO Additional Information:** Deficiency letter dated 3/29/19 requested road plat - see attached

**Use a previously conducted onsite?** YES

**Previous Onsite information:** On-site inspection was held with Vance Wolfe (BLM) on December 7, 2017. Lone Mountain filed archaeology report NMCRIS 139066 on October 3, 2017.

## Other SUPO Attachment

DD\_238H\_General\_SUPO\_20180205102327.pdf



MAP 1

Double Diamond  
Fed Com 238H

Map created with TOPO! ©2010 National Geographic




02/04/18




MAP 2

Double Diamond  
Fed Com 238H

Map created with  National Geographic; ©2005 Tele Atlas; Rel. 8/2005











SECTION 14, TOWNSHIP 24-S, RANGE 31-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

MAP 4

DETAIL VIEW  
SCALE: 1" = 100'



LEASE NAME & WELL NO.: DOUBLE DIAMOND 24S21E1414 238H  
238H LATITUDE N 32.2109581 238H LONGITUDE W 103.7428434




ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID  
BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY  
FEET.

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER  
MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY,  
AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO  
THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS  
SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140  
TELEPHONE (817) 744-7512 • FAX (817) 744-7554  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM



Being a proposed road easement being 30 feet in width, 15 feet left, and 15 feet right of the above platted centerline total line footage containing 227.34 feet or 13.78 rods, containing 0.16 acres more or less.



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM




*Stan W. Lloyd*

Stan W. Lloyd, P.S. No. 19642  
MARCH 30, 2018

DOUBLE DIAMOND SURFACE PAD SITE ROAD EASEMENT	REVISION:		NOTES:
	INT	DATE	
DATE: 03/30/18			1. ORIGINAL DOCUMENT SIZE: 8.5" X 11" 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET. 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY TAP ROCK OPERATING, LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY. 4. B.O.L. = BEGINNING OF LINE 5. E.O.L. = END OF LINE
FILE: EP_DOUBLE_DIAMOND_SURFACE_PAD_SITE_RD			
DRAWN BY: AMD			
SHEET: 1 OF 1			



# EXHIBIT 2 VICINITY MAP



LEASE NAME & WELL NO.: DOUBLE DIAMOND 24S21E1414 228H

SECTION 14 TWP 24-S RGE 31-E SURVEY N.M.P.M.

COUNTY EDDY STATE NM

DESCRIPTION 305' FSL & 910' FEL

## DISTANCE & DIRECTION

FROM INT. OF NM-31, & NM-128-E, HEAD EAST ON NM-128 E  $\pm 19.6$  MILES, THENCE SOUTHWEST (RIGHT) ON BUCK JACKSON RD.  $\pm 1.1$  MILES, THENCE SOUTHEAST, (LEFT) ON LEASE RD  $\pm 1.6$  MILES, THENCE WEST ON PROPOSED RD  $\pm 215$  FEET TO A POINT  $\pm 332$  FEET SOUTHEAST OF THE LOCATION.

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.




SCALE: 1" = 10000'  
0' 5000' 10000'




**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 787-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM



Map created with TOPO! ©2010 National Geographic



TN-MN  
7°  
02/04/18






SECTION 14, TOWNSHIP 24-S, RANGE 31-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

MAP 4

DETAIL VIEW  
SCALE: 1" = 100'



LEASE NAME & WELL NO.: DOUBLE DIAMOND 24S21E1414 238H  
238H LATITUDE N 32.2109581 238H LONGITUDE W 103.7428434



SCALE: 1" = 100'  
0' 50' 100'


ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID  
BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY  
FEET.

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER  
MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY,  
AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO  
THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS  
SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM



Being a proposed road easement being 30 feet in width, 15 feet left, and 15 feet right of the above platted centerline total line footage containing 227.34 feet or 13.78 rods, containing 0.16 acres more or less.



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM




*Stan W. Lloyd*  
Stan W. Lloyd, P.S. No. 19642  
MARCH 30, 2018

DOUBLE DIAMOND SURFACE PAD SITE ROAD EASEMENT	REVISION:		NOTES:
	INT	DATE	
DATE: 03/30/18			<p>1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"</p> <p>2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.</p> <p>3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY TAP ROCK OPERATING, LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.</p> <p>4. B.O.L. = BEGINNING OF LINE</p> <p>5. E.O.L. = END OF LINE</p>
FILE: EP_DOUBLE_DIAMOND_SURFACE_PAD_SITE_RD			
DRAWN BY: AMD			
SHEET: 1 OF 1			



# EXHIBIT 2 VICINITY MAP



LEASE NAME & WELL NO.: DOUBLE DIAMOND 24S21E1414 228H

SECTION 14 TWP 24-S RGE 31-E SURVEY N.M.P.M.

COUNTY EDDY STATE NM

DESCRIPTION 305' FSL & 910' FEL

## DISTANCE & DIRECTION

FROM INT. OF NM-31, & NM-128-E, HEAD EAST ON NM-128 E ±19.6 MILES,  
THENCE SOUTHWEST (RIGHT) ON BUCK JACKSON RD. ±1.1 MILES, THENCE  
SOUTHEAST, (LEFT) ON LEASE RD ±1.6 MILES, THENCE WEST ON PROPOSED  
RD ±215 FEET TO A POINT ±332 FEET SOUTHEAST OF THE LOCATION.

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.




SCALE: 1" = 10000'  
0' 5000' 10000'



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM




Map created with TOPOI ©2010 National Geographic



TN+MN  
7°  
02/04/18









SECTION 14, TOWNSHIP 24-S, RANGE 31-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

MAP 6

DETAIL VIEW  
SCALE: 1" = 100'



LEASE NAME & WELL NO.: DOUBLE DIAMOND 24S21E1414 238H  
238H LATITUDE N 32.2109581 238H LONGITUDE W 103.7428434



ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID  
BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY  
FEET.



THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER  
MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY,  
AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO  
THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS  
SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM



TOPOI map printed on 02/04/18 from "Untitled.tpo"



MAP 7


TN \* MN  
7°  
02/04/18




SECTION 14, TOWNSHIP 24-S, RANGE 31-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

MAP 8

DETAIL VIEW  
SCALE: 1" = 100'



LEASE NAME & WELL NO.: DOUBLE DIAMOND 24S21E1414 238H  
238H LATITUDE N 32.2109581 238H LONGITUDE W 103.7428434




ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID  
BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY  
FEET.

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER  
MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY,  
AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO  
THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS  
SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.


 **TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY  
1400 EVERMAN PARKWAY, Ste. 145 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM





Double Diamond Fed Com 238H  
rig diagram

1" = 80'






TOP OF PAD ELEVATION: 3585.9292  
 CUT SLOPE: 33.33% 3.000:1 18.43°  
 FILL SLOPE: 33.33% 3.000:1 18.43°  
 BALANCE TOLERANCE (C.Y.): 0.00  
 CUT SWELL FACTOR: 1.00  
 FILL SHRINK FACTOR: 1.00

PAD EARTHWORK VOLUMES  
 CUT 128,917.1 C.F., 4,774.71 C.Y.  
 FILL: 128,917.1 C.F., 4,774.71 C.Y.  
 AREA: 231518.3 SQ.FT., 5.315 ACRES


SECTION 14, TOWNSHIP 24-S, RANGE 31-E, N.M.P.M.  
 EDDY COUNTY, NEW MEXICO




A-A'



B-B'



C-C'



Horizontal Scale = 1:60  
 Vertical Scale = 1:10



1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140  
 TELEPHONE: (817) 744-7512 • FAX (817) 744-7554  
 2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
 TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
 WWW.TOPOGRAPHIC.COM

DOUBLE DIAMOND 24S21E1414 PAD SITE	REVISION:		NOTES:
	INT	DATE	
DATE: 01/26/18			1. ORIGINAL DOCUMENT SIZE: 8.5" X 11" 2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET. 3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY TAP ROCK OPERATING, LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.
FILE: CD_DOUBLE_DIAMOND_UNIT			
DRAWN BY: EAH			
SHEET:			



Michael Blake Brown, P.S. No. 18329  
 JANUARY 26, 2018


MAP 11

SCALE: 1" = 100'

0' 50' 100'

SECTION 14, TOWNSHIP 24-S, RANGE 31-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

MAP 12



**TAP**  
ROCK



**TOPOGRAPHIC**  
LOYALTY INNOVATION LEGACY

1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM



Michael Blake Brown, P.S. No. 18329  
JANUARY 26, 2018

DOUBLE DIAMOND 24S21E1414 PAD SITE	REVISION:	
	INT	DATE
DATE: 01/26/18		
FILE: CD_DOUBLE_DIAMOND_UNIT		
DRAWN BY: EAH		
SHEET :		

NOTES:

1. ORIGINAL DOCUMENT SIZE: 8.5" X 11"
2. ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREIN ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.
3. CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT, IN RELATION TO THE EVIDENCE FOUND DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY TAP ROCK OPERATING, LLC. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY






SECTION 14, TOWNSHIP 24-S, RANGE 31-E, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

DETAIL VIEW  
SCALE: 1" = 100'

MAP 10

interim reclaim  
40' on north  
100' on west



LEASE NAME & WELL NO.: DOUBLE DIAMOND 24S21E1414 238H  
238H LATITUDE N 32.2109581 238H LONGITUDE W 103.7428434

N

SCALE: 1" = 100'  
0' 50' 100'

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID  
BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY  
FEET.

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER  
MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY,  
AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO  
THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS  
SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140  
TELEPHONE: (817) 744-7512 • FAX (817) 744-7554  
2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705  
TELEPHONE: (432) 682-1653 OR (800) 767-1553 • FAX (432) 682-1743  
WWW.TOPOGRAPHIC.COM

Tap Rock Operating LLC  
Double Diamond Fed Com 238H  
SHL 305' FSL & 860' FEL  
BHL 200' FNL & 330' FEL  
Sec. 14, T. 24 S., R. 31 E., Eddy County, NM

SURFACE PLAN PAGE 1

Surface Use Plan

1. ROAD DIRECTIONS & DESCRIPTIONS (See MAPS 1 - 4)

From the equivalent of Mile Post 23.4 on US 285 between Carlsbad & Loving...  
Go E 19.5 miles on paved NM 31 to the equivalent of Mile Post 19.5  
Then turn right and go SW 3.1 miles on caliche County Road 786  
Then turn left and go SW 1/3 mile on a caliche road to a well  
Then go East 1/4 mile on a caliche road to a second well  
Then turn left and go N 100 yards on a caliche road  
Then turn right and go E 1/2 mile on a caliche road  
Then turn left and go N 0.4 mile on a caliche road  
Then turn left and go W 227' cross-country to the proposed pad

Non-county roads will be maintained as needed to Gold Book standards. This includes pulling ditches, preserving the crown, and cleaning culverts. This will be done at least once a year, and more often as needed. Caliche will be hauled from an existing pit on private land in NENE 7-23s-31e.

2. ROAD TO BE BUILT OR UPGRADED (See MAP 4)

227' of new resource road will be built. The new road will be crowned and ditched, have a 14' wide driving surface, and be surfaced with caliche. Maximum disturbed width = 30'. Maximum grade = 1%. Maximum cut or fill = 1'. No upgrade, culvert, cattle guard, or vehicle turn out is needed.

3. EXISTING WELLS (See MAP 5)

Existing oil, gas, SWD, and P & A wells are within a mile. No water or injection well is within a mile.

Tap Rock Operating LLC  
Double Diamond Fed Com 238H  
SHL 305' FSL & 860' FEL  
BHL 200' FNL & 330' FEL  
Sec. 14, T. 24 S., R. 31 E., Eddy County, NM

SURFACE PLAN PAGE 2

4. PROPOSED PRODUCTION FACILITIES (See MAP 6)

Production facilities will be on the southeast sides of the pad. Gas pipeline and power line plans have not been finalized.

5. WATER SUPPLY (See MAP 7)

Water will be trucked from a private water well (C 03662) on private land in NWNE 23-24s-33e.

6. CONSTRUCTION MATERIALS & METHODS (see MAPS 8 & 9)

NM One Call (811) will be notified before construction starts. Top  $\approx 6$ " of soil and brush will be stockpiled north of the pad. Pipe racks will be to the south. A closed loop drilling system will be used. Caliche will be hauled from existing pit on private land in NENE 7-23s-31e.

7. WASTE DISPOSAL

All trash will be placed in a portable trash cage. It will be hauled to the Eddy County landfill. There will be no trash burning. Contents (drill cuttings, mud, salts, and other chemicals) of the mud tanks will be hauled to R360's state approved (NM1-6-0) disposal site at Halfway. Human waste will be disposed of in chemical toilets and hauled to the Carlsbad wastewater treatment plant.

8. ANCILLARY FACILITIES

There will be no airstrip or camp. Camper trailers will be on location for the company man, tool pusher, or mud logger.



Tap Rock Operating LLC  
Double Diamond Fed Com 238H  
SHL 305' FSL & 860' FEL  
BHL 200' FNL & 330' FEL  
Sec. 14, T. 24 S., R. 31 E., Eddy County, NM

SURFACE PLAN PAGE 3

#### 9. WELL SITE LAYOUT

See Rig Diagram for depictions of the well pad, trash cage, access onto the location, parking, living facilities, and rig orientation.

#### 10. RECLAMATION (See MAPS 10 - 12)

Interim reclamation will shrink the well pad  $\approx 26\%$  by removing caliche and reclaiming the north 40' and west 100', leaving 3.76 acres for producing 5 wells and truck turn arounds. Disturbed areas will be contoured to match pre-construction grades. Soil and brush will be evenly spread over disturbed areas. Disturbed areas will be seeded in accordance with BLM requirements. Enough stockpiled topsoil will be retained to cover the remainder of the pad when the wells are plugged. Once the last well is plugged, then the remainder of the pad and new road will be similarly reclaimed. Noxious weeds will be controlled.

Land use:

$$\begin{aligned} 30' \times 227' \text{ road} &= 0.16 \text{ acre} \\ + 420' \times 530' \text{ pad} &= 5.11 \text{ acres} \\ \text{short term} &= 5.27 \text{ acres} \end{aligned}$$

$$\begin{aligned} &\text{short term} = 5.27 \text{ acres} \\ &- \text{interim reclamation on well pad} = 1.35 \text{ acres} \\ &3.92 \text{ acres long term (0.16 ac. road + 3.76 ac. pad)} \end{aligned}$$

#### 11. SURFACE OWNER

All construction will be on BLM, 620 E. Greene, Carlsbad NM 88220. Phone is 575 234-5972.



Tap Rock Operating LLC  
Double Diamond Fed Com 238H  
SHL 305' FSL & 860' FEL  
BHL 200' FNL & 330' FEL  
Sec. 14, T. 24 S., R. 31 E., Eddy County, NM


SURFACE PLAN PAGE 4

## 12. OTHER INFORMATION

On-site inspection was held with Vance Wolfe (BLM) on December 7, 2017.  
Lone Mountain filed archaeology report NMCRIS 139066 on October 3, 2017.

## CERTIFICATION

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U. S. C. 1001 for the filing of false statements. Executed this 4th day of February, 2018.



-----  
Brian Wood, Consultant

Permits West, Inc.

37 Verano Loop, Santa Fe, NM 87508

(505) 466-8120

FAX: (505) 466-9682

Cellular: (505) 699-2276

Field representative will be:

Doug Sproul

Tap Rock Operating, LLC

602 Park Point Dr., Suite 200, Golden CO 80401

Phone: (720) 772-5090



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## PWD Data Report

05/01/2018

### Section 1 - General

Would you like to address long-term produced water disposal? NO

### Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

### **Section 3 - Unlined Pits**

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

### **Section 4 - Injection**

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Assigned injection well API number?

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Injection well name:

Injection well API number:

## Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

## Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment:





U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Bond Info Data Report

05/01/2018

### Bond Information

Federal/Indian APD: FED

BLM Bond number: NMB001443

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment: