

Carlsbad Field Office
OCD Artesia

FORM APPROVED
OMB No. 1004-0137
Expires October 31, 2014

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: ☒ DRILL ☐ REENTER		5. Lease Serial No. NMLC0065928A
1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator CQG OPERATING LLC		7. If Unit or CA Agreement, Name and No.
3a. Address 600 West Illinois Ave Midland TX 79701		8. Lease Name and Well No. LITTLEFIELD 33 FEDERAL 806H
3b. Phone No. (include area code) (432)683-7443		9. API Well No. 30-015-45167
4. Location of Well (Report location clearly and in accordance with any State requirements.) At surface LOT 10 / 300 FSL / 2406 FWL / LAT 32.0009264 / LONG -103.9904338 At proposed prod. zone NENW / 200 FNL / 1884 FWL / LAT 32.0205148 / LONG -103.9918364		10. Field and Pool, or Exploratory WILDCAT / PURPLE SAGE WOLFCAMP
11. Sec., T. R. M. or Blk. and Survey or Area SEC 33 / T26S / R29E / NMP		12. County or Parish EDDY
13. State NM		14. Distance in miles and direction from nearest town or post office* 15 miles
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 200 feet	16. No. of acres in lease 419.41	17. Spacing Unit dedicated to this well 463.13
18. Distance from proposed location* to nearest well, drilling, completed, 745 feet applied for, on this lease, ft.	19. Proposed Depth 10062 feet / 16944 feet	20. BLM/BIA Bond No. on file FED: NMB000215
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 2858 feet	22. Approximate date work will start* 07/01/2018	23. Estimated duration 30 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, must be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the BLM.

25. Signature (Electronic Submission)	Name (Printed/Typed) Mayte Reyes / Ph: (575)748-6945	Date 04/03/2018
Title Regulatory Analyst		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575)234-5959	Date 08/02/2018
Title Assistant Field Manager Lands & Minerals		
Office CARLSBAD		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

APPROVED WITH CONDITIONS

Approval Date: 08/02/2018

RUP.

8-13-18

NM OIL CONSERVATION
ARTESIA DISTRICT

AUG 10 2018

RECEIVED

INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM 1: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to allow evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications.

Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease.

The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Collection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

- I. SHL: LOT 10 / 300 FSL / 2406 FWL / TWSP: 26S / RANGE: 29E / SECTION: 33 / LAT: 32.0009264 / LONG: -103.9904338 (TVD: 0 feet, MD: 0 feet)
PPP: NESW / 2245 FSL / 1884 FWL / TWSP: 26S / RANGE: 29E / SECTION: 28 / LAT: 32.0162309 / LONG: -103.9919483 (TVD: 10887 feet, MD: 15300 feet)
PPP: LOT 10 / 330 FSL / 1884 FWL / TWSP: 26S / RANGE: 29E / SECTION: 33 / LAT: 32.0010109 / LONG: -103.9920118 (TVD: 10850 feet, MD: 11050 feet)
BHL: NENW / 200 FNL / 1884 FWL / TWSP: 26S / RANGE: 29E / SECTION: 28 / LAT: 32.0205148 / LONG: -103.9918364 (TVD: 10062 feet, MD: 16944 feet)

BLM Point of Contact

Name: Judith Yeager

Title: Legal Instruments Examiner

Phone: 5752345936

Email: jyeager@blm.gov

CONFIDENTIAL

Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

CONFIDENTIAL

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	COG Operating LLC
LEASE NO.:	NMLC0065928A
WELL NAME & NO.:	Littlefield 33 Federal Com 806H
SURFACE HOLE FOOTAGE:	300'/S & 2406'/W
BOTTOM HOLE FOOTAGE:	200'/N & 1884'/W
LOCATION:	Section 33, T.26 S., R.29 E., NMPM
COUNTY:	Eddy County, New Mexico

Potash	☒ None	☐ Secretary	☐ R-111-P
Cave/Karst Potential	☐ Low	☒ Medium	☐ High
Variance	☐ None	☒ Flex Hose	☐ Other
Wellhead	☒ Conventional	☐ Multibowl	
Other	☐ 4 String Area	☐ Capitan Reef	☐ WIPP

A. Hydrogen Sulfide

1. Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The **10 3/4** inch surface casing shall be set at approximately **400** feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 7 5/8 inch intermediate casing is:
 - Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.**
 - ❖ In **Medium Cave/Karst Areas** if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface
3. The minimum required fill of cement behind the 5 1/2 X 5 inch production casing is:
 - Cement should tie-back at least **200** feet into previous casing string. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **3000 (3M)** psi
3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 7 5/8 inch intermediate casing shoe shall be **5000 (5M)** psi.

D. SPECIAL REQUIREMENT(S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.

- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

Waste Minimization Plan (WMP)

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

MHH 07212018

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties

Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.

During office hours call (575) 627-0272.

After office hours call (575)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Operator shall perform the intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the

plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

COG Operating, LLC - Littlefield 33 Federal Com 806H

1. Geologic Formations

TVD of target	10,062' EOL	Pilot hole depth	NA
MD at TD:	16,944'	Deepest expected fresh water:	200'

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Quaternary Fill	Surface	Water	
Rustler	488	Water	
Top of Salt	636	Salt	
Base of Salt	2642	Salt	
Lamar	2822	Salt Water	
Delaware	2860	Salt Water	
Bone Spring	6519	Oil/Gas	
1st Bone Spring	7436	Oil/Gas	
2nd Bone Spring	8585	Oil/Gas	
3rd Bone Spring	9300	Oil/Gas	
Wolfcamp	9664	Oil/Gas	
Wolfcamp B	10138	Oil/Gas	
Wolfcamp C	10432	Oil/Gas	
Wolfcamp D	10749	Target Oil/Gas	
Strawn	12183	Not Penetrated	

2. Casing Program - SEE CoA

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Body
	From	To							
13.5"	0	600	10.75"	45.5	N80	BTC	9.00	1.41	38.10
9.875"	0	10065	7.875" 7.5"	29.7	P110	BTC	1.51	1.45	3.63
6.75"	0	9565	5.5"	23	P110	BTC	2.52	2.66	4.03
6.75"	9565	16,944	5"	18	P110	BTC	2.52	2.66	4.03
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

Intermediate casing will be kept at least 1/3 full while running casing to mitigate collapse. Surface burst based on 0.7 frac gradient at the shoe with Gas Gradient 0.1 psi/ft to surface and
All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

The 5" casing will be run back 500' into the intermediate casing to ensure the coupling OD clearance is greater than .422" for the cement bond tie in.

4. Pressure Control Equipment

N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
---	---

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	x	Tested to:
9-7/8"	13-5/8"	3M	Annular	x	3000 psi
			Blind Ram	X	3M
			Pipe Ram	X	
			Double Ram		
			Other*		
6-3/4"	13-5/8"	5M	Annular	x	50% testing pressure
			Blind Ram	x	5M
			Pipe Ram	x	
			Double Ram		
			Other*		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
Y	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?
N	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

PECOS DISTRICT SURFACE USE CONDITIONS OF APPROVAL

OPERATOR'S NAME:	COG Operating LLC
LEASE NO.:	NMLC0065928A
WELL NAME & NO.:	Littlefield 33 Federal Com 806H
SURFACE HOLE FOOTAGE:	300'/S & 2406'/W
BOTTOM HOLE FOOTAGE:	200'/N & 1884'/W
LOCATION:	Section 33, T.26 S., R.29 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Cave/Karst
 - Hydrology
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Cave and Karst Conditions of Approval for APDs

****** Depending on location, additional Drilling, Casing, and Cementing procedures may be required by engineering to protect critical karst groundwater recharge areas.

Cave/Karst Surface Mitigation

The following stipulations will be applied to minimize impacts during construction, drilling and production:

Construction:

In the advent that any underground voids are opened up during construction activities, construction activities will be halted and the BLM will be notified immediately.

No Blasting:

No blasting will be utilized for pad construction. The pad will be constructed and leveled by adding the necessary fill and caliche.

Pad Berming:

- The entire perimeter of the well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.
- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g., caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised. (Any access road crossing the berm cannot be lower than the berm height.)
- Following a rain event, all fluids will vacuumed off of the pad and hauled off-site and disposed at a proper disposal facility.

Tank Battery Liners and Berms:

Tank battery locations and all facilities will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing, or equivalent, to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

Leak Detection System:

A method of detecting leaks is required. The method could incorporate gauges to measure loss, siting valves and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present. Leak detection plan will be submitted to BLM for approval.

Automatic Shut-off Systems:

Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

Cave/Karst Subsurface Mitigation

The following stipulations will be applied to protect cave/karst and ground water concerns:

Rotary Drilling with Fresh Water:

Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

Directional Drilling:

Kick off for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

Lost Circulation:

ALL lost circulation zones from the surface to the base of the cave occurrence zone will be logged and reported in the drilling report.

Regardless of the type of drilling machinery used, if a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cave-bearing zone, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

Abandonment Cementing:

Upon well abandonment in cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

Pressure Testing:

The operator will perform annual pressure monitoring on all casing annuli and reported in a sundry notice. If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

FLOWLINES (SURFACE):

- Flowlines will be routed around sinkholes and other karst features to avoid or lessen the possibility of encountering near surface voids and to minimize the possibility of leaks and spills from entering karst systems.
- If a void is encountered alignments may be rerouted to avoid the karst feature and lessen; the potential of subsidence or collapse of karst features, buildup of toxic or

combustible gas, or other possible impacts to cave and karst resources from the buried pipeline.

- Regular monitoring is required to quickly identify leaks for their immediate and proper treatment.
- All spills or leaks will be reported to the BLM immediately for their immediate and proper treatment.

Hydrology

The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The berm shall be maintained through the life of the well and after interim reclamation has been completed. Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion.

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour production, whichever is greater. Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect pressure drops, siting valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill out sloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, Shale Green from the BLM Standard Environmental Color Chart (CC-001: June 2008).

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 3, for Shallow Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass (<i>Setaria macrostachya</i>)	1.0
Green Sprangletop (<i>Leptochloa dubia</i>)	2.0
Sideoats Grama (<i>Bouteloua curtipendula</i>)	5.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

08/02/2018

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Mayte Reyes

Signed on: 04/03/2018

Title: Regulatory Analyst

Street Address: 2208 W Main Street

City: Artesia

State: NM

Zip: 88210

Phone: (575)748-6945

Email address: Mreyes1@concho.com

Field Representative

Representative Name: Rand French

Street Address: 2208 West Main Street

City: Artesia

State: NM

Zip: 88210

Phone: (575)748-6940

Email address: rfrench@concho.com



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data Report

08/02/2018

APD ID: 10400029027

Submission Date: 04/03/2018

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Well Type: OIL WELL

Well Work Type: Drill

Highlighted data
reflects the most
recent changes

[Show Final Text](#)

Section 1 - General

APD ID: 10400029027

Tie to previous NOS?

Submission Date: 04/03/2018

BLM Office: CARLSBAD

User: Mayte Reyes

Title: Regulatory Analyst

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMLC0065928A

Lease Acres: 419.41

Surface access agreement in place? N

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO

APD Operator: COG OPERATING LLC

Operator letter of designation:

Operator Info

Operator Organization Name: COG OPERATING LLC

Operator Address: 600 West Illinois Ave

Zip: 79701

Operator PO Box:

Operator City: Midland

State: TX

Operator Phone: (432)683-7443

Operator Internet Address: RODOM@CONCHO.COM

Section 2 - Well Information

Well in Master Development Plan? NO

Mater Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: WILDCAT

Pool Name: PURPLE SAGE
WOLFCAMP GAS

Is the proposed well in an area containing other mineral resources? USEABLE WATER,OIL

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Describe other minerals:

Is the proposed well in a Helium production area? N Use Existing Well Pad? NO New surface disturbance?

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: Number: 705H, 706H, 805H

LITTLEFIELD 33 FEDERAL COMAND 806H

Well Class: HORIZONTAL

Number of Legs:

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: EXPLORATORY (WILDCAT)

Describe sub-type:

Distance to town: 15 Miles

Distance to nearest well: 745 FT

Distance to lease line: 200 FT

Reservoir well spacing assigned acres Measurement: 463.13 Acres

Well plat: COG_Littlefield_806H_C102_20180601081032.pdf

Well work start Date: 07/01/2018

Duration: 30 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number:

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1	300	FSL	240 6	FWL	26S	29E	33	Lot 10	32.00092 64	- 103.9904 338	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 065928 A	285 8	0	0
KOP Leg #1	300	FSL	240 6	FWL	26S	29E	33	Lot 10	32.00092 64	- 103.9904 338	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 065928 A	285 8	0	0
PPP Leg #1	330	FSL	188 4	FWL	26S	29E	33	Lot 10	32.00101 09	- 103.9921 18	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 065928 A	- 799 2	110 50	108 50



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

08/02/2018

APD ID: 10400029027

Submission Date: 04/03/2018

Operator Name: COG OPERATING LLC

Highlighted data
reflects the most
recent changes

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Show Final Text

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	QUATERNARY	2858	0	0		NONE	No
2	RUSTLER	2371	488	488		NONE	No
3	TOP SALT	2222	636	636	SALT	NONE	No
4	BASE OF SALT	217	2642	2642	ANHYDRITE	NONE	No
5	LAMAR	36	2822	2822	LIMESTONE	OTHER : Salt Water	No
6	DELAWARE	-1	2860	2860		OTHER : Salt Water	No
7	BONE SPRING	-3660	6519	6519		NATURAL GAS,OIL	No
8	BONE SPRING 1ST	-4577	7436	7436		NATURAL GAS,OIL	No
9	BONE SPRING 2ND	-5726	8585	8585	SANDSTONE	NATURAL GAS,OIL	No
10	BONE SPRING 3RD	-6441	9300	9300		NATURAL GAS,OIL	No
11	WOLFCAMP	-6806	9664	9664		NATURAL GAS,OIL	No
12	WOLFCAMP	-7279	10138	10138		NATURAL GAS,OIL	No
13	WOLFCAMP	-7573	10432	10432		NATURAL GAS,OIL	No
14	WOLFCAMP	-7891	10749	10749		NATURAL GAS,OIL	Yes
15	STRAWN	-9324	12183	12183		NATURAL GAS,OIL	No

Section 2 - Blowout Prevention

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Pressure Rating (PSI): 3M

Rating Depth: 9565

Equipment: Annular. Accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold.

Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP to the choke manifold. See attached for specs and hydrostatic test chart.

Testing Procedure: BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested. Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets.

Choke Diagram Attachment:

COG_Littlefield_806H_3M_Choke_20180328143723.pdf

BOP Diagram Attachment:

COG_Littlefield_806H_3M_BOP_20180328143731.pdf

COG_Littlefield_806H_Flex_Hose_20180717152347.pdf

Pressure Rating (PSI): 5M

Rating Depth: 10065

Equipment: Annular, Blind Ram, Pipe Ram. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold

Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP to the choke manifold. See attached for specs and hydrostatic test chart.

Testing Procedure: BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested. Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets.

Choke Diagram Attachment:

COG_Littlefield_806H_5M_Choke_20180328143803.pdf

BOP Diagram Attachment:

COG_Littlefield_806H_5M_BOP_20180328143809.pdf

COG_Littlefield_806H_Flex_Hose_20180717152404.pdf

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	13.5	10.75	NEW	API	N	0	600	0	600	-6999	-7974	600	N-80	45.5	OTHER - BTC	9	1.41	DRY	38.1	DRY	38.1
2	INTERMEDIATE	9.875	7.875	NEW	API	Y	0	10065	0	10065	-6999	-18749	10065	P-110	29.7	OTHER - BTC	1.51	1.45	DRY	3.63	DRY	3.63
3	PRODUCTION	6.75	5.0	NEW	API	N	0	16944	0	16944	-6999	-24211	16944	P-110	18	OTHER - BTC	2.52	2.66	DRY	4.03	DRY	4.03

Casing Attachments

Casing ID: 1 String Type: SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

COG_Littlefield_806H_Casing_Rpt_20180328143908.pdf

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Casing Attachments

Casing ID: 2 String Type: INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

COG_Littlefield_806H_Casing_Rpt_20180328143903.pdf

Casing Design Assumptions and Worksheet(s):

COG_Littlefield_806H_Casing_Rpt_20180328143850.pdf

Casing ID: 3 String Type: PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

COG_Littlefield_806H_Casing_Rpt_20180328143844.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	600	30	1.75	13.5	52	75	Class C	4% Gel + 1% CaCl2
SURFACE	Tail		0	600	250	1.34	14.8	335	75	Class C	2% CaCl2
INTERMEDIATE	Lead		0	1006 5	830	3.6	10.3	2988	50	Tuned Light Blend	As needed
INTERMEDIATE	Tail		0	1006 5	250	1.08	16.4	270	50	Tail: Class H	As needed
PRODUCTION	Lead		0	1694 4	40	2.5	11.9	100	35	50:50:10 H Blend	As needed

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
PRODUCTION	Tail		0	1694 4	900	1.24	14.4	1116	35	50:50:2 Class H Blend	As needed

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

Describe the mud monitoring system utilized: PVT/Pason/Visual Monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
600	1006 5	OTHER : Brine Diesel Emulsion	8.4	9							Brine Diesel Emulsion
0	600	OTHER : FW Gel	8.6	8.8							FW Gel
1006 5	1694 4	OIL-BASED MUD	9.6	11							OBM

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

None planned

List of open and cased hole logs run in the well:

CNL,GR

Coring operation description for the well:

None planned

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 5760

Anticipated Surface Pressure: 3361.78

Anticipated Bottom Hole Temperature(F): 160

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

COG_Littlefield_806H_H2S_SUP_20180328144202.pdf

COG_Littlefield_806H_H2S_Schem_20180328144210.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

COG_Littlefield_806H_Direct_Rpt_20180328144245.pdf

COG_Littlefield_806H_AC_20180328144236.pdf


Other proposed operations facets description:

Other proposed operations facets attachment:


COG_Littlefield_806H_Drilling_Rpt_20180328144227.pdf

Other Variance attachment:


3M Choke Manifold Equipment (WITH MGS + CLOSED LOOP)



5M Choke Manifold Equipment (WITH MGS + CLOSED LOOP)



3,000 psi BOP Schematic





POWERING PROGRESS™

MTR DATA BOOK

CUSTOMER: AUSTIN DISTRIBUTING

DATE: 11/20/2014

Purchase Order: PENDING

Sales Order #: 205663

Product Description: 10K3.566.0CK4.1/1610KFLGE/E L/E

Hose S/N: D-112014-10

CONTENTS INCLUDED

1	GMCO FITTINGS
	14-177-1 INSERT STEM
	14-245-1 INSERT HEAD
	14-242-1 FERRULE
2	EDWARDS FABRICATION LIFT EYE CLAMPS
	19351, 19356 Individual Test Certificates for Each Clamp
3	4 1/16 10K FLANGES
	R20834 Heat Numbers
4	WELDING SPECIFICATIONS
	Certification and Procedure for welding
5	NDE RESULTS
	1921 Ultrasonic Test Results and Imaging
6	TEST CHART
	Chart Recording of Hydrostatic Test
7	TEST CERTIFICATE
	Document Product Details & Positive Results of Hydrostatic Testing
8	CERTIFICATE OF CONFORMANCE
	A Declaration of the conformity with the type approval
9	IMAGES
	Images of the product prior to shipping.
10	PACKING LIST
	Details of Shipping Contents, Dimensions and Weights



PLYMOUTH TUBE CO. USA

672 W State Road 14, Winamac, Indiana 46988

Phone: (574) 948-3125 Fax-Cold Draw: (574) 948-3850 Fax-Hot Mill: (574) 948-7220

PRODUCT CERTIFICATION

SALES ORDER - LINE / RLS

119679 - 1 / 1

SOLD TO

J P Steel

6841 FM 362

Brookshire, TX 77423

USA

WORK ORDER 006409

HEAT NUMBER 486597

MELT SOURCE TMK IPSCO Koppel-USA Mfg/Melt

956 HXXX +64-15

14-177-1

ISO 9001: 2008

Registered

CUSTOMER P.O. 17554	CUSTOMER PART JP 3.562X.531	QUANTITY 9,736.34 Lb	LADING NO 00071757	CERT ID / REV 01	CERT DATE 06/18/2014								
PART DESCRIPTION EJ35620531DR1724-00 Spec: ASTM A-519 Seamless Mech. Alloy Smls Mechanical, HF [D/E] Smls Q&T Grade: 4130 OD: 3.5625" Tol+.0360" Tol-.0360" Wall: 0.5310" Tol+.0530" Tol-.0530" AW Lgth Type: Random Lgth: 17.00' / 24.00' End Finish: Debur ID & OD Finish Type: Quench & Temper L80/N80 Oil: Light Oil													
CERTIFICATION REQUIREMENTS ASTM A-519-06 / API 5CT Quench & Tempered. Induction heated, water quenched and infrared pyrometer monitored. Tensiles tested were 1" STRIP specimens per A370. Ultrasonic tested and passed. Tubes UT inspected to ASTM E213/API 5CT 10.15 and SR2 requirements w/ 5% notches. Test covered 100% full length of OD & ID surfaces both longitudinal & transverse.													
Chemical Analysis													
C .31	Mn .51	P .011	S .003	Si .27	Al .015	Cr .97	Mo .21	Ni .13	Pb -----	Cu .16	V .006	Ti -----	Sn .008
Cb .001	Ca .0017	N .0095	As .0039	Sb .0014	H -----								
Product Checks													
CHK01	C .317	Mn .52	P .012	S .005	Si .275	Al .016	Cr .96	Mo .211	Ni .123	Pb	Cu .148	V .0034	Ti
CHK02	.31	.52	.011	.0043	.275	.016	.96	.211	.123		.147	.0035	
CHK01	Sn .0091	Cb .000	Ca .0017	N .0000	As .0095	Sb .0000	H						
CHK02	.0091	.000	.0016	.0000	.0099	.0000							
Physical Properties													

I certify that the described material has been manufactured, inspected, and tested in accordance with the above specification(s) and satisfies the requirements.

David J. Paulin
Quality Assurance



PLYMOUTH TUBE CO. USA
 572 W State Road 14, Wlameac, Indiana 46896
 Phone: (674) 948-3125 Fax-Cold Draw: (674) 948-3850 Fax-Hot Mill: (674) 948-7220

PRODUCT CERTIFICATION

SALES ORDER - LINE / RLS

119679 - 1 / 1

SOLD TO

J P Steel
 6811 FM 362
 Brookshire, TX 77423
 USA

WORK ORDER 006409

HEAT NUMBER 486597

MELT SOURCE TMK IPSCO Koppel-USA Mfg/Melt

**ISO 9001: 2008
 Registered**

CUSTOMER P.O. 17554	CUSTOMER PART JP 3.562X.531	QUANTITY 9,736.34 Lb	LADING NO 00071757	CERT ID / REV 01	CERT DATE 06/18/2014																																																		
PART DESCRIPTION EJ35620531DR1724-00																																																							
<table border="1"> <tr> <td>Grain Size</td> <td>J1</td> <td>J2</td> <td>J3</td> <td>J4</td> <td>J5</td> <td>J6</td> <td>J7</td> <td>J8</td> <td>J9</td> <td>J10</td> <td>J11</td> <td>J12</td> <td>C</td> <td>R</td> <td>S</td> <td>AN</td> <td>AT</td> <td>BH</td> <td>BT</td> <td>CH</td> <td>CT</td> <td>DH</td> <td>DT</td> <td>SAM 'B'</td> </tr> <tr> <td>7</td> <td>50</td> <td>49</td> <td>48</td> <td>45</td> <td>42</td> <td>38</td> <td>35</td> <td>33</td> <td>33</td> <td>33</td> <td>33</td> <td>32</td> <td>--</td> <td>--</td> <td>--</td> <td>0.0</td> <td>0.5</td> <td>1.0</td> <td>1.0</td> <td>0.0</td> <td>0.0</td> <td>1.0</td> <td>1.5</td> <td>-----</td> </tr> </table>						Grain Size	J1	J2	J3	J4	J5	J6	J7	J8	J9	J10	J11	J12	C	R	S	AN	AT	BH	BT	CH	CT	DH	DT	SAM 'B'	7	50	49	48	45	42	38	35	33	33	33	33	32	--	--	--	0.0	0.5	1.0	1.0	0.0	0.0	1.0	1.5	-----
Grain Size	J1	J2	J3	J4	J5	J6	J7	J8	J9	J10	J11	J12	C	R	S	AN	AT	BH	BT	CH	CT	DH	DT	SAM 'B'																															
7	50	49	48	45	42	38	35	33	33	33	33	32	--	--	--	0.0	0.5	1.0	1.0	0.0	0.0	1.0	1.5	-----																															
<table border="1"> <tr> <td>SAM 'D'</td> <td>Freq.</td> <td>Severity</td> </tr> <tr> <td>-----</td> <td>.000</td> <td>.000</td> </tr> </table>						SAM 'D'	Freq.	Severity	-----	.000	.000																																												
SAM 'D'	Freq.	Severity																																																					
-----	.000	.000																																																					
Methods of Manufacturing																																																							
<table border="1"> <tr> <td>Method of Mfg 1</td> <td>Method of Mfg 2</td> <td>Method of Mfg 3</td> </tr> <tr> <td>Electric Arc Furnace Melted</td> <td>Aircraft Quality</td> <td>Continuous Cast</td> </tr> <tr> <td>Method of Mfg 4</td> <td>Method of Mfg 5</td> <td></td> </tr> <tr> <td>Mfg.Using Clean Steel Practice</td> <td>Ladle Refined</td> <td></td> </tr> </table>						Method of Mfg 1	Method of Mfg 2	Method of Mfg 3	Electric Arc Furnace Melted	Aircraft Quality	Continuous Cast	Method of Mfg 4	Method of Mfg 5		Mfg.Using Clean Steel Practice	Ladle Refined																																							
Method of Mfg 1	Method of Mfg 2	Method of Mfg 3																																																					
Electric Arc Furnace Melted	Aircraft Quality	Continuous Cast																																																					
Method of Mfg 4	Method of Mfg 5																																																						
Mfg.Using Clean Steel Practice	Ladle Refined																																																						
Mechanical Properties																																																							
<table border="1"> <tr> <td></td> <td>Rc-High</td> <td>Rc-Low</td> <td>Tensile</td> <td>Yield .2%</td> <td>Yield .5%</td> <td>Elong%</td> <td>Reduction</td> <td>Aust TempF</td> <td>Aust Time</td> <td>TemperTempF</td> </tr> <tr> <td>1</td> <td>20</td> <td>19</td> <td>107000</td> <td>91800</td> <td>91800</td> <td>28</td> <td>59</td> <td>1640</td> <td>6.17</td> <td>1315</td> </tr> <tr> <td></td> <td colspan="10">TemperTime</td> </tr> <tr> <td>1</td> <td colspan="10">79</td> </tr> </table>							Rc-High	Rc-Low	Tensile	Yield .2%	Yield .5%	Elong%	Reduction	Aust TempF	Aust Time	TemperTempF	1	20	19	107000	91800	91800	28	59	1640	6.17	1315		TemperTime										1	79															
	Rc-High	Rc-Low	Tensile	Yield .2%	Yield .5%	Elong%	Reduction	Aust TempF	Aust Time	TemperTempF																																													
1	20	19	107000	91800	91800	28	59	1640	6.17	1315																																													
	TemperTime																																																						
1	79																																																						
Charpy Impact Tests																																																							
<table border="1"> <tr> <td></td> <td>Temp 1</td> <td>Size 1</td> <td>Orient 1</td> <td>PtLb-Tl-Pc 1</td> <td>LExp-Tl-Pc 1</td> <td>%Shr-Tl-Pc 1</td> <td>PtLb-Tl-Pc 2</td> <td>LExp-Tl-Pc 2</td> </tr> <tr> <td>1</td> <td>-30C</td> <td>10X10</td> <td>Long</td> <td>126</td> <td>.073</td> <td>100</td> <td>128</td> <td>.068</td> </tr> <tr> <td></td> <td colspan="8">%Shr-Tl-Pc 2 PtLb-Tl-Pc 3 LExp-Tl-Pc 3 %Shr-Tl-Pc 3</td> </tr> <tr> <td>1</td> <td colspan="8">100 125 .073 100</td> </tr> </table>							Temp 1	Size 1	Orient 1	PtLb-Tl-Pc 1	LExp-Tl-Pc 1	%Shr-Tl-Pc 1	PtLb-Tl-Pc 2	LExp-Tl-Pc 2	1	-30C	10X10	Long	126	.073	100	128	.068		%Shr-Tl-Pc 2 PtLb-Tl-Pc 3 LExp-Tl-Pc 3 %Shr-Tl-Pc 3								1	100 125 .073 100																					
	Temp 1	Size 1	Orient 1	PtLb-Tl-Pc 1	LExp-Tl-Pc 1	%Shr-Tl-Pc 1	PtLb-Tl-Pc 2	LExp-Tl-Pc 2																																															
1	-30C	10X10	Long	126	.073	100	128	.068																																															
	%Shr-Tl-Pc 2 PtLb-Tl-Pc 3 LExp-Tl-Pc 3 %Shr-Tl-Pc 3																																																						
1	100 125 .073 100																																																						
This test report data is for the heat Chemistry Stated above. The material in this test report is: 1) Manufactured in the USA. 2) Free from Polybrominated Biphenyls (PBB), Polybrominated Diphenyl Ethers (PBDE), and Mercury contamination.																																																							

I certify that the described material has been manufactured, inspected, and tested in accordance with the above specification(s) and satisfies the requirements.

David J. Jenkins
 Quality Assurance



PLYMOUTH TUBE CO. USA

572 W State Road 14, Winamac, Indiana 46986

Phone: (574) 848-3125 Fax-Cold Draw: (574) 848-3850 Fax-Hot Mill: (574) 848-7220

PRODUCT CERTIFICATION

SALES ORDER - LINE / RLS

119679 - 1 / 1

SOLD TO

J P Steel
6811 FM 362
Brookshire, TX 77423
USA

WORK ORDER 006409

HEAT NUMBER 486597

MELT SOURCE TMK IPSCO Koppel-USA Mfg/Melt

**ISO 9001: 2008
Registered**

CUSTOMER P.O.	CUSTOMER PART	QUANTITY	LADING NO	CERT ID / REV	CERT DATE
17554	JP 3.562X.531	9,736.34 Lb	00071757	01	06/18/2014
PART DESCRIPTION EJ35620531DR1724-00					
3) No Repairs by welding					
End of Certification					

I certify that the described material has been manufactured, inspected, and tested in accordance with the above specification(s) and satisfies the requirements.


Quality Assurance

AKZ = Achromatopsiezeichnung, Eching ink marking, Gravure à l'encre, FK = Farbschabzeichnung, colour marking, marquage par couleur, PS = Farbabschabzeichnung, parti standing, marquage à la peinture, FSD = Farbschabdruck, Colour jet printer, traitement à jet d'encre de couleur, UK = Lasermarkzeichnung, Laser marking, Marquage laser, PEK = Etikettenmarkzeichnung, tag marking, marquage sur étiquette, PS = Prägenamel, die stamp, marquage par poinçonnage, TS = Tintenstrahlzeicheneinführung, ink jet spray marking, traitement à jet d'encre

Benteler Steel/Tube GmbH
Postfach 13 40
33043 Paderborn
Deutschland
Tel.: +49.5254.81-0 Fax: +49.5254.13888

Ersetzt / replace

Dok. Nr. / Doc. No. 65-716081/001/E vom / dated 26.09.2012

BENTELER 
Steel/Tube

ABNAHMEPRÜFZEUGNIS EN 10204-3.1
INSPECTION CERTIFICATE EN 10204-3.1
CERTIFICAT DE RECEPTION EN 10204-3.1

Dokument-Nr.: 65-716081/002/P
Document No.:
No. du document:

Prüf-Nr.:
Inspection No.:
No. du certificat:

Blatt: 2 / 4
Page:
Page:

Pos.	Stück	Maße	Länge	Gewicht	Schmelzen-Nr.	Prüfdruck	Rohr-Nr.-Gruppe	Vielfachlängen
Item	Number	Dimensions	Length	Weight	Heat No.	Test pressure	Tube number group	Multiple lengths
Poste	Nombre	Dimensions	Longueur	Poids	No. de coulée	Pression d'épreuve	Série de no. des tubes	Longueurs multiples
			feet	lbs				
0002	34	4.500" O.D. * 0.625" 17 FT - 24 FT	748,36	19326	573599			

Schmelzenanalyse [%] / Heat analysis [%] / Analyse sur coulée [%]

Pos.	Schmelzen-Nr.	C	SI	MN	P	S	CR	MO	NI
Item	Heat No.								
Poste	No. de coulée								
0002	573599	0,310	0,220	0,53	0,007	0,002	0,89	0,17	0,09

Prüfergebnisse / Test results / Résultats des essais

Die Rohre wurden zerstörungsfrei geprüft: The tubes are non destructive tested: Les tubes ont passé un essai non destructif:	UT-long.imperfections: acc. to API 5CT, SR 2; UT-long. Test method: acc. to ASTM-E 213; Outside notch depth: 5,0 %; Inside notch depth: 5,0 %; UT-transv. imperfections: acc. to API 5CT, SR2; acc. to ASTM-E 213; Outside notch depth: 5,0 %; Inside notch depth: 5,0 %; UT-lamination detection: acc. to EN 10246-14, table 1	PASSED
Augensichtkontrolle: Visual inspection: Examen visuel:	MATERIALVERWECHSLUNGSPRÜFUNG: Material conformity test: Vérification de la nuance:	PASSED
	MAßKONTROLLE: Dimensions examination: Vérification des dimensions:	PASSED

Ergebnisse der mechanischen Prüfung / Results of mechanical testing / Résultats des essais mécaniques

Die Probennahme erfolgte an Vielfachlängen.
The sampling was carried out on multiple lengths.
L'échantillonnage était réalisé aux longueurs multiples.

Benteler Steel/Tube GmbH
Postfach 13 40
33043 Paderborn
Deutschland
Tel.: +49.5254.81-0 Fax: +49.5254.13866

Ersetzt / replace

Dok. Nr. / Doc. No. 65-716081/001/E vom / dated 26.09.2012

BENTELER
Steel/Tube

ABNAHMEPRÜFZEUGNIS EN 10204-3.1
INSPECTION CERTIFICATE EN 10204-3.1
CERTIFICAT DE RECEPTION EN 10204-3.1

Dokument-Nr.: 65-716081/002/P
Document No.:
No. du document:

Prüf-Nr.:
Inspection No.:
No. du certificat:

Blatt: 3 / 4
Page:
Page:

Zugversuch längs Streifenprobe / Tensile test longitudinal Strip test specimen / Essai de traction longitudinale Bande decoupee sur tube

Pos. Item Poste	Proben-Nr. Specimen No. No. de l'éprouvette	Schmelzen-Nr. Heat No. No. de coulée	Probenabmessung Specimen dimensions Dimensions de l'éprouv.	Streckgrenze Yield strength Limite élastique	Zugfestigkeit Tensile strength Résistance à la traction	Dehnung Elongation Allongement	Einschnürung Area reduction Coefficient de striction
Anforderungen Requirements Exigences			mm	RT 0,5 % MPa 552-656	Rm MPa MIN 655	A2" % MIN 14	1. Formel 1. Formula 1. Formule
0002	000001	573599	25,40 X 15,40	637	758	36	
0002	000002	573599	25,40 X 15,70	635	769	36	

Härteprüfung / Hardness test / Essai de dureté

Pos. Item Poste	Proben-Nr. Specimen No. No. de l'éprouv.	Schmelzen-Nr. Heat No. No. de coulée	Härte Hardness Dureté
Anforderungen Requirements Exigences			HRC HB HV HRB HBW MAX 22.0
0002	000001	573599	020

Kerbschlagbiegeversuch Notched bar impact test / Essai de flexion par choc (résilience) [1 CHARPY_V]

Pos. Item Poste	Proben-Nr. Specimen No. No. de l'éprouv.	Schmelzen-Nr. Heat No. No. de coulée	Probenabmessung Specimen dimensions Dimensions de l'éprouv.	Probenlage Specimen position Position de l'éprouvette	Prüftemperatur Test temperature Température d'essai	Kerbschlagarbeit Absorbed energy Energie absorbée	Kerbschlagzähigkeit Impact strength Résistance au choc	Verf.-Bruchanteil Shear fracture Rupture ductile
Anforderungen Requirements Exigences			Länge Breite Höhe Length Width Height Longueur Largeur Hauteur	längs (L) longitudinal (L) longitudinal (L)		einzel mittel single average individuelle moyenne	einzel mittel single average individuelle moyenne	
			mm mm mm	quer (Q) transversal (Q) transversal (Q)	GRAD °C -30	ft-lbf ft-lbf MIN 020	J/cm²	
0002	000001	573599	55 10,00 10,00	L	-30	116 110 111	112	

Benteler Steel/Tube GmbH
Postfach 13 40
33043 Paderborn
Deutschland
Tel.: +49.5254.81-0 Fax: +49.5254.13666

Ersetzt / replace

Dok. Nr. / Doc. No. 65-716081/001/E vom / dated 26.09.2012

BENTELER 

Steel/Tube

ABNAHMEPRÜFZEUGNIS EN 10204-3.1

INSPECTION CERTIFICATE EN 10204-3.1
CERTIFICAT DE RECEPTION EN 10204-3.1

Dokument-Nr.:

Document No.:
No. du document:

65-716081/002/P

Prüf-Nr.:

Inspection No.:
No. du certificat:

Blatt: 4 / 4

Page:
Page:

Wärmebehandlung / Heat treatment / Traitement thermique

Hardening temperature: 850°C, Holding time: 1 min, Cooling: water / Tempering temperature: 735°C, Holding time: 6 min, Cooling: air

Vermerk / Remark / Remarque

Certificate remarks: Steel is manufactured to fine grain practice. The tubes comply with the requirements of NACE MR0175-03., hardness max. 22 HRC. No mercury, mercury compounds or mercury bearing instruments and / or equipment has been used in any manner which might cause contamination in manufacture assembly, or test of material. No weld repair has been carried out.:
Certificate-Remark: The steel will be produced by an electric arc furnace, ladle furnace and continuous casting machine, stirring by argon. The mode of operation in this process is commonly referred to as "clean steel process". The products are fully killed.

Verkäufer(in) / Salesman/ woman in charge / Personne chargée : Mr Storm, Tel.: 05254/81-4274, Fax: 4289

Dinslaken, 26.10.2012, TEL.: 02064.623-5370 FAX: 02064.623-5390

Abnahmebeauftragter

Inspection representative

Contrôleur

DR. BASEL KEITA / Thei

Es wird bestätigt, daß die gelieferten Erzeugnisse den techn. Lieferbedingungen des Auftrages entsprechen. Dieses Dokument wurde mittels EDV erstellt und ist ohne Unterschrift rechtsgültig.
We certify that the supplied products comply with the order specification. This document was prepared by means of electronic data processing and is valid without signature.
Nous attestons que les produits livrés sont conformes aux stipulations de la commande. Ce document a été établi par traitement électronique de l'information et est valide sans signature.

P.O. BOX 924469
HOUSTON, TX 77292
PHONE: (713) 290-8490



6645 W. TIDWELL
HOUSTON, TX 77092
FAX: (713) 290-8627

To: J.P. STEEL, LLC
PO BOX 592
KATY, TX 77492-0592

Report Date: 10/18/13
Report No: 250944.0
Rev.: A
Cust Acct: JPS10050

PO#: 15484
Material: 4.50" OD X .625" WALL 4130 Q & T ALLOY
ID/Heat: HT# 573599
Job Info:

Tensile Test Results

No./Location	Size (in.)	Area (in ²)	Ult. Load (lbs.)	Yield (psi)	Tensile (psi)	Elong. (%)	R. of A. (%)	Hardness
1	.495	.1924		90,200	112,300	26	73	

Unless otherwise stated, yield stress is 0.2% offset, gage length is 2 in. for 1/2 in. bars or 1 in. for 1/4 in. bars.

Signed: _____

MIKE MASON

Our reports are for the exclusive use of our customer and our name may be used only with prior written approval. Our reports apply only to the sample tested or inspected and do not necessarily represent the quality of other apparently similar or identical materials. All test specimens and testing conforms to ASTM A-370 requirements unless otherwise stated. This test report shall not be reproduced, except in full, without the written approval of P&B Testing Inc.



ARCELORMITTAL TUBULAR PRODUCTS
SHELBY LLC.
132 WEST MAIN STREET
SHELBY, OHIO 44875-1471
Telephone 419/342-1200 FAX: 419/342-1437

**MATERIAL
TEST
REPORT**

ISO/TS 16949:2009 ISO 9001:2008

14-242-1 956444464A-F

SHELBY ORDER NO.
447180

C U S T O M E R	MARMON KEYSTONE CORPORATION 6441 BINGLE ROAD HOUSTON TX 77092 ATTN: EARTHA JILES				SPECIFICATION ASTM A513 GMCO A513 DOM 1 01-10 FAX: (713)460-5414				CUSTOMER ORDER 35-057810-03			
--------------------------------------	---	--	--	--	--	--	--	--	--------------------------------	--	--	--

GRADE 520	SIZE(O.D x ID x WALL) 7.250 X 6.000 X .625	QUANTITY 17509 LB	396.00 FT	SHIPPED 09/02/14	DATE 09/02/14
--------------	---	----------------------	-----------	---------------------	------------------

CONDITION ASTM 513 Type 5 Produced to OD/ID Ref: WALL EW TUFFDOM STRESS RELIEVE ANNEAL	PART NO. REV.	S#00335344 50064541
--	------------------	------------------------

HEAT NO. 4131797	CHEMICAL ANALYSIS												GRAIN SIZE
	C	Mn	P	S	Si	Ni	Cr	Mo	Cu	V	Al	OTHER	
	.16	1.41	.012	.003	.220	.010	.040	.010	.040	.002	.040	.0030 CA TI .0010 Cb .0020	

MECHANICAL PROPERTIES										MAGNAFLUX	
HEAT NO.	LOAD NO.	YIELD PSI	TENSILE PSI	ELONG %	RED AREA %	HARDNESS BHN ROCKWELL		IMPACT FT.-LBS SIZE TEMP C -20-30 RESULTS	FREQ.	SEVERITY	
4131797	T6457128	76900	89400	2.0" 33			RB 92	10.0X10.0 128 57 140 68 133 65			

JOMINY HARDENABILITY (EXPRESSED IN 16THS)																
HEAT NO.	1	2	3	4	5	6	7	8	10	12	14	16	20	24	28	32

J-K RATING				SLAG-OXIDE RATING			
HEAT NO.	A	B	C	D	INGOT	OXIDE	SLAG

MELT SOURCE	OTHER INSPECTION	THIS TEST REPORT NOTARIZED WHEN REQUIRED SWORN AND SUBSCRIBED BEFORE ME THIS _____ DAY OF _____
-------------	------------------	---

Material under this mtr was not exposed to mercury during processing.

NOTARY PUBLIC
Frank Simeone



Edwards Fabrication, Inc.

1385 Hwy. 35 Bypass S. O: (361) 790-7910
P.O. Box 2350 F: (361) 790-7927
Rockport, TX 78381

tedwards@edwardsfabrication.com
www.edwardsfabrication.com

CERTIFICATE OF TEST

Client:
Gates E & S North America
134 44th Street
Corpus Christi, TX 78405

Purchase Order: 16522

Certificate Number			Date of Examination	
19351			09/11/14	
ID#	Part Number	Description	SWL*	Proofload
19351	7361-0864	4.0" Lift-Eye Clamp 2 Bolt	4205 lbs.	8410 lbs.
DO NOT WELD, CUT, ADD-TO, TAKE AWAY ANY COMPONENTS OR MAKE ANY MODIFICATION TO THIS CLAMP UNIT. Doing so voids this test certificate.				
* Safe Work Load				

THIS PRODUCT IS MANUFACTURED IN THE U.S.A.

We hereby verify that the above information is correct
as contained in the records of Edwards Fabrication L.L.C.

Michael White
Test Operator



Thomas F. Edwards
President
Edwards Fabrication L.L.C.



Edwards Fabrication, L.L.C.

1385 Hwy. 35 Bypass S. O: (361) 790-7910
P.O. Box 2350 F: (361) 790-7927
Rockport, TX 78381

tedwards@edwardsfabrication.com
www.edwardsfabrication.com

CERTIFICATE OF TEST

Client:
Gates E & S North America
134 44th Street
Corpus Christi, TX 78405

Purchase Order: 16522

Certificate Number				Date of Examination			
19356				09/11/14			
ID#	Part Number	Description	SWL*	Proofload			
19356	7361-0864	4.0" Lift-Eye Clamp 2 Bolt	4208 lbs.	8416 lbs.			
DO NOT WELD, CUT, ADD-TO, TAKE AWAY ANY COMPONENTS OR MAKE ANY MODIFICATION TO THIS CLAMP UNIT. Doing so voids this test certificate.							
* Safe Work Load							

THIS PRODUCT IS MANUFACTURED IN THE U.S.A.

We hereby verify that the above information is correct
as contained in the records of Edwards Fabrication L.L.C.

Michael White
Test Operator



Thomas F. Edwards
President
Edwards Fabrication L.L.C.

API Monogram Licensee
ISO 9001-2008 Certified
PED 97/23/EC
AD 2000-Merkblatt W0



MARS FORGE PVT. LTD.

Rajkot Gondal Nh. 8-B, Village : Shapar - 360024 Dist. Rajkot (Guj.) India.
Tel. No. : 91 - 2827 - 252190, 252191, Fax No. : 91 - 2827 - 252119
E-mail : info@marsforge.com, Web. : www.marsforge.com

MATERIAL TEST REPORT

The certificate of Material as per EN 10204 3.1

Customer : R & S OILFILED INC.USA

Doc.No.F-P-21-12/

TC Ref No : 21/KJ2014-20

DATE 25.08.2014	Purchase Order Ref.No. : 520 Dated 31.07.2014	Invoice No. : 21	MF Drawing No. : MF 0294-01F
Chemical Analysis Ref: 54/270714	Physical Analysis Ref MFT-644, MFI-147	Test Certificate Ref 025396	Mode of Shipping : SEA
Quantity : 27 PCS	Part Description: Weld Neck Flange, 4-1/16" 10M x 4" SCH XXH AISI 4130 N.Q.T	PSL LEVEL 2	Raw Material Spec No MARS 6A -001 REV.03
Heat Code Punch : R 20834	R & S Part Number : RSMFW410X...		Melting Practice : EAF→LRF→VD→CCM
Heat Number: R 20834	Grade/Condition: SAE4130	Reduction Ratio: Raw Material Reduction Ratio : 1:3.02	

CHEMICAL ANALYSIS RESULTS

Elements	C.	Mn.	Si.	Cr.	Ni.	Mo.	S.	P.	V.	Cu.
Minimum %	0.28	0.40	0.15	0.80	---	0.15	---	---	---	---
Maximum %	0.33	0.60	0.35	1.10	0.25	0.25	0.025	0.025	0.10	---
Heat Analysis %	0.32	0.55	0.19	1.07	0.21	0.22	0.005	0.008	0.003	0.30

MECHANICAL PROPERTIES(QTC SIZE: 4"x 4")

(ASTM A 370)	Requirement	Actual
0.2% Yield Strength (PSI)	75,000 PSI MIN	78798 PSI
Tensile Strength (PSI)	95,000 PSI MIN	104814 PSI
% Elongation	18.0% MIN	25.20%
% Reduction Of Area	35.0% MIN	70.30%
Hardness (HBW)	207-235 HBW	207 TO 229 HBW

CHARPY IMPACT PROPERTIES

Size	10 x 10 x 55mm	DIRN	L
Impact	20 Ft-Lbs Min @ -75° F		
Energy (ft-lbs)	51.63	57.53	50.15
Average	53.10 Ft Lbs		
L.E. (Inch)	0.026	0.029	0.024

HEAT TREATMENT

CYCLE	TEMPERATURE(C)	TEMPERATURE (F)	TIME@TEMP	QUENCH MEDIA
Normalized	910 °C	1670 °F	150 Minutes	AIR COOLED
Austenitized	880 °C	1616 °F	150 Minutes	WATER QUENCHED
Tempered	695 °C	1283 °F	150 Minutes	AIR COOLED

Water Temperature IN AT 35°C AND OUT AT 45°C


NON DESTRUCTIVE EXAM (NDE)

	Yes/No	Spec Number
Ultrasonic Testing (UT)	NO	---
Magnetic Particle Inspection (MPI)	YES	---

*Country of origin - India

ASME Section-V,Article -7

* We hereby declare that the material herein described is in accordance with specifications of the order.



API Monogram Licensee
ISO 9001-2008 Certified
PED 97/23/EC
AD 2000-Merkblatt W0



MARS FORGE PVT. LTD.

Rajkot Gondal Nh. 8-B, Village : Shapar - 360024 Dist. Rajkot (Guj.) India.
Tel. No. : 91 - 2827 - 252190, 252191, Fax No. : 91 - 2827 - 252119
E-mail : info@marsforge.com, Web. : www.marsforge.com

Doc No : F-P-21-17

MAGNETIC PARTICLE EXAMINATION REPORT

PART No.	: RSMFW410X	DATE	: 25.08.2014
PART NAME	: Weld Neck Flange, 4-1/16" 10M X 4" SCH XXH AISI	INSPECTOR/LEVEL	: ASNT L-II
HEAT NO	: 4130 N.Q.T	QUANTITY	: 27 PCS
PROC No	: R 20834	REJECT	: None
W-21-09			
ACCEPT	: W-P-21-09		
WO/PO No.	: Acceptable		
	: R&S PO#520 Dated 31.07.2014		

TEST PROCEDURE

EQUIPMENT	: "Magnafield "Make , Electromagnetic Crack Detector
DETECTING MEDIA	: Fluorescent Powder
METHOD	: Wet fluorescent method
CURRENT APPLY	: H.W.D.C./A.C. Current used
LOCATION	: Cover 100% (Assessable) area of the job
MAGNETIZATION	: Longitudinal
TYPE OF MAGNETIZATION	: Continuous
EXAMINATION	: Surface & sub surface defect.
REFERENCE STANDARD	: ASME Section V, Article 7, SE709
TESTED BY	: HITESH MAHETA
DATE OF TEST	: 02.08.2014

OBSERVATION : No relevant indication found

RESULT : Jobs are found satisfactory in MPT.

For, MARS FORGE PVT. LTD.





ISO 9001 : 2008

PED 97/23/EC

AD 2000-Merkblatt WO

**MARS FORGE PVT. LTD.**

"Shraddha House" M-170, Gujarat Housing Board
Akshar Marg, Rajkot - 360 001. Gujarat (India)
Tel. No. : 91 - 281 - 244 83 83, 247 90 88, Fax : 91- 281 - 245533

Works : Rajkot Gondal Nh. 8-B, Village : Shapar, Dist. Rajkot (Guj.) Ind
Tel. No. : 91 - 2827 - 252190, 252191, Fax No. : 91 - 2827 - 2521
E-mail : info@marsforge.com, Web. : www.marsforge.com

TEST CERTIFICATE

TC Ref : 12/A/2011-2012

Date : 27-05-2012

Our Drawing No.	: MF 0285 P1
Heat No. Code	: R 15965
Quantity	: 159 Nos.
Sample Qty.	: 01 Nos.
Chemical Analysis Ref.	: 111/07052012
Physical Analysis Ref.	: AI-277
Test Certificate Ref.	: 1111

Customer : R & S OILFIELD INC. HOUSTON - USA.	
Customer's Part No.	: 4 - 1500 WN
Purchase Order Ref.	: 172 / Dt.19-03-2012
Delivery Challan No.	: 12/ DT : 27.05.2011
Vehicle No.	: BY SEA

CHEMICAL ANALYSIS RESULTS :


Material	Heat No.	C.	Mn.	Si.	Cr.	Ni.	Mo.	S.	P.	V.
Specified A350 LF2	SPECN.	---	0.60	0.10	---	---	---	---	---	---
		0.35	1.05	0.35	0.30	0.40	0.12	0.050	0.040	0.08
Actual	R 15965	0.20	0.93	0.20	0.058	0.076	0.021	0.008	0.009	0.002

Hardness Reqd. Range	Hardness Actual	ASTM Grain Size	Heat Treatment	Jominy Value	INCLUSION RATING			
					A	B	C	D
187 BHN MAX.	143 - 174 BHN	6-7	Normalised	---	<u>1.0</u> 0.5	<u>0.5</u> ---	---	<u>1.0</u> ---

* NORMALISED AT 930° C, SOAK FOR 120 MINUTES, AIR COOL.

PHYSICAL TEST RESULTS :

Heat Code On Forgings	Yield PSI.	UTS PSI.	%E	%RA.	Impact (dirn. - L, Size- 10x10x55 mm) 27 Joules min. at -50° F			
---	45000	70000	22.00	30.00	I	II	III	Avg.
PUNCH R 15965	50235	76393	33.80	67.10	67 1.40	65 2.30	63 1.31	65.16 J.



[Signature]
QUALITY CONTROL





MORRIS INSPECTIONS

Mailing Address:
2316 Memorial Pkwy.
Portland, TX 78374-3206

Business Telephone:
(361) 643-7066
Cellular Telephone:
(361) 877-0776

**QW-484 SUGGESTED FORMAT FOR MANUFACTURER'S RECORD OF WELDER
OR WELDING OPERATOR QUALIFICATION TESTS**
(See QW-301, Section IX, ASME Boiler and Pressure Vessel Code)

Welder's Name	<u>JEFFREY CHARLES TOWNSEND</u>		S. & No.	
Welding Process(es)	<u>Shielded Metal Arc Welding</u>	Type	<u>Manual</u>	Position (QW-405.1)
Welding Procedure Specification No.	<u>SM-4130</u>	PQR No.	<u>SM-4130</u>	Backing (QW-402.7)
Material Spec. (QW-403) No.	<u>HF-4130</u>	Grade	<u>LN80</u>	P-No. <u>-</u> Group <u>-</u>
To				
Material Spec (QW403) No.	<u>HF-4130</u>	Grade	<u>LN80</u>	P-No. <u>-</u> Group <u>-</u>
Test Thickness	<u>.531"</u>	Range	<u>Up to 1.062"</u>	Test Dia. <u>4.00"</u> Range <u>2 7/8" O.D. over</u>
Process(es)	<u>SMAW</u>		<u>SMAW</u>	
Filler Metal (QW-404) Spec.	SFA <u>5.1</u>	SFA <u>5.5</u>	SFA <u>5.5</u>	
	Class No. <u>E-6010</u>	Class No. <u>E-8018</u>	Class No. <u>E-8018</u>	
	F No. <u>3</u> A No. <u>1</u>	F No. <u>4</u> A No. <u>3</u>	F No. <u>4</u> A No. <u>3</u>	
Filler Diameter (QW-404.6)	<u>1/8"</u>	<u>5/32"</u>	<u>5/32"</u>	
Weld Deposit Thickness	<u>.125"</u>	<u>.406"</u>	<u>.406"</u>	
Consumable Insert (QW-404.22)	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	
Gas (QW-408) Shielding	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	
Flow Rate	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	
Gas (QW-408) Purge	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	
Flow Rate	<u>N/A</u>	<u>N/A</u>	<u>N/A</u>	
Elec. (QW-409) AC-DC	<u>Direct</u>	<u>Direct</u>	<u>Direct</u>	
Polarity	<u>Reverse</u>	<u>Reverse</u>	<u>Reverse</u>	
Volt Range	<u>22-26</u>	<u>23-27</u>	<u>23-27</u>	
Amp Range	<u>80-120</u>	<u>150-210</u>	<u>150-210</u>	
Progression (QW-405.3)	Root <u>Up</u>	Hot Pass <u>Up</u>	Filter <u>Up</u>	Cap. <u>Up</u>
Transfer Mode (QW-409.2) GMAW	<u>N/A</u>			
Other		Preheat	<u>700 E.</u>	PWHT. <u>N/A</u>

For Information Only
Material 4130 IS NOT listed in ASME Section IX
but acceptable.

Submerged Arc Flux Trade Name

Guided Bend Test Results (QW-482.2(a), QW-482.3(a), QW-482.3(b))

Specimen No.	Type	Figure No.	Results	Specimen No.	Type	Figure No.	Results

Radiographic Test Results (QW-304 & QW-305)

For alternative qualification of groove welds by radiography

Radiographic Results: Satisfactory

Test Conducted by J. Morris - MORRIS INSPECTIONS

Laboratory—Test No. 09-019

We certify that the statements in this record are correct and that the test welds prepared, welded and tested in accordance with the requirements of Section IX of the ASME Code.

Joe Morris

Organization

DU-TEX, INC.

Date March 23, 2009

By

(Details of record of tests are illustrative only and may be modified to conform to the type and number of test required by the Code.)

NOTE: Any essential variables in addition to those above shall be recorded. This form modified for information and typing purposes. (QW-301.4)



MORRIS INSPECTIONS

Mailing Address:

2316 Memorial Pkwy.

Portland, TX 78374-3206

Business Telephone

(361) 643-7066


Cellular Telephone

(361) 877-0776

QW-483 SUGGESTED FORMAT FOR PROCEDURE QUALIFICATION RECORD (PQR) (See QW-201.2, Section IX, ASME Boiler and Pressure Vessel Code)

Company Name DU-TEX, INC.
 Procedure Qualification Record No. SM-4130 Date March 24, 2009
 WPS No. SM-4130 Transfer Mode GMAW N/A
 Welding Process(es) Shielded Metal Arc Welding
 Types (Manual, Automatic, Semi-Auto.) Manual

JOINTS (QW-402)



BASE METALS (QW-403)

Material Spec. HF-4130 To HF-4130
 Type or Grade LN 80 To LN 80
 P-No. - Grp. - to P-No. - Grp. -
 Thickness Tested .750" Range: .1875" - 1.500"
 Diameter Tested 4.500" Range: Proc. unlimited
 No Pass Greater than 1/2" in thickness No
 Backing: Yes No XX Material Weld Metal only
 Other Material 4130 IS NOT listed in ASME Section IX

FILLER METALS (QW404)

Process(es) SAW SAW
 Weld Metal Analysis A-No. 1 3
 Weld Bead Number 1 & 2 Balance
 Dia of Electrode 1/8" 5/32"
 Filler Metal F-No. 3 4
 SFA Specification 5.1 5.5
 AWS Classification E-6010 E-8018
 Weld Deposit Range .250" 1.250"
 Weld Deposit Thickness .125" .625"
 Tungsten: Size N/A Type: - Class: -
 Flux Trade Name: N/A Designation: -
 Other -

POSTWELD HEAT TREATMENT (QW-407)

Temperature None applied
 Time -
 Other -

GAS (QW-408)

Process(es) SAW-N/A
 Shielding -
 Flow Rate -
 Purge -
 Flow Rate -
 Other -

ELECTRICAL CHARACTERISTICS (QW-409)

Process(es) SAW SAW
 Current Direct Direct
 Polarity Reverse Reverse
 Volts Range 22-26 23-27
 AMPS Range 80-120 150-210
 Other -

POSITION (QW-405)

Position of Test Groove 6-G
 Weld Progression (Up, Down, Flat)
 Root Up Hot Pass Up Filler Up Cap Up

PREHEAT (QW-406)

Preheat Temp. 700 F.
 Interpass Temp. Min. - Max. -
 Other -

TECHNIQUE (QW-410)

Process(es) SAW SAW
 Travel Speed Variable Variable
 String or Weave Bead String String
 Oscillation None None
 Multi or Single Pass (per side) Multiple Multiple
 Single or Multi Electrodes Single Single
 Peening None None
 Other -

QW-483 (Back)

Tensile Test (QW-150)

NOTE: MATERIAL SPECS

Electrode Tensile Strength is 80,000 PSI

Specimen No.	Width	Thickness	Area	Ultimate Total Load lbs.	Ultimate Unit Stress psi	Character of Failure & Location
T - 1	.751"	.743"	.558"	45,000	80,645	Satisfactory-Broke in Weld Area
T - 2	.748"	.748"	.554"	44,400	80,144	Satisfactory-Broke in Weld Area

Guided Bend Test (QW-160)

Specimen No.	Type	Figure No.	Results	Specimen No.	Type	Figure	Results
6G - SB1	SBend	QW462.2	Satisfactory				
6G - SB2	SBend	QW462.2	Satisfactory				
6G - SB3	SBend	QW462.2	Satisfactory				
6G - SB4	SBend	QW462.2	Satisfactory				

Toughness Tests (QW-170)

Specimen No.	Notch Location	Specimen Size	Test Temp.	Impact Values	Lateral Exp.		Drop Weight	
					% Shear	Mils	Break	No Break

Average ft/lb for this size _____

Minimum ft/lb for this size _____

Fillet Weld Test (QW-180)

Pos.	Spec. No.	Contour	Leg No. 1	Leg No. 2	Throat	Bend Defects	Macro-Pent.	Results

Other Tests

Type of Test _____

Deposit Analysis _____

Other _____

Welder's Name Jeffrey Charles Townsend S.S.# _____ Stamp No. N/ATest conducted by: J. Morris-MORRIS INSPECTIONS Laboratory Test No. 09-022

We certify that the statements in this record are correct and that the test welds were prepared, welded and tested in accordance with the requirements of Section IX of the ASME Code.

Date March 25, 2009 By Joe Morris Manufacturer DU-TEX, INC.

Details of record of tests are illustrative only and may be modified to conform to the type and number of tests required by the Code. This form modified for information and typing purposes (QW200.2(D))

Non-Destructive Testing Report

06972

Customer: Gates

Date: 11/20/14

Project: 192114

Ultrasonic ☒
Magnetic Particle ☐
Liquid Penetrant ☐

Section # Level

NRS-PA-VT/2013/R-00
ASME
P

Shear wave	☒	Angle	
Straight Beam	☒	60	☒
Unit Type	Ref Beam	70	☒
Ref Standard	T.D./R	45	☒
Range	5"	0	☒

60 ✓

70 ✓

45 ↗

0 ✓

AC _____

Wet _____

Continuous

Residual

Background

DC _____

Dry _____

Dwell Time _____

Penetrant # _____

Developer # _____

Cleaner # _____

1998, 1999, 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665, 2666, 2667, 2668, 2669, 2670, 2671, 2672, 2673, 2674, 2675, 2676, 2677, 2678, 2679, 26

[illegible]

Inspector: Joe Kalders

SNT Level ~~77A~~

PG # of


Customer Representative:

Hours 2 Mileage

PO BOX 23036 CORPUS CHRISTI, TEXAS 78403

PHONE # 361-533-4563 / FAX # 361-884-1984 / E-MAIL emanahan@nqsltd.com (Eric) / Iray@nqsltd.com (Bud)

The image shows a circular flow chart from Chart Pool USA Inc., located at Bridge Portage, Indiana. The chart features concentric circles representing different scales for various engineering parameters. The outermost scale is labeled 'TEST DATE' and ranges from 0 to 30. Moving inward, the next scale is 'GRADE' (ranging from 0 to 20), followed by 'TEST PRESSURE' (ranging from 0 to 18,000). The innermost scale is 'WORKING PRESSURE' (ranging from 0 to 10,000). A central circle contains the company logo and name. Handwritten annotations include 'END 14-11-16', 'END 14-11-16', 'END 14-11-16', and 'END 14-11-16'. There are also handwritten numbers like '7330', '8000', '10000', '12000', '14000', and '16000' along the scales.



GATES E & S NORTH AMERICA, INC.
134 44TH STREET
CORPUS CHRISTI, TEXAS 78405

PHONE: 361-887-9807
FAX: 361-887-0812
EMAIL: Tim.Cantu@gates.com
WEB: www.gates.com

10K CHOKE AND KILL ASSEMBLY PRESSURE TEST CERTIFICATE

Customer :	AUSTIN DISTRIBUTING	Test Date:	11/20/2014
Customer Ref. :	PENDING	Hose Serial No.:	D-112014-10
Invoice No. :	205663	Created By:	NORMA MATA
Product Description:	10K3.566.0CK4.1/1610KFLGE/E L/E		
End Fitting 1 :	4 1/16 10K FLG	End Fitting 2 :	4 1/16 10K FLG
Gates Part No. :	4773-6291	Assembly Code :	L34116080813D-112014-10
Working Pressure :	10,000 PSI	Test Pressure :	15,000 PSI

Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 15,000 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality Manager :
Date :
Signature :

QUALITY
11/20/2014

Technical Supervisor :
Date :
Signature :

PRODUCTION
11/20/2014



POWERING PROGRESS™

Gates E&S North America, Inc.
134 - 44th St.
CORPUS CHRISTI, TEXAS 78405
PHONE : (361) 887-9807
FAX: (361) 887-0812
Tim.Cantu@gates.com

CERTIFICATE OF CONFORMANCE

This is to verify that all Parts and/or Materials included in this shipment have been manufactured and/or processed in Conformance with applicable drawings and specifications, and that Records of Required Tests are on file and subject to examination. The following items were assembled at Gates E & S, North America Inc., facilities in Corpus Christi, TX, USA. This hose assembly was designed and manufactured to meet all the requirements of API Spec 7K.

CUSTOMER: AUSTIN DISTRIBUTING
CUSTOMERS P.O.#: PENDING
PART DESCRIPTION: 10K3.566.0CK4.1/1610KFLGE/E L/E
SALES ORDER #: 205663
QUANTITY: 1
SERIAL #: D-112014-10




SIGNATURE:


TITLE:

DATE:

QUALITY

11/20/2014





ILL ASSEMBLY PRESSURE TEST CERTIFICATE

AUSTIN DISTRIBUTING	Test Date:	11/20/2014
PENDING	Hose Serial No.:	D 112014 10
205663	Created By:	NORMA MATA
10K3.566.0CK4.1/1610KFLGE-E L/E		
4 1/16 10K FLG	End Fitting:	4 1/16 10K FLG
4773-6291	Assembly Code:	LJ41160S0813D 112014 10
10,000 PSI	Test Pressure:	15,000 PSI

we certify that the following hose assembly has been tested to the



PACKING LIST

Gates E&S North America
134 - 44th St.
CORPUS CHRISTI, TEXAS 78405
PHONE : (361) 887-9807
FAX: (361) 887-0812
 Tim.Cantu@gates.com

CUSTOMER. : AUSTIN DISTRIBUTING
PURCHASE ORDER # : PENDING
DATE : 11/20/2014
SALES ORDER # : 205663

SOLD TO: AUSTIN DISTRIBUTING
P.O. BOX 7890
AMARILLO, TEXAS
79114


SHIP TO: 0
0
0
0

PACKAGING: ENCLOSED CRATE

PRODUCT DESCRIPTION:

[illegible]

5,000 psi BOP Schematic





POWERING PROGRESS™

MTR DATA BOOK

CUSTOMER: AUSTIN DISTRIBUTING

DATE: 11/20/2014

Purchase Order: PENDING

Sales Order #: 205663

Product Description: 10K3.566.0CK4.1/1610KFLGE/E L/E

Hose S/N: D-112014-10

CONTENTS INCLUDED

1	GMCO FITTINGS
	14-177-1 INSERT STEM
	14-245-1 INSERT HEAD
	14-242-1 FERRULE
2	EDWARDS FABRICATION LIFT EYE CLAMPS
	19351, 19356 Individual Test Certificates for Each Clamp
3	4 1/16 10K FLANGES
	R20834 Heat Numbers
4	WELDING SPECIFICATIONS
	Certification and Procedure for welding
5	NDE RESULTS
	1921 Ultrasonic Test Results and Imaging
6	TEST CHART
	Chart Recording of Hydrostatic Test
7	TEST CERTIFICATE
	Document Product Details & Positive Results of Hydrostatic Testing
8	CERTIFICATE OF CONFORMANCE
	A Declaration of the conformity with the type approval
9	IMAGES
	Images of the product prior to shipping.
10	PACKING LIST
	Details of Shipping Contents, Dimensions and Weights



PLYMOUTH TUBE CO. USA
 672 W State Road 14, Winamac, Indiana 46988
 Phone: (574) 946-3125 Fax-Cold Draw: (574) 946-3850 Fax-Hot Mill: (574) 946-7220

PRODUCT CERTIFICATION

SALES ORDER - LINE / RLS

119679 - 1 / 1

SOLD TO

J P Steel

6841 FM 362

Brookshire, TX 77423

USA

WORK ORDER 006409

HEAT NUMBER 486507

MELT SOURCE TMK IPSCO Koppel-USA Mfg/Melt

956 HXXX +64-15

14-177-1

ISO 9001: 2008

Registered

CUSTOMER P.O. 17554	CUSTOMER PART JP 3.562X.531	QUANTITY 9,736.34 Lb	LADING NO 00071757	CERT ID / REV 01	CERT DATE 06/18/2014								
PART DESCRIPTION EJ35620531DR1724-00 Spec: ASTM A-519 Seamless Mech. Alloy Smls Mechanical, HF [D/E] Smls Q&T Grade: 4130 OD: 3.5625" Tol+.0360" Tol-.0360" Wall: 0.5310" Tol+.0530" Tol-.0530" AW Lgth Type: Random Lgth: 17.00' / 24.00' End Finish: Debur ID & OD Finish Type: Quench & Temper L80/N80 Oil: Light Oil													
CERTIFICATION REQUIREMENTS ASTM A-519-06 / API 5CT Quench & Tempered. Induction heated, water quenched and infrared pyrometer monitored. Tensiles tested were 1" STRIP specimens per A370. Ultrasonic tested and passed. Tubes UT inspected to ASTM E213/API 5CT 10.16 and SR2 requirements w/ 5% notches. Test covered 100% full length of OD & ID surfaces both longitudinal & transverse.													
Chemical Analysis													
C .31	Mn .51	P .011	S .003	Si .27	Al .015	Cr .97	Mo .21	Ni .13	Pb -----	Cu .16	V .006	Ti -----	Sn .008
Cb .001	Ca .0017	N .0095	As .0039	Sb .0014	H -----								
Product Checks													
CHK01	C .317	Mn .52	P .012	S .005	Si .275	Al .016	Cr .96	Mo .211	Ni .123	Pb	Cu .148	V .0034	Ti
CHK02	C .31	Mn .52	P .011	S .0043	Si .275	Al .016	Cr .96	Mo .211	Ni .123	Pb	Cu .147	V .0035	Ti
CHK01	Sn .0091	Cb .000	Ca .0017	N .0000	As .0095	Sb .0000	H						
CHK02	Sn .0091	Cb .000	Ca .0016	N .0000	As .0099	Sb .0000	H						
Physical Properties													

I certify that the described material has been manufactured, inspected, and tested in accordance with the above specification(s) and satisfies the requirements.

David Coulter
 Quality Assurance



PLYMOUTH TUBE CO. USA®

672 W State Road 14, Winamac, Indiana 46898
Phone: (574) 948-3125 Fax-Cold Draw: (574) 948-3860 Fax-Hot Mill: (574) 948-7220

PRODUCT CERTIFICATION

SALES ORDER - LINE / RLS

119679 - 1 / 1

SOLD TO

J P Steel
6811 FM 362
Brookshire, TX 77423
USA

WORK ORDER 006409

HEAT NUMBER 486597

MELT SOURCE TMK IPSCO Koppel-USA Mfg/Melt

ISO 9001: 2008

Registered

CUSTOMER P.O. 17554	CUSTOMER PART JP 3.562X.531	QUANTITY 9,736.34 Lb	LADING NO 00071757	CERT ID / REV 01	CERT DATE 06/18/2014																																																		
PART DESCRIPTION EJ35620531DR1724-00																																																							
<table border="0"> <tr> <td>Grain Size</td> <td>J1</td><td>J2</td><td>J3</td><td>J4</td><td>J5</td><td>J6</td><td>J7</td><td>J8</td><td>J9</td><td>J10</td><td>J11</td><td>J12</td><td>C</td><td>R</td><td>S</td><td>AR</td><td>AT</td><td>BH</td><td>BT</td><td>CH</td><td>CT</td><td>DE</td><td>DT</td><td>SAM 'B'</td> </tr> <tr> <td></td> <td>7</td><td>50</td><td>49</td><td>48</td><td>45</td><td>42</td><td>38</td><td>35</td><td>33</td><td>33</td><td>33</td><td>32</td><td>--</td><td>--</td><td>--</td><td>0.0</td><td>0.5</td><td>1.0</td><td>1.0</td><td>0.0</td><td>0.0</td><td>1.0</td><td>1.5</td><td>-----</td> </tr> </table>						Grain Size	J1	J2	J3	J4	J5	J6	J7	J8	J9	J10	J11	J12	C	R	S	AR	AT	BH	BT	CH	CT	DE	DT	SAM 'B'		7	50	49	48	45	42	38	35	33	33	33	32	--	--	--	0.0	0.5	1.0	1.0	0.0	0.0	1.0	1.5	-----
Grain Size	J1	J2	J3	J4	J5	J6	J7	J8	J9	J10	J11	J12	C	R	S	AR	AT	BH	BT	CH	CT	DE	DT	SAM 'B'																															
	7	50	49	48	45	42	38	35	33	33	33	32	--	--	--	0.0	0.5	1.0	1.0	0.0	0.0	1.0	1.5	-----																															
<table border="0"> <tr> <td>SAM 'D'</td> <td>Freq.</td> <td>Severity</td> </tr> <tr> <td>-----</td> <td>.000</td> <td>.000</td> </tr> </table>						SAM 'D'	Freq.	Severity	-----	.000	.000																																												
SAM 'D'	Freq.	Severity																																																					
-----	.000	.000																																																					
Methods of Manufacturing																																																							
<table border="0"> <tr> <td>Method of Mfg 1</td> <td>Method of Mfg 2</td> <td>Method of Mfg 3</td> </tr> <tr> <td>Electric Arc Furnace Melted</td> <td>Aircraft Quality</td> <td>Continuous Cast</td> </tr> <tr> <td>Method of Mfg 4</td> <td>Method of Mfg 5</td> <td></td> </tr> <tr> <td>Mfg.Using Clean Steel Practice</td> <td>Ladle Refined</td> <td></td> </tr> </table>						Method of Mfg 1	Method of Mfg 2	Method of Mfg 3	Electric Arc Furnace Melted	Aircraft Quality	Continuous Cast	Method of Mfg 4	Method of Mfg 5		Mfg.Using Clean Steel Practice	Ladle Refined																																							
Method of Mfg 1	Method of Mfg 2	Method of Mfg 3																																																					
Electric Arc Furnace Melted	Aircraft Quality	Continuous Cast																																																					
Method of Mfg 4	Method of Mfg 5																																																						
Mfg.Using Clean Steel Practice	Ladle Refined																																																						
Mechanical Properties																																																							
<table border="0"> <tr> <td></td> <td>Rc-High</td> <td>Rc-Low</td> <td>Tensile</td> <td>Yield .2%</td> <td>Yield .5%</td> <td>Elong%</td> <td>Reduction</td> <td>Aust TempF</td> <td>Aust Time</td> <td>TemperTempF</td> </tr> <tr> <td>1</td> <td>20</td> <td>19</td> <td>107000</td> <td>91800</td> <td>91800</td> <td>28</td> <td>59</td> <td>1640</td> <td>6.17</td> <td>1315</td> </tr> </table>							Rc-High	Rc-Low	Tensile	Yield .2%	Yield .5%	Elong%	Reduction	Aust TempF	Aust Time	TemperTempF	1	20	19	107000	91800	91800	28	59	1640	6.17	1315																												
	Rc-High	Rc-Low	Tensile	Yield .2%	Yield .5%	Elong%	Reduction	Aust TempF	Aust Time	TemperTempF																																													
1	20	19	107000	91800	91800	28	59	1640	6.17	1315																																													
<table border="0"> <tr> <td></td> <td>TemperTime</td> </tr> <tr> <td>1</td> <td>79</td> </tr> </table>							TemperTime	1	79																																														
	TemperTime																																																						
1	79																																																						
Charpy Impact Tests																																																							
<table border="0"> <tr> <td></td> <td>Temp 1</td> <td>Size 1</td> <td>Orient 1</td> <td>FtLb-T1-Pc 1</td> <td>LExp-T1-Pc 1</td> <td>%Shr-T1-Pc 1</td> <td>FtLb-T1-Pc 2</td> <td>LExp-T1-Pc 2</td> </tr> <tr> <td>1</td> <td>-30C</td> <td>10X10</td> <td>Long</td> <td>126</td> <td>.073</td> <td>100</td> <td>128</td> <td>.068</td> </tr> </table>							Temp 1	Size 1	Orient 1	FtLb-T1-Pc 1	LExp-T1-Pc 1	%Shr-T1-Pc 1	FtLb-T1-Pc 2	LExp-T1-Pc 2	1	-30C	10X10	Long	126	.073	100	128	.068																																
	Temp 1	Size 1	Orient 1	FtLb-T1-Pc 1	LExp-T1-Pc 1	%Shr-T1-Pc 1	FtLb-T1-Pc 2	LExp-T1-Pc 2																																															
1	-30C	10X10	Long	126	.073	100	128	.068																																															
<table border="0"> <tr> <td></td> <td>%Shr-T1-Pc 2</td> <td>FtLb-T1-Pc 3</td> <td>LExp-T1-Pc 3</td> <td>%Shr-T1-Pc 3</td> </tr> <tr> <td>1</td> <td>100</td> <td>125</td> <td>.073</td> <td>100</td> </tr> </table>							%Shr-T1-Pc 2	FtLb-T1-Pc 3	LExp-T1-Pc 3	%Shr-T1-Pc 3	1	100	125	.073	100																																								
	%Shr-T1-Pc 2	FtLb-T1-Pc 3	LExp-T1-Pc 3	%Shr-T1-Pc 3																																																			
1	100	125	.073	100																																																			
This test report data is for the heat Chemistry Stated above. The material in this test report is: 1) Manufactured in the USA. 2) Free from Polybrominated Biphenyls (PBB), Polybrominated Diphenyl Ethers (PBDE), and Mercury contamination.																																																							

I certify that the described material has been manufactured, inspected, and tested in accordance with the above specification(s) and satisfies the requirements.

David J. Smith
Quality Assurance



PLYMOUTH TUBE CO. USA

572 W State Road 14, Winamac, Indiana 46898
Phone: (574) 948-3125 Fax-Cold Draw: (574) 948-3850 Fax-Hot Mill: (574) 948-7220

PRODUCT CERTIFICATION

SALES ORDER - LINE / RLS

119679 - 1 / 1

SOLD TO

**J P Steel
6811 FM 382
Brookshire, TX 77423
USA**

WORK ORDER 006409

HEAT NUMBER 486597

MELT SOURCE TMK IPSCO Koppel-USA Mfg/Melt

**ISO 9001: 2008
Registered**

CUSTOMER P.O.	CUSTOMER PART	QUANTITY	LADING NO	CERT ID / REV	CERT DATE
17554	JP 3.562X.531	9,736.34 Lb	00071757	01	06/18/2014
PART DESCRIPTION EJ35620531DR1724-00					
3) No Repairs by welding					
End of Certification					

I certify that the described material has been manufactured, inspected, and tested in accordance with the above specification(s) and satisfies the requirements.


Quality Assurance

Benteler Steel/Tube GmbH
Postfach 13 40
33043 Paderborn
Deutschland
Tel.: +49.5254.81-0 Fax: +49.5254.13688

Ersetzt / replace

Dok. Nr. / Doc. No. 65-716081/001/E vom / dated 26.09.2012

BENTELER 
Steel/Tube

956HXxxT64wB-1H
14-245-1

ABNAHMEPRÜFZEUGNIS EN 10204-3.1
INSPECTION CERTIFICATE EN 10204-3.1
CERTIFICAT DE RECEPTION EN 10204-3.1
EN 10204:2005-01

Benteler Steel/Tube GmbH - Postfach 1340 - 33043 Paderborn - Deutschland

JP Steel
PO Box 592
BROOKSHIRE TX 77492
USA

Dokument-Nr.: 65-716081/002/P
Document No.:
No. du document:
Kunden-Bestell-Nr.: BST 12-12036 / JP 11459
Purchase Order No.:
No. de commande du client:
Benteler Auftrags-Nr.: 1678593
Benteler Order No.:
No. de commande Benteler:
Versandanzeigen-Nr.: 6571039
Dispatch Note No.:
No. d'avis d'expédition:
Produkt: NAHTLOSE STAHLROHRE
Product: SEAMLESS STEEL TUBES
Produit: TUBES D'ACIER SANS SOUDURE

Prüf-Nr.:
Inspection No.:
No. du certificat:
Hersteller: Warmrohrwerk Osnabrück
Manufacturer: DMH EN ISO 9001, ISO/TS-16949 CERTIFIED BY TÜV KORD CERT
Producteur: PFD 87/23/EC CERTIFIED BY TÜV KORD SYSTEMS
Herstellerzeichen: 
Manufacturer's brand:
Marque du producteur:
Stempel des Abnahmebeauftragten: WA
Stamp of the inspection representative:
Poinçon du contrôleur:
Stahlschmelzungsverfahren: ELEKTROSTAHL
Steelmaking process: ELECTRIC FURNACE
Procédé d'élaboration de l'acier: FOUR ELECTRIQUE

Blatt: 1 / 4
Page:
Page:

Lieferbedingungen: ASTM-A 519-2006

Terms of delivery:
Conditions de livraison:

Maße - Toleranzen: outside diameter acc. to customer request, wall thickness acc. to customer request, ASTM-A 519-2006

Dimensions-tolerances:
Dimensions-tolérances:

Stahlsorte: GRADE 4130

Steel grade:
Nuance d'acier:

Lieferzustand: QT

Delivery condition:
État de livraison:

Produktkennzeichnung: PKE: BENTELER SIGN BENTELER DIMENSIONS GRADE 4130 BST 12-12036 / JP 11459 ASTM-A 519 WA

Product marking:

Marquage du produit:

AIZ = Ätzmarkenzeichnung, Etching line marking, Gravure à l'acide . FK = Farbkennzeichnung, colour marking, marquage par couleur . PS = Farbstrichkennzeichnung, penit marking, marquage par pointes . F&D = Farbstrichkennzeichnung, Colour jet primer, marquage à jet d'encre de couleur . LK = Laserkennzeichnung, Laser marking, Marquage laser . PKL = Etikettenkennzeichnung, tag marking, marquage sur étiquette . PS = Prägenmarkenzeichnung, stamp marking, marquage par poinçonnage . TS = Transversalkennzeichnung, bid jet spray marking, marquage à jet d'encre .

Benteler Steel/Tube GmbH
Postfach 13 40
33043 Paderborn
Deutschland
Tel.: +49.5254.81-0 Fax: +49.5254.13888

Ersetzt / replace

Dok. Nr. / Doc. No. 65-716081/001/E vom / dated 26.09.2012

BENTELER 

Steel/Tube

ABNAHMEPRÜFZEUGNIS EN 10204-3.1
INSPECTION CERTIFICATE EN 10204-3.1
CERTIFICAT DE RECEPTION EN 10204-3.1

Dokument-Nr.:
Document No.:
No. du document:

65-716081/002/P

Prüf-Nr.:
Inspection No.:
No. du certificat:

Blatt: 2 / 4
Page:
Page:

Pos.	Stück	Maße	Länge	Gewicht	Schmelzen-Nr.	Prüfdruck	Rohr-Nr.-Gruppe	Vielfachlängen
Item	Number	Dimensions	Length	Weight	Heat No.	Test pressure	Tube number group	Multiple lengths
Poste	Nombre	Dimensions	Longueur	Poids	No. de coulée	Pression d'épreuve	Série de no. des tubes	Longueurs multiples
		feet	feet	lbs				
0002	34	4.500" O.D. * 0.625" 17 FT - 24 FT	748,36	19326	573599			

Schmelzenanalyse [%] / Heat analysis [%] / Analyse sur coulée [%]

Pos.	Schmelzen-Nr.	C	SI	MN	P	S	CR	MO	NI
Item	Heat No.								
Poste	No. de coulée								
0002	573599	0,310	0,220	0,53	0,007	0,002	0,89	0,17	0,09

Prüfgergebnisse / Test results / Résultats des essais

Die Rohre wurden zerstörungsfrei geprüft: The tubes are non destructive tested: Les tubes ont passé un essai non destructif:	UT-long.imperfections: acc. to API 5CT, SR 2; UT-long. Test method: acc. to ASTM-E 213; Outside notch depth: 5,0 %; Inside notch depth: 5,0 %; UT-transv. imperfections: acc. to API 5CT, SR2; acc. to ASTM-E 213; Outside notch depth: 5,0 %; Inside notch depth: 5,0 %; UT-lamination detection: acc. to EN 10246-14, table 1	PASSED
Augensichtkontrolle: Visual inspection: Examen visuel:	PASSED	PASSED
Materialverwechslungsprüfung: Material conformity test: Vérification de la nuance:	PASSED	PASSED
Maßkontrolle: Dimensions examination: Vérification des dimensions:	PASSED	PASSED

Ergebnisse der mechanischen Prüfung / Results of mechanical testing / Résultats des essais mécaniques

Die Probennahme erfolgte an Vielfachlängen.
The sampling was carried out on multiple lengths.
L'échantillonnage était réalisé aux longueurs multiples.

Benteler Steel/Tube GmbH
Postfach 13 40
33043 Paderborn
Deutschland
Tel.: +49.5254.81-0 Fax: +49.5254.13566

Ersetzt / replace

Dok. Nr. / Doc. No. 65-716081/001/E vom / dated 26.09.2012

BENTELER 

Steel/Tube

ABNAHMEPRÜFZEUGNIS EN 10204-3.1
INSPECTION CERTIFICATE EN 10204-3.1
CERTIFICAT DE RECEPTION EN 10204-3.1

Dokument-Nr.: 65-716081/002/P
Document No.:
No. du document:

Prüf-Nr.:
Inspection No.:
No. du certificat:

Blatt: 3 / 4
Page:
Page:

Zugversuch längs Streifenprobe / Tensile test longitudinal Strip test specimen / Essai de traction longitudinale Bande decoupee sur tube

Pos. Item Poste	Proben-Nr. Specimen No. No. de l'éprouvette	Schmelzen-Nr. Heat No. No. de coulée	Probenabmessung Specimen dimensions Dimensions de l'éprouv.	Streckgrenze Yield strength Limite élastique	Zugfestigkeit Tensile strength Résistance à la traction	Dehnung Elongation Allongement	Einschnürung Area reduction Coefficient de striction
Anforderungen Requirements Exigences			mm	RT 0,5 % MPa 682-685	Rm MPa MIN 665	A2" % MIN 14	1. Formel 1. Formula 1. Formule
0002	000001	573599	25,40 X 15,40	637	758	36	
0002	000002	573599	25,40 X 15,70	635	769	36	

Härteprüfung / Hardness test / Essai de dureté

Pos. Item Poste	Proben-Nr. Specimen No. No. de l'éprouv.	Schmelzen-Nr. Heat No. No. de coulée	Härte Hardness Dureté
Anforderungen Requirements Exigences			HRC HB HV HRB HBS
0002	000001	573599	MAX 22,0 020

Kerbschlagbiegeversuch Notched bar impact test / Essai de flexion per choc (résilience) [1 CHARPY V]

Pos. Item Poste	Proben-Nr. Specimen No. No. de l'éprouv.	Schmelzen-Nr. Heat No. No. de coulée	Probenabmessung Specimen dimensions Dimensions de l'éprouvette	Probenlage Specimen position Position de l'éprouvette	Prüftemperatur Test temperature Température d'essai	Kerbschlagarbeit Absorbed energy Energie absorbée	Kerbschlagzähigkeit Impact strength Résistance au choc	Verf.-Bruchanteil Shear fracture Rupture ductile
Anforderungen Requirements Exigences			Länge Breite Höhe Length Width Height Longueur Largeur Hauteur	längs (L) longitudinal (L) longitudinal (L)		einzel mittel single average individuelle moyenne	einzel mittel single average individuelle moyenne	
			mm mm mm	quer (Q) transversal (Q) transversal (Q)	GRAD °C -30	ft-lbf ft-lbf MIN 020	J/cm²	
0002	000001	573599	55 10,00 10,00	L	-30	116 110 111		
			10,00 10,00					
			10,00 10,00			112		

Benteler Steel/Tube GmbH
Postfach 13 40
33043 Paderborn
Deutschland
Tel.: +49.5254.81-0 Fax: +49.5254.13566

Ersetzt / replace

Dok. Nr. / Doc. No. 65-716081/001/E vom / dated 26.09.2012

BENTELER 

Steel/Tube

ABNAHMEPRÜFZEUGNIS EN 10204-3.1

INSPECTION CERTIFICATE EN 10204-3.1

CERTIFICAT DE RECEPTION EN 10204-3.1

Dokument-Nr.:

Document No.:

No. du document:

65-716081/002/P

Prüf-Nr.:

Inspection No.:

No. du certificat:

Blatt: 4 / 4

Page:

Page:

Wärmebehandlung / Heat treatment / Traitement thermique

Hardening temperature: 850°C, Holding time: 1 min, Cooling: water / Tempering temperature: 735°C, Holding time: 6 min, Cooling: air

Vermerk / Remark / Remarque

Certificate remarks: Steel is manufactured to fine grain practice. The tubes comply with the requirements of NACE MR0175-03., hardness max. 22 HRC, No mercury, mercury compounds or mercury bearing instruments and / or equipment has been used in any manner which might cause contamination in manufacture assembly, or test of material. No weld repair has been carried out.:
Certificate-Remark: The steel will be produced by an electric arc furnace, ladle furnace and continuous casting machine, stirring by argon. The mode of operation in this process is commonly referred to as "clean steel process". The products are fully killed.

Verkäufer(in) / Salesman/ woman in charge / Personne chargée : Mr Storm, Tel.: 05254/81-4274, Fax: 4289

Dinslaken, 26.10.2012, TEL.: 02064.623-5370 FAX: 02064.623-5390

Abnahmebeauftragter

Inspection representative

Contrôleur

DR. BASEL KEITA / The

Es wird bestätigt, daß die gelieferten Erzeugnisse den techn. Lieferbedingungen des Auftrages entsprechen. Dieses Dokument wurde mittels EDV erstellt und ist ohne Unterschrift rechtmäßig.
We certify that the supplied products comply with the order specification. This document was prepared by means of electronic data processing and is valid without signature.
Nous attestons que les produits livrés sont conformes aux stipulations de la commande. Ce document a été établi par traitement électronique de l'information et est valide sans signature.

P.O. BOX 924469
HOUSTON, TX 77292
PHONE: (713) 290-8490



6645 W. TIDWELL
HOUSTON, TX 77092
FAX: (713) 290-8627

To: J.P. STEEL, LLC
PO BOX 592
KATY, TX 77492-0592

Report Date: 10/18/13
Report No: 250944.0
Rev.: A
Cust Acct: JPS10050

PO#: 15484
Material: 4.50" OD X .625" WALL 4130 Q & T ALLOY
ID/Heat: HT# 573599
Job Info:

Tensile Test Results

No./Location	Size (in.)	Area (in^2)	Ult. Load (lbs.)	Yield (psi)	Tensile (psi)	Elong. (%)	R. of A. (%)	Hardness
1	.495	.1924		90,200	112,300	26	73	

Unless otherwise stated, yield stress is 0.2% offset, gage length is 2 in. for 1/2 in. bars or 1 in. for 1/4 in. bars.

Signed: _____

MIKE MASON

Our reports are for the exclusive use of our customer and our name may be used only with prior written approval. Our reports apply only to the sample tested or inspected and do not necessarily represent the quality of other apparently similar or identical materials. All test specimens and testing conforms to ASTM A-370 requirements unless otherwise stated. This test report shall not be reproduced, except in full, without the written approval of P&B Testing Inc.



ARCELORMITTAL TUBULAR PRODUCTS
SHELBY LLC.
132 WEST MAIN STREET
SHELBY, OHIO 44875-1471
Telephone 419/342-1200 FAX: 419/342-1437

**MATERIAL
TEST
REPORT**

ISO/TS 16949:2009 ISO 9001:2008

14-242-1 956444469A-F

SHELBY ORDER NO.
447180

C U S T O M E R	MARMON KEYSTONE CORPORATION 6441 BINGLE ROAD HOUSTON TX 77092 ATTN: EARTHA JILES				SPECIFICATION ASTM A513 GMCO A513 DOM 1 01-10 FAX: (713)460-5414				CUSTOMER ORDER 35-057810-03			
--------------------------------------	---	--	--	--	--	--	--	--	------------------------------------	--	--	--

GRADE 520	SIZE(O.D x ID x WALL) 7.250 X 6.000 X .625	QUANTITY 17509 LB	396.00 FT	SHIPPED 09/02/14	DATE 09/02/14
--------------	---	----------------------	-----------	---------------------	------------------

CONDITION ASTM 513 Type 5 Produced to OD/ID Ref: WALL EW TUFFDOM STRESS RELIEVE ANNEAL	PART NO. REV.	S#00335344 50064541
--	------------------	------------------------

HEAT NO. 4131797	CHEMICAL ANALYSIS													GRAIN SIZE
	C	Mn	P	S	Si	Ni	Cr	Mo	Cu	V	Al	OTHER		
	.16	1.41	.012	.003	.220	.010	.040	.010	.040	.002	.040	.0030 CA TI .0010 Cb .0020		

MECHANICAL PROPERTIES										MAGNAFLUX	
HEAT NO. 4131797	LOAD NO. T6457128	YIELD PSI 76900	TENSILE PSI 89400	ELONG % 2.0" 33	RED AREA %	HARDNESS		IMPACT FT.-LBS SIZE 10.0X10.0 TEMP C -20-30 RESULTS 128 57 140 68 133 65	FREQ.	SEVERITY	
						BHN	ROCKWELL RB 92				

JOMINY HARDENABILITY (EXPRESSED IN 16THS)																
HEAT NO.	1	2	3	4	5	6	7	8	10	12	14	16	20	24	28	32

J-K RATING				SLAG-OXIDE RATING			
HEAT NO.	A	B	C	D	INGOT	OXIDE	SLAG
					Q. C. INSPT		

MELT SOURCE OTHER INSPECTION EN 10204 3.1	Melted and Manufactured in USA	THIS TEST REPORT NOTARIZED WHEN REQUIRED SWORN AND SUBSCRIBED BEFORE ME THIS _____ DAY OF _____
---	--------------------------------	---

Material under this mtr was not exposed to mercury during processing.

NOTARY PUBLIC

Frank Simeone



Edwards Fabrication..

1385 Hwy. 35 Bypass S. O: (361) 790-7910
P.O. Box 2350 F: (361) 790-7927
Rockport, TX 78381

tedwards@edwardsfabrication.com
www.edwardsfabrication.com

CERTIFICATE OF TEST

Client:
Gates E & S North America
134 44th Street
Corpus Christi, TX 78405

Purchase Order: 16522

Certificate Number			Date of Examination	
19351			09/11/14	
ID#	Part Number	Description	SWL*	Proofload
19351	7361-0864	4.0" Lift-Eye Clamp 2 Bolt	4205 lbs.	8410 lbs.
DO NOT WELD, CUT, ADD-TO, TAKE AWAY ANY COMPONENTS OR MAKE ANY MODIFICATION TO THIS CLAMP UNIT. Doing so voids this test certificate.				
* Safe Work Load				

THIS PRODUCT IS MANUFACTURED IN THE U.S.A.

We hereby verify that the above information is correct
as contained in the records of Edwards Fabrication L.L.C.

Michael White
Test Operator



Thomas F. Edwards
President
Edwards Fabrication L.L.C.



Edwards Fabrication

1385 Hwy. 35 Bypass S. O: (361) 790-7910
P.O. Box 2350 F: (361) 790-7927
Rockport, TX 78381

tedwards@edwardsfabrication.com
www.edwardsfabrication.com

CERTIFICATE OF TEST

Client:
Gates E & S North America
134 44th Street
Corpus Christi, TX 78405

Purchase Order: 16522

Certificate Number			Date of Examination	
19356			09/11/14	
ID#	Part Number	Description	SWL*	Proofload
19356	7361-0864	4.0" Lift-Eye Clamp 2 Bolt	4208 lbs.	8416 lbs.
DO NOT WELD, CUT, ADD-TO, TAKE AWAY ANY COMPONENTS OR MAKE ANY MODIFICATION TO THIS CLAMP UNIT. Doing so voids this test certificate.				
* Safe Work Load				

THIS PRODUCT IS MANUFACTURED IN THE U.S.A.

We hereby verify that the above information is correct
as contained in the records of Edwards Fabrication L.L.C.

Michael White
Test Operator



Thomas F. Edwards
President
Edwards Fabrication L.L.C.

API Monogram Licensee
ISO 9001-2008 Certified
PED 97/23/EC
AD 2000-Merkblatt W0



MARS FORGE PVT. LTD.

Rajkot Gondal Nh. 8-B, Village : Shapar - 360024 Dist. Rajkot (Guj.) India.
Tel. No. : 91 - 2827 - 252190, 252191, Fax No. : 91 - 2827 - 252119
E-mail : info@marsforge.com, Web. : www.marsforge.com

MATERIAL TEST REPORT

The certificate of Material as per EN 10204 3.1

Customer : R & S OILFIELD INC.USA

Doc.No.F-P-21-12/

TC Ref No : 21/KJ2014-20

DATE 25.08.2014	Purchase Order Ref.No. : 520 Dated 31.07.2014	Invoice No. : 21	MF Drawing No. : MF 0294-01F
Chemical Analysis Ref: 54/270714	Physical Analysis Ref MFT-644, MFI-147	Test Certificate Ref 025396	Mode of Shipping : SEA
Quantity : 27 PCS	Part Description: Weld Neck Flange, 4-1/16" 10M X 4" SCH XXH AISI 4130 N.Q.T	PSL LEVEL 2	Raw Material Spec No MARS 6A -001 REV.03
Heat Code Punch : R 20834	R & S Part Number : RSMFW410X...	Grade/Condition: SAE4130	Melting Practice : EAF—LRF—VD—CCM
Heat Number: R 20834	Reduction Ratio: Raw Material Reduction Ratio : 1:3.02		

CHEMICAL ANALYSIS RESULTS

Elements	C.	Mn.	Si.	Cr.	Ni.	Mo.	S.	P.	V.	Cu.
Minimum %	0.28	0.40	0.15	0.80	---	0.15	---	---	---	---
Maximum %	0.33	0.60	0.35	1.10	0.25	0.25	0.025	0.025	0.10	0.30
Heat Analysis %	0.32	0.55	0.19	1.07	0.21	0.22	0.005	0.008	0.003	0.05

MECHANICAL PROPERTIES(QTC SIZE: 4"x 4")

CHARPY IMPACT PROPERTIES

(ASTM A 370)	Requirement	Actual	Size	10 x 10 x 55mm	DIRN	L
0.2% Yield Strength (PSI)	75,000 PSI MIN	78798 PSI	Impact		20 Ft-Lbs Min @ -75° F	
Tensile Strength (PSI)	95,000 PSI MIN	104814 PSI	Energy (ft-lbs)	51.63	57.53	50.15
% Elongation	18.0% MIN	25.20%	Average		53.10 Ft Lbs	
% Reduction Of Area	35.0% MIN	70.30%	L.E. (inch)	0.026	0.029	0.024
Hardness (HBW)	207-235 HBW	207 TO 229 HBW				

HEAT TREATMENT

CYCLE	TEMPERATURE(C)	TEMPERATURE (F)	TIME@TEMP	QUENCH MEDIA
Normalized	910 °C	1670 °F	150 Minutes	AIR COOLED
Austenitized	880 °C	1616 °F	150 Minutes	WATER QUENCHED
Tempered	695 °C	1283 °F	150 Minutes	AIR COOLED

Water Temperature IN AT 35°C AND OUT AT 45°C

NON DESTRUCTIVE EXAM (NDE)

	Yes/No	Spec Number
Ultrasonic Testing (UT)	NO	---
Magnetic Particle Inspection (MPI)	YES	ASME Section-V,Article -7

*Country of origin - India

* We hereby declare that the material herein described is in accordance with specifications of the order.



API Monogram Licensee
ISO 9001-2008 Certified
PED 97/23/EC
AD 2000-Merkblatt W0



MARS FORGE PVT. LTD.

Rajkot Gondal Nh. 8-B, Village : Shapar - 360024 Dist. Rajkot (Guj.) India.
Tel. No. : 91 - 2827 - 252190, 252191, Fax No. : 91 - 2827 - 252119
E-mail : info@marsforge.com, Web. : www.marsforge.com

Doc No : F-P-21-17

MAGNETIC PARTICLE EXAMINATION REPORT

PART No.	: RSMFW410X	DATE	: 25.08.2014
PART NAME	: Weld Neck Flange, 4-1/16" 10M X 4" SCH XXH AISI 4130 N.Q.T	INSPECTOR/LEVEL	: ASNT L-II
HEAT NO	: R 20834	QUANTITY	: 27 PCS
PROC No	: W-P-21-09	REJECT	: None
ACCEPT	: Acceptable		
WO/PO No.	: R&S PO#520 Dated 31.07.2014		

TEST PROCEDURE


EQUIPMENT	: "Magnafield "Make , Electromagnetic Crack Detector
DETECTING MEDIA	: Fluorescent Powder
METHOD	: Wet fluorescent method
CURRENT APPLY	: H.W.D.C./A.C. Current used
LOCATION	: Cover 100% (Assessable) area of the job
MAGNETIZATION	: Longitudinal
TYPE OF MAGNETIZATION	: Continuous
EXAMINATION	: Surface & sub surface defect.
REFERENCE STANDARD	: ASME Section V, Article 7, SE709
TESTED BY	: HITESH MAHETA
DATE OF TEST	: 02.08.2014

OBSERVATION : No relevant indication found

RESULT : Jobs are found satisfactory in MPT.

For, MARS FORGE PVT. LTD.





MARS FORGE PVT. LTD.

"Shraddha House" M-170, Gujarat Housing Board
Akshar Marg, Rajkot - 360 001, Gujarat (India)
Tel. No. : 91 - 281 - 244 83 83, 247 90 88, Fax : 91- 281 - 245533

Works : Rajkot Gondal Nh. 8-B, Village : Shapar, Dist. Rajkot (Guj.) Ind
Tel. No. : 91 - 2827 - 252190, 252191, Fax No. : 91 - 2827 - 2521
E-mail : info@marsforge.com, Web. : www.marsforge.co

TEST CERTIFICATE

TC Ref : 12/A/2011-2012

Date : 27-05-2012

Our Drawing No.	: MF 0285 PI
Heat No. Code	: R 15965
Quantity	: 159 Nos.
Sample Qty.	: 01 Nos.
Chemical Analysis Ref.	: 111/07052012
Physical Analysis Ref.	: AI-277
Test Certificate Ref.	: 1111

Customer : R & S OILFIELD INC. HOUSTON - USA.
Customer's Part No. : 4 - 1500 WN
Purchase Order Ref. : 172 / Dt.19-03-2012
Delivery Challan No. : 12/ DT : 27.05.2011
Vehicle No. : BY SEA

CHEMICAL ANALYSIS RESULTS :

Material	Heat No.	C.	Mn.	Si.	Cr.	Ni.	Mo.	S.	P.	V.
Specified A350 LF2	SPECN.	---	0.60	0.10	--	---	---	---	--	---
		0.35	1.05	0.35	0.30	0.40	0.12	0.050	0.040	0.08
Actual	R 15965	0.20	0.93	0.20	0.058	0.076	0.021	0.008	0.009	0.002

Hardness Reqd. Range	Hardness Actual	ASTM Grain Size	Heat Treatment	Jominy Value	INCLUSION RATING			
					A	B	C	D
187 BHN MAX.	143 - 174 BHN	6-7	Normalised	---	<u>1.0</u> 0.5	<u>0.5</u> ---	---	<u>1.0</u> ---

* NORMALISED AT 930° C, SOAK FOR 120 MINUTES, AIR COOL.

PHYSICAL TEST RESULTS :

Heat Code On Forgings	Yield PSI.	UTS PSI.	%E	%RA.	Impact (dirn. - L, Size- 10x10x55 mm) 27 Joules min. at -50° F			
---	45000	70000	22.00	30.00	I	II	III	Avg.
PUNCH R 15965	50235	76393	33.80	67.10	67 1.40	65 2.30	63 1.31	65.16 J.



Signature
QUALITY CONTROL





MORRIS INSPECTIONS

Mailing Address:
2316 Memorial Pkwy.
Portland, TX 78374-3206

Business Telephone
(361) 643-7066
Cellular Telephone
(361) 877-0776

**QW-484 SUGGESTED FORMAT FOR MANUFACTURER'S RECORD OF WELDER
OR WELDING OPERATOR QUALIFICATION TESTS**
(See QW-301, Section IX, ASME Boiler and Pressure Vessel Code)

Welder's Name	<u>JEFFREY CHARLES TOWNSEND</u>		S. B. No.		
Welding Process(es)	<u>Shielded Metal Arc Welding</u>		Type	<u>Manual</u>	Position (QW-405.1)
Welding Procedure Specification No.	<u>SM-4130</u>	POR No.	<u>SM-4130</u>	Backing (QW-402.7)	<u>None</u>
Material Spec. (QW-403) No.	<u>HF-4130</u>	Grade	<u>LN80</u>	P-No.	<u>-</u>
				Group	<u>-</u>
To					
Material Spec (QW-403) No.	<u>HF-4130</u>	Grade	<u>LN80</u>	P-No.	<u>-</u>
Test Thickness	<u>.531"</u>	Range	<u>Up to 1.062"</u>	Test Dia.	<u>4.00"</u>
Process(es)	<u>SMAW</u>		<u>SMAW</u>		Range <u>2 7/8" O.D. over</u>
Filler Metal (QW-404) Spec.	<u>SFA 5.1</u>		<u>SFA 5.5</u>		<u>SFA</u>
	Class No. <u>E-6010</u>		Class No. <u>E-8018</u>		Class No.
	F No. <u>3</u> A No. <u>1</u>		F No. <u>4</u> A No. <u>3</u>		F No. A No.
Filler Diameter (QW-404.6)	<u>1/8"</u>		<u>5/32"</u>		
Weld Deposit Thickness	<u>.125"</u>		<u>.406"</u>		
Consumable Insert (QW-404.22)	<u>N/A</u>		<u>N/A</u>		
Gas (QW-408) Shielding	<u>N/A</u>		<u>N/A</u>		
Flow Rate	<u>N/A</u>		<u>N/A</u>		
Gas (QW-408) Purge	<u>N/A</u>		<u>N/A</u>		
Flow Rate	<u>N/A</u>		<u>N/A</u>		
Elec. (QW-409) AC-DC	<u>Direct</u>		<u>Direct</u>		
Polarity	<u>Reverse</u>		<u>Reverse</u>		
Volt Range	<u>22-26</u>		<u>23-27</u>		
Amp Range	<u>80-120</u>		<u>150-210</u>		
Progression (QW-405.3)	Root <u>Up</u>	Hot Pass	<u>Up</u>	Filler <u>Up</u>	Cap <u>Up</u>
Transfer Mode (QW-409.2) GMAW	<u>N/A</u>				
Other			Preheat	<u>700 F.</u>	PWHT. <u>N/A</u>

For Information Only
Material 4130 IS NOT listed in ASME Section IX
but acceptable.

Submerged Arc Flux Trade Name

Guided Bend Test Results (QW-482.2(a), QW-482.2(a), QW-482.2(b))

Specimen No.	Type	Figure No.	Results	Specimen No.	Type	Figure No.	Results
			Radiographic Results in lieu of Sidebends				

Radiographic Test Results (QW-304 & QW-305)

For alternative qualification of groove welds by radiography

Radiographic Results: Satisfactory

Test Conducted by J. Morris - MORRIS INSPECTIONS

Laboratory--Test No. 09-019

We certify that the statements in this record are correct and that the test welds prepared, welded and tested in accordance with the requirements of Section IX of the ASME Code.

Date March 23, 2009

Organization DU-TEX, INC.

(Details of record of tests are illustrative only and may be modified to conform to the type and number of tests required by the Code.)

NOTE: Any essential variables in addition to those above shall be recorded. This form modified for information and typing purposes. (QW-301.4).



MORRIS INSPECTIONS


Mailing Address:
2316 Memorial Pkwy.
Portland, TX 78374-3206

Business Telephone:
(361) 643-7066
Cellular Telephone:
(361) 877-0776

QW-483 SUGGESTED FORMAT FOR PROCEDURE QUALIFICATION RECORD (PQR)
(See QW-201.2, Section IX, ASME Boiler and Pressure Vessel Code)

Company Name DU-TEX, INC. Date March 24, 2009
Procedure Qualification Record No. SM-4130
WPS No. SM-4130 Transfer Mode GMAW N/A
Welding Process(es) Shielded Metal Arc Welding
Types (Manual, Automatic, Semi-Auto.) Manual

JOINTS (QW-402)



BASE METALS (QW-403)

Material Spec. HF-4130 To HF-4130
Type or Grade LN 80 To LN 80
P-No. - Grp. - To P-No. - Grp. -
Thickness Tested .750" Range: .1875" - 1.500"
Diameter Tested 4.500" Range: Proc. unlimited
No Pass Greater than 1/8" in thickness No
Backing: Yes No XX Material Weld Metal only
Other Material 4130 IS NOT listed in ASME Section IX

FILLER METALS (QW404)

Process(es) SMW SMW
Weld Metal Analysis A-No. 1 3
Weld Bead Number 1 & 2 Balance
Dia of Electrode 1/8" 5/32"
Filler Metal F-No. 3 4
SFA Specification 5.1 5.5
AWS Classification E-6010 E-8018
Weld Deposit Range .250" 1.250"
Weld Deposit Thickness .125" .625"
Tungsten: Size N/A Type: - Class: -
Flux Trade Name: N/A Designation: -
Other -

POSITION (QW-405)

Position of Test Groove 6-G
Weld Progression (Up, Down, Flat) -
Root Up Hot Pass Up Filler Up Cap Up

PREHEAT (QW-406)

Preheat Temp. 700° F.
Interpass Temp. Min. - Max. -
Other -

POSTWELD HEAT TREATMENT (QW-407)

Temperature None applied
Time -
Other -

GAS (QW-408)

Process(es) SMW-N/A
Shielding -
Flow Rate -
Purge -
Flow Rate -
Other -

ELECTRICAL CHARACTERISTICS (QW-409)

Process(es)	SMW	SMW
Current	Direct	Direct
Polarity	Reverse	Reverse
Volts Range	22-26	23-27
AMPS Range	80-120	150-210
Other	-	-

TECHNIQUE (QW-410)

Process(es)	SMW	SMW
Travel Speed	Variable	Variable
String or Weave Bead	String	String
Oscillation	None	None
Multi or Single Pass (per side)	Multiple	Multiple
Single or Multi Electrodes	Single	Single
Peening	None	None
Other	-	-

QW-483 (Back)

Tensile Test (QW-150)

NOTE: MATERIAL SPECS

Electrode Tensile Strength is 80,000 PSI

Specimen No.	Width	Thickness	Area	Ultimate Total Load lbs.	Ultimate Unit Stress psi	Character of Failure & Location
T - 1	.751"	.743"	.558"	45,000	80,645	Satisfactory-Broke in Weld Area
T - 2	.748"	.748"	.554"	44,400	80,144	Satisfactory-Broke in Weld Area

Guided Bend Test (QW-160)

Specimen No.	Type	Figure No.	Results	Specimen No.	Type	Figure	Results
6G - SB1	SBend	QW462.2	Satisfactory				
6G - SB2	SBend	QW462.2	Satisfactory				
6G - SB3	SBend	QW462.2	Satisfactory				
6G - SB4	SBend	QW462.2	Satisfactory				

Toughness Tests (QW-170)

Specimen No.	Notch Location	Specimen Size	Test Temp.	Impact Values	Lateral Exp.		Drop Weight	
					% Shear	Mils	Break	No Break

Average ft/lb for this size _____

Minimum ft/lb for this size _____

Fillet Weld Test (QW-180)

Pos.	Spec. No.	Contour	Leg No. 1	Leg No. 2	Throat	Bend Defects	Macro-Pent.	Results

Other Tests

Type of Test: _____

Deposit Analysis: _____

Other: _____

Welder's Name Jeffrey Charles Townsend S.S.# _____ Stamp No. N/ATest conducted by: J. Morris-MORRIS INSPECTIONS Laboratory Test No. 09-022

We certify that the statements in this record are correct and that the test welds were prepared, welded and tested in accordance with the requirements of Section IX of the ASME Code.

Date March 25, 2009 Manufacturer DU-TEX, INC.

Details of record of tests are illustrative only and may be modified to conform to the type and number of tests required by the Code. This form modified for information and typing purposes (QW200.2(D))

NQS INSPECTION, LTD

06972

Non-Destructive Testing Report

Report # _____

Customer: Gates

Date: 11/20/14

Project: 192114

METHOD

Ultrasonic	<u>✓</u>	Procedure #	<u>NRS- PA-VT/2013/Ruo</u>
Magnetic Particle	<u> </u>	Standard #	<u>ASME</u>
Liquid Penetrant	<u> </u>	Section # Level	<u>II</u>

TECHNIQUE

Shear wave		Angle	AC _____	DC _____	Dwell Time _____
Straight Beam		60 	Wet _____	Dry _____	Penetrant # _____
Unit Type	<u>Dr. 301A</u>	70 	Continuous _____		Developer # _____
Ref Standard	<u>I.D./R2</u>	45 	Residual _____		Cleaner # _____
Range	<u>5"</u>	0 	Background _____		

RESULTS

[illegible]Inspector: Joe Baker SNT Level 11/1


PG # _____ of _____

Customer Representative: [Signature]

Hours 2 Mileage

PO BOX 23036 CORPUS CHRISTI, TEXAS 78403

PHONE # 361-533-4563 / FAX # 361-884-1984 / E-MAIL emanahan@nqsltd.com (Eric) / lray@nqsltd.com (Bud)





GATES E & S NORTH AMERICA, INC.
134 44TH STREET
CORPUS CHRISTI, TEXAS 78405

PHONE: 361-887-9807
FAX: 361-887-0812
EMAIL: Tim.Cantu@gates.com
WEB: www.gates.com

10K CHOKE AND KILL ASSEMBLY PRESSURE TEST CERTIFICATE

Customer :	AUSTIN DISTRIBUTING	Test Date:	11/20/2014
Customer Ref. :	PENDING	Hose Serial No.:	D-112014-10
Invoice No. :	205663	Created By:	NORMA MATA
Product Description:	10K3.566.0CK4.1/1610KFLGE/E L/E		
End Fitting 1 :	4 1/16 10K FLG	End Fitting 2 :	4 1/16 10K FLG
Gates Part No. :	4773-6291	Assembly Code :	L34116080813D-112014-10
Working Pressure :	10,000 PSI	Test Pressure :	15,000 PSI

Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 15,000 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality Manager :	QUALITY	Technical Supervisor :	PRODUCTION
Date :	11/20/2014	Date :	11/20/2014
Signature :		Signature :	



POWERING PROGRESS™

Gates E&S North America, Inc.
134 - 44th St.
CORPUS CHRISTI, TEXAS 78405
PHONE : (361) 887-9807
FAX: (361) 887-0812
Tim.Cantu@gates.com

CERTIFICATE OF CONFORMANCE

This is to verify that all Parts and/or Materials included in this shipment have been manufactured and/or processed in Conformance with applicable drawings and specifications, and that Records of Required Tests are on file and subject to examination. The following items were assembled at Gates E & S, North America Inc., facilities in Corpus Christi, TX, USA. This hose assembly was designed and manufactured to meet all the requirements of API Spec 7K.

CUSTOMER: AUSTIN DISTRIBUTING
CUSTOMERS P.O.#: PENDING
PART DESCRIPTION: 10K3.566.0CK4.1/1610KFLGE/E L/E
SALES ORDER #: 205663
QUANTITY: 1
SERIAL #: D-112014-10





SIGNATURE:


TITLE:

DATE:

QUALITY

11/20/2014





ILL ASSEMBLY PRESSURE TEST CERTIFICATE

AUSTIN DISTRIBUTING	Test Date:	11/20/2014
PENDING	Hose Serial No.:	D 112014-10
205663	Created By:	NORMA MATA
10K3.566.0CK4.1/1610KFLGE/E L/E		
4 1/16 10K FLG	End Fitting 2:	4 1/16 10K FLG
4773-6291	Assembly Code:	L341160S0813D-112014-10
10,000 PSI	Test Pressure:	15,000 PSI

the following hose assembly has been tested to the





Gates E&S North America
134 - 44th St.
CORPUS CHRISTI, TEXAS 78405
PHONE : (361) 887-9807
FAX: (361) 887-0812
 Tim.Cantu@gates.com

[illegible]

Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Body
	From	To							
13.5"	0	975	10.75"	45.5	N80	BTC	5.54	1.20	23.44
9.875"	0	11750	7.625"	29.7	P110	BTC	1.29	1.11	3.11
6.75"	0	11250	5.5"	23	P110	BTC	1.95	2.04	3.25
6.75"	11250	17,212	5"	18	P110	BTC	1.95	2.04	3.25
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

Intermediate casing will be kept at least 1/3 full while running casing to mitigate collapse. Surface burst based on 0.7 frac gradient at the shoe with Gas Gradient 0.1 psi/ft to surface and
All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

The 5" casing will be run back 500' into the intermediate casing to ensure the coupling OD clearance is greater than .422" for the cement bond tie in.

Casing Program

Hole Size	Casing		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
	From	To							
17.5"	0	875	13.375"	54.5	J55	STC	2.82	1.27	10.78
12.25"	0	4000	9.625"	40	J55	LTC	1.22	1.00	3.25
12.25"	4000	4875	9.625"	40	L80	LTC	1.21	1.45	5.73
8.75"	0	14,768	5.5"	17	P110	LTC	1.50	2.69	2.54
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

Intermediate casing will be kept at least 1/3 full while running casing to mitigate collapse. Intermediate burst based on 0.7 frac gradient at the shoe with Gas Gradient 0.1 psi/ft to surface.
All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Body
	From	To							
13.5"	0	600	10.75"	45.5	N80	BTC	9.00	1.41	38.10
9.875"	0	10065	7.875"	29.7	P110	BTC	1.51	1.45	3.63
6.75"	0	9565	5.5"	23	P110	BTC	2.52	2.66	4.03
6.75"	9565	16,944	5"	18	P110	BTC	2.52	2.66	4.03
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

Intermediate casing will be kept at least 1/3 full while running casing to mitigate collapse. Surface burst based on 0.7 frac gradient at the shoe with Gas Gradient 0.1 psi/ft to surface and
All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

The 5" casing will be run back 500' into the intermediate casing to ensure the coupling OD clearance is greater than .422" for the cement bond tie in.

Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Body
	From	To							
13.5"	0	600	10.75"	45.5	N80	BTC	9.00	1.41	38.10
9.875"	0	10065	7.875"	29.7	P110	BTC	1.51	1.45	3.63
6.75"	0	9565	5.5"	23	P110	BTC	2.52	2.66	4.03
6.75"	9565	16,944	5"	18	P110	BTC	2.52	2.66	4.03
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

Intermediate casing will be kept at least 1/3 full while running casing to mitigate collapse. Surface burst based on 0.7 frac gradient at the shoe with Gas Gradient 0.1 psi/ft to surface and
All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

The 5" casing will be run back 500' into the intermediate casing to ensure the coupling OD clearance is greater than .422" for the cement bond tie in.

Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Body
	From	To							
13.5"	0	600	10.75"	45.5	N80	BTC	9.00	1.41	38.10
9.875"	0	10065	7.875"	29.7	P110	BTC	1.51	1.45	3.63
6.75"	0	9565	5.5"	23	P110	BTC	2.52	2.66	4.03
6.75"	9565	16,944	5"	18	P110	BTC	2.52	2.66	4.03
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

Intermediate casing will be kept at least 1/3 full while running casing to mitigate collapse. Surface burst based on 0.7 frac gradient at the shoe with Gas Gradient 0.1 psi/ft to surface and
All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

The 5" casing will be run back 500' into the intermediate casing to ensure the coupling OD clearance is greater than .422" for the cement bond tie in.

Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Body
	From	To							
13.5"	0	600	10.75"	45.5	N80	BTC	9.00	1.41	38.10
9.875"	0	10065	7.875"	29.7	P110	BTC	1.51	1.45	3.63
6.75"	0	9565	5.5"	23	P110	BTC	2.52	2.66	4.03
6.75"	9565	16,944	5"	18	P110	BTC	2.52	2.66	4.03
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

Intermediate casing will be kept at least 1/3 full while running casing to mitigate collapse. Surface burst based on 0.7 frac gradient at the shoe with Gas Gradient 0.1 psi/ft to surface and
All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

The 5" casing will be run back 500' into the intermediate casing to ensure the coupling OD clearance is greater than .422" for the cement bond tie in.

COG OPERATING LLC
HYDROGEN SULFIDE DRILLING OPERATIONS PLAN

1. HYDROGEN SULFIDE TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

- a. The hazards and characteristics of hydrogen sulfide (H₂S).
- b. The proper use and maintenance of personal protective equipment and life support systems.
- c. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
- d. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

- a. The effects of H₂S on metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
- b. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
- c. The contents and requirements of the H₂S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

2. H₂S SAFETY EQUIPMENT AND SYSTEMS

Note: All H₂S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H₂S. If H₂S greater than 100 ppm is encountered in the gas stream we will shut in and install H₂S equipment.

- a. Well Control Equipment:
 - Flare line.
 - Choke manifold with remotely operated choke.
 - Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
 - Auxiliary equipment to include: annular preventer, mud-gas separator, rotating head.

- b. Protective equipment for essential personnel:
Mark II Surviveair 30-minute units located in the dog house and at briefing areas.
- c. H2S detection and monitoring equipment:
2 - portable H2S monitor positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 ppm are reached.
- d. Visual warning systems:
Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.
- e. Mud Program:
The mud program has been designed to minimize the volume of H2S circulated to the surface.
- f. Metallurgy:
All drill strings, casings, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- g. Communication:
Company vehicles equipped with cellular telephone.

COG OPERATING LLC has conducted a review to determine if an H2S contingency plan is required for the above referenced well. We were able to conclude that any potential hazardous volume would be minimal. H2S concentrations of wells in this area from surface to TD are low enough; therefore, we do not believe that an H2S contingency plan is necessary.

W A R N I N G

**YOU ARE ENTERING AN H₂S AREA
AUTHORIZED PERSONNEL ONLY**

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED***
- 2. HARD HATS REQUIRED***
- 3. SMOKING IN DESIGNATED AREAS ONLY***
- 4. BE WIND CONSCIOUS AT ALL TIMES***
- 5. CK WITH COG OPERATING LLC FOREMAN AT MAIN OFFICE***

COG OPERATING LLC

1-575-748-6940

EMERGENCY CALL LIST


	<u>OFFICE</u>	<u>MOBILE</u>
COG OPERATING LLC OFFICE	575-748-6940	
SETH WILD	432-683-7443	432-528-3633
WALTER ROYE	575-748-6940	432-934-1886

EMERGENCY RESPONSE NUMBERS

	<u>OFFICE</u>
STATE POLICE	575-748-9718
EDDY COUNTY SHERIFF	575-746-2701
EMERGENCY MEDICAL SERVICES (AMBULANCE)	911 or 575-746-2701
EDDY COUNTY EMERGENCY MANAGEMENT (HARRY BURGESS)	575-887-9511
STATE EMERGENCY RESPONSE CENTER (SERC)	575-476-9620
CARLSBAD POLICE DEPARTMENT	575-885-2111
CARLSBAD FIRE DEPARTMENT	575-885-3125
NEW MEXICO OIL CONSERVATION DIVISION	575-748-1283
INDIAN FIRE & SAFETY	800-530-8693
HALLIBURTON SERVICES	800-844-8451

COG Operating LLC
H₂S Equipment Schematic
Terrain: Shinnery sand hills.

Well pad will be 400' x 400'
with cellar in center of pad



COG OPERATING, LLC

Eddy County, NM (NAD27) NMZ

Littlefield 33 Fed COM

#806H

OH

Plan: Plan #1 - IP

8

Standard Planning Report

12 March, 2018

Planning Report

Database: EDM 5000.14 Single User Db
Company: COG OPERATING, LLC
Project: Eddy County, NM (NAD27) NMZ
Site: Littlefield 33 Fed COM
Well: #806H
Wellbore: OH
Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Project	Eddy County, NM (NAD27) NMZ		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site		Littlefield 33 Fed COM			
Site Position:		Northing:	364,187.75 usft	Latitude:	32° 0' 2.885 N
From:	Map	Easting:	606,400.58 usft	Longitude:	103° 59' 24.352 W
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "	Grid Convergence:	0.18 °

Well	#806H					
Well Position	+N/-S	0.03 usft	Northing:	364,187.78 usft	Latitude:	32° 0' 2.884 N
	+E/-W	45.01 usft	Easting:	606,445.59 usft	Longitude:	103° 59' 23.829 W
Position Uncertainty		0.00 usft	Wellhead Elevation:		Ground Level:	2,858.00 usft

Wellbore	OH					
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)	
	IGRF2015	03/12/18	7.05	59.78	47,689.68280947	

Design	Plan #1 - IP				
Audit Notes:					
Version:	Phase:	PLAN	Tie On Depth:	0.00	
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)	
	10,902.00	0.00	0.00	0.53	

Plan Survey Tool Program	Date 03/12/18				
Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks	
1	0.00	17,882.45 Plan #1 - IP (OH)	MWD	MWD v3:standard declination	

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Bulld Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,566.67	1.00	245.00	1,566.66	-0.25	-0.53	1.50	1.50	0.00	245.00	
9,434.54	1.00	245.00	9,433.34	-58.28	-124.98	0.00	0.00	0.00	0.00	
9,501.21	0.00	0.00	9,500.00	-58.52	-125.50	1.50	-1.50	0.00	180.00	
10,342.35	0.00	0.00	10,341.14	-58.52	-125.50	0.00	0.00	0.00	0.00	
11,157.44	89.66	338.70	10,862.00	423.89	-313.59	11.00	11.00	0.00	338.70	
12,248.87	89.66	0.53	10,868.56	1,490.94	-509.15	2.00	0.00	2.00	90.07	
17,882.45	89.66	0.53	10,902.00	7,124.18	-457.13	0.00	0.00	0.00	0.00	PBHL(L33FC#806H)

Planning Report

Database: EDM 5000.14 Single User Db
 Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Site: Littlefield 33 Fed COM
 Well: #806H
 Wellbore: OH
 Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
SHL(L33FC#806H) - FTP(L33FC#806H)									
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,566.67	1.00	245.00	1,566.66	-0.25	-0.53	-0.25	1.50	1.50	0.00
1,600.00	1.00	245.00	1,599.99	-0.49	-1.05	-0.50	0.00	0.00	0.00
1,700.00	1.00	245.00	1,699.98	-1.23	-2.64	-1.25	0.00	0.00	0.00
1,800.00	1.00	245.00	1,799.96	-1.97	-4.22	-2.01	0.00	0.00	0.00
1,900.00	1.00	245.00	1,899.95	-2.70	-5.80	-2.76	0.00	0.00	0.00
2,000.00	1.00	245.00	1,999.93	-3.44	-7.38	-3.51	0.00	0.00	0.00
2,100.00	1.00	245.00	2,099.92	-4.18	-8.96	-4.26	0.00	0.00	0.00
2,200.00	1.00	245.00	2,199.90	-4.92	-10.54	-5.01	0.00	0.00	0.00
2,300.00	1.00	245.00	2,299.88	-5.65	-12.13	-5.77	0.00	0.00	0.00
2,400.00	1.00	245.00	2,399.87	-6.39	-13.71	-6.52	0.00	0.00	0.00
2,500.00	1.00	245.00	2,499.85	-7.13	-15.29	-7.27	0.00	0.00	0.00
2,600.00	1.00	245.00	2,599.84	-7.87	-16.87	-8.02	0.00	0.00	0.00
2,700.00	1.00	245.00	2,699.82	-8.60	-18.45	-8.78	0.00	0.00	0.00
2,800.00	1.00	245.00	2,799.81	-9.34	-20.04	-9.53	0.00	0.00	0.00
2,900.00	1.00	245.00	2,899.79	-10.08	-21.62	-10.28	0.00	0.00	0.00
3,000.00	1.00	245.00	2,999.78	-10.82	-23.20	-11.03	0.00	0.00	0.00
3,100.00	1.00	245.00	3,099.76	-11.56	-24.78	-11.78	0.00	0.00	0.00
3,200.00	1.00	245.00	3,199.75	-12.29	-26.36	-12.54	0.00	0.00	0.00
3,300.00	1.00	245.00	3,299.73	-13.03	-27.94	-13.29	0.00	0.00	0.00
3,400.00	1.00	245.00	3,399.72	-13.77	-29.53	-14.04	0.00	0.00	0.00
3,500.00	1.00	245.00	3,499.70	-14.51	-31.11	-14.79	0.00	0.00	0.00
3,600.00	1.00	245.00	3,599.69	-15.24	-32.69	-15.54	0.00	0.00	0.00
3,700.00	1.00	245.00	3,699.67	-15.98	-34.27	-16.30	0.00	0.00	0.00
3,800.00	1.00	245.00	3,799.66	-16.72	-35.85	-17.05	0.00	0.00	0.00
3,900.00	1.00	245.00	3,899.64	-17.46	-37.43	-17.80	0.00	0.00	0.00
4,000.00	1.00	245.00	3,999.63	-18.19	-39.02	-18.55	0.00	0.00	0.00
4,100.00	1.00	245.00	4,099.61	-18.93	-40.60	-19.31	0.00	0.00	0.00
4,200.00	1.00	245.00	4,199.60	-19.67	-42.18	-20.06	0.00	0.00	0.00
4,300.00	1.00	245.00	4,299.58	-20.41	-43.76	-20.81	0.00	0.00	0.00
4,400.00	1.00	245.00	4,399.57	-21.14	-45.34	-21.56	0.00	0.00	0.00
4,500.00	1.00	245.00	4,499.55	-21.88	-46.92	-22.31	0.00	0.00	0.00
4,600.00	1.00	245.00	4,599.53	-22.62	-48.51	-23.07	0.00	0.00	0.00
4,700.00	1.00	245.00	4,699.52	-23.36	-50.09	-23.82	0.00	0.00	0.00
4,800.00	1.00	245.00	4,799.50	-24.09	-51.67	-24.57	0.00	0.00	0.00
4,900.00	1.00	245.00	4,899.49	-24.83	-53.25	-25.32	0.00	0.00	0.00
5,000.00	1.00	245.00	4,999.47	-25.57	-54.83	-26.08	0.00	0.00	0.00
5,100.00	1.00	245.00	5,099.46	-26.31	-56.41	-26.83	0.00	0.00	0.00

Planning Report

Database: EDM 5000.14 Single User Db
 Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Site: Littlefield 33 Fed COM
 Well: #806H
 Wellbore: OH
 Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,200.00	1.00	245.00	5,199.44	-27.04	-58.00	-27.58	0.00	0.00	0.00
5,300.00	1.00	245.00	5,299.43	-27.78	-59.58	-28.33	0.00	0.00	0.00
5,400.00	1.00	245.00	5,399.41	-28.52	-61.16	-29.08	0.00	0.00	0.00
5,500.00	1.00	245.00	5,499.40	-29.26	-62.74	-29.84	0.00	0.00	0.00
5,600.00	1.00	245.00	5,599.38	-29.99	-64.32	-30.59	0.00	0.00	0.00
5,700.00	1.00	245.00	5,699.37	-30.73	-65.91	-31.34	0.00	0.00	0.00
5,800.00	1.00	245.00	5,799.35	-31.47	-67.49	-32.09	0.00	0.00	0.00
5,900.00	1.00	245.00	5,899.34	-32.21	-69.07	-32.84	0.00	0.00	0.00
6,000.00	1.00	245.00	5,999.32	-32.94	-70.65	-33.60	0.00	0.00	0.00
6,100.00	1.00	245.00	6,099.31	-33.68	-72.23	-34.35	0.00	0.00	0.00
6,200.00	1.00	245.00	6,199.29	-34.42	-73.81	-35.10	0.00	0.00	0.00
6,300.00	1.00	245.00	6,299.28	-35.16	-75.40	-35.85	0.00	0.00	0.00
6,400.00	1.00	245.00	6,399.26	-35.90	-76.98	-36.61	0.00	0.00	0.00
6,500.00	1.00	245.00	6,499.25	-36.63	-78.56	-37.36	0.00	0.00	0.00
6,600.00	1.00	245.00	6,599.23	-37.37	-80.14	-38.11	0.00	0.00	0.00
6,700.00	1.00	245.00	6,699.21	-38.11	-81.72	-38.86	0.00	0.00	0.00
6,800.00	1.00	245.00	6,799.20	-38.85	-83.30	-39.61	0.00	0.00	0.00
6,900.00	1.00	245.00	6,899.18	-39.58	-84.89	-40.37	0.00	0.00	0.00
7,000.00	1.00	245.00	6,999.17	-40.32	-86.47	-41.12	0.00	0.00	0.00
7,100.00	1.00	245.00	7,099.15	-41.06	-88.05	-41.87	0.00	0.00	0.00
7,200.00	1.00	245.00	7,199.14	-41.80	-89.63	-42.62	0.00	0.00	0.00
7,300.00	1.00	245.00	7,299.12	-42.53	-91.21	-43.38	0.00	0.00	0.00
7,400.00	1.00	245.00	7,399.11	-43.27	-92.79	-44.13	0.00	0.00	0.00
7,500.00	1.00	245.00	7,499.09	-44.01	-94.38	-44.88	0.00	0.00	0.00
7,600.00	1.00	245.00	7,599.08	-44.75	-95.96	-45.63	0.00	0.00	0.00
7,700.00	1.00	245.00	7,699.06	-45.48	-97.54	-46.38	0.00	0.00	0.00
7,800.00	1.00	245.00	7,799.05	-46.22	-99.12	-47.14	0.00	0.00	0.00
7,900.00	1.00	245.00	7,899.03	-46.96	-100.70	-47.89	0.00	0.00	0.00
8,000.00	1.00	245.00	7,999.02	-47.70	-102.28	-48.64	0.00	0.00	0.00
8,100.00	1.00	245.00	8,099.00	-48.43	-103.87	-49.39	0.00	0.00	0.00
8,200.00	1.00	245.00	8,198.99	-49.17	-105.45	-50.14	0.00	0.00	0.00
8,300.00	1.00	245.00	8,298.97	-49.91	-107.03	-50.90	0.00	0.00	0.00
8,400.00	1.00	245.00	8,398.96	-50.65	-108.61	-51.65	0.00	0.00	0.00
8,500.00	1.00	245.00	8,498.94	-51.38	-110.19	-52.40	0.00	0.00	0.00
8,600.00	1.00	245.00	8,598.93	-52.12	-111.78	-53.15	0.00	0.00	0.00
8,700.00	1.00	245.00	8,698.91	-52.86	-113.36	-53.91	0.00	0.00	0.00
8,800.00	1.00	245.00	8,798.90	-53.60	-114.94	-54.66	0.00	0.00	0.00
8,900.00	1.00	245.00	8,898.88	-54.33	-116.52	-55.41	0.00	0.00	0.00
9,000.00	1.00	245.00	8,998.86	-55.07	-118.10	-56.16	0.00	0.00	0.00
9,100.00	1.00	245.00	9,098.85	-55.81	-119.68	-56.91	0.00	0.00	0.00
9,200.00	1.00	245.00	9,198.83	-56.55	-121.27	-57.67	0.00	0.00	0.00
9,300.00	1.00	245.00	9,298.82	-57.28	-122.85	-58.42	0.00	0.00	0.00
9,400.00	1.00	245.00	9,398.80	-58.02	-124.43	-59.17	0.00	0.00	0.00
9,434.54	1.00	245.00	9,433.34	-58.28	-124.98	-59.43	0.00	0.00	0.00
9,501.21	0.00	0.00	9,500.00	-58.52	-125.50	-59.68	1.50	-1.50	0.00
9,600.00	0.00	0.00	9,598.80	-58.52	-125.50	-59.68	0.00	0.00	0.00
9,700.00	0.00	0.00	9,698.80	-58.52	-125.50	-59.68	0.00	0.00	0.00
9,800.00	0.00	0.00	9,798.80	-58.52	-125.50	-59.68	0.00	0.00	0.00
9,900.00	0.00	0.00	9,898.80	-58.52	-125.50	-59.68	0.00	0.00	0.00
10,000.00	0.00	0.00	9,998.80	-58.52	-125.50	-59.68	0.00	0.00	0.00
10,100.00	0.00	0.00	10,098.80	-58.52	-125.50	-59.68	0.00	0.00	0.00
10,200.00	0.00	0.00	10,198.80	-58.52	-125.50	-59.68	0.00	0.00	0.00
10,300.00	0.00	0.00	10,298.80	-58.52	-125.50	-59.68	0.00	0.00	0.00
10,342.35	0.00	0.00	10,341.15	-58.52	-125.50	-59.68	0.00	0.00	0.00

Planning Report

Database: EDM 5000.14 Single User Db
Company: COG OPERATING, LLC
Project: Eddy County, NM (NAD27) NMZ
Site: Littlefield 33 Fed COM
Well: #806H
Wellbore: OH
Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
KOP: 10342.35' MD, 10341.14' TVD									
10,350.00	0.84	338.70	10,348.79	-58.47	-125.52	-59.63	11.01	11.01	0.00
10,400.00	6.34	338.70	10,398.68	-55.55	-126.66	-56.72	11.00	11.00	0.00
10,450.00	11.84	338.70	10,448.03	-48.19	-129.53	-49.39	11.00	11.00	0.00
10,500.00	17.34	338.70	10,496.40	-36.46	-134.10	-37.70	11.00	11.00	0.00
10,550.00	22.84	338.70	10,543.34	-20.47	-140.34	-21.76	11.00	11.00	0.00
10,600.00	28.34	338.70	10,588.42	-0.35	-148.18	-1.72	11.00	11.00	0.00
10,650.00	33.84	338.70	10,631.22	23.70	-157.56	22.24	11.00	11.00	0.00
10,700.00	39.34	338.70	10,671.35	51.46	-168.38	49.90	11.00	11.00	0.00
10,750.00	44.84	338.70	10,708.43	82.67	-180.55	81.00	11.00	11.00	0.00
10,800.00	50.34	338.70	10,742.14	117.05	-193.96	115.25	11.00	11.00	0.00
10,850.00	55.84	338.70	10,772.16	154.29	-208.47	152.35	11.00	11.00	0.00
10,900.00	61.34	338.70	10,798.20	194.03	-223.97	191.95	11.00	11.00	0.00
10,950.00	66.84	338.70	10,820.04	235.92	-240.30	233.69	11.00	11.00	0.00
11,000.00	72.34	338.70	10,837.47	279.56	-257.32	277.17	11.00	11.00	0.00
11,050.00	77.84	338.70	10,850.33	324.56	-274.86	322.01	11.00	11.00	0.00
11,100.00	83.34	338.70	10,858.50	370.50	-292.77	367.78	11.00	11.00	0.00
11,150.00	88.84	338.70	10,861.90	416.96	-310.89	414.07	11.00	11.00	0.00
11,157.44	89.66	338.70	10,862.00	423.89	-313.59	420.97	10.99	10.99	0.00
EOC: 11157.44' MD, 10862.00' TVD, 89.66° INC, 338.70° AZ, 420.97' VS									
11,200.00	89.66	339.55	10,862.25	463.66	-328.75	460.60	2.00	0.00	2.00
11,300.00	89.66	341.55	10,862.85	557.94	-362.05	554.57	2.00	0.00	2.00
11,400.00	89.66	343.55	10,863.45	653.34	-392.03	649.68	2.00	0.00	2.00
11,500.00	89.65	345.55	10,864.05	749.72	-418.67	745.81	2.00	0.00	2.00
11,600.00	89.65	347.55	10,864.66	846.97	-441.92	842.84	2.00	0.00	2.00
11,700.00	89.65	349.55	10,865.26	944.97	-461.77	940.66	2.00	0.00	2.00
11,800.00	89.65	351.55	10,865.87	1,043.61	-478.18	1,039.14	2.00	0.00	2.00
11,900.00	89.65	353.55	10,866.47	1,142.76	-491.15	1,138.17	2.00	0.00	2.00
12,000.00	89.66	355.55	10,867.07	1,242.30	-500.64	1,237.62	2.00	0.00	2.00
12,100.00	89.66	357.55	10,867.67	1,342.11	-506.65	1,337.37	2.00	0.00	2.00
12,200.00	89.66	359.55	10,868.27	1,442.07	-509.18	1,437.30	2.00	0.00	2.00
12,248.87	89.66	0.53	10,868.56	1,490.94	-509.15	1,486.17	2.00	0.00	2.00
12,300.00	89.66	0.53	10,868.86	1,542.07	-508.68	1,537.30	0.00	0.00	0.00
12,400.00	89.66	0.53	10,869.46	1,642.06	-507.75	1,637.29	0.00	0.00	0.00
12,500.00	89.66	0.53	10,870.05	1,742.06	-506.83	1,737.29	0.00	0.00	0.00
12,600.00	89.66	0.53	10,870.64	1,842.05	-505.91	1,837.29	0.00	0.00	0.00
12,700.00	89.66	0.53	10,871.24	1,942.04	-504.98	1,937.29	0.00	0.00	0.00
12,800.00	89.66	0.53	10,871.83	2,042.04	-504.06	2,037.29	0.00	0.00	0.00
12,900.00	89.66	0.53	10,872.42	2,142.03	-503.14	2,137.29	0.00	0.00	0.00
13,000.00	89.66	0.53	10,873.02	2,242.03	-502.21	2,237.28	0.00	0.00	0.00
13,100.00	89.66	0.53	10,873.61	2,342.02	-501.29	2,337.28	0.00	0.00	0.00
13,200.00	89.66	0.53	10,874.20	2,442.01	-500.37	2,437.28	0.00	0.00	0.00
13,300.00	89.66	0.53	10,874.80	2,542.01	-499.44	2,537.28	0.00	0.00	0.00
13,400.00	89.66	0.53	10,875.39	2,642.00	-498.52	2,637.28	0.00	0.00	0.00
13,500.00	89.66	0.53	10,875.99	2,742.00	-497.60	2,737.28	0.00	0.00	0.00
13,600.00	89.66	0.53	10,876.58	2,841.99	-496.67	2,837.27	0.00	0.00	0.00
13,700.00	89.66	0.53	10,877.17	2,941.98	-495.75	2,937.27	0.00	0.00	0.00
13,800.00	89.66	0.53	10,877.77	3,041.98	-494.83	3,037.27	0.00	0.00	0.00
13,900.00	89.66	0.53	10,878.36	3,141.97	-493.90	3,137.27	0.00	0.00	0.00
14,000.00	89.66	0.53	10,878.95	3,241.97	-492.98	3,237.27	0.00	0.00	0.00
14,100.00	89.66	0.53	10,879.55	3,341.96	-492.06	3,337.26	0.00	0.00	0.00
14,200.00	89.66	0.53	10,880.14	3,441.95	-491.13	3,437.26	0.00	0.00	0.00
14,300.00	89.66	0.53	10,880.73	3,541.95	-490.21	3,537.26	0.00	0.00	0.00
14,400.00	89.66	0.53	10,881.33	3,641.94	-489.29	3,637.26	0.00	0.00	0.00

Planning Report

Database: EDM 5000.14 Single User Db
 Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Site: Littlefield 33 Fed COM
 Well: #806H
 Wellbore: OH
 Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
14,500.00	89.66	0.53	10,881.92	3,741.94	-488.36	3,737.26	0.00	0.00	0.00
14,600.00	89.66	0.53	10,882.52	3,841.93	-487.44	3,837.26	0.00	0.00	0.00
14,700.00	89.66	0.53	10,883.11	3,941.92	-486.52	3,937.25	0.00	0.00	0.00
14,800.00	89.66	0.53	10,883.70	4,041.92	-485.59	4,037.25	0.00	0.00	0.00
14,900.00	89.66	0.53	10,884.30	4,141.91	-484.67	4,137.25	0.00	0.00	0.00
15,000.00	89.66	0.53	10,884.89	4,241.91	-483.75	4,237.25	0.00	0.00	0.00
15,100.00	89.66	0.53	10,885.48	4,341.90	-482.82	4,337.25	0.00	0.00	0.00
15,200.00	89.66	0.53	10,886.08	4,441.89	-481.90	4,437.25	0.00	0.00	0.00
15,300.00	89.66	0.53	10,886.67	4,541.89	-480.98	4,537.24	0.00	0.00	0.00
15,400.00	89.66	0.53	10,887.26	4,641.88	-480.05	4,637.24	0.00	0.00	0.00
15,500.00	89.66	0.53	10,887.86	4,741.88	-479.13	4,737.24	0.00	0.00	0.00
15,600.00	89.66	0.53	10,888.45	4,841.87	-478.21	4,837.24	0.00	0.00	0.00
15,700.00	89.66	0.53	10,889.05	4,941.86	-477.28	4,937.24	0.00	0.00	0.00
15,800.00	89.66	0.53	10,889.64	5,041.86	-476.36	5,037.24	0.00	0.00	0.00
15,900.00	89.66	0.53	10,890.23	5,141.85	-475.44	5,137.23	0.00	0.00	0.00
16,000.00	89.66	0.53	10,890.83	5,241.85	-474.51	5,237.23	0.00	0.00	0.00
16,100.00	89.66	0.53	10,891.42	5,341.84	-473.59	5,337.23	0.00	0.00	0.00
16,200.00	89.66	0.53	10,892.01	5,441.83	-472.66	5,437.23	0.00	0.00	0.00
16,300.00	89.66	0.53	10,892.61	5,541.83	-471.74	5,537.23	0.00	0.00	0.00
16,400.00	89.66	0.53	10,893.20	5,641.82	-470.82	5,637.22	0.00	0.00	0.00
16,500.00	89.66	0.53	10,893.79	5,741.81	-469.89	5,737.22	0.00	0.00	0.00
16,600.00	89.66	0.53	10,894.39	5,841.81	-468.97	5,837.22	0.00	0.00	0.00
16,700.00	89.66	0.53	10,894.98	5,941.80	-468.05	5,937.22	0.00	0.00	0.00
16,800.00	89.66	0.53	10,895.57	6,041.80	-467.12	6,037.22	0.00	0.00	0.00
16,900.00	89.66	0.53	10,896.17	6,141.79	-466.20	6,137.22	0.00	0.00	0.00
17,000.00	89.66	0.53	10,896.76	6,241.78	-465.28	6,237.21	0.00	0.00	0.00
17,100.00	89.66	0.53	10,897.36	6,341.78	-464.35	6,337.21	0.00	0.00	0.00
17,200.00	89.66	0.53	10,897.95	6,441.77	-463.43	6,437.21	0.00	0.00	0.00
17,300.00	89.66	0.53	10,898.54	6,541.77	-462.51	6,537.21	0.00	0.00	0.00
17,400.00	89.66	0.53	10,899.14	6,641.76	-461.58	6,637.21	0.00	0.00	0.00
17,500.00	89.66	0.53	10,899.73	6,741.75	-460.66	6,737.21	0.00	0.00	0.00
17,600.00	89.66	0.53	10,900.32	6,841.75	-459.74	6,837.20	0.00	0.00	0.00
17,700.00	89.66	0.53	10,900.92	6,941.74	-458.81	6,937.20	0.00	0.00	0.00
17,800.00	89.66	0.53	10,901.51	7,041.74	-457.89	7,037.20	0.00	0.00	0.00
17,882.45	89.66	0.53	10,902.00	7,124.18	-457.13	7,119.65	0.00	0.00	0.00

TD: 17882.45' MD, 10902.00' TVD - PBHL(L33FC#806H)

Design Targets

Target Name *	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
SHL(L33FC#806H) - hit/miss target - Shape - Point	0.00	0.00	0.00	0.00	0.00	364,187.78	606,445.59	32° 0' 2.884 N	103° 59' 23.829 W
FTP(L33FC#806H) - plan misses target center by 522.97usft at 0.00usft MD (0.00 TVD, 0.00 N, 0.00 E) - Point	0.00	0.00	0.00	29.08	-522.16	364,216.86	605,923.43	32° 0' 3.188 N	103° 59' 29.892 W
PBHL(L33FC#806H) - plan hits target center - Point	0.00	0.00	10,902.00	7,124.18	-457.13	371,311.96	605,988.46	32° 1' 13.403 N	103° 59' 28.876 W


Planning Report

Database: EDM 5000.14 Single User Db
Company: COG OPERATING, LLC
Project: Eddy County, NM (NAD27) NMZ
Site: Littlefield 33 Fed COM
Well: #806H
Wellbore: OH
Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
10,342.35	10,341.15	-58.52	-125.50	KOP: 10342.35' MD, 10341.14' TVD
11,157.44	10,862.00	423.89	-313.59	EOC: 11157.44' MD, 10862.00' TVD, 89.66° INC, 338.70° AZ, 420.97' VS
17,882.45	10,902.00	7,124.18	-457.13	TD: 17882.45' MD, 10902.00' TVD



COG OPERATING, LLC
#806H
Eddy County, NM (NAD27) NMZ
Plan #1 - IP

PROJECT DETAILS: Eddy County, NM (NAD27) NMZ
Geodetic System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone: New Mexico East 3001
System Datum: Mean Sea Level

Ground Elev: 2858.00
Northing
364187.78
RKB @ 2883.00usft (Latahwa 44 - KB=25')
Easting
606445.59
Latitude
32° 0' 2.884 N
Longitude
103° 59' 23.829 W

WELLBORE TARGET DETAILS (MAP CO-ORDINATES AND LAT/LONG)					
Name	TVD	+N/-S	+E/-W	Northing	Easting
FTP(L33FC#806H)	0.00	29.08	-522.16	364216.86	605923.43
SHL(L33FC#806H)	0.00	0.00	0.00	364187.78	606445.59
PBHL(L33FC#806H)	10902.00	7124.18	-457.13	371311.96	605988.46


SECTION DETAILS									
Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2	1500.00	0.00	0.00	1500.00	0.00	0.00	0.00	0.00	0.00
3	1566.67	1.00	245.00	1566.66	-0.25	-0.63	1.50	245.00	-0.25
4	9434.54	1.00	245.00	9433.34	-58.28	-124.98	0.00	0.00	-59.43
5	9501.21	0.00	0.00	9500.00	-58.52	-125.50	1.50	180.00	-59.68
6	10342.35	0.00	0.00	10341.14	-58.52	-125.50	0.00	0.00	-59.68
7	11157.44	89.66	338.70	10862.00	423.89	-313.59	11.00	338.70	420.97
8	12248.87	89.66	0.53	10868.56	1490.94	-509.15	2.00	90.07	1486.17
9	17882.45	89.66	0.53	10902.00	7124.18	-457.13	0.00	0.00	7119.65

KOP: 10342.35' MD, 10341.14' TVD

PBHL(L33FC#806H)

EOC: 11157.44' MD, 10862.00' TVD, 89.66° INC, 338.70° AZ, 420.97° VS

Vertical Section at 0.53° (600 usft/in)



TD: 17882.45' MD, 10902.00' TVD

PBHL(L33FC#806H)

23:20, March 12 2018

Well Planning: Gabriel Cruz

COG OPERATING, LLC

Eddy County, NM (NAD27) NMZ

Littlefield 33 Fed COM

#806H

OH

Plan #1 - IP

Anticollision Report

12 March, 2018

Anticollision Report

Company:	COG OPERATING, LLC	Local Co-ordinate Reference:	Well #806H
Project:	Eddy County, NM (NAD27) NMZ	TVD Reference:	RKB @ 2883.00usft (Latshaw 44 - KB=25')
Reference Site:	Littlefield 33 Fed COM	MD Reference:	RKB @ 2883.00usft (Latshaw 44 - KB=25')
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	#806H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.000 sigma
Reference Wellbore	OH	Database:	EDM 5000.14 Single User Db
Reference Design:	Plan #1 - IP	Offset TVD Reference:	Offset Datum

Reference	Plan #1 - IP
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria
Interpolation Method:	Stations
Depth Range:	Unlimited
Results Limited by:	Maximum center-center distance of 9,999.98 usft
Warning Levels Evaluated at:	2.000 Sigma
Error Model:	ISCWSA
Scan Method:	Closest Approach 3D
Error Surface:	Pedal Curve
Casing Method:	Not applied

Survey Tool Program	Date	03/12/18
From (usft)	To (usft)	Survey (Wellbore)
0.00	17,882.45	Plan #1 - IP (OH)
Tool Name	Description	
MWD	MWD v3:standard declination	

Summary						
Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
Littlefield 33 Fed COM						
#705H - OH - Plan #1 - IP	2,808.15	2,809.10	43.96	32.11	3.710	CC
#705H - OH - Plan #1 - IP	7,100.00	7,100.83	54.62	23.75	1.770	ES
#705H - OH - Plan #1 - IP	9,501.21	9,501.41	66.81	25.13	1.603	SF
#706H - OH - Plan #1 - IP	1,500.00	1,499.70	45.01	38.55	6.966	CC
#706H - OH - Plan #1 - IP	4,500.00	4,501.17	54.43	35.13	2.821	ES
#706H - OH - Plan #1 - IP	9,501.21	9,500.90	82.36	40.54	1.970	SF
#805H - OH - Plan #1 - IP	1,500.00	1,500.70	89.97	83.51	13.920	CC, ES
#805H - OH - Plan #1 - IP	17,877.86	17,758.63	612.12	344.85	2.290	SF

Offset Design Littlefield 33 Fed COM - #705H - OH - Plan #1 - IP													Offset Site Error:	0.00 usft
Survey Program: 0-MWD													Offset Well Error:	0.00 usft
Reference	Offset	Semi Major Axis	Reference	Offset	Highside	Offset Wellbore Centre	Distance	Minimum	Separation	Warning				
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Tooface (")	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Separation (usft)	Factor		
0.00	0.00	0.20	0.20	0.00	0.00	89.86	0.11	45.01	45.01					
100.00	100.00	100.20	100.20	0.08	0.08	89.86	0.11	45.01	45.01	44.84	.169	266.294		
200.00	200.00	200.20	200.20	0.31	0.31	89.86	0.11	45.01	45.01	44.39	.619	72.766		
300.00	300.00	300.20	300.20	0.53	0.53	89.86	0.11	45.01	45.01	43.94	1.068	42.141		
400.00	400.00	400.20	400.20	0.76	0.76	89.86	0.11	45.01	45.01	43.49	1.518	29.658		
500.00	500.00	500.20	500.20	0.98	0.98	89.86	0.11	45.01	45.01	43.04	1.967	22.881		
600.00	600.00	600.20	600.20	1.21	1.21	89.86	0.11	45.01	45.01	42.59	2.417	18.625		
700.00	700.00	700.20	700.20	1.43	1.43	89.86	0.11	45.01	45.01	42.14	2.866	15.704		
800.00	800.00	800.20	800.20	1.66	1.66	89.86	0.11	45.01	45.01	41.69	3.316	13.575		
900.00	900.00	900.20	900.20	1.88	1.88	89.86	0.11	45.01	45.01	41.24	3.765	11.954		
1,000.00	1,000.00	1,000.20	1,000.20	2.11	2.11	89.86	0.11	45.01	45.01	40.80	4.215	10.679		
1,100.00	1,100.00	1,100.20	1,100.20	2.33	2.33	89.86	0.11	45.01	45.01	40.35	4.664	9.650		
1,200.00	1,200.00	1,200.20	1,200.20	2.56	2.56	89.86	0.11	45.01	45.01	39.90	5.114	8.802		
1,300.00	1,300.00	1,300.20	1,300.20	2.78	2.78	89.86	0.11	45.01	45.01	39.45	5.563	8.090		
1,400.00	1,400.00	1,400.20	1,400.20	3.01	3.01	89.86	0.11	45.01	45.01	39.00	6.013	7.486		
1,500.00	1,500.00	1,500.20	1,500.20	3.23	3.23	89.86	0.11	45.01	45.01	38.55	6.462	6.965		
1,566.67	1,566.66	1,567.66	1,567.66	3.37	3.37	-155.46	0.11	44.41	44.95	38.21	6.740	6.669		
1,600.00	1,599.99	1,600.98	1,600.98	3.43	3.44	-155.77	0.11	43.83	44.89	38.03	6.867	6.538		
1,700.00	1,699.98	1,700.98	1,700.98	3.62	3.64	-156.72	0.11	42.08	44.75	37.49	7.254	6.168		
1,800.00	1,799.96	1,800.98	1,800.94	3.81	3.84	-157.67	0.11	40.34	44.61	36.96	7.648	5.833		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Reference Site: Littlefield 33 Fed COM
 Site Error: 0.00 usft
 Reference Well: #806H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.000 sigma
 Database: EDM 5000.14 Single User Db
 Offset TVD Reference: Offset Datum

Offset Design Littlefield 33 Fed COM - #705H - OH - Plan #1 - IP													Offset Site Error: 0.00 usft
Survey Program: 0-MWD													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (")	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
1,900.00	1,899.95	1,900.98	1,900.92	4.01	4.05	-158.63	0.11	38.59	44.49	36.44	8.048	5.528	
2,000.00	1,999.93	2,000.97	2,000.90	4.21	4.26	-159.59	0.11	36.85	44.38	35.93	8.454	5.250	
2,100.00	2,099.92	2,100.97	2,100.88	4.41	4.47	-160.56	0.11	35.10	44.28	35.42	8.863	4.996	
2,200.00	2,199.90	2,200.97	2,200.87	4.62	4.68	-161.54	0.11	33.36	44.20	34.92	9.276	4.764	
2,300.00	2,299.88	2,300.96	2,300.85	4.82	4.89	-162.51	0.11	31.61	44.12	34.43	9.693	4.552	
2,400.00	2,399.87	2,400.96	2,400.83	5.03	5.10	-163.49	0.11	29.87	44.07	33.95	10.113	4.357	
2,500.00	2,499.85	2,500.96	2,500.81	5.24	5.32	-164.47	0.11	28.12	44.02	33.48	10.535	4.179	
2,600.00	2,599.84	2,600.96	2,600.79	5.45	5.54	-165.45	0.11	26.38	43.99	33.03	10.959	4.014	
2,700.00	2,699.82	2,700.95	2,700.78	5.67	5.75	-166.44	0.11	24.63	43.96	32.58	11.385	3.862	
2,800.00	2,799.81	2,800.95	2,800.76	5.88	5.97	-167.42	0.11	22.89	43.96	32.14	11.813	3.721	
2,808.15	2,807.96	2,809.10	2,808.91	5.90	5.99	-167.50	0.11	22.74	43.96	32.11	11.848	3.710 CC	
2,900.00	2,899.79	2,900.95	2,900.74	6.09	6.19	-168.41	0.11	21.14	43.96	31.72	12.243	3.591	
3,000.00	2,999.78	3,000.94	3,000.72	6.31	6.41	-169.39	0.11	19.40	43.98	31.31	12.674	3.470	
3,100.00	3,099.76	3,100.94	3,100.70	6.53	6.63	-170.37	0.11	17.65	44.01	30.91	13.106	3.358	
3,200.00	3,199.75	3,200.94	3,200.69	6.74	6.85	-171.35	0.11	15.91	44.06	30.52	13.540	3.254	
3,300.00	3,299.73	3,300.94	3,300.67	6.96	7.07	-172.33	0.11	14.16	44.11	30.14	13.974	3.157	
3,400.00	3,399.72	3,400.93	3,400.65	7.18	7.29	-173.31	0.11	12.42	44.18	29.77	14.410	3.066	
3,500.00	3,499.70	3,500.93	3,500.63	7.40	7.51	-174.28	0.11	10.67	44.27	29.42	14.846	2.982	
3,600.00	3,599.69	3,600.93	3,600.61	7.62	7.73	-175.25	0.11	8.93	44.36	29.08	15.284	2.903	
3,700.00	3,699.67	3,700.92	3,700.60	7.84	7.95	-176.22	0.11	7.18	44.47	28.75	15.722	2.829	
3,800.00	3,799.66	3,800.92	3,800.58	8.06	8.18	-177.18	0.11	5.44	44.59	28.43	16.160	2.759	
3,900.00	3,899.64	3,900.92	3,900.56	8.28	8.40	-178.13	0.11	3.69	44.72	28.12	16.600	2.694	
4,000.00	3,999.63	4,000.92	4,000.54	8.50	8.62	-179.08	0.11	1.94	44.87	27.83	17.040	2.633	
4,100.00	4,099.61	4,100.91	4,100.52	8.72	8.84	-179.98	0.11	0.20	45.03	27.55	17.480	2.576	
4,200.00	4,199.60	4,200.91	4,200.50	8.94	9.07	-179.05	0.11	-1.55	45.20	27.28	17.922	2.522	
4,300.00	4,299.58	4,300.91	4,300.49	9.17	9.29	-178.12	0.11	-3.29	45.38	27.02	18.363	2.471	
4,400.00	4,399.57	4,400.90	4,400.47	9.39	9.51	-177.20	0.11	-5.04	45.57	26.77	18.805	2.423	
4,500.00	4,499.55	4,500.90	4,500.45	9.61	9.74	-176.29	0.11	-6.78	45.78	26.53	19.248	2.378	
4,600.00	4,599.53	4,600.90	4,600.43	9.83	9.96	-175.38	0.11	-8.53	45.99	26.30	19.691	2.336	
4,700.00	4,699.52	4,700.90	4,700.41	10.06	10.19	-174.49	0.11	-10.27	46.22	26.09	20.135	2.296	
4,800.00	4,799.50	4,800.89	4,800.40	10.28	10.41	-173.60	0.11	-12.02	46.46	25.88	20.578	2.258	
4,900.00	4,899.49	4,900.89	4,900.38	10.50	10.63	-172.72	0.11	-13.76	46.71	25.69	21.023	2.222	
5,000.00	4,999.47	5,000.89	5,000.36	10.73	10.86	-171.86	0.11	-15.51	46.97	25.51	21.467	2.188	
5,100.00	5,099.46	5,100.88	5,100.34	10.95	11.08	-171.00	0.11	-17.25	47.24	25.33	21.912	2.156	
5,200.00	5,199.44	5,200.88	5,200.32	11.17	11.31	-170.15	0.11	-19.00	47.53	25.17	22.358	2.126	
5,300.00	5,299.43	5,300.88	5,300.31	11.40	11.53	-169.32	0.11	-20.74	47.82	25.02	22.803	2.097	
5,400.00	5,399.41	5,400.88	5,400.29	11.62	11.76	-168.49	0.11	-22.49	48.12	24.87	23.249	2.070	
5,500.00	5,499.40	5,500.87	5,500.27	11.85	11.98	-167.67	0.11	-24.23	48.43	24.74	23.695	2.044	
5,600.00	5,599.38	5,600.87	5,600.25	12.07	12.21	-166.87	0.11	-25.98	48.76	24.61	24.142	2.020	
5,700.00	5,699.37	5,700.87	5,700.23	12.30	12.43	-166.07	0.11	-27.72	49.09	24.50	24.589	1.996	
5,800.00	5,799.35	5,800.86	5,800.22	12.52	12.66	-165.29	0.11	-29.47	49.43	24.39	25.036	1.974	
5,900.00	5,899.34	5,900.86	5,900.20	12.75	12.88	-164.51	0.11	-31.21	49.78	24.29	25.483	1.953	
6,000.00	5,999.32	6,000.86	6,000.18	12.97	13.11	-163.75	0.11	-32.96	50.14	24.21	25.931	1.934	
6,100.00	6,099.31	6,100.86	6,100.16	13.19	13.33	-163.00	0.11	-34.70	50.50	24.13	26.378	1.915	
6,200.00	6,199.29	6,200.85	6,200.14	13.42	13.56	-162.26	0.11	-36.45	50.88	24.05	26.826	1.897	
6,300.00	6,299.28	6,300.85	6,300.13	13.64	13.78	-161.53	0.11	-38.19	51.27	23.99	27.275	1.880	
6,400.00	6,399.26	6,400.85	6,400.11	13.87	14.01	-160.81	0.11	-39.94	51.66	23.94	27.723	1.863	
6,500.00	6,499.25	6,500.84	6,500.09	14.10	14.23	-160.10	0.11	-41.69	52.06	23.89	28.172	1.848	
6,600.00	6,599.23	6,600.84	6,600.07	14.32	14.46	-159.41	0.11	-43.43	52.47	23.85	28.620	1.833	
6,700.00	6,699.21	6,700.84	6,700.05	14.55	14.69	-158.72	0.11	-45.18	52.88	23.81	29.069	1.819	
6,800.00	6,799.20	6,800.84	6,800.03	14.77	14.91	-158.05	0.11	-46.92	53.31	23.79	29.519	1.806	
6,900.00	6,899.18	6,900.83	6,900.02	15.00	15.14	-157.38	0.11	-48.67	53.74	23.77	29.968	1.793	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Reference Site: Littlefield 33 Fed COM
 Site Error: 0.00 usft
 Reference Well: #806H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.000 sigma
 Database: EDM 5000.14 Single User Db
 Offset TVD Reference: Offset Datum

Offset Design Littlefield 33 Fed COM - #705H - OH - Plan #1 - IP													Offset Site Error: 0.00 usft
Survey Program: 0-MWD													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Tooface (')	Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)				Between Centres (usft)	Between Ellipses (usft)
7,000.00	6,999.17	7,000.83	7,000.00	15.22	15.36	156.73	0.11	-50.41	54.18	23.76	30.418	1.781	
7,100.00	7,099.15	7,100.83	7,099.98	15.45	15.59	156.09	0.11	-52.16	54.62	23.75	30.867	1.770 ES	
7,200.00	7,199.14	7,200.82	7,199.96	15.67	15.81	155.45	0.11	-53.90	55.07	23.76	31.317	1.759	
7,300.00	7,299.12	7,300.82	7,299.94	15.90	16.04	154.83	0.11	-55.65	55.53	23.76	31.767	1.748	
7,400.00	7,399.11	7,400.82	7,399.93	16.13	16.27	154.22	0.11	-57.39	56.00	23.78	32.218	1.738	
7,500.00	7,499.09	7,500.82	7,499.91	16.35	16.49	153.62	0.11	-59.14	56.47	23.80	32.668	1.729	
7,600.00	7,599.08	7,600.81	7,599.89	16.58	16.72	153.03	0.11	-60.88	56.95	23.83	33.118	1.719	
7,700.00	7,699.06	7,700.81	7,699.87	16.80	16.94	152.44	0.11	-62.63	57.43	23.86	33.569	1.711	
7,800.00	7,799.05	7,800.81	7,799.85	17.03	17.17	151.87	0.11	-64.37	57.92	23.90	34.020	1.702	
7,900.00	7,899.03	7,900.80	7,899.84	17.25	17.40	151.31	0.11	-66.12	58.41	23.94	34.471	1.695	
8,000.00	7,999.02	8,000.80	7,999.82	17.48	17.62	150.76	0.11	-67.86	58.91	23.99	34.922	1.687	
8,100.00	8,099.00	8,100.80	8,099.80	17.71	17.85	150.21	0.11	-69.61	59.42	24.05	35.373	1.680	
8,200.00	8,198.99	8,200.80	8,199.78	17.93	18.07	149.68	0.11	-71.35	59.93	24.11	35.824	1.673	
8,300.00	8,298.97	8,300.79	8,299.76	18.16	18.30	149.15	0.11	-73.10	60.45	24.17	36.275	1.666	
8,400.00	8,398.96	8,400.79	8,399.75	18.38	18.53	148.64	0.11	-74.84	60.97	24.24	36.727	1.660	
8,500.00	8,498.94	8,500.79	8,499.73	18.61	18.75	148.13	0.11	-76.59	61.49	24.31	37.178	1.654	
8,600.00	8,598.93	8,600.78	8,599.71	18.84	18.98	147.63	0.11	-78.33	62.02	24.39	37.630	1.648	
8,700.00	8,698.91	8,700.78	8,699.69	19.06	19.21	147.14	0.11	-80.08	62.56	24.48	38.081	1.643	
8,800.00	8,798.90	8,800.78	8,799.67	19.29	19.43	146.66	0.11	-81.82	63.10	24.56	38.533	1.637	
8,900.00	8,898.88	8,900.78	8,899.66	19.52	19.66	146.18	0.11	-83.57	63.64	24.66	38.985	1.632	
9,000.00	8,998.86	9,000.77	8,999.64	19.74	19.89	145.72	0.11	-85.31	64.19	24.75	39.437	1.628	
9,100.00	9,098.85	9,100.77	9,099.62	19.97	20.11	145.26	0.11	-87.06	64.74	24.85	39.889	1.623	
9,200.00	9,198.83	9,200.77	9,199.60	20.20	20.34	144.81	0.11	-88.81	65.30	24.96	40.341	1.619	
9,300.00	9,298.82	9,300.76	9,299.58	20.42	20.56	144.37	0.11	-90.55	65.86	25.07	40.793	1.614	
9,400.00	9,398.80	9,400.76	9,399.56	20.65	20.79	143.93	0.11	-92.30	66.42	25.18	41.246	1.610	
9,434.54	9,433.34	9,435.30	9,434.10	20.73	20.87	143.78	0.11	-92.90	66.62	25.22	41.402	1.609	
9,501.21	9,500.00	9,501.41	9,500.20	20.87	21.01	28.65	0.11	-93.47	66.81	25.13	41.683	1.603 SF	
9,600.00	9,598.80	9,592.16	9,590.69	21.06	21.20	25.94	5.39	-94.42	71.55	29.56	41.989	1.704	
9,700.00	9,698.80	9,678.27	9,674.52	21.25	21.38	18.45	24.38	-97.84	90.76	48.72	42.044	2.159	
9,800.00	9,798.80	9,756.23	9,746.73	21.45	21.54	11.39	53.08	-103.02	125.27	83.44	41.828	2.995	
9,900.00	9,898.80	9,824.20	9,805.55	21.64	21.68	6.47	86.52	-109.05	173.33	131.83	41.492	4.177	
10,000.00	9,998.80	9,882.12	9,851.82	21.84	21.81	3.28	120.76	-115.22	232.19	191.02	41.168	5.640	
10,100.00	10,098.80	9,930.92	9,887.61	22.03	21.95	1.19	153.39	-121.10	299.35	258.43	40.921	7.315	
10,200.00	10,198.80	9,971.93	9,915.17	22.23	22.08	-0.23	183.25	-126.49	372.85	332.08	40.768	9.146	
10,300.00	10,298.80	10,000.00	9,932.63	22.43	22.17	-1.06	204.89	-130.39	451.26	410.64	40.619	11.109	
10,342.35	10,341.14	10,019.43	9,944.00	22.51	22.25	-1.58	220.39	-133.18	485.52	444.82	40.702	11.829	
10,350.00	10,348.79	10,021.70	9,945.29	22.52	22.26	19.27	222.23	-133.51	491.76	451.06	40.702	12.082	
10,400.00	10,398.68	10,036.97	9,953.76	22.63	22.32	16.79	234.73	-135.77	531.49	490.79	40.702	13.058	
10,450.00	10,448.03	10,050.00	9,960.69	22.73	22.38	14.96	245.59	-137.72	569.28	528.61	40.669	13.998	
10,500.00	10,496.40	10,069.38	9,970.48	22.83	22.47	13.55	262.05	-140.69	604.94	564.25	40.691	14.867	
10,550.00	10,543.34	10,086.33	9,978.52	22.93	22.55	12.47	276.73	-143.34	638.42	597.73	40.686	15.691	
10,600.00	10,588.42	10,100.00	9,984.66	23.02	22.61	11.62	288.75	-145.51	669.59	628.94	40.655	16.470	
10,650.00	10,631.22	10,121.35	9,993.59	23.12	22.73	11.00	307.84	-148.95	698.31	657.63	40.678	17.167	
10,700.00	10,671.35	10,150.00	10,004.31	23.21	22.88	10.59	333.98	-153.66	724.73	683.99	40.742	17.788	
10,750.00	10,708.43	10,150.00	10,004.31	23.32	22.88	10.06	333.98	-153.66	748.30	707.66	40.642	18.412	
10,800.00	10,742.14	10,175.91	10,012.74	23.46	23.04	9.86	358.09	-158.01	769.23	728.54	40.690	18.904	
10,850.00	10,772.16	10,200.00	10,019.47	23.63	23.18	9.73	380.85	-162.11	787.60	746.87	40.731	19.337	
10,900.00	10,798.20	10,213.16	10,022.70	23.84	23.27	9.56	393.41	-164.37	803.13	762.40	40.733	19.717	
10,950.00	10,820.04	10,231.96	10,026.74	24.08	23.40	9.53	411.47	-167.63	815.93	775.16	40.770	20.013	
11,000.00	10,837.47	10,250.00	10,030.00	24.36	23.52	9.54	428.93	-170.78	825.92	785.10	40.819	20.234	
11,050.00	10,850.33	10,269.75	10,032.85	24.68	23.66	9.64	448.17	-174.25	833.06	792.17	40.888	20.374	
11,100.00	10,858.50	10,300.00	10,035.79	25.04	23.88	9.94	477.79	-178.58	837.56	796.56	40.993	20.432	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Reference Site: Littlefield 33 Fed COM
 Site Error: 0.00 usft
 Reference Well: #806H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.000 sigma
 Database: EDM 5000.14 Single User Db
 Offset TVD Reference: Offset Datum

Offset Design Littlefield 33 Fed COM - #705H - OH - Plan #1 - IP													Offset Site Error: 0.00 usft
Survey Program: 0-MWD													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis			Distance						
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
11,150.00	10,861.90	10,300.00	10,035.79	25.43	23.88	9.91	477.79	-179.59	838.89	797.82	41.064	20.429	
11,157.44	10,862.00	10,310.48	10,036.40	25.49	23.96	10.05	488.08	-181.44	838.77	797.68	41.092	20.412	
11,169.41	10,862.07	10,315.02	10,036.60	25.59	24.00	10.11	492.55	-182.25	838.72	797.60	41.121	20.396	
11,200.00	10,862.25	10,333.52	10,037.00	25.84	24.14	10.34	510.75	-185.53	839.11	797.91	41.206	20.364	
11,300.00	10,862.85	10,410.02	10,037.29	26.77	24.79	11.27	586.21	-198.10	842.35	800.80	41.554	20.271	
11,400.00	10,863.45	10,502.93	10,037.65	27.80	25.64	12.36	678.26	-210.64	846.05	804.05	42.002	20.143	
11,500.00	10,864.05	10,595.36	10,038.00	28.91	26.57	13.44	770.20	-220.15	850.01	807.47	42.540	19.982	
11,600.00	10,864.66	10,687.35	10,038.35	30.08	27.56	14.48	861.95	-226.67	854.20	811.04	43.168	19.788	
11,700.00	10,865.26	10,778.89	10,038.70	31.31	28.60	15.50	953.42	-230.23	858.61	814.72	43.886	19.564	
11,800.00	10,865.87	10,871.59	10,039.05	32.58	29.69	16.49	1,044.47	-230.87	863.21	818.51	44.695	19.313	
11,900.00	10,866.47	10,968.97	10,039.42	33.89	30.90	17.43	1,143.49	-229.96	867.50	821.89	45.611	19.020	
12,000.00	10,867.07	11,068.43	10,039.80	35.21	32.18	18.13	1,242.94	-229.05	870.91	824.33	46.578	18.698	
12,100.00	10,867.67	11,168.18	10,040.17	36.55	33.52	18.59	1,342.69	-228.14	873.30	825.73	47.573	18.357	
12,200.00	10,868.27	11,268.12	10,040.55	37.90	34.90	18.81	1,442.62	-227.22	874.61	826.04	48.573	18.006	
12,248.87	10,868.56	11,316.98	10,040.74	38.57	35.60	18.83	1,491.48	-226.77	874.85	825.79	49.055	17.834	
12,300.00	10,868.86	11,368.11	10,040.93	39.26	36.33	18.83	1,542.61	-226.30	874.95	825.39	49.565	17.653	
12,400.00	10,869.46	11,468.11	10,041.31	40.66	37.80	18.82	1,642.60	-225.39	875.15	824.56	50.594	17.298	
12,500.00	10,870.05	11,568.11	10,041.68	42.09	39.29	18.82	1,742.60	-224.47	875.35	823.69	51.668	16.942	
12,600.00	10,870.64	11,668.11	10,042.06	43.55	40.82	18.81	1,842.59	-223.55	875.56	822.77	52.782	16.588	
12,700.00	10,871.24	11,768.11	10,042.44	45.04	42.37	18.81	1,942.59	-222.64	875.76	821.82	53.936	16.237	
12,800.00	10,871.83	11,868.11	10,042.82	46.55	43.95	18.80	2,042.58	-221.72	875.96	820.84	55.125	15.890	
12,900.00	10,872.42	11,968.11	10,043.20	48.09	45.54	18.80	2,142.58	-220.80	876.16	819.81	56.349	15.549	
13,000.00	10,873.02	12,068.11	10,043.57	49.65	47.15	18.79	2,242.57	-219.89	876.36	818.76	57.604	15.214	
13,100.00	10,873.61	12,168.11	10,043.95	51.23	48.78	18.79	2,342.57	-218.97	876.57	817.68	58.888	14.885	
13,200.00	10,874.20	12,268.11	10,044.33	52.82	50.43	18.78	2,442.56	-218.06	876.77	816.57	60.201	14.564	
13,300.00	10,874.80	12,368.11	10,044.71	54.43	52.09	18.78	2,542.56	-217.14	876.97	815.43	61.539	14.251	
13,400.00	10,875.39	12,468.11	10,045.09	56.06	53.76	18.77	2,642.55	-216.22	877.17	814.27	62.902	13.945	
13,500.00	10,875.99	12,568.11	10,045.46	57.70	55.44	18.77	2,742.55	-215.31	877.38	813.09	64.287	13.648	
13,600.00	10,876.58	12,668.11	10,045.84	59.35	57.13	18.76	2,842.54	-214.39	877.58	811.88	65.693	13.359	
13,700.00	10,877.17	12,768.11	10,046.22	61.01	58.83	18.76	2,942.54	-213.47	877.78	810.66	67.119	13.078	
13,800.00	10,877.77	12,868.11	10,046.60	62.68	60.54	18.75	3,042.53	-212.56	877.98	809.42	68.564	12.805	
13,900.00	10,878.36	12,968.11	10,046.98	64.36	62.26	18.75	3,142.53	-211.64	878.18	808.16	70.026	12.541	
14,000.00	10,878.95	13,068.11	10,047.35	66.06	63.98	18.74	3,242.52	-210.72	878.39	806.88	71.504	12.284	
14,100.00	10,879.55	13,168.11	10,047.73	67.75	65.71	18.74	3,342.52	-209.81	878.59	805.59	72.997	12.036	
14,200.00	10,880.14	13,268.11	10,048.11	69.46	67.45	18.73	3,442.51	-208.89	878.79	804.28	74.505	11.795	
14,300.00	10,880.73	13,368.11	10,048.49	71.18	69.19	18.73	3,542.51	-207.97	878.99	802.96	76.027	11.562	
14,400.00	10,881.33	13,468.11	10,048.86	72.90	70.94	18.72	3,642.50	-207.06	879.19	801.63	77.561	11.336	
14,500.00	10,881.92	13,568.11	10,049.24	74.62	72.70	18.72	3,742.50	-206.14	879.40	800.29	79.106	11.117	
14,600.00	10,882.52	13,668.11	10,049.62	76.35	74.45	18.71	3,842.49	-205.22	879.60	798.93	80.664	10.905	
14,700.00	10,883.11	13,768.11	10,050.00	78.09	76.22	18.71	3,942.49	-204.31	879.80	797.57	82.231	10.699	
14,800.00	10,883.70	13,868.11	10,050.38	79.83	77.98	18.70	4,042.48	-203.39	880.00	796.19	83.809	10.500	
14,900.00	10,884.30	13,968.11	10,050.75	81.58	79.75	18.70	4,142.48	-202.47	880.20	794.81	85.395	10.307	
15,000.00	10,884.89	14,068.11	10,051.13	83.33	81.52	18.69	4,242.47	-201.56	880.41	793.42	86.991	10.121	
15,100.00	10,885.48	14,168.11	10,051.51	85.09	83.30	18.69	4,342.47	-200.64	880.61	792.01	88.595	9.940	
15,200.00	10,886.08	14,268.11	10,051.89	86.84	85.08	18.68	4,442.46	-199.73	880.81	790.60	90.207	9.764	
15,300.00	10,886.67	14,368.11	10,052.27	88.61	86.86	18.68	4,542.46	-198.81	881.01	789.19	91.826	9.594	
15,400.00	10,887.26	14,468.11	10,052.64	90.37	88.65	18.67	4,642.45	-197.89	881.21	787.76	93.452	9.430	
15,500.00	10,887.86	14,568.11	10,053.02	92.14	90.43	18.67	4,742.44	-196.98	881.42	786.33	95.085	9.270	
15,600.00	10,888.45	14,668.10	10,053.40	93.91	92.22	18.66	4,842.44	-196.06	881.62	784.90	96.724	9.115	
15,700.00	10,889.05	14,768.10	10,053.78	95.69	94.01	18.66	4,942.43	-195.14	881.82	783.45	98.369	8.964	
15,800.00	10,889.64	14,868.10	10,054.16	97.47	95.81	18.65	5,042.43	-194.23	882.02	782.00	100.020	8.818	
15,900.00	10,890.23	14,968.10	10,054.53	99.25	97.60	18.65	5,142.42	-193.31	882.23	780.55	101.676	8.677	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: COG OPERATING, LLC
Project: Eddy County, NM (NAD27) NMZ
Reference Site: Littlefield 33 Fed COM
Site Error: 0.00 usft
Reference Well: #806H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.000 sigma
Database: EDM 5000.14 Single User Db
Offset TVD Reference: Offset Datum

Offset Design Littlefield 33 Fed COM - #705H - OH - Plan #1 - IP													Offset Site Error:	0.00 usft
Survey Program: 0-MWD													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)						
16,000.00	10,890.83	15,068.10	10,054.91	101.03	99.40	18.64	5,242.42	-192.39	882.43	779.09	103.337	8.539		
16,100.00	10,891.42	15,168.10	10,055.29	102.81	101.20	18.64	5,342.41	-191.48	882.63	777.63	105.003	8.406		
16,200.00	10,892.01	15,268.10	10,055.67	104.60	103.00	18.63	5,442.41	-190.56	882.83	776.16	106.674	8.276		
16,300.00	10,892.61	15,368.10	10,056.04	106.39	104.80	18.63	5,542.40	-189.64	883.03	774.69	108.349	8.150		
16,400.00	10,893.20	15,468.10	10,056.42	108.18	106.61	18.62	5,642.40	-188.73	883.24	773.21	110.028	8.027		
16,500.00	10,893.79	15,568.10	10,056.80	109.97	108.41	18.62	5,742.39	-187.81	883.44	771.73	111.711	7.908		
16,600.00	10,894.39	15,668.10	10,057.18	111.77	110.22	18.61	5,842.39	-186.89	883.64	770.24	113.398	7.792		
16,700.00	10,894.98	15,768.10	10,057.56	113.56	112.03	18.61	5,942.38	-185.98	883.84	768.76	115.088	7.680		
16,800.00	10,895.57	15,868.10	10,057.93	115.36	113.84	18.60	6,042.38	-185.06	884.05	767.26	116.782	7.570		
16,900.00	10,896.17	15,968.10	10,058.31	117.16	115.65	18.60	6,142.37	-184.14	884.25	765.77	118.479	7.463		
17,000.00	10,896.76	16,068.10	10,058.69	118.96	117.46	18.60	6,242.37	-183.23	884.45	764.27	120.179	7.359		
17,100.00	10,897.36	16,168.10	10,059.07	120.76	119.27	18.59	6,342.36	-182.31	884.65	762.77	121.882	7.258		
17,200.00	10,897.95	16,268.10	10,059.45	122.57	121.09	18.59	6,442.36	-181.39	884.85	761.27	123.588	7.160		
17,300.00	10,898.54	16,368.10	10,059.82	124.37	122.90	18.58	6,542.35	-180.48	885.06	759.76	125.296	7.064		
17,400.00	10,899.14	16,468.10	10,060.20	126.18	124.72	18.58	6,642.35	-179.56	885.26	758.25	127.008	6.970		
17,500.00	10,899.73	16,568.10	10,060.58	127.98	126.53	18.57	6,742.34	-178.65	885.46	756.74	128.721	6.879		
17,600.00	10,900.32	16,668.10	10,060.96	129.79	128.35	18.57	6,842.34	-177.73	885.66	755.23	130.437	6.790		
17,700.00	10,900.92	16,768.10	10,061.34	131.60	130.17	18.56	6,942.33	-176.81	885.87	753.71	132.155	6.703		
17,800.00	10,901.51	16,868.10	10,061.71	133.41	131.99	18.56	7,042.33	-175.90	886.07	752.19	133.875	6.619		
17,882.45	10,902.00	16,944.04	10,062.00	134.91	133.37	18.55	7,118.26	-175.20	886.26	751.05	135.214	6.554		

Anticollision Report

Company: COG OPERATING, LLC
Project: Eddy County, NM (NAD27) NMZ
Reference Site: Littlefield 33 Fed COM
Site Error: 0.00 usft
Reference Well: #806H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.000 sigma
Database: EDM 5000.14 Single User Db
Offset TVD Reference: Offset Datum

Offset Design Littlefield 33 Fed COM - #706H - OH - Plan #1 - IP													Offset Site Error:	0.00 usft
Survey Program: 0-MWD													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Tooffset (")	Distance		Minimum Separation (usft)	Separation Factor	Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)						
0.00	0.00	0.30	-0.30	0.00	0.00	-90.04	-0.03	-45.01	45.01					
100.00	100.00	100.30	99.70	0.08	0.08	-90.04	-0.03	-45.01	45.01	44.84	.169	265.940		
200.00	200.00	200.30	199.70	0.31	0.31	-90.04	-0.03	-45.01	45.01	44.39	.619	72.740		
300.00	300.00	300.30	299.70	0.53	0.53	-90.04	-0.03	-45.01	45.01	43.94	1.068	42.132		
400.00	400.00	400.30	399.70	0.76	0.76	-90.04	-0.03	-45.01	45.01	43.49	1.518	29.654		
500.00	500.00	500.30	499.70	0.98	0.98	-90.04	-0.03	-45.01	45.01	43.04	1.967	22.878		
600.00	600.00	600.30	599.70	1.21	1.21	-90.04	-0.03	-45.01	45.01	42.59	2.417	18.623		
700.00	700.00	700.30	699.70	1.43	1.43	-90.04	-0.03	-45.01	45.01	42.14	2.866	15.702		
800.00	800.00	800.30	799.70	1.66	1.66	-90.04	-0.03	-45.01	45.01	41.69	3.316	13.574		
900.00	900.00	900.30	899.70	1.88	1.88	-90.04	-0.03	-45.01	45.01	41.24	3.766	11.953		
1,000.00	1,000.00	1,000.30	999.70	2.11	2.11	-90.04	-0.03	-45.01	45.01	40.79	4.215	10.678		
1,100.00	1,100.00	1,100.30	1,099.70	2.33	2.33	-90.04	-0.03	-45.01	45.01	40.35	4.665	9.649		
1,200.00	1,200.00	1,200.30	1,199.70	2.56	2.56	-90.04	-0.03	-45.01	45.01	39.90	5.114	8.801		
1,300.00	1,300.00	1,300.30	1,299.70	2.78	2.78	-90.04	-0.03	-45.01	45.01	39.45	5.564	8.090		
1,400.00	1,400.00	1,400.30	1,399.70	3.01	3.01	-90.04	-0.03	-45.01	45.01	39.00	6.013	7.485		
1,500.00	1,500.00	1,499.70	1,499.70	3.23	3.23	-90.04	-0.03	-45.01	45.01	38.55	6.461	6.966 CC		
1,566.67	1,566.66	1,567.75	1,565.58	3.37	3.37	25.27	-0.03	-45.57	45.05	38.31	6.740	6.685		
1,600.00	1,599.99	1,601.09	1,598.90	3.43	3.44	25.58	-0.03	-46.15	45.11	38.24	6.867	6.569		
1,700.00	1,699.98	1,701.09	1,698.89	3.62	3.64	26.51	-0.03	-47.90	45.29	38.03	7.254	6.243		
1,800.00	1,799.96	1,801.09	1,798.87	3.81	3.84	27.44	-0.03	-49.64	45.48	37.83	7.649	5.946		
1,900.00	1,899.95	1,901.10	1,898.85	4.01	4.05	28.35	-0.03	-51.39	45.68	37.63	8.049	5.675		
2,000.00	1,999.93	2,001.10	1,998.83	4.21	4.26	29.26	-0.03	-53.14	45.89	37.43	8.454	5.428		
2,100.00	2,099.92	2,101.10	2,098.81	4.41	4.47	30.16	-0.03	-54.88	46.11	37.25	8.864	5.202		
2,200.00	2,199.90	2,201.10	2,198.80	4.62	4.68	31.05	-0.03	-56.63	46.35	37.07	9.278	4.995		
2,300.00	2,299.88	2,301.11	2,298.78	4.82	4.89	31.93	-0.03	-58.37	46.59	36.90	9.695	4.806		
2,400.00	2,399.87	2,401.11	2,398.76	5.03	5.10	32.80	-0.03	-60.12	46.85	36.73	10.115	4.631		
2,500.00	2,499.85	2,501.11	2,498.74	5.24	5.32	33.66	-0.03	-61.86	47.12	36.58	10.538	4.471		
2,600.00	2,599.84	2,601.12	2,598.72	5.45	5.54	34.51	-0.03	-63.61	47.39	36.43	10.964	4.323		
2,700.00	2,699.82	2,701.12	2,698.71	5.67	5.75	35.38	-0.03	-65.35	47.68	36.29	11.391	4.186		
2,800.00	2,799.81	2,801.12	2,798.69	5.88	5.97	36.19	-0.03	-67.10	47.98	36.16	11.820	4.059		
2,900.00	2,899.79	2,901.12	2,898.67	6.09	6.19	37.01	-0.03	-68.84	48.29	36.04	12.251	3.942		
3,000.00	2,999.78	3,001.13	2,998.65	6.31	6.41	37.82	-0.03	-70.59	48.61	35.92	12.684	3.832		
3,100.00	3,099.76	3,101.13	3,098.63	6.53	6.63	38.62	-0.03	-72.33	48.94	35.82	13.118	3.730		
3,200.00	3,199.75	3,201.13	3,198.62	6.74	6.85	39.41	-0.03	-74.08	49.27	35.72	13.553	3.635		
3,300.00	3,299.73	3,301.14	3,298.60	6.96	7.07	40.18	-0.03	-75.82	49.62	35.63	13.990	3.547		
3,400.00	3,399.72	3,401.14	3,398.58	7.18	7.29	40.95	-0.03	-77.57	49.98	35.55	14.428	3.464		
3,500.00	3,499.70	3,501.14	3,498.56	7.40	7.51	41.71	-0.03	-79.31	50.34	35.47	14.866	3.386		
3,600.00	3,599.69	3,601.14	3,598.54	7.62	7.73	42.45	-0.03	-81.06	50.71	35.41	15.306	3.313		
3,700.00	3,699.67	3,701.15	3,698.52	7.84	7.95	43.19	-0.03	-82.80	51.09	35.35	15.746	3.245		
3,800.00	3,799.66	3,801.15	3,798.51	8.06	8.18	43.91	-0.03	-84.55	51.48	35.30	16.187	3.181		
3,900.00	3,899.64	3,901.15	3,898.49	8.28	8.40	44.62	-0.03	-86.29	51.88	35.25	16.629	3.120		
4,000.00	3,999.63	4,001.16	3,998.47	8.50	8.62	45.32	-0.03	-88.04	52.29	35.22	17.071	3.063		
4,100.00	4,099.61	4,101.16	4,098.45	8.72	8.84	46.01	-0.03	-89.78	52.70	35.19	17.515	3.009		
4,200.00	4,199.60	4,201.16	4,198.43	8.94	9.07	46.69	-0.03	-91.53	53.12	35.16	17.958	2.958		
4,300.00	4,299.58	4,301.16	4,298.42	9.17	9.29	47.36	-0.03	-93.27	53.55	35.15	18.403	2.910		
4,400.00	4,399.57	4,401.17	4,398.40	9.39	9.51	48.02	-0.03	-95.02	53.98	35.14	18.848	2.864		
4,500.00	4,499.55	4,501.17	4,498.38	9.61	9.74	48.67	-0.03	-96.77	54.43	35.13	19.293	2.821 ES		
4,600.00	4,599.53	4,601.17	4,598.36	9.83	9.96	49.30	-0.03	-98.51	54.88	35.14	19.739	2.780		
4,700.00	4,699.52	4,701.18	4,698.34	10.06	10.19	49.93	-0.03	-100.26	55.33	35.15	20.185	2.741		
4,800.00	4,799.50	4,801.18	4,798.33	10.28	10.41	50.55	-0.03	-102.00	55.79	35.16	20.631	2.704		
4,900.00	4,899.49	4,901.18	4,898.31	10.50	10.63	51.15	-0.03	-103.75	56.26	35.19	21.078	2.669		
5,000.00	4,999.47	5,001.18	4,998.29	10.73	10.86	51.75	-0.03	-105.49	56.74	35.21	21.526	2.636		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Reference Site: Littlefield 33 Fed COM
 Site Error: 0.00 usft
 Reference Well: #806H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.000 sigma
 Database: EDM 5000.14 Single User Db
 Offset TVD Reference: Offset Datum

Offset Design Littlefield 33 Fed COM - #706H - OH - Plan #1 - IP											Offset Site Error: 0.00 usft		
Survey Program: 0-MWD											Offset Well Error: 0.00 usft		
Reference		Offset		Semi Major Axis		Distance							
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
5,100.00	5,099.46	5,101.19	5,098.27	10.95	11.08	52.33	-0.03	-107.24	57.22	35.25	21.973	2,604	
5,200.00	5,199.44	5,201.19	5,198.25	11.17	11.31	52.91	-0.03	-108.98	57.71	35.29	22.421	2,574	
5,300.00	5,299.43	5,301.19	5,298.24	11.40	11.53	53.48	-0.03	-110.73	58.20	35.33	22.869	2,545	
5,400.00	5,399.41	5,401.20	5,398.22	11.62	11.76	54.03	-0.03	-112.47	58.70	35.38	23.318	2,517	
5,500.00	5,499.40	5,501.20	5,498.20	11.85	11.98	54.58	-0.03	-114.22	59.20	35.43	23.767	2,491	
5,600.00	5,599.38	5,601.20	5,598.18	12.07	12.21	55.12	-0.03	-115.96	59.71	35.49	24.216	2,466	
5,700.00	5,699.37	5,701.20	5,698.16	12.30	12.43	55.65	-0.03	-117.71	60.22	35.56	24.665	2,442	
5,800.00	5,799.35	5,801.21	5,798.14	12.52	12.66	56.17	-0.03	-119.45	60.74	35.63	25.115	2,419	
5,900.00	5,899.34	5,901.21	5,898.13	12.75	12.88	56.68	-0.03	-121.20	61.27	35.70	25.564	2,397	
6,000.00	5,999.32	6,001.21	5,998.11	12.97	13.11	57.18	-0.03	-122.94	61.80	35.78	26.014	2,375	
6,100.00	6,099.31	6,101.22	6,098.09	13.19	13.33	57.67	-0.03	-124.69	62.33	35.87	26.464	2,355	
6,200.00	6,199.29	6,201.22	6,198.07	13.42	13.56	58.16	-0.03	-126.43	62.87	35.95	26.915	2,336	
6,300.00	6,299.28	6,301.22	6,298.05	13.64	13.78	58.64	-0.03	-128.18	63.41	36.04	27.365	2,317	
6,400.00	6,399.26	6,401.22	6,398.04	13.87	14.01	59.10	-0.03	-129.92	63.96	36.14	27.816	2,299	
6,500.00	6,499.25	6,501.23	6,498.02	14.10	14.24	59.57	-0.03	-131.67	64.51	36.24	28.267	2,282	
6,600.00	6,599.23	6,601.23	6,598.00	14.32	14.46	60.02	-0.03	-133.41	65.06	36.35	28.717	2,266	
6,700.00	6,699.21	6,701.23	6,697.98	14.55	14.69	60.46	-0.03	-135.16	65.62	36.45	29.169	2,250	
6,800.00	6,799.20	6,801.24	6,797.96	14.77	14.91	60.90	-0.03	-136.90	66.19	36.57	29.620	2,234	
6,900.00	6,899.18	6,901.24	6,897.95	15.00	15.14	61.33	-0.03	-138.65	66.75	36.68	30.071	2,220	
7,000.00	6,999.17	7,001.24	6,997.93	15.22	15.36	61.76	-0.03	-140.39	67.32	36.80	30.523	2,206	
7,100.00	7,099.15	7,101.24	7,097.91	15.45	15.59	62.17	-0.03	-142.14	67.90	36.92	30.974	2,192	
7,200.00	7,199.14	7,201.25	7,197.89	15.67	15.82	62.58	-0.03	-143.89	68.47	37.05	31.426	2,179	
7,300.00	7,299.12	7,301.25	7,297.87	15.90	16.04	62.98	-0.03	-145.63	69.06	37.18	31.878	2,166	
7,400.00	7,399.11	7,401.25	7,397.86	16.13	16.27	63.38	-0.03	-147.38	69.64	37.31	32.330	2,154	
7,500.00	7,499.09	7,501.26	7,497.84	16.35	16.49	63.77	-0.03	-149.12	70.23	37.45	32.782	2,142	
7,600.00	7,599.08	7,601.26	7,597.82	16.58	16.72	64.15	-0.03	-150.87	70.82	37.59	33.234	2,131	
7,700.00	7,699.06	7,701.26	7,697.80	16.80	16.95	64.53	-0.03	-152.61	71.41	37.73	33.686	2,120	
7,800.00	7,799.05	7,801.26	7,797.78	17.03	17.17	64.90	-0.03	-154.36	72.01	37.87	34.138	2,109	
7,900.00	7,899.03	7,901.27	7,897.77	17.25	17.40	65.26	-0.03	-156.10	72.61	38.02	34.591	2,099	
8,000.00	7,999.02	8,001.27	7,997.75	17.48	17.62	65.62	-0.03	-157.85	73.21	38.17	35.043	2,089	
8,100.00	8,099.00	8,101.27	8,097.73	17.71	17.85	65.97	-0.03	-159.59	73.82	38.32	35.495	2,080	
8,200.00	8,198.99	8,201.28	8,197.71	17.93	18.08	66.32	-0.03	-161.34	74.43	38.48	35.948	2,070	
8,300.00	8,298.97	8,301.28	8,297.69	18.16	18.30	66.66	-0.03	-163.08	75.04	38.64	36.401	2,061	
8,400.00	8,398.96	8,401.28	8,397.67	18.38	18.53	66.99	-0.03	-164.83	75.65	38.80	36.853	2,053	
8,500.00	8,498.94	8,501.28	8,497.66	18.61	18.75	67.32	-0.03	-166.57	76.27	38.96	37.306	2,044	
8,600.00	8,598.93	8,601.29	8,597.64	18.84	18.98	67.64	-0.03	-168.32	76.89	39.13	37.759	2,036	
8,700.00	8,698.91	8,701.29	8,697.62	19.06	19.21	67.96	-0.03	-170.06	77.51	39.30	38.212	2,028	
8,800.00	8,798.90	8,801.29	8,797.60	19.29	19.43	68.28	-0.03	-171.81	78.13	39.47	38.665	2,021	
8,900.00	8,898.88	8,901.30	8,897.58	19.52	19.66	68.59	-0.03	-173.55	78.76	39.64	39.118	2,013	
9,000.00	8,998.86	9,001.30	8,997.57	19.74	19.89	68.89	-0.03	-175.30	79.39	39.81	39.571	2,006	
9,100.00	9,098.85	9,101.30	9,097.55	19.97	20.11	69.19	-0.03	-177.04	80.02	39.99	40.024	1,999	
9,200.00	9,198.83	9,201.30	9,197.53	20.20	20.34	69.49	-0.03	-178.79	80.65	40.17	40.477	1,992	
9,300.00	9,298.82	9,301.31	9,297.51	20.42	20.57	69.78	-0.03	-180.53	81.28	40.35	40.930	1,986	
9,400.00	9,398.80	9,401.31	9,397.49	20.65	20.79	70.06	-0.03	-182.28	81.92	40.54	41.383	1,980	
9,434.54	9,433.34	9,433.23	9,432.03	20.73	20.86	70.16	-0.03	-182.88	82.14	40.61	41.534	1,978	
9,501.21	9,500.00	9,500.90	9,499.70	20.87	21.01	-44.75	-0.03	-183.49	82.36	40.54	41.819	1,970 SF	
9,600.00	9,598.80	9,586.81	9,585.30	21.06	21.20	-43.77	5.20	-186.54	89.22	47.14	42.071	2,121	
9,700.00	9,698.80	9,668.78	9,665.00	21.25	21.38	-41.41	21.41	-196.00	111.71	69.67	42.040	2,657	
9,800.00	9,798.80	9,743.30	9,734.10	21.45	21.56	-39.12	45.35	-209.97	148.56	106.75	41.811	3,553	
9,900.00	9,898.80	9,808.75	9,791.00	21.64	21.73	-37.40	73.21	-226.23	197.62	156.12	41.504	4,762	
10,000.00	9,998.80	9,865.01	9,836.35	21.84	21.89	-36.21	101.93	-242.99	256.59	215.38	41.215	6,226	
10,100.00	10,098.80	9,912.82	9,871.88	22.03	22.05	-35.39	129.54	-259.11	323.37	282.38	40.992	7,889	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Reference Site: Littlefield 33 Fed COM
 Site Error: 0.00 usft
 Reference Well: #806H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.000 sigma
 Database: EDM 5000.14 Single User Db
 Offset TVD Reference: Offset Datum

Offset Design Littlefield 33 Fed COM - #706H - OH - Plan #1 - IP													Offset Site Error: 0.00 usft
Survey Program: 0-MWD													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
10,200.00	10,198.80	9,950.00	9,897.40	22.23	22.19	-34.86	152.88	-272.73	396.26	355.47	40.799	9.713	
10,300.00	10,298.80	9,987.68	9,921.23	22.43	22.35	-34.39	178.08	-287.44	473.85	433.06	40.792	11.616	
10,342.35	10,341.14	10,000.00	9,928.55	22.51	22.41	-34.25	186.64	-292.43	507.89	467.11	40.782	12.454	
10,350.00	10,348.79	10,000.00	9,928.55	22.52	22.41	-12.69	186.64	-292.43	514.09	473.33	40.755	12.614	
10,400.00	10,398.68	10,018.18	9,938.93	22.63	22.50	-11.14	199.53	-299.96	553.34	512.56	40.786	13.567	
10,450.00	10,448.03	10,034.10	9,947.58	22.73	22.58	-10.00	211.06	-306.69	590.55	549.77	40.777	14.483	
10,500.00	10,496.40	10,050.00	9,955.82	22.83	22.67	-9.14	222.81	-313.55	625.56	584.80	40.760	15.347	
10,550.00	10,543.34	10,067.48	9,964.38	22.93	22.77	-8.48	235.98	-321.23	658.27	617.52	40.752	16.153	
10,600.00	10,588.42	10,084.81	9,972.36	23.02	22.87	-7.98	249.25	-328.98	688.58	647.84	40.739	16.902	
10,650.00	10,631.22	10,100.00	9,978.94	23.12	22.97	-7.58	261.08	-335.89	716.40	675.69	40.710	17.597	
10,700.00	10,671.35	10,120.40	9,987.13	23.21	23.11	-7.31	277.22	-345.30	741.62	700.91	40.716	18.214	
10,750.00	10,708.43	10,150.00	9,997.71	23.32	23.31	-7.18	301.09	-359.24	764.42	723.65	40.773	18.748	
10,800.00	10,742.14	10,150.00	9,997.71	23.46	23.31	-6.89	301.09	-359.24	784.17	743.49	40.676	19.279	
10,850.00	10,772.16	10,175.49	10,005.54	23.63	23.51	-6.87	322.04	-371.46	801.21	760.50	40.716	19.678	
10,900.00	10,798.20	10,200.00	10,011.95	23.84	23.70	-6.88	342.47	-383.39	815.58	774.82	40.755	20.012	
10,950.00	10,820.04	10,200.00	10,011.95	24.08	23.70	-6.73	342.47	-383.39	827.26	786.53	40.721	20.315	
11,000.00	10,837.47	10,231.77	10,018.59	24.36	23.98	-6.91	369.30	-399.04	835.59	794.79	40.805	20.478	
11,050.00	10,850.33	10,250.00	10,021.54	24.68	24.14	-7.01	384.83	-408.11	841.30	800.44	40.863	20.588	
11,100.00	10,858.50	10,269.58	10,024.00	25.04	24.32	-7.17	401.60	-417.90	844.10	803.16	40.943	20.616	
11,150.00	10,861.90	10,300.00	10,026.38	25.43	24.61	-7.50	427.80	-433.19	844.20	803.15	41.058	20.561	
11,157.44	10,862.00	10,300.00	10,026.38	25.49	24.61	-7.50	427.80	-433.19	843.85	802.78	41.071	20.546	
11,200.00	10,862.25	10,307.40	10,026.69	25.84	24.69	-7.61	434.18	-436.91	842.76	801.59	41.167	20.471	
11,207.80	10,862.30	10,310.35	10,026.78	25.92	24.72	-7.65	436.73	-438.40	842.73	801.54	41.191	20.459	
11,300.00	10,862.85	10,382.23	10,027.21	26.77	25.47	-8.51	499.10	-474.11	844.87	803.35	41.528	20.345	
11,400.00	10,863.45	10,485.43	10,027.60	27.80	26.67	-9.73	590.17	-522.66	848.06	806.06	42.002	20.191	
11,500.00	10,864.05	10,589.37	10,027.98	28.91	27.98	-10.93	683.58	-568.21	851.62	809.03	42.583	19.999	
11,600.00	10,864.66	10,694.03	10,028.38	30.08	29.38	-12.11	779.26	-610.63	855.52	812.24	43.278	19.768	
11,700.00	10,865.26	10,799.44	10,028.77	31.31	30.85	-13.27	877.11	-649.78	859.75	815.66	44.089	19.500	
11,800.00	10,865.87	10,905.59	10,029.18	32.58	32.39	-14.41	977.05	-685.55	864.28	819.26	45.021	19.197	
11,900.00	10,866.47	11,012.50	10,029.58	33.89	33.97	-15.53	1,078.98	-717.81	869.09	823.02	46.072	18.864	
12,000.00	10,867.07	11,120.17	10,029.99	35.21	35.58	-16.62	1,182.77	-746.42	874.16	826.92	47.236	18.506	
12,100.00	10,867.67	11,228.61	10,030.41	36.55	37.21	-17.68	1,288.30	-771.28	879.45	830.94	48.509	18.130	
12,200.00	10,868.27	11,337.80	10,030.82	37.90	38.85	-18.71	1,395.46	-792.26	884.94	835.06	49.881	17.741	
12,248.87	10,868.56	11,391.45	10,031.03	38.57	39.66	-19.20	1,448.37	-801.07	887.69	837.10	50.583	17.549	
12,300.00	10,868.86	11,447.85	10,031.24	39.26	40.50	-19.73	1,504.17	-809.26	890.45	839.12	51.331	17.347	
12,400.00	10,869.46	11,559.05	10,031.66	40.66	42.15	-20.57	1,614.62	-822.18	895.00	842.22	52.773	16.959	
12,500.00	10,870.05	11,671.19	10,032.08	42.09	43.81	-21.14	1,726.41	-830.86	898.29	844.13	54.164	16.585	
12,600.00	10,870.64	11,783.91	10,032.50	43.55	45.45	-21.45	1,839.05	-835.17	900.22	844.75	55.472	16.229	
12,700.00	10,871.24	11,906.92	10,032.91	45.04	47.22	-21.51	1,948.21	-835.27	900.79	843.98	56.809	15.856	
12,800.00	10,871.83	11,993.08	10,033.27	46.55	48.48	-21.51	2,048.20	-834.34	901.00	842.95	58.046	15.522	
12,900.00	10,872.42	12,106.92	10,033.64	48.09	50.16	-21.50	2,148.20	-833.41	901.20	841.70	59.507	15.144	
13,000.00	10,873.02	12,206.92	10,034.01	49.65	51.67	-21.50	2,248.19	-832.47	901.41	840.51	60.901	14.801	
13,100.00	10,873.61	12,306.92	10,034.38	51.23	53.20	-21.49	2,348.18	-831.54	901.62	839.29	62.323	14.467	
13,200.00	10,874.20	12,393.08	10,034.75	52.82	54.53	-21.48	2,448.18	-830.61	901.82	838.16	63.666	14.165	
13,300.00	10,874.80	12,506.92	10,035.12	54.43	56.31	-21.48	2,548.17	-829.68	902.03	836.79	65.241	13.826	
13,400.00	10,875.39	12,606.92	10,035.48	56.06	57.89	-21.47	2,648.17	-828.75	902.24	835.50	66.734	13.520	
13,500.00	10,875.99	12,706.92	10,035.85	57.70	59.48	-21.47	2,748.16	-827.82	902.44	834.20	68.248	13.223	
13,600.00	10,876.58	12,806.92	10,036.22	59.35	61.09	-21.46	2,848.16	-826.89	902.65	832.87	69.781	12.935	
13,700.00	10,877.17	12,906.92	10,036.59	61.01	62.72	-21.46	2,948.15	-825.96	902.86	831.53	71.333	12.657	
13,800.00	10,877.77	12,993.08	10,036.96	62.68	64.13	-21.45	3,048.15	-825.03	903.07	830.28	72.789	12.407	
13,900.00	10,878.36	13,106.92	10,037.33	64.36	66.00	-21.44	3,148.14	-824.10	903.27	828.79	74.485	12.127	
14,000.00	10,878.95	13,206.92	10,037.69	66.06	67.66	-21.44	3,248.14	-823.17	903.48	827.40	76.084	11.875	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Reference Site: Littlefield 33 Fed COM
 Site Error: 0.00 usft
 Reference Well: #806H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at 2.000 sigma
 Database: EDM 5000.14 Single User Db
 Offset TVD Reference: Offset Datum

Offset Design Littlefield 33 Fed COM - #706H - OH - Plan #1 - IP												Offset Site Error:	0.00 usft
Survey Program: O-MWD												Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Tooface (')	Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)					
14,100.00	10,879.55	13,306.92	10,038.06	67.75	69.32	-21.43	3,348.13	-822.24	903.69	825.99	11.631		
14,200.00	10,880.14	13,406.92	10,038.43	69.46	71.00	-21.43	3,448.13	-821.30	903.89	824.57	11.395		
14,300.00	10,880.73	13,506.92	10,038.80	71.18	72.69	-21.42	3,548.12	-820.37	904.10	823.14	11.167		
14,400.00	10,881.33	13,606.93	10,039.17	72.90	74.38	-21.42	3,648.12	-819.44	904.31	821.70	10.947		
14,500.00	10,881.92	13,706.93	10,039.54	74.62	76.08	-21.41	3,748.11	-818.51	904.51	820.25	10.734		
14,600.00	10,882.52	13,806.93	10,039.90	76.35	77.78	-21.41	3,848.11	-817.58	904.72	818.78	10.528		
14,700.00	10,883.11	13,906.93	10,040.27	78.09	79.49	-21.40	3,948.10	-816.65	904.93	817.31	10.328		
14,800.00	10,883.70	13,993.07	10,040.64	79.83	80.97	-21.39	4,048.10	-815.72	905.13	815.95	10.149		
14,900.00	10,884.30	14,106.93	10,041.01	81.58	82.94	-21.39	4,148.09	-814.79	905.34	814.34	9.949		
15,000.00	10,884.89	14,206.93	10,041.38	83.33	84.67	-21.38	4,248.08	-813.86	905.55	812.84	9.768		
15,100.00	10,885.48	14,306.93	10,041.75	85.09	86.40	-21.38	4,348.08	-812.93	905.76	811.34	9.593		
15,200.00	10,886.08	14,406.93	10,042.12	86.84	88.14	-21.37	4,448.07	-812.00	905.96	809.83	9.424		
15,300.00	10,886.67	14,506.93	10,042.48	88.61	89.88	-21.37	4,548.07	-811.07	906.17	808.31	9.260		
15,400.00	10,887.26	14,606.93	10,042.85	90.37	91.63	-21.36	4,648.06	-810.13	906.38	806.78	9.101		
15,500.00	10,887.86	14,706.93	10,043.22	92.14	93.38	-21.35	4,748.06	-809.20	906.58	805.25	8.947		
15,600.00	10,888.45	14,806.93	10,043.59	93.91	95.14	-21.35	4,848.05	-808.27	906.79	803.72	8.797		
15,700.00	10,889.05	14,906.93	10,043.96	95.69	96.89	-21.34	4,948.05	-807.34	907.00	802.17	8.653		
15,800.00	10,889.64	15,006.93	10,044.33	97.47	98.66	-21.34	5,048.04	-806.41	907.20	800.63	8.512		
15,900.00	10,890.23	15,106.93	10,044.69	99.25	100.42	-21.33	5,148.04	-805.48	907.41	799.08	8.376		
16,000.00	10,890.83	15,206.93	10,045.06	101.03	102.19	-21.33	5,248.03	-804.55	907.62	797.52	8.244		
16,100.00	10,891.42	15,293.07	10,045.43	102.81	103.71	-21.32	5,348.03	-803.62	907.83	796.08	8.124		
16,200.00	10,892.01	15,406.93	10,045.80	104.60	105.73	-21.32	5,448.02	-802.69	908.03	794.40	7.991		
16,300.00	10,892.61	15,506.93	10,046.17	106.39	107.51	-21.31	5,548.02	-801.76	908.24	792.83	7.870		
16,400.00	10,893.20	15,606.93	10,046.54	108.18	109.28	-21.30	5,648.01	-800.83	908.45	791.26	7.752		
16,500.00	10,893.79	15,706.93	10,046.90	109.97	111.06	-21.30	5,748.01	-799.90	908.65	789.68	7.637		
16,600.00	10,894.39	15,806.93	10,047.27	111.77	112.85	-21.29	5,848.00	-798.96	908.86	788.10	7.526		
16,700.00	10,894.98	15,906.93	10,047.64	113.56	114.63	-21.29	5,948.00	-798.03	909.07	786.52	7.418		
16,800.00	10,895.57	15,993.07	10,048.01	115.36	116.17	-21.28	6,047.99	-797.10	909.28	785.06	7.320		
16,900.00	10,896.17	16,106.93	10,048.38	117.16	118.20	-21.28	6,147.98	-796.17	909.48	783.35	7.210		
17,000.00	10,896.76	16,206.93	10,048.75	118.96	119.99	-21.27	6,247.98	-795.24	909.69	781.76	7.111		
17,100.00	10,897.36	16,293.07	10,049.12	120.76	121.54	-21.26	6,347.97	-794.31	909.90	780.29	7.021		
17,200.00	10,897.95	16,406.93	10,049.48	122.57	123.58	-21.26	6,447.97	-793.38	910.10	778.57	6.919		
17,300.00	10,898.54	16,506.93	10,049.85	124.37	125.37	-21.25	6,547.96	-792.45	910.31	776.97	6.827		
17,400.00	10,899.14	16,593.07	10,050.22	126.18	126.92	-21.25	6,647.96	-791.52	910.52	775.50	6.744		
17,500.00	10,899.73	16,706.93	10,050.59	127.98	128.97	-21.24	6,747.95	-790.59	910.73	773.77	6.650		
17,600.00	10,900.32	16,806.93	10,050.96	129.79	130.77	-21.24	6,847.95	-789.66	910.93	772.17	6.565		
17,700.00	10,900.92	16,906.93	10,051.33	131.60	132.57	-21.23	6,947.94	-788.73	911.14	770.56	6.481		
17,800.00	10,901.51	17,006.93	10,051.69	133.41	134.37	-21.23	7,047.94	-787.79	911.35	768.95	6.400		
17,882.45	10,902.00	17,075.52	10,052.00	134.91	135.61	-21.22	7,130.38	-787.03	911.52	767.76	6.340		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Reference Site: Littlefield 33 Fed COM
 Site Error: 0.00 usft
 Reference Well: #806H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.000 sigma
 Database: EDM 5000.14 Single User Db
 Offset TVD Reference: Offset Datum

Offset Design Littlefield 33 Fed COM - #805H - OH - Plan #1 - IP													Offset Site Error: 0.00 usft
Survey Program: 0-MWD													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	
0.00	0.00	0.70	0.70	0.00	0.00	89.87	0.21	89.97	89.97				
100.00	100.00	100.70	100.70	0.08	0.09	89.87	0.21	89.97	89.97	89.80	.170	528.776	
200.00	200.00	200.70	200.70	0.31	0.31	89.87	0.21	89.97	89.97	89.35	.620	145.188	
300.00	300.00	300.70	300.70	0.53	0.54	89.87	0.21	89.97	89.97	88.90	1.069	84.146	
400.00	400.00	400.70	400.70	0.76	0.76	89.87	0.21	89.97	89.97	88.45	1.519	59.240	
500.00	500.00	500.70	500.70	0.98	0.98	89.87	0.21	89.97	89.97	88.00	1.968	45.710	
600.00	600.00	600.70	600.70	1.21	1.21	89.87	0.21	89.97	89.97	87.55	2.418	37.211	
700.00	700.00	700.70	700.70	1.43	1.43	89.87	0.21	89.97	89.97	87.10	2.867	31.378	
800.00	800.00	800.70	800.70	1.66	1.66	89.87	0.21	89.97	89.97	86.65	3.317	27.125	
900.00	900.00	900.70	900.70	1.88	1.88	89.87	0.21	89.97	89.97	86.20	3.766	23.888	
1,000.00	1,000.00	1,000.70	1,000.70	2.11	2.11	89.87	0.21	89.97	89.97	85.75	4.216	21.341	
1,100.00	1,100.00	1,100.70	1,100.70	2.33	2.33	89.87	0.21	89.97	89.97	85.30	4.665	19.284	
1,200.00	1,200.00	1,200.70	1,200.70	2.56	2.56	89.87	0.21	89.97	89.97	84.86	5.115	17.589	
1,300.00	1,300.00	1,300.70	1,300.70	2.78	2.78	89.87	0.21	89.97	89.97	84.41	5.565	16.169	
1,400.00	1,400.00	1,400.70	1,400.70	3.01	3.01	89.87	0.21	89.97	89.97	83.96	6.014	14.960	
1,500.00	1,500.00	1,500.70	1,500.70	3.23	3.23	89.87	0.21	89.97	89.97	83.51	6.464	13.920 CC, ES	
1,566.67	1,566.66	1,567.36	1,567.36	3.37	3.38	-155.29	0.21	89.97	90.50	83.75	6.750	13.408	
1,600.00	1,599.99	1,600.69	1,600.69	3.43	3.46	-155.44	0.21	89.97	91.03	84.14	6.886	13.219	
1,700.00	1,699.98	1,700.68	1,700.68	3.62	3.68	-155.89	0.21	89.97	92.62	85.32	7.299	12.689	
1,800.00	1,799.96	1,800.66	1,800.66	3.81	3.91	-156.32	0.21	89.97	94.21	86.50	7.716	12.210	
1,900.00	1,899.95	1,900.65	1,900.65	4.01	4.13	-156.74	0.21	89.97	95.81	87.68	8.136	11.776	
2,000.00	1,999.93	2,000.63	2,000.63	4.21	4.36	-157.15	0.21	89.97	97.42	88.86	8.560	11.381	
2,100.00	2,099.92	2,100.62	2,100.62	4.41	4.58	-157.54	0.21	89.97	99.03	90.04	8.986	11.021	
2,200.00	2,199.90	2,200.60	2,200.60	4.62	4.81	-157.92	0.21	89.97	100.65	91.23	9.414	10.691	
2,300.00	2,299.88	2,300.58	2,300.58	4.82	5.03	-158.28	0.21	89.97	102.26	92.42	9.844	10.388	
2,400.00	2,399.87	2,400.57	2,400.57	5.03	5.26	-158.64	0.21	89.97	103.89	93.61	10.276	10.110	
2,500.00	2,499.85	2,500.55	2,500.55	5.24	5.48	-158.99	0.21	89.97	105.52	94.81	10.709	9.853	
2,600.00	2,599.84	2,600.54	2,600.54	5.45	5.70	-159.32	0.21	89.97	107.15	96.00	11.144	9.615	
2,700.00	2,699.82	2,700.52	2,700.52	5.67	5.93	-159.65	0.21	89.97	108.78	97.20	11.580	9.394	
2,800.00	2,799.81	2,800.51	2,800.51	5.88	6.15	-159.96	0.21	89.97	110.42	98.40	12.017	9.189	
2,900.00	2,899.79	2,900.49	2,900.49	6.09	6.38	-160.27	0.21	89.97	112.06	99.61	12.455	8.997	
3,000.00	2,899.78	3,000.48	3,000.48	6.31	6.60	-160.56	0.21	89.97	113.70	100.81	12.894	8.819	
3,100.00	3,099.76	3,100.46	3,100.46	6.53	6.83	-160.85	0.21	89.97	115.35	102.02	13.333	8.651	
3,200.00	3,199.75	3,200.45	3,200.45	6.74	7.05	-161.13	0.21	89.97	117.00	103.23	13.774	8.495	
3,300.00	3,299.73	3,300.43	3,300.43	6.96	7.28	-161.40	0.21	89.97	118.65	104.44	14.214	8.347	
3,400.00	3,399.72	3,400.42	3,400.42	7.18	7.50	-161.67	0.21	89.97	120.31	105.65	14.656	8.209	
3,500.00	3,499.70	3,500.40	3,500.40	7.40	7.73	-161.93	0.21	89.97	121.97	106.87	15.098	8.079	
3,600.00	3,599.69	3,600.39	3,600.39	7.62	7.95	-162.18	0.21	89.97	123.63	108.09	15.540	7.955	
3,700.00	3,699.67	3,700.37	3,700.37	7.84	8.18	-162.42	0.21	89.97	125.29	109.31	15.983	7.839	
3,800.00	3,799.66	3,800.36	3,800.36	8.06	8.40	-162.66	0.21	89.97	126.96	110.53	16.426	7.729	
3,900.00	3,899.64	3,900.34	3,900.34	8.28	8.63	-162.89	0.21	89.97	128.62	111.75	16.870	7.624	
4,000.00	3,999.63	4,000.33	4,000.33	8.50	8.85	-163.12	0.21	89.97	130.29	112.98	17.314	7.525	
4,100.00	4,099.61	4,100.31	4,100.31	8.72	9.08	-163.34	0.21	89.97	131.96	114.21	17.758	7.431	
4,200.00	4,199.60	4,200.30	4,200.30	8.94	9.30	-163.55	0.21	89.97	133.64	115.43	18.203	7.342	
4,300.00	4,299.58	4,300.28	4,300.28	9.17	9.53	-163.76	0.21	89.97	135.31	116.66	18.647	7.256	
4,400.00	4,399.57	4,400.27	4,400.27	9.39	9.75	-163.97	0.21	89.97	136.99	117.89	19.092	7.175	
4,500.00	4,499.55	4,500.25	4,500.25	9.61	9.97	-164.16	0.21	89.97	138.67	119.13	19.538	7.097	
4,600.00	4,599.53	4,600.23	4,600.23	9.83	10.20	-164.36	0.21	89.97	140.35	120.36	19.983	7.023	
4,700.00	4,699.52	4,700.22	4,700.22	10.06	10.42	-164.55	0.21	89.97	142.03	121.60	20.429	6.952	
4,800.00	4,799.50	4,800.20	4,800.20	10.28	10.65	-164.73	0.21	89.97	143.71	122.84	20.875	6.884	
4,900.00	4,899.49	4,900.19	4,900.19	10.50	10.87	-164.92	0.21	89.97	145.39	124.07	21.321	6.819	
5,000.00	4,999.47	5,000.17	5,000.17	10.73	11.10	-165.09	0.21	89.97	147.08	125.31	21.767	6.757	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Reference Site: Littlefield 33 Fed COM
 Site Error: 0.00 usft
 Reference Well: #806H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.000 sigma
 Database: EDM 5000.14 Single User Db
 Offset TVD Reference: Offset Datum

Offset Design Littlefield 33 Fed COM - #805H - OH - Plan #1 - IP													Offset Site Error: 0.00 usft
Survey Program: 0-MWD													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
5,100.00	5,099.46	5,100.16	5,100.16	10.95	11.32	-165.27	0.21	89.97	148.77	126.55	22.213	6.697	
5,200.00	5,199.44	5,200.14	5,200.14	11.17	11.55	-165.43	0.21	89.97	150.46	127.80	22.660	6.640	
5,300.00	5,299.43	5,300.13	5,300.13	11.40	11.77	-165.60	0.21	89.97	152.15	129.04	23.106	6.585	
5,400.00	5,399.41	5,400.11	5,400.11	11.62	12.00	-165.76	0.21	89.97	153.84	130.28	23.553	6.531	
5,500.00	5,499.40	5,500.10	5,500.10	11.85	12.22	-165.92	0.21	89.97	155.53	131.53	24.000	6.480	
5,600.00	5,599.38	5,600.08	5,600.08	12.07	12.45	-166.07	0.21	89.97	157.22	132.78	24.447	6.431	
5,700.00	5,699.37	5,700.07	5,700.07	12.30	12.67	-166.23	0.21	89.97	158.92	134.02	24.894	6.384	
5,800.00	5,799.35	5,800.05	5,800.05	12.52	12.90	-166.37	0.21	89.97	160.61	135.27	25.341	6.338	
5,900.00	5,899.34	5,900.04	5,900.04	12.75	13.12	-166.52	0.21	89.97	162.31	136.52	25.789	6.294	
6,000.00	5,999.32	6,000.02	6,000.02	12.97	13.35	-166.66	0.21	89.97	164.01	137.77	26.236	6.251	
6,100.00	6,099.31	6,100.01	6,100.01	13.19	13.57	-166.80	0.21	89.97	165.71	139.02	26.683	6.210	
6,200.00	6,199.29	6,200.01	6,199.99	13.42	13.80	-166.94	0.21	89.97	167.40	140.27	27.131	6.170	
6,300.00	6,299.28	6,300.02	6,299.98	13.64	14.02	-167.07	0.21	89.97	169.11	141.53	27.579	6.132	
6,400.00	6,399.26	6,400.04	6,399.96	13.87	14.24	-167.20	0.21	89.97	170.81	142.78	28.026	6.094	
6,500.00	6,499.25	6,500.05	6,499.95	14.10	14.47	-167.33	0.21	89.97	172.51	144.03	28.474	6.058	
6,600.00	6,599.23	6,600.07	6,599.93	14.32	14.69	-167.46	0.21	89.97	174.21	145.29	28.922	6.023	
6,700.00	6,699.21	6,700.09	6,699.91	14.55	14.92	-167.58	0.21	89.97	175.92	146.55	29.370	5.990	
6,800.00	6,799.20	6,800.10	6,799.90	14.77	15.14	-167.70	0.21	89.97	177.62	147.80	29.818	5.957	
6,900.00	6,899.18	6,900.12	6,899.88	15.00	15.37	-167.82	0.21	89.97	179.33	149.06	30.266	5.925	
7,000.00	6,999.17	7,000.13	6,999.87	15.22	15.59	-167.94	0.21	89.97	181.03	150.32	30.714	5.894	
7,100.00	7,099.15	7,100.15	7,099.85	15.45	15.82	-168.05	0.21	89.97	182.74	151.58	31.163	5.864	
7,200.00	7,199.14	7,200.16	7,199.84	15.67	16.04	-168.16	0.21	89.97	184.45	152.84	31.611	5.835	
7,300.00	7,299.12	7,300.18	7,299.82	15.90	16.27	-168.27	0.21	89.97	186.16	154.10	32.059	5.807	
7,400.00	7,399.11	7,400.19	7,399.81	16.13	16.49	-168.38	0.21	89.97	187.87	155.36	32.507	5.779	
7,500.00	7,499.09	7,500.21	7,499.79	16.35	16.72	-168.49	0.21	89.97	189.58	156.62	32.956	5.752	
7,600.00	7,599.08	7,600.22	7,599.78	16.58	16.94	-168.59	0.21	89.97	191.29	157.88	33.404	5.726	
7,700.00	7,699.06	7,700.24	7,699.76	16.80	17.17	-168.69	0.21	89.97	193.00	159.14	33.853	5.701	
7,800.00	7,799.05	7,800.25	7,799.75	17.03	17.39	-168.79	0.21	89.97	194.71	160.41	34.301	5.676	
7,900.00	7,899.03	7,900.27	7,899.73	17.25	17.62	-168.89	0.21	89.97	196.42	161.67	34.750	5.652	
8,000.00	7,999.02	8,000.28	7,999.72	17.48	17.84	-168.99	0.21	89.97	198.13	162.94	35.198	5.629	
8,100.00	8,099.00	8,100.30	8,099.70	17.71	18.07	-169.09	0.21	89.97	199.85	164.20	35.647	5.606	
8,200.00	8,198.99	8,200.31	8,199.69	17.93	18.29	-169.18	0.21	89.97	201.56	165.47	36.096	5.584	
8,300.00	8,298.97	8,300.33	8,299.67	18.16	18.52	-169.27	0.21	89.97	203.28	166.73	36.544	5.562	
8,400.00	8,398.96	8,400.34	8,399.66	18.38	18.74	-169.36	0.21	89.97	204.99	168.00	36.993	5.541	
8,500.00	8,498.94	8,500.36	8,499.64	18.61	18.97	-169.45	0.21	89.97	206.71	169.26	37.442	5.521	
8,600.00	8,598.93	8,600.37	8,599.63	18.84	19.19	-169.54	0.21	89.97	208.42	170.53	37.890	5.501	
8,700.00	8,698.91	8,700.39	8,699.61	19.06	19.42	-169.63	0.21	89.97	210.14	171.80	38.339	5.481	
8,800.00	8,798.90	8,800.41	8,799.60	19.29	19.64	-169.71	0.21	89.97	211.86	173.07	38.788	5.462	
8,900.00	8,898.88	8,900.42	8,899.58	19.52	19.86	-169.80	0.21	89.97	213.57	174.34	39.237	5.443	
9,000.00	8,998.86	9,000.44	8,999.56	19.74	20.09	-169.88	0.21	89.97	215.29	175.61	39.686	5.425	
9,100.00	9,098.85	9,100.45	9,099.55	19.97	20.31	-169.96	0.21	89.97	217.01	176.87	40.135	5.407	
9,200.00	9,198.83	9,200.47	9,199.53	20.20	20.54	-170.04	0.21	89.97	218.73	178.14	40.584	5.390	
9,300.00	9,298.82	9,300.48	9,299.52	20.42	20.76	-170.12	0.21	89.97	220.45	179.41	41.033	5.372	
9,400.00	9,398.80	9,400.50	9,399.50	20.65	20.99	-170.19	0.21	89.97	222.17	180.69	41.481	5.356	
9,434.54	9,433.34	9,434.04	9,434.04	20.73	21.06	-170.22	0.21	89.97	222.76	181.13	41.634	5.350	
9,501.21	9,500.00	9,500.70	9,500.70	20.87	21.21	74.75	0.21	89.97	223.33	181.41	41.923	5.327	
9,600.00	9,598.80	9,600.51	9,599.50	21.06	21.44	74.75	0.21	89.97	223.33	180.99	42.340	5.275	
9,700.00	9,698.80	9,700.51	9,699.50	21.25	21.66	74.75	0.21	89.97	223.33	180.57	42.759	5.223	
9,800.00	9,798.80	9,800.51	9,799.50	21.45	21.89	74.75	0.21	89.97	223.33	180.15	43.179	5.172	
9,900.00	9,898.80	9,900.51	9,899.50	21.64	22.11	74.75	0.21	89.97	223.33	179.73	43.600	5.122	
10,000.00	9,998.80	10,000.51	9,999.50	21.84	22.34	74.75	0.21	89.97	223.33	179.31	44.021	5.073	
10,100.00	10,098.80	10,100.51	10,099.50	22.03	22.56	74.75	0.21	89.97	223.33	178.89	44.443	5.025	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Reference Site: Littlefield 33 Fed COM
 Site Error: 0.00 usft
 Reference Well: #806H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.000 sigma
 Database: EDM 5000.14 Single User Db
 Offset TVD Reference: Offset Datum

Offset Design Littlefield 33 Fed COM - #805H - OH - Plan #1 - IP													Offset Site Error: 0.00 usft
Survey Program: O-MWD													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface ('')	Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)					Between Centres (usft)
10,200.00	10,198.80	10,200.51	10,199.50	22.23	22.79	74.75	0.21	89.97	223.33	178.47	44.865	4.978	
10,300.00	10,298.80	10,300.51	10,299.50	22.43	23.01	74.75	0.21	89.97	223.33	178.05	45.288	4.931	
10,342.35	10,341.14	10,341.84	10,341.84	22.51	23.10	74.75	0.21	89.97	223.33	177.87	45.465	4.912	
10,350.00	10,348.79	10,349.25	10,349.25	22.52	23.12	96.06	0.21	89.97	223.34	177.84	45.497	4.909	
10,400.00	10,398.68	10,394.04	10,393.97	22.63	23.22	96.15	2.32	89.99	224.31	178.62	45.694	4.909	
10,450.00	10,448.03	10,438.81	10,438.34	22.73	23.32	96.20	8.26	90.04	226.95	181.07	45.883	4.946	
10,500.00	10,496.40	10,483.52	10,481.97	22.83	23.42	96.20	17.96	90.13	231.24	185.18	46.065	5.020	
10,550.00	10,543.34	10,528.14	10,524.52	22.93	23.52	96.14	31.34	90.25	237.15	190.90	46.243	5.128	
10,600.00	10,588.42	10,572.63	10,565.65	23.02	23.61	96.01	48.26	90.41	244.62	198.20	46.424	5.269	
10,650.00	10,631.22	10,616.97	10,605.06	23.12	23.70	95.82	68.55	90.59	253.60	206.98	46.613	5.441	
10,700.00	10,671.35	10,661.17	10,642.49	23.21	23.79	95.54	92.04	90.81	264.00	217.19	46.816	5.639	
10,750.00	10,708.43	10,705.22	10,677.67	23.32	23.90	95.17	118.52	91.05	275.75	228.72	47.039	5.862	
10,800.00	10,742.14	10,749.15	10,710.41	23.46	24.01	94.72	147.79	91.31	288.75	241.46	47.289	6.106	
10,850.00	10,772.16	10,792.98	10,740.50	23.63	24.13	94.19	179.84	91.60	302.88	255.31	47.572	6.367	
10,900.00	10,798.20	10,836.78	10,767.78	23.84	24.27	93.58	213.88	91.92	318.03	270.14	47.894	6.640	
10,950.00	10,820.04	10,880.60	10,792.11	24.08	24.42	92.89	250.31	92.25	334.09	285.83	48.256	6.923	
11,000.00	10,837.47	10,924.52	10,813.33	24.36	24.59	92.14	288.75	92.60	350.91	302.25	48.664	7.211	
11,050.00	10,850.33	10,968.65	10,831.32	24.68	24.77	91.33	329.03	92.96	368.38	319.26	49.117	7.500	
11,100.00	10,858.50	11,013.08	10,845.92	25.04	24.98	90.48	370.98	93.35	386.35	336.73	49.616	7.787	
11,150.00	10,861.90	11,057.95	10,856.98	25.43	25.21	89.60	414.45	93.74	404.67	354.51	50.162	8.067	
11,157.44	10,862.00	11,064.67	10,858.32	25.49	25.24	89.47	421.04	93.80	407.42	357.17	50.249	8.108	
11,200.00	10,862.25	11,103.76	10,864.38	25.84	25.46	90.34	459.64	94.15	422.93	372.17	50.760	8.332	
11,300.00	10,862.85	11,201.99	10,868.27	26.77	26.07	90.74	553.75	95.01	457.10	404.94	52.160	8.763	
11,400.00	10,863.45	11,306.87	10,869.00	27.80	26.84	90.70	648.86	95.88	487.95	434.12	53.830	9.065	
11,500.00	10,864.05	11,389.27	10,869.72	28.91	27.52	90.66	744.99	96.75	515.46	459.95	55.516	9.285	
11,600.00	10,864.66	11,486.30	10,870.46	30.08	28.41	90.64	842.02	97.63	539.60	482.11	57.493	9.386	
11,700.00	10,865.26	11,584.12	10,871.20	31.31	29.39	90.61	939.83	98.52	560.34	500.71	59.633	9.396	
11,800.00	10,865.87	11,682.61	10,871.95	32.58	30.45	90.60	1,038.31	99.42	577.65	515.74	61.918	9.329	
11,900.00	10,866.47	11,781.64	10,872.70	33.89	31.59	90.58	1,137.33	100.32	591.52	527.19	64.330	9.195	
12,000.00	10,867.07	11,881.09	10,873.45	35.21	32.79	90.57	1,236.78	101.23	601.92	535.07	66.851	9.004	
12,100.00	10,867.67	11,980.84	10,874.21	36.55	34.06	90.57	1,336.52	102.14	608.84	539.38	69.466	8.765	
12,200.00	10,868.27	12,080.78	10,874.97	37.90	35.38	90.57	1,436.45	103.05	612.28	540.12	72.160	8.485	
12,248.87	10,868.56	12,129.65	10,875.34	38.57	36.04	90.57	1,485.32	103.49	612.69	539.19	73.502	8.336	
12,300.00	10,868.86	12,180.78	10,875.73	39.26	36.74	90.58	1,536.44	103.96	612.69	537.77	74.923	8.178	
12,400.00	10,869.46	12,280.78	10,876.48	40.66	38.15	90.59	1,636.44	104.87	612.68	534.92	77.761	7.879	
12,500.00	10,870.05	12,380.78	10,877.24	42.09	39.59	90.61	1,736.43	105.78	612.67	532.00	80.669	7.595	
12,600.00	10,870.64	12,480.78	10,878.00	43.55	41.06	90.62	1,836.42	106.69	612.65	529.02	83.639	7.325	
12,700.00	10,871.24	12,580.78	10,878.76	45.04	42.56	90.64	1,936.42	107.60	612.64	525.98	86.664	7.069	
12,800.00	10,871.83	12,680.78	10,879.52	46.55	44.09	90.65	2,036.41	108.51	612.63	522.89	89.739	6.827	
12,900.00	10,872.42	12,780.78	10,880.28	48.09	45.65	90.67	2,136.40	109.42	612.62	519.76	92.860	6.597	
13,000.00	10,873.02	12,880.78	10,881.03	49.65	47.22	90.68	2,236.39	110.33	612.61	516.59	96.021	6.380	
13,100.00	10,873.61	12,980.78	10,881.79	51.23	48.81	90.70	2,336.39	111.24	612.60	513.38	99.219	6.174	
13,200.00	10,874.20	13,080.78	10,882.55	52.82	50.42	90.72	2,436.38	112.15	612.59	510.14	102.450	5.979	
13,300.00	10,874.80	13,180.78	10,883.31	54.43	52.05	90.73	2,536.37	113.06	612.58	506.87	105.711	5.795	
13,400.00	10,875.39	13,280.78	10,884.07	56.06	53.69	90.75	2,636.37	113.97	612.57	503.57	109.000	5.620	
13,500.00	10,875.99	13,380.78	10,884.82	57.70	55.34	90.76	2,736.36	114.88	612.56	500.24	112.314	5.454	
13,600.00	10,876.58	13,480.78	10,885.58	59.35	57.01	90.78	2,836.35	115.79	612.54	496.89	115.650	5.297	
13,700.00	10,877.17	13,580.78	10,886.34	61.01	58.68	90.79	2,936.34	116.70	612.53	493.53	119.008	5.147	
13,800.00	10,877.77	13,680.78	10,887.10	62.68	60.37	90.81	3,036.34	117.61	612.52	490.14	122.385	5.005	
13,900.00	10,878.36	13,780.78	10,887.86	64.36	62.06	90.82	3,136.33	118.52	612.51	486.73	125.780	4.870	
14,000.00	10,878.95	13,880.78	10,888.62	66.06	63.77	90.84	3,236.32	119.43	612.50	483.31	129.191	4.741	
14,100.00	10,879.55	13,980.78	10,889.37	67.75	65.48	90.85	3,336.32	120.34	612.49	479.87	132.618	4.618	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: COG OPERATING, LLC
 Project: Eddy County, NM (NAD27) NMZ
 Reference Site: Littlefield 33 Fed COM
 Site Error: 0.00 usft
 Reference Well: #806H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
 TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.000 sigma
 Database: EDM 5000.14 Single User Db
 Offset TVD Reference: Offset Datum

Offset Design Littlefield 33 Fed COM - #805H - OH - Plan #1 - IP													Offset Site Error: 0.00 usft
Survey Program: O-MWD													Offset Well Error: 0.00 usft
Reference		Offset		Semi Major Axis		Highside Tooface (')	Distance					Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)		Separation Factor
14,200.00	10,880.14	14,080.78	10,890.13	69.46	67.20	90.87	3,436.31	121.25	612.48	476.42	136.058	4.502	
14,300.00	10,880.73	14,180.78	10,890.89	71.18	68.92	90.88	3,536.30	122.16	612.47	472.96	139.511	4.390	
14,400.00	10,881.33	14,280.78	10,891.65	72.90	70.65	90.90	3,636.29	123.07	612.46	469.48	142.976	4.284	
14,500.00	10,881.92	14,380.78	10,892.41	74.62	72.39	90.92	3,736.29	123.98	612.45	466.00	146.452	4.182	
14,600.00	10,882.52	14,480.77	10,893.17	76.35	74.13	90.93	3,836.28	124.89	612.44	462.50	149.938	4.085	
14,700.00	10,883.11	14,580.77	10,893.92	78.09	75.88	90.95	3,936.27	125.80	612.43	459.00	153.434	3.991	
14,800.00	10,883.70	14,680.77	10,894.68	79.83	77.63	90.96	4,036.26	126.71	612.42	455.48	156.939	3.902	
14,900.00	10,884.30	14,780.77	10,895.44	81.58	79.39	90.98	4,136.26	127.62	612.41	451.96	160.452	3.817	
15,000.00	10,884.89	14,880.77	10,896.20	83.33	81.15	90.99	4,236.25	128.54	612.40	448.43	163.973	3.735	
15,100.00	10,885.48	14,980.77	10,896.96	85.09	82.91	91.01	4,336.24	129.45	612.39	444.89	167.501	3.656	
15,200.00	10,886.08	15,080.77	10,897.71	86.84	84.68	91.02	4,436.24	130.36	612.38	441.34	171.037	3.580	
15,300.00	10,886.67	15,180.77	10,898.47	88.61	86.45	91.04	4,536.23	131.27	612.37	437.79	174.578	3.508	
15,400.00	10,887.26	15,280.77	10,899.23	90.37	88.22	91.05	4,636.22	132.18	612.36	434.23	178.126	3.438	
15,500.00	10,887.86	15,380.77	10,899.99	92.14	90.00	91.07	4,736.21	133.09	612.35	430.67	181.680	3.370	
15,600.00	10,888.45	15,480.77	10,900.75	93.91	91.78	91.09	4,836.21	134.00	612.34	427.10	185.238	3.306	
15,700.00	10,889.05	15,580.77	10,901.51	95.69	93.56	91.10	4,936.20	134.91	612.33	423.53	188.802	3.243	
15,800.00	10,889.64	15,680.77	10,902.26	97.47	95.34	91.12	5,036.19	135.82	612.32	419.95	192.371	3.183	
15,900.00	10,890.23	15,780.77	10,903.02	99.25	97.13	91.13	5,136.19	136.73	612.31	416.36	195.944	3.125	
16,000.00	10,890.83	15,880.77	10,903.78	101.03	98.92	91.15	5,236.18	137.64	612.30	412.78	199.522	3.069	
16,100.00	10,891.42	15,980.77	10,904.54	102.81	100.71	91.16	5,336.17	138.55	612.29	409.19	203.103	3.015	
16,200.00	10,892.01	16,080.77	10,905.30	104.60	102.50	91.18	5,436.16	139.46	612.28	405.59	206.689	2.962	
16,300.00	10,892.61	16,180.77	10,906.06	106.39	104.30	91.19	5,536.16	140.37	612.27	401.99	210.278	2.912	
16,400.00	10,893.20	16,280.77	10,906.81	108.18	106.09	91.21	5,636.15	141.28	612.26	398.39	213.870	2.863	
16,500.00	10,893.79	16,380.77	10,907.57	109.97	107.89	91.22	5,736.14	142.19	612.25	394.79	217.466	2.815	
16,600.00	10,894.39	16,480.77	10,908.33	111.77	109.69	91.24	5,836.14	143.10	612.24	391.18	221.065	2.770	
16,700.00	10,894.98	16,580.77	10,909.09	113.56	111.49	91.25	5,936.13	144.01	612.23	387.57	224.667	2.725	
16,800.00	10,895.57	16,680.77	10,909.85	115.36	113.30	91.27	6,036.12	144.92	612.22	383.95	228.271	2.682	
16,900.00	10,896.17	16,780.77	10,910.61	117.16	115.10	91.29	6,136.11	145.83	612.21	380.33	231.878	2.640	
17,000.00	10,896.76	16,880.77	10,911.36	118.96	116.91	91.30	6,236.11	146.74	612.20	376.72	235.488	2.600	
17,100.00	10,897.36	16,980.77	10,912.12	120.76	118.71	91.32	6,336.10	147.65	612.19	373.09	239.101	2.560	
17,200.00	10,897.95	17,080.77	10,912.88	122.57	120.52	91.33	6,436.09	148.56	612.19	369.47	242.715	2.522	
17,300.00	10,898.54	17,180.77	10,913.64	124.37	122.33	91.35	6,536.09	149.47	612.18	365.84	246.332	2.485	
17,400.00	10,899.14	17,280.77	10,914.40	126.18	124.14	91.36	6,636.08	150.38	612.17	362.22	249.951	2.449	
17,500.00	10,899.73	17,380.77	10,915.15	127.98	125.95	91.38	6,736.07	151.29	612.16	358.59	253.572	2.414	
17,600.00	10,900.32	17,480.77	10,915.91	129.79	127.77	91.39	6,836.06	152.20	612.15	354.95	257.195	2.380	
17,700.00	10,900.92	17,580.77	10,916.67	131.60	129.58	91.41	6,936.06	153.11	612.14	351.32	260.819	2.347	
17,800.00	10,901.51	17,680.77	10,917.43	133.41	131.39	91.42	7,036.05	154.02	612.13	347.69	264.446	2.315	
17,877.86	10,901.97	17,758.63	10,918.02	134.82	132.81	91.44	7,113.90	154.73	612.12	344.85	267.271	2.290 SF	
17,882.45	10,902.00	17,756.07	10,918.00	134.91	132.76	91.44	7,111.34	154.71	612.12	344.98	267.187	2.291	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation


Anticollision Report

Company: COG OPERATING, LLC
Project: Eddy County, NM (NAD27) NMZ
Reference Site: Littlefield 33 Fed COM
Site Error: 0.00 usft
Reference Well: #806H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.000 sigma
Database: EDM 5000.14 Single User Db
Offset TVD Reference: Offset Datum

Reference Depths are relative to RKB @ 2883.00usft (Latshaw 44 - KB
 Offset Depths are relative to Offset Datum
 Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: #806H
 Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30
 Grid Convergence at Surface is: 0.18°



CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation


Anticollision Report

Company: COG OPERATING, LLC
Project: Eddy County, NM (NAD27) NMZ
Reference Site: Littlefield 33 Fed COM
Site Error: 0.00 usft
Reference Well: #806H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Plan #1 - IP

Local Co-ordinate Reference: Well #806H
TVD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
MD Reference: RKB @ 2883.00usft (Latshaw 44 - KB=25')
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.000 sigma
Database: EDM 5000.14 Single User Db
Offset TVD Reference: Offset Datum

Reference Depths are relative to RKB @ 2883.00usft (Latshaw 44 - KB
Offset Depths are relative to Offset Datum
Central Meridian is 104° 20' 0.000 W

Coordinates are relative to: #806H
Coordinate System is US State Plane 1927 (Exact solution), New Mexico East 30
Grid Convergence at Surface is: 0.18°



COG Operating, LLC - Littlefield 33 Federal Com 806H

1. Geologic Formations

TVD of target	10,062' EOL	Pilot hole depth	NA
MD at TD:	16,944'	Deepest expected fresh water:	200'

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Quaternary Fill	Surface	Water	
Rustler	488	Water	
Top of Salt	636	Salt	
Base of Salt	2642	Salt	
Lamar	2822	Salt Water	
Delaware	2860	Salt Water	
Bone Spring	6519	Oil/Gas	
1st Bone Spring	7436	Oil/Gas	
2nd Bone Spring	8585	Oil/Gas	
3rd Bone Spring	9300	Oil/Gas	
Wolfcamp	9664	Oil/Gas	
Wolfcamp B	10138	Oil/Gas	
Wolfcamp C	10432	Oil/Gas	
Wolfcamp D	10749	Target Oil/Gas	
Strawn	12183	Not Penetrated	

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Body
	From	To							
13.5"	0	600	10.75"	45.5	N80	BTC	9.00	1.41	38.10
9.875"	0	10065	7.875"	29.7	P110	BTC	1.51	1.45	3.63
6.75"	0	9565	5.5"	23	P110	BTC	2.52	2.66	4.03
6.75"	9565	16,944	5"	18	P110	BTC	2.52	2.66	4.03
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

Intermediate casing will be kept at least 1/3 full while running casing to mitigate collapse. Surface burst based on 0.7 frac gradient at the shoe with Gas Gradient 0.1 psi/ft to surface and
All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

The 5" casing will be run back 500' into the intermediate casing to ensure the coupling OD clearance is greater than .422" for the cement bond tie in.

COG Operating, LLC - Littlefield 33 Federal Com 806H

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary?	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

3. Cementing Program

Casing	# Sks	Wt. lb/ gal	Yld ft3/ sack	H ₂ O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surf.	30	13.5	1.75	9	12	Lead: Class C + 4% Gel + 1% CaCl ₂
	250	14.8	1.34	6.34	8	Tail: Class C + 2% CaCl ₂
Inter.	830	10.3	3.6	21.48	16	Tuned Light Blend
	250	16.4	1.08	4.32	8	Tail: Class H
Prod	40	11.9	2.5	19	72	Lead: 50:50:10 H Blend
	900	14.4	1.24	5.7	19	Tail: 50:50:2 Class H Blend

Volumes Subject to Observed Hole Conditions and/or Fluid Caliper Results

Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Casing String	TOC	% Excess
Surface	0'	75%
1 st Intermediate	0'	50%
Production	9,565'	35% OH in Lateral (KOP to EOL)

4. Pressure Control Equipment

N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
---	--

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	x	Tested to:
9-7/8"	13-5/8"	3M	Annular	x	3000 psi
			Blind Ram		3M
			Pipe Ram		
			Double Ram		
			Other*		
6-3/4"	13-5/8"	5M	Annular	x	50% testing pressure
			Blind Ram	x	5M
			Pipe Ram	x	
			Double Ram		
			Other*		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
Y	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?
N	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

COG Operating, LLC - Littlefield 33 Federal Com 806H

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	Surf. Shoe	FW Gel	8.6 - 8.8	28-34	N/C
Surf csg	9-5/8" Int shoe	Brine Diesel Emulsion	8.4 - 9	28-34	N/C
7-5/8" Int shoe	Lateral TD	OBM	9.6 - 11	35-45	<20

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
Y	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
Y	No Logs are planned based on well control or offset log information.
N	Drill stem test? If yes, explain.
N	Coring? If yes, explain.

Additional logs planned		Interval
N	Resistivity	Pilot Hole TD to ICP
N	Density	Pilot Hole TD to ICP
Y	CBL	Production casing (If cement not circulated to surface)
Y	Mud log	Intermediate shoe to TD
N	PEX	

COG Operating, LLC - Littlefield 33 Federal Com 806H

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	5760 psi at 10062' TVD
Abnormal Temperature	NO 160 Deg. F.

No abnormal pressure or temperature conditions are anticipated. Sufficient mud materials to maintain mud properties and weight increase requirements will be kept on location at all times.

Sufficient supplies of Paper/LCM for periodic sweeps to control seepage and losses will be maintained on location.

Hydrogen Sulfide (H ₂ S) monitors will be installed prior to drilling out the surface shoe. If H ₂ S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
N	H ₂ S is present
Y	H ₂ S Plan attached

8. Other Facets of Operation

Y	Is it a walking operation?
Y	Is casing pre-set?

x	H ₂ S Plan.
x	BOP & Choke Schematics.
x	Directional Plan



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

SUPO Data Report

08/02/2018

APD ID: 10400029027

Submission Date: 04/03/2018

highlighted data
reflects the most
recent changes

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

COG_Littlefield_806H_Exist_Rd_20180328144303.pdf

Existing Road Purpose: ACCESS

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

COG_Littlefield_806H_Maps_Plats_20180328152624.pdf

New road type: TWO-TRACK

Length: 83

Feet

Width (ft.): 30

Max slope (%): 33

Max grade (%): 1

Army Corp of Engineers (ACOE) permit required? NO

ACOE Permit Number(s):

New road travel width: 14

New road access erosion control: Water will be diverted where necessary to avoid ponding, prevent erosion, maintain good drainage, and to be consistent with local drainage patterns.

New road access plan or profile prepared? NO

New road access plan attachment:

Access road engineering design? NO

Access road engineering design attachment:

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Access surfacing type: OTHER

Access topsoil source: ONSITE

Access surfacing type description: Caliche

Access onsite topsoil source depth: 6

Offsite topsoil source description:

Onsite topsoil removal process: Blading

Access other construction information: No turnouts are planned. Re-routing access road around proposed well location.

Access miscellaneous information:

Number of access turnouts:

Access turnout map:

Drainage Control

New road drainage crossing: OTHER

Drainage Control comments: None necessary.

Road Drainage Control Structures (DCS) description: None needed.

Road Drainage Control Structures (DCS) attachment:

Access Additional Attachments

Additional Attachment(s):

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

COG_Littlefield_806H_1Mile_Data_20180328144319.pdf

Existing Wells description:

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

Production Facilities description: Production will be sent to the proposed Littlefield 33 CTB 1. A tank battery and facilities will be constructed adjacent to the north side of the Littlefield 33 Federal Com 705H, 706H, 805H and 806H as shown on the production facility layout. The tank battery and facilities will be installed according to API specifications. No flow lines are anticipated at this time.

Production Facilities map:

COG_Littlefield_CTB_1_20180328100744.pdf

COG_Littlefield_806H_Prod_Facility_20180328144332.pdf

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Section 5 - Location and Types of Water Supply

Water Source Table

Water source use type: INTERMEDIATE/PRODUCTION CASING

Water source type: OTHER

Describe type: Brine H2O

Source latitude:

Source longitude:

Source datum:

Water source permit type: PRIVATE CONTRACT

Source land ownership: COMMERCIAL

Water source transport method: TRUCKING

Source transportation land ownership: COMMERCIAL

Water source volume (barrels): 22500

Source volume (acre-feet): 2.9000947

Source volume (gal): 945000

Water source use type: STIMULATION, SURFACE CASING

Water source type: OTHER

Describe type: Fresh H2O

Source latitude:

Source longitude:

Source datum:

Water source permit type: PRIVATE CONTRACT

Source land ownership: PRIVATE

Water source transport method: PIPELINE

Source transportation land ownership: PRIVATE

Water source volume (barrels): 337500

Source volume (acre-feet): 43.50142

Source volume (gal): 14175000

Water source and transportation map:

COG_Littlefield_806H_BrineH2O_20180328144349.pdf

COG_Littlefield_806H_FreshH2O_20180328144400.pdf

Water source comments: Fresh water will be obtained from High Roller Wells, LLC CP-417610 water well located in Section 1. 58 T1. Brine water will be obtained from the Malaga I Brine station in Section 2. T21S. R25E., and will be provided by Malaga Brine Station.

New water well? NO

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method:

Drill material:

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Construction Materials description: Caliche will be obtained from the actual well site if available. If not available onsite, caliche will be obtained from Brantley caliche pit located in Section 14, T26S, R28E.

Construction Materials source location attachment:

Section 7 - Methods for Handling Waste

Waste type: DRILLING

Waste content description: Drilling fluids and produced oil and water during drilling and completion operations

Amount of waste: 6000 barrels

Waste disposal frequency : One Time Only

Safe containment description: All drilling waste will be stored safely and disposed of properly

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: Trucked to an approved disposal facility

Waste type: SEWAGE

Waste content description: Human waste and gray water

Amount of waste: 250 gallons

Waste disposal frequency : Weekly

Safe containment description: Waste will be properly contained and disposed of properly at a state approved disposal facility

Safe containmant attachment:

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: Trucked to an approved disposal facility

Waste type: GARBAGE

Waste content description: Garbage and trash produced during drilling and completion operations

Amount of waste: 125 pounds

Waste disposal frequency : Weekly

Safe containment description: Garbage and trash produced during drilling and completion operations will be collected in a trash container and disposed of properly at a state approved disposal facility

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: Trucked to an approved disposal facility

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit?

Reserve pit length (ft.) **Reserve pit width (ft.)**

Reserve pit depth (ft.) **Reserve pit volume (cu. yd.)**

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? YES

Description of cuttings location Roll off cuttings containers on tracks

Cuttings area length (ft.) **Cuttings area width (ft.)**

Cuttings area depth (ft.) **Cuttings area volume (cu. yd.)**

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: YES

Ancillary Facilities attachment:

COG_Littlefield_806H_GCP_20180328144507.pdf

Comments: GCP attached.

Section 9 - Well Site Layout

Well Site Layout Diagram:

COG_Littlefield_CTB_1_20180328102237.pdf

COG_Littlefield_806H_Prod_Facility_20180328144519.pdf

Comments: Production will be sent to the proposed Littlefield 33 CTB 1. A tank battery and facilities will be constructed adjacent to the north side of the Littlefield 33 Federal Com 705H, 706H, 805H and 806H as shown on the production facility layout. The tank battery and facilities will be installed according to API specifications. No flow lines are anticipated at this time.

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: LITTLEFIELD 33 FEDERAL COM

Multiple Well Pad Number: 705H, 706H, 805H AND 806H

Recontouring attachment:

Drainage/Erosion control construction: No waddles will be needed for this location, since the surface runoff will be controlled by the access road that is located on the west side of the pad.

Drainage/Erosion control reclamation: Reclaim east side 80'

Well pad proposed disturbance (acres): 3.67	Well pad interim reclamation (acres): 0.01	Well pad long term disturbance (acres): 2.94
Road proposed disturbance (acres): 0.03	Road interim reclamation (acres): 0.03	Road long term disturbance (acres): 0.03
Powerline proposed disturbance (acres): 0	Powerline interim reclamation (acres): 0	Powerline long term disturbance (acres): 0
Pipeline proposed disturbance (acres): 0	Pipeline interim reclamation (acres): 0	Pipeline long term disturbance (acres): 0
Other proposed disturbance (acres): 0	Other interim reclamation (acres): 0	Other long term disturbance (acres): 0
Total proposed disturbance: 3.7	Total interim reclamation: 0.04	Total long term disturbance: 2.97

Disturbance Comments:

Reconstruction method: New construction of pad.

Topsoil redistribution: East 80'

Soil treatment: None

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Existing Vegetation at the well pad: Shinnery Oak/Mesquite grassland

Existing Vegetation at the well pad attachment:

Existing Vegetation Community at the road: Shinnery Oak/Mesquite grassland

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline: Shinnery Oak/Mesquite grassland

Existing Vegetation Community at the pipeline attachment:

Existing Vegetation Community at other disturbances: N/A

Existing Vegetation Community at other disturbances attachment:

Non native seed used? NO

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? NO

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? NO

Seed harvest description:

Seed harvest description attachment:

Seed Management

Seed Table

Seed type:

Seed source:

Seed name:

Source name:

Source address:

Source phone:

Seed cultivar:

Seed use location:

PLS pounds per acre:

Proposed seeding season:

Seed Summary

Total pounds/Acre:

Seed Type	Pounds/Acre
-----------	-------------

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

Seed reclamation attachment:

Operator Contact/Responsible Official Contact Info

First Name: Rand

Last Name: French

Phone: (432)254-5556

Email: rfrench@concho.com

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? NO

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: N/A

Weed treatment plan attachment:

Monitoring plan description: N/A

Monitoring plan attachment:

Success standards: N/A

Pit closure description: N/A

Pit closure attachment:

COG_Littlefield_806H_Closed_Loop_20180328144537.pdf

Section 11 - Surface Ownership

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

Operator Name: COG OPERATING LLC

Well Name: LITTLEFIELD 33 FEDERAL COM

Well Number: 806H

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Section 12 - Other Information

Right of Way needed? NO

Use APD as ROW?

ROW Type(s):

ROW Applications

SUPO Additional Information:


Use a previously conducted onsite? YES

Previous Onsite information: Onsite completed on 1/16/2018 by Rand French (COG) and Jeff Robertson (BLM).

Other SUPO Attachment

COG_Littlefield_806H_Certification_20180328144728.pdf

SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
VICINITY MAP



DISTANCES IN MILES

NOT TO SCALE

DIRECTIONS TO LOCATION

FROM U.S. HWY 285 AND CALICHE CR. 726 (CATFISH RD.) GO EAST ON CR. 726 2.3 MILES TO A ROAD SURVEY AND FOLLOW FLAGS NORTH 83° TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

COG OPERATING, LLC
LITTLEFIELD 33 FED COM 806H
LOCATED 300 FT. FROM THE SOUTH LINE
AND 2406 FT. FROM THE WEST LINE OF
SECTION 33, TOWNSHIP 26 SOUTH,
RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018

SURVEY NO. 5787

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341


CARLSBAD, NEW MEXICO

SITE MAP

735'

EL. 2865.2'

EL. 2862.3'



015 75 150 300
SCALE 1" = 150'

CTIONS TO LOCATION
FROM U.S. HWY 285 AND CALICHE CR. 726 (CATFISH RD.) GO EAST ON CR. 726 2.3 MILES TO A ROAD SURVEY AND FOLLOW FLAGS NORTH 83' TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

I, FILMON F. JARAMILLO, A NEW MEXICO REGISTERED PROFESSIONAL SURVEYOR CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF. THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

[Signature]
DATE

COC OPERATING, LLC
LITTLEFIELD 33 FED COM 806H
LOCATED 300 FT. FROM THE SOUTH LINE
AND 2406 FT. FROM THE WEST LINE OF
SECTION 33, TOWNSHIP 26 SOUTH,
RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341
SURVEY NO. 5787

SITE MAP

735'

EL. 2865.2'

EL. 2862.3'

30'

TOP SOIL AREA

**LITTLEFIELD
33 CTB 1**

A	LITTLEFIELD 33 FED COM 706H
B	LITTLEFIELD 33 FED COM 806H
C	LITTLEFIELD 33 FED COM 705H
D	LITTLEFIELD 33 FED COM 805H

200' NORTH
OFFSET
EL. 2858.1'

N89°54'00"E

535.13 FT

EL. 2858.1'

PROPOSED PAD

EL. 2859.5'

BERM

200'

**LITTLEFIELD 33
FED COM 806H**

ELEV. = 2858.0'

4.914±

ACRES

LAT. = 32.0009264°N (NAD83)

LONG. = 105.9904338°W

NMSP EAST (FT)

N = 364245.09

E = 647631.49

200'

200' SOUTH
OFFSET
EL. 2858.5'

EL. 2857.0'

EL. 2864.7'

S89°54'03"W

KINDER MORGAN BPL

535.12 FT

PROPOSED 83 LF

ACCESS ROAD

BPL NO SIGN

B/W FENCE

CALICHE ROAD (CR. 726 CATFISH)

NEW MEXICO

TEXAS

EL. 2857.9'

735'

EL. 2858.7'

015 75 150 300

SCALE 1" = 150'

DIRECTIONS TO LOCATION

FROM U.S. HWY 285 AND CALICHE CR. 726 (CATFISH RD.) GO EAST
ON CR. 726 2.3 MILES TO A ROAD SURVEY AND FOLLOW FLAGS
NORTH 83° TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

I, FILIMON F. JARAMILLO, A NEW MEXICO REGISTERED PROFESSIONAL
SURVEYOR CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR
THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF AND THIS SURVEY AND PLAT
MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

COG OPERATING, LLC

LITTLEFIELD 33 FED COM 806H

LOCATED 300 FT. FROM THE SOUTH LINE

AND 2406 FT. FROM THE WEST LINE OF

SECTION 33, TOWNSHIP 26 SOUTH,

RANGE 29 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018

SURVEY NO. 5787

FILIMON F. JARAMILLO PLS# 128872


DATE

MADRON SURVEYING, INC.

301 SOUTH CANAL
(575) 234-3341

CARLSBAD, NEW MEXICO

SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
LOCATION VERIFICATION MAP



USGS QUAD MAP:
ROSS RANCH
RED BLUFF


NOT TO SCALE

COG OPERATING, LLC
LITTLEFIELD 33 FED COM 806H
LOCATED 300 FT. FROM THE SOUTH LINE
AND 2406 FT. FROM THE WEST LINE OF
SECTION 33, TOWNSHIP 26 SOUTH,
RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341 SURVEY NO. 5787

SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
VICINITY MAP



DISTANCES IN MILES

NOT TO SCALE

DIRECTIONS TO LOCATION

FROM U.S. HWY 285 AND CALICHE CR. 726 (CATFISH RD.) GO EAST ON CR. 726 2.3 MILES TO A ROAD SURVEY AND FOLLOW FLAGS NORTH 83° TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

COG OPERATING, LLC
LITTLEFIELD 33 FED COM 806H
LOCATED 300 FT. FROM THE SOUTH LINE
AND 2406 FT. FROM THE WEST LINE OF
SECTION 33, TOWNSHIP 26 SOUTH,
RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018

SURVEY NO. 5787

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341

CARLSBAD, NEW MEXICO


LITTLEFIELD 33 CTB 1

COG OPERATING, LLC

IN THE SW/4 LOT 6, SE/7 LOT 7, NE/4 LOT 10, & NW/4 LOT 11 OF
SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018

AERIAL PHOTO




SHEET: 3-3

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SURVEY NO. 5959

SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL ACCESS ROUTE MAP



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
NOV. 2015

COG OPERATING, LLC
LITTLEFIELD 33 FED COM 806H
LOCATED 300 FT. FROM THE SOUTH LINE
AND 2406 FT. FROM THE WEST LINE OF
SECTION 33, TOWNSHIP 26 SOUTH,
RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018

SURVEY NO. 5787



MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

ACCESS ROAD PLAT


ACCESS ROAD FROM CR. 726 (CATFISH RD.) TO LITTLEFIELD 33 FED COM 708H, 808H, 707H, & 807H

COG OPERATING, LLC

CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MARCH 28, 2018



SEE NEXT SHEET (2-5) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 1-5

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 28 DAY OF MARCH 2018

FILMON F. JARAMILLO, PLS 12797

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6134

ACCESS ROAD PLAT

ACCESS ROAD FROM CR. 726 (CATFISH RD.) TO LITTLEFIELD 33 FED COM 708H, 808H, 707H, & 807H

COG OPERATING, LLC

CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MARCH 28, 2018

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN LOT 9 OF SAID SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M., WHENCE THE SOUTHWEST CLOSING CORNER OF SAID SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M. BEARS S89°06'28"W, A DISTANCE OF 1062.89 FEET;
THENCE N00°12'38"W A DISTANCE OF 35.12 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHWEST CLOSING CORNER OF SAID SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M. BEARS S87°12'59"W, A DISTANCE OF 1063.89 FEET;

SAID STRIP OF LAND BEING 35.12 FEET OR 2.13 RODS IN LENGTH, CONTAINING 0.024 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

LOT 9 35.12 L.F. 2.13 RODS 0.024 ACRES

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 27TH DAY OF MARCH 2018.

FILMON F. JARAMILLO PLS 12797

301 SOUTH CANAL
(575) 234-3341

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6134

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO


GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-5

ACCESS ROAD FROM CR. 726 (CATFISH RD.) TO LITTLEFIELD 33 FED COM 708H, 808H, 707H, & 807H

COG OPERATING, LLC
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MARCH 28, 2018



MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 **CARLSBAD, NEW MEXICO**

SURVEY NO. 6134


CARLSBAD, NEW MEXICO

ACCESS ROAD PLAT

ACCESS ROAD FROM CR. 726 (CATFISH RD.) TO LITTLEFIELD 33 FED COM 708H, 808H, 707H, & 807H

COG OPERATING, LLC

CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MARCH 28, 2018



SHEET: 4-5

SURVEY NO. 6134


MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

ACCESS ROAD PLAT

ACCESS ROAD FROM CR. 726 (CATFISH RD.) TO LITTLEFIELD 33 FED COM 708H, 808H, 707H, & 807H

COG OPERATING, LLC

**CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MARCH 28, 2018**



■ BLM LAND ■ STATE LAND □ FEE LAND

SHEET: 5-5


MADRON SURVEYING, INC.

301 SOUTH CANAL
(575) 234-3341

CARLSBAD, NEW MEXICO

SURVEY NO. 6134

1-MILE MAP



- SH SURFACE LOCATION
- BH BOTTOM OF HOLE
- XY WELLS WITHIN 1 MILE

COG OPERATING, LLC
LITTLEFIELD 33 FED COM 806H
 LOCATED 300 FT. FROM THE SOUTH LINE
 AND 2406 FT. FROM THE WEST LINE OF
 SECTION 33, TOWNSHIP 26 SOUTH,
 RANGE 29 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 **CARLSBAD, NEW MEXICO**

SURVEY NO. 5787

[illegible]


CONCHO
COG Operating LLC
2208 West Main Street
Artesia, NM 88210

Well Site Layout

Production Facility Layout

Littlefield 33 CTB 1
Section 33- T26S- R29E

Exhibit 3




Legend
O = 750 BBL Steel Oil Tank
W = 750 BBL Steel Water Tank
S = 1000 BBL Steel Water Tank
2P = 2 Phase Separator
3P = 3Phase Separator
HT = Heater Treater
X = Valve
G = Gas Scrubber
CP = Control Panel

LITTLEFIELD 33 CTB 1

COG OPERATING, LLC

IN THE SW/4 LOT 6, SE/7 LOT 7, NE/4 LOT 10, & NW/4 LOT 11 OF
SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018



DESCRIPTION

A CERTAIN PIECE OR PARCEL OF LAND AND REAL ESTATE LYING IN BUREAU OF LAND MANAGEMENT LAND IN THE SW/4 LOT 6, SE/7 LOT 7, NE/4 LOT 10, & NW/4 LOT 11 OF SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

BEGINNING AT THE NORTHEAST CORNER OF THE PARCEL, WHENCE THE NORTH QUARTER CORNER OF SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M. BEARS N01°37'33\"W, A DISTANCE OF 1471.89 FEET; THENCE S00°06'49\"E A DISTANCE OF 400.02 FEET TO THE SOUTHEAST CORNER OF THE PARCEL; THENCE S89°54'00\"W A DISTANCE OF 535.13 FEET TO THE SOUTHWEST CORNER OF THE PARCEL; THENCE N00°05'39\"W A DISTANCE OF 399.98 FEET TO THE NORTHWEST CORNER OF THE PARCEL; THENCE N89°53'44\"E A DISTANCE OF 534.99 FEET TO THE NORTHEAST CORNER OF THE PARCEL, THE POINT OF BEGINNING; CONTAINING 4.913 ACRES MORE OR LESS.

GENERAL NOTES

1.) THE INTENT OF THIS SURVEY IS TO ACQUIRE A BUSINESS LEASE FOR THE PURPOSE OF BUILDING A CENTRAL TANK BATTERY

2.) BASIS OF BEARING IS NEW MEXICO STATE PLANE EAST ZONE MODIFIED TO THE SURFACE (NAD83), COORDINATES ARE NAD 83, ELEVATIONS ARE NAVD 88

DRIVING DIRECTIONS: FROM U.S. HWY 285 AND CALICHE CR. 726 (CATFISH RD.) GO EAST ON CR. 726 2.3 MILES TO A ROAD SURVEY AND FOLLOW FLAGS NORTH 483' TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

SHEET: 1-3

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 17th DAY OF JANUARY, 2018

FILMON F. JARAMILLO, PLS. 12797
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 5959

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO


LITTLEFIELD 33 CTB 1

COG OPERATING, LLC

IN THE SW/4 LOT 6, SE/7 LOT 7, NE/4 LOT 10, & NW/4 LOT 11 OF
SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018

QUAD MAP



SHEET: 2-3

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SURVEY NO. 5959


LITTLEFIELD 33 CTB 1

COG OPERATING, LLC

IN THE SW/4 LOT 6, SE/7 LOT 7, NE/4 LOT 10, & NW/4 LOT 11 OF
SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018

AERIAL PHOTO



SHEET: 3-3

MADRON SURVEYING, INC.


301 SOUTH CANAL
(575) 234-3341



CARLSBAD, NEW MEXICO

SURVEY NO. 5959

**Well Site Layout
Production Facility Layout**
Littlefield 33 Federal Com 806H
Section 33 - 26S - 29E

Exhibit 3





Map Legend

Littlefield 33 Fed Com #806H To Malaga I Brine

Date: 3/21/2018
Author: Whynne McDonald
State: New Mexico
County: Eddy

Disclaimer: This is not a legal survey document.

Route

0 0.75 1.5 3 4.5 6 Miles




CONCHO
COG Operating LLC
2208 West Main Street
Artesia, NM 88210

Well Site Layout

Production Facility Layout

Littlefield 33 CTB 1
Section 33- T26S- R29E

Exhibit 3



North


Legend
O = 750 BBL Steel Oil Tank
W = 750 BBL Steel Water Tank
S = 1000 BBL Steel Water Tank
2P = 2 Phase Separator
3P = 3Phase Separator
HT = Heater Treater
X = Valve
G = Gas Scrubber
CP = Control Panel

LITTLEFIELD 33 CTB 1

COG OPERATING, LLC

IN THE SW/4 LOT 6, SE/7 LOT 7, NE/4 LOT 10, & NW/4 LOT 11 OF
SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018



DESCRIPTION

A CERTAIN PIECE OR PARCEL OF LAND AND REAL ESTATE LYING IN BUREAU OF LAND MANAGEMENT LAND IN THE SW/4 LOT 6, SE/7 LOT 7, NE/4 LOT 10, & NW/4 LOT 11 OF SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

BEGINNING AT THE NORTHEAST CORNER OF THE PARCEL, WHENCE THE NORTH QUARTER CORNER OF SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M. BEARS N01°37'33"W, A DISTANCE OF 1471.89 FEET;
THENCE S00°06'49"E A DISTANCE OF 400.02 FEET TO THE SOUTHEAST CORNER OF THE PARCEL;
THENCE S89°54'00"W A DISTANCE OF 535.13 FEET TO THE SOUTHWEST CORNER OF THE PARCEL;
THENCE N00°05'39"W A DISTANCE OF 399.98 FEET TO THE NORTHWEST CORNER OF THE PARCEL;
THENCE N89°53'44"E A DISTANCE OF 534.99 FEET TO THE NORTHEAST CORNER OF THE PARCEL, THE POINT OF BEGINNING;
CONTAINING 4.913 ACRES MORE OR LESS.

GENERAL NOTES

- 1.) THE INTENT OF THIS SURVEY IS TO ACQUIRE A BUSINESS LEASE FOR THE PURPOSE OF BUILDING A CENTRAL TANK BATTERY
- 2.) BASIS OF BEARING IS NEW MEXICO STATE PLANE EAST ZONE MODIFIED TO THE SURFACE (NAD83), COORDINATES ARE NAD 83, ELEVATIONS ARE NAVD 88

DRIVING DIRECTIONS: FROM U.S. HWY 285 AND CALICHE CR. 726 (CATFISH RD.) GO EAST ON CR. 726 2.3 MILES TO A ROAD SURVEY AND FOLLOW FLAGS NORTH 483' TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

SHEET: 1-3

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 17TH DAY OF JANUARY 2018

FILMON F. JARAMILLO, PLS. 12797
MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 5959


LITTLEFIELD 33 CTB 1

COG OPERATING, LLC

IN THE SW/4 LOT 6, SE/7 LOT 7, NE/4 LOT 10, & NW/4 LOT 11 OF
SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018

QUAD MAP



SHEET: 2-3

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SURVEY NO. 5959


LITTLEFIELD 33 CTB 1

COG OPERATING, LLC

IN THE SW/4 LOT 6, SE/7 LOT 7, NE/4 LOT 10, & NW/4 LOT 11 OF
SECTION 33, TOWNSHIP 26 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JANUARY 17, 2018

AERIAL PHOTO



SHEET: 3-3

MADRON SURVEYING, INC.


301 SOUTH CANAL
(575) 234-3361

CARLSBAD, NEW MEXICO

SURVEY NO. 5959

**Well Site Layout
Production Facility Layout**
Littlefield 33 Federal Com 806H
Section 33 - 26S - 29E

Exhibit 3







Exhibit 1

"I further certify that COG will comply with Rule 19.15.17 NMAC by using a Closed Loop System."

Surface Use Plan
COG Operating LLC
Littlefield 33 Federal Com 806H
SHL: 300' FSL & 2406' FWL Lot 10
Section 33, T26S, R29E
BHL: 200' FNL & 1884' FWL UL C
Section 28, T26S, R29E
Eddy County, New Mexico

OPERATOR CERTIFICATION

I hereby certify that I, or persons under my direct supervision, have inspected the drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or COG Operating LLC, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 22nd day of MARCH, 2018.

Signed: 

Printed Name: Mayte Reyes

Position: Senior Regulatory Analyst

Address: 2208 W. Main Street, Artesia, NM 88210

Telephone: (575) 748-6945

E-mail: mreyes1@concho.com

Field Representative (if not above signatory): Rand French

Telephone: (575) 748-6940. E-mail: rfrench@concho.com



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

PWD Data Report

08/02/2018

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Assigned injection well API number?

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Injection well name:

Injection well API number:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment:



**U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT**

Bond Info Data Report

08/02/2018

Bond Information

Federal/Indian APD: FED

BLM Bond number: NMB000215

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment: