

**NM OIL CONSERVATION
ARTESIA DISTRICT**

SEP 28 2018

Form 3160-3
(June 2015)

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

RECEIVED

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other 1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone			5. Lease Serial No. NMNM0404441 6. If Indian, Allottee or Tribe Name 7. If Unit or CA Agreement, Name and No. 8. Lease Name and Well No. BELLOQ 11 FED 222H 322488 9. API Well No. 6137 30-015-45275	
2. Name of Operator DEVON ENERGY PRODUCTION COMPANY LP			10. Field and Pool, or Exploratory LIVINGSTON RIDGE / BONESPRING	
3a. Address 333 West Sheridan Avenue Oklahoma City OK 73102			3b. Phone No. (include area code) (405)552-6571	
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface SWSW / 300 FSL / 510 FWL / LAT 32.3125667 / LONG -103.7554734 At proposed prod. zone NENW / 100 FNL / 1980 FWL / LAT 32.3259675 / LONG -103.7507192			11. Sec., T. R. M. or Blk. and Survey or Area SEC 11 / T23S / R31E / NMP	
14. Distance in miles and direction from nearest town or post office*			12. County or Parish EDDY	
13. State NM				
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 300 feet			16. No of acres in lease 1440	
17. Spacing Unit dedicated to this well 160				
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 440 feet			19. Proposed Depth 10341 feet / 15316 feet	
20. BLM/BIA Bond No. in file FED: CO1104				
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3428 feet			22. Approximate date work will start* 12/15/2018	
23. Estimated duration 45 days				
24. Attachments				
The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)				
1. Well plat certified by a registered surveyor. 2. A Drilling Plan. 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). 5. Operator certification. 6. Such other site specific information and/or plans as may be requested by the BLM.				
25. Signature (Electronic Submission)			Name (Printed/Typed) Jenny Harms / Ph: (405)552-6560	
Title Regulatory Compliance Professional			Date 08/25/2017	
Approved by (Signature) (Electronic Submission)			Name (Printed/Typed) Cody Layton / Ph: (575)234-5959	
Title Assistant Field Manager Lands & Minerals			Date 09/24/2018	
Office CARLSBAD				
Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached.				
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.				

APPROVED WITH CONDITIONS

(Continued on page 2)

Approval Date: 09/24/2018

*(Instructions on page 2)

INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM 1: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM connects this information to a new evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

1. SHL: SWSW / 300 FSL / 510 FWL / TWSP: 23S / RANGE: 31E / SECTION: 11 / LAT: 32.3125667 / LONG: -103.7554734 (TVD: 0 feet, MD: 0 feet)
PPP: SESW / 100 FSL / 1825 FWL / TWSP: 23S / RANGE: 31E / SECTION: 11 / LAT: 32.312 / LONG: -103.751231 (TVD: 9849 feet, MD: 9974 feet)
BHL: NENW / 100 FNL / 1980 FWL / TWSP: 23S / RANGE: 31E / SECTION: 11 / LAT: 32.3259675 / LONG: -103.7507192 (TVD: 10341 feet, MD: 15316 feet)

BLM Point of Contact

Name: Tenille Ortiz

Title: Legal Instruments Examiner

Phone: 5752342224

Email: tortiz@blm.gov

CONFIDENTIAL

Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

CONFIDENTIAL

**PECOS DISTRICT
DRILLING OPERATIONS
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	Devon Energy Production Company, L.P>
LEASE NO.:	NMNM-0404441
WELL NAME & NO.:	Belloq 11 Fed 212H
SURFACE HOLE FOOTAGE:	0300' FSL & 1850' FWL
BOTTOM HOLE FOOTAGE	0290' FNL & 1980' FWL
LOCATION:	Section 11, T. 23 S., R 31 E., NMPM
COUNTY:	County, New Mexico

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☐ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

A. Hydrogen Sulfide

1. **Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.

4. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Potash Areas:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log.

Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

R-111-P Potash/WIPP

Possible water flows in the Salado and Castile.

Possible lost circulation in the Red Beds, Rustler, and Delaware.

Abnormal pressures may exist within the 3rd Bone Spring Sandstone and subsequent formations.

1. The 13-3/8 inch surface casing shall be set at approximately 715 feet (**in a competent bed below the Magenta Dolomite, which is a Member of the Rustler, and if salt is encountered, set casing at least 25 feet above the salt**) and cemented to the surface. **Excess calculates to 11% - Additional cement may be required.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Intermediate casing shall be kept fluid filled while running into hole to meet BLM minimum collapse requirements.

2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:

☐ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to potash. Excess calculates to 23% - Additional cement may be required.**

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
☐ Cement to surface. If cement does not circulate, contact the appropriate BLM office. **Excess calculates to 7% - Additional cement may be required.**
4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

5. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).
3. **Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be psi.**
 - a. **Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.**
 - b. **If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.**
 - c. **Manufacturer representative shall install the test plug for the initial BOP test.**
 - d. **Operator shall perform the intermediate casing integrity test to 70% of the casing burst. This will test the multi-bowl seals.**
 - e. **If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.**

4. The appropriate BLM office shall be notified a minimum of hours in advance for a representative to witness the tests.
- a. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**.
 - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - d. The results of the test shall be reported to the appropriate BLM office.
 - e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
 - f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

C. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

E. WIPP Requirements

The proposed well is located within 330' of the WIPP Land Withdrawal Area boundary. As a result, Devon Energy Production Company, L. P. is required to submit daily drilling reports, logs and deviation survey information to the Bureau of Land Management and the Department of Energy per requirements of the Joint Powers Agreement until a total vertical depth of 7,000 feet is reached. These reports will have at a minimum the rate of penetration and a clearly marked section showing the deviation for each 500 foot interval. Operator may be required to do more frequent deviation surveys based on the daily information submitted and may be required to take other corrective measures. Information from this well will be included in the Quarterly Drilling Report. Information will also be provided to the New Mexico Oil Conservation Division after drilling activities have been completed. Upon completion of the well, the operator shall submit a complete directional survey. Any future entry into the well for purposes of completing additional drilling will require supplemental information.

Devon Energy Production Company, L. P. can email the required information to Mr. Melvin Balderrama at Melvin.Balderama@wipp.ws or Mr. J. Neatherlin at Jimmy.Neatherlin@wipp.ws fax to his attention at 575-234-6062.

JAM 012918

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	DEVON ENERGY PRODUCTION
LEASE NO.:	NMNM0404441
WELL NAME & NO.:	BELLOQ 11 FED 222H
SURFACE HOLE FOOTAGE:	300'/S & 1850'/W
BOTTOM HOLE FOOTAGE:	290'/N & 1980'/W
LOCATION:	SECTION 11, T23S, R31E
COUNTY:	EDDY

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Lesser Prairie-Chicken Timing Stipulations
 - Ground-level Abandoned Well Marker
 - Wildlife
 - Range
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Oil & Gas Related Sites
 - Pipelines
 - Electric Lines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

Livestock Watering Requirement

Devon must contact the allotment holder prior to construction to identify the location of the pipeline. Devon must take measures to protect the pipeline from compression or other damages. If the pipeline is damaged or compromised in any way near the proposed project as a result of oil and gas activity, Devon is responsible for repairing the pipeline immediately. Devon must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that provide water to livestock.

During construction, Devon shall minimize disturbance to existing fences, water lines, troughs, windmills, and other improvements on public lands. Devon is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the grazing permittee/allottee prior to disturbing any range improvement projects. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

Wildlife Corridors

Two 330 x 1,400-foot protected wildlife corridors would be designated within the Uber North Drill Island 11-14. One corridor would be located along the west section edge (0' FWL extending 330' east) and the second corridor would be located 1645' FEL extending 330' west. This area would encompass the draw (riparian habitat) and dunes within the drill island area. No oil and gas development or construction activities would be allowed within this corridor.

Escape Ramps

Devon would need to construct and maintain escape ramps according to the following criteria:

- Earthen escape ramps would be required to be constructed to sufficiently support livestock at no more than a 30-degree slope and spaced no more than 500 feet apart.
- If trench is left open under an 8-hour time period, it would not be required to have an escape ramp; however, before the trench is backfilled, Lucid would inspect the trench for wildlife and remove any species that are trapped at a distance of at least 100 yards away from the trench.

During the onsite examination, Devon worked with the BLM to locate the proposed pads off of dune features and out of riparian habitat identified within the drill island area. Devon would be required to keep all oil and gas development and construction activities out of these areas.

Wildlife Corridors

Two 330 x 1,400-foot protected wildlife corridors would be designated within the Uber North Drill Island 11-14. One corridor would be located along the west section edge (0' FWL extending 330' east) and the second corridor would be located 1645' FEL extending 330' west. This area would encompass the draw (riparian habitat) and dunes within the drill island area. No oil and gas development or construction activities would be allowed within this corridor.

Raptor Nest Mitigation

- A BLM Wildlife Biologist must be contacted by the operator prior to construction activities to determine if the raptor nest is active.
- Raptor nests on special, natural habitat features, such as trees, large brush, cliff faces and escarpments, will be protected by not allowing surface disturbance within up to 200 meters of nests or by delaying activity for up to 90 days, or a combination of both. Exceptions to this requirement for raptor nests will be considered if the nests expected to be disturbed are inactive, the proposed activity is of short duration (e.g. habitat enhancement projects, fences, pipelines), and will not result in continuing activity in proximity to the nest.
- Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db. measured at 30 ft. from the source of the noise.

Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006. The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all power line structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. The holder without liability or expense shall make such modifications and/or additions to the United States.

Permitted Exceptions for Drilling in the Designated Potash Area

1. Drilling within the Designated Potash Area. It is the intent of the Department of the Interior to administer oil and gas operations throughout the Designated Potash Area in a manner which promotes safe, orderly co-development of oil, gas, and potash resources. It is the policy of the Department of the Interior to deny approval of most applications for permits to drill oil and gas wells from surface locations within the Designated Potash Area. Three exceptions to this policy will be permitted if the drilling will occur under the following conditions from:
 - a. A Drilling Island associated with a Development Area established under this Order or a Drilling Island established under a prior Order;

- b. A Barren Area and the Authorized Officer determines that such operations will not adversely affect active or planned potash mining operations in the immediate vicinity of the proposed drill-site; or
- c. A Drilling Island, not covered by (a) above or single well site established under this Order by the approval and in the sole discretion of the Authorized Officer, provided that such site was jointly recommended to the Authorized Officer by the oil and gas lessee(s) and the nearest potash lessee(s).

Development Areas

- 2. When processing an application for permit to drill (APD) an oil or gas well in the Designated Potash Area that complies with regulatory requirements, the Authorized Officer will determine whether to establish a Development Area in connection with the application, and if so, will determine the boundaries of the Development Area and the location within the Development Area of one or more Drilling Islands from which drilling will be permitted. The BLM may also designate a Development Area outside of the APD process based on information in its possession, and may modify the boundaries of a Development Area. Existing wells may be included within the boundaries of a Development Area. A Development Area may include Federal oil and gas leases and other Federal and non-Federal lands.
 - a. After designating or modifying a Development Area, the BLM will issue a Notice to Lessees, consistent with its authorities under 43 CFR Subpart 3105 and part 3180, information lessees that future drilling on lands under an oil and gas lease within that Development Area will:
 - i. occur, under most circumstances, from a Barren Area or A Drilling Island within the Development Area; and
 - ii. be managed under a unit or communitization agreement, generally by a single operator, consistent with BLM regulations and this Order. Unit and communitization agreements will be negotiated among lessees. The BLM will consider whether a specific plan of development is necessary or advisable for a particular Drilling Island.
 - b. The Authorized Officer reserves the right to approve an operator or successor operator of a Development Area and/or a Drilling Island, if applicable, to ensure that the operator has the resources to operate and extract the oil and gas resources consistent with the requirements of this Order and all applicable laws and regulations, and has provided financial assurance in the amount required by the Authorized Officer.
 - c. The Authorized Officer will determine the appropriate designation of a Development Area in terms of location, shape and size. In most cases, a single Drilling Island will be established for each Development Area. In establishing the location, shape and size of a Development Area and an associated Drilling Island, the Authorized Officer will consider:
 - i. the appropriate location, shape, and size of a Development Area and associated Drillings Island to allow effective extraction of oil and gas resources while managing the impact on potash resources;
 - ii. the application of available oil and gas drilling and production technology in the Permian Basin;

- iii. the applicable geology of the Designated Potash Area and optimal locations to minimize loss of potash ore while considering co-development of both resources;
 - iv. any long term exploration and/or mining plans provided by the potash industry;
 - v. whether a Barren Area may be the most appropriate area for a Drilling Island;
 - vi. the requirements of this Order; and
 - vii. any other relevant factors
- d. As the Authorized Officer establishes a Development Area, the Authorized Officer will more strictly apply the factors listed in Section 6.e.(2)(d), especially the appropriate application of the available oil and gas drilling and production technology in the Permian Basin, when closer to current traditional (non-solution) potash mining operations. Greater flexibility in the application of the factors listed in Section 6.e(2)(d) will be applied further from current and near-term traditional (non-solution) potash mining operations. No Drilling Islands will be established within one mile of any area where approved potash mining operations will be conducted within 3 years consistent with the 3-year mine plan referenced above (Section 6.d.(8)) without the consent of the affected potash lessee(s).
 - e. The Authorized Officer may establish a Development Area associated with a well or wells drilled from a Barren Area as appropriate and necessary.
 - f. As part of the consideration for establishing Development Areas and Drilling Islands, the BLM will consider input from the potash lessees and the oil and gas lessees or mineral right owner who would be potentially subject to a unitization agreement supporting the Development Area, provided that the input is given timely.

Buffer Zones

- 3. Buffer Zones of ¼ mile for oil wells and ½ mile for gas wells are hereby established. These Buffer Zones will stay in effect until such time as revised distances are adopted by the BLM Director or other BLM official, as delegated. However, the Authorized Officer may adjust the Buffer Zones in an individual case, when the facts and circumstances demonstrate that such adjustment would enhance conservation and would not compromise safety. The Director will base revised Buffer Zones on science, engineering, and new technology and will consider comments and reports from the Joint Industry Technical Committee and other interested parties in adopting any revisions.

Unitization and Communitization

- 4. To more properly conserve the potash, oil and gas resources in the Designated Potash Area and to adequately protect the rights of all parties in interest, including the United States, it is the policy of the Department of the Interior that all Federal oil and gas leases within a Development Area should be unitized or subject to an approved communitization agreement unless there is a compelling reason for another operating system. The Authorized Officer will make full use of his/her authorities wherever necessary or advisable to require unitization and/or communitization pursuant to the regulations in 43 CFR Subparts 3105 and 3180. The Authorized Officer will use his/her discretion to the fullest extent possible to assure that any communitization agreement and any unit plan of operations hereafter approved or prescribed within the Designated Potash Area will

adhere to the provisions of this Order. The Authorized Officer will work with Federal lessees, and with the State Of New Mexico as provided below, to include non-Federal mineral rights owners in unit or communitization agreements to the extent possible.

5. Coordination with the State of New Mexico.

- a. If the effective operation of any Development Area requires that the New Mexico Oil Conservation Division (NMOCD) revise the State's mandatory well spacing requirements, the BLM will participate as needed in such a process. The BLM may adopt the NMOCD spacing requirements and require lessees to enter into communitization agreements based on those requirements.
- b. The BLM will cooperate with the NMOCD in the implementation of that agency's rules and regulations.
- c. In taking any action under Section 6.e. of this Order, the Authorized Officer will take into consideration the applicable rules and regulations of the NMOCD.

To minimize impacts to potash resources, the proposed well is confined within the boundaries of the established Uber North Drill Island (See Potash Memo and Map in attached file for Drill Island description).

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and inslaping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.


Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.


Construction Steps

1. Salvage topsoil
2. Construct road


3. Redistribute topsoil
4. Revegetate slopes




Typical Turnout Plan




Level Ground Section



Side Hill Section



Typical Outslope Section



Typical Inslope Section

Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

STANDARD STIPULATIONS FOR OIL AND GAS RELATED SITES

A copy of the application (Grant/Sundry Notice) and attachments, including stipulations and map, will be on location during construction. BLM personnel may request to view a copy of your permit during construction to ensure compliance with all stipulations.

The holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer, BLM.

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant and for all response costs, penalties, damages, claims, and other costs arising from the provisions of the Resource Conservation and Recovery Act (RCRA), 42 U.S.C. Chap. 82, Section 6901 et. seq., from the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), 42 U.S.C. Chap. 109, Section 9601 et. seq., and from other applicable environmental statutes.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976, as amended (15 U.S.C. 2601, et. seq.) with regard to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized by this grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation and Liability Act, Section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et. seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et. seq.) on the right-of-way (unless the release or threatened release is wholly unrelated to

the right-of-way holder's activity on the right-of-way). This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the site or related pipeline(s), any oil or other pollutant should be discharged from site facilities, the pipeline(s) or from containers or vehicles impacting Federal lands, the control and total removal, disposal, and cleanup of such oil or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages to Federal lands resulting therefrom, the Authorized Officer may take such measures as deemed necessary to control and cleanup the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any liability or responsibility.

5. Sites shall be maintained in an orderly, sanitary condition at all times. Waste materials, both liquid and solid, shall be disposed of promptly at an appropriate, authorized waste disposal facility in accordance with all applicable State and Federal laws. "Waste" means all discarded matter including, but not limited to, human waste, trash, garbage, refuse, petroleum products, brines, chemicals, oil drums, ashes, and equipment.

6. The operator will notify the Bureau of Land Management (BLM) authorized officer and nearest Fish and Wildlife Service (FWS) Law Enforcement office within 24 hours, if the operator discovers a dead or injured federally protected species (i.e., migratory bird species, bald or golden eagle, or species listed by the FWS as threatened or endangered) in or adjacent to a pit, trench, tank, exhaust stack, or fence. (If the operator is unable to contact the FWS Law Enforcement office, the operator must contact the nearest FWS Ecological Services office.)

7. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" designated by the Rocky Mountain Five-State Interagency Committee. The color selected for this project is **Shale Green**, Munsell Soil Color Chart Number 5Y 4/2.

8. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on the holder's behalf, on public or Federal land shall be immediately reported to the Authorized Officer. The holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to the proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

9. A sales contract for removal of mineral material (caliche, sand, gravel, fill dirt) from an authorized pit, site, or on location must be obtained from the BLM prior to commencing construction. There are several options available for purchasing mineral material: contact the BLM office (575-234-5972).

10. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

11. Once the site is no longer in service or use, the site must undergo final abandonment. At final abandonment, the site and access roads must undergo "final" reclamation so that the character and productivity of the land are restored. Earthwork for final reclamation must be completed within six (6) months of the abandonment of the site. All pads and facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact. After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

12. The holder shall stockpile an adequate amount of topsoil where blading occurs. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles. The topsoil will be used for final reclamation.

13. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

- | | |
|---|---|
| <input type="checkbox"/> seed mixture 1 | <input type="checkbox"/> seed mixture 3 |
| <input type="checkbox"/> seed mixture 2 | <input type="checkbox"/> seed mixture 4 |
| <input checked="" type="checkbox"/> seed mixture 2/LPC <input type="checkbox"/> Aplomado Falcon Mixture | |

14. In those areas where erosion control structures are required to stabilize soil conditions, the holder shall install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound management practices. Any earth work will require prior approval by the Authorized Officer.

15. Open-topped Tanks - The operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps

16. The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an

impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S.

Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock enclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

17. Open-Vent Exhaust Stack Enclosures – The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (Recommended enclosure structures on open-vent exhaust stacks are in the shape of a cone.) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

18. Containment Structures - Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

19. Special Stipulations:

Lesser Prairie-Chicken

Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted. Exhaust noise from permanent engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

B. PIPELINES

BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the

Resource Conservation and Recovery Act, 42 U.S.C.6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.
6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.
7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:
- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
 - Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
 - The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)
8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.
9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.
11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

☐ seed mixture 1

☐ seed mixture 3

☐ seed mixture 2

☐ seed mixture 4

☒ seed mixture 2/LPC

☐ Aplomado Falcon Mixture

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches that are not otherwise fenced, screened, or netted to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or

other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

19. Special Stipulations:

Lesser Prairie-Chicken

Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

C. ELECTRIC LINES

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to

any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.

5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes from the poles removed.

Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials

Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Below Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

Species	lb/acre
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Jenny Harms**Signed on:** 08/25/2017**Title:** Regulatory Compliance Professional**Street Address:** 333 W Sheridan Ave**City:** Oklahoma City**State:** OK**Zip:** 73102**Phone:** (405)552-6560**Email address:** jenny.harms@dvn.com**Field Representative****Representative Name:** Ray Vaz**Street Address:** 6488 Seven Rivers Hwy**City:** Artesia**State:** NM**Zip:** 88210**Phone:** (575)748-1871**Email address:** ray.vaz@dvn.com

APD ID: 10400020749

Submission Date: 08/25/2017

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Type: OIL WELL

Well Work Type: Drill


[Show Final Text](#)**Section 1 - General**

APD ID: 10400020749

Tie to previous NOS?

Submission Date: 08/25/2017

BLM Office: CARLSBAD

User: Jenny Harms

Title: Regulatory Compliance

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM0404441

Lease Acres: 1440

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO

APD Operator: DEVON ENERGY PRODUCTION COMPANY LP

Operator letter of designation:

Operator Info

Operator Organization Name: DEVON ENERGY PRODUCTION COMPANY LP

Operator Address: 333 West Sheridan Avenue

Zip: 73102

Operator PO Box:

Operator City: Oklahoma City State: OK

Operator Phone: (405)552-6571

Operator Internet Address:

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: BELLOQ 11 FED

 Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: LIVINGSTON
RIDGE

Pool Name: BONESPRING

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Is the proposed well in an area containing other mineral resources? NATURAL GAS,OIL

Describe other minerals:

Is the proposed well in a Helium production area? N Use Existing Well Pad? YES New surface disturbance? Y

Type of Well Pad: MULTIPLE WELL

Well Class: HORIZONTAL

Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Describe sub-type:

Distance to town:

Distance to lease line: 300 FT

Reservoir well spacing assigned acres Measurement: 160 Acres

Well plat: BELLOQ_11_FED_222H_C_102_8_10_2018_20180814143221.pdf

Duration: 45 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1		FSL		FWL	23S	31E	11	Aliquot SWS W			EDD Y	NEW MEXI CO	NEW MEXI CO		NMNM 040444 1			
KOP Leg #1		FSL		FWL	23S	31E	11	Aliquot SESW			EDD Y	NEW MEXI CO	NEW MEXI CO		NMNM 040444 1			
PPP Leg #1		FSL		FWL	23S	31E	11	Aliquot SESW			EDD Y	NEW MEXI CO	NEW MEXI CO		NMNM 040444 1			

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
EXIT Leg #1		FNL		FWL	23S	31E	11	Aliquot NENW			EDD Y	NEW MEXI CO	NEW MEXI CO		NMNM 040444 1			
BHL Leg #1		FNL		FWL	23S	31E	11	Aliquot NENW			EDD Y	NEW MEXI CO	NEW MEXI CO		NMNM 040444 1			

12. 10. 1947

13. 10. 1947

14. 10. 1947

15. 10. 1947

16. 10. 1947

17. 10. 1947

18. 10. 1947


19. 10. 1947

20. 10. 1947

SITE MAP



SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
INTERIM SITE BUILD PLAN



0 20 100 200 400
SCALE 1" = 200'

2.847± ACRES INTERIM PAD RECLAMATION AREA
12.216± ACRES GRADING SITE RECLAMATION AREA
3.017± ACRES NON-RECLAIMED AREA
18.080± ACRES BELLOQ & GALAPAGOS WELL PAD


DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11 FED 222H
LOCATED 300 FT. FROM THE SOUTH LINE
AND 510 FT. FROM THE WEST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JULY 11, 2018

SURVEY NO. 6177B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
LOCATION VERIFICATION MAP



USGS QUAD MAP:
LOS MEDANOS
BOOTLEG RIDGE

NOT TO SCALE

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11 FED 222H


LOCATED 300 FT. FROM THE SOUTH LINE
AND 510 FT. FROM THE WEST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JULY 11, 2018

SURVEY NO. 6177B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
VICINITY MAP



DISTANCES IN MILES

NOT TO SCALE

DIRECTIONS TO LOCATION

FROM STATE HIGHWAY 128 AND CR 798 (RED ROAD) GO NORTH ON CR 798 4.7 MILES, TURN LEFT ON CALICHE ROAD AND GO WEST 0.15 OF A MILE, BEND RIGHT AND GO NORTHWEST 0.2 OF A MILE, TURN LEFT AND GO SOUTHWEST 0.6 OF A MILE, TURN LEFT AND GO SOUTH 660' TO PROPOSED ROAD SURVEY AND FOLLOW FLAGS SOUTHEAST 431', THEN SOUTH 50' TO THE NORTHEAST PAD CORNER.

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11 FED 222H

LOCATED 300 FT. FROM THE SOUTH LINE
AND 510 FT. FROM THE WEST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JULY 11, 2018

MADRON SURVEYING, INC. 301 SOUTH CANAL
(575) 234-3341

SURVEY NO. 6177B
CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL PHOTO



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
NOV. 2017

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11 FED 222H

LOCATED 300 FT. FROM THE SOUTH LINE
AND 510 FT. FROM THE WEST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JULY 11, 2018

SURVEY NO. 6177B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL ACCESS ROUTE MAP



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
NOV. 2017

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11 FED 222H


LOCATED 300 FT. FROM THE SOUTH LINE
AND 510 FT. FROM THE WEST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JULY 11, 2018

SURVEY NO. 6177B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

1-MILE WELL MAP



WELL DATA FROM NMOCD GIS - 7/3/18

[SH] SURFACE LOCATION

[BH] BOTTOM OF HOLE

⊗ WELLS WITHIN 1 MILE

----- WELL PATH

- - - - - 1/4 MILE BOUNDARY

———— 1-MILE BOUNDARY

DEVON ENERGY PRODUCTION COMPANY, L.P.

BELLOQ 11 FED 222H


LOCATED 300 FT. FROM THE SOUTH LINE
AND 510 FT. FROM THE WEST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO




JULY 11, 2018

SURVEY NO. 6177B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO



CROSS SECTIONS



DEVON ENERGY PRODUCTION COMPANY, L.P.
PAD GRADING AND CROSS SECTIONS
FOR BELLOQ 11 FED 222H
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

015 75 150 300
SCALE 1" = 150' - 1" = 30' VER



CUT	FILL	NET
63729 CU. YD	15537 CU. YD	48191 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED

JULY 11, 2018
MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SHEET 2-3
SURVEY NO. 6177B

CROSS SECTIONS



DEVON ENERGY PRODUCTION COMPANY, L.P.
PAD GRADING AND CROSS SECTIONS
FOR BELLOQ 11 FED 222H
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

015 75 150 300
SCALE 1" = 150' - 1" = 30' VER

CUT	FILL	NET
63729 CU. YD	15537 CU. YD	48191 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED


JULY 11, 2018
MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

SHEET 3-3
SURVEY NO. 6177B


ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 231H, 511H, 515H, & BELLOQ 11 FED 222H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JULY 11, 2018



SEE NEXT SHEET (2-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 1-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12 DAY OF JULY 2018

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6177B

ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 231H, 521H, 515H, & BELLOQ 11 FED 222H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JULY 11, 2018

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE NW/4 NW/4 OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE NORTHWEST CORNER OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N60°44'36"W, A DISTANCE OF 1221.97 FEET;
THENCE N00°08'29"W A DISTANCE OF 599.90 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE NORTHWEST CORNER OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S89°51'18"W, A DISTANCE OF 1064.62 FEET;

SAID STRIP OF LAND BEING 599.90 FEET OR 36.36 RODS IN LENGTH, CONTAINING 0.413 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

NW/4 NW/4 599.90 FT 36.36 RODS 0.413 ACRES

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,
NEW MEXICO, THIS 11 DAY OF JULY, 2018.

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-4

MADRON SURVEYING, INC. **CARLSBAD, NEW MEXICO**

301 SOUTH CANAL
(575) 234-3341


MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6177B


ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 231H, 521H, 515H, & BELLOQ 11 FED 222H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JULY 11, 2018



SEE NEXT SHEET (4-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12TH DAY OF JULY 2018

FILMON F. JARAMILLO
NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SHEET: 3-4

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO

SURVEY NO. 6177B

ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 291H, 521H, 515H, & BELLOQ 11 FED 222H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JULY 11, 2018

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SW/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S89°51'18"W, A DISTANCE OF 1064.62 FEET;
THENCE N00°08'29"W A DISTANCE OF 435.02 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE S89°51'58"W A DISTANCE OF 276.00 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S60°58'15"W, A DISTANCE OF 900.69 FEET;

SAID STRIP OF LAND BEING 711.02 FEET OR 43.09 RODS IN LENGTH, CONTAINING 0.490 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SW/4 711.02 L.F. 43.09 RODS 0.490 ACRES

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,
NEW MEXICO, THIS 12 DAY OF JULY 2018

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 4-4

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6177B



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

09/26/2018

APD ID: 10400020749

Submission Date: 08/25/2017

Highlighted data
reflects the most
recent changes

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Number: 222H

Show Final Text

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	UNKNOWN	3428	0	0	ALLUVIUM	NONE	No
2	BUSTLER	2773	655	665	SANDSTONE	NONE	No
3	BASE OF SALT	-706	4134	4378	SALT	NONE	No
4	DELAWARE	-958	4384	4398	SANDSTONE	NATURAL GAS,OIL	No
5	BONE SPRING	-4836	8264	8264	SANDSTONE	NATURAL GAS,OIL	Yes

Section 2 - Blowout Prevention

Pressure Rating (PSI): 3M

Rating Depth: 6000

Equipment: BOP/BOPE will be installed per Onshore Oil & Gas Order #2 requirements prior to drilling below 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 3M will be installed on the wellhead system. BOP/BOPE will be tested by an independent service company per Onshore Oil & Gas Order #2 requirements and MASP (Maximum Anticipated Surface Pressure) calculations. If the system is upgraded, all the components installed will be functional and tested.

Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP stack to the choke manifold. See attached for specs for hydrostatic test chart.

Testing Procedure: A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Choke Diagram Attachment:

BELLOQ_11_FED_222H_3M_BOPE_20180814144224.pdf


BOP Diagram Attachment:

BELLOQ_11_FED_222H_3M_BOPE_20180814144231.pdf

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Number: 222H



Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP stack to the choke manifold. See attached for specs for hydrostatic test chart.

Testing Procedure: A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Choke Diagram Attachment:

BELLOQ_11_FED_222H_5M_BOPE_20180814144408.pdf

BOP Diagram Attachment:

BELLOQ_11_FED_222H_5M_BOPE_20180814144416.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	750	0	750	-6710	-7319	750	H-40	48	STC	1.125	1	BUOY	1.6	BUOY	1.6
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	6000	0	6000	-6710	-10899	6000	J-55	40	OTHER - BTC	1.125	1	BUOY	1.6	BUOY	1.6
3	PRODUCTION	8.75	5.5	NEW	API	N	0	15316	0	10341	-6710	-21286	15316	P-110	17	OTHER - BTC	1.125	1	BUOY	1.6	BUOY	1.6

Casing Attachments

Casing Attachments

Casing ID: 1 **String Type:** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

BELLOQ_11_FED_222H_SurfCsg_Ass_20180814144635.pdf

Casing ID: 2 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

BELLOQ_11_FED_222H_Int_Csg_Ass_20180814144646.pdf

Casing ID: 3 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

BELLOQ_11_FED_222H_ProdCasing_Ass_20180814144702.pdf

Section 4 - Cement

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Number: 222H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead					1.33				C	

INTERMEDIATE	Lead					1.94				C	
INTERMEDIATE	Tail									C	
PRODUCTION	Lead					3.27				TUNED	
PRODUCTION	Tail									H	

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

Describe the mud monitoring system utilized: PVT/Pason/Visual Monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	750	OTHER : FRESH WATER	8.5	9				2			
750	6000	OTHER : BRINE	10	10.5				2			
6000	10341	WATER-BASED MUD	8.5	9							

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Number: 222H

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Will run GRMWD from TD to from KOP. Cement bond logs will be run in vertical to determine top of cement. Stated logs run will be in the completion report and submitted to the BLM.

List of open and cased hole logs run in the well:

CALIPER,CBL,DS,GR,MUDLOG

Coring operation description for the well:

N/A

Section 7 - Pressure

NOTE: (per the BLM, the following information is required)

NOTE: (per the BLM, the following information is required)

NOTE: (per the BLM, the following information is required)

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

Belloq_11_Fed_222H_H2S_PLAN__20180814145222.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Devon_Belloq_11_Fed_222H__AC_Report_Permit_Plan_1_20180814145258.pdf

Devon_Belloq_11_Fed_222H__Permit_Plan_1_20180814145258.pdf

Devon_Belloq_11_Fed_222H__Plot_Permit_Plan_1_20180814145259.pdf

Other proposed operations facets description:

NOTE: (per the BLM, the following information is required)
NOTE: (per the BLM, the following information is required)
NOTE: (per the BLM, the following information is required)
NOTE: (per the BLM, the following information is required)
NOTE: (per the BLM, the following information is required)

Other proposed operations facets attachment:

Belloq_11_Fed_222H_Drilling_Plan_20180814145306.pdf

BELLOQ_11_FED_222H_Gas_Capture_20180814145328.pdf

BELLOQ_11_FED_222H_Clsd_Loop_20180814145328.pdf

BELLOQ_11_FED_222H_MB_Verb_20180814145329.pdf

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED


Well Number: 222H

BELLOQ_11_FED_222H_MB_Wellhd_20180814145330.pdf


Other Variance attachment:

BELLOQ_11_FED_222H_Co_flex_20180814145338.pdf


13-5/8" 5M BOPE & Closed Loop Equipment Schematic




Equipment Schematic



Equipment Schematic



13-5/8" 3M BOPE & Closed Loop Equipment Schematic



Casing Assumptions and Load Cases

Surface

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Surface Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Displace to Gas	Formation Pore Pressure	Dry gas from next casing point

Surface Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Surface Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	3 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Intermediate

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Intermediate Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Fracture @ Shoe	Formation Pore Pressure	Dry gas

Intermediate Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Intermediate Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Production

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Production Casing Burst Design

Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Fluid in hole (water or produced water) + test psi
Tubing Leak	Formation Pore Pressure	Packer @ KOP, leak below surface 8.6 ppg packer fluid
Stimulation	Formation Pore Pressure	Max frac pressure with heaviest frac fluid

Production Casing Collapse Design

Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC.	None
Cementing	Wet cement weight	Water (8.33ppg)

Production Casing Tension Design

Load Case	Assumptions
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A



**Devon Energy Center
333 West Sheridan Avenue
Oklahoma City, Oklahoma 73102-5015**

Hydrogen Sulfide (H₂S) Contingency Plan

For



Belloq 11 Fed 222H

**Sec-11 T-23S R-31E
300' FSL & 510 FWL
LAT. = 32.3125667' N (NAD83)
LONG = 103.7554734' W**

Eddy County NM

Belloq 11 Fed 222H

This is an open drilling site. H₂S monitoring equipment and emergency response equipment will be used within 500' of zones known to contain H₂S, including warning signs, wind indicators and H₂S monitor.



Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated from the location entrance road. Crews should then block the entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE. There are no homes or buildings in or near the ROE.

Assumed 100 ppm ROE = 3000'

100 ppm H₂S concentration shall trigger activation of this plan.

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must

- **Isolate the area and prevent entry by other persons into the 100 ppm ROE.**
- **Evacuate any public places encompassed by the 100 ppm ROE.**
- **Be equipped with H₂S monitors and air packs in order to control the release.**
- **Use the “buddy system” to ensure no injuries occur during the response**
- **Take precautions to avoid personal injury during this operation.**
- **Contact operator and/or local officials to aid in operation. See list of phone numbers attached.**
- **Have received training in the**
 - **Detection of H₂S, and**
 - **Measures for protection against the gas,**
 - **Equipment used for protection and emergency response.**

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H₂S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO₂	2.21 Air = 1	2 ppm	N/A	1000 ppm

Contacting Authorities

Devon Energy Corp. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. Devon Energy Corp. Company response must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER)

Hydrogen Sulfide Drilling Operation Plan

I. HYDROGEN SULFIDE (H₂S) TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H₂S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H₂S metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H₂S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan.

II. HYDROGEN SULFIDE TRAINING

Note: All H₂S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H₂S.

1. Well Control Equipment

- A. Flare line
- B. Choke manifold – Remotely Operated
- C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
- D. Auxiliary equipment may include if applicable: annular preventer and rotating head.
- E. Mud/Gas Separator

2. Protective equipment for essential personnel:

30-minute SCBA units located at briefing areas, as indicated on well site diagram, with escape units available in the top doghouse. As it may be difficult to communicate audibly while wearing these units, hand signals shall be utilized.

3. H₂S detection and monitoring equipment:

Portable H₂S monitors positioned on location for best coverage and response. These units have warning lights which activate when H₂S levels reach 10 ppm and audible sirens which activate at 15 ppm. Sensor locations:

- Bell nipple
- Possum Belly/Shale shaker
- Rig floor
- Choke manifold
- Cellar

Visual warning systems:

- A. Wind direction indicators as shown on well site diagram
- B. Caution/ Danger signs shall be posted on roads providing direct access to locations. Signs will be painted a high visibility yellow with black lettering of sufficient size to be reasonable distance from the immediate location. Bilingual signs will be used when appropriate.

4. Mud program:

The mud program has been designed to minimize the volume of H₂S circulated to surface. Proper mud weight, safe drilling practices and the use of H₂S scavengers will minimize hazards when penetrating H₂S bearing zones.

5. Metallurgy:

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold lines, and valves shall be H₂S trim.
- B. All elastomers used for packing and seals shall be H₂S trim.

6. Communication:

- A. Company personnel have/use cellular telephones in the field.
- B. Land line (telephone) communications at Office

7. Well testing:

- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safety and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H₂S environment will use the closed chamber method of testing.
- B. There will be no drill stem testing.

Devon Energy Corp. Company Call List

Drilling Supervisor – Basin – Jonathan Fisher	405-228-8976
Randy Gladden – Day 575-748-1805 Cell 575-513-9463	
EHS Professional – Jason Robison	405-541-2841

Agency Call List

Lea County (575)	Hobbs	
	Lea County Communication Authority	393-3981
	State Police	392-5588
	City Police	397-9265
	Sheriff's Office	393-2515
	Ambulance	911
	Fire Department	397-9308
	LEPC (Local Emergency Planning Committee)	393-2870
	NMOCD	393-6161
	US Bureau of Land Management	393-3612
Eddy County (575)	Carlsbad	
	State Police	885-3137
	City Police	885-2111
	Sheriff's Office	887-7551
	Ambulance	911
	Fire Department	885-3125
	LEPC (Local Emergency Planning Committee)	887-3798
	US Bureau of Land Management	887-6544
	NM Emergency Response Commission (Santa Fe)	(505) 476-9600
	24 HR	(505) 827-9126
	National Emergency Response Center	(800) 424-8802
	National Pollution Control Center: Direct	(703) 872-6000
	For Oil Spills	(800) 280-7118
	Emergency Services	
	Wild Well Control	(281) 784-4700
	Cudd Pressure Control	(915) 699-0139 (915) 563-3356
	Halliburton	(575) 746-2757
	B. J. Services	(575) 746-3569
	Native Air – Emergency Helicopter – Hobbs	(575) 392-6429
	Flight For Life - Lubbock, TX	(806) 743-9911
Give GPS position:	Aerocare - Lubbock, TX	(806) 747-8923
	Med Flight Air Amb - Albuquerque, NM	(575) 842-4433
	Lifeguard Air Med Svc. Albuquerque, NM	(800) 222-1222
	Poison Control (24/7)	(575) 272-3115
	Oil & Gas Pipeline 24 Hour Service	(800) 364-4366
	NOAA – Website - www.nhc.noaa.gov	

Prepared in conjunction with
Dave Small



WCDSC Permian NM

Eddy County (NAD 83 NM Eastern)

Sec 11-T23S-R31E

Belloq 11 Fed 222H

Wellbore #1

Permit Plan 1

Anticollision Report

31 July, 2018

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Reference	Permit Plan 1		
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria		
Interpolation Method:	MD Interval 50.00ft	Error Model:	ISCWSA
Depth Range:	Unlimited	Scan Method:	Closest Approach 3D
Results Limited by:	Maximum center-center distance of 1,500.00 ft	Error Surface:	Pedal Curve
Warning Levels Evaluated at:	2.00 Sigma	Casing Method:	Not applied

Survey Tool Program	Date 7/31/2018			
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description
0.00	15,316.32	Permit Plan 1 (Wellbore #1)	MWD+HDGM	OWSG MWD + HDGM

Summary						
Site Name	Reference Measured Depth (ft)	Offset Measured Depth (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
Sec 11-T23S-R31E						
Barclay 11 G Federal #007 (P&A) - Wellbore #1 - Wellbo						Out of range
Barclay 11 H Federal #001 SWD - Wellbore #1 - Wellbor						Out of range
Barclay 11 K Federal #011 (Active) - Wellbore #1 - Wellb						Out of range
Barclay 11 M Federal #013 (Shut in) - Wellbore #1 - Well	3,411.70	3,396.44	347.20	264.68	4.207	Alert, CC
Barclay 11 M Federal #013 (Shut in) - Wellbore #1 - Well	3,950.00	3,936.51	361.35	258.08	3.499	Alert, ES
Barclay 11 M Federal #013 (Shut in) - Wellbore #1 - Well	4,500.00	4,491.51	403.33	279.69	3.262	Alert, SF
Barclay 11 N Federal #014 - Wellbore #1 - Wellbore #1	8,700.00	8,595.00	632.98	405.14	2.778	Alert, SF
Barclay 11 N Federal #014 - Wellbore #1 - Wellbore #1	8,740.62	8,595.00	631.67	404.37	2.779	Alert, CC, ES
Belloq 11-2 Fed State Com 223H - Wellbore #1 - Permit						Out of range
Belloq 11-2 Fed State Com 234 - Wellbore #1 - Design #						Out of range
Belloq 11-2 Fed State com 512H - Wellbore #1 - Permit P	8,800.72	8,637.80	742.29	679.94	11.905	CC, ES
Belloq 11-2 Fed State com 512H - Wellbore #1 - Permit P	8,850.00	8,664.52	743.24	680.75	11.894	SF
Belloq 11-2 Fed State Com 513H - Wellbore #1 - Permit						Out of range
Belloq 11-2 Fed State Com 514H - Wellbore #1 - Permit						Out of range
Belloq 11-2 Fed State Com 522H - Wellbore #1 - Permit	8,696.22	8,612.69	127.92	64.88	2.029	Minor Risk, CC
Belloq 11-2 Fed State Com 522H - Wellbore #1 - Permit	8,700.00	8,615.85	127.93	64.86	2.028	Minor Risk, ES, SF
Belloq 11-2 Fed State Com 523H - Wellbore #1 - Permit	9,234.61	8,990.43	1,333.88	1,269.36	20.675	CC, ES
Belloq 11-2 Fed State Com 523H - Wellbore #1 - Permit	9,300.00	9,017.11	1,335.03	1,270.40	20.658	SF
Belloq 11-2 Fed State Com 524H - Wellbore #1 - Permit						Out of range

Offset Design												
Sec 11-T23S-R31E - Barclay 11 M Federal #013 (Shut in) - Wellbore #1 - Wellbore #1												
Survey Program: 250-INC-ONLY												
Reference												
Offset												
Semi Major Axis												
Distance												
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor
0.00	0.00	9.80	-9.80	0.50	0.51	23.49	328.99	142.97	358.72			
50.00	50.00	40.20	40.20	0.50	0.64	23.49	328.99	142.97	358.72	357.57	1.15	312.769
100.00	100.00	90.20	90.20	0.52	1.04	23.49	328.99	142.97	358.72	357.16	1.56	230.021
150.00	150.00	140.20	140.20	0.59	1.51	23.49	328.99	142.97	358.72	356.62	2.10	171.129
200.00	200.00	190.20	190.20	0.70	1.99	23.49	328.99	142.97	358.72	356.02	2.69	133.202
250.00	250.00	259.78	240.20	0.84	2.78	23.49	328.99	142.97	358.72	355.09	3.62	98.977
300.00	300.00	290.21	290.20	0.99	3.43	23.49	328.99	142.97	358.72	354.30	4.41	81.289
350.00	350.00	340.21	340.20	1.15	4.48	23.49	328.99	142.97	358.72	353.09	5.63	63.756
400.00	400.00	390.57	390.56	1.31	5.55	23.45	329.53	142.97	359.21	352.35	6.86	52.390

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design													Offset Site Error:	0.00 ft
Sec 11-T23S-R31E - Barclay 11 M Federal #013 (Shut in) - Wellbore #1 - Wellbore #1													Offset Well Error:	0.50 ft
Survey Program: 250-INC-ONLY														
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (ft)	Separation Factor	Warning			
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)				Between Centres (ft)	Between Ellipses (ft)	
450.00	450.00	441.76	441.74	1.48	6.63	23.46	329.38	142.97	359.08	350.97	8.11	44.279		
500.00	500.00	509.75	490.20	1.65	8.09	23.49	328.99	142.97	358.72	348.99	9.73	36.862		
550.00	550.00	540.25	540.20	1.82	8.76	23.49	328.99	142.97	358.72	348.14	10.58	33.912		
600.00	600.00	590.25	590.20	1.99	9.87	23.49	328.99	142.97	358.72	346.86	11.86	30.251		
650.00	650.00	640.25	640.20	2.16	10.97	23.49	328.99	142.97	358.72	345.58	13.14	27.302		
700.00	700.00	691.11	691.05	2.34	12.10	23.45	329.58	142.97	359.26	344.82	14.44	24.879		
750.00	750.00	742.11	742.05	2.51	13.23	23.46	329.37	142.97	359.07	343.32	15.75	22.805		
800.00	800.00	799.69	790.20	2.69	14.51	23.49	328.99	142.97	358.72	341.52	17.20	20.859		
850.00	850.00	840.31	840.20	2.87	15.41	23.49	328.99	142.97	358.72	340.44	18.27	19.630		
900.00	900.00	890.67	890.55	3.04	16.52	23.46	329.46	142.97	359.15	339.58	19.57	18.355		
950.00	950.00	942.84	942.72	3.22	17.68	23.47	329.24	142.97	358.95	338.05	20.90	17.174		
1,000.00	1,000.00	990.34	990.20	3.40	18.71	23.49	328.99	142.97	358.72	336.60	22.11	16.223		
1,050.00	1,050.00	1,040.34	1,040.20	3.58	19.78	23.49	328.99	142.97	358.72	335.36	23.35	15.361		
1,100.00	1,100.00	1,090.62	1,090.47	3.75	20.85	23.46	329.47	142.97	359.16	334.56	24.60	14.600		
1,150.00	1,150.00	1,141.96	1,141.81	3.93	21.94	23.47	329.33	142.97	359.03	333.16	25.87	13.879		
1,200.00	1,200.00	1,193.30	1,193.15	4.11	23.03	23.49	328.97	142.97	358.71	331.57	27.14	13.218		
1,222.81	1,222.81	1,216.73	1,216.57	4.19	23.53	23.50	328.74	142.97	358.50	330.79	27.72	12.934		
1,250.00	1,250.00	1,240.38	1,240.20	4.29	24.03	23.49	328.99	142.97	358.72	330.40	28.32	12.667		
1,300.00	1,300.00	1,290.38	1,290.20	4.46	25.10	23.49	328.99	142.97	358.72	329.16	29.56	12.135		
1,350.00	1,350.00	1,340.90	1,340.72	4.64	26.17	23.45	329.53	142.97	359.21	328.40	30.81	11.658		
1,400.00	1,400.00	1,392.07	1,391.88	4.82	27.26	23.46	329.36	142.97	359.06	326.98	32.08	11.193		
1,450.00	1,450.00	1,449.59	1,440.20	5.00	28.48	23.49	328.99	142.97	358.72	325.23	33.48	10.714		
1,500.00	1,500.00	1,490.41	1,490.20	5.18	29.35	23.49	328.99	142.97	358.72	324.19	34.53	10.389		
1,550.00	1,550.00	1,540.41	1,540.20	5.36	30.42	23.49	328.99	142.97	358.72	322.95	35.77	10.028		
1,600.00	1,600.00	1,590.41	1,590.20	5.53	31.48	23.49	328.99	142.97	358.72	321.70	37.01	9.692		
1,650.00	1,650.00	1,640.41	1,640.20	5.71	32.54	23.49	328.99	142.97	358.72	320.46	38.26	9.377		
1,700.00	1,700.00	1,690.41	1,690.20	5.89	33.61	23.49	328.99	142.97	358.72	319.22	39.50	9.082		
1,750.00	1,750.00	1,741.01	1,740.79	6.07	34.68	23.42	330.02	142.97	359.66	318.90	40.75	8.825		
1,800.00	1,800.00	1,791.62	1,791.39	6.25	35.76	23.43	329.88	142.97	359.53	317.53	42.01	8.559		
1,850.00	1,850.00	1,842.22	1,841.99	6.43	36.84	23.45	329.66	142.97	359.33	316.06	43.26	8.305		
1,900.00	1,900.00	1,981.51	1,890.20	6.61	39.80	23.49	328.99	142.97	358.72	312.31	46.41	7.730		
1,950.00	1,950.00	1,943.44	1,943.20	6.78	38.99	23.49	328.93	142.97	358.67	312.89	45.77	7.836		
1,988.79	1,988.79	1,982.70	1,982.45	6.92	39.83	23.52	328.55	142.97	358.32	311.58	46.75	7.665		
2,000.00	2,000.00	1,990.49	1,990.20	6.96	39.99	23.49	328.99	142.97	358.72	311.76	46.96	7.640		
2,050.00	2,050.00	2,040.49	2,040.20	7.14	41.06	23.49	328.99	142.97	358.72	310.52	48.20	7.443		
2,100.00	2,100.00	2,090.49	2,090.20	7.32	42.12	23.49	328.99	142.97	358.72	309.28	49.44	7.255		
2,150.00	2,150.00	2,140.49	2,140.20	7.50	43.18	23.49	328.99	142.97	358.72	308.03	50.68	7.078		
2,200.00	2,200.00	2,190.77	2,190.48	7.68	44.25	23.42	330.00	142.97	359.64	307.70	51.93	6.925		
2,250.00	2,250.00	2,241.41	2,241.11	7.86	45.33	23.43	329.90	142.97	359.55	306.36	53.19	6.760		
2,300.00	2,300.00	2,292.05	2,291.75	8.04	46.41	23.44	329.72	142.97	359.38	304.94	54.45	6.601		
2,350.00	2,350.00	2,342.69	2,342.38	8.22	47.49	23.46	329.43	142.97	359.12	303.42	55.70	6.447		
2,400.00	2,400.00	2,409.44	2,390.20	8.39	48.91	23.49	328.99	142.97	358.72	301.41	57.30	6.260		
2,450.00	2,450.00	2,443.98	2,443.66	8.57	49.64	23.52	328.57	142.97	358.35	300.13	58.21	6.156		
2,454.11	2,454.11	2,448.14	2,447.83	8.59	49.73	23.52	328.53	142.97	358.31	299.99	58.32	6.144		
2,500.00	2,500.00	2,490.56	2,490.20	8.75	50.63	23.49	328.99	142.97	358.72	299.33	59.39	6.040		
2,550.00	2,550.00	2,540.56	2,540.20	8.93	51.70	-75.48	328.99	142.97	358.65	298.02	60.62	5.916		
2,576.81	2,576.80	2,567.36	2,567.00	9.02	52.27	-75.54	328.99	142.97	358.56	297.27	61.29	5.850		
2,600.00	2,599.99	2,590.58	2,590.22	9.10	52.76	-75.66	329.82	142.97	359.20	297.34	61.86	5.806		
2,650.00	2,649.97	2,641.35	2,640.98	9.27	53.84	-75.88	329.75	142.97	358.81	295.69	63.11	5.685		
2,700.00	2,699.94	2,692.10	2,691.73	9.44	54.92	-76.18	329.57	142.97	358.18	293.82	64.36	5.565		
2,750.00	2,749.88	2,742.83	2,742.46	9.61	56.00	-76.55	329.26	142.97	357.32	291.71	65.61	5.446		
2,800.00	2,799.79	2,793.54	2,793.16	9.78	57.08	-77.02	328.84	142.97	356.25	289.39	66.86	5.328		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Barclay 11 M Federal #013 (Shut in) - Wellbore #1 - Wellbore #1												Offset Site Error:	0.00 ft
Survey Program: 250-INC-ONLY												Offset Well Error:	0.50 ft
Reference		Offset		Semi Major Axis			Distance			Minimum Separation		Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Separation Factor		
2,850.00	2,849.66	2,840.28	2,839.86	9.95	58.08	-77.56	328.99	142.97	355.59	287.57	68.03	5.227	
2,900.00	2,899.49	2,890.11	2,889.69	10.12	59.14	-78.21	328.99	142.97	354.73	285.47	69.26	5.122	
2,950.00	2,949.28	2,940.74	2,940.32	10.30	60.21	-78.99	329.50	142.97	354.29	283.78	70.51	5.025	
3,000.00	2,999.01	2,991.65	2,991.23	10.47	61.30	-79.84	329.28	142.97	353.13	281.37	71.77	4.921 Alert	
3,050.00	3,048.68	3,042.51	3,042.08	10.65	62.38	-80.76	328.89	142.97	351.79	278.77	73.02	4.818 Alert	
3,100.00	3,098.29	3,088.94	3,088.49	10.82	63.37	-81.72	328.99	142.97	350.92	276.73	74.19	4.730 Alert	
3,150.00	3,147.82	3,138.48	3,138.02	11.00	64.42	-82.82	328.99	142.97	349.99	274.57	75.42	4.641 Alert	
3,200.00	3,197.28	3,188.37	3,187.91	11.18	65.48	-84.05	329.58	142.97	349.71	273.05	76.66	4.562 Alert	
3,250.00	3,246.66	3,238.84	3,238.38	11.36	66.56	-85.35	329.44	142.97	348.83	270.92	77.92	4.477 Alert	
3,300.00	3,295.94	3,325.36	3,326.14	11.54	68.54	-86.66	328.99	142.97	347.80	267.72	80.08	4.343 Alert	
3,350.00	3,345.14	3,335.83	3,335.34	11.72	68.84	-88.12	328.99	142.97	347.39	266.83	80.56	4.312 Alert	
3,400.00	3,394.25	3,384.94	3,384.45	11.91	70.24	-89.64	328.99	142.97	347.20	265.05	82.15	4.227 Alert	
3,411.70	3,405.74	3,396.44	3,395.94	11.95	70.57	-90.00	328.99	142.97	347.20	264.68	82.52	4.207 Alert, CC	
3,450.00	3,443.35	3,434.05	3,433.55	12.09	71.64	-91.17	328.99	142.97	347.27	263.53	83.74	4.147 Alert	
3,500.00	3,492.45	3,483.15	3,482.65	12.28	73.04	-92.70	328.99	142.97	347.59	262.27	85.33	4.074 Alert	
3,550.00	3,541.56	3,533.09	3,532.58	12.47	74.47	-94.25	329.71	142.97	348.89	261.95	86.94	4.013 Alert	
3,600.00	3,590.66	3,583.06	3,582.55	12.66	75.90	-95.79	329.53	142.97	349.55	261.00	88.55	3.947 Alert	
3,650.00	3,639.76	3,633.04	3,632.53	12.85	77.32	-97.32	329.23	142.97	350.34	260.17	90.17	3.885 Alert	
3,700.00	3,688.86	3,683.03	3,682.51	13.04	78.75	-98.85	328.81	142.97	351.26	259.47	91.79	3.827 Alert	
3,750.00	3,737.97	3,728.90	3,728.17	13.24	80.86	-100.23	328.99	142.97	353.01	258.92	94.09	3.752 Alert	
3,800.00	3,787.07	3,778.00	3,777.27	13.43	82.86	-101.70	328.99	142.97	354.84	258.55	96.28	3.685 Alert	
3,850.00	3,836.17	3,830.14	3,829.35	13.63	84.98	-103.23	330.48	142.97	358.40	259.81	98.59	3.635 Alert	
3,900.00	3,885.27	3,883.29	3,882.47	13.82	87.15	-104.79	329.75	142.97	360.02	259.09	100.93	3.567 Alert	
3,950.00	3,934.38	3,936.51	3,935.64	14.02	89.31	-106.35	328.43	142.97	361.35	258.08	103.27	3.499 Alert, ES	
4,000.00	3,983.48	3,974.89	3,973.68	14.22	90.70	-107.42	328.99	142.97	364.49	259.61	104.89	3.475 Alert	
4,050.00	4,032.58	4,023.99	4,022.78	14.42	92.55	-108.80	328.99	142.97	367.47	260.54	106.93	3.437 Alert	
4,100.00	4,081.69	4,073.10	4,071.89	14.62	94.40	-110.16	328.99	142.97	370.67	261.70	108.97	3.401 Alert	
4,150.00	4,130.79	4,126.40	4,125.06	14.82	96.41	-111.52	331.48	142.97	376.53	265.35	111.17	3.387 Alert	
4,200.00	4,179.89	4,180.04	4,178.65	15.02	98.44	-112.98	330.57	142.97	379.32	265.95	113.37	3.346 Alert	
4,250.00	4,228.99	4,249.15	4,219.19	15.22	100.93	-114.09	328.99	142.97	381.50	265.43	116.07	3.287 Alert	
4,300.00	4,278.10	4,269.96	4,268.30	15.42	101.54	-115.36	328.99	142.97	385.50	268.63	116.87	3.298 Alert	
4,350.00	4,327.20	4,320.27	4,318.59	15.63	103.03	-116.59	329.60	142.97	390.27	271.72	118.55	3.292 Alert	
4,400.00	4,376.30	4,374.30	4,372.61	15.83	104.62	-117.94	329.07	142.97	394.19	273.86	120.32	3.276 Alert	
4,450.00	4,425.40	4,417.35	4,415.60	16.04	105.73	-118.98	328.99	142.97	398.61	276.98	121.63	3.277 Alert	
4,500.00	4,474.51	4,491.51	4,464.71	16.24	107.55	-120.14	328.99	142.97	403.33	279.69	123.64	3.262 Alert, SF	
4,550.00	4,523.61	4,515.59	4,513.81	16.45	108.06	-121.27	328.99	142.97	408.21	283.88	124.33	3.283 Alert	
4,600.00	4,572.71	4,564.70	4,562.91	16.65	109.09	-122.37	328.99	142.97	413.25	287.70	125.55	3.292 Alert	
4,650.00	4,621.81	4,613.80	4,612.01	16.86	110.12	-123.45	328.99	142.97	418.44	291.67	126.76	3.301 Alert	
4,700.00	4,670.92	4,662.90	4,661.12	17.06	111.15	-124.50	328.99	142.97	423.77	295.79	127.98	3.311 Alert	
4,750.00	4,720.02	4,712.18	4,710.39	17.27	112.18	-125.47	329.96	142.97	430.11	300.91	129.20	3.329 Alert	
4,800.00	4,769.12	4,762.05	4,760.25	17.48	113.23	-126.49	329.89	142.97	435.65	305.21	130.43	3.340 Alert	
4,850.00	4,818.23	4,811.92	4,810.13	17.69	114.27	-127.49	329.72	142.97	441.24	309.57	131.66	3.351 Alert	
4,900.00	4,867.33	4,861.81	4,860.01	17.90	115.32	-128.47	329.45	142.97	446.87	313.97	132.89	3.363 Alert	
4,950.00	4,916.43	4,935.52	4,906.63	18.10	116.87	-129.37	328.99	142.97	452.46	317.83	134.62	3.361 Alert	
5,000.00	4,965.53	4,961.59	4,959.78	18.31	117.41	-130.37	328.62	142.97	458.26	322.90	135.36	3.386 Alert	
5,050.00	5,014.64	5,006.69	5,004.84	18.52	118.36	-131.15	328.99	142.97	464.78	328.29	136.49	3.405 Alert	
5,100.00	5,063.74	5,055.79	5,053.94	18.73	119.40	-132.01	328.99	142.97	471.10	333.39	137.70	3.421 Alert	
5,150.00	5,112.84	5,104.89	5,103.04	18.94	120.43	-132.84	328.99	142.97	477.52	338.60	138.92	3.437 Alert	
5,200.00	5,161.94	5,154.00	5,152.14	19.16	121.46	-133.65	328.99	142.97	484.04	343.91	140.13	3.454 Alert	
5,250.00	5,211.05	5,203.67	5,201.81	19.37	122.51	-134.38	330.02	142.97	491.49	350.13	141.36	3.477 Alert	
5,300.00	5,260.15	5,253.51	5,251.64	19.58	123.55	-135.17	329.91	142.97	498.10	355.51	142.59	3.493 Alert	
5,350.00	5,309.25	5,303.34	5,301.48	19.79	124.60	-135.94	329.70	142.97	504.73	360.90	143.83	3.509 Alert	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Sec 11-T23S-R31E - Barclay 11 M Federal #013 (Shut in) - Wellbore #1 - Wellbore #1													Offset Site Error:	0.00 ft
Survey Program: 250-INC-ONLY													Offset Well Error:	0.50 ft
Reference		Offset		Semi Major Axis			Distance							Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor		
5,400.00	5,358.35	5,461.52	5,348.55	20.00	127.93	-136.69	328.99	142.97	511.04	363.71	147.33	3.469	Alert	
5,450.00	5,407.46	5,412.42	5,397.66	20.21	126.90	-137.40	328.99	142.97	518.00	371.52	146.48	3.536	Alert	
5,500.00	5,456.56	5,452.90	5,451.02	20.43	127.75	-138.18	328.54	142.97	524.71	377.20	147.52	3.557	Alert	
5,550.00	5,505.66	5,497.79	5,495.86	20.64	128.70	-138.76	328.99	142.97	532.15	383.51	148.64	3.580	Alert	
5,600.00	5,554.77	5,546.89	5,544.97	20.85	129.73	-139.42	328.99	142.97	539.33	389.47	149.88	3.599	Alert	
5,650.00	5,603.87	5,595.99	5,594.07	21.07	130.77	-140.05	328.99	142.97	546.58	395.51	151.08	3.618	Alert	
5,700.00	5,652.97	5,645.10	5,643.17	21.28	131.80	-140.68	328.99	142.97	553.90	401.61	152.29	3.637	Alert	
5,750.00	5,702.07	5,694.20	5,692.27	21.49	132.84	-141.28	328.99	142.97	561.28	407.77	153.51	3.656	Alert	
5,800.00	5,751.18	5,743.30	5,741.38	21.71	133.87	-141.87	328.99	142.97	568.72	413.99	154.72	3.676	Alert	
5,850.00	5,800.28	5,792.41	5,790.48	21.92	134.91	-142.45	328.99	142.97	576.21	420.27	155.94	3.695	Alert	
5,900.00	5,849.38	5,841.51	5,839.58	22.14	135.94	-143.01	328.99	142.97	583.77	426.61	157.16	3.715	Alert	
5,950.00	5,898.48	5,890.61	5,888.68	22.35	136.98	-143.55	328.99	142.97	591.37	433.00	158.37	3.734	Alert	
6,000.00	5,947.59	5,940.08	5,938.13	22.57	138.02	-143.95	331.10	142.97	600.51	440.91	159.60	3.763	Alert	
6,050.00	5,996.69	5,989.56	5,987.61	22.78	139.06	-144.47	331.03	142.97	608.16	447.33	160.83	3.781	Alert	
6,100.00	6,045.79	6,039.05	6,037.10	23.00	140.11	-144.99	330.93	142.97	615.83	453.78	162.05	3.800	Alert	
6,150.00	6,094.90	6,088.54	6,086.59	23.21	141.15	-145.50	330.78	142.97	623.52	460.24	163.28	3.819	Alert	
6,200.00	6,144.00	6,138.04	6,136.08	23.43	142.19	-146.00	330.58	142.97	631.22	466.72	164.50	3.837	Alert	
6,250.00	6,193.10	6,187.54	6,185.58	23.64	143.24	-146.49	330.34	142.97	638.95	473.22	165.73	3.855	Alert	
6,300.00	6,242.20	6,237.04	6,235.08	23.86	144.28	-146.97	330.06	142.97	646.68	479.73	166.95	3.873	Alert	
6,350.00	6,291.31	6,286.55	6,284.58	24.08	145.32	-147.44	329.73	142.97	654.44	486.26	168.18	3.891	Alert	
6,400.00	6,340.41	6,427.32	6,330.61	24.29	148.29	-147.90	328.99	142.97	661.96	490.64	171.32	3.864	Alert	
6,450.00	6,389.51	6,385.58	6,383.60	24.51	147.41	-148.36	328.94	142.97	669.98	499.36	170.63	3.927	Alert	
6,500.00	6,438.61	6,435.09	6,433.11	24.73	148.46	-148.81	328.49	142.97	677.77	505.92	171.85	3.944	Alert	
6,550.00	6,487.72	6,479.99	6,477.92	24.94	149.41	-149.15	328.99	142.97	686.20	513.23	172.98	3.967	Alert	
6,600.00	6,536.82	6,529.09	6,527.02	25.16	150.44	-149.55	328.99	142.97	694.35	520.16	174.19	3.986	Alert	
6,650.00	6,585.92	6,578.20	6,576.12	25.38	151.48	-149.93	328.99	142.97	702.54	527.12	175.41	4.005	Alert	
6,700.00	6,635.02	6,627.44	6,625.35	25.59	152.52	-150.25	330.04	142.97	711.39	534.76	176.64	4.027	Alert	
6,750.00	6,684.13	6,677.35	6,675.27	25.81	153.57	-150.63	329.97	142.97	719.59	541.72	177.87	4.046	Alert	
6,800.00	6,733.23	6,727.28	6,725.19	26.03	154.63	-151.01	329.82	142.97	727.77	548.66	179.11	4.063	Alert	
6,850.00	6,782.33	6,777.21	6,775.11	26.25	155.68	-151.38	329.58	142.97	735.92	555.57	180.35	4.081	Alert	
6,900.00	6,831.44	6,822.22	6,821.64	26.47	158.11	-151.75	328.99	142.97	743.89	560.94	182.95	4.066	Alert	
6,950.00	6,880.54	6,877.09	6,874.99	26.68	157.79	-152.13	328.82	142.97	752.15	569.33	182.82	4.114	Alert	
7,000.00	6,929.64	6,921.99	6,919.84	26.90	158.74	-152.42	328.99	142.97	760.62	576.67	183.95	4.135	Alert	
7,050.00	6,978.74	6,971.09	6,968.94	27.12	159.78	-152.74	328.99	142.97	769.02	583.86	185.17	4.153	Alert	
7,100.00	7,027.85	7,020.19	7,018.05	27.34	160.82	-153.06	328.99	142.97	777.45	591.06	186.39	4.171	Alert	
7,150.00	7,076.95	7,069.30	7,067.15	27.56	161.86	-153.37	328.99	142.97	785.90	598.29	187.61	4.189	Alert	
7,200.00	7,126.05	7,118.57	7,116.41	27.77	162.90	-153.61	330.08	142.97	794.99	606.16	188.83	4.210	Alert	
7,250.00	7,175.15	7,168.47	7,166.32	27.99	163.95	-153.91	330.02	142.97	803.45	613.37	190.07	4.227	Alert	
7,300.00	7,224.26	7,218.39	7,216.23	28.21	165.01	-154.22	329.87	142.97	811.87	620.56	191.31	4.244	Alert	
7,350.00	7,273.36	7,268.31	7,266.14	28.43	166.06	-154.52	329.64	142.97	820.27	627.72	192.55	4.260	Alert	
7,400.00	7,322.46	7,318.23	7,316.07	28.65	167.12	-154.83	329.31	142.97	828.64	634.85	193.79	4.276	Alert	
7,450.00	7,371.57	7,368.17	7,365.99	28.87	168.18	-155.13	328.90	142.97	836.99	641.96	195.03	4.292	Alert	
7,500.00	7,420.67	7,413.09	7,410.87	29.09	169.13	-155.37	328.99	142.97	845.62	649.47	196.15	4.311	Alert	
7,550.00	7,469.77	7,462.19	7,459.97	29.31	170.16	-155.63	328.99	142.97	854.23	656.85	197.37	4.328	Alert	
7,600.00	7,518.87	7,511.30	7,509.07	29.53	171.20	-155.89	328.99	142.97	862.85	664.26	198.60	4.345	Alert	
7,650.00	7,567.98	7,561.71	7,559.48	29.75	172.27	-156.11	329.60	142.97	871.82	671.97	199.85	4.362	Alert	
7,700.00	7,617.08	7,612.16	7,609.93	29.97	173.34	-156.38	329.39	142.97	880.37	679.26	201.10	4.378	Alert	
7,750.00	7,666.18	7,675.35	7,656.38	30.19	174.67	-156.63	328.99	142.97	888.83	686.21	202.62	4.387	Alert	
7,800.00	7,715.28	7,707.75	7,705.48	30.41	175.36	-156.87	328.99	142.97	897.51	694.03	203.48	4.411	Alert	
7,850.00	7,764.39	7,756.86	7,754.59	30.63	176.40	-157.10	328.99	142.97	906.22	701.51	204.71	4.427	Alert	
7,900.00	7,813.49	7,806.71	7,804.43	30.84	177.45	-157.31	329.49	142.97	915.19	709.25	205.95	4.444	Alert	
7,950.00	7,862.59	7,952.90	7,852.79	31.06	180.55	-157.56	328.99	142.97	923.67	714.44	209.22	4.415	Alert	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: WCDSC Permian NM
Project: Eddy County (NAD 83 NM Eastern)
Reference Site: Sec 11-T23S-R31E
Site Error: 0.00 ft
Reference Well: Belloq 11 Fed 222H
Well Error: 0.50 ft
Reference Wellbore: Wellbore #1
Reference Design: Permit Plan 1

Local Co-ordinate Reference: Well Belloq 11 Fed 222H
TVD Reference: RKB @ 3453.80ft
MD Reference: RKB @ 3453.80ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM r5000.141_Prod US
Offset TVD Reference: Offset Datum

Offset Design										Sec 11-T23S-R31E - Barclay 11 M Federal #013 (Shut in) - Wellbore #1 - Wellbore #1		Offset Site Error:		0.00 ft	
Survey Program: 250-INC-ONLY												Offset Well Error:		0.50 ft	
Reference		Offset		Semi Major Axis			Distance							Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft) +E/-W (ft)		Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor			
8,000.00	7,911.69	7,908.52	7,906.24	31.28	179.61	-157.80	328.95	142.97	932.40	723.92	208.48	4.472	Alert		
8,050.00	7,960.80	7,953.30	7,951.00	31.51	180.56	-157.99	328.99	142.97	941.17	731.57	209.60	4.490	Alert		
8,100.00	8,009.90	8,002.41	8,000.10	31.73	181.60	-158.21	328.99	142.97	949.94	739.12	210.82	4.506	Alert		
8,150.00	8,059.00	8,051.51	8,049.20	31.95	182.64	-158.42	328.99	142.97	958.72	746.68	212.04	4.521	Alert		
8,200.00	8,108.11	8,100.61	8,098.31	32.17	183.68	-158.62	328.99	142.97	967.52	754.25	213.27	4.537	Alert		
8,250.00	8,157.21	8,149.72	8,147.41	32.39	184.72	-158.82	328.99	142.97	976.33	761.84	214.49	4.552	Alert		
8,300.00	8,206.31	8,198.82	8,196.51	32.61	185.75	-159.02	328.99	142.97	985.15	769.43	215.71	4.567	Alert		
8,350.00	8,255.41	8,247.92	8,245.61	32.83	186.79	-159.21	328.99	142.97	993.98	777.04	216.94	4.582	Alert		
8,400.00	8,304.52	8,297.02	8,294.72	33.05	187.83	-159.40	328.99	142.97	1,002.82	784.66	218.16	4.597	Alert		
8,450.00	8,353.62	8,346.13	8,343.82	33.27	188.87	-159.59	328.99	142.97	1,011.67	792.29	219.39	4.611	Alert		
8,500.00	8,402.72	8,395.23	8,392.92	33.49	189.91	-159.78	328.99	142.97	1,020.53	799.93	220.61	4.626	Alert		
8,550.00	8,451.82	8,444.33	8,442.02	33.71	190.95	-159.96	328.99	142.97	1,029.41	807.57	221.83	4.640	Alert		
8,600.00	8,500.93	8,404.00	8,401.62	33.93	190.10	-159.81	328.99	142.97	1,042.14	821.99	220.15	4.734	Alert		
8,650.00	8,550.03	8,404.00	8,401.62	34.15	190.10	-159.81	328.99	142.97	1,056.32	837.15	219.17	4.820	Alert		
8,700.00	8,599.13	8,404.00	8,401.62	34.37	190.10	-159.81	328.99	142.97	1,072.64	854.84	217.80	4.925	Alert		
8,750.00	8,648.24	8,404.00	8,401.62	34.59	190.10	-159.81	328.99	142.97	1,091.01	874.91	216.10	5.049			
8,800.00	8,697.34	8,404.00	8,401.62	34.81	190.10	-159.81	328.99	142.97	1,111.32	897.22	214.10	5.191			
8,850.00	8,746.44	8,404.00	8,401.62	35.04	190.10	-159.81	328.99	142.97	1,133.48	921.63	211.85	5.350			
8,900.00	8,795.54	8,404.00	8,401.62	35.26	190.10	-159.81	328.99	142.97	1,157.38	947.97	209.41	5.527			
8,950.00	8,844.65	8,404.00	8,401.62	35.48	190.10	-159.81	328.99	142.97	1,182.91	976.11	206.80	5.720			
9,000.00	8,893.75	8,404.00	8,401.62	35.70	190.10	-159.81	328.99	142.97	1,209.97	1,005.90	204.07	5.929			
9,050.00	8,942.85	8,404.00	8,401.62	35.92	190.10	-159.81	328.99	142.97	1,238.45	1,037.21	201.25	6.154			
9,100.00	8,991.95	8,404.00	8,401.62	36.14	190.10	-159.81	328.99	142.97	1,268.27	1,069.90	198.37	6.394			
9,150.00	9,041.06	8,404.00	8,401.62	36.36	190.10	-159.81	328.99	142.97	1,299.33	1,103.87	195.46	6.648			
9,200.00	9,090.16	8,404.00	8,401.62	36.58	190.10	-159.81	328.99	142.97	1,331.54	1,139.00	192.54	6.916			
9,250.00	9,139.26	8,404.00	8,401.62	36.81	190.10	-159.81	328.99	142.97	1,364.82	1,175.20	189.63	7.197			
9,300.00	9,188.36	8,404.00	8,401.62	37.03	190.10	-159.81	328.99	142.97	1,399.10	1,212.36	186.75	7.492			
9,350.00	9,237.47	8,404.00	8,401.62	37.25	190.10	-159.81	328.99	142.97	1,434.31	1,250.40	183.90	7.799			
9,400.00	9,286.57	8,404.00	8,401.62	37.47	190.10	-159.81	328.99	142.97	1,470.37	1,289.26	181.11	8.119			

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Barclay 11 N Federal #014 - Wellbore #1 - Wellbore #1													Offset Site Error:	0.00 ft
Survey Program: 141-INC-ONLY													Offset Well Error:	10.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)						
0.00	0.00	11.20	11.20	0.50	10.00	77.27	330.61	1,462.93	1,499.82					
50.00	50.00	61.20	61.20	0.50	10.02	77.27	330.61	1,462.93	1,499.82	1,489.31	10.52	142.607		
100.00	100.00	111.20	111.20	0.52	10.05	77.27	330.61	1,462.93	1,499.82	1,489.26	10.57	141.923		
150.00	150.00	161.20	161.20	0.59	10.14	77.27	330.61	1,462.93	1,499.82	1,489.10	10.73	139.827		
200.00	200.00	211.54	211.54	0.70	10.34	77.26	330.81	1,462.93	1,499.87	1,488.83	11.04	135.885		
250.00	250.00	264.79	261.20	0.84	10.64	77.27	330.61	1,462.93	1,499.82	1,488.35	11.47	130.711		
300.00	300.00	311.21	311.20	0.99	10.96	77.27	330.61	1,462.93	1,499.82	1,487.88	11.95	125.560		
350.00	350.00	361.68	361.67	1.15	11.37	77.26	330.76	1,462.93	1,499.86	1,487.34	12.52	119.841		
400.00	400.00	412.78	411.20	1.31	11.85	77.27	330.61	1,462.93	1,499.82	1,486.67	13.16	114.001		
450.00	450.00	461.22	461.20	1.48	12.35	77.27	330.61	1,462.93	1,499.82	1,486.00	13.83	108.478		
500.00	500.00	511.82	511.80	1.65	12.92	77.26	330.74	1,462.93	1,499.85	1,485.29	14.57	102.968		
550.00	550.00	562.87	562.85	1.82	13.54	77.27	330.57	1,462.93	1,499.81	1,484.46	15.35	97.680		
554.99	554.99	567.96	567.94	1.83	13.60	77.27	330.54	1,462.93	1,499.81	1,484.37	15.44	97.168		
600.00	600.00	611.22	611.20	1.99	14.20	77.27	330.61	1,462.93	1,499.82	1,483.63	16.19	92.628		
650.00	650.00	662.06	662.04	2.16	14.93	77.26	330.71	1,462.93	1,499.85	1,482.76	17.09	87.759		
700.00	700.00	711.23	711.20	2.34	15.68	77.27	330.61	1,462.93	1,499.82	1,481.81	18.01	83.254		
750.00	750.00	761.23	761.20	2.51	16.50	77.27	330.61	1,462.93	1,499.82	1,480.81	19.01	78.898		
800.00	800.00	812.61	812.57	2.69	17.36	77.26	330.89	1,462.93	1,499.89	1,479.83	20.05	74.796		
850.00	850.00	864.44	864.40	2.87	18.26	77.27	330.54	1,462.93	1,499.81	1,478.68	21.13	70.992		
861.05	861.05	875.89	875.85	2.91	18.46	77.27	330.42	1,462.93	1,499.78	1,478.42	21.37	70.193		
900.00	900.00	913.40	913.34	3.04	19.16	77.26	330.68	1,462.93	1,499.84	1,477.63	22.21	67.538		
917.33	917.33	932.39	932.33	3.10	19.52	77.27	330.51	1,462.93	1,499.80	1,477.18	22.62	66.300		
950.00	950.00	961.27	961.20	3.22	20.11	77.27	330.61	1,462.93	1,499.82	1,476.49	23.33	64.285		
1,000.00	1,000.00	1,015.15	1,015.07	3.40	21.21	77.27	330.58	1,462.93	1,499.82	1,475.22	24.60	60.958		
1,008.48	1,008.48	1,024.37	1,024.29	3.43	21.40	77.27	330.46	1,462.93	1,499.80	1,474.97	24.82	60.419		
1,050.00	1,050.00	1,156.68	1,061.20	3.58	24.14	77.27	330.61	1,462.93	1,499.82	1,472.11	27.71	54.120		
1,100.00	1,100.00	1,116.31	1,116.20	3.75	23.25	77.27	330.51	1,462.93	1,499.81	1,472.80	27.01	55.536		
1,106.73	1,106.73	1,123.71	1,123.60	3.78	23.41	77.27	330.39	1,462.93	1,499.79	1,472.60	27.18	55.177		
1,150.00	1,150.00	1,161.32	1,161.20	3.93	24.24	77.27	330.61	1,462.93	1,499.82	1,471.65	28.17	53.243		
1,200.00	1,200.00	1,211.32	1,211.20	4.11	25.33	77.27	330.61	1,462.93	1,499.82	1,470.38	29.44	50.941		
1,250.00	1,250.00	1,261.32	1,261.20	4.29	26.44	77.27	330.61	1,462.93	1,499.82	1,469.10	30.72	48.816		
1,300.00	1,300.00	1,311.32	1,311.20	4.46	27.55	77.27	330.61	1,462.93	1,499.82	1,467.81	32.01	46.850		
1,350.00	1,350.00	1,361.32	1,361.20	4.64	28.67	77.27	330.61	1,462.93	1,499.82	1,466.51	33.31	45.026		
1,400.00	1,400.00	1,411.32	1,411.20	4.82	29.79	77.27	330.61	1,462.93	1,499.82	1,465.21	34.61	43.331		
1,450.00	1,450.00	1,461.32	1,461.20	5.00	30.92	77.27	330.61	1,462.93	1,499.82	1,463.90	35.92	41.753		
1,500.00	1,500.00	1,511.32	1,511.20	5.18	32.06	77.27	330.61	1,462.93	1,499.82	1,462.59	37.23	40.280		
1,550.00	1,550.00	1,561.32	1,561.20	5.36	33.20	77.27	330.61	1,462.93	1,499.82	1,461.27	38.55	38.904		
1,600.00	1,600.00	1,611.32	1,611.20	5.53	34.34	77.27	330.61	1,462.93	1,499.82	1,459.95	39.87	37.614		
1,650.00	1,650.00	1,661.32	1,661.20	5.71	35.49	77.27	330.61	1,462.93	1,499.82	1,458.62	41.20	36.404		
1,700.00	1,700.00	1,711.32	1,711.20	5.89	36.64	77.27	330.61	1,462.93	1,499.82	1,457.30	42.53	35.267		
1,750.00	1,750.00	1,761.32	1,761.20	6.07	37.79	77.27	330.61	1,462.93	1,499.82	1,455.96	43.86	34.197		
1,800.00	1,800.00	1,811.32	1,811.20	6.25	38.94	77.27	330.61	1,462.93	1,499.82	1,454.63	45.19	33.187		
1,850.00	1,850.00	1,861.32	1,861.20	6.43	40.10	77.27	330.61	1,462.93	1,499.82	1,453.29	46.53	32.234		
2,550.00	2,550.00	2,564.15	2,563.96	8.93	56.55	-21.69	331.11	1,462.93	1,499.68	1,434.21	65.48	22.904		
2,600.00	2,599.99	2,614.35	2,614.16	9.10	57.73	-21.69	330.69	1,462.93	1,498.83	1,432.00	66.83	22.427		
2,650.00	2,649.97	2,664.55	2,664.34	9.27	58.92	-21.70	330.25	1,462.93	1,497.47	1,429.28	68.19	21.962		
2,700.00	2,699.94	2,726.26	2,711.14	9.44	60.58	-21.74	330.61	1,462.93	1,495.77	1,425.76	70.01	21.364		
2,750.00	2,749.88	2,761.68	2,761.08	9.61	61.45	-21.79	330.61	1,462.93	1,493.49	1,422.43	71.06	21.017		
2,800.00	2,799.79	2,816.27	2,815.66	9.78	62.81	-21.85	330.57	1,462.93	1,490.70	1,418.12	72.58	20.538		
2,850.00	2,849.66	2,861.50	2,860.86	9.95	63.88	-21.91	330.61	1,462.93	1,487.42	1,413.59	73.83	20.147		
2,900.00	2,899.49	2,911.33	2,910.69	10.12	65.07	-21.99	330.61	1,462.93	1,483.63	1,408.44	75.19	19.733		
2,950.00	2,949.28	2,961.12	2,960.48	10.30	66.25	-22.07	330.61	1,462.93	1,479.33	1,402.79	76.54	19.327		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Barclay 11 N Federal #014 - Wellbore #1 - Wellbore #1													Offset Site Error:	0.00 ft
Survey Program: 141-INC-ONLY													Offset Well Error:	10.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)						
3,000.00	2,999.01	3,010.85	3,010.21	10.47	67.44	-22.17	330.61	1,462.93	1,474.54	1,396.64	77.90	18.928		
3,050.00	3,048.68	3,061.18	3,060.52	10.65	68.64	-22.34	332.00	1,462.93	1,469.56	1,390.29	79.27	18.538		
3,100.00	3,098.29	3,111.84	3,111.18	10.82	69.85	-22.45	331.82	1,462.93	1,463.73	1,383.08	80.66	18.148		
3,150.00	3,147.82	3,162.45	3,161.77	11.00	71.06	-22.57	331.49	1,462.93	1,457.37	1,375.33	82.04	17.765		
3,200.00	3,197.28	3,282.75	3,208.48	11.18	74.01	-22.68	330.61	1,462.93	1,450.38	1,365.22	85.16	17.032		
3,250.00	3,246.66	3,263.45	3,262.75	11.36	73.47	-22.84	330.37	1,462.93	1,443.05	1,358.26	84.79	17.018		
3,300.00	3,295.94	3,307.91	3,307.14	11.54	74.66	-23.00	330.61	1,462.93	1,435.34	1,349.18	86.15	16.660		
3,350.00	3,345.14	3,357.10	3,356.34	11.72	75.94	-23.18	330.61	1,462.93	1,427.08	1,339.48	87.60	16.290		
3,400.00	3,394.25	3,406.21	3,405.45	11.91	77.21	-23.35	330.61	1,462.93	1,418.43	1,329.38	89.05	15.929		
3,450.00	3,443.35	3,455.31	3,454.55	12.09	78.48	-23.50	330.61	1,462.93	1,409.76	1,319.26	90.50	15.578		
3,500.00	3,492.45	3,504.78	3,504.00	12.28	79.76	-23.71	331.89	1,462.93	1,401.41	1,309.45	91.95	15.240		
3,550.00	3,541.56	3,554.70	3,553.92	12.47	81.06	-23.86	331.78	1,462.93	1,392.72	1,299.30	93.42	14.907		
3,600.00	3,590.66	3,604.64	3,603.85	12.66	82.36	-24.01	331.56	1,462.93	1,384.02	1,289.13	94.90	14.585		
3,650.00	3,639.76	3,654.58	3,653.79	12.85	83.65	-24.16	331.22	1,462.93	1,375.30	1,278.94	96.37	14.271		
3,700.00	3,688.86	3,736.98	3,700.06	13.04	85.83	-24.29	330.61	1,462.93	1,366.52	1,267.80	98.72	13.842		
3,750.00	3,737.97	3,754.49	3,753.68	13.24	86.25	-24.45	330.19	1,462.93	1,357.80	1,258.48	99.32	13.671		
3,800.00	3,787.07	3,799.23	3,798.27	13.43	87.58	-24.62	330.61	1,462.93	1,349.30	1,248.47	100.83	13.382		
3,850.00	3,836.17	3,848.33	3,847.37	13.63	88.96	-24.78	330.61	1,462.93	1,340.70	1,238.32	102.39	13.095		
3,900.00	3,885.27	3,897.43	3,896.47	13.82	90.33	-24.95	330.61	1,462.93	1,332.12	1,228.18	103.95	12.816		
3,950.00	3,934.38	3,946.54	3,945.58	14.02	91.71	-25.12	330.61	1,462.93	1,323.55	1,218.04	105.51	12.545		
4,000.00	3,983.48	3,996.77	3,995.77	14.22	93.13	-25.39	332.61	1,462.93	1,315.54	1,208.44	107.10	12.284		
4,050.00	4,032.58	4,047.28	4,046.27	14.42	94.55	-25.56	332.36	1,462.93	1,306.93	1,198.23	108.70	12.023		
4,100.00	4,081.68	4,097.80	4,096.78	14.62	95.97	-25.72	331.93	1,462.93	1,298.28	1,187.98	110.30	11.770		
4,150.00	4,130.79	4,148.34	4,147.31	14.82	97.39	-25.88	331.30	1,462.93	1,289.59	1,177.69	111.90	11.524		
4,200.00	4,179.89	4,198.90	4,197.85	15.02	98.81	-26.04	330.49	1,462.93	1,280.86	1,167.35	113.51	11.285		
4,250.00	4,228.99	4,241.40	4,240.19	15.22	100.01	-26.20	330.61	1,462.93	1,272.38	1,157.48	114.89	11.074		
4,300.00	4,278.10	4,291.93	4,290.71	15.42	101.43	-26.42	331.19	1,462.93	1,264.06	1,147.56	116.50	10.850		
4,350.00	4,327.20	4,344.84	4,343.61	15.63	102.93	-26.61	330.72	1,462.93	1,255.46	1,137.29	118.18	10.624		
4,400.00	4,376.30	4,388.80	4,387.50	15.83	104.13	-26.77	330.61	1,462.93	1,246.97	1,127.40	119.57	10.429		
4,450.00	4,425.40	4,436.04	4,436.60	16.04	106.93	-26.97	330.61	1,462.93	1,238.52	1,115.97	122.55	10.106		
4,500.00	4,474.51	4,487.06	4,485.71	16.24	106.72	-27.17	330.61	1,462.93	1,230.10	1,107.56	122.53	10.039		
4,550.00	4,523.61	4,536.16	4,534.81	16.45	107.85	-27.37	330.61	1,462.93	1,221.68	1,097.83	123.85	9.864		
4,600.00	4,572.71	4,585.26	4,583.91	16.65	108.98	-27.57	330.61	1,462.93	1,213.28	1,088.12	125.17	9.693		
4,650.00	4,621.81	4,634.37	4,633.01	16.86	110.11	-27.78	330.61	1,462.93	1,204.90	1,078.41	126.49	9.526		
4,700.00	4,670.92	4,683.47	4,682.12	17.06	111.24	-27.99	330.61	1,462.93	1,196.53	1,068.73	127.81	9.362		
4,750.00	4,720.02	4,733.61	4,732.24	17.27	112.40	-28.27	332.00	1,462.93	1,188.63	1,059.48	129.15	9.203		
4,800.00	4,769.12	4,783.89	4,782.51	17.48	113.56	-28.48	331.79	1,462.93	1,180.23	1,049.73	130.50	9.044		
4,850.00	4,818.23	4,834.18	4,832.79	17.69	114.72	-28.69	331.43	1,462.93	1,171.80	1,039.96	131.85	8.888		
4,900.00	4,867.33	4,940.01	4,878.53	17.90	117.00	-28.86	330.61	1,462.93	1,163.22	1,028.90	134.32	8.660		
4,950.00	4,916.43	4,934.80	4,933.39	18.10	117.04	-29.09	330.27	1,462.93	1,154.84	1,020.29	134.54	8.583		
5,000.00	4,965.53	4,978.19	4,976.73	18.31	117.69	-29.31	330.61	1,462.93	1,146.67	1,011.28	135.39	8.469		
5,050.00	5,014.64	5,027.29	5,025.84	18.52	118.57	-29.54	330.61	1,462.93	1,138.42	1,001.96	136.46	8.342		
5,100.00	5,063.74	5,076.40	5,074.94	18.73	119.45	-29.78	330.61	1,462.93	1,130.19	992.66	137.54	8.217		
5,150.00	5,112.84	5,125.50	5,124.04	18.94	120.33	-30.01	330.61	1,462.93	1,121.98	983.37	138.61	8.095		
5,200.00	5,161.94	5,175.02	5,173.55	19.16	121.22	-30.31	331.63	1,462.93	1,114.15	974.46	139.69	7.976		
5,250.00	5,211.05	5,224.86	5,223.39	19.37	122.11	-30.55	331.54	1,462.93	1,105.95	965.17	140.78	7.856		
5,300.00	5,260.15	5,274.72	5,273.24	19.58	123.01	-30.80	331.35	1,462.93	1,097.73	955.87	141.86	7.738		
5,350.00	5,309.25	5,324.58	5,323.10	19.79	123.90	-31.04	331.07	1,462.93	1,089.50	946.55	142.95	7.621		
5,400.00	5,358.35	5,396.96	5,369.55	20.00	125.17	-31.26	330.61	1,462.93	1,081.22	936.80	144.42	7.486		
5,450.00	5,407.46	5,424.32	5,422.83	20.21	125.69	-31.52	330.23	1,462.93	1,073.00	927.87	145.13	7.393		
5,500.00	5,456.56	5,469.25	5,467.76	20.43	126.34	-31.78	330.61	1,462.93	1,065.06	919.08	145.98	7.296		
5,550.00	5,505.66	5,518.35	5,516.86	20.64	127.13	-32.05	330.61	1,462.93	1,057.02	910.05	146.97	7.192		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Barclay 11 N Federal #014 - Wellbore #1 - Wellbore #1													Offset Site Error:	0.00 ft
Survey Program: 141-INC-ONLY													Offset Well Error:	10.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (ft)	Separation Factor	Warning			
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference	Offset (ft)		Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)				Between Centres (ft)	Between Ellipses (ft)	
5,600.00	5,554.77	5,567.46	5,565.97	20.85	127.92	-32.32	330.61	1,462.93	1,049.00	901.04	147.96	7.090		
5,650.00	5,603.87	5,616.61	5,615.11	21.07	128.71	-32.61	330.85	1,462.93	1,041.10	892.15	148.94	6.990		
5,700.00	5,652.97	5,665.91	5,664.42	21.28	129.50	-32.89	330.84	1,462.93	1,033.12	883.18	149.94	6.890		
5,750.00	5,702.07	5,715.21	5,713.72	21.49	130.30	-33.18	330.79	1,462.93	1,025.15	874.22	150.93	6.792		
5,800.00	5,751.18	5,764.52	5,763.03	21.71	131.09	-33.46	330.73	1,462.93	1,017.20	865.28	151.92	6.696		
5,850.00	5,800.28	5,839.02	5,811.48	21.92	132.32	-33.75	330.61	1,462.93	1,009.26	855.91	153.35	6.581		
5,900.00	5,849.38	5,863.14	5,861.65	22.14	132.68	-34.05	330.52	1,462.93	1,001.35	847.44	153.91	6.506		
5,950.00	5,898.48	5,911.18	5,909.68	22.35	133.63	-34.35	330.61	1,462.93	993.54	838.47	155.07	6.407		
6,000.00	5,947.59	5,960.29	5,958.79	22.57	134.53	-34.65	330.61	1,462.93	985.73	829.56	156.16	6.312		
6,050.00	5,996.69	6,009.39	6,007.89	22.78	135.42	-34.97	330.61	1,462.93	977.94	820.67	157.26	6.219		
6,100.00	6,045.79	6,058.49	6,056.99	23.00	136.32	-35.28	330.61	1,462.93	970.18	811.82	158.36	6.126		
6,150.00	6,094.90	6,107.83	6,106.33	23.21	137.22	-35.64	331.15	1,462.93	962.69	803.22	159.46	6.037		
6,200.00	6,144.00	6,157.31	6,155.80	23.43	138.12	-35.96	331.10	1,462.93	954.97	794.40	160.57	5.947		
6,250.00	6,193.10	6,206.78	6,205.28	23.64	139.02	-36.29	331.01	1,462.93	947.26	785.59	161.68	5.859		
6,300.00	6,242.20	6,256.26	6,254.76	23.86	139.93	-36.63	330.87	1,462.93	939.57	776.79	162.78	5.772		
6,350.00	6,291.31	6,347.96	6,302.51	24.08	141.64	-36.95	330.61	1,462.93	931.85	767.14	164.71	5.658		
6,400.00	6,340.41	6,355.23	6,353.73	24.29	141.73	-37.30	330.48	1,462.93	924.22	759.22	165.00	5.601		
6,450.00	6,389.51	6,402.24	6,400.71	24.51	142.74	-37.65	330.61	1,462.93	916.75	750.52	166.22	5.515		
6,500.00	6,438.61	6,451.34	6,449.81	24.73	143.73	-38.01	330.61	1,462.93	909.25	741.82	167.42	5.431		
6,550.00	6,487.72	6,500.45	6,498.92	24.94	144.72	-38.38	330.61	1,462.93	901.79	733.16	168.62	5.348		
6,600.00	6,536.82	6,549.64	6,548.10	25.16	145.72	-38.79	331.32	1,462.93	894.71	724.88	169.83	5.268		
6,650.00	6,585.92	6,599.41	6,597.87	25.38	146.73	-39.17	331.27	1,462.93	887.30	716.26	171.05	5.187		
6,700.00	6,635.02	6,649.18	6,647.64	25.59	147.73	-39.56	331.15	1,462.93	879.90	707.63	172.26	5.108		
6,750.00	6,684.13	6,698.96	6,697.42	25.81	148.74	-39.94	330.96	1,462.93	872.49	699.01	173.48	5.029		
6,800.00	6,733.23	6,773.99	6,744.43	26.03	150.27	-40.30	330.61	1,462.93	865.05	689.82	175.23	4.937 Alert		
6,850.00	6,782.33	6,798.53	6,796.99	26.25	150.75	-40.72	330.34	1,462.93	857.69	681.77	175.92	4.876 Alert		
6,900.00	6,831.44	6,844.22	6,842.64	26.47	151.76	-41.12	330.61	1,462.93	850.65	673.50	177.15	4.802 Alert		
6,950.00	6,880.54	6,893.32	6,891.74	26.68	152.80	-41.54	330.61	1,462.93	843.51	665.11	178.40	4.728 Alert		
7,000.00	6,929.64	6,942.42	6,940.84	26.90	153.84	-41.96	330.61	1,462.93	836.42	656.76	179.66	4.656 Alert		
7,050.00	6,978.74	6,991.71	6,990.12	27.12	154.88	-42.45	331.58	1,462.93	829.90	648.97	180.92	4.587 Alert		
7,100.00	7,027.85	7,041.71	7,040.12	27.34	155.94	-42.89	331.51	1,462.93	822.87	640.67	182.20	4.516 Alert		
7,150.00	7,076.95	7,091.73	7,090.13	27.56	157.00	-43.34	331.34	1,462.93	815.83	632.36	183.47	4.447 Alert		
7,200.00	7,126.05	7,141.75	7,140.15	27.77	158.06	-43.79	331.07	1,462.93	808.79	624.04	184.75	4.378 Alert		
7,250.00	7,175.15	7,218.00	7,186.35	27.99	159.69	-44.20	330.61	1,462.93	801.68	615.07	186.61	4.296 Alert		
7,300.00	7,224.26	7,241.81	7,240.20	28.21	160.18	-44.69	330.24	1,462.93	794.69	607.38	187.31	4.243 Alert		
7,350.00	7,273.36	7,286.21	7,284.56	28.43	161.20	-45.14	330.61	1,462.93	788.15	599.58	188.56	4.180 Alert		
7,400.00	7,322.46	7,335.31	7,333.66	28.65	162.29	-45.63	330.61	1,462.93	781.47	591.59	189.88	4.116 Alert		
7,450.00	7,371.57	7,384.41	7,382.77	28.87	163.38	-46.12	330.61	1,462.93	774.84	583.65	191.19	4.053 Alert		
7,500.00	7,420.67	7,433.77	7,432.11	29.09	164.47	-46.68	331.56	1,462.93	768.84	576.33	192.51	3.994 Alert		
7,550.00	7,469.77	7,483.81	7,482.16	29.31	165.58	-47.20	331.48	1,462.93	762.30	568.46	193.84	3.933 Alert		
7,600.00	7,518.87	7,533.87	7,532.21	29.53	166.69	-47.72	331.30	1,462.93	755.75	560.57	195.17	3.872 Alert		
7,650.00	7,567.98	7,583.94	7,582.27	29.75	167.80	-48.24	331.03	1,462.93	749.20	552.69	196.51	3.813 Alert		
7,700.00	7,617.08	7,645.99	7,628.28	29.97	169.20	-48.72	330.61	1,462.93	742.62	544.47	198.15	3.748 Alert		
7,750.00	7,666.18	7,684.09	7,682.41	30.19	170.02	-49.29	330.17	1,462.93	736.10	536.92	199.18	3.696 Alert		
7,800.00	7,715.28	7,728.22	7,726.48	30.41	171.34	-49.82	330.61	1,462.93	730.18	529.44	200.75	3.637 Alert		
7,850.00	7,764.39	7,777.32	7,775.59	30.63	172.61	-50.38	330.61	1,462.93	724.07	521.82	202.25	3.580 Alert		
7,900.00	7,813.49	7,826.42	7,824.69	30.84	173.89	-50.96	330.61	1,462.93	718.03	514.27	203.76	3.524 Alert		
7,950.00	7,862.59	7,875.53	7,873.78	31.06	175.16	-51.62	331.91	1,462.93	712.93	507.65	205.27	3.473 Alert		
8,000.00	7,911.69	7,925.75	7,924.00	31.28	176.47	-52.22	331.85	1,462.93	707.01	500.20	206.81	3.419 Alert		
8,050.00	7,960.80	7,975.98	7,974.23	31.51	177.77	-52.83	331.68	1,462.93	701.09	492.74	208.35	3.365 Alert		
8,100.00	8,009.90	8,026.22	8,024.46	31.73	179.08	-53.43	331.39	1,462.93	695.16	485.28	209.89	3.312 Alert		
8,150.00	8,059.00	8,076.48	8,074.71	31.95	180.38	-54.05	330.98	1,462.93	689.24	477.81	211.42	3.260 Alert		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Barclay 11 N Federal #014 - Wellbore #1 - Wellbore #1												Offset Site Error:	0.00 ft
Survey Program: 141-INC-ONLY												Offset Well Error:	10.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (ft)	Separation Factor	Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		+N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)			
8,200.00	8,108.11	8,126.74	8,124.96	32.17	181.69	-54.66	330.46	1,462.93	683.31	470.34	212.96	3.209	Alert
8,250.00	8,157.21	8,170.34	8,168.41	32.39	182.88	-55.24	330.61	1,462.93	677.91	463.49	214.41	3.162	Alert
8,300.00	8,206.31	8,219.44	8,217.51	32.61	184.20	-55.89	330.61	1,462.93	672.51	456.53	215.98	3.114	Alert
8,350.00	8,255.41	8,268.54	8,266.61	32.83	185.53	-56.56	330.61	1,462.93	667.20	449.66	217.55	3.067	Alert
8,400.00	8,304.52	8,318.30	8,316.34	33.05	186.87	-57.33	332.27	1,462.93	663.21	444.08	219.13	3.027	Alert
8,450.00	8,353.62	8,369.76	8,367.79	33.27	188.26	-58.04	332.08	1,462.93	657.97	437.21	220.76	2.980	Alert
8,500.00	8,402.72	8,421.24	8,419.26	33.49	189.65	-58.74	331.65	1,462.93	652.64	430.26	222.38	2.935	Alert
8,550.00	8,451.82	8,472.75	8,470.76	33.71	191.04	-59.44	330.98	1,462.93	647.23	423.23	224.00	2.889	Alert
8,600.00	8,500.93	8,524.28	8,522.26	33.93	192.43	-60.14	330.06	1,462.93	641.73	416.11	225.62	2.844	Alert
8,650.00	8,550.03	8,563.34	8,561.23	34.15	193.35	-60.75	330.61	1,462.93	637.36	410.52	226.84	2.810	Alert
8,700.00	8,599.13	8,595.00	8,592.86	34.37	194.15	-61.22	330.61	1,462.93	632.98	405.14	227.84	2.778	Alert, SF
8,740.62	8,639.02	8,595.00	8,592.86	34.55	194.15	-61.22	330.61	1,462.93	631.67	404.37	227.31	2.779	Alert, CC, ES
8,750.00	8,648.24	8,595.00	8,592.86	34.59	194.15	-61.22	330.61	1,462.93	631.74	404.68	227.06	2.782	Alert
8,800.00	8,697.34	8,595.00	8,592.86	34.81	194.15	-61.22	330.61	1,462.93	634.46	409.48	224.98	2.820	Alert
8,850.00	8,746.44	8,595.00	8,592.86	35.04	194.15	-61.22	330.61	1,462.93	641.08	419.42	221.66	2.892	Alert
8,900.00	8,795.54	8,595.00	8,592.86	35.26	194.15	-61.22	330.61	1,462.93	651.47	434.22	217.25	2.999	Alert
8,950.00	8,844.65	8,595.00	8,592.86	35.48	194.15	-61.22	330.61	1,462.93	665.47	453.55	211.92	3.140	Alert
9,000.00	8,893.75	8,595.00	8,592.86	35.70	194.15	-61.22	330.61	1,462.93	682.86	476.95	205.90	3.316	Alert
9,050.00	8,942.85	8,595.00	8,592.86	35.92	194.15	-61.22	330.61	1,462.93	703.37	503.98	199.39	3.528	Alert
9,100.00	8,991.95	8,595.00	8,592.86	36.14	194.15	-61.22	330.61	1,462.93	726.75	534.17	192.59	3.774	Alert
9,150.00	9,041.06	8,595.00	8,592.86	36.36	194.15	-61.22	330.61	1,462.93	752.73	567.07	185.66	4.054	Alert
9,200.00	9,090.16	8,595.00	8,592.86	36.58	194.15	-61.22	330.61	1,462.93	781.05	602.30	178.76	4.369	Alert
9,250.00	9,139.26	8,595.00	8,592.86	36.81	194.15	-61.22	330.61	1,462.93	811.47	639.48	171.99	4.718	Alert
9,300.00	9,188.36	8,595.00	8,592.86	37.03	194.15	-61.22	330.61	1,462.93	843.76	678.32	165.43	5.100	
9,350.00	9,237.47	8,595.00	8,592.86	37.25	194.15	-61.22	330.61	1,462.93	877.70	718.56	159.14	5.515	
9,400.00	9,286.57	8,595.00	8,592.86	37.47	194.15	-61.22	330.61	1,462.93	913.13	759.97	153.16	5.962	
9,450.00	9,335.67	8,595.00	8,592.86	37.69	194.15	-61.22	330.61	1,462.93	949.86	802.36	147.50	6.440	
9,500.00	9,384.78	8,595.00	8,592.86	37.91	194.15	-61.22	330.61	1,462.93	987.76	845.59	142.18	6.948	
9,550.00	9,433.88	8,595.00	8,592.86	38.14	194.15	-61.22	330.61	1,462.93	1,026.70	889.52	137.18	7.484	
9,600.00	9,482.98	8,595.00	8,592.86	38.36	194.15	-61.22	330.61	1,462.93	1,066.56	934.06	132.51	8.049	
9,650.00	9,532.08	8,595.00	8,592.86	38.58	194.15	-61.22	330.61	1,462.93	1,107.24	979.10	128.14	8.641	
9,700.00	9,581.19	8,595.00	8,592.86	38.80	194.15	-61.22	330.61	1,462.93	1,148.66	1,024.59	124.08	9.258	
9,750.00	9,630.29	8,595.00	8,592.86	39.02	194.15	-61.22	330.61	1,462.93	1,190.74	1,070.45	120.29	9.899	
9,800.00	9,679.39	8,595.00	8,592.86	39.25	194.15	-61.22	330.61	1,462.93	1,233.41	1,116.64	116.77	10.562	
9,850.00	9,728.49	8,595.00	8,592.86	39.47	194.15	-61.22	330.61	1,462.93	1,276.61	1,163.11	113.50	11.248	
9,900.00	9,777.60	8,595.00	8,592.86	39.69	194.15	-55.04	330.61	1,462.93	1,320.22	1,209.79	110.43	11.955	
9,950.00	9,826.66	8,595.00	8,592.86	39.91	194.15	-34.80	330.61	1,462.93	1,362.94	1,255.75	107.20	12.714	
10,000.00	9,875.36	8,595.00	8,592.86	40.11	194.15	-20.42	330.61	1,462.93	1,404.17	1,300.48	103.69	13.542	
10,050.00	9,923.32	8,595.00	8,592.86	40.31	194.15	-11.86	330.61	1,462.93	1,443.74	1,343.80	99.95	14.445	
10,100.00	9,970.18	8,595.00	8,592.86	40.49	194.15	-6.86	330.61	1,462.93	1,481.50	1,385.49	96.01	15.431	

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Belloq 11-2 Fed State com 512H - Wellbore #1 - Permit Plan 1													Offset Site Error: 0.00 ft	
Survey Program: 0-MWD+HDGM													Offset Well Error: 0.50 ft	
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor		
0.00	0.00	27.70	27.70	0.50	0.50	89.85	3.62	1,429.68	1,429.69					
50.00	50.00	77.70	77.70	0.50	0.51	89.85	3.62	1,429.68	1,429.69	1,428.67	1.01	1,411.623		
100.00	100.00	127.70	127.70	0.52	0.55	89.85	3.62	1,429.68	1,429.69	1,428.62	1.07	1,336.549		
150.00	150.00	177.70	177.70	0.59	0.65	89.85	3.62	1,429.68	1,429.69	1,428.45	1.24	1,154.158		
200.00	200.00	227.70	227.70	0.70	0.78	89.85	3.62	1,429.68	1,429.69	1,428.21	1.48	967.870		
250.00	250.00	277.70	277.70	0.84	0.92	89.85	3.62	1,429.68	1,429.69	1,427.93	1.76	813.705		
300.00	300.00	327.70	327.70	0.99	1.07	89.85	3.62	1,429.68	1,429.69	1,427.63	2.06	693.528		
350.00	350.00	377.70	377.70	1.15	1.24	89.85	3.62	1,429.68	1,429.69	1,427.31	2.38	600.437		
400.00	400.00	427.70	427.70	1.31	1.40	89.85	3.62	1,429.68	1,429.69	1,426.98	2.71	527.470		
450.00	450.00	477.70	477.70	1.48	1.57	89.85	3.62	1,429.68	1,429.69	1,426.64	3.05	469.298		
500.00	500.00	527.70	527.70	1.65	1.74	89.85	3.62	1,429.68	1,429.69	1,426.30	3.39	422.105		
550.00	550.00	577.70	577.70	1.82	1.91	89.85	3.62	1,429.68	1,429.69	1,425.96	3.73	383.191		
600.00	600.00	627.70	627.70	1.99	2.09	89.85	3.62	1,429.68	1,429.69	1,425.61	4.08	350.631		
650.00	650.00	677.70	677.70	2.16	2.26	89.85	3.62	1,429.68	1,429.69	1,425.26	4.43	323.031		
700.00	700.00	727.70	727.70	2.34	2.44	89.85	3.62	1,429.68	1,429.69	1,424.91	4.78	299.366		
750.00	750.00	777.70	777.70	2.51	2.61	89.85	3.62	1,429.68	1,429.69	1,424.56	5.13	278.866		
800.00	800.00	827.70	827.70	2.69	2.79	89.85	3.62	1,429.68	1,429.69	1,424.21	5.48	260.948		
850.00	850.00	877.70	877.70	2.87	2.96	89.85	3.62	1,429.68	1,429.69	1,423.86	5.83	245.161		
900.00	900.00	927.70	927.70	3.04	3.14	89.85	3.62	1,429.68	1,429.69	1,423.50	6.19	231.151		
950.00	950.00	977.70	977.70	3.22	3.32	89.85	3.62	1,429.68	1,429.69	1,423.15	6.54	218.637		
1,000.00	1,000.00	1,027.70	1,027.70	3.40	3.50	89.85	3.62	1,429.68	1,429.69	1,422.79	6.89	207.394		
1,050.00	1,050.00	1,077.70	1,077.70	3.58	3.67	89.85	3.62	1,429.68	1,429.69	1,422.44	7.25	197.241		
1,100.00	1,100.00	1,127.70	1,127.70	3.75	3.85	89.85	3.62	1,429.68	1,429.69	1,422.08	7.60	188.027		
1,150.00	1,150.00	1,177.70	1,177.70	3.93	4.03	89.85	3.62	1,429.68	1,429.69	1,421.73	7.96	179.629		
1,200.00	1,200.00	1,227.70	1,227.70	4.11	4.21	89.85	3.62	1,429.68	1,429.69	1,421.37	8.31	171.943		
1,250.00	1,250.00	1,277.70	1,277.70	4.29	4.38	89.85	3.62	1,429.68	1,429.69	1,421.02	8.67	164.884		
1,300.00	1,300.00	1,327.70	1,327.70	4.46	4.56	89.85	3.62	1,429.68	1,429.69	1,420.66	9.03	158.378		
1,350.00	1,350.00	1,377.70	1,377.70	4.64	4.74	89.85	3.62	1,429.68	1,429.69	1,420.30	9.38	152.364		
1,400.00	1,400.00	1,427.70	1,427.70	4.82	4.92	89.85	3.62	1,429.68	1,429.69	1,419.95	9.74	146.787		
1,450.00	1,450.00	1,477.70	1,477.70	5.00	5.10	89.85	3.62	1,429.68	1,429.69	1,419.59	10.10	141.602		
1,500.00	1,500.00	1,527.70	1,527.70	5.18	5.28	89.85	3.62	1,429.68	1,429.69	1,419.23	10.45	136.769		
1,550.00	1,550.00	1,577.70	1,577.70	5.36	5.45	89.85	3.62	1,429.68	1,429.69	1,418.88	10.81	132.254		
1,600.00	1,600.00	1,627.70	1,627.70	5.53	5.63	89.85	3.62	1,429.68	1,429.69	1,418.52	11.17	128.026		
1,650.00	1,650.00	1,677.70	1,677.70	5.71	5.81	89.85	3.62	1,429.68	1,429.69	1,418.16	11.52	124.059		
1,700.00	1,700.00	1,727.70	1,727.70	5.89	5.99	89.85	3.62	1,429.68	1,429.69	1,417.81	11.88	120.330		
1,750.00	1,750.00	1,777.70	1,777.70	6.07	6.17	89.85	3.62	1,429.68	1,429.69	1,417.45	12.24	116.818		
1,800.00	1,800.00	1,827.70	1,827.70	6.25	6.35	89.85	3.62	1,429.68	1,429.69	1,417.09	12.60	113.504		
1,850.00	1,850.00	1,877.70	1,877.70	6.43	6.53	89.85	3.62	1,429.68	1,429.69	1,416.73	12.95	110.372		
1,900.00	1,900.00	1,927.70	1,927.70	6.61	6.70	89.85	3.62	1,429.68	1,429.69	1,416.38	13.31	107.409		
1,950.00	1,950.00	1,977.70	1,977.70	6.78	6.88	89.85	3.62	1,429.68	1,429.69	1,416.02	13.67	104.599		
2,000.00	2,000.00	2,027.70	2,027.70	6.96	7.06	89.85	3.62	1,429.68	1,429.69	1,415.66	14.03	101.933		
2,050.00	2,050.00	2,077.70	2,077.70	7.14	7.24	89.85	3.62	1,429.68	1,429.69	1,415.30	14.38	99.399		
2,100.00	2,100.00	2,127.70	2,127.70	7.32	7.42	89.85	3.62	1,429.68	1,429.69	1,414.95	14.74	96.987		
2,150.00	2,150.00	2,177.70	2,177.70	7.50	7.60	89.85	3.62	1,429.68	1,429.69	1,414.59	15.10	94.690		
2,200.00	2,200.00	2,227.70	2,227.70	7.68	7.78	89.85	3.62	1,429.68	1,429.69	1,414.23	15.46	92.498		
2,250.00	2,250.00	2,277.70	2,277.70	7.86	7.96	89.85	3.62	1,429.68	1,429.69	1,413.87	15.81	90.406		
2,300.00	2,300.00	2,327.70	2,327.70	8.04	8.14	89.85	3.62	1,429.68	1,429.69	1,413.52	16.17	88.406		
2,350.00	2,350.00	2,377.70	2,377.70	8.22	8.31	89.85	3.62	1,429.68	1,429.69	1,413.16	16.53	86.492		
2,400.00	2,400.00	2,427.70	2,427.70	8.39	8.49	89.85	3.62	1,429.68	1,429.69	1,412.80	16.89	84.660		
2,450.00	2,450.00	2,477.70	2,477.70	8.57	8.67	89.85	3.62	1,429.68	1,429.69	1,412.44	17.25	82.903		
2,500.00	2,500.00	2,527.70	2,527.70	8.75	8.85	89.85	3.62	1,429.68	1,429.69	1,412.08	17.60	81.217		
2,550.00	2,550.00	2,577.70	2,577.70	8.93	9.03	-9.08	3.62	1,429.68	1,429.42	1,411.46	17.96	79.607		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Belloq 11-2 Fed State com 512H - Wellbore #1 - Permit Plan 1													Offset Site Error:	0.00 ft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.50 ft
Reference	Offset		Semi Major Axis		Distance		Minimum		Separation		Warning			
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor		
2,600.00	2,599.99	2,627.69	2,627.69	9.10	9.21	-9.08	3.62	1,429.68	1,428.61	1,410.30	18.31	78.030		
2,650.00	2,649.97	2,677.67	2,677.67	9.27	9.39	-9.09	3.62	1,429.68	1,427.26	1,408.61	18.66	76.502		
2,700.00	2,699.94	2,727.64	2,727.64	9.44	9.57	-9.11	3.62	1,429.68	1,425.38	1,406.38	19.00	75.002		
2,750.00	2,749.88	2,777.58	2,777.58	9.61	9.75	-9.13	3.62	1,429.68	1,422.96	1,403.60	19.35	73.527		
2,800.00	2,799.79	2,827.49	2,827.49	9.78	9.92	-9.15	3.62	1,429.68	1,420.00	1,400.30	19.70	72.076		
2,850.00	2,849.66	2,877.36	2,877.36	9.95	10.10	-9.18	3.62	1,429.68	1,416.50	1,396.45	20.05	70.648		
2,900.00	2,899.49	2,927.19	2,927.19	10.12	10.28	-9.22	3.62	1,429.68	1,412.47	1,392.07	20.40	69.243		
2,950.00	2,949.28	2,976.98	2,976.98	10.30	10.46	-9.26	3.62	1,429.68	1,407.90	1,387.15	20.75	67.858		
3,000.00	2,999.01	3,026.71	3,026.71	10.47	10.64	-9.30	3.62	1,429.68	1,402.79	1,381.69	21.10	66.495		
3,050.00	3,048.68	3,076.38	3,076.38	10.65	10.82	-9.35	3.62	1,429.68	1,397.15	1,375.71	21.45	65.150		
3,100.00	3,098.29	3,125.99	3,125.99	10.82	10.99	-9.41	3.62	1,429.68	1,390.98	1,369.18	21.79	63.825		
3,150.00	3,147.82	3,175.52	3,175.52	11.00	11.17	-9.47	3.62	1,429.68	1,384.27	1,362.13	22.14	62.517		
3,200.00	3,197.28	3,224.98	3,224.98	11.18	11.35	-9.53	3.62	1,429.68	1,377.03	1,354.54	22.49	61.227		
3,250.00	3,246.66	3,274.36	3,274.36	11.36	11.52	-9.60	3.62	1,429.68	1,369.27	1,346.43	22.84	59.953		
3,300.00	3,295.94	3,323.64	3,323.64	11.54	11.70	-9.68	3.62	1,429.68	1,360.97	1,337.78	23.19	58.695		
3,350.00	3,345.14	3,372.84	3,372.84	11.72	11.88	-9.76	3.62	1,429.68	1,352.14	1,328.61	23.54	57.451		
3,400.00	3,394.25	3,421.95	3,421.95	11.91	12.05	-9.84	3.62	1,429.68	1,342.88	1,319.00	23.88	56.226		
3,450.00	3,443.35	3,471.05	3,471.05	12.09	12.23	-9.91	3.62	1,429.68	1,333.59	1,309.36	24.23	55.035		
3,500.00	3,492.45	3,516.49	3,516.49	12.28	12.39	-9.97	3.61	1,429.71	1,324.32	1,299.76	24.57	53.911		
3,550.00	3,541.56	3,556.74	3,556.74	12.47	12.53	-10.03	3.55	1,429.95	1,315.33	1,290.46	24.88	52.870		
3,600.00	3,590.66	3,597.09	3,597.08	12.66	12.67	-10.08	3.41	1,430.48	1,306.68	1,281.49	25.19	51.869		
3,650.00	3,639.76	3,637.54	3,637.52	12.85	12.81	-10.13	3.19	1,431.28	1,298.36	1,272.86	25.50	50.911		
3,700.00	3,688.86	3,678.08	3,678.05	13.04	12.94	-10.18	2.90	1,432.36	1,290.37	1,264.56	25.81	49.992		
3,750.00	3,737.97	3,718.72	3,718.66	13.24	13.08	-10.22	2.54	1,433.71	1,282.73	1,256.61	26.12	49.105		
3,800.00	3,787.07	3,759.44	3,759.35	13.43	13.22	-10.26	2.09	1,435.35	1,275.42	1,248.99	26.43	48.253		
3,850.00	3,836.17	3,800.00	3,799.86	13.63	13.35	-10.30	1.58	1,437.27	1,268.45	1,241.71	26.74	47.434		
3,900.00	3,885.27	3,841.13	3,840.93	13.82	13.49	-10.33	0.98	1,439.49	1,261.82	1,234.76	27.05	46.643		
3,950.00	3,934.38	3,882.09	3,881.81	14.02	13.63	-10.36	0.31	1,441.98	1,255.53	1,228.16	27.36	45.883		
4,000.00	3,983.48	3,923.13	3,922.75	14.22	13.77	-10.39	-0.44	1,444.76	1,249.58	1,221.90	27.67	45.154		
4,050.00	4,032.58	3,964.23	3,963.72	14.42	13.91	-10.41	-1.26	1,447.83	1,243.97	1,215.99	27.98	44.453		
4,100.00	4,081.69	4,005.40	4,004.74	14.62	14.06	-10.43	-2.17	1,451.19	1,238.71	1,210.41	28.29	43.780		
4,150.00	4,130.79	4,046.62	4,045.80	14.82	14.20	-10.45	-3.15	1,454.84	1,233.78	1,205.18	28.60	43.133		
4,200.00	4,179.89	4,106.16	4,092.79	15.02	14.40	-10.46	-4.34	1,459.27	1,229.12	1,200.14	28.98	42.407		
4,250.00	4,228.99	4,143.63	4,142.34	15.22	14.53	-10.48	-5.60	1,463.96	1,224.47	1,195.18	29.29	41.802		
4,300.00	4,278.10	4,206.59	4,191.88	15.42	14.75	-10.49	-6.86	1,468.64	1,219.83	1,190.14	29.69	41.088		
4,350.00	4,327.20	4,243.19	4,241.43	15.63	14.88	-10.51	-8.12	1,473.32	1,215.18	1,185.19	29.99	40.513		
4,400.00	4,376.30	4,307.03	4,290.98	15.83	15.10	-10.52	-9.38	1,478.01	1,210.54	1,180.14	30.39	39.827		
4,450.00	4,425.40	4,342.76	4,340.52	16.04	15.23	-10.54	-10.64	1,482.69	1,205.89	1,175.19	30.70	39.281		
4,500.00	4,474.51	4,407.46	4,390.07	16.24	15.45	-10.55	-11.90	1,487.37	1,201.24	1,170.14	31.10	38.621		
4,550.00	4,523.61	4,442.32	4,439.61	16.45	15.58	-10.57	-13.15	1,492.06	1,196.60	1,165.19	31.41	38.101		
4,600.00	4,572.71	4,507.89	4,489.16	16.65	15.81	-10.59	-14.41	1,496.74	1,191.95	1,160.14	31.81	37.465		
4,650.00	4,621.81	4,541.89	4,538.70	16.86	15.93	-10.60	-15.67	1,501.42	1,187.30	1,155.19	32.12	36.970		
4,700.00	4,670.92	4,608.33	4,588.25	17.06	16.16	-10.62	-16.93	1,506.10	1,182.66	1,150.13	32.53	36.358		
4,750.00	4,720.02	4,641.45	4,637.80	17.27	16.28	-10.64	-18.19	1,510.79	1,178.01	1,145.19	32.83	35.887		
4,800.00	4,769.12	4,708.76	4,687.34	17.48	16.52	-10.65	-19.45	1,515.47	1,173.37	1,140.12	33.24	35.297		
4,850.00	4,818.23	4,741.02	4,736.89	17.69	16.63	-10.67	-20.71	1,520.15	1,168.72	1,135.18	33.54	34.847		
4,900.00	4,867.33	4,809.20	4,786.43	17.90	16.87	-10.69	-21.97	1,524.84	1,164.08	1,130.12	33.96	34.278		
4,950.00	4,916.43	4,840.58	4,835.98	18.10	16.99	-10.70	-23.23	1,529.52	1,159.43	1,125.18	34.25	33.849		
5,000.00	4,965.53	4,909.63	4,885.53	18.31	17.23	-10.72	-24.49	1,534.20	1,154.79	1,120.11	34.68	33.300		
5,050.00	5,014.64	4,940.15	4,935.07	18.52	17.34	-10.74	-25.75	1,538.89	1,150.14	1,115.17	34.97	32.890		
5,100.00	5,063.74	4,989.93	4,984.62	18.73	17.52	-10.76	-27.01	1,543.57	1,145.50	1,110.17	35.33	32.425		
5,150.00	5,112.84	5,039.71	5,034.16	18.94	17.70	-10.77	-28.27	1,548.25	1,140.85	1,105.16	35.69	31.969		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Belloq 11-2 Fed State com 512H - Wellbore #1 - Permit Plan 1													Offset Site Error:	0.00 ft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.50 ft
Reference		Offset		Semi Major Axis			Distance			Minimum Separation		Separation Factor	Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)			
5,200.00	5,161.94	5,089.50	5,083.71	19.16	17.88	-10.79	-29.53	1,552.94	1,136.21	1,100.16	36.05	31.522		
5,250.00	5,211.05	5,139.28	5,133.25	19.37	18.06	-10.81	-30.79	1,557.62	1,131.56	1,095.16	36.41	31.083		
5,300.00	5,260.15	5,189.06	5,182.80	19.58	18.24	-10.83	-32.05	1,562.30	1,126.92	1,090.15	36.76	30.652		
5,350.00	5,309.25	5,238.84	5,232.35	19.79	18.41	-10.85	-33.31	1,566.99	1,122.27	1,085.15	37.13	30.229		
5,400.00	5,358.35	5,288.63	5,281.89	20.00	18.59	-10.87	-34.57	1,571.67	1,117.63	1,080.14	37.49	29.815		
5,450.00	5,407.46	5,338.41	5,331.44	20.21	18.77	-10.88	-35.83	1,576.35	1,112.98	1,075.14	37.85	29.408		
5,500.00	5,456.56	5,388.19	5,380.98	20.43	18.95	-10.90	-37.09	1,581.04	1,108.34	1,070.13	38.21	29.008		
5,550.00	5,505.66	5,437.97	5,430.53	20.64	19.13	-10.92	-38.34	1,585.72	1,103.70	1,065.13	38.57	28.616		
5,600.00	5,554.77	5,487.76	5,480.07	20.85	19.32	-10.94	-39.60	1,590.40	1,099.05	1,060.12	38.93	28.231		
5,650.00	5,603.87	5,537.54	5,529.62	21.07	19.50	-10.96	-40.86	1,595.08	1,094.41	1,055.12	39.29	27.853		
5,700.00	5,652.97	5,587.32	5,579.17	21.28	19.68	-10.98	-42.12	1,599.77	1,089.76	1,050.11	39.66	27.481		
5,750.00	5,702.07	5,637.10	5,628.71	21.49	19.86	-11.00	-43.38	1,604.45	1,085.12	1,045.10	40.02	27.116		
5,800.00	5,751.18	5,686.89	5,678.26	21.71	20.04	-11.02	-44.64	1,609.13	1,080.48	1,040.10	40.38	26.757		
5,850.00	5,800.28	5,736.67	5,727.80	21.92	20.22	-11.04	-45.90	1,613.82	1,075.83	1,035.09	40.74	26.405		
5,900.00	5,849.38	5,786.45	5,777.35	22.14	20.40	-11.06	-47.16	1,618.50	1,071.19	1,030.08	41.11	26.059		
5,950.00	5,898.48	5,836.23	5,826.89	22.35	20.58	-11.08	-48.42	1,623.18	1,066.55	1,025.08	41.47	25.718		
6,000.00	5,947.59	5,886.02	5,876.44	22.57	20.77	-11.10	-49.68	1,627.87	1,061.91	1,020.07	41.83	25.384		
6,050.00	5,996.69	5,935.80	5,925.99	22.78	20.95	-11.12	-50.94	1,632.55	1,057.26	1,015.06	42.20	25.055		
6,100.00	6,045.79	5,985.58	5,975.53	23.00	21.13	-11.14	-52.20	1,637.23	1,052.62	1,010.06	42.56	24.731		
6,150.00	6,094.90	6,035.36	6,025.08	23.21	21.31	-11.16	-53.46	1,641.92	1,047.98	1,005.05	42.93	24.413		
6,200.00	6,144.00	6,085.15	6,074.62	23.43	21.50	-11.18	-54.72	1,646.60	1,043.34	1,000.04	43.29	24.100		
6,250.00	6,193.10	6,134.93	6,124.17	23.64	21.68	-11.20	-55.98	1,651.28	1,038.69	995.04	43.66	23.792		
6,300.00	6,242.20	6,184.71	6,173.71	23.86	21.86	-11.23	-57.24	1,655.97	1,034.05	990.03	44.02	23.490		
6,350.00	6,291.31	6,234.49	6,223.26	24.08	22.04	-11.25	-58.50	1,660.65	1,029.41	985.02	44.39	23.192		
6,400.00	6,340.41	6,284.28	6,272.81	24.29	22.23	-11.27	-59.76	1,665.33	1,024.77	980.02	44.75	22.899		
6,450.00	6,389.51	6,334.06	6,322.35	24.51	22.41	-11.29	-61.02	1,670.02	1,020.13	975.01	45.12	22.610		
6,500.00	6,438.61	6,383.84	6,371.90	24.73	22.59	-11.31	-62.28	1,674.70	1,015.48	970.00	45.48	22.326		
6,550.00	6,487.72	6,433.62	6,421.44	24.94	22.78	-11.34	-63.53	1,679.38	1,010.84	964.99	45.85	22.047		
6,600.00	6,536.82	6,483.41	6,470.99	25.16	22.96	-11.36	-64.79	1,684.06	1,006.20	959.99	46.22	21.772		
6,650.00	6,585.92	6,533.19	6,520.54	25.38	23.15	-11.38	-66.05	1,688.75	1,001.56	954.98	46.58	21.501		
6,700.00	6,635.02	6,582.97	6,570.08	25.59	23.33	-11.41	-67.31	1,693.43	996.92	949.97	46.95	21.234		
6,750.00	6,684.13	6,632.75	6,619.63	25.81	23.51	-11.43	-68.57	1,698.11	992.28	944.96	47.32	20.971		
6,800.00	6,733.23	6,682.54	6,669.17	26.03	23.70	-11.45	-69.83	1,702.80	987.64	939.96	47.68	20.713		
6,850.00	6,782.33	6,732.32	6,718.72	26.25	23.88	-11.48	-71.09	1,707.48	983.00	934.95	48.05	20.458		
6,900.00	6,831.44	6,782.10	6,768.26	26.47	24.07	-11.50	-72.35	1,712.16	978.36	929.94	48.42	20.207		
6,950.00	6,880.54	6,831.88	6,817.81	26.68	24.25	-11.53	-73.61	1,716.85	973.72	924.93	48.78	19.960		
7,000.00	6,929.64	6,881.67	6,867.36	26.90	24.44	-11.55	-74.87	1,721.53	969.08	919.93	49.15	19.716		
7,050.00	6,978.74	6,931.45	6,916.90	27.12	24.62	-11.58	-76.13	1,726.21	964.44	914.92	49.52	19.476		
7,100.00	7,027.85	6,981.23	6,966.45	27.34	24.80	-11.60	-77.39	1,730.90	959.80	909.91	49.89	19.239		
7,150.00	7,076.95	7,031.01	7,015.99	27.56	24.99	-11.63	-78.65	1,735.58	955.16	904.91	50.26	19.006		
7,200.00	7,126.05	7,080.80	7,065.54	27.77	25.17	-11.65	-79.91	1,740.26	950.52	899.90	50.62	18.776		
7,250.00	7,175.15	7,130.58	7,115.08	27.99	25.36	-11.68	-81.17	1,744.95	945.88	894.89	50.99	18.549		
7,300.00	7,224.26	7,180.36	7,164.63	28.21	25.54	-11.70	-82.43	1,749.63	941.24	889.88	51.36	18.326		
7,350.00	7,273.36	7,230.14	7,214.18	28.43	25.73	-11.73	-83.69	1,754.31	936.61	884.88	51.73	18.106		
7,400.00	7,322.46	7,279.93	7,263.72	28.65	25.91	-11.76	-84.95	1,759.00	931.97	879.87	52.10	17.889		
7,450.00	7,371.57	7,329.71	7,313.27	28.87	26.10	-11.78	-86.21	1,763.68	927.33	874.86	52.47	17.674		
7,500.00	7,420.67	7,379.49	7,362.81	29.09	26.29	-11.81	-87.47	1,768.36	922.69	869.86	52.84	17.463		
7,550.00	7,469.77	7,429.27	7,412.36	29.31	26.47	-11.84	-88.72	1,773.04	918.05	864.85	53.21	17.255		
7,600.00	7,518.87	7,479.06	7,461.90	29.53	26.66	-11.86	-89.98	1,777.73	913.42	859.84	53.57	17.049		
7,650.00	7,567.98	7,528.84	7,511.45	29.75	26.84	-11.89	-91.24	1,782.41	908.78	854.84	53.94	16.847		
7,700.00	7,617.08	7,588.28	7,570.63	29.97	27.06	-11.93	-92.69	1,787.77	903.97	849.61	54.35	16.632		
7,750.00	7,666.18	7,652.34	7,634.50	30.19	27.30	-11.99	-93.98	1,792.59	898.40	843.63	54.77	16.404		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Belloq 11-2 Fed State com 512H - Wellbore #1 - Permit Plan 1													Offset Site Error:	0.00 ft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.50 ft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor		
7,800.00	7,715.28	7,716.14	7,698.18	30.41	27.53	-12.08	-94.99	1,798.38	892.05	836.88	55.17	16.169		
7,850.00	7,764.39	7,779.66	7,761.63	30.63	27.76	-12.18	-95.73	1,799.09	884.91	829.35	55.56	15.927		
7,900.00	7,813.49	7,842.85	7,824.79	30.84	27.98	-12.31	-96.19	1,800.79	877.00	821.06	55.94	15.678		
7,950.00	7,862.59	7,905.68	7,887.62	31.06	28.20	-12.47	-96.37	1,801.49	868.31	812.01	56.30	15.422		
8,000.00	7,911.69	7,957.45	7,939.39	31.28	28.38	-12.61	-96.38	1,801.51	859.12	802.45	56.66	15.161		
8,050.00	7,960.80	8,006.56	7,988.50	31.51	28.55	-12.75	-96.38	1,801.51	849.91	792.88	57.03	14.903		
8,100.00	8,009.90	8,055.66	8,037.60	31.73	28.72	-12.89	-96.38	1,801.51	840.70	783.31	57.39	14.648		
8,150.00	8,059.00	8,104.76	8,086.70	31.95	28.89	-13.04	-96.38	1,801.51	831.51	773.75	57.76	14.397		
8,200.00	8,108.11	8,153.86	8,135.81	32.17	29.06	-13.18	-96.38	1,801.51	822.31	764.19	58.12	14.148		
8,250.00	8,157.21	8,202.97	8,184.91	32.39	29.23	-13.34	-96.38	1,801.51	813.13	754.64	58.49	13.903		
8,300.00	8,206.31	8,252.07	8,234.01	32.61	29.40	-13.49	-96.38	1,801.51	803.94	745.09	58.85	13.661		
8,350.00	8,255.41	8,299.26	8,281.20	32.83	29.56	-13.67	-96.06	1,801.51	794.79	735.57	59.22	13.421		
8,400.00	8,304.52	8,343.52	8,325.33	33.05	29.71	-14.05	-92.87	1,801.49	785.90	726.30	59.60	13.187		
8,450.00	8,353.62	8,386.82	8,368.15	33.27	29.86	-14.67	-86.47	1,801.44	777.38	717.40	59.98	12.961		
8,500.00	8,402.72	8,428.73	8,409.01	33.49	29.99	-15.51	-77.21	1,801.38	769.35	708.98	60.37	12.744		
8,550.00	8,451.82	8,468.88	8,447.43	33.71	30.12	-16.54	-65.56	1,801.31	761.99	701.23	60.76	12.541		
8,600.00	8,500.93	8,507.03	8,483.08	33.93	30.24	-17.71	-52.03	1,801.22	755.48	694.34	61.14	12.356		
8,650.00	8,550.03	8,542.99	8,515.81	34.15	30.34	-18.98	-37.12	1,801.12	750.04	688.53	61.51	12.194		
8,700.00	8,599.13	8,576.71	8,545.57	34.37	30.43	-20.32	-21.31	1,801.02	745.88	684.04	61.84	12.061		
8,750.00	8,648.24	8,608.16	8,572.46	34.59	30.51	-21.69	-5.00	1,800.91	743.23	681.10	62.13	11.963		
8,800.00	8,697.34	8,637.40	8,596.63	34.81	30.58	-23.06	11.46	1,800.80	742.29	679.94	62.35	11.805		
8,800.72	8,698.05	8,637.80	8,596.96	34.82	30.58	-23.08	11.70	1,800.80	742.29	679.94	62.35	11.905 CC, ES		
8,850.00	8,746.44	8,664.52	8,618.26	35.04	30.64	-24.41	27.81	1,800.69	743.24	680.75	62.49	11.894 SF		
8,900.00	8,795.54	8,689.63	8,637.58	35.26	30.70	-25.72	43.85	1,800.59	746.22	683.69	62.53	11.834		
8,950.00	8,844.65	8,712.85	8,654.81	35.48	30.74	-26.97	59.42	1,800.49	751.36	688.90	62.46	12.030		
9,000.00	8,893.75	8,734.34	8,670.17	35.70	30.78	-28.17	74.44	1,800.39	758.74	696.47	62.27	12.184		
9,050.00	8,942.85	8,750.00	8,681.01	35.92	30.81	-29.06	85.74	1,800.31	768.43	706.53	61.90	12.414		
9,100.00	8,991.95	8,772.61	8,696.10	36.14	30.85	-30.37	102.58	1,800.20	780.38	718.81	61.57	12.675		
9,150.00	9,041.06	8,789.66	8,707.04	36.36	30.87	-31.37	115.66	1,800.12	794.63	733.57	61.06	13.014		
9,200.00	9,090.16	8,800.00	8,713.48	36.58	30.89	-31.98	123.75	1,800.06	811.14	750.80	60.34	13.443		
9,250.00	9,139.26	8,820.15	8,725.60	36.81	30.92	-33.19	139.84	1,799.96	829.75	769.97	59.78	13.879		
9,300.00	9,188.36	8,833.80	8,733.49	37.03	30.94	-34.01	150.98	1,799.88	850.47	791.42	59.05	14.404		
9,350.00	9,237.47	8,850.00	8,742.51	37.25	30.96	-34.99	164.43	1,799.79	873.17	814.82	58.35	14.964		
9,400.00	9,286.57	8,850.00	8,742.51	37.47	30.96	-34.99	164.43	1,799.79	897.79	840.55	57.24	15.684		
9,450.00	9,335.67	8,869.45	8,752.83	37.69	30.98	-36.17	180.92	1,799.69	924.00	867.38	56.62	16.318		
9,500.00	9,384.78	8,879.82	8,758.09	37.91	30.99	-36.79	189.85	1,799.63	951.93	896.13	55.79	17.062		
9,550.00	9,433.88	8,900.00	8,767.89	38.14	31.02	-38.01	207.50	1,799.51	981.50	926.28	55.22	17.774		
9,600.00	9,482.98	8,900.00	8,767.89	38.36	31.02	-38.01	207.50	1,799.51	1,012.22	958.04	54.18	18.682		
9,650.00	9,532.08	8,900.00	8,767.89	38.58	31.02	-38.01	207.50	1,799.51	1,044.42	991.24	53.18	19.639		
9,700.00	9,581.19	8,915.25	8,774.87	38.80	31.04	-38.93	221.06	1,799.42	1,077.71	1,025.11	52.59	20.491		
9,750.00	9,630.29	8,922.85	8,778.21	39.02	31.06	-39.38	227.87	1,799.38	1,112.16	1,060.29	51.86	21.445		
9,800.00	9,679.39	8,930.01	8,781.28	39.25	31.08	-39.81	234.35	1,799.34	1,147.62	1,096.46	51.16	22.431		
9,850.00	9,728.49	8,950.00	8,789.41	39.47	31.13	-41.00	252.61	1,799.22	1,184.23	1,133.43	50.81	23.309		
9,900.00	9,777.60	8,950.00	8,789.41	39.69	31.13	-34.63	252.61	1,799.22	1,221.27	1,171.24	50.03	24.413		
9,950.00	9,826.66	8,950.00	8,789.41	39.91	31.13	-14.25	252.61	1,799.22	1,257.97	1,208.73	49.24	25.548		
10,000.00	9,875.36	8,950.00	8,789.41	40.11	31.13	-0.21	252.61	1,799.22	1,293.75	1,245.31	48.44	26.709		
10,050.00	9,923.32	8,967.21	8,795.90	40.31	31.18	7.12	268.54	1,799.11	1,328.06	1,280.07	47.99	27.673		
10,100.00	9,970.18	8,976.74	8,799.29	40.49	31.21	11.18	277.46	1,799.05	1,360.95	1,313.58	47.37	28.731		
10,150.00	10,015.58	9,000.00	8,806.93	40.66	31.28	12.93	299.42	1,798.91	1,392.34	1,345.33	47.01	29.618		
10,200.00	10,059.18	9,000.00	8,806.93	40.81	31.28	14.24	299.42	1,798.91	1,421.46	1,375.26	46.20	30.766		
10,250.00	10,100.65	9,000.00	8,806.93	40.95	31.28	14.89	299.42	1,798.91	1,448.83	1,403.41	45.42	31.896		
10,300.00	10,139.66	9,020.57	8,812.93	41.08	31.34	14.85	319.09	1,798.78	1,473.66	1,428.83	45.03	32.733		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Belloq 11-2 Fed State com 512H - Wellbore #1 - Permit Plan 1													Offset Site Error:	0.00 ft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.50 ft
Reference		Offset		Semi Major Axis		Distance							Warning	
Measured Depth	Vertical Depth	Measured Depth	Vertical Depth	Reference	Offset	Highside Toolface	Offset Wellbore Centre		Between Centres	Between Ellipses	Minimum Separation	Separation Factor		
(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(°)	+N/-S	+E/-W	(ft)	(ft)	(ft)			
10,350.00	10,175.92	9,032.63	8,816.13	41.19	31.38	14.81	330.72	1,798.70	1,496.68	1,452.18	44.50	33.630		

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Belloq 11-2 Fed State Com 522H - Wellbore #1 - Permit Plan 1													Offset Site Error:	0.00 ft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.50 ft
Reference		Offset		Semi Major Axis			Distance							Warning
Measured Depth Depth (ft)	Vertical Depth (ft)	Measured Depth Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor		
0.00	0.00	27.80	27.80	0.50	0.50	89.86	3.46	1,369.72	1,369.73					
50.00	50.00	77.80	77.80	0.50	0.51	89.86	3.46	1,369.72	1,369.73	1,368.71	1.01	1,352.383		
100.00	100.00	127.80	127.80	0.52	0.55	89.86	3.46	1,369.72	1,369.73	1,368.66	1.07	1,280.313		
150.00	150.00	177.80	177.80	0.59	0.65	89.86	3.46	1,369.72	1,369.73	1,368.49	1.24	1,105.549		
200.00	200.00	227.80	227.80	0.70	0.78	89.86	3.46	1,369.72	1,369.73	1,368.25	1.48	927.106		
250.00	250.00	277.80	277.80	0.84	0.92	89.86	3.46	1,369.72	1,369.73	1,367.97	1.76	779.445		
300.00	300.00	327.80	327.80	0.99	1.07	89.86	3.46	1,369.72	1,369.73	1,367.67	2.06	664.339		
350.00	350.00	377.80	377.80	1.15	1.24	89.86	3.46	1,369.72	1,369.73	1,367.35	2.38	575.176		
400.00	400.00	427.80	427.80	1.31	1.40	89.86	3.46	1,369.72	1,369.73	1,367.02	2.71	505.286		
450.00	450.00	477.80	477.80	1.48	1.57	89.86	3.46	1,369.72	1,369.73	1,366.68	3.05	449.566		
500.00	500.00	527.80	527.80	1.65	1.74	89.86	3.46	1,369.72	1,369.73	1,366.34	3.39	404.361		
550.00	550.00	577.80	577.80	1.82	1.91	89.86	3.46	1,369.72	1,369.73	1,366.00	3.73	367.086		
600.00	600.00	627.80	627.80	1.99	2.09	89.86	3.46	1,369.72	1,369.73	1,365.65	4.08	335.897		
650.00	650.00	677.80	677.80	2.16	2.26	89.86	3.46	1,369.72	1,369.73	1,365.30	4.43	309.459		
700.00	700.00	727.80	727.80	2.34	2.44	89.86	3.46	1,369.72	1,369.73	1,364.95	4.78	286.789		
750.00	750.00	777.80	777.80	2.51	2.61	89.86	3.46	1,369.72	1,369.73	1,364.60	5.13	267.152		
800.00	800.00	827.80	827.80	2.69	2.79	89.86	3.46	1,369.72	1,369.73	1,364.25	5.48	249.988		
850.00	850.00	877.80	877.80	2.87	2.97	89.86	3.46	1,369.72	1,369.73	1,363.90	5.83	234.865		
900.00	900.00	927.80	927.80	3.04	3.14	89.86	3.46	1,369.72	1,369.73	1,363.54	6.19	221.444		
950.00	950.00	977.80	977.80	3.22	3.32	89.86	3.46	1,369.72	1,369.73	1,363.19	6.54	209.456		
1,000.00	1,000.00	1,027.80	1,027.80	3.40	3.50	89.86	3.46	1,369.72	1,369.73	1,362.83	6.89	198.686		
1,050.00	1,050.00	1,077.80	1,077.80	3.58	3.67	89.86	3.46	1,369.72	1,369.73	1,362.48	7.25	188.959		
1,100.00	1,100.00	1,127.80	1,127.80	3.75	3.85	89.86	3.46	1,369.72	1,369.73	1,362.12	7.60	180.133		
1,150.00	1,150.00	1,177.80	1,177.80	3.93	4.03	89.86	3.46	1,369.72	1,369.73	1,361.77	7.96	172.087		
1,200.00	1,200.00	1,227.80	1,227.80	4.11	4.21	89.86	3.46	1,369.72	1,369.73	1,361.41	8.32	164.725		
1,250.00	1,250.00	1,277.80	1,277.80	4.29	4.39	89.86	3.46	1,369.72	1,369.73	1,361.06	8.67	157.963		
1,300.00	1,300.00	1,327.80	1,327.80	4.46	4.56	89.86	3.46	1,369.72	1,369.73	1,360.70	9.03	151.730		
1,350.00	1,350.00	1,377.80	1,377.80	4.64	4.74	89.86	3.46	1,369.72	1,369.73	1,360.34	9.38	145.968		
1,400.00	1,400.00	1,427.80	1,427.80	4.82	4.92	89.86	3.46	1,369.72	1,369.73	1,359.99	9.74	140.626		
1,450.00	1,450.00	1,477.80	1,477.80	5.00	5.10	89.86	3.46	1,369.72	1,369.73	1,359.63	10.10	135.658		
1,500.00	1,500.00	1,527.80	1,527.80	5.18	5.28	89.86	3.46	1,369.72	1,369.73	1,359.27	10.45	131.029		
1,550.00	1,550.00	1,577.80	1,577.80	5.36	5.45	89.86	3.46	1,369.72	1,369.73	1,358.92	10.81	126.703		
1,600.00	1,600.00	1,627.80	1,627.80	5.53	5.63	89.86	3.46	1,369.72	1,369.73	1,358.56	11.17	122.653		
1,650.00	1,650.00	1,677.80	1,677.80	5.71	5.81	89.86	3.46	1,369.72	1,369.73	1,358.20	11.52	118.852		
1,700.00	1,700.00	1,727.80	1,727.80	5.89	5.99	89.86	3.46	1,369.72	1,369.73	1,357.85	11.88	115.280		
1,750.00	1,750.00	1,777.80	1,777.80	6.07	6.17	89.86	3.46	1,369.72	1,369.73	1,357.49	12.24	111.915		
1,800.00	1,800.00	1,827.80	1,827.80	6.25	6.35	89.86	3.46	1,369.72	1,369.73	1,357.13	12.60	108.740		
1,850.00	1,850.00	1,877.80	1,877.80	6.43	6.53	89.86	3.46	1,369.72	1,369.73	1,356.77	12.95	105.740		
1,900.00	1,900.00	1,927.80	1,927.80	6.61	6.71	89.86	3.46	1,369.72	1,369.73	1,356.42	13.31	102.901		
1,950.00	1,950.00	1,977.80	1,977.80	6.78	6.88	89.86	3.46	1,369.72	1,369.73	1,356.06	13.67	100.210		
2,000.00	2,000.00	2,027.80	2,027.80	6.96	7.06	89.86	3.46	1,369.72	1,369.73	1,355.70	14.03	97.655		
2,050.00	2,050.00	2,077.80	2,077.80	7.14	7.24	89.86	3.46	1,369.72	1,369.73	1,355.34	14.38	95.228		
2,100.00	2,100.00	2,127.80	2,127.80	7.32	7.42	89.86	3.46	1,369.72	1,369.73	1,354.99	14.74	92.917		
2,150.00	2,150.00	2,177.80	2,177.80	7.50	7.60	89.86	3.46	1,369.72	1,369.73	1,354.63	15.10	90.716		
2,200.00	2,200.00	2,227.80	2,227.80	7.68	7.78	89.86	3.46	1,369.72	1,369.73	1,354.27	15.46	88.617		
2,250.00	2,250.00	2,277.80	2,277.80	7.86	7.96	89.86	3.46	1,369.72	1,369.73	1,353.91	15.81	86.612		
2,300.00	2,300.00	2,327.80	2,327.80	8.04	8.14	89.86	3.46	1,369.72	1,369.73	1,353.55	16.17	84.696		
2,350.00	2,350.00	2,377.80	2,377.80	8.22	8.31	89.86	3.46	1,369.72	1,369.73	1,353.20	16.53	82.863		
2,400.00	2,400.00	2,427.80	2,427.80	8.39	8.49	89.86	3.46	1,369.72	1,369.73	1,352.84	16.89	81.107		
2,450.00	2,450.00	2,477.80	2,477.80	8.57	8.67	89.86	3.46	1,369.72	1,369.73	1,352.48	17.25	79.424		
2,500.00	2,500.00	2,527.80	2,527.80	8.75	8.85	89.86	3.46	1,369.72	1,369.73	1,352.12	17.60	77.810		
2,550.00	2,550.00	2,577.80	2,577.80	8.93	9.03	-9.07	3.46	1,369.72	1,369.46	1,351.50	17.96	76.267		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company: WCDSC Permian NM
 Project: Eddy County (NAD 83 NM Eastern)
 Reference Site: Sec 11-T23S-R31E
 Site Error: 0.00 ft
 Reference Well: Belloq 11 Fed 222H
 Well Error: 0.50 ft
 Reference Wellbore: Wellbore #1
 Reference Design: Permit Plan 1

Local Co-ordinate Reference: Well Belloq 11 Fed 222H
 TVD Reference: RKB @ 3453.80ft
 MD Reference: RKB @ 3453.80ft
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at 2.00 sigma
 Database: EDM r5000.141_Prod US
 Offset TVD Reference: Offset Datum

Offset Design Sec 11-T23S-R31E - Belloq 11-2 Fed State Com 522H - Wellbore #1 - Permit Plan 1													Offset Site Error: 0.00 ft
Survey Program: 0-MWD+HDGM													Offset Well Error: 0.50 ft
Reference		Offset		Semi Major Axis			Distance						Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	
2,600.00	2,599.99	2,627.79	2,627.79	9.10	9.21	-9.08	3.46	1,369.72	1,368.65	1,350.34	18.31	74.753	
2,650.00	2,649.97	2,677.77	2,677.77	9.27	9.39	-9.09	3.46	1,369.72	1,367.30	1,348.65	18.66	73.287	
2,700.00	2,699.94	2,735.24	2,735.24	9.44	9.59	-9.11	3.41	1,369.63	1,365.34	1,346.32	19.03	71.759	
2,750.00	2,749.88	2,798.63	2,798.63	9.61	9.81	-9.12	3.08	1,368.97	1,362.40	1,342.99	19.41	70.179	
2,800.00	2,799.79	2,861.89	2,861.87	9.78	10.02	-9.13	2.43	1,367.68	1,358.43	1,338.64	19.79	68.641	
2,850.00	2,849.66	2,924.98	2,924.92	9.95	10.23	-9.13	1.46	1,365.78	1,353.43	1,333.26	20.17	67.116	
2,900.00	2,899.49	2,979.05	2,978.95	10.12	10.41	-9.13	0.43	1,363.75	1,347.51	1,327.00	20.51	65.687	
2,950.00	2,949.28	3,028.63	3,028.48	10.30	10.58	-9.13	-0.53	1,361.85	1,341.03	1,320.18	20.85	64.317	
3,000.00	2,999.01	3,078.14	3,077.94	10.47	10.75	-9.14	-1.49	1,359.95	1,334.02	1,312.84	21.19	62.965	
3,050.00	3,048.68	3,127.57	3,127.32	10.65	10.91	-9.15	-2.45	1,358.06	1,326.48	1,304.96	21.52	61.629	
3,100.00	3,098.29	3,176.91	3,176.62	10.82	11.08	-9.17	-3.41	1,356.17	1,318.41	1,296.55	21.86	60.310	
3,150.00	3,147.82	3,226.16	3,225.83	11.00	11.25	-9.19	-4.36	1,354.29	1,309.80	1,287.60	22.20	59.006	
3,200.00	3,197.28	3,275.32	3,274.94	11.18	11.41	-9.22	-5.32	1,352.41	1,300.66	1,278.13	22.53	57.718	
3,250.00	3,246.66	3,324.38	3,323.95	11.36	11.58	-9.25	-6.27	1,350.53	1,291.00	1,268.13	22.87	56.445	
3,300.00	3,295.94	3,373.32	3,372.86	11.54	11.75	-9.29	-7.22	1,348.65	1,280.81	1,257.60	23.21	55.185	
3,350.00	3,345.14	3,422.16	3,421.65	11.72	11.92	-9.33	-8.16	1,346.78	1,270.09	1,246.54	23.55	53.939	
3,400.00	3,394.25	3,470.90	3,470.34	11.91	12.08	-9.37	-9.11	1,344.92	1,258.94	1,235.06	23.88	52.710	
3,450.00	3,443.35	3,519.63	3,519.02	12.09	12.25	-9.39	-10.06	1,343.05	1,247.76	1,223.54	24.22	51.514	
3,500.00	3,492.45	3,568.36	3,567.71	12.28	12.42	-9.42	-11.00	1,341.19	1,236.57	1,212.01	24.56	50.350	
3,550.00	3,541.56	3,617.09	3,616.39	12.47	12.59	-9.45	-11.95	1,339.32	1,225.38	1,200.49	24.90	49.216	
3,600.00	3,590.66	3,665.82	3,665.08	12.66	12.76	-9.48	-12.89	1,337.46	1,214.20	1,188.96	25.24	48.111	
3,650.00	3,639.76	3,714.54	3,713.76	12.85	12.92	-9.50	-13.84	1,335.59	1,203.01	1,177.43	25.58	47.034	
3,700.00	3,688.86	3,763.27	3,762.45	13.04	13.09	-9.53	-14.78	1,333.73	1,191.83	1,165.91	25.92	45.984	
3,750.00	3,737.97	3,812.00	3,811.13	13.24	13.26	-9.56	-15.73	1,331.86	1,180.64	1,154.38	26.26	44.960	
3,800.00	3,787.07	3,860.73	3,859.81	13.43	13.43	-9.59	-16.67	1,329.99	1,169.46	1,142.85	26.60	43.961	
3,850.00	3,836.17	3,909.46	3,908.50	13.63	13.60	-9.62	-17.62	1,328.13	1,158.27	1,131.33	26.94	42.987	
3,900.00	3,885.27	3,958.19	3,957.18	13.82	13.77	-9.65	-18.56	1,326.26	1,147.09	1,119.80	27.29	42.037	
3,950.00	3,934.38	4,006.92	4,005.87	14.02	13.94	-9.69	-19.51	1,324.40	1,135.90	1,108.27	27.63	41.108	
4,000.00	3,983.48	4,055.65	4,054.55	14.22	14.11	-9.72	-20.45	1,322.53	1,124.72	1,096.74	27.98	40.203	
4,050.00	4,032.58	4,104.38	4,103.24	14.42	14.28	-9.75	-21.40	1,320.67	1,113.53	1,085.21	28.32	39.318	
4,100.00	4,081.69	4,153.11	4,151.92	14.62	14.45	-9.78	-22.34	1,318.80	1,102.35	1,073.69	28.67	38.454	
4,150.00	4,130.79	4,201.84	4,200.60	14.82	14.62	-9.82	-23.29	1,316.94	1,091.17	1,062.16	29.01	37.610	
4,200.00	4,179.89	4,250.57	4,249.29	15.02	14.79	-9.85	-24.24	1,315.07	1,079.99	1,050.63	29.36	36.786	
4,250.00	4,228.99	4,300.71	4,297.97	15.22	14.97	-9.89	-25.18	1,313.21	1,068.80	1,039.09	29.71	35.974	
4,300.00	4,278.10	4,348.02	4,346.66	15.42	15.13	-9.93	-26.13	1,311.34	1,057.62	1,027.57	30.05	35.192	
4,350.00	4,327.20	4,403.25	4,395.34	15.63	15.33	-9.96	-27.07	1,309.47	1,046.44	1,016.02	30.42	34.396	
4,400.00	4,376.30	4,445.48	4,444.03	15.83	15.48	-10.00	-28.02	1,307.61	1,035.26	1,004.51	30.75	33.668	
4,450.00	4,425.40	4,505.79	4,492.71	16.04	15.69	-10.04	-28.96	1,305.74	1,024.08	992.94	31.14	32.888	
4,500.00	4,474.51	4,542.94	4,541.39	16.24	15.82	-10.08	-29.91	1,303.88	1,012.90	981.45	31.45	32.210	
4,550.00	4,523.61	4,608.33	4,590.08	16.45	16.05	-10.12	-30.85	1,302.01	1,001.72	969.87	31.85	31.447	
4,600.00	4,572.71	4,640.40	4,638.76	16.65	16.16	-10.16	-31.80	1,300.15	990.54	958.40	32.15	30.814	
4,650.00	4,621.81	4,689.13	4,687.45	16.86	16.33	-10.21	-32.74	1,298.28	979.36	946.87	32.50	30.138	
4,700.00	4,670.92	4,737.86	4,736.13	17.06	16.51	-10.25	-33.69	1,296.42	968.19	935.34	32.85	29.476	
4,750.00	4,720.02	4,786.59	4,784.82	17.27	16.68	-10.29	-34.63	1,294.55	957.01	923.81	33.20	28.828	
4,800.00	4,769.12	4,835.32	4,833.50	17.48	16.85	-10.34	-35.58	1,292.69	945.83	912.28	33.55	28.193	
4,850.00	4,818.23	4,884.05	4,882.18	17.69	17.02	-10.39	-36.52	1,290.82	934.66	900.76	33.90	27.571	
4,900.00	4,867.33	4,932.77	4,930.87	17.90	17.19	-10.43	-37.47	1,288.95	923.48	889.23	34.25	26.961	
4,950.00	4,916.43	4,981.50	4,979.55	18.10	17.37	-10.48	-38.42	1,287.09	912.31	877.70	34.60	26.364	
5,000.00	4,965.53	5,030.23	5,028.24	18.31	17.54	-10.53	-39.36	1,285.22	901.13	866.18	34.96	25.779	
5,050.00	5,014.64	5,078.96	5,076.92	18.52	17.71	-10.58	-40.31	1,283.36	889.96	854.65	35.31	25.204	
5,100.00	5,063.74	5,127.69	5,125.61	18.73	17.89	-10.64	-41.25	1,281.49	878.79	843.12	35.66	24.642	
5,150.00	5,112.84	5,176.42	5,174.29	18.94	18.06	-10.69	-42.20	1,279.63	867.61	831.60	36.02	24.090	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Belloq 11-2 Fed State Com 522H - Wellbore #1 - Permit Plan 1													Offset Site Error:	0.00 ft
Survey Program: O-MWD+HDGM													Offset Well Error:	0.50 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)						
5,200.00	5,161.94	5,225.15	5,222.97	19.16	18.23	-10.75	-43.14	1,277.76	856.44	820.07	36.37	23.548		
5,250.00	5,211.05	5,273.88	5,271.66	19.37	18.40	-10.80	-44.09	1,275.90	845.27	808.55	36.72	23.017		
5,300.00	5,260.15	5,322.61	5,320.34	19.58	18.58	-10.86	-45.03	1,274.03	834.10	797.02	37.08	22.496		
5,350.00	5,309.25	5,371.34	5,369.03	19.79	18.75	-10.92	-45.98	1,272.17	822.93	785.50	37.43	21.985		
5,400.00	5,358.35	5,420.07	5,417.71	20.00	18.92	-10.99	-46.92	1,270.30	811.77	773.98	37.79	21.483		
5,450.00	5,407.46	5,468.80	5,466.40	20.21	19.10	-11.05	-47.87	1,268.43	800.60	762.46	38.14	20.990		
5,500.00	5,456.56	5,517.53	5,515.08	20.43	19.27	-11.11	-48.81	1,266.57	789.43	750.94	38.50	20.506		
5,550.00	5,505.66	5,566.25	5,563.76	20.64	19.44	-11.18	-49.76	1,264.70	778.27	739.41	38.85	20.031		
5,600.00	5,554.77	5,614.98	5,612.45	20.85	19.62	-11.25	-50.70	1,262.84	767.10	727.90	39.21	19.565		
5,650.00	5,603.87	5,663.71	5,661.13	21.07	19.79	-11.32	-51.65	1,260.97	755.94	716.38	39.56	19.107		
5,700.00	5,652.97	5,712.44	5,709.82	21.28	19.96	-11.40	-52.60	1,259.11	744.78	704.86	39.92	18.657		
5,750.00	5,702.07	5,761.17	5,758.50	21.49	20.14	-11.47	-53.54	1,257.24	733.62	693.34	40.28	18.214		
5,800.00	5,751.18	5,809.90	5,807.19	21.71	20.31	-11.55	-54.49	1,255.38	722.46	681.83	40.63	17.780		
5,850.00	5,800.28	5,858.63	5,855.87	21.92	20.49	-11.63	-55.43	1,253.51	711.30	670.31	40.99	17.353		
5,900.00	5,849.38	5,907.36	5,904.55	22.14	20.66	-11.71	-56.38	1,251.65	700.14	658.80	41.35	16.933		
5,950.00	5,898.48	5,956.09	5,953.24	22.35	20.83	-11.80	-57.32	1,249.78	688.99	647.28	41.71	16.521		
6,000.00	5,947.59	6,004.82	6,001.92	22.57	21.01	-11.89	-58.27	1,247.91	677.83	635.77	42.06	16.115		
6,050.00	5,996.69	6,053.55	6,050.61	22.78	21.18	-11.98	-59.21	1,246.05	666.68	624.26	42.42	15.716		
6,100.00	6,045.79	6,102.28	6,099.29	23.00	21.36	-12.07	-60.16	1,244.18	655.53	612.75	42.78	15.324		
6,150.00	6,094.90	6,151.00	6,147.98	23.21	21.53	-12.17	-61.10	1,242.32	644.38	601.25	43.14	14.938		
6,200.00	6,144.00	6,200.27	6,196.66	23.43	21.71	-12.27	-62.05	1,240.45	633.24	589.74	43.50	14.558		
6,250.00	6,193.10	6,248.46	6,245.35	23.64	21.88	-12.38	-62.99	1,238.59	622.09	578.24	43.85	14.185		
6,300.00	6,242.20	6,297.19	6,294.03	23.86	22.05	-12.49	-63.94	1,236.72	610.95	566.74	44.21	13.818		
6,350.00	6,291.31	6,345.92	6,342.71	24.08	22.23	-12.60	-64.88	1,234.86	599.81	555.23	44.57	13.457		
6,400.00	6,340.41	6,405.35	6,391.40	24.29	22.44	-12.72	-65.83	1,232.99	588.67	543.70	44.97	13.090		
6,450.00	6,389.51	6,443.38	6,440.08	24.51	22.58	-12.84	-66.78	1,231.13	577.53	532.24	45.29	12.751		
6,500.00	6,438.61	6,507.89	6,488.77	24.73	22.81	-12.96	-67.72	1,229.26	566.40	520.69	45.71	12.391		
6,550.00	6,487.72	6,540.84	6,537.45	24.94	22.93	-13.09	-68.67	1,227.39	555.27	509.26	46.01	12.068		
6,600.00	6,536.82	6,589.57	6,586.14	25.16	23.10	-13.23	-69.61	1,225.53	544.14	497.77	46.37	11.734		
6,650.00	6,585.92	6,638.30	6,634.82	25.38	23.28	-13.37	-70.56	1,223.66	533.02	486.28	46.74	11.405		
6,700.00	6,635.02	6,687.03	6,683.50	25.59	23.45	-13.52	-71.50	1,221.80	521.90	474.80	47.10	11.081		
6,750.00	6,684.13	6,735.76	6,732.19	25.81	23.63	-13.68	-72.45	1,219.93	510.78	463.32	47.46	10.763		
6,800.00	6,733.23	6,784.48	6,780.87	26.03	23.80	-13.84	-73.39	1,218.07	499.66	451.84	47.82	10.449		
6,850.00	6,782.33	6,833.21	6,829.56	26.25	23.98	-14.01	-74.34	1,216.20	488.55	440.37	48.18	10.140		
6,900.00	6,831.44	6,881.94	6,878.24	26.47	24.15	-14.19	-75.28	1,214.34	477.45	428.90	48.55	9.835		
6,950.00	6,880.54	6,930.67	6,926.93	26.68	24.33	-14.37	-76.23	1,212.47	466.35	417.44	48.91	9.535		
7,000.00	6,929.64	6,979.40	6,975.61	26.90	24.50	-14.57	-77.17	1,210.61	455.25	405.98	49.27	9.239		
7,050.00	6,978.74	7,028.13	7,024.29	27.12	24.68	-14.77	-78.12	1,208.74	444.16	394.52	49.64	8.948		
7,100.00	7,027.85	7,076.86	7,072.98	27.34	24.85	-14.98	-79.06	1,206.87	433.07	383.07	50.00	8.661		
7,150.00	7,076.95	7,125.59	7,121.66	27.56	25.03	-15.21	-80.01	1,205.01	421.99	371.63	50.37	8.378		
7,200.00	7,126.05	7,174.32	7,170.35	27.77	25.20	-15.45	-80.96	1,203.14	410.92	360.19	50.73	8.100		
7,250.00	7,175.15	7,223.05	7,219.03	27.99	25.38	-15.70	-81.90	1,201.28	399.85	348.76	51.10	7.825		
7,300.00	7,224.26	7,271.78	7,267.72	28.21	25.55	-15.97	-82.85	1,199.41	388.80	337.33	51.46	7.555		
7,350.00	7,273.36	7,320.51	7,316.40	28.43	25.73	-16.25	-83.79	1,197.55	377.75	325.91	51.83	7.288		
7,400.00	7,322.46	7,369.24	7,365.08	28.65	25.90	-16.54	-84.74	1,195.68	366.70	314.50	52.20	7.025		
7,450.00	7,371.57	7,417.96	7,413.77	28.87	26.08	-16.86	-85.68	1,193.82	355.67	303.10	52.57	6.766		
7,500.00	7,420.67	7,466.69	7,462.45	29.09	26.25	-17.20	-86.63	1,191.95	344.65	291.72	52.94	6.510		
7,550.00	7,469.77	7,515.42	7,511.14	29.31	26.43	-17.56	-87.57	1,190.09	333.65	280.34	53.31	6.259		
7,600.00	7,518.87	7,564.15	7,559.82	29.53	26.60	-17.94	-88.52	1,188.22	322.65	268.97	53.68	6.010		
7,650.00	7,567.98	7,612.88	7,608.51	29.75	26.78	-18.35	-89.46	1,186.35	311.67	257.62	54.06	5.766		
7,700.00	7,617.08	7,661.61	7,657.19	29.97	26.95	-18.79	-90.41	1,184.49	300.71	246.28	54.43	5.525		
7,750.00	7,666.18	7,710.34	7,705.87	30.19	27.13	-19.26	-91.35	1,182.62	289.77	234.96	54.81	5.287		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Belloq 11-2 Fed State Com 522H - Wellbore #1 - Permit Plan 1													Offset Site Error:	0.00 ft
Survey Program: O-MWD+HDGM													Offset Well Error:	0.50 ft
Reference		Offset		Semi Major Axis			Distance							
Measured Depth Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning	
7,800.00	7,715.28	7,759.07	7,754.56	30.41	27.30	-19.77	-92.30	1,180.76	278.84	223.66	55.19	5.053		
7,850.00	7,764.39	7,807.80	7,803.24	30.63	27.48	-20.33	-93.24	1,178.89	267.94	212.37	55.57	4.822	Alert	
7,900.00	7,813.49	7,856.53	7,851.93	30.84	27.65	-20.92	-94.19	1,177.03	257.06	201.11	55.95	4.595	Alert	
7,950.00	7,862.59	7,905.26	7,900.61	31.06	27.83	-21.57	-95.14	1,175.16	246.22	189.88	56.34	4.371	Alert	
8,000.00	7,911.69	7,953.24	7,948.55	31.28	28.00	-22.28	-96.06	1,173.34	235.42	178.69	56.73	4.150	Alert	
8,050.00	7,960.80	7,999.36	7,994.64	31.51	28.17	-23.04	-96.76	1,171.96	225.09	167.93	57.16	3.938	Alert	
8,100.00	8,009.90	8,045.68	8,040.95	31.73	28.33	-23.90	-97.21	1,171.07	215.38	157.80	57.58	3.741	Alert	
8,150.00	8,059.00	8,092.19	8,087.47	31.95	28.49	-24.88	-97.41	1,170.68	206.31	148.31	58.00	3.557	Alert	
8,200.00	8,108.11	8,140.63	8,135.91	32.17	28.66	-26.00	-97.41	1,170.66	197.75	139.33	58.42	3.385	Alert	
8,250.00	8,157.21	8,189.74	8,185.01	32.39	28.83	-27.25	-97.41	1,170.66	189.29	130.45	58.83	3.217	Alert	
8,300.00	8,206.31	8,238.84	8,234.11	32.61	29.00	-28.61	-97.41	1,170.66	180.92	121.66	59.26	3.053	Alert	
8,350.00	8,255.41	8,287.94	8,283.21	32.83	29.17	-30.11	-97.41	1,170.66	172.67	112.98	59.69	2.893	Alert	
8,400.00	8,304.52	8,337.04	8,332.32	33.05	29.34	-31.75	-97.41	1,170.66	164.54	104.40	60.14	2.736	Alert	
8,450.00	8,353.62	8,386.15	8,381.42	33.27	29.51	-33.55	-97.41	1,170.66	156.56	95.96	60.59	2.584	Alert	
8,500.00	8,402.72	8,435.25	8,430.52	33.49	29.68	-35.55	-97.41	1,170.66	148.74	87.68	61.07	2.436	Minor Risk	
8,550.00	8,451.82	8,484.35	8,479.62	33.71	29.85	-37.76	-97.41	1,170.66	141.13	79.58	61.55	2.293	Minor Risk	
8,600.00	8,500.93	8,530.08	8,525.34	33.93	30.01	-40.30	-96.72	1,170.66	134.14	72.06	62.09	2.161	Minor Risk	
8,650.00	8,550.03	8,573.47	8,568.56	34.15	30.15	-44.07	-92.93	1,170.63	129.47	66.84	62.63	2.067	Minor Risk	
8,696.22	8,595.42	8,612.69	8,607.27	34.36	30.29	-48.63	-86.71	1,170.59	127.92	64.88	63.04	2.029	Minor Risk, CC	
8,700.00	8,599.13	8,615.85	8,610.37	34.37	30.30	-49.04	-86.09	1,170.59	127.93	64.86	63.07	2.028	Minor Risk, ES, SF	
8,750.00	8,648.24	8,656.82	8,650.20	34.59	30.43	-54.78	-76.56	1,170.53	130.31	67.07	63.25	2.060	Minor Risk	
8,800.00	8,697.34	8,696.04	8,687.61	34.81	30.55	-60.74	-64.79	1,170.45	137.24	74.22	63.02	2.178	Minor Risk	
8,850.00	8,746.44	8,733.28	8,722.31	35.04	30.66	-66.40	-51.27	1,170.37	148.94	86.58	62.36	2.388	Minor Risk	
8,900.00	8,795.54	8,768.41	8,754.16	35.26	30.77	-71.44	-36.48	1,170.27	165.25	103.90	61.35	2.693	Alert	
8,950.00	8,844.65	8,800.00	8,781.99	35.48	30.85	-75.57	-21.54	1,170.17	185.72	125.77	59.96	3.098	Alert	
9,000.00	8,893.75	8,832.11	8,809.38	35.70	30.94	-79.30	-4.80	1,170.06	209.79	150.97	58.81	3.567	Alert	
9,050.00	8,942.85	8,860.73	8,832.98	35.92	31.01	-82.20	11.40	1,169.96	236.93	179.44	57.49	4.121	Alert	
9,100.00	8,991.95	8,887.30	8,854.13	36.14	31.07	-84.56	27.47	1,169.85	266.67	210.47	56.20	4.745	Alert	
9,150.00	9,041.06	8,911.94	8,873.06	36.36	31.13	-86.48	43.23	1,169.75	298.62	243.64	54.98	5.432		
9,200.00	9,090.16	8,934.76	8,889.98	36.58	31.18	-88.05	58.55	1,169.65	332.45	278.62	53.83	6.176		
9,250.00	9,139.26	8,950.00	8,900.93	36.81	31.22	-88.99	69.15	1,169.58	367.98	315.76	52.22	7.047		
9,300.00	9,188.36	8,975.46	8,918.59	37.03	31.27	-90.39	87.49	1,169.47	404.74	352.95	51.79	7.815		
9,350.00	9,237.47	9,000.00	8,934.81	37.25	31.34	-91.56	105.90	1,169.35	442.88	391.49	51.39	8.618		
9,400.00	9,286.57	9,010.43	8,941.47	37.47	31.36	-92.01	113.93	1,169.29	481.91	431.88	50.04	9.631		
9,450.00	9,335.67	9,026.06	8,951.16	37.69	31.40	-92.64	126.18	1,169.22	521.96	472.69	49.27	10.593		
9,500.00	9,384.78	9,050.00	8,965.36	37.91	31.47	-93.49	145.46	1,169.09	562.99	513.80	49.19	11.445		
9,550.00	9,433.88	9,050.00	8,965.36	38.14	31.47	-93.49	145.46	1,169.09	604.46	556.77	47.69	12.674		
9,600.00	9,482.98	9,066.71	8,974.79	38.36	31.52	-94.02	159.25	1,169.00	646.69	599.33	47.36	13.654		
9,650.00	9,532.08	9,078.48	8,981.19	38.58	31.55	-94.36	169.13	1,168.94	689.52	642.68	46.83	14.722		
9,700.00	9,581.19	9,100.00	8,992.35	38.80	31.61	-94.93	187.53	1,168.82	733.04	686.16	46.89	15.635		
9,750.00	9,630.29	9,100.00	8,992.35	39.02	31.61	-94.93	187.53	1,168.82	776.69	730.75	45.94	16.908		
9,800.00	9,679.39	9,100.00	8,992.35	39.25	31.61	-94.93	187.53	1,168.82	821.06	775.94	45.12	18.198		
9,850.00	9,728.49	9,118.52	9,001.40	39.47	31.66	-95.36	203.69	1,168.71	865.56	820.37	45.18	19.157		
9,900.00	9,777.60	9,127.12	9,005.42	39.69	31.69	-87.94	211.28	1,168.66	910.44	865.58	44.86	20.295		
9,950.00	9,826.66	9,136.32	9,009.60	39.91	31.71	-63.72	219.48	1,168.61	954.16	909.65	44.51	21.436		
10,000.00	9,875.36	9,150.00	9,015.57	40.11	31.75	-46.21	231.79	1,168.53	996.09	951.84	44.25	22.511		
10,050.00	9,923.32	9,150.00	9,015.57	40.31	31.75	-34.99	231.79	1,168.53	1,036.08	992.62	43.46	23.841		
10,100.00	9,970.18	9,168.76	9,023.27	40.49	31.81	-28.00	248.90	1,168.42	1,073.82	1,030.57	43.25	24.827		
10,150.00	10,015.58	9,180.89	9,027.95	40.66	31.84	-23.30	260.09	1,168.35	1,109.37	1,066.59	42.79	25.928		
10,200.00	10,059.18	9,200.00	9,034.84	40.81	31.90	-20.06	277.91	1,168.23	1,142.60	1,100.10	42.49	26.890		
10,250.00	10,100.65	9,200.00	9,034.84	40.95	31.90	-17.62	277.91	1,168.23	1,173.27	1,131.63	41.65	28.170		
10,300.00	10,139.66	9,220.22	9,041.48	41.08	31.96	-15.89	297.01	1,168.11	1,201.30	1,159.96	41.34	29.057		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Belloq 11-2 Fed State Com 522H - Wellbore #1 - Permit Plan 1													Offset Site Error:	0.00 ft
Survey Program: O-MWD+HDGM													Offset Well Error:	0.50 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (ft)	Separation Factor	Warning			
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)						
10,350.00	10,175.92	9,234.12	9,045.65	41.19	32.00	-14.54	310.26	1,168.02	1,226.70	1,185.83	40.87	30.016		
10,400.00	10,209.17	9,250.00	9,050.02	41.28	32.05	-13.50	325.53	1,167.92	1,249.35	1,208.90	40.44	30.890		
10,450.00	10,239.13	9,250.00	9,050.02	41.36	32.05	-12.64	325.53	1,167.92	1,269.37	1,229.65	39.72	31.958		
10,500.00	10,265.59	9,277.47	9,056.57	41.44	32.13	-12.05	352.21	1,167.75	1,286.09	1,246.53	39.56	32.510		
10,550.00	10,288.35	9,300.00	9,060.98	41.49	32.20	-11.57	374.30	1,167.61	1,300.16	1,260.84	39.31	33.071		
10,600.00	10,307.22	9,300.00	9,060.98	41.55	32.20	-11.17	374.30	1,167.61	1,311.17	1,272.41	38.75	33.836		
10,650.00	10,322.07	9,322.49	9,064.52	41.59	32.27	-10.91	396.51	1,167.46	1,319.10	1,280.53	38.58	34.194		
10,700.00	10,332.79	9,350.00	9,067.66	41.63	32.36	-10.75	423.83	1,167.29	1,324.27	1,285.78	38.49	34.406		
10,750.00	10,339.29	9,350.00	9,067.66	41.67	32.36	-10.62	423.83	1,167.29	1,326.02	1,287.85	38.16	34.746		
10,800.00	10,341.52	9,368.20	9,069.02	41.71	32.42	-10.60	441.98	1,167.17	1,324.88	1,286.79	38.09	34.782		
10,850.00	10,341.14	9,383.46	9,069.71	41.76	32.47	-10.62	457.23	1,167.07	1,322.41	1,284.35	38.07	34.738		
10,900.00	10,340.74	9,401.77	9,070.00	41.82	32.52	-10.63	475.53	1,166.95	1,321.24	1,283.12	38.12	34.657		
10,950.00	10,340.34	9,441.92	9,070.00	41.88	32.66	-10.66	515.68	1,166.69	1,320.93	1,282.63	38.30	34.490		
11,000.00	10,339.94	9,508.09	9,070.00	41.97	32.90	-10.69	565.67	1,166.37	1,320.66	1,282.13	38.54	34.268		
11,050.00	10,339.54	9,541.91	9,070.00	42.06	33.04	-10.72	615.67	1,166.04	1,320.39	1,281.66	38.74	34.087		
11,100.00	10,339.14	9,608.10	9,070.00	42.16	33.31	-10.75	665.66	1,165.72	1,320.13	1,281.11	39.01	33.837		
11,150.00	10,338.74	9,641.89	9,070.00	42.28	33.47	-10.79	715.65	1,165.40	1,319.86	1,280.62	39.24	33.639		
11,200.00	10,338.33	9,708.11	9,070.00	42.41	33.78	-10.82	765.64	1,165.07	1,319.59	1,280.04	39.55	33.364		
11,250.00	10,337.93	9,741.88	9,070.00	42.56	33.96	-10.85	815.64	1,164.75	1,319.32	1,279.52	39.80	33.150		
11,300.00	10,337.53	9,808.12	9,070.00	42.72	34.31	-10.88	865.63	1,164.42	1,319.05	1,278.91	40.15	32.855		
11,350.00	10,337.13	9,841.87	9,070.00	42.90	34.50	-10.91	915.62	1,164.10	1,318.79	1,278.37	40.42	32.628		
11,400.00	10,336.73	9,908.14	9,070.00	43.09	34.89	-10.95	965.62	1,163.78	1,318.52	1,277.72	40.80	32.315		
11,450.00	10,336.33	9,941.86	9,070.00	43.29	35.10	-10.98	1,015.61	1,163.45	1,318.25	1,277.16	41.10	32.077		
11,500.00	10,335.93	10,008.15	9,070.00	43.51	35.51	-11.01	1,065.60	1,163.13	1,317.99	1,276.48	41.51	31.750		
11,550.00	10,335.52	10,041.85	9,070.00	43.74	35.74	-11.04	1,115.59	1,162.81	1,317.72	1,275.90	41.83	31.504		
11,600.00	10,335.12	10,108.16	9,070.00	43.99	36.19	-11.07	1,165.59	1,162.48	1,317.46	1,275.18	42.27	31.165		
11,650.00	10,334.72	10,141.83	9,070.00	44.25	36.43	-11.11	1,215.58	1,162.16	1,317.19	1,274.58	42.61	30.913		
11,700.00	10,334.32	10,208.17	9,070.00	44.52	36.91	-11.14	1,265.57	1,161.83	1,316.93	1,273.84	43.09	30.566		
11,750.00	10,333.92	10,241.82	9,070.00	44.81	37.17	-11.17	1,315.57	1,161.51	1,316.67	1,273.23	43.44	30.309		
11,800.00	10,333.52	10,308.19	9,070.00	45.11	37.68	-11.20	1,365.56	1,161.19	1,316.40	1,272.46	43.94	29.957		
11,850.00	10,333.12	10,341.81	9,070.00	45.42	37.94	-11.23	1,415.55	1,160.86	1,316.14	1,271.82	44.32	29.698		
11,900.00	10,332.71	10,408.20	9,070.00	45.74	38.48	-11.27	1,465.54	1,160.54	1,315.88	1,271.03	44.85	29.342		
11,950.00	10,332.31	10,441.80	9,070.00	46.07	38.76	-11.30	1,515.54	1,160.21	1,315.62	1,270.38	45.24	29.082		
12,000.00	10,331.91	10,508.21	9,070.00	46.41	39.32	-11.33	1,565.53	1,159.89	1,315.35	1,269.56	45.79	28.725		
12,050.00	10,331.51	10,541.78	9,070.00	46.77	39.61	-11.36	1,615.52	1,159.57	1,315.09	1,268.89	46.20	28.465		
12,100.00	10,331.11	10,608.22	9,070.00	47.13	40.20	-11.40	1,665.51	1,159.24	1,314.83	1,268.06	46.78	28.109		
12,150.00	10,330.71	10,641.77	9,070.00	47.50	40.50	-11.43	1,715.51	1,158.92	1,314.57	1,267.37	47.20	27.851		
12,200.00	10,330.31	10,708.23	9,070.00	47.88	41.11	-11.46	1,765.50	1,158.59	1,314.31	1,266.51	47.80	27.497		
12,250.00	10,329.91	10,741.76	9,070.00	48.27	41.42	-11.49	1,815.49	1,158.27	1,314.05	1,265.82	48.24	27.242		
12,300.00	10,329.50	10,808.25	9,070.00	48.67	42.05	-11.52	1,865.49	1,157.95	1,313.79	1,264.94	48.86	26.891		
12,350.00	10,329.10	10,841.75	9,070.00	49.08	42.37	-11.56	1,915.48	1,157.62	1,313.53	1,264.23	49.31	26.639		
12,400.00	10,328.70	10,908.26	9,070.00	49.49	43.02	-11.59	1,965.47	1,157.30	1,313.28	1,263.33	49.95	26.294		
12,450.00	10,328.30	10,941.73	9,070.00	49.91	43.35	-11.62	2,015.46	1,156.98	1,313.02	1,262.61	50.41	26.046		
12,500.00	10,327.90	11,008.27	9,070.00	50.34	44.01	-11.65	2,065.46	1,156.65	1,312.76	1,261.69	51.07	25.706		
12,550.00	10,327.50	11,041.72	9,070.00	50.78	44.35	-11.69	2,115.45	1,156.33	1,312.50	1,260.96	51.55	25.463		
12,600.00	10,327.10	11,108.28	9,070.00	51.22	45.03	-11.72	2,165.44	1,156.00	1,312.25	1,260.03	52.22	25.130		
12,650.00	10,326.69	11,141.71	9,070.00	51.67	45.38	-11.75	2,215.44	1,155.68	1,311.99	1,259.28	52.71	24.892		
12,700.00	10,326.29	11,208.30	9,070.00	52.13	46.08	-11.78	2,265.43	1,155.36	1,311.74	1,258.34	53.40	24.565		
12,750.00	10,325.89	11,241.70	9,070.00	52.59	46.44	-11.81	2,315.42	1,155.03	1,311.48	1,257.58	53.90	24.333		
12,800.00	10,325.49	11,308.31	9,070.00	53.06	47.15	-11.85	2,365.41	1,154.71	1,311.23	1,256.62	54.60	24.014		
12,850.00	10,325.09	11,341.69	9,070.00	53.54	47.51	-11.88	2,415.41	1,154.38	1,310.97	1,255.86	55.11	23.787		
12,900.00	10,324.69	11,408.32	9,070.00	54.02	48.23	-11.91	2,465.40	1,154.06	1,310.72	1,254.89	55.83	23.476		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Offset Design Sec 11-T23S-R31E - Belloq 11-2 Fed State Com 522H - Wellbore #1 - Permit Plan 1													Offset Site Error:	0.00 ft
Survey Program: O-MWD+HDGM													Offset Well Error:	0.50 ft
Reference		Offset		Semi Major Axis			Distance							Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor		
12,950.00	10,324.29	11,441.67	9,070.00	54.51	48.60	-11.94	2,515.39	1,153.74	1,310.46	1,254.11	56.35	23.256		
13,000.00	10,323.88	11,508.33	9,070.00	55.00	49.34	-11.98	2,565.39	1,153.41	1,310.21	1,253.13	57.08	22.953		
13,050.00	10,323.48	11,541.66	9,070.00	55.50	49.71	-12.01	2,615.38	1,153.09	1,309.96	1,252.35	57.61	22.738		
13,100.00	10,323.08	11,608.35	9,070.00	56.00	50.46	-12.04	2,665.37	1,152.76	1,309.71	1,251.35	58.36	22.443		
13,150.00	10,322.68	11,641.65	9,070.00	56.51	50.84	-12.07	2,715.36	1,152.44	1,309.45	1,250.56	58.89	22.234		
13,200.00	10,322.28	11,708.36	9,070.00	57.02	51.61	-12.11	2,765.36	1,152.12	1,309.20	1,249.55	59.65	21.948		
13,250.00	10,321.88	11,741.64	9,070.00	57.54	51.99	-12.14	2,815.35	1,151.79	1,308.95	1,248.75	60.20	21.745		
13,300.00	10,321.48	11,808.37	9,070.00	58.06	52.76	-12.17	2,865.34	1,151.47	1,308.70	1,247.74	60.96	21.467		
13,350.00	10,321.07	11,841.62	9,070.00	58.59	53.15	-12.20	2,915.34	1,151.15	1,308.45	1,246.93	61.52	21.270		
13,400.00	10,320.67	11,908.38	9,070.00	59.12	53.93	-12.24	2,965.33	1,150.82	1,308.20	1,245.90	62.30	21.000		
13,450.00	10,320.27	11,941.61	9,070.00	59.65	54.33	-12.27	3,015.32	1,150.50	1,307.95	1,245.09	62.86	20.809		
13,500.00	10,319.87	12,008.39	9,070.00	60.19	55.12	-12.30	3,065.31	1,150.17	1,307.70	1,244.06	63.65	20.547		
13,550.00	10,319.47	12,041.60	9,070.00	60.74	55.52	-12.33	3,115.31	1,149.85	1,307.45	1,243.24	64.21	20.362		
13,600.00	10,319.07	12,108.41	9,070.00	61.28	56.32	-12.37	3,165.30	1,149.53	1,307.20	1,242.19	65.01	20.108		
13,650.00	10,318.67	12,141.59	9,070.00	61.83	56.72	-12.40	3,215.29	1,149.20	1,306.96	1,241.37	65.58	19.928		
13,700.00	10,318.26	12,208.42	9,070.00	62.39	57.53	-12.43	3,265.28	1,148.88	1,306.71	1,240.32	66.39	19.682		
13,750.00	10,317.86	12,241.58	9,070.00	62.95	57.93	-12.46	3,315.28	1,148.55	1,306.46	1,239.49	66.97	19.508		
13,800.00	10,317.46	12,308.43	9,070.00	63.51	58.75	-12.50	3,365.27	1,148.23	1,306.22	1,238.43	67.79	19.269		
13,850.00	10,317.06	12,341.56	9,070.00	64.07	59.16	-12.53	3,415.26	1,147.91	1,305.97	1,237.60	68.37	19.101		
13,900.00	10,316.66	12,408.44	9,070.00	64.64	59.98	-12.56	3,465.26	1,147.58	1,305.72	1,236.53	69.20	18.870		
13,950.00	10,316.26	12,441.55	9,070.00	65.21	60.39	-12.60	3,515.25	1,147.26	1,305.48	1,235.69	69.79	18.707		
14,000.00	10,315.86	12,508.46	9,070.00	65.78	61.22	-12.63	3,565.24	1,146.94	1,305.23	1,234.61	70.62	18.483		
14,050.00	10,315.45	12,541.54	9,070.00	66.36	61.63	-12.66	3,615.23	1,146.61	1,304.99	1,233.77	71.22	18.325		
14,100.00	10,315.05	12,608.47	9,070.00	66.94	62.47	-12.69	3,665.23	1,146.29	1,304.75	1,232.69	72.06	18.108		
14,150.00	10,314.65	12,641.53	9,070.00	67.53	62.89	-12.73	3,715.22	1,145.96	1,304.50	1,231.85	72.66	17.954		
14,200.00	10,314.25	12,708.48	9,070.00	68.11	63.73	-12.76	3,765.21	1,145.64	1,304.26	1,230.76	73.50	17.744		
14,250.00	10,313.85	12,741.51	9,070.00	68.70	64.15	-12.79	3,815.21	1,145.32	1,304.02	1,229.91	74.11	17.596		
14,300.00	10,313.45	12,808.49	9,070.00	69.29	65.00	-12.82	3,865.20	1,144.99	1,303.77	1,228.81	74.96	17.392		
14,350.00	10,313.05	12,841.50	9,070.00	69.88	65.42	-12.86	3,915.19	1,144.67	1,303.53	1,227.96	75.57	17.249		
14,400.00	10,312.64	12,908.51	9,070.00	70.48	66.28	-12.89	3,965.18	1,144.34	1,303.29	1,226.86	76.43	17.052		
14,450.00	10,312.24	12,941.49	9,070.00	71.08	66.70	-12.92	4,015.18	1,144.02	1,303.05	1,226.00	77.05	16.913		
14,500.00	10,311.84	13,008.52	9,070.00	71.68	67.56	-12.96	4,065.17	1,143.70	1,302.81	1,224.90	77.91	16.721		
14,550.00	10,311.44	13,041.48	9,070.00	72.28	67.98	-12.99	4,115.16	1,143.37	1,302.57	1,224.04	78.53	16.587		
14,600.00	10,311.04	13,108.53	9,070.00	72.89	68.85	-13.02	4,165.16	1,143.05	1,302.33	1,222.93	79.40	16.401		
14,650.00	10,310.64	13,141.46	9,070.00	73.50	69.28	-13.05	4,215.15	1,142.72	1,302.09	1,222.06	80.03	16.271		
14,700.00	10,310.24	13,208.54	9,070.00	74.11	70.15	-13.09	4,265.14	1,142.40	1,301.85	1,220.95	80.90	16.091		
14,750.00	10,309.83	13,241.45	9,070.00	74.72	70.58	-13.12	4,315.13	1,142.08	1,301.61	1,220.08	81.53	15.965		
14,800.00	10,309.43	13,308.55	9,070.00	75.33	71.45	-13.15	4,365.13	1,141.75	1,301.38	1,218.96	82.41	15.791		
14,850.00	10,309.03	13,341.44	9,070.00	75.95	71.88	-13.19	4,415.12	1,141.43	1,301.14	1,218.09	83.04	15.668		
14,900.00	10,308.63	13,408.57	9,070.00	76.56	72.76	-13.22	4,465.11	1,141.11	1,300.90	1,216.97	83.93	15.500		
14,950.00	10,308.23	13,441.43	9,070.00	77.18	73.19	-13.25	4,515.11	1,140.78	1,300.66	1,216.10	84.56	15.381		
15,000.00	10,307.83	13,508.58	9,070.00	77.81	74.07	-13.28	4,565.10	1,140.46	1,300.43	1,214.97	85.46	15.217		
15,050.00	10,307.43	13,541.42	9,070.00	78.43	74.51	-13.32	4,615.09	1,140.13	1,300.19	1,214.10	86.10	15.102		
15,100.00	10,307.02	13,608.59	9,070.00	79.05	75.39	-13.35	4,665.08	1,139.81	1,299.96	1,212.96	86.99	14.943		
15,150.00	10,306.62	13,641.40	9,070.00	79.68	75.83	-13.38	4,715.08	1,139.49	1,299.72	1,212.09	87.63	14.831		
15,200.00	10,306.22	13,708.60	9,070.00	80.31	76.72	-13.42	4,765.07	1,139.16	1,299.49	1,210.95	88.54	14.677		
15,250.00	10,305.82	13,741.39	9,070.00	80.94	77.15	-13.45	4,815.06	1,138.84	1,299.25	1,210.07	89.18	14.569		
15,300.00	10,305.42	13,808.62	9,070.00	81.57	78.05	-13.48	4,865.05	1,138.51	1,299.02	1,208.93	90.09	14.420		
15,316.32	10,305.29	13,807.70	9,070.00	81.78	78.04	-13.49	4,881.37	1,138.41	1,298.94	1,208.73	90.21	14.399		

Anticollision Report

Company: WCDSC Permian NM
 Project: Eddy County (NAD 83 NM Eastern)
 Reference Site: Sec 11-T23S-R31E
 Site Error: 0.00 ft
 Reference Well: Belloq 11 Fed 222H
 Well Error: 0.50 ft
 Reference Wellbore: Wellbore #1
 Reference Design: Permit Plan 1

Local Co-ordinate Reference: Well Belloq 11 Fed 222H
 TVD Reference: RKB @ 3453.80ft
 MD Reference: RKB @ 3453.80ft
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at 2.00 sigma
 Database: EDM r5000.141_Prod US
 Offset TVD Reference: Offset Datum

Offset Design Sec 11-T23S-R31E - Belloq 11-2 Fed State Com 523H - Wellbore #1 - Permit Plan 1													Offset Site Error:	0.00 ft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.50 ft
Reference		Offset		Semi Major Axis			Distance							
Measured Depth Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore +N/-S (ft)	Centre +E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning	
8,150.00	8,059.00	8,132.11	8,117.01	31.95	28.57	-11.44	-92.90	2,463.51	1,492.85	1,435.11	57.73	25.857		
8,200.00	8,108.11	8,174.85	8,159.75	32.17	28.72	-11.48	-93.55	2,463.28	1,483.30	1,425.21	58.08	25.537		
8,250.00	8,157.21	8,218.02	8,202.91	32.39	28.87	-11.53	-93.75	2,463.20	1,473.96	1,415.52	58.43	25.224		
8,300.00	8,206.31	8,267.12	8,252.01	32.61	29.04	-11.61	-93.75	2,463.20	1,464.71	1,405.92	58.79	24.913		
8,350.00	8,255.41	8,316.22	8,301.11	32.83	29.20	-11.68	-93.75	2,463.20	1,455.47	1,396.32	59.15	24.606		
8,400.00	8,304.52	8,365.32	8,350.22	33.05	29.37	-11.76	-93.75	2,463.20	1,446.23	1,386.72	59.51	24.302		
8,450.00	8,353.62	8,414.43	8,399.32	33.27	29.54	-11.84	-93.75	2,463.20	1,436.99	1,377.12	59.87	24.002		
8,500.00	8,402.72	8,463.53	8,448.42	33.49	29.71	-11.91	-93.75	2,463.20	1,427.76	1,367.53	60.23	23.705		
8,550.00	8,451.82	8,512.63	8,497.52	33.71	29.88	-11.99	-93.75	2,463.20	1,418.53	1,357.94	60.59	23.412		
8,600.00	8,500.93	8,560.48	8,545.37	33.93	30.04	-12.07	-93.64	2,463.20	1,409.30	1,348.36	60.95	23.124		
8,650.00	8,550.03	8,604.41	8,589.21	34.15	30.19	-12.25	-91.09	2,463.19	1,400.21	1,338.91	61.30	22.843		
8,700.00	8,599.13	8,647.49	8,631.90	34.37	30.33	-12.56	-85.33	2,463.15	1,391.33	1,329.69	61.64	22.571		
8,750.00	8,648.24	8,689.28	8,672.77	34.59	30.46	-13.00	-76.70	2,463.10	1,382.72	1,320.74	61.98	22.308		
8,800.00	8,697.34	8,729.41	8,711.35	34.81	30.58	-13.53	-65.63	2,463.03	1,374.47	1,312.15	62.32	22.055		
8,850.00	8,746.44	8,767.62	8,747.26	35.04	30.69	-14.15	-52.60	2,462.94	1,366.68	1,304.03	62.65	21.815		
8,900.00	8,795.54	8,803.73	8,780.33	35.26	30.79	-14.83	-38.11	2,462.85	1,359.45	1,296.48	62.97	21.589		
8,950.00	8,844.65	8,837.65	8,810.50	35.48	30.87	-15.55	-22.64	2,462.75	1,352.89	1,289.62	63.27	21.382		
9,000.00	8,893.75	8,869.34	8,837.82	35.70	30.95	-16.29	-6.59	2,462.65	1,347.13	1,283.57	63.56	21.195		
9,050.00	8,942.85	8,900.00	8,863.37	35.92	31.03	-17.07	10.36	2,462.54	1,342.28	1,278.45	63.83	21.029		
9,100.00	8,991.95	8,926.25	8,884.50	36.14	31.09	-17.78	25.93	2,462.44	1,338.44	1,274.38	64.06	20.894		
9,150.00	9,041.06	8,950.00	8,902.98	36.36	31.14	-18.46	40.84	2,462.35	1,335.72	1,271.46	64.25	20.788		
9,200.00	9,090.16	8,975.18	8,921.89	36.58	31.20	-19.21	57.47	2,462.24	1,334.19	1,269.76	64.43	20.709		
9,234.61	9,124.15	8,990.43	8,932.97	36.74	31.23	-19.68	67.95	2,462.18	1,333.88	1,269.36	64.52	20.675 CC, ES		
9,250.00	9,139.26	9,000.00	8,939.79	36.81	31.25	-19.98	74.67	2,462.14	1,333.94	1,269.37	64.57	20.659		
9,300.00	9,188.36	9,017.11	8,951.69	37.03	31.29	-20.53	86.96	2,462.06	1,335.03	1,270.40	64.63	20.658 SF		
9,350.00	9,237.47	9,035.78	8,964.24	37.25	31.33	-21.15	100.78	2,461.97	1,337.52	1,272.86	64.66	20.687		
9,400.00	9,286.57	9,050.00	8,973.50	37.47	31.36	-21.63	111.57	2,461.90	1,341.46	1,276.85	64.61	20.763		
9,450.00	9,335.67	9,069.15	8,985.54	37.69	31.40	-22.29	126.45	2,461.81	1,346.85	1,282.29	64.56	20.861		
9,500.00	9,384.78	9,084.06	8,994.57	37.91	31.43	-22.81	138.33	2,461.73	1,353.75	1,289.31	64.44	21.008		
9,550.00	9,433.88	9,100.00	9,003.87	38.14	31.46	-23.38	151.27	2,461.65	1,362.15	1,297.86	64.29	21.188		
9,600.00	9,482.98	9,110.86	9,010.00	38.36	31.49	-23.77	160.23	2,461.59	1,372.06	1,308.01	64.05	21.423		
9,650.00	9,532.08	9,122.91	9,018.80	38.58	31.51	-24.21	170.31	2,461.53	1,383.47	1,319.68	63.78	21.691		
9,700.00	9,581.19	9,134.18	9,022.58	38.80	31.54	-24.62	179.86	2,461.47	1,396.36	1,332.89	63.47	21.999		
9,750.00	9,630.29	9,150.00	9,030.66	39.02	31.57	-25.20	193.46	2,461.38	1,410.75	1,347.57	63.19	22.327		
9,800.00	9,679.39	9,150.00	9,030.66	39.25	31.57	-25.20	193.46	2,461.38	1,426.55	1,363.86	62.69	22.756		
9,850.00	9,728.49	9,163.85	9,037.42	39.47	31.60	-25.72	205.55	2,461.30	1,443.75	1,381.42	62.33	23.163		
9,900.00	9,777.60	9,172.62	9,041.55	39.69	31.62	-18.88	213.29	2,461.26	1,462.28	1,400.39	61.89	23.627		
9,950.00	9,826.66	9,181.99	9,045.83	39.91	31.64	3.60	221.62	2,461.20	1,481.16	1,419.74	61.42	24.116		
10,000.00	9,875.36	9,200.00	9,053.68	40.11	31.67	19.07	237.83	2,461.10	1,499.95	1,438.94	61.01	24.584		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to RKB @ 3453.80ft

Offset Depths are relative to Offset Datum


Central Meridian is -104.333334

Coordinates are relative to: Belloq 11 Fed 222H

Coordinate System is US State Plane 1983, New Mexico Eastern Zone

Grid Convergence at Surface is: 0.31°

Ladder Plot



LEGEND

Belloq 11-2 Fed State Com 522H, Wellbore #1, Permit Plan 1 V0
 Belloq 11-2 Fed State Com 512H, Wellbore #1, Permit Plan 1 V0
 Barclay 11 N Federal #014, Wellbore #1, Wellbore #1 V0

Anticollision Report

Company:	WCDSC Permian NM	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Project:	Eddy County (NAD 83 NM Eastern)	TVD Reference:	RKB @ 3453.80ft
Reference Site:	Sec 11-T23S-R31E	MD Reference:	RKB @ 3453.80ft
Site Error:	0.00 ft	North Reference:	Grid
Reference Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 ft	Output errors are at	2.00 sigma
Reference Wellbore	Wellbore #1	Database:	EDM r5000.141_Prod US
Reference Design:	Permit Plan 1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to RKB @ 3453.80ft

Offset Depths are relative to Offset Datum


Central Meridian is -104.333334

Coordinates are relative to: Belloq 11 Fed 222H

Coordinate System is US State Plane 1983, New Mexico Eastern Zone

Grid Convergence at Surface is: 0.31°

Separation Factor Plot



LEGEND

Belloq 11-2 Fed State Com 522H, Wellbore #1, Permit Plan 1 VO
 Barclay 11 M Federal #013 (Shut in), Wellbore #1, Wellbore #1 VO
 Barclay 11 N Federal #014, Wellbore #1, Wellbore #1 VO

WCDSC Permian NM

Eddy County (NAD 83 NM Eastern)

Sec 11-T23S-R31E

Belloq 11 Fed 222H

Wellbore #1

Plan: Permit Plan 1

Standard Planning Report - Geographic

31 July, 2018

Planning Report - Geographic

Database: EDM r5000.141_Prod US
 Company: WCDSC Permian NM
 Project: Eddy County (NAD 83 NM Eastern)
 Site: Sec 11-T23S-R31E
 Well: Belloq 11 Fed 222H
 Wellbore: Wellbore #1
 Design: Permit Plan 1

Local Co-ordinate Reference: Well Belloq 11 Fed 222H
 TVD Reference: RKB @ 3453.80ft
 MD Reference: RKB @ 3453.80ft
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Project	Eddy County (NAD 83 NM Eastern)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Sec 11-T23S-R31E			
Site Position:		Northing:	488,170.26 usft	Latitude: 32.340736
From:	Map	Easting:	719,281.88 usft	Longitude: -103.757161
Position Uncertainty:	0.00 ft	Slot Radius:	13-3/16 "	Grid Convergence: 0.31 °

Well	Belloq 11 Fed 222H			
Well Position	+N/-S	0.00 ft	Northing:	477,925.35 usft
	+E/-W	0.00 ft	Easting:	719,858.14 usft
Position Uncertainty	0.50 ft	Wellhead Elevation:	Ground Level: 3,428.80 ft	

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2015	7/31/2018	6.92	60.10	47,855.97161456

Design	Permit Plan 1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	16.45

Plan Survey Tool Program	Date 7/31/2018			
Depth From (ft)	Depth To (ft)	Survey (Wellbore)	Tool Name	Remarks
1	0.00	15,316.32 Permit Plan 1 (Wellbore #1)	MWD+HDGM OWSG MWD + HDGM	

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00	
3,369.69	10.87	98.93	3,364.49	-12.77	81.26	1.25	1.25	0.00	98.93	
9,885.18	10.87	98.93	9,763.04	-203.47	1,295.20	0.00	0.00	0.00	0.00	
10,805.73	90.46	0.40	10,341.50	373.00	1,410.00	10.00	8.65	-10.70	-98.29	
15,316.32	90.46	0.40	10,305.29	4,883.33	1,441.49	0.00	0.00	0.00	0.00	PBHL - Belloq 11 Fed

Planning Report - Geographic

Database:	EDM r5000.141_Prod US	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Company:	WCDSC Permian NM	TVD Reference:	RKB @ 3453.80ft
Project:	Eddy County (NAD 83 NM Eastern)	MD Reference:	RKB @ 3453.80ft
Site:	Sec 11-T23S-R31E	North Reference:	Grid
Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
100.00	0.00	0.00	100.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
200.00	0.00	0.00	200.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
300.00	0.00	0.00	300.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
400.00	0.00	0.00	400.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
500.00	0.00	0.00	500.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
600.00	0.00	0.00	600.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
700.00	0.00	0.00	700.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
800.00	0.00	0.00	800.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
900.00	0.00	0.00	900.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
1,000.00	0.00	0.00	1,000.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
1,100.00	0.00	0.00	1,100.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
1,200.00	0.00	0.00	1,200.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
1,300.00	0.00	0.00	1,300.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
1,400.00	0.00	0.00	1,400.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
1,500.00	0.00	0.00	1,500.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
1,600.00	0.00	0.00	1,600.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
1,700.00	0.00	0.00	1,700.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
1,800.00	0.00	0.00	1,800.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
1,900.00	0.00	0.00	1,900.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
2,000.00	0.00	0.00	2,000.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
2,100.00	0.00	0.00	2,100.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
2,200.00	0.00	0.00	2,200.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
2,300.00	0.00	0.00	2,300.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
2,400.00	0.00	0.00	2,400.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
2,500.00	0.00	0.00	2,500.00	0.00	0.00	477,925.35	719,858.14	32.312567	-103.755474
2,600.00	1.25	98.93	2,599.99	-0.17	1.08	477,925.18	719,859.21	32.312566	-103.755470
2,700.00	2.50	98.93	2,699.94	-0.68	4.31	477,924.67	719,862.45	32.312565	-103.755460
2,800.00	3.75	98.93	2,799.79	-1.52	9.70	477,923.83	719,867.83	32.312562	-103.755442
2,900.00	5.00	98.93	2,899.49	-2.71	17.23	477,922.64	719,875.37	32.312559	-103.755418
3,000.00	6.25	98.93	2,999.01	-4.23	26.91	477,921.12	719,885.05	32.312555	-103.755387
3,100.00	7.50	98.93	3,098.29	-6.09	38.74	477,919.27	719,896.87	32.312549	-103.755348
3,200.00	8.75	98.93	3,197.28	-8.28	52.70	477,917.07	719,910.84	32.312543	-103.755303
3,300.00	10.00	98.93	3,295.94	-10.81	68.79	477,914.54	719,926.93	32.312536	-103.755251
3,369.69	10.87	98.93	3,364.49	-12.77	81.26	477,912.58	719,939.40	32.312530	-103.755211
3,400.00	10.87	98.93	3,394.25	-13.65	86.91	477,911.70	719,945.05	32.312528	-103.755193
3,500.00	10.87	98.93	3,492.45	-16.58	105.54	477,908.77	719,963.68	32.312520	-103.755132
3,600.00	10.87	98.93	3,590.66	-19.51	124.17	477,905.84	719,982.31	32.312511	-103.755072
3,700.00	10.87	98.93	3,688.86	-22.43	142.80	477,902.92	720,000.94	32.312503	-103.755012
3,800.00	10.87	98.93	3,787.07	-25.36	161.44	477,899.99	720,019.57	32.312495	-103.754952
3,900.00	10.87	98.93	3,885.27	-28.29	180.07	477,897.06	720,038.20	32.312486	-103.754891
4,000.00	10.87	98.93	3,983.48	-31.21	198.70	477,894.14	720,056.83	32.312478	-103.754831
4,100.00	10.87	98.93	4,081.69	-34.14	217.33	477,891.21	720,075.47	32.312470	-103.754771
4,200.00	10.87	98.93	4,179.89	-37.07	235.96	477,888.28	720,094.10	32.312461	-103.754711
4,300.00	10.87	98.93	4,278.10	-39.99	254.59	477,885.36	720,112.73	32.312453	-103.754650
4,400.00	10.87	98.93	4,376.30	-42.92	273.23	477,882.43	720,131.36	32.312445	-103.754590
4,500.00	10.87	98.93	4,474.51	-45.85	291.86	477,879.50	720,149.99	32.312436	-103.754530
4,600.00	10.87	98.93	4,572.71	-48.78	310.49	477,876.58	720,168.62	32.312428	-103.754470
4,700.00	10.87	98.93	4,670.92	-51.70	329.12	477,873.65	720,187.26	32.312420	-103.754409
4,800.00	10.87	98.93	4,769.12	-54.63	347.75	477,870.72	720,205.89	32.312411	-103.754349
4,900.00	10.87	98.93	4,867.33	-57.56	366.38	477,867.79	720,224.52	32.312403	-103.754289
5,000.00	10.87	98.93	4,965.53	-60.48	385.02	477,864.87	720,243.15	32.312395	-103.754229
5,100.00	10.87	98.93	5,063.74	-63.41	403.65	477,861.94	720,261.78	32.312387	-103.754168
5,200.00	10.87	98.93	5,161.94	-66.34	422.28	477,859.01	720,280.41	32.312378	-103.754108
5,300.00	10.87	98.93	5,260.15	-69.26	440.91	477,856.09	720,299.05	32.312370	-103.754048

Planning Report - Geographic

Database:	EDM r5000.141_Prod US	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Company:	WCDCS Permian NM	TVD Reference:	RKB @ 3453.80ft
Project:	Eddy County (NAD 83 NM Eastern)	MD Reference:	RKB @ 3453.80ft
Site:	Sec 11-T23S-R31E	North Reference:	Grid
Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
5,400.00	10.87	98.93	5,358.35	-72.19	459.54	477,853.16	720,317.68	32.312362	-103.753987
5,500.00	10.87	98.93	5,456.56	-75.12	478.17	477,850.23	720,336.31	32.312353	-103.753927
5,600.00	10.87	98.93	5,554.77	-78.04	496.81	477,847.31	720,354.94	32.312345	-103.753867
5,700.00	10.87	98.93	5,652.97	-80.97	515.44	477,844.38	720,373.57	32.312337	-103.753807
5,800.00	10.87	98.93	5,751.18	-83.90	534.07	477,841.45	720,392.20	32.312328	-103.753746
5,900.00	10.87	98.93	5,849.38	-86.82	552.70	477,838.53	720,410.84	32.312320	-103.753686
6,000.00	10.87	98.93	5,947.59	-89.75	571.33	477,835.60	720,429.47	32.312312	-103.753626
6,100.00	10.87	98.93	6,045.79	-92.68	589.96	477,832.67	720,448.10	32.312303	-103.753566
6,200.00	10.87	98.93	6,144.00	-95.61	608.60	477,829.75	720,466.73	32.312295	-103.753505
6,300.00	10.87	98.93	6,242.20	-98.53	627.23	477,826.82	720,485.36	32.312287	-103.753445
6,400.00	10.87	98.93	6,340.41	-101.46	645.86	477,823.89	720,503.99	32.312278	-103.753385
6,500.00	10.87	98.93	6,438.61	-104.39	664.49	477,820.96	720,522.62	32.312270	-103.753325
6,600.00	10.87	98.93	6,536.82	-107.31	683.12	477,818.04	720,541.26	32.312262	-103.753264
6,700.00	10.87	98.93	6,635.02	-110.24	701.75	477,815.11	720,559.89	32.312253	-103.753204
6,800.00	10.87	98.93	6,733.23	-113.17	720.38	477,812.18	720,578.52	32.312245	-103.753144
6,900.00	10.87	98.93	6,831.44	-116.09	739.02	477,809.26	720,597.15	32.312237	-103.753084
7,000.00	10.87	98.93	6,929.64	-119.02	757.65	477,806.33	720,615.78	32.312228	-103.753023
7,100.00	10.87	98.93	7,027.85	-121.95	776.28	477,803.40	720,634.41	32.312220	-103.752963
7,200.00	10.87	98.93	7,126.05	-124.87	794.91	477,800.48	720,653.05	32.312212	-103.752903
7,300.00	10.87	98.93	7,224.26	-127.80	813.54	477,797.55	720,671.68	32.312203	-103.752843
7,400.00	10.87	98.93	7,322.46	-130.73	832.17	477,794.62	720,690.31	32.312195	-103.752782
7,500.00	10.87	98.93	7,420.67	-133.65	850.81	477,791.70	720,708.94	32.312187	-103.752722
7,600.00	10.87	98.93	7,518.87	-136.58	869.44	477,788.77	720,727.57	32.312178	-103.752662
7,700.00	10.87	98.93	7,617.08	-139.51	888.07	477,785.84	720,746.20	32.312170	-103.752602
7,800.00	10.87	98.93	7,715.28	-142.44	906.70	477,782.92	720,764.84	32.312162	-103.752541
7,900.00	10.87	98.93	7,813.49	-145.36	925.33	477,779.99	720,783.47	32.312153	-103.752481
8,000.00	10.87	98.93	7,911.69	-148.29	943.96	477,777.06	720,802.10	32.312145	-103.752421
8,100.00	10.87	98.93	8,009.90	-151.22	962.60	477,774.14	720,820.73	32.312137	-103.752361
8,200.00	10.87	98.93	8,108.11	-154.14	981.23	477,771.21	720,839.36	32.312129	-103.752300
8,300.00	10.87	98.93	8,206.31	-157.07	999.86	477,768.28	720,857.99	32.312120	-103.752240
8,400.00	10.87	98.93	8,304.52	-160.00	1,018.49	477,765.35	720,876.62	32.312112	-103.752180
8,500.00	10.87	98.93	8,402.72	-162.92	1,037.12	477,762.43	720,895.26	32.312104	-103.752120
8,600.00	10.87	98.93	8,500.93	-165.85	1,055.75	477,759.50	720,913.89	32.312095	-103.752059
8,700.00	10.87	98.93	8,599.13	-168.78	1,074.39	477,756.57	720,932.52	32.312087	-103.751999
8,800.00	10.87	98.93	8,697.34	-171.70	1,093.02	477,753.65	720,951.15	32.312079	-103.751939
8,900.00	10.87	98.93	8,795.54	-174.63	1,111.65	477,750.72	720,969.78	32.312070	-103.751879
9,000.00	10.87	98.93	8,893.75	-177.56	1,130.28	477,747.79	720,988.41	32.312062	-103.751818
9,100.00	10.87	98.93	8,991.95	-180.48	1,148.91	477,744.87	721,007.05	32.312054	-103.751758
9,200.00	10.87	98.93	9,090.16	-183.41	1,167.54	477,741.94	721,025.68	32.312045	-103.751698
9,300.00	10.87	98.93	9,188.36	-186.34	1,186.18	477,739.01	721,044.31	32.312037	-103.751638
9,400.00	10.87	98.93	9,286.57	-189.27	1,204.81	477,736.09	721,062.94	32.312029	-103.751577
9,500.00	10.87	98.93	9,384.78	-192.19	1,223.44	477,733.16	721,081.57	32.312020	-103.751517
9,600.00	10.87	98.93	9,482.98	-195.12	1,242.07	477,730.23	721,100.20	32.312012	-103.751457
9,700.00	10.87	98.93	9,581.19	-198.05	1,260.70	477,727.31	721,118.84	32.312004	-103.751397
9,800.00	10.87	98.93	9,679.39	-200.97	1,279.33	477,724.38	721,137.47	32.311995	-103.751336
9,885.14	10.87	98.93	9,763.00	-203.46	1,295.20	477,721.89	721,153.33	32.311988	-103.751285
KOP @ 9885' MD, 96' FSL, 1808' FWL									
9,885.18	10.87	98.93	9,763.04	-203.47	1,295.20	477,721.89	721,153.34	32.311988	-103.751285
9,900.00	10.76	91.05	9,777.60	-203.71	1,297.97	477,721.64	721,156.10	32.311988	-103.751276
9,973.66	12.95	56.16	9,849.78	-199.23	1,311.72	477,726.12	721,169.85	32.312000	-103.751231
First Take Point @ 9974' MD, 100' FSL, 1825' FEL									
10,000.00	14.58	47.42	9,875.36	-195.34	1,316.61	477,730.01	721,174.74	32.312010	-103.751216
10,100.00	22.51	27.77	9,970.18	-169.82	1,334.84	477,755.53	721,192.97	32.312080	-103.751156
10,200.00	31.60	18.47	10,059.18	-127.93	1,352.11	477,797.42	721,210.24	32.312195	-103.751099

Planning Report - Geographic

Database:	EDM r5000.141_Prod US	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Company:	WCDSC Permian NM	TVD Reference:	RKB @ 3453.80ft
Project:	Eddy County (NAD 83 NM Eastern)	MD Reference:	RKB @ 3453.80ft
Site:	Sec 11-T23S-R31E	North Reference:	Grid
Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
10,300.00	41.08	13.07	10,139.66	-70.92	1,367.88	477,854.43	721,226.01	32.312351	-103.751047
10,400.00	50.74	9.42	10,209.17	-0.55	1,381.68	477,924.80	721,239.82	32.312545	-103.751001
10,500.00	60.48	6.66	10,265.59	81.07	1,393.10	478,006.42	721,251.23	32.312769	-103.750963
10,600.00	70.26	4.40	10,307.22	171.43	1,401.77	478,096.78	721,259.91	32.313017	-103.750933
10,700.00	80.07	2.39	10,332.79	267.81	1,407.45	478,193.16	721,265.58	32.313282	-103.750913
10,800.00	89.90	0.51	10,341.52	367.27	1,409.95	478,292.62	721,268.09	32.313555	-103.750903
10,805.73	90.46	0.40	10,341.50	373.00	1,410.00	478,298.35	721,268.13	32.313571	-103.750903
10,900.00	90.46	0.40	10,340.74	467.27	1,410.66	478,392.62	721,268.79	32.313830	-103.750899
11,000.00	90.46	0.40	10,339.94	567.26	1,411.36	478,492.61	721,269.49	32.314105	-103.750895
11,100.00	90.46	0.40	10,339.14	667.25	1,412.05	478,592.60	721,270.19	32.314380	-103.750891
11,200.00	90.46	0.40	10,338.33	767.25	1,412.75	478,692.60	721,270.89	32.314655	-103.750887
11,300.00	90.46	0.40	10,337.53	867.24	1,413.45	478,792.59	721,271.58	32.314930	-103.750883
11,400.00	90.46	0.40	10,336.73	967.24	1,414.15	478,892.59	721,272.28	32.315204	-103.750879
11,500.00	90.46	0.40	10,335.93	1,067.23	1,414.85	478,992.58	721,272.98	32.315479	-103.750875
11,600.00	90.46	0.40	10,335.12	1,167.23	1,415.54	479,092.57	721,273.68	32.315754	-103.750871
11,700.00	90.46	0.40	10,334.32	1,267.22	1,416.24	479,192.57	721,274.38	32.316029	-103.750867
11,800.00	90.46	0.40	10,333.52	1,367.22	1,416.94	479,292.56	721,275.07	32.316304	-103.750863
11,900.00	90.46	0.40	10,332.71	1,467.21	1,417.64	479,392.56	721,275.77	32.316579	-103.750859
12,000.00	90.46	0.40	10,331.91	1,567.20	1,418.34	479,492.55	721,276.47	32.316853	-103.750855
12,100.00	90.46	0.40	10,331.11	1,667.20	1,419.04	479,592.55	721,277.17	32.317128	-103.750851
12,200.00	90.46	0.40	10,330.31	1,767.19	1,419.73	479,692.54	721,277.87	32.317403	-103.750847
12,300.00	90.46	0.40	10,329.50	1,867.19	1,420.43	479,792.53	721,278.56	32.317678	-103.750843
12,400.00	90.46	0.40	10,328.70	1,967.18	1,421.13	479,892.53	721,279.26	32.317953	-103.750839
12,500.00	90.46	0.40	10,327.90	2,067.18	1,421.83	479,992.52	721,279.96	32.318228	-103.750835
12,600.00	90.46	0.40	10,327.10	2,167.17	1,422.53	480,092.52	721,280.66	32.318503	-103.750831
12,700.00	90.46	0.40	10,326.29	2,267.16	1,423.22	480,192.51	721,281.36	32.318777	-103.750827
12,800.00	90.46	0.40	10,325.49	2,367.16	1,423.92	480,292.50	721,282.06	32.319052	-103.750823
12,900.00	90.46	0.40	10,324.69	2,467.15	1,424.62	480,392.50	721,282.75	32.319327	-103.750819
13,000.00	90.46	0.40	10,323.88	2,567.15	1,425.32	480,492.49	721,283.45	32.319602	-103.750815
13,100.00	90.46	0.40	10,323.08	2,667.14	1,426.02	480,592.49	721,284.15	32.319877	-103.750811
13,200.00	90.46	0.40	10,322.28	2,767.14	1,426.71	480,692.48	721,284.85	32.320152	-103.750807
13,300.00	90.46	0.40	10,321.48	2,867.13	1,427.41	480,792.48	721,285.55	32.320426	-103.750803
13,400.00	90.46	0.40	10,320.67	2,967.12	1,428.11	480,892.47	721,286.24	32.320701	-103.750799
13,500.00	90.46	0.40	10,319.87	3,067.12	1,428.81	480,992.46	721,286.94	32.320976	-103.750795
13,600.00	90.46	0.40	10,319.07	3,167.11	1,429.51	481,092.46	721,287.64	32.321251	-103.750791
13,700.00	90.46	0.40	10,318.26	3,267.11	1,430.21	481,192.45	721,288.34	32.321526	-103.750787
13,800.00	90.46	0.40	10,317.46	3,367.10	1,430.90	481,292.45	721,289.04	32.321801	-103.750783
13,900.00	90.46	0.40	10,316.66	3,467.10	1,431.60	481,392.44	721,289.73	32.322076	-103.750779
14,000.00	90.46	0.40	10,315.86	3,567.09	1,432.30	481,492.43	721,290.43	32.322350	-103.750775
14,100.00	90.46	0.40	10,315.05	3,667.08	1,433.00	481,592.43	721,291.13	32.322625	-103.750771
14,200.00	90.46	0.40	10,314.25	3,767.08	1,433.70	481,692.42	721,291.83	32.322900	-103.750767
14,300.00	90.46	0.40	10,313.45	3,867.07	1,434.39	481,792.42	721,292.53	32.323175	-103.750763
14,400.00	90.46	0.40	10,312.64	3,967.07	1,435.09	481,892.41	721,293.22	32.323450	-103.750759
14,500.00	90.46	0.40	10,311.84	4,067.06	1,435.79	481,992.40	721,293.92	32.323725	-103.750755
14,600.00	90.46	0.40	10,311.04	4,167.06	1,436.49	482,092.40	721,294.62	32.323999	-103.750751
14,700.00	90.46	0.40	10,310.24	4,267.05	1,437.19	482,192.39	721,295.32	32.324274	-103.750747
14,800.00	90.46	0.40	10,309.43	4,367.05	1,437.88	482,292.39	721,296.02	32.324549	-103.750743
14,900.00	90.46	0.40	10,308.63	4,467.04	1,438.58	482,392.38	721,296.72	32.324824	-103.750739
15,000.00	90.46	0.40	10,307.83	4,567.03	1,439.28	482,492.38	721,297.41	32.325099	-103.750735
15,100.00	90.46	0.40	10,307.02	4,667.03	1,439.98	482,592.37	721,298.11	32.325374	-103.750731
15,200.00	90.46	0.40	10,306.22	4,767.02	1,440.68	482,692.36	721,298.81	32.325649	-103.750727
15,300.00	90.46	0.40	10,305.42	4,867.02	1,441.37	482,792.36	721,299.51	32.325923	-103.750723
15,315.50	90.46	0.40	10,305.29	4,882.52	1,441.48	482,807.86	721,299.62	32.325966	-103.750722
Last Take Point @ 15316' MD, 100' FNL, 1980' FWL									

Planning Report - Geographic

Database:	EDM r5000.141_Prod US	Local Co-ordinate Reference:	Well Belloq 11 Fed 222H
Company:	WCDSC Permian NM	TVD Reference:	RKB @ 3453.80ft
Project:	Eddy County (NAD 83 NM Eastern)	MD Reference:	RKB @ 3453.80ft
Site:	Sec 11-T23S-R31E	North Reference:	Grid
Well:	Belloq 11 Fed 222H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
15,316.31	90.46	0.40	10,305.29	4,883.33	1,441.49	482,808.67	721,299.62	32.325968	-103.750722
PBHL; 100' FNL, 1980' FWL									
15,316.32	90.46	0.40	10,305.29	4,883.33	1,441.49	482,808.67	721,299.62	32.325968	-103.750722

Design Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- Shape	(°)	(°)	(ft)	(ft)	(ft)	(usft)	(usft)		
PBHL - Belloq 11 Fed 22	0.00	0.00	0.00	4,883.11	1,442.26	482,808.45	721,300.40	32.325968	-103.750719
- plan misses target center by 5091.65ft at 0.00ft MD (0.00 TVD, 0.00 N, 0.00 E)									
- Point									

Plan Annotations					
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates			
		+N/-S (ft)	+E/-W (ft)	Comment	
9,885.14	9,763.00	-203.46	1,295.20	KOP @ 9885' MD, 96' FSL, 1808' FWL	
9,973.66	9,849.78	-199.23	1,311.72	First Take Point @ 9974' MD, 100' FSL, 1825' FEL	
15,315.50	10,305.29	4,882.52	1,441.48	Last Take Point @ 15316' MD, 100' FNL, 1980' FWL	
15,316.31	10,305.29	4,883.33	1,441.49	PBHL; 100' FNL, 1980' FWL	

Devon Energy

WELL DETAILS: Belloq 11 Fed 222H



RKB @ 3453.80ft
3428.80

Northing 477925.35 Easting 719858.14 Latitude 32.312567 Longitude -103.755473

SECTION DETAILS Permit Plan 1

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	VSect	Annotation
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2500.00	0.00	0.00	2500.00	0.00	0.00	0.00	0.00	
3369.69	10.87	98.93	3364.49	-12.77	61.26	1.25	10.76	
9885.18	10.87	98.93	9763.04	-203.47	1295.20	0.00	171.54	KOP @ 9885' MD, 96' FSL, 1808' FWL
10805.73	90.46	0.40	10341.50	373.00	1410.00	10.00	756.92	
15316.32	90.46	0.40	10305.29	4883.33	1441.49	0.00	5091.64	Last Take Point @ 15316' MD, 100' FNL, 1980' FWL

devon



Devon Energy, Belloq 11 Fed 222H

1. Geologic Formations

TVD of target	10341	Pilot hole depth	N/A
MD at TD:	15316	Deepest expected fresh water:	

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Rustler	649		
Salado	1004		
Base of Salt	4134		
Delaware	4384		
Bell Canyon	4424		
Cherry Canyon	5299		
Brushy Canyon	6559		
Lower Brushy	7954		
1BSLM	8264		
1BSSS	9309		
2BSLM	9529		
2BSSS	9819		
2BSSS UPR	9979		
2BSSS MID	10107		
2BSSS LWR	10261		

*H2S, water flows, loss of circulation, abnormal pressures, etc.

Devon Energy, Belloq 11 Fed 222H

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (PPF)	Grade	Conn.
	From	To				
17.5"	0	750'	13.375"	48	H-40	STC
12.25"	0	6,000'	9.625"	40	J-55	BTC
8.75"	0	TD	5.5"	17	P-110	BTC
BLM Minimum Safety Factor				Collapse: 1.125	Burst: 1.00	Tension: 1.6 Dry 1.8 Wet

- All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h Must have table for contingency casing
- Rustler top will be validated via drilling parameters (i.e. reduction in ROP) and surface casing setting depth revised accordingly if needed.
- Variance is requested for collapse rating on intermediate casing. Operator will keep pipe full while running casing. No losses are expected in subsequent hole section.
- Int casing shoe will be selected based on drilling data, gamma, and flows experienced while drilling. Setting depth will be revised accordingly if needed.
- A variance is requested to waive the centralizer requirement for the intermediate and production casing strings if drilling conditions dictate

Devon Energy, Belloq 11 Fed 222H

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Devon Energy, Belloq 11 Fed 222H

3. Cementing Program (3-String Primary Design)

Casing	# Sks	TOC	Wt. (lb/gal)	H ₂ O (gal/sk)	Yld (ft ³ /sack)	Slurry Description
Surface	783	Surf	13.2	6.33	1.33	Lead: Class C Cement + additives
Int	1290	Surf	9	20.6	1.94	Lead: Class C Cement + additives
	190	500' above shoe	13.2	6.42	1.33	Tail: Class H / C + additives
Production	448	500' tieback	9	20.6	1.94	Lead: Class H / C + additives
	957	KOP	13.2	5.31	1.6	Tail: Class H / C + additives

If a DV tool is ran the depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. Slurry weights will be adjusted based on estimated fracture gradient of the formation. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. If cement is not returned to surface during the primary cement job on the surface casing string, a planned top job will be conducted immediately after completion of the primary job.

Casing String	% Excess
Surface	100%
Intermediate	50%
Production	10%

Devon Energy, Belloq 11 Fed 222H

4. Pressure Control Equipment

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
Int 1	13-5/8"	3M	Annular	X	50% of rated working pressure
			Blind Ram		5M
			Pipe Ram		
			Double Ram		
			Other*		
Production	13-5/8"	5M	Annular (5M)	X	50% of rated working pressure
			Blind Ram		5M
			Pipe Ram		
			Double Ram	X	
			Other *		
			Annular		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other *		

Devon Energy, Belloq 11 Fed 222H

5. Mud Program

6. Depth		Type	Weight (ppg)	Vis	Water Loss
From	To				
0	750'	FW	8.5 – 9.0	28-34	N/C
750'	6000'	Brine	10 – 10.5	28-34	N/C
6,000'	TD	WBM	8.5 – 9.0	28-34	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
X	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned	Interval
Resistivity	
Density	
X CBL	Production casing
X Mud log	KOP to TD

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	4299 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H ₂ S) monitors will be installed prior to drilling out the surface shoe. If H ₂ S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
N	H ₂ S is present
Y	H ₂ S Plan attached

Devon Energy, Belloq 11 Fed 222H

8. Other facets of operation

Is this a walking operation? Potentially

1. If operator elects, drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
2. The drilling rig will then batch drill the intermediate sections and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
3. The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.

NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed from the pad until all wells have production casing run/cemented.

Will be pre-setting casing? Potentially


1. Spudder rig will move in and drill surface hole.
 - a. Rig will utilize fresh water based mud to drill surface hole to TD. Solids control will be handled entirely on a closed loop basis.
2. After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
3. The wellhead will be installed and tested once the 10 3/4" surface casing is cut off and the WOC time has been reached.
4. A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with a pressure gauge installed on the wellhead.
5. Spudder rig operations is expected to take 4-5 days per well on a multi well pad.
6. The NMOCD will be contacted and notified 24 hours prior to commencing spudder rig operations.
7. Drilling operations will be performed with the drilling rig. At that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
 - a. The NMOCD will be contacted / notified 24 hours before the drilling rig moves back on to the pad with the pre-set surface casing.

Attachments

- ☒ Directional Plan
☐ Other, describe



Commitment Runs Deep



Design Plan
Operation and Maintenance Plan
Closure Plan

SENM - Closed Loop Systems
June 2010

I. Design Plan

Devon uses MI SWACO closed loop system (CLS). The MI SWACO CLS is designed to maintain drill solids at or below 5%. The equipment is arranged to progressively remove solids from the largest to the smallest size. Drilling fluids can thus be reused and savings is realized on mud and disposal costs. Dewatering may be required with the centrifuges to insure removal of ultra fine solids.

The drilling location is constructed to allow storm water to flow to a central sump normally the cellar. This insures no contamination leaves the drilling pad in the event of a spill. Storm water is reused in the mud system or stored in a reserve fluid tank farm until it can be reused. All lubricants, oils, or chemicals are removed immediately from the ground to prevent the contamination of storm water. An oil trap is normally installed on the sump if an oil spill occurs during a storm.

A tank farm is utilized to store drilling fluids including fresh water and brine fluids. The tank farm is constructed on a 20 ml plastic lined, bermed pad to prevent the contamination of the drilling site during a spill. Fluids from other sites may be stored in these tanks for processing by the solids control equipment and reused in the mud system. At the end of the well the fluids are transported from the tank farm to an adjoining well or to the next well for the rig.

Prior to installing a closed-loop system on site, the topsoil, if present, will be stripped and stockpiled for use as the final cover or fill at the time of closure.

Signs will be posted on the fence surrounding the closed-loop system unless the closed-loop system is located on a site where there is an existing well, that is operated by Devon.


II. Operations and Maintenance Plan

Primary Shakers: The primary shakers make the first removal of drill solids from the drilling mud as it leaves the well bore. The shakers are sized to handle maximum drilling rate at optimal screen size. The shakers normally remove solids down to 74 microns.

Mud Cleaner: The Mud Cleaner cleans the fluid after it leaves the shakers. A set of hydrocyclones are sized to handle 1.25 to 1.5 times the maximum circulating rate. This ensures all the fluid is being processed to an average cut point of 25 microns. The wet discharged is dewatered on a shaker equipped with ultra fine mesh screens and generally cut at 40 microns.



Closed Loop Schematic



Centrifuges: The centrifuges can be one or two in number depending on the well geometry or depth of well. The centrifuges are sized to maintain low gravity solids at 5% or below. They may or may not need a dewatering system to enhance the removal rates. The centrifuges can make a cut point of 8-10 microns depending on bowl speed, feed rate, solids loading and other factors.

The centrifuge system is designed to work on the active system and be flexible to process incoming fluids from other locations. This set-up is also dependant on well factors.

Dewatering System: The dewatering system is a chemical mixing and dosing system designed to enhance the solids removal of the centrifuge. Not commonly used in shallow wells. It may contain pH adjustment, coagulant mixing and dosing, and polymer mixing and dosing. Chemical flocculation binds ultra fine solids into a mass that is within the centrifuge operating design. The

dewatering system improves the centrifuge cut point to infinity or allows for the return of clear water or brine fluid. This ability allows for the ultimate control of low gravity solids.

Cuttings Boxes: Cuttings boxes are utilized to capture drill solids that are discarded from the solids control equipment. These boxes are set upon a rail system that allows for the removal and replacement of a full box of cuttings with an empty one. They are equipped with a cover that insures no product is spilled into the environment during the transportation phase.

Process Tank: (Optional) The process tank allows for the holding and process of fluids that are being transferred into the mud system. Additionally, during times of lost circulation the process tank may hold active fluids that are removed for additional treatment. It can further be used as a mixing tank during well control conditions.

Sump and Sump Pump: The sump is used to collect storm water and the pump is used to transfer this fluid to the active system or to the tank for to hold in reserve. It can also be used to collect fluids that may escape during spills. The location contains drainage ditches that allow the location fluids to drain to the sump.

Reserve Fluids (Tank Farm): A series of frac tanks are used to replace the reserve pit. These are steel tanks that are equipped with a manifold system and a transfer pump. These tanks can contain any number of fluids used during the drilling process. These can include fresh water, cut brine, and saturated salt fluid. The fluid can be from the active well or reclaimed fluid from other locations. A 20 ml liner and berm system is employed to ensure the fluids do not migrate to the environment during a spill.

If a leak develops, the appropriate division district office will be notified within 48 hours of the discovery and the leak will be addressed. Spill prevention is accomplished by maintaining pump packing, hoses, and pipe fittings to insure no leaks are occurring. During an upset condition the source of the spill is isolated and repaired as soon as it is discovered. Free liquid is removed by a diaphragm pump and returned to the mud system. Loose topsoil may be used to stabilize the spill and the contaminated soil is excavated and placed in the cuttings boxes. After the well is finished and the rig has moved, the entire location is scrapped and testing will be performed to determine if a release has occurred.

All trash is kept in a wire mesh enclosure and removed to an approved landfill when full. All spent motor oils are kept in separate containers and they are removed and sent to an approved recycling center. Any spilled lubricants, pipe

dope, or regulated chemicals are removed from soil and sent to landfills approved for these products.

These operations are monitored by Mi Swaco service technicians. Daily logs are maintained to ensure optimal equipment operation and maintenance. Screen and chemical use is logged to maintain inventory control. Fluid properties are monitored and recorded and drilling mud volumes are accounted for in the mud storage farm. This data is kept for end of well review to insure performance goals are met. Lessons learned are logged and used to help with continuous improvement.

A MI SWACO field supervisor manages from 3-5 wells. They are responsible for training personnel, supervising installations, and inspecting sites for compliance of MI SWACO safety and operational policy.

III. Closure Plan

A maximum 340' X 340' caliche pad is built per well. All of the trucks and steel tanks fit on this pad. All fluid cuttings go to the steel tanks to be hauled by various trucking companies to an agency approved disposal.

A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Devon proposes using a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 3000 (3M) psi.


- Wellhead will be installed by wellhead representatives.
- If the welding is performed by a third party, the wellhead representative will monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- Wellhead representative will install the test plug for the initial BOP test.
- Wellhead company will install a solid steel body pack-off to completely isolate the lower head after cementing intermediate casing. After installation of the pack-off, the pack-off and the lower flange will be tested to 3M, as shown on the attached schematic. Everything above the pack-off will not have been altered whatsoever from the initial nipple up. Therefore the BOP components will not be retested at that time.
- If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head will be cut and top out operations will be conducted.
- Devon will pressure test all seals above and below the mandrel (but still above the casing) to full working pressure rating.
- Devon will test the casing to 0.22 psi/ft or 1500 psi, whichever is greater, as per Onshore Order #2.

After running the 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 3M will be installed on the wellhead system and will undergo a 250 psi low pressure test followed by a 3,000 psi high pressure test. The 3,000 psi high and 250 psi low test will cover testing requirements a maximum of 30 days, as per Onshore Order #2. If the well is not complete within 30 days of this BOP test, another full BOP test will be conducted, as per Onshore Order #2.

After running the 9-5/8" intermediate casing with a mandrel hanger, the 13-5/8" BOP/BOPE system with a minimum rating of 3M will already be installed on the wellhead.

The pipe rams will be operated and checked each 24 hour period and each time the drill pipe is out of the hole. These tests will be logged in the daily driller's log. A 2" kill line and 3" choke line will be incorporated into the drilling spool below the ram BOP. In addition to the rams and annular preventer, additional BOP accessories include a kelly cock, floor safety valve, choke lines, and choke manifold rated at 3,000 psi WP.

Devon's proposed wellhead manufactures will be FMC Technologies, Cactus Wellhead, or Cameron.





Fluid Technology

ContiTech Beattie Corp.
Website: www.contitechbeattie.com

Monday, June 14, 2010

RE: Drilling & Production Hoses
Lifting & Safety Equipment

To Helmerich & Payne,

A Continental Contitech hose assembly can perform as intended and suitable for the application regardless of whether the hose is secured or unsecured in its configuration. As a manufacturer of High Pressure Hose Assemblies for use in Drilling & Production, we do offer the corresponding lifting and safety equipment, this has the added benefit of easing the lifting and handling of each hose assembly whilst affording hose longevity by ensuring correct handling methods and procedures as well as securing the hose in the unlikely event of a failure; but in no way does the lifting and safety equipment affect the performance of the hoses providing the hoses have been handled and installed correctly. It is good practice to use lifting & safety equipment but not mandatory.


Should you have any questions or require any additional information/clarifications then please do not hesitate to contact us.

ContiTech Beattie is part of the Continental AG Corporation and can offer the full support resources associated with a global organization.

Best regards,

Robin Hodgson
Sales Manager
ContiTech Beattie Corp

ContiTech Beattie Corp,
11535 Brittonmoore Park Drive,
Houston, TX 77041
Phone: +1 (832) 327-0141
Fax: +1 (832) 327-0148
www.contitechbeattie.com



RIG 212



QUALITY DOCUMENT

PHOENIX RUBBER

INDUSTRIAL LTD.

6728 Szeged, Budapesti út 10. Hungary • H-6701 Szeged, P. O. Box 152
 Phone: (3662) 556-737 • Fax: (3662) 556-738

SALES & MARKETING: H-1092 Budapest, Ráday u. 42-44. Hungary • H-1440 Budapest, P. O. Box 26
 Phone: (361) 456-4200 • Fax: (361) 217-2972, 456-4273 • www.burusemergo.hu

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE				CERT. N°: 552	
PURCHASER: Phoenix Beattie Co.			P.O. N°: 1519FA-871		
PHOENIX RUBBER order N°: 170466		HOSE TYPE: 3" ID Choke and Kill Hose			
HOSE SERIAL N°: 34128		NOMINAL / ACTUAL LENGTH: 11,43 m			
W.P. 68,96 MPa 10000 psi		T.P. 103,4 MPa 15000 psi		Duration: 60 min.	
Pressure test with water at ambient temperature <div style="text-align: center;">See attachment. (1 page)</div>					
↑ 10 mm = 10 Min. → 10 mm = 25 MPa					
COUPLINGS					
Type	Serial N°		Quality	Heat N°	
3" coupling with 4 1/16" Flange end	720	719	AISI 4130	C7626	
			AISI 4130	47357	
API Spec 16 C Temperature rate: "B"					
All metal parts are flawless					
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.					
Date:	Inspector		Quality Control		
29. April. 2002.			PHOENIX RUBBER Industrial Ltd. Hose Inspection and VERIFIED TRUE COPY PHOENIX RUBBER G.C.		

14094-65

40920-0-00015 N800C

6	GN	+0.000	PC	14.00
	RD	+0.000	PC	14.00
	SL	+0.000	PC	14.00
7	GN	+0.000	PC	13.43
	RD	+0.000	PC	13.43
	SL	+0.000	PC	13.43
6	GN	+0.000	PC	13.23
	RD	+0.000	PC	13.23
	SL	+0.000	PC	13.23
5	GN	+0.000	PC	13.00
	RD	+0.000	PC	13.00
	SL	+0.000	PC	13.00
4	GN	+0.000	PC	13.00
	RD	+0.000	PC	13.00
	SL	+0.000	PC	13.00
3	GN	+0.000	PC	13.00
	RD	+0.000	PC	13.00
	SL	+0.000	PC	13.00
2	GN	+0.000	PC	13.00
	RD	+0.000	PC	13.00
	SL	+0.000	PC	13.00

PHOENIX RUBBER
Industrial Ltd.
Hose Inspection and
Certification Dept.

VERIFIED TRUE CO.
PHOENIX RUBBER CO.

APD ID: 10400020749

Submission Date: 08/25/2017

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Number: 222H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

BELLOQ_11_FED_222H_EXISITING_RD_20180814145402.pdf

Existing Road Purpose: ACCESS,FLUID TRANSPORT

Row(s) Exist? NO

ROW ID(s)

ID:




Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

BELLOQ_11_FED_222H_ACCESS_RD_20180814145428.pdf



Max slope (%): 6

Feet

Width (ft.): 30

Max grade (%): 4

Army Corp of Engineers (ACOE) permit required? NO

ACOE Permit Number(s):

New road travel width: 14

New road access erosion control: Water Drainage Ditch

New road access plan or profile prepared? NO

New road access plan attachment:

Access road engineering design? NO

Access road engineering design attachment:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Number: 222H

Access surfacing type: GRAVEL

Access topsoil source: ONSITE

Access surfacing type description:

Access onsite topsoil source depth: 6

Offsite topsoil source description:

Onsite topsoil removal process: See attached Interim reclamation diagram.

Access other construction information:

Access miscellaneous information:

Number of access turnouts:

Access turnout map:

Drainage Control

New road drainage crossing: OTHER

Drainage Control comments: na

Road Drainage Control Structures (DCS) description: na

Road Drainage Control Structures (DCS) attachment:

Access Additional Attachments

Additional Attachment(s):

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

BELLOQ_11_FED_222H_1mile_20180814145453.pdf

Existing Wells description:

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? DEFER

Section 5 - Location and Types of Water Supply

Water Source Table

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Number: 222H

Water source use type: STIMULATION

Water source type: OTHER

[REDACTED]

Source latitude:

Source longitude:

Source datum:

Water source permit type: OTHER

Source land ownership: FEDERAL

Water source transport method: PIPELINE

Source transportation land ownership: STATE

[REDACTED]

Water source and transportation map:

BELLOQ_11_FED_222H_WATER_X_MAP_20180814145604.PDF

Water source comments: The attached Water Transfer Map is a proposal only and the final route and documentation will be provided by a Devon contractor prior to installation. When available Devon will always follow existing disturbance.

New water well? NO

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method:

Drill material:

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Number: 222H

Section 6 - Construction Materials

Construction Materials description: Dirt fill and caliche will be used to construct well pad. Map attached.

Construction Materials source location attachment:

BELLOQ_11_FED_222H_Caliche_Map_20180814145628.pdf

Section 7 - Methods for Handling Waste

Waste type: PRODUCED WATER

Waste content description: Average produced BWPD over the first year of production

[REDACTED] barrels

Waste disposal frequency : Daily

Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: OFF-LEASE INJECTION **Disposal location ownership:** PRIVATE

Disposal type description:

Disposal location description: Multiple methods for handling waste will be utilized. Via trucking, Dvn owned disposal system and or third party pipeline take away.

Waste type: COMPLETIONS/STIMULATION

Waste content description: Flow back water during completion operations.

[REDACTED] barrels

Waste disposal frequency : One Time Only

Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: Various disposal locations in Lea and Eddy counties.

Waste type: FLOWBACK

Waste content description: Average produced BWPD over the flowback period (first 30 days of production).

[REDACTED] barrels

Waste disposal frequency : Daily

Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: OFF-LEASE INJECTION **Disposal location ownership:** STATE

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Number: 222H

Disposal type description:

Disposal location description: Produced water during flowback will be disposed of at various disposals in Lea and Eddy County.

Waste type: DRILLING

Waste content description: Water Based Cuttings

Amount of waste: 1082 barrels

Waste disposal frequency : Daily

Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL **Disposal location ownership:** COMMERCIAL FACILITY

Disposal type description:

Disposal location description: All cuttings will disposed of at R360, Sundance, or equivalent.

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit?

Reserve pit length (ft.) **Reserve pit width (ft.)**

Reserve pit depth (ft.) **Reserve pit volume (cu. yd.)**

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? NO

Description of cuttings location

Cuttings area length (ft.) **Cuttings area width (ft.)**

Cuttings area depth (ft.) **Cuttings area volume (cu. yd.)**

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Well Number: 222H

Existing Vegetation Community at the road: Shinnery, yucca, grasses and mesquite.

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline: Shinnery, yucca, grasses and mesquite.

Existing Vegetation Community at the pipeline attachment:

Existing Vegetation Community at other disturbances: Shinnery, yucca, grasses and mesquite.

Existing Vegetation Community at other disturbances attachment:

Non native seed used? NO

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? NO

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? NO

Seed harvest description:

Seed harvest description attachment:

Seed Management

Seed Table

Seed type:

Seed name:

Source name:

Source phone:

Seed cultivar:

Seed use location:

PLS pounds per acre:

Seed source:

Source address:

Proposed seeding season:

Seed Summary	
Seed Type	Pounds/Acre

Total pounds/Acre:

Seed reclamation attachment:

Operator Contact/Responsible Official Contact Info

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Number: 222H

First Name: JACOB

Last Name: OCHOA

Phone: (575)748-9934

Email: JACOB.OCHOA@DVN.COM

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? NO

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: Maintain weeds on an as need basis.

Weed treatment plan attachment:

Monitoring plan description: Monitor as needed.

Monitoring plan attachment:

Success standards: N/A

Pit closure description: N/A

Pit closure attachment:

Section 11 - Surface Ownership

Disturbance type: PIPELINE

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Number: 222H

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: EXISTING ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11 FED

Well Number: 222H

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Section 12 - Other Information

ROW Type(s):

ROW Applications

Use a previously conducted onsite? YES

Previous Onsite information: 5/2/2017 Belloq

Other SUPO Attachment

Belloq_11_FED_222H_FLOWLINES_20180814150005.pdf


766109F_5_FL_1_GL_BELLOQ_231_BELLOQ_CTB_1_P_R2_20180814150008.pdf

BELLOQ_11_WELL_PAD_2_ELECTRIC_LINE_P_R1_20180814150011.pdf

BELLOQ_11_2_231_CTB_roads_20180814150023.pdf

BELLOQ_11_CTB_1_PAD_P_20180814150039.pdf

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL ACCESS ROUTE MAP



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
NOV. 2017

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11 FED 222H

LOCATED 300 FT. FROM THE SOUTH LINE
AND 510 FT. FROM THE WEST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JULY 11, 2018


SURVEY NO. 6177B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO


ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 231H, 511H, 515H, & BELLOQ 11 FED 222H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JULY 11, 2018



SEE NEXT SHEET (2-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12 DAY OF JULY 2018

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SHEET: 1-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEY NO. 6177B

ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 231H, 521H, 515H, & BELLOQ 11 FED 222H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JULY 11, 2018

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE NW/4 NW/4 OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE NORTHWEST CORNER OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N60°44'36"W, A DISTANCE OF 1221.97 FEET;
THENCE N00°08'29"W A DISTANCE OF 599.90 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE NORTHWEST CORNER OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S89°51'18"W, A DISTANCE OF 1064.62 FEET;

SAID STRIP OF LAND BEING 599.90 FEET OR 36.36 RODS IN LENGTH, CONTAINING 0.413 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

NW/4 NW/4 599.90 FT 36.36 RODS 0.413 ACRES

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,
NEW MEXICO, THIS 12 DAY OF JULY 2018.

FILIMON F. JARAMILLO, PLS. 12797
301 SOUTH CANAL
(575) 234-3341

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6177B

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.


SHEET: 2-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO


ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 231H, 521H, 515H, & BELLOQ 11 FED 222H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JULY 11, 2018



SEE NEXT SHEET (4-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 3-4

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12 DAY OF JULY 2018

FILMON F. JARAMILLO, SURVEYOR
MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6177B

ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 291H, 521H, 515H, & BELLOQ 11 FED 222H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JULY 11, 2018

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SW/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S89°51'18"W, A DISTANCE OF 1064.62 FEET;
THENCE N00°08'29"W A DISTANCE OF 435.02 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE S89°51'58"W A DISTANCE OF 276.00 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S60°58'15"W, A DISTANCE OF 900.69 FEET;

SAID STRIP OF LAND BEING 711.02 FEET OR 43.09 RODS IN LENGTH, CONTAINING 0.490 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SW/4 711.02 L.F. 43.09 RODS 0.490 ACRES

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,
NEW MEXICO, THIS 21 DAY OF JULY 2018

FILIMON F. JARAMILLO, PLS. 12797

301 SOUTH CANAL
(575) 234-3341

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 4-4

MADRON SURVEYING, INC.

SURVEY NO. 6177B
CARLSBAD, NEW MEXICO

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

PLAT
One Mile Radius Map

devon
This map is for illustrative purposes only and is neither a legally recorded map nor a survey and is not intended to be used as one. Devon makes no warranty, representation, or guarantee of any kind regarding this map.

USA Contiguous Equidistant Conic
Datum: North American 1983
Created by: FME Server
Map is current as of 8/6/2018



0 0.27 1 inch = 0.36 miles

BELLOQ 11 FED 222H
WA017392935


TOMB RAIDER 1-12 FED 61H

Nearest wellbore to SHL: 5417 ft.

BELLOQ 2 STATE 5H

Nearest wellbore to BHL: 435 ft.

- Unknown SHL
- Active SHL
- Inactive SHL
- × BHL



1E - 8

28S - 31E - 2

28S - 31E - 1

28S - 32E - 6

23310104

615

Total: 12,911.57 ft

6,332.82 ft

1E - 10

28S - 31E - 1

28S - 31E - 12

28S - 32E - 7

1E - 15


28S - 31E - 14

28S - 31E - 15


28S - 32E - 18

Section 1

Devon Energy - Well Pad Rig Location Layout Safety Equipment Location



SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
INTERIM SITE BUILD PLAN



0 20 100 200 400
SCALE 1" = 200'

2.847± ACRES INTERIM PAD RECLAMATION AREA
12.216± ACRES GRADING SITE RECLAMATION AREA
3.017± ACRES NON-RECLAIMED AREA
18.080± ACRES BELLOQ & GALAPAGOS WELL PAD

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11 FED 222H
LOCATED 300 FT. FROM THE SOUTH LINE
AND 510 FT. FROM THE WEST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

JULY 11, 2018


SURVEY NO. 6177B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

FLOWLINE PLAT

FIVE-8" POLY FLOWLINES AND ONE-8" POLY FLEX GAS LIFT LINE BURIED IN THE SAME DITCH
FROM BELLOQ 11 FED STATE COM 231H, 521H, 511H, & 515H & BELLOQ 11 FED 222H TO BELLOQ 11 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P. CENTERLINE SURVEY OF A PIPELINE CROSSING SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. EDDY COUNTY, STATE OF NEW MEXICO AUGUST 6, 2018



SEE NEXT SHEET (2-4) FOR DESCRIPTION

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 6 DAY OF AUGUST 2018.


[Signature]
FILMON F. JARAMILLO, S.P.S. 12797

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 5316B

SHEET: 1-4

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO (575) 234-3341



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

FLOWLINE PLAT

FIVE-8" POLY FLOWLINES AND ONE-8" POLY FLEX GAS LIFT LINE BURIED IN THE SAME DITCH
FROM BELLOQ 11 FED STATE COM 231H, 521H, 511H, & 515H & BELLOQ 11 FED 222H TO BELLOQ 11 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AUGUST 6, 2018

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SW/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S57°47'57"W, A DISTANCE OF 565.33 FEET;
THENCE N00°09'11"W A DISTANCE OF 164.97 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N89°51'02"E A DISTANCE OF 627.80 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N00°09'30"W A DISTANCE OF 360.06 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE WEST QUARTER CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N31°40'57"W, A DISTANCE OF 2131.64 FEET;

SAID STRIP OF LAND BEING 1152.83 FEET OR 69.87 RODS IN LENGTH, CONTAINING 0.794 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SW/4 1152.83 L.F. 69.87 RODS 0.794 ACRES

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-4

MADRON SURVEYING, INC.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 12th DAY OF AUGUST 2018

FILMON F. JARAMILLO, PLS 12797
301 SOUTH CANAL
(575) 234-3341

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341


SURVEY NO. 5316B

CARLSBAD, NEW MEXICO

FLOWLINE PLAT

**FIVE-8" POLY FLOWLINES AND ONE-8" POLY FLEX GAS LIFT LINE BURIED IN THE SAME DITCH
FROM BELLOQ 11 FED STATE COM 231H, 521H, 511H, & 515H & BELLOQ 11 FED 222H TO BELLOQ 11 CTB 1**


**DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AUGUST 6, 2018**



FLOWLINE PLAT

**FIVE-8" POLY FLOWLINES AND ONE-8" POLY FLEX GAS LIFT LINE BURIED IN THE SAME DITCH
FROM BELLOQ 11 FED STATE COM 231H, 521H, 511H, & 515H & BELLOQ 11 FED 222H TO BELLOQ 11 CTB 1**

**DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AUGUST 6, 2018**



FIVE-8" POLY FLOWLINES AND ONE-8" POLY FLEX GAS LIFT LINE BURIED IN THE SAME DITCH FROM BELLOQ 11 FED STATE COM 231H, 521H, 511H, & 515H & BELLOQ 11 FED 222H TO BELLOQ 11 CTB 1

SHEET: 1-4

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

ADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 5316B

FLOWLINE PLAT

FIVE-8" POLY FLOWLINES AND ONE-8" POLY FLEX GAS LIFT LINE BURIED IN THE SAME DITCH
FROM BELLOQ 11 FED STATE COM 231H, 521H, 511H, & 515H & BELLOQ 11 FED 222H TO BELLOQ 11 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AUGUST 6, 2018

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SW/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S57°47'57"W, A DISTANCE OF 565.33 FEET;
THENCE N00°09'11"W A DISTANCE OF 164.97 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N89°51'02"E A DISTANCE OF 627.80 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N00°09'30"W A DISTANCE OF 360.06 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE WEST QUARTER CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N31°40'57"W, A DISTANCE OF 2131.64 FEET;

SAID STRIP OF LAND BEING 1152.83 FEET OR 69.87 RODS IN LENGTH, CONTAINING 0.794 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SW/4 1152.83 L.F. 69.87 RODS 0.794 ACRES

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-4

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO, THIS 22 DAY OF AUGUST 2018


MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 5316B

FLOWLINE PLAT

FIVE-8" POLY FLOWLINES AND ONE-8" POLY FLEX GAS LIFT LINE BURIED IN THE SAME DITCH
FROM BELLOQ 11 FED STATE COM 231H, 521H, 511H, & 515H & BELLOQ 11 FED 222H TO BELLOQ 11 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AUGUST 6, 2018



FLOWLINE PLAT

**FIVE-8" POLY FLOWLINES AND ONE-8" POLY FLEX GAS LIFT LINE BURIED IN THE SAME DITCH
FROM BELLOQ 11 FED STATE COM 231H, 521H, 511H, & 515H & BELLOQ 11 FED 222H TO BELLOQ 11 CTB 1**

**DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AUGUST 6, 2018**





EXHIBIT "A"
PAGE 1 of 4
ELECTRIC LINE PLAT
SECTION 11, T23S-R31E, N.M.P.M.
EDDY COUNTY, NEW MEXICO




LINE	BEARING	DISTANCE
L1	S 02°28'06" W	167.11'
L2	N 89°59'29" W	233.39'
L3	S 00°02'52" W	48.15'

30' EASEMENT AREA = 0.309 ACRE(S)
448.65 FEET OR 27.19 RODS

SEE THE ATTACHED LEGAL DESCRIPTION
Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.




B.L. Laman
Date Signed: 03-21-2018
Horizonrow, LLC
P.O. Box 548, Dry Creek, LA.
(903) 388-3045 70637
Employee of Horizonrow, LLC

HORIZON ROW LLC

Drawn for:

Drawn by: JEANNIE PERRY Date: 03/11/2018

DEVON ENERGY PRODUCTION COMPANY, L.P.	LINE NUMBER: ELB029
BELLOQ 11 WELL PAD 2 ELECTRIC LINE	WBS NUMBER: CC-127871.01.FAC
PROPOSED 30' EASEMENT ON THE PROPERTY OF BUREAU OF LAND MANAGEMENT SECTION 11, T23S-R31E, N.M.P.M.	SCALE: 1" = 1000'
	REVISIONS:
	SHEET: 1 OF 4



SECTION 11, T23S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO

ELECTRIC LINE PLAT

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of Section 11, Township 23 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 1" iron pipe w/ BC found for the west quarter corner of Section 11, T23S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence S 22°51'13" E, a distance of 2143.53' to the **Point of Beginning** of this easement, having coordinates of Northing=478290.41 feet, Easting=720167.62 feet, and continuing the following courses;

Thence S 02°28'06" W, a distance of 167.11' to an angle point;


Thence N 89°59'29" W, a distance of 233.39' to an angle point;

Thence S 00°02'52" W, a distance of 48.15' to the **Point of Ending**, having coordinates of Northing=478075.34 feet, Easting=719926.99 feet, from said point a 2" iron pipe w/ BC found for the southwest corner of Section 11, T23S-R31E, N.M.P.M., Eddy County, New Mexico bears S 51°59'02" W a distance of 732.36', covering a total of **448.65' or 27.19 rods** and having an area of **0.309 acres**.


NOTES:

Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.


B.L. Laman PLS 22404
Date Signed: 03/21/2018
Horizon Row, LLC
P.O. Box 548, Dry Creek, LA
(903) 388-3045 70637
Employee of Horizon Row, LLC





QUAD MAP

SECTION 11, T23S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

PROPOSED 30' EASEMENT

Drawn by:
JEANNIE PERRY

Date: 03/13/2018

Drawn for:



devon

LINE NUMBER:
EL8029

WBS NUMBER:
CC-127671.01.FAC


SCALE:
1" = 2000'

REVISIONS:

SHEET:
3 OF 4

EXHIBIT "A"

PAGE 4 of 4



AERIAL MAP

SECTION 11, T23S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

PROPOSED 30' EASEMENT

Drawn by:
JEANNIE PERRY

Date: 03/11/2018

Drawn for:



LINE NUMBER:
ELB029

WBS NUMBER:
CC-127671.01.FAC

SCALE:
1" = 2000'

REVISIONS:


SHEET:
4 OF 4

DEVON ENERGY PRODUCTION COMPANY, L.P.

BELLOQ MDP 11 PADS, CTBS, WELLS AND ACCESS ROADS
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

OCTOBER 23, 2017


SEC 11
T.23S., R.31E.




MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO (575) 234-3341

ACCESS ROAD PLAT
ACCESS ROAD TO THE BELLOQ MDP 11 PAD 2

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JUNE 12, 2017



SEE NEXT SHEET (2-2) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12TH DAY OF JUNE 2017

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SHEET: 1-2

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEY NO. 5230A

ACCESS ROAD PLAT
ACCESS ROAD TO THE BELLOQ MDP 11 PAD 2

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JUNE 12, 2017

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SW/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S43°29'10"W, A DISTANCE OF 1164.10 FEET;

THENCE S37°29'41"E A DISTANCE OF 430.87 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;

THENCE S00°08'51"E A DISTANCE OF 50.08 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S66°56'36"W, A DISTANCE OF 1155.83 FEET;

SAID STRIP OF LAND BEING 480.95 FEET OR 29.15 RODS IN LENGTH, CONTAINING 0.331 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SW/4 480.95 L.F. 29.15 RODS 0.331 ACRES

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12 DAY OF JUNE 2017

[Signature]
FILMON F. JARAMILLO, SURVEYOR
REGISTERED PROFESSIONAL SURVEYOR
NO. 12797

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.


SHEET: 2-2

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341


SURVEY NO. 5230A

ACCESS ROAD PLAT
ACCESS ROAD TO THE BELLOQ 11-2 FED STATE COM 231H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JUNE 12, 2017



SEE NEXT SHEET (2-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12TH DAY OF JUNE 2017.

MADRON SURVEYING, INC.
501 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341
SURVEY NO. 5231B

SHEET: 1-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

ACCESS ROAD PLAT
ACCESS ROAD TO THE BELLOQ 11-2 FED STATE COM 231H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JUNE 12, 2017

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SW/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S66°56'36"W, A DISTANCE OF 1155.83 FEET;
THENCE S00°08'38"E A DISTANCE OF 290.84 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE S45°00'00"W A DISTANCE OF 225.83 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S89°51'18"W, A DISTANCE OF 904.70 FEET;


SAID STRIP OF LAND BEING 516.47 FEET OR 31.30 RODS IN LENGTH, CONTAINING 0.356 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SW/4 516.47 L.F. 31.30 RODS 0.356 ACRES

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12th DAY OF JUNE 2017.


FILMON F. JARAMILLO, SURVEYOR
MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.


SHEET: 2-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO


SURVEY NO. 5231B

ACCESS ROAD PLAT
ACCESS ROAD TO THE BELLOQ 11-2 FED STATE COM 231H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JUNE 12, 2017



SEE NEXT SHEET (4-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12 DAY OF JUNE 2017.

(Signature of Filimon F. Jaramillo)
FILIMON F. JARAMILLO, SURVEYOR NO. 12797

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SHEET: 3-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEY NO. 5231B

ACCESS ROAD PLAT
ACCESS ROAD TO THE BELLOQ 11-2 FED STATE COM 231H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JUNE 12, 2017

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE NW/4 NW/4 OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE NORTHWEST CORNER OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S89°51'18"W, A DISTANCE OF 904.70 FEET;

THENCE S45°00'00"W A DISTANCE OF 7.72 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;

THENCE N90°00'00"W A DISTANCE OF 200.00 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE NORTHWEST CORNER OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N89°44'26"W, A DISTANCE OF 699.24 FEET;

SAID STRIP OF LAND BEING 207.72 FEET OR 12.59 RODS IN LENGTH, CONTAINING 0.143 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

NW/4 NW/4 207.72 L.F. 12.59 RODS 0.143 ACRES

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12 DAY OF JUNE 2017

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.


SHEET: 4-4

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341


SURVEY NO. 5231B

ACCESS ROAD PLAT
ACCESS ROAD TO THE BELLOQ 11 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MAY 15, 2017



SEE NEXT SHEET (2-2) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 1-2

MADRON SURVEYING, INC.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO: THIS 22ND DAY OF MAY, 2017

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 5240

CARLSBAD, NEW MEXICO

ACCESS ROAD PLAT
ACCESS ROAD TO THE BELLOQ 11 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MAY 15, 2017

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SW/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S31°37'49"W, A DISTANCE OF 1541.24 FEET;
THENCE N89°59'45"E A DISTANCE OF 85.05 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S34°14'40"W, A DISTANCE OF 1587.49 FEET;

SAID STRIP OF LAND BEING 85.05 FEET OR 5.15 RODS IN LENGTH, CONTAINING 0.059 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SW/4 85.05 L.F. 5.15 RODS 0.059 ACRES

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, MY CERTIFICATE IS EXECUTED AT CARLSBAD,
NEW MEXICO, THIS 28 DAY OF MAY 2017

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-2


MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 **CARLSBAD, NEW MEXICO**

SURVEY NO. 5240

BELLOQ 11 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
IN THE SW/4 SW/4 & SE/4 SW/4 & NW/4 SW/4 & NE/4 SW/4 OF
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

MAY 15, 2017



DESCRIPTION

A CERTAIN PIECE OR PARCEL OF LAND AND REAL ESTATE LYING IN THE SW/4 SW/4 & SE/4 SW/4 & NW/4 SW/4 & NE/4 SW/4 OF SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

BEGINNING AT THE SOUTHWEST CORNER OF THE PARCEL, WHENCE THE SOUTHWEST CORNER OF SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S47°14'23\"W, A DISTANCE OF 1218.46 FEET;
THENCE N00°08'43\"W A DISTANCE OF 500.06 FEET TO THE NORTHWEST CORNER OF THE PARCEL;
THENCE N89°51'17\"E A DISTANCE OF 500.06 FEET TO THE NORTHEAST CORNER OF THE PARCEL;
THENCE S00°08'29\"E A DISTANCE OF 500.06 FEET TO THE SOUTHEAST CORNER OF THE PARCEL;
THENCE S89°51'18\"W A DISTANCE OF 500.03 FEET TO THE SOUTHWEST CORNER OF THE PARCEL, TO THE POINT OF BEGINNING;
CONTAINING 4.783 ACRES IN THE SW/4 SW/4 & 0.905 ACRES IN THE SE/4 SW/4 & 0.044 ACRES IN THE NW/4 SW/4 & 0.008 ACRES IN THE NE/4 SW/4 FOR A TOTAL OF 5.740 ACRES MORE OR LESS.

GENERAL NOTES

- 1.) THE INTENT OF THIS SURVEY IS TO ACQUIRE A BUSINESS LEASE FOR THE PURPOSE OF BUILDING A CENTRAL TANK BATTERY
- 2.) BASIS OF BEARING IS NEW MEXICO STATE PLANE EAST ZONE MODIFIED TO THE SURFACE (NAD83)

DRIVING DIRECTIONS: FROM STATE HIGHWAY 128 AND CR 798 (RED ROAD) GO NORTH ON CR 798 4.7 MILES, TURN LEFT ON CALICHE ROAD AND GO WEST 0.15 OF A MILE, BEND RIGHT AND GO NORTHWEST 0.2 OF A MILE, TURN LEFT AND GO SOUTHWEST 0.6 OF A MILE, TURN LEFT AND GO SOUTH 188', TURN LEFT GO EAST 85' TO THE NORTHWEST PAD CORNER.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 15th DAY OF MAY 2017.

[Signature of Filmon F. Jaramillo]
FILMON F. JARAMILLO, SURVEYOR
301 SOUTH CANAL
(505) 234-3341

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 5240

SHEET: 1-3


MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

BELLOQ 11 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
IN THE SW/4 SW/4 & SE/4 SW/4 & NW/4 SW/4 & NE/4 SW/4 OF
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

MAY 15, 2017

QUAD MAP



SHEET: 2-3

SURVEY NO. 5240


MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

BELLOQ 11 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
IN THE SW/4 SW/4 & SE/4 SW/4 & NW/4 SW/4 & NE/4 SW/4 OF
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

MAY 15, 2017

AERIAL PHOTO




SHEET: 3-3

SURVEY NO. 5240

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

PLAN VIEW



DEVON ENERGY PRODUCTION COMPANY, L.P.
 GRADING PLAN AND CROSS SECTIONS
 FOR BELLOQ 11 CTB 1
 SECTION 11, TOWNSHIP 23 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

012 60 120 240
 SCALE 1" = 120'




CUT	FILL	NET
11766 CU. YD	20087 CU. YD	8321 CU. YD (FILL)

EARTHWORK QUANTITIES ARE ESTIMATED

MAY 15, 2017
 MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
 (575) 234-3341

SHEET 1-2
 SURVEY NO. 6240

CROSS SECTIONS



DEVON ENERGY PRODUCTION COMPANY, L.P.
 GRADING PLAN AND CROSS SECTIONS
FOR BELLOQ 11 CTB 1
 SECTION 11, TOWNSHIP 23 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

012 60 120 240
 SCALE 1" = 120' - 1" = 20' VER


MAY 15, 2017

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
 (575) 234-3341


SHEET 2-2
 SURVEY NO. 5240

ACCESS ROAD PLAT
ACCESS ROAD TO THE BELLOQ 11 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MAY 15, 2017



SEE NEXT SHEET (2-2) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 1-2

MADRON SURVEYING, INC.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 15TH DAY OF MAY, 2017

FILMON F. JARAMILLO, SURVEYOR

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 5240

CARLSBAD, NEW MEXICO

ACCESS ROAD PLAT
ACCESS ROAD TO THE BELLOQ 11 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MAY 15, 2017

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 SW/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S31°37'49"W, A DISTANCE OF 1541.24 FEET;

THENCE N89°59'45"E A DISTANCE OF 85.05 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHWEST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S34°14'40"W, A DISTANCE OF 1587.49 FEET;


SAID STRIP OF LAND BEING 85.05 FEET OR 5.15 RODS IN LENGTH, CONTAINING 0.059 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 SW/4 85.05 L.F. 5.15 RODS 0.059 ACRES

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,
NEW MEXICO, THIS 15 DAY OF MAY 2017



GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-2

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 **CARLSBAD, NEW MEXICO**

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 5240



Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Injection well name:

Assigned injection well API number?

Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment:

Bond Information**Federal/Indian APD: FED****BLM Bond number: CO1104****BIA Bond number:****Do you have a reclamation bond? NO****Is the reclamation bond a rider under the BLM bond?****Is the reclamation bond BLM or Forest Service?****BLM reclamation bond number:****Forest Service reclamation bond number:****Forest Service reclamation bond attachment:****Reclamation bond number:****Reclamation bond amount:****Reclamation bond rider amount:****Additional reclamation bond information attachment:**

10

11

12

13

14