

Carlsbad Field Office
OCD Artesia

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT **DISTRICT II-ARTESIA O.C.D.**

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other 1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone			5. Lease Serial No. NMNM135240 6. If Indian, Allottee or Tribe Name 7. If Unit or C/A Agreement, Name and No. 8. Lease Name and Well No. CRAZY HORSE 0304 FED COM 1H 322439	
2. Name of Operator CL&F OPERATING LLC 3a. Address 16945 Northchase Drive #500 Houston TX 77060 3b. Phone No. (include area code) 370951 (281)873-3013			9. API Well No. 30-015-45338 10. Field and Pool, or Exploratory PARKWAY / BONE SPRING 96680 CARTERS CANYON 11. Section, T, R, M, or Bk. and Survey or Area SEC 2 / T20S / R30E / NMP	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SWSW / 110 FSL / 436 FWL / LAT 32.595335 / LONG -103.949971 At proposed prod. zone SWSW / 500 FSL / 330 FWL / LAT 32.596508 / LONG -103.984504				
14. Distance in miles and direction from nearest town or post office* 15 miles			12. County or Parish EDDY 13. State NM	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 110 feet		16. No of acres in lease 639.95		17. Spacing Unit dedicated to this well 320
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 3544 feet		19. Proposed Depth 8372 feet / 18851 feet		20. BLM/BIA Bond No. in file FED: NMB001314
21. Elevations (Show whether DF, KDB, RT, GL., etc.) 3218 feet		22. Approximate date work will start* 04/01/2018		23. Estimated duration 90 days
24. Attachments				

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|---|---|
| 1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM. |
|---|---|

25. Signature (Electronic Submission)		Name (Printed/Typed) Brian Wood / Ph: (505)466-8120		Date 02/07/2018	
Title President		Name (Printed/Typed) Christopher Walls / Ph: (575)234-2234		Date 10/05/2018	
Approved by (Signature) (Electronic Submission)		Name (Printed/Typed) Christopher Walls / Ph: (575)234-2234		Date 10/05/2018	
Title Petroleum Engineer		Office CARLSBAD			

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction

APPROVED WITH CONDITIONS

INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM 1: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM connects this information to a new evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

I. SHL: SWSW / 110 FSL / 436 FWL / TWSP: 20S / RANGE: 30E / SECTION: 2 / LAT: 32.595335 / LONG: -103.949971 (TVD: 0 feet, MD: 0 feet)
PPP: SWSE / 473 FNL / 2640 FEL / TWSP: 20S / RANGE: 30E / SECTION: 4 / LAT: 32.596496 / LONG: -103.97706 (TVD: 8400 feet, MD: 16569 feet)
PPP: SESE / 508 FSL / 0 FEL / TWSP: 20S / RANGE: 30E / SECTION: 4 / LAT: 32.596468 / LONG: -103.951456 (TVD: 8432 feet, MD: 13951 feet)
PPP: SWSW / 110 FSL / 436 FWL / TWSP: 20S / RANGE: 30E / SECTION: 2 / LAT: 32.595335 / LONG: -103.949971 (TVD: 0 feet, MD: 0 feet)
PPP: SESE / 357 FNL / 0 FEL / TWSP: 20S / RANGE: 30E / SECTION: 3 / LAT: 32.595991 / LONG: -103.951456 (TVD: 8498 feet, MD: 8642 feet)
BHL: SWSW / 500 FSL / 330 FWL / TWSP: 20S / RANGE: 30E / SECTION: 4 / LAT: 32.596508 / LONG: -103.984504 (TVD: 8372 feet, MD: 18851 feet)

BLM Point of Contact

Name: Katrina Ponder

Title: Geologist

Phone: 5752345969

Email: kponder@blm.gov

Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	CL&F Resources LP
LEASE NO.:	NMNM135240
WELL NAME & NO.:	Crazy Horse 0304 Fed Com 1H
SURFACE HOLE FOOTAGE:	110'/S & 436'/W
BOTTOM HOLE FOOTAGE:	500'/S & 330'/W
LOCATION:	Section 2, T.20 S., R. 30 E., NMPM
COUNTY:	Eddy County, New Mexico

Potash	<input type="radio"/> None	<input type="radio"/> Secretary	<input checked="" type="radio"/> R-111-P
Cave/Karst Potential	<input type="radio"/> Low	<input type="radio"/> Medium	<input checked="" type="radio"/> High
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	
Other	<input checked="" type="checkbox"/> 4 String Area	<input checked="" type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP

A. Hydrogen Sulfide

1. Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The 20 inch surface casing shall be set at approximately 321 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **24 hours in the Potash Area** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength,

whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

A MINIMUM OF TWO CASING STRINGS CEMENTED TO SURFACE IS REQUIRED IN HIGH CAVE/KARST AREAS. THE CEMENT MUST BE IN A SOLID SHEATH. THEREFORE, ONE INCH OPERATIONS ARE NOT SUFFICIENT TO PROTECT CAVE KARST RESOURCES. A CASING DESIGN THAT HAS A ONE INCH JOB PERFORMED DOES NOT COUNT AS A SOLID SHEATH. ON A THREE STRING DESIGN; IF THE PRIMARY CEMENT JOB ON THE SURFACE CASING DOES NOT CIRCULATE, THEN THE NEXT TWO CASING STRINGS MUST BE CEMENTED TO SURFACE.

2. The minimum required fill of cement behind the 13 3/8 inch first intermediate casing is:

- Cement to surface. If cement does not circulate see B.1.a, c-d above.
Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.

❖ **Special Capitan Reef requirements.** If lost circulation (50% or greater) occurs below the Base of the Salt, the operator shall do the following:

- Switch to fresh water mud to protect the Capitan Reef and use fresh water mud until setting the intermediate casing. The appropriate BLM office is to be notified for a PET to witness the switch to fresh water.
- Daily drilling reports from the Base of the Salt to the setting of the intermediate casing are to be submitted to the BLM CFO engineering staff via e-mail by 0800 hours each morning. Any lost circulation encountered is to be recorded on these drilling reports. The daily drilling report should show mud volume per shift/tour. Failure to submit these reports will result in an Incidence of Non-Compliance being issued for failure to comply with the Conditions of Approval. If not already planned, the operator shall run a caliper survey for the intermediate well bore and submit to the appropriate BLM office.

3. The minimum required fill of cement behind the 9 5/8 inch second intermediate casing is:

Operator has proposed DV tool at depth of 1930' but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range. If an ECP is used, it is to be set a

minimum of 50' below the shoe to provide cement across the shoe. If it cannot be set below the shoe, a CBL shall be run to verify cement coverage.

- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
 - b. Second stage above DV tool:
 - Cement to surface. If cement does not circulate, contact the appropriate BLM office. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to Capitan Reef. Excess calculates to 3% - additional cement will be required.**
4. The minimum required fill of cement behind the 5 1/2 inch production casing is:
- Cement should tie-back at least **50 feet above the Capitan Reef** (Top of Capitan Reef estimated at 2293'). **Excess calculates to 12% - additional cement will be required.**

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2.
 - Option 1:**
 - i. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 20 inch surface casing shoe shall be **2000 (2M) psi. In the case where the only BOP installed is an annular preventer, it shall be tested to a minimum of 2000 psi (which may require upgrading to 3M or 5M annular).**
 - ii. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 9 5/8 inch second intermediate casing shoe shall be **5000 (5M) psi. Variance is approved to use 3M Annular.**

Option 2:

- i. **Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 5000 (5M) psi.**

- a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
- b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- c. Manufacturer representative shall install the test plug for the initial BOP test.
- d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

D. SPECIAL REQUIREMENT(S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

Waste Minimization Plan (WMP)

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

MHH 10042018

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties
Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.
During office hours call (575) 627-0272.
After office hours call (575)

☒ Eddy County
Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County
Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the

plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	CL&F Resources LP
LEASE NO.:	NMNM135240
WELL NAME & NO.:	Crazy Horse 0304 Fed Com 1H
SURFACE HOLE FOOTAGE:	110'/S & 436'/W
BOTTOM HOLE FOOTAGE	500'/S & 330'/W
LOCATION:	Section 2, T.20 S., R. 30 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Rangeland
 - Hydrology
 - Cave/Karst
 - Recreation
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Rangeland Mitigation:

Cattle Guard Requirement

Any new or existing cattle guards on the access route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations. Once the road is abandoned, the fence would be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Fence Requirement

Where entry granted across a fence line, the fence must be braced and tied off on both sides of the passageway prior to cutting. Once the work is completed, the fence will be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

Livestock Watering Requirement

Structures that provide water to livestock, such as windmills, pipelines, drinking troughs, and earthen reservoirs, will be avoided by moving the proposed action.

Any damage to fences, cattle guards, and pipelines or structures that provide water to livestock during construction, throughout the life of the project, and caused by its operation, must be immediately corrected by CL&F. CL&F must notify the grazing allottee or the private surface landowner and the BLM-CFO (575-234-5972) if any damage occurs to pipelines or structures that provide water to livestock.

Hydrology:

The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. The compacted berm shall be constructed at a minimum of 12 inches with impermeable mineral material (e.g. caliche). Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed. Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion. Stockpiling of topsoil is required. The top soil shall be stockpiled in an appropriate location to prevent loss of soil due to water or wind erosion and not used for berming or erosion control. If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour production, whichever is greater. Automatic shut off, check valves, or similar systems

will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect pressure drops, situating valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

Cave/Karst Surface Mitigation:

The following stipulations will be applied to minimize impacts during construction, drilling and production:

Construction:

In the advent that any underground voids are opened up during construction activities, construction activities will be halted and the BLM will be notified immediately.

No Blasting:

No blasting will be utilized for pad construction. The pad will be constructed and leveled by adding the necessary fill and caliche.

Pad Berming:

- The entire perimeter of the well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.
- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g., caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised. (Any access road crossing the berm cannot be lower than the berm height.)

- Following a rain event, all fluids will be vacuumed off of the pad and hauled off-site and disposed at a proper disposal facility.

Tank Battery Liners and Berms:

Tank battery locations and all facilities will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing, or equivalent, to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

Leak Detection System:

A method of detecting leaks is required. The method could incorporate gauges to measure loss, situate valves and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present. Leak detection plan will be submitted to BLM for approval.

Automatic Shut-off Systems:

Automatic shut off, check valves, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

Cave/Karst Subsurface Mitigation:

The following stipulations will be applied to protect cave/karst and ground water concerns:

Rotary Drilling with Fresh Water:

Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

Directional Drilling:

Kick off for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

Lost Circulation:

ALL lost circulation zones from the surface to the base of the cave occurrence zone will be logged and reported in the drilling report.

Regardless of the type of drilling machinery used, if a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cave-bearing zone, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

Abandonment Cementing:

Upon well abandonment in cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

Pressure Testing:

The operator will perform annual pressure monitoring on all casing annuli and reported in a sundry notice. If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

FLOWLINES (SURFACE):

- Flowlines will be routed around sinkholes and other karst features to avoid or lessen the possibility of encountering near surface voids and to minimize the possibility of leaks and spills from entering karst systems.
- If a void is encountered alignments may be rerouted to avoid the karst feature and lessen; the potential of subsidence or collapse of karst features, buildup of toxic or combustible gas, or other possible impacts to cave and karst resources from the buried pipeline.
- Regular monitoring is required to quickly identify leaks for their immediate and proper treatment.
- All spills or leaks will be reported to the BLM immediately for their immediate and proper treatment.

ACCESS ROAD MITIGATION

- Roads will be routed around sinkholes and other karst features to avoid or lessen the possibility of encountering near surface voids and to minimize changes to runoff or possible leaks and spills from entering karst systems.
- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, cave passages, or voids are penetrated during construction and no further construction will be done until clearance has been issued by the Authorized Officer.
- Turnout ditches and drainage leadoffs will not be constructed in such a manner as to increase or decrease the natural flow of water into or out of cave or karst features.
- Special restoration stipulations or realignment may be required.
- All spills or leaks will be reported to the BLM immediately for their immediate and proper treatment.

Recreation (Hackberry Lake SRMA) Mitigation Measures:

Pipelines shall be buried a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. Power poles and associated ground structures (poles, guy wires) will not be placed within 20 feet of recreation trails. Guy wires must be equipped with a sleeve, tape or other industry approved apparatus that is highly visible during the day and reflective at night. Appropriate safety signage will be in place during all phases of the project. Upon completion of construction, the road shall be returned to pre-construction condition with no bumps or dips. All vehicle and equipment operators will observe speed limits and practice responsible defensive driving habits.

Potash Mitigation Measures:

Lessees must comply with the 2012 Secretarial Potash Order. The Order is designed to manage the efficient development of oil, gas, and potash resources. Section 6 of the Order provides general provisions which must be followed to minimize conflict between the industries and ensure the safety of operations.

To minimize impacts to potash resources, the proposed well is confined within the boundaries of the established Crazy Horse State Drill Island (See Potash Memo and Map in attached file for Drill Island description).

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.


Turnouts

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

VRM Facility Requirement

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

Hackberry SRMA Requirements

Pipelines shall be buried a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. Power poles and associated ground structures (poles, guy wires) will not be placed within 20 feet of recreation trails. Guy wires must be equipped with a sleeve, tape or other industry approved apparatus that is highly visible during the day and reflective at night. Appropriate safety signage will be in place during all phases of the project. Upon completion of construction, the road shall be returned to pre-construction condition with no bumps or dips. All vehicle and equipment operators will observe speed limits and practice responsible defensive driving habits.

B. PIPELINES

BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of

a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.

6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.

7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:

- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
- Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
- The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)

8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.

9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

<input checked="" type="checkbox"/> seed mixture 1	<input type="checkbox"/> seed mixture 3
<input type="checkbox"/> seed mixture 2	<input type="checkbox"/> seed mixture 4
<input type="checkbox"/> seed mixture 2/LPC	<input type="checkbox"/> Aplomado Falcon Mixture

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder

before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches [that are not otherwise fenced, screened, or netted] to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

Karst:

- The BLM, Carlsbad Field Office, will be informed immediately if any subsurface drainage channels, passages, or voids are intersected by trenching, and no pipe will be laid in the trench at that point until clearance has been issued by the Authorized Officer.
- If a void is encountered alignments may be rerouted to avoid the karst feature and lessen; the potential of subsidence or collapse of karst features, buildup of toxic or combustible gas, or other possible impacts to cave and karst resources from the buried pipeline.
- Special restoration stipulations or realignment may be required at such intersections, if any.
- A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect pressure drops, siting valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

- Regular monitoring is required to quickly identify leaks for their immediate and proper treatment.
- All spills or leaks will be reported to the BLM immediately for their immediate and proper treatment.

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 1 for Loamy Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed shall be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed shall be planted using a drill equipped with a depth regulator to ensure proper depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture shall be evenly and uniformly planted over the disturbed area (small/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed shall be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre shall be doubled. The seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains lovegrass (<i>Eragrostis intermedia</i>)	0.5
Sand dropseed (<i>Sporobolus cryptandrus</i>)	1.0
Sideoats grama (<i>Bouteloua curtipendula</i>)	5.0
Plains bristlegrass (<i>Setaria macrostachya</i>)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

10/05/2018

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Brian Wood

Signed on: 02/07/2018

Title: President

Street Address: 37 Verano Loop

City: Santa Fe

State: NM

Zip: 87508

Phone: (505)466-8120

Email address: afmss@permitswest.com

Field Representative

Representative Name:

Street Address:

City:

State:

Zip:

Phone:

Email address:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data Report

10/05/2018

APD ID: 10400027002

Submission Date: 02/07/2018

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Well Type: OIL WELL

Well Work Type: Drill

Highlighted data
reflects the most
recent changes

[Show Final Text](#)

Section 1 - General

APD ID: 10400027002

Tie to previous NOS?

Submission Date: 02/07/2018

BLM Office: CARLSBAD

User: Brian Wood

Title: President

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM135240

Lease Acres: 639.95

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? NO

Permitting Agent? YES

APD Operator: CL&F OPERATING LLC

Operator letter of designation:

Operator Info

Operator Organization Name: CL&F OPERATING LLC

Operator Address: 16945 Northchase Drive #500

Zip: 77060

Operator PO Box:

Operator City: Houston

State: TX

Operator Phone: (281)873-3013

Operator Internet Address:

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: PARKWAY

Pool Name: BONE SPRING

Is the proposed well in an area containing other mineral resources? POTASH

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Describe other minerals:

Is the proposed well in a Helium production area? N

Use Existing Well Pad? NO

New surface disturbance?

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name:

Number: 1H

Well Class: HORIZONTAL

CRAZY HORSE

Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 15 Miles

Distance to nearest well: 3544 FT

Distance to lease line: 110 FT

Reservoir well spacing assigned acres Measurement: 320 Acres

Well plat: CH_1H_Plat_20180206132546.pdf

Well work start Date: 04/01/2018

Duration: 90 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number: 7977

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1	110	FSL	436	FWL	20S	30E	2	Aliquot SWS W	32.59533 5	- 103.9499 71	EDD Y	NEW MEXI CO	NEW MEXI CO	S	STATE	321 8	0	0
KOP Leg #1	110	FSL	436	FWL	20S	30E	2	Aliquot SWS W	32.59533 5	- 103.9499 71	EDD Y	NEW MEXI CO	NEW MEXI CO	S	STATE	- 481 6	805 3	803 4
PPP Leg #1	110	FSL	436	FWL	20S	30E	2	Aliquot SWS W	32.59533 5	- 103.9499 71	EDD Y	NEW MEXI CO	NEW MEXI CO	S	STATE	321 8	0	0

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
PPP Leg #1	357	FNL	0	FEL	20S	30E	3	Aliquot SESE	32.59599 1	- 103.9514 56	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 135240	- 528 0	864 2	849 8
PPP Leg #1	473	FNL	264 0	FEL	20S	30E	4	Aliquot SWSE	32.59649 6	- 103.9770 6	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 055423 3	- 518 2	165 69	840 0
PPP Leg #1	508	FSL	0	FEL	20S	30E	4	Aliquot SESE	32.59646 8	- 103.9514 56	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 000677 5A	- 521 4	139 51	843 2
EXIT Leg #1	500	FSL	330	FWL	20S	30E	4	Aliquot SWS W	32.59650 8	- 103.9845 04	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 055423 3	- 515 4	188 51	837 2
BHL Leg #1	500	FSL	330	FWL	20S	30E	4	Aliquot SWS W	32.59650 8	- 103.9845 04	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 055423 3	- 515 4	188 51	837 2



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

10/05/2018

APD ID: 10400027002

Submission Date: 02/07/2018

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Well Type: OIL WELL

Well Work Type: Drill

Highlighted data
reflects the most
recent changes.

[Show Final Text](#)

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	---	3218	0	0	OTHER : Quaternary caliche	USEABLE WATER	No
2	RUSTLER ANHYDRITE	2843	375	375		NONE	No
3	TOP SALT	2738	480	480		NATURAL GAS,CO2,OIL	No
4	TANSILL	1506	1712	1712	SANDSTONE	NONE	No
5	YATES	1382	1836	1836	SANDSTONE	NONE	No
6	SEVEN RIVERS	1083	2135	2135	GYPSUM	NONE	No
7	CAPITAN REEF	925	2293	2293	LIMESTONE	USEABLE WATER	No
8	DELAWARE	-401	3619	3619	SANDSTONE	NATURAL GAS,CO2,OIL	No
9	BONE SPRING	-3192	6410	6420	OTHER : Carbonate	NATURAL GAS,CO2,OIL	No
10	BONE SPRING 1ST	-4393	7611	7627	SANDSTONE	NATURAL GAS,CO2,OIL	No
11	BONE SPRING 2ND	-5121	8339	8388	SANDSTONE	NATURAL GAS,CO2,OIL	Yes
12	WOLFCAMP	-6526	9744	9744	OTHER : Shale	NATURAL GAS,CO2,OIL	No
13	WOLFCAMP	-6997	10215	10215	OTHER : Carbonate	OIL	No
14	STRAWN	-7754	10972	10972		NATURAL GAS,CO2,OIL	No

Section 2 - Blowout Prevention

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Pressure Rating (PSI): 2M

Rating Depth: 10000

Equipment: A 10,000' 2,000 psi and 5,000 psi BOPE system will be used below surface casing to TD. BOPE accessories will include a kelly cock, floor safety valve, inside BOP, choke manifold, and line

Requesting Variance? YES

Variance request: A variance is requested for the use of a diverter on the 26" section. A variance is requested for the use of a 20" 3M Annular on the 17 1/2" and 12 1/4" sections.

Testing Procedure: Independent service company will test BOP / BOPE to 250 psi low and the high pressure as listed above. System may be upgraded to a higher pressure, but still tested at % listed for component WP as listed above. If the system is upgraded, all the components for that section will be functional and tested. Pipe rams will be functionally checked each 24-hour period. Blind rams will be operationally checked on each TOH. These checks will be noted on the IADC records onsite.

Choke Diagram Attachment:

CH_1H_Choke_20180207103440.pdf

BOP Diagram Attachment:

CH_1H_BOP_20180207103751.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	CONDUCTOR	36	OTHER	NEW	API	N	0	80	0	80	3218		80	H-40	157.5	OTHER - Weld						
2	SURFACE	26	20.0	NEW	API	N	0	321	0	321	3218		321	J-55	94	OTHER - BTC	3.46	11.14	DRY	46.4	DRY	49
3	INTERMEDIATE	17.5	13.375	NEW	API	N	0	1880	0	1880	3218		1880	J-55	54.5	OTHER - BTC	1.29	2.46	DRY	8.87	DRY	8.32
4	INTERMEDIATE	12.25	9.625	NEW	API	N	0	3680	0	3680			3680	J-55	40	LTC	1.6	1.82	DRY	3.47	DRY	4.27
5	INTERMEDIATE	12.25	9.625	NEW	API	N	0	3680	0	3680			3680	J-55	40	LTC	1.6	1.82	DRY	3.47	DRY	4.27
6	PRODUCTION	8.75	5.5	NEW	API	N	0	18851	0	8372	3218		18851	P-110	20	OTHER - Atlas BK	3	1.2	DRY	2.2	DRY	2.1

Casing Attachments

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Casing Attachments

Casing ID: 1 **String Type:** CONDUCTOR

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Casing ID: 2 **String Type:** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

CH_1H_Casing_Design_Assumptions_20180207104317.pdf

Casing ID: 3 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

CH_1H_Casing_Design_Assumptions_20180207104446.pdf

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Casing Attachments

Casing ID: 4 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

CH_1H_Casing_Design_Assumptions_20180207104852.pdf

Casing ID: 5 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

CH_1H_Casing_Design_Assumptions_20180207105726.pdf

Casing ID: 6 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

CH_1H_Casing_Design_Assumptions_20180207104723.pdf

Section 4 - Cement

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
CONDUCTOR	Lead		0	80	0	0	0	0	0	Redi Mix	None

SURFACE	Lead		0	321	800	1.34	14.8	1072	100	Class C	2% PF01 (CACI2)
---------	------	--	---	-----	-----	------	------	------	-----	---------	-----------------

INTERMEDIATE	Lead		0	1880	1200	1.75	13.5	2100	100	Class C	4% PF120 (Gel) & 1% PF01 (CACI2) & 3# PF42 (Koalseal) & 1/8# PF29 (Cellophane)
INTERMEDIATE	Tail		0	1880	200	1.33	14.8	266	100	Class C	1% PF01 (CACI2)
INTERMEDIATE	Lead		0	3680	220	2.05	12.6	451	50	Class C 35/65 Poz	5% PF44 (Salt) & 6% PF20 (Gel) & 3# PF42 (Kolseal) & .4# PF45 (Defoam) & 1/8# PF29 (Cellophane)
INTERMEDIATE	Tail		0	3680	200	1.32	14.8	264	50	Class C	.2% PF13 (Retarder)
INTERMEDIATE	Lead		0	3860	350	2.05	12.6	717	50	Class C 35/65 Poz	5% PF44 (Salt) & 6% PF20 (Gel) & 3# PF42 (Kolseal) & .4# PF45 (Defoam) & 1/8# PF29 (Cellophane)
INTERMEDIATE	Tail		0	3680	200	1.32	14.8	264	50	Class C	.2% PF13 (Retarder)
PRODUCTION	Lead		0	1885 1	880	2.47	11.9	2173	25	Class H 50/50 Poz	5% PF44 (Salt) & 10% PF20 (Gel) & .2% PF153 (Anti-settle) & .4# PF45 (Defoam) & 3# PF42 (Koalseal) & 1/8# PF29 (Cellophane)
PRODUCTION	Tail		0	1885 1	2450	1.31	14.2	3209	25	Class H 50/50 Poz	5% PF44 (Salt) & 2% PF20 (Gel) & .3% FL & .1% PF813 (Retarder) & .2% PF65 (Dispersant) & .3% PF606 (Fluid Loss)

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials to maintain mud properties and meet minimum lost circulation (e. g., cedar bark) and weight increase (e. g., barite, bentonite) requirements will be on site at all times.

Describe the mud monitoring system utilized: A Pason, or similar, system will be used to monitor fluid loss or gain.

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	321	OTHER : Fresh water	8.4	9							
1880	3860	OTHER : Fresh water	8.4	8.7							
3860	1885 1	OTHER : Cut brine	8.4	9.5							
321	1880	OTHER : Brine water	10	10.1							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Mud logging program will be used from 3300' to TD. No open hole log is planned at this time. A gyro may be used from surface to first intermediate casing shoe if warranted. GR/MWD will be used from 80' to TD. Completion CBL may be run in vertical to free fall depth of curve 40+.

List of open and cased hole logs run in the well:

CBL,GR,MWD

Coring operation description for the well:

No core or drill stem test is planned.

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 4344

Anticipated Surface Pressure: 2474.44

Anticipated Bottom Hole Temperature(F): 140

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

CH_1H_H2S_Plan_20180207110611.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

CH_1H_Horizontal_Drill_Plan_20180207103027.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:

CH_1H_General_Drill_Plan_20180207103039.pdf


CH_1H_Speedhead_Specs_20180207103727.pdf

Other Variance attachment:


Choke Manifold

1


Minimum Configuration of Choke Side



LOCATION: Approximately 15 miles NE of Carlsbad NM
COUNTY: Eddy STATE: New Mexico
RIG NAME & No. Any Rig



LOCATION: Approximately 15 miles NE of Carlsbad NM
COUNTY: Eddy STATE: New Mexico



Coflex Hose Certification



Field Technology
Quality Document

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE				CERT. NO: 746	
PURCHASER: Phoenix Beattie Co.				P.O. NO: 002491	
CONTITECH ORDER NO: 412638		HOSE TYPE: 3" ID Choke and Kill Hose			
HOSE SERIAL NO: 52777		NOMINAL / ACTUAL LENGTH: 10,67 m			
W.P. 68,98 MPa 10000 psi		T.P. 103,4 MPa 15000 psi		Duration: 60 - min.	
<p>Pressures test with water at ambient temperature</p> <p>Ses attachment (1 page)</p> <p>↑ 10 mm = 10 MPa → 10 mm = 25 MPa</p>					
COUPLINGS					
Type	Serial N°		Quality	Heat N°	
3" coupling with 4 1/16" Flange end	917	913	API 4130 API 4130	T7690A 26084	
INFOCHIP INSTALLED				API Spec 18 C Temperature rate: "B"	
All metal parts are stainless					
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.					
Date:	Inspector		Quality Control		
04. April. 2008			Continental Rubber Inspection Dept Quality Control Dept (10)		

Collex Hose Certification

Collex Hose
100% Virgin
Polyethylene
100% Virgin
Polyethylene
100% Virgin
Polyethylene

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----

Cofflex Hose Certification

Form No 100/1.2

PHOENIX Beattie

Phoenix Beattie Corp

11131 Grimsdon Park Drive
Tulsa, OK 77411
Tel: (820) 877-4100
Fax: (820) 877-4100
E-mail: sales@phoenixbeattie.com
www.phoenixbeattie.com

Delivery Note

Customer Order Number	376-359-001	Delivery Note Number	003078	Page	1
Customer / Invoice Address HELMERICH & PAYNE INT'L DRILLING CO 1437 SOUTH BOULDER TULSA, OK 74119		Delivery / Address HELMERICH & PAYNE JOC ATTN: JOE STEPHENSON - RIG 370 13609 INDUSTRIAL ROAD INDUSTRIA, TX 77015			

Customer Acc No	Phoenix Beattie Contract Manager	Phoenix Beattie Reference	Date
801	JJL	006330	05/23/2008

Item No	Beattie Part Number / Description	Qty Ordered	Qty Sent	Qty To Follow
1	HP100K3A-35-4F1 3" 10K 16G C&S HOSE x 35ft OAL CM 4.1/16" API SPEC FLANGE E/ End 1: 4.1/16" 10Kpsi API Spec 6A Type 60X Flange End 2: 4.1/16" 10Kpsi API Spec 6A Type 68X Flange C/w BX155 Standard ring groove at each end Suitable for H2S Service Working pressure: 10,000psi Test pressure: 15,000psi Standard: API 16G Full specification Armor Guarding: Included Fire Rating: Not Included Temperature rating: -20 Deg C to +160 Deg C	1	1	0
2	SECK3-HPP3 LIFTING & SAFETY EQUIPMENT TO SUIT HP100K3-35-F1 2 x 160mm ID Safety Clamps 2 x 240mm ID Lifting Collars & element C's 2 x 7ft Stainless Steel wire rope 3/4" CD 4 x 7.75t Shackles	1	1	0
3	SC725-20JCS SAFETY CLAMP 200MM 7.25T C/S GALVANISED	1	1	0

Production Tree



Crazy Horse 1H, 2H, 3H, 4H

Production Tree

2-9/16"-5M

Quote# WH170816-01D

Upper Tree Assembly 2-9/16" (FE)

A5P-EN 7-1/16"-10M X 2-9/16"-5M, DD

TC1A-EN HGR 7-1/16"-10M X 2-7/8"

8Rd EUE Top, w/ 2-7/8" 8Rd EUE Btm, DD


Gate Valve, 2-9/16"-5M, DD Run

Tee, 2-9/16"-5M x 2-1/16"-5M, DD

Gate Valve, 2-1/16"-5M, DD Wing

Adjustable Choke 2-1/16-5M FE X FE, DD,

WEECO 2-1/16"-5M x 2" 1502, DD



TC1A-EN Hanger

7-1/16"-10M X 2-7/8" EUE Top

w/ 2-7/8" 8Rd EUE Bottom, DD



SY ENERGY

WELLHEAD & FRAC

email sales@syenergypg.com

5.5 20# P110 BK Connection Data



Precision Connections BK-HT

5.5 in. 20 lb/ft P-110 with 6.3 in. Coupling OD

Pipe Body

Nominal OD	5.500	inches
Nominal Weight	20.00	lb/ft
Wall Thickness	0.361	inches
Plain End Weight	19.81	lb/ft
Drift	4.653	inches
Nominal ID	4.778	inches
Grade	P-110	
Min Yield	110,000	lb/in ²
Min Tensile	125,000	lb/in ²
Critical Section Area	5.828	in ²
Pipe Body Yield Strength	641	kips
Min Internal Yield Pressure	12,640	psi
Collapse Pressure	11,100	psi

Connection

Coupling OD	6.300	inches
Coupling Length	8.250	inches
Make Up Loss	4.125	inches
Critical Section Area	8.456	in ²
Internal Pressure Rating	100%	
External Pressure Rating	100%	
Tension Efficiency	100%	
Connection Strength	641	kips
Compression Efficiency	100%	
Uniaxial Bend Rating	80.0	° / 100 ft
Min Make Up Torque	8,300	ft-lbs
Yield Torque	32,000	ft-lbs

This documentation contains confidential and proprietary information not to be reproduced or divulged in whole or in part to anyone outside of your company without prior written authorization from Precision Connections, LLC, and such documentation and information is provided to you upon such conditions of confidentiality.

v1.1

10/10/2016




Torque Data Sheet - Precision Connections BK-HT

5.5 in. 20 lb/ft P-110 with 6.3 in. Coupling OD

Min Make Up Torque	8,300	ft-lbs
Max Make Up Torque	24,000	ft-lbs
Optimum Torque	11,500	ft-lbs
Max Operating Torque	27,200	ft-lbs
Yield Torque	32,000	ft-lbs

Representative Torque Turn Graph




v1.1

10/10/2016

Precision Connections BK

Semi Premium Connection

Designed Primarily for High Torque Frac Strings



Better Buttress Sealing Modified buttress thread for tighter thread sealing and pin nose seal stabilization.

• API Thread Tolerance – Verified fit of several major insert manufacturers.

• BK Thread Tolerance – Minimizes thread gap for better thread sealing. Uses a Custom Premium Insert.



Advanced Relief Groove ensures more threads are engaged for maximum sealing. The thicker midpoint cross sectional area provides additional coupling strength.

BK Relief Groove



Dark areas indicate unengaged thread regions

First Generation Relief Groove



• **Strength Pin Nose to Pin Nose** contact for high torque resistance, higher pressure ratings, higher bending loads and higher structural compressive loading. Smooth Premium Bore with no I-Area to get hung up on.



BK




Buttress



Pressure ↑



High RPM Fatigue Resistance from Low Stress Runout Threads The BK uses the field proven buttress thread with low stress runout threads to extend the time it can be rotated through a dogleg at high RPM.



Crazy Horse 03 - 04 Fed Com	# 1H

	Burst	Collapse	Joint
Per BLM	1,000	1,125	1,600
			1,800
			(Soaked)

Csg Size	Set Depth TWD	Set Depth MD	Grade	Weight	Conn Collapse	Burst	Conn Yield	Body Yld	M/JD Air Weight	TVD Air Weight	Drill Mud Weight	Mud Gradient	Cnt Weight	Cnt Gradient	Frac Gradient	Gas Gradient
13 3/8"	1980	1880	JFS	54.5	BIC	1.130	2.730	9095.000	1853.000	102.460	102.460	-10.00 ^{psi}	34.20	0.74	0.70	0.11
(will use NM allowed 1.125)																
SH Safety Factor Collapse	1.20	Mud			Collapse / TVD * MG	1.16										
	1.20	Cement			Collapse / TVD * CG - MG	2.75										
SH Safety Factor Burst	1.30	Mud			Burst / TVD * FG - GG	2.46										
SH Safety Factor Conn	1.80	Top Joint			Conn Yd / MD * Wt	8.87										
SH Safety Factor Body	2.00	Top Joint			Body Yd / MD * Wt	8.33										

Burst	Collapse	Joint
3.000	1.125	2.000 (Dry)
		1.000 (Borred)

Per BLM	Burst	Collapse	Joint	
	1,000	1,125	1,600	(Dry)
			1,800	(Bouryed)

[illegible]

	Burst	Collapse	Joint
Per BLM	1.000	1.125	1.600 (Dry)
			1.800 (Bourved)

Csg Site	Set Depth	Set Depth	Set Depth	Grade	Weight	Conn	Collapse	Burst	Conn Yield	Body Yield	MD Air Weight	TVD Air Weight	Drig Mud Weight	Mud Gradient	Cmt Weight	Cmt Gradient	Frac Gradient	Gas Gradient
5- 1/2"	8795	18851	P110	20	Atlas Bk	11,100	12,640	667,080	661,000	377,020	175,900	9,50	0.49	13.05	0.68	0.70	0.11	

SH Safety Factor Collapse	1.20	Cement	Collapse / TVD * MG	5.84	Actual Safety factors
	1.70	Cement	Collapse / TVD * CG * MG	6.84	
SH Safety Factor Burst	1.30	Mud	Burst / TVD * FG * GG	2.44	
	1.80	Top Joint	Conn Yd / MD * Wt	1.77	Conn Yd @ CurveTVD
SH Safety Factor Conn	2.00	Top Joint	Body Yd / MD * Wt	1.70	Conn Yd @ CurveTVD
	2.00	Top Joint	Body Yd / MD * Wt	1.70	Actual Safety Factors

Per BJM	Burst	1,000	Joint	1,125	1,600	(Dry)	1,800	(Barrel)

Minimum MU Torque	6,000	ftlbs
Maximum MU Torque	17,250	ftlbs
Optimum MU Torque	8,300	ftlbs
Max Operating Torque	19,550	ftlbs
Yield Torque	23,000	ftlbs

Per BLM	Burst	Collapse	Joint	
	1.000	1.125	1.600	(Dry)
			1.800	(Bourbed)

Crazy Horse 03:- 04 Fed Com

1H :

Int 1																	
Cdg Size	Set Depth	Set Depth	Grade	Weight	Conn	Collapse	Burst	Conn Yield	Body Yield	MD Air Weight	TD Air Weight	Drift Mud Weight	Mud Gradient	Cmt Weight	Cmt Gradient	Frac Gradient	Gas Gradient
13 3/8"	1880	1880	J55	54.5	DTG	1.130	2,130	909,000	353,000	102,460	102,460	770,000	0.52	11.20	0.74	0.70	0.11
S1 Safety Factor Collapse				1.20	Mud	Collapse / TD - MG	1.16										
S1 Safety Factor Burst				1.50	Mud	Burst / TD - CG - MG	2.75										
S1 Safety Factor Conn				1.80	Top Joint	Conn Yd / MD - WT	8.87										
S1 Safety Factor Body				2.00	Top Joint	Body Yd / MD - WI	8.33										
						Actual Safety factor											
(with use NIM allowed 1.125)																	
										Burst	Collapse	Joint					
										Per Blm	1.000	1.125	1.600	(Dpy)			
												1.800	(boveyd)				

Production																																																																																																																																																																																																																																																																																															
Cage Size	Set Depth TVD	Set Depth MD	Grade	Weight	Conn	Collapse	Burst	Conn Yield	Reel Yield	MD Air Weight	TVD Air Weight	Dwg Mud Weight	Mud Gradient	Cmt Weight	Cmt Gradient	Frac Gradient	Gas Gradient																																																																																																																																																																																																																																																																														
5-1/2"	8795	18851	P-10	20	AHSS BK	11.100	12.560	667,000	6541000	377,020	175,900	9.50	0.49	13.0%	0.68	0.70	0.11																																																																																																																																																																																																																																																																														
<table><tr><td>Sst Safety Factor Collapse</td><td>1.20</td><td>Mud</td><td>Collapse / TVD * MG</td><td>2.55</td><td colspan="13"></td></tr><tr><td>Sst Safety Factor Burst</td><td>1.30</td><td>Cement</td><td>Collapse / TVD * CG -MG</td><td>6.84</td><td colspan="13"></td></tr><tr><td>Sst Safety Factor Conn</td><td>1.30</td><td>Mud</td><td>Burst / TVD * FG -GG</td><td>2.44</td><td colspan="13"></td></tr><tr><td>Sst Safety Factor Body</td><td>1.80</td><td>Top Joint</td><td>Conn Yd / MD * WT</td><td>1.77</td><td colspan="13"></td></tr><tr><td>Sst Safety Factor Body</td><td>2.00</td><td>Top Joint</td><td>Body Yd / MD * WT</td><td>1.70</td><td colspan="13"></td></tr><tr><td></td><td></td><td></td><td>Conn Yd @ Curve TVD</td><td>3.79</td><td colspan="13"></td></tr><tr><td></td><td></td><td></td><td>Body Yd @ Curve TVD</td><td>3.64</td><td colspan="13"></td></tr><tr><td></td><td></td><td></td><td>Actual Safety Factors</td><td></td><td colspan="13"></td></tr><tr><td colspan="4"></td><td>Per Blm</td><td>L.000</td><td>L.135</td><td>bolt</td><td>1.600</td><td>(dry)</td><td colspan="8"></td></tr><tr><td colspan="4"></td><td></td><td>1.000</td><td>1.135</td><td>bolt</td><td>1.800</td><td>(Boreal)</td><td colspan="8"></td></tr><tr><td colspan="4"></td><td></td><td colspan="4"></td><td>Maximum MU Torque</td><td>6,000</td><td>fibs</td><td colspan="6"></td></tr><tr><td colspan="4"></td><td></td><td colspan="4"></td><td>Maximum MU Torque</td><td>12,250</td><td>fibs</td><td colspan="6"></td></tr><tr><td colspan="4"></td><td></td><td colspan="4"></td><td>Optimum MU Torque</td><td>8,300</td><td>fibs</td><td colspan="6"></td></tr><tr><td colspan="4"></td><td></td><td colspan="4"></td><td>Max Operating Torque</td><td>19,550</td><td>fibs</td><td colspan="6"></td></tr><tr><td colspan="4"></td><td></td><td colspan="4"></td><td>Yield Torque</td><td>23,000</td><td>fibs</td><td colspan="6"></td></tr></table>																		Sst Safety Factor Collapse	1.20	Mud	Collapse / TVD * MG	2.55														Sst Safety Factor Burst	1.30	Cement	Collapse / TVD * CG -MG	6.84														Sst Safety Factor Conn	1.30	Mud	Burst / TVD * FG -GG	2.44														Sst Safety Factor Body	1.80	Top Joint	Conn Yd / MD * WT	1.77														Sst Safety Factor Body	2.00	Top Joint	Body Yd / MD * WT	1.70																	Conn Yd @ Curve TVD	3.79																	Body Yd @ Curve TVD	3.64																	Actual Safety Factors																			Per Blm	L.000	L.135	bolt	1.600	(dry)														1.000	1.135	bolt	1.800	(Boreal)																		Maximum MU Torque	6,000	fibs																Maximum MU Torque	12,250	fibs																Optimum MU Torque	8,300	fibs																Max Operating Torque	19,550	fibs																Yield Torque	23,000	fibs						
Sst Safety Factor Collapse	1.20	Mud	Collapse / TVD * MG	2.55																																																																																																																																																																																																																																																																																											
Sst Safety Factor Burst	1.30	Cement	Collapse / TVD * CG -MG	6.84																																																																																																																																																																																																																																																																																											
Sst Safety Factor Conn	1.30	Mud	Burst / TVD * FG -GG	2.44																																																																																																																																																																																																																																																																																											
Sst Safety Factor Body	1.80	Top Joint	Conn Yd / MD * WT	1.77																																																																																																																																																																																																																																																																																											
Sst Safety Factor Body	2.00	Top Joint	Body Yd / MD * WT	1.70																																																																																																																																																																																																																																																																																											
			Conn Yd @ Curve TVD	3.79																																																																																																																																																																																																																																																																																											
			Body Yd @ Curve TVD	3.64																																																																																																																																																																																																																																																																																											
			Actual Safety Factors																																																																																																																																																																																																																																																																																												
				Per Blm	L.000	L.135	bolt	1.600	(dry)																																																																																																																																																																																																																																																																																						
					1.000	1.135	bolt	1.800	(Boreal)																																																																																																																																																																																																																																																																																						
									Maximum MU Torque	6,000	fibs																																																																																																																																																																																																																																																																																				
									Maximum MU Torque	12,250	fibs																																																																																																																																																																																																																																																																																				
									Optimum MU Torque	8,300	fibs																																																																																																																																																																																																																																																																																				
									Max Operating Torque	19,550	fibs																																																																																																																																																																																																																																																																																				
									Yield Torque	23,000	fibs																																																																																																																																																																																																																																																																																				

Crazy Horse 03 - 04 Fed Com	# 1H	:	:	:
-----------------------------	------	---	---	---

Int 1																											
Csg Size	Set Depth TYD	Set Grade	Weight	Conn	Collapse Burst	Conn -Yield	Body Yield	JMD Air Weight	VVD Air Weight	Drg Mud Weight	Mud Gradient	Cnt Weight	Cnt Gradient	Frac Gradient	Gas Gradient												
13 3/8"	1880	MD	54.5	B/C	1,130 2,730	909,000	553,000	102,460	102,460	102,460	0.52	14.20	0.74	0.70	0.11												
SH Safety Factor Collapse																											
1.20	Mud	Collapse / TYD * MG	1.16																								
1.20	Cement	Collapse / TYD * CG - MG	2.75																								
SH Safety Factor Burst	1.30	Mud Burst / TYD * GG - SG	2.46																								
SH Safety Factor Conn	1.80	Top Joint Conn Vd / MD * W	8.87																								
SH Safety Factor Body	2.00	Top Joint Body Vd / MD * W	8.33																								
Actual Safety factor																											
(well use NMA allowed 1.125)																											
<table><tr><td></td><td>Burst</td><td>Collapse</td><td>Joint</td></tr><tr><td>Per BLM</td><td>1.000</td><td>1.125</td><td>1.600 (Drg)</td></tr><tr><td></td><td></td><td></td><td>1.800 (Revised)</td></tr></table>																	Burst	Collapse	Joint	Per BLM	1.000	1.125	1.600 (Drg)				1.800 (Revised)
	Burst	Collapse	Joint																								
Per BLM	1.000	1.125	1.600 (Drg)																								
			1.800 (Revised)																								

Production																																																																													
Cig Size	Set Depth	Set Depth MO	Grade	Weight	Conn	Collapse	Burst	Conn Yield	Body Yield	MD Air Weight	TD Air Weight	Dwg Mud Weight	Mud Gradient	Cmt Weight	Cmt Gradient	Fac Gradient	Gas Gradient																																																												
5.42"	8.75	18851	P110	20	Atlas BK	11,100	12,640	667,080	641,000	377,020	175,900	9.50	0.49	13.05	0.68	0.70	0.11																																																												
SH Safety Factor Collapse	1.20	Mud	Collapse / TVD * CG	2.55	6.54	Actual Safety Factors																																																																							
SH Safety Factor Burst	1.20	Cement	Collapse / TVD * FG - MG	2.44	6.84																																																																								
SH Safety Factor Conn	1.80	Mud	Burst / TVD * FG - FG	2.44																																																																									
SH Safety Factor Body	1.80	Top Joint	Conn / Vd / MD * Vt	1.77																																																																									
	2.00	Top Joint	Conn / Vd / MD * Vt	1.70																																																																									
			Body / Vd @ Curve / TVD	3.79																																																																									
			Body / Vd @ Curve / TVD	3.64																																																																									
			Actual Safety Factors																																																																										
<table><tr><th colspan="2">Per BLM</th><th>Burst</th><th>Collapse</th><th>Joint</th><th>Joint</th></tr><tr><th></th><th>1,000</th><th></th><th>1,135</th><th></th><th>(Dn)</th></tr><tr><td colspan="2"></td><td colspan="2"></td><td>1,800</td><td>(Bore)</td></tr><tr><td colspan="5"></td><td>Minimum MU Torque</td></tr><tr><td colspan="5"></td><td>Maximum MU Torque</td></tr><tr><td colspan="5"></td><td>Optimum MU Torque</td></tr><tr><td colspan="5"></td><td>Max Operating Torque</td></tr><tr><td colspan="5"></td><td>Wear Torque</td></tr><tr><td colspan="5"></td><td>23,000</td></tr><tr><td colspan="5"></td><td>ft/lbs</td></tr></table>																		Per BLM		Burst	Collapse	Joint	Joint		1,000		1,135		(Dn)					1,800	(Bore)						Minimum MU Torque						Maximum MU Torque						Optimum MU Torque						Max Operating Torque						Wear Torque						23,000						ft/lbs
Per BLM		Burst	Collapse	Joint	Joint																																																																								
	1,000		1,135		(Dn)																																																																								
				1,800	(Bore)																																																																								
					Minimum MU Torque																																																																								
					Maximum MU Torque																																																																								
					Optimum MU Torque																																																																								
					Max Operating Torque																																																																								
					Wear Torque																																																																								
					23,000																																																																								
					ft/lbs																																																																								

Crazy Horse 03 - 04 Fed Com

Int 1																													
Csg Size	Set Depth TND	Set Depth MD	Grade	Weight	Conn	Collapse	Burst	Conn Yield	Body Yield	210 Air Weight	TVD Air Weight	Drft Mud Weight	Mud Gradient	Cnt Weight	Cnt Gradient	Frac Gradient	Gas Gradient												
13 3/8"	1880	1880	155	54.5	01C	1.130	2.7303	909,000	533,000	102,460	102,460	7.10 00F	0.52	14.20	0.74	0.70	0.11												
S1 Safety Factor Collapse																													
	1.20	Mud		Collapse / TND * MG		1.16																							
S1 Safety Factor Burst	1.30	Mud		Collapse / VND * RG * GG		2.75																							
S1 Safety Factor Conn	1.80	Top Joint		Conn tv / MTD * Wt		8.87																							
S1 Safety Factor Body	2.00	Top Joint		Body tv / MD * Wt		8.33																							
Actual Safety factor																													
(wall use NM allowed 1.125)																													
<table><tr><td>Burst</td><td>Collapse</td><td>Joint</td></tr><tr><td>Per BLM</td><td>1.000</td><td>1.125</td></tr><tr><td></td><td></td><td>1.600 (DN)</td></tr><tr><td></td><td></td><td>1.800 (Borey)</td></tr></table>																		Burst	Collapse	Joint	Per BLM	1.000	1.125			1.600 (DN)			1.800 (Borey)
Burst	Collapse	Joint																											
Per BLM	1.000	1.125																											
		1.600 (DN)																											
		1.800 (Borey)																											

Production																																																																								
Cup Size	Set Depth	Set Grade	Weight	Conn MD	Collapse Burst	Conn Yield	Body Yield	MD Air Weight	TVD Air Weight	Mud Gradient	Cnt Weight	Cnt Gradient	Trac Gradient	Gas Gradient																																																										
5 1/2"	8735	18851	2-10	20	48lbs BK	11.100	115400	567,000	641,000	377,020	113,900	9.30	0.49	13.05	0.68	0.70	0.11																																																							
<table><tr><th colspan="4">SI Safety Factor Collapse</th><th colspan="4">SI Safety Factor Burst</th><th colspan="4">SI Safety Factor Conn</th><th colspan="4">SI Safety Factor Body</th><th colspan="4">SI Safety Factor MD</th><th colspan="4">SI Safety Factor Mud</th><th colspan="4">SI Safety Factor Gas</th></tr><tr><th>1.20</th><th>Mud</th><th>Collapse / TVD * MG</th><th>2.55</th><th>1.20</th><th>Mud</th><th>Collapse / TVD * CG * MG</th><th>6.84</th><th>1.20</th><th>Mud</th><th>Collapse / TVD * WG * MG</th><th>2.44</th><th>1.20</th><th>Mud</th><th>Collapse / TVD * WG * MG</th><th>1.77</th><th>1.20</th><th>Mud</th><th>Conn Yd @ Curve</th></tr></table>																	SI Safety Factor Collapse				SI Safety Factor Burst				SI Safety Factor Conn				SI Safety Factor Body				SI Safety Factor MD				SI Safety Factor Mud				SI Safety Factor Gas				1.20	Mud	Collapse / TVD * MG	2.55	1.20	Mud	Collapse / TVD * CG * MG	6.84	1.20	Mud	Collapse / TVD * WG * MG	2.44	1.20	Mud	Collapse / TVD * WG * MG	1.77	1.20	Mud	Conn Yd @ Curve	YTD	3.79	Actual Safety Factors	1.20	Mud	Body Yd @ Curve <th>YTD</th> <th>3.64</th> <th>Actual Safety Factors</th>	YTD	3.64	Actual Safety Factors
SI Safety Factor Collapse				SI Safety Factor Burst				SI Safety Factor Conn				SI Safety Factor Body				SI Safety Factor MD				SI Safety Factor Mud				SI Safety Factor Gas																																																
1.20	Mud	Collapse / TVD * MG	2.55	1.20	Mud	Collapse / TVD * CG * MG	6.84	1.20	Mud	Collapse / TVD * WG * MG	2.44	1.20	Mud	Collapse / TVD * WG * MG	1.77	1.20	Mud	Conn Yd @ Curve																																																						
Actual Safety Factors				Actual Safety Factors				Actual Safety Factors				Actual Safety Factors				Actual Safety Factors				Actual Safety Factors				Actual Safety Factors																																																


| | Per BLM | | Burst | | Collapse Joint | | Joint | | Dry | | Wet | | Wet | | Wet | | Wet | | |----------------------|-------|----------------------|-------|----------------------|-------|----------------------|-------|----------------------|-------|----------------------|-------|----------------------|-------|----------------------|-------|----------------------|-------| | 1.000 | 1.125 | 1.000 | 1.125 | 1.000 | 1.125 | 1.000 | 1.125 | 1.000 | 1.125 | 1.000 | 1.125 | 1.000 | 1.125 | 1.000 | 1.125 | 1.000 | 1.125 | | Minimum MU Torque | | Minimum MU Torque | | Minimum MU Torque | | Minimum MU Torque | | Minimum MU Torque | | Minimum MU Torque | | Minimum MU Torque | | Minimum MU Torque | | Minimum MU Torque | | | 12,250 | | 12,250 | | 12,250 | | 12,250 | | 12,250 | | 12,250 | | 12,250 | | 12,250 | | 12,250 | | | Optimum MU Torque | | Optimum MU Torque | | Optimum MU Torque | | Optimum MU Torque | | Optimum MU Torque | | Optimum MU Torque | | Optimum MU Torque | | Optimum MU Torque | | Optimum MU Torque | | | 8,300 | | 8,300 | | 8,300 | | 8,300 | | 8,300 | | 8,300 | | 8,300 | | 8,300 | | 8,300 | | | 13,500 | | 13,500 | | 13,500 | | 13,500 | | 13,500 | | 13,500 | | 13,500 | | 13,500 | | 13,500 | | | Max Operating Torque | | Max Operating Torque | | Max Operating Torque | | Max Operating Torque | | Max Operating Torque | | Max Operating Torque | | Max Operating Torque | | Max Operating Torque | | Max Operating Torque | | | 23,000 | | 23,000 | | 23,000 | | 23,000 | | 23,000 | | 23,000 | | 23,000 | | 23,000 | | 23,000 | | | Yield Torque | | Yield Torque | | Yield Torque | | Yield Torque | | Yield Torque | | Yield Torque | | Yield Torque | | Yield Torque | | Yield Torque | | | 23,000 | | 23,000 | | 23,000 | | 23,000 | | 23,000 | | 23,000 | | 23,000 | | 23,000 | | 23,000 | | | | | | | | | | | | | | | | | | |



CL&F Operating LLC

Crazy Horse 03-04 Fed Com #1H
SURFACE LOCATION 110' FSL & 436' FWL
SECTION 2 T20S R30E
EDDY COUNTY, NEW MEXICO
Latitude: N 32.595335 Longitude: W-103.949971

"CONTINGENCY PLAN"



422 West Main street suite 6
Artesia, New Mexico
(575)746/1096 (432)363/0198 fax

WELL CONTROL EMERGENCY RESPONSE PLAN

CL&F OPERATING LLC

CUSTOMER COPY



Permit Number:	Date issue:	District- NM
API #:	Form W-1 Rec-	County-EDDY
Type: New Drill	ACRES-	

<u>Operator</u> CL&F Operating LLC	
---------------------------------------	--

Lease Name: Crazy Horse 03-04 Fed Com

Well Number: 1H

Location:

Total Depth: TVD 8372' MDTD 18851'

Section: SECTION 2 T20S R30E

Abstract:

Surface Location: 110' SOUTH 436' WEST

Dist to Nearest Lease Line 110'

Dist to Nearest Well:

Directions: Approximately 15 miles NE of Carlsbad, NM.

THIS PERMIT IS GRANTED PURSUANT TO BUREAU OF LAND MANAGEMENT 43 CFR 3160
ONSHORE OIL AND GAS ORDER NO. 6 HYDROGEN SULFIDE OPERATIONS

=

Permit Plat:

CL&F Operating LLC

Crazy Horse 03-04 Fed Com #1H

Location in Survey: 110' FSL & 436' FWL in SECTION 2 T20S R30E

EDDY COUNTY, NEW MEXICO

This is a Hydrogen Sulfide field and shall be drilled in accordance with BLM ONSHORE
ORDER NO. 6

*****Information in this section was provided to American Safety Services Inc. by**

Sierra-Hamilton.***

CL&F OPERATING LLC Emergency Contact List

Division & Title	Name	Office	Residence	Cellular
<i>Drilling Operations</i>	Russ Ginanni	432.425.7450	432.218.6473	432.425.7450
Wellsite Supervisor	TBD			
Field Superintendent	TBD			
Engineer	TBD			
Drilling Manager	Mark Stover	281.873.9378		281.352.0391
Geologist	Mark Parrott	281.873.3033		713.560.7707
Land	Allison Gill	281.873.3013		337.302.7188
Public Safety	Facility	Contact	Direct	Cellular
<i>EDDY COUNTY:</i>				
Sheriff Department	Artesia, NM		575-746-9888	
Fire Department	Artesia, NM		575-746-2701	
Ambulance	Artesia, NM		911	
State Police	Artesia, NM		575-746-2703	
City Police	Artesia, NM		575-746-2703	
Sheriff Department	Carlsbad, NM		575-887-7551	
Fire Department	Carlsbad, NM		575-885-2111	
Ambulance	Carlsbad, NM		911	
State Police	Carlsbad, NM		575-885-3137	
City Police	Carlsbad, NM		575-885-2111	
Hospital	Carlsbad, NM		575-887-4121	
Flight for Life	CARLSBAD, NM		800.242.6199	
AEROCARE	ARTESIA, NM		800.800.0900	

Latitude	N 32.595357			
Longitude	W -103.94876			
Safety Contractor	Name	Office	Residence	Cellular
American Safety		575.746.1096		
Safety Supervisor NM	Tell Montoya	575.746.1096	575.749.0009	432.653.3866
Safety Manager NM	Andres Holguin	575.746.1096	575.202.2720	575.513.5033
Owner	Kevin Hokett	575.746.1096	432.363.3911	432.208.4372

DIRECTIONS: FROM CARLSBAD NM TAKE HWY 62/180 EAST FOR 16 MILES TO HWY 360 TURN NORTH FOR 8 MILES TO CR 222 (SHUGART RD.) TURN RIGHT (EAST) FOR .1 MILES TO LEASE ROAD ON RIGHT FOLLOW LEASE RD TO LOCATION.

TABLE OF CONTENTS

EXECUTIVE SUMMARY	7
RESPONSE LEVELS	8
LEVEL 1 WELL CONTROL INCIDENTS	8
LEVEL 2 WELL CONTROL INCIDENT	10
LEVEL 3 WELL CONTROL INCIDENTS	14
DUTIES AND RESPONSIBILITIES, RIG SUPERVISOR	19
EXAMPLE OF WORK ZONES	24
APPENDIX	25

Additional H2s information is included at the end of the plan.....

Prepared by:

American Safety Services Inc

422 west main street suite 6

Artesia, New Mexico 88210

This publication is confidential and proprietary. Any part thereof may not be reproduced or transmitted in any form or by any other means, electronic or mechanical, including photocopying, recording, storage in an information retrieval system, or otherwise, without the prior written permission of *American Safety Services Inc.*

Executive Summary

This plan is intended to document **CL&F Operating LLC** procedures for dealing with well control emergency situations. American Safety Services Inc encourages taking all preventative measures required to reduce the probability of a well control incident from occurring. If it does occur, however, this pre-developed strategic action plan can be implemented quickly and decisively in response to the emergency. It is intended to supplement the **CL&F Operating LLC** Emergency Procedure and other similar plans.

This Well Control Emergency Response Plan (WCERP) was formulated during low-stress, non-emergency conditions. It is our experience that those response actions hastily grasped during the event suffer from the panic, confusion and indecisiveness of persons not normally involved with high-stress situations.

In any emergency response plan the health and safety of people is the prime concern. Generally, persons not familiar with highly specialized oil well firefighting, capping and dealing with the high pressures and flow rates associated with blow-outs should not attempt to handle one of these events. Guidelines for early response procedures are included to mitigate risks, losses and damages, however.

There are three incident levels for which an emergency well control response is required. These levels are based on the severity and potential impacts of the incident. They are simply labeled Level 1, Level 2 and Level 3, with Level 1 being the least serious and Level 3 the worst. Level 3 denotes a complete loss of well control with no opportunity for regaining it using equipment and procedures available on-site. These correspond roughly to the Emergency Categories listed in the General Emergency Procedure.

In dealing with a well control emergency response, each person has duties and responsibilities. All critical tasks must be delegated to one person with minimal overlap. Thus, each responsibility is handled effectively without undue duplication.

The on-site organization is supervised and controlled by the Team Leader for the rig involved in the blow-out. The overall situation is controlled by the Manager over the area in which the blowout occurs who will serve as the Incident Commander. For most operations this will be the Manager (Drilling Operations) or the Manager (Exploration). These are individuals with long experience who are familiar with

CL&F Operating LLC's drilling and workover operations, corporate internal structure, corporate culture, personnel, various support services, and the capabilities of all emergency response groups including American Safety Services Inc. Each commander is assisted by several deputies, each of whom deals with responsibilities in their areas of expertise. This provides the most efficient and effective method of dealing with the emergency, protecting human lives and health, mitigating damages, and protecting the environment.

Response Levels

This plan involves three types of incidents classified as Level 1, Level 2 and Level 3 depending on the seriousness of the incident. A **Level 1** incident involves an uncomplicated kick that requires only normal operating procedures by the

CL&F Operating LLC Rig Supervisor (Company Man) and the drilling crew with notification to the Team Leader (TL) having supervisory authority over that rig. A **Level 2** incident involves a complication of some type that requires extraordinary measures to be taken by the Company Man, drilling contractor personnel, the TL, Sr. Drilling Engineer and, in some instances, American Safety Services Inc to successfully deal with the situation. A **Level 3** incident involves the complete loss of well control. Response to this type incident requires declaration of a Major Incident, activation of the Well Control Organization within **CL&F Operating LLC** and all the personnel listed below to provide On-Scene Command at the site, Headquarters Control, Support Services and Operations Engineering Support.

Level 1 Well Control Incidents

Characteristics

Definition

A Level 1 incident is defined as a well control problem that occurs during drilling or workover operations for which formal or informal standard operating procedures (SOPs) exist to control the event. There are no injuries or fires associated with this type incident and the situation can be brought under control using only the resources available on-site.

Action Requirement	These SOPs are executed by the rig crewmembers under the supervision of the toolpusher and CL&F Operating LLC Drilling Supervisor. The appropriate Team Leader is notified about the incident and the actions taken to control it. Support is rarely required from Drilling Services or from the well control services contractor unless the event escalates to a more serious level.
---------------------------	--

Examples

Drilling- related incidents	<ul style="list-style-type: none"> • An uncomplicated kick • Complete loss of circulation (e.g., >500 bph) with hydrocarbon zone open • Leak in casing with a permeable hydrocarbon zone open
Completion- or Workover- related incidents	<ul style="list-style-type: none"> • Unable to kill a well to start a workover • Tripping with high loss rate (e.g., >250 bph) • A kick taken after the well is killed • Hole in surface/intermediate/production casing due to corrosion or damage • Swabbing the well in during pipe tripping
Production- related incidents	<ul style="list-style-type: none"> • Pressure on production casing that cannot be bled down • Small leak on master valve, swab valve or wing valve on tree • Erosion and failure of the vent line to the pit, tank or test unit • Master valve frozen or stem broken with valve in closed position
Simultaneous operations incidents	<ul style="list-style-type: none"> • Moving in rig or workover unit with wellhead damage due to collision • Wellhead damage during heavy lift operations while installing BOPs, wireline lubricator, coiled tubing, etc. • Close approach/near miss drilling past existing well(s) from same drilling pad while drilling new well

Additional incidents

- Chemical stocks for mixing kill weight mud fall below pre-determined adequate levels
- Kick tolerance falls below pre-determined level (e.g., 2 ppg or 24 bbls)
- Casing wear exceeds acceptable amount
- Failure of critical equipment (e.g., main power system on rig)
- Severe lost circulation and continued mud losses to the loss zone
- Impending severe weather
- Flow after cementing intermediate casing, production casing, or production liner

Response Actions**Responsible party**

Rig Supervisor

Process overview The following table provides an overview of the actions required during a Level 1 well control incident:

Step	Action
1	<ul style="list-style-type: none">• Evaluate the situation• Determine that the incident is Level 1
2	Notify all personnel on location
3	Immediately execute initial response action based on standard operating procedures
4	Notify Team Leader
5	Continue using standard operating procedures until situation is resolved

Level 2 Well Control Incident

Characteristics

Definition

A Level 2 emergency can be defined as an abnormal well control event involving some sort of complication in which:

- Well control has **not** been lost at the surface
- Resources beyond the normal capabilities of the rig crew or production operations staff may be required such as unfamiliar or complex well control procedures
- Outside well control consultation, materials, special equipment or personnel may be required

There are no injuries or fires associated with this incident level since control has not been lost. The situation is not sufficiently threatening to declare a Major Emergency or to activate an Incident Command System to deal with the situation.

Action Required

Trained drilling staff should be able to handle a Level 2 emergency in the normal course of drilling or working over a well by:

- Removing the complication, thereby reducing the incident severity to Level 1 status, then using SOPs to circulate out the kick and resolve the problem
- Prepare a specialized procedure to control the incident with the complication remaining throughout the procedure

It is important that action be taken quickly to resolve the situation. Level 2 incidents are more serious than Level 1 incidents and they can escalate quickly to a complete loss of well control (i.e., a Level 3 incident). Even if control is not lost at the surface, an underground blowout or other similar event can occur if measures are not taken quickly.

Examples**Drilling-related incidents**

- Kick with no pipe in the hole
- Kick with the bit off the bottom
- Drill collars or other BHA components across the pipe rams, well shut in on the annular preventer
- Kick while fishing, pipe off bottom, fish in hole
- Kick with the bit off bottom, pipe stuck
- Kick with very high intensity or large volume taken (high shut-in pressure)

- Kick with simultaneous losses (above or below the bit)
- Kick with bit or drill string plugged
- Kick with critical equipment failure (e.g., pumps, electrical system, etc.)
- Kick with hole in drill string
- Kick without sufficient chemicals to weight up mud
- Kick with wireline in the hole
- Shallow gas kick with diversion
- Low volume flow after cementing surface casing

**Level 1 incidents
escalating to a
Level 2 while
circulating out a
kick**

- Exceeding maximum allowable surface pressure while circulating kick out of the open hole section (before kick reaches the casing shoe)
- Suspected underground cross-flow requiring further diagnosis
- Small leak in BOP or wellhead
- Leak in stab-in safety valve through ball seat and/or operating system seal
- Gas hydrate (ice) plug in circulation system
- Choke plugged or cut out
- Washout in drill string or in surface equipment
- Dropped drill string
- Sheared drillpipe
- Loss of BOP control function

**Completion-or
workover- related
incidents**

- Fishing operation performed under pressure
- Potential underground crossflow
- Leak in wireline BOP, lubricator and/or tree valves
- Fishing or milling operation performed under pressure with coiled tubing or snubbing unit where loss of well control is imminent

Production-related incidents

- Production casing leak with tubing leak
- Leak in master valve with failure of ESD valve control
- Leak in tubing with casing valve leak
- Tree component eroded to critical limit by sand
- Surface safety valves do not effectively shut-off flow

Simultaneous operations incidents

- Drilling into existing well casing from new well
- Casing leak develops during workover operations
- Damage to tree, wellhead or casing near surface due to heavy dropped object
- Motor vehicle collision resulting in severe damage to tree or wellhead
- Inability to access casing annulus due to inoperative (stuck) side outlet valve on wellhead

Response Actions

Responsible party Rig Supervisor

Process overview The following table provides an overview of the actions required during a Level 2 well control incident:

Step	Action
1	Evaluate the situation; determine that the situation constitutes a Level 2 Incident classification and advise the Team Leader
2	Down man rig; remove all non-essential personnel and equipment from the site
3	Execute initial response actions to protect personnel, the rig, the well and the reservoir
4	Develop a procedure to remove the complication and deal with the situation using SOPs
5	If complication cannot be removed, prepare a non-standard procedure to deal with the incident

6	Consult with the appropriate Team Leader, Drilling Engineer and well control specialists, if needed
7	Obtain approval for execution of either action plan from the Team Leader
8	Execute approved procedure to resolve situation (may require the participation of well control specialists to assist)
9	Review outcome of procedure with the Team Leader

Level 3 Well Control Incidents

Characteristics

Definition	A Level 3 emergency denotes a total loss of well control with no opportunity to restore it using all the resources available on-site.
Action Required	Level 3 Incidents require the declaration of a Major Emergency and the activation of a fully-functional Incident Command System to effectively deal with the situation.

Discussion

A Level 3 Incident is, quite simply, a blowout. These incidents are equivalent to Category 2 or Category 3 Emergencies, depending on the severity and circumstances involved in the blowout. The Well Control Organization must be activated upon determining that the well is out of control and measures must immediately be taken to protect people, the environment and material assets in that order.

These emergencies, although serious at the outset, have the potential to escalate further during control procedures. Such escalation may cause serious structural damage or total loss of the rig, BOP stack and wellhead due to explosion, fire, or cratering. Other nearby wells may also be damaged due to underground crossflow and erosion caused by the blow-out. This could result in multiple, simultaneous well control problems on several wells. Clearly, prompt decisive action is needed to avoid this situation.

The response to a Level 3 Incident can be divided into stages for clarity. Different activities, personnel, equipment and safety issues exist at each stage. These are discussed more fully below:

Phase 1: Initial response

Phase 1 is the initial reaction to the well control emergency. It commences at the outset of the Level 3 Incident when it is clear that control is lost and cannot be regained. Actions such as evacuation, exclusion zone establishment and site isolation occur during this stage. Preliminary work to provide water for fire fighting and setting on-scene command facilities at the site are included. It ends when well control intervention operations site begin including fire extinguishment operations.

Phase 2: Well control operations

Phase 2 is the on-site operations phase of the well control emergency. This phase begins when actual well control actions are initiated at the site using surface intervention techniques. It ends when the well has been brought under control by any means. This phase is concluded when the Incident Commander officially declares the emergency resolved, and well salvage and recovery operations begin.

Phase 3: Relief well planning and drilling

Phase 3 is the relief well planning and drilling phase of the well control emergency. It begins when the Incident Commander approves a relief well as part of the well control project. It ends when the blow-out well is intersected and killed by pumping through the relief well or when the well is brought under control using surface intervention techniques and the Incident Commander declares the emergency resolved. Note that Phase 2 and Phase 3 operations can occur simultaneously depending on the circumstances of the blowout event.

Phase 4: Well recovery operations

Phase 4 is the recovery phase of operations on the now dead blow-out well. This phase begins when the well or blow-out is brought under control. It ends when normal drilling, workover or production operations resume or when well is plugged and abandoned.

Phase 5: Post-incident evaluation

Phase 5 involves evaluation of the incident following resolution of the emergency situation. This phase begins at or near the conclusion of well recovery operations. It ends with the submission of the final incident report to CL&F Operating LLC management.

Examples

Drilling-related Incidents

- Underground flow with BOP stack closed and gas, oil or water broaches to the surface
- Uncontrolled flow to surface through drillpipe with no means of shutting off the flow
- Gas or oil comes to surface through the drillpipe x casing annulus and the BOP cannot control the flow
- Uncontrolled flow from BOP stack with drill string out of the hole and unable to close blind rams
- Drilling rig on fire due to blowout
- Surface failure of choke line, kill line or choke manifold and well cannot be shut-in

Workover-related Incidents

- Loss of BOP function
- Uncontrolled flow to surface through tubing with no means of shutting off flow
- Gas or oil comes to surface through casing x tubing annulus and stack does not shut off flow
- Uncontrolled flow from BOP stack with no tubing in the hole and unable to close blind rams
- Completion rig on fire due to blowout
- Failure of existing wellhead component with no way to stop the flow
- Collision, irreparable damage to wellhead and leak during rig move in or move out

Production-related Incidents

- Collision between vehicle and wellhead resulting in major leak
- Wellhead/tree on fire with no way to shut off flow
- Mechanical failure of master valve, wing valve or flowline with no means to stop the flow

Simultaneous operations Incidents

- Falling object from rig damages wellhead or flowline resulting in catastrophic leak
- Gas cloud from major leak prevents access to wellhead or tree to shut-in well

Response Actions

Responsible party

Rig Supervisor

Process overview The following table provides an overview of the actions required by the Rig Supervisor or Sr. CL&F Operating LLC employee during a Level 3 well control incident:

Step	Action
1	Evaluate situation and determine that well control is lost with no means to restore control
2	Order all personnel at the site to a designated Safe Area
3	Account for all personnel on the site. If all personnel cannot be accounted for, organize a Search and Rescue Party and attempt to locate all personnel if it is safe for them to do so
4	Determine injuries, if any, and provide first aid. Assess the need for air ambulance evacuation of injured persons. Assign personnel to mark the landing site for helicopter in the Safe Area
5	Notify the Team Leader about the situation and request declaration of a Major Emergency
6	Establish Exclusion Zone around site and mark zone boundary using available supplies and materials
7	Post a watch to secure the rig and prevent unauthorized persons from entering the Exclusion Zone
8	Notify and evacuate nearby rigs, homes, businesses or other facilities if they are affected by the blow-out plume

9	Down man the rig and move non-essential personnel away from the area. Note: Do not release the rig crew until they are interviewed regarding events leading up to the blowout incident.
10	Request that the local Fire Station provide equipment and personnel to contain the fire and protect nearby assets with water spray, if it is safe to do so. <u>Note:</u> Do not attempt to extinguish fire at rig; wait for well control specialists to enter the Exclusion Zone.
11	Complete <i>Initial Status Report</i> and fax to American Safety Services Inc. 432-363-0198
12	Remain on the site and coordinate support services needed for initial well control efforts; await the arrival of the Team Leader (On-Scene Commander)
13	Contain pollution/oil spill, if possible and if safe to do so
14	Monitor well conditions, keep a log recording all observations and report any changes to Team Leader (if not yet on-site) by radio and to CWC via fax or phone
15	Brief American Safety Services Inc First Responder upon arrival at the site; assist First Responder in determining if boundaries of Exclusion Zone should be moved
16	Remain on-site to assist with well control operations

Duties and Responsibilities, Rig Supervisor

Reports to:	On-Scene Commander
--------------------	--------------------

Team Authority	Job Title
Team Member	Rig Supervisor (Company Man)

Pre-Spud

Responsibility
Daily duties on location include: <ul style="list-style-type: none"> • Conducts safety meetings • Designates two Safe Areas (Muster Areas) for emergencies • Maintains census of all personnel on site • Reviews his duties and the <i>Initial Response Checklist</i>
Maintains supply of <i>Communications Record</i> at the wellsite
Maintains a current copy of CL&F Operating LLC General Emergency Procedure at the site and in toolpusher's quarters
Provides training to rig personnel on required response steps in each type of incident including mustering at designated Safe Areas and evacuation, if required. Periodically runs Search and Rescue exercises to ensure team readiness.

Level 1

Well control incident

Responsibility
Determines that the incident is a Level 1 incident; responds quickly to the situation before it can escalate to a more serious level: <ul style="list-style-type: none"> • Obtains data necessary for response • Prepares a procedure for dealing with the incident • Follows standard operating procedures to deal with the situation • Notifies the Team Leader about the incident and steps taken to resolve it

Level 2

Well control incident

Responsibility
Determines that the situation is a Level 2 incident and defines the complication involved; responds to the situation to keep it from escalating to a more serious incident level: <ul style="list-style-type: none"> • Determines the best way to remove the complication, thus lowering the incident to Level 1

- Contacts the Team Leader, Sr. Drilling Engineer and possibly American Safety Services Inc for consultation about the problem
- Prepares a procedure to remove the complication, lower the severity level and deal with the incident using SOPs; alternatively, jointly prepares a procedure to deal with the situation without removing the complication
- Reviews procedure with Team Leader and obtains approval to proceed
- Advises Team Leader of the outcome

Level 3

Well control incident

Responsibility

Determines that the situation constitutes a complete loss of well control that cannot be regained using assets on-site

Level 3

Phase 1: Initial Response

Responsibility

Executes steps outlined in the *Initial Response Checklist* to deal quickly and decisively with the situation at the wellsite; maintains records of all contacts and communications using the *Communications Record*, if possible

With the assistance of the Toolpusher:

- Musters all personnel on the rig to one of the designated Safe Areas
- Accounts for all personnel at each Safe Area by comparing personnel at the muster point to the current on-site personnel census
- Determines the extent of any injuries, provides emergency first aid treatment and assesses the need for air evacuation of injured persons on an emergency basis
- Locates a safe landing zone for emergency aircraft to evacuate injured personnel, if required, and marks it for med-evac helicopter
- Notifies Team Leader about situation and recommends classification of event as Level 3 Incident; provides initial report on event and current activities
- Notifies nearby rigs, facilities, residences, businesses and other persons that could be at risk from the blow-out
- Once site is evacuated, establishes Exclusion Zone around the well/rig, marks with on-hand materials and posts a watch to keep everyone out of the Exclusion Zone

NOTE: Do not re-enter the Exclusion Zone for any reason until well control specialists arrive to assist.

- Meets with local security personnel and requests they secure and restrict access to the blow-out site
- Requests assistance to evacuate nearby rigs, facilities, residences and businesses that may be affected by the blow-out

- If site evacuation is not required, contains the fire and protect assets by eliminating possible ignition sources and using a protective water spray by local fire department, if available

Note: Do not attempt to extinguish the fire.

- Completes *Initial Status Report* and faxes to:
American Safety Services Inc - Fax 432-363-0198
- Contains pollution and/or spill, if possible without exposing personnel to danger or contamination
- Monitors well conditions and maintains a log. Reports any significant changes in blow-out behavior to Team Leader
- Briefs the American Safety Services Inc First Responder upon his arrival at the site
- Relinquishes control of the wellsite to the On-Scene Commander (Team Leader) upon his arrival
- Remains at the site and assists in well control efforts, as needed

Level 3

Phase 2: Well control

Responsibility	
Assists with well control operations and support, as needed	
Prepares a detailed report of incidents immediately preceding the blow-out and provides to the On-Scene Incident Commander; reviews the report's content with the American Safety Services Inc Team Leader	

Level 3

Phase 3 Relief well

Responsibility	
Assists in well control planning, as needed, from his/her knowledge of the local area	
Visually surveys prospective relief well sites and roads for obstructions such as high lines, pipelines, unsatisfactory topography and other problems; provides details on each site to the Relief Well Design Team	
Provides information to the Rig Supervisor on the relief well rig and others supporting relief well drilling operations regarding local drilling conditions and any expected problems while drilling relief well and making intercept	
Assists On-Scene Commander to co-ordinate activities during relief well drilling	

Level 3

Phase 4: Well recovery

Responsibility	
Assists in planning well recovery work as directed by the On-Scene Commander	
Assists in developing recommendation to cease recovery operations, abandon blow-out well and substitute relief well after sidetracking	

Supervises well recovery work on the blow-out well if feasible, or abandonment if not

Level 3

**Phase 5:
Post-incident
evaluation**

Responsibility

Assists On-Scene Commander in preparing post-incident report and evaluation from field standpoint; includes his summary of events leading up to the incident and review of initial response efforts

Initial Risk Assessment

The Rig Supervisor will be the first to assess risks and determine the boundaries of the Exclusion Zone. The Exclusion Zone determines the minimum safe distance away from the blown-out well. It is based primarily on the concentration of combustible gas and/or toxic gas in the atmosphere. In general, the Exclusion Zone should be positioned according to the following:

Hazard	Maximum Limit
Combustible gas	10% of LEL*
Hydrogen Sulfide	10 ppm
Flammable liquid	10 bbls
Noise	85 dB

*Lower Explosive Limit

Other hazards such as proximity to vehicular traffic, sources of ignition, threats to production facilities and other risks must be evaluated and steps taken to ensure that the Exclusion Zone boundary is set far enough away from the blow-out site to reduce risks to all personnel to an acceptable level.

Once the Exclusion Zone Boundaries are set, no person should enter the area without special training, equipment and companion personnel. Often in such situations, persons not familiar with the potential of sudden catastrophic failures inside the Exclusion Zone venture too close to the blow-out in search of fellow workers, valuables left behind during the evacuation or curiosity. Sometimes, these mistaken few become victims if a failure, such as a spontaneous ignition of the plume, occurs while they are inside the Exclusion Zone.

Boundaries of the Exclusion Zone are not firm, and may need to be moved from time to time depending on several conditions such as:

- Flowrate from the well (increasing or decreasing)
- Zone of flow (increased H₂S concentration in the plume)
- Changes in atmospheric conditions (reduced air temperature, wind velocity, wind direction, atmospheric inversion, etc.)
- Hydrocarbon runoff with collection offsite
- Ignition of the plume
- Self-extinguishment of a fire
- Changes in boundary threshold limits

Risk management in the early stages of a blowout is accomplished primarily by prohibiting access to the site. Separation of potential victims from potential hazards is a very effective method of mitigating risks. In the case of Exclusion Zone boundary establishment, personnel are simply kept away from all hazards.


Situation Awareness

This is an area of human factors involving perceptions of people involved in high stress situations. Basically, it is the assessment of the person's concepts and thought processes when multiple data inputs are involved in an emergency. The best example of this area of study involves jet fighter pilots in combat situations.

In high stress situations the human mind can go into sensory overload easily. Alarms are sounding, warning lights are flashing, and there is normally panic, shouting, and rapid movements. All of these render many persons incapable of determining what information is valid and should be honored, and what inputs are redundant or meaningless and should be ignored.

Work zones have been established to control access to areas in which well control specialists and certain support personnel can function safely. Others that do not fully understand the risks involved are simply not allowed to enter these areas. This has been successful in limiting exposure and consequential injuries to those people with poorly developed situation awareness during well control operations.

Example of Work Zones



Appendix

Appendix A	Initial Response Checklist
Appendix B	Initial Status Report
Appendix C	Communications Record

Appendix A

Initial Response Checklist

Has pressure containment and flow control been completely lost and cannot	Yes <input type="checkbox"/>	No <input type="checkbox"/>
---	------------------------------	-----------------------------

be regained?		
--------------	--	--

If "yes" this is a Level 3 Well Control Incident

Date:	Time:	Well Name & No.:
Drilling Contractor:		Rig Number:
CL&F Operating LLC DRL Supervisor:		CL&F Operating LLC Sr. Supervisor:

ACTIONS (Check off as performed)

<input type="checkbox"/>	Evacuate all personnel to designated muster area
<input type="checkbox"/>	Check names at muster area against Check-In Sheet; account for all personnel
<input type="checkbox"/>	If all personnel are <u>not</u> at muster area, determine how many personnel are missing, where they were last seen and visually check the area, if possible, to see if they are safe
<input type="checkbox"/>	Activate Search and Rescue Team to recover missing personnel, if required
<input type="checkbox"/>	Provide emergency first aid for any injuries
<input type="checkbox"/>	Determine if emergency medical services and ambulance transport are needed; locate landing site for med-evac helicopter and mark site
<input type="checkbox"/>	Notify nearby rigs or production facilities about potential danger from blow-out
<input type="checkbox"/>	Notify Team Leader about incident; recommend Major Emergency declaration
<input type="checkbox"/>	Establish "Exclusion Zone" around location and mark with available supplies
<input type="checkbox"/>	Secure the area and do not let unauthorized persons inside Exclusion Zone
<input type="checkbox"/>	Contain pollution, if possible
<input type="checkbox"/>	Remain on site pending arrival of Team Leader
<input type="checkbox"/>	Monitor well conditions and report any changes to Team Leader
<input type="checkbox"/>	Brief First Responder upon arrival at location
<input type="checkbox"/>	Assist with well control operations, as needed
<input type="checkbox"/>	

*Do not re-enter the Exclusion Zone unless absolutely necessary until qualified help arrives

**If well is on fire, do not attempt to put the fire out; if well is not on fire, try to keep it from catching on fire

--	--

Act quickly and decisively	Wait on instructions
Evacuate the rig or wellsite, if necessary	Hang around the rig
Wait in the Muster Area	Leave the well site
Answer questions asked by CL&F Operating LLC Team Leader and well control specialist truthfully	Talk to the press or the public without clearance; don't speculate about the cause of the incident; don't exaggerate
	Be a hero

Appendix B

Initial Status Report

Preliminary Information:

Operator:	_____	Well Name & Number:	_____
Rig:	_____	Company Man:	_____
Rig Phone:	_____	Cell Phone:	_____
Office Phone:	_____	Office FAX:	_____
Directions to site: _____			


Blow-out Information:

Time of blow-out:	_____	Well on fire?	_____
Operation at time of blow-out: _____			
Point of Escape:	_____	Est. Flowrate:	_____
Type of Fluid:	_____	H ₂ S? Yes <input type="checkbox"/> No <input type="checkbox"/>	CO ₂ ? Yes <input type="checkbox"/> No <input type="checkbox"/>
Height of plume before it ignites?	_____ ft	Total Height of flame:	_____ ft
Mud Weight:	ppg MD: _____ ft	TVD:	_____ ft
Last shoe test:		EMW @	depth
Rig Condition: _____			
BOP Condition:		Closing Unit OK? _____	
Condition of drill string:		TIW valve installed? Yes <input type="checkbox"/> No <input type="checkbox"/>	

Response:

Personnel Evacuated?	Yes <input type="checkbox"/> No <input type="checkbox"/>	Number Missing:	_____
Exclusion Zone set up?	Yes <input type="checkbox"/> No <input type="checkbox"/>	Injuries?	_____
Nearby rigs notified?	Yes <input type="checkbox"/> No <input type="checkbox"/>	Air Ambulance needed/called?	Yes <input type="checkbox"/> No <input type="checkbox"/>
Location Secured?	Yes <input type="checkbox"/> No <input type="checkbox"/>	Regulatory Agencies notified?	Yes <input type="checkbox"/> No <input type="checkbox"/>
Residents evacuated?	Yes <input type="checkbox"/> No <input type="checkbox"/>	Pollution contained?	Yes <input type="checkbox"/> No <input type="checkbox"/>

Drawing of Location:



Appendix C

Communications Record

Phone Transactions / Time Schedule / Contact Verification

Time	Description of Action	Contact
------	-----------------------	---------

[illegible]

Hydrogen Sulfide (H₂S) Properties and Effects

H₂S is an **Extremely Toxic**, Flammable, Explosive and Corrosive Gas. It is heavier than air, paralyses you of smell. Causes breathing to stop and death will result.

At low concentration H₂S has the odor of rotten eggs. The smell is very offensive. At slightly high concentration H₂S will cause sense of smell to disappear and you are slowly poisoning yourself. At even slightly higher concentrations DEATH will result.

Properties of Hydrogen Sulfide (H₂S)

Extremely deadly toxic gas

Colorless

Heavier than air

Burns with a blue flame

Produces Sulphur Dioxide (SO₂) when burned (another toxic gas)

Highly corrosive

Irritant skin and eyes

Soluble in water and other liquids

Extremely flammable and explosive.

Hydrogen Sulfide (H₂S) Toxicity Chart

Concentrations	Effects
Less than 1 PPM	Odor
1-PPM	May cause stress or health symptoms in sensitive people
10-PPM	Permissible Exposure Limit (PEL) Allowed 8 hours exposure without breathing apparatus.
15-PPM	Short Term Exposure Limit (STEL) 15-minute exposure 4 times a day allowed without breathing apparatus.
100-PPM	Immediately Dangerous to Life and Health (IDLH) No exposure allowed without breathing apparatus.
150 – 250 PPM	Loss of smell will result within a few minutes, burning of eyes, throat and coughing.
500-PPM	Destroys sense of reasoning and balance, ceases respiratory function within minutes and death will result.

200-PPM	Unconscious quickly, followed by loss of lung function, heart failure and death if not rescued and treated.
---------	---

1000-PPM	Immediate loss of bodily functions including the lungs. Heart will arrest, DEATH within minutes if not rescued immediately and treated.
----------	---

10,000 PPM is 1 %

Sulphur Dioxide (SO₂) Toxicity Chart

<u>Concentration</u>	<u>Effects</u>
-----------------------------	-----------------------

1-PPM	Odor
-------	------

2-PPM	Permissible Exposure Limit (PEL) Safe for 8 hours without breathing apparatus
-------	---

5-PPM	Short Term Exposure Limit (STEL) Safe for 15 Minutes – four time a day without breathing apparatus.
-------	---

12-PPM	Burning of eyes, breathing irritation. Causes damage to the wall lining of the lungs.
--------	---

100-PPM	Immediately Dangerous to Life and Health (IDLH) Causes serious decaying of skin tissue of respiratory system.
---------	--

150-PPM	Extreme irritation, tolerated only for a few minutes.
---------	---

500-PPM

Sense of suffocation with first breath requires medical aid.

1000-PPM

Death will result unless rescued and medical aid is provided.

SO₂ is known to be a cancer-causing agent.

H₂S Emergency Levels:


	Level I Low Impact Unconfirmed	Level II Significant Impact Potential	Level III Major Impact Hazard to People
Drilling	Problems During Drilling in a sour gas zone and the well has significant losses or gas-cut mud or kick	Equipment malfunction while circulating a kick or unable to maintain circulating volumes	Uncontrolled flow of sour gas (ignited or unignited) from the wellbore
Testing	Sour gas zone is open and an event occurs that has the potential to lead to a well control problem (leak at surface setup) Limited release.	An equipment malfunction restricts the ability to manage any level I emergency.	Uncontrollable flow of sour gas (ignited or unignited) from the wellbore.

Rig Crew Emergency Action

Position	Report to	Duties
Rig Manager	Drilling Supervisor	Activate the H ₂ S Alarm. Supervise evacuation to Safe Briefing Area. Return to Drill Floor and Account for Essential personnel. Report to CO MAN for further Instructions.

Driller on Duty	Rig Manager	Prepare to Secure Well. Check Drill Crew personnel for H2S Safety Equipment Readiness. In Case of Emergency Remove Non- Essential Personnel from Rig Floor
Drill Crew	Driller	Check their H2S Breathing Equipment for Readiness and Follow Instruction of the Driller.
H2S Safety Supervisor	Report to Rig Floor	Ensure that all Personnel are Using Required Breathing Apparatus. Report to CO MAN Monitor all Operations and Monitor all Personnel Under Air.
Service Company Personnel Visitors	Safe Briefing Area	Report to Safe Area and Await Further Instructions.
All Non Essential Personnel	Safe Briefing Area	Await further Instructions

SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY, NEW MEXICO.



basin surveys
focused on excellence
in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241

(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

CL&F OPERATING LLC

REF: CRAZY HORSE 0304 FED COM #1H / WELL PAD TOPO

THE CRAZY HORSE 0304 FED COM #1H LOCATED 110' FROM
THE SOUTH LINE AND 436' FROM THE WEST LINE OF
SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST.

N.M.P.M., EDDY COUNTY, NEW MEXICO.

W.O. Number: 33327

Drawn By: K. GOAD

Date: 10-04-2017


Survey Date: 09-27-2017

Sheet 1 of 1 Sheets

**Crazy Horse Fed Com #1H
H₂S Contingency Plan:
2 Mile Radius Map**

Section 2, Township 20S, Range 30E
Eddy County, New Mexico


● Surface Hole Location



NAD 1983 New Mexico State Plane East
FIPS 2001 Feet

FOURTH MEET.

Prepared by Permits West, Inc., January 12, 2018
for CL & F Operating, LLC





Integrity Directional Services, LLC

Survey Report



Company: CL&F Operating LLC
Project: Eddy County, NM (NAD 83)
Site: Sec 2, T20S, R30E
Well: Crazy Horse 1H
Wellbore: Wellbore #1
Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
TVD Reference: KB=25 @ 3239.00ft
MD Reference: KB=25 @ 3239.00ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Multi User Db

Project	Eddy County, NM (NAD 83)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Sec 2, T20S, R30E		
Site Position:		Northing:	580,683.2000 usft
From:	Map	Easting:	659,216.4000 usft
Position Uncertainty:	0.00 ft	Slot Radius:	13-3/16 "
		Latitude:	32.595768
		Longitude:	-103.950570
		Grid Convergence:	0.21 °

Well	Crazy Horse 1H		
Well Position	+N/-S	0.00 ft	Northing: 580,526.3000 usft
	+E/-W	0.00 ft	Easting: 659,401.5000 usft
Position Uncertainty	0.00 ft	Wellhead Elevation:	0.00 ft
		Latitude:	32.595335
		Longitude:	-103.949971
		Ground Level:	3,214.00 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	HDGM	8/3/2017	7.45	60.45	48,274

Design	Plan #1				
Audit Notes:					
Version:	Phase:	PLAN	Tie On Depth:	0.00	
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.00	0.00	0.00	272.10	

Survey Tool Program	Date 10/11/2017				
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
0.00	18,850.65	Plan #1 (Wellbore #1)	MWD	MWD - Standard	

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00

Integrity Directional Services, LLC

Survey Report



Company: CL&F Operating LLC
 Project: Eddy County, NM (NAD 83)
 Site: Sec 2, T20S, R30E
 Well: Crazy Horse 1H
 Wellbore: Wellbore #1
 Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
 TVD Reference: KB=25 @ 3239.00ft
 MD Reference: KB=25 @ 3239.00ft
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Database: EDM 5000.1 Multi User Db

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00
4,100.00	0.00	0.00	4,100.00	0.00	0.00	0.00	0.00	0.00	0.00
4,200.00	0.00	0.00	4,200.00	0.00	0.00	0.00	0.00	0.00	0.00
4,300.00	0.00	0.00	4,300.00	0.00	0.00	0.00	0.00	0.00	0.00
4,400.00	0.00	0.00	4,400.00	0.00	0.00	0.00	0.00	0.00	0.00
4,470.85	0.00	0.00	4,470.85	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 2.00									
4,500.00	0.58	344.06	4,500.00	0.14	-0.04	0.05	2.00	2.00	0.00
4,600.00	2.58	344.06	4,599.96	2.80	-0.80	0.90	2.00	2.00	0.00
4,700.00	4.58	344.06	4,699.76	8.81	-2.52	2.84	2.00	2.00	0.00
4,770.85	6.00	344.06	4,770.30	15.09	-4.31	4.86	2.00	2.00	0.00
Start 3282.36 hold at 4770.85 MD									
4,800.00	6.00	344.06	4,799.29	18.02	-5.15	5.80	0.00	0.00	0.00
4,900.00	6.00	344.06	4,898.74	28.07	-8.02	9.04	0.00	0.00	0.00

Agility Directional Services, LLC

Survey Report



Company: CL&F Operating LLC
Project: Eddy County, NM (NAD 83)
Site: Sec 2, T20S, R30E
Well: Crazy Horse 1H
Wellbore: Wellbore #1
Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
TVD Reference: KB=25 @ 3239.00ft
MD Reference: KB=25 @ 3239.00ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Multi User Db

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,000.00	6.00	344.06	4,998.20	38.12	-10.89	12.28	0.00	0.00	0.00
5,100.00	6.00	344.06	5,097.65	48.17	-13.76	15.51	0.00	0.00	0.00
5,200.00	6.00	344.06	5,197.10	58.22	-16.63	18.75	0.00	0.00	0.00
5,300.00	6.00	344.06	5,296.55	68.28	-19.50	21.99	0.00	0.00	0.00
5,400.00	6.00	344.06	5,396.01	78.33	-22.37	25.23	0.00	0.00	0.00
5,500.00	6.00	344.06	5,495.46	88.38	-25.24	28.46	0.00	0.00	0.00
5,600.00	6.00	344.06	5,594.91	98.43	-28.11	31.70	0.00	0.00	0.00
5,700.00	6.00	344.06	5,694.36	108.48	-30.98	34.94	0.00	0.00	0.00
5,800.00	6.00	344.06	5,793.81	118.53	-33.85	38.17	0.00	0.00	0.00
5,900.00	6.00	344.06	5,893.27	128.58	-36.72	41.41	0.00	0.00	0.00
6,000.00	6.00	344.06	5,992.72	138.63	-39.59	44.65	0.00	0.00	0.00
6,100.00	6.00	344.06	6,092.17	148.68	-42.46	47.89	0.00	0.00	0.00
6,200.00	6.00	344.06	6,191.62	158.73	-45.33	51.12	0.00	0.00	0.00
6,300.00	6.00	344.06	6,291.08	168.79	-48.20	54.36	0.00	0.00	0.00
6,400.00	6.00	344.06	6,390.53	178.84	-51.07	57.60	0.00	0.00	0.00
6,500.00	6.00	344.06	6,489.98	188.89	-53.95	60.83	0.00	0.00	0.00
6,600.00	6.00	344.06	6,589.43	198.94	-56.82	64.07	0.00	0.00	0.00
6,700.00	6.00	344.06	6,688.88	208.99	-59.69	67.31	0.00	0.00	0.00
6,800.00	6.00	344.06	6,788.34	219.04	-62.56	70.54	0.00	0.00	0.00
6,900.00	6.00	344.06	6,887.79	229.09	-65.43	73.78	0.00	0.00	0.00
7,000.00	6.00	344.06	6,987.24	239.14	-68.30	77.02	0.00	0.00	0.00
7,100.00	6.00	344.06	7,086.69	249.19	-71.17	80.26	0.00	0.00	0.00
7,200.00	6.00	344.06	7,186.14	259.24	-74.04	83.49	0.00	0.00	0.00
7,300.00	6.00	344.06	7,285.60	269.30	-76.91	86.73	0.00	0.00	0.00
7,400.00	6.00	344.06	7,385.05	279.35	-79.78	89.97	0.00	0.00	0.00
7,500.00	6.00	344.06	7,484.50	289.40	-82.65	93.20	0.00	0.00	0.00
7,600.00	6.00	344.06	7,583.95	299.45	-85.52	96.44	0.00	0.00	0.00
7,700.00	6.00	344.06	7,683.41	309.50	-88.39	99.68	0.00	0.00	0.00
7,800.00	6.00	344.06	7,782.86	319.55	-91.26	102.91	0.00	0.00	0.00
7,900.00	6.00	344.06	7,882.31	329.60	-94.13	106.15	0.00	0.00	0.00
8,000.00	6.00	344.06	7,981.76	339.65	-97.00	109.39	0.00	0.00	0.00
8,053.21	6.00	344.06	8,034.68	345.00	-98.53	111.11	0.00	0.00	0.00
Start DLS 12.00 TFO -74.08									
8,100.00	9.27	308.31	8,081.07	349.69	-102.16	114.91	12.00	6.98	-76.40
8,200.00	20.08	286.11	8,177.74	359.48	-125.06	138.15	12.00	10.81	-22.21
8,300.00	31.74	279.46	8,267.55	368.60	-167.65	181.05	12.00	11.66	-6.64
8,400.00	43.57	276.16	8,346.58	376.65	-228.08	241.74	12.00	11.83	-3.30
8,500.00	55.47	274.05	8,411.39	383.28	-303.71	317.56	12.00	11.89	-2.11
8,600.00	67.39	272.47	8,459.13	388.19	-391.23	405.20	12.00	11.92	-1.57
8,700.00	79.32	271.15	8,487.73	391.18	-486.82	500.83	12.00	11.93	-1.32
8,795.37	90.71	269.99	8,496.00	392.12	-581.67	595.65	12.00	11.94	-1.22
Start 10055.92 hold at 8795.37 MD - Crazy Horse 1H EP									
8,800.00	90.71	269.99	8,495.95	392.12	-586.30	600.28	0.00	0.00	0.00
8,900.00	90.71	269.99	8,494.71	392.10	-686.29	700.20	0.00	0.00	0.00

Integrity Directional Services, LLC

Survey Report



Company: CL&F Operating LLC
 Project: Eddy County, NM (NAD 83)
 Site: Sec 2, T20S, R30E
 Well: Crazy Horse 1H
 Wellbore: Wellbore #1
 Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
 TVD Reference: KB=25 @ 3239.00ft
 MD Reference: KB=25 @ 3239.00ft
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Database: EDM 5000.1 Multi User Db

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,000.00	90.71	269.99	8,493.48	392.08	-786.28	800.12	0.00	0.00	0.00
9,100.00	90.71	269.99	8,492.25	392.06	-886.27	900.05	0.00	0.00	0.00
9,200.00	90.71	269.99	8,491.01	392.04	-986.26	999.97	0.00	0.00	0.00
9,300.00	90.71	269.99	8,489.78	392.02	-1,086.26	1,099.90	0.00	0.00	0.00
9,400.00	90.71	269.99	8,488.55	392.00	-1,186.25	1,199.82	0.00	0.00	0.00
9,500.00	90.71	269.99	8,487.32	391.98	-1,286.24	1,299.75	0.00	0.00	0.00
9,600.00	90.71	269.99	8,486.08	391.97	-1,386.23	1,399.67	0.00	0.00	0.00
9,700.00	90.71	269.99	8,484.85	391.95	-1,486.23	1,499.60	0.00	0.00	0.00
9,800.00	90.71	269.99	8,483.62	391.93	-1,586.22	1,599.52	0.00	0.00	0.00
9,900.00	90.71	269.99	8,482.38	391.91	-1,686.21	1,699.45	0.00	0.00	0.00
10,000.00	90.71	269.99	8,481.15	391.89	-1,786.20	1,799.37	0.00	0.00	0.00
10,100.00	90.71	269.99	8,479.92	391.87	-1,886.20	1,899.29	0.00	0.00	0.00
10,200.00	90.71	269.99	8,478.68	391.85	-1,986.19	1,999.22	0.00	0.00	0.00
10,300.00	90.71	269.99	8,477.45	391.83	-2,086.18	2,099.14	0.00	0.00	0.00
10,400.00	90.71	269.99	8,476.22	391.81	-2,186.17	2,199.07	0.00	0.00	0.00
10,500.00	90.71	269.99	8,474.98	391.79	-2,286.17	2,298.99	0.00	0.00	0.00
10,600.00	90.71	269.99	8,473.75	391.77	-2,386.16	2,398.92	0.00	0.00	0.00
10,700.00	90.71	269.99	8,472.52	391.76	-2,486.15	2,498.84	0.00	0.00	0.00
10,800.00	90.71	269.99	8,471.28	391.74	-2,586.14	2,598.77	0.00	0.00	0.00
10,900.00	90.71	269.99	8,470.05	391.72	-2,686.14	2,698.69	0.00	0.00	0.00
11,000.00	90.71	269.99	8,468.82	391.70	-2,786.13	2,798.61	0.00	0.00	0.00
11,100.00	90.71	269.99	8,467.58	391.68	-2,886.12	2,898.54	0.00	0.00	0.00
11,200.00	90.71	269.99	8,466.35	391.66	-2,986.11	2,998.46	0.00	0.00	0.00
11,300.00	90.71	269.99	8,465.12	391.64	-3,086.11	3,098.39	0.00	0.00	0.00
11,400.00	90.71	269.99	8,463.89	391.62	-3,186.10	3,198.31	0.00	0.00	0.00
11,500.00	90.71	269.99	8,462.65	391.60	-3,286.09	3,298.24	0.00	0.00	0.00
11,600.00	90.71	269.99	8,461.42	391.58	-3,386.08	3,398.16	0.00	0.00	0.00
11,700.00	90.71	269.99	8,460.19	391.56	-3,486.07	3,498.09	0.00	0.00	0.00
11,800.00	90.71	269.99	8,458.95	391.55	-3,586.07	3,598.01	0.00	0.00	0.00
11,900.00	90.71	269.99	8,457.72	391.53	-3,686.06	3,697.93	0.00	0.00	0.00
12,000.00	90.71	269.99	8,456.49	391.51	-3,786.05	3,797.86	0.00	0.00	0.00
12,100.00	90.71	269.99	8,455.25	391.49	-3,886.04	3,897.78	0.00	0.00	0.00
12,200.00	90.71	269.99	8,454.02	391.47	-3,986.04	3,997.71	0.00	0.00	0.00
12,300.00	90.71	269.99	8,452.79	391.45	-4,086.03	4,097.63	0.00	0.00	0.00
12,400.00	90.71	269.99	8,451.55	391.43	-4,186.02	4,197.56	0.00	0.00	0.00
12,500.00	90.71	269.99	8,450.32	391.41	-4,286.01	4,297.48	0.00	0.00	0.00
12,600.00	90.71	269.99	8,449.09	391.39	-4,386.01	4,397.41	0.00	0.00	0.00
12,700.00	90.71	269.99	8,447.85	391.37	-4,486.00	4,497.33	0.00	0.00	0.00
12,800.00	90.71	269.99	8,446.62	391.35	-4,585.99	4,597.26	0.00	0.00	0.00
12,900.00	90.71	269.99	8,445.39	391.34	-4,685.98	4,697.18	0.00	0.00	0.00
13,000.00	90.71	269.99	8,444.16	391.32	-4,785.98	4,797.10	0.00	0.00	0.00
13,100.00	90.71	269.99	8,442.92	391.30	-4,885.97	4,897.03	0.00	0.00	0.00
13,200.00	90.71	269.99	8,441.69	391.28	-4,985.96	4,996.95	0.00	0.00	0.00

Integrity Directional Services, LLC

Survey Report



Company: CL&F Operating LLC
Project: Eddy County, NM (NAD 83)
Site: Sec 2, T20S, R30E
Well: Crazy Horse 1H
Wellbore: Wellbore #1
Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
TVD Reference: KB=25 @ 3239.00ft
MD Reference: KB=25 @ 3239.00ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Multi User Db

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
13,300.00	90.71	269.99	8,440.46	391.26	-5,085.95	5,096.88	0.00	0.00	0.00
13,400.00	90.71	269.99	8,439.22	391.24	-5,185.95	5,196.80	0.00	0.00	0.00
13,500.00	90.71	269.99	8,437.99	391.22	-5,285.94	5,296.73	0.00	0.00	0.00
13,600.00	90.71	269.99	8,436.76	391.20	-5,385.93	5,396.65	0.00	0.00	0.00
13,700.00	90.71	269.99	8,435.52	391.18	-5,485.92	5,496.58	0.00	0.00	0.00
13,800.00	90.71	269.99	8,434.29	391.16	-5,585.92	5,596.50	0.00	0.00	0.00
13,900.00	90.71	269.99	8,433.06	391.15	-5,685.91	5,696.42	0.00	0.00	0.00
14,000.00	90.71	269.99	8,431.82	391.13	-5,785.90	5,796.35	0.00	0.00	0.00
14,100.00	90.71	269.99	8,430.59	391.11	-5,885.89	5,896.27	0.00	0.00	0.00
14,200.00	90.71	269.99	8,429.36	391.09	-5,985.88	5,996.20	0.00	0.00	0.00
14,300.00	90.71	269.99	8,428.12	391.07	-6,085.88	6,096.12	0.00	0.00	0.00
14,400.00	90.71	269.99	8,426.89	391.05	-6,185.87	6,196.05	0.00	0.00	0.00
14,500.00	90.71	269.99	8,425.66	391.03	-6,285.86	6,295.97	0.00	0.00	0.00
14,600.00	90.71	269.99	8,424.42	391.01	-6,385.85	6,395.90	0.00	0.00	0.00
14,700.00	90.71	269.99	8,423.19	390.99	-6,485.85	6,495.82	0.00	0.00	0.00
14,800.00	90.71	269.99	8,421.96	390.97	-6,585.84	6,595.74	0.00	0.00	0.00
14,900.00	90.71	269.99	8,420.73	390.95	-6,685.83	6,695.67	0.00	0.00	0.00
15,000.00	90.71	269.99	8,419.49	390.94	-6,785.82	6,795.59	0.00	0.00	0.00
15,100.00	90.71	269.99	8,418.26	390.92	-6,885.82	6,895.52	0.00	0.00	0.00
15,200.00	90.71	269.99	8,417.03	390.90	-6,985.81	6,995.44	0.00	0.00	0.00
15,300.00	90.71	269.99	8,415.79	390.88	-7,085.80	7,095.37	0.00	0.00	0.00
15,400.00	90.71	269.99	8,414.56	390.86	-7,185.79	7,195.29	0.00	0.00	0.00
15,500.00	90.71	269.99	8,413.33	390.84	-7,285.79	7,295.22	0.00	0.00	0.00
15,600.00	90.71	269.99	8,412.09	390.82	-7,385.78	7,395.14	0.00	0.00	0.00
15,700.00	90.71	269.99	8,410.86	390.80	-7,485.77	7,495.07	0.00	0.00	0.00
15,800.00	90.71	269.99	8,409.63	390.78	-7,585.76	7,594.99	0.00	0.00	0.00
15,900.00	90.71	269.99	8,408.39	390.76	-7,685.76	7,694.91	0.00	0.00	0.00
16,000.00	90.71	269.99	8,407.16	390.74	-7,785.75	7,794.84	0.00	0.00	0.00
16,100.00	90.71	269.99	8,405.93	390.73	-7,885.74	7,894.76	0.00	0.00	0.00
16,200.00	90.71	269.99	8,404.69	390.71	-7,985.73	7,994.69	0.00	0.00	0.00
16,300.00	90.71	269.99	8,403.46	390.69	-8,085.72	8,094.61	0.00	0.00	0.00
16,400.00	90.71	269.99	8,402.23	390.67	-8,185.72	8,194.54	0.00	0.00	0.00
16,500.00	90.71	269.99	8,401.00	390.65	-8,285.71	8,294.46	0.00	0.00	0.00
16,600.00	90.71	269.99	8,399.76	390.63	-8,385.70	8,394.39	0.00	0.00	0.00
16,700.00	90.71	269.99	8,398.53	390.61	-8,485.69	8,494.31	0.00	0.00	0.00
16,800.00	90.71	269.99	8,397.30	390.59	-8,585.69	8,594.23	0.00	0.00	0.00
16,900.00	90.71	269.99	8,396.06	390.57	-8,685.68	8,694.16	0.00	0.00	0.00
17,000.00	90.71	269.99	8,394.83	390.55	-8,785.67	8,794.08	0.00	0.00	0.00
17,100.00	90.71	269.99	8,393.60	390.53	-8,885.66	8,894.01	0.00	0.00	0.00
17,200.00	90.71	269.99	8,392.36	390.52	-8,985.66	8,993.93	0.00	0.00	0.00
17,300.00	90.71	269.99	8,391.13	390.50	-9,085.65	9,093.86	0.00	0.00	0.00
17,400.00	90.71	269.99	8,389.90	390.48	-9,185.64	9,193.78	0.00	0.00	0.00
17,500.00	90.71	269.99	8,388.66	390.46	-9,285.63	9,293.71	0.00	0.00	0.00

Integrity Directional Services, LLC

Survey Report



Company: CL&F Operating LLC
Project: Eddy County, NM (NAD 83)
Site: Sec 2, T20S, R30E
Well: Crazy Horse 1H
Wellbore: Wellbore #1
Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
TVD Reference: KB=25 @ 3239.00ft
MD Reference: KB=25 @ 3239.00ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Multi User Db

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
17,600.00	90.71	269.99	8,387.43	390.44	-9,385.63	9,393.63	0.00	0.00	0.00
17,700.00	90.71	269.99	8,386.20	390.42	-9,485.62	9,493.56	0.00	0.00	0.00
17,800.00	90.71	269.99	8,384.96	390.40	-9,585.61	9,593.48	0.00	0.00	0.00
17,900.00	90.71	269.99	8,383.73	390.38	-9,685.60	9,693.40	0.00	0.00	0.00
18,000.00	90.71	269.99	8,382.50	390.36	-9,785.60	9,793.33	0.00	0.00	0.00
18,100.00	90.71	269.99	8,381.26	390.34	-9,885.59	9,893.25	0.00	0.00	0.00
18,200.00	90.71	269.99	8,380.03	390.33	-9,985.58	9,993.18	0.00	0.00	0.00
18,300.00	90.71	269.99	8,378.80	390.31	-10,085.57	10,093.10	0.00	0.00	0.00
18,400.00	90.71	269.99	8,377.57	390.29	-10,185.57	10,193.03	0.00	0.00	0.00
18,500.00	90.71	269.99	8,376.33	390.27	-10,285.56	10,292.95	0.00	0.00	0.00
18,600.00	90.71	269.99	8,375.10	390.25	-10,385.55	10,392.88	0.00	0.00	0.00
18,700.00	90.71	269.99	8,373.87	390.23	-10,485.54	10,492.80	0.00	0.00	0.00
18,800.00	90.71	269.99	8,372.63	390.21	-10,585.53	10,592.72	0.00	0.00	0.00
18,851.29	90.71	269.99	8,372.00	390.20	-10,636.82	10,643.98	0.00	0.00	0.00

TD at 18851.29 - Crazy Horse 1H BHL

Design Targets

Target Name

- hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Crazy Horse 1H BHL - plan hits target center - Point	0.00	0.00	8,372.00	390.20	-10,636.82	580,916.5000	648,764.7000	32.596508	-103.984505
Crazy Horse 1H EP - plan hits target center - Point	0.00	0.00	8,496.00	392.12	-581.67	580,918.4192	658,819.8312	32.596418	-103.951855

Formations

Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
68.00	68.00	Bone Springs			
1,836.00	1,836.00	Yates	Empty	0.00	
2,135.00	2,135.00	Seven Rivers	Empty	0.00	
3,619.00	3,619.00	Delaware Sand	Empty	0.00	
7,627.20	7,611.00	1st Bone Springs Sand	Empty	0.00	
8,389.64	8,339.00	2nd Bone Springs Sand	Empty	0.00	
8,646.81	8,475.00	Upper Target Window	Empty	0.00	
8,713.23	8,490.00	Target	Empty	0.00	

Integrity Directional Services, LLC
Survey Report



Company: CL&F Operating LLC
Project: Eddy County, NM (NAD 83)
Site: Sec 2, T20S, R30E
Well: Crazy Horse 1H
Wellbore: Wellbore #1
Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
TVD Reference: KB=25 @ 3239.00ft
MD Reference: KB=25 @ 3239.00ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Multi User Db

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
4471	4471	0	0	Start Build 2.00
4771	4770	15	-4	Start 3282.36 hold at 4770.85 MD
8053	8035	345	-99	Start DLS 12.00 TFO -74.08
8795	8496	392	-582	Start 10055.92 hold at 8795.37 MD
18,851	8372	390	-10,637	TD at 18851.29

Checked By: _____ Approved By: _____ .Date: _____

CL&F Operating LLC

Eddy County, NM (NAD 83)

Sec 2, T20S, R30E

Crazy Horse 1H

Wellbore #1

Plan #1

Anticollision Report

11 October, 2017



Integrity Directional Services, LLC

Anticollision Report



Company: CL&F Operating LLC	Local Co-ordinate Reference: Well Crazy Horse 1H
Project: Eddy County, NM (NAD 83)	TVD Reference: KB=25 @ 3239.00ft
Reference Site: Sec 2, T20S, R30E	MD Reference: KB=25 @ 3239.00ft
Site Error: 0.00 ft	North Reference: Grid
Reference Well: Crazy Horse 1H	Survey Calculation Method: Minimum Curvature
Well Error: 0.00 ft	Output errors are at 2.00 sigma
Reference Wellbore Wellbore #1	Database: EDM 5000.1 Multi User Db
Reference Design: Plan #1	Offset TVD Reference: Offset Datum

Reference Plan #1	
Filter type: NO GLOBAL FILTER: Using user defined selection & filtering criteria	
Interpolation Method: MD + Stations Interval 100.00ft	Error Model: ISCWSA
Depth Range: Unlimited	Scan Method: Closest Approach 3D
Results Limited by: Maximum center-center distance of 10,000.00 ft	Error Surface: Elliptical Conic
Warning Levels Evaluated at: 2.00 Sigma	Casing Method: Not applied

Survey Tool Program	Date 10/11/2017	
From (ft)	To (ft)	Survey (Wellbore)
0.00	18,850.65	Plan #1 (Wellbore #1)
		Tool Name MWD
		Description MWD - Standard

Site Name	Reference Measured Depth (ft)	Offset Measured Depth (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
Sec 2, T20S, R30E						
Crazy Horse 2H - Wellbore #1 - Plan #1	3,558.39	3,558.39	29.99	14.27	1.908	CC
Crazy Horse 2H - Wellbore #1 - Plan #1	3,600.00	3,599.96	30.00	14.10	1.887	ES
Crazy Horse 2H - Wellbore #1 - Plan #1	3,700.00	3,699.68	30.58	14.23	1.871	SF

Offset Design Sec 2, T20S, R30E - Crazy Horse 2H - Wellbore #1 - Plan #1												Offset Site Error:	0.00 ft
Survey Program: 0-MWD												Offset Well Error:	0.00 ft
Reference Measured Depth (ft)	Vertical Depth (ft)	Offset Measured Depth (ft)	Vertical Depth (ft)	Semi Major Axis Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
0.00	0.00	0.00	0.00	0.00	0.00	74.53	8.00	28.90	29.99				
100.00	100.00	100.00	100.00	0.08	0.08	74.53	8.00	28.90	29.99	29.82	0.17	177.885	
200.00	200.00	200.00	200.00	0.31	0.31	74.53	8.00	28.90	29.99	29.37	0.62	48.514	
300.00	300.00	300.00	300.00	0.53	0.53	74.53	8.00	28.90	29.99	28.92	1.07	28.087	
400.00	400.00	400.00	400.00	0.76	0.76	74.53	8.00	28.90	29.99	28.47	1.52	19.765	
500.00	500.00	500.00	500.00	0.98	0.98	74.53	8.00	28.90	29.99	28.02	1.97	15.247	
600.00	600.00	600.00	600.00	1.21	1.21	74.53	8.00	28.90	29.99	27.57	2.42	12.411	
700.00	700.00	700.00	700.00	1.43	1.43	74.53	8.00	28.90	29.99	27.12	2.87	10.464	
800.00	800.00	800.00	800.00	1.66	1.66	74.53	8.00	28.90	29.99	26.67	3.32	9.045	
900.00	900.00	900.00	900.00	1.88	1.88	74.53	8.00	28.90	29.99	26.22	3.76	7.965	
1,000.00	1,000.00	1,000.00	1,000.00	2.11	2.11	74.53	8.00	28.90	29.99	25.77	4.21	7.115	
1,100.00	1,100.00	1,100.00	1,100.00	2.33	2.33	74.53	8.00	28.90	29.99	25.32	4.66	6.430	
1,200.00	1,200.00	1,200.00	1,200.00	2.56	2.56	74.53	8.00	28.90	29.99	24.87	5.11	5.864	
1,300.00	1,300.00	1,300.00	1,300.00	2.78	2.78	74.53	8.00	28.90	29.99	24.42	5.56	5.390	
1,400.00	1,400.00	1,400.00	1,400.00	3.01	3.01	74.53	8.00	28.90	29.99	23.97	6.01	4.987	
1,500.00	1,500.00	1,500.00	1,500.00	3.23	3.23	74.53	8.00	28.90	29.99	23.52	6.46	4.640	
1,600.00	1,600.00	1,600.00	1,600.00	3.46	3.46	74.53	8.00	28.90	29.99	23.08	6.91	4.339	
1,700.00	1,700.00	1,700.00	1,700.00	3.68	3.68	74.53	8.00	28.90	29.99	22.63	7.36	4.074	
1,800.00	1,800.00	1,800.00	1,800.00	3.91	3.91	74.53	8.00	28.90	29.99	22.18	7.81	3.839	
1,900.00	1,900.00	1,900.00	1,900.00	4.13	4.13	74.53	8.00	28.90	29.99	21.73	8.26	3.630	
2,000.00	2,000.00	2,000.00	2,000.00	4.35	4.35	74.53	8.00	28.90	29.99	21.28	8.71	3.443	
2,100.00	2,100.00	2,100.00	2,100.00	4.58	4.58	74.53	8.00	28.90	29.99	20.83	9.16	3.274	
2,200.00	2,200.00	2,200.00	2,200.00	4.80	4.80	74.53	8.00	28.90	29.99	20.38	9.61	3.121	
2,300.00	2,300.00	2,300.00	2,300.00	5.03	5.03	74.53	8.00	28.90	29.99	19.93	10.06	2.981	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Integrity Directional Services, LLC

Anticollision Report



Company: CL&F Operating LLC
Project: Eddy County, NM (NAD 83)
Reference Site: Sec 2, T20S, R30E
Site Error: 0.00 ft
Reference Well: Crazy Horse 1H
Well Error: 0.00 ft
Reference Wellbore: Wellbore #1
Reference Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
TVD Reference: KB=25 @ 3239.00ft
MD Reference: KB=25 @ 3239.00ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: EDM 5000.1 Multi User Db
Offset TVD Reference: Offset Datum

Offset Design Sec 2, T20S, R30E - Crazy Horse 2H - Wellbore #1 - Plan #1													Offset Site Error:	0.00 ft
Survey Program: 0-MWD													Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	Offset Wellbore Centre +E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor		
2,400.00	2,400.00	2,400.00	2,400.00	5.25	5.25	74.53	8.00	28.90	29.99	19.48	10.51	2.854		
2,500.00	2,500.00	2,500.00	2,500.00	5.48	5.48	74.53	8.00	28.90	29.99	19.03	10.96	2.737		
2,600.00	2,600.00	2,600.00	2,600.00	5.70	5.70	74.53	8.00	28.90	29.99	18.58	11.41	2.629		
2,700.00	2,700.00	2,700.00	2,700.00	5.93	5.93	74.53	8.00	28.90	29.99	18.13	11.86	2.529		
2,800.00	2,800.00	2,800.00	2,800.00	6.15	6.15	74.53	8.00	28.90	29.99	17.68	12.31	2.437		
2,900.00	2,900.00	2,900.00	2,900.00	6.38	6.38	74.53	8.00	28.90	29.99	17.23	12.76	2.351		
3,000.00	3,000.00	3,000.00	3,000.00	6.60	6.60	74.53	8.00	28.90	29.99	16.78	13.21	2.271		
3,100.00	3,100.00	3,100.00	3,100.00	6.83	6.83	74.53	8.00	28.90	29.99	16.33	13.65	2.196		
3,200.00	3,200.00	3,200.00	3,200.00	7.05	7.05	74.53	8.00	28.90	29.99	15.88	14.10	2.126		
3,300.00	3,300.00	3,300.00	3,300.00	7.28	7.28	74.53	8.00	28.90	29.99	15.43	14.55	2.060		
3,400.00	3,400.00	3,400.00	3,400.00	7.50	7.50	74.53	8.00	28.90	29.99	14.98	15.00	1.999		
3,500.00	3,500.00	3,500.00	3,500.00	7.73	7.73	74.53	8.00	28.90	29.99	14.53	15.45	1.941		
3,558.39	3,558.39	3,558.39	3,558.39	7.86	7.86	74.53	8.00	28.90	29.99	14.27	15.72	1.908 CC		
3,600.00	3,600.00	3,599.96	3,599.96	7.95	7.95	74.40	8.07	28.90	30.00	14.10	15.90	1.887 ES		
3,700.00	3,700.00	3,699.68	3,699.65	8.18	8.18	69.93	10.49	28.73	30.58	14.23	16.35	1.871 SF		
3,800.00	3,800.00	3,799.11	3,799.90	8.40	8.40	59.99	16.36	28.32	32.72	15.92	16.80	1.948		
3,900.00	3,900.00	3,898.02	3,897.37	8.63	8.62	47.24	25.59	27.67	37.78	20.54	17.24	2.191		
4,000.00	4,000.00	3,996.17	3,994.71	8.85	8.84	35.12	38.10	26.79	46.88	29.19	17.69	2.650		
4,100.00	4,100.00	4,094.38	4,091.72	9.07	9.07	25.73	53.38	25.73	59.83	41.69	18.15	3.297		
4,200.00	4,200.00	4,193.11	4,189.20	9.30	9.31	19.64	69.03	24.63	74.08	55.48	18.60	3.983		
4,300.00	4,300.00	4,291.84	4,286.67	9.52	9.56	15.53	84.68	23.54	88.89	69.84	19.05	4.665		
4,400.00	4,400.00	4,390.57	4,384.15	9.75	9.81	12.61	100.32	22.44	104.02	84.51	19.51	5.332		
4,470.85	4,470.85	4,460.52	4,453.20	9.91	10.00	11.01	111.41	21.67	114.86	95.03	19.83	5.792		
4,500.00	4,500.00	4,489.33	4,481.64	9.97	10.07	26.36	115.98	21.35	119.21	99.27	19.94	5.978		
4,600.00	4,599.96	4,588.44	4,579.50	10.20	10.34	25.07	131.69	20.25	132.19	111.80	20.38	6.485		
4,700.00	4,699.76	4,687.95	4,677.74	10.42	10.61	24.59	147.46	19.15	142.05	121.24	20.81	6.826		
4,770.85	4,770.30	4,758.61	4,747.51	10.58	10.81	24.64	158.66	18.36	147.12	126.02	21.10	6.972		
4,800.00	4,799.29	4,787.71	4,776.24	10.65	10.89	24.74	163.27	18.04	148.88	127.65	21.24	7.011		
4,900.00	4,898.74	4,887.52	4,874.78	10.87	11.17	25.04	179.09	16.94	154.93	133.23	21.70	7.140		
5,000.00	4,998.20	4,987.33	4,973.33	11.10	11.45	25.33	194.91	15.83	160.98	138.81	22.16	7.263		
5,100.00	5,097.65	5,087.15	5,071.87	11.33	11.75	25.59	210.73	14.72	167.03	144.40	22.63	7.381		
5,200.00	5,197.10	5,186.96	5,170.42	11.56	12.05	25.84	226.55	13.62	173.09	149.99	23.10	7.493		
5,300.00	5,296.55	5,286.78	5,268.97	11.80	12.34	26.07	242.37	12.51	179.15	155.58	23.57	7.601		
5,400.00	5,396.01	5,386.59	5,367.51	12.04	12.64	26.29	258.19	11.40	185.21	161.17	24.04	7.703		
5,500.00	5,495.46	5,486.40	5,466.06	12.28	12.95	26.49	274.01	10.30	191.27	166.76	24.52	7.802		
5,600.00	5,594.91	5,585.22	5,564.60	12.52	13.26	26.67	289.83	9.19	197.34	172.35	24.99	7.896		
5,700.00	5,694.36	5,686.03	5,663.15	12.77	13.57	26.85	305.65	8.08	203.41	177.94	25.47	7.986		
5,800.00	5,793.81	5,785.84	5,761.69	13.02	13.88	27.02	321.47	6.98	209.48	183.53	25.95	8.073		
5,900.00	5,893.27	5,885.66	5,860.24	13.26	14.19	27.18	337.29	5.87	215.55	189.12	26.43	8.156		
6,000.00	5,992.72	5,985.47	5,958.79	13.52	14.51	27.33	353.11	4.77	221.63	194.72	26.91	8.235		
6,100.00	6,092.17	6,085.29	6,057.33	13.77	14.82	27.47	368.93	3.66	227.70	200.31	27.39	8.312		
6,200.00	6,191.62	6,185.10	6,155.88	14.02	15.14	27.60	384.75	2.55	233.78	205.90	27.88	8.386		
6,300.00	6,291.08	6,284.91	6,254.42	14.28	15.47	27.73	400.57	1.45	239.86	211.49	28.36	8.456		
6,400.00	6,390.53	6,384.73	6,352.97	14.53	15.79	27.85	416.39	0.34	245.94	217.08	28.85	8.524		
6,500.00	6,489.98	6,484.54	6,451.52	14.79	16.11	27.96	432.21	-0.77	252.02	222.68	29.34	8.590		
6,600.00	6,589.43	6,584.35	6,550.06	15.05	16.44	28.07	448.03	-1.87	258.10	228.27	29.83	8.653		
6,700.00	6,688.88	6,684.17	6,648.61	15.31	16.77	28.18	463.85	-2.98	264.18	233.86	30.32	8.714		
6,800.00	6,788.34	6,783.98	6,747.15	15.57	17.10	28.28	479.67	-4.09	270.26	239.45	30.81	8.772		
6,900.00	6,887.79	6,883.80	6,845.70	15.83	17.42	28.37	495.49	-5.19	276.34	245.04	31.30	8.829		
7,000.00	6,987.24	6,983.61	6,944.25	16.09	17.76	28.46	511.31	-6.30	282.43	250.64	31.79	8.884		
7,100.00	7,086.69	7,083.42	7,042.79	16.36	18.09	28.55	527.13	-7.40	288.51	256.23	32.29	8.936		
7,200.00	7,186.14	7,183.24	7,141.34	16.62	18.42	28.63	542.95	-8.51	294.60	261.82	32.78	8.987		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Integrity Directional Services, LLC

Anticollision Report



Company: CL&F Operating LLC
Project: Eddy County, NM (NAD 83)
Reference Site: Sec 2, T20S, R30E
Site Error: 0.00 ft
Reference Well: Crazy Horse 1H
Well Error: 0.00 ft
Reference Wellbore: Wellbore #1
Reference Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
TVD Reference: KB=25 @ 3239.00ft
MD Reference: KB=25 @ 3239.00ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.1 Multi User Db
Offset TVD Reference: Offset Datum

Offset Design Sec 2, T20S, R30E - Crazy Horse 2H - Wellbore #1 - Plan #1												Offset Site Error:	0.00 ft
Survey Program: 0-MWD												Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (ft)	Separation Factor	Warning		
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Between Centres (ft)	Between Ellipses (ft)					
7,300.00	7,285.60	7,283.05	7,239.88	16.89	18.75	28.72	558.77	-9.62	300.69	267.41	33.27	9.036	
7,400.00	7,385.05	7,382.86	7,338.43	17.15	19.09	28.79	574.59	-10.72	306.77	273.00	33.77	9.084	
7,500.00	7,484.50	7,482.68	7,436.97	17.42	19.42	28.87	590.41	-11.83	312.86	278.59	34.27	9.130	
7,600.00	7,583.95	7,582.49	7,535.52	17.69	19.76	28.94	606.23	-12.94	318.95	284.18	34.76	9.175	
7,700.00	7,683.41	7,682.31	7,634.07	17.95	20.10	29.01	622.05	-14.04	325.04	289.77	35.26	9.218	
7,800.00	7,782.86	7,782.12	7,732.61	18.22	20.44	29.07	637.87	-15.15	331.12	295.36	35.76	9.259	
7,900.00	7,882.31	7,881.93	7,831.16	18.49	20.77	29.14	653.69	-16.25	337.21	300.95	36.26	9.300	
8,000.00	7,981.76	7,981.75	7,929.70	18.76	21.11	29.20	669.51	-17.36	343.30	306.54	36.76	9.339	
8,053.21	8,034.68	8,032.31	7,979.59	18.91	21.29	29.16	677.70	-18.33	346.64	309.62	37.02	9.364	
8,075.00	8,056.33	8,050.00	7,996.95	18.96	21.35	49.32	680.89	-19.42	348.31	311.20	37.11	9.386	
8,100.00	8,081.07	8,074.15	8,020.53	19.03	21.44	63.99	685.59	-21.70	350.66	313.44	37.23	9.420	
8,125.00	8,105.65	8,096.41	8,042.09	19.10	21.52	72.71	690.26	-24.62	353.49	316.15	37.34	9.468	
8,150.00	8,130.00	8,118.60	8,063.40	19.17	21.61	78.14	695.24	-28.31	356.77	319.32	37.45	9.527	
8,175.00	8,154.05	8,140.71	8,084.41	19.24	21.71	81.70	700.51	-32.75	360.50	322.94	37.56	9.598	
8,200.00	8,177.74	8,162.76	8,105.10	19.32	21.80	84.15	706.06	-37.93	364.67	326.99	37.68	9.679	
8,225.00	8,200.99	8,184.73	8,125.45	19.40	21.90	85.87	711.89	-43.83	369.27	331.47	37.80	9.769	
8,250.00	8,223.75	8,206.63	8,145.42	19.48	22.01	87.10	717.98	-50.44	374.28	336.35	37.93	9.869	
8,275.00	8,245.96	8,228.46	8,164.99	19.57	22.12	87.99	724.32	-57.74	379.69	341.64	38.06	9.977	
8,300.00	8,267.55	8,250.00	8,183.94	19.66	22.22	88.62	730.84	-65.64	385.50	347.31	38.20	10.093	
8,325.00	8,288.46	8,271.91	8,202.82	19.76	22.34	89.06	737.71	-74.35	391.69	353.34	38.35	10.214	
8,350.00	8,308.64	8,293.53	8,221.05	19.86	22.46	89.35	744.73	-83.63	398.24	359.74	38.50	10.343	
8,375.00	8,328.03	8,315.10	8,238.80	19.97	22.59	89.52	751.96	-93.52	405.15	366.47	38.68	10.475	
8,400.00	8,346.58	8,336.61	8,256.04	20.09	22.72	89.59	759.38	-104.03	412.40	373.54	38.86	10.612	
8,425.00	8,364.24	8,358.08	8,272.76	20.22	22.85	89.59	766.99	-115.12	419.98	380.92	39.06	10.752	
8,450.00	8,380.96	8,379.50	8,288.95	20.35	22.99	89.51	774.78	-125.78	427.87	388.59	39.28	10.894	
8,475.00	8,396.69	8,400.00	8,303.96	20.50	23.13	89.35	782.40	-138.49	436.06	396.55	39.50	11.038	
8,500.00	8,411.39	8,422.26	8,319.68	20.67	23.29	89.18	790.85	-151.78	444.53	404.76	39.77	11.178	
8,525.00	8,425.02	8,443.61	8,334.19	20.84	23.44	88.95	799.12	-165.09	453.28	413.23	40.04	11.320	
8,550.00	8,437.54	8,464.97	8,348.12	21.04	23.61	88.68	807.53	-178.92	462.28	421.93	40.34	11.459	
8,575.00	8,448.92	8,486.33	8,361.46	21.25	23.78	88.37	816.08	-193.26	471.52	430.85	40.67	11.595	
8,600.00	8,459.13	8,507.73	8,374.19	21.48	23.96	88.03	824.76	-208.10	480.98	439.97	41.01	11.727	
8,625.00	8,468.14	8,529.17	8,386.30	21.73	24.16	87.66	833.57	-223.44	490.66	449.27	41.39	11.854	
8,650.00	8,475.92	8,550.67	8,397.78	21.99	24.35	87.26	842.50	-239.26	500.53	458.74	41.79	11.977	
8,675.00	8,482.46	8,571.55	8,408.29	22.27	24.56	86.82	851.27	-255.04	510.58	468.36	42.22	12.094	
8,700.00	8,487.73	8,591.48	8,417.75	22.57	24.76	86.32	859.74	-270.40	520.85	478.19	42.66	12.210	
8,725.00	8,491.72	8,611.37	8,426.64	22.89	24.97	85.80	868.31	-285.99	531.34	488.21	43.13	12.320	
8,750.00	8,494.42	8,631.23	8,434.96	23.22	25.19	85.26	876.96	-301.82	542.04	498.42	43.62	12.427	
8,775.00	8,495.82	8,651.08	8,442.71	23.57	25.41	84.71	885.69	-317.86	552.93	508.80	44.13	12.530	
8,795.37	8,496.00	8,667.25	8,448.60	23.86	25.61	84.24	892.86	-331.10	561.94	517.37	44.57	12.608	
8,800.00	8,495.95	8,670.93	8,449.89	23.93	25.65	84.41	894.50	-334.14	564.00	519.32	44.67	12.625	
8,900.00	8,494.71	8,754.60	8,473.71	25.50	26.75	87.41	932.35	-404.79	609.55	562.45	47.10	12.941	
9,000.00	8,493.48	8,844.63	8,487.38	27.26	28.08	89.03	973.75	-483.46	655.80	605.92	49.88	13.148	
9,100.00	8,492.25	8,936.13	8,489.15	29.19	29.59	89.35	1,015.78	-564.68	701.75	648.74	53.01	13.238	
9,200.00	8,491.01	9,025.01	8,488.24	31.23	31.15	89.40	1,056.50	-643.67	747.59	691.24	56.34	13.268	
9,300.00	8,489.78	9,113.89	8,487.32	33.39	32.83	89.44	1,097.23	-722.66	793.42	733.54	59.88	13.250	
9,400.00	8,488.55	9,202.76	8,486.40	35.62	34.58	89.47	1,137.95	-801.65	839.26	775.66	63.60	13.197	
9,500.00	8,487.32	9,291.64	8,485.49	37.93	36.42	89.50	1,178.67	-880.64	885.09	817.63	67.46	13.120	
9,600.00	8,486.08	9,380.51	8,484.57	40.29	38.31	89.53	1,219.40	-959.63	930.93	859.48	71.45	13.029	
9,700.00	8,484.85	9,469.39	8,483.65	42.71	40.26	89.56	1,260.12	-1,038.63	976.77	901.23	75.54	12.930	
9,800.00	8,483.62	9,558.26	8,482.74	45.16	42.26	89.58	1,300.84	-1,117.62	1,022.60	942.89	79.72	12.828	
9,900.00	8,482.38	9,647.14	8,481.82	47.64	44.29	89.60	1,341.57	-1,196.61	1,068.44	984.47	83.97	12.724	
10,000.00	8,481.15	9,762.16	8,480.63	50.16	46.97	89.63	1,393.57	-1,299.20	1,113.80	1,024.96	88.83	12.538	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Integrity Directional Services, LLC

Anticollision Report



Company: CL&F Operating LLC
Project: Eddy County, NM (NAD 83)
Reference Site: Sec 2, T20S, R30E
Site Error: 0.00 ft
Reference Well: Crazy Horse 1H
Well Error: 0.00 ft
Reference Wellbore: Wellbore #1
Reference Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
TVD Reference: KB=25 @ 3239.00ft
MD Reference: KB=25 @ 3239.00ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.1 Multi User Db
Offset TVD Reference: Offset Datum

Offset Design Sec 2, T20S, R30E - Crazy Horse 2H - Wellbore #1 - Plan #1												Offset Site Error:	0.00 ft
Survey Program: O-MWD												Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (ft)	Separation Factor	Warning		
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)					
10,100.00	8,479.92	9,912.92	8,479.02	52.69	50.54	89.65	1,455.89	-1,436.44	1,155.17	1,060.57	94.60	12.211	
10,200.00	8,478.68	10,070.69	8,477.27	55.25	54.33	89.67	1,513.28	-1,583.37	1,191.58	1,090.85	100.73	11.830	
10,300.00	8,477.45	10,234.95	8,475.39	57.83	58.31	89.69	1,564.34	-1,739.46	1,222.70	1,115.51	107.19	11.407	
10,400.00	8,476.22	10,404.98	8,473.39	60.43	62.46	89.70	1,607.68	-1,903.84	1,248.22	1,134.27	113.95	10.954	
10,500.00	8,474.98	10,579.83	8,471.28	63.03	66.72	89.71	1,642.00	-2,075.24	1,267.88	1,146.91	120.98	10.480	
10,600.00	8,473.75	10,758.35	8,469.07	65.65	71.05	89.72	1,666.19	-2,252.07	1,281.46	1,153.26	128.21	9.995	
10,700.00	8,472.52	10,939.24	8,466.79	68.29	75.39	89.72	1,679.42	-2,432.43	1,288.80	1,153.23	135.57	9.507	
10,800.00	8,471.28	11,071.40	8,465.11	70.93	78.54	89.71	1,682.52	-2,564.54	1,290.97	1,149.20	141.69	9.111	
10,900.00	8,470.05	11,171.38	8,463.83	73.58	80.94	89.71	1,684.18	-2,664.50	1,292.66	1,145.68	146.99	8.794	
11,000.00	8,468.82	11,271.37	8,462.55	76.23	83.36	89.71	1,685.85	-2,764.47	1,294.35	1,142.05	152.30	8.499	
11,100.00	8,467.58	11,371.36	8,461.28	78.90	85.81	89.71	1,687.52	-2,864.43	1,296.03	1,138.41	157.62	8.222	
11,200.00	8,466.35	11,471.34	8,460.00	81.57	88.27	89.71	1,689.18	-2,964.40	1,297.72	1,134.76	162.96	7.963	
11,300.00	8,465.12	11,571.33	8,458.72	84.24	90.75	89.71	1,690.85	-3,064.36	1,299.41	1,131.10	168.31	7.720	
11,400.00	8,463.89	11,671.31	8,457.45	86.93	93.24	89.70	1,692.52	-3,164.32	1,301.09	1,127.43	173.67	7.492	
11,500.00	8,462.65	11,771.30	8,456.17	89.61	95.75	89.70	1,694.18	-3,264.29	1,302.78	1,123.74	179.04	7.277	
11,600.00	8,461.42	11,871.28	8,454.90	92.30	98.28	89.70	1,695.85	-3,364.25	1,304.47	1,120.05	184.42	7.073	
11,700.00	8,460.19	11,971.27	8,453.62	95.00	100.81	89.70	1,697.52	-3,464.21	1,306.15	1,116.35	189.80	6.882	
11,800.00	8,458.95	12,071.26	8,452.34	97.69	103.36	89.70	1,699.19	-3,564.18	1,307.84	1,112.64	195.20	6.700	
11,900.00	8,457.72	12,171.24	8,451.07	100.39	105.92	89.70	1,700.85	-3,664.14	1,309.53	1,108.93	200.60	6.528	
12,000.00	8,456.49	12,271.23	8,449.79	103.10	108.49	89.70	1,702.52	-3,764.10	1,311.21	1,105.21	206.00	6.365	
12,100.00	8,455.25	12,371.21	8,448.52	105.80	111.07	89.69	1,704.19	-3,864.07	1,312.90	1,101.48	211.42	6.210	
12,200.00	8,454.02	12,471.20	8,447.24	108.51	113.66	89.69	1,705.85	-3,964.03	1,314.59	1,097.75	216.83	6.063	
12,300.00	8,452.79	12,571.19	8,445.96	111.23	116.26	89.69	1,707.52	-4,064.00	1,316.27	1,094.01	222.26	5.922	
12,400.00	8,451.55	12,671.17	8,444.69	113.94	118.86	89.69	1,709.19	-4,163.96	1,317.96	1,090.27	227.69	5.789	
12,500.00	8,450.32	12,771.16	8,443.41	116.66	121.47	89.69	1,710.85	-4,263.92	1,319.64	1,086.53	233.12	5.661	
12,600.00	8,449.09	12,871.14	8,442.14	119.37	124.09	89.69	1,712.52	-4,363.89	1,321.33	1,082.78	238.55	5.539	
12,700.00	8,447.85	12,971.13	8,440.86	122.09	126.71	89.69	1,714.19	-4,463.85	1,323.02	1,079.02	243.99	5.422	
12,800.00	8,446.62	13,071.11	8,439.58	124.82	129.34	89.68	1,715.85	-4,563.81	1,324.70	1,075.27	249.44	5.311	
12,900.00	8,445.39	13,171.10	8,438.31	127.54	131.97	89.68	1,717.52	-4,663.78	1,326.39	1,071.51	254.88	5.204	
13,000.00	8,444.16	13,271.09	8,437.03	130.26	134.61	89.68	1,719.19	-4,763.74	1,328.08	1,067.75	260.33	5.101	
13,100.00	8,442.92	13,371.07	8,435.76	132.99	137.26	89.68	1,720.86	-4,863.71	1,329.76	1,063.98	265.78	5.003	
13,200.00	8,441.69	13,471.06	8,434.48	135.72	139.91	89.68	1,722.52	-4,963.67	1,331.45	1,060.21	271.24	4.909	
13,300.00	8,440.46	13,571.04	8,433.20	138.44	142.56	89.68	1,724.19	-5,063.63	1,333.14	1,056.44	276.69	4.818	
13,400.00	8,439.22	13,671.03	8,431.93	141.17	145.22	89.67	1,725.86	-5,163.60	1,334.82	1,052.67	282.15	4.731	
13,500.00	8,437.99	13,771.01	8,430.65	143.90	147.88	89.67	1,727.52	-5,263.56	1,336.51	1,048.89	287.62	4.647	
13,600.00	8,436.76	13,871.00	8,429.38	146.64	150.55	89.67	1,729.19	-5,363.52	1,338.20	1,045.12	293.08	4.566	
13,700.00	8,435.52	13,970.99	8,428.10	149.37	153.21	89.67	1,730.86	-5,463.49	1,339.88	1,041.34	298.55	4.488	
13,800.00	8,434.29	14,070.97	8,426.82	152.10	155.89	89.67	1,732.52	-5,563.45	1,341.57	1,037.55	304.01	4.413	
13,900.00	8,433.06	14,170.96	8,425.55	154.84	158.56	89.67	1,734.19	-5,663.42	1,343.25	1,033.77	309.48	4.340	
14,000.00	8,431.82	14,270.94	8,424.27	157.57	161.24	89.67	1,735.86	-5,763.38	1,344.94	1,029.99	314.96	4.270	
14,100.00	8,430.59	14,370.93	8,423.00	160.31	163.92	89.66	1,737.52	-5,863.34	1,346.63	1,026.20	320.43	4.203	
14,200.00	8,429.36	14,470.92	8,421.72	163.05	166.60	89.66	1,739.19	-5,963.31	1,348.31	1,022.41	325.90	4.137	
14,300.00	8,428.12	14,570.90	8,420.44	165.78	169.29	89.66	1,740.86	-6,063.27	1,350.00	1,018.62	331.38	4.074	
14,400.00	8,426.89	14,670.89	8,419.17	168.52	171.98	89.66	1,742.53	-6,163.23	1,351.69	1,014.83	336.86	4.013	
14,500.00	8,425.66	14,770.87	8,417.89	171.25	174.67	89.66	1,744.19	-6,263.20	1,353.37	1,011.04	342.33	3.953	
14,600.00	8,424.42	14,870.86	8,416.62	174.00	177.36	89.66	1,745.86	-6,363.16	1,355.06	1,007.25	347.81	3.896	
14,700.00	8,423.19	14,970.84	8,415.34	176.74	180.05	89.66	1,747.53	-6,463.13	1,356.75	1,003.45	353.30	3.840	
14,800.00	8,421.96	15,070.83	8,414.06	179.48	182.75	89.65	1,749.19	-6,563.09	1,358.43	999.66	358.78	3.786	
14,900.00	8,420.73	15,170.82	8,412.79	182.22	185.45	89.65	1,750.86	-6,663.05	1,360.12	995.86	364.26	3.734	
15,000.00	8,419.49	15,270.80	8,411.51	184.96	188.15	89.65	1,752.53	-6,763.02	1,361.81	992.06	369.75	3.683	
15,100.00	8,418.26	15,370.79	8,410.23	187.71	190.85	89.65	1,754.19	-6,862.98	1,363.49	988.26	375.23	3.634	
15,200.00	8,417.03	15,470.77	8,408.96	190.45	193.56	89.65	1,755.86	-6,962.94	1,365.18	984.46	380.72	3.586	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Integrity Directional Services, LLC

Anticollision Report



Company: CL&F Operating LLC
Project: Eddy County, NM (NAD 83)
Reference Site: Sec 2, T20S, R30E
Site Error: 0.00 ft
Reference Well: Crazy Horse 1H
Well Error: 0.00 ft
Reference Wellbore: Wellbore #1
Reference Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
TVD Reference: KB=25 @ 3239.00ft
MD Reference: KB=25 @ 3239.00ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: EDM 5000.1 Multi User Db
Offset TVD Reference: Offset Datum

Offset Design Sec 2, T20S, R30E - Crazy Horse 2H - Wellbore #1 - Plan #1												Offset Site Error:	0.00 ft
Survey Program: 0-MWD												Offset Well Error:	0.00 ft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Between Centres (ft)	Between Ellipses (ft)	Minimum Separation (ft)	Separation Factor	Warning
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)		Offset Wellbore Centre +N/S (ft)	+E/W (ft)					
15,300.00	8,415.79	15,570.76	8,407.68	193.19	196.26	89.65	1,757.53	-7,062.91	1,366.87	980.66	385.20	3.539	
15,400.00	8,414.56	15,670.74	8,405.41	195.93	198.97	89.65	1,759.19	-7,162.87	1,368.55	976.86	391.69	3.494	
15,500.00	8,413.33	15,770.73	8,405.13	198.68	201.68	89.65	1,760.86	-7,262.84	1,370.24	973.06	397.18	3.450	
15,600.00	8,412.09	15,870.72	8,403.85	201.42	204.39	89.64	1,762.53	-7,362.80	1,371.92	969.25	402.67	3.407	
15,700.00	8,410.86	15,970.70	8,402.58	204.17	207.10	89.64	1,764.20	-7,462.76	1,373.61	965.45	408.16	3.365	
15,800.00	8,409.63	16,070.69	8,401.30	206.91	209.81	89.64	1,765.86	-7,562.73	1,375.30	961.64	413.65	3.325	
15,900.00	8,408.39	16,170.67	8,400.03	209.66	212.53	89.64	1,767.53	-7,662.69	1,376.98	957.84	419.15	3.285	
16,000.00	8,407.16	16,270.66	8,398.75	212.40	215.24	89.64	1,769.20	-7,762.65	1,378.67	954.03	424.64	3.247	
16,100.00	8,405.93	16,370.64	8,397.47	215.15	217.96	89.64	1,770.86	-7,862.62	1,380.36	950.23	430.13	3.209	
16,200.00	8,404.69	16,470.63	8,396.20	217.89	220.67	89.64	1,772.53	-7,962.58	1,382.04	946.42	435.62	3.173	
16,300.00	8,403.46	16,570.62	8,394.92	220.64	223.39	89.63	1,774.20	-8,062.55	1,383.73	942.61	441.12	3.137	
16,400.00	8,402.23	16,670.60	8,393.65	223.39	226.11	89.63	1,775.86	-8,162.51	1,385.42	938.80	446.61	3.102	
16,500.00	8,401.00	16,770.59	8,392.37	226.14	228.83	89.63	1,777.53	-8,262.47	1,387.10	934.99	452.11	3.068	
16,600.00	8,399.76	16,870.57	8,391.09	228.88	231.55	89.63	1,779.20	-8,362.44	1,388.79	931.18	457.61	3.035	
16,700.00	8,398.53	16,970.56	8,389.82	231.63	234.28	89.63	1,780.86	-8,462.40	1,390.48	927.37	463.10	3.003	
16,800.00	8,397.30	17,070.55	8,388.54	234.38	237.00	89.63	1,782.53	-8,562.36	1,392.16	923.56	468.60	2.971	
16,900.00	8,396.06	17,170.53	8,387.27	237.13	239.72	89.63	1,784.20	-8,662.33	1,393.85	919.75	474.10	2.940	
17,000.00	8,394.83	17,270.52	8,385.99	239.87	242.45	89.63	1,785.87	-8,762.29	1,395.54	915.94	479.60	2.910	
17,100.00	8,393.60	17,370.50	8,384.71	242.62	245.18	89.62	1,787.53	-8,862.26	1,397.22	912.13	485.10	2.880	
17,200.00	8,392.36	17,470.49	8,383.44	245.37	247.90	89.62	1,789.20	-8,962.22	1,398.91	908.31	490.59	2.851	
17,300.00	8,391.13	17,570.47	8,382.16	248.12	250.63	89.62	1,790.87	-9,062.18	1,400.59	904.50	496.09	2.823	
17,400.00	8,389.90	17,670.46	8,380.89	250.87	253.36	89.62	1,792.53	-9,162.15	1,402.28	900.69	501.59	2.796	
17,500.00	8,388.66	17,770.45	8,379.61	253.62	256.09	89.62	1,794.20	-9,262.11	1,403.97	896.87	507.09	2.769	
17,600.00	8,387.43	17,870.43	8,378.33	256.37	258.82	89.62	1,795.87	-9,362.07	1,405.65	893.06	512.59	2.742	
17,700.00	8,386.20	17,970.42	8,377.06	259.12	261.55	89.62	1,797.53	-9,462.04	1,407.34	889.24	518.10	2.716	
17,800.00	8,384.96	18,070.40	8,375.78	261.87	264.28	89.61	1,799.20	-9,562.00	1,409.03	885.43	523.60	2.691	
17,900.00	8,383.73	18,170.39	8,374.51	264.62	267.01	89.61	1,800.87	-9,661.97	1,410.71	881.61	529.10	2.666	
18,000.00	8,382.50	18,270.37	8,373.23	267.37	269.74	89.61	1,802.53	-9,761.93	1,412.40	877.80	534.60	2.642	
18,100.00	8,381.26	18,370.36	8,371.95	270.12	272.47	89.61	1,804.20	-9,861.89	1,414.09	873.98	540.10	2.618	
18,200.00	8,380.03	18,470.35	8,370.68	272.87	275.21	89.61	1,805.87	-9,961.86	1,415.77	870.17	545.61	2.595	
18,300.00	8,378.80	18,570.33	8,369.40	275.62	277.94	89.61	1,807.54	-10,061.82	1,417.46	866.35	551.11	2.572	
18,400.00	8,377.57	18,670.32	8,368.13	278.37	280.67	89.61	1,809.20	-10,161.78	1,419.15	862.53	556.61	2.550	
18,500.00	8,376.33	18,770.30	8,366.85	281.12	283.41	89.61	1,810.87	-10,261.75	1,420.83	858.72	562.12	2.528	
18,600.00	8,375.10	18,870.29	8,365.57	283.87	286.14	89.60	1,812.54	-10,361.71	1,422.52	854.90	567.62	2.506	
18,700.00	8,373.87	18,970.27	8,364.30	286.63	288.88	89.60	1,814.20	-10,461.68	1,424.21	851.08	573.13	2.485	
18,800.00	8,372.63	19,070.26	8,363.02	289.38	291.62	89.60	1,815.87	-10,561.64	1,425.89	847.26	578.63	2.464	
18,851.29	8,372.00	19,121.54	8,362.37	290.28	293.02	89.60	1,816.72	-10,612.91	1,426.76	845.81	580.95	2.456	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Integrity Directional Services, LLC
Anticollision Report




Company: CL&F Operating LLC
Project: Eddy County, NM (NAD 83)
Reference Site: Sec 2, T20S, R30E
Site Error: 0.00 ft
Reference Well: Crazy Horse 1H
Well Error: 0.00 ft
Reference Wellbore: Wellbore #1
Reference Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
TVD Reference: KB=25 @ 3239.00ft
MD Reference: KB=25 @ 3239.00ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: EDM 5000.1 Multi User Db
Offset TVD Reference: Offset Datum

Reference Depths are relative to KB=25 @ 3239.00ft
Offset Depths are relative to Offset Datum
Central Meridian is -104.333334

Coordinates are relative to: Crazy Horse 1H
Coordinate System is US State Plane 1983, New Mexico Eastern Zone
Grid Convergence at Surface is: 0.21°

Ladder Plot



LEGEND

□ Crazy Horse 2H, Wellbore #1, Plan #1 V0

Integrity Directional Services, LLC
Anticollision Report




Company: CL&F Operating LLC
Project: Eddy County, NM (NAD 83)
Reference Site: Sec 2, T20S, R30E
Site Error: 0.00 ft
Reference Well: Crazy Horse 1H
Well Error: 0.00 ft
Reference Wellbore: Wellbore #1
Reference Design: Plan #1

Local Co-ordinate Reference: Well Crazy Horse 1H
TVD Reference: KB=25 @ 3239.00ft
MD Reference: KB=25 @ 3239.00ft
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: EDM 5000.1 Multi User Db
Offset TVD Reference: Offset Datum

Reference Depths are relative to KB=25 @ 3239.00ft
Offset Depths are relative to Offset Datum
Central Meridian is -104.333334

Coordinates are relative to: Crazy Horse 1H
Coordinate System is US State Plane 1983, New Mexico Eastern Zone
Grid Convergence at Surface is: 0.21°

Separation Factor Plot



LEGEND

□ Crazy Horse 2H, Wellbore #1, Plan #1 V0

CL & F Operating LLC
Crazy Horse 0304 Fed Com 1H
SHL 110' FSL & 436' FWL Sec. 2
BHL 500' FSL & 330' FEL Sec. 4
T. 20 S., R. 30 E., Eddy County, NM

DRILL PLAN PAGE 1

Drilling Program

1. ESTIMATED TOPS

Formation Name	TVD	MD	Bearing
Quaternary caliche	000'	000'	water
Rustler anhydrite	375'	375'	N/A
Top salt	480'	480'	N/A
Tansill sandstone	1712'	1712'	N/A
Yates sandstone	1836'	1836'	N/A
Seven Rivers gypsum	2135'	2135'	N/A
Capitan Reef limestone	2293'	2293'	water
Delaware sandstone	3619'	3619'	hydrocarbons
Bone Spring carbonate	6410'	6420'	hydrocarbons
1 st Bone Spring sandstone	7611'	7627'	hydrocarbons
(KOP	8035'	8053'	hydrocarbons)
2nd Bone Spring sandstone (& goal)	8339'	8388'	hydrocarbons
Horizontal TD	8372'	18851'	hydrocarbons
Wolfcamp shale	9744'	9744'	hydrocarbons
Wolfcamp B carbonate	10215'	10215'	hydrocarbons
Strawn	10792'	10792'	hydrocarbons
Pilot Hole TD (Strawn)	10972'	10972'	hydrocarbons

2. NOTABLE ZONES

Second Bone Spring sand is the goal. Closest water well (CP 00775) is 4428' southeast. Water bearing strata were found from 46' to 336' in the 350' deep well.

CL & F Operating LLC
 Crazy Horse 0304 Fed Com 1H
 SHL 110' FSL & 436' FWL Sec. 2
 BHL 500' FSL & 330' FEL Sec. 4
 T. 20 S., R. 30 E., Eddy County, NM

DRILL PLAN PAGE 2

3. PRESSURE CONTROL

A 10,000' 2,000 psi and 5,000 psi BOPE system will be used below surface casing to TD. See attached BOP, choke manifold, co-flex hose, and speed head diagrams.

A Variance is requested from BLM for the use of a diverter on the 26" section.

A Variance is requested from BLM for the use of a 20" 3M Annular on the 17 1/2" and 12 1/4" sections.

BOP Installed on this size hole	Section Depth	MW Anticipated	Size	Min Required WP	Device Closure Type (not sequence)	Application	Tested To
26"	321'	9	None	None	Annular		100% Diverter Assy - No Test Used
					Ram		
					Ram		
					Double Pipe & Blind		
					Other - Diverter	X	
17.5"	1880'	10	20"	2M	Annular	X	50% of 2000 psi component WP
					Ram		
					Ram		
					Double Pipe & Blind		
					Other		
12.25"	3860'	8.4	20"	2M	Annular	X	50% of 2000 psi component WP
					Ram		
					Ram		
					Double Pipe & Blind		
					Other		
8.75" x 8.5"	8372' TVD 18,851' MD	9.5	13.625"	5M	Annular	X	70% of WP
					Ram		100% of 5000 psi component WP
					Ram		
					Double Pipe & Blind	X	
					Other		

CL & F Operating LLC
Crazy Horse 0304 Fed Com 1H
SHL 110' FSL & 436' FWL Sec. 2
BHL 500' FSL & 330' FEL Sec. 4
T. 20 S., R. 30 E., Eddy County, NM

DRILL PLAN PAGE 3

Independent service company will test BOP / BOPE to 250 psi low and the high pressure as listed above.
System may be upgraded to a higher pressure, but still tested at % listed for component WP as listed above.
If the system is upgraded, all the components for that section will be functional and tested.
Pipe rams will be functionally checked each 24-hour period. Blind rams will be operationally checked on each TOH.
These checks will be noted on the IADC records onsite.
Other BOPE accessories will include a kelly cock, floor safety valve, inside BOP, choke manifold, and lines.
See attached BOPE schematics.
Formation integrity test will be performed per Onshore Order # 2. On exploratory wells, or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. All will be tested in accordance with Onshore oil and Gas Order # 2 III.1.i.
A Variance is requested from BLM for the use of a flexible choke line from the BOP to the choke manifold. See attached specifications and hydrostatic test chart.
A Multibowl wellhead (may) be used. The BOP will be tested per Onshore order # 2 after installation on the 1st Intermediate casing (13 3/8" @ 1880') which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken, the system must be tested. <u>Should a conventional wellhead be used, testing provisions will apply to each section as components are set.</u>

4. CASING & CEMENT

All casing will be API and new. See attached casing assumption worksheet.

An 8.75" pilot hole will be drilled to 10,972'. It will be plugged back to the KOP (8053' MD) with 950 sacks Class H mixed at 15.6 pounds per gallon.

CL & F Operating LLC
 Crazy Horse 0304 Fed Com 1H
 SHL 110' FSL & 436' FWL Sec. 2
 BHL 500' FSL & 330' FEL Sec. 4
 T. 20 S., R. 30 E., Eddy County, NM

DRILL PLAN PAGE 4

Hole O. D.	Interval	Casing O. D.	Weight (lbs)	Grade	Joint	MW	SF Collapse	SF Burst	SF Joint Tension	SF Body Tension
36"	0' - 80'	30" cond.	157.5	H40	Weld	FW	NA	NA	NA	NA
26"	0' - 321' TVD	20" surface	94	J55	BTC	9.00	3.46	11.14	46.40	49.00
17.5"	0' - 1880' TVD	13.375" inter. 1	54.5	J55	BTC	10.00	1.29	2.46	8.87	8.32
12.25"	0' - 3680' TVD	9.625" inter. 2	40	J55	LTC	8.40	1.6	1.82	3.47	4.27
8.75" x 8.5"	0' - 8372' TVD 0' - 18851' MD	5.5" product.	20	P110	Atlas BK	9.50	3.00	1.20	2.20	2.10
				BLM Minimum Safety Factor				1.125	1.000	1.6 Dry
										1.8 Wet
All casing strings will be tested in accordance with Onshore Oil & Gas Order # 2 III.B.1.h										
Sierra Hamilton standards used for all SF calculations. Collapse 1.3, Burst 1.2, Tension Jt 1.8, Tension Body 2.0										
Assumed .70 FG and 100% evacuation of Gas @ .11 GR										

Special Conditions

Is casing new? If used, attach certification as required in Onshore Order # 1.	Y
Does Casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not, provide justification (loading assumptions, casing design criteria).	Y
Will intermediate pipe be kept at least 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is the well located within the Capitan Reef?	Y
If yes, does production casing cement tie back a minimum of 50' above the Reef?	Y
Is well within the designated 4 string boundry?	Y
Is the well located in SOPA but not R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	
Is the well located in R-111-P and SOPA?	Y
If yes, are the first three strings cemented to surface?	Y
Is 2nd string set 100' to 600' below base of salt?	Y
Is well located in high Cave / Karst?	Y

CL & F Operating LLC
 Crazy Horse 0304 Fed Com 1H
 SHL 110' FSL & 436' FWL Sec. 2
 BHL 500' FSL & 330' FEL Sec. 4
 T. 20 S., R. 30 E., Eddy County, NM

DRILL PLAN PAGE 5

If yes, are there two strings cemented to surface?	Y
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is the well located in critical Cave / Karst?	N
If yes, are there three strings cemented to surface?	

TOC for all casing will be surface.

Casing	Depth	Lead Tail	Sacks	Density ppg	Yield	Volume cu ft	H2O gal/sack	Excess OH	500# Comp Strength (hours)	Blend
30" conduct.	80'		A/R					A/R		Redi Mix
20" surface	321'	Lead	800	14.8	1.34	1072	6.3	100%	7.01	Class C & 2% PF01 (CACI2)
		Tail	None					100%		
13.375" inter. 1	1880'	Lead	1200	13.5	1.75	2100	8.9	100%	7.47	Class C & 4% PF120 (Gel) & 1% PF01 (CACI2) & 3# PF42 (Koalseal) & 1/8# PF29 (Cellophane)
		Tail	200	14.8	1.33	266	6.3	100%	4.01	Class C & 1% PF01 (CACI2)
9.625" inter. 2	3860'	Lead Stg 1	350	12.6	2.05	717	15.36	50%	11.3	Class C 35/65 Poz & 5% PF44 (Salt) & 6% PF20 (Gel) & 3# PF42 (Kolseal) & .4# PF45 (Defoam) & 1/8# PF29 (Cellophane)
		Tail Stg 1	200	14.8	1.32	264	6.3	50%	5.45	Class C & .2% PF13 (Retarder)

CL & F Operating LLC
 Crazy Horse 0304 Fed Com 1H
 SHL 110' FSL & 436' FWL Sec. 2
 BHL 500' FSL & 330' FEL Sec. 4
 T. 20 S., R. 30 E., Eddy County, NM

DRILL PLAN PAGE 6

		Lead Stg 2	220	12.6	2.05	451	15.36	50%	16.5	Class C 35/65 Poz & 5% PF44 (Salt) & 6% PF20 (Gel) & 3# PF42 (Kolseal) & .4# PF45 (Defoam) & 1/8# PF29 (Cellophane)
		Tail Stg 2	200	14.8	1.32	264	6.3	50%	5.9	Class C & .2% PF13 (Retarder)
5.5" product.	18851'	Lead	880	11.9	2.47	2173	13.84	25%	62.79	Class H 50/50 Poz & 5% PF44 (Salt) & 10% PF20 (Gel) & .2% PF153 (Anti-settle) & .4# PF45 (Defoam) & 3# PF42 (Koalseal) & 1/8# PF29 (Cellophane)
		Tail	2450	14.2	1.31	3209	5.96	25%	23.45	Class H 50/50 Poz & 5% PF44 (Salt) & 2% PF20 (Gel) & .3% FL & .1% PF813 (Retarder) & .2% PF65 (Dispersant) & .3% PF606 (Fluid Loss)
DV Tool depth(s) will be adjusted based on hole conditions. ECP usage will be determined by hole conditions at the time.										
Cement volumes will be adjusted per fluid caliper or other device if ran, percentage excess may increase.										
DV tool (if required) will be positioned 50 - 100' below 13.375" casing. Expect set depth 1730 - 1780'										
Lab reports with the 500 psi compressive strength times for all slurries will be onsite.										

CL & F Operating LLC
Crazy Horse 0304 Fed Com 1H
SHL 110' FSL & 436' FWL Sec. 2
BHL 500' FSL & 330' FEL Sec. 4
T. 20 S., R. 30 E., Eddy County, NM

DRILL PLAN PAGE 7

Bow spring centralizers will be run on every second joint of the surface casing. Bow spring centralizers will be run on every third joint of the intermediate casing strings. Bow spring centralizers will be run on every fourth joint of the vertical portion of the production casing. Positive centralizers will be run on every second joint of the curve and horizontal portions of the production casing.

5. MUD PROGRAM

Sufficient mud materials to maintain mud properties and meet minimum lost circulation (e. g., cedar bark) and weight increase (e. g., barite, bentonite) requirements will be on site at all times. A Pason, or similar, system will be used to monitor fluid loss or gain. A closed loop system will be used.

Type	Interval (MD)	lb/gal	Viscosity	Fluid Loss
fresh water	0' - 321'	8.4 - 9.0	29 - 40	NC
brine water	321' - 1880'	10.0 - 10.1	29 - 32	NC
fresh water	1880' - 3860'	8.4 - 8.7	28 - 32	NC
cut brine	3860' - 18851'	8.4 - 9.5	29 - 36	NC
brine mud	possible pilot hole (TVD) 8035' - 10972'	9.5 - 9.8	36 - 38	<10 cc

6. CORES, TESTS, & LOGS

No core or drill stem test is planned. Mud logging program will be used from ≈3300' to TD. No open hole log is planned at this time. A gyro may be used from surface to first intermediate casing shoe if warranted. GR/MWD will be used from 80' to TD. Completion CBL may be run in vertical to free fall depth of curve 40' ±.

CL & F Operating LLC
Crazy Horse 0304 Fed Com 1H
SHL 110' FSL & 436' FWL Sec. 2
BHL 500' FSL & 330' FEL Sec. 4
T. 20 S., R. 30 E., Eddy County, NM

DRILL PLAN PAGE 8

7. DOWN HOLE CONDITIONS

Maximum expected bottom hole pressure is ≈ 4344 psi. Expected bottom hole temperature is $\approx 140^{\circ}$ F. Water flows, lost circulation, and abnormally high pressures are possible from the Sevens Rivers to TD.

H₂S is potentially present from the Seven Rivers to TD. H₂S monitors will be installed before drilling out of the surface casing. If H₂S is detected in concentrations > 100 ppm, then CL & F will comply with Onshore Order 6. If H₂S is encountered, then CL & F will provide measured values and formations to BLM.

8. OTHER INFORMATION

Anticipated spud date is upon approval. It is expected it will take ≈ 3 months to drill and complete the well.

Wellhead Conventional



Crazy Horse 1H, 2H, 3H, 4H
Conventional Wellhead
13-3/8" X 9-5/8" X 7"
Quote# WH170816-010

Tubing Head


11"-5M x 7"-10M w/SSO
(2) 1-13/16"-10M HWO
Gate Valve
(2) 1-13/16"-10M x 2" LPO

Casing Spool

13-3/8"-3M x 11"-5M
BP, w/2 2-1/16"-5M SSO

Casing Head

13-5/8"-3M x 13-3/8" SOW
2-2" LPO, w/Baseplate



9" x 7" HPPE Seal

11" x 7" C-22
Casing Hanger

10-3/4" X 9-5/8"
OE Seal

13-5/8" x 9-5/8" C-22
Casing Hanger



SY NERGY
WELLHEAD & FRAC

email: sales@syenergypg.com

Wellhead Multibowl




Crazy Horse 1H, 2H, 3H, 4H
Multi-Bowl System
13-3/8" X 9-5/8" X 7"
Quote# MB170821-010

Tubing Head

11"-5M x 7"-10M w/SSO
(2) 1-13/16"-10M HWO Gate Valve
(2) 1-13/16"-10M x 2" 1502

7-1/16"-5M



13-5/8"-5M

7" Obl P Seal

Casing Spool- MBS

13-5/8"-5M X 13-5/8"-5M
w/(2) 2-1/16"-5M SSO
(2) 2-1/16"-5M HWO Gate Valve

13-5/8" X 7" C-22
Casing Hanger




13-5/8"-5M

13-5/8" X 9-5/8" MBS
Packoff Assembly

Casing Head- MBS

13-5/8"-5M X 13-3/8" SOW

13-5/8" X 9-5/8" Mandrel
Casing Hanger, Fluted



13-3/8" SOW



SY ENERGY
WELLHEAD & FRAC

email sales@syenergypg.com

Production Tree



Crazy Horse 1H, 2H, 3H, 4H

Production Tree

2-9/16"-5M

Quote# WH170816-01D

Upper Tree Assembly 2-9/16" (FE)

ASP-EN 7-1/16"-10M X 2-9/16"-5M, DD

TC1A-EN HGR 7-1/16"-10M X 2-7/8"

8Rd EUE Top, w/ 2-7/8" 8Rd EUE Btm, DD


Gate Valve, 2-9/16"-5M, DD Run

Tee, 2-9/16"-5M x 2-1/16"-5M, DD

Gate Valve, 2-1/16"-5M, DD Wing

Adjustable Choke 2-1/16"-5M FE X FE, DD,

WEECO 2-1/16"-5M x 2" 1502, DD



TC1A-EN Hanger

7-1/16"-10M X 2-7/8" EUE Top

w/ 2-7/8" 8Rd EUE Bottom, DD



SY ENERGY

WELLHEAD & FRAC

email sales@syenergypg.com

5.5 20# P110 BK Connection Data



Precision Connections BK-HT

5.5 in. 20 lb/ft P-110 with 6.3 in. Coupling OD

Pipe Body

Nominal OD	5.500	inches
Nominal Weight	20.00	lb/ft
Wall Thickness	0.361	inches
Plain End Weight	19.81	lb/ft
Drift	4.653	inches
Nominal ID	4.778	inches
Grade	P-110	
Min Yield	110,000	lb/in ²
Min Tensile	125,000	lb/in ²
Critical Section Area	5.828	in ²
Pipe Body Yield Strength	641	kips
Min Internal Yield Pressure	12,640	psi
Collapse Pressure	11,100	psi

Connection

Coupling OD	6.300	inches
Coupling Length	8.250	inches
Make Up Loss	4.125	inches
Critical Section Area	8.456	in ²
Internal Pressure Rating	100%	
External Pressure Rating	100%	
Tension Efficiency	100%	
Connection Strength	641	kips
Compression Efficiency	100%	
Uniaxial Bend Rating	80.0	° / 100 ft
Min Make Up Torque	8,300	ft-lbs
Yield Torque	32,000	ft-lbs

This documentation contains confidential and proprietary information not to be reproduced or divulged in whole or in part to anyone outside of your company without prior written authorization from Precision Connections, LLC, and such documentation and information is provided to you upon such conditions of confidentiality.

v1.1

10/10/2016




Torque Data Sheet - Precision Connections BK-HT

5.5 in. 20 lb/ft P-110 with 6.3 in. Coupling OD

Min Make Up Torque	8,300	ft-lbs
Max Make Up Torque	24,000	ft-lbs
Optimum Torque	11,500	ft-lbs
Max Operating Torque	27,200	ft-lbs
Yield Torque	32,000	ft-lbs

Representative Torque Turn Graph




v1.1

10/10/2016

Precision Connections BK

Semi Premium Connection


Designed Primarily for High Torque Frac Strings



Better Buttress Sealing Modified buttress thread for tighter thread sealing and pin nose seal stabilization.

• **API Thread Tolerance** – Verified fit of several major insert manufacturers.

• **BK Thread Tolerance** – Minimizes thread gap for better thread sealing. *Uses a Custom Premium Insert.*



Advanced Relief Groove ensures more threads are engaged for maximum sealing. The thicker midpoint cross sectional area provides additional coupling strength.

BK Relief Groove



Dark areas indicate unengaged thread regions

First Generation Relief Groove



Strength Pin-Nose to Pin-Nose contact for high torque resistance, higher pressure ratings, higher bending loads and higher structural compressive loading. Smooth Premium Bore with no I-Area to get hung up on.



BK

Buttress

Pressure



High RPM Fatigue Resistance from Low Stress Runout Threads The BK uses the field proven buttress thread with low stress runout threads to extend the time it can be rotated through a dogleg at high RPM.





U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

SUPO Data Report

10/05/2018

APD ID: 10400027002

Submission Date: 02/07/2018

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Well Type: OIL WELL

Well Work Type: Drill



[Show Final Text](#)

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

CH_1H_Road_Map_20180207110650.pdf

Existing Road Purpose: ACCESS

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

CH_1H_New_Road_Map_20180207110714.pdf

New road type: RESOURCE

Length: 4193.3 Feet

Width (ft.): 30

Max slope (%): 0

Max grade (%): 1

Army Corp of Engineers (ACOE) permit required? NO

ACOE Permit Number(s):

New road travel width: 14

New road access erosion control: Crown and ditch

New road access plan or profile prepared? NO

New road access plan attachment:

Access road engineering design? NO

Access road engineering design attachment:

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Access surfacing type: OTHER

Access topsoil source: ONSITE

Access surfacing type description: Caliche

Access onsite topsoil source depth: 6

Offsite topsoil source description:

Onsite topsoil removal process: Grader

Access other construction information: Upgrades on the existing road will be needed on the following segments (listed from southwest to northeast): Build up roadbed for ¼ mile in N2SW4 Sec. 15 Install 3 vehicle turnouts from NENE Sec. 15 to NESW Sec. 11 Widen, crown, and ditch 2,000' pipeline road in N2SW4 Sec. 11

Access miscellaneous information:

Number of access turnouts: 3

Access turnout map:

Drainage Control

New road drainage crossing: OTHER

Drainage Control comments: Crown and ditch

Road Drainage Control Structures (DCS) description: None

Road Drainage Control Structures (DCS) attachment:

Access Additional Attachments

Additional Attachment(s):

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

CH_1H_Well_Map_20180207111110.pdf

Existing Wells description:

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

Production Facilities description: A 400' x 400' tank battery will be built 500' southwest of and off the pad. Buried flowlines and fuel gas lines will parallel the 687.5' road between the two facilities. Topsoil will be stockpiled north of the battery. Power line plans have not been decided.

Production Facilities map:

CH_1H_Production_Facilities_09192018_20180919104454.pdf

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Section 5 - Location and Types of Water Supply

Water Source Table

Water source use type: DUST CONTROL,
INTERMEDIATE/PRODUCTION CASING, STIMULATION, SURFACE
CASING

Water source type: GW WELL

Describe type:

Source longitude:

Source latitude:

Source datum:

Water source permit type: WATER WELL

Source land ownership: PRIVATE

Water source transport method: TRUCKING

Source transportation land ownership: FEDERAL

Water source volume (barrels): 20000

Source volume (acre-feet): 2.577862

Source volume (gal): 840000

Water source and transportation map:

CH_1H_Water_Source_Map_20180207111556.pdf

Water source comments:

New water well? NO

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method:

Drill material:

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

State appropriation permit:

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Additional information attachment:

Section 6 - Construction Materials

Construction Materials description: NM One Call (811) will be notified before construction starts. Top 6" of soil and brush will be stockpiled west of the pad. Pipe racks will be to the northeast. A closed loop drilling system will be used. Caliche will be hauled from existing Constructors, Inc. pit on private land in NWNE 34-21s-27e.

Construction Materials source location attachment:

CH_1H_Construction_Methods_20180207111644.pdf

Section 7 - Methods for Handling Waste

Waste type: DRILLING

Waste content description: Cuttings, mud, salts, and other chemicals

Amount of waste: 2000 barrels

Waste disposal frequency : Daily

Safe containment description: Steel tanks

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** PRIVATE

Disposal type description:

Disposal location description: R360's state approved (NM1-6-0) disposal site at Halfway. NM

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit?

Reserve pit length (ft.) **Reserve pit width (ft.)**

Reserve pit depth (ft.) **Reserve pit volume (cu. yd.)**

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? YES

Description of cuttings location Steel tanks on pad

Cuttings area length (ft.)

Cuttings area width (ft.)

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Cuttings area depth (ft.)

Cuttings area volume (cu. yd.)

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: NO

Ancillary Facilities attachment:

Comments:

Section 9 - Well Site Layout

Well Site Layout Diagram:

CH_1H_Well_Site_Layout_20180207111809.pdf

Comments:

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: CRAZY HORSE

Multiple Well Pad Number: 1H

Recontouring attachment:

CH_1H_Recontour_Plat_20180207111830.pdf

CH_1H_Interim_Reclamation_Diagram_20180207111838.pdf

Drainage/Erosion control construction: Crown and ditch

Drainage/Erosion control reclamation: Harrowed on the contour

Well pad proposed disturbance (acres): 5.17
Road proposed disturbance (acres): 2.89
Powerline proposed disturbance (acres): 0
Pipeline proposed disturbance (acres): 0.47
Other proposed disturbance (acres): 3.67
Total proposed disturbance: 12.2

Well pad interim reclamation (acres): 0.57
Road interim reclamation (acres): 0
Powerline interim reclamation (acres): 0
Pipeline interim reclamation (acres): 0.47
Other interim reclamation (acres): 0
Total interim reclamation: 1.04

Well pad long term disturbance (acres): 4.6
Road long term disturbance (acres): 2.89
Powerline long term disturbance (acres): 0
Pipeline long term disturbance (acres): 0
Other long term disturbance (acres): 3.67
Total long term disturbance: 11.16

Disturbance Comments:

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Reconstruction method: Interim reclamation will shrink the well pad 11% by removing caliche and reclaiming the north 50', leaving 4.60 acres for 2 CL & F wells, truck turn arounds, and through truck traffic to the battery. Disturbed areas will be contoured to match pre-construction grades. Soil and brush will be evenly spread over disturbed areas. Disturbed areas will be seeded in accordance with BLM and State Land Office requirements

Topsoil redistribution: Enough stockpiled topsoil will be retained to cover the remainder of the pad and battery when the wells are plugged. Once the last well is plugged, then the remainder of the pad, battery, and new road will be similarly reclaimed. Noxious weeds will be controlled.

Soil treatment: None

Existing Vegetation at the well pad:

Existing Vegetation at the well pad attachment:

Existing Vegetation Community at the road:

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline:

Existing Vegetation Community at the pipeline attachment:

Existing Vegetation Community at other disturbances:

Existing Vegetation Community at other disturbances attachment:

Non native seed used? NO

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? NO

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? NO

Seed harvest description:

Seed harvest description attachment:

Seed Management

Seed Table

Seed type:

Seed source:

Seed name:

Source name:

Source address:

Source phone:

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Seed cultivar:

Seed use location:

PLS pounds per acre:

Proposed seeding season:

Seed Summary	
Seed Type	Pounds/Acre

Total pounds/Acre:

Seed reclamation attachment:

Operator Contact/Responsible Official Contact Info

First Name:

Last Name:

Phone:

Email:

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? NO

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: To BLM/State Land Office standards

Weed treatment plan attachment:

Monitoring plan description: To BLM/State Land Office standards

Monitoring plan attachment:

Success standards: To BLM/State Land Office satisfaction

Pit closure description: No pit

Pit closure attachment:

Section 11 - Surface Ownership

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT, STATE GOVERNMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

DOD Local Office:

NPS Local Office:

State Local Office: SANTA FE

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Disturbance type: EXISTING ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: PIPELINE

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: CL&F OPERATING LLC

Well Name: CRAZY HORSE 0304 FED COM

Well Number: 1H

Section 12 - Other Information

Right of Way needed? NO

Use APD as ROW?

ROW Type(s):

ROW Applications


SUPO Additional Information: Most (9.11 acres) construction will be on BLM. Remaining (3.087 acres) construction will be on NM State Land Office land for which CL & F is obtaining a Well Site Business Lease. NM State Land Office address is PO Box 1148, Santa Fe NM 87504. Their phone number is (505) 827-5728.

Use a previously conducted onsite? YES



Previous Onsite information: On-site inspection was held with Jim Rutley, Bobby Ballard, Jim Goodbar, Chelsie Dugan, and June Hernandez (all BLM) on September 26, 2017.

Other SUPO Attachment

CH_1H_General_SUPO_09192018_20180919104631.pdf




104 08667° W 104 05000° W 104 03333° W 104 01667° W 104.00000° W 103.98333° W 103.96667° W 103.95000° W 103.93333° W WGS84 103.90000° W



TN + MN
7°
01/07/



WGS84 103 95000' W



TN 4,MIN


02/03/18

SECTION 16, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY, NEW MEXICO.

MAP 4

OWNER: STATE OF NEW MEXICO

1. SEE DOCUMENTS FILED FOR RECORD IN THIS OFFICE WHICH DESCRIBE IN DETAIL THE RECONSTRUCTION OF THIS SECTION.
2. COORDINATES AND BEARINGS ARE BASED ON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM NAD 83 AND DISTANCES ARE OF SURFACE VALUE.



LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 16, TOWNSHIP 20 SOUTH, RANGE 30 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY.

BEGINNING AT A POINT ON THE EAST SECTION LINE WHICH LIES S.00°05'30\"E., 1059.2 FEET FROM THE EAST QUARTER CORNER OF SAID SECTION 16; THENCE S.79°56'28\"W., 646.9 FEET; THENCE S.76°08'43\"W., 2136.1 FEET; THENCE N.79°20'47\"W., 313.4 FEET TO THE END OF THIS LINE WHICH LIES N.23°35'13\"W., 1075.3 FEET FROM THE SOUTH QUARTER CORNER OF SAID SECTION 16. SAID STRIP OF LAND BEING 3096.4 FEET OR 187.66 RODS IN LENGTH AND CONTAINING 2.13 ACRES, MORE OR LESS, AND BEING ALLOCATED BY FORTIES AS FOLLOWS.

NE/4SE/4 73.76 RODS OR 0.84 ACRES
SE/4SE/4 6.53 RODS OR 0.07 ACRES

SW/4SE/4 82.62 RODS OR 0.94 ACRES
SE/4NW/4 24.75 RODS OR 0.28 ACRES

I HEREBY CERTIFY THAT THIS MAP WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THE STATE.

GARY L. JONES

No. 7977
No. 5074

basin
surveys

focused on excellence
in the oilfield

P.O. Box 1786

1120 N. West County Rd.
Hobbs, New Mexico 88241

(575) 393-7316 - Office

(575) 392-2206 - Fax
basinsurveys.com

1000 0 1000 2000 FEET

CL&F OPERATING LLC

REF: CRAZY HORSE LEASE ROAD

A LEASE ROAD CROSSING STATE LAND IN
SECTION 16, TOWNSHIP 20 SOUTH, RANGE 30 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO.

W.O. Number: 33328

Drawn By: K. GOAD


Date: 01-11-2018

Survey Date: 01-11-2018

Sheet 4 of 4 Sheets

SECTION 15, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY, NEW MEXICO.

MAP 5



OWNER: U.S.A.


1. SEE DOCUMENTS FILED FOR RECORD IN THIS OFFICE WHICH DESCRIBE IN DETAIL THE RECONSTRUCTION OF THIS SECTION.
2. COORDINATES AND BEARINGS ARE BASED ON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM NAD 83 AND DISTANCES ARE OF SURFACE VALUE.

LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 15, TOWNSHIP 20 SOUTH, RANGE 30 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

SEC. 15 7268.8 FEET = 1.38 MILES = 440.53 RODS = 5.01 ACRES

I HEREBY CERTIFY THAT THIS MAP WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.



GARY L. JONES, P.S. No. 7977
No. 5074

basin surveys
focused on excellence
in the oilfield

P.O. Box 1786 (575) 393-7316 - Office
1120 N. West County Rd. (575) 392-2206 - Fax
Hobbs, New Mexico 88241 basinsurveys.com

1000 0 1000 2000 FEET


CL&F OPERATING LLC

REF: CRAZY HORSE LEASE ROAD

A LEASE ROAD CROSSING USA LAND IN
SECTION 15, TOWNSHIP 20 SOUTH, RANGE 30 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO.

**SECTION 14, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY, NEW MEXICO.**

MAP 6




LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 14, TOWNSHIP 20 SOUTH, RANGE 30 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

SEC. 14 463.5 FEET = 0.09 MILES = 28.09 RODS = 0.32 ACRES

I HEREBY CERTIFY THAT THIS MAP WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.



GARY L. JONES, P.S. No. 7977
No. 5074

basin surveys
focused on excellence
in the oilfield

P.O. Box 1786 (575) 393-7316 - Office
1120 N. West County Rd. (575) 392-2206 - Fax
Hobbs, New Mexico 88241 basin-surveys.com

1000 0 1000 2000 FEET


CL&F OPERATING LLC

REF: CRAZY HORSE LEASE ROAD

A LEASE ROAD CROSSING USA LAND IN
SECTION 14, TOWNSHIP 20 SOUTH, RANGE 30 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO.

SECTION 11, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY, NEW MEXICO.

MAP 7



OWNER: U.S.A.


1. SEE DOCUMENTS FILED FOR RECORD IN THIS OFFICE WHICH DESCRIBE IN DETAIL THE RECONSTRUCTION OF THIS SECTION.
2. COORDINATES AND BEARINGS ARE BASED ON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM NAD 83 AND DISTANCES ARE OF SURFACE VALUE.

LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 11, TOWNSHIP 20 SOUTH, RANGE 30 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

SEC. 11 7984.1 FEET = 1.51 MILES = 483.88 RODS = 5.50 ACRES

I HEREBY CERTIFY THAT THIS MAP WAS PREPARED FROM FIELD NOTES OF AN ACTIVE SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.



GARY L. JONES, P.S. No. 7977
No. 5074

basin surveys
focused on excellence
in the oilfield

P.O. Box 1786 (575) 393-7316 - Office
1120 N. West County Rd. (575) 392-2206 - Fax
Hobbs, New Mexico 88241 basin-surveys.com

1000 0 1000 2000 FEET


CL&F OPERATING LLC

REF: CRAZY HORSE LEASE ROAD


A LEASE ROAD CROSSING USA LAND IN
SECTION 11, TOWNSHIP 20 SOUTH, RANGE 30 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO.

SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY, NEW MEXICO.

MAP 8



CARLSBAD, NM IS ±25 MILES TO THE SOUTHWEST OF LOCATION.



CL&F OPERATING LLC

REF: CRAZY HORSE 0304 FED COM #1H / WELL PAD TOPO

THE CRAZY HORSE 0304 FED COM #1H LOCATED 110' FROM
THE SOUTH LINE AND 436' FROM THE WEST LINE OF
SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST.

N.M.P.M., EDDY COUNTY, NEW MEXICO.

basin
surveys

focused on excellence
in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com


W.O. Number: 33327

Drawn By: K. GOAD

Date: 10-04-2017

Survey Date: 09-27-2017

Sheet 1 of 1 Sheets



103.96667° W




7°

02/03/18

SECTION 11, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY,
NEW MEXICO.

MAP 7



OWNER: U.S.A.


1. SEE DOCUMENTS FILED FOR RECORD IN THIS OFFICE WHICH DESCRIBE IN DETAIL THE RECONSTRUCTION OF THIS SECTION.
2. COORDINATES AND BEARINGS ARE BASED ON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM NAD 83 AND DISTANCES ARE OF SURFACE VALUE.

LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 11, TOWNSHIP 20 SOUTH, RANGE 30 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

SEC. 11 7984.1 FEET = 1.51 MILES = 483.88 RODS = 5.50 ACRES

I HEREBY CERTIFY THAT THIS MAP WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.



GARY L. JONES, P.L.S.

No. 7977

No. 5074

basin surveys

focused on excellence
in the oilfield

P.O. Box 1786

1120 N. West County Rd.
Hobbs, New Mexico 88241

(575) 393-7316 - Office

(575) 392-2206 - Fax
basinsurveys.com

1000 0 1000 2000 FEET

CL&F OPERATING LLC

REF: CRAZY HORSE LEASE ROAD

A LEASE ROAD CROSSING USA LAND IN
SECTION 11, TOWNSHIP 20 SOUTH, RANGE 30 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO.

W.O. Number: 33328

Drawn By: K. GOAD


Date: 01-11-2018

Survey Date: 01-11-2018

Sheet 1 of 4 Sheets


SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY, NEW MEXICO.

MAP 8



Proposed CRAZY HORSE 0304 FED COM #1H Battery
CL&F OPERATING LLC
CRAZY HORSE 0304 FED COM #1H
ELEV. - 3218'
Lat - N 32.595335'
Long - W 103.949971'
NMSPE - N 580526.3
E 659401.5
(NAD-83)

CARLSBAD, NM IS ±25 MILES TO THE SOUTHWEST OF LOCATION.



CL&F OPERATING LLC

REF: CRAZY HORSE 0304 FED COM #1H / WELL PAD TOPO


THE CRAZY HORSE 0304 FED COM #1H LOCATED 110' FROM
THE SOUTH LINE AND 436' FROM THE WEST LINE OF
SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST.

N.M.P.M., EDDY COUNTY, NEW MEXICO.

basin
surveys
focused on excellence
in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com


W.O. Number: 33327 | Drawn By: K. GOAD | Date: 10-04-2017 | Survey Date: 09-27-2017 | Sheet 1 of 1 Sheets





SECTION 11, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY,
NEW MEXICO.

MAP 7



OWNER: U.S.A.


1. SEE DOCUMENTS FILED FOR RECORD IN THIS OFFICE WHICH DESCRIBE IN DETAIL THE RECONSTRUCTION OF THIS SECTION.
2. COORDINATES AND BEARINGS ARE BASED ON THE NEW MEXICO STATE PLANE COORDINATE SYSTEM NAD 83 AND DISTANCES ARE OF SURFACE VALUE.

LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 11, TOWNSHIP 20 SOUTH, RANGE 30 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

SEC. 11 7984.1 FEET = 1.51 MILES = 483.88 RODS = 5.50 ACRES

I HEREBY CERTIFY THAT THIS MAP WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE



GARY L. JONES, P.S. No. 7977
No. 5074

basin surveys

P.O. Box 1786 (575) 393-7316 - Office
1120 N. West County Rd. (575) 392-2206 - Fax
Hobbs, New Mexico 88241 basin-surveys.com

1000 0 1000 2000 FEET


CL&F OPERATING LLC

REF: CRAZY HORSE LEASE ROAD


A LEASE ROAD CROSSING USA LAND IN
SECTION 11, TOWNSHIP 20 SOUTH, RANGE 30 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO.

SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY, NEW MEXICO.

MAP 8



CARLSBAD, NM IS ±25 MILES TO THE SOUTHWEST OF LOCATION.



CL&F OPERATING LLC

REF: CRAZY HORSE 0304 FED COM #1H / WELL PAD TOPO

THE CRAZY HORSE 0304 FED COM #1H LOCATED 110' FROM
THE SOUTH LINE AND 436' FROM THE WEST LINE OF
SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST.

N.M.P.M., EDDY COUNTY, NEW MEXICO.

basin
surveys
focused on excellence
in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241

(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com


W.O. Number: 33327


Drawn By: K. GOAD

Date: 10-04-2017

Survey Date: 09-27-2017


Sheet 1 of 1 Sheets





SECTION 10, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY, NEW MEXICO.

MAP 11




LEGAL DESCRIPTION

A TRACT OF LAND LOCATED IN SECTION 10, TOWNSHIP 20 SOUTH, RANGE 30 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS.

BEGINNING AT A POINT WHICH LIES S.00°06'17\"E., 651.9 FEET AND S.89°52'36\"W., 41.1 FEET FROM THE NORTHEAST CORNER OF SAID SECTION 10; THENCE S.06°03'05\"W., 400.0 FEET; THENCE N.83°57'45\"W., 400.0 FEET; THENCE N.06°02'20\"E., 400.0 FEET; THENCE S.83°57'15\"E., 400.0 FEET TO THE POINT OF BEGINNING. SAID TRACT OF LAND CONTAINING 3.673 ACRES, MORE OR LESS.

I HEREBY CERTIFY THAT THIS MAP WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.



GARY L. JONES

No. 7977

No. 5074

basin surveys
focused on excellence
in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com


1000 0 1000 2000 FEET



CL&F OPERATING LLC

REF: PROPOSED CRAZY HORSE 0304 FED COM 1H&2H TANK BATTERY


A TRACT OF LAND LOCATED IN
SECTION 10, TOWNSHIP 20 SOUTH, RANGE 30 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO.



SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY, NEW MEXICO.

MAP 14

30' wide
topsoil pile



100 0 100 200 FEET
SCALE: 1" = 100'

CL&F OPERATING LLC

REF: CRAZY HORSE 0304 FED COM #1H / WELL PAD TOPO

THE CRAZY HORSE 0304 FED COM #1H LOCATED 110' FROM
THE SOUTH LINE AND 436' FROM THE WEST LINE OF
SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST.

N.M.P.M., EDDY COUNTY, NEW MEXICO.

**basin
surveys**

focused on excellence
in the oilfield

P.O. Box 1786

1120 N. West County Rd.
Hobbs, New Mexico 88241

(575) 393-7316 - Office

(575) 392-2206 - Fax
basinsurveys.com

W.O. Number: 33327



Drawn By: K. GOAD

Date: 10-04-2017

Survey Date: 09-27-2017

Sheet 1 of 1 Sheets

TOPO! map printed on 02/03/18 from "Untitled.tpo"




TN 6 MW
7°
02/03/18

Crazy Horse 0304 Fed Com 1H
rig diagram

NORTH


1" = 100'



SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY,


NEW MEXICO.

MAP 17




SECTION 10, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY, NEW MEXICO.

MAP 18



I HEREBY CERTIFY THAT THIS MAP WAS PREPARED
FROM FIELD NOTES OF AN ACTUAL SURVEY AND
MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND
SURVEYS AS SPECIFIED BY THIS STATE.



GARY L. JONES, P.S. No. 7977
No. 5074

basin
surveys
used on excellence
in the oilfield

P.O. Box 1786 (575) 393-7316 - Office
1120 N. West County Rd. (575) 392-2206 - Fax
Hobbs, New Mexico 88241 basinsurveys.com

100 0 100 200 FEET

CL&F OPERATING LLC

REF: PROPOSED CRAZY HORSE 0304 FED COM 1H&2H TANK BATTERY


A TRACT OF LAND LOCATED IN
SECTION 10, TOWNSHIP 20 SOUTH, RANGE 30 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO.

SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST. N.M.P.M.,
EDDY COUNTY, NEW MEXICO.

MAP 16

50' x 500' = 0.57 acre
interim reclamation

30' wide
topsoil pile



CL&F OPERATING LLC

REF: CRAZY HORSE 0304 FED COM #1H / WELL PAD TOPO

THE CRAZY HORSE 0304 FED COM #1H LOCATED 110' FROM
THE SOUTH LINE AND 436' FROM THE WEST LINE OF
SECTION 2, TOWNSHIP 20 SOUTH, RANGE 30 EAST.
N.M.P.M., EDDY COUNTY, NEW MEXICO.

basin
surveys

focused on excellence
in the oilfield
P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

W.O. Number: 33327

Drawn By: K. GOAD

Date: 10-04-2017

Survey Date: 09-27-2017

Sheet 1 of 1 Sheets

CL & F Operating LLC
Crazy Horse 0304 Fed Com 1H
SHL 110' FSL & 436' FWL Sec. 2
T. 20 S., R. 30 E., Eddy County, NM

SURFACE PLAN PAGE 1

Surface Use Plan

1. ROAD DIRECTIONS & DESCRIPTIONS (See MAPS 1 - 9)

From the junction of US 285 and US 62/180 in Carlsbad...
Go NE 15.6 miles on paved US 62/180 to the equivalent of Mile Post 50.7
Then turn left and go North 3.5 miles on paved NM 360
Then turn right and go NE 1.1 miles on a caliche road to a P&A well
Then turn left and go NNW 350' on a dirt road
Then turn right and go NE 1.4 miles on a curving then straight dirt road
Then turn left and go NW 1/3 mile on a dirt pipeline patrol road to valves
Then go NW 488.5' cross-country to the far side of a power line
Then turn right and go NE 2294.9 cross-country parallel to the power line
Then turn left and go NW 722.4' cross-country to the proposed well pad

From the well pad, go SSE 290.6' cross-country
Then turn right and go SW 396.9' cross-country to the central tank battery

Non-paved roads will be maintained as needed to Gold Book standards. This includes pulling ditches, preserving the crown, and cleaning culverts. This will be done at least once a year, and more often as needed. Caliche will be hauled from Constructors, Inc. existing pit on private land in NWNE 34-21s-27e.

2. ROAD TO BE BUILT OR UPGRADED (See MAPS 3 & 7-9)

4,193.3' of new resource road will be built. The new road will be crowned and ditched, have a 14' wide driving surface, and be surfaced with caliche. Maximum disturbed width = 30'. Maximum grade = 1%. Maximum cut or fill = 1'. No culvert, cattle guard, or vehicle turn out is needed.

CL & F Operating LLC
Crazy Horse 0304 Fed Com 1H
SHL 110' FSL & 436' FWL Sec. 2
T. 20 S., R. 30 E., Eddy County, NM

SURFACE PLAN PAGE 2

Upgrades on the existing road will be needed on the following segments (listed from southwest to northeast):

Build up roadbed for ¼ mile in N2SW4 Sec. 15
Install 3 vehicle turnouts from NENE Sec. 15 to NESW Sec. 11
Widen, crown, and ditch ≈2,000' pipeline road in N2SW4 Sec. 11

3. EXISTING WELLS (See MAP 10)

Existing oil, gas, water, and P & A wells are within a mile. No disposal or injection well is within a mile.

4. PROPOSED PRODUCTION FACILITIES (See MAPS 11 & 12)

A 400' x 400' tank battery will be built ≈500' southwest of and off the pad. Buried flowlines and fuel gas lines will parallel the 687.5' road between the two facilities. Topsoil will be stockpiled north of the battery. Power line plans have not been decided.

5. WATER SUPPLY (See MAP 13)

Water will be trucked from an existing water station on private land in SWNW 34-17s-28e.

6. CONSTRUCTION MATERIALS & METHODS (see MAPS 14 & 15)

NM One Call (811) will be notified before construction starts. Top ≈6" of soil and brush will be stockpiled west of the pad. Pipe racks will be to the northeast. A closed loop drilling system will be used. Caliche will be hauled from existing Constructors, Inc. pit on private land in NWNE 34-21s-27e.

CL & F Operating LLC
Crazy Horse 0304 Fed Com 1H
SHL 110' FSL & 436' FWL Sec. 2
T. 20 S., R. 30 E., Eddy County, NM

SURFACE PLAN PAGE 3

7. WASTE DISPOSAL

All trash will be placed in a portable trash cage. It will be hauled to the Eddy County landfill. There will be no trash burning. Contents (drill cuttings, mud, salts, and other chemicals) of the mud tanks will be hauled to R360's state approved (NM1-6-0) disposal site at Halfway. Human waste will be disposed of in chemical toilets and hauled to the Carlsbad wastewater treatment plant.

8. ANCILLARY FACILITIES

There will be no airstrip or camp. Camper trailers will be on location for the company man, tool pusher, or mud logger.

9. WELL SITE LAYOUT

See Rig Diagram for depictions of the well pad, trash cage, access onto the location, parking, living facilities, and rig orientation.

10. RECLAMATION (See MAPS 16 - 18)

Interim reclamation will shrink the well pad $\approx 11\%$ by removing caliche and reclaiming the north 50', leaving 4.60 acres for 2 CL & F wells, truck turn arounds, and through truck traffic to the battery. Disturbed areas will be contoured to match pre-construction grades. Soil and brush will be evenly spread over disturbed areas. Disturbed areas will be seeded in accordance with BLM and State Land Office requirements. Enough stockpiled topsoil will be retained to cover the remainder of the pad and battery when the wells are plugged. Once the last well is plugged, then the remainder of the pad, battery, and new road will be similarly reclaimed. Noxious weeds will be controlled.

CL & F Operating LLC
Crazy Horse 0304 Fed Com 1H
SHL 110' FSL & 436' FWL Sec. 2
T. 20 S., R. 30 E., Eddy County, NM

SURFACE PLAN PAGE 4

Land use will be:

450' x 500' pad = 5.17 acres
30' x 4193.3' road = 2.89 acres
30' x 687.5' pipelines = 0.47 acre
+ 400' x 400' battery = 3.67 acres
short term = 12.20 acres

short term = 12.20 acres
- 30' x 687.5' pipelines = 0.47 acre
- 50' x 500' interim reclamation on well pad = 0.57 acre
11.16 acres long term (2.89 ac. road + 4.60 ac. pad + 3.67 ac. battery)

11. SURFACE OWNER

Most (9.11 acres) construction will be on BLM. Remaining (3.087 acres) construction will be on NM State Land Office land for which CL & F is obtaining a Well Site Business Lease. NM State Land Office address is PO Box 1148, Santa Fe NM 87504. Their phone number is (505) 827-5728.

12. OTHER INFORMATION


On-site inspection was held with Jim Rutley, Bobby Ballard, Jim Goodbar, Chelsie Dugan, and June Hernandez (all BLM) on September 26, 2017.

CL & F Operating LLC
Crazy Horse 0304 Fed Com 1H
SHL 110' FSL & 436' FWL Sec. 2
T. 20 S., R. 30 E., Eddy County, NM

SURFACE PLAN PAGE 5

CERTIFICATION

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U. S. C. 1001 for the filing of false statements. Executed this 3rd day of February, 2018.



Brian Wood, Consultant
Permits West, Inc.

37 Verano Loop, Santa Fe, NM 87508

(505) 466-8120

FAX: (505) 466-9682

Cellular: (505) 699-2276

Field representative will be:

Allison Johnson

CL & F Operating LLC

16945 Northchase Dr., Suite 500

Houston TX 77060

Phone: (281) 873-3013

FAX: (281) 872-4398



Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Injection well name:

Assigned injection well API number?

Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment:

Bond Information

Federal/Indian APD: FED

BLM Bond number: NMB001314

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment: