

RECEIVED

JAN 30 2019

FORM APPROVED  
OMB No. 1004-0137  
Expires: January 31, 2018

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
DISTRICT II-ARTESIA O.C.D.  
**APPLICATION FOR PERMIT TO DRILL OR REENTER**

|   |   |   |
|---|---|---|
| 1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER  |   | 5. Lease Serial No.<br>NMNM0504364B   |
| 1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other   |   | 6. If Indian, Allottee or Tribe Name  |
| 1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone  |   | 7. If Unit or CA Agreement, Name and No.                                    |
| 2. Name of Operator<br>PERCUSSION PETROLEUM OPERATING LLC   |   | 8. Lease Name and Well No.<br>LAKEWOOD FEDERAL COM<br>8H<br>324926          |
| 3a. Address<br>919 Milam Street, Suite 2475 Houston TX 77002  | 3b. Phone No. (include area code)<br>(713)589-2337  | 9. API Well No.<br>30-015-45676   |
| 4. Location of Well (Report location clearly and in accordance with any State requirements. *)<br>At surface SWSE / 572 FSL / 2336 FEL / LAT 32.625744 / LONG -104.471392<br>At proposed prod. zone SWSE / 20 FSL / 2566 FEL / LAT 32.609762 / LONG -104.472393 |   | 10. Field and Pool, or Exploratory<br>N. SEVEN RIVERS; GLORIETA -YESO 97565 |
| 11. Sec., T. R. M. or Blk. and Survey or Area<br>SEC 27 / T19S / R25E / NMP   |   |   |
| 14. Distance in miles and direction from nearest town or post office*<br>15 miles   |   | 12. County or Parish<br>EDDY  |
| 13. State<br>NM   |   |   |
| 15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)<br>304 feet   | 16. No of acres in lease<br>480                     | 17. Spacing Unit dedicated to this well<br>160                              |
| 18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 20 feet  | 19. Proposed Depth<br>2641 feet / 8177 feet         | 20. BLM/BIA Bond No. in file<br>FED: NMB001424                              |
| 21. Elevations (Show whether DF, KDB, RT, GL, etc.)<br>3483 feet  | 22. Approximate date work will start*<br>11/01/2018 | 23. Estimated duration<br>90 days   |
| 24. Attachments   |   |   |

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification.  |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM.            |

|  |  |                    |
|--|--|--------------------|
| 25. Signature<br>(Electronic Submission)           | Name (Printed/Typed)<br>Brian Wood / Ph: (505)466-8120 | Date<br>08/20/2018 |
| Title<br>President                                 |  |                    |
| Approved by (Signature)<br>(Electronic Submission) | Name (Printed/Typed)<br>Ty Allen / Ph: (575)234-5978   | Date<br>12/20/2018 |
| Title<br>Wildlife Biologist<br>CARLSBAD            |  |                    |

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**APPROVED WITH CONDITIONS**  
Approval Date: 12/20/2018

RWP 2-1-12

## INSTRUCTIONS

**GENERAL:** This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

**ITEM I:** If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

**ITEM 4:** Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

**ITEM 14:** Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

**ITEMS 15 AND 18:** If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

**ITEM 22:** Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

**ITEM 24:** If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

## NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

**AUTHORITY:** 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

**PRINCIPAL PURPOSES:** The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

**ROUTINE USE:** Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

**EFFECT OF NOT PROVIDING INFORMATION:** Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to allow evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

**BURDEN HOURS STATEMENT:** Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 L.S., Washington, D.C. 20240.

## **Additional Operator Remarks**

### **Location of Well**

1. SHL: SWSE / 572 FSL / 2336 FEL / TWSP: 19S / RANGE: 25E / SECTION: 27 / LAT: 32.625744 / LONG: -104.471392 ( TVD: 0 feet, MD: 0 feet )  
PPP: SWSE / 1320 FSL / 2585 FEL / TWSP: 19S / RANGE: 25E / SECTION: 34 / LAT: 32.613296 / LONG: -104.472359 ( TVD: 2631 feet, MD: 6891 feet )  
PPP: NWSE / 2640 FSL / 2619 FEL / TWSP: 19S / RANGE: 25E / SECTION: 34 / LAT: 32.616994 / LONG: -104.473323 ( TVD: 2621 feet, MD: 5577 feet )  
PPP: SWSE / 572 FSL / 2336 FEL / TWSP: 19S / RANGE: 25E / SECTION: 27 / LAT: 32.625744 / LONG: -104.471392 ( TVD: 0 feet, MD: 0 feet )  
BHL: SWSE / 20 FSL / 2566 FEL / TWSP: 19S / RANGE: 25E / SECTION: 34 / LAT: 32.609762 / LONG: -104.472393 ( TVD: 2641 feet, MD: 8177 feet )

### **BLM Point of Contact**

Name: Katrina Ponder

Title: Geologist

Phone: 5752345969

Email: kponder@blm.gov

---

**Approval Date: 12/20/2018**

(Form 3160-3, page 3)

### **Review and Appeal Rights**

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

## PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

|                       |                                    |
|-----------------------|------------------------------------|
| OPERATOR'S NAME:      | Percussion Petroleum Operating LLC |
| LEASE NO.:            | NMNM0504364B                       |
| WELL NAME & NO.:      | Lakewood Federal Com 8H            |
| SURFACE HOLE FOOTAGE: | 572'/S & 2336'/E                   |
| BOTTOM HOLE FOOTAGE:  | 20'/S & 2566'/E                    |
| LOCATION:             | Section 27, T.19 S., R.25 E., NMPM |
| COUNTY:               | Eddy County, New Mexico            |

|                      |   |                                       |                                       |
|----------------------|---|---------------------------------------|---------------------------------------|
| Potash               | <input checked="" type="radio"/> None         | <input type="radio"/> Secretary       | <input type="radio"/> R-111-P         |
| Cave/Karst Potential | <input type="radio"/> Low                     | <input type="radio"/> Medium          | <input checked="" type="radio"/> High |
| Variance             | <input checked="" type="radio"/> None         | <input type="radio"/> Flex Hose       | <input type="radio"/> Other           |
| Wellhead             | <input checked="" type="radio"/> Conventional | <input type="radio"/> Multibowl       |                                       |
| Other                | <input type="checkbox"/> 4 String Area        | <input type="checkbox"/> Capitan Reef | <input type="checkbox"/> WIPP         |

### A. HYDROGEN SULFIDE

1. Hydrogen Sulfide (H<sub>2</sub>S) monitors shall be installed prior to drilling out the surface shoe. If H<sub>2</sub>S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

### B. CASING

**HIGH CAVE/KARST – OPERATOR HAS PROPOSED A CONTINGENCY CASING IF LOST CIRCULATION OCCURS WHILE DRILLING THE SURFACE HOLE.**

**IF LOST CIRCULATION OCCURS WHILE DRILLING THE 8-3/4" HOLE, THE CEMENT PROGRAM FOR THE 7" X 5-1/2" CASING WILL NEED TO BE MODIFIED AND THE BLM IS TO BE CONTACTED PRIOR TO RUNNING THE CASING. A MINIMUM OF TWO CASING STRINGS CEMENTED TO SURFACE IS REQUIRED IN HIGH CAVE/KARST AREAS. THE CEMENT MUST BE IN A SOLID SHEATH THEREFORE, ONE INCH OPERATIONS WILL NOT BE PERMITTED. A DV TOOL WILL BE REQUIRED.**

### **Contingency Surface Casing Plan:**

1. The 13 3/8 inch contingency surface casing shall be set at approximately 400 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

### **Casing Plan without Contingency:**

2. The 9 5/8 inch surface casing shall be set at approximately 1279 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
3. The minimum required fill of cement behind the 7 X 5 1/2 inch production casing is:
  - Cement to surface. If cement does not circulate, contact the appropriate BLM office. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.**

### **C. PRESSURE CONTROL**

1. **Contingency** - Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **13-3/8 inch** surface casing shoe shall be **3000 (3M) psi**.
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **9-5/8 inch** surface casing shoe shall be **3000 (3M) psi**.

### **D. SPECIAL REQUIREMENT(S)**

#### **Communitization Agreement**

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

**MHH 12152018**

## GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties  
Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.  
During office hours call (575) 627-0272.  
After office hours call (575)

☒ Eddy County  
Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

☒ Lea County  
Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)  
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
    - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.



3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

**B. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
  - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the

plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

**C. DRILLING MUD**

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

**D. WASTE MATERIAL AND FLUIDS**

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.



**U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT**

## Operator Certification Data Report

12/27/2018

### Operator Certification

*I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.*

**NAME:** Brian Wood

**Signed on:** 08/20/2018

**Title:** President

**Street Address:** 37 Verano Loop

**City:** Santa Fe

**State:** NM

**Zip:** 87508

**Phone:** (505)466-8120

**Email address:** afmss@permitswest.com

### Field Representative

**Representative Name:**

**Street Address:**

**City:**

**State:**

**Zip:**

**Phone:**

**Email address:**



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Application Data Report

12/27/2018

APD ID: 10400032902

Submission Date: 08/20/2018

Operator Name: PERCUSSION PETROLEUM OPERATING LLC

Highlighted data  
reflects the most  
recent changes

Well Name: LAKEWOOD FEDERAL COM

Well Number: 8H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

### Section 1 - General

APD ID: 10400032902

Tie to previous NOS?

Submission Date: 08/20/2018

BLM Office: CARLSBAD

User: Brian Wood

Title: President

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM0504364B

Lease Acres: 480

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? NO

Permitting Agent? YES

APD Operator: PERCUSSION PETROLEUM OPERATING LLC

Operator letter of designation:

### Operator Info

Operator Organization Name: PERCUSSION PETROLEUM OPERATING LLC

Operator Address: 919 Milam Street, Suite 2475

Zip: 77002

Operator PO Box:

Operator City: Houston

State: TX

Operator Phone: (713)589-2337

Operator Internet Address:

### Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: LAKEWOOD FEDERAL COM

Well Number: 8H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: N. SEVEN RIVERS; Pool Name:

GLORIETA -YESO

Is the proposed well in an area containing other mineral resources? USEABLE WATER,NATURAL GAS,OIL

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

**Describe other minerals:**

**Is the proposed well in a Helium production area?** N **Use Existing Well Pad?** NO **New surface disturbance?**

**Type of Well Pad:** MULTIPLE WELL

**Multiple Well Pad Name:**  
LAKEWOOD FEDERAL COM

**Number:** 7H

**Well Class:** HORIZONTAL

**Number of Legs:** 1

**Well Work Type:** Drill

**Well Type:** OIL WELL

**Describe Well Type:**

**Well sub-Type:** INFILL

**Describe sub-type:**

**Distance to town:** 15 Miles

**Distance to nearest well:** 20 FT

**Distance to lease line:** 304 FT

**Reservoir well spacing assigned acres Measurement:** 160 Acres

**Well plat:** Lake\_8H\_Plat\_GasCap\_Plan\_20181019083426.pdf

**Well work start Date:** 11/01/2018

**Duration:** 90 DAYS

### Section 3 - Well Location Table

**Survey Type:** RECTANGULAR

**Describe Survey Type:**

**Datum:** NAD83

**Vertical Datum:** NAVD88

**Survey number:** 3239

|                  | NS-Foot | NS Indicator | EW-Foot  | EW Indicator | Twsp | Range | Section | Aliquot/Lot/Tract    | Latitude      | Longitude           | County   | State             | Meridian          | Lease Type | Lease Number         | Elevation | MD  | TVD |
|------------------|---------|--------------|----------|--------------|------|-------|---------|----------------------|---------------|---------------------|----------|-------------------|-------------------|------------|----------------------|-----------|-----|-----|
| SHL<br>Leg<br>#1 | 572     | FSL          | 233<br>6 | FEL          | 19S  | 25E   | 27      | Aliquot<br>SWSE<br>4 | 32.62574<br>4 | -<br>104.4713<br>92 | EDD<br>Y | NEW<br>MEXI<br>CO | NEW<br>MEXI<br>CO | F          | NMNM<br>050436<br>4B | 348<br>3  | 0   | 0   |
| KOP<br>Leg<br>#1 | 572     | FSL          | 233<br>6 | FEL          | 19S  | 25E   | 27      | Aliquot<br>SWSE<br>4 | 32.62574<br>4 | -<br>104.4713<br>92 | EDD<br>Y | NEW<br>MEXI<br>CO | NEW<br>MEXI<br>CO | F          | NMNM<br>050436<br>4B | 272<br>3  | 760 | 760 |
| PPP<br>Leg<br>#1 | 572     | FSL          | 233<br>6 | FEL          | 19S  | 25E   | 27      | Aliquot<br>SWSE<br>4 | 32.62574<br>4 | -<br>104.4713<br>92 | EDD<br>Y | NEW<br>MEXI<br>CO | NEW<br>MEXI<br>CO | F          | NMNM<br>050436<br>4B | 348<br>3  | 0   | 0   |

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

|                   | NS-Foot  | NS Indicator | EW-Foot  | EW Indicator | Twsp | Range | Section | Aliquot/Lot/Tract | Latitude      | Longitude           | County   | State             | Meridian          | Lease Type | Lease Number   | Elevation | MD       | TVD      |
|-------------------|----------|--------------|----------|--------------|------|-------|---------|-------------------|---------------|---------------------|----------|-------------------|-------------------|------------|----------------|-----------|----------|----------|
| PPP<br>Leg<br>#1  | 264<br>0 | FSL          | 261<br>9 | FEL          | 19S  | 25E   | 34      | Aliquot<br>NWSE   | 32.61699<br>4 | -<br>104.4733<br>23 | EDD<br>Y | NEW<br>MEXI<br>CO | NEW<br>MEXI<br>CO | F          | NMNM<br>015291 | 862       | 557<br>7 | 262<br>1 |
| PPP<br>Leg<br>#1  | 132<br>0 | FSL          | 258<br>5 | FEL          | 19S  | 25E   | 34      | Aliquot<br>SWSE   | 32.61329<br>6 | -<br>104.4723<br>59 | EDD<br>Y | NEW<br>MEXI<br>CO | NEW<br>MEXI<br>CO | F          | NMNM<br>031200 | 852       | 689<br>1 | 263<br>1 |
| EXIT<br>Leg<br>#1 | 20       | FSL          | 256<br>6 | FEL          | 19S  | 25E   | 34      | Aliquot<br>SWSE   | 32.60976<br>2 | -<br>104.4723<br>93 | EDD<br>Y | NEW<br>MEXI<br>CO | NEW<br>MEXI<br>CO | F          | NMNM<br>031200 | 842       | 817<br>7 | 264<br>1 |
| BHL<br>Leg<br>#1  | 20       | FSL          | 256<br>6 | FEL          | 19S  | 25E   | 34      | Aliquot<br>SWSE   | 32.60976<br>2 | -<br>104.4723<br>93 | EDD<br>Y | NEW<br>MEXI<br>CO | NEW<br>MEXI<br>CO | F          | NMNM<br>031200 | 842       | 817<br>7 | 264<br>1 |





U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Drilling Plan Data Report

12/27/2018

APD ID: 10400032902

Submission Date: 08/20/2018

Highlighted data  
reflects the most  
recent changes

Operator Name: PERCUSSION PETROLEUM OPERATING LLC

Well Name: LAKEWOOD FEDERAL COM

Well Number: 8H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

### Section 1 - Geologic Formations

| Formation ID | Formation Name | Elevation | True Vertical Depth | Measured Depth | Lithologies     | Mineral Resources | Producing Formation |
|--------------|----------------|-----------|---------------------|----------------|-----------------|-------------------|---------------------|
| 1            | QUATERNARY     | 3483      | 0                   | 0              | OTHER : Caliche | USEABLE WATER     | No                  |
| 2            | GRAYBURG       | 2870      | 613                 | 613            | DOLOMITE        | NATURAL GAS,OIL   | No                  |
| 3            | SAN ANDRES     | 2685      | 798                 | 799            | DOLOMITE        | NATURAL GAS,OIL   | No                  |
| 4            | GLORIETA       | 1125      | 2358                | 2390           | DOLOMITE        | NATURAL GAS,OIL   | No                  |
| 5            | YESO           | 970       | 2513                | 2621           | DOLOMITE        | NATURAL GAS,OIL   | Yes                 |

### Section 2 - Blowout Prevention

Pressure Rating (BOP) : 5000

Rating Depth: 5000

**Equipment:** A 3000-psi 5000' rated BOP stack consisting of annular preventer and double (blind and pipe) ram will be used below surface casing to TD.

**Requesting Variance?** NO

**Variance request:**

**Testing Procedure:** Pressure tests will be conducted before drilling out from under all casing strings. Third party test crews will conduct all tests. All tests will be recorded for 10-minutes on low pressure (500 psi) and 10-minutes on high pressure (3000-psi). After BOP testing is complete, test casing (without test plug) to 2000-psi for 30 minutes. All tests will be charted on a plot. BOPs will be function tested every day.

**Choke Diagram Attachment:**

Lake\_8H\_Choke\_20180808125805.pdf

**BOP Diagram Attachment:**

Lake\_8H\_BOP\_20180808125813.pdf

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

### Section 3 - Casing

| Casing ID | String Type | Hole Size | Csg Size | Condition | Standard | Tapered String | Top Set MD | Bottom Set MD | Top Set TVD | Bottom Set TVD | Top Set MSL | Bottom Set MSL | Calculated casing length MD | Grade | Weight | Joint Type  | Collapse SF | Burst SF | Joint SF Type | Joint SF | Body SF Type | Body SF |
|-----------|-------------|-----------|----------|-----------|----------|----------------|------------|---------------|-------------|----------------|-------------|----------------|-----------------------------|-------|--------|-------------|-------------|----------|---------------|----------|--------------|---------|
| 1         | SURFACE     | 12.25     | 9.625    | NEW       | API      | N              | 0          | 1279          | 0           | 1274           | 3483        |                | 1279                        | J-55  | 36     | LTC         | 1.125       | 1.125    | DRY           | 1.8      | DRY          | 1.8     |
| 2         | PRODUCTION  | 8.75      | 7.0      | NEW       | API      | N              | 0          | 2350          | 0           | 2323           | 3483        |                | 2350                        | L-80  | 32     | OTHER - BTC | 1.125       | 1.125    | DRY           | 1.8      | DRY          | 1.8     |
| 3         | PRODUCTION  | 8.75      | 5.5      | NEW       | API      | N              | 2350       | 8177          | 2323        | 2641           |             |                | 5827                        | L-80  | 17     | OTHER - BTC | 1.125       | 1.125    | DRY           | 1.8      | DRY          | 1.8     |

#### Casing Attachments

**Casing ID:** 1      **String Type:** SURFACE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

Lake\_8H\_Casing\_Design\_Assumptions\_20180808125841.pdf

Operator Name: PERCUSSION PETROLEUM OPERATING LLC

Well Name: LAKEWOOD FEDERAL COM

Well Number: 8H

#### Casing Attachments

Casing ID: 2 String Type: PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Lake\_8H\_Casing\_Design\_Assumptions\_20180808125924.pdf

Casing ID: 3 String Type: PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Lake\_8H\_Casing\_Design\_Assumptions\_20180808125953.pdf

#### Section 4 - Cement

| String Type | Lead/Tail | Stage Tool Depth | Top MD | Bottom MD | Quantity(sx) | Yield | Density | Cu Ft | Excess% | Cement type | Additives                             |
|-------------|-----------|------------------|--------|-----------|--------------|-------|---------|-------|---------|-------------|---------------------------------------|
| SURFACE     | Lead      |                  | 0      | 1279      | 636          | 1.32  | 14.8    | 840   | 100     | Class C     | 2% CaCl + ¼ pound per sack celloflake |

|            |      |  |      |      |      |      |      |      |    |                 |   |
|------------|------|--|------|------|------|------|------|------|----|-----------------|---|
| PRODUCTION | Lead |  | 0    | 2350 | 495  | 1.97 | 12.6 | 975  | 50 | 65/65/6 Class C | 6% gel + 5% salt + ¼ pound per sack celloflake + 0.2% C41-P |
| PRODUCTION | Tail |  | 0    | 2350 | 1370 | 1.32 | 14.8 | 1808 | 50 | Class C         | 2% CaCl + ¼ pound per sack celloflake                       |
| PRODUCTION | Lead |  | 2350 | 8177 | 495  | 1.97 | 12.6 | 975  | 50 | 65/65/6 Class C | 6% gel + 5% salt + ¼ pound per sack                         |

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

| String Type | Lead/Tail | Stage Tool Depth | Top MD | Bottom MD | Quantity(sx) | Yield | Density | Cu Ft | Excess% | Cement type | Additives  |
|-------------|-----------|------------------|--------|-----------|--------------|-------|---------|-------|---------|-------------|--|
| PRODUCTION  | Tail      |                  | 2350   | 8177      | 1370         | 1.32  | 14.8    | 1808  | 50      | Class C     | celloflake + 0.2% C41-P<br>2% CaCl + ¼ pound per sack celloflake |

### Section 5 - Circulating Medium

**Mud System Type:** Closed

**Will an air or gas system be Used?** NO

**Description of the equipment for the circulating system in accordance with Onshore Order #2:**

**Diagram of the equipment for the circulating system in accordance with Onshore Order #2:**

**Describe what will be on location to control well or mitigate other conditions:** All necessary mud products (LCM) will be on site to handle any abnormal hole condition that may be encountered while drilling this well.

**Describe the mud monitoring system utilized:** An electronic/mechanical mud monitor with a minimum pit volume totalizer, stroke counter, and flow sensor will be used.

### Circulating Medium Table

| Top Depth | Bottom Depth | Mud Type                      | Min Weight (lbs/gal) | Max Weight (lbs/gal) | Density (lbs/cu ft) | Gel Strength (lbs/100 sqft) | PH | Viscosity (CP) | Salinity (ppm) | Filtration (cc) | Additional Characteristics |
|-----------|--------------|-------------------------------|----------------------|----------------------|---------------------|-----------------------------|----|----------------|----------------|-----------------|----------------------------|
| 1279      | 2087         | OTHER : Fresh water/cut brine | 8.3                  | 9.2                  |                     |                             |    |                |                |                 |                            |
| 2087      | 8177         | OTHER : Cut brine             | 8.6                  | 9.2                  |                     |                             |    |                |                |                 |                            |
| 0         | 1279         | OTHER : Fresh water/gel       | 8.4                  | 9.2                  |                     |                             |    |                |                |                 |                            |

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

## **Section 6 - Test, Logging, Coring**

**List of production tests including testing procedures, equipment and safety measures:**

A mud logger will be used from GL to TD. Samples will be collected every 10' in the lateral pay zone.

No electric logs are planned at this time.

**List of open and cased hole logs run in the well:**

MUDLOG

**Coring operation description for the well:**

No core or drill stem test is planned.

## **Section 7 - Pressure**

**Anticipated Bottom Hole Pressure:** 1127

**Anticipated Surface Pressure:** 545.98

**Anticipated Bottom Hole Temperature(F):** 109

**Anticipated abnormal pressures, temperatures, or potential geologic hazards?** NO

**Describe:**

**Contingency Plans geohazards description:**

**Contingency Plans geohazards attachment:**

**Hydrogen Sulfide drilling operations plan required?** YES

**Hydrogen sulfide drilling operations plan:**

Lake\_8H\_H2S\_Plan\_20180808130215.pdf

## **Section 8 - Other Information**

**Proposed horizontal/directional/multi-lateral plan submission:**

Lake\_8H\_Horizontal\_Drill\_Plan\_20180808130233.pdf


**Other proposed operations facets description:**

**Other proposed operations facets attachment:**

Lake\_8H\_Drill\_Plan\_20181012163837.pdf

Lake\_8H\_Contingency\_Plan\_20181012163942.pdf

**Other Variance attachment:**



## Pressure Testing


- All testing to be done with 3<sup>rd</sup> party testing crews
- All tests should be done for each BOP/Valve/Choke Manifold:
  - Recorded for 10 minutes on low pressure (500 psi)
  - Recorded for 10 minutes on high pressure (3000 psi)
  - All BOP testing will be completed with a test plug in place in wellhead
- After BOP testing is complete, test casing (without test plug) to 2000 psi for 30 minutes
- Company representative to email all copies of all plots to Drilling Engineer as well as save in the well file.
- BOP's shall be function tested every day.**

## Gas Buster Operation

- Flow should be directed to pits unless choke is needed to control gas
- Adjustable choke to adjusted only by Percussion Rep on location
- Flare should remain burning (pilot lit) anytime fluid is going through gas buster
- Choke needs to be monitored to not overrun gas buster

## Nipple-Up

- Raise stack and center over the wellhead
- Install DSA and ring gaskets
- Lower stack onto DSA
- Torque DSA flange bolts in a star pattern to the specified torque
- Verify BOP is centered to the rotary table
- Install rotating head
- Install hydraulic lines to BOP
- Verify manifold line-up
- Test BOP & manifold





## Casing Design Criteria and Load Case Assumptions

Percussion Petroleum Operating, LLC.  
919 Milam Street, Suite 2475  
Houston, TX 77002

### Lakewood Federal Com horizontal Wells

1. Collapse:  $DF_c=1.125$ 
  - a. Full Internal Evacuation: Collapse force equal to the mud gradient in which the casing will be run (0.65 psi/ft). The effects of axial load on collapse will be considered.
  - b. Cementing: Collapse force equal to the gradient of planned cement slurries to planned depths and minimum mud gradient in which the casing will be run above that (0.65 psi/ft) and an internal force equal to mud gradient of displacement fluid (0.43 psi/ft)
  
2. Burst:  $DF_b=1.125$ 
  - a. Pressure Test: psi casing test with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.
  - b. Injection Down Casing: psi surface injection pressure plus an internal pressure gradient of 0.65 psi/ft with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.
  
3. Tensile:  $DF_T=1.8$ 
  - a. Overpull: A downward force of 100,000 lbs is applied at the shoe along with the weight of the casing string utilizing the effects of buoyancy (10.5 ppg).

| 4. Surface Casing Program |              |           |                   |                                   |            |                        |             |                     |                   |
|---------------------------|--------------|-----------|-------------------|-----------------------------------|------------|------------------------|-------------|---------------------|-------------------|
| Casing Size (in)          | Weight (ppf) | Grade     | Connection        | ID                                | ID (drift) | Collapse (psi)         | Burst (psi) | Tension (1,000 lbs) | Capacity (bbl/ft) |
| 9-5/8"                    | 36           | J-55      | STC               | 8.921                             | 8.765      | 2,020                  | 3,520       | 394                 | 0.0773            |
| Safety Factors            |              |           |                   |                                   |            |                        |             |                     |                   |
|                           | API Rec. SF  | ACTUAL SF | Case              | External Fluids                   |            | Internal Fluids        |             |                     |                   |
| Collapse                  | 1.125        | 3.30      | Lost Circulation  | Mud                               |            | None                   |             |                     |                   |
| Burst                     | 1.125        | 1.46      | Plug Bump         | Green Cement + 2ksi surf pressure |            | Displacement Fluid/Mud |             |                     |                   |
| Tension                   | 1.8          | 2.80      | 100 klbs Overpull | Mud                               |            | Mud                    |             |                     |                   |

**Buoyed Casing Weight: 40,798 lbs (assuming 8.4 ppg fluid and 1,300' casing-worst case scenario)**





| Production Casing Program |              |           |                   |                                   |            |                        |             |                     |                   |
|---------------------------|--------------|-----------|-------------------|-----------------------------------|------------|------------------------|-------------|---------------------|-------------------|
| Casing Size (in)          | Weight (ppf) | Grade     | Connection        | ID                                | ID (drift) | Collapse (psi)         | Burst (psi) | Tension (1,000 lbs) | Capacity (bbl/ft) |
| 7"                        | 32           | L-80      | BTC               | 6.094                             | 5.969      | 8,600                  | 9,060       | 745                 | 0.0361            |
| 5-1/2"                    | 17           | L-80      | BTC               | 4.892                             | 4.767      | 6,280                  | 7,740       | 348                 | 0.0232            |
| Safety Factors            |              |           |                   |                                   |            |                        |             |                     |                   |
|                           | API Rec. SF  | ACTUAL SF | Case              | External Fluids                   |            | Internal Fluids        |             |                     |                   |
| Collapse                  | 1.125        | 3.75      | Lost Circulation  | Mud                               |            | None                   |             |                     |                   |
| Burst                     | 1.125        | 2.47      | Plug Bump         | Green Cement + 2ksi surf pressure |            | Displacement Fluid/Mud |             |                     |                   |
| Tension                   | 1.8          | 2.29      | 100 klbs Overpull | Mud                               |            | Mud                    |             |                     |                   |

**Buoyed Casing Weight: 86,522 lbs (assuming 8.4 ppg fluid and 3,500' TVD-worst case scenario)**



## Casing Design Criteria and Load Case Assumptions

Percussion Petroleum Operating, LLC.  
919 Milam Street, Suite 2475  
Houston, TX 77002

### Lakewood Federal Com horizontal Wells

1. Collapse:  $DF_c=1.125$ 
  - a. Full Internal Evacuation: Collapse force equal to the mud gradient in which the casing will be run (0.65 psi/ft). The effects of axial load on collapse will be considered.
  - b. Cementing: Collapse force equal to the gradient of planned cement slurries to planned depths and minimum mud gradient in which the casing will be run above that (0.65 psi/ft) and an internal force equal to mud gradient of displacement fluid (0.43 psi/ft)
2. Burst:  $DF_b=1.125$ 
  - a. Pressure Test: psi casing test with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.
  - b. Injection Down Casing: psi surface injection pressure plus an internal pressure gradient of 0.65 psi/ft with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.
3. Tensile:  $DF_T=1.8$ 
  - a. Overpull: A downward force of 100,000 lbs is applied at the shoe along with the weight of the casing string utilizing the effects of buoyancy (10.5 ppg).

| 4. Surface Casing Program |              |           |                   |                                   |            |                        |             |                     |                   |
|---------------------------|--------------|-----------|-------------------|-----------------------------------|------------|------------------------|-------------|---------------------|-------------------|
| Casing Size (In)          | Weight (ppf) | Grade     | Connection        | ID                                | ID (drift) | Collapse (psi)         | Burst (psi) | Tension (1,000 lbs) | Capacity (bbf/ft) |
| 9-5/8"                    | 36           | J-55      | STC               | 8.921                             | 8.765      | 2,020                  | 3,520       | 394                 | 0.0773            |
| Safety Factors            |              |           |                   |                                   |            |                        |             |                     |                   |
|                           | API Rec. SF  | ACTUAL SF | Case              | External Fluids                   |            | Internal Fluids        |             |                     |                   |
| Collapse                  | 1.125        | 3.30      | Lost Circulation  | Mud                               |            | None                   |             |                     |                   |
| Burst                     | 1.125        | 1.46      | Plug Bump         | Green Cement + 2ksi surf pressure |            | Displacement Fluid/Mud |             |                     |                   |
| Tension                   | 1.8          | 2.80      | 100 klbs Overpull | Mud                               |            | Mud                    |             |                     |                   |

**Buoyed Casing Weight: 40,798 lbs (assuming 8.4 ppg fluid and 1,300' casing-worst case scenario)**



| Production Casing Program |              |           |                   |                                   |            |                        |             |                     |                   |
|---------------------------|--------------|-----------|-------------------|-----------------------------------|------------|------------------------|-------------|---------------------|-------------------|
| Casing Size (in)          | Weight (ppf) | Grade     | Connection        | ID                                | ID (drift) | Collapse (psi)         | Burst (psi) | Tension (1,000 lbs) | Capacity (bbl/ft) |
| 7"                        | 32           | L-80      | BTC               | 6.094                             | 5.969      | 8,600                  | 9,060       | 745                 | 0.0361            |
| 5-1/2"                    | 17           | L-80      | BTC               | 4.892                             | 4.767      | 6,280                  | 7,740       | 348                 | 0.0232            |
| Safety Factors            |              |           |                   |                                   |            |                        |             |                     |                   |
|                           | API Rec. SF  | ACTUAL SF | Case              | External Fluids                   |            | Internal Fluids        |             |                     |                   |
| Collapse                  | 1.125        | 3.75      | Lost Circulation  | Mud                               |            | None                   |             |                     |                   |
| Burst                     | 1.125        | 2.47      | Plug Bump         | Green Cement + 2ksi surf pressure |            | Displacement Fluid/Mud |             |                     |                   |
| Tension                   | 1.8          | 2.29      | 100 klbs Overpull | Mud                               |            | Mud                    |             |                     |                   |

**Buoyed Casing Weight: 86,522 lbs (assuming 8.4 ppg fluid and 3,500' TVD-worst case scenario)**



## Casing Design Criteria and Load Case Assumptions

Percussion Petroleum Operating, LLC.  
919 Milam Street, Suite 2475  
Houston, TX 77002

### Lakewood Federal Com horizontal Wells

1. Collapse:  $DF_c=1.125$ 
  - a. Full Internal Evacuation: Collapse force equal to the mud gradient in which the casing will be run (0.65 psi/ft). The effects of axial load on collapse will be considered.
  - b. Cementing: Collapse force equal to the gradient of planned cement slurries to planned depths and minimum mud gradient in which the casing will be run above that (0.65 psi/ft) and an internal force equal to mud gradient of displacement fluid (0.43 psi/ft)
  
2. Burst:  $DF_b=1.125$ 
  - a. Pressure Test: psi casing test with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.
  - b. Injection Down Casing: psi surface injection pressure plus an internal pressure gradient of 0.65 psi/ft with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.
  
3. Tensile:  $DF_t=1.8$ 
  - a. Overpull: A downward force of 100,000 lbs is applied at the shoe along with the weight of the casing string utilizing the effects of buoyancy (10.5 ppg).

| 4. Surface Casing Program |              |           |                   |                                   |            |                        |             |                     |                   |
|---------------------------|--------------|-----------|-------------------|-----------------------------------|------------|------------------------|-------------|---------------------|-------------------|
| Casing Size (In)          | Weight (ppf) | Grade     | Connection        | ID                                | ID (drift) | Collapse (psi)         | Burst (psi) | Tension (1,000 lbs) | Capacity (bbl/ft) |
| 9-5/8"                    | 36           | J-55      | STC               | 8.921                             | 8.765      | 2,020                  | 3,520       | 394                 | 0.0773            |
| Safety Factors            |              |           |                   |                                   |            |                        |             |                     |                   |
|                           | API Rec. SF  | ACTUAL SF | Case              | External Fluids                   |            | Internal Fluids        |             |                     |                   |
| Collapse                  | 1.125        | 3.30      | Lost Circulation  | Mud                               |            | None                   |             |                     |                   |
| Burst                     | 1.125        | 1.46      | Plug Bump         | Green Cement + 2ksi surf pressure |            | Displacement Fluid/Mud |             |                     |                   |
| Tension                   | 1.8          | 2.80      | 100 klbs Overpull | Mud                               |            | Mud                    |             |                     |                   |

**Buoyed Casing Weight: 40,798 lbs (assuming 8.4 ppg fluid and 1,300' casing-worst case scenario)**



| Production Casing Program |              |           |                   |                                   |            |                        |             |                     |                   |
|---------------------------|--------------|-----------|-------------------|-----------------------------------|------------|------------------------|-------------|---------------------|-------------------|
| Casing Size (in)          | Weight (ppf) | Grade     | Connection        | ID                                | ID (drift) | Collapse (psi)         | Burst (psi) | Tension (1,000 lbs) | Capacity (bbl/ft) |
| 7"                        | 32           | L-80      | BTC               | 6.094                             | 5.969      | 8,600                  | 9,060       | 745                 | 0.0361            |
| 5-1/2"                    | 17           | L-80      | BTC               | 4.892                             | 4.767      | 6,280                  | 7,740       | 348                 | 0.0232            |
| Safety Factors            |              |           |                   |                                   |            |                        |             |                     |                   |
|                           | API Rec. SF  | ACTUAL SF | Case              | External Fluids                   |            | Internal Fluids        |             |                     |                   |
| Collapse                  | 1.125        | 3.75      | Lost Circulation  | Mud                               |            | None                   |             |                     |                   |
| Burst                     | 1.125        | 2.47      | Plug Bump         | Green Cement + 2ksi surf pressure |            | Displacement Fluid/Mud |             |                     |                   |
| Tension                   | 1.8          | 2.29      | 100 klbs Overpull | Mud                               |            | Mud                    |             |                     |                   |

**Buoyed Casing Weight: 86,522 lbs (assuming 8.4 ppg fluid and 3,500' TVD-worst case scenario)**

## **Contingency Planning – Lakewood Federal Area Wells**

**Prepared by Lelan J. Anders, Percussion Petroleum Operating, LLC.**

### **INTRODUCTION:**


This document is designed to address the issues that could arise at any time drilling horizontal Yeso wells. Percussion Petroleum Operating (PPO) is going to follow regularly used practices and procedures in order to drill the wells to TD and still keep them economical to operate.

### **SCENARIO:**

If a complete loss of circulation occurs while drilling above 400 ft MD.

### **CORRECTIVE ACTIONS:**


1. Pump an LCM sweep and attempt to regain circulation – if unsuccessful go to step 2
2. Continue drilling at attempt to seal off lost circulation zone with drill cuttings
  1. Monitor torque and drag on drill string to determine if pipe is sticking
  2. Have contingency plan to 'drill dry' – have plenty of water on hand and well control in place
  3. Continue to 'dry drill' until torque and drag dictate a different plan
3. If 'dry drilling' is unsuccessful – Run contingency surface casing string
  1. Ream out 12-1/4" open hole to 17-1/2" open hole
  2. Run contingency 13-3/8" 48# H-40, STC casing to no more than 400' MD
  3. Cement 13-3/8" casing using Class C cement
    - i. Pump at minimum 100% excess cement
      1. 65/35/6 Class C Cement, 12.8 ppg, 1.87 yield, 10.15 gal/sk to be used on initial cement job.
    - ii. Top off cement from surface using 1" if necessary
      1. Top off will be 200 sks of 65/35/6 Class C Cement, 12.8 ppg, 1.87 yield, 10.15 gal/sk
      2. Second top off will be performed with same cement if needed.
    - iii. Insure that cement has cured for a minimum of 12 hours prior to drilling out
4. Install 13-3/8" 3M wellhead and drill to surface casing depth with 12-1/4" OD bit
5. Run and cement surface casing as planned



**Schematic Closed Loop Drilling Rig\***

1. Pipe Rack
2. Drill Rig
3. House Trailers/ Offices
4. Generator/Fuel/Storage
5. Overflow-Frac Tank
6. Skids
7. Roll Offs
8. Hopper or Centrifuge
9. Mud Tanks
10. Loop Drive
11. Generator (only for use with centrifuge)

\*Not drawn to scale: Closed loop system requires at least 30 feet beyond mud tanks. Ideally 60 feet would be available




Above: Centrifugal Closed Loop System



**Closed Loop Drilling System:** Mud tanks to right (1)  
Hopper in air to settle out solids (2)  
Water return pipe (3)  
Shaker between hopper and mud tanks (4)  
Roll offs on skids (5)

#### Flow Chart for Drilling Fluids and Solids




Photos Courtesy of Gandy Corporation Oil  
Field Service


**PERMITS WEST** INC.  
PROVIDING PERMITS for LAND USERS  
17Virano Corp. Santa Fe, New Mexico 87508 (505) 466-8120



Percussion's  
Lakewood Federal Com 8H  
rig diagram

Prevailing Wind  
out of South  
or SSE

 NORTH  
1" = 50'





## **Hydrogen Sulfide Drilling Operations Plan**

**Percussion Petroleum Operating, LLC.**

**919 Milam Street, Suite 2475**

**Houston, TX 77002**

1. **H<sub>2</sub>S Safety Instructions to the following:**
  - Characteristics of H<sub>2</sub>S.
  - Physical effects and hazards.
  - Principal and operation of H<sub>2</sub>S detectors, warning system and briefing areas.
  - Evacuation procedures, routes and First Aid.
  - Proper use of safety equipment and life support systems.
  - Essential personnel meeting medical evaluation criteria will receive additional training on the proper use of 30 min pressure demand air packs.
2. **H<sub>2</sub>S Detection & Alarm Systems:**
  - H<sub>2</sub>S sensor/detectors to be located on the drilling rig floor, in the base of the sub structure/cellar area, on the mud returns pits by the shale shaker. Additional H<sub>2</sub>S monitors may be placed as deemed necessary.
  - An audio alarm system will be installed on the derrick, the floor, and in the doghouse.
3. **Windssocks and Wind Streamers:**
  - Windssocks at mud pit area should be high enough to be visible.
  - Windssock on the rig floor/top of doghouse should be high enough to be visible.
4. **Condition Flags & Signs:**
  - Warning sign on access road to location
  - Flags to be displayed on sign at entrance to location
    - i. Green Flag – Normal Safe Operation Condition
    - ii. Yellow Flag – Potential Pressure and Danger
    - iii. Red Flag – Danger (H<sub>2</sub>S present in dangerous concentrations) Only H<sub>2</sub>S trained personnel admitted on location
5. **Well Control Equipment:**
  - See attached APD



6. Communications:

- While working under masks, chalkboards will be used for communications
- Hand signals will be used where chalk board is inappropriate
- Two-way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at drilling foreman's trailer or living quarters.

7. Drilling Stem Testing:

- No Drill Stem Tests or hole coring is planned at this time.

8. Drilling contractor supervisor will be required to be familiar with the effects H<sub>2</sub>S has on tubular goods and other mechanical equipment.

9. If H<sub>2</sub>S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H<sub>2</sub>S scavenger chemicals if necessary.

10. Emergency Contacts:

| Emergency Contact Information - H <sub>2</sub> S Contingency Plan |                              |              |              |                               |
|---|------------------------------|--------------|--------------|-------------------------------|
| Percussion Petroleum Operating, LLC                               | 713-518-1331                 |              |              |                               |
| Key Parties at Percussion Petroleum                               |                              | Office       | Mobile       | Email                         |
| Lelan J Anders  | Vice President of Operations | 713-429-1291 | 281-908-1752 | Lelan@PercussionPetroleum.com |
| Lupe Carrillo   | Chief Operating Officer      | 713-589-9509 | 832-776-1869 | Lupe@PercussionPetroleum.com  |
| John H. Campbell III  | Chief Executive Officer      | 713-589-4683 | 936-718-6488 | John@PercussionPetroleum.com  |

| Artesia, New Mexico:                 |              |
|--------------------------------------|--------------|
| Ambulance                            | 911          |
| State Police                         | 575-746-2703 |
| City Police                          | 575-746-2703 |
| Sheriff's Office                     | 575-746-9888 |
| Fire Department                      | 575-746-2701 |
| Local Emergency Planning Committee   | 575-746-2122 |
| New Mexico Oil Conservation Division | 575-748-1283 |

| Carlsbad, New Mexico:                |              |
|--------------------------------------|--------------|
| Ambulance                            | 911          |
| State Police                         | 575-885-3137 |
| City Police                          | 575-885-2111 |
| Sheriff's Office                     | 575-887-7551 |
| Fire Department                      | 575-887-3798 |
| Local Emergency Planning Committee   | 575-887-6544 |
| New Mexico Oil Conservation Division | 575-887-6544 |




| <b>Santa Fe, New Mexico:</b>                     |              |
|--|--------------|
| New Mexico Emergency Response Commission         | 505-476-9600 |
| New Mexico Emergency Response Commission (24 hr) | 505-827-9126 |
| New Mexico State Emergency Operations Center     | 505-476-9635 |

| <b>Federal Contacts:</b>                            |              |
|---|--------------|
| Carlsbad BLM Office                                 | 575-234-5972 |
| National Emergency Response Center (Washington, DC) | 800-424-8802 |

| <b>Medical:</b>                            |              |
|--|--------------|
| Flight for Life - Lubbock, TX              | 806-743-9911 |
| AeroCare - Lubbock, TX                     | 806-747-8923 |
| Med Flight Air Ambulance - Albuquerque, NM | 505-842-4433 |
| SB Air Med Service - Albuquerque, NM       | 505-842-4949 |

| <b>Well Control/Other:</b> |              |
|----------------------------|--------------|
| Wild Well Control          | 281-784-4700 |
| Boots & Coots IWC          | 800-256-9688 |
| B.J. Services              | 575-746-3569 |
| Halliburton                | 575-746-2757 |

# WELL SITE PLAN



NOTE:  
SEE "TOPOGRAPHICAL AND ACCESS ROAD MAP"  
FOR PROPOSED ROAD LOCATION.

## PERCUSSION PETROLEUM OPERATING, LLC

LAKEWOOD FEDERAL #8H WELL LOCATED 572 FEET FROM  
THE SOUTH LINE AND 2336 FEET FROM THE EAST LINE OF  
SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO



PROVIDING SURVEYING SERVICES  
SINCE 1946  
**JOHN WEST SURVEYING COMPANY**  
412 N. DAL PASO HOBBS, N.M. 88240  
(575) 393-3117 www.jwsc.biz  
TBPLS# 10021000


|                      |                   |               |
|----------------------|-------------------|---------------|
| Survey Date: 4/03/18 | CAD Date: 5/02/18 | Drawn By: ACK |
| W.O. No.: 18110404   | Rev: 06/19/18     | Rel. W.O.:    |
|                      |                   | Sheet 1 of 1  |

# Percussion Petroleum Operating, LLC

Lakewood Federal Com 9H/8H/7H  
H<sub>2</sub>S Contingency Plan:  
Radius Map

Section 27, Township 19S, Range 25E  
Eddy County, New Mexico



⊙ Surface Hole Location



NAD 1983 New Mexico State Plane East  
FIPS 3001 Feet

**PERCUSSION PETROLEUM**

Prepared by Permian West, Inc., June 26, 2018  
for Percussion Petroleum Operating, LLC






Company: Percussion Petroleum, LLC  
Project: Eddy County, NM  
Site: Lakewood Federal  
Well: 08H  
Wellbore: OH  
Rig: Silver Oak 1  
Design: Plan #4 / 11:35, May 31 2018



PROJECT DETAILS Eddy County, NM  
Geodetic System: US State Plane 1983  
Datum: North American Datum 1983  
Elevation: GCS 1980  
Horizontal Units: Feet  
Vertical Units: Feet  
System Datum: Mean Sea Level



**TOTAL CORRECTION**  
Magnetic North is 7.37° East of Grid North (Magnetic Convergence)  
To convert a Magnetic Direction to a Grid Direction, Add 7.37°

WELL DETAILS: 08H

RKB-17 @ 3500.00 uft (Silver Oak 1)

Northings: 591500.60  
Eastings: 488748.70  
Latitude: 32.828009  
Longitude: -104.471870


SECTION DETAILS

| Boc | MD      | Inc   | AN     | TVD     | FW/S     | +E-W    | Deg   | V-Sect  |
|-----|---------|-------|--------|---------|----------|---------|-------|---------|
| 1   | 0.00    | 0.00  | 0.00   | 0.00    | 0.00     | 0.00    | 0.00  | 0.00    |
| 2   | 685.00  | 0.00  | 0.00   | 685.00  | 0.00     | 0.00    | 0.00  | 0.00    |
| 3   | 769.99  | 7.50  | 233.90 | 759.78  | -2.89    | -3.86   | 10.00 | 2.91    |
| 4   | 2089.90 | 7.50  | 233.90 | 2075.34 | -104.52  | -143.89 | 0.00  | 103.70  |
| 5   | 2938.12 | 85.56 | 180.31 | 2801.00 | -871.60  | -202.20 | 10.00 | 872.58  |
| 6   | 8177.35 | 85.56 | 180.31 | 2641.00 | -5910.50 | -230.30 | 0.00  | 6911.66 |

WELLBORE TARGET DETAILS (MAP CO-ORDINATES)

| Name        | TVD     | AN/S     | +E-W    | Northings | Eastings  | Shape |
|-------------|---------|----------|---------|-----------|-----------|-------|
| LF 08H: FTP | 2601.00 | -471.50  | -202.20 | 590254.10 | 495518.80 | Point |
| LF 08H: BHL | 2841.00 | -3910.50 | -230.30 | 585590.10 | 495518.80 | Point |
| LF 08H: LTP | 2841.00 | -5830.50 | -229.80 | 585570.10 | 495518.80 | Point |


Asimuths to Grid North  
True North: 0.07°  
Magnetic North: 7.37°



Magnetic Field  
Strength: 47980.80 T  
Dip Angle: 60.27°  
Date: 5/29/2018  
Model: IGRF2015

Disclaimer:

All data, including but not limited to, location/survey data is provided by customer and subject to customer approval.



Start 5238.23 hold at 2638.12 MD

LF 08H: FTP

LF 08H: LTP

LF 08H: BHL

Vertical Section at 180.31° (100 uft/in)

Plan: Plan #4 (08H/OH) Silver Oak 1

Created By: Daniel Benn Date: 11:35, May 31 2018

Company: Percussion Petroleum, LLC  
Project: Eddy County, NM  
Site: Lakewood Federal  
Well: 08H  
Wellbore: OH  
Design: Plan #4

Local Co-ordinate Reference: Well 08H  
TVD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
MD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Database: WBDS\_SQL\_2

Project: Eddy County, NM

Map System: US State Plane 1983  
Geo Datum: North American Datum 1983  
Map Zone: New Mexico Eastern Zone

System Datum: Mean Sea Level

Site: Lakewood Federal

|                       |       |           |              |                 |                   |             |
|-----------------------|-------|-----------|--------------|-----------------|-------------------|-------------|
| Site Position:        | From: | Lat/Long  | Northing:    | 590,773.06 usft | Latitude:         | 32.624012   |
|                       |       |           | Easting:     | 499,537.28 usft | Longitude:        | -104.469105 |
| Position Uncertainty: |       | 0.00 usft | Slot Radius: | 13.200 in       | Grid Convergence: | -0.07 °     |

Well: 08H

|                      |      |           |                     |                 |               |               |
|----------------------|------|-----------|---------------------|-----------------|---------------|---------------|
| Well Position        | +N-S | 0.00 usft | Northing:           | 591,500.60 usft | Latitude:     | 32.626009     |
|                      | +E-W | 0.00 usft | Easting:            | 498,748.70 usft | Longitude:    | -104.471670   |
| Position Uncertainty |      | 0.00 usft | Wellhead Elevation: | usft            | Ground Level: | 3,483.00 usft |

Wellbore: OH

| Magnetics | Model Name | Sample Date | Declination (°) | Dip Angle (°) | Field Strength (nT) |
|-----------|------------|-------------|-----------------|---------------|---------------------|
|           | IGRF2015   | 5/29/2018   | 7.30            | 60.27         | 47,980.89457034     |

Design: Plan #4

Audit Notes:

Version: Phase: PLAN Tie On Depth: 0.00

| Vertical Section: | Depth From (TVD) | +N-S   | +E-W   | Direction |
|-------------------|------------------|--------|--------|-----------|
|                   | (usft)           | (usft) | (usft) | (°)       |
|                   | 0.00             | 0.00   | 0.00   | 180.31    |

Survey Tool Program: Date 5/31/2018

| From (usft) | To (usft) | Survey (Wellbore) | Tool Name | Description            |
|-------------|-----------|-------------------|-----------|------------------------|
| 0.00        | 8,177.06  | Plan #4 (OH)      | MWD+IGRF  | OWSG MWD + IGRF or WMM |





# Wellbenders Standard Plan With Toolface



Company: Percussion Petroleum, LLC  
Project: Eddy County, NM  
Site: Lakewood Federal  
Well: 08H  
Wellbore: OH  
Design: Plan #4

Local Co-ordinate Reference: Well 08H  
TVD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
MD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Database: WBDS\_SQL\_2

## Planned Survey

| MD<br>(usft) | Inc<br>(°) | Azi (azimuth)<br>(°) | TVD<br>(usft) | N/S<br>(usft) | EW<br>(usft) | V. Sec<br>(usft) | DLeg<br>(°/100ft) | Build<br>(°/100ft) | Turn<br>(°/100ft) | TFace<br>(°) |
|--------------|------------|----------------------|---------------|---------------|--------------|------------------|-------------------|--------------------|-------------------|--------------|
| 0.00         | 0.00       | 0.00                 | 0.00          | 0.00          | 0.00         | 0.00             | 0.00              | 0.00               | 0.00              | 0.00         |
| 100.00       | 0.00       | 0.00                 | 100.00        | 0.00          | 0.00         | 0.00             | 0.00              | 0.00               | 0.00              | 0.00         |
| 200.00       | 0.00       | 0.00                 | 200.00        | 0.00          | 0.00         | 0.00             | 0.00              | 0.00               | 0.00              | 0.00         |
| 300.00       | 0.00       | 0.00                 | 300.00        | 0.00          | 0.00         | 0.00             | 0.00              | 0.00               | 0.00              | 0.00         |
| 400.00       | 0.00       | 0.00                 | 400.00        | 0.00          | 0.00         | 0.00             | 0.00              | 0.00               | 0.00              | 0.00         |
| 500.00       | 0.00       | 0.00                 | 500.00        | 0.00          | 0.00         | 0.00             | 0.00              | 0.00               | 0.00              | 0.00         |
| 600.00       | 0.00       | 0.00                 | 600.00        | 0.00          | 0.00         | 0.00             | 0.00              | 0.00               | 0.00              | 0.00         |
| 685.00       | 0.00       | 0.00                 | 685.00        | 0.00          | 0.00         | 0.00             | 0.00              | 0.00               | 0.00              | 0.00         |
| 700.00       | 1.50       | 233.90               | 700.00        | -0.12         | -0.16        | 0.12             | 10.00             | 10.00              | 0.00              | 233.90       |
| 750.00       | 6.50       | 233.90               | 749.86        | -2.17         | -2.98        | 2.19             | 10.00             | 10.00              | 0.00              | 0.00         |
| 759.99       | 7.50       | 233.90               | 759.78        | -2.89         | -3.96        | 2.91             | 10.00             | 10.00              | 0.00              | 0.00         |
| 800.00       | 7.50       | 233.90               | 799.44        | -5.96         | -8.18        | 6.01             | 0.00              | 0.00               | 0.00              | 0.00         |
| 900.00       | 7.50       | 233.90               | 898.59        | -13.65        | -18.72       | 13.75            | 0.00              | 0.00               | 0.00              | 0.00         |
| 1,000.00     | 7.50       | 233.90               | 997.73        | -21.34        | -29.27       | 21.50            | 0.00              | 0.00               | 0.00              | 0.00         |
| 1,100.00     | 7.50       | 233.90               | 1,096.88      | -29.03        | -39.82       | 29.25            | 0.00              | 0.00               | 0.00              | 0.00         |
| 1,200.00     | 7.50       | 233.90               | 1,196.02      | -36.72        | -50.36       | 36.99            | 0.00              | 0.00               | 0.00              | 0.00         |
| 1,300.00     | 7.50       | 233.90               | 1,295.17      | -44.41        | -60.91       | 44.74            | 0.00              | 0.00               | 0.00              | 0.00         |
| 1,400.00     | 7.50       | 233.90               | 1,394.31      | -52.10        | -71.45       | 52.49            | 0.00              | 0.00               | 0.00              | 0.00         |
| 1,500.00     | 7.50       | 233.90               | 1,493.46      | -59.79        | -82.00       | 60.23            | 0.00              | 0.00               | 0.00              | 0.00         |
| 1,600.00     | 7.50       | 233.90               | 1,592.60      | -67.48        | -92.54       | 67.98            | 0.00              | 0.00               | 0.00              | 0.00         |
| 1,700.00     | 7.50       | 233.90               | 1,691.75      | -75.17        | -103.09      | 75.73            | 0.00              | 0.00               | 0.00              | 0.00         |
| 1,800.00     | 7.50       | 233.90               | 1,790.89      | -82.86        | -113.64      | 83.47            | 0.00              | 0.00               | 0.00              | 0.00         |
| 1,900.00     | 7.50       | 233.90               | 1,890.03      | -90.55        | -124.18      | 91.22            | 0.00              | 0.00               | 0.00              | 0.00         |
| 2,000.00     | 7.50       | 233.90               | 1,989.18      | -98.24        | -134.73      | 98.96            | 0.00              | 0.00               | 0.00              | 0.00         |
| 2,086.90     | 7.50       | 233.90               | 2,075.34      | -104.92       | -143.89      | 105.70           | 0.00              | 0.00               | 0.00              | 0.00         |
| 2,100.00     | 8.34       | 226.59               | 2,088.31      | -106.08       | -145.27      | 106.86           | 10.00             | 6.41               | -55.84            | -53.88       |
| 2,150.00     | 12.32      | 209.31               | 2,137.50      | -113.22       | -150.52      | 114.04           | 10.00             | 7.96               | -34.56            | -46.63       |



# Wellbenders Standard Plan With Toolface



Company: Percussion Petroleum, LLC  
Project: Eddy County, NM  
Site: Lakewood Federal  
Well: 08H  
Wellbore: OH  
Design: Plan #4

Local Co-ordinate Reference: Well 08H  
TVD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
MD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Database: WBDS\_SQL\_2

## Planned Survey

| MD<br>(usft) | Inc<br>(°) | Azi (azimuth)<br>(°) | TVD<br>(usft) | N/S<br>(usft) | E/W<br>(usft) | V. Sec<br>(usft) | DLeg<br>(°/100ft) | Build<br>(°/100ft) | Turn<br>(°/100ft) | TFace<br>(°) |
|--------------|------------|----------------------|---------------|---------------|---------------|------------------|-------------------|--------------------|-------------------|--------------|
| 2,200.00     | 16.84      | 200.76               | 2,185.89      | -124.65       | -155.70       | 125.49           | 10.00             | 9.05               | -17.10            | -29.62       |
| 2,250.00     | 21.57      | 195.81               | 2,233.09      | -140.28       | -160.78       | 141.15           | 10.00             | 9.46               | -9.89             | -21.34       |
| 2,300.00     | 26.40      | 192.59               | 2,278.76      | -159.99       | -165.71       | 160.88           | 10.00             | 9.65               | -6.44             | -16.66       |
| 2,350.00     | 31.28      | 190.31               | 2,322.55      | -183.62       | -170.46       | 184.54           | 10.00             | 9.76               | -4.56             | -13.71       |
| 2,400.00     | 36.19      | 188.59               | 2,364.12      | -211.01       | -174.99       | 211.95           | 10.00             | 9.82               | -3.43             | -11.71       |
| 2,450.00     | 41.12      | 187.24               | 2,403.15      | -241.93       | -179.27       | 242.90           | 10.00             | 9.86               | -2.71             | -10.29       |
| 2,500.00     | 46.06      | 186.13               | 2,439.36      | -276.16       | -183.26       | 277.15           | 10.00             | 9.88               | -2.22             | -9.23        |
| 2,550.00     | 51.01      | 185.18               | 2,472.46      | -313.43       | -186.94       | 314.44           | 10.00             | 9.90               | -1.88             | -8.42        |
| 2,600.00     | 55.96      | 184.37               | 2,502.20      | -353.47       | -190.28       | 354.49           | 10.00             | 9.91               | -1.63             | -7.80        |
| 2,650.00     | 60.93      | 183.64               | 2,528.36      | -395.96       | -193.24       | 397.00           | 10.00             | 9.92               | -1.45             | -7.31        |
| 2,700.00     | 65.89      | 182.98               | 2,550.73      | -440.58       | -195.82       | 441.63           | 10.00             | 9.93               | -1.32             | -6.93        |
| 2,750.00     | 70.86      | 182.37               | 2,569.15      | -487.00       | -197.98       | 488.06           | 10.00             | 9.94               | -1.22             | -6.63        |
| 2,800.00     | 75.83      | 181.79               | 2,583.48      | -534.85       | -199.72       | 535.92           | 10.00             | 9.94               | -1.15             | -6.41        |
| 2,850.00     | 80.80      | 181.24               | 2,593.60      | -583.78       | -201.02       | 584.86           | 10.00             | 9.94               | -1.10             | -6.24        |
| 2,900.00     | 85.77      | 180.71               | 2,599.45      | -633.42       | -201.86       | 634.50           | 10.00             | 9.94               | -1.07             | -6.13        |
| 2,938.12     | 89.56      | 180.31               | 2,601.00      | -671.50       | -202.20       | 672.58           | 10.00             | 9.94               | -1.06             | -6.07        |
| 3,000.00     | 89.56      | 180.31               | 2,601.47      | -733.37       | -202.53       | 734.46           | 0.00              | 0.00               | 0.00              | 0.00         |
| 3,100.00     | 89.56      | 180.31               | 2,602.24      | -833.37       | -203.07       | 834.45           | 0.00              | 0.00               | 0.00              | 0.00         |
| 3,200.00     | 89.56      | 180.31               | 2,603.00      | -933.36       | -203.60       | 934.45           | 0.00              | 0.00               | 0.00              | 0.00         |
| 3,300.00     | 89.56      | 180.31               | 2,603.76      | -1,033.36     | -204.14       | 1,034.45         | 0.00              | 0.00               | 0.00              | 0.00         |
| 3,400.00     | 89.56      | 180.31               | 2,604.53      | -1,133.36     | -204.68       | 1,134.45         | 0.00              | 0.00               | 0.00              | 0.00         |
| 3,500.00     | 89.56      | 180.31               | 2,605.29      | -1,233.35     | -205.21       | 1,234.44         | 0.00              | 0.00               | 0.00              | 0.00         |
| 3,600.00     | 89.56      | 180.31               | 2,606.05      | -1,333.35     | -205.75       | 1,334.44         | 0.00              | 0.00               | 0.00              | 0.00         |
| 3,700.00     | 89.56      | 180.31               | 2,606.82      | -1,433.34     | -206.29       | 1,434.44         | 0.00              | 0.00               | 0.00              | 0.00         |
| 3,800.00     | 89.56      | 180.31               | 2,607.58      | -1,533.34     | -206.82       | 1,534.43         | 0.00              | 0.00               | 0.00              | 0.00         |
| 3,900.00     | 89.56      | 180.31               | 2,608.34      | -1,633.33     | -207.36       | 1,634.43         | 0.00              | 0.00               | 0.00              | 0.00         |
| 4,000.00     | 89.56      | 180.31               | 2,609.11      | -1,733.33     | -207.90       | 1,734.43         | 0.00              | 0.00               | 0.00              | 0.00         |



## Wellbenders Standard Plan With Toolface



Company: Percussion Petroleum, LLC  
Project: Eddy County, NM  
Site: Lakewood Federal  
Well: 08H  
Wellbore: OH  
Design: Plan #4

Local Co-ordinate Reference: Well 08H  
TVD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
MD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Database: WBDS\_SQL\_2

### Planned Survey

| MD<br>(usft) | Inc<br>(°) | Azi (azimuth)<br>(°) | TVD<br>(usft) | N/S<br>(usft) | E/W<br>(usft) | V. Sec<br>(usft) | DLeg<br>(°/100ft) | Build<br>(°/100ft) | Turn<br>(°/100ft) | TFace<br>(°) |
|--------------|------------|----------------------|---------------|---------------|---------------|------------------|-------------------|--------------------|-------------------|--------------|
| 4,100.00     | 89.56      | 180.31               | 2,609.87      | -1,833.32     | -208.43       | 1,834.43         | 0.00              | 0.00               | 0.00              | 0.00         |
| 4,200.00     | 89.56      | 180.31               | 2,610.63      | -1,933.32     | -208.97       | 1,934.42         | 0.00              | 0.00               | 0.00              | 0.00         |
| 4,300.00     | 89.56      | 180.31               | 2,611.40      | -2,033.32     | -209.50       | 2,034.42         | 0.00              | 0.00               | 0.00              | 0.00         |
| 4,400.00     | 89.56      | 180.31               | 2,612.16      | -2,133.31     | -210.04       | 2,134.42         | 0.00              | 0.00               | 0.00              | 0.00         |
| 4,500.00     | 89.56      | 180.31               | 2,612.92      | -2,233.31     | -210.58       | 2,234.41         | 0.00              | 0.00               | 0.00              | 0.00         |
| 4,600.00     | 89.56      | 180.31               | 2,613.69      | -2,333.30     | -211.11       | 2,334.41         | 0.00              | 0.00               | 0.00              | 0.00         |
| 4,700.00     | 89.56      | 180.31               | 2,614.45      | -2,433.30     | -211.65       | 2,434.41         | 0.00              | 0.00               | 0.00              | 0.00         |
| 4,800.00     | 89.56      | 180.31               | 2,615.21      | -2,533.29     | -212.19       | 2,534.41         | 0.00              | 0.00               | 0.00              | 0.00         |
| 4,900.00     | 89.56      | 180.31               | 2,615.98      | -2,633.29     | -212.72       | 2,634.40         | 0.00              | 0.00               | 0.00              | 0.00         |
| 5,000.00     | 89.56      | 180.31               | 2,616.74      | -2,733.29     | -213.26       | 2,734.40         | 0.00              | 0.00               | 0.00              | 0.00         |
| 5,100.00     | 89.56      | 180.31               | 2,617.51      | -2,833.28     | -213.79       | 2,834.40         | 0.00              | 0.00               | 0.00              | 0.00         |
| 5,200.00     | 89.56      | 180.31               | 2,618.27      | -2,933.28     | -214.33       | 2,934.39         | 0.00              | 0.00               | 0.00              | 0.00         |
| 5,300.00     | 89.56      | 180.31               | 2,619.03      | -3,033.27     | -214.87       | 3,034.39         | 0.00              | 0.00               | 0.00              | 0.00         |
| 5,400.00     | 89.56      | 180.31               | 2,619.80      | -3,133.27     | -215.40       | 3,134.39         | 0.00              | 0.00               | 0.00              | 0.00         |
| 5,500.00     | 89.56      | 180.31               | 2,620.56      | -3,233.26     | -215.94       | 3,234.39         | 0.00              | 0.00               | 0.00              | 0.00         |
| 5,600.00     | 89.56      | 180.31               | 2,621.32      | -3,333.26     | -216.48       | 3,334.38         | 0.00              | 0.00               | 0.00              | 0.00         |
| 5,700.00     | 89.56      | 180.31               | 2,622.09      | -3,433.26     | -217.01       | 3,434.38         | 0.00              | 0.00               | 0.00              | 0.00         |
| 5,800.00     | 89.56      | 180.31               | 2,622.85      | -3,533.25     | -217.55       | 3,534.38         | 0.00              | 0.00               | 0.00              | 0.00         |
| 5,900.00     | 89.56      | 180.31               | 2,623.61      | -3,633.25     | -218.09       | 3,634.37         | 0.00              | 0.00               | 0.00              | 0.00         |
| 6,000.00     | 89.56      | 180.31               | 2,624.38      | -3,733.24     | -218.62       | 3,734.37         | 0.00              | 0.00               | 0.00              | 0.00         |
| 6,100.00     | 89.56      | 180.31               | 2,625.14      | -3,833.24     | -219.16       | 3,834.37         | 0.00              | 0.00               | 0.00              | 0.00         |
| 6,200.00     | 89.56      | 180.31               | 2,625.90      | -3,933.23     | -219.69       | 3,934.36         | 0.00              | 0.00               | 0.00              | 0.00         |
| 6,300.00     | 89.56      | 180.31               | 2,626.67      | -4,033.23     | -220.23       | 4,034.36         | 0.00              | 0.00               | 0.00              | 0.00         |
| 6,400.00     | 89.56      | 180.31               | 2,627.43      | -4,133.22     | -220.77       | 4,134.36         | 0.00              | 0.00               | 0.00              | 0.00         |
| 6,500.00     | 89.56      | 180.31               | 2,628.19      | -4,233.22     | -221.30       | 4,234.36         | 0.00              | 0.00               | 0.00              | 0.00         |
| 6,600.00     | 89.56      | 180.31               | 2,628.96      | -4,333.22     | -221.84       | 4,334.35         | 0.00              | 0.00               | 0.00              | 0.00         |
| 6,700.00     | 89.56      | 180.31               | 2,629.72      | -4,433.21     | -222.38       | 4,434.35         | 0.00              | 0.00               | 0.00              | 0.00         |



# Wellbenders Standard Plan With Toolface



Company: Percussion Petroleum, LLC  
Project: Eddy County, NM  
Site: Lakewood Federal  
Well: 08H  
Wellbore: OH  
Design: Plan #4

Local Co-ordinate Reference: Well 08H  
TVD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
MD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Database: WBDS\_SQL\_2

## Planned Survey

| MD<br>(usft) | Inc<br>(°) | Azi (azimuth)<br>(°) | TVD<br>(usft) | N/S<br>(usft) | E/W<br>(usft) | V. Sec<br>(usft) | DLeg<br>(°/100ft) | Build<br>(°/100ft) | Turn<br>(°/100ft) | TFace<br>(°) |
|--------------|------------|----------------------|---------------|---------------|---------------|------------------|-------------------|--------------------|-------------------|--------------|
| 6,800.00     | 89.56      | 180.31               | 2,630.48      | -4,533.21     | -222.91       | 4,534.35         | 0.00              | 0.00               | 0.00              | 0.00         |
| 6,900.00     | 89.56      | 180.31               | 2,631.25      | -4,633.20     | -223.45       | 4,634.34         | 0.00              | 0.00               | 0.00              | 0.00         |
| 7,000.00     | 89.56      | 180.31               | 2,632.01      | -4,733.20     | -223.99       | 4,734.34         | 0.00              | 0.00               | 0.00              | 0.00         |
| 7,100.00     | 89.56      | 180.31               | 2,632.77      | -4,833.19     | -224.52       | 4,834.34         | 0.00              | 0.00               | 0.00              | 0.00         |
| 7,200.00     | 89.56      | 180.31               | 2,633.54      | -4,933.19     | -225.06       | 4,934.34         | 0.00              | 0.00               | 0.00              | 0.00         |
| 7,300.00     | 89.56      | 180.31               | 2,634.30      | -5,033.19     | -225.59       | 5,034.33         | 0.00              | 0.00               | 0.00              | 0.00         |
| 7,400.00     | 89.56      | 180.31               | 2,635.07      | -5,133.18     | -226.13       | 5,134.33         | 0.00              | 0.00               | 0.00              | 0.00         |
| 7,500.00     | 89.56      | 180.31               | 2,635.83      | -5,233.18     | -226.67       | 5,234.33         | 0.00              | 0.00               | 0.00              | 0.00         |
| 7,600.00     | 89.56      | 180.31               | 2,636.59      | -5,333.17     | -227.20       | 5,334.32         | 0.00              | 0.00               | 0.00              | 0.00         |
| 7,700.00     | 89.56      | 180.31               | 2,637.36      | -5,433.17     | -227.74       | 5,434.32         | 0.00              | 0.00               | 0.00              | 0.00         |
| 7,800.00     | 89.56      | 180.31               | 2,638.12      | -5,533.16     | -228.28       | 5,534.32         | 0.00              | 0.00               | 0.00              | 0.00         |
| 7,900.00     | 89.56      | 180.31               | 2,638.88      | -5,633.16     | -228.81       | 5,634.32         | 0.00              | 0.00               | 0.00              | 0.00         |
| 8,000.00     | 89.56      | 180.31               | 2,639.65      | -5,733.16     | -229.35       | 5,734.31         | 0.00              | 0.00               | 0.00              | 0.00         |
| 8,100.00     | 89.56      | 180.31               | 2,640.41      | -5,833.15     | -229.89       | 5,834.31         | 0.00              | 0.00               | 0.00              | 0.00         |
| 8,177.35     | 89.56      | 180.31               | 2,641.00      | -5,910.50     | -230.30       | 5,911.66         | 0.00              | 0.00               | 0.00              | 0.00         |

Checked By: \_\_\_\_\_ Approved By: \_\_\_\_\_ Date: \_\_\_\_\_



**PERCUSSION**  
PETROLEUM  
LLC

## **Percussion Petroleum, LLC**

**Eddy County, NM  
Lakewood Federal  
08H**

**OH  
Plan #4**

## **Anticollision Report**

**31 May, 2018**



|                    |                           |                              |                                      |
|--------------------|---------------------------|------------------------------|--------------------------------------|
| Company:           | Percussion Petroleum, LLC | Local Co-ordinate Reference: | Well 08H                             |
| Project:           | Eddy County, NM           | TVD Reference:               | RKB=17' @ 3500.00usft (Silver Oak 1) |
| Reference Site:    | Lakewood Federal          | MD Reference:                | RKB=17' @ 3500.00usft (Silver Oak 1) |
| Site Error:        | 0.00 usft                 | North Reference:             | Grid                                 |
| Reference Well:    | 08H                       | Survey Calculation Method:   | Minimum Curvature                    |
| Well Error:        | 0.00 usft                 | Output errors are at         | 2.00 sigma                           |
| Reference Wellbore | OH                        | Database:                    | WBDS_SQL_2                           |
| Reference Design:  | Plan #4                   | Offset TVD Reference:        | Reference Datum                      |

|                              |   |
|------------------------------|---|
| Reference                    | Plan #4   |
| Filter type:                 | NO GLOBAL FILTER: Using user defined selection & filtering criteria |
| Interpolation Method:        | MD + Stations Interval 100.00usft                                   |
| Depth Range:                 | Unlimited   |
| Results Limited by:          | Maximum center-center distance of 9,999.00 us                       |
| Warning Levels Evaluated at: | 2.00 Sigma  |
| Error Model:                 | ISCWSA  |
| Scan Method:                 | Closest Approach 3D   |
| Error Surface:               | Pedal Curve   |
| Casing Method:               | Not applied   |

|                     |           |                   |           |                        |
|---------------------|-----------|-------------------|-----------|------------------------|
| Survey Tool Program |           | Date 5/31/2018    |           |                        |
| From (usft)         | To (usft) | Survey (Wellbore) | Tool Name | Description            |
| 0.00                | 8,177.06  | Plan #4 (OH)      | MWD+IGRF  | OWSG MWD + IGRF or WMM |

| Site Name                       | Reference Measured Depth (usft) | Offset Measured Depth (usft) | Distance Between Centres (usft) | Distance Between Ellipses (usft) | Separation Factor | Warning |
|---------------------------------|---------------------------------|------------------------------|---------------------------------|----------------------------------|-------------------|---------|
| Offset Well - Wellbore - Design |                                 |                              |                                 |                                  |                   |         |
| Lakewood Federal                |                                 |                              |                                 |                                  |                   |         |
| 07H - OH - Plan #3              | 689.44                          | 689.61                       | 19.15                           | 14.66                            | 4.271             | CC, ES  |
| 07H - OH - Plan #3              | 8,177.35                        | 8,502.88                     | 381.70                          | 231.11                           | 2.535             | SF      |
| 09H - OH - Plan #2              | 200.00                          | 200.00                       | 20.00                           | 18.99                            | 19.717            | CC, ES  |
| 09H - OH - Plan #2              | 2,150.00                        | 2,143.92                     | 62.32                           | 46.29                            | 3.888             | SF      |

| Offset Design Lakewood Federal - 07H - OH - Plan #3 |                       |                       |                       |                  |               |                       |                                     |                   |                        |                         |                           | Offset Site Error: | 0.00 usft |
|---|-----------------------|-----------------------|-----------------------|------------------|---------------|-----------------------|-------------------------------------|-------------------|------------------------|-------------------------|---------------------------|--------------------|-----------|
| Survey Program: 0-MWD+IGRF                          |                       |                       |                       |                  |               |                       |                                     |                   |                        |                         |                           | Offset Well Error: | 0.00 usft |
| Reference   | Offset                | Semi Major Axis       |                       | Distance         |               | Minimum Separation    |                                     | Separation Factor |                        | Warning                 |                           |                    |           |
| Measured Depth (usft)                               | Vertical Depth (usft) | Measured Depth (usft) | Vertical Depth (usft) | Reference (usft) | Offset (usft) | Highside Toolface (°) | Offset Wellbore Centre +N/-S (usft) | +E/-W (usft)      | Between Centres (usft) | Between Ellipses (usft) | Minimum Separation (usft) | Separation Factor  | Warning   |
| 0.00  | 0.00                  | 0.00                  | 0.00                  | 0.00             | 0.00          | 68.94                 | 7.20                                | 18.70             | 20.04                  |                         |                           |                    |           |
| 100.00  | 100.00                | 100.00                | 100.00                | 0.15             | 0.15          | 68.94                 | 7.20                                | 18.70             | 20.04                  | 19.74                   | 0.30                      | 67.348             |           |
| 200.00  | 200.00                | 200.00                | 200.00                | 0.51             | 0.51          | 68.94                 | 7.20                                | 18.70             | 20.04                  | 19.02                   | 1.01                      | 19.752             |           |
| 300.00  | 300.00                | 300.00                | 300.00                | 0.87             | 0.87          | 68.94                 | 7.20                                | 18.70             | 20.04                  | 18.31                   | 1.73                      | 11.573             |           |
| 400.00  | 400.00                | 400.00                | 400.00                | 1.22             | 1.22          | 68.94                 | 7.20                                | 18.70             | 20.04                  | 17.59                   | 2.45                      | 8.184              |           |
| 500.00  | 500.00                | 500.00                | 500.00                | 1.58             | 1.58          | 68.94                 | 7.20                                | 18.70             | 20.04                  | 16.87                   | 3.17                      | 6.331              |           |
| 600.00  | 600.00                | 600.12                | 600.11                | 1.94             | 1.92          | 71.31                 | 6.33                                | 18.70             | 19.74                  | 15.87                   | 3.87                      | 5.107              |           |
| 685.00  | 685.00                | 685.17                | 685.14                | 2.25             | 2.21          | 77.32                 | 4.21                                | 18.70             | 19.16                  | 14.71                   | 4.45                      | 4.303              |           |
| 689.44  | 689.44                | 689.61                | 689.57                | 2.26             | 2.22          | -156.18               | 4.06                                | 18.70             | 19.15                  | 14.66                   | 4.48                      | 4.271              | CC, ES    |
| 700.00  | 700.00                | 700.17                | 700.13                | 2.30             | 2.26          | -155.35               | 3.70                                | 18.70             | 19.24                  | 14.68                   | 4.55                      | 4.223              |           |
| 750.00  | 749.86                | 750.08                | 750.01                | 2.47             | 2.43          | -154.57               | 1.96                                | 18.69             | 22.06                  | 17.16                   | 4.90                      | 4.505              |           |
| 759.99  | 759.78                | 760.01                | 759.94                | 2.52             | 2.46          | -154.98               | 1.62                                | 18.69             | 23.10                  | 18.12                   | 4.97                      | 4.644              |           |
| 800.00  | 799.44                | 800.24                | 799.66                | 2.65             | 2.60          | -156.72               | 0.23                                | 18.69             | 27.57                  | 22.33                   | 5.25                      | 5.257              |           |
| 900.00  | 898.59                | 900.88                | 898.95                | 3.00             | 2.95          | -159.32               | -3.24                               | 18.69             | 38.83                  | 32.90                   | 5.93                      | 6.545              |           |
| 1,000.00  | 997.73                | 1,001.53              | 998.25                | 3.38             | 3.30          | -160.75               | -6.71                               | 18.68             | 50.14                  | 43.50                   | 6.63                      | 7.559              |           |
| 1,100.00  | 1,096.88              | 1,102.18              | 1,097.54              | 3.77             | 3.66          | -161.65               | -10.17                              | 18.68             | 61.46                  | 54.12                   | 7.34                      | 8.373              |           |
| 1,200.00  | 1,196.02              | 1,202.82              | 1,196.83              | 4.18             | 4.02          | -162.27               | -13.64                              | 18.67             | 72.79                  | 64.74                   | 8.05                      | 9.039              |           |
| 1,300.00  | 1,295.17              | 1,303.47              | 1,296.12              | 4.58             | 4.38          | -162.73               | -17.11                              | 18.67             | 84.13                  | 75.36                   | 8.77                      | 9.592              |           |
| 1,400.00  | 1,394.31              | 1,404.12              | 1,395.42              | 5.00             | 4.74          | -163.07               | -20.58                              | 18.66             | 95.48                  | 85.98                   | 9.49                      | 10.058             |           |
| 1,500.00  | 1,493.46              | 1,504.77              | 1,494.71              | 5.41             | 5.10          | -163.34               | -24.04                              | 18.66             | 106.82                 | 96.61                   | 10.22                     | 10.456             |           |
| 1,600.00  | 1,592.60              | 1,605.41              | 1,594.00              | 5.83             | 5.46          | -163.56               | -27.51                              | 18.65             | 118.17                 | 107.23                  | 10.94                     | 10.800             |           |
| 1,700.00  | 1,691.75              | 1,706.06              | 1,693.29              | 6.25             | 5.83          | -163.75               | -30.98                              | 18.65             | 129.52                 | 117.85                  | 11.67                     | 11.099             |           |
| 1,800.00  | 1,790.89              | 1,806.71              | 1,792.59              | 6.67             | 6.19          | -163.90               | -34.45                              | 18.64             | 140.87                 | 128.47                  | 12.40                     | 11.361             |           |

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

|                           |                           |                                     |                                      |
|---------------------------|---------------------------|-------------------------------------|--------------------------------------|
| <b>Company:</b>           | Percussion Petroleum, LLC | <b>Local Co-ordinate Reference:</b> | Well 08H                             |
| <b>Project:</b>           | Eddy County, NM           | <b>TVD Reference:</b>               | RKB=17' @ 3500.00usft (Silver Oak 1) |
| <b>Reference Site:</b>    | Lakewood Federal          | <b>MD Reference:</b>                | RKB=17' @ 3500.00usft (Silver Oak 1) |
| <b>Site Error:</b>        | 0.00 usft                 | <b>North Reference:</b>             | Grid                                 |
| <b>Reference Well:</b>    | 08H                       | <b>Survey Calculation Method:</b>   | Minimum Curvature                    |
| <b>Well Error:</b>        | 0.00 usft                 | <b>Output errors are at</b>         | 2.00 sigma                           |
| <b>Reference Wellbore</b> | OH                        | <b>Database:</b>                    | WBDS_SQL_2                           |
| <b>Reference Design:</b>  | Plan #4                   | <b>Offset TVD Reference:</b>        | Reference Datum                      |

| Offset Design Lakewood Federal - 07H - OH - Plan#3 |                             |                             |                             |           |        |                             |   |                 |                              |                               |                                 |                      | Offset Site Error: 0.00 usft |
|--|-----------------------------|-----------------------------|-----------------------------|-----------|--------|-----------------------------|---|-----------------|------------------------------|-------------------------------|---------------------------------|----------------------|------------------------------|
| Survey Program: 0-MWD+IGRF                         |                             |                             |                             |           |        |                             |   |                 |                              |                               |                                 |                      | Offset Well Error: 0.00 usft |
| Measured<br>Depth<br>(usft)                        | Vertical<br>Depth<br>(usft) | Measured<br>Depth<br>(usft) | Vertical<br>Depth<br>(usft) | Reference | Offset | Highside<br>Toolface<br>(°) | Offset Wellbore Centre<br>+N/-S<br>(usft) | +E/-W<br>(usft) | Between<br>Centres<br>(usft) | Between<br>Ellipses<br>(usft) | Minimum<br>Separation<br>(usft) | Separation<br>Factor | Warning                      |
| 1,900.00   | 1,890.03                    | 1,907.35                    | 1,891.88                    | 7.10      | 6.55   | -164.03                     | -37.91                                    | 18.64           | 152.22                       | 139.09                        | 13.13                           | 11.594               |                              |
| 2,000.00   | 1,989.18                    | 2,008.00                    | 1,991.17                    | 7.52      | 6.92   | -164.14                     | -41.38                                    | 18.63           | 163.57                       | 149.71                        | 13.86                           | 11.801               |                              |
| 2,086.90   | 2,075.34                    | 2,078.34                    | 2,077.46                    | 7.89      | 7.17   | -164.23                     | -44.39                                    | 18.63           | 173.44                       | 159.00                        | 14.44                           | 12.015               |                              |
| 2,100.00   | 2,088.31                    | 2,108.65                    | 2,090.46                    | 7.95      | 7.28   | -156.89                     | -44.85                                    | 18.63           | 174.98                       | 160.38                        | 14.59                           | 11.990               |                              |
| 2,150.00   | 2,137.50                    | 2,140.76                    | 2,139.84                    | 8.18      | 7.40   | -140.26                     | -46.57                                    | 18.62           | 181.82                       | 166.92                        | 14.89                           | 12.207               |                              |
| 2,200.00   | 2,185.89                    | 2,189.51                    | 2,188.56                    | 8.43      | 7.58   | -133.34                     | -48.27                                    | 18.62           | 190.34                       | 175.09                        | 15.26                           | 12.476               |                              |
| 2,250.00   | 2,233.09                    | 2,237.23                    | 2,236.26                    | 8.70      | 7.75   | -130.74                     | -49.94                                    | 18.62           | 200.89                       | 185.27                        | 15.61                           | 12.867               |                              |
| 2,300.00   | 2,278.76                    | 2,283.56                    | 2,282.56                    | 9.00      | 7.92   | -130.29                     | -51.56                                    | 18.62           | 213.89                       | 197.93                        | 15.96                           | 13.400               |                              |
| 2,350.00   | 2,322.55                    | 2,328.15                    | 2,327.12                    | 9.32      | 8.08   | -130.93                     | -53.11                                    | 18.62           | 229.79                       | 213.49                        | 16.30                           | 14.096               |                              |
| 2,400.00   | 2,364.12                    | 2,381.93                    | 2,380.78                    | 9.68      | 8.28   | -132.91                     | -56.48                                    | 18.61           | 248.27                       | 231.58                        | 16.69                           | 14.878               |                              |
| 2,450.00   | 2,403.15                    | 2,443.47                    | 2,441.49                    | 10.07     | 8.53   | -135.17                     | -66.34                                    | 18.60           | 267.31                       | 250.25                        | 17.06                           | 15.667               |                              |
| 2,500.00   | 2,439.36                    | 2,509.74                    | 2,505.29                    | 10.50     | 8.81   | -137.24                     | -84.16                                    | 18.57           | 286.26                       | 268.89                        | 17.38                           | 16.475               |                              |
| 2,550.00   | 2,472.46                    | 2,581.42                    | 2,571.45                    | 10.98     | 9.17   | -139.09                     | -111.58                                   | 18.53           | 304.57                       | 286.97                        | 17.60                           | 17.303               |                              |
| 2,600.00   | 2,502.20                    | 2,659.07                    | 2,638.68                    | 11.50     | 9.61   | -140.69                     | -150.35                                   | 18.47           | 321.65                       | 303.92                        | 17.73                           | 18.138               |                              |
| 2,650.00   | 2,528.36                    | 2,743.11                    | 2,704.79                    | 12.07     | 10.19  | -142.02                     | -202.11                                   | 18.40           | 336.89                       | 319.10                        | 17.79                           | 18.935               |                              |
| 2,700.00   | 2,550.73                    | 2,833.54                    | 2,766.64                    | 12.68     | 10.95  | -143.02                     | -267.94                                   | 18.30           | 349.67                       | 331.82                        | 17.84                           | 19.596               |                              |
| 2,750.00   | 2,569.15                    | 2,929.74                    | 2,820.22                    | 13.33     | 11.93  | -143.66                     | -347.71                                   | 18.18           | 359.39                       | 341.38                        | 18.01                           | 19.953               |                              |
| 2,800.00   | 2,583.48                    | 3,030.36                    | 2,861.16                    | 14.01     | 13.14  | -143.89                     | -439.48                                   | 18.05           | 365.55                       | 347.08                        | 18.47                           | 19.792               |                              |
| 2,850.00   | 2,593.60                    | 3,133.31                    | 2,885.80                    | 14.73     | 14.53  | -143.67                     | -539.29                                   | 17.90           | 367.81                       | 348.43                        | 19.38                           | 18.982               |                              |
| 2,900.00   | 2,599.45                    | 3,224.72                    | 2,892.51                    | 15.46     | 15.86  | -143.12                     | -630.36                                   | 17.76           | 366.24                       | 345.54                        | 20.70                           | 17.692               |                              |
| 2,933.86   | 2,600.95                    | 3,258.55                    | 2,892.90                    | 15.98     | 16.37  | -143.02                     | -664.20                                   | 17.71           | 365.51                       | 344.07                        | 21.44                           | 17.049               |                              |
| 2,938.12   | 2,601.00                    | 3,262.82                    | 2,892.95                    | 16.04     | 16.43  | -143.02                     | -668.46                                   | 17.71           | 365.52                       | 343.99                        | 21.53                           | 16.980               |                              |
| 3,000.00   | 2,601.47                    | 3,325.57                    | 2,893.67                    | 16.99     | 17.40  | -143.03                     | -731.21                                   | 17.41           | 365.73                       | 342.90                        | 22.83                           | 16.021               |                              |
| 3,100.00   | 2,602.24                    | 3,425.57                    | 2,894.81                    | 18.60     | 19.01  | -143.07                     | -831.20                                   | 16.87           | 366.03                       | 341.04                        | 24.99                           | 14.645               |                              |
| 3,200.00   | 2,603.00                    | 3,525.57                    | 2,895.96                    | 20.25     | 20.66  | -143.11                     | -931.19                                   | 16.33           | 366.34                       | 339.11                        | 27.23                           | 13.452               |                              |
| 3,300.00   | 2,603.76                    | 3,625.56                    | 2,897.11                    | 21.95     | 22.36  | -143.14                     | -1,031.18                                 | 15.80           | 366.64                       | 337.11                        | 29.53                           | 12.416               |                              |
| 3,400.00   | 2,604.53                    | 3,725.56                    | 2,898.25                    | 23.68     | 24.09  | -143.18                     | -1,131.17                                 | 15.26           | 366.95                       | 335.08                        | 31.87                           | 11.513               |                              |
| 3,500.00   | 2,605.29                    | 3,825.56                    | 2,899.40                    | 25.44     | 25.84  | -143.21                     | -1,231.16                                 | 14.72           | 367.25                       | 333.01                        | 34.25                           | 10.723               |                              |
| 3,600.00   | 2,606.05                    | 3,925.56                    | 2,900.54                    | 27.22     | 27.62  | -143.25                     | -1,331.15                                 | 14.19           | 367.56                       | 330.91                        | 36.65                           | 10.028               |                              |
| 3,700.00   | 2,606.82                    | 4,025.56                    | 2,901.69                    | 29.01     | 29.42  | -143.29                     | -1,431.15                                 | 13.65           | 367.87                       | 328.79                        | 39.08                           | 9.414                |                              |
| 3,800.00   | 2,607.58                    | 4,125.56                    | 2,902.83                    | 30.82     | 31.22  | -143.32                     | -1,531.14                                 | 13.11           | 368.17                       | 326.65                        | 41.52                           | 8.867                |                              |
| 3,900.00   | 2,608.34                    | 4,225.56                    | 2,903.98                    | 32.65     | 33.04  | -143.36                     | -1,631.13                                 | 12.58           | 368.48                       | 324.50                        | 43.98                           | 8.379                |                              |
| 4,000.00   | 2,609.11                    | 4,325.56                    | 2,905.12                    | 34.48     | 34.88  | -143.39                     | -1,731.12                                 | 12.04           | 368.78                       | 322.34                        | 46.44                           | 7.940                |                              |
| 4,100.00   | 2,609.87                    | 4,425.56                    | 2,906.27                    | 36.32     | 36.71  | -143.43                     | -1,831.11                                 | 11.50           | 369.09                       | 320.17                        | 48.92                           | 7.545                |                              |
| 4,200.00   | 2,610.63                    | 4,525.56                    | 2,907.41                    | 38.17     | 38.56  | -143.46                     | -1,931.10                                 | 10.97           | 369.40                       | 317.99                        | 51.41                           | 7.186                |                              |
| 4,300.00   | 2,611.40                    | 4,625.56                    | 2,908.56                    | 40.02     | 40.41  | -143.50                     | -2,031.09                                 | 10.43           | 369.70                       | 315.81                        | 53.90                           | 6.860                |                              |
| 4,400.00   | 2,612.16                    | 4,725.56                    | 2,909.70                    | 41.88     | 42.27  | -143.53                     | -2,131.08                                 | 9.89            | 370.01                       | 313.62                        | 56.39                           | 6.561                |                              |
| 4,500.00   | 2,612.92                    | 4,825.56                    | 2,910.85                    | 43.74     | 44.13  | -143.57                     | -2,231.08                                 | 9.36            | 370.32                       | 311.43                        | 58.89                           | 6.288                |                              |
| 4,600.00   | 2,613.69                    | 4,925.56                    | 2,911.99                    | 45.61     | 46.00  | -143.60                     | -2,331.07                                 | 8.82            | 370.62                       | 309.23                        | 61.39                           | 6.037                |                              |
| 4,700.00   | 2,614.45                    | 5,025.55                    | 2,913.14                    | 47.48     | 47.87  | -143.64                     | -2,431.06                                 | 8.28            | 370.93                       | 307.03                        | 63.90                           | 5.805                |                              |
| 4,800.00   | 2,615.21                    | 5,125.55                    | 2,914.29                    | 49.36     | 49.75  | -143.67                     | -2,531.05                                 | 7.75            | 371.24                       | 304.83                        | 66.40                           | 5.591                |                              |
| 4,900.00   | 2,615.98                    | 5,225.55                    | 2,915.43                    | 51.24     | 51.62  | -143.71                     | -2,631.04                                 | 7.21            | 371.55                       | 302.63                        | 68.91                           | 5.392                |                              |
| 5,000.00   | 2,616.74                    | 5,325.55                    | 2,916.58                    | 53.12     | 53.50  | -143.74                     | -2,731.03                                 | 6.67            | 371.85                       | 300.43                        | 71.42                           | 5.206                |                              |
| 5,100.00   | 2,617.51                    | 5,425.55                    | 2,917.72                    | 55.00     | 55.38  | -143.78                     | -2,831.02                                 | 6.13            | 372.16                       | 298.23                        | 73.93                           | 5.034                |                              |
| 5,200.00   | 2,618.27                    | 5,525.55                    | 2,918.87                    | 56.88     | 57.27  | -143.81                     | -2,931.01                                 | 5.60            | 372.47                       | 296.03                        | 76.44                           | 4.873                |                              |
| 5,300.00   | 2,619.03                    | 5,625.55                    | 2,920.01                    | 58.77     | 59.16  | -143.85                     | -3,031.01                                 | 5.06            | 372.78                       | 293.83                        | 78.95                           | 4.722                |                              |
| 5,400.00   | 2,619.80                    | 5,725.55                    | 2,921.16                    | 60.66     | 61.04  | -143.88                     | -3,131.00                                 | 4.52            | 373.09                       | 291.63                        | 81.46                           | 4.580                |                              |
| 5,500.00   | 2,620.56                    | 5,825.55                    | 2,922.30                    | 62.55     | 62.93  | -143.92                     | -3,230.99                                 | 3.99            | 373.39                       | 289.43                        | 83.97                           | 4.447                |                              |
| 5,600.00   | 2,621.32                    | 5,925.55                    | 2,923.45                    | 64.44     | 64.82  | -143.95                     | -3,330.98                                 | 3.45            | 373.70                       | 287.23                        | 86.48                           | 4.321                |                              |
| 5,700.00   | 2,622.09                    | 6,025.55                    | 2,924.59                    | 66.33     | 66.72  | -143.99                     | -3,430.97                                 | 2.91            | 374.01                       | 285.03                        | 88.98                           | 4.203                |                              |
| 5,800.00   | 2,622.85                    | 6,125.55                    | 2,925.74                    | 68.23     | 68.61  | -144.02                     | -3,530.96                                 | 2.38            | 374.32                       | 282.83                        | 91.49                           | 4.091                |                              |
| 5,900.00   | 2,623.61                    | 6,225.55                    | 2,926.88                    | 70.12     | 70.50  | -144.05                     | -3,630.95                                 | 1.84            | 374.63                       | 280.63                        | 94.00                           | 3.986                |                              |

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

**Company:** Percussion Petroleum, LLC  
**Project:** Eddy County, NM  
**Reference Site:** Lakewood Federal  
**Site Error:** 0.00 usft  
**Reference Well:** 08H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Plan #4

**Local Co-ordinate Reference:** Well 08H  
**TVD Reference:** RKB=17' @ 3500.00usft (Silver Oak 1)  
**MD Reference:** RKB=17' @ 3500.00usft (Silver Oak 1)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at:** 2.00 sigma  
**Database:** WBDS\_SQL\_2  
**Offset TVD Reference:** Reference Datum

| Offset Design Lakewood Federal - 07H - OH - Plan#3 |                       |                       |                       |                  |               |                       |                                     |              |                        |                         |                           |                   | Offset Site Error: | 0.00 usft |
|--|-----------------------|-----------------------|-----------------------|------------------|---------------|-----------------------|-------------------------------------|--------------|------------------------|-------------------------|---------------------------|-------------------|--------------------|-----------|
| Survey Program: 0-MWD+IGRF                         |                       |                       |                       |                  |               |                       |                                     |              |                        |                         |                           |                   | Offset Well Error: | 0.00 usft |
| Reference  |                       | Offset                |                       | Semi Major Axis  |               |                       | Distance                            |              |                        |                         |                           |                   |                    | Warning   |
| Measured Depth (usft)                              | Vertical Depth (usft) | Measured Depth (usft) | Vertical Depth (usft) | Reference (usft) | Offset (usft) | Highside Toolface (°) | Offset Wellbore Centre +N/-S (usft) | +E/-W (usft) | Between Centres (usft) | Between Ellipses (usft) | Minimum Separation (usft) | Separation Factor |                    |           |
| 6,000.00   | 2,624.38              | 6,325.54              | 2,928.03              | 72.02            | 72.40         | -144.09               | -3,730.94                           | 1.30         | 374.94                 | 278.44                  | 96.50                     | 3.885             |                    |           |
| 6,100.00   | 2,625.14              | 6,425.54              | 2,929.18              | 73.91            | 74.30         | -144.12               | -3,830.94                           | 0.77         | 375.25                 | 276.24                  | 99.00                     | 3.790             |                    |           |
| 6,200.00   | 2,625.90              | 6,525.54              | 2,930.32              | 75.81            | 76.19         | -144.16               | -3,930.93                           | 0.23         | 375.56                 | 274.05                  | 101.50                    | 3.700             |                    |           |
| 6,300.00   | 2,626.67              | 6,625.54              | 2,931.47              | 77.71            | 78.09         | -144.19               | -4,030.92                           | -0.31        | 375.86                 | 271.86                  | 104.00                    | 3.614             |                    |           |
| 6,400.00   | 2,627.43              | 6,725.54              | 2,932.61              | 79.61            | 79.99         | -144.23               | -4,130.91                           | -0.84        | 376.17                 | 269.67                  | 106.50                    | 3.532             |                    |           |
| 6,500.00   | 2,628.19              | 6,825.54              | 2,933.76              | 81.51            | 81.89         | -144.26               | -4,230.90                           | -1.38        | 376.48                 | 267.49                  | 109.00                    | 3.454             |                    |           |
| 6,600.00   | 2,628.96              | 6,925.54              | 2,934.90              | 83.41            | 83.79         | -144.29               | -4,330.89                           | -1.92        | 376.79                 | 265.30                  | 111.49                    | 3.380             |                    |           |
| 6,700.00   | 2,629.72              | 7,025.54              | 2,936.05              | 85.31            | 85.69         | -144.33               | -4,430.88                           | -2.45        | 377.10                 | 263.12                  | 113.99                    | 3.308             |                    |           |
| 6,800.00   | 2,630.48              | 7,125.54              | 2,937.19              | 87.21            | 87.59         | -144.36               | -4,530.88                           | -2.99        | 377.41                 | 260.94                  | 116.48                    | 3.240             |                    |           |
| 6,900.00   | 2,631.25              | 7,225.54              | 2,938.34              | 89.12            | 89.49         | -144.40               | -4,630.87                           | -3.53        | 377.72                 | 258.76                  | 118.97                    | 3.175             |                    |           |
| 7,000.00   | 2,632.01              | 7,325.54              | 2,939.48              | 91.02            | 91.40         | -144.43               | -4,730.86                           | -4.06        | 378.03                 | 256.58                  | 121.45                    | 3.113             |                    |           |
| 7,100.00   | 2,632.77              | 7,425.54              | 2,940.63              | 92.92            | 93.30         | -144.46               | -4,830.85                           | -4.60        | 378.34                 | 254.41                  | 123.94                    | 3.053             |                    |           |
| 7,200.00   | 2,633.54              | 7,525.54              | 2,941.77              | 94.83            | 95.20         | -144.50               | -4,930.84                           | -5.14        | 378.65                 | 252.23                  | 126.42                    | 2.995             |                    |           |
| 7,300.00   | 2,634.30              | 7,625.54              | 2,942.92              | 96.73            | 97.11         | -144.53               | -5,030.83                           | -5.68        | 378.97                 | 250.06                  | 128.90                    | 2.940             |                    |           |
| 7,400.00   | 2,635.07              | 7,725.53              | 2,944.06              | 98.64            | 99.01         | -144.56               | -5,130.82                           | -6.21        | 379.28                 | 247.89                  | 131.38                    | 2.887             |                    |           |
| 7,500.00   | 2,635.83              | 7,825.53              | 2,945.21              | 100.54           | 100.92        | -144.60               | -5,230.81                           | -6.75        | 379.59                 | 245.73                  | 133.86                    | 2.836             |                    |           |
| 7,600.00   | 2,636.59              | 7,925.53              | 2,946.36              | 102.45           | 102.82        | -144.63               | -5,330.81                           | -7.29        | 379.90                 | 243.56                  | 136.34                    | 2.786             |                    |           |
| 7,700.00   | 2,637.36              | 8,025.53              | 2,947.50              | 104.35           | 104.73        | -144.66               | -5,430.80                           | -7.82        | 380.21                 | 241.40                  | 138.81                    | 2.739             |                    |           |
| 7,800.00   | 2,638.12              | 8,125.53              | 2,948.65              | 106.26           | 106.63        | -144.70               | -5,530.79                           | -8.36        | 380.52                 | 239.24                  | 141.28                    | 2.693             |                    |           |
| 7,900.00   | 2,638.88              | 8,225.53              | 2,949.79              | 108.16           | 108.54        | -144.73               | -5,630.78                           | -8.90        | 380.83                 | 237.08                  | 143.75                    | 2.649             |                    |           |
| 8,000.00   | 2,639.65              | 8,325.53              | 2,950.94              | 110.07           | 110.45        | -144.76               | -5,730.77                           | -9.43        | 381.14                 | 234.92                  | 146.22                    | 2.607             |                    |           |
| 8,100.00   | 2,640.41              | 8,425.53              | 2,952.08              | 111.98           | 112.35        | -144.80               | -5,830.76                           | -9.97        | 381.46                 | 232.77                  | 148.68                    | 2.566             |                    |           |
| 8,177.35   | 2,641.00              | 8,502.88              | 2,952.97              | 113.45           | 113.83        | -144.82               | -5,908.11                           | -10.39       | 381.70                 | 231.11                  | 150.59                    | 2.535 SF          |                    |           |



|                    |                           |                              |                                      |
|--------------------|---------------------------|------------------------------|--------------------------------------|
| Company:           | Percussion Petroleum, LLC | Local Co-ordinate Reference: | Well 08H                             |
| Project:           | Eddy County, NM           | TVD Reference:               | RKB=17' @ 3500.00usft (Silver Oak 1) |
| Reference Site:    | Lakewood Federal          | MD Reference:                | RKB=17' @ 3500.00usft (Silver Oak 1) |
| Site Error:        | 0.00 usft                 | North Reference:             | Grid                                 |
| Reference Well:    | 08H                       | Survey Calculation Method:   | Minimum Curvature                    |
| Well Error:        | 0.00 usft                 | Output errors are at         | 2.00 sigma                           |
| Reference Wellbore | OH                        | Database:                    | WBDS_SQL_2                           |
| Reference Design:  | Plan #4                   | Offset TVD Reference:        | Reference Datum                      |

| Offset Design Lakewood Federal - 09H - OH - Plan #2 |                             |                             |                             |                     |                  |                             |                              |                               |                                 |                      | Offset Site Error: | 0.00 usft     |
|---|-----------------------------|-----------------------------|-----------------------------|---------------------|------------------|-----------------------------|------------------------------|-------------------------------|---------------------------------|----------------------|--------------------|---------------|
| Survey Program: 0-MWD+GRF                           |                             |                             |                             |                     |                  |                             |                              |                               |                                 |                      | Offset Well Error: | 0.00 usft     |
| Reference   |                             | Offset                      |                             | Semi Major Axis     |                  | Highside<br>Toolface<br>(°) | Distance                     |                               | Minimum<br>Separation<br>(usft) | Separation<br>Factor | Warning            |               |
| Measured<br>Depth<br>(usft)                         | Vertical<br>Depth<br>(usft) | Measured<br>Depth<br>(usft) | Vertical<br>Depth<br>(usft) | Reference<br>(usft) | Offset<br>(usft) |                             | Between<br>Centres<br>(usft) | Between<br>Ellipses<br>(usft) |                                 |                      |                    |               |
| 0.00  | 0.00                        | 0.00                        | 0.00                        | 0.00                | 0.00             | -110.79                     | -7.10                        | -18.70                        | 20.00                           |                      |                    |               |
| 100.00  | 100.00                      | 100.00                      | 100.00                      | 0.15                | 0.15             | -110.79                     | -7.10                        | -18.70                        | 20.00                           | 19.70                | 0.30               | 67.228        |
| 200.00  | 200.00                      | 200.00                      | 200.00                      | 0.51                | 0.51             | -110.79                     | -7.10                        | -18.70                        | 20.00                           | 18.99                | 1.01               | 19.717 CC, ES |
| 300.00  | 300.00                      | 297.38                      | 297.05                      | 0.87                | 0.89             | -111.54                     | -9.97                        | -25.27                        | 27.33                           | 25.58                | 1.75               | 15.595        |
| 400.00  | 400.00                      | 396.79                      | 395.88                      | 1.22                | 1.24             | -112.13                     | -14.28                       | -35.12                        | 38.13                           | 35.69                | 2.45               | 15.585        |
| 500.00  | 500.00                      | 503.80                      | 494.71                      | 1.58                | 1.67             | -112.46                     | -18.58                       | -44.96                        | 48.94                           | 45.76                | 3.18               | 15.389        |
| 600.00  | 600.00                      | 595.62                      | 593.54                      | 1.94                | 2.04             | -112.67                     | -22.89                       | -54.81                        | 59.74                           | 55.88                | 3.86               | 15.459        |
| 685.00  | 685.00                      | 680.12                      | 677.55                      | 2.25                | 2.38             | -112.79                     | -26.55                       | -63.17                        | 68.93                           | 64.46                | 4.47               | 15.413        |
| 700.00  | 700.00                      | 704.95                      | 692.39                      | 2.30                | 2.49             | 13.29                       | -27.19                       | -64.65                        | 70.36                           | 65.75                | 4.61               | 15.261        |
| 750.00  | 749.86                      | 744.99                      | 742.04                      | 2.47                | 2.65             | 13.82                       | -29.36                       | -69.60                        | 72.38                           | 67.46                | 4.92               | 14.722        |
| 759.99  | 759.78                      | 754.98                      | 751.97                      | 2.52                | 2.69             | 14.03                       | -29.79                       | -70.59                        | 72.28                           | 67.29                | 4.99               | 14.493        |
| 800.00  | 799.44                      | 805.04                      | 791.72                      | 2.65                | 2.89             | 14.95                       | -31.52                       | -74.55                        | 71.54                           | 66.23                | 5.30               | 13.490        |
| 900.00  | 898.59                      | 894.90                      | 891.08                      | 3.00                | 3.26             | 17.33                       | -35.85                       | -84.44                        | 69.77                           | 63.80                | 5.97               | 11.680        |
| 1,000.00  | 997.73                      | 1,005.16                    | 990.43                      | 3.38                | 3.72             | 19.84                       | -40.18                       | -94.34                        | 68.13                           | 61.40                | 6.73               | 10.122        |
| 1,100.00  | 1,096.88                    | 1,105.21                    | 1,089.79                    | 3.77                | 4.13             | 22.46                       | -44.50                       | -104.24                       | 66.63                           | 59.17                | 7.46               | 8.928         |
| 1,200.00  | 1,196.02                    | 1,205.27                    | 1,189.14                    | 4.18                | 4.54             | 25.20                       | -48.83                       | -114.13                       | 65.27                           | 57.07                | 8.21               | 7.954         |
| 1,300.00  | 1,295.17                    | 1,305.33                    | 1,288.50                    | 4.58                | 4.95             | 28.04                       | -53.16                       | -124.03                       | 64.07                           | 55.11                | 8.96               | 7.149         |
| 1,400.00  | 1,394.31                    | 1,405.39                    | 1,387.85                    | 5.00                | 5.36             | 30.99                       | -57.49                       | -133.93                       | 63.04                           | 53.30                | 9.73               | 6.477         |
| 1,500.00  | 1,493.46                    | 1,505.45                    | 1,487.21                    | 5.41                | 5.77             | 34.03                       | -61.81                       | -143.82                       | 62.17                           | 51.66                | 10.52              | 5.912         |
| 1,600.00  | 1,592.60                    | 1,605.51                    | 1,586.57                    | 5.83                | 6.19             | 37.14                       | -66.14                       | -153.72                       | 61.49                           | 50.17                | 11.32              | 5.434         |
| 1,700.00  | 1,691.75                    | 1,705.57                    | 1,685.92                    | 6.25                | 6.60             | 40.32                       | -70.47                       | -163.62                       | 60.99                           | 48.86                | 12.13              | 5.028         |
| 1,800.00  | 1,790.89                    | 1,805.63                    | 1,785.28                    | 6.67                | 7.01             | 43.53                       | -74.80                       | -173.51                       | 60.68                           | 47.72                | 12.96              | 4.682         |
| 1,900.00  | 1,890.03                    | 1,905.68                    | 1,884.63                    | 7.10                | 7.42             | 46.77                       | -79.12                       | -183.41                       | 60.56                           | 46.75                | 13.81              | 4.387         |
| 1,910.02  | 1,899.97                    | 1,904.33                    | 1,894.59                    | 7.14                | 7.42             | 47.10                       | -79.56                       | -184.40                       | 60.56                           | 46.71                | 13.85              | 4.373         |
| 2,000.00  | 1,989.18                    | 2,005.74                    | 1,983.99                    | 7.52                | 7.84             | 50.01                       | -83.45                       | -193.31                       | 60.64                           | 45.97                | 14.67              | 4.135         |
| 2,086.90  | 2,075.34                    | 2,081.11                    | 2,070.33                    | 7.89                | 8.15             | 52.81                       | -87.21                       | -201.91                       | 60.86                           | 45.49                | 15.38              | 3.958         |
| 2,100.00  | 2,088.31                    | 2,105.81                    | 2,083.34                    | 7.95                | 8.25             | 60.61                       | -87.78                       | -203.20                       | 60.95                           | 45.41                | 15.54              | 3.922         |
| 2,150.00  | 2,137.50                    | 2,143.92                    | 2,132.78                    | 8.18                | 8.41             | 81.95                       | -89.93                       | -208.13                       | 62.32                           | 46.29                | 16.03              | 3.888 SF      |
| 2,200.00  | 2,185.89                    | 2,193.03                    | 2,181.60                    | 8.43                | 8.61             | 97.43                       | -92.06                       | -212.99                       | 66.05                           | 49.39                | 16.66              | 3.965         |
| 2,250.00  | 2,233.09                    | 2,241.14                    | 2,229.43                    | 8.70                | 8.81             | 110.72                      | -94.14                       | -217.75                       | 73.41                           | 56.09                | 17.32              | 4.238         |
| 2,300.00  | 2,278.76                    | 2,287.88                    | 2,275.90                    | 9.00                | 9.00             | 122.12                      | -96.17                       | -222.38                       | 85.40                           | 67.48                | 17.93              | 4.764         |
| 2,350.00  | 2,322.55                    | 2,332.91                    | 2,320.66                    | 9.32                | 9.18             | 131.35                      | -98.12                       | -226.84                       | 102.44                          | 84.01                | 18.43              | 5.557         |
| 2,400.00  | 2,364.12                    | 2,375.87                    | 2,363.37                    | 9.68                | 9.36             | 138.48                      | -99.98                       | -231.10                       | 124.40                          | 105.55               | 18.86              | 6.598         |
| 2,450.00  | 2,403.15                    | 2,416.44                    | 2,403.70                    | 10.07               | 9.53             | 143.80                      | -101.73                      | -235.11                       | 150.91                          | 131.70               | 19.22              | 7.853         |
| 2,500.00  | 2,439.36                    | 2,454.31                    | 2,441.35                    | 10.50               | 9.68             | 147.68                      | -103.37                      | -238.86                       | 181.52                          | 161.99               | 19.53              | 9.293         |
| 2,550.00  | 2,472.46                    | 2,489.19                    | 2,476.03                    | 10.98               | 9.83             | 150.41                      | -104.88                      | -242.32                       | 215.81                          | 195.99               | 19.82              | 10.889        |
| 2,600.00  | 2,502.20                    | 2,520.82                    | 2,507.47                    | 11.50               | 9.96             | 152.19                      | -106.25                      | -245.45                       | 253.35                          | 233.28               | 20.08              | 12.620        |
| 2,650.00  | 2,528.36                    | 2,574.97                    | 2,561.13                    | 12.07               | 10.19            | 155.41                      | -110.93                      | -250.80                       | 292.62                          | 272.20               | 20.43              | 14.326        |
| 2,700.00  | 2,550.73                    | 2,640.95                    | 2,625.55                    | 12.68               | 10.50            | 158.37                      | -123.47                      | -257.26                       | 331.56                          | 310.91               | 20.66              | 16.051        |
| 2,750.00  | 2,569.15                    | 2,722.35                    | 2,702.37                    | 13.33               | 10.91            | 161.05                      | -149.04                      | -265.00                       | 369.39                          | 348.76               | 20.64              | 17.900        |
| 2,800.00  | 2,583.48                    | 2,828.23                    | 2,795.50                    | 14.01               | 11.53            | 163.48                      | -198.17                      | -274.46                       | 404.84                          | 384.73               | 20.11              | 20.130        |
| 2,850.00  | 2,593.60                    | 2,850.00                    | 2,879.70                    | 14.73               | 11.65            | 165.04                      | -265.83                      | -283.11                       | 435.53                          | 416.63               | 18.89              | 23.051        |
| 2,900.00  | 2,599.45                    | 2,900.00                    | 2,995.51                    | 15.46               | 11.94            | 166.83                      | -424.67                      | -295.28                       | 457.34                          | 442.20               | 15.14              | 30.211        |
| 2,938.12  | 2,601.00                    | 3,359.84                    | 3,053.78                    | 16.04               | 16.92            | 167.56                      | -640.27                      | -301.95                       | 464.69                          | 452.56               | 12.12              | 38.325        |
| 3,000.00  | 2,601.47                    | 3,446.41                    | 3,055.74                    | 16.99               | 18.14            | 167.59                      | -726.81                      | -302.50                       | 465.19                          | 452.74               | 12.45              | 37.372        |
| 3,100.00  | 2,602.24                    | 3,546.41                    | 3,057.07                    | 18.60               | 19.63            | 167.60                      | -826.79                      | -303.04                       | 465.74                          | 451.92               | 13.81              | 33.720        |
| 3,200.00  | 2,603.00                    | 3,646.41                    | 3,058.39                    | 20.25               | 21.19            | 167.61                      | -926.78                      | -303.58                       | 466.29                          | 451.04               | 15.25              | 30.573        |
| 3,300.00  | 2,603.76                    | 3,746.41                    | 3,059.72                    | 21.95               | 22.79            | 167.63                      | -1,026.77                    | -304.13                       | 466.84                          | 450.09               | 16.75              | 27.875        |
| 3,400.00  | 2,604.53                    | 3,846.41                    | 3,061.05                    | 23.68               | 24.45            | 167.64                      | -1,126.76                    | -304.67                       | 467.39                          | 449.10               | 18.28              | 25.562        |
| 3,500.00  | 2,605.29                    | 3,946.40                    | 3,062.37                    | 25.44               | 26.14            | 167.66                      | -1,226.75                    | -305.21                       | 467.94                          | 448.09               | 19.85              | 23.569        |
| 3,600.00  | 2,606.05                    | 4,046.40                    | 3,063.70                    | 27.22               | 27.86            | 167.67                      | -1,326.73                    | -305.75                       | 468.49                          | 447.04               | 21.45              | 21.843        |
| 3,700.00  | 2,606.82                    | 4,146.40                    | 3,065.03                    | 29.01               | 29.60            | 167.69                      | -1,426.72                    | -306.29                       | 469.04                          | 445.98               | 23.06              | 20.338        |

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

**Company:** Percussion Petroleum, LLC  
**Project:** Eddy County, NM  
**Reference Site:** Lakewood Federal  
**Site Error:** 0.00 usft  
**Reference Well:** 08H  
**Well Error:** 0.00 usft  
**Reference Wellbore:** OH  
**Reference Design:** Plan #4

**Local Co-ordinate Reference:** Well 08H  
**TVD Reference:** RKB=17' @ 3500.00usft (Silver Oak 1)  
**MD Reference:** RKB=17' @ 3500.00usft (Silver Oak 1)  
**North Reference:** Grid  
**Survey Calculation Method:** Minimum Curvature  
**Output errors are at** 2.00 sigma  
**Database:** WBDS\_SQL\_2  
**Offset TVD Reference:** Reference Datum

| Offset Design Lakewood Federal - 09H - OH - Plan #2 |                             |                             |                             |                     |                  |                             |   |                 |                                 |                      |         | Offset Site Error: | 0.00 usft |
|---|-----------------------------|-----------------------------|-----------------------------|---------------------|------------------|-----------------------------|---|-----------------|---------------------------------|----------------------|---------|--------------------|-----------|
| Survey Program: 0-MWD+IGRF                          |                             |                             |                             |                     |                  |                             |   |                 |                                 |                      |         | Offset Well Error: | 0.00 usft |
| Reference   |                             | Offset                      |                             | Semi Major Axis     |                  | Highside<br>Toolface<br>(°) | Distance                                  |                 | Minimum<br>Separation<br>(usft) | Separation<br>Factor | Warning |                    |           |
| Measured<br>Depth<br>(usft)                         | Vertical<br>Depth<br>(usft) | Measured<br>Depth<br>(usft) | Vertical<br>Depth<br>(usft) | Reference<br>(usft) | Offset<br>(usft) |                             | Offset Wellbore Centre<br>+N/-S<br>(usft) | +E/-W<br>(usft) |                                 |                      |         |                    |           |
| 3,800.00  | 2,607.58                    | 4,246.40                    | 3,066.35                    | 30.82               | 31.36            | 167.70                      | -1,526.71                                 | -306.83         | 469.59                          | 444.90               | 24.69   | 19.019             |           |
| 3,900.00  | 2,608.34                    | 4,346.40                    | 3,067.68                    | 32.65               | 33.14            | 167.71                      | -1,626.70                                 | -307.37         | 470.14                          | 443.81               | 26.33   | 17.854             |           |
| 4,000.00  | 2,609.11                    | 4,446.40                    | 3,069.01                    | 34.48               | 34.93            | 167.73                      | -1,726.69                                 | -307.91         | 470.70                          | 442.71               | 27.98   | 16.820             |           |
| 4,100.00  | 2,609.87                    | 4,546.40                    | 3,070.33                    | 36.32               | 36.74            | 167.74                      | -1,826.68                                 | -308.45         | 471.25                          | 441.60               | 29.64   | 15.896             |           |
| 4,200.00  | 2,610.63                    | 4,646.39                    | 3,071.66                    | 38.17               | 38.55            | 167.76                      | -1,926.66                                 | -308.99         | 471.80                          | 440.49               | 31.31   | 15.068             |           |
| 4,300.00  | 2,611.40                    | 4,746.39                    | 3,072.98                    | 40.02               | 40.38            | 167.77                      | -2,026.65                                 | -309.54         | 472.35                          | 439.36               | 32.98   | 14.320             |           |
| 4,400.00  | 2,612.16                    | 4,846.39                    | 3,074.31                    | 41.88               | 42.21            | 167.78                      | -2,126.64                                 | -310.08         | 472.90                          | 438.24               | 34.66   | 13.643             |           |
| 4,500.00  | 2,612.92                    | 4,946.39                    | 3,075.64                    | 43.74               | 44.05            | 167.80                      | -2,226.63                                 | -310.62         | 473.45                          | 437.11               | 36.34   | 13.027             |           |
| 4,600.00  | 2,613.69                    | 5,046.39                    | 3,076.96                    | 45.61               | 45.90            | 167.81                      | -2,326.62                                 | -311.16         | 474.00                          | 435.97               | 38.03   | 12.464             |           |
| 4,700.00  | 2,614.45                    | 5,146.39                    | 3,078.29                    | 47.48               | 47.75            | 167.82                      | -2,426.60                                 | -311.70         | 474.55                          | 434.84               | 39.72   | 11.948             |           |
| 4,800.00  | 2,615.21                    | 5,246.38                    | 3,079.62                    | 49.36               | 49.60            | 167.84                      | -2,526.59                                 | -312.24         | 475.11                          | 433.70               | 41.41   | 11.474             |           |
| 4,900.00  | 2,615.98                    | 5,346.38                    | 3,080.94                    | 51.24               | 51.46            | 167.85                      | -2,626.58                                 | -312.78         | 475.66                          | 432.56               | 43.10   | 11.036             |           |
| 5,000.00  | 2,616.74                    | 5,446.38                    | 3,082.27                    | 53.12               | 53.33            | 167.87                      | -2,726.57                                 | -313.32         | 476.21                          | 431.41               | 44.80   | 10.631             |           |
| 5,100.00  | 2,617.51                    | 5,546.38                    | 3,083.60                    | 55.00               | 55.19            | 167.88                      | -2,826.56                                 | -313.86         | 476.76                          | 430.27               | 46.49   | 10.255             |           |
| 5,200.00  | 2,618.27                    | 5,646.38                    | 3,084.92                    | 56.88               | 57.06            | 167.89                      | -2,926.55                                 | -314.40         | 477.31                          | 429.12               | 48.19   | 9.905              |           |
| 5,300.00  | 2,619.03                    | 5,746.38                    | 3,086.25                    | 58.77               | 58.94            | 167.91                      | -3,026.53                                 | -314.95         | 477.86                          | 427.98               | 49.89   | 9.579              |           |
| 5,400.00  | 2,619.80                    | 5,846.37                    | 3,087.58                    | 60.66               | 60.81            | 167.92                      | -3,126.52                                 | -315.49         | 478.41                          | 426.83               | 51.59   | 9.274              |           |
| 5,500.00  | 2,620.56                    | 5,946.37                    | 3,088.90                    | 62.55               | 62.69            | 167.93                      | -3,226.51                                 | -316.03         | 478.96                          | 425.68               | 53.29   | 8.989              |           |
| 5,600.00  | 2,621.32                    | 6,046.37                    | 3,090.23                    | 64.44               | 64.57            | 167.95                      | -3,326.50                                 | -316.57         | 479.52                          | 424.53               | 54.99   | 8.721              |           |
| 5,700.00  | 2,622.09                    | 6,146.37                    | 3,091.55                    | 66.33               | 66.45            | 167.96                      | -3,426.49                                 | -317.11         | 480.07                          | 423.38               | 56.69   | 8.469              |           |
| 5,800.00  | 2,622.85                    | 6,246.37                    | 3,092.88                    | 68.23               | 68.34            | 167.97                      | -3,526.47                                 | -317.65         | 480.62                          | 422.23               | 58.39   | 8.231              |           |
| 5,900.00  | 2,623.61                    | 6,346.37                    | 3,094.21                    | 70.12               | 70.22            | 167.99                      | -3,626.46                                 | -318.19         | 481.17                          | 421.08               | 60.09   | 8.007              |           |
| 6,000.00  | 2,624.38                    | 6,446.37                    | 3,095.53                    | 72.02               | 72.11            | 168.00                      | -3,726.45                                 | -318.73         | 481.72                          | 419.93               | 61.79   | 7.796              |           |
| 6,100.00  | 2,625.14                    | 6,546.36                    | 3,096.86                    | 73.91               | 74.00            | 168.01                      | -3,826.44                                 | -319.27         | 482.27                          | 418.78               | 63.50   | 7.595              |           |
| 6,200.00  | 2,625.90                    | 6,646.36                    | 3,098.19                    | 75.81               | 75.89            | 168.03                      | -3,926.43                                 | -319.81         | 482.83                          | 417.63               | 65.20   | 7.405              |           |
| 6,300.00  | 2,626.67                    | 6,746.36                    | 3,099.51                    | 77.71               | 77.78            | 168.04                      | -4,026.41                                 | -320.36         | 483.38                          | 416.48               | 66.90   | 7.225              |           |
| 6,400.00  | 2,627.43                    | 6,846.36                    | 3,100.84                    | 79.61               | 79.67            | 168.05                      | -4,126.40                                 | -320.90         | 483.93                          | 415.33               | 68.60   | 7.054              |           |
| 6,500.00  | 2,628.19                    | 6,946.36                    | 3,102.17                    | 81.51               | 81.57            | 168.07                      | -4,226.39                                 | -321.44         | 484.48                          | 414.17               | 70.31   | 6.891              |           |
| 6,600.00  | 2,628.96                    | 7,046.36                    | 3,103.49                    | 83.41               | 83.46            | 168.08                      | -4,326.38                                 | -321.98         | 485.03                          | 413.02               | 72.01   | 6.736              |           |
| 6,700.00  | 2,629.72                    | 7,146.35                    | 3,104.82                    | 85.31               | 85.35            | 168.09                      | -4,426.37                                 | -322.52         | 485.59                          | 411.87               | 73.71   | 6.588              |           |
| 6,800.00  | 2,630.48                    | 7,246.35                    | 3,106.14                    | 87.21               | 87.25            | 168.11                      | -4,526.36                                 | -323.06         | 486.14                          | 410.72               | 75.41   | 6.446              |           |
| 6,900.00  | 2,631.25                    | 7,346.35                    | 3,107.47                    | 89.12               | 89.15            | 168.12                      | -4,626.34                                 | -323.60         | 486.69                          | 409.57               | 77.12   | 6.311              |           |
| 7,000.00  | 2,632.01                    | 7,446.35                    | 3,108.80                    | 91.02               | 91.04            | 168.13                      | -4,726.33                                 | -324.14         | 487.24                          | 408.42               | 78.82   | 6.182              |           |
| 7,100.00  | 2,632.77                    | 7,546.35                    | 3,110.12                    | 92.92               | 92.94            | 168.15                      | -4,826.32                                 | -324.68         | 487.79                          | 407.27               | 80.52   | 6.058              |           |
| 7,200.00  | 2,633.54                    | 7,646.35                    | 3,111.45                    | 94.83               | 94.84            | 168.16                      | -4,926.31                                 | -325.22         | 488.34                          | 406.12               | 82.22   | 5.939              |           |
| 7,300.00  | 2,634.30                    | 7,746.34                    | 3,112.78                    | 96.73               | 96.74            | 168.17                      | -5,026.30                                 | -325.77         | 488.90                          | 404.97               | 83.92   | 5.825              |           |
| 7,400.00  | 2,635.07                    | 7,846.34                    | 3,114.10                    | 98.64               | 98.64            | 168.19                      | -5,126.28                                 | -326.31         | 489.45                          | 403.82               | 85.63   | 5.716              |           |
| 7,500.00  | 2,635.83                    | 7,946.34                    | 3,115.43                    | 100.54              | 100.54           | 168.20                      | -5,226.27                                 | -326.85         | 490.00                          | 402.67               | 87.33   | 5.611              |           |
| 7,600.00  | 2,636.59                    | 8,046.34                    | 3,116.76                    | 102.45              | 102.44           | 168.21                      | -5,326.26                                 | -327.39         | 490.55                          | 401.53               | 89.03   | 5.510              |           |
| 7,700.00  | 2,637.36                    | 8,146.34                    | 3,118.08                    | 104.35              | 104.34           | 168.22                      | -5,426.25                                 | -327.93         | 491.10                          | 400.38               | 90.73   | 5.413              |           |
| 7,800.00  | 2,638.12                    | 8,246.34                    | 3,119.41                    | 106.26              | 106.24           | 168.24                      | -5,526.24                                 | -328.47         | 491.66                          | 399.23               | 92.43   | 5.319              |           |
| 7,900.00  | 2,638.88                    | 8,346.34                    | 3,120.73                    | 108.16              | 108.15           | 168.25                      | -5,626.23                                 | -329.01         | 492.21                          | 398.08               | 94.13   | 5.229              |           |
| 8,000.00  | 2,639.65                    | 8,446.33                    | 3,122.06                    | 110.07              | 110.05           | 168.26                      | -5,726.21                                 | -329.55         | 492.76                          | 396.93               | 95.83   | 5.142              |           |
| 8,100.00  | 2,640.41                    | 8,546.33                    | 3,123.39                    | 111.98              | 111.95           | 168.28                      | -5,826.20                                 | -330.09         | 493.31                          | 395.79               | 97.53   | 5.058              |           |
| 8,177.35  | 2,641.00                    | 8,623.68                    | 3,124.41                    | 113.45              | 113.42           | 168.29                      | -5,903.55                                 | -330.51         | 493.74                          | 394.90               | 98.84   | 4.995              |           |

Company: Percussion Petroleum, LLC  
Project: Eddy County, NM  
Reference Site: Lakewood Federal  
Site Error: 0.00 usft  
Reference Well: 08H  
Well Error: 0.00 usft  
Reference Wellbore: OH  
Reference Design: Plan #4

Local Co-ordinate Reference: Well 08H  
TVD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
MD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Output errors are at: 2.00 sigma  
Database: WBDS\_SQL\_2  
Offset TVD Reference: Reference Datum

Reference Depths are relative to RKB=17' @ 3500.00usft (Silver Oak 1) Coordinates are relative to: 08H


Offset Depths are relative to Offset Datum

Central Meridian is -104.333334

Coordinate System is US State Plane 1983, New Mexico Eastern Zone

Grid Convergence at Surface is: -0.07°

## Ladder Plot



### LEGEND

—x— 08H, OH, Plan #2 V0    —△— 07H, OH, Plan #5 V0

Company: Percussion Petroleum, LLC  
Project: Eddy County, NM  
Reference Site: Lakewood Federal  
Site Error: 0.00 usft  
Reference Well: 08H  
Well Error: 0.00 usft  
Reference Wellbore: OH  
Reference Design: Plan #4

Local Co-ordinate Reference: Well 08H  
TVD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
MD Reference: RKB=17' @ 3500.00usft (Silver Oak 1)  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature  
Output errors are at: 2.00 sigma  
Database: WBDS\_SQL\_2  
Offset TVD Reference: Reference Datum

Reference Depths are relative to RKB=17' @ 3500.00usft (Silver Oak 1) Coordinates are relative to: 08H


Offset Depths are relative to Offset Datum

Central Meridian is -104.333334

Coordinate System is US State Plane 1983, New Mexico Eastern Zone

Grid Convergence at Surface is: -0.07°

## Separation Factor Plot



### LEGEND

—x— 08H, OH, Plan #2 VO —△— 08H, OH, Plan #3 VO

Percussion Petroleum Operating, LLC  
Lakewood Federal Com 8H  
SHL 572' FSL & 2336' FEL 27-19S-25E  
BHL 20' FSL & 2566' FEL 34-19S-25E  
Eddy County, NM

DRILL PLAN PAGE 1

Drilling Program

1. ESTIMATED TOPS

| Formation/Lithology     | TVD   | MD    | Contents      |
|-------------------------|-------|-------|---------------|
| Quaternary caliche      | 000'  | 000'  | water         |
| Grayburg dolomite       | 613'  | 613'  | hydrocarbons  |
| San Andres dolomite     | 798'  | 799'  | hydrocarbons  |
| (KOP                    | 2076' | 2087' | hydrocarbons) |
| Glorieta silty dolomite | 2358' | 2390' | hydrocarbons  |
| Yeso dolomite & goal    | 2513' | 2621' | hydrocarbons  |
| TD                      | 2641' | 8177' | hydrocarbons  |

2. NOTABLE ZONES

Yeso is the goal. Closest water well (RA 03304) is 3706' NW. Water bearing strata were found from 90' to 118' in the 130' deep well.

3. PRESSURE CONTROL

A 3000-psi 5000' rated BOP stack consisting of annular preventer and double (blind and pipe) ram will be used below surface casing to TD. See attached BOP and choke manifold diagrams.

Pressure tests will be conducted before drilling out from under all casing strings. Third party test crews will conduct all tests. All tests will be recorded for 10-minutes on low pressure (500 psi) and 10-minutes on high pressure (3000-psi). After BOP testing is complete, test casing (without test plug) to 2000-psi for 30 minutes. All tests will be charted on a plot. BOPs will be function tested every day.

Percussion Petroleum Operating, LLC  
 Lakewood Federal Com 8H  
 SHL 572' FSL & 2336' FEL 27-19S-25E  
 BHL 20' FSL & 2566' FEL 34-19S-25E  
 Eddy County, NM

DRILL PLAN PAGE 2

4. CASING & CEMENT

All casing will be API and new. A contingency plan is attached.

| Hole O. D. | Set MD        | Set TVD       | Casing O. D.   | Weight (lb/ft) | Grade | Joint | Collapse | Burst | Tension |
|------------|---------------|---------------|----------------|----------------|-------|-------|----------|-------|---------|
| 12.25"     | 0' - 1279'    | 0' - 1274'    | Surface 9.625" | 36             | J-55  | LTC   | 1.125    | 1.125 | 1.8     |
| 8.75"      | 0' - 2350'    | 0' - 2323'    | Prod. 1 7"     | 32             | L-80  | BTC   | 1.125    | 1.125 | 1.8     |
| 8.75"      | 2350' - 8177' | 2323' - 2641' | Prod. 2 5.5"   | 17             | L-80  | BTC   | 1.125    | 1.125 | 1.8     |

| Casing Name | Type | Sacks       | Yield | Cu. Ft. | Weight  | Blend   |
|-------------|------|-------------|-------|---------|---|---|
| Surface     | Lead | 636         | 1.32  | 840     | 14.8  | Class C + 2% CaCl + ¼ pound per sack celloflake                               |
| TOC = GL    |      | 100% Excess |       |         | Stop collar 10' above shoe with centralizer. One on 1st collar and every 4 <sup>th</sup> collar to GL.                            |   |
| Production  | Lead | 495         | 1.97  | 975     | 12.6  | 65/65/6 Class C + 6% gel + 5% salt + ¼ pound per sack celloflake + 0.2% C41-P |
|             | Tail | 1370        | 1.32  | 1808    | 14.8  | Class C + 2% CaCl + ¼ pound per sack celloflake                               |
| TOC = GL    |      | 50% Excess  |       |         | Stop collar 10' above shoe with centralizer. One on 1st collar and every 10 collars to 1200' with 1 centralizer in 9.625" casing. |   |

5. MUD PROGRAM

An electronic/mechanical mud monitor with a minimum pit volume totalizer, stroke counter, and flow sensor will be used. All necessary mud products (LCM) will be on site to handle any abnormal hole condition that may be encountered while drilling this well. A closed loop system will be used.

Percussion Petroleum Operating, LLC  
Lakewood Federal Com 8H  
SHL 572' FSL & 2336' FEL 27-19S-25E  
BHL 20' FSL & 2566' FEL 34-19S-25E  
Eddy County, NM

DRILL PLAN PAGE 3

| Type                  | Interval (MD) | lb/gal    | Viscosity | Fluid Loss | Plastic Viscosity | Yield Point |
|-----------------------|---------------|-----------|-----------|------------|-------------------|-------------|
| fresh water/gel       | 0' - 1279'    | 8.4 - 9.2 | 36-42     | NC         | 3-5               | 5-7         |
| fresh water/cut brine | 1279' - 2087' | 8.3 - 9.2 | 28-30     | NC         | 1                 | 1           |
| cut brine             | 2087' - 8177' | 8.6 - 9.2 | 29-32     | NC         | 4-5               | 6-10        |

#### 6. CORES, TESTS, & LOGS

No core or drill stem test is planned.

A mud logger will be used from GL to TD. Samples will be collected every 10' in the lateral pay zone.

No electric logs are planned at this time.

#### 7. DOWN HOLE CONDITIONS

No abnormal pressure or temperature is expected. Maximum expected bottom hole pressure is  $\approx 1127$  psi. Expected bottom hole temperature is  $\approx 109^{\circ}$  F.

A Hydrogen Sulfide Drilling Operation Plan is attached.

#### 8. OTHER INFORMATION

Anticipated spud date is upon approval. It is expected it will take  $\approx 1$  month to drill and complete the well.

St. Devote LLC has operating rights in NMNM-0504364B, NMNM-015921, and NMNM-031200. St. Devote LLC is a subsidiary of Percussion.

## **Contingency Planning – Lakewood Federal Area Wells**

**Prepared by Lelan J. Anders, Percussion Petroleum Operating, LLC.**

### **INTRODUCTION:**

This document is designed to address the issues that could arise at any time drilling horizontal Yeso wells. Percussion Petroleum Operating (PPO) is going to follow regularly used practices and procedures in order to drill the wells to TD and still keep them economical to operate.

### **SCENARIO:**

If a complete loss of circulation occurs while drilling above 400 ft MD.

### **CORRECTIVE ACTIONS:**

1. Pump an LCM sweep and attempt to regain circulation – if unsuccessful go to step 2
2. Continue drilling at attempt to seal off lost circulation zone with drill cuttings
  1. Monitor torque and drag on drill string to determine if pipe is sticking
  2. Have contingency plan to 'drill dry' – have plenty of water on hand and well control in place
  3. Continue to 'dry drill' until torque and drag dictate a different plan
3. If 'dry drilling' is unsuccessful – Run contingency surface casing string
  1. Ream out 12-1/4" open hole to 17-1/2" open hole
  2. Run contingency 13-3/8" 48# H-40, STC casing to no more than 400' MD
  3. Cement 13-3/8" casing using Class C cement
    - i. Pump at minimum 200% excess cement
      1. 400 sks 65/35/6 Class C Cement, 12.8 ppg, 1.87 yield, 10.15 gal/sk to be used on initial cement job.
    - ii. Top off cement from surface using 1" if necessary
      1. Top off will be 200 sks of 65/35/6 Class C Cement, 12.8 ppg, 1.87 yield, 10.15 gal/sk
      2. Second top off will be performed with same cement if needed.
    - iii. Insure that cement has cured for a minimum of 12 hours prior to drilling out
  4. Install 13-3/8" 3M wellhead and drill to surface casing depth with 12-1/4" OD bit
  5. Run and cement surface casing as planned





U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## SUPO Data Report

12/27/2018

APD ID: 10400032902

Submission Date: 08/20/2018

Highlighted data  
reflects the most  
recent changes

Operator Name: PERCUSSION PETROLEUM OPERATING LLC

Well Name: LAKEWOOD FEDERAL COM

Well Number: 8H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

### Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

Lake\_8H\_Road\_Map\_20180808130259.pdf

Existing Road Purpose: ACCESS

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

### Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

Lake\_8H\_New\_Road\_Map\_20180808130316.pdf

New road type: RESOURCE

Length: 981.4

Feet

Width (ft.): 30

Max slope (%): 0

Max grade (%): 1

Army Corp of Engineers (ACOE) permit required? NO

ACOE Permit Number(s):

New road travel width: 14

New road access erosion control: Crowned and ditched

New road access plan or profile prepared? NO

New road access plan attachment:

Access road engineering design? NO

Access road engineering design attachment:

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

**Access surfacing type:** OTHER

**Access topsoil source:** ONSITE

**Access surfacing type description:** Caliche

**Access onsite topsoil source depth:** 8

**Offsite topsoil source description:**

**Onsite topsoil removal process:** Grader

**Access other construction information:** No culvert, cattle guard, or vehicle turn out is needed. Drainage crossing will be low style with no culvert. No upgrade is needed.

**Access miscellaneous information:**

**Number of access turnouts:**

**Access turnout map:**

### Drainage Control

**New road drainage crossing:** OTHER

**Drainage Control comments:** Crowned and ditched

**Road Drainage Control Structures (DCS) description:** None

**Road Drainage Control Structures (DCS) attachment:**

### Access Additional Attachments

**Additional Attachment(s):**

## Section 3 - Location of Existing Wells

**Existing Wells Map?** YES

**Attach Well map:**

Lake\_8H\_Well\_Map\_20180808130331.pdf

**Existing Wells description:**

## Section 4 - Location of Existing and/or Proposed Production Facilities

**Submit or defer a Proposed Production Facilities plan?** SUBMIT

**Production Facilities description:** A 369.2' long 4" O D. HDPE flow line will be laid on the surface south 15' and west 354.2' to a central tank battery on the proposed 10H/11H pad. Maximum operating pressure will be 100 psi. A 369' long overhead raptor safe 3-phase power line will be built south to an existing power line.

**Production Facilities map:**

Lake\_8H\_Production\_Facilities\_20180808130342.pdf

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

## Section 5 - Location and Types of Water Supply

### Water Source Table

**Water source use type:** DUST CONTROL, DUST CONTROL, DUST CONTROL, DUST CONTROL, STIMULATION, STIMULATION, STIMULATION, STIMULATION, SURFACE CASING, SURFACE CASING, SURFACE CASING, SURFACE CASING

**Water source type:** GW WELL

**Describe type:**

**Source longitude:**

**Source latitude:**

**Source datum:**

**Water source permit type:** OTHER

**Source land ownership:** PRIVATE

**Water source transport method:** PIPELINE

**Source transportation land ownership:** PRIVATE

**Water source volume (barrels):** 10000

**Source volume (acre-feet):** 1.288931

**Source volume (gal):** 420000

#### Water source and transportation map:

Lake\_8H\_Water\_Source\_Map\_20180808130358.pdf

**Water source comments:** Water will be piped via temporary 12,400' long surface 10" Kevlar lay flat pipelines (2) from Percussion's existing lined fresh water pond on its own land in NE4 26-19s-25e. Pipeline route will not be bladed or excavated. Route is all private.

**New water well?** NO

### New Water Well Info

**Well latitude:**

**Well Longitude:**

**Well datum:**

**Well target aquifer:**

**Est. depth to top of aquifer(ft):**

**Est thickness of aquifer:**

**Aquifer comments:**

**Aquifer documentation:**

**Well depth (ft):**

**Well casing type:**

**Well casing outside diameter (in.):**

**Well casing inside diameter (in.):**

**New water well casing?**

**Used casing source:**

**Drilling method:**

**Drill material:**

**Grout material:**

**Grout depth:**

**Casing length (ft.):**

**Casing top depth (ft.):**

**Well Production type:**

**Completion Method:**

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

**Water well additional information:**

**State appropriation permit:**

**Additional information attachment:**

### Section 6 - Construction Materials

**Construction Materials description:** NM One Call (811) will be notified before construction starts. Percussion will move its two 3" poly surface lines north of the pad. Top 6" of soil and brush will be stockpiled northwest of the pad. V-door will face west. Closed loop drilling system will be used. Caliche will be hauled from existing caliche pits on private land. Arkland caliche pit is in NWNE 23-19s-25e. Seven Rivers caliche pit is in SWSW 6-20s-26e.

**Construction Materials source location attachment:**

Lake\_8H\_Construction\_Methods\_20180808130418.pdf

### Section 7 - Methods for Handling Waste

**Waste type:** DRILLING

**Waste content description:** Drill cuttings, mud, salts, and other chemicals

**Amount of waste:** 1000 barrels

**Waste disposal frequency :** Daily

**Safe containment description:** Steel tanks

**Safe containmant attachment:**

**Waste disposal type:** HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** PRIVATE

**Disposal type description:**

**Disposal location description:** R360's state approved (NM-01-0006) disposal site at Halfway, NM

### Reserve Pit

**Reserve Pit being used?** NO

**Temporary disposal of produced water into reserve pit?**

**Reserve pit length (ft.)** **Reserve pit width (ft.)**

**Reserve pit depth (ft.)** **Reserve pit volume (cu. yd.)**

**Is at least 50% of the reserve pit in cut?**

**Reserve pit liner**

**Reserve pit liner specifications and installation description**

### Cuttings Area

**Cuttings Area being used?** NO

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

**Are you storing cuttings on location?** YES

**Description of cuttings location** Steel tanks on pad

**Cuttings area length (ft.)**

**Cuttings area width (ft.)**

**Cuttings area depth (ft.)**

**Cuttings area volume (cu. yd.)**

**Is at least 50% of the cuttings area in cut?**

**WCuttings area liner**

**Cuttings area liner specifications and installation description**

### Section 8 - Ancillary Facilities

**Are you requesting any Ancillary Facilities?:** NO

**Ancillary Facilities attachment:**

**Comments:**

### Section 9 - Well Site Layout

**Well Site Layout Diagram:**

Lake\_8H\_Well\_Site\_Layout\_20180808130507.pdf

**Comments:**

### Section 10 - Plans for Surface Reclamation

**Type of disturbance:** New Surface Disturbance

**Multiple Well Pad Name:** LAKEWOOD FEDERAL COM

**Multiple Well Pad Number:** 7H

**Recontouring attachment:**

Lake\_8H\_Interim\_Reclamation\_Diagram\_20180808130714.pdf

Lake\_8H\_Recontour\_Plat\_20180808130721.pdf

**Drainage/Erosion control construction:** Crowned and ditched

**Drainage/Erosion control reclamation:** Harrowed on the contour

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

|   |  |   |
|---|--|---|
| <b>Well pad proposed disturbance (acres):</b> 1.98  | <b>Well pad interim reclamation (acres):</b> 0.15  | <b>Well pad long term disturbance (acres):</b> 1.83 |
| <b>Road proposed disturbance (acres):</b> 0.66      | <b>Road interim reclamation (acres):</b> 0         | <b>Road long term disturbance (acres):</b> 0.66     |
| <b>Powerline proposed disturbance (acres):</b> 0.25 | <b>Powerline interim reclamation (acres):</b> 0.25 | <b>Powerline long term disturbance (acres):</b> 0   |
| <b>Pipeline proposed disturbance (acres):</b> 5.94  | <b>Pipeline interim reclamation (acres):</b> 5.94  | <b>Pipeline long term disturbance (acres):</b> 0    |
| <b>Other proposed disturbance (acres):</b> 0        | <b>Other interim reclamation (acres):</b> 0        | <b>Other long term disturbance (acres):</b> 0       |
| <b>Total proposed disturbance:</b> 8.83             | <b>Total interim reclamation:</b> 6.34             | <b>Total long term disturbance:</b> 2.49            |

**Disturbance Comments:**

**Reconstruction method:** Interim reclamation will be completed within 6 months of completing the well. Interim reclamation will consist of shrinking the well pad 0.15 acre by removing caliche and reclaiming 20' on the northwest side of the pad. This will leave 1.83 acres for the anchors, pump jacks, and tractor-trailer turn around. Disturbed areas will be contoured to match pre-construction grades. Soil and brush will be evenly spread over disturbed areas and harrowed on the contour. Disturbed areas will be seeded in accordance with surface owner's requirements.

**Topsoil redistribution:** Enough stockpiled topsoil will be retained to cover the remainder of the pad when the well is plugged. Once the well is plugged, then the rest of the pad and new road will be similarly reclaimed within 6 months of plugging. Noxious weeds will be controlled.

**Soil treatment:** None

**Existing Vegetation at the well pad:**

**Existing Vegetation at the well pad attachment:**

**Existing Vegetation Community at the road:**

**Existing Vegetation Community at the road attachment:**

**Existing Vegetation Community at the pipeline:**

**Existing Vegetation Community at the pipeline attachment:**

**Existing Vegetation Community at other disturbances:**

**Existing Vegetation Community at other disturbances attachment:**

**Non native seed used?** NO

**Non native seed description:**

**Seedling transplant description:**

**Will seedlings be transplanted for this project?** NO

**Seedling transplant description attachment:**

**Will seed be harvested for use in site reclamation?** NO

**Seed harvest description:**

**Seed harvest description attachment:**

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

### Seed Management

#### Seed Table

**Seed type:**

**Seed source:**

**Seed name:**

**Source name:**

**Source address:**

**Source phone:**

**Seed cultivar:**

**Seed use location:**

**PLS pounds per acre:**

**Proposed seeding season:**

#### Seed Summary

**Total pounds/Acre:**

| Seed Type | Pounds/Acre |
|-----------|-------------|
|-----------|-------------|

**Seed reclamation attachment:**

#### Operator Contact/Responsible Official Contact Info

**First Name:** Ryan

**Last Name:** Barber

**Phone:** (979)292-6279

**Email:** ryan@percussionpetroleum.com

**Seedbed prep:**

**Seed BMP:**

**Seed method:**

**Existing invasive species?** NO

**Existing invasive species treatment description:**

**Existing invasive species treatment attachment:**

**Weed treatment plan description:** To BLM standards

**Weed treatment plan attachment:**

**Monitoring plan description:** To BLM standards

**Monitoring plan attachment:**

**Success standards:** To BLM satisfaction

**Pit closure description:** No pit

**Pit closure attachment:**

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

### **Section 11 - Surface Ownership**

**Disturbance type:** WELL PAD

**Describe:**

**Surface Owner:** PRIVATE OWNERSHIP

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Fee Owner:** Ross Ranch Inc

**Fee Owner Address:** P.O. Box 216 Lakewood NM 88254

**Phone:** (575)365-4797

**Email:**

**Surface use plan certification:** NO

**Surface use plan certification document:**

**Surface access agreement or bond:** Agreement

**Surface Access Agreement Need description:** To be provided

**Surface Access Bond BLM or Forest Service:**

**BLM Surface Access Bond number:**

**USFS Surface access bond number:**



**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

**Disturbance type:** OTHER

**Describe:** Power Line

**Surface Owner:** PRIVATE OWNERSHIP

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Fee Owner:** Ross Ranch Inc

**Fee Owner Address:** P.O. box 216 Lakewood NM 88254

**Phone:** (575)365-4797

**Email:**

**Surface use plan certification:** NO

**Surface use plan certification document:**

**Surface access agreement or bond:** Agreement

**Surface Access Agreement Need description:** To be provided

**Surface Access Bond BLM or Forest Service:**

**BLM Surface Access Bond number:**

**USFS Surface access bond number:**

**Disturbance type:** EXISTING ACCESS ROAD

**Describe:**

**Surface Owner:** PRIVATE OWNERSHIP

**Other surface owner description:**

**BIA Local Office:**

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Fee Owner:** Ross Ranch Inc

**Fee Owner Address:** P.O. Box 216 Lakewood NM 88254

**Phone:** (575)365-4797

**Email:**

**Surface use plan certification:** NO

**Surface use plan certification document:**

**Surface access agreement or bond:** Agreement

**Surface Access Agreement Need description:** To be provided

**Surface Access Bond BLM or Forest Service:**

**BLM Surface Access Bond number:**

**USFS Surface access bond number:**

**Disturbance type:** NEW ACCESS ROAD

**Describe:**

**Surface Owner:** STATE GOVERNMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:** SANTA FE NM

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Disturbance type:** OTHER

**Describe:** Pipeline

**Surface Owner:** PRIVATE OWNERSHIP

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Operator Name:** PERCUSSION PETROLEUM OPERATING LLC

**Well Name:** LAKEWOOD FEDERAL COM

**Well Number:** 8H

**Fee Owner:** Ross Ranch Inc

**Fee Owner Address:** P.O. Box 216 Lakewood NM 88254

**Phone:** (575)365-4797

**Email:**

**Surface use plan certification:** NO

**Surface use plan certification document:**

**Surface access agreement or bond:** Agreement

**Surface Access Agreement Need description:** To be provided

**Surface Access Bond BLM or Forest Service:**

**BLM Surface Access Bond number:**

**USFS Surface access bond number:**

## Section 12 - Other Information

**Right of Way needed?** NO

**Use APD as ROW?**

**ROW Type(s):**

### ROW Applications


**SUPO Additional Information:**

**Use a previously conducted onsite?** YES



**Previous Onsite Information:** On-site inspection was held with Jessie Bassett (BLM) on April 3, 2018. Lone Mountain inspected the project area and submitted archaeology report NMCRIS-140197 on April 11, 2018.

### Other SUPO Attachment


Lake\_8H\_SUPO\_20180808130748.pdf





TOPOI map printed on 06/26/18 from "Untitled.tpo"




TN 4 MN  
7°  
06/26/18



Map created with ©2010 National Geographic, ©2005 Tele Atlas, Rel. 8/2005









# WELL SITE PLAN

MAP 5



NOTE:  
SEE "TOPOGRAPHICAL AND ACCESS ROAD MAP"  
FOR PROPOSED ROAD LOCATION.




**PERCUSSION PETROLEUM OPERATING, LLC**

LAKWOOD FEDERAL #8H WELL LOCATED 572 FEET FROM  
THE SOUTH LINE AND 2336 FEET FROM THE EAST LINE OF  
SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO




PROVIDING SURVEYING SERVICES  
SINCE 1946  
**JOHN WEST SURVEYING COMPANY**  
412 N. DAL PASO HOBBS, N.M. 88240  
(575) 393-3117 www.jwsc.biz  
TBPLS# 10021000

|                      |                   |               |
|----------------------|-------------------|---------------|
| Survey Date: 4/03/18 | CAD Date: 5/02/18 | Drawn By: ACK |
| W.O. No.: 18110404   | Rev: 06/19/18     | Rel. W.O.:    |
|                      |                   | Sheet 1 of 1  |



# WELL SITE PLAN

MAP 5



NOTE:  
SEE "TOPOGRAPHICAL AND ACCESS ROAD MAP"  
FOR PROPOSED ROAD LOCATION.


## PERCUSSION PETROLEUM OPERATING, LLC


LAKEWOOD FEDERAL #8H WELL LOCATED 572 FEET FROM  
THE SOUTH LINE AND 2336 FEET FROM THE EAST LINE OF  
SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO



PROVIDING SURVEYING SERVICES  
SINCE 1946  
**JOHN WEST SURVEYING COMPANY**  
412 N. DAL PASO HOBBS, N.M. 88240  
(575) 393-3117 www.jwsc.biz  
TBPLS# 10021000

|                      |                   |               |
|----------------------|-------------------|---------------|
| Survey Date: 4/03/18 | CAD Date: 5/02/18 | Drawn By: ACK |
| W.O. No.: 18110404   | Rev: 06/19/18     | Rel. W.O.:    |
|                      |                   | Sheet 1 of 1  |





#### DESCRIPTION

SURVEY FOR A FLOW LINE CROSSING SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO, AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT ON THE WEST LINE OF THE SW/4 SE/4 OF SECTION 27, WHICH LIES N00°15'30"W 331.7 FEET FROM THE SOUTH QUARTER CORNER OF SAID SECTION; THEN N80°29'41"E 77.2 FEET; THEN S89°05'02"E 150.0 FEET TO A SURVEY LINE WHICH BEARS N00°32'10"E 15.0 FEET THEN CONTINUING S89°05'02"E 661.2 FEET TO A SURVEY LINE WHICH BEARS N00°19'25"W 15.0 FEET THEN CONTINUING S89°05'02"E 169.0 FEET, 930.2 FEET IN ALL; THEN N82°39'19"E 687.6 FEET; THEN S89°38'36"E 160.2 FEET TO A SURVEY LINE WHICH BEARS N00°07'51"W 15.0 FEET THEN CONTINUING S89°38'36"E 144.8 FEET, 305.0 FEET IN ALL; THEN S38°44'20"E 147.8 FEET TO A POINT IN THE SOUTHEAST QUARTER OF THE SOUTHEAST QUARTER OF SAID SECTION 27, WHICH LIES N55°39'44"W 558.2 FEET FROM THE SOUTHEAST CORNER OF SAID SECTION.

TOTAL LENGTH EQUALS 2242.8 FEET OR 135.93 RODS.

| LINE | BEARING     | DISTANCE |
|------|-------------|----------|
| L1   | N80°29'41"E | 77.2'    |
| L2   | S89°05'02"E | 980.2'   |
| L3   | N82°39'19"E | 687.6'   |
| L4   | S89°38'36"E | 305.0'   |
| L5   | S38°44'20"E | 147.8'   |
| L6   | N00°32'10"E | 15.0'    |
| L7   | N00°19'25"W | 15.0'    |
| L8   | N00°07'51"W | 15.0'    |

#### NOTE

BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM, "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM, 1983. DISTANCES ARE SURFACE VALUES.


I, RONALD J. EIDSON, NEW MEXICO PROFESSIONAL SURVEYOR No. 3239, DO HEREBY CERTIFY THAT THIS SURVEY PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH THIS PLAT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM RESPONSIBLE FOR THIS SURVEY; THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO; AND THAT THIS IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

RONALD J. EIDSON

DATE: 03/26/2018

#### LEGEND

⊙ DENOTES FOUND CORNER AS NOTED



#### PERCUSSION PETROLEUM OPERATING, LLC

SURVEY FOR A FLOW LINE FROM THE LAKEWOOD FEDERAL #10H & #11H BATTERY TO AN EXISTING PAD CROSSING SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO

Survey Date: 2/26/18

CAD Date: 3/22/18

Drawn By: ACK


W.O. No. 18110365

Rev

Rel. W.O.:

Sheet 1 of 1

PROVIDING SURVEYING SERVICES SINCE 1946  
**JOHN WEST SURVEYING COMPANY**  
 412 N. DAL PASO HOBBS, N.M. 88240  
 (575) 393-3117 www.jwsc.biz  
 TBPLS# 10021000



#### DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE CROSSING STATE OF NEW MEXICO LAND IN SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO, AND BEING 15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT IN THE SOUTHEAST QUARTER OF THE SOUTHWEST QUARTER OF SAID SECTION 27, WHICH LIES N22°11'01\"/>

SAID STRIP OF LAND BEING 127.0 FEET OR 7.70 RODS IN LENGTH, CONTAINING 0.087 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SW/4 7.70 RODS OR 0.087 ACRES

#### NOTE

BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM, "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM, 1983. ELEVATIONS ARE SURFACE VALUES.

I, RONALD J. EIDSON, NEW MEXICO PROFESSIONAL SURVEYOR No. 3239, DO HEREBY CERTIFY THAT THIS SURVEY PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH THIS PLAT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM RESPONSIBLE FOR THIS SURVEY; THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO; AND THAT THIS IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

RONALD J. EIDSON *Ronald J. Eidson*

DATE: 03/26/2018

PROVIDING SURVEYING SERVICES SINCE 1946  
**JOHN WEST SURVEYING COMPANY**  
 412 N. DAL PASO HOBBS, N.M. 88240  
 (575) 393-3117 www.jwsc.biz  
 TBPLS# 10021000

#### LEGEND

⊙ DENOTES FOUND CORNER AS NOTED

1000 0 1000 2000 FEET  
 Scale: 1"=1000'

#### PERCUSSION PETROLEUM OPERATING, LLC

**SURVEY FOR A FLOW LINE FROM THE LAKEWOOD FEDERAL #10H & #11H BATTERY TO AN EXISTING PAD CROSSING SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO**

Survey Date: 2/26/18

CAD Date: 3/22/18

Drawn By: ACK


W.O. No.: 18110365

Rev.:

Rel. W.O.:

Sheet 1 of 1

MAP 9



### DESCRIPTION

SURVEY FOR AN ELECTRIC LINE CROSSING SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO, AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT IN THE SOUTHEAST QUARTER, WHICH LIES N89°59'46\"/>

TOTAL LENGTH EQUALS 369.0 FEET OR 22.36 RODS.

### NOTE

- 1) BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983. DISTANCES ARE SURFACE VALUES.
- 2) LATITUDE AND LONGITUDE VALUES SHOWN HEREON ARE RELATIVE TO THE NORTH AMERICAN DATUM 1983 (NAD83).


I, RONALD J. EIDSON, NEW MEXICO PROFESSIONAL SURVEYOR No. 3239, DO HEREBY CERTIFY THAT THIS SURVEY MAP AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

RONALD J. EIDSON

DATE: 6/18/2018

### LEGEND

- ⊙ - DENOTES FOUND CORNER AS NOTED
- - DENOTES CENTERLINE SURVEY



### PERCUSSION PETROLEUM OPERATING, LLC

SURVEY FOR AN ELECTRIC LINE TO THE  
LAKEWOOD FEDERAL #7H, #8H & #9H  
CROSSING SECTION 27,  
TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M.  
EDDY COUNTY, NEW MEXICO

Survey Date: 06/08/18

CAD Date: 06/15/18


Drawn By: LSL

W.O. No.: 18110694

Rev.:

Rel. W.O.:

Sheet 1 of 1



Percussion's  
existing ponds

Lakewood Federal Com  
7H, 8H, 9H pad

32.6265, -104.47131  
32.6252, -104.47228  
32.62581, -104.471  
32.62581, -104.471  
32.62551, -104.47095

water supply lines

Google Earth


MAP 10

2000 ft




# WELL SITE PLAN

MAP 11



NOTE:  
SEE "TOPOGRAPHICAL AND ACCESS ROAD MAP"  
FOR PROPOSED ROAD LOCATION.




**PERCUSSION PETROLEUM OPERATING, LLC**

LAKEWOOD FEDERAL #8H WELL LOCATED 572 FEET FROM  
THE SOUTH LINE AND 2336 FEET FROM THE EAST LINE OF  
SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO






PROVIDING SURVEYING SERVICES  
SINCE 1946  
**JOHN WEST SURVEYING COMPANY**  
412 N. DAL PASO HOBBS, N.M. 88240  
(575) 393-3117 www.jwsc.biz  
TBPLS# 10021000

|                      |                   |               |
|----------------------|-------------------|---------------|
| Survey Date: 4/03/18 | CAD Date: 5/02/18 | Drawn By: ACK |
| W.O. No.: 18110404   | Rev: 06/19/18     | Rel. W.O.:    |
|                      |                   | Sheet 1 of 1  |



MAP 12



# PERCUSSION PETROLEUM OPERATING, LLC


LAKEWOOD FEDERAL #7H, #8H & #9H WELL PAD IN  
SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST,  
N.M.P.M., EDDY COUNTY, NEW MEXICO

100 0 100  
Scale: 1"=100'




PROVIDING SURVEYING SERVICES  
SINCE 1946  
**JOHN WEST SURVEYING COMPANY**  
412 N. DAL PASO HOBBS, N.M. 88240  
(575) 393-3117 www.jwsc.biz  
TBPLS# 10021000

|                      |                   |                     |
|----------------------|-------------------|---------------------|
| Survey Date: 2/21/18 | CAD Date: 7/02/18 | Drawn By: ACK       |
| W.O. No.: 18130756   | Rev: .            | Rel. W.O.: 18110403 |
|                      |                   | Sheet 1 of 1        |




# WELL SITE PLAN

MAP 14



NOTE:  
SEE "TOPOGRAPHICAL AND ACCESS ROAD MAP"  
FOR PROPOSED ROAD LOCATION.



## PERCUSSION PETROLEUM OPERATING, LLC

LAKEWOOD FEDERAL #8H WELL LOCATED 572 FEET FROM THE SOUTH LINE AND 2336 FEET FROM THE EAST LINE OF SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO

|                      |                   |               |
|----------------------|-------------------|---------------|
| Survey Date: 4/03/18 | CAD Date: 5/02/18 | Drawn By: ACK |
| W.O. No.: 18110404   | Rev: 06/19/18     | Rel. W.O.:    |
|                      |                   | Sheet 1 of 1  |



PROVIDING SURVEYING SERVICES  
SINCE 1946  
**JOHN WEST SURVEYING COMPANY**  
412 N. DAL PASO HOBBS, N.M. 88240  
(575) 393-3117 www.jwsc.biz  
TBPLS# 10021000


Percussion's  
Lakewood Federal Com 8H  
rig diagram

Prevailing Wind  
out of South  
or SSE




NORTH

1" = 50'




# WELL SITE PLAN

MAP 15



NOTE:  
SEE "TOPOGRAPHICAL AND ACCESS ROAD MAP"  
FOR PROPOSED ROAD LOCATION.




## PERCUSSION PETROLEUM OPERATING, LLC

LAKEWOOD FEDERAL #8H WELL LOCATED 572 FEET FROM  
THE SOUTH LINE AND 2336 FEET FROM THE EAST LINE OF  
SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO







PROVIDING SURVEYING SERVICES  
SINCE 1946  
**JOHN WEST SURVEYING COMPANY**  
412 N. DAL PASO HOBBS, N.M. 88240  
(575) 393-3117 www.jwsc.biz  
TBPLS# 10021000

|                      |                   |               |
|----------------------|-------------------|---------------|
| Survey Date: 4/03/18 | CAD Date: 5/02/18 | Drawn By: ACK |
| W.O. No.: 18110404   | Rev: 06/19/18     | Rel. W.O.:    |
|                      |                   | Sheet 1 of 1  |



MAP 16



PROVIDING SURVEYING SERVICES  
SINCE 1946  
**JOHN WEST SURVEYING COMPANY**  
412 N. DAL PASO HOBBS, N.M. 88240  
(575) 393-3117 [www.jwsc.biz](http://www.jwsc.biz)  
TBPLS# 10021000

**PERCUSSION PETROLEUM OPERATING, LLC**

LAKWOOD FEDERAL #7H, #8H & #9H WELL PAD IN  
SECTION 27, TOWNSHIP 19 SOUTH, RANGE 25 EAST,  
N.M.P.M., EDDY COUNTY, NEW MEXICO

|                      |                   |                     |
|----------------------|-------------------|---------------------|
| Survey Date: 2/21/18 | CAD Date: 7/02/18 | Drawn By: ACK       |
| W.O. No.: 18130756   | Rev: .            | Rel. W.O.: 18110403 |

Sheet 1 of 1

Percussion Petroleum Operating, LLC  
Lakewood Federal Com 8H  
SHL 572' FSL & 2336' FEL 27-19S-25E  
Eddy County, NM

SURFACE PLAN PAGE 1

Surface Use Plan

1. ROAD DIRECTIONS & DESCRIPTIONS (See MAPS 1 - 5)

From the junction of US 82 & US 285 in Artesia...  
Go South 15.6 miles on US 285 to the equivalent of Mile Post 53.6  
Then turn right and go West 3.8 miles on paved County Road 23 (Rock Daisy)  
Then turn right and go North 0.3 mon a caliche road  
Then turn right and East cross-country 411' to the proposed 10H/11H pad  
Cross 270' of the 10H/11H pad  
Proceed Southeast 300.4' cross-country to the 7H/8H/9H pad

Non-county roads will be maintained as needed to Gold Book standards. This includes pulling ditches and preserving the crown. This will be done at least once a year, and more often as needed.

2. ROAD TO BE BUILT OR UPGRADED (See MAPS 4 & 5)

The 981.4' of new resource road will be crowned and ditched, have a 14' wide driving surface, and be surfaced with caliche. Maximum disturbed width = 30'. Maximum grade = 1%. Maximum cut or fill = 2'. No culvert, cattle guard, or vehicle turn out is needed. Drainage crossing will be low water style with no culvert. No upgrade is needed.

3. EXISTING WELLS (See MAP 6)

Existing oil, gas, water, disposal, and P & A wells are within a mile. No injection well is within a mile radius.



Percussion Petroleum Operating, LLC  
Lakewood Federal Com 8H  
SHL 572' FSL & 2336' FEL 27-19S-25E  
Eddy County, NM

SURFACE PLAN PAGE 2

4. PROPOSED PRODUCTION FACILITIES (See MAPS 7 - 9)

A 369.2' long  $\approx 4"$  O D. HDPE flow line will be laid on the surface south 15' and west 354.2' to a central tank battery on the proposed 10H/11H pad. Maximum operating pressure will be  $<100$  psi. A 369' long overhead raptor safe 3-phase power line will be built south to an existing power line.

5. WATER SUPPLY (See MAP 10)

Water will be piped via temporary  $\approx 12,400'$  long surface 10" Kevlar lay flat pipelines (2) from Percussion's existing lined fresh water pond on its own land in NE4 26-19s-25e. Pipeline route will not be bladed or excavated. Route is all private.

6. CONSTRUCTION MATERIALS & METHODS (See MAPS 11 - 13)

NM One Call (811) will be notified before construction starts. Percussion will move its two 3" poly surface lines north of the pad. Top  $\approx 6"$  of soil and brush will be stockpiled northwest of the pad. V-door will face west. Closed loop drilling system will be used. Caliche will be hauled from existing caliche pits on private land. Arkland caliche pit is in NWNE 23-19s-25e. Seven Rivers caliche pit is in SWSW 6-20s-26e.

7. WASTE DISPOSAL

All trash will be placed in a portable trash cage. It will be hauled to the Eddy County landfill. There will be no trash burning. Contents (drill cuttings, mud, salts, and other chemicals) of the mud tanks will be hauled to R360's state approved (NM-01-0006) disposal site at Halfway. Human waste will be disposed of in chemical toilets and hauled to the Artesia wastewater treatment plant.

Percussion Petroleum Operating, LLC  
Lakewood Federal Com 8H  
SHL 572' FSL & 2336' FEL 27-19S-25E  
Eddy County, NM

SURFACE PLAN PAGE 3

#### 8. ANCILLARY FACILITIES

There will be no airstrip or camp. Camper trailers will be on location for the company man, tool pusher, and mud logger.

#### 9. WELL SITE LAYOUT (See MAP 14)

Also see Rig Layout diagram for depictions of the well pad, trash cage, access onto the location, parking, living facilities, and rig orientation.

#### 10. RECLAMATION (See MAPS 15 & 16)

Interim reclamation will be completed within 6 months of completing the well. Interim reclamation will consist of shrinking the well pad 0.15 acre by removing caliche and reclaiming 20' on the northwest side of the pad. This will leave 1.83 acres for the anchors, pump jacks, and tractor-trailer turn around. Disturbed areas will be contoured to match pre-construction grades. Soil and brush will be evenly spread over disturbed areas and harrowed on the contour. Disturbed areas will be seeded in accordance with surface owner's requirements.

Enough stockpiled topsoil will be retained to cover the remainder of the pad when the well is plugged. Once the well is plugged, then the rest of the pad and new road will be similarly reclaimed within 6 months of plugging. Noxious weeds will be controlled. Land use will be:

30' x 981.4' road = 0.66 acre  
30' x 369.4' flowline = 0.25 acre  
30' x 369' power line = 0.25 acre  
20' x 12,400' water line from pond = 5.69 acres  
+ 270' x 320' well pad = 1.98 acres  
8.83 acres short term  
- 0.25 acre flowline  
- 0.25 acre power line  
- 5.69 acres water line from pond  
- 0.15 acre interim reclamation on well pad  
2.49 acres long term (0.66 ac. road + 1.83 ac. pad)

Percussion Petroleum Operating, LLC  
Lakewood Federal Com 8H  
SHL 572' FSL & 2336' FEL 27-19S-25E  
Eddy County, NM

SURFACE PLAN PAGE 4

#### 11. SURFACE OWNER

Most road and some flowline construction will be on NM State Land Office land (SESW Section 27 of 19s-25e). NMSLO address is P. O. Box 1148, Santa Fe NM 87504. Phone is 505 827-5763. Percussion will apply for easements.

Remaining road and flowline construction and all pad and power line construction will be on private land (SWSE 27-19s-25e) owned by Ross Ranch Inc. (P. O. Box 216, Lakewood NM 88254; (575) 365-4797). Percussion has an agreement with Ross.

#### 12. OTHER INFORMATION

On-site inspection was held with Jessie Bassett (BLM) on April 3, 2018.


Lone Mountain inspected the project area and submitted archaeology report NMCRIS-140197 on April 11, 2018.

Percussion Petroleum Operating, LLC  
Lakewood Federal Com 8H  
SHL 572' FSL & 2336' FEL 27-19S-25E  
Eddy County, NM

SURFACE PLAN PAGE 5

CERTIFICATION

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U. S. C. 1001 for the filing of false statements. Executed this 4th day of August, 2018.



---

Brian Wood, Consultant

Permits West, Inc.

37 Verano Loop, Santa Fe, NM 87508

(505) 466-8120

FAX: (505) 466-9682

Cellular: (505) 699-2276

Field representative will be:

Lelan Anders, Operations Manager  
Percussion Petroleum Operating, LLC  
919 Milam, Suite 2475  
Houston TX 77002  
Office: (713) 429-1291  
Mobile: (281) 908-1752





**U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT**

## **PWD Data Report**

**12/27/2018**

### **Section 1 - General**

**Would you like to address long-term produced water disposal? NO**

### **Section 2 - Lined Pits**

**Would you like to utilize Lined Pit PWD options? NO**

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Lined pit PWD on or off channel:**

**Lined pit PWD discharge volume (bbl/day):**

**Lined pit specifications:**

**Pit liner description:**

**Pit liner manufacturers information:**

**Precipitated solids disposal:**

**Describe precipitated solids disposal:**

**Precipitated solids disposal permit:**

**Lined pit precipitated solids disposal schedule:**

**Lined pit precipitated solids disposal schedule attachment:**

**Lined pit reclamation description:**

**Lined pit reclamation attachment:**

**Leak detection system description:**

**Leak detection system attachment:**

**Lined pit Monitor description:**

**Lined pit Monitor attachment:**

**Lined pit: do you have a reclamation bond for the pit?**

**Is the reclamation bond a rider under the BLM bond?**

**Lined pit bond number:**

**Lined pit bond amount:**

**Additional bond information attachment:**

### **Section 3 - Unlined Pits**

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

### **Section 4 - Injection**

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

**Injection well type:**

**Injection well number:**

**Injection well name:**

**Assigned Injection well API number?**

**Injection well API number:**

**Injection well new surface disturbance (acres):**

**Minerals protection information:**

**Mineral protection attachment:**

**Underground Injection Control (UIC) Permit?**

**UIC Permit attachment:**

### **Section 5 - Surface Discharge**

**Would you like to utilize Surface Discharge PWD options? NO**

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Surface discharge PWD discharge volume (bbl/day):**

**Surface Discharge NPDES Permit?**

**Surface Discharge NPDES Permit attachment:**

**Surface Discharge site facilities information:**

**Surface discharge site facilities map:**

### **Section 6 - Other**

**Would you like to utilize Other PWD options? NO**

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Other PWD discharge volume (bbl/day):**

**Other PWD type description:**

**Other PWD type attachment:**

**Have other regulatory requirements been met?**

**Other regulatory requirements attachment:**





**U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT**

## **Bond Info Data Report**

12/27/2018

### **Bond Information**

**Federal/Indian APD: FED**

**BLM Bond number: NMB001424**

**BIA Bond number:**

**Do you have a reclamation bond? NO**

**Is the reclamation bond a rider under the BLM bond?**

**Is the reclamation bond BLM or Forest Service?**

**BLM reclamation bond number:**

**Forest Service reclamation bond number:**

**Forest Service reclamation bond attachment:**

**Reclamation bond number:**

**Reclamation bond amount:**

**Reclamation bond rider amount:**

**Additional reclamation bond information attachment:**