

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENTFORM APPROVED  
OMB NO. 1004-0137  
Expires: January 31, 2018**SUNDRY NOTICES AND REPORTS ON WELLS**  
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.*5. Lease Serial No.  
NMNM2748

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.  
KIRK FEDERAL COM 3H

9. API Well No.

30-015-45662

10. Field and Pool or Exploratory Area  
LOCO HILLS-GLORIETA-YESO11. County or Parish, State  
EDDY COUNTY, NM**SUBMIT IN TRIPLICATE - Other instructions on page 2**

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

EOG RESOURCES INCORPORATED

Contact: TINA HUERTA

E-Mail: tina\_huerta@eogresources.com

3a. Address

MIDLAND, TX 79702

3b. Phone No. (include area code)

Ph: 575-748-4168  
ARTESIA DISTRICT

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Sec 12 T17S R30E NWNW 1296FNL 628FWL  
32.852722 N Lat, 103.931938 W Lon

FEB 08 2019

RECEIVED

**12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	Change to Original A PD
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomple horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomple in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.

EOG Resources, Inc. respectfully requests to amend the surface hole size and casing size to 17-1/2 inch hole and 13-3/8 inch casing (casing and cement design as attached). We request the addition of an intermediate casing string (casing design and cement attached), due to potential water flow in the area. Production cement will tie back 500 ft into previous casing string. We request a change to an offline cementing procedure for the surface interval of this well as shown on page 2.

Anticipated spud date of 2-15-19.

SEE ATTACHED FOR  
CONDITIONS OF APPROVALCarlsbad Field Office  
OCD Artesia

All Previous COAs Still Apply, Except for the Following:

14. I hereby certify that the foregoing is true and correct.

Electronic Submission #452420 verified by the BLM Well Information System

For EOG RESOURCES INCORPORATED, sent to the Carlsbad

Committed to AFMSS for processing by PRISCILLA PEREZ on 02/01/2019 (19PP0906SE)

Name (Printed/Typed) TINA HUERTA

Title REGULATORY SPECIALIST

Signature (Electronic Submission)

Date 01/29/2019

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved By JEREMY PORTER

Title PETROLEUM ENGINEER

Date 02/04/2019

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office Carlsbad

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

\*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\*

RWP 2-21-19

## Revisions to Operator-Submitted EC Data for Sundry Notice #452420

	<b>Operator Submitted</b>	<b>BLM Revised (AFMSS)</b>
Sundry Type:	APDCH NOI	APDCH NOI
Lease:	NMLC029338B	NMNM2748
Agreement:		
Operator:	EOG RESOURCES INC. 104 SOUTH FOURTH STREET ARTESIA, NM 88210 Ph: 575-748-1471	EOG RESOURCES INCORPORATED  MIDLAND, TX 79702 Ph: 432.686.3600
Admin Contact:	TINA HUERTA REGULATORY SPECIALIST E-Mail: tina_huerta@eogresources.com  Ph: 575-748-4168	TINA HUERTA REGULATORY SPECIALIST E-Mail: tina_huerta@eogresources.com  Ph: 575-748-4168
Tech Contact:	TINA HUERTA REGULATORY SPECIALIST E-Mail: tina_huerta@eogresources.com  Ph: 575-748-4168	TINA HUERTA REGULATORY SPECIALIST E-Mail: tina_huerta@eogresources.com  Ph: 575-748-4168
Location:		
State:	NM	NM
County:	EDDY	EDDY
Field/Pool:	LOCO HILLS;GLORIETA-YESO	LOCO HILLS-GLORIETA-YESO
Well/Facility:	KIRK FEDERAL COM 3H Sec 12 T17S R30E NWNW 1296FNL 628FWL	KIRK FEDERAL COM 3H Sec 12 T17S R30E NWNW 1296FNL 628FWL 32.852722 N Lat, 103.931938 W Lon

## Kirk Federal Com #3H Sundry

## Surface &amp; Intermediate Hole Casing:

Hole Size	Interval	Csg OD	Weight	Grade	Conn	DF <sub>min</sub> Collapse	DF <sub>min</sub> Burst	DF <sub>min</sub> Tension
17.5"	0'-400'	13.375"	48#	H-40/ J-55	STC	1.125	1.25	1.60
12.25"	0' -100'	9.625	40#	J-55	LTC	1.125	1.25	1.60
12.25"	100' - 3,300'	9.625	36#	J-55	LTC	1.125	1.25	1.60
12.25"	3,300' - 3,500'	9.625	40#	J-55	LTC	1.125	1.25	1.60
8.75"	0' - 4,928'	7"	29#	L-80	BTC	1.125	1.25	1.60
8.75"	4,928'-9,102'	5 1/2"	17#	L-80	BTC	1.125	1.25	1.60

## Surface &amp; Intermediate Cement:

Depth	No. Sacks	Wt. lb/gal	Yld Ft <sup>3</sup> /ft	Volume Ft <sup>3</sup>	Slurry Description
400'	425	14.8	1.32	100	Tail: Class 'C' + 2%PF1(Calcium Chloride) (100% excess)
3500'*	1075	12.8	1.79	343	Lead: 35:65 Poz C + .02 gal/sk Anti Foam + 1% Extender + .13 lb/sk Lost Circulation (TOC @ Surface) 100% Excess
	200	14.8	1.33	47	Tail: Class C + 0.13% Anti Foam
9102'	160	11.9	2.47	70	Lead: Class 50/50 PozC + 5%PF44(BWOW)(Salt) + 10% PF20(Bentonite Gel) +.2%PF153(Anti Settling Agent( + 3#/sk OF42(Kolseal) + 0.125#/sk PF29 (celloflake) + 0.4#/sk PF45 (Defoamer) (TOC @ 500' into previous casing string) 35% Excess
	965	13	1.48	254	Tail: Class PVL + 1.3% PF44(BWOW)(Salt) + 5% PF174 (Expanding Cement) + 0.5% PF606 (Fluid Loss) + 0.1% PF153 (Anti Settling Agent) + 0.4#/sk PF45 (Defoamer) 35% Excess
*Cement will be done in 2 stages if water flow is encountered. If water flow is encountered in the salt section DV Tool placement will be placed below salt interval. If water flow is encountered below the salt section DV tool placement will be above water flow depth. Cement volumes will be adjusted accordingly.					

- Kirk Federal Lease – Batch Drilling and Offline Cementing Procedure
  - Kirk Federal Com #1H – MIRU Spudder Rig
  - Drill 17 ½" hole to approx. 400'
  - TOOH with drill string
  - Run 13 3/8" 48# H 40 Surface Casing
  - Land on conductor pipe
  
- Move Spudder Rig to Kirk Federal Com #2H
  - Drill 17 ½" hole to approx. 400'
  - TOOH with drill string
  - Run 13 3/8" 48# H 40 Surface Casing
  - Land on conductor pipe
  
- Move Spudder Rig to Kirk Federal Com #3H
  - Drill 17 ½" hole to approx. 400'
  - TOOH with drill string
  - Run 13 3/8" 48# H 40 Surface Casing
  - Land on conductor pipe
  
- RU Cement company on Kirk Federal Com #1H
  - Pump 425 sx. "C" with 2% CaCl<sub>2</sub>
  - Wt. 14.8 ppg Yield 1.32
  - If cement does not circulate, WOC 6Hrs for Temp. Survey
  - While WOC, move to Kirk Fed. # 2H
  - Pump 425 sx. "C" with 2% CaCl<sub>2</sub>
  - Wt. 14.8 ppg Yield 1.32
  - If cement does not circulate, WOC 6Hrs for Temp. Survey
  - While WOC , move to Kirk 3H
  - Pump 425 sx. "C" with 2% CaCl<sub>2</sub>
  - Wt. 14.8 ppg Yield 1.32
  - After 6 hours, run temperature survey on each well
  - Pump 1" stage of cement on Kirk 1H, Kirk 2H in sequence.
  - After cement is to surface on Kirk 1H and Kirk 2H, move to Kirk 3H
  - Cement in 1" stages as necessary to bring cement to surface
  
- Each well will be secured by installing 13 5/8" x 13 3/8" x 3K Multibowl wellhead with a 3K blind flange installed on top of the wellhead.
  
- Rotary Tools will be moved in within 3 weeks of setting surface
  - BOPE will be installed and tested in accordance with Onshore Order 2

**Kirk Federal Com #3H**

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0 – 400'	Fresh Water	8.6-8.8	28-32	N/c
400' – 3,500' Vertical	Brine	9.2-10.2	32-34	N/c
3,500' – 9,102' Vertical/Curve/Lateral	Cut Brine	8.8-9.4	30-34	N/c

# PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

<b>OPERATOR'S NAME:</b>	<b>EOG Resources Incorporated</b>
<b>LEASE NO.:</b>	<b>NMNM2748</b>
<b>WELL NAME &amp; NO.:</b>	<b>KIRK FEDERAL COM 3H</b>
<b>SURFACE HOLE FOOTAGE:</b>	<b>1296'/N &amp; 628'/W</b>
<b>BOTTOM HOLE FOOTAGE</b>	<b>502'/N &amp; 100'/E</b>
<b>LOCATION:</b>	<b>Section 12, T.17 S., R.30 E., NMPM</b>
<b>COUNTY:</b>	<b>EDDY County, New Mexico</b>

COA

H2S	<input checked="" type="radio"/> Yes	<input type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP

**All previous COAs still apply, except for the following:**

## A. CASING

1. The 13 3/8 inch surface casing shall be set at approximately 400 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of 8 hours or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:

**Option 1**

**Single Stage**

- Cement to surface. If cement does not circulate see B.1.a, c-d above.

**Operator must contact BLM before proceeding to option 2.**

**Option 2:**

Operator has proposed DV tool. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range. If operator circulates cement on the first stage, operator is approved to inflate the ACP and run the DV tool cancellation plug and cancel the second stage of the proposed cement plan. If cement does not circulate, operator will inflate ACP and proceed with the second stage..

- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
- b. Second stage above DV tool:
  - Cement to surface. If cement does not circulate, contact the appropriate BLM office.

3. The minimum required fill of cement behind the 7 X 5 ½ inch production casing is:

- Cement should tie-back at least **200 feet** into the previous casing. Operator shall provide method of verification.

**B. PRESSURE CONTROL**

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).

2.

**Option 1**

- Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **3000 (3M) psi**.

## **Option 2**

Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **3,000 (3M)** psi.

- a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
- b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- c. Manufacturer representative shall install the test plug for the initial BOP test.
- d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

## **C. SPECIAL REQUIREMENT (S)**

### **Communitization Agreement**

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

**JJP242019**



## GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties

Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.

During office hours call (575) 627-0272.

After office hours call (575)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)  
393-3612

1. The operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - a) When the operator proposes to set surface casing with Spudder Rig
  - b) Notify the BLM when moving in and removing the Spudder Rig.
  - c) Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
  - d) BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.

### A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24

hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

#### B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification

matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
  - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
  - c. The tests shall be done by an independent service company utilizing a test plug. The results of the test shall be reported to the appropriate BLM office.

- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.