# RECEIVED

Form 3160-3 (June 2015)

JUN 0 3 2019

FORM APPROVED OMB No. 1004-0137 Expires: January 31, 2018

# UNITED STATES

DEPARTMENT OF THE INTERIOR


BUREAU OF LAND MANAGEDISTRICT II-ARTESIA O.C.D.

5.	Lease	Seria	l No
NN	1NM0	1283	3

APPLICATION FOR PERMIT TO DI	RILL O	REENIER		6. If Indian, Affolie of Tribe Name			
lb. Type of Well: Oil Well Gas Well Ot	EENTER her ngle Zone	Multiple Zone		7. If Unit or CA Agreement, Name and No  8. Lease Name and Well No.  OSAGE BOYD 15 FEDERAL COM  13H  317253			
2. Name of Operator PERCUSSION PETROLEUM OPERATING LLC				9. API Well No. 30-0/3	-4607/		
3a. Address 919 Milam Street, Suite 2475 Houston TX 77002	3b. Phone (713)589	e No. (include area cod 1-2337	e)	10. Field and Pool, o N. SEVEN RIVERS	r Exploratory ; GLORIETA -YESO		
<ol> <li>Location of Well (Report location clearly and in accordance we At surface NWNW / 649 FNL / 1180 FWL / LAT 32.652</li> <li>At proposed prod. zone NWNW / 20 FNL / 1185 FWL / LAT 32.652</li> </ol>	008/LOI	NG -104.477351	7363	11. Sec., T. R. M. or SEC 22 / T19S / R2	Blk. and Survey or Area 25E / NMP		
14. Distance in miles and direction from nearest town or post office 14 miles	ce*			12. County or Parish EDDY	13. State NM		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig, unit line, if any)	16. No of <b>240</b>	facres in lease	17. Spacir	ng Unit dedicated to th	is well		
18. Distance from proposed location* to nearest well, drilling, completed, 20 feet applied for, on this lease, ft.	į ,	osed Depth t / 7982 feet		BIA Bond No. in file			
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3468 feet	01/02/20	oximate date work will 19 tachments	start*	23. Estimated duration 30 days	on		
The following, completed in accordance with the requirements of (as applicable)	Onshore (	Oil and Gas Order No.	I, and the H	lydraulic Fracturing ru	lle per 43 CFR 3162.3-3		
<ol> <li>Well plat certified by a registered surveyor.</li> <li>A Drilling Plan.</li> <li>A Surface Use Plan (if the location is on National Forest System SUPO must be filed with the appropriate Forest Service Office)</li> </ol>		Item 20 above).  5. Operator certific	cation.		existing bond on file (se		
25. Signature (Electronic Submission)	: I	me <i>(Printed/Typed)</i> an Wood / Ph: (505)4	66-8120	·	Date 11/06/2018		
Title President							
Approved by (Signature) (Electronic Submission)	;	me <i>(Printed/Typed)</i> dy Layton / Ph: (575)2	234-5959		Date 05/29/2019		
Title Assistant Field Manager Lands & Minerals	Off CA	ice RLSBAD		, , ,			

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the



\*(Instructions on page 2)

(Continued on page 2)

applicant to conduct operations thereon. Conditions of approval, if any, are attached

6-12-19

#### INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the wen, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionany drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

### NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service wen or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record win be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM conects this information to anow evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Conection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

**Approval Date: 05/29/2019** 

(Form 3160-3, page 2)

# **Additional Operator Remarks**

# **Location of Well**

1. SHL: NWNW / 649 FNL / 1180 FWL / TWSP: 19S / RANGE: 25E / SECTION: 22 / LAT: 32.652008 / LONG: -104.477351 ( TVD: 0 feet, MD: 0 feet )

PPP: NWNW / 1325 FNL / 1185 FWL / TWSP: 19S / RANGE: 25E / SECTION: 15 / LAT: 32.664595 / LONG: -104.477357 ( TVD: 2544 feet, MD: 6706 feet )

BHL: NWNW / 20 FNL / 1185 FWL / TWSP: 19S / RANGE: 25E / SECTION: 15 / LAT: 32.668093 / LONG: -104.477363 ( TVD: 2510 feet, MD: 7982 feet )

# **BLM Point of Contact**

Name: Tanja Baca

Title: Admin Support Assistant

Phone: 5752345940 Email: tabaca@blm.gov

(Form 3160-3, page 3)

**Approval Date: 05/29/2019** 

# **Review and Appeal Rights**

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

(Form 3160-3, page 4)

# PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

**OPERATOR'S NAME:** | Percussion Petroleum Operating, LLC

**LEASE NO.: | NMNM-012833** 

WELL NAME & NO.: | Osage Boyd 15 Federal Com 13H

SURFACE HOLE FOOTAGE: | 0649' FNL & 1180' FWL

BOTTOM HOLE FOOTAGE | 0020' FNL & 1185' FWL Sec. 15, T. 19 S., R 25 E.

LOCATION: | Section 22, T. 19 S., R 25 E., NMPM

**COUNTY:** | County, New Mexico

# **Communitization Agreement**

The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.

- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

# A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

# **□** Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

- 1. Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.
- 2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. If the drilling rig is removed without approval an Incident of Non-Compliance will be written and will be a "Major" violation.
- 3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
- 4. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

#### B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

### Wait on cement (WOC) for Water Basin:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until

Page 2 of 6

cement has been in place at least <u>8 hours</u>. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.

Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Medium Cave/Karst

Possibility of water flow sin the San Andres.

Possibility of lost circulation in the San Andres and Artesia Group.

### **Contingency Surface Casing Plan:**

- 1. The 13-3/8 inch surface casing shall be set at approximately 400 feet and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

### **Casing Plan without Contingency:**

2. The 9-5/8 inch surface casing shall be set at approximately 1279 feet and cemented to the surface (If contingency casing is used the 9-5/8" casing will become the intermediate casing).

Page 3 of 6

**Approval Date: 05/29/2019** 

- a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
- b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

If cement does not circulate to surface on the intermediate casing, the cement on the production casing must come to surface.

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

3.	The minimum	required fill	of cement	behind t	the 7 X	5-1/2 inch	production	casing i	S
----	-------------	---------------	-----------	----------	---------	------------	------------	----------	---

Cement to surface.	If cement does not circulate, contact the appropriate BI	_M
office.		

4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

### C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be psi.

- 3. The appropriate BLM office shall be notified a minimum of hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - a. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**.
  - b. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
  - c. The results of the test shall be reported to the appropriate BLM office.
  - d. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
  - e. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

Page 5 of 6

**Approval Date: 05/29/2019** 

### D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

### E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 052819

Page 6 of 6

**Approval Date: 05/29/2019** 



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT



# **Operator Certification**

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Brian Wood Si	igned on:	11/06/2018
---------------------	-----------	------------

Title: President

Street Address: 37 Verano Loop

City: Santa Fe State: NM Zip: 87508

Phone: (505)466-8120

Email address: afmss@permitswest.com

# Field Representative

Representative Name	:	
Street Address:		
City:	State:	Zip:
Phone:		
Email address:		



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT



APD ID: 10400036037 Submission Date: 11/06/2018

**Operator Name: PERCUSSION PETROLEUM OPERATING LLC** 

Well Name: OSAGE BOYD 15 FEDERAL COM

Well Number: 13H

Well Work Type: Drill

Highlighted data reflects the most recent changes

**Show Final Text** 

Section 1 - General

APD ID:

10400036037

Tie to previous NOS?

Submission Date: 11/06/2018

**BLM Office: CARLSBAD** 

Well Type: OIL WELL

User: Brian Wood

Title: President

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM012833

Lease Acres: 240

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? NO

**Permitting Agent? YES** 

APD Operator: PERCUSSION PETROLEUM OPERATING LLC

Operator letter of designation:

**Operator Info** 

Operator Organization Name: PERCUSSION PETROLEUM OPERATING LLC

Operator Address: 919 Milam Street, Suite 2475

Zip: 77002

**Operator PO Box:** 

**Operator City:** Houston

State: TX

**Operator Phone:** (713)589-2337

**Operator Internet Address:** 

**Section 2 - Well Information** 

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: OSAGE BOYD 15 FEDERAL COM

Well Number: 13H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: N. SEVEN RIVERS; Pool Name:

**GLORIETA -YESO** 

Is the proposed well in an area containing other mineral resources? USEABLE WATER, NATURAL GAS, OIL

Well Name: OSAGE BOYD 15 FEDERAL COM Well Number: 13H

Describe other minerals:

Is the proposed well in a Helium production area? N Use Existing Well Pad? NO New surface disturbance?

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: OSAGE BOYD 15 FEDERAL Number: 12H

Well Class: HORIZONTAL

COM

Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL **Describe Well Type:** 

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 14 Miles Distance to nearest well: 20 FT

Distance to lease line: 140 FT

Reservoir well spacing assigned acres Measurement: 160 Acres

Well plat:

Osage\_13H\_Plat\_GasCap\_Plan\_20181106113244.pdf

Well work start Date: 01/02/2019 **Duration: 30 DAYS** 

# **Section 3 - Well Location Table**

Survey Type: RECTANGULAR

**Describe Survey Type:** 

Datum: NAD83 Vertical Datum: NAVD88

Survey number: 7977

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	ΔΛΤ
SHL	649	FNL	118	FWL	19S	25E	22	Aliquot	32.65200	-	EDD	NEW	NEW	F	FEE	346	0	0
Leg			0					NWN	8	104.4773	Υ	MEXI				8	:	
#1								W		51		СО	СО					
КОР	465	FNL	118	FWL	19S	25E	22	Aliquot	32.65251	-	EDD	NEW	NEW	F	FEE	142	205	204
Leg			5					NWN	18	104.4773	Υ	MEXI				7	2	1
#1								W		348		co	СО					
PPP	132	FNL	118	FWL	19S	25E	15	Aliquot	32.66459	-	DON	NEW	NEW	F	NMNM	924	670	254
Leg	5		5					NWN	5	104.4773	Α	MEXI	MEXI		012833		6	4
#1			!					w		57	ANA	СО	СО					

Well Name: OSAGE BOYD 15 FEDERAL COM Well Number: 13H

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	DVT
EXIT Leg #1	20	FNL	118 5	FWL	19S	25E	15	Aliquot NWN W	32.66809 3	- 104.4773 63	EDD Y	NEW MEXI CO	FIRS T PRIN	F	NMNM 012833	958	798 2	251 0
BHL Leg #1	20	FNL	118 5	FWL	198	25E	15	Aliquot NWN W	32.66809 3	- 104.4773 63	EDD Y	NEW MEXI CO	FIRS T PRIN		NMNM 012833	958	798 2	251 0



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

# Drilling Plan Data Report

05/30/2019

**APD ID:** 10400036037 **Submission Date:** 11/06/2018

**Operator Name: PERCUSSION PETROLEUM OPERATING LLC** 

Highlighted data reflects the most recent changes

Well Name: OSAGE BOYD 15 FEDERAL COM

Well Number: 13H

Show Final Text

Well Type: OIL WELL

Well Work Type: Drill

# **Section 1 - Geologic Formations**

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	QUATERNARY	3468	Ö	0	OTHER : Caliche	USEABLE WATER	No
2	GRAYBURG	2870	598	598	DOLOMITE	NATURAL GAS,OIL	No
3	SAN ANDRES	2685	783	785	DOLOMITE	NATURAL GAS,OIL	No
4	GLORIETA	1125	2343	2393	DOLOMITE	NATURAL GAS,OIL	No
5	YESO	970	2498	2650	DOLOMITE	NATURAL GAS,OIL	Yes

### **Section 2 - Blowout Prevention**

Pressure Rating (PSI): 3M

Rating Depth: 5000

**Equipment:** A 3000-psi 5000' rated BOP stack consisting of annular preventer and double (blind and pipe) ram will be used below surface casing to TD.

Requesting Variance? NO

#### Variance request:

**Testing Procedure:** Pressure tests will be conducted before drilling out from under all casing strings. Third party test crews will conduct all tests. All tests will be recorded for 10-minutes on low pressure (500 psi) and 10-minutes on high pressure (3000-psi). After BOP testing is complete, test casing (without test plug) to 2000-psi for 30 minutes. All tests will be charted on a plot. BOPs will be function tested every day.

#### **Choke Diagram Attachment:**

Osage\_13H\_Choke\_20181106113805.pdf

# **BOP Diagram Attachment:**

Osage\_13H\_BOP\_20181106113812.pdf

Well Name: OSAGE BOYD 15 FEDERAL COM Well Number: 13H

# **Section 3 - Casing**

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	12.2 5	9.625	NEW	API	N	0	1279	0	1275	3468		1279	J-55	36	LTC	_	1.12 5	DRY	1.8	DRY	1.8
_	PRODUCTI ON	8.75	7.0	NEW	API	Υ	0	2300	0	2273	3468		2300	L-80	32	BUTT	_	1.12 5	DRY	1.8	DRY	1.8
T .	PRODUCTI ON	8.75	5.5	NEW	API	Υ	2300	7982	2273	2510			5682	L-80	17	BUTT		1.12 5	DRY	1.8	DRY	1.8

# **Casing Attachments**

Casing ID: 1

String Type: SURFACE

**Inspection Document:** 

**Spec Document:** 

**Tapered String Spec:** 

Casing Design Assumptions and Worksheet(s):

 $Osage\_13H\_Casing\_Design\_Assumptions\_20181106113835.pdf$ 

Well Name: OSAGE BOYD 15 FEDERAL COM Well Number: 13H

# **Casing Attachments**

Casing ID: 2

String Type: PRODUCTION

**Inspection Document:** 

**Spec Document:** 

**Tapered String Spec:** 

Osage\_13H\_Casing\_Design\_Assumptions\_20181106113900.pdf

Casing Design Assumptions and Worksheet(s):

Osage\_13H\_Casing\_Design\_Assumptions\_20181106113931.pdf

Casing ID: 3

String Type:PRODUCTION

**Inspection Document:** 

**Spec Document:** 

**Tapered String Spec:** 

Osage\_13H\_Casing\_Design\_Assumptions\_20181106113956.pdf

Casing Design Assumptions and Worksheet(s):

Osage\_13H\_Casing\_Design\_Assumptions\_20181106114006.pdf

# Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	1279	637	1.32	14.8	840	100	Class C	2% CaCl + ¼ pound per sack celloflake

PRODUCTION	Lead	0	2300	495	1.97	12.6	975	50	65/65/6 Class C	6% gel + 5% salt + ¼ pound per sack celloflake + 0.2% C41-P
PRODUCTION	Tail	0	2300	1323	1.32	14.8	1746	50	Class C	2% CaCl + ¼ pound per sack celloflake
PRODUCTION	Lead	2300	7982	495	1.97	12.6	975	50	65/65/6 Class C	6% gel + 5% salt + ¼ pound per sack

Well Name: OSAGE BOYD 15 FEDERAL COM Well Number: 13H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
											celloflake + 0.2% C41-P
PRODUCTION	Tail		2300	7982	1323	1.32	14.8	1746	50	Class C	2% CaCl + ¼ pound per sack celloflake

# **Section 5 - Circulating Medium**

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: All necessary mud products (LCM) will be on site to handle any abnormal hole condition that may be encountered while drilling this well.

**Describe the mud monitoring system utilized:** An electronic/mechanical mud monitor with a minimum pit volume totalizer, stroke counter, and flow sensor will be used.

# **Circulating Medium Table**

O Top Depth	Bottom Depth	odk DTHER : Fresh	Win Weight (lbs/gal)	က် ကax Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	РН	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
		water/gel	_	<u> </u>							
1279	2052	OTHER : Fresh water/cut brine	8.3	9.2							
2052	7982	OTHER : Cut brine	8.6	9.2							

Well Name: OSAGE BOYD 15 FEDERAL COM Well Number: 13H

# Section 6 - Test, Logging, Coring

#### List of production tests including testing procedures, equipment and safety measures:

A mud logger will be used from GL to TD. Samples will be collected every 10' in the lateral pay zone.

No electric logs are planned at this time.

List of open and cased hole logs run in the well:

**MUDLOG** 

Coring operation description for the well:

No core or drill stem test is planned.

### Section 7 - Pressure

Anticipated Bottom Hole Pressure: 1087 Anticipated Surface Pressure: 527.32

Anticipated Bottom Hole Temperature(F): 108

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geoharzards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

Osage\_13H\_H2S\_Plan\_20181106114526.pdf

#### **Section 8 - Other Information**

Proposed horizontal/directional/multi-lateral plan submission:

Osage\_13H\_Horizontal\_Drill\_Plan\_20181106114549.pdf


Other proposed operations facets description:

Other proposed operations facets attachment:

Osage\_13H\_Drill\_Plan\_20181106114559.pdf
Osage\_13H\_Contingency\_Plan\_20181106114605.pdf

Other Variance attachment:





# **Pressure Testing**

- a. All testing to be done with 3<sup>rd</sup> party testing crews
- b. All tests should be done for each BOP/Valve/Choke Manifold:
  - 1. Recorded for 10 minutes on low pressure (500 psi)
  - 2. Recorded for 10 minutes on high pressure (3000 psi)
  - 3. All BOP testing will be completed with a test plug in place in wellhead
- c. After BOP testing is complete, test casing (without test plug) to 2000 psi for 30 minutes
- d. Company representative to email all copies of all plots to Drilling Engineer as well as save in the well file.
- e. BOP's shall be function tested every day.


# Gas Buster Operation

- a. Flow should be directed to pits unless choke is needed to control gas
- b. Adjustable choke to adjusted only by Percussion Rep on location
- c. Flare should remain burning (pilot lit) anytime fluid is going through gas buster
- d. Choke needs to be monitored to not overrun gas buster



# Nipple-Up

- a. Raise stack and center over the wellhead
- b. Install DSA and ring gaskets
- c. Lower stack onto DSA
- d. Torque DSA flange bolts in a star pattern to the specified torque
- e. Verify BOP is centered to the rotary table
- f. Install rotating head
- g. Install hydraulic lines to BOP
- h. Verify manifold line-up
- i. Test BOP & manifold





# **Casing Design Criteria and Load Case Assumptions**

# Percussion Petroleum Operating, LLC. 919 Milam Street, Suite 2475 Houston, TX 77002

#### Lakewood Federal Com horizontal Wells

#### 1. Collapse: $DF_c=1.125$

- a. Full Internal Evacuation: Collapse force equal to the mud gradient in which the casing will be run (0.65 psi/ft). The effects of axial load on collapse will be considered.
- b. Cementing: Collapse force equal to the gradient of planned cement slurries to planned depths and minimum mud gradient in which the casing will be run above that (0.65 psi/ft) and an internal force equal to mud gradient of displacement fluid (0.43 psi/ft)

#### 2. Burst: DF<sub>B</sub>=1.125

- a. Pressure Test: psi casing test with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.
- b. Injection Down Casing: psi surface injection pressure plus an internal pressure gradient of 0.65 psi/ft with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.

#### 3. Tensile: DF<sub>T</sub>=1.8

a. Overpull: A downward force of 100,000 lbs is applied at the shoe along with the weight of the casing string utilizing the effects of buoyancy (10.5 ppg).

			4	. Surfa	ace Casing F	Program			
Casing Size (in)	Weight (ppf)	Grade	Connection	ID	ID (drift)	Collapse (psi)	Burst (psi)	Tension (1,000 lbs)	Capacity (bbl/ft)
9-5/8"	36	J-55	STC	8.921	8.765	2,020	3,520	394	0.0773
				Saf	ety Factors				
	API Rec. SF	ACTUAL SF	Case		External Fluids		In	ternal Fluids	3
Collapse	1.125	3.30	Lost Circula	tion	Mu	ıd		None	
Burst	1.125	1.46	Plug Bum	p	Green Cerr surf pre	1	Displac	cement Fluid	I/Mud
Tension	1.8	2.80	100 klbs Ove	erpull	Mu	ıd		Mud	

Buoyed Casing Weight: 40,798 lbs (assuming 8.4 ppg fluid and 1,300' casing-worst case scenario)



			Pro	duction	n Casing Pro	gram			- "
Casing Size (in)	Weight (ppf)	Grade	Connection	ID	ID (drift)	Collapse (psi)	Burst (psi)	Tension (1,000 lbs)	Capacity (bbl/ft)
7"	32	L-80	BTC	6.094	5.969	8,600	9,060	745	0.0361
5-1/2"	17	L-80	BTC	4.892	4.767	6,280	7,740	348	0.0232
				Safe	ety Factors				
	API	ACTUAL	Case		Externa	Fluids	ln:	ternal Fluids	;
	Rec. SF	SF							
Collapse	1.125	3.75	Lost Circula	tion	Mu	ıd		None	
Burst	1.125	2.47	Plug Bum	р	Green Cem	ent + 2ksi	Displac	ement Fluic	l/Mud
					surf pre	ssure			•
Tension	1.8	2.29	100 klbs Ove	rpull	Mu	d		Mud	

Buoyed Casing Weight: 86,522 lbs (assuming 8.4 ppg fluid and 3,500' TVD-worst case scenario)



# **Casing Design Criteria and Load Case Assumptions**

# Percussion Petroleum Operating, LLC. 919 Milam Street, Suite 2475 Houston, TX 77002

#### Lakewood Federal Com horizontal Wells

#### 1. Collapse: DF<sub>C</sub>=1.125

- a. Full Internal Evacuation: Collapse force equal to the mud gradient in which the casing will be run (0.65 psi/ft). The effects of axial load on collapse will be considered.
- b. Cementing: Collapse force equal to the gradient of planned cement slurries to planned depths and minimum mud gradient in which the casing will be run above that (0.65 psi/ft) and an internal force equal to mud gradient of displacement fluid (0.43 psi/ft)

#### 2. Burst: DF<sub>8</sub>=1.125

- a. Pressure Test: psi casing test with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.
- b. Injection Down Casing: psi surface injection pressure plus an internal pressure gradient of 0.65 psi/ft with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.

#### 3. Tensile: DF<sub>T</sub>=1.8

a. Overpull: A downward force of 100,000 lbs is applied at the shoe along with the weight of the casing string utilizing the effects of buoyancy (10.5 ppg).

			4	. Surfa	ace Casing F	Program			
Casing Size (in)	Weight (ppf)	Grade	Connection	ID	ID (drift)	Collapse (psi)	Burst (psi)	Tension (1,000 lbs)	Capacity (bbl/ft)
9-5/8"	36	J-55	STC	8.921	8.765	2,020	3,520	394	0.0773
			1000000	Safe	ety Factors				
	API Rec. SF	ACTUAL SF	Case		External Fluids		lr	iternal Fluids	3
Collapse	1.125	3.30	Lost Circula	tion	Mι	ıd		None	
Burst	1.125	1.46	Plug Bum	р	Green Cerr surf pre		si Displacement		I/Mud
Tension	1.8	2.80	100 klbs Ove	rpull	Mu	ıd	Mud		

Buoyed Casing Weight: 40,798 lbs (assuming 8.4 ppg fluid and 1,300' casing-worst case scenario)



	11-11-11		Pro	duction	n Casing Pro	gram			*
Casing Size (in)	Weight (ppf)	Grade	Connection	ID	ID (drift)	Collapse (psi)	Burst (psi)	Tension (1,000 lbs)	Capacity (bbl/ft)
7"	32	L-80	BTC	6.094	5.969	8,600	9,060	745	0.0361
5-1/2"	17	L-80	BTC	4.892	4.767	6,280	7,740	348	0.0232
				Safe	ety Factors				
	API	ACTUAL	Case		Externa	Fluids	In	ternal Fluids	3
	Rec. SF	SF							
Collapse	1.125	3.75	Lost Circula	tion	Mu	d		None	
Burst	1.125	2.47	Plug Bum	р	Green Cem surf pre		Displac	cement Fluid	l/Mud
Tension	1.8	2.29	100 klbs Ove	rpull	Mu	id ·		Mud	

Buoyed Casing Weight: 86,522 lbs (assuming 8.4 ppg fluid and 3,500' TVD-worst case scenario)



# **Casing Design Criteria and Load Case Assumptions**

# Percussion Petroleum Operating, LLC. 919 Milam Street, Suite 2475 Houston, TX 77002

#### Lakewood Federal Com horizontal Wells

### 1. Collapse: DF<sub>c</sub>=1.125

- a. Full Internal Evacuation: Collapse force equal to the mud gradient in which the casing will be run (0.65 psi/ft). The effects of axial load on collapse will be considered.
- b. Cementing: Collapse force equal to the gradient of planned cement slurries to planned depths and minimum mud gradient in which the casing will be run above that (0.65 psi/ft) and an internal force equal to mud gradient of displacement fluid (0.43 psi/ft)

### 2. Burst: DF<sub>B</sub>=1.125

- a. Pressure Test: psi casing test with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.
- b. Injection Down Casing: psi surface injection pressure plus an internal pressure gradient of 0.65 psi/ft with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.

### 3. Tensile: DF<sub>T</sub>=1.8

a. Overpull: A downward force of 100,000 lbs is applied at the shoe along with the weight of the casing string utilizing the effects of buoyancy (10.5 ppg).

			4	. Surfa	ace Casing I	Program			
Casing Size (in)	Weight (ppf)	Grade	Connection	ID	ID (drift)	Collapse (psi)	Burst (psi)	Tension (1,000 lbs)	Capacity (bbl/ft)
9-5/8"	36	J-55	STC	8.921	8.765	2,020	3,520	394	0.0773
				Saf	ety Factors				
	API Rec. SF	ACTUAL SF	Case		Externa	l Fluids	Internal Fluids		
Collapse	1.125	3.30	Lost Circula	tion	Mu	ıd		None	
Burst	1.125	1.46	Plug Bum	р	Green Cerr surf pre		ksi Displacement Fluid/Mu		I/Mud
Tension	1.8	2.80	100 klbs Ove	rpull	Mι	ıd		Mud	

Buoyed Casing Weight: 40,798 lbs (assuming 8.4 ppg fluid and 1,300' casing-worst case scenario)



			Pro	duction	n Casing Pro	gram			
Casing Size (in)	Weight (ppf)	Grade	Connection	ID	ID (drift)	Collapse (psi)	Burst (psi)	Tension (1,000 lbs)	Capacity (bbl/ft)
7"	32	L-80	BTC	6.094	5.969	8,600	9,060	745	0.0361
5-1/2"	17	L-80	BTC	4.892	4.767	6,280	7,740	348	0.0232
				Safe	ety Factors				
	API	ACTUAL	Case		External	Fluids	ln:	ternal Fluids	3
	Rec.	SF							
	SF								
Collapse	1.125	3.75	Lost Circula	tion	Mu	d		None	
Burst	1.125	2.47	Plug Bum	р	Green Cem	ent + 2ksi	Displac	ement Fluic	I/Mud
					surf pre	essure			
Tension	1.8	2.29	100 klbs Ove	rpull	Mu	d		Mud	

Buoyed Casing Weight: 86,522 lbs (assuming 8.4 ppg fluid and 3,500' TVD-worst case scenario)



# Casing Design Criteria and Load Case Assumptions

# Percussion Petroleum Operating, LLC. 919 Milam Street, Suite 2475 Houston, TX 77002

#### **Lakewood Federal Com horizontal Wells**

### 1. Collapse: DF<sub>c</sub>=1.125

- a. Full Internal Evacuation: Collapse force equal to the mud gradient in which the casing will be run (0.65 psi/ft). The effects of axial load on collapse will be considered.
- b. Cementing: Collapse force equal to the gradient of planned cement slurries to planned depths and minimum mud gradient in which the casing will be run above that (0.65 psi/ft) and an internal force equal to mud gradient of displacement fluid (0.43 psi/ft)

#### 2. Burst: DF<sub>B</sub>=1.125

- a. Pressure Test: psi casing test with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.
- b. Injection Down Casing: psi surface injection pressure plus an internal pressure gradient of 0.65 psi/ft with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.

### 3. Tensile: DF<sub>T</sub>=1.8

a. Overpull: A downward force of 100,000 lbs is applied at the shoe along with the weight of the casing string utilizing the effects of buoyancy (10.5 ppg).

			4	. Surfa	ace Casing F	rogram			
Casing Size (in)	Weight (ppf)	Grade	Connection	ID	ID (drift)	Collapse (psi)	Burst (psi)	Tension (1,000 lbs)	Capacity (bbl/ft)
9-5/8"	36	J-55	STC	8.921	8.765	2,020	3,520	394	0.0773
				Safe	ety Factors				
	API Rec. SF	ACTUAL SF	Case		External Fluids		In	ternal Fluids	3
Collapse	1.125	3.30	Lost Circula	tion	Mι	d		None	
Burst	1.125	1.46	Plug Bum	р	Green Cem surf pre		Displac	cement Fluid	l/Mud
Tension	1.8	2.80	100 klbs Ove	rpull	Mu	d		Mud	

Buoyed Casing Weight: 40,798 lbs (assuming 8.4 ppg fluid and 1,300' casing-worst case scenario)



			Pro	duction	Casing Pro	gram			
Casing Size (in)	Weight (ppf)	Grade	Connection	ID	ID (drift)	Collapse (psi)	Burst (psi)	Tension (1,000 lbs)	Capacity (bbl/ft)
7"	32	L-80	BTC	6.094	5.969	8,600	9,060	745	0.0361
5-1/2"	17	L-80	BTC	4.892	4.767	6,280	7,740	348	0.0232
				Safe	ety Factors				
	API Rec. SF	ACTUAL SF	Case		External	Fluids	In	ternal Fluids	6
Collapse	1.125	3.75	Lost Circula	tion	Mu	d		None	
Burst	1.125	2.47	Plug Bum	р	Green Cem surf pre		Displac	ement Fluic	I/Mud
Tension	1.8	2.29	100 klbs Ove	rpull	Mu	d		Mud	

Buoyed Casing Weight: 86,522 lbs (assuming 8.4 ppg fluid and 3,500' TVD-worst case scenario)



# **Casing Design Criteria and Load Case Assumptions**

# Percussion Petroleum Operating, LLC. 919 Milam Street, Suite 2475 Houston, TX 77002

### Lakewood Federal Com horizontal Wells

#### 1. Collapse: DF<sub>C</sub>=1.125

- a. Full Internal Evacuation: Collapse force equal to the mud gradient in which the casing will be run (0.65 psi/ft). The effects of axial load on collapse will be considered.
- b. Cementing: Collapse force equal to the gradient of planned cement slurries to planned depths and minimum mud gradient in which the casing will be run above that (0.65 psi/ft) and an internal force equal to mud gradient of displacement fluid (0.43 psi/ft)

### 2. Burst: DF<sub>B</sub>=1.125

- a. Pressure Test: psi casing test with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.
- b. Injection Down Casing: psi surface injection pressure plus an internal pressure gradient of 0.65 psi/ft with an external force equal to the mud gradient in which the casing will be run (0.65 psi/ft), which is a more conservative backup force than pore pressure.

### 3. Tensile: DF<sub>T</sub>=1.8

a. Overpull: A downward force of 100,000 lbs is applied at the shoe along with the weight of the casing string utilizing the effects of buoyancy (10.5 ppg).

			4	. Surfa	ace Casing F	rogram			
Casing Size (in)	Weight (ppf)	Grade	Connection	ID	ID (drift)	Collapse (psi)	Burst (psi)	Tension (1,000 lbs)	Capacity (bbl/ft)
9-5/8"	36	J-55	STC	8.921	8.765	2,020	3,520	394	0.0773
				Saf	ety Factors				
	API Rec. SF	ACTUAL SF	Case		Externa	Fluids	Ir	ternal Fluids	3
Collapse	1.125	3.30	Lost Circula	tion	Mu	ıd		None	
Burst	1.125	1.46	Plug Bum	Plug Bump Green Cement + 2ksi Displacement Flui surf pressure		I/Mud			
Tension	1.8	2.80	100 klbs Ove	rpuli	Mu	ıd		Mud	

Buoyed Casing Weight: 40,798 lbs (assuming 8.4 ppg fluid and 1,300' casing-worst case scenario)



			Pro	duction	n Casing Pro	ogram		<del></del>	
Casing Size (in)	Weight (ppf)	Grade	Connection	ID	ID (drift)	Collapse (psi)	Burst (psi)	Tension (1,000 lbs)	Capacity (bbl/ft)
7"	32	L-80	BTC	6.094	5.969	8,600	9,060	745	0.0361
5-1/2"	17	L-80	BTC	4.892	4.767	6,280	7,740	348	0.0232
				Safe	ety Factors				
	API	ACTUAL	Case		External	Fluids	In	ternal Fluids	3
	Rec.	SF							
	SF								
Collapse	1.125	3.75	Lost Circula	tion	Mu	ıd		None	
Burst	1.125	2.47	Plug Bum	р	Green Cem	ent + 2ksi	Displac	ement Fluid	I/Mud
					surf pre	essure			
Tension	1.8	2.29	100 klbs Ove	rpull	Mu	ıd		Mud	

Buoyed Casing Weight: 86,522 lbs (assuming 8.4 ppg fluid and 3,500' TVD-worst case scenario)



# **Hydrogen Sulfide Drilling Operations Plan**

# Percussion Petroleum Operating, LLC. 919 Milam Street, Suite 2475 Houston, TX 77002

- 1. H<sub>2</sub>S Safety Instructions to the following:
  - Characteristics of H<sub>2</sub>S.
  - Physical effects and hazards.
  - Principal and operation of H<sub>2</sub>S detectors, warning system and briefing areas.
  - Evacuation procedures, routes and First Aid.
  - Proper use of safety equipment and life support systems.
  - Essential personnel meeting medical evaluation criteria will receive additional training on the proper use of 30 min pressure demand air packs.

### 2. H<sub>2</sub>S Detection & Alarm Systems:

- H<sub>2</sub>S sensor/detectors to be located on the drilling rig floor, in the base of the sub structure/cellar area, on the mud returns pits by the shale shaker. Additional H<sub>2</sub>S monitors may be placed as deemed necessary.
- An audio alarm system will be installed on the derrick, the floor, and in the doghouse.

#### 3. Windsocks and Wind Streamers:

- Windsocks at mud pit area should be high enough to be visible.
- Windsock on the rig floor/top of doghouse should be high enough to be visible.

### 4. Condition Flags & Signs:

- Warning sign on access road to location
- Flags to be displayed on sign at entrance to location
  - i. Green Flag Normal Safe Operation Condition
  - ii. Yellow Flag Potential Pressure and Danger
  - iii. Red Flag Danger (H<sub>2</sub>S present in dangerous concentrations) Only H<sub>2</sub>S trained personnel admitted on location

### 5. Well Control Equipment:

See attached APD



#### 6. Communications:

- While working under masks, chalkboards will be used for communications
- Hand signals will be used where chalk board is inappropriate
- Two-way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at drilling foreman's trailer or living quarters.

### 7. Drilling Stem Testing:

- No Drill Stem Tests or hole coring is planned at this time.
- 8. Drilling contractor supervisor will be required to be familiar with the effects H<sub>2</sub>S has on tubular goods and other mechanical equipment.
- If H2S is encountered, mud system will be altered if necessary to maintain control of formation.
   A mud gas separator will be brought into service along with H2S scavenger chemicals if necessary.

### 10. Emergency Contacts:

Emergency Contact Information H2S Contingency Plan				
Precussion Petroleum Operating, LLC	713-518-1331			
Key Parties at Percussion Petroleum		Office	Mobile	Email
Lelan J Anders	Vice President of Operations	713-429-1291	281-908-1752	Lelan@PercussionPetroleum.com
Lupe Carrillo	Chief Operating Officer	713-589-9509	832-776-1869	Lupe@PercussionPetroleum.com
John H. Campbell III	Chief Executive Officer	713-589-4683	936-718-6488	John@PercussionPetroleum.com

Artesia; New Mexico:	
Ambulance	911
State Police	575-746-2703
City Police	575-746-2703
Sheriff's Office	575-746-9888
Fire Department	575-746-2701
Local Emergency Planning Committee	575-746-2122
New Mexico Oil Conservation Division	575-748-1283

Carlsbad, New Mexico:	
Ambulance	911
State Police	575-885-3137
City Police	575-885-2111
Sheriff's Office	575-887-7551
Fire Department	575-887-3798
Local Emergency Planning Committee	575-887-6544
New Mexico Oil Conservation Division	575-887-6544





Santa Fe, New Mexico:	
New Mexico Emergency Response Commission	505-476-9600
New Mexico Emergency Response Commission (24 hr)	505-827-9126
New Mexico State Emergency Operations Center	505-476-9635


Federal Contacts:	
Carlsbad BLM Office	575-234-5972
National Emergency Response Center (Washington, DC)	800-424-8802

Medical:	
Flight for Life - Lubbock, TX	806-743-9911
AeroCare - Lubbock, TX	806-747-8923
Med Flight Air Ambulance - Albuquerque, NM	505-842-4433
SB Air Med Service - Albuquerque, NM	505-842-4949

Well Control /Other:	
Wild Well Control	281-784-4700
Boots & Coots IWC	800-256-9688
B.J. Services	575-746-3569
Halliburton	575-746-2757











Company: Project:

Project

Percussion Petroleum, LLC Eddy County, NM

Site: Osage Boyd 15 FED COM Well: #13H

Wellbore: ОН Design: Plan #1

Eddy County, NM

Map System: US State Plane 1983

North American Datum 1983 Geo Datum: New Mexico Eastern Zone Map Zone:

Site Osage Boyd 15 FED COM

Site Position: From: Position Uncertainty:

0.00 usft

Northing:

Easting: Slot Radius:

Wellhead Elevation:

600,962.30 usft 496,514.50 usft 13.200 in

Latitude:

Local Co-ordinate Reference

Survey Calculation Method

North Refere

System Datum:

Longitude: **Grid Convergence:** 

32.652008 -104,478969 -0.08

Well #13H - Slot 13

Well Position +N/-S +E/-W **Position Uncertainty** 

0.00 usft 0.00 usft 0.00 usft

Northing: 600,961.60 usfi Easting:

497.012.60 usft

Latitude: Longitude:

Well #13H - Slot 13

Minimum Curvature

WBDS\_SQL\_2

Mean Sea Level

Grid

RKB = 17' @ 3485.00usft

RKB = 17' @ 3485.00usft

32.652008 -104.477351

Wellbore ОН

Ground Level:

3,468.00 usft

Model Name Sample Date Magnetics

Plan #1 Design

Audit Notes:

Tie On Depth:

0.00

Vertical Section: Depth From (TVD) (usft) 0.00

0.00

Survey Tool Program Date 07/19/18

From To (usft) Survey (Wellbore) 0.00 7,982.18 Plan #1 (OH)

Tool Name

OWSG MWD + IGRF or WMM

07/19/18 10:12:09AM

Page 2

MWD+IGRF





Company: Percussion Petroleum, LLC
Broject: Eddy County, NM
Site: Osage Boyd 15 FED COM
Well: #13H
Wellbore: OH
Design: Plan #1

Local Coordinate Reference: Well #13H - Slot 13

TVD/Reference: RKB = 17' @ 3485.00usft

MDReference: Grid

North Reference: Grid

Survey Calculation Method: Minimum Curvature

Darabase: WBDS\_SQL\_2

المعادد المساعد الماسانية			12. 12. 12. 12. 12. 12. 12. 12. 12. 12.		SHEET THE				William China and Land Annual	والمرابع والقابعة المستق
Planned Survey	egun e tra to an ancher	THE RESERVE AND PROPERTY.	the same and the same to be a set	arani kumu manda aran aran	LINE STREET, N. S. LINES, SUPERIOR	Appendix of the second	The second secon	CONTRACTOR OF SUSSEC	الله المالية ا	All reserved and the second
		以为"五百里"				量的工程的			<b>经产品</b>	
MD	lnc Azi	(azimuth)	TVD - F	N/S						Face
(usft) 0.00	0.00		1 To 1			The state of the s	200	Tananan an	/100ft)	(1)
100.00		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
350.00	0.00	0.00	350.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	1.00	1.53	400.00	0.44	0.01	0.44	2.00	2.00	0.00	1.53
500.00	3.00	1.53	499.93	3.92	0.11	3.92	2.00	2.00	0.00	0.00
600.00	5.00	1.53	599.68	10.90	0.29	10.90	2.00	2.00	0.00	0.00
695.29	6.91	1.53	694.45	20.78	0.56	20.78	2.00	2.00	0.00	0.00
700.00	6.91	1.53	699.13	21.34	0.57	21.34	0.00	0.00	0.00	0.00
800.00	6.91	1.53	798.40	33.36	0.89	33.36	0.00	0.00	0.00	0.00
900.00	6.91	1.53	897.68	45.38	1.22	45.38	0.00	0.00	0.00	0.00
1,000.00	6.91	1.53	996.95	57.40	1.54	57.40	0.00	0.00	0.00	0.00
1,100.00	6.91	1.53	1,096.23	69.42	1.86	69.42	0.00	0.00	0.00	0.00
1,200.00	6.91	1.53	1,195.50	81.44	2.18	81.44	0.00	0.00	0.00	0.00
1,300.00	6.91	1.53	1,294.78	93.46	2.50	93.46	0.00	0.00	0.00	0.00
1,400.00	6.91	1.53	1,394.05	105.48	2.83	105.48	0.00	0.00	0.00	0.00
1,500.00	6.91	1.53	1,493.33	117.50	3.15	117.50	0.00	0.00	0.00	0.00
1,600.00	6.91	1.53	1,592.60	129.52	3.47	129.52	0.00	0.00	0.00	0.00
1,700.00	6.91	1.53	1,691.88	141.54	3.79	141.54	0.00	0.00	0.00	0.00
1,800.00	6.91	1.53	1,791.15	153:55	4.11	153.56	0.00	0.00	0.00	0.00
1,900.00	6.91	1.53	1,890.42	165.57	4.43	165.58	0.00	0.00	0.00	0.00
2,000.00	6.91	1.53	1,989.70	177.59	4.76	177.60	0.00	0.00	0.00	0.00
2,051.58	6.91	1.53	2,040.91	183.79	4.92	183.80	0.00	0.00	0.00	0.00
2,100.00	11.75	0.82	2,088.67	191.64	5.07	191.64	10.00	10.00	-1.47	-1.72
2,150.00	16.75	0.51	2,137.12	203.94	5.21	203.94	10.00	10.00	-0.62	-1.02
2,200.00	21.75	0.34	2,184.31	220.41	5.33	220.41	10.00	10.00	-0.34	-0.72

07/19/18 10:12:09AM

Page 3





Company: Percussion Petroleum, LLC
Project: Project: Project: Percussion Petroleum, LLC
Project: Percussion Petroleum, LLC
Project: Percussion Petroleum, LLC
Petroleum, L

III -> SLocal Co-ordinate Reference:
ITVD Reference:
MD Reference:
North Reference:
Survey | Calculation Method:
Database:

Well #13H - Slot 13 RKB = 17' @ 3485.00usft RKB = 17' @ 3485.00usft

Minimum Curvature

WBDS\_SQL\_2

									والمتوار ومنهوا والمسية المثار بساويسان	and the same
Planned Survey	Calleria representation	AND THE RESIDENCE OF THE PROPERTY OF			en a especial contract of the		nate was A Chicago State Drugge.	OBSTANCE OF THE PARTY OF THE PARTY.	THE PARTY OF THE P	
MD	Inc Azi	(azimuth)	TVD	N/S V F E		<b>是数等系</b>				<b>新聞歌歌</b>
(usft)			(usft)			V Sec		Build // /100ft)	Turn %/100ft)	Face /
2,250.00	26.75	0.24	2,229.88	240.94	5.43	240.94	10.00	10.00	-0.22	-0.56
2,300.00	31.75	0.16	2,273.50	265.36	5.51	265.36	10.00	10.00	-0.15	-0.46
2,350.00	36.75	0.10	2,314.82	293.48	5.58	293.49	10.00	10.00	-0.11	-0.39
2,400.00	41.75	0.06	2,353.53	325.11	5.62	325.11	10.00	10.00	-0.09	-0.35
2,450.00	46.74	0.02	2,389.33	359.98	5.64	359.98	10.00	10.00	-0.07	-0.31
2,500.00	51.74	359.99	2,421.96	397.84	5.64	397.85	10.00	10.00	-0.06	-0.28
2,550.00	56.74	359.96	2,451.17	438.41	5.62	438.41	10.00	10.00	-0.05	-0.26
2,600.00	61.74	359.94	2,476.73	481.36	5.59	481.37	10.00	10.00	-0.05	-0.25
2,650.00	66.74	359.91	2,498.45	526.38	5.53	526.38	10.00	10.00	-0.04	-0.24
2,700.00	71.74	359.89	2,516.16	573.12	5.45	573.12	10.00	10.00	-0.04	-0.23
2,750.00	76.74	359.87	2,529.74	621.23	5.35	621.23	10.00	10.00	-0.04	-0.22
2,800.00	81.74	359.85	2,539.06	670.33	5.23	670.34	10.00	10.00	-0.04	-0.21
2,850.00	86.74	359.84	2,544.08	720.06	5.10	720.07	10.00	10.00	-0.04	-0.21
2,882.55	90.00	359.82	2,545.00	752.60	5,00	752.60	10.00	10.00	-0.04	-0.21
. 2,900.00	90.00	359.82	2,545.00	770.05	4.95	770.05	0.00	0.00	0.00	0.00
3,000.00	90.00	359.82	2,545.00	870.05	4.64	870.05	0.00	0.00	0.00	0.00
3,100.00	90.00	359.82	2,545.00	970.05	4.33	970.05	0.00	0.00	0.00	0.00
3,200:00	90.00	359.82	2,545.00	1,070.05	4.03	1,070.05	0.00	0.00	0.00	0.00
3,300.00	90.00	359.82	2,545.00	1,170.05	3.72	1,170.05	0.00	0.00	0.00	0.00
3,400.00	90.00	359.82	2,545.00	1,270.04	3.41	1,270.05	0.00	0.00	0.00	0.00
3,500.00	90.00	359.82	2,545.00	1,370.04	3.11	1,370.05	0.00	0.00	0.00	0.00
3,600.00	90.00	359.82	2,545.00	1,470.04	2.80	1,470.05	0.00	0.00	0.00	0.00
3,700.00	90.00	359.82	2,545.00	1,570.04	2.49	1,570.04	0.00	0.00	0.00	0.00
3,800.00	90.00	359.82	2,545.00	1,670.04	2.19	1,670.04	0.00	0.00	0.00	0.00
3,900.00	90.00	359.82	2,545.00	1,770.04	1.88	1,770.04	0.00	0.00	0.00	0.00
4,000.00	90.00	359.82	2,545.00	1,870.04	1.57	1,870.04	0.00	0.00	0.00	0.00
4,100.00	90.00	359.82	2,545.00	1,970.04	1.27	1,970.04	0.00	0.00	0.00	0.00

07/19/18 10:12:09AM

Page 4





	4.5									图
Company: Project: Site: Well: Wellbore: Design:	Percussion Petrolet Eddy County, NM Osage Boyd 15 FE #13H OH Plan #1					Local Co-ordina TVD Reference: MD Reference: North Reference Survey Calculat Database:		Well #13H - Slot 1 RKB = 17' @ 348! RKB = 17' @ 348! Grid Minimum Curvatul WBDS_SQL_2	5.00usft 5.00usft	
Planned Surve	У			_ sale to serve at the					<del> </del>	
MD (usft)	lnc (°)	Azi (azimuth)	TVD (usft)	N/S المراجعة	E/W (usft)	V. Sec (usft)	DLeg: (°/100ft)	Build (°/100ft)	Turn (°/100ft)	TFace (°)
4,200.0	90.00	359.82	2,545.00	2,070.04	0.96	2,070.04	0.00	0.00	0.00	0.00
4,300.0	00.00	359.82	2,545.00	2,170.04	0.65	2,170.04	0.00	0.00	0.00	0.00
4,400.0	00.00	359.82	2,545.00	2,270.04	0.35	2,270.04	0.00	0.00	0.00	0.00
4,500.0	90.00	359.82	2,545.00	2,370.04	0.04	2,370.04	0.00	0.00	0.00	0.00
4,600.0	00.00	359.82	2,545.00	2,470.04	-0.27	2,470.04	0.00	0.00	0.00	0.0
4,700.0	90.00	359.82	2,545.00	2,570.04	-0.58	2,570.04	0.00	0.00	0.00	0.0
4,800.0	00.00	359.82	2,545.00	2,670.04	-0.88	2,670.04	0.00	0.00	0.00	0.0
4,900.0	00 90.00	359.82	2,545.00	2,770.04	-1.19	2,770.04	0.00	0.00	0.00	0.0
5,000.0	00 90.00	359.82	2,545.00	2,870.04	-1.50	2,870.04	0.00	0.00	0.00	0.0
5,100.0	00 90.00	359.82	2,545.00	2,970.04	-1.80	2,970.03	0.00	0.00	0.00	0.0
5,200.0	90.00	359.82	2,545.00	3,070.04	-2.11	3,070.03	0.00	0.00	0.00	0.00
5,300.0	00.00	359.82	2,545.00	3,170.04	-2.42	3,170.03	0.00	0.00	0.00	0.0
5,400.0	00.00	359.82	2,545.00	3,270.04	-2.72	3,270.03	0.00	0.00	0.00	0.0
5,500.0	00.00	359.82	2,545.00	3,370.03	-3.03	3,370.03	0.00	0.00	0.00	0.0
5,600.0	90.00	359.82	2,545.00	3,470.03	-3.34	3,470.03	0.00	0.00	0.00	0.0
5,700.0	90.00	359.82	2,545.00	3,570.03	-3.64	3,570.03	0.00	0.00	0.00	0.0
5,800.0	00.00	359.82	2,545.00	3,670.03	-3.95	3,670.03	0.00	0.00	0.00	0.00
5,900.0	90.00	359.82	2,545.00	3,770.03	-4.26	3,770.03	0.00	0.00	0.00	0.0
6,000.0	90.00	359.82	2,545.00	3,870.03	-4.56	3,870.03	0.00	0.00	0.00	0.0
6,100.0	90.00	359.82	2,545.00	3,970.03	-4.87	3,970.03	0.00	0.00	0.00	0.0
6,200.0	90.00	359.82	2,545.00	4,070.03	-5.18	4,070.03	0.00	0.00	0.00	0.0
6,300.0	90.00	359.82	2,545.00	4,170.03	-5.48	4,170.03	0.00	0.00	0.00	0.0
6,400.0	90.00	359.82	2,545.00	4,270.03	-5.79	4,270.03	0.00	0.00	0.00	0.00
6,500.0	90.00	359.82	2,545.00	4,370.03	-6.10	4,370.02	0.00	0.00	0.00	0.0
6,600.0	90.00	359.82	2,545.00	4,470.03	-6.40	4,470.02	0.00	0.00	0.00	0.00
6,631.3	90.00	359.82	2,545.00	4,501.40	-6.50	4,501.39	0.00	0.00	0.00	0.00
6,700.0	00 91.27	0.35	2,544.24	4,570.02	-6.39	4,570.02	2.00	1.85	0.77	22.69

07/19/18 10:12:09AM

Page 5





Company: Project: Site: Well:

Percussion Petroleum, LLC Eddy County, NM Osage Boyd 15 FED COM

Wellbore:

`#13H

OH Design: Plan #1

lanned Survey		The second of th	TOTAL STREET, THE TANK OF THE PERSON OF THE		The state of the s		CONTRACTOR OF STREET	THE PERSON NAMED IN		•
MD (usft)	Inc (°)	Azi (azimuth)	TVD (usft)	N/S (usft)	E/W (usft)				Turn /100ft)	TFace
6,720.25	91.64	0.51	2,543.73	4,590.27	-6.24	4,590.26	2.00	1.85	0.77	22.6
6,800.00	91.64	0.51	2,541.45	4,669.98	-5.53	4,669.98	0.00	0.00	0.00	0.0
6,900.00	91.64	0.51	2,538.58	4,769.94	-4.64	4,769.93	0.00	0.00	0.00	0.0
7,000.00	91.64	0.51	2,535.72	4,869.89	-3.75	4,869.89	0.00	0.00	0.00	0.0
7,100.00	91.64	0.51	2,532.86	4,969.85	-2.86	4,969.84	0.00	0.00	0.00	0.0
7,200.00	91.64	0.51	2,530.00	5,069.80	-1.97	5,069.80	0.00	0.00	0.00	0.0
7,300.00	91.64	0.51	2,527.14	5,169.76	-1.08	5,169.75	0.00	0.00	0.00	0.0
7,400.00	91.64	0.51	2,524.27	5,269.71	-0.19	5,269.71	0.00	0.00	0.00	0.0
7,500.00	91.64	0.51	2,521.41	5,369.67	0.70	5,369.67	0.00	0.00	0.00	0.
7,600.00	91.64	0.51	2,518.55	5,469.62	1.59	5,469.62	0.00	0.00	0.00	0.
7,700.00	91.64	0.51	2,515.69	5,569.58	2.48	5,569.58	0.00	0.00	0.00	0.
7,800.00	91.64	0.51	2,512.83	5,669.53	3.37	5,669.53	0.00	0.00	0.00	0.0
7,860.25	91.64	0.51	2,511.10	5,729.75	3.90	5,729.75	0.00	0.00	0.00	0.0
7,900.00	90.88	0.29	2,510.23	5,769.49	4.18	5,769.49	2.00	-1.92	-0.55	-163.
7,957.09	89.78	359.97	2,509.90	5,826.58	4.31	5,826.58	2.00	-1.92	-0.55	-163.
7,982.21	89.78	359.97	2,510.00	5,851.70	4.30	5,851.70	0.00	0.00	0.00	0.

		· · · · · · · · · · · · · · · · · · ·
1		
I Checked By:	Approved By:	Doto:
Checked by.	Approved By:	Date:
·		

07/19/18 10:12:09AM

Page 6



# Percussion Petroleum, LLC

Eddy County, NM Osage Boyd 15 FED COM #13H

OH Plan #1

# **Anticollision Report**

19 July, 2018







Company:

Percussion Petroleum, LLC

Project:

Eddy County, NM

Reference Site:

Osage Boyd 15 FED COM

Site Error:

0.00 usft

Reference Well: Well Error:

Reference

Filter type:

(usft)

#13H 0.00 usft Reference Wellbore OH

Local Co-ordinate Reference:

Well #13H - Slot 13

TVD Reference:

RKB = 17' @ 3485.00usft

MD Reference:

RKB = 17' @ 3485.00usft

North Reference:

Survey Calculation Method: Output errors are at

Minimum Curvature 2.00 sigma

Database:

WBDS\_SQL\_2 Reference Datum

Reference Design: Plan #1

Offset TVD Reference:

Plan #1

NO GLOBAL FILTER: Using user defined selection & filtering criteria

Interpolation Method: Stations

Error Model:

Depth Range:

0.00 to 7,982.21usft

Scan Method:

**ISCWSA** Closest Approach 3D

Results Limited by:

Maximum center-center distance of 1,000.00 us

**Error Surface:** 

Pedal Curve

Warning Levels Evaluated at:

2.00 Sigma

Casing Method:

Not applied

Survey Tool Program,

Date 07/19/18

Erom To

(usft) Survey (Wellbore)

0.00

7,982.18 Plan#1 (OH)

MWD+IGRF

OWSG MWD + IGRF or WMM

Summary	n describeration with the filter	I * ; * Tipleken wenne og at at tre	по- и пинадали пискатива в	MAINT TOTAL SEE SEEDING	B Print Statement of Statement	ABOTE BARON ON SETTERAL OR
	発展を設定され	場はコー			I HAVE I	<b>化工程程序</b>
	, ∉⊷t∵ Reference	Offset	∵`Distai	nce L	和1997、1999年18	是是是不到
	Measured:	Measured	Between	Between: S	Separation: 👉 🚐 🗛	Varning
Site Name	Depth	Depth :	Centres	Ellipses	Factor	
Offset Well Wellbore - Design	€(usft).	(üsft)	(usft)	(usft)		
Osage Boyd 15 FED COM	· · · · · · · · · · · · · · · · · · ·		1 9/192297 17.0	e u laga imaguny lamanan.	Tablidi in lan Atha in 1842 - La 1844 -	and the state of t
#12H - OH - Plan #1	350.00	350.00	19.10	17.01	9.140 CC	
#12H - OH - Plan #1	400.00	399.83	19.34	16.89	7.903 ES	
#12H - OH - Plan #1	7,982.21	8,326.39	382.37	257.56	3.064 SF	
#14H - OH - Plan #1	350.00	350.00	20.80	18.71	9.953 CC	
#14H - OH - Plan #1	400.00	399.81	21.02	18.57	8.590 ES	
#14H - OH - Plan #1	7,982.21	8,185.08	287.14	140.09	1,953 SF	
	·					

Offset D	esign - ,	Osage	Boyd 15	FED COM	- #12H	- OH - Pla	n #1 Offset Wellbor L+N/S	CHANGE COLL STREET AND STREET AND	SHOW THE PARTY	mata ret esta ataba	**********	C	offset Site Error:	0.00 usft
Survey Pro	gram: 0-M	WD+IGRF:	<b>第一节</b>		12/21	NATION AND ADDRESS OF THE PARTY.	The seat of		1.48	W. Buch	<b>公園野</b> 工業	1 - Late - 1 - 10	ffset Well Error:	0 00 นร์กเ
Refer	ence	Off	etel	Semi Major	Axis		Terror Mar		Dista	nce -	AND THE	3.02		- 11.
Measured:	Vertical	Measured	Vertical	Reference	Offset	Highside	Offset Wellbor	e Centre	Between	Between	Minimum :	Separation	Warning	
(usft)	(risft)	Lucht	Depth A	(iieft)	Tieff I	Flooriace	EdNS⊼ 1 3	+E/-W	Centres	Ellipses	Separation	Factor	行事等的	
<b>等模型:</b>	40 TE	7457	TO SELECT	是提供工工	THE PARTY	产业直接	Signature of the state of the s	(nzit)	- 1999	Riusit)	a logith for	工作工作等	RANGE OF STREET	1.47
0.00	0.00	0.00	0.00	0.00	0.00	-90.90	-0.30	-19.10	19.10					
100.00	100.00	100,00	100.00	0.15	0.15	-90.90	-0.30	-19.10	19.10	18.80	0.30	64.203		
200.00	200.00	200.00	200.00	0.51	0.51	-90.90	-0.30	-19.10	19.10	18.09	1.01	18.830		
300.00	300,00	300.00	300.00	0.87	0.87	-90.90	-0.30	-19.10	19.10	17.37	1.73	11.033		
350.00	350.00	350.00	350.00	1.04	1.04	-90.90	-0.30	-19.10	19.10	17.01	2.09	9.140 CC		
400.00	400.00	399.83	399.83	1.22	1.22	-92.60	0.07	-19.32	19.34	16.89	2.45	7.903 ES		
500,00	499.93	499.47	499.40	1.59	1.58	-93.83	3.04	-21.10	21.23	18.07	3.16	6.714		
600.00	599,68	599.02	598.71	1.95	1.94	-95.71	8.98	-24.66	25.04	21.15	3.89	6.439		
695.29	694.45	693.83	693.02	2.31	2.30	-97.65	17.34	-29.66	30.44	25.84	4.60	6.615		
700.00	699.13	701.46	697.69	2.33	2.33	-97.79	17.79	-29.93	30.74	26.09	4.65	6.612		
800.00	798.40	801.68	796.83	2.72	2.72	-100.24	27.52	-35,75	37.14	31.72	5.43	6.846		
900.00	897.68	901.89	895.97	3.12	3.12	-101.96	37.24	-41.57	43.59	37.37	6.21	7.014		}
1,000.00	996.95	1,002.11	995.11	3.52	3.52	-103.24	46.96	<b>-4</b> 7.39	50.06	43.05	7.01	7.140		
1,100.00	1,096.23	1,102.32	1,094.25	3.92	3.92	-104.22	56.6B	-53.21	56.56	48.74	7.81	7.238		
1,200.00	1,195.50	1,202.54	1,193.38	4.33	4.33	-105.01	66.40	-59.03	63.06	54.44	8.62	7.315		
1,300.00	1,294.78	1,302.75	1,292.52	4.74	4.73	-105.64	76.12	-64.85	69,58	60.15	9.43	7.378		j
1,400.00	1.394.05	1,402.97	1,391,66	5.16	5.14	-106.17	85.85	-70.67	76.11	CE 0C	40.04	7 420		
1,500.00	1,493.33	1,503.19	1,490,80	5.57	5.55					65.86	10.24	7.430		
1,600.00	1,493.33	1,603.40	1,490,80			-106.61	95.57	-76.49	82.64	71.58	11.06	7.474		ĺ
1	1,691.88			5.98	5.96	-106,99	105.29	-82.30	89.17	77.30	11.87	7.511		
1,700.00	1,091.00	1,703.62	1,689.08 1,788.22	6.40 6.81	6.37	-107.32	115.01	-88.12	95.71	83.02	12.69	7.543		
1,800.00	1,791.15	1,790.17	1,708.22	6.81	6.75	-107.60	124.73	-93.94	102.25	88.77	13.47	7.588		





Company: Project:

Percussion Petroleum, LLC

Reference Site:

Eddy County, NM Osage Boyd 15 FED COM

Site Error:

0.00 usft

Reference Well: #13H Well Error: 0.00 usft Reference Wellbore OH Reference Design: Plan #1

Local Co-ordinate Reference:

**TVD Reference:** 

RKB = 17' @ 3485.00usft RKB = 17' @ 3485.00usft

MD Reference: North Reference:

Survey Calculation Method: Minimum Curvature

Output errors are at

2.00 sigma WBDS\_SQL\_2

Well #13H - Slot 13

Database: Offset TVD Reference:

Reference Datum

			Boyd 15	FED COM	- #12F	l - OH - Pla	n#1		PRET CONCE		*, * * *	,	Offset Sité Error:	0.00 usft
Survey Pro Refer			×.	Semi Major	- A vita			Photography	nie.		, ***		Offset Well Error:	0.00 usft
Measured	Find Day		et Vertical	Reference	7	Highside	Offset Wellbo				Minimum	Separation	Warning	
Depth	Depth.	Depth	Depth		- h	Toolface	+N/ S	+E/,W	Centres	- Ellipses	Separation	Factor	a teaching.	
(usft)	(usit)	(usft)	(usfi)	(usft)	(usft)	(1)	(usft)	(usft)	(usft)	(usft)	(usft)	- 1		
1,900.00	1,890.42	1,904.05	1,887.36	7.22	7.19	-107.85	134.46	-99.76	108.79		14.32	7.595		
2,000.00	1,989.70	2,004.26	1,986.50	7.64	7.60	-108.08	144.18	-105.58	115.33		15.14	7.617		
2,051.58 2,100.00	2,040.91 2,088.67	2,047.21 2,104.58	2,037.64 2,085.54	7.85 8.07	7.78 8.02	-108.18 -108.13	149,19 153,89	-108.58 -111.40	118.71 122.47		15.53 15.97	7.644 7.667		
2,150.00	2,137.12	2,144.74	2,134.54	8.33	8.18	-110.11	158.69	-114.27	127.78		16.38	7.801		
2,200.00	2,184.31	2,206.77	2,182.71	8.62	8.44	-113.48	163.42	-117.10	135.05		16.89	7.996		
0.050.00	0 000 00	0.040.50	0.000.00	0.05	0.50	447.05	400.00	440.50	444.00				*	
2,250.00 2,300.00	2,229.88 2,273.50	2,240.50 2,286.21	2,229.68 2,275.09	8.95 9.31	8.58 8.76	-117.65 -122.09	168.02 172.48	-119.86 -122.52	144.96 158.18		17.28 17.69	8.391 8.941		
2,350.00		2,329.99	2,318.59	9.72	8.94	-126.35	176.74	-125.08	175.25		18.07	9,698		
2,400.00	2,353.53	2,371.53	2,359.86	10.17	9.11	-130,10	180.79	-127.50	196.44		18.41	10.671		
2,450.00	2,389.33	2,421.49	2,409.37	10.67	9.33	-134.43	186.77	-130.41	221.16	202.39	18.77	11.782		
2,500.00	2,421.96	2,481.12	2,467.53	11.21	9.62	-138.67	199.33	122 04	246.86	227.74	10.17	12.012		
2,550.00		2,546.87	2,529.76	11.80	9.98	-142.29	220.11	-133.84 -137.53	246.86 272.63		19.12 19.38	12.912 14.071		
2,600.00	2,476.73		2,595.81	12.44	10.46	-145,41	251.50	-141.47	297.73		19.50	15.271		
2,650.00	2,498.45	2,702.61	2,664.65	13.11	11.07	-148.10	296,58	-145.62	321.37		19.42	16.546		
2,700.00	2,516.16	2,795.88	2,733.80	13.82	11.91	-150.37	358,86	-149.82	342.61	323.50	19.11	17.926		
2,750.00	2,529.74	2,901.10	2,798.54	14.57	13.02	-152.21	441.52	-153.83	360.40	341.84	18.56	19.420		
2,800.00	2,539.06	3,018.08	2,851.46	15.34	14.48	-153.54	545.56	-157.20	373.56		17.86	20.920		
2,850.00	2,544.08	3,144.35	2,883.68	16.12	16.26	-154.29	667.37	-159.40	381.01	363.74	17.27	22.062		
2,882.55	2,545.00	3,229.23	2,890.00	16.65	17.54	-154.44	751.93	-160.00	382.43	365.29	17.14	22.313		
2,900.00	2,545.00	3,246.90	2,890.00	16.93	17.81	-154.44	769.61	-160.05	382.42	364.99	17.43	21.935		
3,000.00	2,545.00	3,346.90	2,890.00	18.58	19.39	-154.45	869.61	-160.31	382.41	363.22	19,19	19.929		
3,100.00	2,545.00	3,446.90	2,890.00	20.28	21.03	-154.45	969.61	-160.51	382.39		21.02	18.194		
3,200.00	2,545.00	3,546.90	2,890.00	22.01	22.71	-154.46	1,069.61	-160.85	382.37		22.91	16.692		
3,300.00	2,545.00	3,646.90	2,890.00	23.77	24.42	-154.46	1,169.61	-161.11	382.35	357,51	24.84	15.391		
3,400.00	2,545.00	3,746,90	2,890.00	25.56	26.16	-154.47	1,269.61	-161.38	382.34	355.52	26.82	14.258		
3,500.00	2,545.00	3,846.90	2,890.00	27.36	27.93	-154.47	1,369.61	-161.64	382,32	353,50	28.82	13.267		
	2,545.00	3,946.90	2,890.00	29.18	29.71	-154.48	1,469.60	-161.91	382.30		30.84	12.396		
3,700.00		4,046.90	2,890.00	31.00	31.51	-154.48	1,569.60	-162.18	382.28	349.40	32.88	11.625		
3,800.00	2,545.00	4,146.90	2,890.00	32.84	33.32	-154.49	1,669.60	-162.44	382.27	347.32	34.94	10.940		
3,900.00	2,545.00	4,246.90	2,890.00	34.69	35.15	-154.50	1,769.60	-162.71	382.25	345.24	37.01	10.327		
4,000.00	2,545.00	4,346.90	2,890.00	36.55	36.98	-154.50	1,869.60	-162.98	382.23	343.14	39,09	9.777		
4,100.00	2,545.00	4,446.90	2,890.00	38.41	38.82	-154.51	1,969.60	-163.24	382.21	341.03	41.18	9.280		
4,200.00	2,545.00	4,546.90	2,890.00	40.27	40.67	-154.51	2,069.60	-163.51	382,20	338.91	43.28	8.830		
	2,545.00	4,646.90	2,890.00	42.14	42.52	-154.52	2,169.60	-163.78	382.18	336.79	45,39	8.420		
4,400.00	2,545.00	4,746.90	2,890.00	44.02	44.38	-154.52	2,269.60	-164.04	382.16	334.67	47.50	8.046		
4,500.00	2,545.00	4,846.90	2,890.00	45.89	46.24	-154.53	2,369.60	-164.31	382.15	332.53	49.61	7.703		
4,600.00	2,545.00	4,946.90	2,890.00	47.77	48.11	-154.53	2,469.60	-164.58	382.13	330.40	51.73	7.387		
4,700.00	2,545.00	5,046.90	2,890.00	49.66	49.98	-154.54	2,569.60	-164.84	382.11	328.26	53.85	7.095		
4,800.00	2,545.00	5,146.90	2,890.00	51.54	51.86	-154.54	2,669.60	-165.11	382.09	326.11	55,98	6.826		
4,900.00	2,545.00	5,246.90	2,890.00	53.43	53.74	-154.55	2,769.60	-165.37	382.08	323.97	58.11	6.575		
5,000.00	2,545.00	5,346.90	2,890.00	55.32	55.62	-154.56	2,869.60	-165.64	382.06	321.82	60.24	6.342		
5,100,00	2,545.00	5,446.90	2,890.00	57.21	57.50	-154.56	2,969.60	-165.9 <b>1</b>	382.04	319.67	62.37	6.125		
5,200.00	2,545.00	5,546.90	2,890.00	59.11	59.38	-154.57	3,069.60	-166.17	382.02	317.52	64.51	5.922		
5,300.00	2,545.00	5,646.90	2,890.00	61.00	61.27	-154.57	3,169.60	-166,44	382.01	315.36	66.64	5.732		
5,400.00	2,545.00	5,746.90	2,890.00	62.90	63.16	-154.58	3,269,60	-166.71	381.99	313.21	68.78	5.554		
5,500.00	2,545.00	5,846.90	2,890.00	64.79	65.05	-154.58	3,369.60	-166.97	381.97	311.05	70.92	5.386		
5,600.00	2,545.00	5,946.90	2,890.00	66.69	66.94	-154.59	3,469.60	-167.24	381.95	308.90	73.06	5.228		
5,700.00	2,545.00	6,046.90	2,890.00	68.59	68.83	-154.59	3,569.60	-167.51	381.94	306.74	75.20	5.079		
	2,545.00	6,146.90	2,890.00	70.49	70.73	-154.60	3,669.60	-167.77	381.92	304.58	77,34	4.938		
5,900.00	2,545.00	6,246.90	2,890.00	72.39	72.62	-154.60	3,769.60	-168.04	381.90	302.42	79.49	4,805		
6,000.00	2,545.00	6,346.90	2,890.00	74.29	74.52	-154.61	3,869.60	-168.31	381.89	300.26	81.63	4.678		





Company.

Percussion Petroleum, LLC

Eddy County, NM Project: -Reference Site:

Osage Boyd 15 FED COM

Site Error 0.00 usft

Reference Well: #13H Well Error: 0.00 usft Reference Wellbore OH

Reference Design: Plan #1

TVD Reference: MD Reference:

North Reference:

Survey Calculation Method: Output errors)are at Database:

Offset TVD Reference:

Local Co-ordinate Reference: Well#13H - Slot 13

RKB = 17' @ 3485.00usft RKB = 17' @ 3485.00usft

Minimum Curvature

2.00 sigma WBDS\_SQL\_2 Reference Datum

	eşign gram: 0-M	WD+IGRE	B030 13	LD COM	- π  <b>∠</b>	7 7 THE	ın #1	* T\$	<u></u>	. ناد رین شوه	Charles S	Offs Separation Factor	et Site Error:	0.00 u
Refer		Offs	et 🖹	Semi Major	Axis	- 1.5°.			Dista	ince		Uns	et Well Error:	, 0.00 û
	-Vertical	Measured	Vertical -	Reference	Offset 15	Highside	Offset Wellbo	e Centre	Belween .	Between	Minimum	Separation	Warning	
Depth	Depth	Depth.	. Depth⊋-		30.00	Toolface	F +N-S	ŧĖ.W	Centres	Ellipses	Separation	Factor	T. T. T. T.	
(üsft)	(usft)	(usft)	· ((usft))	(usft)	(usft)		(usft)	((usft) 等之	(usft) =	(üsft).	(usft)			÷ .
6,100.00	2,545.00	6,451.01	2,889.84	76.20	76.50	-154.61	3,973.71	-168.53	381.72	297.97	83.75	4.558		
6,200.00	2,545.00	6,554.71	2,887.96	78.10	78.46	-154.59	4,077.39	-168.12	379.77	293.87	85.91	4.421		
6,300.00	2,545.00	6,654.69	2,886.03	80.00	80.36	-154.57	4,177.35	-167.68	377.70	289.60	88.10	4.287		
6,400.00	2,545.00	6,754.67	2,884.09	81.91	82.26	-154.54	4,277.31	-167.25	375.64	285.34	90.30	4.160		
6,500.00	2,545.00	6,854.65	2,882.15	83.81	84.16	-154.52	4,377.26	-166.81	373.57	281.07	92.50	4.038		
6,600.00	2,545.00	6,954.62	2,880.22	85.72	86.06	-154.49	4,477.22	-166.38	371.50	276.79	94.71	3.923		
6,631.37	2,545.00	6,985.99	2,879.61	86.32	86.65	-154.48	4,508.58	-166.24	370.85	275.45	95.40	3.887		
6,690.70	2,544.43	7,045.31	2,878.46	87.45	87.78	-154.47	4,567.89	-165,98	370.24	273.54	96.70	3.829		
6,700.00	2,544.24	7,054.61	2,878.28	87.62	87.96	-154.47	4,577.19	-165.94	370.25	273,35	96.90	3.821		
6,720.25	2,543.73	7,074.86	2,877.89	88.01	88.34	-154.46	4,597.44	-165,85	370.39	273.05	97.34	3.805		
6,800.00	2,541.45	7,154.61	2,876.34	89.53	89.86	-154.46	4,677.17	-165.50	371.21	272.14	99.07	3.747		
6,900.00	2,538.58	7,254.60	2,874.40	91.43	91.76	-154.46	4,777.14	-165.07	372.24	271.01	101.24	3.677		
7,000.00	2,535.72	7,354.60	2,872.47	93.34	93.66	-154.46	4,877.12	-164.63	373.27	269.87	103,40	3,610		
7,100.00	2,532.86	7,454.59	2,870.53	95.24	95.57	-154.46	4,977.09	-164.19	374.30	268.73	105.57	3.546		
7,200.00	2,530.00	7,554.59	2,868.59	97.15	97.47	-154.45	5,077.07	-163.76	375.33	267.59	107.74	3.484		
7,300.00	2,527.14	7,654.58	2,866.66	99.06	99.37	-154.45	5,177.04	-163.32	376.36	266.46	109.91	3.424		
7,400.00	2,524.27	7,754.58	2,864.72	100.96	101.28	-154.45	5,277.02	-162.89	377.39	265.32	112.08	3.367		
7,500.00	2,521.41	7,854.57	2,862.78	102.87	103.18	-154.45	5,376.99	-162.45	378.42	264.18	114.25	3.312		
7,600.00	2,518.55	7,954.57	2,860.84	104,78	105.09	-154.45	5,476.97	-162.01	379.45	263.04	116,42	3.259		
7,700.00	2,515.69	8,054.56	2,858.91	106.68	106.99	-154.45	5,576.94	-161.58	380.48	261.90	118.59	3.209		
7,800.00	2,512.83	8,154.56	2,856.97	108,59	108.90	-1 <b>5</b> 4.45	5,676.92	-161.14	381.51	260.76	120.76	3.159		
7,860.25	2,511.10	8,214.80	2,855.80	109.74	110.05	-154.44	5,737,15	-160.88	382.13	260.07	122.06	3,131		
7,900.00	2,510.23	8,252.77	2,855.10	110.50	110.77	-154.44	5,775.11	-160.72	382,31	259.35	122.96	3.109		
7,957.09	2,509.90	8,303.28	2,854.79	111.59	111.73	-154.44	5,825.62	-160.65	382.31	258.06	124.26	3.077		
7,960.97	2,509.92	8,306.71	2,854.80	111,66	111.80	-154.44	5,829.05	-160.65	382.31	257.97	124.34	3.075		
7,982.21	2,510.00	8,326.39	2,854.93	112.07	112.17	-154.44	5,848.73	-160.68	382.37	257.56	124.81	3.064 SF		





Company: Project:

Percussion Petroleum, LLC

Reference Site:

Eddy County, NM Osage Boyd 15 FED COM

Site Error:

0.00 usft

Reference Well: Well Error:

Reference Design:

#13H

Plan #1

0.00 usft Reference Wellbore OH

Local Co-ordinate Reference:

TVD Reference:

MD Reference:

North Reference:

Survey Calculation Method:

Output errors are at Database:

Offset TVD Reference:

Well#13H - Slot 13

RKB = 17' @ 3485.00usft

RKB = 17' @ 3485.00usft

Grid

Minimum Curvature

2.00 sigma WBDS\_SQL\_2

Reference Datum

Offset D	esign	Osage	Boyd 15	FED COM	i - #14F	I - OH - P	an #1		.,•	•	** .,		Offset Site Error: 0.00 usft
Survey Pro					erine. Santari			1. St. 100				. 1	Offset Well Érror: - 0.00 usft
Refer	, 7 TT TT TT		et	Semi Majoi		neboreat	Offset Wellbo	ati Šanaka ir	Dist	ance	Minimum	•	AL 275 P
Denth	Denth	Measured Depth	Depth	Reference"	Onset	Highside Toolface	+N/S	+E/-W	Between Centres	Ellipses	Separation:		Warning
(usft)	(usft)	(usft)	(usft)	(usft)	(usft)	(*)	(usft)	(usft)	(usft)	(üsft)	(usft)		
0.00	0.00	0.00	0.00	0.00	0.00	90.28	-0.10	20.80	20.80				244
100.00	100.00	100.00	100.00	0.15	0.15	90.28	-0.10	20.80	20.80	20.50	0.30	69.909	•
200.00	200.00	200.00	200.00	0.51	0.51	90.28	-0:10	20.80	20.80	19.79	1.01	20.503	
300.00	300.00	300.00	300.00	0.87	0.87	90.28	<b>-0.10</b>	20.80	20,80	19.07	1.73	12.013	
350.00	350.00	350.00	350.00	1.04	1.04	90.28	-0.10	20.80	20.80	18.71	2.09	9,953 (	
400.00	400.00	399.81	399.81	1.22	1.22	. 88.92	0.27	21.03	21.02	18.57	2.45	8.590 E	ES .
500.00	499.93	499.40	499.33	1.59	1.58	90.21	3.20	22.87	22.78	19.62	3.16	7.205	
600.00	599.68	598.92	598.60	1.95	1.94	92.26	9.06	26.54	26.33	22.45	3.89	6.774	
695.29	694.45	693.63	692.81	2.31	2.30	94.35	17.34	31.73	31.40	26.80	4.60	6.827	
700.00	699.13	698.31	697.45	2.33	2.32	94.45	17.82	32.03	31.70	27.06	4.64	6.837	
800.00	798.40	801.97	796.39	2.72	2.72	95.48	28.44	38.68	38.16	32.73	5.43	7.031	
000.00	907.69	002.49	905.39	2 12	2 12	06 17	20.10	45.20	44.64	29.42	6 22	7 177	
900.00	897.68 996.95	902.18	895.38 994.37	3.12 3.52	3.13 3.54	96.17 96.68	39,10 49,75	45.36 52.03	44.64 51.13	38,42 44,11	6.22 7.02	7.177 7.281	
1,100.00	1,096.23	1,102.60	1,093.37	3.92	3.95	97.08	60.41	58.71	57.63	49.80	7.83	7.358	
1,200.00	1,195.50	1,202.81	1,192.36	4.33	4.36	97.40	71.06	65.38	64.12	55.48	8.65	7.416	
1,300.00	1,294.78	1,303.02	1,291.35	4.74	4.78	97.66	81.72	72.06	70.62	61.16	9.46	7.461	
·					,								
1,400.00	1,394.05	1,403.24	1,390.34	5.16	5.20	97.88	92.37	78.73	77.12	66.83	10.29	7.498	
1,500.00	1,493.33	1,503.45	1,489.34	5.57	5.62	98.06	103.02	85.41	83.62	72.51	11.11	7.528	·
1,600.00 1,700.00	1,592.60 1,691.88	1,596.34 1,703.87	1,588.33 1,687.32	5.98 6.40	6.00 6.46	98.21 98.35	113,68 124,33	92.08 98.76	90.12 96.62	78.21 83.86	11.90 12.76	7.571 7.573	
1,800.00	1,791.15	1,804.08	1,786.32	6.81	6.88	98.47	134.99	105.43	103.12	89.53	13.59	7.590	
1,000.00	1,731.10	1,004.00	1,100.02	0.01	0.00	30.41	104,00	100.40	100.12	05.00	10.00	1.000	
1,900.00	1,890.42	1,904.29	1,885.31	7.22	7.30	98.57	145.64	112.10	109.62	95.21	14.41	7.606	
2,000.00	1,989.70	1,995.49	1,984.30	7.64	7.68	98.66	156.30	118.78	116.12	100.92	15.20	7.637	
2,051.58	2,040.91	2,046.97	2,035,36	7.85	7.90	98.71	161.79	122.22	119.47	103.84	15.63	7.643	
2,100.00	2,088.67	2,095.20	2,083.21	8.07	8.10	100.04	166.94	125.45	123.01	106.95	16.05	7.663	
2,150.00	2,137.12	2,144.58	2,132.20	8.33	8.31	102.70	172.22	128.75	127.64	111.12	16.52	7.727	
2,200.00	2;184.31	2,193.16	2,180.40	8.62	8.52	106.58	177.40	132.00	133.83	116.82	17.01	7.867	
2,250.00	2,229.88	2,240.57	2,227.43	8.95	8.72	111.28	182.47	135,17	142.33	124.83	17.50	8.133	
2;300.00	2,273.50	2,292.53	2,278.74	9.31	8.95	116.59	189.76	138.63	153.18	135.16	18.02	8.502	
2,350.00	2,314.82	2,347.38	2,331.96	9.72	9.23	121.25	202.44	142.22	165.09	146.56	18,53	8.911	
2,400.00	2,353.53	2,404.53	2,385.86	10.17	9.56	125.23	221.00	145.85	177.62	158.61	19.01	9.345	
2,450.00	2,389.33	2,464.15	2,439.84	10.67	9.94	128.60	246.01	149.49	190.35	170.91	19,44	9.792	
2,500.00	2,421.96	2,526.42	2,493.12	11.21	10.40	131.43	277.97	153.08	202.90	183.10	19.81	10.243	
2,550.00	2,451,17	2,591.44	2,544.72	11.80	10.94	133,81	317.32	156.55	214.93	194.81	20.12	10.685	
2,600.00	2,476.73	2,659.28	2,593.46	12.44	11.57	135.77	364.34	159.83	226.08	205.72	20.36	11.102	
2,650.00	2,498.45	2,729.88	2,637.92	13.11	12.32	137.36	419.04	162.83	236.05	215,45	20.59	11.463	
2,700.00	2,516.16	2,803.08	2,676,58	13.82	13.18	138.60	481.09	165.42	244.53	223.72	20.81	11.748	
2,750.00	2,529.74	2,803.08	2,707.85	14.57	14.17	139.52	549.71	167.52	251.27	230.18	21.09	11.913	
2,800.00	2,529.06	2,955.88	2,730.26	15.34	15.25	140.13	623.62	169.02	256.06	234.58	21.47	11.924	
2,850.00	2,544.08	3,034.41	2,742.66	16.12	16.42	140.44	701.09	169.85	258.72	236.70	22.03	11.746	
2,882.55	2,545.00	3,085.85	2,745.00	16.65	17.20	140.48	752.46	170.00	259.28	236,78	22.49	11.526	
	A # 12 ==	0.465.5	0717					,					
2,900.00	2,545.00	3,103.45	2,745.00	16.93	17.48	140.47	770.07	170.00	259.31	236.43	22.88	11.333	
3,000.00	2,545.00	3,203.45	2,745.00	18.58	19.07	140.42	870.07	169.98	259.50	234.33	25.17	10.311	
3,100.00 3,200.00	2,545.00 2,545.00	3,303.45 3,403.45	2,745.00 2,745.00	20.28 22.01	20.72 22.41	140.37 140.32	970.07 1,070.07	169.97 169.96	259.68 259.87	232.14 229.89	27.54 29.98	9.429 8.668	
3,200.00	2,545.00	3,503.45	2,745.00	23.77	24.14	140.32	1,170.07	169.96	260.06	229.69	32.47	8.009	
5,550.00		0,000.70	L, 10.00	20.11	2 6 17	. 10.21	1,170.07	103.34	200,00	221.50	32.77	5.003	
3,400.00	2,545.00	3,603.45	2,745.00	25.56	25.89	140.22	1,270.07	169.93	260.24	225.24	35.01	7.434	
3,500.00	2,545.00	3,703.45	2,745.00	27.36	27.66	140.17	1,370.07	169,91	260.43	222.85	37.58	6.931	,
3,600.00	2,545.00	3,803.45	•	29.18	29.45	140.12	1,470.07	169.90	260.62	220.44	40.18	6.487	
3,700.00	2,545.00	3,903.45		31.00	31.26	140.07	1,570.07	169.89	260.81	218.01	42.80	6.094	
3,800.00	2,545.00	4,003.45	2,745.00	32.84	33.08	140.02	1,670.07	169.87	261.00	215.55	45.44	5.743	
3,900.00	2,545.00	4,103.45	2,745.00	34.69	34.91	139.97	1,770.07	169.86	261.18	213.08	48.10	5.430	
							contraint C		_				





Company: Percussion Petroleum, LLC
Project: Eddy County, NM

Project: Reference Site:

Osage Boyd 15 FED COM

Site Error: 0.00 usft
Reference Well: #13H
Well Error: 0.00 usft
Reference Wellbore OH

Reference Design:

Plan #1

Local Co-ordinate Reference: Well #13H - Slot 13
TVD Reference: RKB = 17' @ 3485.
MD Reference: RKB = 17' @ 3485.

RKB = 17' @ 3485.00usft

RKB = 17' @ 3485.00usft

MD Reference: RKB = 17' @ 3485.0
North Reference: Grid Grid Minimum Curvature
Output errors are at 2.00 sigma
Database WBDS\_SQL\_2
Offset TVD Reference: Reference Datum

Offset D	esign:	Osage	Boyd 15	FED COM	i - #14H	- OH - PI	an #1	SALES FOR DOS.	Demonitors.	CONTRACTOR TO	ACT AND THE		ffset Site Error:	0.00 usft-
Survey Pro	gram: 10 M	WD+IGRE			a. Reside					Selection of the select		o	fiset Well Error:	0.00 usft
Refer	ence)	Offs	et .	Semi Majo	Axis		Offset Wellbo		Dista	nce The			and the second of the contract of the contrac	enter de la companya
Depth	Depth	Depth	Depth	areleience.	Uliset	Toolface	+N/-S	re Centre	Centres	Ellipses	Separation	Separation	Warnin	
a (üsft)	(usft)	(usft)	- Ingiti :	(usft)	(usft)	(3)	Offset Wellbo +N/-S (usft)	(usft)	* (usft)	(usft)	_ (usft)			
4,000.00	2,545.00	4,203.45	2,745.00	36.55	36.75	139.92	1,870.07	169.84	261.37	210.59	50.78	ا . فتانطىناناتە ما 5.147	20 م منسالہ اتفاق ا	المشامية كالتمشية
4,100.00	2,545.00	4,303.45	2,745.00	38.41	38.59	139.88	1,970.06	169.83	261.56	208.09	53.47	4.891		i
4,200.00	2,545.00	4,403.45	2,745.00	40.27	40.44	139.83	2,070.06	169,82	261.75	205.57	56.18	4.659		
4,300.00	2,545.00	4,503.45	2,745.00	42.14	42.30	139.78	2,170.06	169.80	261.94	203.05	58.89	4.448		
4,400.00	2,545.00	4,603.45	2,745.00	44.02	44.16	139.73	2,270.06	169.79	262.13	200.51	61.62	4.254		
4,500.00	2,545.00	4,703.45	2,745.00	45.89	46.03	139.68	2,370.06	169.77	262.32	197.97	64.35	4.076		
4,600.00	2,545.00	4,803.45	2,745.00	47.77	47.90	139.63	2,470.06	169.76	262.51	195.41	67.09	3.913		
4,700.00	2,545.00	4,903.45	2,745.00	49.66	49.77	139.58	2,570.06	169.75	262.70	192.85	69.85	3.761		
4,800.00	2,545.00	5,003.45	2,745.00	51,54	51.65	139.53	2,670.06	169.73	262.89	190.28	72.60	3.621		
4,900.00	2,545.00 2,545.00	5,103.45 5,203.45	2,745.00	53.43	53.53	139.49	2,770.06	169.72	263.08	187.71	75.37	3.490		
5,000.00	2,545.00	5,203.45	2,745.00	55.32	55.41	139.44	2,870.06	169.70	263.27	185.12	78.14	3.369		
5,100.00	2,545.00	5,303.45	2,745.00	57.21	57.30	139:39	2,970.06	169.69	263.46	182.53	80.92	3.256		
5,200.00	2,545.00	5,403.44	2,745.00	59.11	59.18	139.34	3,070.06	169.68	263.65	179.94	83.71	3.150		-
5,300.00	2,545.00	5,503.44	2,745.00	61.00	61.07	139.29	3,170.06	169.66	263.84	177.34	86.50	3.050		
5,400.00	2,545.00	5,603.44	2,745.00	62.90	62.96	139.24	3,270.06	169.65	264.03	174.73	89.30	2.957		ĺ
5,500.00	2,545.00	5,703.44	2,745.00	64.79	64.85	139.20	3,370.06	169.63	264.22	172.12	92.10	2.869		
5,600.00	2,545.00	5,803.44	2,745.00	66.69	66.75	139.15	3,470.06	169.62	264.41	169.51	94.91	2.786		
5,700.00	2,545.00	5,903.44	2,745.00	68.59	68.64	139.10	3,570,06	169.61	264.60	166.88	97.72	2.708		
5,800.00	2,545.00	6,003.44	2,745.00	70.49	70.54	139.05	3,670.06	169.59	264,80	164.26	100.54	2.634		
5,900.00	2,545.00	6,103.44 6,203.44	2,745.00	72.39	72.43	139.00	3,770.06	169.58	264.99	161.63	103.36	2.564		
6,000.00	2,545.00	6,203,44	2,745.00	74.29	74.33	138.96	3,870.06	169.56	265.18	158.99	106.19	2.497		
6,100.00	2,545.00	6,303.44	2,745.00	76.20	76.23	138.91	3,970.06	169.55	265.37	156.35	109.02	2.434		
6,200.00	2,545.00	6,403.44	2,745.00	78.10	78.13	138.86	4,070.06	169.54	265.57	153.71	111.86	2.374		
6,300.00	2,545.00	6,503.44	2,745.00	80.00	80.03	138.81	4,170.06	169.52	265.76	151.06	114.70	2.317		1
6,400.00	2,545.00 2,545.00	6,603.44 6,703.44	2,745.00 2,745.00	81.91	81.93 83.83	138.77	4,270.06	169.51	265.95	148.41	117.54	2.263		
6,500.00	2,545.00	6,703.44	2,745.00	83.81	83.83	138.72	4,370.05	169.49	266.14	145.75	120.39	2.211		
6,600.00	2,545.00	6,803.44	2,745.00	85.72	85.73	138.67	4,470.05	169.48	266.34	143.09	123.25	2.161		
6,631.37	2,545.00	6,834.81	2,745.00	86.32	86.33	138.66	4,501.42	169.48	266.40	142.25	124.14	2.146		
6,700.00	2,544.24	6,903.43	2,745.00	87.62	87.63	138.78	4,570.05	169.47	266.89	141.07	125.82	2.121		
6,720.25 6,800.00	2,543.73 2,541.45	6,923.67 7,003.39	2,745.00 2,745.00	88.01 89.53	88.02 89.54	138.88	4,590.29	169.46	267,18	140.97	126.21	2.117		
0,000.00	2,541.45	7,003.39	2,745.00	69.53	69.54	139.31	4,670.01	169.45	268.43	140.82	127.61	2.104		
6,900.00	2,538.58	7,103.34	2,745.00	91.43	91.44	139.85	4,769.96	169.44	270.02	140.68	129.34	2.088		
7,000.00	2,535.72	7,203.30	2,745.00	93.34	93.34	140.39	4,869,92	169.43	271.64	140.60	131.04	2.073		i
7,100.00	2,532.86	7,303.25	2,745.00	95.24	95.25	140.92	4,969.87	169.41	273.28	140.58	132,70	2.059		
7,200.00 7,300.00	2,530.00 2,527.14	7,403.21 7,503.16	2,745.00 2,745.00	97.15 99.06	97.15 99.05	141.44 141.95	5,069.82 5,169.78	169.40 169.38	274.94 276.63	140.61 140.69	134,34 135,94	2.047 2.035		
7,300.00	2,527.14	7,000.10	2,740.00	33.00	33.00	141.33	3,103.70	103.30	270,03	140.03	133.34	2.033		
7,400.00	2,524.27	7,603.12	2,745.00	100,96	100.96	142.46	5,269.73	169.37	278.34	140.82	137.51	2.024		
7,500.00	2,521.41	7,703.07	2,745.00	102.87	102.86	142.97	5,369,69	169.36	280.07	141.01	139.06	2.014		į
7,600.00 7,700.00	2,518.55 2,515.69	7,803.03 7,902.98	2,745.00 2,745.00	104.78	104.77 106.68	143.46	5,469.64	169.34	281.82	141.24	140.58	2.005		
7,700.00	2,512.83	8,002.94	2,745.00	106.68 108.59	108.58	143.95 144.44	5,569.60 5,669.55	169.33 169.31	283.59 285.38	141.52 141.85	142.07 143.53	1.996 1.988		
1,000.00	2,0 (2.00	0,002.04	2,7 10.00	100.03	100.00	1-1-74	5,003.00	100.01	200.00	171.00	140.00	1,300		
7,860.25	2,511.10	8,063,16	2,745.00	109.74	109.73	144.73	5,729.78	169.30	286.47	142.07	144.40	1.984		
7,900.00	2,510.23	8,102.88	2,745.00	110.50	110.49	144.88	5,769.49	169.30	287.02	141.95	145.07	1.979		
7,957.09	2,509.90	8,159.97	2,745.00	111.59	111.58	144.94	5,826.58	169.30	287.21	140.83	146.38	1.962		
7,982.21	2,510.00	B,185.08	2,745.00	112.07	112.06	144.93	5,851.70	169.30	287.14	140.09	147.05	1.953 SF		





Company: Percussion Petroleum, LLC

Project: Eddy County, NM

Reference Site: Osage Boyd 15 FED COM

Site Error: 0.00 usft Reference Well: #13H Well Error: 0.00 usft Reference Wellbore OH Reference Design: Plan #1 Local Co-ordinate Reference: Well #13H - Slot 13
TVD Reference: RKB = 17' @ 3485.00usft
MD Reference: RKB = 17' @ 3485.00usft

North Reference: Grid

Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WBDS\_SQL\_2
Offset TVD Reference: Reference Datum

Reference Depths are relative to RKB = 17' @ 3485.00usft


Offset Depths are relative to Offset Datum

Central Meridian is -104.333334

Coordinates are relative to: #13H - Slot 13

Coordinate System is US State Plane 1983, New Mexico Eastern Zone

Grid Convergence at Surface is: -0.08°







Company Percussion Petroleum, LLC

Reference Site: Osage Boyd 15 FED COM Site Error: 0.00 usft Reference Well: #13H Well:Error: 0.00 usft

Well:Error: 0.00 usf Reference Wellbore OH Reference Design: Plan #1 Local Co-ordinate Reference:

TVD Reference MD Reference North Reference: Survey Calculation Method

Output errors are at Database:
Offset TVD Reference

Well#13H - Slot 13 RKB = 17' @ 3485.00usft

RKB = 17' @ 3485.00usft

Grid

Minimum Curvature 2.00 sigma

WBDS\_SQL\_2 Reference Datum

Reference Depths are relative to RKB = 17' @ 3485.00usft


Offset Depths are relative to Offset Datum

Central Meridian is -104.333334

Coordinates are relative to: #13H - Slot 13

Coordinate System is US State Plane 1983, New Mexico Eastern Zone

Grid Convergence at Surface is: -0.08°



#### **DRILL PLAN PAGE 1**

Percussion Petroleum Operating, LLC Osage Boyd 15 Federal Com 13H

SHL: 649' FNL & 1180' FWL 22-19S-25E BHL: 20' FNL & 1185' FWL 15-19S-25E

Eddy County, NM

# Drilling Program

# 1. ESTIMATED TOPS

Formation/Lithology	TVD	MD	Contents
Quaternary caliche	000′	000'	water
Grayburg dolomite	598'	598′	hydrocarbons
San Andres dolomite	783′	785'	hydrocarbons
(KOP	2041'	2052'	hydrocarbons)
Glorieta silty dolomite	2343'	2393'	hydrocarbons
Yeso dolomite	2498'	2650'	hydrocarbons
TD ·	2510'	8335′	hydrocarbons

## 2. NOTABLE ZONES

Yeso is the goal. Closest water well (RA 02909) is 2797' south. Water bearing strata were found at 120' in this 188' deep well.

### 3. PRESSURE CONTROL

A 3000-psi 5000' rated BOP stack consisting of annular preventer and double (blind and pipe) ram will be used below surface casing to TD. See attached BOP and choke manifold diagrams.

Pressure tests will be conducted before drilling out from under all casing strings. Third party test crews will conduct all tests. All tests will be recorded for 10-minutes on low pressure (500 psi) and 10-minutes on high pressure (3000-psi). After BOP testing is complete, test casing (without test plug) to 2000-psi for 30 minutes. All tests will be charted on a plot. BOPs will be function tested every day.



# **DRILL PLAN PAGE 2**

Percussion Petroleum Operating, LLC Osage Boyd 15 Federal Com 13H

SHL: 649' FNL & 1180' FWL 22-19S-25E BHL: 20' FNL & 1185' FWL 15-19S-25E

Eddy County, NM

# 4. CASING & CEMENT

All casing will be API and new. A contingency plan is attached.

Hole O. D.	Set MD	Set TVD	Casing O. D.	Weight (lb/ft)	Grade	Joint	Collapse	Burst	Tension
12.25"	0' - ; 1279':	0′ - 1275'	Surface 9.625"	36	J-55	LTC	1.125	1.125	1.8
8.75″	0' - 2300'	0′ - 2273′	Prod. 1 7"	32	L-80	втс	1.125	1.125	1.8
8.75"	2300′ - 7982'	2273' - 2510'	Prod. 2 5.5"	17	L-80	втс	1.125	1.125	1.8

Casing Name	Туре	Sacks	Yield	Cu. Ft.	Weight	Blend		
Surface	Lead	637	1.32	840	14.8	Class C + 2% CaCl + ¼ pound per sack celloflake		
TOC = GL	100% Excess			Stop collar 10' above shoe with centralizer.  One on 1st collar and every 4 <sup>th</sup> collar to GL.				
Production	Lead	495	1.97	975	12.6	65/65/6 Class C + 6% gel + 5% salt + ¼ pound per sack celloflake + 0.2% C41-P		
	Tail	1323	1.32	1746	14.8 Class C + 2% CaCl + ¼ pound sack celloflake			
TOC = GL	5	60% Exces	S	One or	lar 10' above shoe with centralizer. In 1st collar and every 10 collars to with 1 centralizer in 9.625" casing.			

# 5. MUD PROGRAM

An electronic/mechanical mud monitor with a minimum pit volume totalizer, stroke counter, and flow sensor will be used. All necessary mud products (LCM) will be on site to handle any abnormal hole condition that may be encountered while drilling this well. A closed loop system will be used.



# Percussion Petroleum Operating, LLC

Osage Boyd 15 Federal Com 13H

SHL: 649' FNL & 1180' FWL 22-19S-25E BHL: 20' FNL & 1185' FWL 15-19S-25E

Eddy County, NM

Туре	Interval (MD)	lb/gal	Viscosity	Fluid Loss	Plastic Viscosity	Yield Point
fresh water/gel	0' - 1279'	8.4 - 9.2	36-42	NC	3-5	5-7
fresh water/cut brine	1279' - 2052'	8.3 - 9.2	28-30	NC	1	1
cut brine	2052' - 7982'	8.6 - 9.2	29-32	NC	4-5	6-10

# 6. CORES, TESTS, & LOGS

No core or drill stem test is planned.

A mud logger will be used from GL to TD. Samples will be collected every 10' in the lateral pay zone.

No electric logs are planned at this time.

# 7. <u>DOWN HOLE CONDITIONS</u>

No abnormal pressure or temperature is expected. Maximum expected bottom hole pressure is  $\approx 1087$  psi. Expected bottom hole temperature is  $\approx 108$ ° F.

A Hydrogen Sulfide Drilling Operation Plan is attached.

# 8. OTHER INFORMATION

Anticipated spud date is upon approval. It is expected it will take  $\approx 1$  month to drill and complete the well.

St. Devote LLC has operating rights in NMNM-012833. St. Devote LLC is a subsidiary of Percussion.



DRILL PLAN PAGE 3



# Contingency Planning - Osage Federal Area Wells

Prepared by Lelan J. Anders, Percussion Petroleum Operating, LLC.

#### INTRODUCTION:

This document is designed to address the issues that could arise at any time drilling horizontal Yeso wells. Percussion Petroleum Operating (PPO) is going to follow regularly used practices and procedures in order to drill the wells to TD and still keep them economical to operate.

#### **SCENARIO:**

If a complete loss of circulation occurs while drilling above 400 ft MD.

#### **CORRECTIVE ACTIONS:**

- 1. Pump an LCM sweep and attempt to regain circulation if unsuccessful go to step 2
- 2. Continue drilling at attempt to seal off lost circulation zone with drill cuttings
  - 1. Monitor torque and drag on drill string to determine if pipe is sticking
  - 2. Have contingency plan to 'drill dry' have plenty of water on hand and well control in place
  - 3. Continue to 'dry drill' until torque and drag dictate a different plan
- 3. If 'dry drilling' is unsuccessful Run contingency surface casing string
  - 1. Ream out 12-1/4" open hole to 17-1/2" open hole
  - 2. Run contingency 13-3/8" 48# H-40, STC casing to no more than 400' MD
  - 3. Cement 13-3/8" casing using Class C cement
    - i. Pump at minimum 200% excess cement
      - 1. 400 sks 65/35/6 Class C Cement, 12.8 ppg, 1.87 yield, 10.15 gal/sk to be used on initial cement job.
    - ii. Top off cement from surface using 1" if necessary
      - 1. Top off will be 200 sks of 65/35/6 Class C Cement, 12.8 ppg, 1.87 yield, 10.15 gal/sk
      - 2. Second top off will be performed with same cement if needed.
    - iii. Insure that cement has cured for a minimum of 12 hours prior to drilling out
  - 4. Install 13-3/8" 3M wellhead and drill to surface casing depth with 12-1/4" OD bit
  - 5. Run and cement surface casing as planned



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT



**APD ID:** 10400036037 **Submission Date:** 11/06/2018

**Operator Name: PERCUSSION PETROLEUM OPERATING LLC** 

Well Name: OSAGE BOYD 15 FEDERAL COM Well Number: 13H

Well Type: OIL WELL Well Work Type: Drill

Highlighted data reflects the most recent changes

**Show Final Text** 

## **Section 1 - Existing Roads**

Will existing roads be used? YES

**Existing Road Map:** 

Osage\_13H\_Road\_Map\_20181106114619.pdf

Existing Road Purpose: ACCESS

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? NO

**Existing Road Improvement Description:** 

**Existing Road Improvement Attachment:** 

#### Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

**New Road Map:** 

Osage\_13H\_New\_Road\_Map\_20181106114630.pdf

New road type: RESOURCE

Length: 620

Feet

Width (ft.): 30

Max slope (%): 0

**Max grade (%):** 5

Army Corp of Engineers (ACOE) permit required? NO

**ACOE Permit Number(s):** 

New road travel width: 14

New road access erosion control: Crowned and ditched

New road access plan or profile prepared? NO

New road access plan attachment:

Access road engineering design? NO

Access road engineering design attachment:

Well Name: OSAGE BOYD 15 FEDERAL COM Well Number: 13H

Access surfacing type: OTHER

Access topsoil source: ONSITE

Access surfacing type description: Caliche

Access onsite topsoil source depth: 6

Offsite topsoil source description:

Onsite topsoil removal process: Grader

Access other construction information:

Access miscellaneous information:

Number of access turnouts:

Access turnout map:

## **Drainage Control**

New road drainage crossing: OTHER

Drainage Control comments: Crowned and ditched

Road Drainage Control Structures (DCS) description: None

Road Drainage Control Structures (DCS) attachment:

### **Access Additional Attachments**

Additional Attachment(s):

# **Section 3 - Location of Existing Wells**

**Existing Wells Map?** YES

Attach Well map:

Osage\_13H\_Well\_Map\_20181106114647.pdf

**Existing Wells description:** 

### Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? SUBMIT

**Production Facilities description:** An 842' long 4" O D. HDPE flow line will be laid on the surface southeast to a proposed central tank battery (CTB). CTB will sit on the south side of Percussion's existing three well Ross Ranch Goodman pad. Maximum operating pressure will be 125 psi. A 668' 3-phase raptor safe overhead power line will be built east to tie into an existing power line that serves the Ross Ranch Goodman pad. A 1549.8' long 4" O D. HDPE crude oil line will be laid on the surface from the CTB southwest to an existing crude oil line at Percussion's Ross Ranch 22 #2 pad. Maximum operating pressure will be 125 psi.

**Production Facilities map:** 

Osage\_13H\_Production\_Facilities\_20181106114706.pdf

Well Name: OSAGE BOYD 15 FEDERAL COM

Well Number: 13H

# **Section 5 - Location and Types of Water Supply**

#### **Water Source Table**

Water source use type: DUST CONTROL,

Water source type: GW WELL

INTERMEDIATE/PRODUCTION CASING, STIMULATION, SURFACE

**CASING** 

Describe type:

Source longitude:

Source latitude:

Source datum:

Water source permit type: PRIVATE CONTRACT

Source land ownership: PRIVATE

Water source transport method: PIPELINE

Source transportation land ownership: PRIVATE

Water source volume (barrels): 10000

Source volume (acre-feet): 1.288931

Source volume (gal): 420000

#### Water source and transportation map:

Osage\_13H\_Water\_Source\_Map\_20181106114720.pdf

**Water source comments:** Water will be piped via temporary 13,000' long surface 10" Kevlar lay flat pipelines (2) from Percussion's existing lined fresh water pond on its own land in NE4 26-19s-25e. Pipeline route will not be bladed or excavated. Route is all private. Route follows existing roads, pads, and pipelines.

New water well? NO

#### **New Water Well Info**

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

**Drilling method:** 

**Drill material:** 

**Grout material:** 

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

**Completion Method:** 

Water well additional information:

Well Name: OSAGE BOYD 15 FEDERAL COM Well Number: 13H

State appropriation permit:

Additional information attachment:

#### Section 6 - Construction Materials

Construction Materials description: NM One Call (811) will be notified before construction starts. Top 6" of soil and brush will be stockpiled north of the pad. V-door will face east. Closed loop drilling system will be used. Caliche will be hauled from existing caliche pit on private land. Arkland caliche pit is in NWNE 23-19s-25e.

**Construction Materials source location attachment:** 

Osage 13H Construction Methods 20181106114736.pdf

### **Section 7 - Methods for Handling Waste**

Waste type: DRILLING

Waste content description: Drill cuttings, mud, salts, and other chemicals

Amount of waste: 1000

barrels

Waste disposal frequency: Daily

Safe containment description: Steel tanks

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL Disposal location ownership: PRIVATE

**FACILITY** 

Disposal type description:

Disposal location description: R360's state approved (NM-01-0006) disposal site at Halfway, NM.

#### Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit?

Reserve pit length (ft.)

Reserve pit width (ft.)

Reserve pit depth (ft.)

Reserve pit volume (cu. yd.)

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

### **Cuttings Area**

Cuttings Area being used? NO

Are you storing cuttings on location? YES

Description of cuttings location Steel tanks on pad

Well Name: OSAGE BOYD 15 FEDERAL COM Well Number: 13H

Cuttings area length (ft.)

Cuttings area width (ft.)

Cuttings area depth (ft.)

Cuttings area volume (cu. yd.)

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

# **Section 8 - Ancillary Facilities**

Are you requesting any Ancillary Facilities?: NO

**Ancillary Facilities attachment:** 

Comments:

Section 9 - Well Site Layout

Well Site Layout Diagram:

Osage\_13H\_Well\_Site\_Layout\_20181106114804.pdf

Comments:

#### **Section 10 - Plans for Surface Reclamation**

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: OSAGE BOYD 15 FEDERAL COM

Multiple Well Pad Number: 12H

Recontouring attachment:

Osage\_13H\_Interim\_Reclamation\_Diagram\_20181106114816.pdf

Osage\_13H\_Recontour\_Plat\_20181106114825.pdf

**Drainage/Erosion control construction:** Crowned and ditched

Drainage/Erosion control reclamation: Harrowed on the contour

Well pad proposed disturbance

(acres): 2.34

Road proposed disturbance (acres):

0.43

Powerline proposed disturbance

(acres): 0.47

Pipeline proposed disturbance

(acres): 7.62

Other proposed disturbance (acres):

0.55

Well pad interim reclamation (acres):

0.39

Road interim reclamation (acres): 0

Powerline interim reclamation (acres):

0.47

Pipeline interim reclamation (acres):

7.62

Other interim reclamation (acres): 0

Total interim reclamation: 8.48

Well pad long term disturbance

(acres): 1.95

Road long term disturbance (acres):

0.43

Powerline long term disturbance

(acres): 0

Pipeline long term disturbance

(acres): 0

Other long term disturbance (acres):

0.55

Well Name: OSAGE BOYD 15 FEDERAL COM Well Number: 13H

Total proposed disturbance: 11.41

Total long term disturbance: 2.93

#### **Disturbance Comments:**

**Reconstruction method:** Interim reclamation will be completed within 6 months of completing the well. Interim reclamation will consist of shrinking the well pad 0.41 acre by removing caliche and reclaiming 50' on the north side of the pad. This will leave 1.95 acres for the anchors, pump jacks, and tractor-trailer turn around. Disturbed areas will be contoured to match preconstruction grades. Soil and brush will be evenly spread over disturbed areas and harrowed on the contour. Disturbed areas will be seeded in accordance with surface owner's requirements.

**Topsoil redistribution:** Enough stockpiled topsoil will be retained to cover the remainder of the pad when the well is plugged. Once the last well is plugged, then the rest of the pad will be similarly reclaimed within 6 months of plugging. Noxious weeds will be controlled.

Soil treatment: None

Existing Vegetation at the well pad:

Existing Vegetation at the well pad attachment:

**Existing Vegetation Community at the road:** 

**Existing Vegetation Community at the road attachment:** 

**Existing Vegetation Community at the pipeline:** 

**Existing Vegetation Community at the pipeline attachment:** 

**Existing Vegetation Community at other disturbances:** 

**Existing Vegetation Community at other disturbances attachment:** 

Non native seed used? NO

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? NO

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? NO

Seed harvest description:

Seed harvest description attachment:

Seed Management

**Seed Table** 

Well Name: OSAGE BOYD	Well Number: 13H Seed source:			
Seed type:				
Seed name:				
Source name:	Source address:			
Source phone:				
Seed cultivar:				
Seed use location:				
PLS pounds per acre:		Proposed seeding season		
Seed S	ummary	Total pounds/Acre:		
Seed Type	Pounds/Acre			
First Name:		Last Name:		
Granton Contact	Responsible Offici	ial Cantagt Info		
First Name:		Last Name:		
Phone:		Email:		
seedbed prep:				
seed BMP:				
Seed method:				
xisting invasive species?	NO			
xisting invasive species tr	eatment description:			
xisting invasive species tr	eatment attachment:			
Veed treatment plan descri	ption: To BLM standards			
Veed treatment plan attach	ment:			
Monitoring plan description	: To BLM standards			
lonitoring plan attachment	:			
Success standards: To BLM	I satisfaction			
Pit closure description: No p	pit			

Section 11 - Surface Ownership

Well Name: OSAGE BOYD 15 FEDERAL COM Well Number: 13H

Disturbance type: EXISTING ACCESS ROAD

Describe:

Surface Owner: PRIVATE OWNERSHIP

Other surface owner description:

**BIA Local Office:** 

**BOR Local Office:** 

**COE Local Office:** 

**DOD Local Office:** 

**NPS Local Office:** 

**State Local Office:** 

**Military Local Office:** 

**USFWS Local Office:** 

Other Local Office:

**USFS** Region:

USFS Forest/Grassland:

**USFS Ranger District:** 

Lakewood NM 88254

Email:

Fee Owner Address: c/o Ross Ranch PO Box 216

Fee Owner: Jerome Hugh Joes

ce owner. before magnitudes

Phone: (575)365-4797

Surface use plan certification: NO

Surface use plan certification document:

Surface access agreement or bond: Agreement

Surface Access Agreement Need description: See attached

**Surface Access Bond BLM or Forest Service:** 

**BLM Surface Access Bond number:** 

**USFS Surface access bond number:** 

Disturbance type: OTHER

**Describe:** Central Tank Battery

Surface Owner: PRIVATE OWNERSHIP

Other surface owner description:

**BIA Local Office:** 

Well Name: OSAGE BOYD 15 FEDERAL COM	Well Number: 13H
BOR Local Office:	
COE Local Office:	
DOD Local Office:	
NPS Local Office:	
State Local Office:	
Military Local Office:	
USFWS Local Office:	
Other Local Office:	
USFS Region:	
USFS Forest/Grassland:	USFS Ranger District:
Fee Owner: Jerome Hugh Jones	Fee Owner Address: c/o Ross Ranch PO Box 216
Phone: (575)365-4797	Lakewood NM 88254 Email:
Surface use plan certification: NO	
Surface use plan certification document:	
Surface access agreement or bond: Agreement	
Surface Access Agreement Need description: See	e attached
Surface Access Bond BLM or Forest Service:	
BLM Surface Access Bond number:	
USFS Surface access bond number:	
Disturbance type: PIPELINE	
Describe:	
Surface Owner: PRIVATE OWNERSHIP	
Other surface owner description:	
BIA Local Office:	
BOR Local Office:	
COE Local Office:	
DOD Local Office:	,
NPS Local Office:	
State Local Office:	

Well Name: OSAGE BOYD 15 FEDERAL COM	Well Number: 13H				
Military Local Office:					
USFWS Local Office:					
Other Local Office:					
USFS Region:	¢.				
USFS Forest/Grassland:	USFS Ranger District:				
Fee Owner: Jerome Hugh Jones	Fee Owner Address: c/o Ross Ranch PO Box 216 Lakewood NM 88254				
Phone: (575)365-4797	Email:				
Surface use plan certification: NO					
Surface use plan certification document:					
Surface access agreement or bond: Agreemen	nt .				
Surface Access Agreement Need description:	See attached				
Surface Access Bond BLM or Forest Service:					
<b>BLM Surface Access Bond number:</b>					
USFS Surface access bond number:					
Disturbance type: WELL PAD					
Describe:					
Surface Owner: PRIVATE OWNERSHIP					
Other surface owner description:					
BIA Local Office:					
BOR Local Office:					
COE Local Office:					
DOD Local Office:					
NPS Local Office:					
State Local Office:					
Military Local Office:					
USFWS Local Office:					
Other Local Office:					
USFS Region:					
USFS Forest/Grassland:	USFS Ranger District:				

Well Name: OSAGE BOYD 15 FEDERAL COM

Well Number: 13H

Fee Owner: Jerome Hugh Jones

Fee Owner Address: c/o Ross Ranch PO Box 216

Lakewood NM 88254

Email:

Phone: (575)365-4797

Surface use plan certification: NO

Surface use plan certification document:

Surface access agreement or bond: Agreement

Surface Access Agreement Need description: See attached

Surface Access Bond BLM or Forest Service:

**BLM Surface Access Bond number:** 

**USFS Surface access bond number:** 

**Disturbance type: OTHER** 

Describe: Power Line

Surface Owner: PRIVATE OWNERSHIP

Other surface owner description:

**BIA Local Office:** 

**BOR Local Office:** 

**COE Local Office:** 

**DOD Local Office:** 

NPS Local Office:

**State Local Office:** 

**Military Local Office:** 

**USFWS Local Office:** 

Other Local Office:

**USFS** Region:

**USFS Forest/Grassland:** 

**USFS Ranger District:** 

Well Name: OSAGE BOYD 15 FEDERAL COM

Well Number: 13H

Fee Owner: Jerome Hugh Jones

Fee Owner Address: c/o Ross Ranch PO Box 216

Phone: (575)365-4797

Lakewood NM 88254

110110: (070)000 4707

Email:

Surface use plan certification: NO

Surface use plan certification document:

Surface access agreement or bond: Agreement

Surface Access Agreement Need description: See attached

Surface Access Bond BLM or Forest Service:

**BLM Surface Access Bond number:** 

**USFS Surface access bond number:** 

Disturbance type: PIPELINE

Describe:

Surface Owner: PRIVATE OWNERSHIP

Other surface owner description:

**BIA Local Office:** 

**BOR Local Office:** 

**COE Local Office:** 

**DOD Local Office:** 

NPS Local Office:

**State Local Office:** 

Military Local Office:

**USFWS Local Office:** 

Other Local Office:

**USFS** Region:

**USFS Forest/Grassland:** 

**USFS Ranger District:** 

Well Name: OSAGE BOYD 15 FEDERAL COM

Well Number: 13H

Fee Owner: Ross&Barbara Whitney Trust

Fee Owner Address: 25601 E. 130th Street Greenwood

MO 64034

Email:

Phone: (816)525-1233

Surface use plan certification: NO

Surface use plan certification document:

Surface access agreement or bond: Agreement

Surface Access Agreement Need description: See attached

**Surface Access Bond BLM or Forest Service:** 

**BLM Surface Access Bond number:** 

**USFS Surface access bond number:** 

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: PRIVATE OWNERSHIP

Other surface owner description:

**BIA Local Office:** 

**BOR Local Office:** 

**COE Local Office:** 

**DOD Local Office:** 

NPS Local Office:

**State Local Office:** 

**Military Local Office:** 

**USFWS Local Office:** 

Other Local Office:

**USFS** Region:

**USFS** Forest/Grassland:

**USFS Ranger District:** 

Well Name: OSAGE BOYD 15 FEDERAL COM

Well Number: 13H

Fee Owner: Jerome Hugh Jones

Fee Owner Address: c/o Ross Ranch PO Box 216

Lakewood NM 88254

Email:

Phone: (575)365-4707

Surface use plan certification: NO

Surface use plan certification document:

Surface access agreement or bond: Agreement

Surface Access Agreement Need description: See attached

Surface Access Bond BLM or Forest Service:

**BLM Surface Access Bond number:** 

**USFS Surface access bond number:** 

### **Section 12 - Other Information**

Right of Way needed? NO

Use APD as ROW?

ROW Type(s):

**ROW Applications** 


# **SUPO Additional Information:**

Use a previously conducted onsite? YES

**Previous Onsite information:** On-site inspection was held with Matt Wirth (BLM) on July 12, 2018. Lone Mountain inspected the well pad and submitted archaeology report NMCRIS-141118 on August 7, 2018. APAC inspected the oil line and submitted report NMCRIS-141712 on October 25, 2018.

# Other SUPO Attachment

Osage\_13H\_SUPO\_20181106114957.pdf
Osage\_13H\_Surface\_Use\_Agreement\_20181106115003.pdf




NATIONAL GEOGRAPHIC






NATIONAL GEOGRAPHIC








# SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

MAP 4



#### PERCUSSION PETROLEUM OPERATING, LLC OSAGE BOYD 15 FEDERAL COM 13H ELEV. - 3468'

Lat - N 32.652008\* Long - W 104.477351\* NMSPCE- N 600961.6 E 497012.6 (NAD-83)

Directions to Location:

FROM US HIGHWAY 285, GO WEST ON ROCKING R RED ROAD 4.6 MILES TO LEASE ROAD, THEN GO SOUTHERLY ON LEASE ROAD 0.1 MILE TO THE PERCUSSION ROSS RANCH 22 #3 LOCATION AND PROPOSED LEASE ROAD.



P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241

(575) 393-7316 - Office (575) 392-2206 - Fax basinsurveys.com ARTESIA, NM IS ±14 MILES TO THE NORTHEAST OF LOCATION.

200 0 200 400 FEET

SCALE: 1" = 200'


# PERCUSSION PETROLEUM OPERATING, LLC


REF: OSAGE BOYD 15 FEDERAL COM 13H / WELL PAD TOPO

THE OSAGE BOYD 15 FEDERAL COM 13H LOCATED 649' FROM
THE NORTH LINE AND 1180' FROM THE WEST LINE OF
SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST,

N.M.P.M., EDDY COUNTY, NEW MEXICO.

W.O. Number: 33762 | Drawn By: K. GOAD | Date: 05-17-2018 | Survey Date: 05-12-2018 | Sheet 1 of 1 Sheets





#### PERCUSSION PETROLEUM OPERATING, LLC OSAGE BOYD 15 FEDERAL COM 13H ELEV. - 3468'

Lat - N 32.652008\* Long - W 104.477351\* NMSPCE- N 600961.6 E 497012.6 (NAD-83)

Directions to Location:

FROM US HIGHWAY 285, GO WEST ON ROCKING R RED ROAD 4.6 MILES TO LEASE ROAD, THEN GO SOUTHERLY ON LEASE ROAD 0.1 MILE TO THE PERCUSSION ROSS RANCH 22 #3 LOCATION AND PROPOSED LEASE ROAD.



P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241

(575) 393-7316 - Office (575) 392-2206 - Fax

ARTESIA, NM IS ±14 MILES TO THE NORTHEAST OF LOCATION.

200 200 400 FEET SCALE: 1" = 200'


# PERCUSSION PETROLEUM OPERATING, LLC


OSAGE BOYD 15 FEDERAL COM 13H / WELL PAD TOPO THE OSAGE BOYD 15 FEDERAL COM 13H LOCATED 649' FROM

THE NORTH LINE AND 1180' FROM THE WEST LINE OF SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST,


N.M.P.M., EDDY COUNTY, NEW MEXICO.

Survey Date: 05-12-2018 Sheet 1 of 1 33762 Drawn By: K. GOAD Date: 05-17-2018 W.O. Number:





MAP 7A



#### PERCUSSION PETROLEUM OPERATING, LLC OSAGE BOYD 15 FEDERAL COM 13H ELEV. - 3468'

Lat - N 32.652008\* Long - W 104.477351\* NMSPCE- N 600961.6 E 497012.6 (NAD-83)

Directions to Location:

FROM US HIGHWAY 285, GO WEST ON ROCKING R RED ROAD 4.6 MILES TO LEASE ROAD, THEN GO SOUTHERLY ON LEASE ROAD 0.1 MILE TO THE PERCUSSION ROSS RANCH 22 #3 LOCATION AND PROPOSED LEASE ROAD.



(575) 393-7316 - Office (575) 392-2206 - Fax P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241


ARTESIA, NM IS ±14 MILES TO THE NORTHEAST OF LOCATION.

200 400 FEET SCALE: 1" = 200'

# PERCUSSION PETROLEUM OPERATING, LLC


REF: OSAGE BOYD 15 FEDERAL COM 13H / WELL PAD TOPO THE OSAGE BOYD 15 FEDERAL COM 13H LOCATED 649' FROM THE NORTH LINE AND 1180' FROM THE WEST LINE OF SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.


W.O. Number: 33762 Drawn By: K. GOAD Date: 05-17-2018 Survey Date: 05-12-2018 Sheet 1 of 1



A TRACT OF LAND LOCATED IN SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS.

BEGINNING AT A POINT WHICH LIES S.89'53'53"W., 424.5 FEET AND S.00'06'07"E., 905.0 FEET FROM THE NORTH QUARTER CORNER OF SAID SECTION 22; THENCE S.41'41'43"W., 198.6 FEET; THENCE S.78'14'07"W., 132.7 FEET; THENCE N.14'32'31"W., 108.7 FEET; THENCE N.76'22'13"E., 297.6 FEET TO THE POINT OF BEGINNING. SAID TRACT OF LAND CONTAINING 0.55 ACRES, MORE OR LESS.





#### LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY.

BEGINNING AT A POINT WHICH LIES S20'46'36"E., 2017.9 FEET FROM THE NORTHWEST CORNER OF SAID SECTION 22; THENCE N44'04'34"E., 857.4 FEET TO A POINT ON THE EAST PROPERTY LINE WHICH LIES S45'54'38"E., 1826.7 FEET FROM THE NORTHWEST CORNER OF SAID SECTION 22. SAID STRIP OF LAND BEING 857.4 FEET OR 51.96 RODS IN LENGTH.



focused on excellence

P.O. Box 1786 1120 N. West County Rd. (575) 393-7316 - Office 1120 N. West County Rd. (575) 392-2206 - Fax Hobbs, New Mexico 88241 basinsurveys.com


1000 1000 2000 FEET

# PERCUSSION PETROLEUM OPERATING, LLC

REF: PROPOSED CRUDE OIL LINE TO OSAGE BATTERY

A PIPELINE CROSSING FEE LAND IN SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

Drawn By: J GOAD 33905 Sheet 1 of 2 W.O. Number: Date: 7-24-2018 Survey Date: 7-12-2018




# LEGAL DESCRIPTION

1000

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY.

BEGINNING AT A POINT ON A POINT ON THE WEST PROPERTY LINE WHICH LIES \$45.54'38"E., 1826.7 FEET FROM THE NORTHWEST CORNER OF SAID SECTION 22; THENCE N44'04'34"E., 189.2 FEET; THENCE N71'55'21"E., 503.2 FEET TO THE END OF THIS LINE WHICH LIES S35'48'21"W., 1202.0 FEET FROM THE NORTH QUARTER CORNER OF SAID SECTION 22. SAID STRIP OF LAND BEING 692.4 FEET OR 41.96 RODS IN LENGTH.



PERCUSSION PETROLEUM OPERATING, LLC REF: PROPOSED CRUDE OIL LINE TO OSAGE BATTERY


1000


2000 FEET


0

A PIPELINE CROSSING FEE LAND IN SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

W.O. Number: 33905 Drawn By: J GOAD Date: 7-24-2018 Survey Date: 7-12-2018 Sheet 2 of 2







SCALE: 1" = 100'

# PERCUSSION PETROLEUM OPERATING, LLC

REF: OSAGE BOYD 15 FEDERAL COM 13H / WELL PAD TOPO THE OSAGE BOYD 15 FEDERAL COM 13H LOCATED 649' FROM


THE NORTH LINE AND 1180' FROM THE WEST LINE OF SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST,


N.M.P.M., EDDY COUNTY, NEW MEXICO.

P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 basinsurveys.com

Drawn By: K. GOAD 33762 Date: 05-17-2018 Survey Date: 05-12-2018 Sheet 1 of 1 Sheets







# PERCUSSION PETROLEUM OPERATING, LLC

OSAGE BOYD 15 FEDERAL COM 12H,13H&14H/WELL PAD TOPO


THE OSAGE BOYD 15 FEDERAL COM 12H,13H&14H LOCATED IN SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.



P.O. Box 1786 (575) 393-7316 - Office 1120 N. West County Rd. (575) 392-2206 - Fax Hobbs, New Mexico 88241 basinsurveys.com

Sheet 1 of 33761 Drawn By: K. GOAD Date: 05-17-2018 Survey Date: 05-12-2018 W.O. Number:

(MAP 11 )



# PERCUSSION PETROLEUM OPERATING, LLC

REF: OSAGE BOYD 15 FEDERAL COM 12H,13H&14H / PAD CROSS SECTION

THE OSAGE BOYD 15 FEDERAL COM 12H,13H&14H LOCATED IN SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.


SULL VEYS
focused on excellence
in the oilfield

P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 8824!

(575) 393-7316 - Office (575) 392-2206 - Fax basinsurveys.com

W.O. Number: 33758 Drawn By: K. GOAD Date: 05-17-2018 Survey Date: 05-12-2018 Sheet 1 of 1 Sheets





100 100 **200 FEET** SCALE: 1" = 100'

# PERCUSSION PETROLEUM OPERATING, LLC

REF: OSAGE BOYD 15 FEDERAL COM 13H / WELL PAD TOPO THE OSAGE BOYD 15 FEDERAL COM 13H LOCATED 649' FROM THE NORTH LINE AND 1180' FROM THE WEST LINE OF SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.



W.O. Number:

33762


P.O. Box 1786 1120 N. West County Rd. (575) 393-7316 - Office 1575) 392-2206 - Fax Hobbs, New Mexico 88241 basinsurveys.com

Drawn By: K. GOAD Date: 05-17-2018 Survey Date: 05-12-2018 Sheet 1 of 1 Percussion's
Osage Boyd 15 Federal Com 13H
rig diagram

Prevailing Wind out of South or SSE


1" = 501

NORTH <





MAP 14



# 100 0 100 200 FEET SCALE: 1" = 100'

# PERCUSSION PETROLEUM OPERATING, LLC

REF: OSAGE BOYD 15 FEDERAL COM 13H / WELL PAD TOPO

THE OSAGE BOYD 15 FEDERAL COM 13H LOCATED 649' FROM

THE NORTH LINE AND 1180' FROM THE WEST LINE OF

SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST,


N.M.P.M., EDDY COUNTY, NEW MEXICO.

focused on excellence in the oilfield

P.O. Box 1786 (575) 393-7316 - Office 1120 N. West County Rd. (575) 392-2206 - Fax Hobbs, New Mexico 88241 basinsurveys.com

W.O. Number: 33762 Drawn By: K. GOAD Date: 05-17-2018 Survey Date: 05-12-2018 Sheet 1 of 1 Sheets

MAP 15





# PERCUSSION PETROLEUM OPERATING, LLC

REF: OSAGE BOYD 15 FEDERAL COM 12H,13H&14H/WELL PAD TOPO

THE OSAGE BOYD 15 FEDERAL COM 12H,13H&14H LOCATED IN SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.


SULLY ON Excellence

P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241

(575) 393—7316 — Office (575) 392—2206 — Fax basinsurveys.com

W.O. Number: 33761 Drawn By: K. GOAD Date: 05-17-2018 Survey Date: 05-12-2018 Sheet 1 of 1

MAP 16:



# PERCUSSION PETROLEUM OPERATING, LLC

REF: OSAGE BOYD 15 FEDERAL COM 12H,13H&14H / PAD CROSS SECTION

THE OSAGE BOYD 15 FEDERAL COM 12H,13H&14H LOCATED IN SECTION 22, TOWNSHIP 19 SOUTH, RANGE 25 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

SUITVEYS
focused on excellence
in the oilfield

P.O. Box 1786 (575) 393-7316 - Office 1120 N. West County Rd. (575) 392-2206 - Fax Hobbs, New Mexico 88241 basinsurveys.com

W.O. Number: 33758 | Drawn By: K. GOAD | Date: 05-17-2018 | Survey Date: 05-12-2018 | Sheet 1 of 1 Sheets

Percussion Petroleum Operating, LLC Osage Boyd 15 Federal Com 13H SHL 649' FNL & 1180' FWL 22-19S-25E Eddy County, NM

# 1. ROAD DIRECTIONS & DESCRIPTIONS (See MAPS 1 – 4)

From the junction of US 82 & US 285 in Artesia...
Go South 13.2 miles on US 285 to the equivalent of Mile Post 56.5
Then turn right and go West 4.6 miles on paved County Road 21 (Rocking R)
Then turn left and go SW 0.2 mile on a caliche road to the SW corner of Percussion's existing Ross Ranch Goodman pad
Then go West 620' cross-country to the SE corner of the 12H/13H/14H pad

Non-county roads will be maintained as needed to Gold Book standards. This includes pulling ditches and preserving the crown. This will be done at least once a year, and more often as needed.

# 2. ROAD TO BE BUILT OR UPGRADED (See MAPS 3 & 4)

The 620' of new resource road will be crowned and ditched, have a 14' wide driving surface, and be surfaced with caliche. Maximum disturbed width = 30'. Maximum grade = 5%. Maximum cut or fill = 3'. No culvert, cattle guard, or vehicle turn out is needed. Upgrade will consist of filling potholes with caliche as needed.

# 3. EXISTING WELLS (See MAP 5)

Existing oil, gas, water, disposal, and P & A wells are within a mile. No injection well is within a mile radius.

# 4. <u>PROPOSED PRODUCTION FACILITIES</u> (See MAPS 6 – 7E)

An 842' long  $\approx$ 4" O D. HDPE flow line will be laid on the surface southeast to a proposed central tank battery (CTB). CTB will sit on the south side of Percussion's existing three well Ross Ranch Goodman pad. Maximum operating pressure will be <125 psi.



Percussion Petroleum Operating, LLC Osage Boyd 15 Federal Com 13H SHL 649' FNL & 1180' FWL 22-19S-25E Eddy County, NM

A 668' 3-phase raptor safe overhead power line will be built east to tie into an existing power line that serves the Ross Ranch Goodman pad.

A 1549.8' long  $\approx$ 4" O D. HDPE crude oil line will be laid on the surface from the CTB southwest to an existing crude oil line at Percussion's Ross Ranch 22 #2 pad. Maximum operating pressure will be <125 psi.

# 5. WATER SUPPLY (See MAP 8)

Water will be piped via temporary ≈13,000' long surface 10" Kevlar lay flat pipelines (2) from Percussion's existing lined fresh water pond on its own land in NE4 26-19s-25e. Pipeline route will not be bladed or excavated. Route is all private. Route follows existing roads, pads, and pipelines.

# 6. CONSTRUCTION MATERIALS & METHODS (See MAPS 9 - 12)

NM One Call (811) will be notified before construction starts. Top  $\approx 6$ " of soil and brush will be stockpiled north of the pad. V-door will face east. Closed loop drilling system will be used. Caliche will be hauled from existing caliche pit on private land. Arkland caliche pit is in NWNE 23-19s-25e.

#### 7. WASTE DISPOSAL

All trash will be placed in a portable trash cage. It will be hauled to the Eddy County landfill. There will be no trash burning. Contents (drill cuttings, mud, salts, and other chemicals) of the mud tanks will be hauled to R360's state approved (NM-01-0006) disposal site at Halfway. Human waste will be disposed of in chemical toilets and hauled to the Artesia wastewater treatment plant.



Percussion Petroleum Operating, LLC Osage Boyd 15 Federal Com 13H SHL 649' FNL & 1180' FWL 22-19S-25E Eddy County, NM

#### 8. ANCILLARY FACILITIES

There will be no airstrip or camp. Camper trailers will be on location for the company man, tool pusher, and mud logger.

# 9. WELL SITE LAYOUT (See MAP 13)

Also see Rig Layout diagram for depictions of the well pad, trash cage, access onto the location, parking, living facilities, and rig orientation.

#### 10. RECLAMATION (See MAPS 14 - 16)

Interim reclamation will be completed within 6 months of completing the well. Interim reclamation will consist of shrinking the well pad 0.41 acre by removing caliche and reclaiming 50' on the north side of the pad. This will leave 1.95 acres for the anchors, pump jacks, and tractor-trailer turn around. Disturbed areas will be contoured to match pre-construction grades. Soil and brush will be evenly spread over disturbed areas and harrowed on the contour. Disturbed areas will be seeded in accordance with surface owner's requirements.

Enough stockpiled topsoil will be retained to cover the remainder of the pad when the well is plugged. Once the last well is plugged, then the rest of the pad will be similarly reclaimed within 6 months of plugging. Noxious weeds will be controlled.



# Percussion Petroleum Operating, LLC Osage Boyd 15 Federal Com 13H SHL 649' FNL & 1180' FWL 22-19S-25E Eddy County, NM

**SURFACE PLAN PAGE 4** 

Land use will be:

30' x 620' road = 0.43 acre
30' x 668' power line = 0.47 acre
30' x 842' flowline = 0.58 acre
30' x 1549.8' crude oil line = 1.07 acres
297.6' x 198.6' x 132.7' x 108.7' CTB = 0.55 acre
20' x 13,000' water line from pond = 5.97 acres
+ 300 x 340' well pad = 2.34 acres
11.41 acres short term
- 0.47 acre power line
- 0.58 acre flowline
- 1.07 acres oil line
- 5.97 acres water line from pond
- 0.39 acre interim reclamation on well pad
2.93 acres (0.43 ac. road + 0.55 ac. CTB + 1.95 ac. pad) long term

### 11. SURFACE OWNER

Well pad, road; power line, CTB, flow line, and 692.4' of oil line construction will be on private land (NWNW & E2NW4 22-19s-25e) owned by Jerome Hugh Jones et al and leased to Ross Ranch, P. O. Box 216, Lakewood NM 88254. Ranch phone number is (575) 365-4797. Jones phone number is (703) 352-0067. Percussion has an agreement with the Ranch and Jones.

Remaining 857.4' of oil line construction will be on private land (SWNW 22-19s-25e) owned by Ross & Barbara Whitney Trust, 25601 E. 130<sup>th</sup> St., Greenwood MO 64034. Phone number is (816) 525-1233. Percussion has an agreement with the Trust.

#### 12. OTHER INFORMATION

On-site inspection was held with Matt Wirth (BLM) on July 12, 2018. Lone Mountain inspected the well pad and submitted archaeology report NMCRIS-141118 on August 7, 2018. APAC inspected the oil line and submitted report NMCRIS-141712 on October 25, 2018.



Percussion Petroleum Operating, LLC Osage Boyd 15 Federal Com 13H SHL 649' FNL & 1180' FWL 22-19S-25E Eddy County, NM

#### **CERTIFICATION**

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U. S. C. 1001 for the filing of false statements. Executed this 3rd day of November, 2018.

Brian Wood, Consultant

Permits West, Inc.

37 Verano Loop, Santa Fe, NM 87508

(505) 466-8120

FAX: (505) 466-9682

Cellular: (505) 699-2276

Field representative will be:

Lelan Anders, Operations Manager Percussion Petroleum Operating, LLC 919 Milam, Suite 2475

Houston TX 77002

Office: (713) 429-1291 Mobile: (281) 908-1752

### To Who It May Concern:

Osage Boyd 15 Federal Com 12H 13H 14H well pad, road, power line, CTB, flow line, and 692.4' of oil line construction will be on private land (NWNW & E2NW4 22-19s-25e) owned by Jerome Hugh Jones et al and leased to Ross Ranch, P. O. Box 216, Lakewood NM 88254. Ranch phone number is (575) 365-4797. Jones phone number is (703) 352-0067. Percussion has an agreement with the Ranch and Jones.

Remaining 857.4' of oil line construction will be on private land (SWNW 22-19s-25e) owned by Ross & Barbara Whitney Trust, 25601 E. 130<sup>th</sup> St., Greenwood MO 64034. Phone number is (816) 525-1233. Percussion has an agreement with the Trust.

Brian Wood



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT



#### Section 1 - General

Would you like to address long-term produced water disposal? NO

#### Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

**Produced Water Disposal (PWD) Location:** 

PWD surface owner:

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Decribe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

**Lined pit Monitor attachment:** 

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

PWD disturbance (acres):

# Section 3 - Unlined Pits

Unlined pit PWD on or off channel:

Decribe precipitated solids disposal:

PWD surface owner:

Unlined pit specifications:

Precipitated solids disposal:

**Produced Water Disposal (PWD) Location:** 

Unlined pit PWD discharge volume (bbl/day):

Would you like to utilize Unlined Pit PWD options? NO

	•
Precipitated solids disposal permit:	
Unlined pit precipitated solids disposal schedule:	
Unlined pit precipitated solids disposal schedule attachment:	
Unlined pit reclamation description:	
Unlined pit reclamation attachment:	
Unlined pit Monitor description:	
Unlined pit Monitor attachment:	
Do you propose to put the produced water to beneficial use?	
Beneficial use user confirmation:	
Estimated depth of the shallowest aquifer (feet):	
Does the produced water have an annual average Total Dissorthat of the existing water to be protected?	lved Solids (TDS) concentration equal to or less than
TDS lab results:	
Geologic and hydrologic evidence:	
State authorization:	
Unlined Produced Water Pit Estimated percolation:	
Unlined pit: do you have a reclamation bond for the pit?	
Is the reclamation bond a rider under the BLM bond?	
Unlined pit bond number:	
Unlined pit bond amount:	
Additional bond information attachment:	
Section 4 - Injection	
Would you like to utilize Injection PWD options? NO	
Produced Water Disposal (PWD) Location:	
PWD surface owner:	PWD disturbance (acres):
Injection PWD discharge volume (bbl/day):	
Injection well mineral owner:	

PWD disturbance (acres):

Injection well type:	
Injection well number:	Injection well name:
Assigned injection well API number?	Injection well API number:
Injection well new surface disturbance (acres):	
Minerals protection information:	
Mineral protection attachment:	
Underground Injection Control (UIC) Permit?	
UIC Permit attachment:	
Section 5 - Surface Discharge	
Would you like to utilize Surface Discharge PWD options? NO	
Produced Water Disposal (PWD) Location:	
PWD surface owner:	PWD disturbance (acres):
Surface discharge PWD discharge volume (bbl/day):	
Surface Discharge NPDES Permit?	
Surface Discharge NPDES Permit attachment:	
Surface Discharge site facilities information:	
Surface discharge site facilities map:	
Section 6 - Other	
Would you like to utilize Other PWD options? NO	
Produced Water Disposal (PWD) Location:	
PWD surface owner:	PWD disturbance (acres):
Other PWD discharge volume (bbl/day):	
Other PWD type description:	
Other PWD type attachment:	
Have other regulatory requirements been met?	
Other regulatory requirements attachment:	



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

# Bond Info Data Report 05/30/2019

### **Bond Information**

Federal/Indian APD: FED

**BLM Bond number: NMB001424** 

**BIA Bond number:** 

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

**BLM** reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

**Reclamation bond amount:** 

Reclamation bond rider amount:

Additional reclamation bond information attachment: