District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION 1220 South St. Francis Dr. Santa Fe. NM 87505

Form C-102 Revised August 1, 2011 Submit one copy to appropriate District Office


☐ AMENDED REPORT

36015-4	6/75WE	LL LOCATION A	ND ACREAGE	DEDICATION	I PLAT

1 API Number 3 25 3 88		9	Pool Code	O Purp	Purple Sage; Wolfcamp					
⁴ Property	Code	,	POKER LAKE UNIT 29 65					. 6,	⁶ Well Number 102H	
7 OGRID No. 260737 37 3075				⁸ Operator Name XTO PERMIAN OPERATING, LLC.				⁹ Elevation 3365'		
[™] Surface Location										
UL or lot no.	Section 29	Township 25 S	Range 31 E	Lot Ida	Feet from the 2,310	North/South line NORTH	Feet from the 720	East/West line WEST	County EDDY	

"Bottom Hole Location If Different From Surface UL or let no. North/South line Section Township Range Feet from the Feet from the East/West line County 26 S 31 E 200 SOUTH 990 WEST EDDY 12 Dedicated Acres Joint or Infill 4 Consolidation Code ¹³ Order No. 800

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.





U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

APD ID: 10400037091

Submission Date: 12/11/2018

Highlighted data reflects the most

recent changes

Operator Name: XTO PERMIAN OPERATING LLC

Well Number: 102H

Well Type: CONVENTIONAL GAS WELL

Well Name: POKER LAKE UNIT 29 BS

Well Work Type: Drill

Show Final Text

Section 1 - Geologic Formations

Formation		41.5	True Vertical	Measured		1	Producing
ID	Formation Name	Elevation	Depth	Depth	Lithologies	Mineral Resources	Formation
1	PERMIAN	3365	0	Ö	OTHER : Quaternary	NONE	No
2	RUSTLER	2519	845	845	SILTSTONE	USEABLE WATER	No
3	TOP SALT	2163	1202	1202	SALT	OTHER : Produced Water	No .
4	BASE OF SALT	-535	3900	3900	SALT	OTHER : Produced Water	No
5	DELAWARE	-753	4118	4118	SANDSTONE	NATURAL GAS,OIL,OTHER : Produced Water	No
6	BONE SPRING	-4671	8036	8036	SANDSTONE .	NATURAL GAS,OIL,OTHER: Produced Water	No
7	BONE SPRING 1ST	-5715	9080	9080	SANDSTONE	NATURAL GAS,OIL,OTHER: Produced Water	No
8	BONE SPRING 2ND	-6395	9760	9760	SANDSTONE	NATURAL GAS,OIL,OTHER: Produced Water	No
9	BONE SPRING 3RD	-7645	11010	11010	SANDSTONE	NATURAL GAS,OIL,OTHER: Produced Water	No
10	WOLFCAMP	-8061	11426	11426	SHALE	NATURAL GAS,OIL,OTHER: Produced Water	Yes

Section 2 - Blowout Prevention

Pressure Rating (PSI): 5M

Rating Depth: 11486

Equipment: The blow out preventer equipment (BOP) for this well consists of a 13-5/8" minimum 5M Hydril and a 13-5/8" minimum 5M Double Ram BOP. MASP should not exceed 3625 psi.

Requesting Variance? YES

Variance request: A variance is requested to allow use of a flex hose as the choke line from the BOP to the Choke Manifold. If this hose is used, a copy of the manufacturer's certification and pressure test chart will be kept on the rig. Attached is an example of a certification and pressure test chart. The manufacturer does not require anchors. In any instance where 10M BOP is required by BLM, XTO requests a variance to utilize 5M annular with 10M ram preventers (a common BOP configuration, which allows use of 10M rams in unlikely event that pressures exceed 5M).

Testing Procedure: All BOP testing will be done by an independent service company. Annular pressure tests will be limited to 50% of the working pressure. When nippling up on the 13-5/8" 5M bradenhead and flange, the BOP test will be limited to 5000 psi. When nippling up on the 9-5/8", the BOP will be tested to a minimum of 5000 psi. All BOP tests will include a low pressure test as per BLM regulations. The 5M BOP diagrams are attached. Blind rams will be functioned tested each trip, pipe rams will be functioned tested each day.