

NM OIL CONSERVATION
ARTESIA DISTRICT

OCT 22 2019

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: ☒ DRILL ☐ REENTER
1b. Type of Well: ☒ Oil Well ☒ Gas Well ☐ Other
1c. Type of Completion: ☐ Hydraulic Fracturing ☐ Single Zone ☒ Multiple Zone

2. Name of Operator
MEWBOURNE OIL COMPANY

3a. Address
PO Box 5270 Hobbs NM 88240

3b. Phone No. (include area code)
(575)393-5905

4. Location of Well (Report location clearly and in accordance with any State requirements. *)
At surface NESE / 2250 FSL / 270 FEL / LAT 32.0413015 / LONG -103.9300949
At proposed prod. zone SESE / 330 FSL / 330 FEL / LAT 32.0213914 / LONG -103.9302757

5. Lease Serial No.
NMLC0061497

6. If Indian, Allottee or Tribe Name

7. If Unit or CA Agreement, Name and No.

8. Lease Name and Well No.

FULLER-13/24WIPFED.COM

9. API Well No.

10. Field and Pool, or Exploratory
PURPLE SAGE WOLFCAMP GAS / LOW

11. Sec. T. R. M. or Blk. and Survey or Area
SEC 13 / T26S / R29E / NMP

14. Distance in miles and direction from nearest town or post office*
25 miles

12. County or Parish
EDDY

13. State
NM

15. Distance from proposed*
location to nearest
property or lease line, ft.
(Also to nearest drig. unit line, if any)
330 feet

16. No of acres in lease
640

17. Spacing Unit dedicated to this well
240

18. Distance from proposed location*
to nearest well, drilling, completed,
applied for, on this lease, ft.
50 feet

19. Proposed Depth
10644 feet / 18079 feet

20. BLM/BIA Bond No. in file
FED: NM1693

21. Elevations (Show whether DF, KDB, RT, GL, etc.)
3043 feet

22. Approximate date work will start*
01/16/2019

23. Estimated duration
60 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM.

25. Signature
(Electronic Submission)

Name (Printed/Typed)
Bradley Bishop / Ph: (575)393-5905

Date
12/05/2018

Title
Regulatory

Approved by (Signature)
(Electronic Submission)

Name (Printed/Typed)
Cody Layton / Ph: (575)234-5959

Date
10/18/2019

Title
Assistant Field Manager Lands & Minerals

Office
CARLSBAD

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

APPROVED WITH CONDITIONS

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	MEWBOURNE OIL COMPANY
LEASE NO.:	NMLC0061497
LOCATION:	Section 13, T.26 S., R.29 E., NMPM
COUNTY:	Eddy County, New Mexico

WELL NAME & NO.:	FULLER 13/12 W1HA FED COM 1H
SURFACE HOLE FOOTAGE:	2250'/S & 330'/E
BOTTOM HOLE FOOTAGE:	330'/N & 330'/E

WELL NAME & NO.:	FULLER 13/12 W1HA FED COM 2H
SURFACE HOLE FOOTAGE:	2250'/S & 360'/E
BOTTOM HOLE FOOTAGE:	330'/N & 990'/E

WELL NAME & NO.:	FULLER 13/24 W1IP FED COM 1H
SURFACE HOLE FOOTAGE:	2250'/S & 270'/E
BOTTOM HOLE FOOTAGE:	330'/S & 330'/E

WELL NAME & NO.:	FULLER 13/24 W1IP FED COM 2H
SURFACE HOLE FOOTAGE:	2250'/S & 300'/E
BOTTOM HOLE FOOTAGE:	330'/S & 990'/E

COA

H2S	<input type="radio"/> Yes	<input checked="" type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input type="radio"/> Low	<input checked="" type="radio"/> Medium	<input type="radio"/> High
Cave/Karst Potential	<input type="radio"/> Critical		
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input type="checkbox"/> Fluid Filled	<input type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including

lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

Hydrogen Sulfide Drilling Operations Plan
Mewbourne Oil Company

1. General Requirements

Rule 118 does not apply to this well because MOC has researched this area and no high concentrations of H₂S were found. MOC will have on location and working all H₂S safety equipment before the Delaware formation for purposes of safety and insurance requirements.

2. Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will have received training from a qualified instructor in the following areas prior to entering the drilling pad area of the well:

1. The hazards and characteristics of hydrogen sulfide gas.
2. The proper use of personal protective equipment and life support systems.
3. The proper use of hydrogen sulfide detectors, alarms, warning systems, briefing areas, evacuation procedures.
4. The proper techniques for first aid and rescue operations.

Additionally, supervisory personnel will be trained in the following areas:

- 1 The effects of hydrogen sulfide on metal components. If high tensile tubular systems are utilized, supervisory personnel will be trained in their special maintenance requirements.
- 2 Corrective action and shut in procedures, blowout prevention, and well control procedures while drilling a well.
- 3 The contents of the Hydrogen Sulfide Drilling Operations Plan.

There will be an initial training session prior to encountering a known hydrogen sulfide source.

The initial training session shall include a review of the site specific Hydrogen Sulfide Drilling Operations Plan.

3. Hydrogen Sulfide Safety Equipment and Systems

All hydrogen sulfide safety equipment and systems will be installed, tested, and operational prior to drilling below the 9 5/8" intermediate casing.

1. Well Control Equipment

- A. Choke manifold with minimum of one adjustable choke/remote choke.
 - B. Blowout preventers equipped with blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
 - C. Auxiliary equipment including annular type blowout preventer.
2. Protective Equipment for Essential Personnel

Thirty minute self contained work unit located in the dog house and at briefing areas.

Additionally: If H₂S is encountered in concentrations less than 10 ppm, fans will be placed in work areas to prevent the accumulation of hazardous amounts of poisonous gas. If higher concentrations of H₂S are detected the well will be shut in and a rotating head, mud/gas separator, remote choke and flare line with igniter will be installed.

3. Hydrogen Sulfide Protection and Monitoring Equipment

Two portable hydrogen sulfide monitors positioned on location for optimum coverage and detection. The units shall have audible sirens to notify personnel when hydrogen sulfide levels exceed 20 PPM.

4. Visual Warning Systems

- A. Wind direction indicators as indicated on the wellsite diagram.
- B. Caution signs shall be posted on roads providing access to location. Signs shall be painted a high visibility color with lettering of sufficient size to be readable at reasonable distances from potentially contaminated areas.

4. **Mud Program**

The mud program has been designed to minimize the amount of hydrogen sulfide entrained in the mud system. Proper mud weight, safe drilling practices, and the use of hydrogen sulfide scavengers will minimize hazards while drilling the well.

5. **Metallurgy**

All tubular systems, wellheads, blowout preventers, drilling spools, kill lines, choke manifolds, and valves shall be suitable for service in a hydrogen sulfide environment when chemically treated.

6. Communications

State & County Officials phone numbers are posted on rig floor and supervisors trailer. Communications in company vehicles and toolpushers are either two way radios or cellular phones.

7. Well Testing

Drill stem testing is not an anticipated requirement for evaluation of this well. If a drill stem test is required, it will be conducted with a minimum number of personnel in the immediate vicinity. The test will be conducted during daylight hours only.

8. Emergency Phone Numbers

Eddy County Sheriff's Office	911 or 575-887-7551
Ambulance Service	911 or 575-885-2111
Carlsbad Fire Dept	911 or 575-885-2111
Loco Hills Volunteer Fire Dept.	911 or 575-677-3266
Closest Medical Facility - Columbia Medical Center of Carlsbad 575-492-5000	

Mewbourne Oil Company	Hobbs District Office 575-393-5905
	Fax 575-397-6252
	2nd Fax 575-393-7259

District Manager	Robin Terrell	575-390-4816
Drilling Superintendent	Frosty Lathan	575-390-4103
	Bradley Bishop	575-390-6838
Drilling Foreman	Wesley Noseff	575-441-0729



Application for Permit to Drill

APD Package Report

Date Printed: 10/18/2019 01:44 PM

APD ID: 10400036359

Well Status: AAPD

APD Received Date: 12/05/2018 10:33 AM

Well Name: FULLER 13/24 W1IP FED CO

Operator: MEWBOURNE OIL COMPANY

Well Number: 1H

APD Package Report Contents

- Form 3160-3 : Error Generating Form
- Operator Certification Report
- Application Report
- Application Attachments
 - Well Plat: 1 file(s)
- Drilling Plan Report
- Drilling Plan Attachments
 - Blowout Prevention Choke Diagram Attachment: 2 file(s)
 - Blowout Prevention BOP Diagram Attachment: 2 file(s)
 - Casing Design Assumptions and Worksheet(s): 4 file(s)
 - Hydrogen sulfide drilling operations plan: 1 file(s)
 - Proposed horizontal/directional/multi-lateral plan submission: 2 file(s)
 - Other Facets: 2 file(s)
- SUPO Report
- SUPO Attachments
 - Existing Road Map: 1 file(s)
 - New Road Map: 1 file(s)
 - Attach Well map: 1 file(s)
 - Production Facilities map: 2 file(s)
 - Water source and transportation map: 1 file(s)
 - Construction Materials source location attachment: 1 file(s)
 - Well Site Layout Diagram: 1 file(s)
 - Other SUPO Attachment: 2 file(s)
- PWD Report
- PWD Attachments
 - None
- Bond Report

- Bond Attachments

-- None



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

10/18/2019

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Bradley Bishop

Signed on: 12/05/2018

Title: Regulatory

Street Address:

City:

State:

Zip:

Phone: (575)393-5905

Email address: bbishop@mewbourne.com

Field Representative

Representative Name:

Street Address:

City:

State:

Zip:

Phone:

Email address:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data Report

10/18/2019

APD ID: 10400036359

Submission Date: 12/05/2018

Highlighted data
reflects the most
recent changes

Operator Name: MEWBOURNE OIL COMPANY

Well Name: FULLER 13/24 W1IP FED COM

Well Number: 1H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - General

APD ID: 10400036359

Tie to previous NOS?

Submission Date: 12/05/2018

BLM Office: CARLSBAD

User: Bradley Bishop

Title: Regulatory

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMLC0061497

Lease Acres: 640

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO

APD Operator: MEWBOURNE OIL COMPANY

Operator letter of designation:

Operator Info

Operator Organization Name: MEWBOURNE OIL COMPANY

Operator Address: PO Box 5270

Zip: 88240

Operator PO Box:

Operator City: Hobbs

State: NM

Operator Phone: (575)393-5905

Operator Internet Address:

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: FULLER 13/24 W1IP FED COM

Well Number: 1H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: PURPLE SAGE
WOLFCAMP GAS

Pool Name: LOWER 3RD
BONE SPRING (HARKY)
SHALE

Operator Name: MEWBOURNE OIL COMPANY

Well Name: FULLER 13/24 W1IP FED COM

Well Number: 1H

Is the proposed well in an area containing other mineral resources? USEABLE WATER,NATURAL GAS,OIL

Is the proposed well in a Helium production area? N Use Existing Well Pad? YES New surface disturbance? Y

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name:

Number: 4

Well Class: HORIZONTAL

FULLER 13/12 HA & IP WELLS

Number of Legs:

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: APPRAISAL

Describe sub-type:

Distance to town: 25 Miles

Distance to nearest well: 50 FT

Distance to lease line: 330 FT

Reservoir well spacing assigned acres Measurement: 240 Acres

Well plat: FULLER13_24W1IPFedCom1H_wellplat_20181116103448.pdf

Well work start Date: 01/16/2019

Duration: 60,DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number:

Reference Datum:

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce
SHL Leg #1	225 0	FSL	270	FEL	26S	29E	13	Aliquot NESE	32.04130 15	- 103.9300 949	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 061497	304 3	0	0	
KOP Leg #1	265 8	FSL	330	FEL	26S	29E	13	Aliquot NESE	32.04242 37	- 103.9302 9	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 061497	- 704 8	101 01	100 91	
PPP Leg #1	0	FNL	330	FEL	26S	29E	24	Aliquot NENE	32.03510 87	- 103.9302 85	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 061581	- 761 5	130 89	106 58	

Operator Name: MEWBOURNE OIL COMPANY

Well Name: FULLER 13/24 W1IP FED COM

Well Number: 1H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce
PPP Leg #1	0	FNL	330	FEL	26S	29E	24	Aliquot NENE	32.03510 87	- 103.9302 85	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 061581	- 761 5	130 89	106 58	
PPP Leg #1	0	FNL	330	FEL	26S	29E	24	Aliquot NENE	32.03510 87	- 103.9302 85	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 061581	- 761 5	130 89	106 58	
PPP Leg #1	232 8	FSL	330	FEL	26S	29E	13	Aliquot NESE	32.04151 65	- 103.9302 894	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 061497	- 756 7	107 50	106 10	
PPP Leg #1	232 8	FSL	330	FEL	26S	29E	13	Aliquot NESE	32.04151 65	- 103.9302 894	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 061497	- 756 7	107 50	106 10	
PPP Leg #1	232 8	FSL	330	FEL	26S	29E	13	Aliquot NESE	32.04151 65	- 103.9302 894	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 061497	- 756 7	107 50	106 10	
EXIT Leg #1	330	FSL	330	FEL	26S	29E	24	Aliquot SESE	32.02139 14	- 103.9302 757	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 061581	- 760 1	180 79	106 44	
BHL Leg #1	330	FSL	330	FEL	26S	29E	24	Aliquot SESE	32.02139 14	- 103.9302 757	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 061581	- 760 1	180 79	106 44	

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (505) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

1 API Number	2 Pool Code 98220	3 Pool Name PURPLE SAGE WOLFCAMP
4 Property Code	5 Property Name FULLER 13/24 W1IP FED COM	6 Well Number 1H
7 OGRID NO. 14744	8 Operator Name MEWBOURNE OIL COMPANY	9 Elevation 3016'

10 Surface Location

UL or lot no.	Section	Township	Range	Lot 1dn	Feet from the	North/South line	Feet from the	East/West line	County
I	13	26S	29E		2250	SOUTH	270	EAST	EDDY

11 Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot 1dn	Feet from the	North/South line	Feet from the	East/West line	County
P	24	26S	29E		330	SOUTH	330	EAST	EDDY

12 Dedicated Acres 480	13 Joint or Infill	14 Consolidation Code	15 Order No.
---------------------------	--------------------	-----------------------	--------------

No allowable will be assigned to this completion until all interest have been consolidated or a non-standard unit has been approved by the division.

<p>CORNER DATA NAD 83 GRID - NM EAST</p> <p>A: FOUND BRASS CAP "1940" N: 371124.3 - E: 661488.2</p> <p>B: FOUND BRASS CAP "1940" N: 373802.7 - E: 661493.7</p> <p>C: FOUND BRASS CAP "1940" N: 376497.1 - E: 661496.5</p> <p>D: FOUND BRASS CAP "1940" N: 379187.8 - E: 661491.3</p> <p>E: FOUND BRASS CAP "1940" N: 381882.4 - E: 661489.4</p> <p>F: FOUND BRASS CAP "1940" N: 381978.1 - E: 664013.6</p> <p>G: FOUND BRASS CAP "1940" N: 382074.4 - E: 666537.7</p> <p>H: FOUND BRASS CAP "1940" N: 379419.0 - E: 666548.9</p> <p>I: FOUND BRASS CAP "1940" N: 376761.3 - E: 666560.2</p> <p>J: FOUND BRASS CAP "1940" N: 374102.9 - E: 666571.7</p> <p>K: FOUND 5/8" REBAR N: 371444.9 - E: 666582.5</p> <p>L: FOUND BRASS CAP "1940" N: 371284.8 - E: 664035.5</p> <p>M: FOUND BRASS CAP "1940" N: 376630.2 - E: 664029.0</p>	<p>GEODETIC DATA NAD 83 GRID - NM EAST</p> <p>SURFACE LOCATION N: 378997.3 - E: 666281.0 LAT: 32.0413023° N LONG: 103.9300948° W</p> <p>PROJECT AREA</p> <p>PRODUCING AREA</p> <p>GEODETIC DATA NAD 83 GRID - NM EAST</p> <p>BOTTOM HOLE N: 371754.2 - E: 666251.9 LAT: 32.0213918° N LONG: 103.9302760° W</p> <p>B. H.</p>	<p>17 OPERATOR CERTIFICATION I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or in a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p>Signature: <u>Bradley Bishop</u> Date: <u>11-15-18</u></p> <p>Printed Name: <u>BRADLEY BISHOP</u></p> <p>E-mail Address: <u>BBISHOP@MEWBOURNE.COM</u></p> <p>18 SURVEYOR CERTIFICATION I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>Date of Survey: <u>10-11-18</u></p> <p>Signature and Seal of Professional Surveyor: <u>Robert M. Howett</u></p> <p>19680 Certificate Number</p>
--	--	---

S 86°23'39" W 2552.83' S 86°24'11" W 2552.83'

Job No.: LS18101141



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

10/18/2019

APD ID: 10400036359

Submission Date: 12/05/2018

Highlighted data
reflects the most
recent changes

Operator Name: MEWBOURNE OIL COMPANY

Well Name: FULLER 13/24 W1P FED COM

Well Number: 1H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	UNKNOWN	3016	27	27		NONE	N
2	RUSTLER	2097	919	919	ANHYDRITE, DOLOMIT E	USEABLE WATER	N
3	TOP SALT	1612	1404	1404	SALT	NONE	N
4	CASTILE	1282	1734	1734	SALT	NONE	N
5	BASE OF SALT	-55	3071	3071	SALT	NONE	N
6	DELAWARE	-245	3261	3261	LIMESTONE	NATURAL GAS, OIL	N
7	BELL CANYON	-265	3281	3281	SANDSTONE	NATURAL GAS, OIL	N
8	CHERRY CANYON	-1548	4564	4564	SANDSTONE	NATURAL GAS, OIL	N
9	MANZANITA	-1653	4669	4669		NONE	N
10	BRUSHY CANYON	-2278	5294	5294	SANDSTONE	NATURAL GAS, OIL	Y
11	BONE SPRING	-4040	7056	7056	LIMESTONE, SHALE	NATURAL GAS, OIL	N
12	BONE SPRING 1ST	-4963	7979	7979	SANDSTONE	NATURAL GAS, OIL	N
13	BONE SPRING 2ND	-5596	8612	8612	SANDSTONE	NATURAL GAS, OIL	N
14	BONE SPRING 3RD	-6885	9901	9901	SANDSTONE	NATURAL GAS, OIL	N
15	WOLFCAMP	-7258	10274	10274	LIMESTONE, SHALE, SA NDSTONE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Operator Name: MEWBOURNE OIL COMPANY

Well Name: FULLER 13/24 W1IP FED COM

Well Number: 1H

Pressure Rating (PSI): 5M

Rating Depth: 18079

Equipment: Annular, Pipe Ram, Blind Ram

Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. Anchors are not required by manufacturer. A multibowl wellhead is being used. See attached schematic.

Testing Procedure: BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested. Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

Choke Diagram Attachment:

Fuller_13_24_W1IP_Fed_Com__1H_5M_BOPE_Choke_Diagram_20190422102555.pdf

Fuller_13_24_W1IP_Fed_Com__1H_Flex_Line_Specs_20190422102556.pdf

BOP Diagram Attachment:

Fuller_13_24_W1IP_Fed_Com__1H_5M_BOPE_Schematic_20190422102618.pdf

Fuller_13_24_W1IP_Fed_Com__1H_Multi_Bowl_WH_20190422102620.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	990	0	990			990	H-40	48	ST&C	1.7	3.82	DRY	6.78	DRY	11.38
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	3185	0	3185			3185	J-55	36	LT&C	1.22	2.13	DRY	3.95	DRY	4.92
3	PRODUCTION	8.75	7.0	NEW	API	N	0	11000	0	10664			11000	P-110	26	LT&C	1.48	1.89	DRY	2.42	DRY	2.9
4	LINER	6.125	4.5	NEW	API	N	10101	18079	10091	10644			7978	P-110	13.5	LT&C	1.48	1.72	DRY	3.14	DRY	3.92

Casing Attachments

Operator Name: MEWBOURNE OIL COMPANY

Well Name: FULLER 13/24 W1IP FED COM

Well Number: 1H

Casing Attachments

Casing ID: 1 **String Type:** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Fuller_13_24_W1IP_Fed_Com_1H_Csg_Assumptions_20181203150500.pdf

Casing ID: 2 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Fuller_13_24_W1IP_Fed_Com_1H_Csg_Assumptions_20181203150601.pdf

Casing ID: 3 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Fuller_13_24_W1IP_Fed_Com_1H_Csg_Assumptions_20181203150714.pdf

Operator Name: MEWBOURNE OIL COMPANY

Well Name: FULLER 13/24 W1IP FED COM

Well Number: 1H

Casing Attachments

Casing ID: 4 String Type: LINER

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Fuller_13_24_W1IP_Fed_Com_1H_Csg_Assumptions_20181203150837.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu-Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	797	530	2.12	12.5	1124	100	Class C	Salt, Gel, Extender, LCM
SURFACE	Tail		797	990	200	1.34	14.8	268	100	Class C	Retarder
INTERMEDIATE	Lead		0	2541	510	2.12	12.5	1081	25	Class C	Salt, Gel, Extender, LCM
INTERMEDIATE	Tail		2541	3185	200	1.34	14.8	268	25	Class C	Retarder
PRODUCTION	Lead	4669	2985	3989	375	2.12	12.5	795	25	Class C	Gel, Retarder, Defoamer, Extender
PRODUCTION	Tail		3989	4669	100	1.34	14.8	134	25	Class C	Retarder
PRODUCTION	Lead	4669	4669	8553	360	2.12	12.5	763	25	Class C	Gel, Retarder, Defoamer, Extender
PRODUCTION	Tail		8553	11000	400	1.18	15.6	472	25	Class H	Retarder, Fluid Loss, Defoamer
LINER	Lead		10101	18079	320	2.97	11.2	950	25	Class C	Salt, Gel, Fluid Loss, Retarder, Dispersant, Defoamer, Anti-Settling Agent

Operator Name: MEWBOURNE OIL COMPANY

Well Name: FULLER 13/24 W1IP FED COM

Well Number: 1H

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Lost circulation material Sweeps Mud scavengers in surface hole

Describe the mud monitoring system utilized: Pason, PVT, visual monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
990	3185	SALT SATURATED	10	10							
3185	10664	WATER-BASED MUD	8.6	9.7							
10644	10664	OIL-BASED MUD	10	12							Mud wieght up to 13.0 ppg may be required for shale control. The highest mud weight needed to balance formation is expected to be 12.0 ppg.
0	990	SPUD MUD	8.6	8.8							

Operator Name: MEWBOURNE OIL COMPANY

Well Name: FULLER 13/24 W1IP FED COM

Well Number: 1H

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Will run GR/CNL from KOP (10101') to surface

List of open and cased hole logs run in the well:

CNL,DS,GR,MWD,MUDLOG

Coring operation description for the well:

None

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 6654

Anticipated Surface Pressure: 4309.24

Anticipated Bottom Hole Temperature(F): 165

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

Fuller_13_24_W1IP_Fed_Com_1H_H2S_Plan_20181203151519.doc

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Fuller_13_24_W1IP_Fed_Com_1H_Dir_Plan_20181203151552.pdf

Fuller_13_24_W1IP_Fed_Com_1H_Dir_Plot_20181203151553.pdf

Other proposed operations facets description:


Other proposed operations facets attachment:

Fuller_13_24_W1IP_Fed_Com_1H_C101_20181203151609.pdf

Fuller_13_24_W1IP_Fed_Com_1H_Drlg_Program_20190422102756.pdf

Other Variance attachment:

5M BOPE & Closed Loop Equipment Schematic



Drawing not to scale

Note: All valves & lines on choke manifold are 4" unless otherwise noted. Exact manifold configuration may vary.



GATES E & S NORTH AMERICA, INC.
134 44TH STREET
CORPUS CHRISTI, TEXAS 78405

PHONE: 361-887-9807
FAX: 361-887-0812
EMAIL: Tim.Cantu@gates.com
WEB: www.gates.com

10K CEMENTING ASSEMBLY PRESSURE TEST CERTIFICATE

Customer :	AUSTIN DISTRIBUTING	Test Date:	4/30/2015
Customer Ref. :	4060578	Hose Serial No.:	D-043015-7
Invoice No. :	500506	Created By:	JUSTIN CROPPER
Product Description:	10K3.548.0CK4.1/1610KFLGE/E LE		
End Fitting 1 :	4 1/16 10K FLG	End Fitting 2 :	4 1/16 10K FLG
Gates Part No. :	4773-6290	Assembly Code :	L36554102914D-043015-7
Working Pressure :	10,000 PSI	Test Pressure :	15,000 PSI

Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 15,000 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality Manager :
Date :
Signature :

QUALITY
4/30/2015
<i>Justin Cropper</i>

Production:
Date :
Signature :

PRODUCTION
4/30/2015
<i>Justin Cropper</i>

Form PTC - 01 Rev.02



Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Fuller 13/24 W1IP Fed Com #1H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3043.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3043.0usft (Original Well Elev)
Site:	Fuller 13/24 W1IP Fed Com #1H	North Reference:	Grid
Well:	SL: 2250 FSL & 270 FEL (Sec 13)	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 330 FSL & 330 FEL (Sec 24)		
Design:	Design #1		

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
SL: 2250 FSL & 270 FEL - plan hits target center - Point	0.00	0.00	0.0	0.0	0.0	378,997.00	666,281.00	32.0413015	-103.9300949
KOP: 2658 FSL & 330 F - plan hits target center - Point	0.00	0.00	10,091.0	408.0	-62.0	379,405.00	666,219.00	32.0424237	-103.9302900
FTP: 2328 FSL & 330 FE - plan hits target center - Point	0.00	0.00	10,609.9	78.0	-60.6	379,075.00	666,220.43	32.0415165	-103.9302894
BHL: 330 FSL & 330 FE - plan hits target center - Point	0.00	0.00	10,644.0	-7,243.0	-29.0	371,754.00	666,252.00	32.0213914	-103.9302757
PPP2: 0 FNL & 330 FEL - plan hits target center - Point	0.00	0.00	10,658.1	-2,253.0	-50.5	376,744.00	666,230.48	32.0351087	-103.9302850

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Fuller 13/24 W1IP Fed Com #1H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3043.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3043.0usft (Original Well Elev)
Site:	Fuller 13/24 W1IP Fed Com #1H	North Reference:	Grid
Well:	SL: 2250 FSL & 270 FEL (Sec 13)	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 330 FSL & 330 FEL (Sec 24)		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
14,900.0	90.16	179.75	10,653.0	-4,064.4	-42.7	4,064.5	0.00	0.00	0.00
15,000.0	90.16	179.75	10,652.7	-4,164.4	-42.3	4,164.5	0.00	0.00	0.00
15,100.0	90.16	179.75	10,652.4	-4,264.4	-41.8	4,264.5	0.00	0.00	0.00
15,200.0	90.16	179.75	10,652.1	-4,364.4	-41.4	4,364.5	0.00	0.00	0.00
15,300.0	90.16	179.75	10,651.9	-4,464.4	-41.0	4,464.5	0.00	0.00	0.00
15,400.0	90.16	179.75	10,651.6	-4,564.4	-40.6	4,564.5	0.00	0.00	0.00
15,500.0	90.16	179.75	10,651.3	-4,664.4	-40.1	4,664.5	0.00	0.00	0.00
15,600.0	90.16	179.75	10,651.0	-4,764.4	-39.7	4,764.5	0.00	0.00	0.00
15,700.0	90.16	179.75	10,650.7	-4,864.4	-39.3	4,864.5	0.00	0.00	0.00
15,800.0	90.16	179.75	10,650.4	-4,964.4	-38.8	4,964.5	0.00	0.00	0.00
15,900.0	90.16	179.75	10,650.2	-5,064.4	-38.4	5,064.5	0.00	0.00	0.00
16,000.0	90.16	179.75	10,649.9	-5,164.4	-38.0	5,164.5	0.00	0.00	0.00
16,100.0	90.16	179.75	10,649.6	-5,264.4	-37.5	5,264.5	0.00	0.00	0.00
16,200.0	90.16	179.75	10,649.3	-5,364.4	-37.1	5,364.5	0.00	0.00	0.00
16,300.0	90.16	179.75	10,649.0	-5,464.4	-36.7	5,464.5	0.00	0.00	0.00
16,400.0	90.16	179.75	10,648.7	-5,564.4	-36.2	5,564.5	0.00	0.00	0.00
16,500.0	90.16	179.75	10,648.5	-5,664.4	-35.8	5,664.5	0.00	0.00	0.00
16,600.0	90.16	179.75	10,648.2	-5,764.4	-35.4	5,764.5	0.00	0.00	0.00
16,700.0	90.16	179.75	10,647.9	-5,864.4	-34.9	5,864.5	0.00	0.00	0.00
16,800.0	90.16	179.75	10,647.6	-5,964.4	-34.5	5,964.5	0.00	0.00	0.00
16,900.0	90.16	179.75	10,647.3	-6,064.4	-34.1	6,064.5	0.00	0.00	0.00
17,000.0	90.16	179.75	10,647.0	-6,164.4	-33.7	6,164.5	0.00	0.00	0.00
17,100.0	90.16	179.75	10,646.8	-6,264.4	-33.2	6,264.5	0.00	0.00	0.00
17,200.0	90.16	179.75	10,646.5	-6,364.4	-32.8	6,364.5	0.00	0.00	0.00
17,300.0	90.16	179.75	10,646.2	-6,464.4	-32.4	6,464.4	0.00	0.00	0.00
17,400.0	90.16	179.75	10,645.9	-6,564.4	-31.9	6,564.4	0.00	0.00	0.00
17,500.0	90.16	179.75	10,645.6	-6,664.4	-31.5	6,664.4	0.00	0.00	0.00
17,600.0	90.16	179.75	10,645.4	-6,764.4	-31.1	6,764.4	0.00	0.00	0.00
17,700.0	90.16	179.75	10,645.1	-6,864.4	-30.6	6,864.4	0.00	0.00	0.00
17,800.0	90.16	179.75	10,644.8	-6,964.4	-30.2	6,964.4	0.00	0.00	0.00
17,900.0	90.16	179.75	10,644.5	-7,064.4	-29.8	7,064.4	0.00	0.00	0.00
18,000.0	90.16	179.75	10,644.2	-7,164.4	-29.3	7,164.4	0.00	0.00	0.00
18,078.6	90.16	179.75	10,644.0	-7,243.0	-29.0	7,243.1	0.00	0.00	0.00

BHL: 330 FSL & 330 FEL (Sec 24)

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Fuller 13/24 W1IP Fed Com #1H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3043.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3043.0usft (Original Well Elev)
Site:	Fuller 13/24 W1IP Fed Com #1H	North Reference:	Grid
Well:	SL: 2250 FSL & 270 FEL (Sec 13)	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 330 FSL & 330 FEL (Sec 24)		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
KOP: 2658 FSL & 330 FEL (Sec 13)									
10,200.0	9.95	179.75	10,190.0	399.4	-62.0	-399.1	10.00	10.00	0.00
10,300.0	19.95	179.75	10,286.5	373.6	-61.9	-373.4	10.00	10.00	0.00
10,400.0	29.95	179.75	10,377.1	331.5	-61.7	-331.2	10.00	10.00	0.00
10,500.0	39.95	179.75	10,458.9	274.3	-61.4	-274.0	10.00	10.00	0.00
10,600.0	49.95	179.75	10,529.6	203.7	-61.1	-203.5	10.00	10.00	0.00
10,700.0	59.95	179.75	10,587.0	122.0	-60.8	-121.7	10.00	10.00	0.00
10,749.6	64.91	179.75	10,609.9	78.0	-60.6	-77.8	10.00	10.00	0.00
FTP: 2328 FSL & 330 FEL (Sec 13)									
10,800.0	69.95	179.75	10,629.3	31.5	-60.4	-31.2	10.00	10.00	0.00
10,900.0	79.95	179.75	10,655.2	-65.0	-60.0	65.2	10.00	10.00	0.00
11,000.0	89.95	179.75	10,664.0	-164.5	-59.5	164.7	10.00	10.00	0.00
11,002.2	90.16	179.75	10,664.0	-166.6	-59.5	166.9	10.00	10.00	0.00
11,100.0	90.16	179.75	10,663.7	-264.5	-59.1	264.7	0.00	0.00	0.00
11,200.0	90.16	179.75	10,663.4	-364.5	-58.7	364.7	0.00	0.00	0.00
11,300.0	90.16	179.75	10,663.2	-464.4	-58.2	464.7	0.00	0.00	0.00
11,400.0	90.16	179.75	10,662.9	-564.4	-57.8	564.7	0.00	0.00	0.00
11,500.0	90.16	179.75	10,662.6	-664.4	-57.4	664.7	0.00	0.00	0.00
11,600.0	90.16	179.75	10,662.3	-764.4	-56.9	764.7	0.00	0.00	0.00
11,700.0	90.16	179.75	10,662.0	-864.4	-56.5	864.7	0.00	0.00	0.00
11,800.0	90.16	179.75	10,661.7	-964.4	-56.1	964.7	0.00	0.00	0.00
11,900.0	90.16	179.75	10,661.5	-1,064.4	-55.6	1,064.7	0.00	0.00	0.00
12,000.0	90.16	179.75	10,661.2	-1,164.4	-55.2	1,164.7	0.00	0.00	0.00
12,100.0	90.16	179.75	10,660.9	-1,264.4	-54.8	1,264.6	0.00	0.00	0.00
12,200.0	90.16	179.75	10,660.6	-1,364.4	-54.4	1,364.6	0.00	0.00	0.00
12,300.0	90.16	179.75	10,660.3	-1,464.4	-53.9	1,464.6	0.00	0.00	0.00
12,400.0	90.16	179.75	10,660.0	-1,564.4	-53.5	1,564.6	0.00	0.00	0.00
12,500.0	90.16	179.75	10,659.8	-1,664.4	-53.1	1,664.6	0.00	0.00	0.00
12,600.0	90.16	179.75	10,659.5	-1,764.4	-52.6	1,764.6	0.00	0.00	0.00
12,700.0	90.16	179.75	10,659.2	-1,864.4	-52.2	1,864.6	0.00	0.00	0.00
12,800.0	90.16	179.75	10,658.9	-1,964.4	-51.8	1,964.6	0.00	0.00	0.00
12,900.0	90.16	179.75	10,658.6	-2,064.4	-51.3	2,064.6	0.00	0.00	0.00
13,000.0	90.16	179.75	10,658.4	-2,164.4	-50.9	2,164.6	0.00	0.00	0.00
13,088.6	90.16	179.75	10,658.1	-2,253.0	-50.5	2,253.2	0.00	0.00	0.00
PPP2: 0 FNL & 330 FEL (Sec 24)									
13,100.0	90.16	179.75	10,658.1	-2,264.4	-50.5	2,264.6	0.00	0.00	0.00
13,200.0	90.16	179.75	10,657.8	-2,364.4	-50.0	2,364.6	0.00	0.00	0.00
13,300.0	90.16	179.75	10,657.5	-2,464.4	-49.6	2,464.6	0.00	0.00	0.00
13,400.0	90.16	179.75	10,657.2	-2,564.4	-49.2	2,564.6	0.00	0.00	0.00
13,500.0	90.16	179.75	10,656.9	-2,664.4	-48.7	2,664.6	0.00	0.00	0.00
13,600.0	90.16	179.75	10,656.7	-2,764.4	-48.3	2,764.6	0.00	0.00	0.00
13,700.0	90.16	179.75	10,656.4	-2,864.4	-47.9	2,864.6	0.00	0.00	0.00
13,800.0	90.16	179.75	10,656.1	-2,964.4	-47.5	2,964.6	0.00	0.00	0.00
13,900.0	90.16	179.75	10,655.8	-3,064.4	-47.0	3,064.6	0.00	0.00	0.00
14,000.0	90.16	179.75	10,655.5	-3,164.4	-46.6	3,164.6	0.00	0.00	0.00
14,100.0	90.16	179.75	10,655.2	-3,264.4	-46.2	3,264.6	0.00	0.00	0.00
14,200.0	90.16	179.75	10,655.0	-3,364.4	-45.7	3,364.6	0.00	0.00	0.00
14,300.0	90.16	179.75	10,654.7	-3,464.4	-45.3	3,464.6	0.00	0.00	0.00
14,400.0	90.16	179.75	10,654.4	-3,564.4	-44.9	3,564.6	0.00	0.00	0.00
14,500.0	90.16	179.75	10,654.1	-3,664.4	-44.4	3,664.6	0.00	0.00	0.00
14,600.0	90.16	179.75	10,653.8	-3,764.4	-44.0	3,764.6	0.00	0.00	0.00
14,700.0	90.16	179.75	10,653.5	-3,864.4	-43.6	3,864.5	0.00	0.00	0.00
14,800.0	90.16	179.75	10,653.3	-3,964.4	-43.1	3,964.5	0.00	0.00	0.00

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Fuller 13/24 W1IP Fed Com #1H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3043.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3043.0usft (Original Well Elev)
Site:	Fuller 13/24 W1IP Fed Com #1H	North Reference:	Grid
Well:	SL: 2250 FSL & 270 FEL (Sec 13)	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 330 FSL & 330 FEL (Sec 24)		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,100.0	2.65	351.36	5,095.7	183.7	-27.9	-183.6	0.00	0.00	0.00
5,200.0	2.65	351.36	5,195.6	188.2	-28.6	-188.1	0.00	0.00	0.00
5,300.0	2.65	351.36	5,295.5	192.8	-29.3	-192.7	0.00	0.00	0.00
5,400.0	2.65	351.36	5,395.4	197.4	-30.0	-197.2	0.00	0.00	0.00
5,500.0	2.65	351.36	5,495.3	201.9	-30.7	-201.8	0.00	0.00	0.00
5,600.0	2.65	351.36	5,595.2	206.5	-31.4	-206.4	0.00	0.00	0.00
5,700.0	2.65	351.36	5,695.1	211.1	-32.1	-210.9	0.00	0.00	0.00
5,800.0	2.65	351.36	5,795.0	215.6	-32.8	-215.5	0.00	0.00	0.00
5,900.0	2.65	351.36	5,894.9	220.2	-33.5	-220.1	0.00	0.00	0.00
6,000.0	2.65	351.36	5,994.8	224.8	-34.2	-224.6	0.00	0.00	0.00
6,100.0	2.65	351.36	6,094.7	229.3	-34.8	-229.2	0.00	0.00	0.00
6,200.0	2.65	351.36	6,194.6	233.9	-35.5	-233.8	0.00	0.00	0.00
6,300.0	2.65	351.36	6,294.5	238.5	-36.2	-238.3	0.00	0.00	0.00
6,400.0	2.65	351.36	6,394.4	243.0	-36.9	-242.9	0.00	0.00	0.00
6,500.0	2.65	351.36	6,494.2	247.6	-37.6	-247.4	0.00	0.00	0.00
6,600.0	2.65	351.36	6,594.1	252.2	-38.3	-252.0	0.00	0.00	0.00
6,700.0	2.65	351.36	6,694.0	256.7	-39.0	-256.6	0.00	0.00	0.00
6,800.0	2.65	351.36	6,793.9	261.3	-39.7	-261.1	0.00	0.00	0.00
6,900.0	2.65	351.36	6,893.8	265.9	-40.4	-265.7	0.00	0.00	0.00
7,000.0	2.65	351.36	6,993.7	270.4	-41.1	-270.3	0.00	0.00	0.00
7,100.0	2.65	351.36	7,093.6	275.0	-41.8	-274.8	0.00	0.00	0.00
7,200.0	2.65	351.36	7,193.5	279.6	-42.5	-279.4	0.00	0.00	0.00
7,300.0	2.65	351.36	7,293.4	284.1	-43.2	-284.0	0.00	0.00	0.00
7,400.0	2.65	351.36	7,393.3	288.7	-43.9	-288.5	0.00	0.00	0.00
7,500.0	2.65	351.36	7,493.2	293.3	-44.6	-293.1	0.00	0.00	0.00
7,600.0	2.65	351.36	7,593.1	297.8	-45.3	-297.7	0.00	0.00	0.00
7,700.0	2.65	351.36	7,693.0	302.4	-46.0	-302.2	0.00	0.00	0.00
7,800.0	2.65	351.36	7,792.9	307.0	-46.6	-306.8	0.00	0.00	0.00
7,900.0	2.65	351.36	7,892.7	311.5	-47.3	-311.3	0.00	0.00	0.00
8,000.0	2.65	351.36	7,992.6	316.1	-48.0	-315.9	0.00	0.00	0.00
8,100.0	2.65	351.36	8,092.5	320.7	-48.7	-320.5	0.00	0.00	0.00
8,200.0	2.65	351.36	8,192.4	325.2	-49.4	-325.0	0.00	0.00	0.00
8,300.0	2.65	351.36	8,292.3	329.8	-50.1	-329.6	0.00	0.00	0.00
8,400.0	2.65	351.36	8,392.2	334.4	-50.8	-334.2	0.00	0.00	0.00
8,500.0	2.65	351.36	8,492.1	338.9	-51.5	-338.7	0.00	0.00	0.00
8,600.0	2.65	351.36	8,592.0	343.5	-52.2	-343.3	0.00	0.00	0.00
8,700.0	2.65	351.36	8,691.9	348.1	-52.9	-347.9	0.00	0.00	0.00
8,800.0	2.65	351.36	8,791.8	352.6	-53.6	-352.4	0.00	0.00	0.00
8,900.0	2.65	351.36	8,891.7	357.2	-54.3	-357.0	0.00	0.00	0.00
9,000.0	2.65	351.36	8,991.6	361.8	-55.0	-361.5	0.00	0.00	0.00
9,100.0	2.65	351.36	9,091.5	366.3	-55.7	-366.1	0.00	0.00	0.00
9,200.0	2.65	351.36	9,191.4	370.9	-56.4	-370.7	0.00	0.00	0.00
9,300.0	2.65	351.36	9,291.3	375.5	-57.1	-375.2	0.00	0.00	0.00
9,400.0	2.65	351.36	9,391.1	380.0	-57.8	-379.8	0.00	0.00	0.00
9,500.0	2.65	351.36	9,491.0	384.6	-58.4	-384.4	0.00	0.00	0.00
9,600.0	2.65	351.36	9,590.9	389.2	-59.1	-388.9	0.00	0.00	0.00
9,700.0	2.65	351.36	9,690.8	393.7	-59.8	-393.5	0.00	0.00	0.00
9,800.0	2.65	351.36	9,790.7	398.3	-60.5	-398.1	0.00	0.00	0.00
9,900.0	2.65	351.36	9,890.6	402.9	-61.2	-402.6	0.00	0.00	0.00
9,924.0	2.65	351.36	9,914.6	404.0	-61.4	-403.7	0.00	0.00	0.00
10,000.0	1.51	351.36	9,990.5	406.7	-61.8	-406.4	1.50	-1.50	0.00
10,100.0	0.01	351.36	10,090.5	408.0	-62.0	-407.7	1.50	-1.50	0.00
10,100.5	0.00	0.00	10,091.0	408.0	-62.0	-407.7	1.50	-1.50	0.00

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Fuller 13/24 W1IP Fed Com #1H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3043.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3043.0usft (Original Well Elev)
Site:	Fuller 13/24 W1IP Fed Com #1H	North Reference:	Grid
Well:	SL: 2250 FSL & 270 FEL (Sec 13)	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 330 FSL & 330 FEL (Sec 24)		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
SL: 2250 FSL & 270 FEL (Sec 13)									
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
990.0	0.00	0.00	990.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.15	351.36	1,000.0	0.0	0.0	0.0	1.50	1.50	0.00
1,100.0	1.65	351.36	1,100.0	1.6	-0.2	-1.6	1.50	1.50	0.00
1,166.5	2.65	351.36	1,166.4	4.0	-0.6	-4.0	1.50	1.50	0.00
1,200.0	2.65	351.36	1,199.9	5.6	-0.8	-5.6	0.00	0.00	0.00
1,300.0	2.65	351.36	1,299.8	10.1	-1.5	-10.1	0.00	0.00	0.00
1,400.0	2.65	351.36	1,399.7	14.7	-2.2	-14.7	0.00	0.00	0.00
1,500.0	2.65	351.36	1,499.6	19.3	-2.9	-19.2	0.00	0.00	0.00
1,600.0	2.65	351.36	1,599.5	23.8	-3.6	-23.8	0.00	0.00	0.00
1,700.0	2.65	351.36	1,699.4	28.4	-4.3	-28.4	0.00	0.00	0.00
1,800.0	2.65	351.36	1,799.3	33.0	-5.0	-32.9	0.00	0.00	0.00
1,900.0	2.65	351.36	1,899.2	37.5	-5.7	-37.5	0.00	0.00	0.00
2,000.0	2.65	351.36	1,999.0	42.1	-6.4	-42.1	0.00	0.00	0.00
2,100.0	2.65	351.36	2,098.9	46.7	-7.1	-46.6	0.00	0.00	0.00
2,200.0	2.65	351.36	2,198.8	51.2	-7.8	-51.2	0.00	0.00	0.00
2,300.0	2.65	351.36	2,298.7	55.8	-8.5	-55.8	0.00	0.00	0.00
2,400.0	2.65	351.36	2,398.6	60.4	-9.2	-60.3	0.00	0.00	0.00
2,500.0	2.65	351.36	2,498.5	64.9	-9.9	-64.9	0.00	0.00	0.00
2,600.0	2.65	351.36	2,598.4	69.5	-10.6	-69.5	0.00	0.00	0.00
2,700.0	2.65	351.36	2,698.3	74.1	-11.3	-74.0	0.00	0.00	0.00
2,800.0	2.65	351.36	2,798.2	78.6	-11.9	-78.6	0.00	0.00	0.00
2,900.0	2.65	351.36	2,898.1	83.2	-12.6	-83.1	0.00	0.00	0.00
3,000.0	2.65	351.36	2,998.0	87.8	-13.3	-87.7	0.00	0.00	0.00
3,100.0	2.65	351.36	3,097.9	92.3	-14.0	-92.3	0.00	0.00	0.00
3,200.0	2.65	351.36	3,197.8	96.9	-14.7	-96.8	0.00	0.00	0.00
3,300.0	2.65	351.36	3,297.7	101.5	-15.4	-101.4	0.00	0.00	0.00
3,400.0	2.65	351.36	3,397.6	106.0	-16.1	-106.0	0.00	0.00	0.00
3,500.0	2.65	351.36	3,497.4	110.6	-16.8	-110.5	0.00	0.00	0.00
3,600.0	2.65	351.36	3,597.3	115.2	-17.5	-115.1	0.00	0.00	0.00
3,700.0	2.65	351.36	3,697.2	119.7	-18.2	-119.7	0.00	0.00	0.00
3,800.0	2.65	351.36	3,797.1	124.3	-18.9	-124.2	0.00	0.00	0.00
3,900.0	2.65	351.36	3,897.0	128.9	-19.6	-128.8	0.00	0.00	0.00
4,000.0	2.65	351.36	3,996.9	133.4	-20.3	-133.3	0.00	0.00	0.00
4,100.0	2.65	351.36	4,096.8	138.0	-21.0	-137.9	0.00	0.00	0.00
4,200.0	2.65	351.36	4,196.7	142.6	-21.7	-142.5	0.00	0.00	0.00
4,300.0	2.65	351.36	4,296.6	147.1	-22.4	-147.0	0.00	0.00	0.00
4,400.0	2.65	351.36	4,396.5	151.7	-23.1	-151.6	0.00	0.00	0.00
4,500.0	2.65	351.36	4,496.4	156.3	-23.7	-156.2	0.00	0.00	0.00
4,600.0	2.65	351.36	4,596.3	160.8	-24.4	-160.7	0.00	0.00	0.00
4,700.0	2.65	351.36	4,696.2	165.4	-25.1	-165.3	0.00	0.00	0.00
4,800.0	2.65	351.36	4,796.1	170.0	-25.8	-169.9	0.00	0.00	0.00
4,900.0	2.65	351.36	4,896.0	174.5	-26.5	-174.4	0.00	0.00	0.00
5,000.0	2.65	351.36	4,995.8	179.1	-27.2	-179.0	0.00	0.00	0.00

Planning Report

Database:	Hobbs	Local Co-ordinate Reference:	Site Fuller 13/24 W1IP Fed Com #1H
Company:	Mewbourne Oil Company	TVD Reference:	WELL @ 3043.0usft (Original Well Elev)
Project:	Eddy County, New Mexico NAD 83	MD Reference:	WELL @ 3043.0usft (Original Well Elev)
Site:	Fuller 13/24 W1IP Fed Com #1H	North Reference:	Grid
Well:	SL: 2250 FSL & 270 FEL (Sec 13)	Survey Calculation Method:	Minimum Curvature
Wellbore:	BHL: 330 FSL & 330 FEL (Sec 24)		
Design:	Design #1		

Project	Eddy County, New Mexico NAD 83		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Fuller 13/24 W1IP Fed Com #1H			
Site Position:		Northing:	378,997.00 usft	Latitude: 32.0413015
From:	Map	Easting:	666,281.00 usft	Longitude: -103.9300949
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "	Grid Convergence: 0.21 °

Well	SL: 2250 FSL & 270 FEL (Sec 13)			
Well Position	+N/-S	0.0 usft	Northing:	378,997.00 usft
	+E/-W	0.0 usft	Easting:	666,281.00 usft
Position Uncertainty	0.0 usft		Wellhead Elevation:	3,043.0 usft
			Ground Level:	3,016.0 usft

Wellbore	BHL: 330 FSL & 330 FEL (Sec 24)				
Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
			(°)	(°)	(nT)
	IGRF2010	11/30/2018	6.82	59.77	47,728

Design	Design #1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction
	(usft)	(usft)	(usft)	(°)
	0.0	0.0	0.0	180.23

Plan Sections										
Measured	Inclination	Azimuth	Vertical	+N/-S	+E/-W	Dogleg	Build	Turn	TFO	Target
Depth	(°)	(°)	Depth	(usft)	(usft)	Rate	Rate	Rate	(°)	
(usft)			(usft)			(°/100usft)	(°/100usft)	(°/100usft)		
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
990.0	0.00	0.00	990.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,166.5	2.65	351.36	1,166.4	4.0	-0.6	1.50	1.50	0.00	351.36	
9,924.0	2.65	351.36	9,914.6	404.0	-61.4	0.00	0.00	0.00	0.00	
10,100.5	0.00	0.00	10,091.0	408.0	-62.0	1.50	-1.50	0.00	180.00	KOP: 2658 FSL & 330 F
11,002.2	90.16	179.75	10,664.0	-166.6	-59.5	10.00	10.00	0.00	179.75	
18,078.6	90.16	179.75	10,644.0	-7,243.0	-29.0	0.00	0.00	0.00	0.00	BHL: 330 FSL & 330 F

Mewbourne Oil Company

Eddy County, New Mexico NAD 83

Fuller 13/24 W1IP Fed Com #1H

SL: 2250 FSL & 270 FEL (Sec 13)

Sec 13, T26S, R29E

BHL: 330 FSL & 330 FEL (Sec 24)

Plan: Design #1

Standard Planning Report

30 November, 2018

Mewbourne Oil Company, Fuller 13/24 W1IP Fed Com #1H
Sec 13, T26S, R29E
SL: 2250' FSL & 270' FEL (Sec 13)
BHL: 330' FSL & 330' FEL (Sec 24)

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	990'	13.375"	48	H40	STC	1.70	3.82	6.78	11.38
12.25"	0'	3185'	9.625"	36	J55	LTC	1.22	2.13	3.95	4.92
8.75"	0'	11000'	7"	26	HCP110	LTC	1.48	1.89	2.42	2.90
6.125"	10101'	18079'	4.5"	13.5	P110	LTC	1.48	1.72	3.14	3.92
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Fuller 13/24 W1IP Fed Com #1H
Sec 13, T26S, R29E
SL: 2250' FSL & 270' FEL (Sec 13)
BHL: 330' FSL & 330' FEL (Sec 24)

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	990'	13.375"	48	H40	STC	1.70	3.82	6.78	11.38
12.25"	0'	3185'	9.625"	36	J55	LTC	1.22	2.13	3.95	4.92
8.75"	0'	11000'	7"	26	HCP110	LTC	1.48	1.89	2.42	2.90
6.125"	10101'	18079'	4.5"	13.5	P110	LTC	1.48	1.72	3.14	3.92
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Fuller 13/24 W1IP Fed Com #1H
Sec 13, T26S, R29E
SL: 2250' FSL & 270' FEL (Sec 13)
BHL: 330' FSL & 330' FEL (Sec 24)

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	990'	13.375"	48	H40	STC	1.70	3.82	6.78	11.38
12.25"	0'	3185'	9.625"	36	J55	LTC	1.22	2.13	3.95	4.92
8.75"	0'	11000'	7"	26	HCP110	LTC	1.48	1.89	2.42	2.90
6.125"	10101'	18079'	4.5"	13.5	P110	LTC	1.48	1.72	3.14	3.92
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Fuller 13/24 WIIIP Fed Com #1H
Sec 13, T26S, R29E
SL: 2250' FSL & 270' FEL (Sec 13)
BHL: 330' FSL & 330' FEL (Sec 24)

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	990'	13.375"	48	H40	STC	1.70	3.82	6.78	11.38
12.25"	0'	3185'	9.625"	36	J55	LTC	1.22	2.13	3.95	4.92
8.75"	0'	11000'	7"	26	HCP110	LTC	1.48	1.89	2.42	2.90
6.125"	10101'	18079'	4.5"	13.5	P110	LTC	1.48	1.72	3.14	3.92
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	




CAMERON

A Schlumberger Company

13-5/8" MN-DS Wellhead System

Ground Level

Ground Level



Capping Hanger 57" conductor cut-off
79

C7585
Rev. 02

NOTE: All dimensions on this drawing are estimated measurements and should be evaluated by engineering.

Mewbourne Oil Company, Fuller 13/24 W1IP Fed Com #1H
Sec 13, T26S, R29E
SL: 2250' FSL & 270' FEL (Sec 13)
BHL: 330' FSL & 330' FEL (Sec 24)

1. Geologic Formations

TVD of target	10,644'	Pilot hole depth	NA
MD at TD:	18,079'	Deepest expected fresh water:	100'

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Quaternary Fill	Surface		
Rustler	919	Water	
Top of Salt	1404		
Castile	1734		
Base of Salt	3071		
Delaware	3261	Oil/Gas	
Bell Canyon	3281	Oil/Gas	
Cherry Canyon	4564	Oil/Gas	
Manzanita Marker	4669		
Brushy Canyon	5294	Oil/Gas	
Bone Spring	7056	Oil/Gas	
1 st Bone Spring Sand	7979		
2 nd Bone Spring Sand	8612		
3 rd Bone Spring Sand	9901		
Abo			
Wolfcamp	10274	Target Zone	
Devonian			
Fusselman			
Ellenburger			
Granite Wash			

*H2S, water flows, loss of circulation, abnormal pressures, etc.

Mewbourne Oil Company, Fuller 13/24 WHP Fed Com #1H
Sec 13, T26S, R29E
SL: 2250' FSL & 270' FEL (Sec 13)
BHL: 330' FSL & 330' FEL (Sec 24)

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
	From	To								
17.5"	0'	990'	13.375"	48	H40	STC	1.70	3.82	6.78	11.38
12.25"	0'	3185'	9.625"	36	J55	LTC	1.22	2.13	3.95	4.92
8.75"	0'	11000'	7"	26	HCP110	LTC	1.48	1.89	2.42	2.90
6.125"	10101'	18079'	4.5"	13.5	P110	LTC	1.48	1.72	3.14	3.92
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Fuller 13/24 W1IP Fed Com #1H
Sec 13, T26S, R29E
SL: 2250' FSL & 270' FEL (Sec 13)
BHL: 330' FSL & 330' FEL (Sec 24)

3. Cementing Program

Casing	# Sk	Wt. lb/ gal	Yld ft3/ sack	H ₂ O gal/ sk	500# Comp. Strength (hours)	Slurry Description
Surf.	530	12.5	2.12	11	10	Lead: Class C + Salt + Gel + Extender + LCM
	200	14.8	1.34	6.3	8	Tail: Class C + Retarder
Inter.	510	12.5	2.12	11	10	Lead: Class C + Salt + Gel + Extender + LCM
	200	14.8	1.34	6.3	8	Tail: Class C + Retarder
Prod. Stg 1	360	12.5	2.12	11	9	Lead: Class C + Gel + Retarder + Defoamer + Extender
	400	15.6	1.18	5.2	10	Tail: Class H + Retarder + Fluid Loss + Defoamer
ECP/DV Tool @ 4669'						
Prod. Stg 2	375	12.5	2.12	11	10	Lead: Class C + Salt + Gel + Extender + LCM
	100	14.8	1.34	6.3	8	Tail: Class C + Retarder
Liner	320	11.2	2.97	18	16	Class C + Salt + Gel + Fluid Loss + Retarder + Dispersant + Defoamer + Anti-Settling Agent

A copy of cement test will be available on location at time of cement job providing pump times & compressive strengths.

Casing String	TOC	% Excess
Surface	0'	100%
Intermediate	0'	25%
Production	2985'	25%
Liner	10101'	25%

Mewbourne Oil Company, Fuller 13/24 WHP Fed Com #1H
Sec 13, T26S, R29E
SL: 2250' FSL & 270' FEL (Sec 13)
BHL: 330' FSL & 330' FEL (Sec 24)

4. Pressure Control Equipment

BOP installed and tested before drilling which hole?	Size?	System Rated WP	Type	✓	Tested to:
12-1/4"	13-5/8"	5M	Annular	X	2,500#
			Blind Ram	X	5,000#
			Pipe Ram	X	
			Double Ram		
			Other*		

*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
Y	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?
Y	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. <ul style="list-style-type: none"> Provide description here: See attached schematic.

Mewbourne Oil Company, Fuller 13/24 W11P Fed Com #1H
Sec 13, T26S, R29E
SL: 2250' FSL & 270' FEL (Sec 13)
BHL: 330' FSL & 330' FEL (Sec 24)

5. Mud Program

TVD		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	990'	FW Gel	8.6-8.8	28-34	N/C
990'	3185'	Saturated Brine	10.0	28-34	N/C
3185'	10664'	Cut Brine	8.6-9.5	28-34	N/C
10664'	10644'	OBM	10.0-13.0	30-40	<10cc

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	Pason/PVT/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
X	Will run GR/CNL from KOP (10,101') to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned		Interval
X	Gamma Ray	10,101' (KOP) to TD
	Density	
	CBL	
	Mud log	
	PEX	

Mewbourne Oil Company, Fuller 13/24 W11P Fed Com #1H
Sec 13, T26S, R29E
SL: 2250' FSL & 270' FEL (Sec 13)
BHL: 330' FSL & 330' FEL (Sec 24)

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	6654 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers in surface hole. Weighted mud for possible over-pressure in Wolfcamp formation.

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
	H2S is present
X	H2S Plan attached

8. Other facets of operation

Is this a walking operation? If yes, describe.
Will be pre-setting casing? If yes, describe.

Attachments

☐ Directional Plan
☐ Other, describe