

RECEIVED

Form 3160-3  
(June 2015)

NOV 20 2019

FORM APPROVED  
OMB No. 1004-0137  
Expires: January 31, 2018

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
DISTRICT 7 - ARTESIA O.C.D.

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM0002425
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No. THUNDERBIRD DEVELOPMENT UNIT 3H 326054
2. Name of Operator APACHE CORPORATION		9. API Well No. 30-01546460
3a. Address 303 Veterans Airpark Lane #1000 Midland TX 79705	3b. Phone No. (include area code) (432)818-1000	10. Field and Pool, or Exploratory YESO / LOCO HILLS; GLORIETA-YESO
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SENE / 2411 FNL / 1090 FEL / LAT 32.8786638 / LONG -103.9719137 At proposed prod. zone SESE / 100 FSL / 1254 FEL / LAT 32.8565666 / LONG -103.9724423		11. Sec., T. R. M. or Blk. and Survey or Area SEC 33 / T16S / R30E / NMP
14. Distance in miles and direction from nearest town or post office* 5.4 miles		12. County or Parish EDDY
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 100 feet		13. State NM
16. No of acres in lease 599.35		17. Spacing Unit dedicated to this well 279.74
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 40 feet		20. BLM/BIA Bond No. in file FED: NMB000736
19. Proposed Depth 4683 feet / 12495 feet		21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3737 feet
22. Approximate date work will start* 07/30/2019		23. Estimated duration 20 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- |                                                                                                                                                |                                                                                                 |
|------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------|
| 1. Well plat certified by a registered surveyor.                                                                                               | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.                                                                                                                            | 5. Operator certification.                                                                      |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM.            |

25. Signature (Electronic Submission)	Name (Printed/Typed) Sorina Flores / Ph: (432)818-1167	Date 02/07/2019
Title Supv of Drilling Services		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575)234-5959	Date 10/24/2019
Title Assistant Field Manager Lands & Minerals		
Office CARLSBAD		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**APPROVED WITH CONDITIONS**  
Approval Date: 10/24/2019

R# 12-3-19

\*(Instructions on page 2)

Need GCP.

(Continued on page 2)

## PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

<b>OPERATOR'S NAME:</b>	<b>Apache Corporation</b>
<b>LEASE NO.:</b>	<b>NMNM0002425</b>
<b>WELL NAME &amp; NO.:</b>	Thunderbird Development Unit 3H
<b>SURFACE HOLE FOOTAGE:</b>	2411'N & 1090'E
<b>BOTTOM HOLE FOOTAGE:</b>	100'S & 1254'E
<b>LOCATION:</b>	Section 33, T.16 S., R.30 E., NMPM
<b>COUNTY:</b>	Eddy County, New Mexico

COA

H2S	<input checked="" type="radio"/> Yes	<input type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Cave/Karst Potential	<input type="radio"/> Critical		
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input type="radio"/> Multibowl	<input checked="" type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input type="checkbox"/> Fluid Filled	<input type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input type="checkbox"/> COM	<input checked="" type="checkbox"/> Unit

### A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the **Yates, Tansill, Queen** formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

### B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **400 feet** (a minimum of **70 feet (Eddy County)** into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8**

- hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9-5/8** inch intermediate casing shall be set at approximately **3200 feet** is:

**Option 1 (Single Stage):**

- Cement to surface. If cement does not circulate see B.1.a, c-d above.

**Option 2:**

Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
  - b. Second stage above DV tool:
    - Cement to surface. If cement does not circulate, contact the appropriate BLM office.
3. The minimum required fill of cement behind the production casing is:

**Option 1 (Single Stage):**

- Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

**Option 2:**

Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.

b. Second stage above DV tool:

- Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

### **C. PRESSURE CONTROL**

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'
- 2.

#### **Option 1:**

- a. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
- b. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the intermediate casing shoe shall be **2000 (2M)** psi.

#### **Option 2:**

1. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
  - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

#### **D. SPECIAL REQUIREMENT (S)**

##### **Unit Wells**

The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit designation, but will replace the unit number with the participating area number when the sign is replaced.

##### **Commercial Well Determination**

A commercial well determination shall be submitted after production has been established for at least six months.

## GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)  
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
    - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
  - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not



hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

**D. WASTE MATERIAL AND FLUIDS**

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**PECOS DISTRICT  
SURFACE USE  
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	Apache Corporation
WELL NAME & NO.:	Thunderbird Development Unit 3H
SURFACE HOLE FOOTAGE:	2411'N & 1090'E
BOTTOM HOLE FOOTAGE:	100'S & 1254'E
LOCATION:	Section 33, T.16 S., R.30 E., NMPM
COUNTY:	Eddy County, New Mexico

**TABLE OF CONTENTS**

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
  - Lesser Prairie-Chicken Timing Stipulations
  - Ground-level Abandoned Well Marker
  - Dunes Sagebrush Lizard Monitoring Stipulation
  - Hydrology
- ☐ **Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- ☐ **Road Section Diagram**
- ☒ **Production (Post Drilling)**
  - Well Structures & Facilities
  - Pipelines
  - Electric Lines
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## **V. SPECIAL REQUIREMENT(S)**

### **Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:**

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leaks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

**Ground-level Abandoned Well Marker to avoid raptor perching:** Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

### **Timing Limitation Exceptions:**

The Carlsbad Field Office will publish an annual map of where the LPC timing and noise stipulations and conditions of approval (Limitations) will apply for the identified year (between March 1 and June 15) based on the latest survey information. The LPC Timing Area map will identify areas which are Habitat Areas (HA), Isolated Population Area (IPA), and Primary Population Area (PPA). The LPC Timing Area map will also have an area in red crosshatch. The red crosshatch area is the only area where an operator is required to submit a request for exception to the LPC Limitations. If an operator is operating outside the red crosshatch area, the LPC Limitations do not apply for that year and an exception to LPC Limitations is not required.

### **Dunes Sagebrush Lizard Trenching Monitor Stipulation**

- Pre-construction contact with a BLM wildlife biologist is required 5 days prior to any ground disturbing activities associated with the project occurs.
- Successful completion of the BLM Trench Stipulation Workshop is required for a non-agency person to be approved as a monitor.
- Any trench left open for (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, an agency approved monitor shall walk the entire length of the open trench and remove all trapped vertebrates. The bottom surface of the trench will be disturbed a minimum of 2 inches in order to

arouse any buried vertebrates. All vertebrates will be released a minimum of 100 yards from the trench.

- For trenches left open for eight (8) hours or more the following requirements apply:
  - Earthen escape ramps and/or structures (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench. Metal structures will not be authorized. Options will be discussed in detail at the required Trench Stipulation Workshop.
  - One approved monitor shall be required to survey up to three miles of trench between the hours of 11 AM-2 PM. A daily report (consolidate if there is more than one monitor) on the vertebrates found and removed from the trench shall be provided to the BLM (email/fax is acceptable) the following morning.
  - Prior to backfilling of the trench all structures used as escape ramps will be removed and the bottom surface of the trench will be disturbed a minimum of 2 inches in order to arouse any buried vertebrates. All vertebrates will be released a minimum of 100 yards from the trench.
- This stipulation shall apply to the entire length of the project in the DSL habitat polygon regardless of land ownership or CCA/CCAA enrollment status.
- A project closeout will be required within three business days of the completion of the project.

### **Hydrology**

The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. The compacted berm shall be constructed at a minimum of 12 inches with impermeable mineral material (e.g. caliche). Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed. Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion. Stockpiling of topsoil is required. The top soil shall be stockpiled in an appropriate location to prevent loss of soil due to water or wind erosion and not used for berming or erosion control. If fluid collects within the bermed area, the

fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.

When crossing ephemeral drainages the pipeline will be buried to a minimum depth of 48 inches from the top of pipe to ground level. Erosion control methods such as gabions and/or rock aprons should be placed on both up and downstream sides of the pipeline crossing. In addition, curled (weed free) wood/straw fiber wattles/logs and/or silt fences should be placed on the downstream side for sediment control during construction and maintained until soils and vegetation have stabilized. Water bars should be placed within the ROW to divert and dissipate surface runoff. A pipeline access road is not permitted to cross these ephemeral drainages. Traffic should be diverted to a preexisting route. Additional seeding may be required in floodplains and drainages to restore energy dissipating vegetation.

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank or 24 hour production, whichever is greater. Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect pressure drops, situating valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

Any water erosion that may occur due to the construction of overhead electric line and during the life of the power line will be quickly corrected and proper measures will be taken to prevent future erosion. A power pole should not be placed in drainages, playas, wetlands, riparian areas, or floodplains and must span across the features at a distance away that would not promote further erosion.

## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### **D. FEDERAL MINERAL MATERIALS PIT**

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

### **F. EXCLOSURE FENCING (CELLARS & PITS)**



**Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

**G. ON LEASE ACCESS ROADS****Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

**Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

- The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

**Crowning**

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

**Ditching**

Ditching shall be required on both sides of the road.

**Turnouts**


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

**Drainage**

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill out sloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

#### **Cross Section of a Typical Lead-off Ditch**



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

#### **Formula for Spacing Interval of Lead-off Ditches**

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

#### **Cattle guards**

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

#### **Fence Requirement**

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

#### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

### Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

## **VII. PRODUCTION (POST DRILLING)**

### **A. WELL STRUCTURES & FACILITIES**

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

#### **Chemical and Fuel Secondary Containment and Exclosure Screening**

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

#### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

#### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

### **B. PIPELINES**

#### **BURIED PIPELINE STIPULATIONS**

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of

the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.

6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.

7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:

- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
- Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
- The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)

8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.

9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

<input type="checkbox"/> seed mixture 1	<input type="checkbox"/> seed mixture 3
<input type="checkbox"/> seed mixture 2	<input type="checkbox"/> seed mixture 4
<input checked="" type="checkbox"/> seed mixture 2/LPC	<input type="checkbox"/> Aplomado Falcon Mixture

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches [that are not otherwise fenced, screened, or netted] to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

19. Special Stipulations:

**Lesser Prairie-Chicken**

Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities



that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

### **C. ELECTRIC LINES**

#### **STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES**

**A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.**

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.

5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant

cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes from the poles removed.

**Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken:**

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

## **VIII. INTERIM RECLAMATION**

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

## **IX. FINAL ABANDONMENT & RECLAMATION**

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

## Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Operator Certification Data Report

10/24/2019

### Operator Certification

*I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are*

**NAME:** Sorina Flores

**Signed on:** 02/07/2019

**Title:** Supv of Drilling Services

**Street Address:** 303 Veterans Airpark Ln #1000

**City:** Midland

**State:** TX

**Zip:** 79705

**Phone:** (432)818-1167

**Email address:** sorina.flores@apachecorp.com

### Field Representative

**Representative Name:**

**Street Address:**

**City:**

**State:**

**Zip:**

**Phone:**

**Email address:**



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Application Data Report

10/24/2019

APD ID: 10400038917

Submission Date: 02/07/2019

Highlighted data  
reflects the most  
recent changes  
[Show Final Text](#)

Operator Name: APACHE CORPORATION

Well Name: THUNDERBIRD DEVELOPMENT UNIT

Well Number: 3H

Well Type: OIL WELL

Well Work Type: Drill

### Section 1 - General

APD ID: 10400038917

Tie to previous NOS?

Submission Date: 02/07/2019

BLM Office: CARLSBAD

User: Sorina Flores

Title: Supv of Drilling Services

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM0002425

Lease Acres: 599.35

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO

APD Operator: APACHE CORPORATION

Operator letter of designation:

### Operator Info

Operator Organization Name: APACHE CORPORATION

Operator Address: 303 Veterans Airpark Lane #1000

Zip: 79705

Operator PO Box:

Operator City: Midland

State: TX

Operator Phone: (432)818-1000

Operator Internet Address:

### Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: THUNDERBIRD DEVELOPMENT UNIT

Well Number: 3H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: YESO

Pool Name: LOCO HILLS;  
GLORIETA-YESO

Operator Name: APACHE CORPORATION

Well Name: THUNDERBIRD DEVELOPMENT UNIT

Well Number: 3H

Is the proposed well in an area containing other mineral resources? USEABLE WATER

Is the proposed well in a Helium production area? N Use Existing Well Pad? NO New surface disturbance?

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: PAD 1 Number: 3H

Well Class: HORIZONTAL

Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 5.4 Miles

Distance to nearest well: 40 FT

Distance to lease line: 100 FT

Reservoir well spacing assigned acres Measurement: 279.74 Acres

Well plat: ThunderbirdDevUnit3H\_Plat\_signed\_20190207082959.pdf

Well work start Date: 07/30/2019

Duration: 20 DAYS

### Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number:

Reference Datum:

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce
	241 1	FNL	109 0	FEL	16S	30E	33	SENE	32.87866 38	- 103.9719 137	EDD Y	NEW MEXI	NEW MEXI	F	NMNM 000242	373 7	0	0	
	238 1	FNL	111 9	FEL	16S	30E	33	SENE	32.87874 54	- 103.9720 098	EDD Y	NEW MEXI	NEW MEXI	F	NMNM 000242	-403	414 1	414 0	
	243 4	FSL	121 6	FEL	16S	30E	33	NESE	32.87746	- 103.9723 225	EDD Y	NEW MEXI	NEW MEXI	F	NMLC0 060325	-881	489 1	461 8	




Operator Name: APACHE CORPORATION

Well Name: THUNDERBIRD DEVELOPMENT UNIT

Well Number: 3H


Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce
	100	FSL	125 4	FEL	16S	30E	4	SESE	32.85656 66	- 103.9724 423	EDD Y	NEW MEXI	NEW MEXI	F	NMLC0 060325	-946	124 95	468 3	
	100	FSL	125 4	FEL	16S	30E	4	SESE	32.85656 66	- 103.9724 423	EDD Y	NEW MEXI	NEW MEXI	F	NMLC0 060325	-946	124 95	468 3	

**APACHE CORPORATION**  
**THUNDERBIRD DEVELOPMENT UNIT #3H**  
**(2411' FNL & 1090' FEL)**  
**SECTION 33, T16S, R30E**  
**N. M. P. M., EDDY CO., NEW MEXICO**



SCALE: 1" = 100'  
 0 50 100

BEARINGS ARE  
 NAD 83 GRID - NM EAST  
 DISTANCES ARE  
 GROUND.



Firm No.: TX 10193838 NM 4655451

Copyright 2014 - All Rights Reserved

	WELL NAME	1.30.19
NO.	REVISION	DATE
JOB NO.:	LS1605193	
DWG. NO.:	1605193PAD	


**RRC**

SURVEYING, LLC

701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 100'
DATE: 6-01-2016
SURVEYED BY: ML/CG
DRAWN BY: RMH
APPROVED BY: RMH
SHEET : 1 OF 1

**APACHE CORPORATION  
INTERIM RECLAMATION  
THUNDERBIRD DEVELOPMENT UNIT #3H  
(2411' FNL & 1090' FEL)  
SECTION 33, T16S, R30E  
N. M. P. M., EDDY CO., NEW MEXICO**



**DIRECTIONS TO LOCATION**

SCALE: 1" = 100'  
0 50 100  
BEARINGS ARE  
NAD 83 GRID - NM EAST  
DISTANCES ARE  
GROUND.

From the intersection of CR-219 (Goat Roper Rd.) and CR-257 (Mallet Rd.)  
Go North on CR-219 approx. 0.2 miles to a lease road on the left;  
Turn left and go Northwest approx. 0.2 miles to lease road on the right;  
Turn right and go North approx. 0.2 miles to a proposed road on the left;  
Turn left and go West approx. 312 feet to location on the South.

Firm No.: TX 10193838 NM 4655451

Copyright 2014 - All Rights Reserved

	WELL NAME	1.30.19
NO.	REVISION	DATE
JOB NO.:	LS1605193	
DWG. NO.:	1605193REC	


**RRC**

SURVEYING, LLC

701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 100'
DATE: 6-01-2016
SURVEYED BY: ML/CG
DRAWN BY: RMH
APPROVED BY: RMH
SHEET : 1 OF 1

# LOCATION VERIFICATION MAP



*SECTION 33, TWP. 16 SOUTH, RGE. 30 EAST,  
N. M. P. M., EDDY CO., NEW MEXICO*

OPERATOR: Apache Corporation  
LEASE: Thunderbird Development Unit  
WELL NO.: 3H  
ELEVATION: 3737'

LOCATION: 2411' FNL & 1090' FEL  
CONTOUR INTERVAL: 10'  
USGS TOPO. SOURCE MAP:  
Henshaw Tank, NM (P. E. 1985)

Firm No.: TX 10193838 NM 4655451

Copyright 2014 - All Rights Reserved

	WELL NAME	1.30.19
NO.	REVISION	DATE
JOB NO.: LS1605193		
DWG. NO.: 1605193LVM		

# RRC


SURVEYING, LLC

701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 1000'  
DATE: 6-01-2016  
SURVEYED BY: ML/CG  
DRAWN BY: LPS  
APPROVED BY: RMH  
SHEET : 1 OF 1

# VICINITY MAP

NOT TO SCALE



*SECTION 33, TWP. 16 SOUTH, RGE. 30 EAST,  
N. M. P. M., EDDY CO., NEW MEXICO*

OPERATOR: Apache Corporation  
LEASE: Thunderbird Development Unit  
WELL NO.: 3H

LOCATION: 2411' FNL & 1090' FEL  
ELEVATION: 3737'

Firm No.: TX 10193838 NM 4655451

Copyright 2014 - All Rights Reserved

	WELL NAME	1.30.19
NO.	REVISION	DATE
JOB NO.: LS1605193		
DWG. NO.: 1605193VM		

# RRC

SURVEYING, LLC

701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200

SCALE: NTS
DATE: 6-01-2016
SURVEYED BY: ML/CG
DRAWN BY: LPS
APPROVED BY: RMH
SHEET : 1 OF 1



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Drilling Plan Data Report

10/24/2019

APD ID: 10400038917

Submission Date: 02/07/2019

Highlighted data  
reflects the most  
recent changes

Operator Name: APACHE CORPORATION

Well Name: THUNDERBIRD DEVELOPMENT UNIT

Well Number: 3H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

### Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	RUSTLER	3737	376	376		POTASH	N
2	TOP SALT	3224	514	514		NONE	N
3	TANSILL	2538	1200	1200		NONE	N
4	YATES	2379	1359	1359		NATURAL GAS,OIL	N
5	SEVEN RIVERS	2119	1619	1619		NATURAL GAS,OIL	N
6	QUEEN	1519	2219	2219		NATURAL GAS,OIL	N
7	GRAYBURG	1086	2652	2652		NATURAL GAS,OIL	N
8	SAN ANDRES	769	2969	2969		NATURAL GAS,OIL	N
9	GLORIETA	-661	4399	4399		NATURAL GAS,OIL	Y
10	YESO	-714	4452	4452		NATURAL GAS,OIL	Y

### Section 2 - Blowout Prevention

Pressure Rating (PSI): 2M

Rating Depth: 8000

Equipment: Rotating Head, Mud Gas Separator, Blow Down Pit, Flare Line, Ignitor

Requesting Variance? YES

**Variance request:** Apache request a variance to use a flexible hose between BOP and choke manifold. Flex hose may vary pending availability. A quality control inspection and test certificate will be available for review.

**Testing Procedure:** BOP/BOPE will be tested by independent service company to 250psi low and high pressure indicated above per Onshore Order 2 requirements. System may be upgraded to higher pressure but sill tested to WP listed . If system is upgraded, all components installed will be functional and tested. Pipe rams will be operationally checked each 24 hr period. Blind rams will be operationally checked on each TOOH. These checks will be noted on daily tour sheets. Other accessories to BOP equipment will include Kelly cock and floor safety valve (inside BOP), choke lines and choke manifold. (see attached schematic)

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

**Choke Diagram Attachment:**

ThunderbirdDevUnit\_BOP\_3M\_2M\_AnnularManifoldSchematic\_20190205162100.pdf

**BOP Diagram Attachment:**

ThunderbirdDevUnit\_BOP\_3M\_2M\_Inst\_on\_Surf\_Manifold\_Schem\_20190205162112.pdf

Flexline\_20190827151231.pdf

**Section 3 - Casing**

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	400	0	400	-974	-1374	400	H-40	48	ST&C	7.21	1.39	BUOY	2.07	BUOY	3.47
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	3200	0	3200	-974	-4174	3200	J-55	36	LT&C	2.19	2.33	BUOY	2.07	BUOY	2.56
3	PRODUCTION	8.5	7.0	NEW	API	N	0	4141	0	4140	-974	-5168	4141	L-80	26	LT&C	2.915	1.12	BUOY	2.4	BUOY	2.81
4	OTHER	8.5	5.5	NEW	API	Y	4141	12495	4140	4683	-5168	-5689	8354	L-80	17	LT&C	2.98	1.17	BUOY	1.94	BUOY	2.25

**Casing Attachments**

**Casing ID:** 1      **String Type:** SURFACE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

ThunderbirdDevUnit\_SurfCsgDesignAssumpt\_20190129141122.pdf

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

#### Casing Attachments

---

**Casing ID:** 2      **String Type:** INTERMEDIATE

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

ThunderbirdDevUnit\_IntermCsgDesignAssumpt\_20190129141134.pdf

---

**Casing ID:** 3      **String Type:** PRODUCTION

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

**Casing Design Assumptions and Worksheet(s):**

ThunderbirdDevUnit\_ProdCsgDesignAssumpt\_20190129141146.pdf

---

**Casing ID:** 4      **String Type:** OTHER      - Tapered Production String

**Inspection Document:**

**Spec Document:**

**Tapered String Spec:**

ThunderbirdDevUnit3H\_ProdCsgTaperedSpecs\_20190207084327.pdf

**Casing Design Assumptions and Worksheet(s):**

ThunderbirdDevUnit\_ProdCsgDesignAssumpt\_20190205144415.pdf

---

#### Section 4 - Cement



**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

String Type	Lead/Tail	Stage Tool	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
OTHER	Lead		0	0	0	0	0	0	0	0	0

SURFACE	Lead		0	400	291	1.33	14.8	387.0 3	25	Class C	1% Calcium Chloride
---------	------	--	---	-----	-----	------	------	------------	----	---------	---------------------

INTERMEDIATE	Lead		0	2560	535	1.87	12.9	1000. 45	25	Class C	5% Salt + 6% Bentonite + 0.5% Suspension Aid + 0.4 #/sk Defoamer
INTERMEDIATE	Tail		2560	3200	205	1.33	14.8	272.6 5	25	Class C	0.2% Retarder
PRODUCTION	Lead	4144	0	3312	275	2.03	12.6	558.2 5	25	Class C	5% Salt + 6% Bentonite + 0.2% Retarder + 0.4#/sk Defoamer
PRODUCTION	Tail		3312	4141	90	1.48	13	133.2	25	TXI Lite	1.3% Salt, 5% Gas Migration Expansion Additive , 0.5% Fluid Loss Agent + 0.1% Anti- settling agent, 0.4#/sk Defoamer

### Section 5 - Circulating Medium

**Mud System Type:** Closed

**Will an air or gas system be Used?** NO

**Description of the equipment for the circulating system in accordance with Onshore Order #2:**

**Diagram of the equipment for the circulating system in accordance with Onshore Order #2:**

**Describe what will be on location to control well or mitigate other conditions:** BOP, Choke Manifold, Gas Buster, Blow Down Pit, Flare Line with Igniter, Pre-Mix Pit, Rotating Head

**Describe the mud monitoring system utilized:** PVT/Pason/Visual Monitoring

### Circulating Medium Table

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	400	SPUD MUD	8.3	9							
3200	4700	OTHER : Cut Brine	8	9.5							
400	3200	SALT SATURATED	9.8	10.5							

### Section 6 - Test, Logging, Coring

**List of production tests including testing procedures, equipment and safety measures:**

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

**List of open and cased hole logs run in the well:**

CBL,CNL/FDC,DS,GR,MWD,MUDLOG

**Coring operation description for the well:**

N/A

### Section 7 - Pressure

**Anticipated Bottom Hole Pressure:** 2000

**Anticipated Surface Pressure:** 969.74

**Anticipated Bottom Hole Temperature(F):** 113

**Anticipated abnormal pressures, temperatures, or potential geologic hazards?** NO

**Describe:**

**Contingency Plans geohazards description:**

**Contingency Plans geohazards attachment:**

**Hydrogen Sulfide drilling operations plan required?** YES

**Hydrogen sulfide drilling operations plan:**

ThunderbirdDevUnit\_H2SOpsContgPlan\_20190130132210.pdf

# **PERMIAN**

**NW DISTRICT - NM EZ NAD 83**

**THUNDERBIRD DEV UNIT PAD (1,2,3,4)**

**THUNDERBIRD DEVL UNIT #3**

**THUNDERBIRD DEVL UNIT #3**

**Plan: Design #1**

## **Standard Survey Report**

**19 October, 2018**

**apachecorp**  
Survey Report

Company:	PERMIAN	Local Co-ordinate Reference:	Well THUNDERBIRD DEVL UNIT #3
Project:	NW DISTRICT - NM EZ NAD 83	TVD Reference:	WELL @ 3763.0ft (Original Well Elev)
Site:	THUNDERBIRD DEV UNIT PAD (1,2,3,4)	MD Reference:	WELL @ 3763.0ft (Original Well Elev)
Well:	THUNDERBIRD DEVL UNIT #3	North Reference:	Grid
Wellbore:	THUNDERBIRD DEVL UNIT #3	Survey Calculation Method:	Minimum Curvature
Design:	Design #1	Database:	PEDM

Project	NW DISTRICT - NM EZ NAD 83		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	THUNDERBIRD DEV UNIT PAD (1,2,3,4)		
Site Position:	Map	Northing:	683,581.90 ft
From:		Easting:	652,371.90 ft
Position Uncertainty:	0.0 ft	Slot Radius:	13.200 in
		Latitude:	32° 52' 43.176 N
		Longitude:	103° 58' 17.968 W
		Grid Convergence:	0.20 °

Well	THUNDERBIRD DEVL UNIT #3		
Well Position	+N/-S	0.0 ft	Northing:
	+E/-W	0.0 ft	Easting:
Position Uncertainty	0.0 ft	Wellhead Elevation:	0.0 ft
		Latitude:	32° 52' 43.176 N
		Longitude:	103° 58' 18.905 W
		Ground Level:	3,737.0 ft

Wellbore	THUNDERBIRD DEVL UNIT #3		
Magnetics	Model Name	Sample Date	Declination
	HDGM	10/16/2018	7.42
			Dip Angle
			60.65
			Field Strength
			48,178

Design	Design #1		
Audit Notes:			
Version:	Phase:	PLAN	Tie On Depth:
			0.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W
	(ft)	(ft)	(ft)
	0.0	0.0	0.0
			Direction
			(°)
			180.96

Survey Tool Program	Date	10/19/2018		
From	To	Survey (Wellbore)	Tool Name	Description
(ft)	(ft)			
0.0	12,495.6	Design #1 (THUNDERBIRD DEVL UNIT #	MWD+HDGM (MWD)	OWSG MWD + HDGM

Planned Survey										
Measured	Inclination	Azimuth	Vertical	+N/-S	+E/-W	Vertical	Dogleg	Build	Turn	
Depth	(°)	(°)	Depth	(ft)	(ft)	Section	Rate	Rate	Rate	
(ft)			(ft)			(ft)	(°/100ft)	(°/100ft)	(°/100ft)	
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00	
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00	
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00	
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00	
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00	
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00	
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00	
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00	
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00	

apachecorp  
Survey Report

Company:	PERMIAN	Local Co-ordinate Reference:	Well THUNDERBIRD DEVL UNIT #3
Project:	NW DISTRICT - NM EZ NAD 83	TVD Reference:	WELL @ 3763.0ft (Original Well Elev)
Site:	THUNDERBIRD DEVL UNIT PAD (1,2,3,4)	MD Reference:	WELL @ 3763.0ft (Original Well Elev)
Well:	THUNDERBIRD DEVL UNIT #3	North Reference:	Grid
Wellbore:	THUNDERBIRD DEVL UNIT #3	Survey Calculation Method:	Minimum Curvature
Design:	Design #1	Database:	PEDM

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00	
1,600.0	1.00	315.00	1,600.0	0.6	-0.6	-0.6	1.00	1.00	0.00	
1,700.0	2.00	315.00	1,700.0	2.5	-2.5	-2.4	1.00	1.00	0.00	
1,800.0	2.00	315.00	1,799.9	4.9	-4.9	-4.9	0.00	0.00	0.00	
1,900.0	2.00	315.00	1,899.8	7.4	-7.4	-7.3	0.00	0.00	0.00	
2,000.0	2.00	315.00	1,999.8	9.9	-9.9	-9.7	0.00	0.00	0.00	
2,100.0	2.00	315.00	2,099.7	12.3	-12.3	-12.1	0.00	0.00	0.00	
2,200.0	2.00	315.00	2,199.7	14.8	-14.8	-14.6	0.00	0.00	0.00	
2,300.0	2.00	315.00	2,299.6	17.3	-17.3	-17.0	0.00	0.00	0.00	
2,400.0	2.00	315.00	2,399.5	19.7	-19.7	-19.4	0.00	0.00	0.00	
2,500.0	2.00	315.00	2,499.5	22.2	-22.2	-21.8	0.00	0.00	0.00	
2,600.0	2.00	315.00	2,599.4	24.7	-24.7	-24.3	0.00	0.00	0.00	
2,700.0	2.00	315.00	2,699.4	27.1	-27.1	-26.7	0.00	0.00	0.00	
2,800.0	1.00	315.00	2,799.3	29.0	-29.0	-28.5	1.00	-1.00	0.00	
2,900.0	0.00	0.00	2,899.3	29.6	-29.6	-29.1	1.00	-1.00	0.00	
3,000.0	0.00	0.00	2,999.3	29.6	-29.6	-29.1	0.00	0.00	0.00	
3,100.0	0.00	0.00	3,099.3	29.6	-29.6	-29.1	0.00	0.00	0.00	
3,200.0	0.00	0.00	3,199.3	29.6	-29.6	-29.1	0.00	0.00	0.00	
3,300.0	0.00	0.00	3,299.3	29.6	-29.6	-29.1	0.00	0.00	0.00	
3,400.0	0.00	0.00	3,399.3	29.6	-29.6	-29.1	0.00	0.00	0.00	
3,500.0	0.00	0.00	3,499.3	29.6	-29.6	-29.1	0.00	0.00	0.00	
3,600.0	0.00	0.00	3,599.3	29.6	-29.6	-29.1	0.00	0.00	0.00	
3,700.0	0.00	0.00	3,699.3	29.6	-29.6	-29.1	0.00	0.00	0.00	
3,800.0	0.00	0.00	3,799.3	29.6	-29.6	-29.1	0.00	0.00	0.00	
3,900.0	0.00	0.00	3,899.3	29.6	-29.6	-29.1	0.00	0.00	0.00	
4,000.0	0.00	0.00	3,999.3	29.6	-29.6	-29.1	0.00	0.00	0.00	
4,100.0	0.00	0.00	4,099.3	29.6	-29.6	-29.1	0.00	0.00	0.00	
4,141.2	0.00	0.00	4,140.5	29.6	-29.6	-29.1	0.00	0.00	0.00	
4,200.0	7.06	191.40	4,199.2	26.1	-30.3	-25.6	12.00	12.00	0.00	
4,300.0	19.06	191.40	4,296.4	4.0	-34.8	-3.4	12.00	12.00	0.00	
4,400.0	31.06	191.40	4,386.8	-37.5	-43.1	38.2	12.00	12.00	0.00	
4,500.0	43.06	191.40	4,466.5	-96.4	-55.0	97.4	12.00	12.00	0.00	
4,600.0	55.06	191.40	4,531.9	-170.4	-69.9	171.5	12.00	12.00	0.00	
4,700.0	67.06	191.40	4,580.2	-256.0	-87.2	257.4	12.00	12.00	0.00	
4,800.0	79.06	191.40	4,609.3	-349.6	-106.1	351.3	12.00	12.00	0.00	
4,891.2	90.00	191.40	4,618.0	-438.4	-124.0	440.4	12.00	12.00	0.00	
4,900.0	90.00	191.14	4,618.0	-447.1	-125.7	449.1	3.00	0.00	-3.00	
5,000.0	90.00	188.14	4,618.0	-545.6	-142.4	548.0	3.00	0.00	-3.00	
5,100.0	90.00	185.14	4,618.0	-645.0	-154.0	647.5	3.00	0.00	-3.00	

apachecorp  
Survey Report

Company:	PERMIAN	Local Co-ordinate Reference:	Well THUNDERBIRD DEVL UNIT #3
Project:	NW DISTRICT - NM EZ NAD 83	TVD Reference:	WELL @ 3763.0ft (Original Well Elev)
Site:	THUNDERBIRD DEV UNIT PAD (1,2,3,4)	MD Reference:	WELL @ 3763.0ft (Original Well Elev)
Well:	THUNDERBIRD DEVL UNIT #3	North Reference:	Grid
Wellbore:	THUNDERBIRD DEVL UNIT #3	Survey Calculation Method:	Minimum Curvature
Design:	Design #1	Database:	PEDM

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
5,200.0	90.00	182.14	4,618.0	-744.8	-160.3	747.3	3.00	0.00	-3.00	
5,278.2	90.00	179.79	4,618.0	-822.9	-161.7	825.5	3.00	0.00	-3.00	
5,300.0	89.56	179.79	4,618.0	-844.7	-161.6	847.3	2.00	-2.00	-0.01	
5,304.1	89.48	179.79	4,618.1	-848.8	-161.6	851.4	2.00	-2.00	-0.01	
5,400.0	89.48	179.79	4,618.9	-944.7	-161.2	947.3	0.00	0.00	0.00	
5,500.0	89.48	179.79	4,619.9	-1,044.7	-160.8	1,047.3	0.00	0.00	0.00	
5,600.0	89.48	179.79	4,620.8	-1,144.7	-160.5	1,147.3	0.00	0.00	0.00	
5,700.0	89.48	179.79	4,621.7	-1,244.7	-160.1	1,247.2	0.00	0.00	0.00	
5,800.0	89.48	179.79	4,622.6	-1,344.7	-159.7	1,347.2	0.00	0.00	0.00	
5,900.0	89.48	179.79	4,623.5	-1,444.7	-159.3	1,447.2	0.00	0.00	0.00	
6,000.0	89.48	179.79	4,624.4	-1,544.7	-159.0	1,547.2	0.00	0.00	0.00	
6,100.0	89.48	179.79	4,625.3	-1,644.7	-158.6	1,647.1	0.00	0.00	0.00	
6,200.0	89.48	179.79	4,626.2	-1,744.7	-158.2	1,747.1	0.00	0.00	0.00	
6,300.0	89.48	179.79	4,627.1	-1,844.7	-157.9	1,847.1	0.00	0.00	0.00	
6,400.0	89.48	179.79	4,628.0	-1,944.7	-157.5	1,947.1	0.00	0.00	0.00	
6,500.0	89.48	179.79	4,628.9	-2,044.7	-157.1	2,047.0	0.00	0.00	0.00	
6,600.0	89.48	179.79	4,629.8	-2,144.7	-156.7	2,147.0	0.00	0.00	0.00	
6,700.0	89.48	179.79	4,630.7	-2,244.7	-156.4	2,247.0	0.00	0.00	0.00	
6,800.0	89.48	179.79	4,631.6	-2,344.7	-156.0	2,347.0	0.00	0.00	0.00	
6,900.0	89.48	179.79	4,632.5	-2,444.7	-155.6	2,446.9	0.00	0.00	0.00	
7,000.0	89.48	179.79	4,633.4	-2,544.7	-155.2	2,546.9	0.00	0.00	0.00	
7,100.0	89.48	179.79	4,634.3	-2,644.7	-154.9	2,646.9	0.00	0.00	0.00	
7,200.0	89.48	179.79	4,635.2	-2,744.6	-154.5	2,746.9	0.00	0.00	0.00	
7,300.0	89.48	179.79	4,636.1	-2,844.6	-154.1	2,846.8	0.00	0.00	0.00	
7,400.0	89.48	179.79	4,637.0	-2,944.6	-153.8	2,946.8	0.00	0.00	0.00	
7,500.0	89.48	179.79	4,637.9	-3,044.6	-153.4	3,046.8	0.00	0.00	0.00	
7,600.0	89.48	179.79	4,638.8	-3,144.6	-153.0	3,146.8	0.00	0.00	0.00	
7,700.0	89.48	179.79	4,639.7	-3,244.6	-152.6	3,246.7	0.00	0.00	0.00	
7,800.0	89.48	179.79	4,640.6	-3,344.6	-152.3	3,346.7	0.00	0.00	0.00	
7,900.0	89.48	179.79	4,641.5	-3,444.6	-151.9	3,446.7	0.00	0.00	0.00	
8,000.0	89.48	179.79	4,642.4	-3,544.6	-151.5	3,546.7	0.00	0.00	0.00	
8,100.0	89.48	179.79	4,643.3	-3,644.6	-151.2	3,646.6	0.00	0.00	0.00	
8,200.0	89.48	179.79	4,644.2	-3,744.6	-150.8	3,746.6	0.00	0.00	0.00	
8,300.0	89.48	179.79	4,645.1	-3,844.6	-150.4	3,846.6	0.00	0.00	0.00	
8,400.0	89.48	179.79	4,646.0	-3,944.6	-150.0	3,946.6	0.00	0.00	0.00	
8,500.0	89.48	179.79	4,646.9	-4,044.6	-149.7	4,046.5	0.00	0.00	0.00	
8,600.0	89.48	179.79	4,647.8	-4,144.6	-149.3	4,146.5	0.00	0.00	0.00	
8,700.0	89.48	179.79	4,648.7	-4,244.6	-148.9	4,246.5	0.00	0.00	0.00	
8,800.0	89.48	179.79	4,649.6	-4,344.6	-148.6	4,346.5	0.00	0.00	0.00	
8,900.0	89.48	179.79	4,650.5	-4,444.6	-148.2	4,446.4	0.00	0.00	0.00	
9,000.0	89.48	179.79	4,651.4	-4,544.6	-147.8	4,546.4	0.00	0.00	0.00	
9,100.0	89.48	179.79	4,652.3	-4,644.6	-147.4	4,646.4	0.00	0.00	0.00	
9,200.0	89.48	179.79	4,653.3	-4,744.6	-147.1	4,746.4	0.00	0.00	0.00	

apachecorp  
Survey Report

Company:	PERMIAN	Local Co-ordinate Reference:	Well THUNDERBIRD DEVL UNIT #3
Project:	NW DISTRICT - NM EZ NAD 83	TVD Reference:	WELL @ 3763.0ft (Original Well Elev)
Site:	THUNDERBIRD DEV UNIT PAD (1,2,3,4)	MD Reference:	WELL @ 3763.0ft (Original Well Elev)
Well:	THUNDERBIRD DEVL UNIT #3	North Reference:	Grid
Wellbore:	THUNDERBIRD DEVL UNIT #3	Survey Calculation Method:	Minimum Curvature
Design:	Design #1	Database:	PEDM

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
9,300.0	89.48	179.79	4,654.2	-4,844.5	-146.7	4,846.3	0.00	0.00	0.00	
9,400.0	89.48	179.79	4,655.1	-4,944.5	-146.3	4,946.3	0.00	0.00	0.00	
9,500.0	89.48	179.79	4,656.0	-5,044.5	-145.9	5,046.3	0.00	0.00	0.00	
9,600.0	89.48	179.79	4,656.9	-5,144.5	-145.6	5,146.3	0.00	0.00	0.00	
9,700.0	89.48	179.79	4,657.8	-5,244.5	-145.2	5,246.2	0.00	0.00	0.00	
9,800.0	89.48	179.79	4,658.7	-5,344.5	-144.8	5,346.2	0.00	0.00	0.00	
9,900.0	89.48	179.79	4,659.6	-5,444.5	-144.5	5,446.2	0.00	0.00	0.00	
10,000.0	89.48	179.79	4,660.5	-5,544.5	-144.1	5,546.2	0.00	0.00	0.00	
10,100.0	89.48	179.79	4,661.4	-5,644.5	-143.7	5,646.1	0.00	0.00	0.00	
10,200.0	89.48	179.79	4,662.3	-5,744.5	-143.3	5,746.1	0.00	0.00	0.00	
10,300.0	89.48	179.79	4,663.2	-5,844.5	-143.0	5,846.1	0.00	0.00	0.00	
10,400.0	89.48	179.79	4,664.1	-5,944.5	-142.6	5,946.1	0.00	0.00	0.00	
10,500.0	89.48	179.79	4,665.0	-6,044.5	-142.2	6,046.0	0.00	0.00	0.00	
10,600.0	89.48	179.79	4,665.9	-6,144.5	-141.9	6,146.0	0.00	0.00	0.00	
10,700.0	89.48	179.79	4,666.8	-6,244.5	-141.5	6,246.0	0.00	0.00	0.00	
10,800.0	89.48	179.79	4,667.7	-6,344.5	-141.1	6,345.9	0.00	0.00	0.00	
10,900.0	89.48	179.79	4,668.6	-6,444.5	-140.7	6,445.9	0.00	0.00	0.00	
11,000.0	89.48	179.79	4,669.5	-6,544.5	-140.4	6,545.9	0.00	0.00	0.00	
11,100.0	89.48	179.79	4,670.4	-6,644.5	-140.0	6,645.9	0.00	0.00	0.00	
11,200.0	89.48	179.79	4,671.3	-6,744.5	-139.6	6,745.8	0.00	0.00	0.00	
11,300.0	89.48	179.79	4,672.2	-6,844.5	-139.2	6,845.8	0.00	0.00	0.00	
11,400.0	89.48	179.79	4,673.1	-6,944.4	-138.9	6,945.8	0.00	0.00	0.00	
11,500.0	89.48	179.79	4,674.0	-7,044.4	-138.5	7,045.8	0.00	0.00	0.00	
11,600.0	89.48	179.79	4,674.9	-7,144.4	-138.1	7,145.7	0.00	0.00	0.00	
11,700.0	89.48	179.79	4,675.8	-7,244.4	-137.8	7,245.7	0.00	0.00	0.00	
11,800.0	89.48	179.79	4,676.7	-7,344.4	-137.4	7,345.7	0.00	0.00	0.00	
11,900.0	89.48	179.79	4,677.6	-7,444.4	-137.0	7,445.7	0.00	0.00	0.00	
12,000.0	89.48	179.79	4,678.5	-7,544.4	-136.6	7,545.6	0.00	0.00	0.00	
12,100.0	89.48	179.79	4,679.4	-7,644.4	-136.3	7,645.6	0.00	0.00	0.00	
12,200.0	89.48	179.79	4,680.3	-7,744.4	-135.9	7,745.6	0.00	0.00	0.00	
12,300.0	89.48	179.79	4,681.2	-7,844.4	-135.5	7,845.6	0.00	0.00	0.00	
12,400.0	89.48	179.79	4,682.1	-7,944.4	-135.2	7,945.5	0.00	0.00	0.00	
12,495.6	89.48	179.79	4,683.0	-8,040.0	-134.8	8,041.1	0.00	0.00	0.00	

Design Targets										
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude		Longitude
bhl THUNDERBIRD DE'	0.00	0.00	4,683.0	-8,040.0	-134.8	675,541.60	652,157.20	32° 51' 23.626 N		103° 58' 20.808 W
- hit/miss target										
- Shape										
- plan hits target center										
- Point										

apachecorp  
Survey Report

Company:	PERMIAN	Local Co-ordinate Reference:	Well THUNDERBIRD DEVL UNIT #3
Project:	NW DISTRICT - NM EZ NAD 83	TVD Reference:	WELL @ 3763.0ft (Original Well Elev)
Site:	THUNDERBIRD DEV UNIT PAD (1,2,3,4)	MD Reference:	WELL @ 3763.0ft (Original Well Elev)
Well:	THUNDERBIRD DEVL UNIT #3	North Reference:	Grid
Wellbore:	THUNDERBIRD DEVL UNIT #3	Survey Calculation Method:	Minimum Curvature
Design:	Design #1	Database:	PEDM

Checked By: \_\_\_\_\_ Approved By: \_\_\_\_\_ Date: \_\_\_\_\_



# **PERMIAN**

**NW DISTRICT - NM EZ NAD 83**

**THUNDERBIRD DEV UNIT PAD (1,2,3,4)**

**THUNDERBIRD DEVL UNIT #3**

**THUNDERBIRD DEVL UNIT #3**

**Plan: Design #1**

## **Standard Survey Report**

**, 19 October, 2018**

# apachecorp

## Survey Report

<b>Company:</b>	PERMIAN	<b>Local Co-ordinate Reference:</b>	Well THUNDERBIRD DEVL UN
<b>Project:</b>	NW DISTRICT - NM EZ NAD 83	<b>TVD Reference:</b>	WELL @ 3763.0ft (Original Wel
<b>Site:</b>	THUNDERBIRD DEV UNIT PAD (1,2,3,4)	<b>MD Reference:</b>	WELL @ 3763.0ft (Original Wel
<b>Well:</b>	THUNDERBIRD DEVL UNIT #3	<b>North Reference:</b>	Grid
<b>Wellbore:</b>	THUNDERBIRD DEVL UNIT #3	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Design:</b>	Design #1	<b>Database:</b>	PEDM

<b>Project</b>	NW DISTRICT - NM EZ NAD 83		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	New Mexico Eastern Zone		

**Site** THUNDERBIRD DEV UNIT PAD (1,2,3,4)

<b>Site Position:</b>		<b>Northing:</b>	683,581.90 ft	<b>Latitude:</b>	
<b>From:</b>	Map	<b>Easting:</b>	652,371.90 ft	<b>Longitude:</b>	
<b>Position Uncertainty:</b>	0.0 ft	<b>Slot Radius:</b>	13.200 in	<b>Grid Convergence:</b>	

<b>Well Position</b>	<b>+N/-S</b>	0.0 ft	<b>Northing:</b>	683,581.60 ft	<b>Latitude:</b>
	<b>+E/-W</b>	0.0 ft	<b>Easting:</b>	652,292.00 ft	<b>Longitude:</b>
<b>Position Uncertainty</b>		0.0 ft	<b>Wellhead Elevation:</b>	0.0 ft	<b>Ground Level:</b>

**Wellbore** THUNDERBIRD DEVL UNIT #3

<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Fi</b>
	HDGM	10/16/2018	7.42	60.65	

**Design** Design #1

**Audit Notes:**

<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>
-----------------	---------------	------	----------------------

<b>Vertical Section:</b>	<b>Depth From (TVD)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>
--------------------------	-------------------------	-------------------	-------------------	----------------------

0.0

0.0

0.0

180.96

## Survey Tool Program

Date 10/19/2018

From  
(ft)To  
(ft)

Survey (Wellbore)

Tool Name

Description

0.0

12,495.6 Design #1 (THUNDERBIRD DEVL UNIT #

MWD+HDGM (MWD)

OWSG MWD + HDG

Measured  
Depth  
(ft)Inclination  
(°)Azimuth  
(°)Vertical Depth  
(ft)+N/-S  
(ft)+E/-W  
(ft)Vert  
Sec  
(f

0.0

0.00

0.00

0.0

0.0

0.0

100.0

0.00

0.00

100.0

0.0

0.0

200.0

0.00

0.00

200.0

0.0

0.0

300.0

0.00

0.00

300.0

0.0

0.0

400.0

0.00

0.00

400.0

0.0

0.0

500.0

0.00

0.00

500.0

0.0

0.0

600.0

0.00

0.00

600.0

0.0

0.0

700.0

0.00

0.00

700.0

0.0

0.0

800.0

0.00

0.00

800.0

0.0

0.0

900.0

0.00

0.00

900.0

0.0

0.0

Well

THUNDERBIRD DEVL UNIT #3

Planned Survey

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Verl Sec (f
1,000.0	0.00	0.00	1,000.0	0.0	0.0	
1,100.0	0.00	0.00	1,100.0	0.0	0.0	
1,200.0	0.00	0.00	1,200.0	0.0	0.0	
1,300.0	0.00	0.00	1,300.0	0.0	0.0	
1,400.0	0.00	0.00	1,400.0	0.0	0.0	
1,500.0	0.00	0.00	1,500.0	0.0	0.0	
1,600.0	1.00	315.00	1,600.0	0.6	-0.6	
1,700.0	2.00	315.00	1,700.0	2.5	-2.5	
1,800.0	2.00	315.00	1,799.9	4.9	-4.9	
1,900.0	2.00	315.00	1,899.8	7.4	-7.4	
2,000.0	2.00	315.00	1,999.8	9.9	-9.9	
2,100.0	2.00	315.00	2,099.7	12.3	-12.3	
2,200.0	2.00	315.00	2,199.7	14.8	-14.8	
2,300.0	2.00	315.00	2,299.6	17.3	-17.3	
2,400.0	2.00	315.00	2,399.5	19.7	-19.7	
2,500.0	2.00	315.00	2,499.5	22.2	-22.2	
2,600.0	2.00	315.00	2,599.4	24.7	-24.7	

2,700.0	2.00	315.00	2,699.4	27.1	-27.1
2,800.0	1.00	315.00	2,799.3	29.0	-29.0
2,900.0	0.00	0.00	2,899.3	29.6	-29.6
3,000.0	0.00	0.00	2,999.3	29.6	-29.6
3,100.0	0.00	0.00	3,099.3	29.6	-29.6
3,200.0	0.00	0.00	3,199.3	29.6	-29.6
3,300.0	0.00	0.00	3,299.3	29.6	-29.6
3,400.0	0.00	0.00	3,399.3	29.6	-29.6
3,500.0	0.00	0.00	3,499.3	29.6	-29.6
3,600.0	0.00	0.00	3,599.3	29.6	-29.6
3,700.0	0.00	0.00	3,699.3	29.6	-29.6
3,800.0	0.00	0.00	3,799.3	29.6	-29.6
3,900.0	0.00	0.00	3,899.3	29.6	-29.6
4,000.0	0.00	0.00	3,999.3	29.6	-29.6
4,100.0	0.00	0.00	4,099.3	29.6	-29.6
4,141.2	0.00	0.00	4,140.5	29.6	-29.6
4,200.0	7.06	191.40	4,199.2	26.1	-30.3
4,300.0	19.06	191.40	4,296.4	4.0	-34.8
4,400.0	31.06	191.40	4,386.8	-37.5	-43.1
4,500.0	43.06	191.40	4,466.5	-96.4	-55.0
4,600.0	55.06	191.40	4,531.9	-170.4	-69.9
4,700.0	67.06	191.40	4,580.2	-256.0	-87.2
4,800.0	79.06	191.40	4,609.3	-349.6	-106.1
4,891.2	90.00	191.40	4,618.0	-438.4	-124.0
4,900.0	90.00	191.14	4,618.0	-447.1	-125.7
5,000.0	90.00	188.14	4,618.0	-545.6	-142.4
5,100.0	90.00	185.14	4,618.0	-645.0	-154.0

**Planned Survey**

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vert Sec (f
5,200.0	90.00	182.14	4,618.0	-744.8	-160.3	
5,278.2	90.00	179.79	4,618.0	-822.9	-161.7	
5,300.0	89.56	179.79	4,618.0	-844.7	-161.6	
5,304.1	89.48	179.79	4,618.1	-848.8	-161.6	
5,400.0	89.48	179.79	4,618.9	-944.7	-161.2	
5,500.0	89.48	179.79	4,619.9	-1,044.7	-160.8	
5,600.0	89.48	179.79	4,620.8	-1,144.7	-160.5	
5,700.0	89.48	179.79	4,621.7	-1,244.7	-160.1	
5,800.0	89.48	179.79	4,622.6	-1,344.7	-159.7	
5,900.0	89.48	179.79	4,623.5	-1,444.7	-159.3	
6,000.0	89.48	179.79	4,624.4	-1,544.7	-159.0	
6,100.0	89.48	179.79	4,625.3	-1,644.7	-158.6	
6,200.0	89.48	179.79	4,626.2	-1,744.7	-158.2	
6,300.0	89.48	179.79	4,627.1	-1,844.7	-157.9	
6,400.0	89.48	179.79	4,628.0	-1,944.7	-157.5	
6,500.0	89.48	179.79	4,628.9	-2,044.7	-157.1	
6,600.0	89.48	179.79	4,629.8	-2,144.7	-156.7	
6,700.0	89.48	179.79	4,630.7	-2,244.7	-156.4	
6,800.0	89.48	179.79	4,631.6	-2,344.7	-156.0	
6,900.0	89.48	179.79	4,632.5	-2,444.7	-155.6	
7,000.0	89.48	179.79	4,633.4	-2,544.7	-155.2	
7,100.0	89.48	179.79	4,634.3	-2,644.7	-154.9	

7,200.0	89.48	179.79	4,635.2	-2,744.6	-154.5
7,300.0	89.48	179.79	4,636.1	-2,844.6	-154.1
7,400.0	89.48	179.79	4,637.0	-2,944.6	-153.8
7,500.0	89.48	179.79	4,637.9	-3,044.6	-153.4
7,600.0	89.48	179.79	4,638.8	-3,144.6	-153.0
7,700.0	89.48	179.79	4,639.7	-3,244.6	-152.6
7,800.0	89.48	179.79	4,640.6	-3,344.6	-152.3
7,900.0	89.48	179.79	4,641.5	-3,444.6	-151.9
8,000.0	89.48	179.79	4,642.4	-3,544.6	-151.5
8,100.0	89.48	179.79	4,643.3	-3,644.6	-151.2
8,200.0	89.48	179.79	4,644.2	-3,744.6	-150.8
8,300.0	89.48	179.79	4,645.1	-3,844.6	-150.4
8,400.0	89.48	179.79	4,646.0	-3,944.6	-150.0
8,500.0	89.48	179.79	4,646.9	-4,044.6	-149.7
8,600.0	89.48	179.79	4,647.8	-4,144.6	-149.3
8,700.0	89.48	179.79	4,648.7	-4,244.6	-148.9
8,800.0	89.48	179.79	4,649.6	-4,344.6	-148.6
8,900.0	89.48	179.79	4,650.5	-4,444.6	-148.2
9,000.0	89.48	179.79	4,651.4	-4,544.6	-147.8
9,100.0	89.48	179.79	4,652.3	-4,644.6	-147.4
9,200.0	89.48	179.79	4,653.3	-4,744.6	-147.1

**Planned Survey**

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Veri Sec (f
9,300.0	89.48	179.79	4,654.2	-4,844.5	-146.7	
9,400.0	89.48	179.79	4,655.1	-4,944.5	-146.3	
9,500.0	89.48	179.79	4,656.0	-5,044.5	-145.9	
9,600.0	89.48	179.79	4,656.9	-5,144.5	-145.6	
9,700.0	89.48	179.79	4,657.8	-5,244.5	-145.2	
9,800.0	89.48	179.79	4,658.7	-5,344.5	-144.8	
9,900.0	89.48	179.79	4,659.6	-5,444.5	-144.5	
10,000.0	89.48	179.79	4,660.5	-5,544.5	-144.1	
10,100.0	89.48	179.79	4,661.4	-5,644.5	-143.7	
10,200.0	89.48	179.79	4,662.3	-5,744.5	-143.3	
10,300.0	89.48	179.79	4,663.2	-5,844.5	-143.0	
10,400.0	89.48	179.79	4,664.1	-5,944.5	-142.6	
10,500.0	89.48	179.79	4,665.0	-6,044.5	-142.2	
10,600.0	89.48	179.79	4,665.9	-6,144.5	-141.9	
10,700.0	89.48	179.79	4,666.8	-6,244.5	-141.5	
10,800.0	89.48	179.79	4,667.7	-6,344.5	-141.1	
10,900.0	89.48	179.79	4,668.6	-6,444.5	-140.7	
11,000.0	89.48	179.79	4,669.5	-6,544.5	-140.4	
11,100.0	89.48	179.79	4,670.4	-6,644.5	-140.0	
11,200.0	89.48	179.79	4,671.3	-6,744.5	-139.6	
11,300.0	89.48	179.79	4,672.2	-6,844.5	-139.2	
11,400.0	89.48	179.79	4,673.1	-6,944.4	-138.9	
11,500.0	89.48	179.79	4,674.0	-7,044.4	-138.5	
11,600.0	89.48	179.79	4,674.9	-7,144.4	-138.1	
11,700.0	89.48	179.79	4,675.8	-7,244.4	-137.8	
11,800.0	89.48	179.79	4,676.7	-7,344.4	-137.4	
11,900.0	89.48	179.79	4,677.6	-7,444.4	-137.0	
12,000.0	89.48	179.79	4,678.5	-7,544.4	-136.6	

12,100.0	89.48	179.79	4,679.4	-7,644.4	-136.3
12,200.0	89.48	179.79	4,680.3	-7,744.4	-135.9
12,300.0	89.48	179.79	4,681.2	-7,844.4	-135.5
12,400.0	89.48	179.79	4,682.1	-7,944.4	-135.2
12,495.6	89.48	179.79	4,683.0	-8,040.0	-134.8

#### Design Targets

##### Target Name

- hit/miss target	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Eas (f
- Shape							
bhl THUNDERBIRD DEVL UNIT	0.00	0.00	4,683.0	-8,040.0	-134.8	675,541.60	€
- plan hits target center							
- Point							

Checked By:

Approved By:

Date:





IT #3

I Elev)

I Elev)

32° 52' 43.176 N  
103° 58' 17.968 W  
0.20 °

32° 52' 43.176 N  
103° 58' 18.905 W  
3,737.0 ft

eld Strength  
(nT)

48,178

0.0

M

[illegible]

tical tion t)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.00
0.0	0.00	0.00	0.00
0.0	0.00	0.00	0.00
0.0	0.00	0.00	0.00
0.0	0.00	0.00	0.00
0.0	0.00	0.00	0.00
-0.6	1.00	1.00	0.00
-2.4	1.00	1.00	0.00
-4.9	0.00	0.00	0.00
-7.3	0.00	0.00	0.00
-9.7	0.00	0.00	0.00
-12.1	0.00	0.00	0.00
-14.6	0.00	0.00	0.00
-17.0	0.00	0.00	0.00
-19.4	0.00	0.00	0.00
-21.8	0.00	0.00	0.00
-24.3	0.00	0.00	0.00

-26.7	0.00	0.00	0.00
-28.5	1.00	-1.00	0.00
-29.1	1.00	-1.00	0.00
-29.1	0.00	0.00	0.00
-29.1	0.00	0.00	0.00
-29.1	0.00	0.00	0.00
-29.1	0.00	0.00	0.00
-29.1	0.00	0.00	0.00
-29.1	0.00	0.00	0.00
-29.1	0.00	0.00	0.00
-29.1	0.00	0.00	0.00
-29.1	0.00	0.00	0.00
-29.1	0.00	0.00	0.00
-29.1	0.00	0.00	0.00
-29.1	0.00	0.00	0.00
-25.6	12.00	12.00	0.00
-3.4	12.00	12.00	0.00
38.2	12.00	12.00	0.00
97.4	12.00	12.00	0.00
171.5	12.00	12.00	0.00
257.4	12.00	12.00	0.00
351.3	12.00	12.00	0.00
440.4	12.00	12.00	0.00
449.1	3.00	0.00	-3.00
548.0	3.00	0.00	-3.00
647.5	3.00	0.00	-3.00

Vertical Elevation (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
747.3	3.00	0.00	-3.00
825.5	3.00	0.00	-3.00
847.3	2.00	-2.00	-0.01
851.4	2.00	-2.00	-0.01
947.3	0.00	0.00	0.00
1,047.3	0.00	0.00	0.00
1,147.3	0.00	0.00	0.00
1,247.2	0.00	0.00	0.00
1,347.2	0.00	0.00	0.00
1,447.2	0.00	0.00	0.00
1,547.2	0.00	0.00	0.00
1,647.1	0.00	0.00	0.00
1,747.1	0.00	0.00	0.00
1,847.1	0.00	0.00	0.00
1,947.1	0.00	0.00	0.00
2,047.0	0.00	0.00	0.00
2,147.0	0.00	0.00	0.00
2,247.0	0.00	0.00	0.00
2,347.0	0.00	0.00	0.00
2,446.9	0.00	0.00	0.00
2,546.9	0.00	0.00	0.00
2,646.9	0.00	0.00	0.00

2,746.9	0.00	0.00	0.00
2,846.8	0.00	0.00	0.00
2,946.8	0.00	0.00	0.00
3,046.8	0.00	0.00	0.00
3,146.8	0.00	0.00	0.00
3,246.7	0.00	0.00	0.00
3,346.7	0.00	0.00	0.00
3,446.7	0.00	0.00	0.00
3,546.7	0.00	0.00	0.00
3,646.6	0.00	0.00	0.00
3,746.6	0.00	0.00	0.00
3,846.6	0.00	0.00	0.00
3,946.6	0.00	0.00	0.00
4,046.5	0.00	0.00	0.00
4,146.5	0.00	0.00	0.00
4,246.5	0.00	0.00	0.00
4,346.5	0.00	0.00	0.00
4,446.4	0.00	0.00	0.00
4,546.4	0.00	0.00	0.00
4,646.4	0.00	0.00	0.00
4,746.4	0.00	0.00	0.00

Location	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,846.3	0.00	0.00	0.00
4,946.3	0.00	0.00	0.00
5,046.3	0.00	0.00	0.00
5,146.3	0.00	0.00	0.00
5,246.2	0.00	0.00	0.00
5,346.2	0.00	0.00	0.00
5,446.2	0.00	0.00	0.00
5,546.2	0.00	0.00	0.00
5,646.1	0.00	0.00	0.00
5,746.1	0.00	0.00	0.00
5,846.1	0.00	0.00	0.00
5,946.1	0.00	0.00	0.00
6,046.0	0.00	0.00	0.00
6,146.0	0.00	0.00	0.00
6,246.0	0.00	0.00	0.00
6,345.9	0.00	0.00	0.00
6,445.9	0.00	0.00	0.00
6,545.9	0.00	0.00	0.00
6,645.9	0.00	0.00	0.00
6,745.8	0.00	0.00	0.00
6,845.8	0.00	0.00	0.00
6,945.8	0.00	0.00	0.00
7,045.8	0.00	0.00	0.00
7,145.7	0.00	0.00	0.00
7,245.7	0.00	0.00	0.00
7,345.7	0.00	0.00	0.00
7,445.7	0.00	0.00	0.00
7,545.6	0.00	0.00	0.00

7,645.6	0.00	0.00	0.00
7,745.6	0.00	0.00	0.00
7,845.6	0.00	0.00	0.00
7,945.5	0.00	0.00	0.00
8,041.1	0.00	0.00	0.00

ting t)	Latitude	Longitude
52,157.20	32° 51' 23.626 N	103° 58' 20.808 W

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

**Production Facilities map:**

ThunderbirddevUnit\_Battery\_20190130140011.pdf

ThunderbirdDevUnit1H\_4H\_ProdLinePlat\_REV\_8.27.19\_20190827151354.pdf

**Section 5 - Location and Types of Water Supply**

**Water Source Table**

**Water source type:** GW WELL

**Water source use type:** SURFACE CASING  
INTERMEDIATE/PRODUCTION  
CASING

**Source latitude:** 32.819386

**Source longitude:** -103.98483

**Source datum:** NAD83

**Water source permit type:** PRIVATE CONTRACT

**Water source transport method:** TRUCKING

**Source land ownership:** PRIVATE

**Source transportation land ownership:** PRIVATE

**Water source volume (barrels):** 2214.2856

**Source volume (acre-feet):** 0.28540614

**Source volume (gal):** 93000

---

**Water source type:** OTHER

**Describe type:** Brine

**Water source use type:** INTERMEDIATE/PRODUCTION  
CASING

**Source latitude:** 32.87279

**Source longitude:** -103.5045

**Source datum:** NAD83

**Water source permit type:** PRIVATE CONTRACT

**Water source transport method:** TRUCKING

**Source land ownership:** STATE

**Source transportation land ownership:** INDIAN  
(TRIBAL/ALLOTTED)

**Water source volume (barrels):** 2214.2856

**Source volume (acre-feet):** 0.28540614



**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

**Source volume (gal):** 93000

---

**Water source and transportation map:**

ThunderbirdDevUnit\_BrineWaterSources\_20190130143811.pdf

ThunderbirdDevUnit\_FreshWaterSources\_20190130143812.pdf

**Water source comments:**

**New water well?** NO

**New Water Well Info**

**Well latitude:**

**Well Longitude:**

**Well datum:**

**Well target aquifer:**

**Est. depth to top of aquifer(ft):**

**Est thickness of aquifer:**

**Aquifer comments:**

**Aquifer documentation:**

**Well depth (ft):**

**Well casing type:**

**Well casing outside diameter (in.):**

**Well casing inside diameter (in.):**

**New water well casing?**

**Used casing source:**

**Drilling method:**

**Drill material:**

**Grout material:**

**Grout depth:**

**Casing length (ft.):**

**Casing top depth (ft.):**

**Well Production type:**

**Completion Method:**

**Water well additional information:**

**State appropriation permit:**

**Additional information attachment:**

**Section 6 - Construction Materials**

**Using any construction materials:** YES

**Construction Materials description:** Caliche from State caliche pit - Sec 36, T15S, R29E

**Construction Materials source location attachment:**

ThunderbirdDevUnit1H\_2H\_3H\_4H\_CalichePitMap\_20190827151456.pdf

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

### Section 7 - Methods for Handling Waste

**Waste type:** DRILLING

**Waste content description:** Drilling fluid from well, during drilling operations, will be stored safely and recycled to next well. Any excess will be hauled to approved NMOCD disposal facility

**Amount of waste:** 3600 barrels

**Waste disposal frequency :** One Time Only

**Safe containment description:** Drilling fluids will be stored in sealed frac tanks

**Safe containmant attachment:**

**Waste disposal type:** RECYCLE

**Disposal location ownership:** OTHER

**Disposal type description:**

**Disposal location description:** Operators next well

**Waste type:** DRILLING

**Waste content description:** Excess cement returns

**Amount of waste:** 40 barrels

**Waste disposal frequency :** Weekly

**Safe containment description:** Cement returns will be stored in steel roll off bins then transferred to disposal vacuum trucks

**Safe containmant attachment:**

**Waste disposal type:** OTHER

**Disposal location ownership:** PRIVATE

**Disposal type description:** Haul to private facility

**Disposal location description:** R360, 6601 W. Hobbs Hwy, Carlsbad, NM, 88220

**Waste type:** SEWAGE

**Waste content description:** Human waste and grey water

**Amount of waste:** 2000 gallons

**Waste disposal frequency :** Weekly

**Safe containment description:** Sewage will be stored in steel waste tanks

**Safe containmant attachment:**

**Waste disposal type:** OTHER

**Disposal location ownership:** STATE

**Disposal type description:** Municipal waste facility

**Disposal location description:** Hobbs Municipal Waste Facility

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

**Waste type:** GARBAGE

**Waste content description:** Household garbage, trash and non-toxic mud sacks

**Amount of waste:** 1500 pounds

**Waste disposal frequency :** Weekly

**Safe containment description:** Garbage will be disposed off in portable trash trailers

**Safe containmant attachment:**

**Waste disposal type:** OTHER

**Disposal location ownership:** STATE

**Disposal type description:** Private Land Fill

**Disposal location description:** Lea County Landfill

### Reserve Pit

**Reserve Pit being used?** NO

**Temporary disposal of produced water into reserve pit?**

**Reserve pit length (ft.)**

**Reserve pit width (ft.)**

**Reserve pit depth (ft.)**

**Reserve pit volume (cu. yd.)**

**Is at least 50% of the reserve pit in cut?**

**Reserve pit liner**

**Reserve pit liner specifications and installation description**

### Cuttings Area

**Cuttings Area being used?** NO

**Are you storing cuttings on location?** YES

**Description of cuttings location** Cuttings will be stored in steel haul off bins & taken to an NMOCD approved disposal facility

**Cuttings area length (ft.)**

**Cuttings area width (ft.)**

**Cuttings area depth (ft.)**

**Cuttings area volume (cu. yd.)**

**Is at least 50% of the cuttings area in cut?**

**WCuttings area liner**

**Cuttings area liner specifications and installation description**

Operator Name: APACHE CORPORATION

Well Name: THUNDERBIRD DEVELOPMENT UNIT

Well Number: 3H

### Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: NO

Ancillary Facilities attachment:

Comments:

### Section 9 - Well Site Layout

Well Site Layout Diagram:

ThunderbirdDevUnit3H\_WellPadPlat\_20190207092408.pdf

ThunderbirdDevUnit1H\_2H\_3H\_4H\_RigLayoutDiagram\_20190207092431.pdf

Comments:

### Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: PAD 1

Multiple Well Pad Number: 3H

Recontouring attachment:

Drainage/Erosion control construction: Slight slope for water drainage

Drainage/Erosion control reclamation: Reclamation is going to follow natural terrain to control erosion, runoff and siltation of surrounding area

Well pad proposed disturbance (acres): 4.775	Well pad interim reclamation (acres): 1.79	Well pad long term disturbance (acres): 2.98
Road proposed disturbance (acres): 0.16	Road interim reclamation (acres): 0.16	Road long term disturbance (acres): 0.16
Powerline proposed disturbance (acres): 0.918	Powerline interim reclamation (acres): 0	Powerline long term disturbance (acres): 0.918
Pipeline proposed disturbance (acres): 1.091	Pipeline interim reclamation (acres): 0	Pipeline long term disturbance (acres): 0
Other proposed disturbance (acres): 0	Other interim reclamation (acres): 0	Other long term disturbance (acres): 0
Total proposed disturbance: 6.944	Total interim reclamation: 1.95	Total long term disturbance: 4.058

**Disturbance Comments:** Other long term/short term disturbance will be for installation of electrical line approx. 1332.27' in length and 30' wide for construction

**Reconstruction method:** Areas planned for interim reclamation will be contoured to original contour if feasible, or if not feasible, to an interim contour that blends with surrounding topography as much as possible. Where applicable, fill material of well pad will be back filled into the cut to bring area back to original contour.

**Topsoil redistribution:** Topsoil that was spread over interim reclamation areas will be stockpiled prior to recontouring. Topsoil will be redistributed evenly over entire disturbed site to ensure successful revegetation

**Soil treatment:** No soil treatment expected

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

**Existing Vegetation at the well pad:**

**Existing Vegetation at the well pad attachment:**

**Existing Vegetation Community at the road:**

**Existing Vegetation Community at the road attachment:**

**Existing Vegetation Community at the pipeline:**

**Existing Vegetation Community at the pipeline attachment:**

**Existing Vegetation Community at other disturbances:**

**Existing Vegetation Community at other disturbances attachment:**

**Non native seed used?** NO

**Non native seed description:**

**Seedling transplant description:**

**Will seedlings be transplanted for this project?** NO

**Seedling transplant description attachment:**

**Will seed be harvested for use in site reclamation?** NO

**Seed harvest description:**

**Seed harvest description attachment:**

## Seed Management

### Seed Table

**Seed type:**

**Seed source:**

**Seed name:**

**Source name:**

**Source address:**

**Source phone:**

**Seed cultivar:**

**Seed use location:**

**PLS pounds per acre:**

**Proposed seeding season:**

### Seed Summary

**Total pounds/Acre:**

Seed Type	Pounds/Acre
-----------	-------------

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

**Seed reclamation attachment:**

**Operator Contact/Responsible Official Contact Info**

**First Name:**

**Last Name:**

**Phone:**

**Email:**

**Seedbed prep:**

**Seed BMP:**

**Seed method:**

**Existing invasive species?** NO

**Existing invasive species treatment description:**

**Existing invasive species treatment attachment:**

**Weed treatment plan description:** Operator will consult with authorized officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

**Weed treatment plan attachment:**

**Monitoring plan description:** Interim reclamation, reclaimed areas, will be monitored periodically to ensure vegetation has re-established, that area is not redisturbed, and erosion is controlled

**Monitoring plan attachment:**

**Success standards:** Objective of interim reclamation is to restore vegetative cover and a portion of landform sufficient to maintain healthy, biologically active topsoil, control erosion, and minimize habitat and forage loss, visual impact, and weed infestation during life of well or facilities. Long term objective of final reclamation is to return land to a condition similar to what existed prior to disturbance. This includes restoration of landform and natural vegetative community, hydrologic systems, visual resources, and wildlife habitats. To ensure that the long term objective will be reached through human and natural processes, actions will be taken to ensure standards are met for site stability, visual quality, hydrological functioning, and vegetative productivity. BLM will be notified 3 days prior to commencement of any reclamation procedures. If circumstances allow, interim and/or final reclamation actions will be completed no later than 6 months from when the final well on location has been completed or plugged. We will gain written permission from BLM if more time is needed.

**Pit closure description:** Not applicable

**Pit closure attachment:**

**Section 11 - Surface Ownership**

**Disturbance type:** WELL PAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Disturbance type:** PIPELINE

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

**Disturbance type:** NEW ACCESS ROAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Disturbance type:** OTHER

**Describe:** ELECTRIC LINE

**Surface Owner:** BUREAU OF LAND MANAGEMENT

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**



**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

## Section 12 - Other Information

**Right of Way needed?** NO

**Use APD as ROW?**

**ROW Type(s):**

### ROW Applications

**SUPO Additional Information:** Apache plans to install an overhead electrical line for the proposed well. The proposed length of the electrical line will be 1332.27 feet from Pad 1- Thunderbird Dev Unit 1H, 2H, 3H, 4H to Pad 2-Thunderbird Dev Unit 5H, 6H. Electrical line will be constructed to provide protection from raptor electrocution. The proposed electrical line does not cross lease boundaries, so a ROW grant will not need to be acquired from BLM.

**Use a previously conducted onsite?** YES

**Previous Onsite information:** 5/26/2016; BLM Rep: Jeffery Robertson; Thunderbird A 1H - 10H


### Other SUPO Attachment

ThunderbirdDevUnit1H\_6H\_ElectricLine\_20190205145023.pdf

ThunderbirdDevUnit3H\_ReclamationPlat\_20190207092515.pdf

# VICINITY MAP

NOT TO SCALE



*SECTION 33, TWP. 16 SOUTH, RGE. 30 EAST,  
N. M. P. M., EDDY CO., NEW MEXICO*

OPERATOR: Apache Corporation  
LEASE: Thunderbird Development Unit  
WELL NO.: 3H

LOCATION: 2411' FNL & 1090' FEL  
ELEVATION: 3737'

Firm No.: TX 10193838 NM 4655451

Copyright 2014 - All Rights Reserved

	WELL NAME	1.30.19
NO.	REVISION	DATE
JOB NO.: LS1605193		
DWG. NO.: 1605193VM		


# RRC

SURVEYING, LLC

701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200

SCALE: NTS
DATE: 6-01-2016
SURVEYED BY: ML/CG
DRAWN BY: LPS
APPROVED BY: RMH
SHEET : 1 OF 1

**APACHE CORPORATION**  
**PROPOSED ACCESS ROAD**  
**FOR THE THUNDERBIRD DEV UNIT #1H, #2H, #3H & #4H WELL LOCATIONS**  
**SECTION 33, T16S, R30E,**  
**N. M. P. M., EDDY CO., NEW MEXICO**



**DESCRIPTION**

A strip of land 30 feet wide, being 231.91 feet or 14.055 rods in length, lying in Section 33, Township 16 South, Range 30 East, N. M. P. M., Eddy County, New Mexico, being 15 feet left and 15 feet right of the following described survey of a centerline across B. L. M. land:

BEGINNING at Engr. Sta. 0+00, a point in the Northeast quarter of Section 33, which bears, S 20°42'56" W, 2,321.29 feet, from a brass cap, stamped "1916", found for the Northeast corner of Section 33;

Thence N 89°49'37" E, 231.91 feet, to Engr. Sta. 2+31.91, the End of Survey, a point in the Northeast quarter of Section 33, which bears, N 51°48'28" W, 762.93 feet, from a brass cap, stamped "1916", found for the East quarter corner of Section 33.

Said strip of land contains 0.160 acres, more or less, and is allocated by forties as follows:

SW 1/4 NE 1/4      14.055 Rods      0.160 Acres


SCALE: 1" = 1000'  
0      500'      1000'

BEARINGS ARE GRID NAD 27  
NM EAST  
DISTANCES ARE HORIZ. GROUND.

LEGEND  
( ) RECORD DATA - GLO  
◆ FOUND MONUMENT AS NOTED  
— PROPOSED ACCESS ROAD

I, R. M. Howett, a N. M. Professional Surveyor, hereby certify that I prepared this plat from an actual survey made on the ground under my direct supervision, said survey and plat meet the Min. Stds. for Land Surveying in the State of N. M. and are true and correct to the best of my knowledge and belief.

*Robert M. Howett*  
Robert M. Howett      NM PS 19680



Firm No.: TX 10193838 NM 4655451

Copyright 2014 - All Rights Reserved


NO.	REVISION	DATE
JOB NO.:	LS1605191RD	
DWG. NO.:	1605191-1	

**RRC**

308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 1000'  
DATE: 6-01-2016  
SURVEYED BY: ML/CG  
DRAWN BY: LPS  
APPROVED BY: RMH  
SHEET : 1 OF 1

**APACHE CORPORATION  
PROPOSED ACCESS ROAD  
FOR THE THUNDERBIRD A #5H & #6H WELL LOCATIONS  
SECTION 33, T16S, R30E,  
N. M. P. M., EDDY CO., NEW MEXICO**



**DESCRIPTION**

A strip of land 30 feet wide, being 86.17 feet or 5.222 rods in length, lying in Section 33, Township 16 South, Range 30 East, N. M. P. M., Eddy County, New Mexico, being 15 feet left and 15 feet right of the following described survey of a centerline across B. L. M. land:

BEGINNING at Engr. Sta. 0+00, a point in the Northeast quarter of Section 33, which bears, S 23°30'41" E, 2,154.84 feet, from a brass cap, stamped "1916", found for the North quarter corner of Section 33;

Thence S 00°00'33" E, 86.17 feet, to Engr. Sta. 0+86.17, the End of Survey, a point in the Northeast quarter of Section 33, which bears, S 40°42'23" W, 2,731.84 feet, from a brass cap, stamped "1916", found for the Northeast corner of Section 33.

Said strip of land contains 0.059 acres, more or less, and is allocated by forties as follows:

SW 1/4 NE 1/4      5.222 Rods      0.059 Acres

SCALE: 1" = 1000'  
0      500'      1000'


BEARINGS ARE GRID NAD 27  
NM EAST  
DISTANCES ARE HORIZ. GROUND.

**LEGEND**

( ) RECORD DATA - GLO  
 FOUND MONUMENT  
 AS NOTED  
 PROPOSED ACCESS ROAD

I, R. M. Howett, a N. M. Professional Surveyor, hereby certify that I prepared this plat from an actual survey made on the ground under my direct supervision, said survey and plat meet the Min. Stds. for Land Surveying in the State of N. M. and are true and correct to the best of my knowledge and belief.

*Robert M. Howett*  
Robert M. Howett      NM PS 19680



Firm No.: TX 10193838 NM 4655451

Copyright 2014 - All Rights Reserved


NO.	REVISION	DATE
JOB NO.:	LS1605195RD	
DWG. NO.:	1605195-1	

**RRC**

308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 1000'
DATE: 6-01-2016
SURVEYED BY: BC/HD
DRAWN BY: LPS
APPROVED BY: RMH
SHEET : 1 OF 1

**APACHE CORPORATION**  
**PROPOSED ELECTRIC LINE FROM THE THUNDERBIRD A #1H, #2H, #3H**  
**& #4H TO THE THUNDERBIRD A #5H & #10H WELL LOCATIONS**  
**SECTION 33, T16S, R30E,**  
**N. M. P. M., EDDY CO., NEW MEXICO**



**DESCRIPTION**

A strip of land 30 feet wide, being 825.17 feet or 50.010 rods in length, lying in Section 33, Township 16 South, Range 30 East, N. M. P. M., Eddy County, New Mexico, being 15 feet left and 15 feet right of the following described survey of a centerline across B. L. M. land:

BEGINNING at Engr. Sta. 0+00, a point in the Northeast quarter of Section 33, which bears, N 82°01'20" W, 1,247.65 feet, from a brass cap, stamped "1916", found for the East quarter corner of Section 33;

Thence S 89°48'42" W, 825.17 feet, to Engr. Sta. 8+25.17, the End of Survey, a point in the Northeast quarter of Section 33, which bears, N 11°26'35" E, 2,877.49 feet, from a brass cap, stamped "1916", found for the South quarter corner of Section 33.

Said strip of land contains 0.568 acres, more or less, and is allocated by forties as follows:

SE 1/4 NE 1/4	5.208 Rods	0.059 Acres
SW 1/4 NE 1/4	44.802 Rods	0.509 Acres

SCALE: 1" = 1000'  
0 500' 1000'

BEARINGS ARE GRID MAG 27  
NM EAST  
DISTANCES ARE HORIZ. GROUND.

**LEGEND**

( ) RECORD DATA - GLO  
 NM EAST  
 DISTANCES ARE HORIZ. GROUND.  
 LEGEND  
 ( ) RECORD DATA - GLO  
 FOUND MONUMENT  
 AS NOTED  
 PROPOSED ELECTRIC LINE

Firm No.: TX 10193838 NM 4655451

I, R. M. Howett, a N. M. Professional Surveyor, hereby certify that I prepared this plat from an actual survey made on the ground under my direct supervision, said survey and plat meet the Min. Stds. for Land Surveying in the State of N. M. and are true and correct to the best of my knowledge and belief.

*Robert M. Howett*  
 Robert M. Howett NM PS 19680



Copyright 2014 - All Rights Reserved

NO.	REVISION	DATE
JOB NO.:	LS1605195EL	
DWG. NO.:	1605195-1	

**RRC**

308 W. BROADWAY ST., HOBBS, NM 88240. (575) 964-8200

SCALE: 1" = 1000'
DATE: 6-01-2016
SURVEYED BY: BC/HD
DRAWN BY: LPS
APPROVED BY: RMH
SHEET : 1 OF 1

Apache Corporation

Thunderbird Dev Unit 3H

1 Mile radius at SHL & BHL - PAD 1

SEC: 4 & 33, T17S 30E

Sortal Overlay OVI

010002000

FEET

POSTED WELL DATA

Well Number

WELL SYMBOLS

Abandoned Oil and Gas Well

Dry Hole, With Show of Gas

Dry Hole, With Show of Oil & Gas

Dry Hole, With Show of Oil

Dry Hole

Injection Well

Location

Oil Well


P&A Oil

Proposed Location


Permitted Location

By: Mike Muncy & Heidi Hirsinger

August 29, 2016



**APACHE CORPORATION**  
**SURVEY OF THE PROPOSED THUNDERBIRD BATTERY SITUATED**  
**WITHIN THE NE 1/4, SE 1/4,**  
**SECTION 33, TOWNSHIP 16 SOUTH, RANGE 30 EAST,**  
**N. M. P. M., EDDY CO., NEW MEXICO**



**LEGEND**  
 (-GLO-) Record Data  
 △ Found Corner As Noted  
 • Calculated Point  
 P.O.B. Point Of Beginning

SCALE: 1" = 200'  
 0 200'

BEARINGS ARE NAD 27 GRID  
 NM EAST & DISTANCES ARE  
 HORIZ. GROUND.



I, Robert M. Howett, New Mexico Professional Surveyor No. 19680, do hereby certify that this survey plat and the actual survey on the ground upon which it is based was performed under my direct supervision and this survey meets the minimum standards for surveying in the State of New Mexico and is true and correct to the best of my knowledge and belief.

*Robert M. Howett*  
 Robert M. Howett  
 Date: 6/17/2016  
 Firm No.: TX 10193838 NM 4655451

**DESCRIPTION**

A tract of land situated within the Northeast quarter, of the Southeast quarter of Section 33, Township 16 South, Range 30 East, N. M. P. M., Eddy County, New Mexico, across B. L. M. land, and being more particularly described by metes and bounds as follows:

BEGINNING at a point, which bears N 06°59'51" W, 1,726.09 feet, from a brass cap, stamped "1916", found for the Southeast corner of Section 33 and being S 12°11'13" W, 949.50 feet, from a brass cap, stamped "1916", found for the East quarter corner of Section 33;

Thence S 30°43'38" W, 200 feet, to a point;

Thence N 59°16'22" W, 400 feet, to a point;

Thence N 30°43'38" E, 200 feet, to a point;

Thence S 59°16'22" E, 400 feet, to the Point Of Beginning.

Said tract of land contains 80,000 square feet or 1.837 acres, more or less.

Copyright 2014 - All Rights Reserved

NO.	REVISION	DATE
JOB NO.:	LS1606200	
DWG. NO.:	1606200BT	

**RRC**

308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1"=200'
DATE: 6-1-2016
SURVEYED BY: BC/HD
DRAWN BY: CMJ
APPROVED BY: RMH
SHEET : 1 OF 1

[illegible]

LINE TABLE		
LINE	BEARING	LENGTH
L1	N 89°49'33" E	97.07'
L2	S 01°59'32" E	672.19'
L3	S 53°41'07" E	101.52'
L4	S 00°12'12" E	307.31'
L5	S 67°21'09" W	112.20'
L6	S 13°52'33" W	111.69'
L7	S 63°49'02" F	181.75'

in

Copyright 2014 – All Rights Reserved

# RRC

SCALE: 1" = 1000'
DATE: 6-01-2016
SURVEYED BY: ML/CG
DRAWN BY: LPS
APPROVED BY: RMH
SHEET : 1 OF 2



**APACHE CORPORATION**  
**PROPOSED BURIED POLY LINE**  
**FROM THE THUNDERBIRD DEVELOPMENT UNIT #1H, #2H, #3H, #4H**  
**TO THE THUNDERBIRD BATTERY**  
**SECTION 33, T16S, R30E,**  
**N. M. P. M., EDDY CO., NEW MEXICO**

DESCRIPTION

A strip of land 30 feet wide, being 1,583.73 feet or 95.984 rods in length, lying in Section 33, Township 16 South, Range 30 East, N. M. P. M., Eddy County, New Mexico, being 15 feet left and 15 feet right of the following described survey of a centerline across B. L. M. land:

BEGINNING at Engr. Sta. 0+00, a point in the Northeast quarter of Section 33, which bears, S 20°37'42" W, 2,330.60 feet, from a brass cap, stamped "1916", found for the Northeast corner of Section 33;

Thence N 89°49'33" E, 97.07 feet, to Engr. Sta. 0+97.07, a P. I. of 88°10'55" right;

Thence S 01°59'32" E, 672.19 feet, to Engr. Sta. 7+69.26, a P. I. of 51°41'35" left;

Thence S 53°41'07" E, 101.52 feet, to Engr. Sta. 8+70.78, a P. I. of 53°28'55" right;

Thence S 00°12'12" E, 307.31 feet, to Engr. Sta. 11+78.09, a P. I. of 67°33'21" right;

Thence S 67°21'09" W, 112.20 feet, to Engr. Sta. 12+90.29, a P. I. of 53°28'36" left;

Thence S 13°52'33" W, 111.69 feet, to Engr. Sta. 14+01.98, a P. I. of 77°41'35" left;

Thence S 63°49'02" E, 181.75 feet, to Engr. Sta. 15+83.73, the End of Survey, a point in the Southeast quarter of Section 33, which bears, N 18°17'06" W, 1,929.06 feet, from a brass cap, stamped "1916", found for the Southeast corner of Section 33.

Said strip of land contains 1.091 acres, more or less, and is allocated by forties as follows:

SW 1/4 NE 1/4	34.001 Rods	0.386 Acres
NE 1/4 SE 1/4	61.983 Rods	0.705 Acres

Firm No.: TX 10193838 NM 4655451

Copyright 2014 - All Rights Reserved


			SCALE: 1" = 1000'
			DATE: 6-01-2016
			SURVEYED BY: ML/CG
			DRAWN BY: LPS
NO.	REVISION	DATE	APPROVED BY: RMH
JOB NO.: LS1605191PL			SHEET : 2 OF 2
DWG. NO.: 1605191-2			

308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

# Thunderbird 1H Brine Water Sources

Source:

Wesserhund



## New Mexico 238


Lovington, NM 89260

- ↑ Head north on NM-238 N  
5.3 mi
- ↙ Turn left onto US-82 W  
32.3 mi
- ↘ Turn right onto Hagerman Cutoff Rd  
3.7 mi
- ↘ Turn right onto Mallett Rd  
0.9 mi
- ↙ Turn left at the 1st cross street onto Goat Ropers Rd  
0.6 mi
- ↙ Turn left  
0.2 mi
- ↙ Turn left  
0.4 mi

Destination: Thunderbird 1H

Source:

Salty Dog



Salty Dog Road

Hobbs, NM 88240

- ↑

1. Head north on Salty Dog Rd toward US-180 E/US-62 E

22 s (453 ft)

Take NM-529 to Hagerman Cutoff Rd in Loco Hills

- ↶

2. Turn left at the 1st cross street onto US-180 W/US-62 W

38 min (38.4 mi)
- ↷

3. Turn right onto NM-529

0.8 mi
- ↶

4. Turn left onto US-82 W

31.0 mi
- 6.6 mi

Continue on Hagerman Cutoff Rd to your destination

- ↷

5. Turn right onto Hagerman Cutoff Rd

13 min (5.9 mi)
- ↷

6. Turn right onto Mallett Rd

3.7 mi
- ↶

7. Turn left at the 1st cross street onto Goat Ropers Rd

0.9 mi
- ↶

8. Turn left

0.6 mi
- ↶

9. Turn left


0.2 mi
- 0.4 mi

Destination: Thunderbird 1H

Loco Hills, New Mexico

Source:

Loco Hills Water Solutions, LLC



Loco Hills, New Mexico


THUNDERBIRD DEV UNIT 1H, 2H, 3H, 4H

PROPOSED CONSTRUCTION MATERIAL SOURCE – STATE CALICHE PIT

SEC 36 T15S R29E




**APACHE CORPORATION  
THUNDERBIRD DEVELOPMENT UNIT #3H  
(2411' FNL & 1090' FEL)  
SECTION 33, T16S, R30E  
N. M. P. M., EDDY CO., NEW MEXICO**



SCALE: 1" = 100'  
0 50 100

BEARINGS ARE  
NAD 83 GRID - NM EAST  
DISTANCES ARE  
GROUND.

Firm No.: TX 10193838 NM 4655451



Copyright 2014 - All Rights Reserved

	WELL NAME	1.30.19
NO.	REVISION	DATE
JOB NO.: LS1605193		
DWG. NO.: 1605193PAD		

**RRC**


SURVEYING, LLC

701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 100'
DATE: 6-01-2016
SURVEYED BY: ML/CG
DRAWN BY: RMH
APPROVED BY: RMH
SHEET : 1 OF 1


**RIG ORIENTATION & LAYOUT (PAD1)**  
(Plat not to scale; Rig layout may vary pending rig availability)

**THUNDERBIRD DEVELOPMENT UNIT 1H, 2H, 3H, 4H**





**APACHE CORPORATION**  
**PROPOSED ELECTRIC LINE FROM THE THUNDERBIRD UNIT #1H, #2H,**  
**#3H & #4H TO THE THUNDERBIRD UNIT #5H & #6H WELL LOCATIONS**  
**SECTION 33, T16S, R30E,**  
**N. M. P. M., EDDY CO., NEW MEXICO**



LINE TABLE		
LINE	BEARING	LENGTH
L1	S 89°48'59" W	611.45'
L2	N 77°28'02" W	435.77'
L3	S 89°48'42" W	285.05'

SCALE: 1" = 1000'  
0 500' 1000'

BEARINGS ARE GRID NAD 27  
NM EAST  
DISTANCES ARE HORIZ. GROUND.


**LEGEND**

- ( ) RECORD DATA - GLO
- ◆ FOUND MONUMENT AS NOTED
- PROPOSED ELECTRIC LINE

Firm No.: TX 10193838 NM 4655451

I, R. M. Howett, a N. M. Professional Surveyor, hereby certify that I prepared this plat from an actual survey made on the ground under my direct supervision, said survey and plat meet the Min. Stds. for Land Surveying in the State of N. M. and are true and correct to the best of my knowledge and belief.

*Robert M. Howett*  
Robert M. Howett NM PS 19680



Copyright 2014 - All Rights Reserved

NO.	REVISION	DATE
JOB NO.:	LS1605195EL	
DWG. NO.:	1605195-1	

**RRC**

308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 1000'
DATE: 6-01-2016
SURVEYED BY: BC/HD
DRAWN BY: LPS
APPROVED BY: RMH
SHEET : 1 OF 1

**APACHE CORPORATION**  
**PROPOSED ELECTRIC LINE**  
**FROM THE THUNDERBIRD UNIT #1H, #2H, #3H & #4H**  
**TO THE THUNDERBIRD UNIT #5H & #6H WELL LOCATIONS**  
**SECTION 33, T16S, R30E,**  
**N. M. P. M., EDDY CO., NEW MEXICO**

DESCRIPTION

A strip of land 30 feet wide, being 1,332.27 feet or 80.744 rods in length, lying in Section 33, Township 16 South, Range 30 East, N. M. P. M., Eddy County, New Mexico, being 15 feet left and 15 feet right of the following described survey of a centerline across B. L. M. land:

BEGINNING at Engr. Sta. 0+00, a point in the Northeast quarter of Section 33, which bears, N 83°54'48" W, 743.04 feet, from a brass cap, stamped "1916", found for the East quarter corner of Section 33;

Thence S 89°48'59" W, 611.45 feet, to Engr. Sta. 6+11.45, a P. I. of 12°42'59" right;

Thence N 77°28'02" W, 435.77 feet, to Engr. Sta. 10+47.72, a P. I. of 12°43'16" left;

Thence S 89°48'42" W, 285.05 feet, to Engr. Sta. 13+32.27, the End of Survey, a point in the Northeast quarter of Section 33, which bears, N 11°26'35" E, 2,877.49 feet, from a brass cap, stamped "1916", found for the South quarter corner of Section 33.

Said strip of land contains 0.918 acres, more or less, and is allocated by forties as follows:


SE 1/4 NE 1/4	35.291 Rods	0.401 Acres
SW 1/4 NE 1/4	45.453 Rods	0.517 Acres

Firm No.: TX 10193838 NM 4655451

Copyright 2014 - All Rights Reserved

<div style="font-size: 48pt; font-weight: bold; margin: 0;">RRC</div>			SCALE: 1" = 1000'
			DATE: 6-01-2016
			SURVEYED BY: BC/HD
			DRAWN BY: LPS
NO.	REVISION	DATE	APPROVED BY: RMH
JOB NO.: LS1605195EL			SHEET : 1 OF 1
DWG. NO.: 1605195-2			308 W. BROADWAY ST., HOBBS, NM 88240 (575) 964-8200

**APACHE CORPORATION  
INTERIM RECLAMATION  
THUNDERBIRD DEVELOPMENT UNIT #3H  
(2411' FNL & 1090' FEL)  
SECTION 33, T16S, R30E  
N. M. P. M., EDDY CO., NEW MEXICO**



**DIRECTIONS TO LOCATION**

SCALE: 1" = 100'  
0 50 100  
BEARINGS ARE  
NAD 83 GRID - NM EAST  
DISTANCES ARE  
GROUND.

From the intersection of CR-219 (Goat Roper Rd.) and CR-257 (Mallet Rd.)  
Go North on CR-219 approx. 0.2 miles to a lease road on the left;  
Turn left and go Northwest approx. 0.2 miles to lease road on the right;  
Turn right and go North approx. 0.2 miles to a proposed road on the left;  
Turn left and go West approx. 312 feet to location on the South.

Firm No.: TX 10193838 NM 4655451

Copyright 2014 - All Rights Reserved

	WELL NAME	1.30.19
NO.	REVISION	DATE
JOB NO.:	LS1605193	
DWG. NO.:	1605193REC	

**RRC**

SURVEYING, LLC

701 S. CECIL ST., HOBBS, NM 88240 (575) 964-8200

SCALE: 1" = 100'
DATE: 6-01-2016
SURVEYED BY: ML/CG
DRAWN BY: RMH
APPROVED BY: RMH
SHEET : 1 OF 1



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## PWD Data Report

10/24/2019

APD ID: 10400038917

Submission Date: 02/07/2019

Operator Name: APACHE CORPORATION

Well Name: THUNDERBIRD DEVELOPMENT UNIT

Well Number: 3H

Well Type: OIL WELL

Well Work Type: Drill

### Section 1 - General

Would you like to address long-term produced water disposal? NO

### Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

**Lined pit Monitor description:**

**Lined pit Monitor attachment:**

**Lined pit: do you have a reclamation bond for the pit?**

**Is the reclamation bond a rider under the BLM bond?**

**Lined pit bond number:**

**Lined pit bond amount:**

**Additional bond information attachment:**

### **Section 3 - Unlined Pits**

**Would you like to utilize Unlined Pit PWD options? NO**

**Produced Water Disposal (PWD) Location:**

**PWD disturbance (acres):**

**PWD surface owner:**

**Unlined pit PWD on or off channel:**

**Unlined pit PWD discharge volume (bbl/day):**

**Unlined pit specifications:**

**Precipitated solids disposal:**

**Describe precipitated solids disposal:**

**Precipitated solids disposal permit:**

**Unlined pit precipitated solids disposal schedule:**

**Unlined pit precipitated solids disposal schedule attachment:**

**Unlined pit reclamation description:**

**Unlined pit reclamation attachment:**

**Unlined pit Monitor description:**

**Unlined pit Monitor attachment:**

**Do you propose to put the produced water to beneficial use?**

**Beneficial use user confirmation:**

**Estimated depth of the shallowest aquifer (feet):**

**Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?**

**TDS lab results:**

**Geologic and hydrologic evidence:**

**State authorization:**

**Unlined Produced Water Pit Estimated percolation:**

**Unlined pit: do you have a reclamation bond for the pit?**

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

**Is the reclamation bond a rider under the BLM bond?**

**Unlined pit bond number:**

**Unlined pit bond amount:**

**Additional bond information attachment:**

#### **Section 4 - Injection**

**Would you like to utilize Injection PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Injection PWD discharge volume (bbl/day):**

**Injection well mineral owner:**

**Injection well type:**

**Injection well number:**

**Injection well name:**

**Assigned injection well API number?**

**Injection well API number:**

**Injection well new surface disturbance (acres):**

**Minerals protection information:**

**Mineral protection attachment:**

**Underground Injection Control (UIC) Permit?**

**UIC Permit attachment:**

#### **Section 5 - Surface Discharge**

**Would you like to utilize Surface Discharge PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Surface discharge PWD discharge volume (bbl/day):**

**Surface Discharge NPDES Permit?**

**Surface Discharge NPDES Permit attachment:**

**Surface Discharge site facilities information:**

**Surface discharge site facilities map:**

#### **Section 6 - Other**

**Would you like to utilize Other PWD options?** NO

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Other PWD discharge volume (bbl/day):**

**Operator Name:** APACHE CORPORATION

**Well Name:** THUNDERBIRD DEVELOPMENT UNIT

**Well Number:** 3H

**Other PWD type description:**

**Other PWD type attachment:**

**Have other regulatory requirements been met?**

**Other regulatory requirements attachment:**



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Bond Info Data Report

10/24/2019

APD ID: 10400038917

Submission Date: 02/07/2019

Operator Name: APACHE CORPORATION

Well Name: THUNDERBIRD DEVELOPMENT UNIT

Well Number: 3H

Well Type: OIL WELL

Well Work Type: Drill

Highlighted data  
reflects the most  
recent changes  
[Show Final Text](#)

### Bond Information

Federal/Indian APD: FED

BLM Bond number: NMB000736

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment: