Form 3160-3 (June 2015)

FORM APPROVED OMB No. 1004-0137 Expires: January 31, 2018

5. Lease Serial No.

UNITED STATES

SD-OCE	ARTES T	NIOE	MANAGEMENT	kiedif
	DOKEAU OF	LAND	MANAGEMENI	1

BUREAU OF LAND MAN				1		NMNM138850		
APPLICATION FOR PERMIT TO I	DRIL	L OR	REENTER			6. If Indian, Allotee	or Tribe	Name
	RÉEN'	ΓER				7. If Unit or CA Ag	reement,	Name and No.
	Other Single	Zone [	Multiple Zone			8. Lease Name and NAILED IT FED C	ЮМ	
2. Name of Operator TAP ROCK OPERATING LLC						9. API Well No.		
3a. Address 602 Park Point Drive Suite 200, Golden, CO 80401	.(720	0) 460-3		cod	(e)	10. Field and Pool, PURPLE SAGE W	or Exploi	ratory
<ol> <li>Location of Well (Report location clearly and in accordance         At surface LOT 1 / 741 FSL / 668 FEL / LAT 32.00219         At proposed prod. zone NESE / 2466 FSL / 331 FEL / L</li> </ol>	71 / L	.ONG -1	03.828275	.82	72004	11. Sec., T. R. M. or SEC 36/T26S/R30		1 Survey or Area
14. Distance in miles and direction from nearest town or post of 20 miles	fice*			}		12. County or Parish EDDY	h	13. State NM
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)	16. 320	No of ac	res in lease	7	17. Spacii 288.4			
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.  25 feet	19. Proposed Depth 11945 feet / 16330 feet				ļ	BIA Bond No. in file		
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3043 feet	22. Approximate date work v 01/01/2020				start*	23. Estimated durati 30 days	on	
		. Attach						
The following, completed in accordance with the requirements o (as applicable)	f Onsh	ore Oil a	and Gas Order No	o. <b>1</b>	, and the H	lydraulic Fracturing r	ule per 43	3 CFR 3162.3-3
Well plat certified by a registered surveyor.     A Drilling Plan.     A Surface Use Plan (if the location is on National Forest Syste SUPO must be filed with the appropriate Forest Service Office	m Lan	ds, the	Item 20 above 5. Operator cert	e). ific	ation.	s unless covered by ar mation and/or plans as		
25. Signature (Electronic Submission)			<i>Printed/Typed)</i> Vood / Ph: (720	—— O) 4	160-3316		Date 10/21/2	019
Title President			_				_	
Approved by (Signature) (Electronic Submission)		,	<i>Printed/Typed)</i> ayton / Ph: (57:	5) 2	234-5959		Date 02/27/2	020
Title Assistant Field Manager Lands & Minerals			ad Field Office				· · · · · · · · · · · · · · · · · · ·	
Application approval does not warrant or certify that the applican applicant to conduct operations thereon.  Conditions of approval, if any, are attached.	t hold	s legal or	equitable title to	th	ose rights i	n the subject lease wh	nich woul	d entitle the
Fitle 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212 pr	nake it	a crime	for any person k	1011	ingly and	willfully to make to a	ny donost	mant or occur.

Approval Date: 02/27/2020

of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

PW3-16-20

.

### **INSTRUCTIONS**

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM I: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the wen, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionany drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

### **NOTICES**

The Privacy Act of 1974 and regulation in 43 CFR 2.48( d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service wen or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record win be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM conects this information to anow evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

**BURDEN HOURS STATEMENT:** Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Conection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

### **Additional Operator Remarks**

### **Location of Well**

0. SHL: LOT 1 / 741 FSL / 668 FEL / TWSP: 26S / RANGE: 30E / SECTION: 36 / LAT: 32.0021971 / LONG: -103.828275 (TVD: 0 feet, MD: 0 feet )
PPP: LOT 1 / 24 FSL / 331 FEL / TWSP: 26S / RANGE: 30E / SECTION: 36 / LAT: 32.0002339 / LONG: -103.8271783 (TVD: 10819 feet, MD: 10885 feet )
BHL: NESE / 2466 FSL / 331 FEL / TWSP: 26S / RANGE: 30E / SECTION: 25 / LAT: 32.0128119 / LONG: -103.8272004 (TVD: 11945 feet, MD: 16330 feet )

### **BLM Point of Contact**

Name: Tyler Hill

Title: LIE

Phone: (575) 234-5972 Email: tjhill@blm.gov

(Form 3160-3, page 3)

### **Review and Appeal Rights**

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

(Form 3160-3, page 4)

# PECOS DISTRICT SURFACE USE CONDITIONS OF APPROVAL

ODEDATORIC MAME.	T D 10 11	
OPERATOR'S NAME:	Tap Rock Operating L	LC
LEASE NO.:	NMNM138850	
COUNTY:	Lea	
	200	
The following conditions of approve the SWSW quarter of Section 25, T2	al are only applicable 6S, R30E.	to the portion of road residing in
See page two for the a	oplicable wells and the	eir legal descriptions.
Standard Conditions of Approval (CC exist or special COAs are required, the	ABLE OF CONTENTS DA) apply to this APD. I' e section with the devia below.	any deviations to these standards
☐ General Provisions		
☐ Permit Expiration		
Archaeology, Paleontology, and	Historical Sites	
Noxious Weeds	ilistorical Sites	
Special Requirements		
Cave/Karst		
□ Construction		
Notification		
Federal Mineral Material Pits		
Roads		
☐ Road Section Diagram		

Ser Committee of the Committee of American Committee			***************************************	SHL	······································			······································			
	Well Name	ULSTR	Foo	tage	Coord	inates	ULSTR	Foo	otage	Coore	dinates
	Nailed It Fed Com 201H	L4 36-26S-30E	330 FSL	279 FWL	32.0010601	-103.8424129	NWSW 25-26S-30E	2464 FSL	638 FWL	32.0128419	-103.8412680
	Nailed It Fed Com 205H	L4 36-26S-30E	330 FSL	304 FWL	32.0010602	-103.8423323	NWSW 25-26S-30E	2464 FSL	-1254 FWL	32.0128378	-103.8392806
	Nailed It Fed Com 211H	L4 36-26S-30E	305 FSL	279 FWL	32.0009914	-103.8424129	NWSW 25-26S-30E	2464 FSL	331 FWL	32.0128440	-103.8422585
W2W2	Nailed It Fed Com 215H	L4 36-26S-30E	305 FSL	304 FWL	32.0009915	-103.8423323	NWSW 25-26S-30E	2464 FSL	946 FWL	32.0128399	-103.8402743
Pad	Nailed It Fed Com 221H	L4 36-26S-30E	330 FSL	384 FWL	32.0010603	-103.8420742	NWSW 25-26S-30E	2464 FSL	331 FWL	32.0128440	-103.8422585
(Slot 1)	Nailed It Fed Com 225H.	L4 36-26S-30E	330 FSL	434 FWL	32.0010604	-103.8419129	NWSW 25-26S-30E	' 2464 FSL	1170 FWL	32.0128384	-103.8395516
	Nailed It Fed Com 231H	L4 36-26S-30E	330 FSL	409 FWL	32.0010604	-103.8419936	NWSW 25-26S-30E	2464 FSL	750 FWL	32.0128412	-103.8409067
	Nailed It Fed Com 241H.	. L4 36-26S-30E	305 FSL 3	384 FWL	32.0009916	-103.8420742	NWSW 25-26S-30E	, 2464 FSL	331 FWL	32.0128440	-103.8422585
100	Nailed It Fed Com 245H	L4 36-26S-30E	305 FSL	434 FWL	32.0009917	-103.8419129	NWSW 25-26S-30E	2464 FSL	1170 FWL	32.0128384	-103.8395516
	Nailed It Fed Com 202H	L3 36-26S-30E	230 FSL	1840 FWL	32.0007876	-103.8373781	NESW 25-26S-30E	2465 FSL	1870 FWL	32.0128336	-103.8372932
	Nailed It Fed Com 207H	L3 36-26S-30E	230 FSL	1865 FWL	32.0007876	-103.8372974	NESW 25-26S-30E	2465 FSL	2486 FWL	32.0128294	-103.8353058
E2W2	Nailed It Fed Com 212H	L3 36-26S-30E	205 FSL	1840 FWL	32.0007189	-103.8373780	NESW 25-26S-30E	2464 FSL	1562 FWL	32.0128357	-103.8382869
Pad	Nailed It Fed Com 217H	L3 36-26S-30E	205 FSL	1865 FWL	32.0007189	-103.8372974	NESW 25-26S-30E	2465 FSL	2178 FWL	32.0128315	-103.8362995
(Slot 2)	Nailed It Fed Com 222H	L3 36-26S-30E	230 FSL	1970 FWL	32.0007878	-103.8369587	NESW 25-26S-30E	2465 FSL	2010 FWL	32.0128327	-103.8368415
(3100.2)	Nailed It Fed Com 232H	L3 36-26S-30E	205 FSL	1970 FWL	32.0007190	-103.8369587	NESW 25-26S-30E	2465 FSL	2430 FWL	32.0128298	-103.8354865
\$1	Nailed It Fed Com 235H	L3 36-26S-30E	230 FSL	1945 FWL	32.0007877	-103.8370394	NESW 25-26S-30E	2464 FSL	1590 FWL	32.0128355	-103.8381966
	Nailed It Fed Com 242H	L3 36-26S-30E	205 FSL	1945 FWL	32.0007190	-103.8370393	NESW 25-26S-30E	2465 FSL	2010 FWL	32.0128327	-103.8368415
1,5	Nailed It Fed Com 203H	L2 36-26S-30E	701 FSL	2225 FEL	32.0020849	-103.8332991	NWSE 25-26S-30E	2465 FSL	2178 FEL	32,0128248	-103.8331593
	Nailed It Fed Com 206H	L2 36-26S-30E	701 FSL	2200 FEL	32.0020849	-103.8332184	NWSE 25-26S-30E	2465 FSL	1562 FEL	32.0128206	-103.8311720
	Nailed It Fed Com 213H	L2 36-26S-30E	676 FSL	2225 FEL	32.0020162	-103.8332990	NWSE 25-26S-30E	2465 FSL	2486 FEL 1	32.0128269	103.8341530
W2E2	Nailed It Fed Com 216H	L2 36-26S-30E	676 FSL	2200 FEL	32.0020162	-103.8332184	NWSE 25-26S-30E	2465 FSL	1870 FEL	32.0128227	-103.8321657
Pad	Nailed It Fed Com 223H	L2 36-26S-30E	701 FSL	2120 FEL	32.0020850	-103.8329603	NWSE 25-26S-30E	2465 FSL	2430 FEL :	32.0128266	-103.8339724
(Slot 3)	Nailed It Fed Com 226H	L2 36-26S-30E	701 FSL	2070 FEL	32.0020851	-103.8327990	NWSE 25-26S-30E	2465 FSL	1590 FEL	32.0128207	-103.8312623
	Nailed It Fed Com 233H	L2 36-26S-30E	701 FSL	2095 FEL	32.0020851	103.8328797_	NWSE 25-26S-30E	. 2465 FSL	2010 FEL	32.0128237	103.8326173
	Nailed It Fed Com 243H	L2 36-26S-30E	676 FSL	2120 FEL	32.0020163	-103.8329603	NWSE 25-26S-30E	2465 FSL	2430 FEL	32.0128266	-103.8339724
	Nailed It Fed Com 246H	L2 36-26S-30E	676 FSL	2070 FEL	32.0020164	-103.8327990	NWSE 25-26S-30E	2465 FSL	1590 FEL	32.0128207	-103.8312623
	Nailed It Fed Com 204H	L1 36-26S-30E	766 FSL	588 FEL	32.0022660	-103.8280170	NESE 25-26S-30E	2466 FSL	946 FEL	32.0128162	-103.8291846
	Nailed It Fed Com 208H	L1 36-26S-30E	766 FSL	563 FEL	32.0022660	*-103.8279364 <b>*</b>	NESE 25-26S-30E	2466 FSL	331 FEL	32.0128119	-103,8272004
. 346 4	Nailed It Fed Com 214H	L1 36-26S-30E	741 FSL	588 FEL	32.0021972	-103.8280170	NESE 25-26S-30E	2465 FSL	1254 FEL	32.0128184	-103.8301783
E2E2 Pad	Nailed It Fed Com 218H	L1 36-26S-30E	741 FSL	563 FEL	<b>32.0021973</b>	-103.8279363	NESE 25-26S-30E	2466 FSL	638 FEL	32.0128141	-103.8281909
(Slot 4)	Nailed It Fed Com 224H	L1 36-26S-30E	766 FSL	668 FEL	32.0022659	-103.8282751	NESE 25-26S-30E	2466 FSL	750 FEL	32.0128149	-103.8285522
(310(-1)	Nailed It Fed Com 234H	L1 36-26S-30E	741 FSL	. ₹ 668 FEL	32.0021971	-103.8282750	NESE 25-26S-30E	2466 FSL	331 FEL	32.0128119	-103.8272004
	Nailed It Fed Com 236H	L1 36-26S-30E	766 FSL	693 FEL	32.0022658	-103.8283557	NESE 25-26S-30E	2465 FSL	1170 FEL	32.0128178	-103.8299072
	Nailed It Fed Com 244H	L1 36-26S-30E	741 FSL	. ₹693 FEL	32.0021971	(-103.8283557)	NESE 25-26S-30E	2466 FSL	. 750 FEL	32.0128149	-103.8285522

### I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

### II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

### III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural resource (historic or prehistoric site or object) discovered by the holder, or any person working on the holder's behalf, on public or Federal land shall be immediately reported to the Authorized Officer. The holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to the proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

OR

If the entire project is covered under the Permian Basin Programmatic Agreement (cultural resources only):

The proponent has contributed funds commensurate to the undertaking into an account for offsite mitigation. Participation in the PA serves as mitigation for the effects of this project on cultural resources. If any human skeletal remains, funerary objects, sacred objects, or objects of cultural patrimony are discovered at any time during construction, all construction activities shall halt and the BLM will be notified as soon as possible within 24 hours. Work shall not resume until a Notice to Proceed is issued by the BLM. See information below discussing NAGPRA.

If the proposed project is split between a Class III inventory and a Permian Basin Programmatic Agreement contribution, the portion of the project covered under Class III inventory should default to the first paragraph stipulations.

The holder is hereby obligated to comply with procedures established in the Native American Graves Protection and Repatriation Act (NAGPRA) to protect such cultural items as human remains, associated funerary objects, sacred objects, and objects of cultural patrimony discovered inadvertently during the course of project implementation. In the event that any of the cultural items listed above are discovered during the course of project work, the proponent shall immediately halt the disturbance and contact the BLM within 24 hours for instructions. The proponent or initiator of any project shall be held responsible for protecting, evaluating, reporting, excavating, treating, and disposing of these cultural items according to the procedures established by the BLM in consultation with Indian Tribes."

Page 3 of 8

Any paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on the holder's behalf, on public or Federal land shall be immediately reported to the Authorized Officer. The holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to the proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

### IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

### SPECIAL REQUIREMENT(S)

### Cave/Karst:

### **Road Construction:**

- Turnout ditches and drainage leadoffs will not be constructed in such a manner as to alter the natural flow of water into or out of cave or karst features.
- Special restoration stipulations or realignment may be required if subsurface features are discovered during construction.

### CONSTRUCTION

### A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

### B. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### C. ON LEASE ACCESS ROADS

### **Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

### Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Page 4 of 8

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

### Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

### Ditching

Ditching shall be required on both sides of the road.

#### Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

### Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

### Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Page 5 of 8

### Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope: 
$$\frac{400'}{4\%} + 100' = 200'$$
 lead-off ditch interval

### Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

### Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Page 6 of 8

### **Construction Steps**

- 1. Salvage topsoil
- 2. Construct road
- 3. Redistribute topsoil
- 4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

### Seed Mixture 2, for Sandy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be <u>no</u> primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law (s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

### **Species**

	I <u>b/acre</u>
Sand dropseed (Sporobolus cryptandrus)	1.0
Sand love grass (Eragrostis trichodes)	1.0
Plains bristlegrass (Setaria macrostachya)	2.0

<sup>\*</sup>Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

## PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:
WELL NAME & NO.:
Nailed It Fed Com 234H
230 FSL / 1840 FWL
2465 FSL / 1870 FWL
LOCATION:
COUNTY:
Sec 36 / 26S / 30E / NMP
Eddy County, New Mexico



H2S	C Yes	⊙ No				
Potash	• None	O Secretary	C R-111-P			
Cave/Karst Potential	C Low	O Medium	© High			
Cave/Karst Potential	Critical					
Variance	© None	© Flex Hose	C Other			
Wellhead	© Conventional	• Multibowl	C Both			
Other	□ 4 String Area	Capitan Reef	WIPP			
Other	Fluid Filled	☐ Cement Squeeze	☐ Pilot Hole			
Special Requirements	☐ Water Disposal	<b>☑</b> COM	□ Unit			

### A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

### **B. CASING**

- 1. The 13-3/8 inch surface casing shall be set at approximately 920 feet (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of <u>8</u> hours or 500 pounds compressive strength, whichever is greater. (This is to

Page 1 of 7

include the lead cement)

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

- 2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
  - Cement to surface. If cement does not circulate see B.1.a, c-d above.
     Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.
  - ❖ In <u>High Cave/Karst Areas</u> if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
- 3. The minimum required fill of cement behind the 7-5/8 inch intermediate casing is:
  - Cement to surface. If cement does not circulate see B.1.a, c-d above. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.
  - ❖ In <u>High Cave/Karst Areas</u> if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
- 4. The minimum required fill of cement behind the 5-1/2 inch production casing is:
  - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

### C. PRESSURE CONTROL

- 1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'
- 2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M)** psi.
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.

Page 2 of 7

- b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- c. Manufacturer representative shall install the test plug for the initial BOP test.
- d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

### D. SPECIAL REQUIREMENT (S)

### **Communitization Agreement**

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

### GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)
  - Eddy County
    Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822
  - ✓ Lea CountyCall the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)393-3612

- 1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
    - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
- 2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
- 3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

### A. CASING

- 1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
- 2. <u>Wait on cement (WOC) for Potash Areas:</u> After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least <u>24 hours</u>. WOC time will be recorded in the driller's log. The casing intergrity test can be done (prior to the cement setting up) immediately after bumping the plug.

- 3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing intergrity test can be done (prior to the cement setting up) immediately after bumping the plug.
- 4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
- 5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
- 6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
- 7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
- 8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

### B. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

Page 5 of 7

- 3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
- 4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
  - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- 5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
  - c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for

the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).

- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

### C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

### D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

## **Operator Certification Data Report**

### **Operator Certification**

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Brian Wood

Title: President

Street Address: 37 Verano Looop

City: Santa Fe

State: NM

Zip: 87508

Signed on: 09/02/2019

Phone: (505)466-8120

Email address: afmss@permitswest.com

### Field Representative

Representative Name:

Street Address:

City:

State:

Phone: (505)466-8120

Email address: afmss@permitswest.com

Zip:



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

## Application Data Repor

APD ID: 10400048145

Submission Date: 10/21/2019

Highlighted data reflects the most

**Operator Name: TAP ROCK OPERATING LLC** 

Well Number: 234H

recent changes

Well Name: NAILED IT FED COM

Show Final Text

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

### Section 1 - General

APD ID:

10400048145

Tie to previous NOS? N

Submission Date: 10/21/2019

**BLM Office: CARLSBAD** 

User: Brian Wood

Title: President

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM138850

Lease Acres: 320

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? N

**Permitting Agent? YES** 

APD Operator: TAP ROCK OPERATING LLC

Operator letter of designation:

### Operator Info

Operator Organization Name: TAP ROCK OPERATING LLC

Operator Address: 602 Park Point Drive Suite 200

Operator PO Box:

Zip: 80401

Operator City: Golden

State: CO

Operator Phone: (720)460-3316

**Operator Internet Address:** 

### Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: NAILED IT FED COM

Well Number: 234H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: PURPLE SAGE

Pool Name:

WOLFCAMP

Is the proposed well in an area containing other mineral resources? OTHER, NATURAL GAS, OIL

Well Name: NAILED IT FED COM

Well Number: 234H

Is the proposed well in an area containing other mineral resources?  $O_T^{\perp}HER,NATURAL\ GAS,OIL$ 

Describe other minerals: Salt

Is the proposed well in a Helium production area? N Use Existing Well Pad? N

New surface disturbance?

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: Nailed Number: Slot 4

It Fed Com

Number of Legs: 1

Well Work Type: Drill

Well Class: HORIZONTAL

Well Type: CONVENTIONAL GAS WELL

**Describe Well Type:** 

Well sub-Type: INFILL

Describe sub-type:

Distance to town: 20 Miles

Distance to nearest well: 25 FT

Distance to lease line: 668 FT

Reservoir well spacing assigned acres Measurement: 288.4 Acres

Well plat:

Nailed\_234H\_C102\_GCP\_20191013083525.pdf

Well work start Date: 01/01/2020

**Duration: 30 DAYS** 

### Section 3 - Well Location Table

Survey Type: RECTANGULAR

**Describe Survey Type:** 

Datum: NAD83

Vertical Datum: NAVD88

Survey number: 11401

Reference Datum: GROUND LEVEL


				_																			
Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	ease Type	Lease Number	Elevation	MD	DVT	Will this well produce from this lease?				
SHL Leg #1	741	FSL	668	FEL	26S	30E	36	Lot 1	32.00219 71	- 103.8282 75	EDD Y	NEW	NEW MEXI CO	S	STATE	304 3	0	0	Y				
KOP Leg #1	24	FSL	331	FEL	268	30E	36	Lot 1	32.00023 39	- 103.8271 783	GRA NT	NEW MEXI CO	NEW MEXI CO	S	STATE	- 831 4:	114 23	113 57	Υ				
PPP Leg #1-1	24	FSL	331	FEL	26S	30E	36	Lot 1	32.00023 39	- 103.8271 783	GRA NT	NEW MEXI CO	— . ,	S	STATE	- 777 6	108 85	108 19	Υ				

Well Name: NAILED IT FED COM

Well Number: 234H

								ract							ē				produce se?
Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Numbe	Elevation	MD	TVD	Will this well pr from this lease
EXIT Leg #1	246 6	FSL	331	FEL	26S	30E	25	Aliquot NESE	32.01281 19	- 103.8272 004	EDD Y		NEW MEXI CO	F	NMNM 138850	- 890 2	163 30	119 45	Y
1	246 6	FSL	331	FEL	26S	30E		Aliquot NESE	32.01281 19	- 103.8272 004	EDD Y	ŀ	NEW MEXI CO	F	NMNM 138850	- 890 2	163 30	119 45	Y

### LOCATION & ELEVATION VERIFICATION MAP





LEASE NAME & WELL NO.:


NAILED IT FED COM 234H

SECTION 36 TWP 26-S RGE 30-E SURVEY N.M.P.M. EDDY STATE NM ELEVATION 3043' COUNTY \_\_\_ DESCRIPTION \_\_\_ 741' FSL & 668' FEL

LATITUDE N 32.0021971 LONGITUDE W 103.8282750

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.


ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.





1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140 <u>TELEPHONE:</u> (817) 744-7512 • FAX (817) 744-7554 2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705 TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743 WWW.TOPOGRAPHIC.COM

### EXHIBIT 2 VICINITY MAP





LEASE NAME & WELL NO .:

NAILED IT FED COM 234H

 SECTION
 36
 TWP
 26-S
 RGE
 30-E
 SURVEY
 N.M.P.M.

 COUNTY
 EDDY
 STATE
 NM

 DESCRIPTION
 741' FSL & 668' FEL

**DISTANCE & DIRECTION** 

FROM INT. OF US-285 & COUNTY RD 396, GO SOUTH ON US-285 ±12.6 MILES
THENCE EAST (LEFT) ON WHITEHORN RD. ±2.4 MILES, THENCE NORTH (LEFT) ON
LONGHORN RD. ±1.9 MILES, THENCE SOUTH (RIGHT) ON WHITEHORN RD. ±3.3
MILES, THENCE WEST (RIGHT) ON PROPOSED RD. ±3.0 MILES, THENCE EAST
(LEFT) ON STATE LINE RD. ±7.0 MILES, THENCE SOUTH (RIGHT) ON A LEASE RD.
± 0.2 MILES, THENCE WEST (RIGHT) ON PROPOSED RD. ±219 FEET TO A POINT
±219 FEET NORTHEAST OF THE LOCATION.

THIS EASEMENT/SERVITUDE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET.

TOPOGRAPHIC
LOYALTY INNOVATION LEGACY

SCALE: 1" =

10000'


1400 EVERMAN PARKWAY, Ste. 146 • FT. WORTH, TEXAS 76140

TELEPHONE: (817) 744-7512 • FAX (817) 744-7554

2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705

TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743

WWW.TOPOGRAPHIC.COM



# EXHIBIT 2B

SECTION 36, TOWNSHIP 26-S, RANGE 30-E, N.M.P.M.

EDDY COUNTY, NEW MEXICO DETAIL VIEW SCALE: 1" = 100" **EPROPOSED** ROAD - ±459' 3042.7 3046.7 PROPOSED SITE PAD NAILED IT FED COM 204H NAILED IT FED COM 224H NAILED IT FED COM 208H NAILED IT FED COM 236H NAILED IT FED COM 214H NAILED IT FED COM 244H NAILED IT FED COM 218H 3043.3 240 230' CENTER OF PAD NAILED IT FED COM 234H X=697862 Y=364899 LAT.: N 32.0021833 LONG.: W 103.8283879 3039.2 3046.6 **TOPSOIL** STORAGE TOWNSHIP LINE NAILED IT FED COM 234H LEASE NAME & WELL NO .: . 234H LATITUDE \_\_\_\_\_ N 32.0021971 234H LONGITUDE \_ W 103.8282750 OHN TREVOR CAPARA CENTER OF PAD IS 736' FSL & 703' FEL SCALE: 1" = 100' YOR 50' 100

John Trevor Carnegie, P.S. No. 11401

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM OF 1983, EAST ZONE, U.S. SURVEY FEET. ELEVATIONS USED ARE NAVD88, OBTAINED THROUGH AN OPUS SOLUTION.

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.



1400 EVERMAN PARKWAY, SIe. 146 • FT. WORTH, TEXAS 76140

TELEPHONE: (817) 744-7512 • FAX (817) 744-7554

2903 NORTH BIG SPRING • MIDAND, TEXAS 79705

TELEPHONE: (432) 682-1653 OR (800) 767-1653 • FAX (432) 682-1743

WWW.TOPOGRAPHIC.COM



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT

### Drilling Plan Data Report

APD ID: 10400048145

Submission Date: 10/21/2019

Highlighted data reflects the most

recent changes

Well Name: NAILED IT FED COM

Well Number: 234H

**Show Final Text** 

Well Type: CONVENTIONAL GAS WELL

Operator Name: TAP ROCK OPERATING LLC

Well Work Type: Drill

### Section 1 - Geologic Formations

Formation		Fig. 1	True Vertical	SECTION OF THE PROPERTY OF THE	The second secon		CONTROL OF THE SECOND
548920	Formation Name QUATERNARY	<u>%⊏ievation</u> 3043	© Deptn	© Depth. \$	Lithologies OTHER : None	Mineral Resources NONE	N N
548921	RUSTLER	2185	858	858	ANHYDRITE	OTHER : Salt	N
548922	SALADO	1633	1410	1410	SALT	OTHER : Salt	N
548923	BASE OF SALT	-406	3449	3460	SALT	OTHER : Salt	N
548924	LAMAR	-618	3661	3675	LIMESTONE	NONE	N
548925	BELL CANYON	-637	3680	3694	SANDSTONE	NATURAL GAS, OIL	N
548926	CHERRY CANYON	-1836	4879	4912	SANDSTONE	NATURAL GAS, OIL	N
548927	BRUSHY CANYON	-2789	5832	5880	SANDSTONE	NATURAL GAS, OIL	N
548928	BONE SPRING	-4538	7581	7647	LIMESTONE	NATURAL GAS, OIL	N
548929	BONE SPRING 1ST	-5483	8526	8592	SANDSTONE	NATURAL GAS, OIL	N
548930	BONE SPRING 2ND	-5833	8876	8942	SANDSTONE	NATURAL GAS, OIL	N
548931	BONE SPRING 3RD	-6716	9759	9825	SANDSTONE	NATURAL GAS, OIL	N
548932	WOLFCAMP	-7776	10819	10885	OTHER : Shale	NATURAL GAS, OIL	Y

### **Section 2 - Blowout Prevention**

Well Name: NAILED IT FED COM Well Number: 234H

Pressure Rating (PSI): 5M Rating Depth: 15000

**Equipment:** A 15,000 a 5,000 psi BOP stack consisting of 3 rams with 2 pipe rams, 1 blind ram, and 1 annular preventer will be used below surface casing to TD. See attachments for BOP and choke manifold diagrams. Also present will be an accumulator that meets the requirements of Onshore Order #2 for the pressure rating of the BOP stack. A rotating head will also be installed as needed. BOP will be inspected and operated as recommended in Onshore Order #2. A top drive check valve and sub equipped with a full opening valve sized to fit the drill pipe and collars will be available on the rig floor in the open position. The wellhead will be a multi-bowl speed head.

Requesting Variance? YES

Variance request: Tap Rock requests a variance to run a multi-bowl speed head for setting the Intermediate 1, Intermediate 2, and Production Strings. Tap Rock requests a variance to drill this well using a co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Tap Rock requests a variance to have the option of batch drilling this well with other wells on the same pad. In the event that this well is batch drilled, after drilling surface, 1st intermediate, and 2nd intermediate hole sections and cementing 2 nd intermediate casing, a 10M dry hole cap with bleed off valve will be installed. The rig will then walk to another well on the pad. When the rig returns to this well and BOPs are installed, the operator will perform a full BOP test. Tap Rock requests a variance to run 7-5/8 BTC casing inside 9-5/8 BTC casing will be less than the 0.422 stand off regulation. Through conversations with BLM representatives, Tap Rock has received approval for this design as long as the 7-5/8 flush casing was run throughout the entire 300 cement tie back section between 9-5/8 and 7-5/8 casing. Tap Rock requests approval to possibly utilize a spudder rig to drill and set casing for the surface interval on this well. The spudder rig will be possibly utilized in order to reduce cost and save time. The wellhead will be installed and tested as soon as the surface casing is cut off per the existing COAs. A blind flange with the same pressure rating as the wellhead will be installed on the well. Once the spudder rig is removed, Tap Rock will secure the wellhead area by placing a guard rail around the cellar. Pressure will be monitored and a means for intervention will be maintained while the drilling rig is not over the well. Spudder rig operations are expected to take 2-3 days per well. Three wells on the pad will have surface casing set by the spudder rig as a part of this operation. The BLM will be notified 24 hours prior to commencing spudder rig operations. Within 90 days of the departure of the spudder rig, drilling operations will recommence on these wells. This rig will have a BOP stack equal or greater to the pressure rating required in the COAs. The BLM will be notified 24 hours before the larger rig moves on the pre-set wells. Tap Rock will have supervision on the spudder rig to ensure compliance with all BLM and NMOCD regulations.

**Testing Procedure:** After surface casing is set and the BOP is nippled up, the BOP pressure tests will be made with a third party tester to 250 psi low, 5000 psi high, and the annular preventer will be tested to 2,500 psi. The BOP will be tested in this manner after nipple-up if any break of the stack occurs.

### **Choke Diagram Attachment:**

Nailed\_Choke\_032918\_20190927121008.pdf

### **BOP Diagram Attachment:**

BOP\_Diagram\_101619\_20191021105509.pdf

Se	Cti	on	3	- Cas	ınq

asing ID	String Type	ole Siz	sg Size	ondition	Standard	apered String	op Set MD	ottom Set MD	op Set TVD	ottom Set TVD	op Set MSL	Bottom Set MSL	alculated-casing	rad	/eight	Joint Type	ollapse SF	urst SF	oint SF Type	oint SF	ody SF Type	ody SF
Ö	\ <u>v</u>	エ   イ	Ö	ŭ	છ '	💾	<u> </u>	m		m	⊢	ď	ق ن ا	ပ	>	3	Ö	面	5	>	ď	m

Well Name: NAILED IT FED COM Well Number: 234H

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	950	0	950	3043	2093	950	J-58	54.5	BUTT	1.13	1.15	DRY	1.6	DRY	1.6
	INTERMED IATE	8.75	7.625	NEW	API	N	0	3425	0	3410	3009	-367	3425	P- 110	29.7	BUTT	1.13	1.15	DRY	1.6	DRY	1.6
	INTERMED IATE	12.2 5	9.625	NEW	API	N	0	3725	0	3710	3009	-667	3725	J-58	40	BUTT	1.13	1.15	DRY	1.6	DRY	1.6
	PRODUCTI ON	6.75	5.5	NEW	API	N	0	11100	0	11034	3009	-7991	1110	0 P- 110	20	OTHER - TXP	1.13	1.15	DRY	1.6	DRY	1.6
	INTERMED IATE	8.75	7.625	NEW	API	Υ	3425	11300	3410	11234	-367	-8191	7875	P- 110		OTHER - W- 513	1.13	1.15	DRY	1.6	DRY	1.6
6	PRODUCTI ON	6.75	5.0	NEW	API	Υ	11100	16330	11034	11945	-7991	-8902	5230	P- 110	18	OTHER - W- 521	1.13	1.13	DRY	1.6	DRY	1.6

Casir	ng Att	achn	nents
-------	--------	------	-------

Casing	ID:	1
--------	-----	---

String Type: SURFACE

**Inspection Document:** 

**Spec Document:** 

**Tapered String Spec:** 

Casing Design Assumptions and Worksheet(s):

Nailed\_Casing\_Design\_Assumptions\_20190927121048.pdf

Operator Name: TAP ROCK OPERATING LLC Well Name: NAILED IT FED COM	Well Number: 234H
Casing Attachments	
Casing ID: 2 String Type: INTERMEDIATE Inspection Document:	
Spec Document:	
Tapered String Spec:	
Casing Design Assumptions and Worksheet(s):  Nailed_Casing_Design_Assumptions_20190927121	131.pdf
Casing ID: 3 String Type: INTERMEDIATE Inspection Document:	
Spec Document:	
Tapered String Spec:	
Casing Design Assumptions and Worksheet(s):  Nailed_Casing_Design_Assumptions_20190927121	112.pdf
Casing ID: 4 String Type: PRODUCTION Inspection Document:	
Spec Document:	
Tapered String Spec:	
Casing Design Assumptions and Worksheet(s):  Nailed_Casing_Design_Assumptions_201909271212	
Nailed_5.5in_TXP_Casing_Spec_20190927121236.	PDF

Operator Name: Well Name: NAIL				TING L	LC		We	II Num	ber: 2	234H	
Casing Attachme	ents										
Casing ID:	5	S	String	Type:li	VTERN	/IEDIA	ΓE	-			-
Inspection D	ocume	nt:									
Spec Docum	ent:										
Tapered Strir	ng Spe	c:									
Nailed_	7.625in	_W513	_Casir								
Casing Desig	ın Assı	umptio	ns and								
Nailed_	Casing <sub>.</sub>	_Desig	n_Assı								
Casing ID:			String <sup>*</sup>								
Spec Docum	ent:										
Tapered Strir  Nailed_  Casing Desig  Nailed_	5in_W5	21_Ca	ns and								
	<del>- "</del>										
Section	4 - C	emen	<b>t</b>								
String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
PRODUCTION	Lead		0	0	0	0	0	0	0	None	0
PRODUCTION	Tail		1080 0	1633 0	453	1.71	14.2	775	25	Class H	Fluid Loss + Dispersant + Retarder + LCM
NTERMEDIATE	Lead		0	0	0	0	0	0	0	None	None
	1	<u> </u>	L	<u></u>	L	L		<u> </u>			
PRODUCTION	Lead		0	0	0	0	0	0	0	None	None

Well Name: NAILED IT FED COM

Well Number: 234H

String Type	Lead/Tail	Stage Tool Depth	Тор МБ	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	570	440	1.8	13.5	792	100	Class C	None
SURFACE	Tail		570	950	391	1.35	14.8	528	100	Class C	5% NCI + LCM
INTERMEDIATE	Lead		0	2980	706	2.18	12.7	1540	65	Class C	Bentonite + 1% CaCL2 + 8% NaCl + LCM
INTERMEDIATE	Tail		2980	3725	289	1.33	14.8	385	65	Class C	5% NaCI + LCM
INTERMEDIATE	Lead		3425	1030 0	325	2.87	11.5	932	35	TXI	Fluid Loss + Dispersant + Retarder + LCM
INTERMEDIATE	Tail		1030 0	1130 0	107	1.27	15	136	35	Class H	Fluid Loss + Dispersant + Retarder + LCM

### Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: All necessary mud products (e. g., barite, cedar bark) for weight addition and fluid loss control will always be on site. Mud program is subject to change due to hole conditions.

**Describe the mud monitoring system utilized:** Electronic Pason mud monitor system complying with Onshore Order 1 will be used.

### **Circulating Medium Table**

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	Н	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	950	OTHER : Fresh water spud mud	8.3	8.3						:	
950	3725	OTHER : Brine Water	10	10	-						
3725	1130 0	OTHER : Fresh water/cut brine	9	9							

Operator Name: TAP ROCK OPERATING LLC

Well Name: NAILED IT FED COM Well Number: 234H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	ЬН	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
1130 0	1633 0	OIL-BASED MUD	13	13							

# Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Electric Logging Program: No open-hole logs are planned at this time for the pilot hole.

GR will be collected while drilling through the MWD tools from 9.625 casing shoe to TD.

A 2-person mud logging program will be used from 9.625 casing shoe to TD.

CBL w/ CCL from as far as gravity will let it fall to TOC.

List of open and cased hole logs run in the well:

GAMMA RAY LOG, CEMENT BOND LOG,

Coring operation description for the well:

No DSTs or cores are planned at this time.

#### Section 7 - Pressure

**Anticipated Bottom Hole Pressure: 8070** 

Anticipated Surface Pressure: 5442

Anticipated Bottom Hole Temperature(F): 175

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geoharzards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

Nailed\_Slot4\_H2S\_Plan\_20190927121836.pdf

**Operator Name: TAP ROCK OPERATING LLC** 

Well Name: NAILED IT FED COM Well Number: 234H

## Section 8 - Other Information

## Proposed horizontal/directional/multi-lateral plan submission:


Nailed\_234H\_Horizontal\_Plan\_20190927121900.pdf

Other proposed operations facets description:

#### Other proposed operations facets attachment:

CoFlex\_Certs\_20190927121929.pdf
Nailed\_234H\_Anticollision\_Report\_20190927121955.pdf
Nailed\_234H\_Drill\_Plan\_v2\_020420\_20200205103440.pdf
Wellhead\_4T\_012720\_20200205103451.pdf

Other Variance attachment:





#### Hydrogen Sulfide Drilling

#### **Operations Plan**

#### Tap Rock Resources

## 1 H2S safety instructions to the following:

- Characteristics of H2S
- Physical effects and hazards
- Principal and operation of H2S detectors, warning system and briefing areas
- Evacuation procedures, routes and first aid
- Proper use of safety equipment & life support systems
- Essential personnel meeting medical evaluation criteria will receive additional training on the proper use of 30min pressure demand air packs

### 2 H2S Detection and Alarm Systems:

- H2S sensor/detectors to be located on the drilling rig floor, in the base of the sub structure / cellar area, on the mud pits in the shale shaker area. Additional H2S detectors may be placed as deemed necessary
- An audio alarm system will be installed on the derrick floor and in the doghouse

## 3 Windsocks and / Wind Streamers:

- Windsocks at mud pit area should be high enough to be visible
- Windsock on the rig floor and / top of doghouse should be high enough to be visible

## 4 Condition Flags and Signs:

- Warning sign on access road to location
- Flags to be displayed on sign at entrance to location
  - o Green Flag Normal Safe Operation Condition
  - Yellow Flag Potential Pressure and Danger
  - Red Flag Danger (H2S present in dangerous concentrations) Only H2S trained personnel admitted on location

#### 5 Well Control Equipment:

See Drilling Operations Plan Schematics

#### 6 Communication:

- While working under masks chalkboards will be used for communications
- Hand signals will be used where chalk board is inappropriate
- Two way radio will be used to communicate off location in case of emergency help is required.
   In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.



## 7 <u>Drilling Stem Testing:</u>

• No DST cores are planned at this time

8 Drilling contractor supervisor will be required to be familiar with the effects H2S has on tubulars good and other mechanical equipment

9 If H2S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H2S scavengers if necessary

## 11 Emergency Contacts

Emergency Conta	acts	
Carlsbad Police Department	575.887.7551	911
Carlsbad Medical Center	575.887.4100	911
Eddy County Fire Service	575.628.5450	911
Eddy County Sherriff	575.887.7551	911
Lea County Fire Service	575.391.2983	911
Lea County Sherriff	575.396.3611	911
Jal Police Department	575.395.2121	911
Jal Fire Department	575.395.2221	911
Tap Rock Resources	720.772.5090	

SECTION 36, TOWNSHIP 26-S, RANGE 30-E, N.M.P.M. **EDDY COUNTY, NEW MEXICO** PRIMARY safety briefing area DETAIL VIEW SCALE: 1" = 100' >150' from well head flare line (straight)
& flare >150' warning signs PROPOSED & windsock from well head highest ground ROAD - ±459 to the northeast 3046.7 PRIMARY egress PROPOSED windsocks on SITE PAD NAILED IT FED COM 204H trig floor & at NAILED IT FED COM 208H mud tanks NAILED IT FED COM 214H NAILED IT FED COM 218H 230 CENTER OF PAD X=697862 Y=364899 SECONDARY safety briefing area LAT.: N 32.0021833 >150' from well head LONG.: W 103.8283879 SECONDARY egress 3039 2 3046.6 NAILED IT FED COM 204H LEASE NAME & WELL NO .: prevailing wind W 103.8280170 N 32.0022660 blows from LATITUDE 204H LONGITUDE South CENTER OF PAD IS 736' FSL & 703' FEL

**EXHIBIT 2B** 

ALL BEARINGS, DISTANCES, AND COORDINATE VALUES CONTAINED HEREON ARE GRID BASED UPON THE NEW MEXICO COORDINATE SYSTEM, EAST ZONE OF THE NORTH AMERICAN DATUM 1983, U.S. SURVEY FEET

THIS PROPOSED PAD SITE LOCATION SHOWN HEREON HAS BEEN SURVEYED ON THE GROUND UNDER MY SUPERVISION AND PREPARED ACCORDING TO THE EVIDENCE FOUND AT THE TIME OF SURVEY, AND DATA PROVIDED BY TAP ROCK OPERATING, LLC. THIS CERTIFICATION IS MADE AND LIMITED TO THOSE PERSONS OR ENTITIES SHOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE. THIS SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY.




1400 EVERMAN PARKWAY, SIe. 146 • FT. WORTH, TEXAS 76140

TELEPHONE: (817) 744-7512 • FAX (817) 744-7554

2903 NORTH BIG SPRING • MIDLAND, TEXAS 79705

TELEPHONE: (432) 682-1653 OR (807) 767-1653 • FAX (432) 682-1743

WWW.TOPOGRAPHIC.COM



Nailed It Fed Com E2E2 Pad H2S Contingency Plan: Radius Map

Section 36, Township 26S, Range 30E Eddy County, New Mexico

## Center of Pad


1:27,000 0 0.25 0.5 1 Miles


> NAD 1983 New Mexico State Plane East FIPS 3001-Feet

> > PERMITS WEST.

Prepared by Permits West, Inc., August 21, 2019 for Tap Rock Operating, LLC







# **Tap Rock Resources**


Eddy Co, NM Nailed It Fed Com 234H

OH

Plan: Plan #1

# **Standard Planning Report**

04 September, 2019



Project Eddy Co, NM US State Plane 1983 Map System: System Datum: Mean Sea Level North American Datum 1983 Geo Datum: Map Zone: New Mexico Eastern Zone Site Nailed It Fed Com Site Position: Northing: 364,379.32 usft 32° 0' 2.836 N Latitude: From: Lat/Long Easting: 695,207.24 usft Longitude: 103° 50' 13.051 W Position Uncertainty: 2.0 usft Slot Radius: 13-3/16" Grid Convergence: 0.26° Well 234H **Well Position** +N/-S 525.1 usft 364,904.45 usft 32° 0' 7.910 N Northing: Latitude: +E/-W 2,689.5 usft Easting: 697,896.71 usft Longitude: 103° 49' 41.790 W Position Uncertainty 3,043.0 usft 2.0 usft Wellhead Elevation: **Ground Level:** Wellbore ОН Model Name Sample Date Dip Angle Declination Field Strength (nT) IGRF2015 6.82 59.79 47,555.27880435 9/3/2019 Design Plan #1 **Audit Notes:** 0.0 Version: Phase: **PLAN** Tie On Depth: Vertical Section: Depth From (TVD) +N/-S +E/-W Direction 4 (usft) (usft) (usft) 0.0 359.68 Plan Survey Tool Program Date 9/4/2019 Depth From Depth To (usft) Survey (Wellbore) Tool Name 0.0 16,329.7 Plan #1 (OH) MWD MWD - Standard

Plan Sections					Charles and the control of the contr			A STATE OF THE STA		
			V-ais-i			Deele-	D.:IId			
Measured Depth	√Inclination	Azimuth	Vertical Depth	+N/-S	+E/-W	Dogleg Rate	Build Rate	Turn Rate	TEO	
(usft)	(°)	(°)	(usft)	(usft)	(usft)	(°/100usft)	(°/100usft)	(°/100usft)	(P) 555	Target
		1//	( <del></del>	(uoit)					17 232	To section 2
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,966.7	10.00	154.60	2,963.3	-52.4	24.9	1.50	1.50	0.00	154.60	
6,866.7	10.00	154.60	6,804.0	-664.2	315.4	0.00	0.00	0.00	0.00	
7,533.3	0.00	0.00	7,467.3	-716.6	340.3	1.50	-1.50	0.00	180.00	
11,423.0	0.00	0.00	11,357.0	-716.6	340.3	0.00	0.00	0.00	0.00	
12,320.9	89.78	359.68	11,930.0	-145.8	337.1	10.00	10.00	0.00	359.68	
16,199.8	89.78	359.68	11,944.9	3,733.0	315.4	0.00	0.00	0.00	0.00 LT	P_234H
16,329.7	89.78	359.68	11,945.4	3,863.0	314.7	0.00	0.00	0.00	0.00 PE	BHL_234H

Planned Survey				5.4.3.T4.1		(A. 12/12/m.)			
								4	* <u>1</u> 2
Measured Depth	Inclination	Azimuth	Vertical Depth	+N/-S	1000000	rtical estion	Dogleg Rate	Build Rate	Turn Rate
(usft)	(°)	Azimatii (°)	(usft)	(usft)		usft)	(°/100usft)	(°/100ùsft)	(°/100usft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	. 0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
858.0	0.00	0.00	858.0	0.0	0.0	0.0	0.00	0.00	0.00
Rustler Anhy	drite								
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00
1,410.0	0.00	0.00	1,410.0	0.0	0.0	0.0	0.00	0.00	0.00
Top Salt	0.00	0.00			0.0	17111 1911 4/10000000			
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00
1			·						
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00
Start Build 1.	.50						The same was		
2,400.0	1.50	154.60	2,400.0	-1.2	0.6	-1.2	1.50	1.50	0.00
2,500.0	3.00	154.60	2,499.9	-4.7	2.2	-4.7	1.50	1.50	0.00
2,600.0	4.50	154.60	2,599.7	-10.6	5.1	-10.7	1.50	1.50	0.00
2,700.0	6.00	154.60	2,699.3	-18.9	9.0	-19.0	1.50	1.50	0.00
	7.50	454.00			44.0	20.0	4.50	4.50	0.00
2,800.0	7.50	154.60	2,798.6	-29.5 -42.5	14.0	-29.6 -42.6	1.50	1.50	0.00 0.00
2,900.0 2,966.7	9.00 10.00	154.60 154.60	2,897.5 2,963.3	-42.5 -52.4	20.2 24.9	-52.6	1.50 1.50	1.50 1.50	0.00
The second second second	and the second second		2,903.3	-32.4	24.5	-52.0	1.50	1.50	27 V 11, US 15 T
	hold at 2966.7 MI		0.000.4	57.0		22 11 12 18 18	2.00	0.00	0.00
3,000.0	10.00	154.60	2,996.1	-57.6	27.4	-57.8	0.00	0.00	0.00
3,100.0	10.00	154.60	3,094.6	-73.3	34.8	-73.5	0.00	0.00	0.00
3,200.0	10.00	154.60	3,193.1	-89.0	42.3	-89.3	0.00	0.00	0.00
3,300.0	10.00	154.60	3,291.6	-104.7	49.7	105.0	0.00	0.00	0.00
3,400.0	10.00	154.60	3,390.0	-120.4	57.2	-120.7	0.00	0.00	0.00
3,459.9	10.00	154.60	3,449.0	-129.8	61.6	-130.1	0.00	0.00	0.00
Base Salt									
3,500.0	10.00	154.60	3,488.5	-136.1	64.6	-136.4	0.00	0.00	0.00
3,600,0	10.00	154.60	3.587.0	-151.8	72.1	152.2	0.00	0.00	0.00
3,668.0	10.00	154.60	3,654.0	-162.4	77.1	162.9	0.00	0.00	0.00
Delaware Mo	•	101.00	3,004.0	102.7		. 52.5	2.00	5.00	
3,675.1	10.00	154.60	3,661.0	-163.6	77.7	-164.0	0.00	0.00	0.00
	10.00	134.00	5,001.0	- 105.0	11.1	104.0	0.00	0.00	0.00
Lamar	10.00	154.60	2 600 0	166.6	79.1	167.0	0.00	0.00	0.00
3,694.4	10.00	154.60	3,680.0	-166.6	79.1	167.0	0.00	0.00	0.00
Beil Canyon	40.00	454.00	2 605 5	407.5	70.5	107.0	0.00	0.00	0.00
3,700.0	10.00	154.60	3,685.5	-167.5	79.5	167.9	0.00	0.00	0.00
3,706.6	10.00	154.60	3,692.0	-168.5	80.0	168.9	0.00	0.00	0.00
Ramsey San	d								
3,800.0	10.00	154.60	3,784.0	-183.1	87.0	183.6	0.00	0.00	0.00
3,900.0	10.00	154.60	3,882.4	-198.8	94.4	199.3	0.00	0.00	0.00
4,000.0	10.00	154.60	3,980.9	-214.5	101.9	215.1	0.00	0.00	0.00
4,100.0	10.00	154.60	4,079.4	-230.2	109.3	230.8	0.00	0.00	0.00
									0.00
4,200.0	10.00	154.60	4,177.9	-245.9	116.8	246.5	0.00	0.00	
4,300.0	10.00	154.60	4,276.4	-261.6	124.2	-262.3	0.00	0.00	0.00
4,400.0	10.00	154.60	4,374.8	-277.3	131.7	278.0	0.00	0.00	0.00
4,500.0	10.00	154.60	4,473.3	-292.9	139.1 146.5	-293.7	0.00	0.00 0.00	0.00 0.00
4,600.0	10.00	154.60	4,571.8	-308.6	146.5	-309.4	0.00	0.00	0.00
4,700.0	10.00	154.60	4,670.3	-324.3	154.0	⟨-325.2	0.00	0.00	0.00
4,800.0	10.00	154.60	4,768.8	-340.0	161.4	-340.9	0.00	0.00	0.00
						1			

Planned S		and it are more than the property will be a seen	an in the second of the second	and the later programme and an all all and district		Angele and the second s	CHICAGO CONTROL CONTROL CONTROL		Contraction and Association	
1 1 1 1 1 1 1 1 1 1	urvey	A						A STATE OF THE STA		
NA.	leasured			Vertical	e de la companya de l		Vertical	Dogleg	Build	Turn
微磁性 医人名巴西伊尔	A. A. A. Market	Inclination	Azimuth	Depth	+N/-S	÷E/-W	Section	Rate	Rate	Rate
	(usft)	(°)	(°),	(usft)	(usft)	(usft)	(usft)	(°/100usft) 🦠 (	°/100usft) (	°/100usft)
	4,900.0	10.00	154.60	4,867.2	-355.7	168.9	-356.6	0.00	0.00	0.00
(	4,911.9 Cherry Canyor	10.00	154.60	4,879.0	-357.6	169.8	-358.5	0.00	0.00	0.00
	5,000.0	10.00	154.60	4,965.7	-371.4	176.3	-372.4	0.00	0.00	0.00
	5,100.0	10.00	154.60	5,064.2	-387.1	183.8	-388.1	0.00	0.00	0.00
	5,200.0 5,300.0	10.00 10.00	154.60 154.60	5,162.7 5,261.2	-402.7 -418.4	191.2 198.7	-403.8 -419.5	0.00 0.00	0.00 0.00	0.00 0.00
	5,400.0	10.00	154.60	5,359.7	-434.1	206.1	-435.3	0.00	0.00	0.00
	5,500.0	10.00	154.60	5,458.1	-449.8	213.6	-451.0	0.00	0.00	0.00
	5,600.0 5,700.0	10.00 10.00	154.60 154.60	5,556.6 5,655.1	-465.5 -481.2	221.0 228.5	-466.7 -482.4	0.00 0.00	0.00 0.00	0.00 0.00
	5,800.0	10.00	154.60	5,753.6	-496.9	235.9	-498.2	0.00	0.00	0.00
_	5,879.6	10.00	154.60	5,832.0	-509.4	241.9	-510.7	0.00	0.00	0.00
E	Brushy Canyo 5,900.0	n 10.00	154.60	5,852.1	-512.6	243.4	-513.9	0.00	0.00	0.00
	6,000.0	10.00	154.60	5,950.5	-528.2	250.8	-529.6	0.00	0.00	0.00
	6,100.0	10.00	154.60	6,049.0	-543.9	258.3	-545.4	0.00	0.00	0.00
	6,200.0 6,300.0	10.00 10.00	154.60 154.60	6,147.5 6,246.0	-559.6 -575.3	265.7 273.2	-561.1 -576.8	0.00 0.00	0.00 0.00	0.00 0.00
	6,400.0	10.00	154.60	6,344.5	-591.0	280.6	-592.5	0.00	0.00	0.00
	6,500.0	10.00	154.60	6,442.9	-606.7	288.1	-608.3	0.00	0.00	0.00
	6,600.0 6,700.0	10.00 10.00	154.60 154.60	6,541.4 6,639.9	-622.4 -638.0	295.5 303.0	-624.0 -639.7	0.00 0.00	0.00 0.00	0.00 0.00
	6,800.0	10.00	154.60	6,738.4	-653.7	310.4	-655.5	0.00	0.00	0.00
	6,866.7	10.00	154.60	6,804.0	-664.2	315.4	-665.9	0.00	0.00	0.00
S	Start Drop -1.5									
	6,900.0 7,000.0	9.50 8.00	154.60 154.60	6,836.9 6,935.7	-669.3 -683.0	317.8 324.3	-671.0 -684.8	1.50 1.50	-1.50 -1.50	0.00 0.00
	7,100.0	6.50	154.60	7,034.9	-694.4	329.7	-696.3	1.50	-1.50	0.00
	7,200.0 7,300.0	5.00 3.50	154.60 154.60	7,134.4 7,234.1	-703.5 -710.2	334.0 337.2	-705.3 -712.0	1.50 1.50	-1.50 -1.50	0.00 0.00
	7,400.0	2.00	154.60	7,334.0	-714.5	339.3	-716.4	1.50	-1.50	0.00
	7,500.0	0.50	154.60	7,434.0	-716.5	340.2	-718.4	1.50	-1.50	0.00
•	7,533.3 Start 3999 7 ba	0.00 old at 7533.3 MD	0.00	7,467.3	-716.6	340.3	-718.5	1.50	-1.50	0.00
	7,600.0	0.00	0.00	7,534.0	-716.6	340.3	-718.5	0.00	0.00	0.00
_	7,647.0	0.00	0.00	7,581.0	-716.6	340.3	-718.5 <sub>.</sub>	0.00	0.00	0.00
E	Bone Spring L		*	a a dia da de			. '		÷	
	7,700.0 7,765.0	0.00 0.00	0.00 0.00	7,634.0 7,699.0	-716.6 -716.6	340.3 340.3	-718.5 -718.5	0.00 0.00	0.00 0.00	0.00 0.00
ŧ	Upper Avalon			7,000.0	,	0.10.0	7.5.5	0.00	0.00	
	7,800.0	0.00	0.00	7,734.0	-716.6	340.3	-718.5	0.00	0.00	0.00
	7,900.0 8,000.0	0.00 0.00	0.00 0.00	7,834.0 7,934.0	-716.6 -716.6	340.3 340.3	-718.5 -718.5	0.00 0.00	0.00 0.00	0.00 0.00
	8,100.0	0.00	0.00	8,034.0	-716.6	340.3	-718.5	0.00	0.00	0.00
_	8,152.0	0.00	0.00	8,086.0	-716.6	340.3	-718.5	0.00	0.00	0.00
V	Middle Avalon 8,200.0	0.00	0.00	8,134.0	-716.6	340.3	-718.5	0.00	0.00	0.00
	8,300.0	0.00	0.00	8,234.0	-716.6	340.3	-718.5	0.00	0.00	0.00
1	8,376.0 Lower Avalon	0.00	0.00	8,310.0	-716.6	340.3	-718.5	0.00	0.00	0.00
	8,400.0	0.00	0.00	8,334.0	-716.6	340.3	-718.5	0.00	0.00	0.00
	8,500.0	0.00	0.00	8,434.0	-716.6	340.3	-718.5	0.00	0.00	0.00
	8,592.0	0.00	0.00	8,526.0	-716.6	340.3	-718.5	0.00	0.00	0.00
1	1st Bone Sprir 8,600.0	ng Sand 0.00	0.00	8,534.0	-716.6	340.3	-718.5	0.00	0.00	0.00
	8,700.0	0.00	0.00	8,634.0	-716.6	340.3	-718.5	0.00	0.00	0.00
	8,800.0	0.00	0.00	8,734.0	-716.6	340.3	-718.5	0.00	0.00	0.00
	8,900.0 8,942.0	0.00 0.00	0.00 0.00	8,834.0 8,876.0	-716.6 -716.6	340.3 340.3	-718.5 -718.5	0.00 0.00	0.00 0.00	0.00 0.00
2	2nd Bone Spri		gr.	3,0.0.0		5.0.0		5.50		
	9,000.0	0.00	0.00	8,934.0	-716.6	340.3	-718.5	0.00	0.00	0.00
	9,100.0	0.00 0.00	0.00 0.00	9,034.0 9,134.0	-716.6 -716.6	340.3 340.3	-718.5 -718.5	0.00 0.00	0.00 0.00	0.00 0.00
	9,200.0 9,227.0	0.00	0.00	9,134.0 9,161.0	-716.6 -716.6	340.3 340.3	-718.5	0.00	0.00	0.00

Planned Survey	Territory II	and the state of t	Money or an arrest description of the second					Will have been been been been been been been be	and the second control of the contro
Flatified Survey		46.5		r significant			X4		
Measured			Vertical	. <b>v</b>	100 300	/ertical	Dogleg	Build	Turn
Depth Inc (usft)	lination (°)	Azimuth (°)	Depth (usft)	+N/-S (usft)		Section (usft)	Rate (°/100usft)	Rate (°/100usft); ('	Rate '/100usft)
	2.3	3 sec. VI	and and a	(doit)	\usubseteq \underline{		(1,000	(1)	, Todasiy
2nd Bone Spring 9,300.0	0.00	0.00	9,234.0	-716.6	340.3	718.5	0.00	0.00	0.00
9,400.0	0.00	0.00	9,334.0	-716.6	340.3	718.5	0.00	0.00	0.00
9,500.0	0.00	0.00	9,434.0	-716.6	340.3	718.5	0.00	0.00	0.00
9,600.0 9,700.0	0.00 0.00	0.00	9,534.0	-716.6	340.3	718.5	0.00	0.00	0.00
9,800.0	0.00	0.00 0.00	9,634.0 9,734.0	-716.6 -716.6	340.3 340.3	-718.5 -718.5	0.00 0.00	0.00 0.00	0.00 0.00
9,825.0	0.00	0.00	9,759.0	-716.6	340.3	718.5	0.00	0.00	0.00
3rd Bone Spring 9,900.0	a comparable of the original control of the control of	0.00	0.004.0	·		7405			
	0.00	0.00	9,834.0	-716.6	340.3	718.5	0.00	0.00	0.00
10,000.0 10,100.0	0.00 0.00	0.00 0.00	9,934.0 10,034.0	-716.6 -716.6	340.3 340.3	718.5 718.5	0.00 0.00	0.00 0.00	0.00 0.00
10,200.0	0.00	0.00	10,134.0	-716.6	340.3	718.5	0.00	0.00	0.00
10,300.0	0.00	0.00	10,234.0	-716.6	340.3	718.5	0.00	0.00	0.00
10,400.0	0.00	0.00	10,334.0	-716.6	340.3	718.5	0.00	0.00	0.00
10,494.0	0.00	0.00	10,428.0	-716.6	340.3	718.5	0.00	0.00	0.00
3rd Bone Spring 10,500.0	Sand 0.00	0.00	10,434.0	-716.6	340.3	718.5	0.00	0.00	0.00
10,600.0	0.00	0.00	10,434.0	-716.6	340.3	718.5	0.00	0.00	0.00
10,700.0	0.00	0.00	10,634.0	-716.6	340.3	718.5	0.00	0.00	0.00
10,794.0 3rd BS W Sand ⊗	0.00	0.00	10,728.0	-716.6 	340.3	718.5	0.00	0.00	0.00
t	0000 p. (100 p. 100 <b>400 p.</b> (100 p. 100 p.		301					Arst Jakinit	*35
10,800.0 10,885.0	0.00 0.00	0.00 0.00	10,734.0 10,819.0	-716.6 -716.6	340.3 340.3	718.5 718.5	0.00 0.00	0.00 0.00	0.00 0.00
Wolfcamp A X Sa	PATANCAL STATE SEASONS CONTROL CONTROL	0.00	10,010.0	1.10.0	040.0	7 10.3	0.00	- 1000 - 127032 103	0.00
10,900.0	0.00	0.00	10,834.0	-716.6	340.3	718.5	0.00	0.00	0.00
11,000.0	0.00	0.00	10,934.0	-716.6	340.3	718.5	0.00	0.00	0.00
11,014.0 Wolfcamp A Y Sa	0.00	0.00	10,948.0	-716.6	340.3	718.5	0.00	0.00	0.00
	indrocoup become soins 1-7000 - 15			740.0	0.10.0				
11,100.0 11,101.0	0.00 0.00	0.00 0.00	11,034.0 11,035.0	-716.6 -716.6	340.3 340.3	718.5 718.5	0.00 0.00	0.00	0.00 0.00
Wolfcamp A Low	managagagaganaganagan serini -	1. N. 1844	11,000.0	7 10.0	540.5	7 10.5	~		0.00
11,200.0	0.00	0.00	11,134.0	-716.6	340.3	718.5	0.00	0.00	0.00
11,300.0	0.00	0.00	11,234.0	-716.6	340.3	718.5	0.00	0.00	0.00
Wolfcamp B 11,400.0	0.00	0.00	11,334.0	-716.6	340.3	718.5	0.00	0.00	0.00
11,423.0	0.00	0.00	11,357.0	-716.6	340.3	718.5	0.00	0.00	0.00
Start Build 10.00	الماء مهمههروسيات وماسي	0.00	11,337.0	-7 10.0	340.3	710.5	0.00	0.00	7.77 777 75
11,450.0	2.70	359.68	11,384.0	-716.0	340.3	717.9	10.00	10.00	0.00
11,500.0	7.70	359.68	11,433.8	-711.4	340.2	713.3	10.00	10.00	0.00
11,550.0 11,600.0	12.70 17.70	359.68 359.68	11,483.0 11,531.2	-702.6 -689.5	340.2 340.1	704.5	10.00	10.00	0.00
						691.4	10.00	10.00	0.00
11,650.0 11,683.9	22.70 26.09	359.68 359.68	11,578.1 11,609.0	-672.2 -658.2	340.0 339.9	-674.1 -660.1	10.00 10.00	10.00 10.00	0.00 0.00
Wolfcamp B1		+ 1 A S ( )	• • • • • • • • • • • • • • • • • • • •						7.77 (1997) 117 20 (1977) 117
11,700.0	27.70	359.68	11,623.3	-651.0	339.9	-652.8	10.00	10.00	0.00
11,750.0 11,800.0	32.70 37.70	359.68 359.68	11,666.5 11,707.4	-625.8 -597.0	339.8 339.6	-627.7 -598.9	10.00 10.00	10.00 10.00	0.00 0.00
11,850.0	42.70	359.68	11,745.6	-564.7	339.4	566.6	10.00	10.00	0.00
11,900.0	47.70	359.68	11,745.6	-564.7 -529.3	339.4	531.2	10.00	10.00	0.00
11,927.8	50.48	359.68	11,799.0	-508.3	339.1	-510.1	10.00	10.00	0.00
Wolfcamp C	50.00	350.00	44.040.0	400.0	222.2	400.0	40.00	40.00	
11,950.0 12,000.0	52.69 57.69	359.68 359.68	11,812.8 11,841.3	-490.9 -449.8	339.0 338.8	-492.8 -451.7	10.00 10.00	10.00 10.00	0.00 0.00
12,050.0	62.69	359.68							
12,050.0	62.69 65.10	359.68 359.68	11,866.2 11,876.7	-406.5 -384.9	338.5 338.4	-408.4 -386.8	10.00 10.00	10.00 10.00	0.00 0.00
FTP_234H	<b>u</b>	555,50	,	55 1.5	000.7	200.0	10.00	.0.00	5.55
12,100.0	67.69	359.68	11,887.1	-361.1	338.3	363.0	10.00	10.00	0.00
12,150.0	72.69	359.68	11,904.1	-314.1	338.0	316.0	10.00	10.00	0.00
12,200.0	77.69	359.68	11,916.8	-265.7	337.8	267.6	10.00	10.00	0.00
12,250.0 12,300.0	82.69 87.69	359.68 359.68	11,925.3 11,929.5	-216.5 -166.7	337.5 337.2	218.4 168.6	10.00 10.00	10.00 10.00	0.00 0.00
12,320.0	89.78	359.68	11,929.5	-166.7 -145.8	337.2 337.1	147.7	10.00	10.00	0.00
Start 3878.9 hold			•					-	
12,400.0	89.78	359.68	11,930.3	-66.7	336.6	-68.6	0.00	0.00	0.00
						r			

ned Survey						75 1 3200			
Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth	Inclination	Azimuth	Depth	+N/-S		Section	Rate	Rate	Rate
(usft)	(°),	(°)	(usft)	(usft)	(usft)	(usft)	(°/100usft)	30000000000000000000000000000000000000	°/100usft)
42.500.0						24.4	0.00	ASSE	0.00
12,500.0	89.78	359.68	11,930.7	33.3	336.1	31.4	0.00	0.00	0.00
12,600.0	89.78	359.68	11,931.1	133.3	335.5	131.4	0.00	0.00	0.00
12,700.0 12,800.0	89.78 89.78	359.68 359.68	11,931.5 11,931.8	233.3 333.3	335.0 334.4	231.4 331.4	0.00 0.00	0.00 0.00	0.00 0.00
12,900.0	89.78	359.68	11,932.2	433.3	333.8	431.4	0.00	0.00	0.00
13,000.0	89.78	359.68	11,932.6	533.3	333.3	531.4	0.00	0.00	0.00
13,100.0	89.78	359.68	11,933.0	633.3	332.7	631.4	0.00	0.00	0.00
13,200.0	89.78	359.68	11,933.4	733.3	332.7	731.4	0.00	0.00	0.00
13,300.0	89.78	359.68	11,933.4	833.3	331.6	831.4	0.00	0.00	0.00
13,400.0	89.78	359.68	11,934.1	933.3	331.1	931.4	0.00	0.00	0.00
13,500.0	89.78	359.68	11,934.5	1,033.3	330.5	1,031.4	0.00	0.00	0.00
13,600.0	89.78	359.68	11,934.9	1,133.3	329.9	1,131.4	0.00	0.00	0.00
13,700.0	89.78	359.68	11,935.3	1,233.3	329.4	1,231.4	0.00	0.00	0.00
13,800.0	89.78	359.68	11,935.7	1,333.3	328.8	1,331.4	0.00	0.00	0.00
13,900.0	89.78	359.68	11,936.1	1,433.3	328.3	1,431.4	0.00	0.00	0.00
14,000.0	89.78	359.68	11,936.4	1,533.3	327.7	1,531.4	0.00	0.00	0.00
14,100.0	89.78	359.68	11,936.8	1,633.3	327.1	1,631.4	0.00	0.00	0.00
14,200.0	89.78	359.68	11,937.2	1,733.3	326.6	1,731.4	0.00	0.00	0.00
14,300.0	89,78	359.68	11,937.6	1,833.3	326.0	1,831.4	0.00	0.00	0.00
14,400.0	89.78	359.68	11,938.0	1,933.3	325.5	1,931.4	0.00	0.00	0.00
14,500.0	89.78	359.68	11,938.4	2,033.3	324.9	2,031.4	0.00	0.00	0.00
14,600.0	89.78	359.68	11,938.8	2,133.3	324.4	2,131.4	0.00	0.00	0.00
14,700.0	89.78	359.68	11,939.1	2,233.3	323.8	2 231.4	0.00	0.00	0.00
14,800.0	89.78	359.68	11,939.5	2,333.3	323.2	2,331.4	0.00	0.00	0.00
14,900.0	89.78	359.68	11,939.9	2,433.2	322.7	2 431.4	0.00	0.00	0.00
15,000.0	89.78	359.68	11,940.3	2,533.2	322.1	2 531.4	0.00	0.00	0.00
15,100.0	89.78	359.68	11,940.7	2,633.2	321.6	2,631.4	0.00	0.00	0.00
15,200.0	89.78	359.68	11,941.1	2,733.2	321.0	2,731.4	0.00	0.00	0.00
15,300.0	89.78	359.68	11,941.4	2,833.2	320.4	2 831.4	0.00	0.00	0.00
15,400.0	89.78	359.68	11,941.8	2,933.2	319.9	2 931.4	0.00	0.00	0.00
15,500.0	89.78	359.68	11,942.2	3,033.2	319.3	3,031.4	0.00	0.00	0.00
15,600.0	89.78	359.68	11,942.6	3,133.2	318.8	3,131.4	0.00	0.00	0.00
15,700.0	89.78	359.68	11,943.0	3,233.2	318.2	3,231.4	0.00	0.00	0.00
15,800.0	89.78	359.68	11,943.4	3,333.2	317.7	3,331.4	0.00	0.00	0.00
15,900.0	89.78	359.68	11,943.7	3,433.2	317.1	3,431.4	0.00	0.00	0.00
16,000.0	89.78	359.68	11,944.1	3,533.2	316.5	3,531.4	0.00	0.00	0.00
16,100.0	89.78	359.68	11,944.5	3,633.2	316.0	3,631.4	0.00	0.00	0.00
16,199.8	89.78	359.68	11,944.9	3,733.0	315.4	3,731.2	0.00	0.00	0.00
	old at 16199.8 N				*				
16,300.0	89.78	359.68	11,945.3	3,833.2	314.9	3,831.4	0.00	0.00	0.00
16,329.7	89.78	359.68	11,945.4	3,863.0	314.7	3,861.1	0.00	0.00	0.00
TD at 16329.	7 - PBHL_234H	•				· 1800		. 1	

	Jip Angle Di	The state of the s	and the state of the state of	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude .	*Longitude.
FTP_234H - plan misses target cer - Point	0.00 nter by 58.7usf	0.01 t at 1207	11,930.0 4.0usft MD	-409.5 (11876.7 TVD,	338.8 -384.9 N, 338	364,494.96 .4 E)	698,235.50	32° 0' 3.842 N	103° 49' 37.878 W
LTP_234H - plan misses target cer - Point	0.00 nter by 0.3usft	0.00 at 16199.	11,945.0 8usft MD (1	3,733.0 11944.9 TVD, 3	315.7 733.0 N, 315.4	368,637.43 4 E)	698,212.45	32° 0' 44.837 N	103° 49' 37.920 W
PBHL_234H - plan misses target cer - Point	0.00 nter by 0.4usft	0.00 at 16329	11,945.5 .7usft MD (1	3,863.0 11945.4 TVD, 3	315.0 863.0 N, 314.	368,767.41 7 E)	698,211.74	32° 0′ 46.123 N	103° 49′ 37.921 W

Formations	eller market (1)	
, Méasured Depth (usft)	Vertical Depth (usft)	Dip Dip Direction Name Lithology (°) (°)
858.0	858.0	Rustler Anhydrite
1,410.0	1,410.0	Top Salt
3,459.9	3,449.0	Base Salt
3,668.0	3,654.0	Delaware Mountain Gp
3,675.1	3,661.0	Lamar
3,694.4	3,680.0	Bell Canyon
3,706.6	3,692.0	Ramsey Sand
4,911.9	4,879.0	Cherry Canyon
5,879.6	5,832.0	Brushy Canyon
7,647.0	7,581.0	Bone Spring Lime
7,765.0	7,699.0	Upper Avalon
8,152.0	8,086.0	Middle Avalon
8,376.0	8,310.0	Lower Avalon
8,592.0	8,526.0	1st Bone Spring Sand
8,942.0	8,876.0	2nd Bone Spring Carb
9,227.0	9,161.0	2nd Bone Spring Sand
9,825.0	9,759.0	3rd Bone Spring Carb
10,494.0	10,428.0	3rd Bone Spring Sand
10,794.0	10,728.0	3rd BS W Sand
10,885.0	10,819.0	Wolfcamp A X Sand
11,014.0	10,948.0	Wolfcamp A Y Sand
11,101.0	11,035.0	Wolfcamp A Lower
11,300.0	11,234.0	Wolfcamp B
11,683.9	11,609.0	Wolfcamp B1
11,927.8	11,799.0	Wolfcamp C

Plan Annotations				
Measured Depth	Vertical Depth	Local Coordin	3.0	
(usft)	(usft)	+N/-S (usft)	+E/-W (usft)	Comment
2.00	A COLUMN	(usit)	(usity	Comment
2,300.0	2,300.0	0.0	0.0	Start Build 1.50
2,966.7	2,963.3	-52.4	24.9	Start 3900.0 hold at 2966.7 MD
6,866.7	6,804.0	-664.2	315.4	Start Drop -1.50
7,533.3	7,467.3	-716.6	340.3	Start 3889.7 hold at 7533.3 MD
11,423.0	11,357.0	-716.6	340.3	Start Build 10.00
12,320.9	11,930.0	-145.8	337.1	Start 3878.9 hold at 12320.9 MD
16,199.8	11,944.9	3,733.0	315.4	Start 130.0 hold at 16199.8 MD
16,329.7	11,945.4	3,863.0	314.7	TD at 16329.7