

MAR 13 2008
OCD-ARTESIA **OCD-ARTESIA**
UNITED STATES

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No 1004-0137
Expires March 31, 2007

APPLICATION FOR PERMIT TO DRILL OR REENTER

Split Estate

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NM 100530
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator EOG Resources, Inc.		7. If Unit or CA Agreement, Name and No.
3a. Address P.O. Box 2267 Midland, TX 79702		8. Lease Name and Well No. CHAMA 3 FED 2H
3b. Phone No. (include area code) 432-686-3642		9. API Well No. 30-015-36208
4. Location of Well (Report location clearly and in accordance with any State requirements *) At surface 760' FSL & 360' FEL (U/L P) At proposed prod zone 760' FSL & 660' FWL (U/L M)		10. Field and Pool, or Exploratory Gopher (Wolfcamp)
14. Distance in miles and direction from nearest town or post office* Approx 5.0 miles SE of Hope, NM		11. Sec., T R. M. or Blk and Survey or Area Section 3, T18S-R23E, N.M.P.M.
15. Distance from proposed* location to nearest property or lease line, ft (Also to nearest drig unit line, if any) 660'	16. No of acres in lease 320	12. County or Parish Eddy
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft 1,120'	19. Proposed Depth 5,000' TVD; 8,512' TMD	13. State NM
21. Elevations (Show whether DF, KDB, RT, GL, etc.) GL 3,923'	22. Approximate date work will start* 02/10/2008	17. Spacing Unit dedicated to this well S/2 Sec 3, T18S-R23E, N.M.P.M.
23. Estimated duration 18		20. BLM/BIA Bond No. on file NM2308

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No 1, must be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above) |
| 2. A Drilling Plan | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office) | 6. Such other site specific information and/or plans as may be required by the BLM. |

25. Signature <i>Donny G. Glanton</i>	Name (Printed/Typed) Donny G. Glanton	Date 01/28/2008
---------------------------------------	--	--------------------

Title
Sr. Lease Operations ROW Representative

Approved by (Signature) <i>/s/ Don Peterson</i>	Name (Printed/Typed) /s/ Don Peterson	Date MAR - 7 2008
---	--	----------------------

Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE
------------------------	---------------------------------

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on page 2)

If earthen pits are used in association with the drilling of this well, an OCD pit permit must be obtained prior to pit construction.

SEE ATTACHED FOR CONDITIONS OF APPROVAL

APPROVAL SUBJECT TO GENERAL REQUIREMENTS AND SPECIAL STIPULATIONS ATTACHED

District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Avenue, Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-402
Revised October 12, 2005
Submit to Appropriate District Office
State Lease- 4 Copies
Fee Lease- 3 Copies

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-015- 36208	Pool Code 7766D	Pool Name Gopher; (Wolfcamp)
Property Code 36921	Property Name CHAMA 3 FED.	Well Number 2H
OGRID No. 7377	Operator Name EOG RESOURCES, INC.	Elevation 3923'

Surface Location


UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	3	18 SOUTH	23 EAST, N.M.P.M.		760'	SOUTH	360'	EAST	EDDY

Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	3	18 SOUTH	23 EAST, N.M.P.M.		760'	SOUTH	660'	WEST	EDDY

Dedicated Acres 320	Joint or Infill	Consolidation Code	Order No.
-------------------------------	-----------------	--------------------	-----------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Donny G. Glanton 8/6/07
Signature Date

Donny G. Glanton

Printed Name

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes or actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

Terry J. Ouel 7/20/2007
Date of Survey

Terry J. Ouel
Signature and Seal of Professional Surveyor

Certificate Number 15079

WO# 070530WL-b (JL)



Donny_Glanton@eogresourc
es.com

02/25/2008 11:53 AM

To tessa_cisneros@nm.blm.gov

cc

bcc

Subject Chama 3 Fed 2H

Tessa,

EOG cetifies that a written agreement has been entered into with the hereinbelow surface owner with respect to the subject well location:

Surface Owner: Crockett Ranch LLC
P.O. Box 265
Artesia, NM 88210
Att: Doepp Crockett 575-703-5972

Please adivse if you have any questions.

Thanks,
Donny G. Glanton

DRILLING PROGRAM

EOG RESOURCES, INC.
CHAMA 3 FED 2H
Eddy Co. NM

1. GEOLOGIC NAME OF SURFACE FORMATION:

Quaternary Alluvium 0-200

2. ESTIMATED TOPS OF IMPORTANT GEOLOGICAL MARKERS:

San Andres	480'
Glorieta	1,750'
Tubb	3,050'
Abo Shale	3,740'
Wolfcamp Pay	4,540'

3. ESTIMATED DEPTHS OF ANTICIPATED FRESH WATER, OIL OR GAS:

Quaternary Alluvium	0-200'	Fresh Water
San Andres	480'	Oil
Glorieta	1,750'	Oil/Gas
Tubb	3,050'	Oil/Gas
Abo/Wolfcamp Pay	4,540'	Gas

No other Formations are expected to give up oil, gas or fresh water in measurable quantities. Surface fresh water sands will be protected by setting 8.625" casing at 900' and circulating cement back to surface.

4. CASING PROGRAM-NEW

Hole	Interval	OD Csg	Weight	Grade	Conn.	<u>Collapse</u>	<u>Burst</u>	<u>Tension</u>
						<u>Design</u>	<u>Design</u>	<u>Design</u>
						<u>Factor</u>	<u>Factor</u>	<u>Factor</u>
see COA 12.250"	0-900'	8.625"	32#	J-55	LT&C	6.01	3.84	11.41
7.875"	0-8,512'	5.5"	17#	N-80	LT&C	2.81	1.25	3.38

Cementing Program:

8.625" Surface Casing:

Cement to surface, Lead: 345 sx 35:65 Poz C +
0.005 pps Static Free + 2% CaCl₂ + 5 pps LCM-1 +
0.005 gps FP-6L + 6% Bentonite, 12.5 ppg, 1.97
yield
Tail: 400 sx Prem Plus C + 0.125 pps CelloFlake +
0.005 FP-6L + 0.005 pps Static Free, 14.8 ppg, 1.33
yield

5.50" Production:

Cement to surface, Lead: 630 sx 50:50 Poz C +
0.005 pps Static Free + 0.125 pps CelloFlake +
0.005 gps FP-6L + 10% Bentonite, 11.8 ppg, 2.29
yield

DRILLING PROGRAM

EOG RESOURCES, INC.
CHAMA 3 FED 2H
Eddy Co. NM

Tail: 745 sx 50:50 Poz C + 2% Bentonite + 0.005
gps FP-6L + 0.005 pps Static Free + 5% NaCl +
0.05% R-3 + 0.2% CD-32 + 0.3% FL-52A, 14.2
ppg, 1.30 yield

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

(SEE EXHIBIT #1)

The blowout preventer equipment (BOP) shown in Exhibit #1 will consist of a double ram-type (5000 psi WP) preventer and an annular preventer (5000-psi WP). Units will be hydraulically operated and the ram-type will be equipped with blind rams on top and drill pipe rams on bottom. All BOP's and accessory equipment will be tested in accordance with Onshore Oil & Gas order No. 2. for a 3M system.

Pipe rams will be operationally checked each 24-hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets.

EOG Resources requests a variance to eliminate the stipulation requiring a BOPE test within 500' of the Wolfcamp. The Wolfcamp is not expected to be abnormally pressured (approx 1,800 lbs.) and the BOPE will be tested to the appropriate pressure requirements as per Onshore Order No. 2 prior to drilling out of the surface casing.

6 TYPES AND CHARACTERISTICS OF THE PROPOSED MUD SYSTEM:

The well will be drilled to TD with a combination of brine, cut brine, and polymer mud system. The applicable depths and properties of this system are as follows:

Depth	Type	Wt	Viscosity		Waterloss
		(PPG)	(sec)	(cc)	
0-900'	Fresh - Gel	8.6-8.8	28-34	N/c	
900'-4,059'	Cut Brine	8.8-9.2	28-34	N/c	
4,059'-8,512'	Polymer (Lateral)	9.0-9.4	40-45	10-25	

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept at the wellsite at all times.

7. AUXILIARY WELL CONTROL AND MONITORING EQUIPMENT:

(A) A kelly cock will be kept in the drill string at all times.

DRILLING PROGRAM

**EOG RESOURCES, INC.
CHAMA 3 FED 2H
Eddy Co. NM**

(B) A full opening drill pipe-stabbing valve (inside BOP) with proper drill pipe connections will be on the rig floor at all times.

8. LOGGING, TESTING AND CORING PROGRAM:

No open-hole logging is anticipated. The Chama 3 Fed #2H is intended to be drilled as a non-pilot hole well. Due to offset well control, the wellbore will be drilled to the kick-off point and then directionally controlled for the horizontal section without running open-hole logs. During the completion phase, a GR log will be run in the vertical portion and tied in with the GR log run acquired while directionally drilling the wellbore.

9. ABNORMAL CONDITIONS, PRESSURES, TEMPERATURES AND POTENTIAL HAZARDS:

The estimated bottom hole temperature (BHT) at TD is 125 degrees F with an estimated maximum bottom-hole pressure (BHP) at TD of 2000 psig. No hydrogen sulfide or other hazardous gases or fluids have been encountered, reported or are known to exist at this depth in this area. No major loss circulation zones have been reported in offsetting wells.

10. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:

The drilling operation should be finished in approximately one month. If the well is productive, an additional 30-60 days will be required for completion and testing before a decision is made to install permanent facilities.

Permit Information:

Well Name: Chama 3 Fed #2H

Location:

SL 760' FSL & 360' FEL, Section 3, T-18-S, R-23-E, Eddy Co., N.M.

BHL 760' FSL & 660' FWL, Section 3, T-18-S, R-23-E, Eddy Co., N.M.

Casing Program:

Casing	Setting Depth	Hole Size	Casing Size	Casing Weight	Casing Grade	Desired TOC
Surface	900'	12-1/4"	8-5/8"	32#	J-55	Surface
Production	8,512'	7-7/8"	5 1/2"	17#	N-80	Surface

Cement Program:

Depth	No. Sacks	Slurries:
900'	345	Lead: 35:65 Poz C + 6% Bentonite+ 0.005 gps FP-6L + 0.005 pps Static Free + 5 pps LCM-1 + 2% CaCl ₂
	400	Tail: Class C + 0.005 gps FP-6L + 0.005 pps Static Free + 0.125 pps CelloFlake
8,512'	630	Lead: 50:50 Poz:Class C + 0.005 gps FP-6L + 10% Bentonite + 0.005 pps Static Free + 0.125 pps CelloFlake
	745	Tail: 50:50 Poz:Class C + 2% Bentonite + 0.005 gps FP-6L + 0.005 pps Static Free + 5% NaCl + 0.3% FL-2A + 0.2% CD-32 + 0.05% R-3

Mud Program:

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0 – 900'	Fresh - Gel	8.6-8.8	28-34	N/c
900' – 4,300'	Cut Brine	8.8-9.2	28-34	N/c
4,300' – 5,000'	Cut Brine	8.8-9.2	28-34	10-15
4,059' – 8,512'	Polymer (Lateral)	9.0-9.4	40-45	10-20

EOG RESOURCES INC.

Planning Report

Database:	EDM	Local Co-ordinate Reference:	Well Chama 3 Fed #2H
Company:	EOG - Midland (3)	TVD Reference:	WELL @ 3942 00ft (Original Well Elev)
Project:	Thames	MD Reference:	WELL @ 3942 00ft (Original Well Elev)
Site:	Chama 3 Fed #2H	North Reference:	Grid
Well:	Chama 3 Fed #2H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Chama 3 Fed #2H		
Design:	Original Plan		

Project	Thames		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Ground Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site	Chama 3 Fed #2H		
Site Position:		Northing:	644,661 00ft
From:	Map	Easting:	396,154 70ft
Position Uncertainty:	0 00 ft	Slot Radius:	"
		Latitude:	32° 46' 18.514 N
		Longitude:	104° 40' 16.261 W
		Grid Convergence:	-0 18 °

Well	Chama 3 Fed #2H		
Well Position	+N/-S	0.00 ft	Northing:
	+E/-W	0.00 ft	Easting:
Position Uncertainty	0.00 ft		Wellhead Elevation:
			Latitude:
			Longitude:
			Ground Level:

Wellbore	Chama 3 Fed #2H				
Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
			(°)	(°)	(nT)
	IGRF2005	7/30/2007	8 57	60.57	49,158

Design	Original Plan			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.00
Vertical Section	Depth From (TVD)	+N/-S	+E/-W	Direction
	(ft)	(ft)	(ft)	(°)
	0.00	0 00	0 00	268.96

Plan Sections										
Measured	Inclination	Azimuth	Vertical	+N/-S	+E/-W	Dogleg	Build	Turn	TFO	Target
Depth	(°)	(°)	Depth	(ft)	(ft)	Rate	Rate	Rate	(°)	
(ft)			(ft)			(°/100ft)	(°/100ft)	(°/100ft)		
0.00	0 00	0 00	0.00	0.00	0 00	0.00	0.00	0.00	0.00	
4,059.00	0 00	0.00	4,059.00	0.00	0.00	0.00	0.00	0 00	0 00	
4,667.86	73.00	268.95	4,516 00	-6.20	-338.11	11.99	11.99	0.00	268.95	
4,837 62	90 00	268.95	4,541.00	-9.26	-505.36	10 01	10 01	0.00	0.00	
5,837 62	90 00	268.95	4,541.00	-27.59	-1,505 19	0.00	0 00	0.00	0 00	
5,904.16	92 00	268.96	4,539 84	-28.80	-1,571.70	3.00	3 00	0.01	0 23	
8,512 03	92.00	268.96	4,449.01	-76.20	-4,177.55	0.00	0.00	0.00	0.00	
8,512.17	92 00	268.96	4,449.00	-76.20	-4,177 70	3.00	2 67	1.37	0 00 BHL (Chama 3 Fed	

EOG RESOURCES INC.

Planning Report

Database: EDM
Company: EOG - Midland (3)
Project: Thames
Site: Chama 3 Fed #2H
Well: Chama 3 Fed #2H
Wellbore: Chama 3 Fed #2H
Design: Original Plan

Local Co-ordinate Reference: Well Chama 3 Fed #2H
TVD Reference: WELL @ 3942.00ft (Original Well Elev)
MD Reference: WELL @ 3942.00ft (Original Well Elev)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N-S (ft)	+E-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00
4,059.00	0.00	0.00	4,059.00	0.00	0.00	0.00	0.00	0.00	0.00
4,100.00	4.92	268.95	4,099.95	-0.03	-1.76	1.76	11.99	11.99	0.00
4,200.00	16.91	268.95	4,197.96	-0.38	-20.65	20.65	11.99	11.99	0.00
4,300.00	28.89	268.95	4,289.91	-1.09	-59.48	59.49	11.99	11.99	0.00
4,400.00	40.88	268.95	4,371.79	-2.14	-116.57	116.59	11.99	11.99	0.00
4,500.00	52.87	268.95	4,440.02	-3.47	-189.41	189.45	11.99	11.99	0.00
4,600.00	64.86	268.95	4,491.62	-5.04	-274.84	274.89	11.99	11.99	0.00
4,667.86	73.00	268.95	4,516.00	-6.20	-338.11	338.16	11.99	11.99	0.00
4,700.00	76.22	268.95	4,524.53	-6.76	-369.08	369.14	10.01	10.01	0.00
4,800.00	86.23	268.95	4,539.76	-8.57	-467.77	467.85	10.01	10.01	0.00
4,837.62	90.00	268.95	4,541.00	-9.26	-505.36	505.44	10.01	10.01	0.00
4,900.00	90.00	268.95	4,541.00	-10.41	-567.72	567.82	0.00	0.00	0.00
5,000.00	90.00	268.95	4,541.00	-12.24	-667.71	667.82	0.00	0.00	0.00

EOG RESOURCES INC.

Planning Report

Database: EDM
Company: EOG - Midland (3)
Project: Thames
Site: Chama 3 Fed #2H
Well: Chama 3 Fed #2H
Wellbore: Chama 3 Fed #2H
Design: Original Plan

Local Co-ordinate Reference: Well Chama 3 Fed #2H
TVD Reference: WELL @ 3942 00ft (Original Well Elev)
MD Reference: WELL @ 3942 00ft (Original Well Elev)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,100.00	90.00	268.95	4,541.00	-14.07	-767.69	767.82	0.00	0.00	0.00
5,200.00	90.00	268.95	4,541.00	-15.90	-867.67	867.82	0.00	0.00	0.00
5,300.00	90.00	268.95	4,541.00	-17.74	-967.66	967.82	0.00	0.00	0.00
5,400.00	90.00	268.95	4,541.00	-19.57	-1,067.64	1,067.82	0.00	0.00	0.00
5,500.00	90.00	268.95	4,541.00	-21.40	-1,167.62	1,167.82	0.00	0.00	0.00
5,600.00	90.00	268.95	4,541.00	-23.23	-1,267.61	1,267.82	0.00	0.00	0.00
5,700.00	90.00	268.95	4,541.00	-25.07	-1,367.59	1,367.82	0.00	0.00	0.00
5,800.00	90.00	268.95	4,541.00	-26.90	-1,467.57	1,467.82	0.00	0.00	0.00
5,837.62	90.00	268.95	4,541.00	-27.59	-1,505.19	1,505.44	0.00	0.00	0.00
5,900.00	91.87	268.96	4,539.98	-28.73	-1,567.54	1,567.81	3.00	3.00	0.01
5,904.16	92.00	268.96	4,539.84	-28.80	-1,571.70	1,571.96	3.00	3.00	0.01
6,000.00	92.00	268.96	4,536.50	-30.54	-1,667.47	1,667.75	0.00	0.00	0.00
6,100.00	92.00	268.96	4,533.02	-32.36	-1,767.39	1,767.69	0.00	0.00	0.00
6,200.00	92.00	268.96	4,529.54	-34.18	-1,867.31	1,867.63	0.00	0.00	0.00
6,300.00	92.00	268.96	4,526.05	-36.00	-1,967.24	1,967.56	0.00	0.00	0.00
6,400.00	92.00	268.96	4,522.57	-37.81	-2,067.16	2,067.50	0.00	0.00	0.00
6,500.00	92.00	268.96	4,519.09	-39.63	-2,167.08	2,167.44	0.00	0.00	0.00
6,600.00	92.00	268.96	4,515.60	-41.45	-2,267.00	2,267.38	0.00	0.00	0.00
6,700.00	92.00	268.96	4,512.12	-43.27	-2,366.93	2,367.32	0.00	0.00	0.00
6,800.00	92.00	268.96	4,508.64	-45.08	-2,466.85	2,467.26	0.00	0.00	0.00
6,900.00	92.00	268.96	4,505.15	-46.90	-2,566.77	2,567.20	0.00	0.00	0.00
7,000.00	92.00	268.96	4,501.67	-48.72	-2,666.70	2,667.14	0.00	0.00	0.00
7,100.00	92.00	268.96	4,498.19	-50.53	-2,766.62	2,767.08	0.00	0.00	0.00
7,200.00	92.00	268.96	4,494.70	-52.35	-2,866.54	2,867.02	0.00	0.00	0.00
7,300.00	92.00	268.96	4,491.22	-54.17	-2,966.46	2,966.96	0.00	0.00	0.00
7,400.00	92.00	268.96	4,487.74	-55.99	-3,066.39	3,066.90	0.00	0.00	0.00
7,500.00	92.00	268.96	4,484.26	-57.80	-3,166.31	3,166.84	0.00	0.00	0.00
7,600.00	92.00	268.96	4,480.77	-59.62	-3,266.23	3,266.78	0.00	0.00	0.00
7,700.00	92.00	268.96	4,477.29	-61.44	-3,366.15	3,366.72	0.00	0.00	0.00
7,800.00	92.00	268.96	4,473.81	-63.26	-3,466.08	3,466.65	0.00	0.00	0.00
7,900.00	92.00	268.96	4,470.32	-65.07	-3,566.00	3,566.59	0.00	0.00	0.00
8,000.00	92.00	268.96	4,466.84	-66.89	-3,665.92	3,666.53	0.00	0.00	0.00
8,100.00	92.00	268.96	4,463.36	-68.71	-3,765.85	3,766.47	0.00	0.00	0.00
8,200.00	92.00	268.96	4,459.87	-70.53	-3,865.77	3,866.41	0.00	0.00	0.00
8,300.00	92.00	268.96	4,456.39	-72.34	-3,965.69	3,966.35	0.00	0.00	0.00
8,400.00	92.00	268.96	4,452.91	-74.16	-4,065.61	4,066.29	0.00	0.00	0.00
8,500.00	92.00	268.96	4,449.42	-75.98	-4,165.54	4,166.23	0.00	0.00	0.00
8,512.03	92.00	268.96	4,449.01	-76.20	-4,177.55	4,178.25	0.00	0.00	0.00
8,512.17	92.00	268.96	4,449.00	-76.20	-4,177.70	4,178.39	3.00	2.67	1.37

BHL (Chama 3 Fed #2H)

Targets

Target Name



hit/miss target	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
Shape									
BHL (Chama 3 Fed #: - plan hits target - Point	0.00	0.00	4,449.00	-76.20	-4,177.70	644,584.80	391,977.00	32° 46' 17.626 N	104° 41' 5.188 W

WELL DETAILS: Chama 3 Fed #2H

+N/-S	+E/-W	Northing	Easting	Ground Level:	3923.00	Latitude	Longitude	Slot
0.00	0.00	644661.00	396154.70			32° 46' 18.514 N	104° 40' 16.261 W	

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFac	Target	Sec
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2	4059.00	0.00	0.00	4059.00	0.00	0.00	0.00	0.00	0.00	
3	4667.86	73.00	268.95	4516.00	-6.20	-338.11	11.99	268.95	338.16	
4	4837.62	90.00	268.95	4541.00	-9.26	-505.36	10.01	0.00	505.44	
5	5837.62	90.00	268.95	4541.00	-27.59	-1505.19	0.00	0.00	1505.44	
6	5904.16	92.00	268.96	4539.84	-28.80	-1571.70	3.00	0.23	1571.96	
7	8512.03	92.00	268.96	4449.01	-76.20	-4177.55	0.00	0.00	4178.25	
8	8512.17	92.00	268.96	4449.00	-76.20	-4177.76	0.00	0.00	4178.39	





EOG Resources, Inc.
P.O. Box 2267
Midland, TX 79702
(432) 686-3600

August 1, 2007

State of New Mexico Energy, Minerals and Natural Resources
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

To Whom It May Concern:

I am writing to request a waiver for the inclusion of an H₂S Contingency Plan for the Chama 3 Fed #2H. The current plan is to complete this well in the Wolfcamp, which is sweet, and I do not anticipate encountering any H₂S bearing formations during drilling operations.

Sincerely,



Jason LaGrega
Drilling Engineer

Chama 3 Fed 2H

5
4





Exhibit 5

WELL NAME: Chama 3 Fed 2H

S

4



Items 1-4: Drilling Trailers

| |
| |
| |
| |

Production Facility Layout

Chama 3 Fed 2H

S

4

Pit

O

Comment: No Facility on well pad. A Flowline will be constructed to the Chama 3 Fed 1H well pad where a separator and meter will be set. The Chama 3 Fed 2H will share Tank of the Chama 3 Fed 1H.

"Not To Scale"

DRILLING PROGRAM

**EOG RESOURCES, INC.
CHAMA 3 FED 2H
Eddy Co. NM**


ATTACHMENT TO EXHIBIT #1


1. Wear ring to be properly installed in head.
2. Blow out preventer and all fittings must be in good condition, 3000 psi W.P. minimum. Exhibit #1.
3. All fittings to be flanged
4. Safety valve must be available on rig floor at all times with proper connections, valve to be full bore 3000 psi W.P. minimum.
5. All choke and fill lines to be securely anchored especially ends of choke lines.
6. Equipment through which bit must pass shall be at least as large as the diameter of the casing being drilled through.
7. Kelly cock on kelly.
8. Extension wrenches and hand wheels to be properly installed.
9. Blow out preventer control to be located as close to driller's position as feasible.
10. Blow out preventer closing equipment to include minimum 40-gallon accumulator, two independent sources of pump power on each closing unit installation, and meet all API specifications.

EXHIBIT 1

EOG Resources, Inc.

Chama 3 Fed. 2H





5M CHOKE MANIFOLD EQUIPMENT - CONFIGURATION OF CHOKES MAY VARY

Although not required for any of the choke manifold systems, buffer tanks are sometimes installed downstream of the choke assemblies for the purpose of manifolding the bleed lines together. When buffer tanks are employed, valves shall be installed upstream to isolate a failure or malfunction without interrupting flow control. Though not shown on 2M, 3M, 10M, OR 15M drawings, it would also be applicable to those situations.

[54 FR 39528, Sept. 27, 1989]

DRILLING PROGRAM

**EOG RESOURCES, INC.
CHAMA 3 FED 2H
Eddy Co. NM**

SURFACE USE PLAN OF OPERATION

**SHL: 760' FSL & 360' FEL, Unit P, Section 3, T18S-R23E, N.M.P.M., Eddy, NM
BHL: 760' FSL & 660' FWL, Unit M, Section 3, T18S-R23E, N.M.P.M., Eddy, NM**

1. EXISTING ROADS:

- a. The well site and elevation plat for the proposed well are reflected on the well site layout; Form C-102. The well was staked by Terry Asel, RPL 15079.
- b. All roads into the location are depicted on Exhibit 2 & 2a.
- c. Directions to Locations: Beginning in Artesia, NM, Go west on Hwy 82 for approx 14.9 miles, Turn south on CR 8 (Santa Road) for 2.1 miles, Turn left on lease road for 0.8 miles, turn right on lease road for 1.0 miles, turn right on lease road for 0.1 miles to staked new road, go south 0.8 miles to location.

2. NEW OR RECONSTRUCTED ACCESS ROAD:

- a. The well site layout, Exhibit 2 shows the layout. The proposed access road, begins on paved CR 8 (Santa Road) and trends ESE to the N Side of the well pad. (See 1c above for driving directions).
- b. The maximum width of the road will be 15'. It will be crowned and made of 6" of rolled and compacted caliche. Water will be deflected, as necessary, to avoid accumulation and prevent soil erosion.
- c. Surface material will be native caliche. This material will be obtained from a BLM approved pit nearest in proximity to the location. The average grade will be approximately 1%.
- d. Cattleguards will be set where fences are cut. No turnouts are planned.

3. LOCATION OF EXISTING WELLS:

Exhibit #3 shows all existing wells within a one-mile radius of this well.

4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

- a. In the event the well is found to be productive, the Chama 3 Fed 1H tank battery would be utilized and the necessary production equipment presently exists at the well site. See Production Facilities Layout diagram.
- b. As a proposed gas well, we do not anticipate the need for electrical service.
- c. All flow lines will adhere to API standards:
- d. As a proposed gas well, we do not anticipate the need for electrical service.
- e. If the well is productive, rehabilitation plans are as follows:

DRILLING PROGRAM

EOG RESOURCES, INC.

CHAMA 3 FED 2H

Eddy Co. NM

- i. The reserve pit will be back filled after the contents of the pit are dry (within 120 days after completion, weather permitting).
- ii. The original topsoil from the well site will be returned to the location. The drill site will be contoured as close as possible to the original state.

5. LOCATION AND TYPE OF WATER SUPPLY:

This location will be drilled using a combination of water mud systems (outlined in the drilling program). The water will be obtained from commercial water stations in the area and hauled to location by transport truck using existing and proposed roads shown in Exhibit 2. On occasion, water will be obtained from existing water wells. In these cases where a poly pipeline is used to transport water for drilling purposes, proper authorizations will be secured. If poly pipeline is used to transport fresh water to the location, proper authorization will be secured by the contractor.

6. CONSTRUCTION MATERIALS

All caliche utilized for the drilling pad and proposed access road will be obtained from an existing BLM approved pit or from prevailing deposits found under the location. All roads will be constructed of rolled and compacted caliche. Will use BLM recommended use of extra caliche from other locations close by roads, if available.

7. METHODS OF HANDLING WASTE MATERIALS

- a. Drill cuttings will be disposed of in the reserve pit.
- b. All trash, junk, and other waste material will be contained in trash cages or trash bins to prevent scattering. When a job is completed, all contents will be removed and disposed of in an approved landfill.
- c. The supplier, including broken sacks, will pick up salts remaining after completion of well.
- d. If necessary, a porto-john will be provided for the rig crews. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete.
- e. Remaining drilling fluids will be allowed to evaporate in the reserve pits until the pits are dry enough to be broken for further drying. If the drilling fluids do not evaporate in a reasonable time they will be hauled off by transports to a state approved disposal site. Later pits will be broken out to speed dry. Water produced during completion will be put in reserve pits. Oil and condensate produced will be put in a storage tank and sold.
- f. Disposal of fluids to be transported by the following companies:
 - i. RGB TRUCKING

DRILLING PROGRAM

EOG RESOURCES, INC.
CHAMA 3 FED 2H
Eddy Co. NM

- ii. LOBO TRUCKING
- iii. I & W TRUCKING
- iv. CRANE HOT OIL & TRANSPORT

8. ANCILLARY FACILITIES:

- a. No airstrip, campsite, or other facilities will be built.

9. WELL SITE LAYOUT:

- a. Exhibit 4 shows the proposed well site layout with dimensions of the pad layout.
- b. Exhibit 5 shows proposed location of reserve and sump pits and living facilities.
- c. Mud pits in the active circulating system will be steel pits and the reserve pits will be lined.
- d. If needed, the reserve pit is to be lined with polyethylene. The pit liner will be 12 mils thick. Pit liner will extend a minimum of two feet (2') over the reserve pit's dykes where the liner will be anchored down.
- e. The reserve pit will be fenced on three sides with four strands of barbed wire during drilling and completion phases. The fourth side will be fenced after all drilling operations have ceased. If the well is a producer, the reserve pit fence will be torn down after the pit contents have dried. The reserve pit and those areas of the location not essential to production facilities will be reclaimed and seeded per BLM requirements.

10. PLANS FOR SURFACE RECLAMATION:

- a. After concluding the drilling and/or completion operations, if the well is found non-commercial, the caliche will be removed from the pad and transported to the original caliche pit or used for other drilling locations. The road will be reclaimed as directed by the BLM. The reserve pit area will be broken out and leveled after drying to a condition where these are feasible. The original top soil will again be returned to the pad and contoured, as close as possible, to the original topography. The pit will be closed per OCD compliance regulations.
- b. The pit lining will be buried or hauled away in order to return the location and road to their pristine nature. All pits will be filled and the location leveled, weather permitting, within 120 days after abandonment.

DRILLING PROGRAM

EOG RESOURCES, INC.
CHAMA 3 FED 2H
Eddy Co. NM

- c. The location and road will be rehabilitated as recommended by the BLM.
- d. The reserve pit will be fenced on three side throughout drilling operations. After the rotary rig is removed, the reserve pit will be fenced on the fourth side to preclude endangering wildlife. The fencing will be in place until the pit is reclaimed.
- e. If the well is deemed commercially productive, the reserve pit will be restored as described in 10(A) within 120 days subsequent to the completion date. Caliche from areas of the pad site not required for operations will be reclaimed. The original top soil will be returned to the area of the drill pad not necessary to operate the well. These unused areas of the drill pad will be contoured, as close as possible, to match the original topography.

11. SURFACE OWNERSHIP

The surface ownership is owned by the Crockett Trust. The surface is multiple use with the primary uses of the region for the grazing of livestock and the production of oil and gas. The proposed road routes and surface location will be restored as directed by the BLM.

EOG and the surface owner have entered into a written surface use agreement

Fee Surface Owner:

Crockett Trust
Doepp Crockett
575.703.5972

12. OTHER INFORMATION:

- a. The area surrounding the well is grassland. The topsoil is sandy & rocky in nature. The vegetation is moderately sparse with native prairie grass and yucca cactus. No wildlife was observed but it is likely that deer, rabbits, coyotes, rodents and birds transverse the area.
- b. There are not dwellings within 2 miles of location.
- c. There is no permanent or live water within 1 miles of the location.
- d. A Cutural Resources Examination has been performed by Danny Boone. Acreage recorded at the BLM office in Carlsbad, New Mexico.

DRILLING PROGRAM

**EOG RESOURCES, INC.
CHAMA 3 FED 2H
Eddy Co. NM**

13. BOND COVERAGE:

a. Bond Coverage is Nationwide; Bond No. NM 2308

COMPANY REPRESENTATIVES:

Representatives responsible for ensuring compliance of the surface use plan are listed below:

Permitting & Land

Mr. Donny G. Glanton
Senior Lease Operations ROW Representative
EOG Resources, Inc.
P.O. Box 2267
Midland, TX 79702
(432) 686-3642 Office
(432) 770-0602 Cell

Drilling

Mr. Jason LaGrega
Division Drilling Engineer
EOG Resources, Inc.
P.O. Box 2267
Midland, TX 79702
(432) 686-3633 Office
(432) 894-1217 Cell

Operations

Mr. Howard Kemp
Production Manager
EOG Resources, Inc.
P.O. Box 2267
Midland, TX 79702
(432) 686-3704 Office
(432) 634-1001 Cell

OPERATOR CERTIFICATION

I certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal Laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true, and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 28th day of January 2008.

Name: Donny G. Glanton

Position: Sr. Lease Operations ROW Representative

Address: P.O. Box 2267 Midland, TX 79705

Telephone: 432-686-3642

Email: donny_glanton@eogresources.com

Signed: _____





EXHIBIT 2




I, TERRY J. ASE, NEW MEXICO PROFESSIONAL SURVEYOR NO. 15079, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND MEETS THE "MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO" AS ADOPTED BY THE NEW MEXICO STATE BOARD OF REGISTRATION FOR PROFESSIONAL ENGINEERS AND SURVEYORS.

Asel Surveying
& Consulting

DRIVING DIRECTIONS:
BEGINNING IN ARTESIA, GO WEST ON HWY. 82 FOR
14.9 MILES, TURN SOUTH ON EDDY COUNTY ROAD
#8 (SANTA ROAD) FOR 2.1 MILES, TURN LEFT ON
LEASE ROAD FOR 0.8 MILES, TURN RIGHT ON
LEASE ROAD FOR 1.0 MILES, TURN RIGHT ON
LEASE ROAD FOR 0.1 MILES TO STAKED NEW ROAD,
GO SOUTH 0.8 MILES TO LOCATION.


⊙ - DENOTES FOUND MONUMENT AS NOTED



CHAMA 3 FED. #2H
IN SECTION 3, TOWNSHIP 18 SOUTH,
RANGE 23 EAST, N.M.P.M., EDDY COUNTY,
NEW MEXICO

Survey Date: 07/05/30	Sheet 1 of 1 Sheets	
W.O. Number: 070530WL-a	Drawn By: JL	Rev:
Date: 07/19/07	070530WL-a	Scale: 1"=1000'

SECTION 3, TOWNSHIP 18 SOUTH, RANGE 23 EAST, N.M.P.M.,
EDDY COUNTY Exhibit 2a Page 1 of 2 NEW MEXICO



DESCRIPTION

PROPOSED PIPELINE

A STRIP OF LAND 30.0 FEET WIDE AND 4176.9 FEET OR 253.15 RODS IN LENGTH IN SECTION 3, TOWNSHIP 18 SOUTH, RANGE 23 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

PROPOSED ROAD A

A STRIP OF LAND 30.0 FEET WIDE AND 282.4 FEET OR 17.12 RODS IN LENGTH IN SECTION 3, TOWNSHIP 18 SOUTH, RANGE 23 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

PROPOSED ROAD B

A STRIP OF LAND 30.0 FEET WIDE AND 2275.4 FEET OR 137.90 RODS IN LENGTH IN SECTION 3, TOWNSHIP 18 SOUTH, RANGE 23 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.




SURVEYORS CERTIFICATE

I, TERRY J. ASEL, NEW MEXICO PROFESSIONAL SURVEYOR NO. 15079, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND MEETS THE "MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO" AS ADOPTED BY THE NEW MEXICO STATE BOARD OF REGISTRATION FOR PROFESSIONAL ENGINEERS AND SURVEYORS.

Terry J. Asel 11/16/2007
Terry J. Asel N.M. R.P.S. No. 15079

Asel Surveying

P.O. BOX 393 - 310 W. TAYLOR
HOBBS, NEW MEXICO - 505-393-9146



LEGEND

- ⊙ - DENOTES FOUND MONUMENT AS NOTED
- ⊗ - DENOTES CALCULATED CORNER

1000' 0 1000' 2000' FEET
SCALE: 1"=1000'


EOG RESOURCES, INC.

SURVEY FOR A PROPOSED PIPELINE AND ROADS IN
SECTION 3, TOWNSHIP 18 SOUTH, RANGE 23 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO

Survey Date: 11/08/07	Sheet 1 of 3 Sheets
W.O. Number: 071108PL/RD	Drawn By: KA
Date: 11/16/07	071108PL.DWG Scale: 1"=1000'

SECTION 3, TOWNSHIP 18 SOUTH, RANGE 23 EAST, N.M.P.M.,
EDDY COUNTY NEW MEXICO

Exhibit 2a Page 2 of 2



DESCRIPTION

SURVEY FOR A PIPELINE EASEMENT CROSSING CROCKETT TRUST LAND IN SECTION 3, TOWNSHIP 18 SOUTH, RANGE 23 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS.

BEGINNING AT A POINT ON THE EAST LINE OF SAID SECTION 3, WHICH LIES N02°10'45"W - 543.8 FEET FROM THE SOUTHEAST CORNER OF SAID SECTION 3; THEN N89°10'19"W - 495.5 FEET; THENCE N02°11'14"W - 1320.7 FEET; THENCE N21°49'29"E - 662.0 FEET; THENCE N08°59'08"E - 162.9 FEET TO A POINT ON THE NORTH LINE OF THE SOUTH HALF OF SAID SECTION 3, WHICH LIES S89°16'08"W - 194.2 FEET FROM THE EAST QUARTER CORNER OF SAID SECTION 3.

TOTAL LENGTH EQUALS 2641.1 FEET OR 160.07 RODS.




SURVEYORS CERTIFICATE

I, TERRY J. ASEL, NEW MEXICO PROFESSIONAL SURVEYOR NO. 15079, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND MEETS THE "MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO" AS ADOPTED BY THE NEW MEXICO STATE BOARD OF REGISTRATION FOR PROFESSIONAL ENGINEERS AND SURVEYORS.

Terry J. Asel 1/11/2008
Terry J. Asel N.M. R.P.S. No. 15079

Asel Surveying

P.O. BOX 393 - 310 W. TAYLOR
HOBBS, NEW MEXICO - 505-393-9146



LEGEND

- - DENOTES FOUND MONUMENT AS NOTED
- ⊗ - DENOTES CALCULATED CORNER


1000' 0 1000' 2000' FEET
SCALE: 1"=1000'

EOG RESOURCES, INC.

SURVEY FOR A PIPELINE EASEMENT IN SECTION 3,
TOWNSHIP 18 SOUTH, RANGE 23 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO

Survey Date: 01/03/08	Sheet 2 of 2 Sheets
W.O. Number: 080103PL-b (Rev A)	Drawn By: KA
Date: 01/11/08	080103PL-b (Rev A).DWG Scale: 1"=1000'

VICINITY MAP




SEC. 3 TWP. 18-S RGE. 23-E
 SURVEY N.M.P.M.
 COUNTY EDDY
 DESCRIPTION 760' FSL & 360' FEL
 ELEVATION 3923'
 OPERATOR EOG RESOURCES INC.
 LEASE CHAMA 3 FED. #2H

SCALE: 1" = 2 MILES


Asel Surveying
 & Consulting

P.O. BOX 393 - 310 W. TAYLOR
 HOBBS, NEW MEXICO - 505-393-9146



DIRECTIONS BEGINNING IN ARTESIA, GO WEST ON HWY. 82 FOR 14.9 MILES, TURN SOUTH ON EDDY COUNTY ROAD #8 (SANTA ROAD) FOR 2.1 MILES, TURN LEFT ON LEASE ROAD FOR 0.8 MILES, TURN RIGHT ON LEASE ROAD FOR 1.0 MILES, TURN RIGHT ON LEASE ROAD FOR 0.1 MILES TO STAKED NEW ROAD, GO SOUTH 0.8 MILES TO LOCATION.

LOCATION VERIFICATION MAP



SCALE: 1" = 2000'

CONTOUR INTERVAL: 10'

SEC. 3 TWP. 18-S RGE. 23-E

SURVEY N.M.P.M.

COUNTY EDDY

DESCRIPTION 760' FSL & 360' FEL

ELEVATION 3923'


OPERATOR EOG RESOURCES INC.

LEASE CHAMA 3 FED. #2H

U.S.G.S. TOPOGRAPHIC MAP
HOPE, N.M.

Asel Surveying
& Consulting

P.O. BOX 393 - 310 W. TAYLOR
HOBBS, NEW MEXICO - 505-393-9146



PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	EOG RESOURCES, INC.
LEASE NO.:	NM100530
WELL NAME & NO.:	CHAMA 3 FED NO. 2H
SURFACE HOLE FOOTAGE:	760' FSL & 360' FEL
BOTTOM HOLE FOOTAGE:	760' FSL & 660' FWL
LOCATION:	Section 3, T. 18 S., R 23 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Aplomado Falcon
 - Cave/Karst
- ☒ **Construction**
 - Notification
 - Topsoil
 - Reserve Pit
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☒ **Road Section Diagram**
- ☒ **Drilling**
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- ☐ **Reserve Pit Closure/Interim Reclamation**
- ☐ **Final Abandonment/Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Mitigation Measures: The mitigation measures include the Pecos District Conditions of Approval and Aplomado Falcon stipulations, and stipulations for High Cave/karst occurrence on the Chama 3 Fed. # 2H. The Chama 3 Fed. # 2H well location is located in a High Cave/Karst area as depicted on the Carlsbad Field Office resource map.

Stipulations for Drilling in Aplomado Falcon Habitat

The following well pads construction and reclamation measures will be implemented to provide for minimal long-term disturbance:

No Yuccas over 5 feet in height will be damaged by vehicular use or any other activity associated with this project.

Remove all caliche from well pads and roads that are plugged and abandoned. Reclamation will consist of disking, mulching, seeding with a drill (See seed mixture below), and application of water to encourage seed germination.

Well pad size will not exceed 300 ft. x 390 ft. (unless multiple wells are drilled from the same well pad). All unused portions of the well pad associated with producing wells will be reclaimed using the seed mixture below:

Buffalograss (<i>Buchloe dactyloides</i>)	4 lbs/acre
Blue grama (<i>Bouteloua gracilis</i>)	1 lbs/acre
Cane bluestem (<i>Bothriochloa barbinodis</i>)	5 lbs/acre
Sideoats grama (<i>Bouteloua curtipendula</i>)	5 lbs/acre
Plains bristlegrass (<i>Setaria macrostachya</i>)	6 lbs/acre

Reserve pits for drilling and disposal are not allowed unless the pit can be effectively netted to the satisfaction of the BLM. Steel tank circulation system must be used if the reserve pit is not netted.

All active raptor nests will be avoided by a minimum of 400 meters by all activities or curtail activities until fledging is complete.

All inactive raptor nests will be avoided by a minimum of 200 meters by all activities.

All roads associated with well development will not exceed 30 ft in width

Chama 3 Federal # 2H: Pit West V-Door North

Cave and Karst

Cave/Karst Surface Mitigation

The following stipulations will be applied to minimize impacts during construction, drilling and production.

Berming:

Tank batteries will be bermed to contain 1 ½ times the content of the largest tank.

Bermed areas will be lined with a permanent 20 mil plastic liner and then lined with a 4 oz. felt liner to prevent tears or punctures in liner.

Cave/Karst Subsurface Mitigation

The following stipulations will be applied to protect cave/karst and ground-water concerns:

Lost Circulation:

ALL lost circulation zones from the surface to the base of the cave occurrence zone will be logged and reported in the drilling report.

Regardless of the type of drilling machinery used, if a void of four feet or more and circulation losses greater than 100 percent occur simultaneously while drilling in any cave-bearing zone, the BLM will be notified immediately by the operator. The BLM will assess the consequences of the situation and work with operator on corrective actions to resolve the problem.

Delayed Blasting:

Any blasting will be phased and time delayed.

Abandonment Cementing:

Upon well abandonment the well bore will be cemented completely from 100 feet below the bottom of the cave bearing zone to the surface.

Record Keeping:

The Operator will track customary drilling activities, including the rate of penetration, pump pressure, weight on bit, bit drops, percent of mud returns, and presence of absence of cuttings returning to the surface. As part of customary record keeping, each detectable void or sudden increase in the rate of penetration not attributable to a change in the formation type should be documented and evaluated as it is encountered.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (505) 234-5972 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall stockpile the topsoil of the well pad. The topsoil shall not be used to backfill the reserve pit and will be used for interim and final reclamation.

C. RESERVE PITS

The reserve pit shall be constructed and closed in accordance with the NMOCD rules.

The reserve pit shall be constructed 125' X 125' on the West side of the well pad V-Door North.

The reserve pit shall be constructed, so that upon completion of drilling operations, the dried pit contents shall be buried a minimum depth of three feet below ground level. Should the pit content level not meet the three foot minimum depth requirement, the excess contents shall be removed until the required minimum depth of three feet below ground level has been met. The operator shall properly dispose of the excess contents at an authorized disposal site.

The reserve pit shall be constructed and maintained so that runoff water from outside the location is not allowed to enter the pit. The berms surrounding the entire perimeter of the pit shall extend a minimum of two (2) feet above ground level. At no time will standing fluids in the pit be allowed to rise above ground level.

The reserve pit shall be fenced on three (3) sides during drilling operations. The fourth side shall be fenced immediately upon rig release.

D. FEDERAL MINERAL MATERIALS PIT

If the operator elects to surface the access road and/or well pad, mineral materials extracted during construction of the reserve pit may be used for surfacing the well pad and access road and other facilities on the lease.

Payment shall be made to the BLM prior to removal of any additional federal mineral materials from any site other than the reserve pit. Call the Carlsbad Field Office at (505) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed thirty (30) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.


Ditching

Ditching shall be required on both sides of the road.

Turnouts

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:

Standard Turnout – Plan View




Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Culvert Installations

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.

Fence Requirement


Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Figure 1 – Cross Sections and Plans For Typical Road Sections



VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 4 hours in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOPE tests

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. **Hydrogen Sulfide has been reported from nearby wells, but no measurements have been recorded. It is recommended that monitoring equipment be onsite for potential Hydrogen Sulfide. If Hydrogen Sulfide is encountered, please report measurements and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

B. CASING

1. The 8-5/8 inch surface casing shall be set **in the lower San Andres at approximately 1280 feet** and cemented to the surface. **Fresh water mud to be used to setting depth of surface casing.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with a surface log readout will be used or a cement bond log shall be run to verify the top of the cement.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement). **Please provide WOC times to inspector for cement slurries.**

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial action will be done prior to drilling out that string.

High cave/karst.

Possible lost circulation in the Grayburg and San Andres formations.

Possible high pressure gas bursts in the Wolfcamp.

- 2. The minimum required fill of cement behind the 5-1/2 inch production casing is:

☒ Cement to surface. If cement does not circulate, contact the appropriate BLM office.

- 3. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. The tests shall be done by an independent service company.
 - b. The results of the test shall be reported to the appropriate BLM office.
 - c. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
 - d. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.

- e. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the **Wolfcamp** formation **if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days**. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

D. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the **Wolfcamp** formation, and shall be used until production casing is run and cemented.

WWI 030608

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Containment Structures

The containment structure shall be constructed to hold the capacity of the entire contents of the largest tank, plus 24 hour production, unless more stringent protective requirements are deemed necessary by the Authorized Officer.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color
Shale Green, Munsell Soil Color Chart # 5Y 4/2

B. PIPELINES

C. ELECTRIC LINES

IX. INTERIM RECLAMATION & RESERVE PIT CLOSURE

A. INTERIM RECLAMATION

If the well is a producer, interim reclamation shall be conducted on the well site in accordance with the orders of the Authorized Officer. The operator shall submit a Sundry Notices and Reports on Wells (Notice of Intent), Form 3160-5, prior to conducting interim reclamation.

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

At the time reserve pits are to be reclaimed, operators should work with BLM surface management specialists to devise the best strategies to reduce the size of the location. Any reductions should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

B. RESERVE PIT CLOSURE

The reserve pit, when dried and closed, shall be recontoured, all trash removed, and reseeded as follows:

Aplomado Falcon Habitat Seed Mixture

Buffalograss (<i>Buchloe dactyloides</i>)	----- 4 lbs/acre
Blue grama (<i>Bouteloua gracilis</i>)	----- 1 lb/acre
Cane bluestem (<i>Bothriochloa barbinodis</i>)	----- 5 lbs/acre
Sideoats grama (<i>Bouteloua curtipendula</i>)	----- 5 lbs/acre
Plains bristlegrass (<i>Setaria macrostachya</i>)	----- 6 lbs/acre

X. FINAL ABANDONMENT & REHABILITATION REQUIREMENTS

Upon abandonment of the well and/or when the access road is no longer in service the Authorized Officer shall issue instructions and/or orders for surface reclamation and restoration of all disturbed areas.

On private surface/federal mineral estate land the reclamation procedures on the road and well pad shall be accomplished in accordance with the private surface landowner agreement.