

A75-08-048
EA-08-1133

SEP 11 2008

S

OCD-ARTESIA

OCD-ARTESIA

Form 3160-3
(April 2004)

FORM APPROVED
OMB No 1004-0137
Expires March 31, 2007

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work. <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. LC-061622	
1b. Type of Well. <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name	
2. Name of Operator Cimarex Energy Co. of Colorado		7. If Unit or CA Agreement, Name and No.	
3a. Address PO Box 140907 Irving, TX 75014		8. Lease Name and Well No County Line 1 Federal No. 3	
3b. Phone No. (include area code) 972-401-3111		9. API Well No. 30-015-36621	
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At Surface 3300' FSL & 330' FEL 4080' FSL & 330' FEL At proposed prod. Zone 3300' FSL & 330' FEL Lateral 1: BHL 4451' FSL & 330' FWL Horizontal Abo test 2971' FSL & 330' FWL		10. Field and Pool, or Exploratory Abo Wildcat	
14. Distance in miles and direction from nearest town or post office* C.L. 09/03/08		11. Sec., T. R. M. or Blk. and Survey or Area Lot 16 1-16S-29E	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig unit line if any) 330'		12. County or Parish Eddy	
16. No of acres in lease 840		13. State NM	
17. Spacing Unit dedicated to this well S2 of Middle 3rd (Lots 13,14,15,16) 160 acres			
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. N/A		19. Proposed Depth Pilot Hole 7,600' MD 11,885' TVD 7,380'	
20. BLM/BIA Bond No. on File NM-2575			
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3,779' GR		22. Approximate date work will start* 05.01.08	
23. Estimated duration 25-30 days			

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above) |
| 2. A Drilling Plan | 5. Operator Certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature Zeno Farris	Name (Printed/Typed) Zeno Farris	Date 04.03.08
------------------------------	-------------------------------------	------------------

Title
Manager Operations Administration

Approved By (Signature) /s/ Don Peterson	Name (Printed/Typed) /s/ Don Peterson	Date SEP - 9 2008
---	--	----------------------

Title
FIELD MANAGER CARLSBAD FIELD OFFICE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached
APPROVAL FOR TWO YEARS

Title 18 U.S.S. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious, or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on page 2)

APPROVAL SUBJECT TO
GENERAL REQUIREMENTS SEE ATTACHED FOR
AND SPECIAL STIPULATIONS CONDITIONS OF APPROVAL
ATTACHED

Roswell Controlled Water Basin

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

I&E - CFO

FORM APPROVED
OMB No 1004-0135
Expires July 31, 1996

SUNDRY NOTICES AND REPORTS ON WELLS
*Do not use this form for proposals to drill or to re-enter an
abandoned well. Use form 3160-3 (APD) for such proposals.*

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator
Cimarex Energy Co. of Colorado

3a. Address
PO Box 140907; Irving, TX 75014-0907

3b. Phone No. (include area code)
972-401-3111

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
SHL 3300 FSL & 330 FEL 3300 FSL & 330 FWL
Lot 16 1-16S-29E Lot 13 1-16S-29E

5. Lease Serial No.

LC-061622

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No

8. Well Name and No.

County Line 1 Federal No. 3

9. API Well No.

30-015-

10. Field and Pool, or Exploratory Area

Abo Wildcat

11. County or Parish, State

Eddy County, NM

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>Change SHL,</u>
	<input checked="" type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	<u>propose dual lateral</u>
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, included estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleation in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

In order to eliminate the need to drill the County Line 1 Federal No. 4 well in the N2/Middle3 of 1-16S-29E, Cimarex has opted to move the SHL of its proposed County Line 1 Federal No. 3 well and drill dual laterals with a 320-acre "Project Area". Location changes shown below. Drilling program changes and access road changes attached.

Previous Location

SHL 3300 FSL & 330 FEL (Lot 16)
BHL 3300 FSL & 330 FWL (Lot 13)

New Location

SHL 4080 FSL & 330 FEL (Lot 9)
Lateral 1 BHL 4951 FSL & 330 FWL (Lot 12)
~~**Lateral 2** BHL 2971 FSL & 330 FWL (Lot 13)~~

*Engp reviewed
9/4/08 mcr*

*NOT Doing As per
call with Zeno 9-4-08
gong*

Access road will now be 534' long and will be on-lease. No ROW required.

Please see attached revised drilling plan, plats, and directional surveys for both laterals.

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Zeno Farris

Signature

Title

Manager Operations Administration

Date

August 12, 2008

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by	Title	Date
Conditions of Approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

Revised Drilling Plan
County Line 1 Federal No. 3 (Dual Laterals)
 Cimarex Energy Co. of Colorado
 SHL 4080 FSL & 330 FEL
 LATERAL 1 BHL 4951 FSL & 330 FWL
 LATERAL 2 BHL 2971 FSL & 330 FWL
 Eddy County, NM

Revised Drilling Plan (surface, intermediate, and pilot hole same as permitted)

Hole	Hole Size	Depth	Casing OD	Weight	Thread	Collar	Grade
<i>Surface</i>	17½"	0' to 340'	New 13½"	48#	8-R	STC	H-40
<i>Intermediate</i>	12¼"	0' to 2500'	New 9½"	40#	8-R	LTC	J-55
<i>Pilot Hole</i>	8¾"	0' to 7600'	New 7"	26#	8-R	LTC	P-110
<i>Lateral 1 (to EOC)</i>	6⅝"	7100' to 7508'	New 4½"	11.6#	8-R	BTC	P-110
<i>Lateral 1 (to TD)</i>	6⅝"	7508' to 11986'	New 4½"	11.6#	8-R	LTC	P-110
<i>Lateral 2 (to EOC)</i>	6⅝"	7040' to 7576'	New 4½"	11.6#	8-R	BTC	P-110
<i>Lateral 2 (to TD)</i>	6⅝"	7576' to 11978'	New 4½"	11.6#	8-R	LTC	P-110

Drill, case, and cement surface, intermediate, and pilot holes as permitted.

For **First Lateral**, Set whipstock plug @ 7170'. Mill window from 7155' to 7165' and kick off 6⅝" hole at 7160'. Drill to TD of MD 11986', TVD 7350'. Install 4½" Peak Completion Assembly 11.6# P-110 **BTC** casing from 7100' to 7508' and **LTC** from 7508' to 11986'.

For **Second Lateral**, set whipstock plug @ 7050'. Mill window from 7035' to 7045' and kick off 6⅝" hole at 7040'. Drill to TD of MD 11978', TVD 7350'. Run 4½" Peak Completion Assembly 11.6# P-110 **BTC** casing from 7040' to 7576' and **LTC** from 7576' to 11978'. Peak assembly for second lateral will have on-off tool for frac-ing purposes.

4½" liner will be PEAK completion liner and will not require cement.

Revised Mud Program (surface, intermediate, and pilot hole same as permitted)

Hole	Depth	Mud Wt	Visc	Fluid Loss	Type Mud
Surface	0' to 340'	8.4 - 8.6	28	NC	FW
Intermediate	340' to 2,500'	10.0	30-32	NC	Brine water
Pilot Hole	2,500' to 7,600'	8.4 - 9.5	30-32	NC	FW, brine
Lateral 1	7,160' to 11,986'	9	28-32	May lose circ	2% KCl
Lateral 2	7,040' to 11,978'	9	28-32	May lose circ	2% KCl

DISTRICT I
1625 N. French Dr., Hobbs, NM 88240

DISTRICT II
1301 W. Grand Avenue, Artesia, NM 88210

DISTRICT III
1000 Rio Brazos Rd., Aztec, NM 87410

DISTRICT IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-102
Revised October 12, 2005

Submit to Appropriate District Office

State Lease - 4 Copies

Fee Lease - 3 Copies

OIL CONSERVATION DIVISION

1220 South St. Francis Dr.
Santa Fe, New Mexico 87505

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-015-	Pool Code 36849 97197	Pool Name County Line Tank; Abo
Property Code 97197 36849	Property Name COUNTY LINE "1" FEDERAL	Well Number 3
OGRID No. 162683	Operator Name CIMAREX ENERGY CO. OF COLORADO	Elevation 3783'

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
LOT 9	1	16 S	29 E		4080	SOUTH	330	EAST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
BH #1 LOT 12	1	16 S	29 E		4951	SOUTH	330	WEST	EDDY
BH #2 LOT 13	1	16 S	29 E		2971	SOUTH	330	WEST	EDDY

Dedicated Acres 320	Joint or Infill	Consolidation Code	Order No.
------------------------	-----------------	--------------------	-----------

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

BOTTOM HOLE LOCATION 1


Lat - N32°57'25.31"
Long - W104°02'08.69"
NMSPC - N 712032.105
E 632614.981
(NAD-83)

BOTTOM HOLE LOCATION 2

Lat - N32°57'05.72"
Long - W104°02'08.69"
NMSPC - N 710052.105
E 632620.777
(NAD-83)

SURFACE LOCATION

Lat - N32°57'16.56"
Long - W104°01'14.52"
NMSPC - N 711161.1
E 637233.0
(NAD-83)



SCALE - 1" = 2000'

OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Zeno Farris 08-12-08
Signature Date

Zeno Farris
Printed Name

SURVEYOR CERTIFICATION


I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

JULY 25, 2008
Date Surveyed
Signature of Surveyor
Professional Surveyor

W.D. Jones
Certificate No. Gary L. Jones 7977


BASIN SURVEYS

SECTION 1, TOWNSHIP 16 SOUTH, RANGE 29 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.



Directions to Location:

FROM THE COUNTY LINE FEDERAL #1 LOCATION, GO
NORTHEASTERLY 0.9 MILES TO PROPOSED LEASE
ROAD.



CIMAREX ENERGY CO. OF COLORADO

REF: COUNTY LINE "1" FEDERAL #3 / WELL PAD TOPO

THE COUNTY LINE "1" FEDERAL #3 LOCATED 4080'

FROM THE SOUTH LINE AND 330' FROM THE EAST LINE OF

SECTION 1, TOWNSHIP 16 SOUTH, RANGE 29 EAST,

N.M.P.M., EDDY COUNTY, NEW MEXICO.

BASIN SURVEYS P.O. BOX 1786-HOBBS, NEW MEXICO

W.O. Number: 20199


Drawn By: J. SMALL

Date: 07-24-2008

Disk: JMS 20199W

Survey Date: 07-23-2008

Sheet 1 of 1 Sheets



COUNTY LINE "1" FEDERAL #3

Located 4080' FSL and 330' FWL

Section 1, Township 16 South, Range 29 East,
N.M.P.M., Eddy County, New Mexico.

**basin
surveys**
focused on excellence
in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(505) 393-7316 - Office
(505) 392-3074 - Fax
basinsurveys.com

W.O. Number: JMS 20199

Survey Date: 07-23-2008

Scale: 1" = 2000'

Date: 07-24-2008

**CIMAREX
ENERGY CO.
OF COLORADO**



Planned Wellpath Report

Preliminary LAT01

Page 1 of 4



INTEQ

REFERENCE WELLPATH IDENTIFICATION

Operator	Cimarex Energy Co. of Colorado	Slot	No. 3H SHL
Area	Eddy County, NM	Well	No. 3H
Field	(County) Sec. 1, T16S, R29E	Wellbore	No. 3H PWB LAT01
Facility	County Line 1 Fed No. 3H		

REPORT SETUP INFORMATION

Projection System	NAD83 / TM New Mexico State Planes, Eastern Zone (3001), US feet	Software System	WellArchitect® 2.0
North Reference	Grid	User	Victor Hernandez
Scale	0.99992	Report Generated	7/31/2008 at 11:10:45 AM
Convergence at slot	0.17° East	Database/Source file	WA_Midland/No. 3H_PWB_LAT01.xml

WELLPATH LOCATION

	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	East[ft]	Easting[USft]	Northing[USft]	Latitude	Longitude
Slot Location	0.00	0.00	637233.00	711161.10	32°57'16.560"N	104°01'14.518"W
Facility Reference Pt			637233.00	711161.10	32°57'16.560"N	104°01'14.518"W
Field Reference Pt			637234.90	710381.30	32°57'08.844"N	104°01'14.523"W

WELLPATH DATUM

Calculation method	Minimum curvature	Rig on No. 3H SHL (RT) to Facility Vertical Datum	18.00ft
Horizontal Reference Pt	Facility Center	Rig on No. 3H SHL (RT) to Mean Sea Level	3801.00ft
Vertical Reference Pt	Rig on No. 3H SHL (RT)	Facility Vertical Datum to Mud Line (Facility)	0.00ft
MD Reference Pt	Rig on No. 3H SHL (RT)	Section Origin	N 0.00, E 0.00 ft
Field Vertical Reference	Mean Sea Level	Section Azimuth	280.68°



Planned Wellpath Report

Preliminary LAT01

Page 2 of 4



INTEQ

REFERENCE WELLPATH IDENTIFICATION

Operator	Cimarex Energy Co. of Colorado	Slot	No. 3H SHL
Area	Eddy County, NM	Well	No. 3H
Field	(County) Sec. 1, T16S, R29E	Wellbore	No. 3H PWB LAT01
Facility	County Line 1 Fed No. 3H		

WELLPATH DATA (52 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	DLS [°/100ft]	Comments
0.00	0.000	280.681	0.00	0.00	0.00	0.00	0.00	Tie On
7160.00	0.000	280.681	7160.00	0.00	0.00	0.00	0.00	KOP
7260.00†	26.000	280.681	7256.60	22.30	4.13	-21.92	26.00	
7360.00†	52.000	280.681	7333.65	84.70	15.70	-83.23	26.00	
7460.00†	78.000	280.681	7375.55	174.55	32.35	-171.53	26.00	
7507.65	90.388	280.681	7380.36	221.86	41.12	-218.02	26.00	EOC
7560.00†	90.388	280.681	7380.01	274.21	50.82	-269.46	0.00	
7660.00†	90.388	280.681	7379.33	374.21	69.36	-367.73	0.00	
7760.00†	90.388	280.681	7378.65	474.21	87.89	-465.99	0.00	
7860.00†	90.388	280.681	7377.97	574.21	106.42	-564.26	0.00	
7960.00†	90.388	280.681	7377.30	674.20	124.96	-662.52	0.00	
8060.00†	90.388	280.681	7376.62	774.20	143.49	-760.79	0.00	
8160.00†	90.388	280.681	7375.94	874.20	162.03	-859.05	0.00	
8260.00†	90.388	280.681	7375.26	974.20	180.56	-957.32	0.00	
8360.00†	90.388	280.681	7374.58	1074.19	199.09	-1055.58	0.00	
8460.00†	90.388	280.681	7373.91	1174.19	217.63	-1153.85	0.00	
8560.00†	90.388	280.681	7373.23	1274.19	236.16	-1252.11	0.00	
8660.00†	90.388	280.681	7372.55	1374.19	254.70	-1350.38	0.00	
8760.00†	90.388	280.681	7371.87	1474.19	273.23	-1448.64	0.00	
8860.00†	90.388	280.681	7371.19	1574.18	291.76	-1546.91	0.00	
8960.00†	90.388	280.681	7370.52	1674.18	310.30	-1645.17	0.00	
9060.00†	90.388	280.681	7369.84	1774.18	328.83	-1743.44	0.00	
9160.00†	90.388	280.681	7369.16	1874.18	347.36	-1841.70	0.00	
9260.00†	90.388	280.681	7368.48	1974.17	365.90	-1939.97	0.00	
9360.00†	90.388	280.681	7367.80	2074.17	384.43	-2038.23	0.00	
9460.00†	90.388	280.681	7367.13	2174.17	402.97	-2136.50	0.00	
9560.00†	90.388	280.681	7366.45	2274.17	421.50	-2234.77	0.00	
9660.00†	90.388	280.681	7365.77	2374.17	440.03	-2333.03	0.00	
9760.00†	90.388	280.681	7365.09	2474.16	458.57	-2431.30	0.00	
9860.00†	90.388	280.681	7364.41	2574.16	477.10	-2529.56	0.00	



Planned Wellpath Report

Preliminary LAT01

Page 3 of 4



INTEQ

REFERENCE WELLPATH IDENTIFICATION

Operator	Cimarex Energy Co. of Colorado	Slot	No. 3H SHL
Area	Eddy County, NM	Well	No. 3H
Field	(County) Sec. 1, T16S, R29E	Wellbore	No. 3H PWB LAT01
Facility	County Line 1 Fed No. 3H		

WELLPATH DATA (52 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	DLS [°/100ft]	Comments
9960.00†	90.388	280.681	7363.74	2674.16	495.63	-2627.83	0.00	
10060.00†	90.388	280.681	7363.06	2774.16	514.17	-2726.09	0.00	
10160.00†	90.388	280.681	7362.38	2874.15	532.70	-2824.36	0.00	
10260.00†	90.388	280.681	7361.70	2974.15	551.24	-2922.62	0.00	
10360.00†	90.388	280.681	7361.02	3074.15	569.77	-3020.89	0.00	
10460.00†	90.388	280.681	7360.35	3174.15	588.30	-3119.15	0.00	
10560.00†	90.388	280.681	7359.67	3274.14	606.84	-3217.42	0.00	
10660.00†	90.388	280.681	7358.99	3374.14	625.37	-3315.68	0.00	
10760.00†	90.388	280.681	7358.31	3474.14	643.90	-3413.95	0.00	
10860.00†	90.388	280.681	7357.63	3574.14	662.44	-3512.21	0.00	
10960.00†	90.388	280.681	7356.95	3674.14	680.97	-3610.48	0.00	
11060.00†	90.388	280.681	7356.28	3774.13	699.51	-3708.74	0.00	
11160.00†	90.388	280.681	7355.60	3874.13	718.04	-3807.01	0.00	
11260.00†	90.388	280.681	7354.92	3974.13	736.57	-3905.27	0.00	
11360.00†	90.388	280.681	7354.24	4074.13	755.11	-4003.54	0.00	
11460.00†	90.388	280.681	7353.56	4174.12	773.64	-4101.80	0.00	
11560.00†	90.388	280.681	7352.89	4274.12	792.18	-4200.07	0.00	
11660.00†	90.388	280.681	7352.21	4374.12	810.71	-4298.33	0.00	
11760.00†	90.388	280.681	7351.53	4474.12	829.24	-4396.60	0.00	
11860.00†	90.388	280.681	7350.85	4574.11	847.78	-4494.86	0.00	
11960.00†	90.388	280.681	7350.17	4674.11	866.31	-4593.13	0.00	
11985.72	90.388	280.681	7350.00†	4699.83	871.08	-4618.40	0.00	No. 3H BHL LAT01



Planned Wellpath Report

Preliminary LAT01

Page 4 of 4



INTEQ

REFERENCE WELLPATH IDENTIFICATION			
Operator	Cimarex Energy Co. of Colorado	Slot	No. 3H SHL
Area	Eddy County, NM	Well	No. 3H
Field	(County) Sec. 1, T16S, R29E	Wellbore	No. 3H PWB LAT01
Facility	County Line 1 Fed No. 3H		

TARGETS									
Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [srv ft]	Grid North [srv ft]	Latitude	Longitude	Shape
1) No. 3H BHL LAT01	11985.72	7350.00	871.08	-4618.40	632614.98	712032.10	32°57'25.310"N	104°02'08.688"W	point

SURVEY PROGRAM Ref Wellbore: No. 3H PWB LAT01					Ref Wellpath: Preliminary LAT01	
Start MD [ft]	End MD [ft]	Positional Uncertainty Model		Log Name/Comment		Wellbore
18.00	11985.72	NaviTrak (Standard)				No. 3H PWB LAT01



Cimarex Energy Co. of Colorado


Location: Eddy County, NM
Field: (County) Sec. 1, T16S, R29E
Facility: County Line 1 Fed No. 3H

Slot: No. 3H SHL
Well: No. 3H
Wellbore: No. 3H PWB LAT01




Well Profile Data

Design Comment	MD (ft)	Inc (°)	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)	VS (ft)
Tie On	0.00	0.000	280.681	0.00	0.00	0.00	0.00	0.00
KOP	7160.00	0.000	280.681	7160.00	0.00	0.00	0.00	0.00
EOC	7507.65	90.388	280.681	7380.36	41.12	-218.02	26.00	221.86
No. 3H BHL LAT01	11985.72	90.388	280.681	7350.00	871.08	-4618.40	0.00	4699.83



LEASE / HARD LINES ARE ESTIMATE ONLY AND ARE SUBJECT TO CUSTOMER APPROVAL.





Planned Wellpath Report

Preliminary LAT02

Page 1 of 4



INTEQ

REFERENCE WELLPATH IDENTIFICATION

Operator	Cimarex Energy Co. of Colorado	Slot	No. 3H SHL
Area	Eddy County, NM	Well	No. 3H
Field	(County) Sec. 1, T16S, R29E	Wellbore	No. 3H PWB LAT02
Facility	County Line 1 Fed No. 3H		

REPORT SETUP INFORMATION

Projection System	NAD83 / TM New Mexico State Planes, Eastern Zone (3001), US feet	Software System	WellArchitect® 2.0
North Reference	Grid	User	Victor Hernandez
Scale	0.99992	Report Generated	7/31/2008 at 11:31:07 AM
Convergence at slot	0.17° East	Database/Source file	WA_Midland/No._3H_PWB_LAT02.xml

WELLPATH LOCATION

	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	East[ft]	Easting[USft]	Northing[USft]	Latitude	Longitude
Slot Location	0.00	0.00	637233.00	711161.10	32°57'16.560"N	104°01'14.518"W
Facility Reference Pt			637233.00	711161.10	32°57'16.560"N	104°01'14.518"W
Field Reference Pt			637234.90	710381.30	32°57'08.844"N	104°01'14.523"W

WELLPATH DATUM

Calculation method	Minimum curvature	Rig on No. 3H SHL (RT) to Facility Vertical Datum	18.00ft
Horizontal Reference Pt	Facility Center	Rig on No. 3H SHL (RT) to Mean Sea Level	3801.00ft
Vertical Reference Pt	Rig on No. 3H SHL (RT)	Facility Vertical Datum to Mud Line (Facility)	0.00ft
MD Reference Pt	Rig on No. 3H SHL (RT)	Section Origin	N 0.00, E 0.00 ft
Field Vertical Reference	Mean Sea Level	Section Azimuth	256.48°



Planned Wellpath Report

Preliminary LAT02

Page 2 of 4



INTEQ

REFERENCE WELLPATH IDENTIFICATION

Operator	Cimarex Energy Co. of Colorado	Slot	No. 3H SHL
Area	Eddy County, NM	Well	No. 3H
Field	(County) Sec. 1, T16S, R29E	Wellbore	No. 3H PWB LAT02
Facility	County Line 1 Fed No. 3H		

WELLPATH DATA (53 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	DLS [°/100ft]	Comments
0.00	0.000	256.480	0.00	0.00	0.00	0.00	0.00	Tie On
7040.00	0.000	256.480	7040.00	0.00	0.00	0.00	0.00	KOP
7140.00†	16.850	256.480	7138.56	14.60	-3.41	-14.19	16.85	
7240.00†	33.700	256.480	7228.67	57.14	-13.36	-55.56	16.85	
7340.00†	50.550	256.480	7302.57	123.97	-28.98	-120.54	16.85	
7440.00†	67.400	256.480	7353.92	209.36	-48.95	-203.56	16.85	
7540.00†	84.250	256.480	7378.32	305.97	-71.53	-297.49	16.85	
7576.44	90.391	256.480	7380.03	342.35	-80.04	-332.87	16.85	EOC
7640.00†	90.391	256.480	7379.59	405.91	-94.89	-394.66	0.00	
7740.00†	90.391	256.480	7378.91	505.91	-118.27	-491.89	0.00	
7840.00†	90.391	256.480	7378.23	605.90	-141.65	-589.11	0.00	
7940.00†	90.391	256.480	7377.55	705.90	-165.03	-686.34	0.00	
8040.00†	90.391	256.480	7376.86	805.90	-188.41	-783.57	0.00	
8140.00†	90.391	256.480	7376.18	905.90	-211.78	-880.79	0.00	
8240.00†	90.391	256.480	7375.50	1005.89	-235.16	-978.02	0.00	
8340.00†	90.391	256.480	7374.82	1105.89	-258.54	-1075.25	0.00	
8440.00†	90.391	256.480	7374.14	1205.89	-281.92	-1172.47	0.00	
8540.00†	90.391	256.480	7373.45	1305.89	-305.30	-1269.70	0.00	
8640.00†	90.391	256.480	7372.77	1405.88	-328.67	-1366.93	0.00	
8740.00†	90.391	256.480	7372.09	1505.88	-352.05	-1464.15	0.00	
8840.00†	90.391	256.480	7371.41	1605.88	-375.43	-1561.38	0.00	
8940.00†	90.391	256.480	7370.73	1705.88	-398.81	-1658.61	0.00	
9040.00†	90.391	256.480	7370.04	1805.88	-422.18	-1755.83	0.00	
9140.00†	90.391	256.480	7369.36	1905.87	-445.56	-1853.06	0.00	
9240.00†	90.391	256.480	7368.68	2005.87	-468.94	-1950.29	0.00	
9340.00†	90.391	256.480	7368.00	2105.87	-492.32	-2047.51	0.00	
9440.00†	90.391	256.480	7367.31	2205.87	-515.70	-2144.74	0.00	
9540.00†	90.391	256.480	7366.63	2305.86	-539.07	-2241.97	0.00	
9640.00†	90.391	256.480	7365.95	2405.86	-562.45	-2339.19	0.00	
9740.00†	90.391	256.480	7365.27	2505.86	-585.83	-2436.42	0.00	



Planned Wellpath Report

Preliminary LAT02

Page 3 of 4



INTEQ

REFERENCE WELLPATH IDENTIFICATION			
Operator	Cimarex Energy Co. of Colorado	Slot	No. 3H SHL
Area	Eddy County, NM	Well	No. 3H
Field	(County) Sec. 1, T16S, R29E	Wellbore	No. 3H PWB LAT02
Facility	County Line 1 Fed No. 3H		

WELLPATH DATA (53 stations) † = interpolated/extrapolated station								
MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	DLS [°/100ft]	Comments
9840.00†	90.391	256.480	7364.59	2605.86	-609.21	-2533.65	0.00	
9940.00†	90.391	256.480	7363.90	2705.85	-632.59	-2630.87	0.00	
10040.00†	90.391	256.480	7363.22	2805.85	-655.96	-2728.10	0.00	
10140.00†	90.391	256.480	7362.54	2905.85	-679.34	-2825.32	0.00	
10240.00†	90.391	256.480	7361.86	3005.85	-702.72	-2922.55	0.00	
10340.00†	90.391	256.480	7361.18	3105.85	-726.10	-3019.78	0.00	
10440.00†	90.391	256.480	7360.49	3205.84	-749.47	-3117.00	0.00	
10540.00†	90.391	256.480	7359.81	3305.84	-772.85	-3214.23	0.00	
10640.00†	90.391	256.480	7359.13	3405.84	-796.23	-3311.46	0.00	
10740.00†	90.391	256.480	7358.45	3505.84	-819.61	-3408.68	0.00	
10840.00†	90.391	256.480	7357.76	3605.83	-842.99	-3505.91	0.00	
10940.00†	90.391	256.480	7357.08	3705.83	-866.36	-3603.14	0.00	
11040.00†	90.391	256.480	7356.40	3805.83	-889.74	-3700.36	0.00	
11140.00†	90.391	256.480	7355.72	3905.83	-913.12	-3797.59	0.00	
11240.00†	90.391	256.480	7355.04	4005.82	-936.50	-3894.82	0.00	
11340.00†	90.391	256.480	7354.35	4105.82	-959.87	-3992.04	0.00	
11440.00†	90.391	256.480	7353.67	4205.82	-983.25	-4089.27	0.00	
11540.00†	90.391	256.480	7352.99	4305.82	-1006.63	-4186.50	0.00	
11640.00†	90.391	256.480	7352.31	4405.82	-1030.01	-4283.72	0.00	
11740.00†	90.391	256.480	7351.63	4505.81	-1053.39	-4380.95	0.00	
11840.00†	90.391	256.480	7350.94	4605.81	-1076.76	-4478.18	0.00	
11940.00†	90.391	256.480	7350.26	4705.81	-1100.14	-4575.40	0.00	
11978.26	90.391	256.480	7350.00†	4744.07	-1109.09	-4612.60	0.00	No. 3H BHL LAT02



Planned Wellpath Report

Preliminary LAT02

Page 4 of 4



INTEQ

REFERENCE WELLPATH IDENTIFICATION

Operator	Cimarex Energy Co. of Colorado	Slot	No. 3H SHL
Area	Eddy County, NM	Well	No. 3H
Field	(County) Sec. 1, T16S, R29E	Wellbore	No. 3H PWB LAT02
Facility	County Line 1 Fed No. 3H		

TARGETS

Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [srv ft]	Grid North [srv ft]	Latitude	Longitude	Shape
1) No. 3H BHL LAT02	11978.26	7350.00	-1109.09	-4612.60	632620.78	710052.10	32°57'05.718"N	104°02'08.685"W	point

SURVEY PROGRAM Ref Wellbore: No. 3H PWB LAT02 Ref Wellpath: Preliminary LAT02

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
18.00	11978.26	NaviTrak (Standard)		No. 3H PWB LAT02



Cimarex Energy Co. of Colorado



Location: Eddy County, NM
Field: (County) Sec. 1, T16S, R29E
Facility: County Line 1 Fed No. 3H

Slot: No. 3H SHL
Well: No. 3H
Wellbore: No. 3H PWB LAT02




Well Profile Data

Design Comment	MD (ft)	Inc (°)	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)	VS (ft)
Tie On	0.00	0.000	256.480	0.00	0.00	0.00	0.00	0.00
KOP	7040.00	0.000	256.480	7040.00	0.00	0.00	0.00	0.00
EOC	7576.44	90.391	256.480	7380.03	-80.04	-332.87	16.85	342.35
No. 3H BHL LAT02	11978.26	90.391	256.480	7350.00	-1109.09	-4612.60	0.00	4744.07



SECTION 1, TOWNSHIP 16 SOUTH, RANGE 29 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.



Directions to Location:

FOLLOW PROPOSED LEASE ROAD NORTH FROM
COUNTY LINE #2H TO PROPOSED LOCATION.

200 0 200 400 FEET
SCALE: 1" = 200'

CIMAREX ENERGY CO. OF COLORADO

REF: COUNTY LINE "1" FEDERAL #3H / WELL PAD TOPO


THE COUNTY LINE "1" FEDERAL #3H LOCATED 3300'
FROM THE SOUTH LINE AND 330' FROM THE EAST LINE OF
SECTION 1, TOWNSHIP 16 SOUTH, RANGE 29 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO.

BASIN SURVEYS P.O. BOX 1786-HOBBS, NEW MEXICO

W.O. Number: 19331 Drawn By: J. SMALL

Date: 03-11-2008 Disk: JMS 19331W

Survey Date: 03-06-2008 Sheet 1 of 1 Sheets



COUNTY LINE "1" FEDERAL #3H
 Located 3300' FSL and 330' FWL
 Section 1, Township 16 South, Range 29 East,
 N.M.P.M., Eddy County, New Mexico.

basin
surveys

focused on excellence
 in the oilfield

P.O. Box 1786
 1120 N. West County Rd.
 Hobbs, New Mexico 88241
 (505) 393-7316 - Office
 (505) 392-3074 - Fax
 basinsurveys.com


W.O. Number: JMS 19331T

Survey Date: 03-06-2008


Scale: 1" = 2000'

Date: 03-11-2008

CIMAREX
ENERGY CO.
OF COLORADO



COUNTY LINE "1" FEDERAL #3H
 Located 3300' FSL and 330' FEL
 Section 1, Township 16 South, Range 29 East,
 N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786
 1120 N. West County Rd.
 Hobbs, New Mexico 88241
 (505) 393-7316 - Office
 (505) 392-3074 - Fax
 basinsurveys.com

W.O. Number: JMS 19331TR

Survey Date: 03-06-2008

Scale: 1" = 2 MILES

Date: 03-11-2008

CIMAREX
 ENERGY CO.
 OF COLORADO

Application to Drill
Cimarex Energy Co. of Colorado
County Line 1 Federal No. 3
Lot 16, Section 1
T16S-R29E, Eddy County, NM

In response to questions asked under Section II B of Bulletin NTL-6, the following information is provided for your consideration:

- 1 Location: SHL 3300' FSL & 330' FEL
BHL 3300' FSL & 330' FEL
- 2 Elevation above sea level: 3,779 GR
- 3 Geologic name of surface formation: Quaternary Alluvium Deposits
- 4 Drilling tools and associated equipment: Conventional rotary drilling rig using fluid as a circulating medium for solids removal.
- 5 Proposed drilling depth: Pilot Hole 7,600' MD 11,885' TVD 7,380'
- 6 Estimated tops of geological markers:

Grayburg	2,260'
San Andres	2,625'
Abo Shale	6,120'
Lower Abo Dolomite	7,350'
Wolfcamp	7,440'
- 7 Possible mineral bearing formation:
Abo Oil

8 Proposed Mud Circulating System:

Depth		Mud Wt	Visc	Fluid Loss	Type Mud
0'	to 465' 340'	8.4 - 8.6	28	NC	FW
465' 340'	to 2650' 2,500'	10.0	30-32	NC	Brine water
2650' 2,500'	to 7,600'	8.4 - 9.5	30-32	NC	FW, brine
7,038'	to 7,538'	9.0	28-32	May lose circ	2% KCl
7,539'	to 11,885'	9.0	28-32	May lose circ	2% KCl

Sufficient mud materials will be kept on location at all times in order to combat lost circulation or unexpected kicks. In order to run DSTs, open hole logs, and casing, the viscosity and water loss may have to be adjusted in order to meet these needs.

Proposed drilling Plan

Drill 8 3/4" hole to 7,600' (pilot hole) and cement (see page 2 - Application to Drill). Set whipstock plug @ 7,170.' Mill window from 7,155' to 7,165.' Kick off 6 1/8" lateral @ 7,160.' Drill 6 1/8" hole to MD 11,885' and TVD 7,380.' Install 4 1/2" **Peak Completion Assembly**. BTC from 7,038' to 7,538.' LTC from 7,539' to 11,885.' Liner length 4,847.' Lateral drill hole length 4,616.'

Application to Drill
Cimarex Energy Co. of Colorado
County Line 1 Federal No. 3
Lot 16, Section 1
T16S-R29E, Eddy County, NM

9 Casing & Cementing Program:

SPE COAS

String	Hole Size	Depth	Type	Casing OD	Casing ID	Weight	Grade	Thread	Collar
Surface	17½"	0 to 340'	New	13⅝"	12.715#	48#	H-40	8-R	STC
Intermediate	12¼"	0 to 2,500'	New	9⅝"	8.835#	40#	J-55	8-R	LTC
Pilot Hole	8¾"	0 to 7,600'	New	7"	6.276#	26#	P-110	8-R	LTC
Lateral	6⅝"	7,038' to 7,538'	New	4½"	4"	11.6#	P-110	8-R	BTC
Lateral	6⅝"	7,539' to 11,885'	New	4½"	4"	11.6#	P-110	8-R	LTC

10 Cementing:

Surface Lead: 300 sx Thixotropic/Premium Plus + 10# Gilsonite + 10# Cal-Seal + 1% CaCl₂ + 0.125# Poly-e-flake (wt 14.2, yld 1.64)
Tail: 220 sk Premium Plus + 2% CaCl₂ (wt 14.8, yld 1.35)

TOC Surface

Intermediate Lead: 415 sx Interfill C + 0.125# Poly-e-flake (wt 11.9, yld 2.45)
Tail: 215 sx Premium Plus + 1% CaCl₂ (wt 14.8, yld 1.33)

TOC Surface

Pilot Hole 610 sx Super H + 0.5% Halad-344 + 0.4% CFR-3 + 1# Salt + 5#k Gilsonite + 0.125# Poly-e-flake + 0.35% HR-7 (wt 13.0, yld 1.67)

TOC 2300'

Lateral No cement needed. Peak completion assembly.

Fresh water zones will be protected by setting 13⅝" casing at 340' and cementing to surface. Hydrocarbon zones will be protected by setting 9⅝" casing at 2500' and cementing to surface, and by setting 7" casing at 7600' and cementing to 2300.'

<u>Collapse Factor</u>	<u>Burst Factor</u>	<u>Tension Factor</u>
1.125	1.125	1.6

11 Pressure control Equipment:

Exhibit "E". A 11" 5000 PSI working pressure B.O.P. consisting of one set of blind rams and one set of pipe rams and a 5000# annular type preventer. A choke manifold and 120 gallon accumulator with floor and remote operating stations and auxiliary power system. Rotating head below 6000.' A kelly cock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

BOP unit will be hydraulically operated. BOP will be nipped up and operated at least once a day while drilling and the blind rams will be operated when out of hole during trips. No abnormal pressure or temperature is expected while drilling. From the base of the surface pipe through the running of production casing, the well will be equipped with a 5000 psi BOP system.

We are requesting a variance for testing the 13⅝" surface casing from Onshore Order No. 2, which states that all casing strings below the conductor shall be pressure tested to 0.22 psi per foot or 1500 psi, whichever is greater, but not to exceed 70% of the manufacturer's stated maximum internal yield. We are requesting to test the 13⅝" casing to 1000 psi using rig pumps. The BOP will be tested to 3000 psi by an independent service company.

Application to Drill
Cimarex Energy Co. of Colorado
County Line 1 Federal No. 3
Lot 16, Section 1
T16S-R29E, Eddy County, NM

12 Testing, Logging and Coring Program:

- A. Mud logging 2 man unit from 5800' to TD
- B. Electric logging program: CNL / LDT / CAL / GR, DLL / CAL / GR
- C. No DSTs or cores are planned at this time.

13 Potential Hazards:

No abnormal pressures or temperatures are expected. In accordance with Onshore Order 6, Cimarex does not anticipate that there will be enough H₂S from the surface to the Strawn formations to meet the BLM's minimum requirements for the submission of an "H₂S Drilling Operation Plan" or "Public Protection Plan" for the drilling and completion of this well. Since we have an H₂S Safety package on all wells, attached is an "H₂S Drilling Operations Plan." Adequate flare lines will be installed off the mud / gas separator where gas may be flared safely. All personnel will be familiar with all aspects of safe operation of equipment being used.

Estimated BHP **2300 psi** Estimated BHT **110°**

14 Road and location construction will begin after BLM approval of APD. Anticipated spud date as soon as approved.

Drilling expected to take 25-35 days

If production casing is run an additional 30 days will be required to complete and construct surface facilities.

15 Other Facets of Operations:

After running casing, cased hole gamma ray neutron collar logs will be run from total depth over possible pay intervals.

Abo pay will be perforated and stimulated.

The proposed well will be tested and potentialized as **an oil well.**




DRILLING PROGNOSIS Cimarex Energy Company

4/3/2008

Well: County Line Fed Com #3
Location: 1-16S-29E
County, State: Eddy County, NM
Surface Location: 3300FSL,330FEL
Bottomhole Loc: 3300FSL,330FWL
E-Mail:
Wellhead:

Lse Serial #:
Field:
Objective:
TVD/MD: 7380 / 11885
Cementing: Halliburton
Mud: MI
Motors:
OH Logs
Rig: Key 880
Offset Wells:

Xmas Tree
Tubing: 2 7/8" L80 EUE
Superintendent: Dee Smith
Engineer: Mark Audas



NOTES:

Install wellhead on 13-3/8" and NU BOP. Test this installation to 1000 psi w/ rig pump. Then after setting 9-5/8" in slips and installing the csg spool, NU BOP (5M) w/ rotating head and test BOP to 5M w/ test unit. Test casing.
Cement volumes for surface csg include a 100% excess in the open hole section. If drilling conditions deem necessary, fluid caliper hole and adjust volumes.
Cement volumes for intermediate csg include a 70% excess in the open hole section. If drilling conditions deem necessary, fluid caliper hole and adjust volumes.
Cement volumes for production csg include a 25% excess in the open hole section. Adjust volumes after caliper + 25% excess.

ALL INVOICES ARE TO SHOW **CIMAREX ENERGY** AS OPERATOR AND USE CIMAREX ACCOUNTING CODES.



Planned Wellpath Report

Preliminary
Page 1 of 3



INTEQ

REFERENCE WELLPATH IDENTIFICATION

Operator	Cimarex Energy Co.	Slot	No. 3 SHL
Area	Eddy County, NM	Well	No. 3
Field	(County) Sec. 1, T16S, R29E	Wellbore	No. 3 PWB
Facility	County Line 1 Fed No. 3		

REPORT SETUP INFORMATION

Projection System	NAD83 / TM New Mexico State Planes, Eastern Zone (3001), US feet	Software System	WellArchitect® 2.0
North Reference	Grid	User	Victor Hernandez
Scale	0.99992	Report Generated	4/2/2008 at 10:26:53 AM
Convergence at slot	0.17° East	Database/Source file	WA_Midland/No. 3 PWB.xml

WELLPATH LOCATION

	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	East[ft]	Easting[USft]	Northing[USft]	Latitude	Longitude
Slot Location	0.00	0.00	637234.90	710381.30	32°57'08.844"N	104°01'14.523"W
Facility Reference Pt			637234.90	710381.30	32°57'08.844"N	104°01'14.523"W
Field Reference Pt			637234.90	710381.30	32°57'08.844"N	104°01'14.523"W

WELLPATH DATUM

Calculation method	Minimum curvature	Rig on No. 3 SHL (RT) to Facility Vertical Datum	18.00ft
Horizontal Reference Pt	Facility Center	Rig on No. 3 SHL (RT) to Mean Sea Level	3797.00ft
Vertical Reference Pt	Rig on No. 3 SHL (RT)	Facility Vertical Datum to Mud Line (Facility)	0.00ft
MD Reference Pt	Rig on No. 3 SHL (RT)	Section Origin	N 0.00, E 0.00 ft
Field Vertical Reference	Mean Sea Level	Section Azimuth	269.99°



INTEQ



Planned Wellpath Report

Preliminary
Page 2 of 3



INTEQ

REFERENCE WELLPATH IDENTIFICATION				
Operator	Cimarex Energy Co.	Slot	No. 3	SHL
Area	Eddy County, NM	Well	No. 3	
Field	(County) Sec. 1, T16S, R29E	Wellbore	No. 3	PWB
Facility	County Line 1 Fed No. 3			

WELLPATH DATA (55 stations) † = interpolated/extrapolated station								
MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	DLS [°/100ft]	Comments
0.00	0.000	269.994	0.00	0.00	0.00	0.00	0.00	Tie On
2260.00†	0.000	269.994	2260.00	0.00	0.00	0.00	0.00	GRAYBURG
2625.00†	0.000	269.994	2625.00	0.00	0.00	0.00	0.00	SAN ANDRES
6120.00†	0.000	269.994	6120.00	0.00	0.00	0.00	0.00	ABO SHALE
7160.00†	0.000	269.994	7160.00	0.00	0.00	0.00	0.00	KOP
7260.00†	30.000	269.994	7255.49	25.59	0.00	-25.59	30.00	
7360.00†	60.000	269.994	7325.40	95.49	-0.01	-95.49	30.00	
7440.59†	84.176	269.994	7350.00	171.60	-0.02	-171.60	30.00	LOWER ABO DOLOMITE
7458.75	89.624	269.994	7350.98	189.73	-0.02	-189.73	30.00	EOC
7460.00†	89.624	269.994	7350.99	190.99	-0.02	-190.99	0.00	
7560.00†	89.624	269.994	7351.65	290.98	-0.03	-290.98	0.00	
7660.00†	89.624	269.994	7352.30	390.98	-0.04	-390.98	0.00	
7760.00†	89.624	269.994	7352.96	490.98	-0.06	-490.98	0.00	
7860.00†	89.624	269.994	7353.61	590.98	-0.07	-590.98	0.00	
7960.00†	89.624	269.994	7354.27	690.98	-0.08	-690.98	0.00	
8060.00†	89.624	269.994	7354.92	790.97	-0.09	-790.97	0.00	
8160.00†	89.624	269.994	7355.58	890.97	-0.10	-890.97	0.00	
8260.00†	89.624	269.994	7356.24	990.97	-0.11	-990.97	0.00	
8360.00†	89.624	269.994	7356.89	1090.97	-0.12	-1090.97	0.00	
8460.00†	89.624	269.994	7357.55	1190.96	-0.13	-1190.96	0.00	
8560.00†	89.624	269.994	7358.20	1290.96	-0.15	-1290.96	0.00	
8660.00†	89.624	269.994	7358.86	1390.96	-0.16	-1390.96	0.00	
8760.00†	89.624	269.994	7359.51	1490.96	-0.17	-1490.96	0.00	
8860.00†	89.624	269.994	7360.17	1590.96	-0.18	-1590.96	0.00	
8960.00†	89.624	269.994	7360.82	1690.95	-0.19	-1690.95	0.00	
9060.00†	89.624	269.994	7361.48	1790.95	-0.20	-1790.95	0.00	
9160.00†	89.624	269.994	7362.14	1890.95	-0.21	-1890.95	0.00	
9260.00†	89.624	269.994	7362.79	1990.95	-0.23	-1990.95	0.00	
9360.00†	89.624	269.994	7363.45	2090.95	-0.24	-2090.95	0.00	
9460.00†	89.624	269.994	7364.10	2190.94	-0.25	-2190.94	0.00	
9560.00†	89.624	269.994	7364.76	2290.94	-0.26	-2290.94	0.00	
9660.00†	89.624	269.994	7365.41	2390.94	-0.27	-2390.94	0.00	
9760.00†	89.624	269.994	7366.07	2490.94	-0.28	-2490.94	0.00	
9860.00†	89.624	269.994	7366.73	2590.93	-0.29	-2590.93	0.00	
9960.00†	89.624	269.994	7367.38	2690.93	-0.30	-2690.93	0.00	
10060.00†	89.624	269.994	7368.04	2790.93	-0.32	-2790.93	0.00	
10160.00†	89.624	269.994	7368.69	2890.93	-0.33	-2890.93	0.00	
10260.00†	89.624	269.994	7369.35	2990.93	-0.34	-2990.93	0.00	
10360.00†	89.624	269.994	7370.00	3090.92	-0.35	-3090.92	0.00	
10460.00†	89.624	269.994	7370.66	3190.92	-0.36	-3190.92	0.00	
10560.00†	89.624	269.994	7371.32	3290.92	-0.37	-3290.92	0.00	
10660.00†	89.624	269.994	7371.97	3390.92	-0.38	-3390.92	0.00	
10760.00†	89.624	269.994	7372.63	3490.91	-0.40	-3490.91	0.00	
10860.00†	89.624	269.994	7373.28	3590.91	-0.41	-3590.91	0.00	
10960.00†	89.624	269.994	7373.94	3690.91	-0.42	-3690.91	0.00	

INTEQ



Planned Wellpath Report

Preliminary
Page 3 of 3



INTEQ

REFERENCE WELLPATH IDENTIFICATION				
Operator	Cimarex Energy Co.	Slot	No. 3	SHL
Area	Eddy County, NM	Well	No. 3	
Field	(County) Sec. 1, T16S, R29E	Wellbore	No. 3	PWB
Facility	County Line 1 Fed No. 3			

WELLPATH DATA (55 stations) † = interpolated/extrapolated station								
MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	DLS [°/100ft]	Comments
11060.00†	89.624	269.994	7374.59	3790.91	-0.43	-3790.91	0.00	
11160.00†	89.624	269.994	7375.25	3890.91	-0.44	-3890.91	0.00	
11260.00†	89.624	269.994	7375.90	3990.90	-0.45	-3990.90	0.00	
11360.00†	89.624	269.994	7376.56	4090.90	-0.46	-4090.90	0.00	
* 11460.00†	89.624	269.994	7377.22	4190.90	-0.47	-4190.90	0.00	
11560.00†	89.624	269.994	7377.87	4290.90	-0.49	-4290.90	0.00	
11660.00†	89.624	269.994	7378.53	4390.90	-0.50	-4390.90	0.00	
11760.00†	89.624	269.994	7379.18	4490.89	-0.51	-4490.89	0.00	
11860.00†	89.624	269.994	7379.84	4590.89	-0.52	-4590.89	0.00	
11884.57	89.624	269.994	7380.00†	4615.47	-0.52	-4615.47	0.00	No. 3H BHL

TARGETS									
Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [srv ft]	Grid North [srv ft]	Latitude	Longitude	Shape
1) No. 3 BHL	11884.57	7380.00	-0.52	-4615.47	632619.81	710380.78	32°57'08.971"N	104°02'08.686"W	point

SURVEY PROGRAM Ref Wellbore: No. 3H PWB Ref Wellpath: Preliminary				
Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
18.00	11884.57	NaviTrak (Standard)		No. 3 PWB





Cimarex Energy Co.



Location: Eddy County, NM
Field: (County) Sec. 1, T16S, R29E
Facility: County Line 1 Fed No. 3.

Slot: No. 3i SHL
Well: No. 3.
Wellbore: No. 3. PWB

Plot reference wellpath is Preliminary	
True vertical depths are referenced to Rig on No. 3H SHL (RT)	Grid System: NAD83 / TM New Mexico State Planes Eastern Zone (3081) US feet
Measured depths are referenced to Rig on No. 3H SHL (RT)	North Reference: Grid north
Rig on No. 3H SHL (RT) to Mean Sea Level: 3797 feet	Scale: True distance
Mean Sea Level to Mud Line (Facility: County Line 1 Fed No. 3H) -3779 feet	Depths are in feet
Coordinates are in feet referenced to Facility Center	Created by: Victor Hernandez on 4/2/2008



Well Profile Data								
Design Comment	MD (ft)	Inc (°)	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)	VS (ft)
Tie On	0.00	0.000	269.994	0.00	0.00	0.00	0.00	0.00
KOP	7160.00	0.000	269.994	7160.00	0.00	0.00	0.00	0.00
EOC	7458.75	89.624	269.994	7350.98	-0.02	-189.73	30.00	189.73
No. 3. BHL	11884.57	89.624	269.994	7380.00	-0.52	-4615.47	0.00	4615.47



PROPOSED WELLPATH REPORT (CSV version)

Prepared by Baker Hughes INTEQ

Software System: WellArchitect®2.0

REFERENCE WELLPATH IDENTIFICATION

Operator Cimarex Energy Co.
 Area Eddy County, NM
 Field (County) Sec. 1, T16S, R29E
 Facility County Line 1 Fed No. 3
 Slot No. 3 SHL
 Well No. 3
 Wellbore No. 3 PWB
 Wellpath Preliminary
 Sidetrack (none)

REPORT SETUP INFORMATION

Projection NAD83 / TM New Mexico State Planes, Eastern Zone (3001), US feet
 North Refe Grid
 Scale 0.99992
 Convergen 0.17° East
 Software S WellArchitect®
 User Victor Hernandez
 Report Gei 4/2/2008 at 10:24:57 AM
 DataBase/ WA_Midland/ev1617.xml

WELLPAT	Local North	Local East	Grid East	Grid North	Latitude	Longitude
	[ft]	[ft]	[ft]	[ft]		
Slot Locati	0	0	637234.9	710381.3	32°57'08.8	104°01'14.523"W
Facility Ref			637234.9	710381.3	32°57'08.8	104°01'14.523"W
Field Refer			637234.9	710381.3	32°57'08.8	104°01'14.523"W

WELLPATH DATUM

Calculation Minimum curvature
 Horizontal Facility Center
 Vertical Re Rig on No. 3 SHL (RT)
 MD Refere Rig on No. 3 SHL (RT)
 Field Vertic Mean Sea Level
 Rig on No. 18.00ft
 Rig on No. 3797.00ft
 Facility Ver 0.00ft
 Section Or 0.00ft
 Section Or 0.00ft
 Section Az 269.99°

WELLPATH	DATA	Wellbore: No. 3 PWB	Wellpath: Preliminary	† = interpolated/extrapolated station					
	MD	Inclination	Azimuth	TVD	Vert Sect	North	East	DLS	Comments
	[ft]	[°]	[°]	[ft]	[ft]	[ft]	[ft]	[°/100ft]	
†	0	0	269.994	0	0	0	0	0	Tie On
†	100	0	269.994	100	0	0	0	0	
†	200	0	269.994	200	0	0	0	0	
†	300	0	269.994	300	0	0	0	0	
†	400	0	269.994	400	0	0	0	0	
†	500	0	269.994	500	0	0	0	0	
†	600	0	269.994	600	0	0	0	0	
†	700	0	269.994	700	0	0	0	0	
†	800	0	269.994	800	0	0	0	0	
†	900	0	269.994	900	0	0	0	0	
†	1000	0	269.994	1000	0	0	0	0	
†	1100	0	269.994	1100	0	0	0	0	
†	1200	0	269.994	1200	0	0	0	0	
†	1300	0	269.994	1300	0	0	0	0	
†	1400	0	269.994	1400	0	0	0	0	
†	1500	0	269.994	1500	0	0	0	0	
†	1600	0	269.994	1600	0	0	0	0	
†	1700	0	269.994	1700	0	0	0	0	
†	1800	0	269.994	1800	0	0	0	0	
†	1900	0	269.994	1900	0	0	0	0	
†	2000	0	269.994	2000	0	0	0	0	

†	2100	0	269.994	2100	0	0	0	0	
†	2200	0	269.994	2200	0	0	0	0	
†	2260	0	269.994	2260	0	0	0	0	GRAYBURG
†	2300	0	269.994	2300	0	0	0	0	
†	2400	0	269.994	2400	0	0	0	0	
†	2500	0	269.994	2500	0	0	0	0	
†	2600	0	269.994	2600	0	0	0	0	
†	2625	0	269.994	2625	0	0	0	0	SAN ANDRES
†	2700	0	269.994	2700	0	0	0	0	
†	2800	0	269.994	2800	0	0	0	0	
†	2900	0	269.994	2900	0	0	0	0	
†	3000	0	269.994	3000	0	0	0	0	
†	3100	0	269.994	3100	0	0	0	0	
†	3200	0	269.994	3200	0	0	0	0	
†	3300	0	269.994	3300	0	0	0	0	
†	3400	0	269.994	3400	0	0	0	0	
†	3500	0	269.994	3500	0	0	0	0	
†	3600	0	269.994	3600	0	0	0	0	
†	3700	0	269.994	3700	0	0	0	0	
†	3800	0	269.994	3800	0	0	0	0	
†	3900	0	269.994	3900	0	0	0	0	
†	4000	0	269.994	4000	0	0	0	0	
†	4100	0	269.994	4100	0	0	0	0	
†	4200	0	269.994	4200	0	0	0	0	
†	4300	0	269.994	4300	0	0	0	0	
†	4400	0	269.994	4400	0	0	0	0	
†	4500	0	269.994	4500	0	0	0	0	
†	4600	0	269.994	4600	0	0	0	0	
†	4700	0	269.994	4700	0	0	0	0	
†	4800	0	269.994	4800	0	0	0	0	
†	4900	0	269.994	4900	0	0	0	0	
†	5000	0	269.994	5000	0	0	0	0	
†	5100	0	269.994	5100	0	0	0	0	
†	5200	0	269.994	5200	0	0	0	0	
†	5300	0	269.994	5300	0	0	0	0	
†	5400	0	269.994	5400	0	0	0	0	
†	5500	0	269.994	5500	0	0	0	0	
†	5600	0	269.994	5600	0	0	0	0	
†	5700	0	269.994	5700	0	0	0	0	
†	5800	0	269.994	5800	0	0	0	0	
†	5900	0	269.994	5900	0	0	0	0	
†	6000	0	269.994	6000	0	0	0	0	
†	6100	0	269.994	6100	0	0	0	0	
†	6120	0	269.994	6120	0	0	0	0	ABO SHALE
†	6200	0	269.994	6200	0	0	0	0	
†	6300	0	269.994	6300	0	0	0	0	
†	6400	0	269.994	6400	0	0	0	0	
†	6500	0	269.994	6500	0	0	0	0	
†	6600	0	269.994	6600	0	0	0	0	
†	6700	0	269.994	6700	0	0	0	0	
†	6800	0	269.994	6800	0	0	0	0	
†	6900	0	269.994	6900	0	0	0	0	
†	7000	0	269.994	7000	0	0	0	0	
†	7100	0	269.994	7100	0	0	0	0	
†	7160	0	269.994	7160	0	0	0	0	KOP
†	7200	12	269.994	7199.71	4.17	0	-4.17	30	
†	7300	42	269.994	7287.79	49.06	-0.01	-49.06	30	
†	7400	72	269.994	7341.64	131.97	-0.01	-131.97	30	
†	7440.59	84.176	269.994	7350	171.6	-0.02	-171.6	30	LOWER ABO DOLOMITE
†	7458.75	89.624	269.994	7350.98	189.73	-0.02	-189.73	30	EOC
†	7500	89.624	269.994	7351.25	230.99	-0.03	-230.99	0	
†	7600	89.624	269.994	7351.91	330.98	-0.04	-330.98	0	
†	7700	89.624	269.994	7352.56	430.98	-0.05	-430.98	0	
†	7800	89.624	269.994	7353.22	530.98	-0.06	-530.98	0	
†	7900	89.624	269.994	7353.87	630.98	-0.07	-630.98	0	
†	8000	89.624	269.994	7354.53	730.97	-0.08	-730.97	0	
†	8100	89.624	269.994	7355.19	830.97	-0.09	-830.97	0	
†	8200	89.624	269.994	7355.84	930.97	-0.11	-930.97	0	
†	8300	89.624	269.994	7356.5	1030.97	-0.12	-1030.97	0	

†	8400	89.624	269.994	7357.15	1130.97	-0.13	-1130.97	0	
†	8500	89.624	269.994	7357.81	1230.96	-0.14	-1230.96	0	
†	8600	89.624	269.994	7358.46	1330.96	-0.15	-1330.96	0	
†	8700	89.624	269.994	7359.12	1430.96	-0.16	-1430.96	0	
†	8800	89.624	269.994	7359.78	1530.96	-0.17	-1530.96	0	
†	8900	89.624	269.994	7360.43	1630.95	-0.18	-1630.95	0	
†	9000	89.624	269.994	7361.09	1730.95	-0.2	-1730.95	0	
†	9100	89.624	269.994	7361.74	1830.95	-0.21	-1830.95	0	
†	9200	89.624	269.994	7362.4	1930.95	-0.22	-1930.95	0	
†	9300	89.624	269.994	7363.05	2030.95	-0.23	-2030.95	0	
†	9400	89.624	269.994	7363.71	2130.94	-0.24	-2130.94	0	
†	9500	89.624	269.994	7364.37	2230.94	-0.25	-2230.94	0	
†	9600	89.624	269.994	7365.02	2330.94	-0.26	-2330.94	0	
†	9700	89.624	269.994	7365.68	2430.94	-0.28	-2430.94	0	
†	9800	89.624	269.994	7366.33	2530.94	-0.29	-2530.94	0	
†	9900	89.624	269.994	7366.99	2630.93	-0.3	-2630.93	0	
†	10000	89.624	269.994	7367.64	2730.93	-0.31	-2730.93	0	
†	10100	89.624	269.994	7368.3	2830.93	-0.32	-2830.93	0	
†	10200	89.624	269.994	7368.95	2930.93	-0.33	-2930.93	0	
†	10300	89.624	269.994	7369.61	3030.92	-0.34	-3030.92	0	
†	10400	89.624	269.994	7370.27	3130.92	-0.35	-3130.92	0	
†	10500	89.624	269.994	7370.92	3230.92	-0.37	-3230.92	0	
†	10600	89.624	269.994	7371.58	3330.92	-0.38	-3330.92	0	
†	10700	89.624	269.994	7372.23	3430.92	-0.39	-3430.92	0	
†	10800	89.624	269.994	7372.89	3530.91	-0.4	-3530.91	0	
†	10900	89.624	269.994	7373.54	3630.91	-0.41	-3630.91	0	
†	11000	89.624	269.994	7374.2	3730.91	-0.42	-3730.91	0	
†	11100	89.624	269.994	7374.86	3830.91	-0.43	-3830.91	0	
†	11200	89.624	269.994	7375.51	3930.91	-0.45	-3930.91	0	
†	11300	89.624	269.994	7376.17	4030.9	-0.46	-4030.9	0	
†	11400	89.624	269.994	7376.82	4130.9	-0.47	-4130.9	0	
†	11500	89.624	269.994	7377.48	4230.9	-0.48	-4230.9	0	
†	11600	89.624	269.994	7378.13	4330.9	-0.49	-4330.9	0	
†	11700	89.624	269.994	7378.79	4430.89	-0.5	-4430.89	0	
†	11800	89.624	269.994	7379.45	4530.89	-0.51	-4530.89	0	
	11884.57	89.624	269.994	7380	4615.47	-0.52	-4615.47	0	No. 3 BHL 1

T A R G E T S

Name	MD	TVD	North	East	Grid East	Grid North	Latitude	Longitude	Shape	Comment	Design Comments
	[ft]	[ft]	[ft]	[ft]	[srv ft]	[srv ft]					
(1) No. 3 B	11884.57	7380	-0.52	-4615.47	632619.8	710380.8	32°57'08.9	104°02'08.	point		


SURVEY PROGRAM Ref Wellbore: No. 3 PWB Ref Wellpath: Preliminary

Start MD End MD Pos Unc M Log Name/ Wellbore

[ft] [ft]
18 11884.57 NaviTrak (Standard) No. 3 PWB

Key Rig 880


Cimarex Energy Co. of Colorado



- Wind Direction Indicators
(wind sock or streamers)
- △ H2S Monitors
(alarms at bell nipple and shale shaker)
- Briefing Areas
- Remote BOP Closing Unit

Exhibit D – Rig Layout
County Line 1 Federal No. 3
 Cimarex Energy Co. of Colorado
 1-16S-29E
 SHL 3300' FSL & 330' FEL
 BHL 3300' FSL & 330' FWL
 Eddy County, NM

SR & A



**DRILLING OPERATIONS
CHOKE MANIFOLD
5M SERVICE**




Exhibit E-1 – Choke Manifold Diagram
County Line 1 Federal No. 3
 Cimarex Energy Co. of Colorado
 1-16S-29E
 SHL 3300' FSL & 330' FEL
 BHL 3300' FSL & 330' FWL
 Eddy County, NM

Hydrogen Sulfide Drilling Operations Plan
Cimarex Energy Co. of Colorado
County Line 1 Federal No. 3
Lot 16, Section 1
T16S-R29E, Eddy County, NM

- 1 All Company and Contract personnel admitted on location must be trained by a qualified H₂S safety instructor to the following:
 - A. Characteristics of H₂S
 - B. Physical effects and hazards
 - C. Proper use of safety equipment and life support systems.
 - D. Principle and operation of H₂S detectors, warning system and briefing areas.
 - E. Evacuation procedure, routes and first aid.
 - F. Proper use of 30 minute pressure demand air pack.
- 2 H₂S Detection and Alarm Systems:
 - A. H₂S detectors and audio alarm system to be located at bell nipple, end of flow line (mud pit) and on derrick floor or doghouse.
- 3 Windsock and/or wind streamers:
 - A. Windsock at mudpit area should be high enough to be visible.
 - B. Windsock at briefing area should be high enough to be visible.
- 4 Condition Flags and Signs:
 - A. Warning sign on access road to location.
 - B. Flags to be displayed on sign at entrance to location. Green flag indicates normal safe condition. Yellow flag indicates potential pressure and danger. Red flag indicates danger (H₂S present in dangerous concentration). Only emergency personnel admitted to location.
- 5 Well control equipment:
 - A. See exhibit "E"
- 6 Communication:
 - A. While working under masks chalkboards will be used for communication.
 - B. Hand signals will be used where chalk board is inappropriate.
 - C. Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.
- 7 Drillstem Testing:

No DSTs or cores are planned at this time.
- 8 Drilling contractor supervisor will be required to be familiar with the effects H₂S has on tubular goods and other mechanical equipment.
- 9 If H₂S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H₂S scavengers if necessary.

H₂S Contingency Plan
Cimarex Energy Co. of Colorado
County Line 1 Federal No. 3
Lot 16, Section 1
T16S-R29E, Eddy County, NM

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must:

- ★ Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- ★ Evacuate any public places encompassed by the 100 ppm ROE.
- ★ Be equipped with H₂S monitors and air packs in order to control the release.
- ★ Use the "buddy system" to ensure no injuries occur during the response.
- ★ Take precautions to avoid personal injury during this operation.
- ★ Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- ★ Have received training in the:
 - ◆ Detection of H₂S, and
 - ◆ Measures for protection against the gas,
 - ◆ Equipment used for protection and emergency response.

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H ₂ S	1.189 Air=1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO ₂	2.21 Air=1	2 ppm	N/A	1000 ppm

Contacting Authorities

Cimarex Energy Co. of Colorado's personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. Cimarex Energy Co. of Colorado's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

H₂S Contingency Plan Emergency Contacts
Cimarex Energy Co. of Colorado
 County Line 1 Federal No. 3
 Lot 16, Section 1
 T16S-R29E, Eddy County, NM

<u>Company Office</u>			
Cimarex Energy Co. of Colorado		800-969-4789	
Co. Office and After-Hours Menu			
<u>Key Personnel</u>			
Name	Title	Office	Mobile
Doug Park	Drilling Manager	972-443-6463	972-333-1407
Dee Smith	Drilling Super	972-443-6491	972-882-1010
Jim Evans	Drilling Super	972-443-6451	972-465-6564
Dorsey Rogers	Field Super		505-200-6105
Roy Shirley	Field Super		432-634-2136
<u>Artesia</u>			
Ambulance		911	
State Police		575-746-2703	
City Police		575-746-2703	
Sheriff's Office		575-746-9888	
Fire Department		575-746-2701	
Local Emergency Planning Committee		575-746-2122	
New Mexico Oil Conservation Division		575-748-1283	
<u>Carlsbad</u>			
Ambulance		911	
State Police		575-885-3137	
City Police		575-885-2111	
Sheriff's Office		575-887-7551	
Fire Department		575-887-3798	
Local Emergency Planning Committee		575-887-6544	
US Bureau of Land Management		575-887-6544	
<u>Santa Fe</u>			
New Mexico Emergency Response Commission (Santa Fe)		505-476-9600	
New Mexico Emergency Response Commission (Santa Fe) 24 Hrs		505-827-9126	
New Mexico State Emergency Operations Center		505-476-9635	
<u>National</u>			
National Emergency Response Center (Washington, D.C.)		800-424-8802	
<u>Medical</u>			
Flight for Life - 4000 24th St.; Lubbock, TX		806-743-9911	
Aerocare - R3, Box 49F; Lubbock, TX		806-747-8923	
Med Flight Air Amb - 2301 Yale Blvd S.E., #D3; Albuquerque, NM		505-842-4433	
SB Air Med Service - 2505 Clark Carr Loop S.E.; Albuquerque, NM		505-842-4949	
<u>Other</u>			
Boots & Coots IWC		800-256-9688	or 281-931-8884
Cudd Pressure Control		432-699-0139	or 432-563-3356
Halliburton		575-746-2757	
B.J. Services		575-746-3569	

Surface Use Plan
Cimarex Energy Co. of Colorado
County Line 1 Federal No. 3
Lot 16, Section 1
T16S-R29E, Eddy County, NM

- 1 Existing Roads: Area maps, Exhibit "B" is a reproduction of Eddy Co. General Highway Map. Exhibit "C" is a reproduction of a USGS Topographic Map, showing existing roads and proposed roads. All existing roads will be maintained in a condition equal to or better than current conditions. Any new roads will be constructed to BLM specifications.
 - A. Exhibit "A" shows the proposed well site as staked.
 - B. Follow proposed lease road North from the County Line 1 Fed #2 to the proposed location.
- 2 Planned Access Roads: 2339.8' of on-lease access road is proposed.
- 3 Location of Existing Wells in a One-Mile Radius - Exhibit A
 - A. Water wells - None known
 - B. Disposal wells - None known
 - C. Drilling wells - None known
 - D. Producing wells - As shown on Exhibit "A"
 - E. Abandoned wells - As shown on Exhibit "A"
- 4 If on completion this well is a producer, Cimarex Energy Co. of Colorado will furnish maps and/or plats showing on site facilities or off site facilities if needed. This will be accompanied by a Sundry Notice.
- 5 Location and Type of Water Supply:

Water will be purchased locally from a commercial source and trucked over the access roads or piped in flexible lines laid on top of the ground.
- 6 Source of Construction Material:

If possible, construction will be obtained from the excavation of drill site. If additional material is needed, it will be purchased from a local source and transported over the access route as shown on Exhibit "C".

Surface Use Plan
Cimarex Energy Co. of Colorado
County Line 1 Federal No. 3
Lot 16, Section 1
T16S-R29E, Eddy County, NM

7 Methods of Handling Waste Material:

- A. Drill cuttings will be separated by a series of solids removal equipment and stored in steel containment pits and then hauled to a state-approved disposal facility.
- B. All trash, junk and other waste material will be contained in trash cages or bins to prevent scattering. When the job is completed all contents will be removed and disposed of in an approved sanitary land fill.
- C. Salts remaining after completion of well will be picked up by supplier including broken sacks.
- D. Sewage from living quarters will drain into holding tanks and be cleaned out periodically. A Porta-John will be provided for the rig crews. This equipment will be properly maintained during the drilling operations and removed upon completion of the well.
- E. Drilling fluids will be contained in steel pits in a closed circulating system. Fluids will be cleaned and reused. Water produced during testing will be contained in the steel pits and disposed of at a state approved disposal facility. Any oil or condensate produced will be stored in test tanks until sold and hauled from the site.

8 Ancillary Facilities:

- A. No camps or airstrips to be constructed.

9 Well Site Layout:

- A. Exhibit "D" shows location and rig layout.
- C. Mud pits in the closed circulating system will be steel pits and the cuttings will be stored in steel containment pits.
- D. Cuttings will be stored in steel pits until they are hauled to a state-approved disposal facility.
- E. If the well is a producer, those areas of the location not essential to production facilities will be reclaimed and seeded per BLM requirements.

10 Plans for Restoration of Surface:

Rehabilitation of the location will start in a timely manner after all drilling operations cease. The type of reclamation will depend on whether the well is a producer or a dry hole.

Drainage systems, if any, will be reshaped to the original configuration with provisions made to alleviate erosion. These may need to be modified in certain circumstances to prevent inundation of the location's pad and surface facilities. After the area has been shaped and contoured, topsoil from the spoil pile will be placed over the disturbed area to the extent possible. Revegetation procedures will comply with BLM standards.

If the well is a dry hole, the pad and road area will be recountoured to match the existing terrain. Topsoil will be spread to the extent possible. Revegetation will comply with BLM standards.

Should the well be a producer, the previously noted procedures will apply to those areas which are not required for production facilities.

Surface Use Plan
Cimarex Energy Co. of Colorado
County Line 1 Federal No. 3
Lot 16, Section 1
T16S-R29E, Eddy County, NM

11 Other Information

- A. Topography consists of a sloping plane with loose tan sands. Vegetation is mainly yucca, mesquite and shin oak.
- B. The wellsite is on surface owned by the Department of the Interior, Bureau of Land Management. The land is used mainly for farming, cattle ranching, recreational use, and oil and gas production.
- C. An Archaeological survey will be conducted on the location and proposed roads, and this report will be filed with the Bureau of Land Management in the Carlsbad BLM office.
- D. There are no know dwellings within 1½ miles of this location.


Operator Certification Statement
Cimarex Energy Co. of Colorado
County Line 1 Federal No. 3
Lot 16, Section 1
T16S-R29E, Eddy County, NM


Operator's Representative

Cimarex Energy Co. of Colorado
P.O. Box 140907
Irving, TX 75014
Office Phone: (972) 443-6489
Zeno Farris

CERTIFICATION: I hereby certify that the statements and plans made in this APD are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Cimarex Energy Co. of Colorado and/or its contractors/subcontractors and is in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provision of U.S.C. 1001 for the filing of a false statement.

NAME: Zeno Farris
Zeno Farris
DATE: April 3, 2008
TITLE: Manager Operations Administration





COUNTY LINE "1" FEDERAL #3
 Located 3300' FSL and 330' FEL
 Section 1, Township 16 South, Range 29 East,
 N.M.P.M., Eddy County, New Mexico.

basin
surveys
 focused on excellence
 in the oilfield

P.O. Box 1786
 1120 N. West County Rd.
 Hobbs, New Mexico 88241
 (505) 393-7316 - Office
 (505) 392-3074 - Fax
 basin-surveys.com

W.O. Number: JMS 19331TR


Survey Date: 03-06-2008

Scale: 1" = 2 MILES

Date: 03-11-2008

CIMAREX
ENERGY CO.
OF COLORADO

Exhibit B



COUNTY LINE "1" FEDERAL #3 *E BK*
 Located 3300' FSL and 330' FWL
 Section 1, Township 16 South, Range 29 East,
 N.M.P.M., Eddy County, New Mexico. *C.L. 07/24/08*

basin
surveys
 focused on excellence
 in the oilfield

P.O. Box 1786
 1120 N. West County Rd.
 Hobbs, New Mexico 88241
 (505) 393-7316 - Office
 (505) 392-3074 - Fax
 basinsurveys.com

W.O. Number: JMS 19331T

Survey Date: 03-06-2008

Scale: 1" = 2000'

Date: 03-11-2008

CIMAREX
ENERGY CO.
OF COLORADO

Exhibit C

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	CIMAREX ENERGY CO OF COLORADO
LEASE NO.:	LC-061622
WELL NAME & NO.:	County Line 1 Federal No. 3
SURFACE HOLE FOOTAGE:	4080' FSL & 330' FEL
BOTTOM HOLE FOOTAGE:	Lateral 1: 4951' FSL & 330' FWL Lateral 2: 2971' FSL & 330' FWL
LOCATION:	Section 1, T. 16 S., R. 29 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Lesser Prairie Chicken
- ☒ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☒ **Road Section Diagram**
- ☒ **Drilling**
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- ☒ **Interim Reclamation**
- ☐ **Final Abandonment/Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Mitigation Measures: The mitigation measures include the Pecos District Conditions of Approval, the standard stipulations for the Lesser Prairie Chicken, and the standard stipulation for permanent resource roads.

Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken: Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

County Line 1 Federal # 3: Closed Loop V-Door East

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (505) 234-5972 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall stockpile the topsoil of the well pad. The topsoil shall not be used to backfill the reserve pit and will be used for interim and final reclamation.

C. Closed Loop System

County Line 1 Federal # 3: Closed Loop V-Door East

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

If the operator elects to surface the access road and/or well pad, mineral materials extracted during construction of the reserve pit may be used for surfacing the well pad and access road and other facilities on the lease.

Payment shall be made to the BLM prior to removal of any additional federal mineral materials from any site other than the reserve pit. Call the Carlsbad Field Office at (505) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed thirty (30) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning


Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:



Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and inslaping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Culvert Installations

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.

Fence Requirement


Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Figure 1 – Cross Sections and Plans For Typical Road Sections



VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of **4 hours** in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOP/BOPE tests

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. **Although Hydrogen Sulfide has not been reported in this section, it is always a potential hazard. It has been reported in T16S R30E, Sections 14 and 24. If Hydrogen Sulfide is encountered, please report measured amounts and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

B. CASING

Changes to the approved APD casing and cement program require submitting a sundry and receiving approval prior to work. Failure to obtain approval prior to work will result in an Incident of Non-Compliance being issued.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Possible lost circulation in Grayburg, San Andres

Possible H₂O flows in Salado and Artesia Group

Possible high pressure gas bursts from the Wolfcamp Formation – applicable to pilot hole

1. The 13-3/8 inch surface casing shall be set at **approximately 465 feet** and cemented to the surface. **If salt is encountered at a depth less than 465 feet, surface casing should be set 25 feet above the top of the salt. Fresh water mud shall be used to setting depth.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement.
 - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
 - ☒ Cement to surface. If cement does not circulate see B.1.a-d above. **Casing to be set at approximately 2650' within the San Andres formation. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**

Formation below the 9-5/8 shoe to be tested according to Onshore Order 2.III.B.1.i
Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole. Report results to BLM office.

3. The minimum required fill of cement behind the 7 inch pilot hole casing is:
 - ☒ Cement should tie-back at least 200 feet into previous casing string. **Operator shall provide method of verification.**

Formation below the kick off point to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe and the mud weight for the bottom of the hole. Report results to BLM office.

Tag cement at bottom of pilot hole and report on subsequent report.

NOTE: Pilot hole will require proper plug when well is plugged.

4. The minimum required fill of cement behind the 4-1/2 inch production casing is:

- ☒ Not required as operator is using Peak Iso-Pak liner. Seal on Peak Systems Iso-Pack liner is to be tested per Onshore Oil and Gas Order 2.III.B.1.b. Please call BLM for witness of seal test.

5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. The appropriate BLM office shall be notified a minimum of **4 hours** in advance for a representative to witness the tests.
 - a. The tests shall be done by an independent service company.
 - b. The results of the test shall be reported to the appropriate BLM office.
 - c. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
 - d. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.
 - e. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation **if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days**. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

- f. A variance to test only the surface casing to the reduced pressure of 1000 psi with the rig pumps is approved. **The BOP will be tested to 3000 psi by an independent service company.**

D. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

E. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

LB 5/16/08 – **WWI 090408**

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Containment Structures

The containment structure shall be constructed to hold the capacity of the entire contents of the largest tank, plus 24 hour production, unless more stringent protective requirements are deemed necessary by the Authorized Officer.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color
Shale Green, Munsell Soil Color Chart # 5Y 4/2

B. PIPELINES

C. ELECTRIC LINES

IX. INTERIM RECLAMATION & RESERVE PIT CLOSURE

A. INTERIM RECLAMATION

If the well is a producer, interim reclamation shall be conducted on the well site in accordance with the orders of the Authorized Officer. The operator shall submit a Sundry Notices and Reports on Wells (Notice of Intent), Form 3160-5, prior to conducting interim reclamation.

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

The operators should work with BLM surface management specialists to devise the best strategies to reduce the size of the location. Any reductions should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

Seed Mixture 2, for Sandy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law (s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Sand dropseed (<i>Sporobolus cryptandrus</i>)	1.0
Sand love grass (<i>Eragrostis trichodes</i>)	1.0
Plains bristlegrass (<i>Setaria macrostachya</i>)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

X. FINAL ABANDONMENT & REHABILITATION REQUIREMENTS

Upon abandonment of the well and/or when the access road is no longer in service the Authorized Officer shall issue instructions and/or orders for surface reclamation and restoration of all disturbed areas.

On private surface/federal mineral estate land the reclamation procedures on the road and well pad shall be accomplished in accordance with the private surface land owner agreement.