

Operator Black Mountain Corp.
 Well Arbel Federal #2
 Unit I Section 30 Township 17 Range 29
 API # 30-015-10341

TOPS

Salado	494
B. Salt	609
Yates	830
N. Rivers	1090
Bowen	1477
Queen	1714
Pennock	1893
Grayburg	2131
Premier	2415
Sand Ancho	2450

← Plug 60' Surface.

- * Contact OCD 24 hrs. prior to any work done.
- * Salt gel mud consisting of 10# brine with 25# of gel per barrel must be placed between each plug.
- * Install dry hole marker as per Rule 202.B.2
- * Plugs are to be set from point indicated up.
- * Plugs must not be less than 100' or 25 Sacks of cement, whichever is greater, unless specifically indicated.
- * Shoe and stub plugs will be 50' above and below shoe or stub and tagged.
- * Surface plug will be from 0' - 60'
- * Where plugs are required, cement must be placed inside and outside of all casing string(s) in the correct footage or sacks required, if no cement exists.
- * Plugs to be tagged will be indicated.

← Perf. @ 525' 2nd.
525- 425' TAG.

← Plug 700'

← Plug @ 2400' TAG
Perfs @ 2424 to 2440'

8 5/8" @ 475'
60/200 SACS. CEMENT

5 1/2" @ 2471'
60/200 SACS. CEMENT

[Handwritten signature]