

PROPOSED

~~CURRENT~~ WELLBORE SCHEMATIC

3/12/97

Elevation 3547' G.L. +12' K.B.

514' - 13 3/8" Csg. Cemented w/500 sxs Circulated
PERFORATE @ 600'. CIRCULATE CEMENT TO SURFACE

MUD

T.O.C. @ 2200' (Temp. Survey)

C.I.B.P. @ 2300' W/35' CEMENT ON TOP

Perfs 2386'-2440'

Perfs 2604'-06'

D.V. Tool @ 2604'

5 1/2" Csg. Cut and Pulled @ 3986'
50 sxs Cement Stub Plug 3818'-4050' (Tagged)

4005' - 8 5/8", 24 & 32# Csg.
Cemented 1st Stage w/250 sxs
Cemented 2nd Stage w/1900 sxs

35 sxs Cement Plug 6400'-6500'

T.O.C. @ 7420' (CBL)

CIBP @ 11000' w/35' cmt.

Perfs 11174'-236'

RTTS Pkr. @ 11264'

Cmt. Ret. @ 11273' sqz. 36 sxs

Perfs 11292'-507'

CIBP @ 12365'

Perfs 12422'-689'

12785' - 5 1/2" Cemented w/900sxs

T.D. @ 12853'

LYNX PETROLEUM
Jones Federal No. 1
1650' FSL & FWL
Section 23, T-19S, R-31E
Eddy County, New Mexico