United States Department of the Interior Geological Survey August 8, 1973

- 1. Swaco adjustable choke in choke manifold.
- 2. Pit volume totalizer.
- 3. Flow line sensor.
- 4. Degasser.

Prior to drilling out under the 9-5/8", the BOP's and related control equipment will be pressure tested to rated working pressure by Yellow Jacket Tools and Services, Inc. who will furnish a copy of the pressure test report to the USGS.

The well will be drilled in accordance with USGS requirements as stated in 30 CFR 221.24, 221.36, and 221.37.

Please contact me at the above address if further information is needed to evaluate this request.

Yours very truly,

E. Y. Wilder

Region Operations Manager

EYW/ls

Attachments