Dominion Oklahoma Texas Exploration and Production Inc (DOTEPI) is hereby authorized to re-complete its New Mexico EV State Well No. 1 (API No. 30-015-25352) located 1980 feet from the South line and 1980 feet from the West line (Unit K) of Section 32, Township 22 South, Range 26 East, NMPM, Eddy County, New Mexico, in such a manner as to permit the injection of produced water for disposal purposes into the Delaware formation from a depth of 2658 feet to 4680 feet through 2 7/8 inch plastic-lined tubing set in a packer located at approximately 2600 feet.

IT IS FURTHER ORDERED THAT:

The operator shall take all steps necessary to ensure that the injected water enters only the proposed injection interval and is not permitted to escape to other formations or onto the surface.

Prior to commencing injection operations into the well and at least once per year thereafter, the casing shall be pressure tested from the surface to the packer setting depth to assure the integrity of said casing.

The casing-tubing annulus shall be loaded with an inert fluid and equipped with a pressure gauge at the surface or left open to the atmosphere to facilitate detection of leakage in the casing, tubing, or packer.

The injection well or system shall be equipped with a pressure limiting device which will limit the wellhead pressure on the injection well to no more than 532 psi.

The Director of the Division may authorize an increase in injection pressure upon a proper showing by the operator of said well that such higher pressure will not result in migration of the injected fluid from the Delaware formation. Such proper showing shall at least consist of a valid step-rate test run in accordance with and acceptable to this office.

The operator shall notify the supervisor of the Artesia District Office in written format of the treatment pressures and initial surface shut-in pressures of all acidizing and fracturing operations or other remedial treatments.

The operator shall notify the supervisor of the Artesia District Office of the date and time of the installation of disposal equipment and of any mechanical integrity test so that the same may be inspected and witnessed.