



BOP rams will be actuated on each trip of drill pipe and will be tested before drilling the plug on each casing string.

\*NOTE: ALL VALVES ARE METAL-TO-METAL SEAL AND FLANGED. ALL COMPONENTS MUST MEET ABOVE MINIMUM PRESSURE RATINGS. ALL COMPONENTS TO BE TESTED TO RATED PRESSURE AFTER ASSEMBLY AND BEFORE FURTHER DOWNHOLE OPERATIONS MAY BE CONDUCTED.

Mobil Producing  
Texas & New Mexico Inc.  
Houston, Texas

MOBIL NO. 14 Government "D"  
(LEASE)

Eddy COUNTY, NM STATE

BLOWOUT PREVENTER ASSEMBLY

13 5/8 x 11 IN. 3000 PSI WP\*

Scale

Date  
Drawn  
Checked  
Approved  
Revised