

11430 - 14350' Brine water to Atoka, KCL-Polymer to Morrow increasing weight as necessary.

14300 - 15000' KCL-Polymer.

7. AUXILIARY EQUIPMENT:

- A. Kelly cock in kelly.
- B. Full-opening valve on rig floor in open position at all times ready to be stabbed into drillpipe if necessary.
- C. Rotating drilling head.

8. TESTING, LOGGING AND CORING PROGRAMS:

- A. Possible DST's in Delaware, Bone Spring, Wolfcamp, Strawn, Atoka and Morrow.
- B. CNL-FDC w/GR and caliper; DIL w/MSFL

9. ABNORMAL PRESSURES, TEMPERATURES OR HYDROGEN SULFIDE GAS: Sufficient material will be kept on location to increase mud weight to handle anticipated pressures. The Wolfcamp and/or Atoka could be abnormally pressured.

10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:

- A. Road and pad construction: June 15, 1985
- B. Spud well: June 24, 1985
- C. Duration of drilling and completion operations should be about 90 days.