

- F. After the rig is moved out and the well is either completed or abandoned, all waste materials will be cleaned up within 30 days. No adverse materials will be left on the location. The reserve pit will be completely fenced and kept closed until it has dried. When the reserve pit is dry enough to breakout and fill and, weather permits, the unused portion of the well site will be leveled and reseeded as per BLM specifications. Only that part of the pad required for production facilities will be kept in use. In the event of a dry hole, only a dry hole marker will remain.

8. Ancillary Facilities:

No airstrip, campsite or other facility will be built as a result of the operations of the proposed well.

9. Well Site Layout:

- A. The drill pad layout, with elevations staked by Dan R. Reddy, Engineer, is shown in Exhibit "D". Dimensions of the pad, pits and location of major rig components are shown. Top soil, if available, will be stockpiled per BLM specifications as determined at the on-site inspection. Since the pad is almost level no major cuts will be required.
- B. Exhibit "D" shows the planned orientation for the rig and associated drilling equipment, reserve pit, trash pit, pipe racks, turn-around and parking areas and access road. No permanent living facilities are planned but a temporary foreman/toolpusher's trailer will be on location during the drilling operations.
- C. The reserve pit will be lined with a high quality plastic sheeting (5-7 mil thickness).