

ABNORMAL CONDITIONS

- A) Pressures: Lost circulation is anticipated in the surface interval of the hole. No other abnormal conditions are anticipated.
Bone Springs pressure gradient = 0.46 psi/ft
- B) Temperatures: No abnormal conditions are anticipated
- C) H₂S: None anticipated
- D) Estimated bottomhole pressure: 2,024 psi

ANTICIPATED START DATE

September 10, 1991

COMPLETION

The location pad will be of sufficient size to accommodate all completion activities and equipment. A string of 2-3/8" 4.7# J-55 tubing will be run for a flowing/pumping string. A Sundry Notice will be submitted with a revised completion program if warranted.