

District I  
1625 N. French Dr., Hobbs, NM 88240  
District II  
811 S. First St., Artesia, NM 88210  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico  
Energy Minerals and Natural Resources  
Department  
Oil Conservation Division  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Form C-144  
Revised April 3, 2017

**For temporary pits, below-grade tanks, and multi-well fluid management pits**, submit to the appropriate NMOC District Office.  
**For permanent pits** submit to the Santa Fe Environmental Bureau office and provide a copy to the appropriate NMOC District Office.

Pit, Below-Grade Tank, or  
Proposed Alternative Method Permit or Closure Plan Application

Type of action: ☐ Below grade tank registration  
☐ Permit of a pit or proposed alternative method  
☒ Closure of a pit, below-grade tank, or proposed alternative method  
☐ Modification to an existing permit/or registration  
☐ Closure plan only submitted for an existing permitted or non-permitted pit, below-grade tank, or proposed alternative method

**DENIED**

**Instructions: Please submit one application (Form C-144) per individual pit, below-grade tank or alternative request**

Please be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.

1.  
Operator: DJR Operating, LLC OGRID #: 371838  
Address: 1 Road 3263 Aztec, NM 87410  
Facility or well name: Jicarilla Apache F 10  
API Number: 30-039-82339 OCD Permit Number: \_\_\_\_\_  
U/L or Qtr/Qtr C Section 16 Township 25N Range 05W County: Rio Arriba  
Center of Proposed Design: Latitude 36.403740 Longitude -107.368217 NAD83  
Surface Owner: ☐ Federal ☐ State ☐ Private ☒ Tribal Trust or Indian Allotment

2.  
☐ **Pit:** Subsection F, G or J of 19.15.17.11 NMAC  
Temporary: ☐ Drilling ☐ Workover  
☐ Permanent ☐ Emergency ☐ Cavitation ☐ P&A ☐ Multi-Well Fluid Management Low Chloride Drilling Fluid ☐ yes ☐ no  
☐ Lined ☐ Unlined Liner type: Thickness \_\_\_\_\_ mil ☐ LLDPE ☐ HDPE ☐ PVC ☐ Other \_\_\_\_\_  
☐ String-Reinforced  
Liner Seams: ☐ Welded ☐ Factory ☐ Other \_\_\_\_\_ Volume: \_\_\_\_\_ bbl Dimensions: L \_\_\_\_\_ x W \_\_\_\_\_ x D \_\_\_\_\_

Operator did not completely fill out Box 3,  
No Notification to Land Owner/OCD attached,  
Operator did not certify liquids, excessive equipment was removed soil cover, etc.

3.  
☒ **Below-grade tank:** Subsection I of 19.15.17.11 NMAC  
Volume: unknown bbl Type of fluid: \_\_\_\_\_  
Tank Construction material: Steel  
☐ Secondary containment with leak detection ☐ Visible sidewalls, liner, 6-inch lift and automatic overflow shut-off  
☐ Visible sidewalls and liner ☐ Visible sidewalls only ☐ Other \_\_\_\_\_  
Liner type: Thickness \_\_\_\_\_ mil ☐ HDPE ☐ PVC ☐ Other \_\_\_\_\_

4.  
☐ **Alternative Method:**  
Submittal of an exception request is required. Exceptions must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

5.  
**Fencing:** Subsection D of 19.15.17.11 NMAC (*Applies to permanent pits, temporary pits, and below-grade tanks*)  
☐ Chain link, six feet in height, two strands of barbed wire at top (*Required if located within 1000 feet of a permanent residence, school, hospital, institution or church*)  
☐ Four foot height, four strands of barbed wire evenly spaced between one and four feet  
☐ Alternate. Please specify \_\_\_\_\_

6.

**Netting:** Subsection E of 19.15.17.11 NMAC (*Applies to permanent pits and permanent open top tanks*)

- ☐ Screen ☐ Netting ☐ Other \_\_\_\_\_
- ☐ Monthly inspections (If netting or screening is not physically feasible)

7.

**Signs:** Subsection C of 19.15.17.11 NMAC

- ☐ 12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers
- ☐ Signed in compliance with 19.15.16.8 NMAC

8.

**Variations and Exceptions:**

Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17 NMAC for guidance.

***Please check a box if one or more of the following is requested, if not leave blank:***

- ☐ Variance(s): Requests must be submitted to the appropriate division district for consideration of approval.
- ☐ Exception(s): Requests must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

9.

**Siting Criteria (regarding permitting):** 19.15.17.10 NMAC***Instructions: The applicant must demonstrate compliance for each siting criteria below in the application. Recommendations of acceptable source material are provided below. Siting criteria does not apply to drying pads or above-grade tanks.*****General siting****Ground water is less than 25 feet below the bottom of a low chloride temporary pit or below-grade tank.**

- ☐ NM Office of the State Engineer - iWATERS database search; ☐ USGS; ☐ Data obtained from nearby wells

☐ Yes ☐ No  
☐ NA

**Ground water is less than 50 feet below the bottom of a Temporary pit, permanent pit, or Multi-Well Fluid Management pit .**

NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells

☐ Yes ☐ No  
☐ NA

Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended. **(Does not apply to below grade tanks)**

- Written confirmation or verification from the municipality; Written approval obtained from the municipality

☐ Yes ☐ No

Within the area overlying a subsurface mine. **(Does not apply to below grade tanks)**

- Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division

☐ Yes ☐ No

Within an unstable area. **(Does not apply to below grade tanks)**

- Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map

☐ Yes ☐ No

Within a 100-year floodplain. **(Does not apply to below grade tanks)**

- FEMA map

☐ Yes ☐ No

**Below Grade Tanks**

Within 100 feet of a continuously flowing watercourse, significant watercourse, lake bed, sinkhole, wetland or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☒ No

Within 200 horizontal feet of a spring or a fresh water well used for public or livestock consumption;.

- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☒ No

**Temporary Pit using Low Chloride Drilling Fluid** (maximum chloride content 15,000 mg/liter)

Within 100 feet of a continuously flowing watercourse, or any other significant watercourse or within 200 feet of any lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). (Applies to low chloride temporary pits.)

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 300 feet from a occupied permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☐ No

Within 200 horizontal feet of a spring or a private, domestic fresh water well used by less than five households for domestic or stock watering purposes, or 300feet of any other fresh water well or spring, in existence at the time of the initial application.

NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 100 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

### **Temporary Pit Non-low chloride drilling fluid**

Within 300 feet of a continuously flowing watercourse, or any other significant watercourse, or within 200 feet of any lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☐ No

Within 500 horizontal feet of a spring or a private, domestic fresh water well used by less than five households for domestic or stock watering purposes, or 1000 feet of any other fresh water well or spring, in the existence at the time of the initial application;

- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 300 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

### **Permanent Pit or Multi-Well Fluid Management Pit**

Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☐ No

Within 500 horizontal feet of a spring or a fresh water well used for domestic or stock watering purposes, in existence at the time of initial application.

- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 500 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

10.

#### **Temporary Pits, Emergency Pits, and Below-grade Tanks Permit Application Attachment Checklist:** Subsection B of 19.15.17.9 NMAC

**Instructions:** Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Hydrogeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC
- ☐ Hydrogeologic Data (Temporary and Emergency Pits) - based upon the requirements of Paragraph (2) of Subsection B of 19.15.17.9 NMAC
- ☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
- ☐ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
- ☐ Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

☐ Previously Approved Design (attach copy of design) API Number: \_\_\_\_\_ or Permit Number: \_\_\_\_\_

11.

#### **Multi-Well Fluid Management Pit Checklist:** Subsection B of 19.15.17.9 NMAC

**Instructions:** Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
- ☐ A List of wells with approved application for permit to drill associated with the pit.
- ☐ Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC
- ☐ Hydrogeologic Data - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC
- ☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC

☐ Previously Approved Design (attach copy of design) API Number: \_\_\_\_\_ or Permit Number: \_\_\_\_\_

12.

**Permanent Pits Permit Application Checklist:** Subsection B of 19.15.17.9 NMAC

**Instructions:** Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Hydrogeologic Report - based upon the requirements of Paragraph (1) of Subsection B of 19.15.17.9 NMAC  
☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC  
☐ Climatological Factors Assessment  
☐ Certified Engineering Design Plans - based upon the appropriate requirements of 19.15.17.11 NMAC  
☐ Dike Protection and Structural Integrity Design - based upon the appropriate requirements of 19.15.17.11 NMAC  
☐ Leak Detection Design - based upon the appropriate requirements of 19.15.17.11 NMAC  
☐ Liner Specifications and Compatibility Assessment - based upon the appropriate requirements of 19.15.17.11 NMAC  
☐ Quality Control/Quality Assurance Construction and Installation Plan  
☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC  
☐ Freeboard and Overtopping Prevention Plan - based upon the appropriate requirements of 19.15.17.11 NMAC  
☐ Nuisance or Hazardous Odors, including H<sub>2</sub>S, Prevention Plan  
☐ Emergency Response Plan  
☐ Oil Field Waste Stream Characterization  
☐ Monitoring and Inspection Plan  
☐ Erosion Control Plan  
☐ Closure Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

13.

**Proposed Closure:** 19.15.17.13 NMAC

**Instructions:** Please complete the applicable boxes, Boxes 14 through 18, in regards to the proposed closure plan.

- Type: ☐ Drilling ☐ Workover ☐ Emergency ☐ Cavitation ☐ P&A ☐ Permanent Pit ☐ Below-grade Tank ☐ Multi-well Fluid Management Pit  
☐ Alternative
- Proposed Closure Method: ☐ Waste Excavation and Removal  
☐ Waste Removal (Closed-loop systems only)  
☐ On-site Closure Method (Only for temporary pits and closed-loop systems)  
☐ In-place Burial ☐ On-site Trench Burial  
☐ Alternative Closure Method

14.

**Waste Excavation and Removal Closure Plan Checklist:** (19.15.17.13 NMAC) **Instructions:** Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.

- ☒ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC  
☒ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.13 NMAC  
☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings)  
☒ Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC  
☒ Re-vegetation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC  
☒ Site Reclamation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC

15.

**Siting Criteria (regarding on-site closure methods only):** 19.15.17.10 NMAC

**Instructions:** Each siting criteria requires a demonstration of compliance in the closure plan. Recommendations of acceptable source material are provided below. Requests regarding changes to certain siting criteria require justifications and/or demonstrations of equivalency. Please refer to 19.15.17.10 NMAC for guidance.

Ground water is less than 25 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> NA
Ground water is between 25-50 feet below the bottom of the buried waste - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA
Ground water is more than 100 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input type="checkbox"/> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> NA
Within 100 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Within 300 horizontal feet of a private, domestic fresh water well or spring used for domestic or stock watering purposes, in existence at the time of initial application. - NM Office of the State Engineer - iWATERS database; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Written confirmation or verification from the municipality; Written approval obtained from the municipality	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Within 300 feet of a wetland. US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance	

adopted pursuant to NMSA 1978, Section 3-27-3, as amended.

- Written confirmation or verification from the municipality; Written approval obtained from the municipality

☐ Yes ☒ No

Within the area overlying a subsurface mine.

- Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division

☐ Yes ☒ No

Within an unstable area.

- Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map

☐ Yes ☒ No

Within a 100-year floodplain.

- FEMA map

☐ Yes ☒ No

16.

**On-Site Closure Plan Checklist:** (19.15.17.13 NMAC) *Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.*

- ☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
- ☐ Proof of Surface Owner Notice - based upon the appropriate requirements of Subsection E of 19.15.17.13 NMAC
- ☐ Construction/Design Plan of Burial Trench (if applicable) based upon the appropriate requirements of Subsection K of 19.15.17.11 NMAC
- ☐ Construction/Design Plan of Temporary Pit (for in-place burial of a drying pad) - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☐ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☐ Waste Material Sampling Plan - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings or in case on-site closure standards cannot be achieved)
- ☐ Soil Cover Design - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
- ☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
- ☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC

17.

**Operator Application Certification:**

I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief.

Name (Print): \_\_\_\_\_ Title: \_\_\_\_\_

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

e-mail address: \_\_\_\_\_ Telephone: \_\_\_\_\_

18.

**OCD Approval:** ☐ Permit Application (including closure plan) ☐ Closure Plan (only) ☐ OCD Conditions (see attachment)

**OCD Representative Signature:** **DENIED** **Approval Date:** \_\_\_\_\_

**Title:** \_\_\_\_\_ **OCD Permit Number:** \_\_\_\_\_

19.

**Closure Report (required within 60 days of closure completion):** 19.15.17.13 NMAC

*Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an approved closure plan has been obtained and the closure activities have been completed.*

☐ **Closure Completion Date:** 4/1/2020

20.

**Closure Method:**

- ☒ Waste Excavation and Removal ☐ On-Site Closure Method ☐ Alternative Closure Method ☐ Waste Removal (Closed-loop systems only)
- ☐ If different from approved plan, please explain.

21.

**Closure Report Attachment Checklist:** *Instructions: Each of the following items must be attached to the closure report. Please indicate, by a check mark in the box, that the documents are attached.*

- ☒ Proof of Closure Notice (surface owner and division)
- ☐ Proof of Deed Notice (required for on-site closure for private land only)
- ☐ Plot Plan (for on-site closures and temporary pits)
- ☒ Confirmation Sampling Analytical Results (if applicable)
- ☒ Waste Material Sampling Analytical Results (required for on-site closure)
- ☒ Disposal Facility Name and Permit Number
- ☒ Soil Backfilling and Cover Installation
- ☒ Re-vegetation Application Rates and Seeding Technique
- ☒ Site Reclamation (Photo Documentation)


On-site Closure Location: Latitude 36.403740 Longitude -107.368217 NAD: ☐ 1927 ☐ 1983

22.

**Operator Closure Certification:**

I hereby certify that the information and attachments submitted with this closure report is true, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan.

Name (Print): Larissa Farrell Title: Regulatory Specialist

Signature:  Date: 5/30/2020

e-mail address: lfarrell@djrlc.com Telephone: (505) 444-0289



April 20, 2020

Project #17035-0181  
NMOCD Incident #nRM2006557992

Ms. Larissa Farrell  
DJR Operating, LLC  
1 Road 3263  
Aztec, New Mexico 87410

Phone: (505) 632-3476  
E-mail: [lfarrell@djrlc.com](mailto:lfarrell@djrlc.com)

**RE: BGT and Release Closure Report for the Jicarilla Apache F-10 Compressor Station Located in Section 16, Township 25N, Range 5W, Rio Arriba County, New Mexico**

Dear Ms. Farrell:

Envirotech, Inc. (Envirotech) of Farmington, New Mexico, was contracted by DJR Operating, LLC (DJR) to provide sampling activities for the closure of a below grade tank (BGT) at the Jicarilla Apache F-10 compressor station located within Section 16, Township 25 North, Range 5 West, Rio Arriba County, New Mexico; see enclosed **Figure 1, Vicinity Map**.

On February 21, 2020, DJR contracted roustabout personnel removed the BGT and Envirotech personnel collected a five-point composite soil sample from the exposed surface of the former location of the BGT. The sample was identified as *BGT Composite* and prepared for field screening activities.

**BGT FIELD SCREENING ANALYSIS**

Field screening for VOCs was conducted with a photo-ionization detector (PID) organic vapor meter (OVM). Prior to performing field screening activities, the PID-OVM was first calibrated with 100 parts per million (ppm) isobutylene gas. The soil sample was also screened in the field for total petroleum hydrocarbons (TPH) per United States Environmental Protection Agency (EPA) Method 418.1 using an Infracal Total Oil and Gas (TOG)/ TPH Analyzer. A 3-point calibration was completed prior to conducting soil screening. The soil sample screening results returned a result of 5,408 mg/kg for TPH and 0.0 ppm for VOCs. Field screening protocol followed the manufacture's operating procedure and, field screening results are provided in **Appendix A, Field Notes**.

The subject location was undergoing de-commissioning, and the location was being fully reclaimed per all applicable regulations; therefore, DJR elected to close the BGT under the following standards per *19.15.29.12 NMAC*.



DJR Operating, LLC  
 Jicarilla Apache F-10  
 BGT and Release Closure  
 Project #17035-0181  
 February 2020  
 Page 2

Depth to Groundwater	Constituent	Method	Limit
≤ 50 feet	Chloride	EPA 300.0	600 mg/kg
	TPH (GRO/DRO/MRO)	EPA Method 8015D	100 mg/kg
	BTEX	EPA Method 8021B	50 mg/kg
	Benzene	EPA Method 8021B	10 mg/kg

Based on the field screening results and elected closure standards, TPH was above the applicable closure criteria; see enclosed **Table 1, Summary of Soil Analytical Results**. Due to the elevated TPH concentrations, a release was confirmed; subsequently, a release notification (C-141) was submitted to the NMOCD and JOGA per *19.15.29.10 NMAC*.

### RELEASE CLOSURE CONFIRMATION LABORATORY ANALYSIS

DJR contracted roustabout personnel completed the remediation excavation on February 28, 2020; the final excavation measured 15 feet by 15 feet by 6 feet in depth. On the same day, Envirotech personnel returned to the site to perform confirmation sampling activities under the witness of DJR representative Richard Graves and JOGA representative Alfred Vigil, Jr. Per the direction of Mr. Vigil, one five-point composite sample was collected from the base of the excavation. The soil sample was placed into individual laboratory provided 4-ounce jars, capped head space free, and transported on ice to Envirotech Analytical Laboratory. The soil sample location is illustrated in **Figure 2, Site Map** and excavation activities are documented in the attached **Site Photography**.

The laboratory analytical results were compared to the most stringent release closure criteria provided in *19.15.29.12 NMAC*. Based on laboratory analytical results, the concentrations of contaminants of concern were below the applicable release closure criteria and do not require further remediation actions; see enclosed **Table 1, Summary of Soil Analytical Results**.

### SUMMARY AND CONCLUSIONS

On February 21, 2020, Envirotech personnel performed confirmation sampling of soil beneath the BGT at the Jicarilla Apache F-10 well site. Based on the field screening results and visual observations of stained soil a release was confirmed. DJR subsequently completed a remediation excavation, and confirmation sampling was performed on February 28, 2020. Upon receipt of laboratory analytical results, on March 24, 2020, DJR personnel backfilled and re-contoured the location of the former BGT. The site was reseeded with the approved Jicarilla Mesa seed mixture.



DJR Operating, LLC  
Jicarilla Apache F-10  
BGT and Release Closure  
Project #17035-0181  
February 2020  
Page 3

Based on the analytical results, Envirotech recommends requesting a **No Further Action** status from the NMOCD and JOGA regarding the BGT closure and subsequent release remediation and reclamation.

#### STATEMENT OF LIMITATIONS

The work and services provided were in accordance with NMOCD and JOGA standards. All observations and conclusions provided here are based on the information and current site conditions found at the subject well site. This work has been conducted and reported in accordance with generally accepted professional practices in geology, engineering, environmental chemistry, and hydrogeology.

We appreciate the opportunity to be of service. If you have any questions or require additional information, please contact our office at (505) 632-0615.

Respectfully submitted,  
**ENVIROTECH, INC.**


Reviewed by:

Brittany Hall  
Environmental Field Technician  
[bhall@envirotech-inc.com](mailto:bhall@envirotech-inc.com)

\_\_\_\_\_  
Felipe Aragon, CHMM, CES  
Environmental Assistant Manager  
[faragon@envirotech-inc.com](mailto:faragon@envirotech-inc.com)

Enclosures: Figure 1, *Vicinity Map*  
Figure 2, *Site Map*  
Appendix A, *Field Notes*  
*Site Photography*  
Table 1, *Summary of Soil Analytical Results*  
*Laboratory Analytical Report*

Cc: Client File 17035



Source: 7.5 Minute, Lapis Point, New Mexico U.S.G.S. Topographic Quadrangle Map  
 Scale: 1:24,000 1" = 2,000

DJR Operating, LLC.  
 Jicarilla Apache F #010 Compressor Station  
 Section 16, Township 25N, Range 5W  
 36.40377, -107.36813  
 Incident No. nRM2006557992



5796 U.S. HIGHWAY 64  
 Farmington, New Mexico 87401  
 505.632.0615

Vicinity Map

Figure #1

Project Number: 17035-0181

Date Drawn: 3/10/2020

DRAWN BY:  
 Brittany Hall

PROJECT MANAGER:  
 Felipe Aragon

Excavation Dimensions:  
15 feet by 15 feet by 6 feet deep

Google Earth

### Legend

- - Excavation
- - 5-point Composite Soil Sample



**envirotech**

5796 U.S. HIGHWAY 64, FARMINGTON, NM 87401 505-632-0615

MAP DRAWN BY:

BAH  
3/5/2020

REVISIONS BY:

NAME  
DATE

APPROVED BY:




FRA  
4/15/2020




Scale  
1"= 18'



## Figure 2, Site Map

DJR Operating, LLC.  
Jicarilla Apache F #010 Compressor Station  
Section 16, Township 25N, Range 5W  
36.40377, -107.36813  
Project #17035-0181  
Incidnet No. nRM2006557992

CLIENT: <u>DJR</u>		 <small>(800) 632-0818 (800) 362-1879          8700 U.S. Hwy 84, Farmington, NM 87401</small>		Environmental Specialist: <u>J. Garcia</u>				
CLIENT/JOB # <u>17035-0181</u>				LAT: <u>36.40377</u>				
START DATE: <u>2/21/20</u>				LONG: <u>-107.36813</u>				
FINISH DATE: <u>2</u>								
Page # <u>1</u> of <u>1</u>								
FIELD REPORT: BELOW GROUND TANK VERIFICATION								
LOCATION NAME:	<u>Jicarilla Apache</u>		WELL #:	<u>F-10</u>				
QUAD/UNIT:	SEC: <u>16</u>	TWP: <u>25N</u>	RNG: <u>5W</u>	Temp Pit: _____ PERM Pit: _____				
QTR/FOOTAGE:	CNTY: <u>Rio Arriba</u>		ST: <u>New Mexico</u>					
Excavation Approx:	Feet X <u>15</u>		Feet X <u>15</u>	Feet Deep <u>3</u>	Cubic Yardage: _____			
Disposal Facility:	_____		Remediation Method: _____					
Land Owner:	_____		API: <u>30-039-82339</u> Pit Volume: _____					
Construction Material:	Double Walled, With Leak Detection:							
Temporary Pit Closure: NMAC 19.15.17 Table II (Permitted after 6/28/2013)								
BGT Closure: NMAC 19.15.17 Table I (Permitted after 6/28/2013)								
BGT Closure: BENZENE $\leq 0.2$ mg/kg, BTEX $\leq 50$ mg/kg, TPH (418.1) $\leq 100$ mg/kg, CHLORIDES $\leq 250$ mg/kg (Permitted before 6/28/2013)								
FIELD 418.1 ANALYSIS								
SAMPLE DESCRIPTION	TIME	SAMPLE ID	LAB #	WEIGHT	mL FREON DILUTION	READING	CALC. (mg/kg)	
<u>200 STD</u>	<u>10:15</u>						<u>284</u>	
<u>BGT Comp</u>	<u>10:28</u>			<u>5</u>	<u>20</u>	<u>4</u>	<u>5,408</u>	
PID RESULTS		SITE PERIMETER			SAMPLE PROFILE			
SAMPLE ID	RESULTS (mg/kgd)							
<u>BGT</u>	<u>0.0</u>							
FIELD CHLORIDES RESULTS								
SAMPLE ID	READING	CALC. (mg/kg)						
SAMPLE ID	ANALYSIS	US EPA						
	BENZENE	8021B/8015						
	BTEX	8021B/80260B						
	GRO & DRO	8015						
	CHLORIDES	EPA300						
	TPH	418.1						
Analyst Signature			NOTES:					
Printed Name								
WO #:			Who ordered/Site Rep.:					

CLIENT: <u>DJR</u>	 <small>(508) 632-0615 (800) 362-1879</small> <small>8788 U.S. Hwy 84, Farmington, NH 07424</small>	Environmental Specialist: <u>BHall</u>
CLIENT/JOB # <u>17035-0181</u>		
START DATE: <u>2/28/2020</u>		LAT: <u>36.40377</u>
FINISH DATE: <u>2/28/2020</u>		LONG: <u>-107.36813</u>
Page # _____ of _____		
FIELD REPORT: BELOW GROUND TANK VERIFICATION		
LOCATION NAME: <u>Jicarilla Apache</u>	WELL #: <u>F10</u>	Temp Pit: _____ PERM Pit: _____
QUAD/UNIT: _____	SEC: <u>16</u> TWP: <u>25 N</u> RNG: <u>SW</u>	PM: _____
QTR/FOOTAGE: _____	CNTY: <u>Rio Arriba</u> ST: <u>New Mexico</u>	
Excavation Approx: <u>15</u>	Feet X <u>15</u>	Feet X <u>86</u> Feet Deep _____ Cubic Yardage: _____
Disposal Facility: _____	Remediation Method: _____	
Land Owner: _____	API: _____	Pit Volume: _____
Construction Material: _____	Double Walled, With Leak Detection: _____	
<div style="border: 1px solid black; padding: 5px;"> <p>Temporary Pit Closure: NMAC 19.15.17 Table II (Permitted after 6/28/2013)</p> <p>BGT Closure: NMAC 19.15.17 Table I (Permitted after 6/28/2013)</p> <p>BGT Closure: BENZENE <math>\leq 0.2</math> mg/kg, BTEX <math>\leq 50</math> mg/kg, TPH (418.1) <math>\leq 100</math> mg/kg, CHLORIDES <math>\leq 250</math> mg/kg (Permitted before 6/28/2013)</p> </div>		
FIELD 418.1 ANALYSIS		
SAMPLE DESCRIPTION	TIME	SAMPLE ID
LAB #	WEIGHT	mL FREON
DILUTION	READING	CALC. (mg/kg)
	1108	200 Std
1	1116	Base
		5
		20
		4
		203
		05
		203
		20
PID RESULTS		
SAMPLE ID	RESULTS (mg/kg)	
1	0.0	
FIELD CHLORIDES RESULTS		
SAMPLE ID	READING	CALC. (mg/kg)
SAMPLE ID	ANALYSIS	US EPA
1	BENZENE	8021B/8015
1	BTEX	8021B/80260B
1	GRO & DRO	8015
1	CHLORIDES	EPA300
	TPH	418.1
		
no other O&G equipment on site		
SAMPLE PROFILE		
		
Analyst Signature: <u>Brian Hall</u> Printed Name: <u>Brian Hall</u>		NOTES: <u>JOGA rep. of old base composite only. (Analog Visi)</u> WO #: _____ Who ordered/Site Rep.: _____

**SITE PHOTOGRAPHY  
BGT AND RELEASE CLOSURE REPORT  
DJR OPERATING, LLC.  
JICARILLA APACHE F #010 COMPRESSOR STATION  
PROJECT #17035-0181  
FEBRUARY 2020**

**February 21, 2020**



Picture 1: View of BGT Removal

**February 28, 2020**



Picture 2: View of Excavation of Former BGT

**SITE PHOTOGRAPHY  
BGT AND RELEASE CLOSURE REPORT  
DJR OPERATING, LLC.  
JICARILLA APACHE F #010 COMPRESSOR STATION  
PROJECT #17035-0181  
FEBRUARY 2020**



Picture 3: View of Backfilled and Recontoured Area (View 1)



Picture 4: View of Backfilled and Recontoured Area (View 2)

Table 1, Summary of Soil Analytical Results  
 DJR Operating, LLC  
 BGT and Release Closure Report  
 Jicarilla Apache F #010  
 Section 16, Township 25N, Range 5W  
 Rio Arriba County, New Mexico  
 Project #17035-0181  
 Incident #nRM2006557992

Sample Description*	Date	Sample Depth* (ft)	EPA Method 8015			EPA Method 8021		EPA Method 300.0
			GRO (mg/kg)	DRO (mg/kg)	MRO (mg/kg)	Benzene (mg/kg)	Total BTEX (mg/kg)	Chlorides (mg/kg)
NMOCD Release Closure Criteria (Table 1 - 19.15.29.12)			Not Applicable			10 mg/kg	50 mg/kg	600 mg/kg
			100 mg/kg					
BGT Comp**	2/21/2020	0.17	5,408			NA	NA	NA
F-10 BGT	2/28/2020	6.0	<20.0	<25.0	<50.0	<0.025	<0.100	<20.0

\*5-point composite soil sample collected beneath the BGT

\*\* - Field Screening Analysis only (EPA Method 418.1)

NA - Not Analyzed

**BOLD** - above NMOCD Closure Criteria



Practical Solutions for a Better Tomorrow



## Analytical Report

### Report Summary

Client: DJR Operating, LLC

Samples Received: 2/28/2020

Job Number: 17035-0181

Work Order: P003004

Project Name/Location: F-10 BGT Closure

Report Reviewed By:

A handwritten signature in black ink, appearing to read 'Walter Hinchman', is written over a light blue rectangular background.

Date: 3/4/20

Walter Hinchman, Laboratory Director



Envirotech Inc. certifies the test results meet all requirements of TNI unless footnoted otherwise.  
Statement of Data Authenticity: Envirotech, Inc, attests the data reported has not been altered in any way.  
Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.  
Envirotech, Inc, holds the Utah TNI certification NM009792018-1 for the data reported.  
Envirotech, Inc, holds the Texas TNI certification T104704557-19-2 for the data reported.



DJR Operating, LLC  
1 Rd 3263  
Aztec NM, 87410

Project Name: F-10 BGT Closure  
Project Number: 17035-0181  
Project Manager: Felipe Aragon

**Reported:**  
03/04/20 14:26

### Analytical Report for Samples

Client Sample ID	Lab Sample ID	Matrix	Sampled	Received	Container
F-10 BGT	P003004-01A	Soil	02/28/20	02/28/20	Glass Jar, 4 oz.
	P003004-01B	Soil	02/28/20	02/28/20	Glass Jar, 4 oz.

Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.



DJR Operating, LLC	Project Name:	F-10 BGT Closure	<b>Reported:</b> 03/04/20 14:26
1 Rd 3263	Project Number:	17035-0181	
Aztec NM, 87410	Project Manager:	Felipe Aragon	

**F-10 BGT**  
**P003004-01 (Solid)**

Reporting									
Analyte	Result	Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes

**Volatile Organics by EPA 8021**

Benzene	ND	0.0250	mg/kg	1	2010002	03/02/20	03/03/20	EPA 8021B	
Toluene	ND	0.0250	mg/kg	1	2010002	03/02/20	03/03/20	EPA 8021B	
Ethylbenzene	ND	0.0250	mg/kg	1	2010002	03/02/20	03/03/20	EPA 8021B	
p,m-Xylene	ND	0.0500	mg/kg	1	2010002	03/02/20	03/03/20	EPA 8021B	
o-Xylene	ND	0.0250	mg/kg	1	2010002	03/02/20	03/03/20	EPA 8021B	
Total Xylenes	ND	0.0250	mg/kg	1	2010002	03/02/20	03/03/20	EPA 8021B	
<i>Surrogate: 4-Bromochlorobenzene-PID</i>		104 %		50-150	2010002	03/02/20	03/03/20	EPA 8021B	

**Nonhalogenated Organics by 8015 - DRO/ORO**

Diesel Range Organics (C10-C28)	ND	25.0	mg/kg	1	2010005	03/02/20	03/03/20	EPA 8015D	
Oil Range Organics (C28-C40)	ND	50.0	mg/kg	1	2010005	03/02/20	03/03/20	EPA 8015D	
<i>Surrogate: n-Nonane</i>		93.8 %		50-200	2010005	03/02/20	03/03/20	EPA 8015D	

**Nonhalogenated Organics by 8015 - GRO**

Gasoline Range Organics (C6-C10)	ND	20.0	mg/kg	1	2010002	03/02/20	03/03/20	EPA 8015D	
<i>Surrogate: 1-Chloro-4-fluorobenzene-FID</i>		91.9 %		50-150	2010002	03/02/20	03/03/20	EPA 8015D	

**Anions by 300.0/9056A**

Chloride	ND	20.0	mg/kg	1	2010003	03/02/20	03/03/20	EPA 300.0/9056A	
----------	----	------	-------	---	---------	----------	----------	--------------------	--

Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.



DJR Operating, LLC	Project Name:	F-10 BGT Closure	<b>Reported:</b> 03/04/20 14:26
1 Rd 3263	Project Number:	17035-0181	
Aztec NM, 87410	Project Manager:	Felipe Aragon	

**Volatile Organics by EPA 8021 - Quality Control****Envirotech Analytical Laboratory**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

**Batch 2010002 - Purge and Trap EPA 5030A****Blank (2010002-BLK1)**

Prepared: 03/02/20 0 Analyzed: 03/03/20 1

Benzene	ND	0.0250	mg/kg							
Toluene	ND	0.0250	"							
Ethylbenzene	ND	0.0250	"							
p,m-Xylene	ND	0.0500	"							
o-Xylene	ND	0.0250	"							
Total Xylenes	ND	0.0250	"							
Surrogate: 4-Bromochlorobenzene-PID	8.58		"	8.00		107	50-150			

**LCS (2010002-BS1)**

Prepared: 03/02/20 0 Analyzed: 03/03/20 1

Benzene	4.79	0.0250	mg/kg	5.00		95.7	70-130			
Toluene	4.78	0.0250	"	5.00		95.7	70-130			
Ethylbenzene	4.78	0.0250	"	5.00		95.5	70-130			
p,m-Xylene	9.52	0.0500	"	10.0		95.2	70-130			
o-Xylene	4.78	0.0250	"	5.00		95.7	70-130			
Total Xylenes	14.3	0.0250	"	15.0		95.4	0-200			
Surrogate: 4-Bromochlorobenzene-PID	8.46		"	8.00		106	50-150			

**Matrix Spike (2010002-MS1)**

Source: P002092-01

Prepared: 03/02/20 0 Analyzed: 03/03/20 1

Benzene	4.95	0.0250	mg/kg	5.00	ND	99.0	54.3-133			
Toluene	4.96	0.0250	"	5.00	ND	99.1	61.4-130			
Ethylbenzene	4.94	0.0250	"	5.00	ND	98.9	61.4-133			
p,m-Xylene	9.86	0.0500	"	10.0	ND	98.6	63.3-131			
o-Xylene	4.95	0.0250	"	5.00	ND	99.0	63.3-131			
Total Xylenes	14.8	0.0250	"	15.0	ND	98.7	0-200			
Surrogate: 4-Bromochlorobenzene-PID	8.69		"	8.00		109	50-150			

**Matrix Spike Dup (2010002-MSD1)**

Source: P002092-01

Prepared: 03/02/20 0 Analyzed: 03/03/20 1

Benzene	4.66	0.0250	mg/kg	5.00	ND	93.2	54.3-133	6.07	20	
Toluene	4.64	0.0250	"	5.00	ND	92.8	61.4-130	6.58	20	
Ethylbenzene	4.63	0.0250	"	5.00	ND	92.6	61.4-133	6.53	20	
p,m-Xylene	9.24	0.0500	"	10.0	ND	92.4	63.3-131	6.51	20	
o-Xylene	4.64	0.0250	"	5.00	ND	92.8	63.3-131	6.40	20	
Total Xylenes	13.9	0.0250	"	15.0	ND	92.5	0-200	6.47	200	
Surrogate: 4-Bromochlorobenzene-PID	8.57		"	8.00		107	50-150			

Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.



DJR Operating, LLC	Project Name:	F-10 BGT Closure	<b>Reported:</b> 03/04/20 14:26
1 Rd 3263	Project Number:	17035-0181	
Aztec NM, 87410	Project Manager:	Felipe Aragon	

## Nonhalogenated Organics by 8015 - DRO/ORO - Quality Control

## Envirotech Analytical Laboratory

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

## Batch 2010005 - DRO Extraction EPA 3570

## Blank (2010005-BLK1)

Prepared &amp; Analyzed: 03/02/20 1

Diesel Range Organics (C10-C28)	ND	25.0	mg/kg							
Oil Range Organics (C28-C40)	ND	50.0	"							
Surrogate: n-Nonane	47.2		"	50.0		94.4	50-200			

## LCS (2010005-BS1)

Prepared &amp; Analyzed: 03/02/20 1

Diesel Range Organics (C10-C28)	436	25.0	mg/kg	500		87.2	38-132			
Surrogate: n-Nonane	47.9		"	50.0		95.9	50-200			

## Matrix Spike (2010005-MS1)

Source: P002081-01

Prepared &amp; Analyzed: 03/02/20 1

Diesel Range Organics (C10-C28)	427	25.0	mg/kg	500	ND	85.4	38-132			
Surrogate: n-Nonane	46.6		"	50.0		93.3	50-200			

## Matrix Spike Dup (2010005-MSD1)

Source: P002081-01

Prepared &amp; Analyzed: 03/02/20 1

Diesel Range Organics (C10-C28)	429	25.0	mg/kg	500	ND	85.8	38-132	0.445	20	
Surrogate: n-Nonane	47.4		"	50.0		94.8	50-200			

Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.



DJR Operating, LLC  
1 Rd 3263  
Aztec NM, 87410

Project Name: F-10 BGT Closure  
Project Number: 17035-0181  
Project Manager: Felipe Aragon

**Reported:**  
03/04/20 14:26

### Nonhalogenated Organics by 8015 - GRO - Quality Control

#### Envirotech Analytical Laboratory

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

#### Batch 2010002 - Purge and Trap EPA 5030A

##### Blank (2010002-BLK1)

Prepared: 03/02/20 0 Analyzed: 03/03/20 1

Gasoline Range Organics (C6-C10)	ND	20.0	mg/kg							
Surrogate: 1-Chloro-4-fluorobenzene-FID	7.44		"	8.00		93.0	50-150			

##### LCS (2010002-BS2)

Prepared: 03/02/20 0 Analyzed: 03/03/20 1

Gasoline Range Organics (C6-C10)	43.6	20.0	mg/kg	50.0		87.1	70-130			
Surrogate: 1-Chloro-4-fluorobenzene-FID	7.47		"	8.00		93.4	50-150			

##### Matrix Spike (2010002-MS2)

Source: P002092-01

Prepared: 03/02/20 0 Analyzed: 03/03/20 1

Gasoline Range Organics (C6-C10)	45.3	20.0	mg/kg	50.0	ND	90.5	70-130			
Surrogate: 1-Chloro-4-fluorobenzene-FID	7.47		"	8.00		93.4	50-150			

##### Matrix Spike Dup (2010002-MSD2)

Source: P002092-01

Prepared: 03/02/20 0 Analyzed: 03/03/20 1

Gasoline Range Organics (C6-C10)	42.4	20.0	mg/kg	50.0	ND	84.8	70-130	6.59	20	
Surrogate: 1-Chloro-4-fluorobenzene-FID	7.52		"	8.00		94.0	50-150			

Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.



DJR Operating, LLC	Project Name:	F-10 BGT Closure	<b>Reported:</b> 03/04/20 14:26
1 Rd 3263	Project Number:	17035-0181	
Aztec NM, 87410	Project Manager:	Felipe Aragon	

**Anions by 300.0/9056A - Quality Control****Envirotech Analytical Laboratory**

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

**Batch 2010003 - Anion Extraction EPA 300.0/9056A****Blank (2010003-BLK1)**

Prepared &amp; Analyzed: 03/02/20 1

Chloride ND 20.0 mg/kg

**LCS (2010003-BS1)**

Prepared &amp; Analyzed: 03/02/20 1

Chloride 250 20.0 mg/kg 250 100 90-110

**Matrix Spike (2010003-MS1)****Source: P002092-01**

Prepared &amp; Analyzed: 03/02/20 1

Chloride 363 20.0 mg/kg 250 107 102 80-120

**Matrix Spike Dup (2010003-MSD1)****Source: P002092-01**

Prepared &amp; Analyzed: 03/02/20 1

Chloride 361 20.0 mg/kg 250 107 102 80-120 0.586 20

**QC Summary Report****Comment:**

Calculations are based off of the raw (non-rounded) data. However, for reporting purposes all QC data is rounded to three significant figures. Therefore, hand calculated values may differ slightly.

Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.



DJR Operating, LLC	Project Name:	F-10 BGT Closure	<b>Reported:</b> 03/04/20 14:26
1 Rd 3263	Project Number:	17035-0181	
Aztec NM, 87410	Project Manager:	Felipe Aragon	

### Notes and Definitions

ND Analyte NOT DETECTED at or above the reporting limit

NR Not Reported


RPD Relative Percent Difference

\*\* Methods marked with \*\* are non-accredited methods.

Soil data is reported on an "as received" weight basis, unless reported otherwise.


Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.


Page 25 of 28



Jicarilla Apache F 10  
 30-039-82339  
 UL-C, Section 16, T25N, R05W  
 Distance to Surface Water 693'





<p>300' Radius</p> <p>500' Radius</p> <p>1000' Radius</p>	<p>Jicarilla Apache F 10</p> <p>30-039-82339</p> <p>UL-C, Section 16, T25N, R05W</p> <p>Distance to Surface Water 693'</p>	<p>Surface Hydrology Map</p> <p></p>
---	--	---



---

## New Mexico Office of the State Engineer Water Column/Average Depth to Water

---

(quarters are 1=NW 2=NE 3=SW 4=SE)  
(quarters are smallest to largest) (NAD83 UTM in meters)

No records found.

**PLSS Search:**

**Section(s):** 16, 8, 9, 10, 15, **Township:** 25N **Range:** 05W  
17, 20, 21, 22

---

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.

---

6/1/20 1:57 PM

WATER COLUMN/ AVERAGE  
DEPTH TO WATER