State of New Mexico Energy Minerals and Natural Resources

: 7 _a		
District I	State of New Mexico	Form C-144
1625 N French Dr , Hobbs, NM 88240	Energy Minerals and Natural Resources	July 21, 2008
District II	Department	For temporary pits, closed-loop sytems, and below-grade tanks, submit to the appropriate NMOCD District Office
1301 W Grand Ave , Artesia, NM 88210 District III	Oil Conservation Division 1220 South St. Francis Dr.	• • • • • • • • • • • • • • • • • • • •
000 Rio Brazos Rd , Aztec, NM 87410	Santa Fe, NM 87505	For permanent pits and exceptions submit to the Santa Fe
istrict IV 220 S. St. Francis Dr., Santa Fe, NM 87505		Environmental Bureau office and provide a copy to the appropriate NMOCD District Office
220 3 St. Planeis DI , Sainta Pe, Nivi 6/303	Pit, Closed-Loop System, Below-Grad	e Tank, or
Propo	Pit, Closed-Loop System, Below-Gradosed Alternative Method Permit or Closed System, below-grade to Closure of a pit, closed-loop system, below-grade to Modification to an existing permit Closure plan only submitted for an existing permit	For permanent pits and exceptions submit to the Santa Fe Environmental Bureau office and provide a copy to the appropriate NMOCD District Office Tank, or aure Plan Application mk, or proposed alternative method ank, or proposed alternative method
Type of action:	Permit of a pit closed-loop system below-grade to	nk or proposed alternative method
Type of action.	Closure of a pit, closed-loop system, below-grade to	ank or proposed alternative method
• `	Modification to an existing permit	The state of the s
	Closure plan only submitted for an existing permitti below-grade tank, or proposed alternative method	ted or non-permitted pit, closed-loop streem.
Instructions: Please submit one at	oplication (Form C-144) per individual pit, closed-loo	
	this request does not relieve the operator of liability should operations re	•
environment Nor does approval relie	eve the operator of its responsibility to comply with any other applicable	governmental authority's rules, regulations or ordinances
Operator: Burlington Resources Oil	& Gas Company, LP	OGRID#: 14538
Address: PO Box 4289, Farmington		
acility or well name: Canyon Larg	o Unit 42	
API Number:	30-039-31030 OCD Permit Number	r
J/L or Qtr/Qtr: L(NW/SW) Section	on: 12 Township: 25N Range:	6W County: Rio Arriba
Center of Proposed Design: Latitude:	36.412233 °N Longitude:	107.425346 °W NAD: 1927X 1983
Surface Owner: X Federal,	State Private Tribal Trust or Indian	n Allotment
2		
X Pit: Subsection F or G of 19 15 17	11 NMAC	
Temporary X Drilling Work		
	avitation P&A	
	ner type Thickness 20 mil X LLDPE	HDPE PVC Other
X String-Reinforced		
Liner Seams: X Welded X Fa	octory Other Volume 7700	bblDimensions Lx W55'x D12'
3	***	
Type of Operation P&A	on H of 19 15 17 11 NMAC Drilling a new well Workover or Drilling (Applies to a	activities which require prior approval of a permit or
туре от ороналол	notice of intent)	activities when require prior approval of a permit of
Drying Pad Above Groun	nd Steel Tanks Haul-off Bins Other	
Lined Unlined Liner	r type Thicknessmil LLDPE H	IDPE PVD Other
Liner Seams Welded Fa	octory Other	
4		
X Below-grade tank: Subsection I		
Volume 120 bl		
Tank Construction material	Metal	and a supplier of
Secondary containment with leak det Visible sidewalls and liner		THAT COVERSION SHUT-OFF
Liner Type Thickness 45		LDPE
Alternative Method:		

Submittal of an exception request is required
Exceptions must be submitted to the Santa Fe Environmental Bureau office for consideration of approval

· · · · · · · · · · · · · · · · · · ·							
Fencing: Subsection D of 19 15 17 11 NMAC (Applies to permanent pit, temporary pits, and below-grade tanks)							
Chain link, six feet in height, two strands of barbed wire at top (Required if located within 1000 feet of a permanent residence, school, hospital, institution or church)							
Four foot height, four strands of barbed wire evenly spaced between one and four feet							
X Alternate Please specify 4' hogwire fence with a single strand of barbed wire on top.							
7		<u>_</u>					
Netting: Subsection E of 19 15 17 11 NMAC (Applies to permanent pits and permanent open top tanks)							
X Screen Netting Other							
Monthly inspections (If netting or screening is not physically feasible)							
8							
Signs: Subsection C of 19 15 17 11 NMAC							
12" X 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers							
X Signed in compliance with 19 15 3 103 NMAC							
9 Administration Assessment Expansions							
Administrative Approvals and Exceptions: Justifications and/or demonstrations of equivalency are required—Please refer to 19.15.17 NMAC for guidance							
Please check a box if one or more of the following is requested, if not leave blank:							
X Administrative approval(s) Requests must be submitted to the appropriate division district of the Santa Fe Environmental Bureau office for consi (Fencing/BGT Liner)	deration of ap	proval					
Exception(s). Requests must be submitted to the Santa Fe Environmental Burcau office for consideration of approval							
10	******						
Siting Criteria (regarding permitting): 19.15 17 10 NMAC							
Instructions: The applicant must demonstrate compliance for each siting criteria below in the application. Recommendations of acceptable source material are provided below. Requests regarding changes to certain siting criteria may require administrative approval from the	ı						
appropriate district office or may be considered an exception which must be submitted to the Santa Fe Environmental Bureau Office for	I						
consideration of approval. Applicant must attach justification for request. Please refer to 19.15.17.10 NMAC for guidance. Siting criteria does not apply to drying pads or above grade-tanks associated with a closed-loop system.	: i						
Ground water is less than 50 feet below the bottom of the temporary pit, permanent pit, or below-grade tank. NM Office of the State Engineer - IWATERS database search; USGS; Data obtained from nearby wells	∐Yes	X No					
Within 300 feet of a continuously flowing watercourse, or 200 feet of any other watercourse, lakebed, sinkhole, or playa lake							
(measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site							
1 5 1 2 2	Пv	V.					
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.	∐Yes	XNo					
(Applies to temporary, emergency, or cavitation pits and below-grade tanks)	□NA						
- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image							
Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.	Yes	No					
(Applied to permanent pits)	X NA						
- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image							
Within 500 horizonal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock watering purposes, or within 1000 horizontal feet of any other fresh water well or spring, in existence at the time of initial application.	Yes	XNo					
- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site	l						
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended	Yes	X No					
- Written confirmation or verification from the municipality; Written approval obtained from the municipality		₩ .					
Within 500 feet of a wetland. - US Fish and Wildlife Wetland Identification map, Topographic map; Visual inspection (certification) of the proposed site	∐Ycs	X No					
Within the area overlying a subsurface mine. - Written confirmation or verification or map from the NM EMNRD - Mining and Mineral Division	∐ Yes	X No					
Within an unstable area.	Yes	XNo					
- Engineering measures incorporated into the design, NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map	ı						
Within a 100-year floodplain - FEMA map	Yes	XNo					

Form C-144 Oil Conservation Division Page 2 of 5

Temporary Pits, Emergency Pits and Below-grade Tanks Permit Application Attachment Checklist: Subsection B of 19 15 17 9 NMAC Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached						
X Hydrogeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC						
Tryangeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 Notice X						
X Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17 10 NMAC						
X String Criteria Compinance Demonstrations - based upon the appropriate requirements of 19.13.17 TO NMAC						
X Operating and Maintenance Plan - based upon the appropriate requirements of 19 15.17.11 NMAC						
X Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of						
19 15 17.9 NMAC and 19 15.17 13 NMAC						
Previously Approved Design (attach copy of design) API or Permit						
Closed-loop Systems Permit Application Attachment Checklist: Subsection B of 19 15 17 9 NMAC Instructions Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached Geologic and Hydrogeologic Data (only for on-site closure) - based upon the requirements of Paragraph (3) of Subsection B of 19 15.17 9						
Siting Criteria Compliance Demonstrations (only for on-site closure) - based upon the appropriate requirements of 19 15 17.10 NMAC						
Design Plan - based upon the appropriate requirements of 19 15 17 11 NMAC						
Operating and Maintenance Plan - based upon the appropriate requirements of 19 15 17.12 NMAC						
Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19 15.17 9 NMAC and 19.15.17 13 NMAC						
Previously Approved Design (attach copy of design) API						
Previously Approved Operating and Maintenance Plan API						
13						
Permanent Pits Permit Application Checklist: Subsection B of 19 15 17.9 NMAC						
Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.						
Hydrogeologic Report - based upon the requirements of Paragraph (I) of Subsection B of 19 15 17 9 NMAC						
Stting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19 15 17.10 NMAC						
Climatological Factors Assessment Certified Engineering Design Plans - based your the appropriate resourcements of 10.15.17.11.NMAC						
 ☐ Certified Engineering Design Plans - based upon the appropriate requirements of 19.15 17 11 NMAC ☐ Dike Protection and Structural Integrity Design based upon the appropriate requirements of 19.15 17 11 NMAC 						
Leak Detection Design - based upon the appropriate requirements of 19.15.17.11 NMAC						
Liner Specifications and Compatibility Assessment - based upon the appropriate requirements of 19.15.17 11 NMAC						
Quality Control/Quality Assurance Construction and Installation Plan						
Operating and Maintenance Plan - based upon the appropriate requirements of 19 15 17 12 NMAC						
Freeboard and Overtopping Prevention Plan - based upon the appropriate requirements of 19 15.17.11 NMAC						
Nuisance or Hazardous Odors, including H2S, Prevention Plan						
Emergency Response Plan						
Oil Field Waste Stream Characterization						
Monitoring and Inspection Plan						
Erosion Control Plan						
Closure Plan - based upon the appropriate requirements of Subsection C of 19 15 17.9 NMAC and 19.15 17 13 NMAC						
Proposed Closure: 19 15 17 13 NMAC						
Instructions: Please complete the applicable boxes, Boxes 14 through 18, in regards to the proposed closure plan.						
Type X Drilling Workover Emergency X Cavitation P&A Permanent Pit X Below-grade Tank Closed-loop System Alternative						
Proposed Closure Method X Waste Excavation and Removal (Below-Grade Tank) Waste Removal (Closed-loop systems only)						
X On-site Closure Method (only for temporary pits and closed-loop systems)						
X In-place Burial On-site Trench						
Alternative Closure Method (Exceptions must be submitted to the Santa Fe Environmental Bureau for consideration)						
Waste Excavation and Removal Closure Plan Checklist: (19 15 17 13 NMAC) Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.						
X Protocols and Procedures - based upon the appropriate requirements of 19.15 17 13 NMAC						
X Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19 15 17.13 NMAC						
X Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings)						
X Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19 15.17 13 NMAC						
X Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15 17 13 NMAC						
Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15 17 13 NMAC						

Form C-144

16 Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only: (19 15 17 13 D NMAC)					
Instructions Please identify the facility or facilities for the disposal of liquids, drilling fluids and drill cuttings. Use attachment if more than two facilities are required	,				
Disposal Facility Name Disposal Facility Permit #					
Disposal Facility Name Disposal Facility Permit #					
Will any of the proposed closed-loop system operations and associated activities occur on or in areas that will not be used for future Yes (If yes, please provide the information No	service and				
Required for impacted areas which will not be used for future service and operations Soil Backfill and Cover Design Specification - based upon the appropriate requirements of Subsection II of 19 15 17 13 NM, Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19 15 17 13 NMAC Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19 15 17 13 NMAC	AC				
17					
Siting Criteria (Regarding on-site closure methods only: 19 15 17 10 NMAC Instructions Each string criteria requires a demonstration of compliance in the closure plan. Recommendations of acceptable source material are provided certain siting criteria may require administrative approval from the appropriate district office or may be considered an exception which must be submitted to office for consideration of approval Justifications and/or demonstrations of equivalency are required. Please (efer to 19 15 17.10 NMAC for guidance)					
Ground water is less than 50 feet below the bottom of the buried waste	Yes X No				
- NM Office of the State Engineer - (WATERS database search, USGS) Data obtained from nearby wells	∐N/A				
Ground water is between 50 and 100 feet below the bottom of the buried waste	X Yes No				
- NM Office of the State Engineer - tWATERS database search, USGS, Data obtained from nearby wells	N/A				
Ground water is more than 100 feet below the bottom of the buried waste	Yes X No				
- NM Office of the State Engineer - tWATERS database search, USGS, Data obtained from nearby wells	∐N/A				
Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark)	Yes XNo				
- Topographic map, Visual inspection (certification) of the proposed site	Yes X No				
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application - Visual inspection (certification) of the proposed site; Aerial photo, satellite image	Yes X No				
Within 500 horizontal feet of a private, domestic fresh water well or spring that less than five households use for domestic or stock watering purposes, or within 1000 horizontal fee of any other fiesh water well or spring, in existence at the time of the initial application. - NM Office of the State Engineer - iWATERS database, Visual inspection (certification) of the proposed site Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted	Yes X No				
pursuant to NMSA 1978, Section 3-27-3, as amended - Written confirmation of verification from the municipality, Written approval obtained from the municipality					
Within 500 feet of a wetland - US Fish and Wildlife Wetland Identification map, Topographic map, Visual inspection (certification) of the proposed site	Yes X No				
Within the area overlying a subsurface mine.	Yes X No				
- Written confirantion or verification or map from the NM EMNRD-Mining and Mineral Division	Yes X No				
Within an unstable area - Engineering measures incorporated into the design, NM Bureau of Geology & Mineral Resources, USGS, NM Geological Society,	Yes XNo				
Topographic map					
Within a 100-year floodplain - FEMA map	Yes X No				
18 On-Site Closure Plan Checklist: (19 15 17 13 NMAC) Instructions: Each of the following items must bee attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.					
X Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19 15 17 10 NMAC					
X Proof of Surface Owner Notice - based upon the appropriate requirements of Subsection F of 19 15 17 13 NMAC					
Construction/Design Plan of Burial Trench (if applicable) based upon the appropriate requirements of 19 15 17 11 NMAC					
Construction/Design Plan of Temporary Pit (for in place burial of a drying pad) - based upon the appropriate requirements of	19 15 17 11 NMAC				
X Protocols and Procedures - based upon the appropriate requirements of 19 15 17 13 NMAC					
Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection F of 19.15 17 13 NMAC					
Waste Material Sampling Plan - based upon the appropriate requirements of Subsection F of 19 15 17 13 NMAC					
X Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings or in case on-site closure standards cannot be achieved) X Soil Cover Design - based upon the appropriate requirements of Subsection H of 19.15 17 13 NMAC					
X Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.13 17.13 NMAC					
X Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19 15 17 13 NMAC					

19 On-mateur Amelianstian Constituentian
Operator Application Certification: I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief
Name (Print) Jamie Goodwin Title Regulatory Technician
1010110
Signature (1000 Cut) Date 12 10 10 10 10 10 10 10 10 10 10 10 10 10
e-mail address Jamie L.Goodwin@conocophillips.com Telephone. 505-326-9784
20 OCD Approval: Permit Application (including closure plan) Closure Plan (only) OCD Conditions (see attachment)
OCD Representative Signature:
Title: Compliance Office OCD Permit Number:
The topological objection of the second of t
21
Closure Report (required within 60 days of closure completion): Subsection K of 19 15 17 13 NMAC
Instructions Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an
approved closure plan has been obtained and the closure activities have been completed
Closure Completion Date:
22 Closure Method:
Waste Excavation and Removal On-site Closure Method Alternative Closure Method Waste Removal (Closed-loop systems only)
If different from approved plan, please explain.
23 Closure Report Regarding Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only:
Instructions: Please identify the facility or facilities for where the liquids, drilling fluids and drill cuttings were disposed. Use attachment if more than two facilities
were utilized.
Disposal Facility Name Disposal Facility Permit Number
Disposal Facility Name Disposal Facility Permit Number
Were the closed-loop system operations and associated activities performed on or in areas that will not be used for future service and operations?
Yes (If yes, please demonstrate compliane to the items below)
Required for impacted areas which will not be used for future service and operations:
Ste Reclamation (Photo Documentation)
Soil Backfilling and Cover Installation Re-vegetation Application Rates and Seeding Technique
Te-vegetation Application rates and seeding recuirique
Cleans Parent Attachment Charlists Instruction First of the following items must be attached to the aleman areast. Black indicate by a check word in
Closure Report Attachment Checklist: Instructions: Each of the following items must be attached to the closure report. Please indicate, by a check mark in the box, that the documents are attached.
Proof of Closure Notice (surface owner and division)
Proof of Deed Notice (required for on-site closure)
Plot Plan (for on-site closures and temporary pits)
Confirmation Sampling Analytical Results (if applicable)
Waste Material Sampling Analytical Results (if applicable)
Disposal Facility Name and Permit Number
Soil Backfilling and Cover Installation
Re-vegetation Application Rates and Seeding Technique
Site Reclamation (Photo Documentation)
On-site Closure Location Latitude Longitude NAD 1927 1983
25
Operator Closure Certification:
I hereby certify that the information and attachments submitted with this closure report is ture, accurate and complete to the best of my knowledge and belief. I also certify that
the closure complies with all applicable closure requirements and conditions specified in the approved closure plan
Name (Print) Title
Signature Date
Date
e-mail address Telephone

DISTRICT I 1625 N. French Dr., Hobbs, N.M. 88240

DISTRICT II 1301 West Grand Avenue, Artesia, N.M. 88210

DISTRICT III 1000 Rio Brazos Rd., Aztec, N.M. 87410

in Dedicated Acres

PC 160.00 ACRES SW/4

DISTRICT IV 1220 S. St. Francis Dr., Santa Fe, NM 87505 State of New Mexico Energy, Minerals & Natural Resources Departments

OIL CONSERVATION DIVISION 1220 South St. Francis Dr. Santa Fe, NM 87505 Form C-102
Pent RECEIVE Revised October 12, 2005

State Lease - 4 Copies
OIL CONS. DIV. DIST. 3 Fee/Lease - 3 Copies

AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION


¹ API	**Pool Code							*Pool Name PICTURED CLIFFS					
⁴ Property C	ode					11		0.1/	ell Number				
			CANYON LARGO UNIT										
OGRID N	э.				*Operator	Name		• E	levation				
		BURLINGTON RESOURCES OIL & GAS COMPANY LP 6							6788'				
					¹⁰ Surface	Location							
UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County				
L	12	25-N	6-W		1855	SOUTH	WEST	RIO ARRIBA					
			11 Bott	om Hole	Location I	f Different Fr	om Surface						
UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County				

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

15 Order No.


¹⁴ Consolidation Code

18 Joint or Infill



BURLINGTON RESOURCES OIL & GAS COMPANY LP

CANYON LARGO UNIT #42, 1855' FSL & 795' FWL SECTION 12, T-25-N, R-6-W, NMPM, RIO ARRIBA COUNTY, NM GROUND ELEVATION: 6788', DATE: NOVEMBER 3, 2009




BETWEEN FOUND MONUMENTS AT THE SOUTHWEST CORNER AND THE WEST QUARTER CORNER OF SECTION 12, TOWNSHIP 25 NORTH, RANGE 6 WEST, N.M.P.M. RIO ARRIBA COUNTY, NEW MEXICO.

LINE BEARS: N 00"25"39" W A DISTANCE OF 2610.09 FEET AS MEASURED BY G.P.S. LOCAL GRID NAD83.


NOTES:

- VECTOR SURVEYS IS NOT LIABLE FOR UNDERGROUND UTILITIES OR PIPELINES. CONTRACTOR SHOULD CALL
 ONE-CALL FOR LOCATION OF ANY MARKED OR UNMARKED BURIED PIPELINES OR CABLES ON WELL PAD AND OR
 ACCESS ROAD AT LEAST TWO (2) WORKING DAYS PRIOR TO CONSTRUCTION.
- 2. RESERVE PIT DIKE. TO BE 8' ABOVE DEEP SIDE (OVERFLOW 3' WIDE AND 1' ABOVE SHALLOW SIDE).



BURLINGTON RESOURCES OIL & GAS COMPANY LP

CANYON LARGO UNIT #42, 1855' FSL & 795' FWL SECTION 12, T-25-N, R-6-W, NMPM, RIO ARRIBA COUNTY, NM GROUND ELEVATION: 6788', DATE: NOVEMBER 3, 2009



HORIZ. SCALE: 1" = 50' VERT. SCALE: 1" = 30'

NOTE:

VECTOR SURVEYS IS NOT LIABLE FOR UNDERGROUND UTILITIES OR PIPELINES. CONTRACTOR SHOULD CALL ONE-CALL FOR LOCATION OF ANY MARKED OR UNMARKED BURIED PIPELINES OR CABLES ON WELL PAD AND OR ACCESS ROAD AT LEAST TWO (2) WORKING DAYS PRIOR TO CONSTRUCTION



New Mexico Office of the State Engineer Water Column/Average Depth to Water

No records found.

.. PLSS Search:

Section(s): 6, 7, 18

Township: 25N

Range: 05W




New Mexico Office of the State Engineer Water Column/Average Depth to Water

No records found.

PLSS Search:

Section(s): 2, 1, 11, 12, 14, **Township:** 25N **Range:**

13



3630

DATA SHEET FOR DEEP GROUND BED CATHODIC. PROTECTION WELLS NORTHWESTERN NEW MEXICO

Operator Metidian Oil Inc. Location: Unit L Sec. 12 Twp 25Rng 06
Name of Well/Wells.or Pipeline Serviced
CANYON LAIGO UNIT# 240
Elevation 6786 Completion Date 8/5/93 Total Depth 463 Land Type F
Casing Strings, Sizes, Types & Depths 6/16 Set 59 of 8 PVC CAGING.
NO GAS, WATER, OF BOULDERS WERE ENCOUNTERED DUTING CASING.
If Casing Strings are cemented, show amounts & types used CemenTed
WITH 12 SACKS
If Cement or Bentonite Plugs have been placed, show depths & amounts used
None
Depths & thickness of water zones with description of water: Fresh, Clear,
Salty, Sulphur, Etc. HiT A WATEL Seep AT 105, And Mole WATEL
AT 220, WATER WAS FrESH, AND A SAMPLE WAS TAKEN.
Depths gas encountered: None
Ground bed depth with type & amount of coke breeze used: #63 DepTH.
Used 132 SACKS of ASbury 218R, (6600#)
Depths anodes placed: 445,416, 404, 404, 395, 360, 356, 301, 295, 289, 231, 226, 226, 214, +208
Depths vent pipes placed: Surface To 463.
Vent pipe perforations: Bollom 360. MEGEIVEM
Remarks:
OIL CON DIV.
The Court is

If any of the above data is unavailable, please indicate so. Copies of all logs, including Drillers Log, Water Analyses & Well Bore Schematics should be submitted when available. Unplugged abandoned wells are to be included.

Land Type may be shown: F-Federal; I-Indian; S-State; P-Fee. If Federal or Indian, add Lease Number.


Form	9-330
(Re-	5-631

UNITED STATES SUBMIT DEPARTMENT OF THE INTERIOR


FLICKIE
(See other In-
structions on


Budget Bureau No 42-R355

	D =	GEOLOGIC	AL SU	RVEY		•	16/6:36	· side)			ION ASIY SERIAL SU.	
WELL CO	NADI ETION	OR RECO	LADI ET	ON I	DEDODI	<u>Λ Ν</u>	D I OG	*	SF_078		THE OR TRIBE NAME	
1a. TYPE OF WE					KEPOKI /	M 1 V	D LOG	<u> </u>				
b. TYPE OF CON	W E	in 🗌 well (Х в	RY 📙	Other				7 Chit AGRE Canyon			
NEW WORK DEEP PLUG DIFF. Other								ŀ	S FARM OR I		• •	
2. NAME OF OPERATOR									Canyon Largo Unit			
	Natural Ga	s Company							9 WELL NO.			
PO Box 990, Farmington, NM 87401									240			
PO BOX	990, Farmi	ngton, NM	8/4U1	i icith an	u State requir	emen	tu) •		10. FIELD AND			
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements). At surface 1800'S, 800'W								-	Basin Dakota 11. SEC. T. R. M., OR PLOCK AND SURVEY			
At top prod. In	terval reported b	clow	10	300 S,	000 W				OR AREA	Т.	-25-N , R - 6-W	
				•					NMPM	, ₁ .	-20-1 1\-0-\\	
At total depth			14. PE	RMIC NO		DATE	ISSUED		12. COUNTY O	n.	13. STATE	
		•			1	•			Rio Ari			
15. DATE SPEDDED	16. DATE T.D.	REACHED 17. DAT	IE COMPL.	(Ready t	o prod.) 18.	ELF	VACIONS (DF	, RKB, R	r, GR, ETC.) •	19. E	LEV. CASINGHEAD	
8-12-73	8-28-		11-26	- 73	-				6786'G	. J		
20. TOTAL DEPTH, MU	& TVD 21. PL	UG, BACK T.D., MD &	TVD 22	HOW M	TIPLE COMPL.,		23. INTER		ROTARY TOOL	s	CABLE TOOLS	
7479'		7462'	D COTTON) . W.D. (1	(D. (N.) (E) D. 1		<u> </u>	>	0-7479'		WAS DIRECTIONAL	
24. PRODUCING INTE		COMPLETION—10	P, BUITOM,	NAME (AND TIDI					123	. WAS DIRECTIONAL SURVEY MADE	
7154-7312-((Dakota)										no	
26. TYPE ELECTRIC	AND OTHER LOGS	RUN								27. W	AS WELL CORED	
IEs; FDC-G	R; Temp. S	Survey									no	
25.					ort all strings	et i						
CASING SIZE	WEIGHT, LB	/FT. DEPTH S		ļ	LE SIZE			NTING R	LCORD		BE FOR	
9 5/8" 4 1/2"	<u>32.3=</u> 11.6=/10.	= '	<u>226'</u> 7479'	13 3/	/ <u>4''</u> !''&7 7/8''		<u>225 cu, f</u> 1875 cu,					
41/2	11.0-710.	34	1419	0 3/4	<u> </u>	<u> </u>	10/3 Cu.	• 1 L •	- / i 1/2 i	 -}		
	<u> </u>	* * *										
29.		LINER RECORI)				30.	T	CBUIG RECO	RD		
817.E	TOP (MD)	BOTTOM (MD)	SACES C	EMENT*	SCREEN (MI	51	SIZE		SPTH SET . (ME) }	PACKER SET (MD)	
		ļ	-				2 3/8		305	SIST	: 3	
31. PERFORATION RE	COLD (Interval, s	.ze and number)	· · · · · · · · · · · · · · · · · · ·		32.	<u>J</u>	ID SHOT	FPACTE	RE, CEMENT	SOLL	EPZE ETC	
7154', 7156	', 7198', 72	236', 7238',	7284',		DEPTH INT						MATERIAL USED	
7286' and 73					7154-73						00 gal. water	
		•										
33.•				PRGI	UCTION							
DATE FIRST PRODUCT	TION PROI	OLCTION METHOD (Flouring, g			and t	vpe of pump	p)			(Producing or	
	1	f	lowing						shut Shi	ut in		
DATE OF TEST	HOURS TESTED	,	PROD	N. FOR PERIOD	OIL-BBL.		GAS-MCF	٠. '	WATER-BBL.	i	GAS-OIL RATIO	
11-26-73	CASING PRESSI	3/4"			<u> </u>		<u> </u>					
SI 722	SI 2472	.RL CALCULATED 24-HOLE RAT		EBL.	GAS	мсғ. 34 А		VATER	BBL.	OIL GE	AVITY-API (CORR.)	
34. DISPOSITION OF	1		, '					1	TEST WITNESS	ED BY		
	C. Rhames											
35. LIST OF ATTACE	AMENTS							!				
36. I hereby certify		•	nformation	is comp	lete and corre	ect as	s determined	from a	ll available re	cords		
signed 🚅		1.111	ті	TLE D	rilling Cl	erk			DATE	<u>Nov</u>	<u>ember 29, 19</u>	




CANYON LARGO UNIT 42 MINES, MILLS AND QUARRIES











Siting Criteria Compliance Demonstration & Hydro Geologic Analysis

The Canyon Largo Unit 42 is not located in an unstable area. The location is not over a mine and is not on the side of a hill as indicated on the Mines, Mills and Quarries Map and Topographic Map. The location of the excavated pit material will not be located within 300' of any continuously flowing watercourse or 200' from any other watercourse as indicated on the Topographic Map. The location is not within a 100-year floodplain area as indicated on the FEMA Map. The Cathodic well data from the Canyon Largo Unit 240 has an elevation of 6786' and groundwater depth of 105'. The subject well has an elevation of 6788' which is greater than the Canyon Largo Unit 42, therefore the groundwater depth is greater than 107'. There are no iWATERS data points located in the area as indicated on the TOPO Map. The hydro geologic analysis indicates the groundwater depth and the San Jose formation will create a stable area for this new location.

Hydrogeological report for Canyon Largo Unit 42

Regional Hydrogeological context:

The San Jose Formation of Eocene age occurs in New Mexico and Colorado, and its outcrop forms the land surface over much of the eastern half of the central basin. It overlies the Nacimiento Formation in the area generally south of the Colorado-New Mexico State line and overlies the Animas Formation in the area generally north of the State line.

The San Jose Formation was deposited in various fluvial-type environments. In general, the unit consists of an interbedded sequence of sandstone, siltstone, and variegated shale. Thickness of the San Jose Formation generally increases from west to east (200 feet in the west and south to almost 2,700 feet in the center of the structural basin). Ground water is associated with alluvial and fluvial sandstone aquifers. Thus, the occurrence of ground water is mainly controlled by the distribution of sandstone in the formation. The distribution of such sandstone is the result of original depositional extent plus any post-depositional modifications, namely erosion and structural deformation. Transmissivity data for San Jose Formation are minimal. Values of 40 and 120 feet squared per day were determined from two aquifer tests (Stone et al, 1983, table 5). The reported or measured discharge from 46 water wells completed in San Jose Formation ranges from 0.15 to 61 gallons per minute and the median is 5 gallons per minute. Most of the wells provide water for livestock and domestic use.

The San Jose Formation is a very suitable unit for recharge from precipitation because soils that form on the unit are sandy and highly permeable and therefore readily adsorb precipitation. However, low annual precipitation, relatively high transpiration and evaporation rates, and deep dissection of the San Jose Formation by the San Juan River and its tributaries all tend to reduce the effective recharge to the unit.

Stone et al., 1983, Hydrogeology and Water Resources of the San Juan Basin, New Mexico: Socorro, New Mexico Bureau of Mines and Mineral Resources Hydrologic Report 6, 70 p.

In

Burlington Resources Oil & Gas Company, LP San Juan Basin Pit Design and Construction Plan

In accordance with Rule 19.15.17 the following information describes the design and construction of temporary pits on Burlington Resources Oil & Gas Company, LP (BR) locations. This is BR's standard procedure for all temporary pits. A separate plan will be submitted for any temporary pit which does not conform to this plan.

- 1. BR will design and construct a properly sized and approved temporary pit which will contain liquids and solids and should prevent contamination of fresh water and protect public health and environment.
- 2. Prior to constructing the pit, topsoil will be stockpiled in the construction zone for later use in restoration.
- 3. BR will sign the well location in compliance with 19.15.3.103 NMAC.
- 4. BR shall construct all new fences around the temporary pit utilizing 48" steel mesh field-fence (hogwire) on the bottom with a single strand of barbed wire on top. T-posts shall be installed every 12 feet and corners shall be anchored utilizing a secondary T-post. Temporary pits will be fenced at all times excluding drilling or workover operations, when the front side of the fence will be temporarily removed for operational purposes.
- 5. BR shall construct the temporary pit so that the foundation and interior slopes are firm and free of rocks, debris, sharp edges or irregularities to prevent liner failure.
- 6. BR shall construct the pit so that the slopes are no steeper than two horizontal feet to one vertical foot.
- 7. Pit walls will be walked down by a crawler type tractor following construction.
- 8. All temporary pits will be lined with a 20-mil, string reinforced, LLDPE liner, complying with EPA SW-846 method 9090A requirements.
- 9. Geotextile will be installed beneath the liner when rocks, debris, sharp edges or irregularities cannot be avoided.
- 10. All liners will be anchored in the bottom of a compacted earth-filled trench at least 18 inches deep.
- 11. BR will minimize liner seams and orient them up and down, not across a slope. Factory seams will be used whenever possible. BR will ensure all field seams are welded by qualified personnel. Field seams will be overlapped four to six inches and will be oriented parallel to the line of maximum slope. BR will minimize the number of field seams in corners and irregularly shaped areas.
- 12. The liner shall be protected from any fluid force or mechanical damage through the use of mud pit slides, or a manifold system.
- 13. The pit shall be protected from run-off by constructing and maintaining diversion ditches around the location or around the perimeter of the pit in some cases.
- 14. The volume of the pit shall not exceed 10 acre-feet, including freeboard.
- 15. Temporary blow pits will be constructed to allow gravity flow to discharge into lined drill pit.
- 16. The lower half of the blow pit (nearest lined pit) will be lined with a 20-mil, string reinforced, LLDPE liner. The upper half of the blow pit will remain unlined as allowed in Rule 19.15.17.11 F.11.
- 17. BR will not allow freestanding liquids to remain on the unlined portion of a temporary blow pit.

Burlington Resources Oil & Gas Company, LP San Juan Basin Maintenance and Operating Plan

In accordance with Rule 19.15.17 the following information describes the operation and maintenance of temporary pits on Burlington Resources Oil & Gas Company, LP (BR) locations. This is BR's standard procedure for all temporary pits. A separate plan will be submitted for any temporary pit which does not conform to this plan.

- 1. BR will operate and maintain a temporary pit to contain liquids and solids and maintain the integrity of the liner and liner system to prevent contamination of fresh water and protect public health and environment.
- 2. BR will conserve drilling fluids by transferring liquids to pits ahead of the rigs whenever possible. All other drilling fluids will be disposed at Basin Disposal Inc., permit # NM-01-005.
- 3. BR will not discharge or store any hazardous waste in any temporary pit.
- 4. If any pit liner's integrity is compromised, or if any penetration of the liner occurs above the liquid's surface, then BR shall notify the Aztec Division office by phone or email within 48 hours of the discovery and repair the damage or replace the liner.
- 5. If a leak develops below the liquid's level, BR shall remove all liquids above the damaged liner within 48 hours and repair the damage or replace the liner. BR shall notify the Aztec Division office by phone or email within 48 hours of the discovery for leaks less than 25 barrels. BR shall notify the Aztec Division office as required pursuant to Subsection B of 19.15.3.116 NMAC shall be reported within twenty-four (24) hours of discovery of leaks greater than 25 barrels. In addition, immediate verbal notification pursuant to Subsection B, Paragraph (1), and Subparagraph (d) of 19.15.3.116 NMAC shall be reported to the division's Environmental Bureau Chief.
- 6. The liner shall be protected from any fluid force or mechanical damage through the use of mud pit slides, or a manifold system.
- 7. The pit shall be protected from run-off by constructing and maintaining diversion ditches around the location or around the perimeter of the pit in some cases.
- 8. BR shall immediately remove any visible layer of oil from the surface of the temporary pit after cessation of a drilling or workover operation. Oil absorbent booms will be utilized to contain and remove oil from the pit's surface. An oil absorbent boom will stored on-site until closure of pit.
- 9. Only fluids generated during the drilling or workover process may be discharged into a temporary pit.
- 10. BR will maintain the temporary pit free of miscellaneous solid waste or debris.
- 11. During drilling operations, BR will inspect the temporary pit at least once daily to ensure compliance with this plan. Inspections will be logged in the IADC reports. BR will file this log with the Aztec Division office upon closure of the pit.
- 12. After drilling operations, BR will inspect the temporary pit weekly so long as liquids remain in the temporary pit. A log of the inspections will be stored at BR's office electronically and will be filed with the Aztec Division office upon closure of the pit.
- 13. BR shall maintain at least two feet of freeboard for a temporary pit.
- 14. BR shall remove all free liquids from a temporary pit within 30 days from the date the operator releases the drilling rig.
- 15. BR shall remove all free liquids from a cavitation pit within 48 hours after completing cavitation. BR may request additional time to remove liquids from the Aztec Division office if it is not feasible to remove liquids within 48 hours.

ConocoPhillips Company San Juan Basin Closure Plan

In accordance with Rule 19.15.17.12 NMAC the following information describes the closure requirements of temporary pits on ConocoPhillips Company (COPC) locations. This is COPC's standard procedure for all temporary pits. A separate plan will be submitted for any temporary pit which does not conform to this plan.

All closure activities will include proper documentation and be available for review upon request and will be submitted to OCD within 60 days of closure of pit closure. Closure report will be filed on C-144 and incorporate the following:

- Details on Capping and Covering, where applicable.
- Plot Plan (Pit Diagram)
- Inspection Reports
- Sampling Results
- C-105
- Copy of Deed Notice will be filed with County Clerk

- All free standing liquids will be removed at the start of the pit closure process from the pit and disposed of in a division—approved facility or recycle, reuse or reclaim the liquids in a manner that the appropriate division district office approves. The facilities to be used will be Basin Disposal (Permit #NM-01-005) and Envirotech Land Farm (Permit #NM-01-011)
- 2. The preferred method of closure for all temporary pits will be on-site burial, assuming that all the criteria listed in sub-section (B) of 19.15.17.13 are met.
- 3. The surface owner shall be notified of COPC's closing of the temporary pit prior to closure as per the approved closure plan via certified mail, return receipt requested.
- 4. Within 6 months of the Rig Off status occurring COPC will ensure that temporary pits are closed, re-contoured, and reseeded.
- 5. Notice of Closure will be given prior to the Aztec Division office between 72 hours and one week via email, or verbally. The notification of closure will include the following:
 - i. Operator's name
 - Location by Unit Letter, Section, Township, and Range. Well name and API number.
- 6. Liner of temporary pit shall be removed above "mud level" after stabilization. Removal of liner will consist of manually or mechanically cutting liner at mud level and removing all remaining liner. Care will be taken to remove "All" of the liner i.e., edges of liner entrenched or buried. All excessive liner will be disposed of at the San Juan County Landfill located on CR 3100.
- 7. Pit contents shall be mixed with non-waste containing, earthen material in order to achieve the solidification process. The solidification process will be accomplished using a combination of natural drying and mechanically mixing. Pit contents will be mixed with non-waste, earthen material to a consistency that is deemed a safe and stable. The mixing ratio shall not exceed 3 parts clean soil to 1 part pit contents.
- 8. A five point composite sample will be taken of the pit using sampling tools and all samples tested per Subsection B of 19.15.17.13(B)(1)(b). In the event that the criteria are not met, all contents will be handled per Subparagraph (a) of Paragraph (1) of Subsection B of 19.15.17.13 i.e., Dig and haul.

Components	Tests Method	Limit (mg/Kg)
Benzene	EPA SW-846 8021B or 8260B	0.2
BTEX	EPA SW-846 8021B or 8260B	50
TPH	EPA SW-846 418.1	2500
GRO/DRO	EPA SW-846 8015M	500
Chlorides	EPA 300.1	1000(500)

9. A five point composite sample will be taken from the cavitation pit pursuant to 19.15.17.13(B)(1)(b)(i) in order to assure there has not been any type of release.

Components	Tests Method	Limit (mg/Kg)
Benzene	EPA SW-846 8021B or 8260B	0.2
BTEX	EPA SW-846 8021B or 8260B	50
TPH ·	EPA SW-846 418.1	2500
GRO/DRO	EPA SW-846 8015M	500
Chlorides	EPA 300.1	500

- 10. Upon completion of solidification and testing standards being passed, the pit area will be backfilled with compacted, non-waste containing, earthen material. A minimum of four feet of cover shall be achieved and the cover shall include one foot of suitable material to establish vegetation at the site, or the background thickness of topsoil, whichever is greater. If standard testing fails COPC will dig and haul all contents pursuant to 19.15.17.13.i.a. After doing such, confirmation sampling will be conducted to ensure a release has not occurred.
- 11. During the stabilization process if the liner is ripped by equipment the Aztec OCD office will be notified within 48 hours and the liner will be repaired if possible. If the liner can not be repaired then all contents will be excavated and removed.
- 12. Dig and Haul Material will be transported to the Envirotech Land Farm located 16 miles south of Bloomfield on Angel Peak Road, CR 7175. Permit # NM010011
- 13. Re-contouring of location will match fit, shape, line, form and texture of the surrounding. Re-shaping will include drainage control, prevent ponding, and prevent erosion. Natural drainages will be unimpeded and water bars and/or silt traps will be place in areas where needed to prevent erosion on a large scale. Final re-contour shall have a uniform appearance with smooth surface, fitting the natural landscape.
- 14. Notification will be sent to OCD when the reclaimed area is seeded.
- 15. COPC shall seed the disturbed areas the first growing season after the operator closes the pit. Seeding will be accomplished via drilling on the contour whenever practical or by other division-approved methods. BLM or Forest Service stipulated seed mixes will used on federal lands. Vegetative cover will equal 70% of the native perennial vegetative cover (un-impacted) consisting of at least three native plant species, including at least one grass, but not including noxious weeds, and maintain that cover through two successive growing seasons. Repeat seeding or planting will be continued until successful vegetative growth occurs.

Туре	Variety or Cultivator	PLS/A 3.0		
Western wheatgrass	Arriba			
Indian ricegrass	Paloma or Rimrock	3.0		
Slender wheatgrass	San Luis	2.0		
Crested wheatgrass	Hy-crest	3.0		
Bottlebrush Squirreltail	Unknown	2.0		
Four-wing Saltbrush	Delar	.25		

Species shall be planted in pounds of pure live seed per acre: Present Pure Live Seed (PLS) = Purity X Germination/100

Two lots of seed can be compared on the basis of PLS as follows:

Source No. One (poor quality)

Purity

50 percent

Germination

40 percent

Percent PLS

20 percent

Source No. two (better quality)

Purity

80 percent

Germination

63 percent

Percent PLS

50 percent

5 lb. bulk seed required to make 2 lb. bulk seed required to make

1 lb. PLS 1 lb. PLS


16. The temporary pit will be located with a steel marker, no less than four inches in diameter, cemented in a hole three feet deep in the center of the onsite burial upon the abandonment of all the wells on the pad. The marker will be flush with the ground to allow access of the active well pad and for safety concerns. The marker will include a threaded collar to be used for future abandonment. The top of the marker will contain a welded steel 12" square plate that indicates the onsite burial of the temporary pit. The plate will be easily removable and a four foot tall riser will be threaded into the top of the collar marker and welded around the base with the operator's information at the time of all wells on the pad are abandoned. The operator's information will include the following: Operator Name, Lease Name, Well Name and number, Unit Number, Section, Township, Range and an indicator that the marker is an onsite burial location.

ConocoPhillips Company San Juan Basin Below Grade Tank Design and Construction

In accordance with NMAC 19.15.17 the following information describes the design and construction of below grade tanks on ConocoPhillips Company (COPC) locations. This is COPC's standard procedure for all below grade tanks (BGT). A separate plan will be submitted for any BGT which does not conform to this plan.

- COPC will design and construct a properly sized and approved BGT which will
 contain liquids and should prevent contamination of fresh water to protect the
 public health and environment.
- 2. COPC signage will comply with 19.15.17.11NMAC. COPC includes Emergency Contact information on all signage.
- 3. COPC has approval to use alternative fencing that provides better protection. COPC constructs fencing around the BGT using 4 foot hog wire fencing topped with two strands of barbed wire, or with a pipe top rail. A six foot chain link fence topped with three strands of barbed wire will be use if the well location is within 1000 feet of permanent residence, school, hospital, institution or church. COPC ensures that all gates associated with the fence are closed and locked when responsible personnel are not onsite.
- 4. COPC will construct a screened, expanded metal covering, on the top of the BGT.
- 5. COPC shall ensure that a below-grade tank is constructed of materials resistant to the below-grade tank's particular contents and resistant to damage from sunlight as shown on design drawing and specification sheet.
- 6. The COPC below-grade tank system shall have a properly constructed foundation consisting of a level base free of rocks, debris, sharp edges or irregularities to prevent punctures, cracks or indentations of the liner or tank bottom as shown on design drawing.
- 7. COPC shall operate and install the below-grade tank to prevent the collection of surface water run-on. COPC has built in shut off devices that do not allow a below-grade tank to overflow. COPC constructs berms and corrugated retaining walls at least 6" above ground to keep from surface water run-on entering the below grade tank as shown on the design plan.
- 8. COPC will construct and use a below-grade tank that does not have double walls. The below-grade tank's side walls will be open for visual inspection for leaks, the below-grade tank's bottom is elevated a minimum of six inches above the underlying ground surface and the below-grade tank is underlain with a geomembrane liner to divert leaked liquid to a location that can be visually inspected.

- 9. COPC has equipped the below-grade tanks with the ability to detect high level in the tank and provide alarm notification and shutdown process streams into the tank. Once high level is detected RTU logic closes the inlet separator sales valve and does not permit vent valve to open. This shutdown of the sales valve and gagging of the vent valves prevents any hydrocarbon process streams from entering the pit tank once a high level is detected. Furthermore, an electronic page is sent to the COPC MSO for that well site and to the designated contract "Water-Hauling" Company indicating a high level and that action must be taken to address this alarm. The environmental drain line from COPC's compressor skid under normal operating conditions is in the open position. The environmental drain line is in place to capture any collected rain water or spilled lubricants from our compressor skids. The swab drain line is a manually operated drain and by normal operating procedures is in the closed position. The tank drain line is also a manually operated drain and during normal operations it is in the closed position.
- 10. The geomembrane liner consists of a 45-mil flexible LLDPE material manufactured by Raven Industries as J45BB. This product is a four layer reinforced laminated containing no adhesives. The outer layers consist of a high strength polyethylene film manufactured using virgin grade resins and stabilizers for UV resistance in exposed applications. The J45BB is reinforced with 1300 denier (minimum) tri-directional scrim reinforcement. It exceeds ASTMD3083 standard by 10%. J45BB has a warranty for 20 years from Raven Industries and is attached. It is typically used in Brine Pond, Oilfield Pit liner and other industrial applications. The manufacture specific sheet is attached and the design attached displays the proper installation of the liner.
- 11. The general specification for design and construction are attached in the COPC document.



DURASMIN®

BOJBBAUF

PROPERTIES	TIESTAMETHOD	380	0BB	J36	3B	. J45	3B	
	,	Min. Roll Averages	Typical Roll Averages	Min. Roll Averages	Typical Roll Averages	Min, Roll Averages	Typical Roll Averages	
Appearance		Black/Black		Black/Black		Black/Black		
Thickness	ASTM D 5199	27 mil	30 mil	32 mil	36 mil	40 mil	45 mil	
Weight Lbs.Per MSF. (oz/yd²)	ASTM D 5261	126 lbs (18.14)	140 lbs (20.16)	151 lbs (21.74)	168 lbs (24.19)	189 lbs (27.21)	210 lbs (30.24)	
Construction		**Extrusion laminated with encapsulated tri-directional scrim reinforcement						
Ply Adhesion	ASTM D 413	16 lbs	20 lbs	19 lbs	24 lbs	25 lbs	31 lbs	
1" Tensile Strength	ASTM D 7003	88 lbf MD 63 lbf DD	110 lbf MD 79 lbf DD	90 lbf MD 70 lbf DD	113 lbf MD 87 lbf DD	110 lbf MD 84 lbf DD	138 lbf MD 105 lbf DD	
L. Tensile Elongation @ Break % (Film Break)	ASTM D 7003	550 MD 550 DD	750 MD 750 DD	550 MD 550 DD	750 MD 750 DD	550 MD 550 DD	750 MD 750 DD	
1º Tensile Elongation @ Peak % (Scrim Break)	ASTM D 7003	20 MD 20 DD	33 MD 33 DD	20 MD 20 DD	30 MD ⁻ 31DD	20 MD 20 DD	36 MD 36 DD	
Tongue Tear Strength	ASTM D 5884	75 lbf MD 75 lbf DD	97 lbf MD 90 lbf DD	75 lbf MD 75 lbf DD	104 lbf MD 92 lbf DD	100 lbf MD 100 lbf DD	117 lbf MD 118 lbf DD	
Grab Tensile	ASTM D 7004	180 lbf MD 180 lbf DD	218 lbf MD 210 lbf DD	180 lbf MD 180 lbf DD	222 lbf MD 223 lbf DD	220 lbf MD 220 lbf DD	257 lbf MD 258 lbf DD	
Trapezoid Tear	ASTM D 4533	120 lbf MD 120 lbf DD	146 lbf MD 141 lbf DD	130 lbf MD 130 lbf DD	189 lbf MD 172 lbf DD	160 lbf MD 160 lbf DD	193 lbf MD 191 lbf DD	
*Dimensional Stability	ASTM D 1204	<1	<0.5	<1	<0.5	<1	<0.5	
Puncture Resistance	ASTM D 4833	50 lbf	64 lbf	65 lbf	83 lbf	80 lbf	99 lbf	
Maximum Use Temperature		180° F	180° F	180° F	180° F	180° F	180° F	
Minimum Use Temperature		-70° F	-70° F	-70° F	-70° F	-70° F	-70° F	

MD = Machine Direction DD = Diagonal Directions



Note: Minimum Roll Averages are set to take into account product variability in addition to testing variability between laboratories.

*Dimensional Stability Maximum Value

**DURA-SKRIM J30BB, J36BB & J45BB are a four layer reinforced laminate containing no adhesives. The outer layers consist of a high strength polyethylene film manufactured using virgin grade resins and stabilizers for UV resistance in exposed applications. DURA-SKRIM J30BB, J36BB & J45BB are reinforced with a 1300 denier (minimum) tri-directional scrim reinforcement.

Note: RAVEN INDUSTRIES MAKES NO WARRANTIES AS TO THE FITNESS FOR A SPECIFIC USE OR MERCHANTABILITY OF PRODUCTS REFERRED TO, no guarantee of satisfactory results from reliance upon contained information or recommendations and disclaims all liability for resulting loss or damage.

PEANTLOGATION

Sioux Falls, South Dakota

SALES OFFICE

RAVEN INDUSTRIES P.O. Box 5107 Sloux Falls, SD 57117-5107 (605) 335-0174 (605) 331-0333 FAX **800-635-3456**

08/06

RAVEN INDUSTRIES INC. EXPOSED GEOMEMBRANE LIMITED WARRANTY

Raven Industries Inc. warrants Dura-Skrim J30BB, J36BB, and J45BB to be free from manufacturing defects and to be able to withstand normal exposure to sunlight for a period of 20 years from the date of sale for normal use in approved applications in the U.S and Canada, excluding Hawaii. This warranty is effective for products sold and shipped from January 1, 2008 to December 31, 2008. These dates will be updated prior to December 31, 2008.

This Limited Warranty does not include damages or defects in the Raven geomembrane resulting from acts of God, casualty or catastrophe including but not limited to: earthquakes, floods, piercing hail, or tornadoes. The term "normal use" as used herein does not include, among other things improper handling during transportation, unloading, storage or installation, the exposure of Raven geomembranes to harmful chemicals, atypical atmospheric conditions, abuse of Raven geomembranes by machinery, equipment or people; improper site preparation or covering materials, excessive pressures or stresses from any source or improper application or installation. Raven geomembrane material warranty is intended for commercial use only and is not in effect for the consumer as defined in the Magnuson Moss Warranty or any similar federal, state, or local statues. The parties expressly agree that the sale hereunder is for commercial or industrial use only.

Should defects or premature loss of use within the scope of the above Limited Warranty occur, Raven Industries Inc. will, at its option, repair or replace the Raven geomembrane on a pro-rata basis at the then current price in such manner as to charge the Purchaser/User only for that portion of the warranted life which has elapsed since purchase of the material. Raven Industries Inc. will have the right to inspect and determine the cause of any alleged defect in the Raven geomembrane and to take appropriate steps to repair or replace the Raven geomembrane if a defect exists which is covered under this warranty. This Limited Warranty extends only to Raven's geomembrane, and does not extend to the installation service of third parties nor does it extend to materials furnished or installed by others in connection with the intended use of the Raven geomembranes.

Any claim for any alleged breach of this warranty must be made in writing, by certified mail, to the General Manager of Engineered Films Division of Raven Industries Inc. within ten (10) days of becoming aware of the alleged defect. Should the required notice not be given, the defect and all warranties are waived by the Purchaser, and Purchaser shall not have any rights under this warranty. Raven Industries Inc. shall not be obligated to perform repairs or replacements under this warranty unless and until the area to be repaired or replaced is clean, dry, and unencumbered. This includes, but is not limited to, the area made available for repair and/or replacement of Raven geomembrane to be free from all water, dirt, sludge, residuals and liquids of any kind. If after inspection it is determined that there is no claim under this Limited Warranty, Purchaser shall reimburse Raven Industries Inc. for its costs associated with the site inspection.

in the event the exclusive remedy provided herein fails in its essential purpose, and in that event only, the Purchaser shall be entitled to a return of the purchase price for so much of the material as Raven Industries Inc. determines to have violated the warranty provided herein. Raven Industries Inc. shall not be liable for direct, indirect, special, consequential or incidental damages resulting from a breach of this warranty including, but not limited to, damages for loss of production, lost profits, personal injury or property damage. Raven Industries Inc. shall not be obligated to reimburse Purchaser for any repairs, replacement, modifications or alterations made by Purchaser unless Raven Industries Inc. specifically authorized, in writing, said repairs, replacements, modifications or alteration in advance of them having been made. Raven Industry's liability under this warranty shall in no event exceed the replacement cost of the material sold to the Purchaser for the particular installation in which it failed.

Raven Industries Inc. neither assumes nor authorizes any person other than the undersigned of Raven Industries Inc. to assume for it any other or additional liability in connection with the Raven geomembrane made on the basis of the Limited Warranty. The Limited Warranty on the Raven geomembrane herein is given in lieu of all other possible material warranties, either expressed or implied, and by accepting delivery of the material; Purchaser waives all other possible warranties, except those specifically given. This Limited Warranty may only be modified by written document mutually executed by Owner and Raven Industries Inc.

Limited Warranty is extended to the purchaser/owner and is non-transferable and non-assignable; i.e., there are no third-party beneficiaries to this warranty.

Purchaser acknowledges by acceptance that the Limited Warranty given herein is accepted in preference to any and other possible materials warranties.

THIS LIMITED WARRANTY SHALL BE GOVERNED BY SOUTH DAKOTA LAW AND VENUE FOR ALL LEGAL PROCEEDINGS IN CONNECTION WITH THIS LIMITED WARRANTY SHALL BE IN MINNEHAHA COUNTY, SOUTH DAKOTA. RAVEN INDUSTRIES INC. MAKES NO WARRANTY OF ANY KIND OTHER THAN THAT GIVEN ABOVE AND HEREBY DISCLAIMS ALL WARRANTIES, BOTH EXPRESSED OR IMPLIED, OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. THIS IS THE ONLY WARRANTY THAT APPLIES TO THE MATERIALS REFERRED TO HEREIN AND RAVEN INDUSTRIES INC. DISCLAIMS ANY LIABILITY FOR ANY WARRANTIES GIVEN BY ANY OTHER PERSON OR ENTITY, EITHER WRITTEN OR ORAL.

RAVEN INDUSTRIES' WARRANTY BECOMES AN OBLIGATION OF RAVEN INDUSTRIES INC. TO PERFORM UNDER THE WARRANTY ONLY UPON RECEIPT OF FINAL PAYMENT AND EXECUTION BY A DULY AUTHORIZED OFFICER OF RAVEN INDUSTRIES INC.

ConocoPhillips Company San Juan Basin Below Grade Tank Maintenance and Operating Plan

In accordance with Rule 19.15.17 the following information describes the operation and maintenance of Below Grade Tank (BGT) on ConocoPhillips Company (COPC) locations. This is COPC's standard procedure for all BGT. A separate plan will be submitted for any BGT which does not conform to this plan.

- COPC will operate and maintain a BGT to contain liquids and solids and maintain
 the integrity of the liner, liner system and secondary containment system to
 prevent contamination of fresh water and protect public health and environment.
 COPC will accomplish this by performing an inspection on a monthly basis,
 installing cathodic protection, and automatic overflow shutoff devices as seen on
 the design plan.
- 2. COPC will not discharge into or store any hazardous waste in the BGT.
- 3. COPC shall operate and install the below-grade tank to prevent the collection of surface water run-on. COPC has built in shut off devices that do not allow a below-grade tank to overflow. COPC constructs berms and corrugated retaining walls at least 6" above ground to keep from surface water run-on entering the below grade tank as shown on the design plan.
- 4. As per 19.17.15.12 Subsection D, Paragraph 3, COPC will inspect the below-grade tank at least monthly reviewing several items which include 1) containment berms adequate and no oil present, 2) tanks had no visible leaks or sign of corrosion, 3) tank valves, flanges, and hatches had no visible leaks and 4) no evidence of significant spillage of produced liquids. In addition, COPC's multi-skilled operators (MSOs) are required to visit each well location once per week. If detected on either inspection, COPC shall remove any visible or measurable layer of oil from the fluid surface of a below-grade tank in an effort to prevent significant accumulation of oil overtime. The written record of the monthly inspections will include the items listed above and will be maintained for five years.
- 5. COPC shall require and maintain a 10" adequate freeboard to prevent overtopping of the below-grade tank.
- 6. If the below grade tank develops a leak, or if any penetration of the pit liner or below grade tank, occurs below the liquid's surface, then COPC shall remove all liquid above the damage or leak line within 48 hours. COPC shall notify the appropriate district office. COPC shall repair or replace the pit liner or below grade tank, within 48 hours of discovery. If the below grade tank or pit liner does not demonstrate integrity, COPC shall promptly remove and install a below grade tank or pit liner that complies with Subsection I of 19.15.17.11 NMAC. COPC shall notify the appropriate district office of a discovery of leaks less than 25 barrels as required pursuant to Subsection B of 19.15.3.116 NMAC shall be reported within twenty-four (24) hours of discovery of leaks greater than 25 barrels. In addition, immediate verbal notification pursuant to Subsection B, Paragraph (1); and Subparagraph (d) of 19.15.3.116 NMAC shall be reported to the division's Environmental Bureau Chief.

ConocoPhillips Company San Juan Basin Below Grade Tank Closure Plan

In accordance with Rule 19.15.17.13 NMAC the following information describes the closure requirements of Below Grade Tanks (BGTs) on ConocoPhillips Company locations hereinafter known as COPC locations. This is COPC's standard procedure for all BGTs. A separate plan will be submitted for any BGT which does not conform to this plan.

General Requirements:

- 1. COPC shall close a below-grade tank within the time periods provided in Subsection A of 19.15.17.13 NMAC. This will include a) below-grade tanks that do not meet the requirements of Paragraphs (1) through (4) of Subsection I of 19.15.17.11 NMAC or is not included in Paragraph (5) of Subsection I of f19.15.17.11 NMAC within five years, if not retrofitted to comply with Paragraphs (1) through (4) of Subsection I of 19.15.17.11 NMAC; b) permitted below-grade tanks within 60 days of cessation of the below-grade tank's operation., or c) an earlier date that the division requires because of imminent danger to fresh water, public health or the environment. For any closure, COPC will file the C144 Closure Report as required.
- 2. COPC shall remove liquids and sludge from a below-grade tank prior to implementing a closure method and shall dispose of the liquids and sludge in a division-approved facility. The facilities to be used will be Basin Disposal (Permit #NM-01-005) and Envirotech Land Farm (Permit #NM-01-011). The liner after being cleaned well (Subsection D, Paragraph 1, Subparagraph (m) of 19.15.9.712 NMAC) will be disposed of at the San Juan County Regional Landfill located on CR 3100.
- 3. COPC will receive prior approval to remove the below-grade tank and dispose of it in a division-approved facility or recycle, reuse, or reclaim it in a manner that the appropriate division district office approves. Documentation of how the below-grade tank was disposed of or recycled will be provided in the closure report.
- 4. If there is any on-site equipment associated with a below-grade tank, then COPC shall remove the equipment, unless the equipment is required for some other purpose.
- 5. COPC shall test the soils beneath the below-grade tank to determine whether a release has occurred. COPC shall collect, at a minimum, a five point, composite sample; collect individual grab samples from any area that is wet, discolored or showing other evidence of a release; and analyze for BTEX, TPH and chlorides to demonstrate that the benzene concentration, as determined by EPA SW-846 methods 8021B or 8260B or other EPA method that the division approves, does not exceed 0.2 mg/kg; total BTEX concentration, as determined by EPA SW-846 methods 8021B or 8260B or other EPA method that the division approves, does not exceed 50 mg/kg; the TPH concentration, as determined by EPA method 418.1 or other EPA method that the division approves, does not exceed 100 mg/kg; and the chloride concentration, as determined by EPA method 300.1 or other EPA method that the division approves, does not exceed 250 mg/kg, or the background concentration, whichever is greater. COPC shall notify the division of its results on form C-141.

- 6. If COPC or the division determines that a release has occurred, then COPC shall comply with 19.15.3.116 NMAC and 19.15.1.19 NMAC, as appropriate.
- 7. If the sampling program demonstrates that a release has not occurred or that any release does not exceed the concentrations specified in Paragraph (4) of Subsection E of 19.15.17.13 NMAC, then COPC shall backfill the excavation with compacted, non-waste containing, earthen material; construct a division-prescribed soil cover; recontour and re-vegetate the site.
- 8. Notice of Closure will be given prior to closure to the Aztec Division office between 72 hours and one week via email or verbally. The notification of closure will include the following:
 - i. Operator's name
 - ii. Location by Unit Letter, Section, Township, and Range. Well name and API number.
- The surface owner shall be notified of COPC's closing of the below-grade tank prior to closure as per the approved closure plan via certified mail, return receipt requested.
- 10. Re-contouring of location will match fit, shape, line, form and texture of the surrounding. Re-shaping will include drainage control, prevent ponding, and prevent erosion. Natural drainages will be unimpeded and water bars and/or silt traps will be place in areas where needed to prevent erosion on a large scale. Final re-contour shall have a uniform appearance with smooth surface, fitting the natural landscape.
- 11. COPC shall seed the disturbed areas the first growing season after the operator closes the pit. Seeding will be accomplished via drilling on the contour whenever practical or by other division-approved methods. BLM stipulated seed mixes will used on federally jurisdicted lands and division-approved seed mixtures (administratively approved if required) will be utilized on all State or private lands. Vegetative cover will equal 70% of the native perennial vegetative cover (unimpacted) consisting of at least three native plant species, including at least one grass, but not including noxious weeds, and maintain that cover through two successive growing seasons. If alternate seed mix is required by the state, private owner or tribe, it will be implemented with administrative approval if needed. COPC will repeat seeding or planting will be continued until successful vegetative growth occurs.
- 12. A minimum of four feet of cover shall be achieved and the cover shall include one foot of suitable material to establish vegetation at the site, or the background thickness of topsoil, whichever is greater.
- 13. All closure activities will include proper documentation and be available for review upon request and will be submitted to OCD within 60 days of closure of the belowgrade tank. Closure report will be filed on C-144 and incorporate the following:
 - Soil Backfilling and Cover Installation
 - Re-vegetation application rates and seeding techniques
 - Photo documentation of the site reclamation
 - Confirmation Sampling Results
 - Proof of closure notice