District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Avenue, Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

## State of New Mexico Energy Minerals and Natural Resources

Revised August 8, 2011
Submit 1 Copy to appropriate District Office to

Form C-141

Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505 Submit 1 Copy to appropriate District Office to accordance with 19.15.29 NMAC.

			Rele	ease Notific	cation	and Co	orrective	Actio	n			
						OPERA'	ΓOR		☐ Initia	al Report	$\boxtimes$	Final Report
Name of Co	mpany Bu	rlington Res	ources O	l & Gas Compa			ystal Tafoya	000=				
Address 340 Facility Nar	DI East 30"	" St, Farmin ff 100	gton, NM				No.(505) 326- be: <b>Gas Well</b>	9837				
·		11 100										
Surface Ow	ner BLM			Mineral C	Owner B	LM (SF-0	78311)		API No	.30-045-31	.794	
	1					OF RE						
Unit Letter A	Section 19	Township 32N	Range 12W	Feet from the 955		South Line North	Feet from the 855	East	/West Line East	County San Juan		
Latitude <u>36.976135</u> Longitude <u>108.129287</u>												
				NAT	URE	OF REL	EASE					
Type of Rele		luced Fluids				Volume of	Release Un	known	Volume R		Non	e
Source of Re	lease Belo	ow Grade Ta	nk			Date and I Unknown	lour of Occurre	nce	October 1	Hour of Disc	covery	
Was Immedia	ate Notice G	Siven?				If YES, To			October	10, 2012		···
			Yes [	No 🛛 Not Re	equired				R	CVD JAN	25 '1	3
By Whom?						Date and I				II CONS.	DIL	6
Was a Watero	course Reac		Yes 🛛 1	No		If YES, Vo	olume Impactin	g the Wa	tercourse.	DIST.	3	
If a Watercou	irse was Imp	pacted, Descr	be Fully.*			I	· F			······		
Describe Cau  Below Grade				n Taken.*								
Delow Grade	e Tank Cios	sure Activitie	es									
Describe Are	a Affected a	and Cleanun A	Action Tak	en *	<del></del>							
The regulate	ry standar	d for closure	at this sit	e was determine	d to be 1		A sample was t	aken and	d then trans	ported to th	e lab a	ınd
				les were below t						elines for R	emedia	ation of
Leaks, Spins	and Keleas	se; merelore	no turtne	r action is requi	rea. 1110	е ппат герог	t is attached fo	or reviev	٧.			
I hereby certi	fy that the in	nformation gi	ven above	is true and comp	lete to th	e best of my	knowledge and	l underst:	and that purs	uant to NM0	OCD n	iles and
regulations al	ll operators	are required to	o report ar	d/or file certain r	elease no	otifications a	nd perform cor	ective ac	ctions for rele	eases which	may en	ndanger
				e of a C-141 repo investigate and re								
				tance of a C-141								
federal, state,	or local law	vs and/or regu	lations.				OT 60					
		بنبهندجر و	f.				OIL CO.	NSER'	VATION	DIVISIC	<u> </u>	
C: com a tourne	-yotal	La Taj	oya						1	$H \cap$	KIN	
Signature:			<i>v</i>			Approved by	Environmental	Speciali	st: YONA		IWU	
Printed Name	e: Crystal T	Гаfоуа						Т	V			$\mathcal{C}$
Title: Field I	Environme	ntal Specialis	t			Approval Da	te: 1/29/26	)13	Expiration I	Date:		
E-mail Addre	ess: crystal.ta	afoya@conoc	ophillips.	com		Conditions of	f Approval: C	144 C	osule	Attoched		
							edod for E			Attached		

AES Q

Animas Environmental Services, LLC

www.animasenvironmental.com

624 E. Comanche Farmington, NM 87401 505-564-2281

> Durango, Colorado 970-403-3274

December 7, 2012

Crystal Tafoya ConocoPhillips San Juan Business Unit Office 214-05 5525 Hwy 64 Farmington, New Mexico 87401

**RE:** Below Grade Tank Closure Report

Cundiff #100

San Juan County, New Mexico

Dear Ms. Tafoya:

Animas Environmental Services, LLC (AES) is pleased to provide the final report associated with the below grade tank (BGT) closure at ConocoPhillips (CoP) Cundiff #100, located in San Juan County, New Mexico. Tank removal had been completed by CoP contractors prior to AES' arrival at the location.

#### 1.0 Site Information

### 1.1 Location

Site Name - Cundiff #100

Legal Description - NE¼ NE¼, Section 19, T32N, R12W, San Juan County, New Mexico Well Latitude/Longitude - N36.97613 and W108.12992, respectively BGT Latitude/Longitude - N36.97594 and W108.13019, respectively Land Jurisdiction - Bureau of Land Management (BLM)

Figure 1. Topographic Site Location Map

Figure 2. Aerial Site Map, October 2012

### 1.2 NMOCD Ranking

Prior to site work, the New Mexico Oil Conservation Division (NMOCD) database was reviewed, and no prior ranking was located. The New Mexico Office of the State Engineer (NMOSE) database was reviewed for nearby water wells, and no registered water wells were reported to be located within 1,000 feet of the location. Additionally, Google Earth and the New Mexico Tech Petroleum Recovery Research Center online mapping tool (<a href="http://ford.nmt.edu/react/project.html">http://ford.nmt.edu/react/project.html</a>) were accessed to aid in the identification of downgradient surface water.

Once on site, AES personnel further assessed the ranking using topographical interpretation, Global Positioning System (GPS) elevation readings, and visual reconnaissance. AES personnel concluded that depth to groundwater at the site was greater than 100 feet below ground surface (bgs). An unnamed wash which drains into McDermott Arroyo is located approximately 440 feet west of the location. Based on this information, the location was assessed a ranking score of 10.

#### 1.3 BGT Closure Assessment

AES was initially contacted by Jess Henson, CoP representative, on October 18, 2012, and on October 19, 2012, Heather Woods and Kelsey Christiansen of AES traveled to the the location. AES personnel collected six soil samples from below the BGT liner. Four samples were collected from the perimeter of the BGT footprint, one sample was collected from the center of the BGT footprint, and one sample was composited from the four perimeter samples and one center sample.

## 2.0 Soil Sampling

On October 19, 2012, AES personnel conducted field screening and collected five soil samples (S-1 through S-5) and one 5-point composite (SC-1) from below the BGT. Soil samples were collected from approximately 0.5 feet below the former BGT for field screening of volatile organic compounds (VOCs) and total petroleum hydrocarbon (TPH). Soil sample SC-1 was field screened for chlorides and submitted for confirmation laboratory analysis. Soil sample locations are included on Figure 2.

### 2.1 Field Screening

#### 2.1.1 Volatile Organic Compounds

A portion of each sample was utilized for field screening of VOC vapors with a photo-ionization detector (PID) organic vapor meter (OVM). Before beginning field screening, the PID-OVM was first calibrated with 100 parts per million (ppm) isobutylene gas.

### 2.1.2 Total Petroleum Hydrocarbons

Soil samples were also analyzed in the field for TPH per USEPA Method 418.1 using a Buck Scientific Model HC-404 Total Hydrocarbon Analyzer Infrared Spectrometer (Buck). A 3-point calibration was completed prior to conducting soil analyses. Field analytical protocol followed AES's Standard Operating Procedure: Field Analysis Total Petroleum Hydrocarbons per EPA Method 418.1.

#### 2.1.3 Chlorides

Soil sample SC-1 was field screened for chlorides using Chloride Drop Count Titration with silver nitrate. Sampling and analysis methods followed procedures provided by Hach Company.

## 2.2 Laboratory Analyses

The composite soil sample SC-1 collected for laboratory analysis was placed into a new, clean, laboratory-supplied container, which was then labeled, placed on ice, and logged onto a sample chain of custody record. The sample was maintained on ice until delivery to the analytical laboratory, Hall Environmental Analysis Laboratory (Hall), in Albuquerque, New Mexico. Soil sample SC-1 was laboratory analyzed for:

- Benzene, toluene, ethylbenzene, and xylene (BTEX) per U.S. Environmental Protection Agency (USEPA) Method 8021B;
- Chloride per USEPA Method 300.0.

## 2.3 Field and Laboratory Analytical Results

Field screening readings for VOCs via OVM ranged from 0.7 ppm in S-3 up to 1.3 ppm in S-1. Field TPH concentrations ranged from 29.2 mg/kg in S-3 up to 53.4 mg/kg in S-2. The field chloride concentration in SC-1 was 40 mg/kg. Field screening results are summarized in Table 1 and presented on Figure 2. The AES Field Screening Report is attached.

Table 1. Soil Field Screening VOCs, TPH, and Chloride Results
Cundiff #100 BGT Closure. October 2012

Sample ID	Date Sampled	Depth below BGT (ft)	VOCs OVM Reading (ppm)	Field TPH (mg/kg)	Field Chlorides (mg/kg)
NMOCD Action	Level (NMAC 19.	15.17.13E)		100	250
S-1	10/19/12	0.5	1.3	48.0	NA
S-2	10/19/12	0.5	1.1	53.4	NA
S-3	10/19/12	0.5	0.7	29.2	NA
S-4	10/19/12	0.5	1.0	34.5	NA
S-5	10/19/12	0.5	1.0	50.0	NA
SC-1	10/19/12	NA	NA	NA	40

NA - not analyzed

Laboratory analytical results reported benzene and total BTEX concentrations in SC-1 as less than 0.050 mg/kg and 0.25 mg/kg, respectively. The laboratory chloride

concentration was below the laboratory detection limit of 30 mg/kg. Laboratory analytical results are summarized in Table 2 and included on Figure 2. Laboratory analytical reports are attached.

Table 2. Soil Laboratory Analytical Results Cundiff #100 BGT Closure, October 2012

Sample ID	Date Sampled	Depth (ft)	Benzene (mg/kg)	BTEX (mg/kg)	TPH- GRO (mg/kg)	TPH- DRO (mg/kg)	Chlorides (mg/kg)
NMOCD Action	n Level (NMAC 19.15	.17.13E)	0.2	50	10	00	250
SC-1	10/19/12	0.5	<0.050	<0.25	NA	NA	<30

NA - not analyzed

### 3.0 Conclusions and Recommendations

NMOCD action levels for BGT closures are specified in New Mexico Administrative Code (NMAC) 19.15.17.13E. Benzene and total BTEX concentrations in SC-1 were below the NMOCD action levels of 0.2 mg/kg and 50 mg/kg, respectively. Field TPH concentrations were below the NMOCD action level of 100 mg/kg, with the highest concentration reported in S-2 with 53.4 mg/kg. Chloride concentrations in SC-1 were also below the NMOCD action level of 250 mg/kg. Based on field screening and laboratory analytical results for benzene, total BTEX, TPH, and chlorides, no further work is recommended.

If you have any questions about this report or site conditions, please do not hesitate to contact Deborah Watson at (505) 564-2281.

Sincerely,

Kelsey Christiansen Environmental Scientist

Lelay Chrodium


Crystal Tafoya Cundiff #100 BGT Closure Report December 7, 2012 Page 5 of 5

Elizabeth McNally, P.E.

### Attachments:

Figure 1. Topographic Site Location Map Figure 2. Aerial Site Map, October 2012 AES Field Screening Report 101912 Hall Analytical Report 1210965

C:\Dropbox\2012 December 2012 (Former Trial File)\ConocoPhillips\Cundiff #100\Cundiff #100 BGT Closure Report 120712.docx







SAMPLE LOCATIONS

Sample ID	Date	OVM- PID (ppm)	TPH (mg/kg)	Chlorides (mg/kg)
NMO	CD ACTION LEVEL		100	250
⊗S-1,⊗	10/19/12	€1.3.8	∜48.0 ⅓	NA
S-2	10/19/12	<b>31.1</b> %	⊗53.4⊗	NA
○S-3	10/19/12	0.7	29.2	NA 🙏
S-4 🌣	10/19/12	<b>31.0</b>	⊗34.5 ⋈	NA
%S-5 ⊗	10/19/12	1.0	∑50.0 <b>⊘</b>	NA
⊗SC-1⊗	10/19/12	NA :	NA 🎖	40

American School and the American Services Services and Company	ME I LE MONTH ALL THROUGH SEASON SPINISHED TO THE RESEARCH	CONTRACTOR TO SERVICE AND A SE	で、今後にことには、子母の「女母」と、 カー・カイ
	Laboratory Analytics	al Results	
Sample ID Date	Benzene BTEX (mg/kg)	TPH - TPH - GRO DRO (mg/kg) (mg/kg)	Chlorides (mg/kg)
NMOCD ACTION LEVEL	Annual Santa Annual Calabar	100	250
SC-1 10/19/12	<0.050 <0.25	NA NA	<30
SAMPLE WAS ANALYZED	PER EPA METHOD 802	1B AND 300.0. NA = NO	[ ANALYZED







	AESTO
İ	Animas Environmental Services, LCC

DRAWN BY:	DATE DRAWN:
C. Lameman	October 22, 2012
REVISIONS BY:	DATE REVISED:
C. Lameman	October 22, 2012
CHECKED BY:	DATE CHECKED:
CHECKED BY: D. Watson	DATE CHECKED: October 22, 2012

# FIGURE 2

## AERIAL SITE MAP BELOW GRADE TANK CLOSURE OCTOBER 2012

ConocoPhillips CUNDIFF #100 SAN JUAN COUNTY, NEW MEXICO NE¼ NE¼, SECTION 19, T32N, R12W N36.97613, W108.12992

## **AES Field Screening Report**

Animas Environmental Services, LLC

www.animasenvironmental.com

624 E. Comanche Farmington, NM 87401 505-564-2281

> Durango, Colorado 970-403-3274

Client: ConocoPhillips

Project Location: Cundiff #100

Date: 10/19/2012

Matrix: Soil

Sample ID	Collection Date	Time of Sample Collection	Sample Location	OVM (ppm)	Field Chloride (mg/kg)	Field TPH Analysis Time	Field TPH* (mg/kg)	TPH PQL (mg/kg)	DF	TPH Analysts Initials
S-1	10/19/2012	11:32	North	1.3	NA	12:20	48.0	20.0	1	КС
S-2	10/19/2012	11:36	South	1.1	NA	12:24	53.4	20.0	1	КС
S-3	10/19/2012	11:40	East	0.7	NA	12:28	29.2	20.0	1	КС
S-4	10/19/2012	11:44	West	1.0	NA	12:31	34.5	20.0	1	КС
S-5	10/19/2012	11:48	Center	1.0	NA	12:35	50.0	20.0	1	КС
SC-1	10/19/2012	11:51	Composite	NA	40		Not	Analyzed for T	PH	

PQL

**Practical Quantitation Limit** 

Field Chloride - Quantab Chloride Titrators or Drop Count Titration with

Lelang Christian

Silver Nitrate

Total Petroleum Hydrocarbons - USEPA 418.1

ND NA

Not Analyzed

DF

Dilution Factor

\*Field TPH concentrations recorded may be below PQL.

Not Detected at the Reporting Limit

Analyst:



Hall Environmental Analysis Laboratory 4901 Hawkins NE Albuquerque, NM 87109 TEL: 505-345-3975 FAX: 505-345-4107 Website: www.hallenvironmental.com

October 25, 2012

Debbie Watson
Animas Environmental Services
624 East Comanche
Farmington, NM 87401
TEL: (505) 486-4071

FAX (505) 324-2022

RE: Cundiff #100 OrderNo.: 1210965

#### Dear Debbie Watson:

Hall Environmental Analysis Laboratory received 1 sample(s) on 10/20/2012 for the analyses presented in the following report.

These were analyzed according to EPA procedures or equivalent. To access our accredited tests please go to <a href="www.hallenvironmental.com">www.hallenvironmental.com</a> or the state specific web sites. See the sample checklist and/or the Chain of Custody for information regarding the sample receipt temperature and preservation. Data qualifiers or a narrative will be provided if the sample analysis or analytical quality control parameters require a flag. All samples are reported as received unless otherwise indicated. Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH and residual chlorine are qualified as being analyzed outside of the recommended holding time.

Please don't hesitate to contact HEAL for any additional information or clarifications.

Sincerely,

Andy Freeman

Laboratory Manager

4901 Hawkins NE

Albuquerque, NM 87109

## **Analytical Report**

#### Lab Order 1210965

Date Reported: 10/25/2012

## Hall Environmental Analysis Laboratory, Inc.

**CLIENT:** Animas Environmental Services

Project: Cundiff #100

Lab ID:

1210965-001

ndiff #100

Matrix: SOIL

Collection Date: 10/19/2012 11:51:00 AM

Client Sample ID: SC-1

**Received Date: 10/20/2012** 

Analyses	Result	RL Qu	al Units	DF	Date Analyzed
EPA METHOD 8021B: VOLATILES					Analyst: NSB
Benzene	ND	0.050	mg/Kg	1	10/22/2012 1:40:01 PM
Toluene	ND	0.050	mg/Kg	1	10/22/2012 1:40:01 PM
Ethylbenzene	ND	0.050	mg/Kg	1	10/22/2012 1:40:01 PM
Xylenes, Total	ND	0.10	mg/Kg	1	10/22/2012 1:40:01 PM
Surr: 4-Bromofluorobenzene	103	80-120	%REC	1	10/22/2012 1:40:01 PM
EPA METHOD 300.0: ANIONS					Analyst: SRM
Chloride	ND	30	mg/Kg	20	10/22/2012 12:28:44 PM

### Qualifiers:

- Value exceeds Maximum Contaminant Level.
- E Value above quantitation range
- J Analyte detected below quantitation limits
- P Sample pH greater than 2
- RL Reporting Detection Limit

- B Analyte detected in the associated Method Blank
- H Holding times for preparation or analysis exceeded
- ND Not Detected at the Reporting Limit
- R RPD outside accepted recovery limits
- S Spike Recovery outside accepted recovery limits Page 1 of 3

## **QC SUMMARY REPORT**

## Hall Environmental Analysis Laboratory, Inc.

WO#:

1210965

25-Oct-12

Client:

Animas Environmental Services

Project:

Cundiff #100

Sample ID MB-4442

SampType: MBLK

TestCode: EPA Method 300.0: Anions

Client ID: **PBS**  Batch ID: 4442

RunNo: 6409

Prep Date: 10/22/2012 Analysis Date: 10/22/2012

SeqNo: 184313

Units: mg/Kg

Result **PQL** 

HighLimit

**RPDLimit** 

Qual

Analyte Chloride

ND 1.5

Sample ID LCS-4442

SampType: LCS

TestCode: EPA Method 300.0: Anions

Client ID: LCSS

Batch ID: 4442

RunNo: 6409

Analysis Date: 10/22/2012

SeqNo: 184314

Units: mg/Kg

Prep Date: 10/22/2012

%REC LowLimit

Analyte

**PQL** 

SPK value SPK Ref Val

100

110

HighLimit %RPD

%RPD

1.5

0

SPK value SPK Ref Val %REC LowLimit

**RPDLimit** Qual

Chloride

15

15.00

**Qualifiers:** 

Value exceeds Maximum Contaminant Level.

Е Value above quantitation range

Analyte detected below quantitation limits J

Sample pH greater than 2

В Analyte detected in the associated Method Blank

Н Holding times for preparation or analysis exceeded

ND Not Detected at the Reporting Limit

RPD outside accepted recovery limits

Page 2 of 3

# **QC SUMMARY REPORT**

## Hall Environmental Analysis Laboratory, Inc.

WO#: 1210965

25-Oct-12

Client:

Animas Environmental Services

Project:

Cundiff#100

Sample ID MB-4420	Samp	Гуре: М	BLK	TestCode: EPA Method 8021B: Volatiles				tiles		
Client ID: PBS	Batc	h ID: 44	20	RunNo: <b>6401</b>						
Prep Date: 10/19/2012	Analysis [	Date: 1	0/22/2012	S	SeqNo: 1	84440	Units: mg/k	ίg		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Benzene	ND	0.050				•			******	
Toluene	ND	0.050								
Ethylbenzene	ND	0.050								
Xylenes, Total	ND	0.10								
Surr: 4-Bromofluorobenzene	1.0		1.000		104	80	120			
Sample ID LCS-4420	Samp	Type: LC	S	TestCode: EPA Method 8021B: Volatiles						

Sample ID LCS-4420 SampType: LCS				TestCode: EPA Method 8021B: Volatiles						
Client ID: LCSS	Batcl	n ID: 44	20	F	RunNo: 6	401				
Prep Date: 10/19/2012	Analysis Date: 10/22/2012			SeqNo: 184441			Units: mg/k	ζg		
Analyte	Result	PQL	SPK value	SPK Ref Val	%REC	LowLimit	HighLimit	%RPD	RPDLimit	Qual
Benzene	1.1	0.050	1.000	0	108	76.3	117			
Toluene	1.1	0.050	1.000	0	107	80	120			
Ethylbenzene	1.1	0.050	1.000	0	108	77	116			
Xylenes, Total	3.2	0.10	3.000	0	107	76.7	117			
Surr: 4-Bromofluorobenzene	1.1		1.000	•	108	80	120			

#### Qualifiers:

Value exceeds Maximum Contaminant Level.

E Value above quantitation range

J Analyte detected below quantitation limits

P Sample pH greater than 2

B Analyte detected in the associated Method Blank

H Holding times for preparation or analysis exceeded

ND Not Detected at the Reporting Limit

R RPD outside accepted recovery limits

Page 3 of 3



Hall Environmental Analysis Laboratory 4901 Hawkins NE Albuquerque, NM 87105

TEL: 505-345-3975 FAX: 505-345-410; Website: www.hallenvironmental.com

# Sample Log-In Check List

Clien	nt Name:	Animas En	/ironmental			Work Order	Number:	12109	965		
Rece	elved by/date	:_AF	- 14	24/2							İ
Logg	ed By:	Andy Freen	nan	10/20/20	12		a	de la	-		
Com	pleted By:	ne	10/22/20	12		0	ne Sha	_			
Revie	ewed By:	A5 11	122/12	2			-	• • • • • • • • • • • • • • • • • •	_		İ
Chal	in of Cust	, ,									·
,	Were seals i					Yes [	No □	Not	Present 🗹		
• • •		Sustody comp	lete?			Yes 🔽	No 🗆	Not	Present		
		sample deliv				Courier					
Log .	<u>In</u>										
4.	Coolers are	present? (see	19. for coole	er specific info	mation)	Yes 🔽	No □		na 🗆		
5. \	Was an atte	mpt made to	cool the samp	oles?		Yes 🔽	No 🗆		na 🗆		
6. \	Were all san	nples received	dat a temper	ature of >0° C	to 6.0°C	Yes <b>⊻</b>	No 🗆		na 🗆		
7. \$	Sample(s) in	proper conta	iner(s)?			Yes 🗹	No 🗆		•		
8. 8	Sufficient sa	mpie volume	for indicated	test(s)?		Yes 🗹	No 🗆				
9. 4	Are samples	(except VOA	and ONG) p	roperly preser	/ed?	Yes 🗹	No 🗆				
10. \	Was preserv	ative added to	o bottles?			Yes 🗆	No 🗹		NA 🗆		
11. \	VOA vials ha	ive zero head	space?	-		Yes 🗌	No 🗆	No V	OA Vials 🗹		
12.	Were any sa	mple contain	ers received l	oroken?		Yes	No 🗹	Г			
		vork match bo pancies on ch		y)		Yes 🗹	No 🗀		# of preserved bottles checked for pH:		
14.	Are matrices	correctly idea	ntified on Cha	in of Custody	?	Yes 🗹	No 🗆		(<	2 or >12 uni	ess noted)
15. I	ls it clear wh	at analyses w	ere requeste	d?			No 🗆		Adjusted?		
		ling times abl customer for		)		Yes 🗹	No L		Checked by	<b>/</b> :	
Spec	iai H <u>andl</u>	ing (if app	licable)					L	· · · · · · · · · · · · · · · · · · ·	<del></del>	
17.	Was client n	otified of all di	screpancies	with this order	?	Yes 🗆	No 🗆		NA 🗹		
	Person	Notified:			Date						
	By Who	om:			Via:	eMail [	Phone	☐ Fa	x 🔲 In Person		
	Regard	ing:									
ŀ	Client I	nstructions:									
18. /	Additional re	marks:									
46 -	n1!!										
19. 9	Cooler Infor Cooler No		Condition	Seal Intact	Seal No	Seal Date	Sign	ed By			
	1	2.8	Good	Yes							

Client: Animas Environmental Services  Mailing Address: 624 E. Comarche Farmington, NA 07-401  Phone #: 505-564-2281				Tum-Around Time:																	
				☐ Standard				HALL ENVIRONMENTAL ANALYSIS LABORATORY www.hallenvironmental.com													
				Cund:ff #100				490	)1 He	wkin							109				
				Project #:				'2 C. 1 .ab-	Te	1. 50	5-345	-397		Fax					المعارضة المعارضة		響を参え
								#2.2							Req	ues					
email or Fax#:				Project Manager:					<u> </u>	sel				18	,,						
QA/QC Package:  Standard   Level 4 (Full Validation)				D. Watson				\$ (802	+ TPH (Gas only)	(Gas/Diesel)				PO4.S	PCB's			į			
Accreditation				Sampler: 14. Woods					포	9		۔ ا۔		200	982				- 1		
□ NELAP □ Other				Undee To Yes The Yes			M		15B	8	\f		82	8		8			ļ	Z	
□ EDD (Type)			Sample remperature de 1996				삤	8	4	֓֞֞֝֞֜֞֜֞֜֞֜֞֜֞֜֝֓֓֓֓֓֓֓֓֓֓֓֜֝֟֜֜֝֝֝֝֝֝֝֝֝֝	<u>s</u>	K	des		0				٤		
Date	Time	Matrix	Sample Request ID	Container Type and #	Preservative Type	i HEAL		BTEX + NEE + SME'S (8021)	BTEX + MTBE	TPH Method 8015B	TPH (Method 418.1)	EDB (Method 504.1)	CCRA 8 Met	Anions (F.C) NO3, NO2, PO4, SO4)	8081 Pesticides / 8082 PCB's	8260B (VOA)	8270 (SemI-VOA)				Air Bubbles (Y or N)
0/19/12	1151	Soil	SC-1	MOHKIT	MADH	12/0965	-1	X						X							上
		ļ				,									<b> </b>			Ì	ŀ		
				-															$\Box$		十
			-		-		7			_	_		_		<del></del>			$\dashv$	<del>-</del>	+	+
<del></del>		12				· · · · · · · · · · · · · · · · · · ·			-	-		_	+	+-	_			$\rightarrow$			+
<del></del>							<del></del>		_	_		4	1	+	<u> </u>				$\dashv$	+	+
														<u> </u>							
		, v																			
			·														Ì				
				<u> </u>								1	1							$\top$	1
	<del> </del>	<u> </u>								$\dashv$	$\dashv$	+	+-	-					$\dashv$	$\dashv$	十
<del></del>								Н	$\dashv$	+		-	+	+	├	,			$\dashv$	+	+
Date:	Time:	Relinquishe	ed hv	Received by:	<u> </u>	Date 1	īme	Day				<u></u>								ㅗ	—
0/19/12 Date:	1649	Hos	the M. Wood	- Mate Vale 19/19/12 1649																	
Date: 2/19/12	Time:	Relinquish	to true lalos de la	Received by:	1	Date I	īme 1000	Activity: CZDO Area: ! Supervoir: Herry Dee Workordured by:						Jes:	, Hei	ator					
	necessary,	samples subr	mitted to Hall Environmental may be subc	ontracted to other ac	credited laboratorie	s. This serves as	notice of this	possit	oility. A	ny sub	-contra	ted da	ta will l	oe clear	ty nota	ated or	the ar	nalytica	al repor	L	