

State of New Mexico  
Energy, Minerals and Natural Resources Department

**Susana Martinez**  
Governor

**David Martin**  
Cabinet Secretary-Designate

**Brett F. Woods, Ph.D.**  
Deputy Cabinet Secretary

**Jami Bailey, Division Director**  
Oil Conservation Division



New Mexico Oil Conservation Division approval and conditions  
listed below are made in accordance with OCD Rule 19.15.7.11  
and are in addition to the actions approved by BLM on the  
following 3160-4 or 3160-5 form.

Operator Signature Date: January 3, 2014

Application Type:

☐ P&A    ☒ Drilling/Casing Change    ☐ Recomplete/DHC  
☐ Location Change    ☐ Other: \_\_\_\_\_

Well information:

API WELL #	Well Name	Well #	Operator Name	Type	Stat	County	Surf_Owner	UL	Sec	Twp	N/S	Rng	W/E
30-039-31193-00-00	JICARILLA APACHE 102	014M	ENERVEST OPERATING L.L.C.	G	N	Rio Arriba	J	N	9	26	N	4	W

Conditions of Approval:

Notify NMOCD 24hrs prior to beginning operations

Hold C-104 for "As drilled plat" and directional survey"

JAN 15 2014

\_\_\_\_\_  
NMOCD Approved by Signature

\_\_\_\_\_  
Date

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

RECEIVED

FORM APPROVED  
OMB No. 1004-0137  
Expires: October 31, 2014

JAN 08 2014

## SUNDRY NOTICES AND REPORTS ON WELLS

**Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.**

SUBMIT IN TRIPLICATE - Other instructions on page 2.

## 1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other2. Name of Operator  
EnerVest Operating, L.L.C.3a. Address  
1001 Fannin Street, Suite 800  
Houston, TX 770023b. Phone No. (include area code)  
713-659-35004. Location of Well (Footage, Sec., T., R., M., or Survey Description)  
SHL: 1310' FSL & 1482' FWL (UL N), Sec. 9 T26N R04W  
BHL: 660' FSL & 1980' FWL (UL N), Sec. 9 T26N R04W5. Lease Serial No.  
Jicarilla Contract 102

6. If Indian, Allottee or Tribe Name

Jicarilla Apache

7. If Unit of CA/Agreement, Name and/or No.

8. Well Name and No.  
Jicarilla Apache 102 #14M9. API Well No.  
30-039-3119310. Field and Pool or Exploratory Area  
Blanco Mesaverde/Basin Dakota11. County or Parish, State  
Rio Arriba, NM

## 12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

## TYPE OF SUBMISSION

☒ Notice of Intent☐ Subsequent Report☐ Final Abandonment Notice

## TYPE OF ACTION

☐ Acidize☐ Alter Casing☐ Casing Repair☒ Change Plans☐ Convert to Injection☐ Deepen☐ Fracture Treat☐ New Construction☐ Plug and Abandon☐ Plug Back☐ Production (Start/Resume)☐ Reclamation☐ Recomplete☐ Temporarily Abandon☐ Water Disposal☐ Water Shut-Off☐ Well Integrity☐ Other

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

EnerVest Operating, L.L.C. intends to modify the drilling plan submitted on 8/15/2013. the surface casing will be 8 5/8" 24# J-55 and the production casing will be 4 1/2" 11.6# N-80 with a hole size of 7 7/8".

The modified drilling plan is attached.

CONDITIONS OF APPROVAL  
Adhere to previously issued stipulations.

OIL CONS. DIV DIST. 3  
JAN 10 2014

BLM'S APPROVAL OR ACCEPTANCE OF THIS  
ACTION DOES NOT RELIEVE THE LESSEE AND  
OPERATOR FROM OBTAINING ANY OTHER  
AUTHORIZATION REQUIRED FOR OPERATIONS  
ON FEDERAL AND INDIAN LANDS

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)

Bart Treviño

Title Regulatory Analyst

Signature

Date 01/03/2014

## THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

William Tambekou

Title

Petroleum Engineer

Date

1/8/2014

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office FFO

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

NMCCD

# **EnerVest Operating, LLC**

## **Jicarilla Apache 102 # 14M**

Surface: 1310' FSL, 1482' FWL Unit N, Sec. 9, T26N R04W  
Bottom Hole: 660' FSL, 1980' FWL Unit N, Sec 9, T26N, R04W  
Rio Arriba County, NM  
GL Elev: 7112'

---

### **Revised Drilling Plan (7-15-2013, 8-6-2013, 12-12-2013)**

All Lease and /or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations, BLM Onshore orders and EnerVest's approved Further Development Project Plan. The operator is fully responsible for the actions of its subcontractors. A copy of the APD and Conditions of Approval will be available to the field representatives to ensure compliance.

#### **4.1, 4.2      ESTIMATED (TVD) FORMATION TOPS (KB) and NOTABLE ZONES:**

The following are estimates of formation and proposed casing depths.

<u>Formation Name</u>	<u>Depth (TVD)</u>	<u>Rock Type</u>	<u>Comments</u>
San Jose	Surface	Sandstone	
Ojo Alamo	3095'	Sandstone	Possible Gas, Water
Kirtland	3599'	Shale	
Fruitland	3645'	Coal, Shale, Sandstone	Possible Lost Circ, Gas, Water
Pictured Cliffs	3835'	Sandstone	Possible Lost Circ, Gas, water
Lewis	4082'	Shale	Sloughing Shale
Mesa Verde (Cliffhouse)	5510'	Sandstone	Possible Lost Circ, Gas, Water
Mesa Verde (Menefee)	5616'	Coal, Sandstone, Shale	Possible Lost Circ, Gas, Water
Mesa Verde (Point Lookout)	5950'	Sandstone	Possible Lost Circ, Gas, Water
Mancos	6087'	Shale	Sloughing Shale
Greenhorn	7935'	Limestone	Gas, Oil
Graneros	7970'	Shale	Gas, Oil, Water
Dakota	7988'	Sandstone	Gas, Oil, Water
Proposed Total Depth	8283'		

Fresh water zones will be adequately protected by setting and cementing the surface casing.  
All zones containing commercial quantities of oil or gas will be cased and cemented.

This well is to be drilled as a directionally drilled "S-shaped" well. The well is to be drilled vertically from surface to a kick off point at +/- 600 ft MD. The well will be directionally drilled at a 144 degree azimuth to a point 806 ft south east of the surface location and at an estimated MD of +/-4500 ft. The well will be drilled vertically from that point to the estimated TD.

## **EnerVest Operating, LLC**

### **Jicarilla Apache 102 # 14M**

Surface: 1310' FSL, 1482' FWL Unit N, Sec. 9, T26N R04W  
Bottom Hole: 660' FSL, 1980' FWL Unit N, Sec 9, T26N, R04W  
Rio Arriba County, NM  
GL Elev: 7112'

---

#### **4.3 PRESSURE CONTROL:**

Maximum expected pressure is ~1822 (.22 pressure gradient) psi. The drilling contract has not yet been awarded, thus the exact BOP and Choke Manifold model to be used is not yet known. A typical 11" 2000 psi model is pictured in Exhibits A & B.

A remote accumulator will be used, the pressures, capacities location of the remote and manual controls will be identified at the time of the BLM supervised BOP test.

BOP equipment, accumulator, choke manifold and all accessories will meet or exceed BLM requirements as listed in Onshore Order #2 for the 2M systems. The pressure control equipment considerations include but will not be limited to:

1. BOP will be a double gate ram preventer with a set of blind rams and a set of properly-sized pipe rams.
2. Accumulator will have sufficient capacity to close the BOP rams and retain 200 psi above pre charge.
3. Accumulator fluid volume is to be maintained at manufacturer's recommendations.
4. BOP will also have manual closing handles available.
5. 2" minimum kill line and kill line valves (2).
6. Choke manifold (2" lines) with 2 adjustable chokes with valves and gauge.
7. Manually operated Kelly cocks available.
8. Safety valve and sub(s) with adequate opening for all drill strings used.
9. Fill line and flow line above the upper-most BOP rams.

BOPs will be pressure tested; after initial installation, before drilling out from under all set and cemented casing strings and any time a seal is broken. The BOPs will also be pressure tested a minimum of once every 21 days by a 3<sup>rd</sup> party. Additionally, the BOPs will be operationally checked every 24 hours.

All tests and pressure tests will be recorded on IADC log.

Ram type preventors, choke manifold and related pressure control equipment will be pressure tested to the rated working pressure of 2000 psi (high) and 250 psi (low).

The casing strings will be pressure tested per BLM Onshore Order #2 for 30 min as follows:

- a. Surface casing tested to 600 psi prior to drilling out the shoe.
- b. The 4 ½" 11.6# N-80 production casing will be tested to 6000 psi at the commencement of completion operations.

## EnerVest Operating, LLC

Jicarilla Apache 102 # 14M

Surface: 1310' FSL, 1482' FWL Unit N, Sec. 9, T26N R04W  
Bottom Hole: 660' FSL, 1980' FWL Unit N, Sec 9, T26N, R04W  
Rio Arriba County, NM  
GL Elev: 7112'

### 4.4 PROPOSED CASING PROGRAM :

The casings program is designed as follows:

Hole/Casing Description	Hole Size	Casing OD	Casing Design					
			Weight lb/ft	Grade	Age	Connection	Top	Bottom
Surface	12 1/4"	8 5/8"	24	J-55	New	ST&C	0	500'
Prod Csg MD	7 7/8"	4 1/2"	11.6	N-80	New	LT&C	500'	8381'
TYD							500'	8283'

**Surface casing is to be cemented to surface. The production casing is to be cemented in 3 stages covering all zones of production potential and the 3<sup>rd</sup> stage is intended to circulate cement to surface.**

### 4.5 CASING CEMENT:

A prototypical cementing program is listed as follows, site-specific cement designs will be produced for each well as the hole conditions warrant. The cement program will be designed to meet the BLM Onshore Order #2 and NMOCD requirements.

**Surface casing** will be cemented to the surface.

Cement and properties; Mix and pump 225 sacks (313 cu ft) Type III cement (or equivalent) cement. Slurry density is to be 14.6 (yield = 1.39 cu ft/sx). Volume will include 100% excess. Cement is to be displaced using a top plug.

Two centralizers will be run on the shoe joint, one centralizer each on the next two joints and then one centralizer on every third joint thereafter.

The surface casing will be pressure tested to 600 psi prior to drilling out the shoe.

**EnerVest Operating, LLC**

**Jicarilla Apache 102 # 14M**

Surface: 1310' FSL, 1482' FWL Unit N, Sec. 9, T26N R04W  
Bottom Hole: 660' FSL, 1980' FWL Unit N, Sec 9, T26N, R04W  
Rio Arriba County, NM  
GL Elev: 7112'

---

**Production casing** will be cemented in 3 stages covering all zones of production potential and the 3<sup>rd</sup> stage is intended to circulate cement to surface. Volumes based on 50% OH excess cement for stage 1, 2 and 3.

Stage 1 cement; mix and pump 548 sacks (1101 cu ft) premium lite high strength cement with CaCl<sub>2</sub>, cellophane, gilsonite and fluid loss agent. Slurry density is to be 12.5 (yield = 2.01 cu ft/sx).

DV tool at +/- 5170 ft. MD

Stage 2 Lead cement; mix and pump 270 sacks (574 cu ft) premium lite slurry with CaCl<sub>2</sub>, cello flake and gilsonite. Estimated slurry density is to be 12.1 (yield = 2.13 cu ft/sx).

Stage 2 Tail cement; mix and pump 50 sacks (70 cu ft) Type III cement (or equivalent) cement. Slurry density is to be 14.6 (yield = 1.39 cu ft/sx). or equivalent cement.

DV tool at +/- 3285 ft. MD

Stage 3 Lead cement; mix and pump 490 sacks (1043 cu ft) premium lite slurry with CaCl<sub>2</sub>, cello flake and gilsonite. Estimated slurry density is to be 12.1 (yield = 2.13 cu ft/sx).

Stage 3 Tail cement; mix and pump 50 sacks (70 cu ft) Type III cement (or equivalent) cement. Slurry density is to be 14.6 (yield = 1.39 cu ft/sx). or equivalent cement.

Two centralizers will be run on the shoe joint, one centralizer on every third joint into the surface casing.

**The production casing will be pressure tested for 30 minutes at the commencement of completion operations as outlined above**

Where cement has not been circulated to surface (or to planned depth) a CBL or temperature survey will be run to determine the TOC for that casing string. A CBL log will be run in the production casing prior to the commencement of completion operations.

## **EnerVest Operating, LLC**

### **Jicarilla Apache 102 # 14M**

Surface: 1310' FSL, 1482' FWL Unit N, Sec. 9, T26N R04W  
Bottom Hole: 660' FSL, 1980' FWL Unit N, Sec 9, T26N, R04W  
Rio Arriba County, NM  
GL Elev: 7112'

---

Cement specifications may vary slightly due to cement type and cement contractor availability.

#### **4.6 MUD PROGRAM**

<b>Depth (MD)</b>	<b>Type</b>	<b>Wt / pp</b>	<b>Visc</b>	<b>Fluid Loss</b>
<b>0-500'</b>	FW gel/Lime Spud Mud	8.4-9.0	30-40	N/C
<b>500'-8381'</b>	LSND/Gel sweeps, LCM as needed	8.7-9.0	20-32	4-6 cc

The well will be drilled utilizing a closed loop mud handling system. The closed loop system will comply with the NMOCD pit rules pertaining to the use of the system and disposal of the drill cuttings and waste. Drilling mud will be moved for re-use to drill subsequent wells whenever possible.

Viscosity, mud weight and other physical and chemical characteristics of the drilling mud will be varied as required to keep the hole clean, circulate drill cuttings, prevent caving, prevent lost circulation and maximize penetration rate.

Sufficient mud and materials will be kept on site to maintain mud properties and meet lost circulation or mud weight requirements at all times.

Mud design may change depending on well conditions, LCM, fluid loss and viscosity will be determined by the EnerVest representative and the mud engineer on site.

#### **4.7 CORING, TESTING, & LOGGING**

No cores or drill stem tests are planned. Well logs to be run are:

**500' to TD;** GR/ Cement Bond Log, at the commencement of completion operations.

**2500' to TD;** Cased hole GR/Neutron

This well will be directionally drilled and a record of the deviation will be run while drilling. A deviation survey will be submitted at the conclusion of the well completion.

**EnerVest Operating, LLC**

**Jicarilla Apache 102 # 14M**

Surface: 1310' FSL, 1482' FWL Unit N, Sec. 9, T26N R04W  
Bottom Hole: 660' FSL, 1980' FWL Unit N, Sec 9, T26N, R04W  
Rio Arriba County, NM  
GL Elev: 7112'

---

**4.8 ANTICIPATED PRESSURES AND TEMPERATURES:**

- |    |                                    |            |
|----|------------------------------------|------------|
| a. | Expected bottom hole pressure:     | < 1822 psi |
| b. | Anticipated abnormal pressure:     | None       |
| c. | Anticipated abnormal temperatures: | None       |
| d. | Anticipated hazardous gas (H2S):   | None       |

If any of the foregoing conditions are unexpectedly encountered, suitable steps will be taken to mitigate according to accepted industry best practices.

**4.9 OTHER INFORMATION:**

The anticipated spud date is spring 2014. The spud date will be dependent on the weather conditions, road conditions and the Conditions of Approval.

The dirt work for road and well pad construction will commence upon approval of the APD and will be dependent on weather conditions.

The well will be spud after well pad construction is complete and a suitable rig becomes available. The duration of drilling operations is expected to be from two to three weeks. The drilling rig and associated equipment will be removed and preparations will be made for the completion of the well.

Completion will start about one to four weeks after the finish of the drilling operations. A completion rig will be moved in for the completion phase. The completion phase of the well is expected to +/- two weeks. The completion phase will include; perforating, acidizing, fracture stimulation and well testing.

Some events/situations may arise that could potentially change the starting date or project duration that are out of EnerVest's control. If such events/situations arise, the proper officials will be promptly notified.