

State of New Mexico  
Energy, Minerals and Natural Resources Department

Susana Martinez  
Governor

David Martin  
Cabinet Secretary-Designate

Brett F. Woods, Ph.D.  
Deputy Cabinet Secretary

Jami Bailey, Division Director  
Oil Conservation Division



New Mexico Oil Conservation Division approval and conditions listed below are made in accordance with OCD Rule 19.15.7.11 and are in addition to the actions approved by BLM on the following 3160-3 APD form.

Operator Signature Date: 7-16-14

Well information;

Operator WPX, Well Name and Number Chico 2306-6D #177H

API# 30-039-31252 Section 6, Township 230 N/S, Range 6 E W

Conditions of Approval:

(See the below checked and handwritten conditions)

- ☒ Notify Aztec OCD 24hrs prior to casing & cement.
- ☒ Hold C-104 for directional survey & "As Drilled" Plat
- ☒ Hold C-104 for NSL NSP, DHC
- ☐ Spacing rule violation. Operator must follow up with change of status notification on other well to be shut in or abandoned
- ☐ Regarding the use of a pit, closed loop system or below grade tank, the operator must comply with the following as applicable:
  - A pit requires a complete C-144 be submitted and approved prior to the construction or use of the pit, pursuant to 19.15.17.8.A
  - A closed loop system requires notification prior to use, pursuant to 19.15.17.9.A
  - A below grade tank requires a registration be filed prior to the construction or use of the below grade tank, pursuant to 19.15.17.8.C
- ☐ Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string
- ☒ Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.

Charles X. ...  
NMOCD Approved by Signature

8-15-2014  
Date KC

CONFIDENTIAL

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

RECEIVED

FORM APPROVED  
OMB No. 1004-0136  
Expires January 31, 2004

JUL 16 2014

## APPLICATION FOR PERMIT TO DRILL OR REENTER



1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMSF-078362
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator WPX Energy Production, LLC		7. If Unit or CA Agreement, Name and No. NMNM 132829(CA)
3a. Address P.O. Box 640 Aztec, NM 87410	3b. Phone No. (include area code) (505) 333-1808	8. Lease Name and Well No. Chaco 2306-06D #177H
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface <sup>D</sup> 1132' FNL & 755' FWL, sec 6, T23N, R6W At proposed prod. zone <sup>E</sup> 1338' FNL & 230' FWL, sec 1, T23N, R7W		9. API Well No. 30-039-31252
14. Distance in miles and direction from nearest town or post office* approximately 2 miles northeast of Lybrook, New Mexico		10. Field and Pool, or Exploratory Lybrook Gallup
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 755'	16. No. of Acres in lease 2530.37	11. Sec., T., R., M., or Blk. and Survey or Area Sur: Sec 6, T23N, R6W BHL: Sec 1, T23N, R7W
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 22'	19. Proposed Depth 11,561' MD / 5,605' TVD	12. County or Parish Rio Arriba County
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 6982' GR	22. Approximate date work will start* October 1, 2014	13. State NM
24. Attachments		23. Estimated duration 1 month

OIL CONS. DIV DIST. 3

AUG 05 2014

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- |   |  |
|---|--|
| 1. Well plat certified by a registered surveyor.  | 4. Bond to cover the operations unless covered by an existing bond on file (see item 20 above).    |
| 2. A Drilling Plan.   | 5. Operator certification.   |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature 	Name (Printed/Typed) Larry Higgins	Date 7/16/14
Title		
Regulatory Specialist Approved by (Signature) 	Name (Printed/Typed) D. Mankiewicz	Date 8/4/14
Title AFM		
Office FFO		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*(Instructions on reverse)

WPX Energy Production, LLC, proposes to develop the Lybrook Gallup formation at the above described location in accordance with the attached drilling and surface use plans.

The well pad surface is on lease under jurisdiction of the BLM.

This location has been archaeologically surveyed by La Plata Archaeological Consultants. Copies of their report have been submitted directly to the BLM.

This well shares this location with the Chaco 2307-06D #176H. A 179' access road is needed. A 449' pipeline connection is required.

This action is subject to  
technical and procedural review  
pursuant to 43 CFR 3165.3 and  
appeal pursuant to 43 CFR 3165.4BLM'S APPROVAL OR ACCEPTANCE OF THIS  
ACTION DOES NOT RELIEVE THE LESSEE AND  
OPERATOR FROM OBTAINING ANY OTHER  
AUTHORIZATION REQUIRED FOR OPERATIONS  
ON FEDERAL AND INDIAN LANDSNMOC  
AVDRILLING OPERATIONS AUTHORIZED  
ARE SUBJECT TO COMPLIANCE WITH  
ATTACHED "GENERAL REQUIREMENTS"

APD Certification:

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Executed this 16th day of July, 2014.

Name Larry Higgins

Position Title Regulatory Specialist


Address P.O. Box 640, Aztec, NM 87410

Telephone (505) 333-1808

Field representative (if not above signatory) \_\_\_\_\_

E-mail [larry.higgins@wpxenergy.com](mailto:larry.higgins@wpxenergy.com)

Date: 07/16/14



Larry Higgins  
Regulatory Spec.  
WPX Energy Production, LLC

District I  
1625 N. French Drive, Hobbs, NM 88240  
Phone: (575) 393-6161 Fax: (575) 393-0720

District II  
811 S. First Street, Artesia, NM 88210  
Phone: (575) 748-1283 Fax: (575) 748-6170

District III  
1000 Rio Brazos Road, Aztec, NM 87410  
Phone: (505) 334-6178 Fax: (505) 334-6170

District IV  
1220 S. St. Francis Drive, Santa Fe, NM 87505  
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico  
Energy, Minerals & Natural Resources Department

Form C-102  
Revised August 1, 2011

Submit one copy to  
Appropriate District Office

OIL CONSERVATION DIVISION  
1220 South St. Francis Drive  
Santa Fe, NM 87505

AMENDED REPORT

RECEIVED

JUL 16 2014

WELL LOCATION AND ACREAGE DEDICATION PLAT

*API Number <b>30-039-31252</b>	*Pool Code 42289	*Pool Name LYBROOK GALLUP
*Property Code <b>313590</b>	*Property Name CHACO 2306-06D	*Well Number 177H
*OGRID No. 120782	*Operator Name WPX ENERGY PRODUCTION, LLC	*Elevation 6982'

<sup>10</sup> Surface Location


UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
D	6	23N	6W	4	1132	NORTH	755	WEST	RIO ARRIBA

<sup>11</sup> Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
E	1	23N	7W	9	1338	NORTH	230	WEST	RIO ARRIBA

<sup>12</sup> Dedicated Acres 192.71	SW/4 NW/4 - Section 6 S/2 N/2 - Section 1	<sup>13</sup> Joint or Infill	<sup>14</sup> Consolidation Code	<sup>15</sup> Order No.
---	--	-------------------------------	----------------------------------	-------------------------

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



END-OF-LATERAL  
1138' FNL 230' FWL  
SECTION 1, T23N, R7W  
LAT: 36.25751°N  
LONG: 107.53527°W  
DATUM: NAD1927  
  
LAT: 36.25752°N  
LONG: 107.53588°W  
DATUM: NAD1983

POINT-OF-ENTRY  
1474' FNL 523' FWL  
SECTION 6, T23N, R6W  
LAT: 36.25659°N  
LONG: 107.51692°W  
DATUM: NAD1927  
  
LAT: 36.25660°N  
LONG: 107.51753°W  
DATUM: NAD1983

SURFACE LOCATION  
1132' FNL 755' FWL  
SECTION 6, T23N, R6W  
LAT: 36.25753°N  
LONG: 107.51615°W  
DATUM: NAD1927  
  
LAT: 36.25754°N  
LONG: 107.51676°W  
DATUM: NAD1983

<sup>17</sup> OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom-hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Signature: *Larry Higgins* Date: 7/16/14

Printed Name: Larry Higgins  
E-mail Address: larry.higgins@wpenergy.com

<sup>18</sup> SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

Date Revised: JULY 15, 2014  
Survey Date: SEPTEMBER 19, 2013

Signature and Seal of Professional Surveyor



JASON C. EDWARDS

Certificate Number 15269

**WPX ENERGY**

Operations Plan

(Note: This procedure will be adjusted on site based upon actual conditions)

**DATE:** 7/10/2014 **FIELD:** Lybrook (Gallup)

**WELL NAME:** Chaco 2306-06D #177H **SURFACE:** BLM

**SH Location:** NWNW Sec 6 -23N -06W **ELEVATION:** 6982' GR

**BH Location:** SWNW Sec 1 -23N -06W **MINERALS:** BLM  
Rio Arriba Co, NM

**MEASURED DEPTH:** 11,561' **LEASE #:** NMSF 078362

**I. GEOLOGY:** Surface formation – San Jose

**A. FORMATION TOPS: ( KB)**

Name	MD	TVD	Name	MD	TVD
Ojo Alamo	1576	1568	Point Lookout	4427	4387
Kirtland	1835	1824	Mancos	4658	4616
Picture Cliffs	2145	2130	<b>Kickoff Point</b>	<b>5069</b>	5025
Lewis	2250	2234	Top Target	5806	5611
Chacra	2581	2562	<b>Landing Point</b>	<b>6140</b>	5692
Cliff House	3705	3673	Base Target	6129	5691
Menefee	3739	3707			
			TD	11561	5605

- B. MUD LOGGING PROGRAM:** Mudlogger on location from surface csg to TD
- C. LOGGING PROGRAM:** LWD GR from surface casing to TD.
- D. NATURAL GAUGES:** Gauge any noticeable increases in gas flow. Record all gauges in Tour book and on morning reports.

**II. DRILLING**

- A. MUD PROGRAM:** LSND mud (WBM) will be used to drill the 12-1/4" Surface hole, the 8 3/4" Directional Vertical hole, and the curve portion of the wellbore. A LSND (WBM) or (OBM) will be used to drill the lateral portion of well. Treat for lost circulation as necessary. Obtain 100% returns prior to cementing. Notify Engineering of any mud losses.
- B. BOP TESTING:** While drill pipe is in use, the pipe rams and the blind rams will be function tested once each trip. The anticipated reservoir is expected to be less than 1300 psi, so the BOPE will be tested to **250 psi (Low) for 5 minutes and 1500 psi (High) for 10 minutes**. Pressure test surface casing to **600 psi for 30 minutes** and intermediate casing to **1500 psi for 30 minutes**. Utilize a BOPE Testing Unit with a recording chart and appropriate test plug for testing. The drum brakes will be inspected and tested each tour. **All tests and inspections will be recorded in the tour book as to time and results.**

**NOTE:** Vertical portion of the well (8-3/4 in.) will be directionally drilled as per attached Directional Plan to +/- 5,069 (MD) / 5,025' (TVD). Curve portion of wellbore will be drilled and landed at +/- 90 deg. at +/- 6,140' (MD) / 5,691' (TVD). 7 in. csg will be set at this point. A 6-1/8" Lateral will be drilled as per the attached Directional Plan to +/- 11,561' (MD) / 5,605' (TVD). Will run 4-1/2 in. Production Liner from +/- 5,990 ft. to TD and cemented. Liner will be tied back to surface w / 4-1/2" Casing for stimulation / testing, then removed from the well.

### III. MATERIALS

#### A. CASING PROGRAM:

<u>CASING TYPE</u>	<u>OH SIZE (IN)</u>	<u>DEPTH (MD) (FT)</u>	<u>CASING SIZE (IN)</u>	<u>WEIGHT(LB)</u>	<u>GRADE</u>
Surface	12.25"	400'+	9.625"	36#	J-55
Intermediate	8.75"	6,140'	7"	23#	K-55
Prod. Liner	6.125"	5,990' - 11,561'	4-1/2"	11.6#	N-80
Tie-Back String	N/A	Surf. - 5,990'	4-1/2"	11.6#	N-80

#### B. FLOAT EQUIPMENT:

1. SURFACE CASING: 9-5/8" notched regular pattern guide shoe. Run (1) standard centralizer on each of the bottom (4) joints of Surface Casing.
2. INTERMEDIATE CASING: 7" cement nose guide shoe with a self-fill insert float. Place float collar one joint above the shoe. Install (1) centralizer on each of the bottom (3) joints and one standard centralizer every (3) joints to 2,500 ft. Run (1) centralizer at 2,700 ft., 2,500 ft., 2,300ft., 2,000ft., 1,500 ft., and 1,000 ft.
3. PRODUCTION LINER: Run 4-1/2" Liner with cement nose guide Float Shoe + 2jts. of 4-1/2" casing + Landing Collar + 4-1/2" pup joint + (2) RSI (Sliding Sleeves) positioned inside the 330ft Hard line. Centralizer program will be determined by Wellbore condition and when Lateral is evaluated by Geoscientists and Reservoir Engineers. Set seals on Liner Hanger. Test TOL to 1500 psi for 15 minutes.
4. TIE-BACK CASING: None

#### C. CEMENTING:

*(Note: Volumes may be adjusted onsite due to actual conditions)*

1. SURFACE: 10 bbl Fr Water Spacer + 190 sx (222.3 cu.ft.) of "Premium Cement" + 2% Calcium Chloride Cement + 0.125# pps of Poly-E-Flake, 15.8 #/gal (1.17 cu ft./sk, Vol 39.58 Bbls.). The 100% excess should circulate cement to the surface. WOC 12 hours. Test csg to 600psi. Total Volume: (222.3 cu-ft/190 sx/39.6 Bbls). TOC at Surface.
2. INTERMEDIATE: 20 bbl (112 cu-ft) Mud Flush III spacer + Lead: 850 sx Foamed 50/50 Poz Cement. 13.0 ppg + 0.1% Halad 766 + 0.2% Versaset + 1.5% Chem-Foamer 760 (Yield :1.43 cu-ft/ sk. / Vol: 1216 cu-ft / 216.5 Bbls.) + TAIL: 100 sx 13.5 #/gal. + 0.2% Versaset + 0.15% HALAD-766 (Yield: 1.28 cu-ft / sk / Vol: 128 cu-ft / 22.8 Bbls.). + Fresh Water Displacement (1,362 cu-ft / +/- 242 Bbls) + 100 sx Top-Out Cement Premium: Yield: (1.17 cu-ft/ sk / (Vol: 117 cu-ft / 20.8 Bbls). Test Casing to 1500 PSI for 30 minutes. Total Cement Volume: (1050 sx / 1461 cu-ft / 260 bbls). Mix with +/- 84,000 SCF Nitrogen. TOC at surface.
3. PRODUCTION LINER: STAGE 1: 10 bbl (56 cu-ft) Fr Water Spacer. **STAGE 2:** 40 bbl 9.5 ppg (224.6 cu-ft) Tuned Spacer III + 0.5 gal/bbl Musol + 38.75 ppb Barite + 0.5 gal/bbl SEM-7. **STAGE 3:** 10 bbl Fr Water Spacer. **STAGE 4: Lead Cement:** 50 / 50 Poz Premium + 0.2% Versaset + 0.2% Halad -766, Yield 1.43 cu ft/sk, 13.0 ppg, (10 sx / 14.3 cu ft. / 2.5 bbls). **STAGE 5:** 200 sx. Foamed Lead Cement: 50 / 50 Poz Standard + 0.2% Versaset + 0.2% HALAD-766 + 1.5% Chem-Foamer 760. Yield 1.97 cu-ft/sk. 13.0 ppg (200 sx / 394 cu-ft. / 70.2 bbls.). **STAGE 6:** Tail Cement : 100 sx. 50/50 Poz Standard + 0.2% Versaset + 0.05% HALAD-766 + .05% SA-1015, Weight: 13.5 ppg ( 100 sx / Yield 1.28 cu ft/sk. / 128 cu ft. / 22.8 bbls) **STAGE 7:** Displace w/ +/- 137 bbl Fr Water. Total Cement ( 536.3 cu ft / 95.5 bbls). Mix Foamed Cement w/ +/- 75,000 SCF Nitrogen. Est. TOC +/- 5,690 ft.

**IV. COMPLETION****A. CBL**

1. Run CCL for perforating.

**B. PRESSURE TEST**

1. Pressure test 4-1/2" casing to 4500 psi max, hold at 1500 psi for 30 minutes. Increase pressure to Open RSI sleeves.

**C. STIMULATION**

1. Stimulate with approximately 2,805,000# 20/40 mesh sand and 340,000# 16/30 mesh sand in 619,113 gallons water with 42,696 mscf N2 for 17 stages.
2. Isolate stages with flow through frac plug.
3. Drill out frac plugs and flowback lateral.

**D. RUNNING TUBING**

1. Production Tubing: Run 2-7/8", 6.5#, J-55, EUE tubing with a SN on top of bottom joint. Land tubing near Top of Liner point of curve (~5,800' MD).

- Although this horizontal well will be drilled past the applicable setbacks, an unorthodox location application is not required because the completed interval in this well, as defined by 19.15.16.7 B(1) NMAC, will be entirely within the applicable setbacks. This approach complies with all applicable rules, including 19.15.16.14 A(3) NMAC, 19.15.16.14 B(2) NMAC, 19.15.16.15 B(2) NMAC, and 19.15.16.15 B(4) NMAC.

---

**NOTE:**

Installation of RSI sleeves at Toe of Lateral.

**Proposed Operations:**

A 4-1/2" 11.6# N-80 Liner will be run to TD and landed +/- 150 ft. into the 7" 23# K-55 Intermediate casing (set at 6,140 ft. MD) with a Liner Hanger and pack-off assembly then cemented to +/- 300 ft above the liner hanger. TOL will be +/- 5,990 ft. (MD) +/- 78 degree angle. TOC: +/- 5,690 ft. (MD).

After cementing and TOL clean up operations are complete, the TOL will be tested to 1500 psi (per BLM).

A 4-1/2" 11.6# N-80 tie-back string with seal assembly will be run and stung into the PBR of the liner hanger, tested to 1500 PSI and hung off at the surface.

The Drilling Rig will be rigged down at this point and Completion operations will begin. After Stimulation and Testing operations are complete the 4-1/2" tie-back string will be removed from the well.

Note: Changes to formation tops, casing landing points, well TD and Directional Plan.

Well Name: Chaco 2306-06D #177  
 Surface Location: Chaco 2306-06D  
 NAD 1927 (NADCON CONUS) , US State Plane 1927 (Exact solution) New Mexico Central 3002  
 Ground Elevation: 6982.00  
 +N/-S +E/-W Northing Easting Latitude Longitude Slot  
 0.00 0.00 1915390.69 126698.32 36.25753 -107.51615  
 WELL @ 6996.00usft (Original Well Elev)



Azimuths to True North  
 Magnetic North: 9.36°  
 Magnetic Field  
 Strength: 50183.6snT  
 Dip Angle: 63.02°  
 Date: 7/8/2014  
 Model: IGRF2010


Project: SJ 06-23N-06W  
 Site: Chaco 2306-06D  
 Well: Chaco 2306-06D #177  
 Design #1 09Jul14 kjs

## ANNOTATIONS

TVD	MD	Inc	Azi	+N/-S	+E/-W	Vsect	Departure	Annotation
550.00	550.00	0.00	0.00	0.00	0.00	0.00	0.00	Start Build 2.00
975.69	977.27	8.55	129.33	-20.16	24.60	-25.80	31.80	Hold 8.55° Inc, 129.33° Az
4599.77	4642.04	8.55	129.33	-365.30	445.81	-467.57	576.36	Start Drop -2.00
5025.46	5069.31	0.00	0.00	-385.46	470.41	-493.37	608.17	KOP 9°100
5576.79	5735.98	60.00	273.55	-365.76	152.71	-175.06	926.48	Hold 60° Inc, 273.55° Az
5606.79	5795.98	60.00	273.55	-362.55	100.85	-123.10	978.44	Begin 9°100 Build
5692.00	6139.52	90.92	273.55	-342.22	-227.05	205.42	1306.96	Landing Pt 90.92° Inc
5605.02	11560.53	90.92	273.55	-6.79	-5636.97	5625.73	6727.27	TD at 11561.53

## DESIGN TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Shape
TD / PBHL Chaco 2306-06D #177H	6005.00	-6.73	-5637.96	1915457.66	121060.75	36.25751	-107.53527	Point
PP Chaco 2306-06D #177H	5692.00	-342.22	-227.05	1915051.46	126466.81	36.25659	-107.51692	Point
- plan hits target center - plan misses target center by 0.01usft at 6139.53usft MD (5692.00 TVD, -342.22 N, -227.05 E)								







## **SAN JUAN BASIN**

**SJ 06-23N-06W**

**Chaco 2306-06D**

**Chaco 2306-06D #177**

**Wellbore #1**

**Plan: Design #1 09Jul14 kjs**

## **Standard Planning Report - Geographic**

**09 July, 2014**



WPX  
Planning Report - Geographic

Database:	COMPASS-PICEANCE	Local Co-ordinate Reference:	Well Chaco 2306-06D #177
Company:	SAN JUAN BASIN	TVD Reference:	WELL @ 6996.00usft (Original Well Elev)
Project:	SJ 06-23N-06W	MD Reference:	WELL @ 6996.00usft (Original Well Elev)
Site:	Chaco 2306-06D	North Reference:	True
Well:	Chaco 2306-06D #177	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1 09Jul14 kjs		

Project	SJ 06-23N-06W, Rio Arriba County, NM		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico Central 3002		

Site	Chaco 2306-06D		
Site Position:		Northing:	1,915,401.88 usft
From:	Lat/Long	Easting:	126,677.83 usft
Position Uncertainty:	0.00 usft	Slot Radius:	13.200 in
		Latitude:	36.25756
		Longitude:	-107.51622
		Grid Convergence:	-0.75 °

Well	Chaco 2306-06D #177		
Well Position	+N/-S	0.00 usft	Northing:
	+E/-W	0.00 usft	Easting:
Position Uncertainty	0.00 usft	Wellhead Elevation:	0.00 usft
		Latitude:	36.25753
		Longitude:	-107.51615
		Ground Level:	6,982.00 usft

Wellbore	Wellbore #1		
Magnetics	Model Name	Sample Date	Declination
			(°)
	IGRF2010	7/8/2014	9.36
			Dip Angle
			(°)
			63.02
			Field Strength
			(nT)
			50,184

Design	Design #1 09Jul14 kjs		
Audit Notes:			
Version:	Phase:	PLAN	Tie On Depth:
			0.00
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W
	(usft)	(usft)	(usft)
	0.00	0.00	0.00
			Direction
			(bearing)
			273.55

Plan Sections										
Measured	Inclination	Azimuth	Vertical	+N/-S	+E/-W	Dogleg	Build	Turn	TFO	Target
Depth	(°)	(bearing)	Depth	(usft)	(usft)	Rate	Rate	Rate	(°)	
(usft)			(usft)			(°/100usft)	(°/100usft)	(°/100usft)		
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
550.00	0.00	0.00	550.00	0.00	0.00	0.00	0.00	0.00	0.00	
977.27	8.55	129.33	975.69	-20.16	24.60	2.00	2.00	0.00	129.33	
4,642.04	8.55	129.33	4,599.77	-365.30	445.81	0.00	0.00	0.00	0.00	
5,069.31	0.00	0.00	5,025.46	-385.46	470.41	2.00	-2.00	0.00	180.00	
5,735.98	60.00	273.55	5,576.79	-365.76	152.71	9.00	9.00	0.00	273.55	
5,795.98	60.00	273.55	5,606.79	-362.55	100.85	0.00	0.00	0.00	0.00	
6,139.52	90.92	273.55	5,692.00	-342.22	-227.05	9.00	9.00	0.00	0.00	
11,561.53	90.92	273.55	5,605.00	-6.73	-5,637.96	0.00	0.00	0.00	0.00	TD / PBHL Chaco 230



WPX  
Planning Report - Geographic

Database: COMPASS-PICEANCE  
Company: SAN JUAN BASIN  
Project: SJ 06-23N-06W  
Site: Chaco 2306-06D  
Well: Chaco 2306-06D #177  
Wellbore: Wellbore #1  
Design: Design #1 09Jul14 kjs

Local Co-ordinate Reference: Well Chaco 2306-06D #177  
TVD Reference: WELL @ 6996.00usft (Original Well Elev)  
MD Reference: WELL @ 6996.00usft (Original Well Elev)  
North Reference: True  
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	1,915,390.69	126,698.33	36.25753	-107.51615
200.00	0.00	0.00	200.00	0.00	0.00	1,915,390.69	126,698.33	36.25753	-107.51615
400.00	0.00	0.00	400.00	0.00	0.00	1,915,390.69	126,698.33	36.25753	-107.51615
550.00	0.00	0.00	550.00	0.00	0.00	1,915,390.69	126,698.33	36.25753	-107.51615
<b>Start Build 2.00</b>									
600.00	1.00	129.33	600.00	-0.28	0.34	1,915,390.41	126,698.66	36.25753	-107.51615
800.00	5.00	129.33	799.68	-6.91	8.43	1,915,383.67	126,706.67	36.25751	-107.51612
977.27	8.55	129.33	975.69	-20.16	24.60	1,915,370.21	126,722.66	36.25748	-107.51607
<b>Hold 8.55° Inc, 129.33° Az</b>									
1,000.00	8.55	129.33	998.17	-22.30	27.21	1,915,368.04	126,725.24	36.25747	-107.51606
1,200.00	8.55	129.33	1,195.95	-41.13	50.20	1,915,348.90	126,747.98	36.25742	-107.51598
1,400.00	8.55	129.33	1,393.72	-59.97	73.19	1,915,329.77	126,770.72	36.25737	-107.51590
1,600.00	8.55	129.33	1,591.50	-78.81	96.17	1,915,310.64	126,793.46	36.25731	-107.51583
1,800.00	8.55	129.33	1,789.28	-97.64	119.16	1,915,291.50	126,816.20	36.25726	-107.51575
2,000.00	8.55	129.33	1,987.06	-116.48	142.15	1,915,272.37	126,838.94	36.25721	-107.51567
2,200.00	8.55	129.33	2,184.84	-135.31	165.13	1,915,253.23	126,861.68	36.25716	-107.51559
2,400.00	8.55	129.33	2,382.62	-154.15	188.12	1,915,234.10	126,884.42	36.25711	-107.51551
2,600.00	8.55	129.33	2,580.40	-172.98	211.11	1,915,214.96	126,907.15	36.25706	-107.51544
2,800.00	8.55	129.33	2,778.18	-191.82	234.10	1,915,195.83	126,929.89	36.25700	-107.51536
3,000.00	8.55	129.33	2,975.96	-210.66	257.08	1,915,176.69	126,952.63	36.25695	-107.51528
3,200.00	8.55	129.33	3,173.74	-229.49	280.07	1,915,157.56	126,975.37	36.25690	-107.51520
3,400.00	8.55	129.33	3,371.52	-248.33	303.06	1,915,138.42	126,998.11	36.25685	-107.51512
3,600.00	8.55	129.33	3,569.30	-267.16	326.04	1,915,119.29	127,020.85	36.25680	-107.51505
3,800.00	8.55	129.33	3,767.08	-286.00	349.03	1,915,100.15	127,043.59	36.25675	-107.51497
4,000.00	8.55	129.33	3,964.86	-304.84	372.02	1,915,081.02	127,066.33	36.25669	-107.51489
4,200.00	8.55	129.33	4,162.64	-323.67	395.00	1,915,061.88	127,089.07	36.25664	-107.51481
4,400.00	8.55	129.33	4,360.42	-342.51	417.99	1,915,042.75	127,111.80	36.25659	-107.51474
4,600.00	8.55	129.33	4,558.20	-361.34	440.98	1,915,023.61	127,134.54	36.25654	-107.51466
4,642.04	8.55	129.33	4,599.77	-365.30	445.81	1,915,019.59	127,139.32	36.25653	-107.51464
<b>Start Drop -2.00</b>									
4,800.00	5.39	129.33	4,756.55	-377.44	460.63	1,915,007.26	127,153.98	36.25649	-107.51459
5,000.00	1.39	129.33	4,956.16	-384.93	469.76	1,914,999.66	127,163.02	36.25647	-107.51456
5,069.31	0.00	0.00	5,025.46	-385.46	470.41	1,914,999.12	127,163.66	36.25647	-107.51456
<b>KOP 9°/100</b>									
5,200.00	11.76	273.55	5,155.23	-384.63	457.07	1,915,000.12	127,150.33	36.25647	-107.51460
5,400.00	29.76	273.55	5,341.48	-380.26	386.60	1,915,005.41	127,079.92	36.25649	-107.51484
5,600.00	47.76	273.55	5,496.79	-372.55	262.13	1,915,014.75	126,955.57	36.25651	-107.51526
5,735.98	60.00	273.55	5,576.79	-365.76	152.71	1,915,022.97	126,846.24	36.25653	-107.51563
<b>Hold 60° Inc, 273.55° Az</b>									
5,795.98	60.00	273.55	5,606.79	-362.55	100.85	1,915,026.86	126,794.43	36.25654	-107.51581
<b>Begin 9°/100 Build</b>									
5,800.00	60.36	273.55	5,608.79	-362.33	97.36	1,915,027.12	126,790.94	36.25654	-107.51582
6,000.00	78.36	273.55	5,678.99	-350.79	-88.68	1,915,041.09	126,605.07	36.25657	-107.51645
6,139.52	90.92	273.55	5,692.00	-342.22	-227.05	1,915,051.47	126,466.82	36.25659	-107.51692
<b>Landing Pt 90.92° Inc</b>									
6,139.53	90.92	273.55	5,692.00	-342.22	-227.05	1,915,051.47	126,466.82	36.25659	-107.51692
<b>PP Chaco 2306-06D #177H</b>									
6,200.00	90.92	273.55	5,691.03	-338.47	-287.40	1,915,056.00	126,406.53	36.25660	-107.51713
6,400.00	90.92	273.55	5,687.82	-326.10	-486.99	1,915,070.99	126,207.11	36.25664	-107.51780
6,600.00	90.92	273.55	5,684.61	-313.72	-686.58	1,915,085.97	126,007.70	36.25667	-107.51848
6,800.00	90.92	273.55	5,681.40	-301.35	-886.17	1,915,100.95	125,808.29	36.25670	-107.51916
7,000.00	90.92	273.55	5,678.19	-288.97	-1,085.76	1,915,115.93	125,608.88	36.25674	-107.51983
7,200.00	90.92	273.55	5,674.98	-276.60	-1,285.35	1,915,130.92	125,409.47	36.25677	-107.52051
7,400.00	90.92	273.55	5,671.77	-264.22	-1,484.94	1,915,145.90	125,210.05	36.25681	-107.52119



WPX  
Planning Report - Geographic

Database:	COMPASS-PICEANCE	Local Co-ordinate Reference:	Well Chaco 2306-06D #177
Company:	SAN JUAN BASIN	TVD Reference:	WELL @ 6996.00usft (Original Well Elev)
Project:	SJ 06-23N-06W	MD Reference:	WELL @ 6996.00usft (Original Well Elev)
Site:	Chaco 2306-06D	North Reference:	True
Well:	Chaco 2306-06D #177	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1 09Jul14 kjs		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
7,600.00	90.92	273.55	5,668.56	-251.85	-1,684.54	1,915,160.88	125,010.64	36.25684	-107.52187
7,800.00	90.92	273.55	5,665.36	-239.47	-1,884.13	1,915,175.87	124,811.23	36.25687	-107.52254
8,000.00	90.92	273.55	5,662.15	-227.10	-2,083.72	1,915,190.85	124,611.82	36.25691	-107.52322
8,200.00	90.92	273.55	5,658.94	-214.72	-2,283.31	1,915,205.83	124,412.41	36.25694	-107.52390
8,400.00	90.92	273.55	5,655.73	-202.35	-2,482.90	1,915,220.81	124,212.99	36.25697	-107.52457
8,600.00	90.92	273.55	5,652.52	-189.97	-2,682.49	1,915,235.80	124,013.58	36.25701	-107.52525
8,800.00	90.92	273.55	5,649.31	-177.60	-2,882.08	1,915,250.78	123,814.17	36.25704	-107.52593
9,000.00	90.92	273.55	5,646.10	-165.22	-3,081.67	1,915,265.76	123,614.76	36.25708	-107.52660
9,200.00	90.92	273.55	5,642.89	-152.85	-3,281.26	1,915,280.75	123,415.34	36.25711	-107.52728
9,400.00	90.92	273.55	5,639.68	-140.47	-3,480.85	1,915,295.73	123,215.93	36.25714	-107.52796
9,600.00	90.92	273.55	5,636.47	-128.10	-3,680.45	1,915,310.71	123,016.52	36.25718	-107.52863
9,800.00	90.92	273.55	5,633.26	-115.72	-3,880.04	1,915,325.69	122,817.11	36.25721	-107.52931
10,000.00	90.92	273.55	5,630.06	-103.35	-4,079.63	1,915,340.68	122,617.70	36.25725	-107.52999
10,200.00	90.92	273.55	5,626.85	-90.97	-4,279.22	1,915,355.66	122,418.28	36.25728	-107.53066
10,400.00	90.92	273.55	5,623.64	-78.60	-4,478.81	1,915,370.64	122,218.87	36.25731	-107.53134
10,600.00	90.92	273.55	5,620.43	-66.22	-4,678.40	1,915,385.63	122,019.46	36.25735	-107.53202
10,800.00	90.92	273.55	5,617.22	-53.85	-4,877.99	1,915,400.61	121,820.05	36.25738	-107.53270
11,000.00	90.92	273.55	5,614.01	-41.47	-5,077.58	1,915,415.59	121,620.63	36.25742	-107.53337
11,200.00	90.92	273.55	5,610.80	-29.10	-5,277.17	1,915,430.57	121,421.22	36.25745	-107.53405
11,400.00	90.92	273.55	5,607.59	-16.72	-5,476.76	1,915,445.56	121,221.81	36.25748	-107.53473
11,561.53	90.92	273.55	5,605.00	-6.73	-5,637.96	1,915,457.66	121,060.75	36.25751	-107.53527

TD at 11561.53 - TD / PBHL Chaco 2306-06D #177H

Design Targets

Target Name	Dip Angle (°)	Dip Dir. (bearing)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
- hit/miss target									
- Shape									
TD / PBHL Chaco 2306-	0.00	0.00	5,605.00	-6.73	-5,637.96	1,915,457.66	121,060.75	36.25751	-107.53527
- plan hits target center									
- Point									
PP Chaco 2306-06D #17	0.00	0.00	5,692.00	-342.22	-227.05	1,915,051.47	126,466.82	36.25659	-107.51692
- plan misses target center by 0.01usft at 6139.53usft MD (5692.00 TVD, -342.22 N, -227.05 E)									
- Point									

Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Comment
550.00	550.00	0.00	0.00	Start Build 2.00
977.27	975.69	-20.16	24.60	Hold 8.55° Inc, 129.33° Az
4,642.04	4,599.77	-365.30	445.81	Start Drop -2.00
5,069.31	5,025.46	-385.46	470.41	KOP 9°/100
5,735.98	5,576.79	-365.76	152.71	Hold 60° Inc, 273.55° Az
5,795.98	5,606.79	-362.55	100.85	Begin 9°/100 Build
6,139.52	5,692.00	-342.22	-227.05	Landing Pt 90.92° Inc
11,561.53	5,605.00	-6.73	-5,637.96	TD at 11561.53

# 1. INTRODUCTION

WPX Energy Production, LLC (WPX), is providing this Surface Use Plan of Operations (SUPO) to the Bureau of Land Management – Farmington Field Office (BLM-FFO) as part of their Chaco 2306-06D Nos. 176H and 177H (176H/177H) Applications for Permit to Drill (APDs). This SUPO is provided per Onshore Oil and Gas Order No. 1.

The 01H and 02H wells will each be permitted by an approved APD. The associated well pad (including construction zone), access road, and pipeline corridor, all of which are located on-lease, will also be permitted under the approved APDs.

Two staging areas will be associated with the project. Elm Ridge Exploration Company's (Elm Ridge's) inactive Lybrook South No.12 well pad will be authorized as a staging area via an agreement between WPX and Elm Ridge (if a Final Abandonment Notice [FAN] has not been issued for the pad) or under the approved APDs (if a FAN has been issued for the well pad). WPX's active Chaco 2306-19E Nos. 188H, 189H, and 205H (188H/189H/205H) well pad will also be used for staging.

A pre-disturbance onsite meeting for the project was held on February 27, 2014. The BLM, WPX, and an environmental consultant (Nelson Consulting, Inc.) attended the meeting.

In addition to the best management practices (BMPs) provided below and in the Surface Reclamation Plan (Reclamation Plan; Appendix A), the general Conditions of Approval will be followed, if any are attached to the approved APDs.

## 2. PROJECT LOCATION AND DESCRIPTION

### 2.1. Project Location

The project area is located in Rio Arriba County, New Mexico. The project area is located approximately 41 miles southeast of the town of Bloomfield, New Mexico. To access the project area, head southward on U.S. Highway 550 from the U.S. Highway 550-U.S. Highway 64 intersection for approximately 49 miles, turn left onto an existing road for approximately 4 miles, turn right onto an existing road for approximately 0.2 mile, and turn left onto an existing road for approximately 0.1 mile. The start of the 176H/177H access road is on the left side of the existing road. The access route from U.S. Highway 550 is depicted on Figure B.1 (Appendix B) and on the construction plats provided in the APD.

The staging areas are located in Sandoval County, approximately 3 miles south of the well pad, access road, and pipeline tie.

The legal locations of the project area and staging areas are listed in the below table (New Mexico Principal Meridian [NMPM]).

**Table 1. Legal Location of Project Area**

Township, Range	Section	Quarter-Quarter	Project Feature
Township 23 North, Range 6 West	6	southwestern ¼ northwestern ¼	Well Pad & Construction Zone
		northwestern ¼ northwestern ¼	Access Road & Pipeline Corridor
	19	southwestern ¼ northwestern ¼	Staging Areas

The latitude and longitude of the bottom holes and surface holes (wellheads) are provided in the below table.

Pipeline markers will be installed along the pipeline corridor within the line of sight. These markers will not create safety hazards.

Construction and maintenance activities will cease when soil or road surfaces become saturated to the extent that construction equipment is unable to stay within the project area and/or when activities cause irreparable harm to roads, soils, or streams. No frozen soils will be used for construction purposes or trench backfilling.

Construction plats are provided in the APDs.

## **9. METHODS FOR HANDLING WASTE DISPOSAL**

---

- ✓ Drilling operations will utilize a closed-loop system. Drilling of the horizontal lateral will be accomplished with water-based mud. All cuttings will be hauled to a commercial disposal facility or land farm. WPX will follow New Mexico Oil Conservation Division "Pit Rule" guidelines and Onshore Order No. 1 regarding the placement, operation, and removal of closed-loop systems. No blow pit will be used.

If drilling has not been initiated on the well pad within 120 days of the well pad being constructed, the operator will submit a site-stabilization plan to the BLM-FFO.

All garbage and trash will be placed in a metal trash basket. The trash and garbage will be hauled off site and dumped in an approved landfill, as needed. Portable toilets will be provided and maintained during construction, as needed (see Figures B.3 and B.4 [Appendix B] for the location of toilets and trash receptacles).

## **10. ANCILLARY FACILITIES**

---

Two staging areas will be used; they are described in Section 2.2 (Project Description). During staging, WPX will stay within the boundaries of the previously disturbed well pads associated with the staging areas. During interim reclamation, WPX will repair any damage to and reseed the staging areas (with the exception of portions of the staging areas that the well pad operators prefer to remain unseeded).

## **11. WELL SITE LAYOUT**

---

The approximate cuts, approximate fills, and orientation for the well pad are depicted on the construction plats in the APDs. Rig orientation and the location of drilling equipment and topsoil or spoil material stockpiles are depicted on Figure B.3 (Appendix B). The layout of the completions rigs is depicted on Figure B.4 (Appendix B). The interim reclamation/long-term disturbance layout is depicted on Figure B.5 (Appendix B) and is described below.

- The following areas (known as the "non-reseed working areas") will remain unreclaimed throughout the lifetime of the project:
  - Production facilities will be located within a 300-by-100-foot (0.7-acre) facility area at the southeastern end of the well pad.
  - The teardrop for the well pad will include a looped, 35-foot-wide driving surface, totaling approximately 0.5 acre.
- The following areas (known as the "reseed working areas") will be reseeded (but not recontoured) during interim reclamation:
  - The center of the teardrop will measure approximately 0.3 acre.

# 3000 PSI BOP Schematic

