

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy Minerals and Natural Resources
Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-144
Revised June 6, 2013

For temporary pits, below-grade tanks, and multi-well fluid management pits, submit to the appropriate NMOCD District Office.
For permanent pits submit to the Santa Fe Environmental Bureau office and provide a copy to the appropriate NMOCD District Office.

Pit, Below-Grade Tank, or

RCUD OCT 1 '14
OIL CONS. DIV.

Proposed Alternative Method Permit or Closure Plan Application

DIST. 3

- Type of action:
- ☐ Below grade tank registration
 - ☐ Permit of a pit or proposed alternative method
 - ☒ Closure of a pit, below-grade tank, or proposed alternative method
 - ☐ Modification to an existing permit/or registration
 - ☐ Closure plan only submitted for an existing permitted or non-permitted pit, below-grade tank, or proposed alternative method

Instructions: Please submit one application (Form C-144) per individual pit, below-grade tank or alternative request

Please be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.

1.
Operator: LOGOS OPERATIONS, LLC OGRID #: 289408
Address: 4001 NORTH BUTLER AVE. BUILDING 7101, FARMINGTON, NM 87401
Facility or well name: ROADRUNNER 2X
API Number: 30-045-35494 OCD Permit Number: 11435
U/L or Qtr/Qtr H Section 2 Township 24N Range 8W County: SAN JUAN
Center of Proposed Design: Latitude 36.343816 Longitude 107.645932 NAD: ☐ 1927 ☒ 1983
Surface Owner: ☐ Federal ☒ State ☐ Private ☐ Tribal Trust or Indian Allotment

2.
☒ **Pit:** Subsection F, G or J of 19.15.17.11 NMAC
Temporary: ☒ Drilling ☐ Workover
☐ Permanent ☐ Emergency ☐ Cavitation ☐ P&A ☐ Multi-Well Fluid Management Low Chloride Drilling Fluid ☐ yes ☐ no
☒ Lined ☐ Unlined Liner type: Thickness 20 mil ☒ LLDPE ☐ HDPE ☐ PVC ☐ Other _____
☒ String-Reinforced
Liner Seams: ☒ Welded ☒ Factory ☐ Other _____ Volume: 8,000 bbl Dimensions: L 130 x W 60 x D 10

3.
☐ **Below-grade tank:** Subsection I of 19.15.17.11 NMAC
Volume: _____ bbl Type of fluid: _____
Tank Construction material: _____
☐ Secondary containment with leak detection ☐ Visible sidewalls, liner, 6-inch lift and automatic overflow shut-off
☐ Visible sidewalls and liner ☐ Visible sidewalls only ☐ Other _____
Liner type: Thickness _____ mil ☐ HDPE ☐ PVC ☐ Other _____

4.
☐ **Alternative Method:**
Submittal of an exception request is required. Exceptions must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

5.
Fencing: Subsection D of 19.15.17.11 NMAC (Applies to permanent pits, temporary pits, and below-grade tanks)
☐ Chain link, six feet in height, two strands of barbed wire at top (Required if located within 1000 feet of a permanent residence, school, hospital, institution or church)
☐ Four foot height, four strands of barbed wire evenly spaced between one and four feet
☐ Alternate. Please specify _____

6.

Netting: Subsection E of 19.15.17.11 NMAC (*Applies to permanent pits and permanent open top tanks*)

- ☐ Screen ☐ Netting ☒ Other: 4' HOG WIRE WITH ONE STRAND OF BARBED WIRE ON TOP
- ☐ Monthly inspections (If netting or screening is not physically feasible)

7.

Signs: Subsection C of 19.15.17.11 NMAC

- ☐ 12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers
- ☒ Signed in compliance with 19.15.16.8 NMAC

8.

Variations and Exceptions:

Justifications and/or demonstrations of equivalency are required. Please refer to 19.15.17 NMAC for guidance.

Please check a box if one or more of the following is requested, if not leave blank:

- ☐ Variance(s): Requests must be submitted to the appropriate division district for consideration of approval.
- ☐ Exception(s): Requests must be submitted to the Santa Fe Environmental Bureau office for consideration of approval.

9.

Siting Criteria (regarding permitting): 19.15.17.10 NMAC

Instructions: The applicant must demonstrate compliance for each siting criteria below in the application. Recommendations of acceptable source material are provided below. Siting criteria does not apply to drying pads or above-grade tanks.

General siting

Ground water is less than 25 feet below the bottom of a low chloride temporary pit or below-grade tank.

- ☐ NM Office of the State Engineer - iWATERS database search; ☐ USGS; ☐ Data obtained from nearby wells

☐ Yes ☐ No
☐ NA

Ground water is less than 50 feet below the bottom of a Temporary pit, permanent pit, or Multi-Well Fluid Management pit.

NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells

☐ Yes ☐ No
☐ NA

Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended. (**Does not apply to below grade tanks**)

- Written confirmation or verification from the municipality; Written approval obtained from the municipality

☐ Yes ☐ No

Within the area overlying a subsurface mine. (**Does not apply to below grade tanks**)

- Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division

☐ Yes ☐ No

Within an unstable area. (**Does not apply to below grade tanks**)

- Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map

☐ Yes ☐ No

Within a 100-year floodplain. (**Does not apply to below grade tanks**)

- FEMA map

☐ Yes ☐ No

Below Grade Tanks

Within 100 feet of a continuously flowing watercourse, significant watercourse, lake bed, sinkhole, wetland or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 200 horizontal feet of a spring or a fresh water well used for public or livestock consumption;

- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Temporary Pit using Low Chloride Drilling Fluid (maximum chloride content 15,000 mg/liter)

Within 100 feet of a continuously flowing watercourse, or any other significant watercourse or within 200 feet of any lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). (Applies to low chloride temporary pits.)

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 300 feet from a occupied permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☐ No

Within 200 horizontal feet of a spring or a private, domestic fresh water well used by less than five households for domestic or stock watering purposes, or 300feet of any other fresh water well or spring, in existence at the time of the initial application.

NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 100 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Temporary Pit Non-low chloride drilling fluid

Within 300 feet of a continuously flowing watercourse, or any other significant watercourse, or within 200 feet of any lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☐ No

Within 500 horizontal feet of a spring or a private, domestic fresh water well used by less than five households for domestic or stock watering purposes, or 1000 feet of any other fresh water well or spring, in the existence at the time of the initial application;

- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 300 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Permanent Pit or Multi-Well Fluid Management Pit

Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark).

- Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application.

- Visual inspection (certification) of the proposed site; Aerial photo; Satellite image

☐ Yes ☐ No

Within 500 horizontal feet of a spring or a fresh water well used for domestic or stock watering purposes, in existence at the time of initial application.

- NM Office of the State Engineer - iWATERS database search; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

Within 500 feet of a wetland.

- US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site

☐ Yes ☐ No

10.

Temporary Pits, Emergency Pits, and Below-grade Tanks Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC

Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Hydrogeologic Report (Below-grade Tanks) - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC
- ☐ Hydrogeologic Data (Temporary and Emergency Pits) - based upon the requirements of Paragraph (2) of Subsection B of 19.15.17.9 NMAC
- ☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
- ☐ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
- ☐ Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

☐ Previously Approved Design (attach copy of design) API Number: _____ or Permit Number: _____

11.

Multi-Well Fluid Management Pit Checklist: Subsection B of 19.15.17.9 NMAC

Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
- ☐ A List of wells with approved application for permit to drill associated with the pit.
- ☐ Closure Plan (Please complete Boxes 14 through 18, if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC
- ☐ Hydrogeologic Data - based upon the requirements of Paragraph (4) of Subsection B of 19.15.17.9 NMAC
- ☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC

☐ Previously Approved Design (attach copy of design) API Number: _____ or Permit Number: _____

12.

Permanent Pits Permit Application Checklist: Subsection B of 19.15.17.9 NMAC

Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Hydrogeologic Report - based upon the requirements of Paragraph (1) of Subsection B of 19.15.17.9 NMAC
☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
☐ Climatological Factors Assessment
☐ Certified Engineering Design Plans - based upon the appropriate requirements of 19.15.17.11 NMAC
☐ Dike Protection and Structural Integrity Design - based upon the appropriate requirements of 19.15.17.11 NMAC
☐ Leak Detection Design - based upon the appropriate requirements of 19.15.17.11 NMAC
☐ Liner Specifications and Compatibility Assessment - based upon the appropriate requirements of 19.15.17.11 NMAC
☐ Quality Control/Quality Assurance Construction and Installation Plan
☐ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
☐ Freeboard and Overtopping Prevention Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
☐ Nuisance or Hazardous Odors, including H₂S, Prevention Plan
☐ Emergency Response Plan
☐ Oil Field Waste Stream Characterization
☐ Monitoring and Inspection Plan
☐ Erosion Control Plan
☐ Closure Plan - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC

13.

Proposed Closure: 19.15.17.13 NMAC

Instructions: Please complete the applicable boxes, Boxes 14 through 18, in regards to the proposed closure plan.

- Type: ☐ Drilling ☐ Workover ☐ Emergency ☐ Cavitation ☐ P&A ☐ Permanent Pit ☐ Below-grade Tank ☐ Multi-well Fluid Management Pit
☐ Alternative
- Proposed Closure Method: ☐ Waste Excavation and Removal
☐ Waste Removal (Closed-loop systems only)
☐ On-site Closure Method (Only for temporary pits and closed-loop systems)
☐ In-place Burial ☐ On-site Trench Burial
☐ Alternative Closure Method

14.

Waste Excavation and Removal Closure Plan Checklist: (19.15.17.13 NMAC) **Instructions:** Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.

- ☐ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC
☐ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of Subsection C of 19.15.17.13 NMAC
☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings)
☐ Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC

15.

Siting Criteria (regarding on-site closure methods only): 19.15.17.10 NMAC

Instructions: Each siting criteria requires a demonstration of compliance in the closure plan. Recommendations of acceptable source material are provided below. Requests regarding changes to certain siting criteria require justifications and/or demonstrations of equivalency. Please refer to 19.15.17.10 NMAC for guidance.

Ground water is less than 25 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA
Ground water is between 25-50 feet below the bottom of the buried waste - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA
Ground water is more than 100 feet below the bottom of the buried waste. - NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	<input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> NA
Within 100 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). - Topographic map; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within 300 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. - Visual inspection (certification) of the proposed site; Aerial photo; Satellite image	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within 300 horizontal feet of a private, domestic fresh water well or spring used for domestic or stock watering purposes, in existence at the time of initial application. - NM Office of the State Engineer - iWATERS database; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input type="checkbox"/> No
Written confirmation or verification from the municipality; Written approval obtained from the municipality	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within 300 feet of a wetland. US Fish and Wildlife Wetland Identification map; Topographic map; Visual inspection (certification) of the proposed site	<input type="checkbox"/> Yes <input type="checkbox"/> No
Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance	

adopted pursuant to NMSA 1978, Section 3-27-3, as amended.

- Written confirmation or verification from the municipality; Written approval obtained from the municipality

☐ Yes ☐ No

Within the area overlying a subsurface mine.

- Written confirmation or verification or map from the NM EMNRD-Mining and Mineral Division

☐ Yes ☐ No

Within an unstable area.

- Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; Topographic map

☐ Yes ☐ No

Within a 100-year floodplain.

- FEMA map

☐ Yes ☐ No

16.

On-Site Closure Plan Checklist: (19.15.17.13 NMAC) *Instructions: Each of the following items must be attached to the closure plan. Please indicate, by a check mark in the box, that the documents are attached.*

- ☐ Siting Criteria Compliance Demonstrations - based upon the appropriate requirements of 19.15.17.10 NMAC
- ☐ Proof of Surface Owner Notice - based upon the appropriate requirements of Subsection E of 19.15.17.13 NMAC
- ☐ Construction/Design Plan of Burial Trench (if applicable) based upon the appropriate requirements of Subsection K of 19.15.17.11 NMAC
- ☐ Construction/Design Plan of Temporary Pit (for in-place burial of a drying pad) - based upon the appropriate requirements of 19.15.17.11 NMAC
- ☐ Protocols and Procedures - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☐ Confirmation Sampling Plan (if applicable) - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☐ Waste Material Sampling Plan - based upon the appropriate requirements of 19.15.17.13 NMAC
- ☐ Disposal Facility Name and Permit Number (for liquids, drilling fluids and drill cuttings or in case on-site closure standards cannot be achieved)
- ☐ Soil Cover Design - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
- ☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
- ☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC

17.

Operator Application Certification:

I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief.

Name (Print): _____ Title: _____

Signature: _____ Date: _____

e-mail address: _____ Telephone: _____

18.

OCD Approval: ☐ Permit Application (including closure plan) ☒ Closure Plan (only) ☐ OCD Conditions (see attachment)

OCD Representative Signature: Jonathan D. Kelly Approval Date: 10/30/2014

Title: Compliance Officer OCD Permit Number: _____

19.

Closure Report (required within 60 days of closure completion): 19.15.17.13 NMAC

Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an approved closure plan has been obtained and the closure activities have been completed.

☒ Closure Completion Date: 6/19/14

20.

Closure Method:

- ☐ Waste Excavation and Removal ☒ On-Site Closure Method ☐ Alternative Closure Method ☐ Waste Removal (Closed-loop systems only)
- ☐ If different from approved plan, please explain.

21.

Closure Report Attachment Checklist: *Instructions: Each of the following items must be attached to the closure report. Please indicate, by a check mark in the box, that the documents are attached.*

- ☒ Proof of Closure Notice (surface owner and division)
- ☐ Proof of Deed Notice (required for on-site closure for private land only)
- ☒ Plot Plan (for on-site closures and temporary pits)
- ☐ Confirmation Sampling Analytical Results (if applicable)
- ☒ Waste Material Sampling Analytical Results (required for on-site closure)
- ☒ Disposal Facility Name and Permit Number
- ☒ Soil Backfilling and Cover Installation
- ☒ Re-vegetation Application Rates and Seeding Technique
- ☒ Site Reclamation (Photo Documentation)


On-site Closure Location: Latitude 36.343816N Longitude 107.645932W NAD: ☐ 1927 ☒ 1983

Operator Closure Certification:

I hereby certify that the information and attachments submitted with this closure report is true, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan.

Name (Print): Jamie Goodwin

Title: Regulatory Tech

Signature: Date: 10/1/14e-mail address: JGoodwin@logosoperating.comTelephone: 505-330-9333

Logos Operating, LLC
San Juan Basin
Closure Report

Lease Name: ROADRUNNER 2X
API NO: 30-045-35494

In accordance with Rule 19.15.17.12 NMAC the following information describes the closure requirements of temporary pits on Logos Operating, LLC (Logos) locations. This is Logos' standard procedure for all temporary pits. A Separate plan will be submitted for any temporary pit that does not conform to this plan.

All closure activities will include proper documentation and be available for review upon request and will be submitted to OCD within 60 days of the pit closure. Closure report will be filed on C-144 and incorporated the following:

- Detail on Capping and Covering, where applicable (See report)
- Plot Plan (Pit diagram) (Included as an attachment)
- Inspection reports (Included as an attachment)
- Sampling Results (Included as an attachment)
- C-105 (Included as an attachment)
- Copy of Deed Notice will be filed with County Clerk (Not required on Federal, State or Tribal land as stated by FAQ dated October 30, 2008)

General Plan

- 1 All free standing liquids will be removed at the start of the pit closure process from the pit and disposed of in a division-approved facility or recycle, reuse or reclaim the liquids in a manner that the appropriate division district office approves.

See All recovered liquids were disposed of at Basin Disposal (permit #NM-01-005) and any sludge or soil required to be removed to facilitate closure was hauled to Envirotech Land Farm (Permit #NM-01-011) and JFJ Landfarm % IEI (Permit #NM-01-0010B).

- 2 The preferred method of closure for all temporary pits will be on-site burial, assuming that all criteria listed in sub-section (D) of 19.15.17.13 are met.

The pit was closed using onsite burial.

- 3 The surface owner shall be notified of Logos proposed closure plan using a means that provides proof of notice i.e., certified mail, return receipt requested.

The closure process notification to the landowner was sent via email. (See attached) (Well located on Federal Land/STATE LAND, certified mail is not required for Federal Land per BLM/OCD).

*Due to confusion on surface owner notification for State land, only the NMOCD was notified. In the future the State Land Office will be notified where the State is the surface owner.

*Variance Explanation: Rule 19.15.17.13 E. If the surface owner is a public entity (BLM/State/Tribal) then an email notification will be sent, of plans to close the temporary pit at least 72 hours, but no more than 1 week, prior to any closure operation. The notice will include the well name, API number, and location.

- 4 Within 6 months of the Rig Off status occurring Logos will ensure that temporary pits are closed, re-contoured, and reseeded.

The closure plan requirements were met due to rig move off date as noted on C-105. (See attached).

- 5 Notice of Closure will be given to the Aztec Division office between 72 hours and one week of closure via email, or verbally, The notification of closure will include the following:
 - i. Operator's name
 - ii. Location by Unit Letter, Section, Township, and Range. Well name and API Number

Notification is attached.

- 6 Pit contents shall be mixed with non-waste containing, earthen material in order to achieve the solidification process. The solidification process will be accomplished using a combination of natural drying and mechanically mixing. Pit contents will be mixed with non-waste, earthen material to a consistency that is deemed a safe and stable. The mixing ratio shall not exceed 3 parts clean soil to 1 part pit contents.

Logos mixed the pit contents with non-waste containing, earthen material in order to achieve the solidification process. The solidification process was accomplished by using a combination of natural drying and mechanically mixing. Pit contents were mixed with non-waste, earthen material to a consistency that is deemed as safe and stable. The mixing ratio consisted of not more than 3 parts clean soil to 1 part pit contents.

- 7 A five point composite sample will be taken of the pit using sampling tools and all samples tested per 19.15.17.13(D)(5). In the event that the criteria are not met, all contents will be handled per 9.15.17.13(D)(7) i.e., Dig and haul.

A five point composite sample was taken of the pit using sampling tools and all samples tested per 19.15.17.13(D)(5). (Sample results attached).

Components	Tests Method	Limit (mg/Kg)	Results (ppm)
Benzene	EPA SW-846 8021B or 8015M	<u>10</u>	<u>SEE</u>
BTEX	EPA SW-846 8021B or 8260B	<u>50</u>	<u>ATTACHED</u>
TPH	EPA SW-846 418.1	<u>2500</u>	
GRO/DRO	EPA SW-846 8015M	<u>1000</u>	
Chlorides	EPA 300.0	<u>80000</u>	

- 8 Upon completion of solidification and testing, Logos will fold the outer edges of the trench liner to overlap the waste material in the pit area, then install a geomembrane cover over the waste material in the pit to prevent collections of infiltration water after the soil cover is in place; geomembrane a 20-mil, string reinforced, LLDPE liner, or equivalent complying with EPA SW-846 method 9090A requirements.

The pit material passed solidification and testing standards. Logos folded the outer edges of the trench liner to overlap the waste material in the pit area, then installed a geomembrane cover over the waste material and folded liner as per 19.15.17.13(8)(a)(b).

- 9 The pit area will be backfilled with compacted, non-waste containing, earthen material. A minimum of four feet of cover shall be achieved and the cover shall include one foot of suitable material to establish vegetation at the site, or the background thickness of topsoil, whichever is greater.

The pit area was then backfilled with compacted, non-waste containing, earthen material. More than four feet of cover was achieved and the cover included one foot of suitable material to establish vegetation at the site.

- 10 Re-contouring of location will match fit, shape, line, form and texture of the surrounding area. Re-shaping will include drainage control, prevent ponding, and prevent erosion. Natural drainages will be unimpeded and water bars and/or silt traps will be placed in areas where needed to prevent erosion on a large scale. Final re-contour shall have a uniform appearance with smooth surface, fitting the natural landscape.

The pit area was re-contoured to match fit, shape, line, form and texture of the surrounding area. Reshaping included drainage control, to prevent ponding and erosion. Natural drainages were unimpeded and water bars and/or silt traps were placed in areas where needed to prevent erosion on a large scale. Final re-contour has a uniform appearance with smooth surface, fitting the natural landscape.

- 11 Notification will be sent to OCD when the reclaimed area is seeded.

Provision 11 was accomplished in accordance with NMOCD 19.15.17.13(5)(d) Notification will be sent to the OCD when re-vegetation is established.

- 12 Logos shall seed the distributed areas the first growing season after the operator closes the pit. Seeding will be accomplished via drilling on the contour whenever practical or by other division-approved methods. BLM or Forest Service stipulated seed mix will be used on federal lands. Vegetative cover will be established that will reflect a life-form ratio of plus or minus fifty percent (50%) of pre-disturbance levels and will equal

seventy (70%) of the native perennial vegetative cover (un-impacted) consisting of at least three native plant species, including at least one grass, but not including noxious weeds, and maintain that cover thorough two successive growing seasons. Repeat seeding or planting will be continued until successful vegetative growth occurs.

Provision 12 was accomplished in accordance with NMOCD 19.15.17.13(5)(d) Notification will be sent to the OCD when re-vegetation is established.

- 13 The temporary pit will be located with a steel marker, no less than four inches in diameter, cemented in a hole three feet deep in the center of the onsite burial. The marker will be flush with the ground to allow access of the active well pad and for safety concerns. The marker will include a threaded collar to be used for future abandonment. The top of the marker will contain a welded steel 12" square plate that indicates the onsite burial of the temporary pit. The plate will be easily removable and a four foot tall riser will be threaded into the top of the collar marker and welded around the base with the operator's information at the time of all wells on the pad are abandoned. The operator's information will include the following: Operator Name, Lease Name, Well Name and number, Unit Number, Section, Township, Range and an indicator that the marker is an onsite burial location.

Provision 13 was accomplished by installing a steel marker in the temporary pit, no less than four inches in diameter, cemented in a hole three feet deep in the center of the onsite burial. The marker is flush with the ground to allow access of the active well pad and for safety concerns. The top of the marker contains a welded steel 12" square plate that indicates the onsite burial of the temporary pit. The plate contains the following: Operator's name, Lease Name, Well Name and number, Unit Number, Section, Township, Range and an indicator that the marker is an onsite burial location.

The plate will be easily removable and a four foot tall riser will be threaded into the top of the collar marker and welded around the base with the following operator's information at the time of all wells on the pad are abandoned. The riser will also indicate that the marker is for an onsite burial location.

Operator Name: LOGOS
Lease Name & Well Number: ROADRUNNER 2X
Unit Letter: H
Section: 2
Township: 24N
Range: 6W
API#: 30-039-31181
OBL

- 14 Logos inspected and documented daily and weekly reports on the above Temporary Pit. Logos inspected any liner breaches, fluid seeps or spills, HC's on top of temporary pit, free of miscellaneous solid waste or debris, discharge line integrity, fence integrity, any dead wildlife or livestock and inspection of the freeboard. Logos will provide maintained documentation of inspections upon request.

Inspection Start Date: 11/27/13

Inspection End Date: 06/11/14

NOTE: During start and end dates of temporary pit inspections no issues found.

DISTRICT I
1825 N. French Dr., Hobbs, N.M. 88240
Phone: (575) 393-8161 Fax: (575) 393-0720

DISTRICT II
811 S. First St., Artesia, N.M. 88210
Phone: (575) 748-1233 Fax: (575) 748-0720

DISTRICT III
1000 Rio Brazos Rd., Aztec, N.M. 87410
Phone: (505) 834-8178 Fax: (505) 834-8170

DISTRICT IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION

1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

*API Number	*Pool Code 19859	*Pool Name DUFERS POINT GALLUP DAKOTA
*Property Code	*Property Name ROAD RUNNER Roadrunner	*Well Number 2X
*OGRID No. 289408	*Operator Name LOGOS OPERATING, LLC	*Elevation 7368'

10 Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
H	2	24-N	8-W		2340	NORTH	713	EAST	SAN JUAN


11 Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
12 Dedicated Acres 168.60			13 Joint or Infill		14 Consolidation Code		15 Order No.		

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

16 T-25-N

T-24-N



17 OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or undivided mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or a working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Signature: *Austin Akers* Date: 10/10/13
Printed Name: Austin Akers
E-mail Address: aakers@logosresourcesllc.com


18 SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

OCTOBER 9, 2013

Date of Survey

Signature and Seal of Surveyor




GLEN W. RUSSELL

Certificate Number

15703

LOGOS OPERATING, LLC

ROADRUNNER #2X, 2340' FNL & 713' FEL
SECTION 2, T-24-N, R-8-W, NMPM, SAN JUAN COUNTY, NM
GROUND ELEVATION: 7368', DATE: OCTOBER 2, 2013



NOTES:

1. VECTOR SURVEYS IS NOT LIABLE FOR UNDERGROUND UTILITIES OR PIPELINES. CONTRACTOR SHOULD CALL ONE-CALL FOR LOCATION OF ANY MARKED OR UNMARKED BURIED PIPELINES OR CABLES ON WELL PAD AND OR ACCESS ROAD AT LEAST TWO (2) WORKING DAYS PRIOR TO CONSTRUCTION.
2. RESERVE PIT DIKE: TO BE 8' ABOVE DEEP SIDE (OVERFLOW - 3' WIDE AND 1' ABOVE SHALLOW SIDE).




Table 1, Summary of Analytical Results
 Logos Operating, LLC
 Roadrunner #2X
 Drill Pit Closure and Backfill Material Sampling Report
 San Juan County, New Mexico
 Project Number 12035-0043

Sample Description	Sample Number	Date	TPH USEPA Method 418.1 (ppm)	TPH USEPA Method 8015 (ppm)	Benzene USEPA Method 8021 (ppm)	BTEX USEPA Method 8021 (ppm)	Chlorides USEPA Method 300.0 (ppm)
NMOCDC/RORA Standards	NA	NA	2500	1000	10	50	80000
Drill Pit Composite	1	2/3/2014	2790	224.8	0.38	3.94	903
Drill Pit Comp	1	3/31/2014	916	NS	NS	NS	NS
NMOCDC/RORA Standards	NA	NA	NA	NA	NA	NA	600
Backfill Material Composite	2	2/3/2014	NS	NS	NS	NS	26.4

NS = Not Sampled

ND = Non-Detect at Stated Method's Detection Limit

* Values in **BOLD** above regulatory standards



Analytical Report

Report Summary

Client: Logos Operating, LLC
Chain Of Custody Number: 16541
Samples Received: 2/4/2014 7:35:00AM
Job Number: 12035-0043
Work Order: P402008
Project Name/Location: Roadrunner #2X

Entire Report Reviewed By:

A handwritten signature in black ink, appearing to read 'Tim Cain', is written over a horizontal line.

Date: 2/7/14

Tim Cain, Laboratory Manager

Supplement to analytical report generated on: 2/7/14 3:27 pm

The results in this report apply to the samples submitted to Envirotech's Analytical Laboratory and were analyzed in accordance with the chain of custody document supplied by you, the client, and as such are for your exclusive use only. The results in this report are based on the sample as received unless otherwise noted. Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc. If you have any questions regarding this analytical report, please don't hesitate to contact Envirotech's Laboratory Staff.



Logos Operating, LLC
PO Box 18
Flora Vista NM, 87415

Project Name: Roadrunner #2X
Project Number: 12035-0043
Project Manager: Tiffany McIntosh

Reported:
07-Feb-14 15:29

Analytical Report for Samples

Client Sample ID	Lab Sample ID	Matrix	Sampled	Received	Container
Drill Pit Composite	P402008-01A	Soil	02/03/14	02/04/14	Glass Jar, 4 oz.
Backfill Material Composite	P402008-02A	Soil	02/03/14	02/04/14	Glass Jar, 4 oz.


Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.

5796 US Highway 64, Farmington, NM 87401

Three Springs - 65 Mercado Street, Suite 115, Durango, CO 81301

Ph (505) 632-0615 Fx (505) 632-1865

Ph (970) 259-0615 Fr (800) 362-1879





Logos Operating, LLC
PO Box 18
Flora Vista NM, 87415

Project Name: Roadrunner #2X
Project Number: 12035-0043
Project Manager: Tiffany McIntosh

Reported:
07-Feb-14 15:29

**Drill Pit Composite
P402008-01 (Solid)**

Analyte	Result	Reporting Limit	Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
Volatile Organics by EPA 8021									
Benzene	0.38	0.05	mg/kg	1	1406034	02/06/14	02/06/14	EPA 8021B	
Toluene	1.04					06/14	02/06/14	EPA 8021B	
Ethylbenzene	0.32					06/14	02/06/14	EPA 8021B	
p,m-Xylene	1.72					06/14	02/06/14	EPA 8021B	
o-Xylene	0.48					06/14	02/06/14	EPA 8021B	
Total Xylenes	2.20					06/14	02/06/14	EPA 8021B	
Total BTEX	3.94					06/14	02/06/14	EPA 8021B	
Surrogate: Bromochlorobenzene						06/14	02/06/14	EPA 8021B	
Surrogate: 1,3-Dichlorobenzene						06/14	02/06/14	EPA 8021B	
Nonhalogenated Organics by 8015									
Gasoline Range Organics (C6-C10)	45.8					02/06/14	02/06/14	EPA 8015D	
Diesel Range Organics (C10-C28)	179					02/06/14	02/06/14	EPA 8015D	
Total Petroleum Hydrocarbons by 418.1									
Total Petroleum Hydrocarbons	2790					02/06/14	02/06/14	EPA 418.1	
Cation/Anion Analysis									
Chloride	903						02/04/14	EPA 300.0	

Benzene
0.05

BTEX
0.05

GR010
59.9

Chloride
9.98


Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.

5796 US Highway 64, Farmington, NM 87401

Three Springs - 65 Mercado Street, Suite 115, Durango, CO 81301

Ph (505) 632-0615 Fx (505) 632-1865

Ph (970) 259-0615 Fr (800) 362-1879





Logos Operating, LLC
PO Box 18
Flora Vista NM, 87415

Project Name: Roadrunner #2X
Project Number: 12035-0043
Project Manager: Tiffany McIntosh

Reported:
07-Feb-14 15:29

Backfill Material Composite
P402008-02 (Solid)

Analyte	Result	Reporting		Units	Dilution	Batch	Prepared	Analyzed	Method	Notes
		Limit								
Cation/Anion Analysis										
Chloride	26.4	9.85	mg/kg	1		1406015	02/04/14	02/04/14	EPA 300.0	


Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.

5796 US Highway 64, Farmington, NM 87401

Three Springs - 65 Mercado Street, Suite 115, Durango, CO 81301

Ph (505) 632-0615 Fx (505) 632-1865

Ph (970) 259-0615 Fr (800) 362-1879





Logos Operating, LLC
PO Box 18
Flora Vista NM, 87415

Project Name: Roadrunner #2X
Project Number: 12035-0043
Project Manager: Tiffany McIntosh

Reported:
07-Feb-14 15:29

Volatile Organics by EPA 8021 - Quality Control

Envirotech Analytical Laboratory

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

Batch 1406034 - Purge and Trap EPA 5030A

Blank (1406034-BLK1)

Prepared & Analyzed: 06-Feb-14

Benzene	ND	0.05	mg/kg							
Toluene	ND	0.05	"							
Ethylbenzene	ND	0.05	"							
p,m-Xylene	ND	0.05	"							
o-Xylene	ND	0.05	"							
Total Xylenes	ND	0.05	"							
Total BTEX	ND	0.05	"							
Surrogate: 1,3-Dichlorobenzene	47.7		ug/L	50.0		95.4	80-120			
Surrogate: Bromochlorobenzene	48.9		"	50.0		97.8	80-120			

Duplicate (1406034-DUP1)

Source: P402008-01

Prepared & Analyzed: 06-Feb-14

Benzene	0.38	0.05	mg/kg		0.38			0.0927	30	
Toluene	1.03	0.05	"		1.04			0.776	30	
Ethylbenzene	0.31	0.05	"		0.32			1.63	30	
p,m-Xylene	1.75	0.05	"		1.72			1.35	30	
o-Xylene	0.46	0.05	"		0.48			3.71	30	
Surrogate: 1,3-Dichlorobenzene	52.1		ug/L	50.0		104	80-120			
Surrogate: Bromochlorobenzene	54.9		"	50.0		110	80-120			

Matrix Spike (1406034-MS1)

Source: P402008-01

Prepared & Analyzed: 06-Feb-14

Benzene	47.7		ug/L	50.0	7.62	80.1	39-150			
Toluene	56.4		"	50.0	20.7	71.4	46-148			
Ethylbenzene	47.5		"	50.0	6.34	82.2	32-160			
p,m-Xylene	105		"	100	34.4	70.9	46-148			
o-Xylene	49.3		"	50.0	9.62	79.5	46-148			
Surrogate: 1,3-Dichlorobenzene	45.2		"	50.0		90.4	80-120			
Surrogate: Bromochlorobenzene	47.2		"	50.0		94.4	80-120			


Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.

5796 US Highway 64, Farmington, NM 87401

Three Springs • 65 Mercado Street, Suite 115, Durango, CO 81301

Ph (505) 632-0615 Fx (505) 632-1865

Ph (970) 259-0615 Fx (800) 362-1879





Logos Operating, LLC	Project Name:	Roadrunner #2X	Reported:
PO Box 18	Project Number:	12035-0043	07-Feb-14 15:29
Flora Vista NM, 87415	Project Manager:	Tiffany McIntosh	

Nonhalogenated Organics by 8015 - Quality Control

Envirotech Analytical Laboratory

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	-----------------	-------	-------------	---------------	------	-------------	-----	-----------	-------

Batch 1406033 - DRO Extraction EPA 3550C

Blank (1406033-BLK1)	Prepared & Analyzed: 06-Feb-14									
Diesel Range Organics (C10-C28)	ND	29.9	mg/kg							
Duplicate (1406033-DUP1)	Source: P402008-01 Prepared & Analyzed: 06-Feb-14									
Diesel Range Organics (C10-C28)	222	59.9	mg/kg		179			21.3	30	
Matrix Spike (1406033-MS1)	Source: P402008-01 Prepared & Analyzed: 06-Feb-14									
Diesel Range Organics (C10-C28)	336	31.6	mg/kg	263	179	59.7	75-125			SPK1


Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.

5796 US Highway 64, Farmington, NM 87401

Ph (505) 632-0615 Fx (505) 632-1865

Three Springs - 65 Mercado Street, Suite 115, Durango, CO 81301

Ph (970) 259-0615 Fr (800) 362-1879





Logos Operating, LLC
PO Box 18
Flora Vista NM, 87415

Project Name: Roadrunner #2X
Project Number: 12035-0043
Project Manager: Tiffany McIntosh

Reported:
07-Feb-14 15:29

Nonhalogenated Organics by 8015 - Quality Control

Envirotech Analytical Laboratory

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 1406034 - Purge and Trap EPA 5030A										
Blank (1406034-BLK1)										
Gasoline Range Organics (C6-C10)	ND	4.98	mg/kg							Prepared & Analyzed: 06-Feb-14
Duplicate (1406034-DUP1)										
Gasoline Range Organics (C6-C10)	52.3	4.99	mg/kg		45.8			13.2	30	Source: P402008-01 Prepared & Analyzed: 06-Feb-14
Matrix Spike (1406034-MS1)										
Gasoline Range Organics (C6-C10)	1.14		mg/L	0.450	0.92	49.2	75-125			SPK1 Source: P402008-01 Prepared & Analyzed: 06-Feb-14


Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.

5796 US Highway 64, Farmington, NM 87401

Three Springs - 65 Mercado Street, Suite 115, Durango, CO 81301

Ph (505) 632-0615 Fx (505) 632-1865

Ph (970) 259-0615 Fr (800) 362-1879





Logos Operating, LLC
PO Box 18
Flora Vista NM, 87415

Project Name: Roadrunner #2X
Project Number: 12035-0043
Project Manager: Tiffany McIntosh

Reported:
07-Feb-14 15:29

Total Petroleum Hydrocarbons by 418.1 - Quality Control

Envirotech Analytical Laboratory

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
---------	--------	--------------------	-------	----------------	------------------	------	----------------	-----	--------------	-------

Batch 1406031 - 418 Freon Extraction

Blank (1406031-BLK1)

Prepared & Analyzed: 06-Feb-14

Total Petroleum Hydrocarbons 35.9 19.9 mg/kg

Duplicate (1406031-DUP1)

Source: P402008-01

Prepared & Analyzed: 06-Feb-14

Total Petroleum Hydrocarbons 2130 19.9 mg/kg 2790 26.9 30

Matrix Spike (1406031-MS1)

Source: P402008-01

Prepared & Analyzed: 06-Feb-14

Total Petroleum Hydrocarbons 1180 mg/L 500 698 97.2 80-120


Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.

5796 US Highway 64, Farmington, NM 87401

Ph (505) 632-0615 Fx (505) 632-1865

Three Springs - 65 Mercado Street, Suite 115, Durango, CO 81301

Ph (970) 259-0615 Fr (800) 362-1879





Logos Operating, LLC
PO Box 18
Flora Vista NM, 87415

Project Name: Roadrunner #2X
Project Number: 12035-0043
Project Manager: Tiffany McIntosh

Reported:
07-Feb-14 15:29

Cation/Anion Analysis - Quality Control

Envirotech Analytical Laboratory

Analyte	Result	Reporting Limit	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Batch 1406015 - Anion Extraction EPA 300.0										
Blank (1406015-BLK1)				Prepared & Analyzed: 04-Feb-14						
Chloride	ND	9.93	mg/kg							
LCS (1406015-BS1)				Prepared & Analyzed: 04-Feb-14						
Chloride	503	9.96	mg/kg	498		101	90-110			
Matrix Spike (1406015-MS1)				Source: P402007-01 Prepared & Analyzed: 04-Feb-14						
Chloride	628	9.97	mg/kg	499	184	89.0	80-120			
Matrix Spike Dup (1406015-MSD1)				Source: P402007-01 Prepared & Analyzed: 04-Feb-14						
Chloride	626	9.93	mg/kg	497	184	89.1	80-120	0.233	20	


Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.

5796 US Highway 64, Farmington, NM 87401

Three Springs - 65 Mercado Street, Suite 115, Durango, CO 81301

Ph (505) 632-0615 Fx (505) 632-1865

Ph (970) 259-0615 Fr (800) 362-1879





Logos Operating, LLC
PO Box 18
Flora Vista NM, 87415

Project Name: Roadrunner #2X
Project Number: 12035-0043
Project Manager: Tiffany McIntosh

Reported:
07-Feb-14 15:29

Notes and Definitions

SPK1 The spike recovery for this QC sample is outside of control limits

DET Analyte DETECTED

ND Analyte NOT DETECTED at or above the reporting limit

NR Not Reported

dry Sample results reported on a dry weight basis

RPD Relative Percent Difference


Partial or incomplete reproduction of this report is prohibited, unless approved by Envirotech, Inc.

5796 US Highway 64, Farmington, NM 87401

Three Springs - 65 Mercado Street, Suite 115, Durango, CO 81301

Ph (505) 632-0615 Fx (505) 632-1865

Ph (970) 259-0615 Fr (800) 362-1879



CHAIN OF CUSTODY RECORD

16541

Client: Logos Operating		Project Name / Location: Roadrunner #2X		ANALYSIS / PARAMETERS																																																					
Email results to: T. McIntosh		Sampler Name: T. McIntosh		<table border="1" style="width:100%; border-collapse: collapse; font-size: 0.8em;"> <tr> <th>TPH (Method 8015)</th> <th>BTEX (Method 8021)</th> <th>VOC (Method 8260)</th> <th>RCRA 8 Metals</th> <th>Cation / Anion</th> <th>RCI</th> <th>TCLP with H/P</th> <th>CO Table 910-1</th> <th>TPH (418.1)</th> <th>CHLORIDE</th> <th></th> <th></th> <th></th> <th></th> <th></th> <th></th> <th>Sample Cool</th> <th>Sample Intact</th> </tr> <tr> <td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td> </tr> </table>																		TPH (Method 8015)	BTEX (Method 8021)	VOC (Method 8260)	RCRA 8 Metals	Cation / Anion	RCI	TCLP with H/P	CO Table 910-1	TPH (418.1)	CHLORIDE							Sample Cool	Sample Intact																		
TPH (Method 8015)	BTEX (Method 8021)	VOC (Method 8260)	RCRA 8 Metals																			Cation / Anion	RCI	TCLP with H/P	CO Table 910-1	TPH (418.1)	CHLORIDE							Sample Cool	Sample Intact																						
Client Phone No.: 505-320-0436		Client No.: 12035-0043																																																							
Sample No. / Identification	Sample Date	Sample Time	Lab No.	No./Volume of Containers	Preservative			TPH	BTEX	VOC	RCRA 8 Metals	Cation / Anion	RCI	TCLP with H/P	CO Table 910-1	TPH (418.1)	CHLORIDE					Sample Cool	Sample Intact																																		
					HNO ₃	HCl	cool																																																		
Drill Pit Composite	2/3/14	1500	P402008-01	1-4 oz jar			X	X	X								X	X				X	X																																		
Backfill Material Composite	1	1510	P402008-02	+			1										X					X	X																																		
Relinquished by: (Signature) <i>T. McIntosh</i>				Date	Time	Received by: (Signature) <i>Minianjire</i>				Date	Time																																														
Relinquished by: (Signature) <i>T. McIntosh</i>						Received by: (Signature)																																																			
Sample Matrix																																																									
Soil <input checked="" type="checkbox"/> Solid <input type="checkbox"/> Sludge <input checked="" type="checkbox"/> Aqueous <input type="checkbox"/> Other <input type="checkbox"/>																																																									
<input type="checkbox"/> Sample(s) dropped off after hours to secure drop off area.				<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: right;"> <p>13.2 14.8</p> <p>4.0</p> </div> </div>																																																					

Submit To Appropriate District Office Two Copies District I 1625 N. French Dr., Hobbs, NM 88240 District II 811 S. First St., Artesia, NM 88210 District III 1000 Rio Brazos Rd., Aztec, NM 87410 District IV 1220 S. St. Francis Dr., Santa Fe, NM 87505	State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505	Form C-105 Revised August 1, 2011 1. WELL API NO. 30-045-35494 2. Type of Lease <input checked="" type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/> FED/INDIAN 3. State Oil & Gas Lease No. LG-1916
--	---	---

WELL COMPLETION OR RECOMPLETION REPORT AND LOG										
4. Reason for filing: <input type="checkbox"/> COMPLETION REPORT (Fill in boxes #1 through #31 for State and Fee wells only) <input checked="" type="checkbox"/> C-144 CLOSURE ATTACHMENT (Fill in boxes #1 through #9, #15 Date Rig Released and #32 and/or #33; attach this and the plat to the C-144 closure report in accordance with 19.15.17.13.K NMAC)						5. Lease Name or Unit Agreement Name ROADRUNNER 6. Well Number: 2X				
7. Type of Completion: <input checked="" type="checkbox"/> NEW WELL <input type="checkbox"/> WORKOVER <input type="checkbox"/> DEEPENING <input type="checkbox"/> PLUGBACK <input type="checkbox"/> DIFFERENT RESERVOIR <input type="checkbox"/> OTHER										
8. Name of Operator LOGOS OPERATING LLC						9. OGRID				
10. Address of Operator 4001 North Butler Avenue, Building 7101 Farmington, NM 87401						11. Pool name or Wildcat				
12. Location	Unit Ltr	Section	Township	Range	Lot	Feet from the	N/S Line	Feet from the	E/W Line	County
Surface:										
BH:										
13. Date Spudded	14. Date T.D. Reached	15. Date Rig Released 12/09/13		16. Date Completed (Ready to Produce)			17. Elevations (DF and RKB, RT, GR, etc.)			
18. Total Measured Depth of Well		19. Plug Back Measured Depth		20. Was Directional Survey Made?			21. Type Electric and Other Logs Run			
22. Producing Interval(s), of this completion - Top, Bottom, Name										

23. CASING RECORD (Report all strings set in well)					
CASING SIZE	WEIGHT LB./FT.	DEPTH SET	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED

24. LINER RECORD				25. TUBING RECORD			
SIZE	TOP	BOTTOM	SACKS CEMENT	SCREEN	SIZE	DEPTH SET	PACKER SET

26. Perforation record (interval, size, and number)				27. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC. DEPTH INTERVAL AMOUNT AND KIND MATERIAL USED 			
---	--	--	--	--	--	--	--

28. PRODUCTION							
Date First Production		Production Method (Flowing, gas lift, pumping - Size and type pump)			Well Status (Prod. or Shut-in)		
Date of Test	Hours Tested	Choke Size	Prod'n For Test Period	Oil - Bbl	Gas - MCF	Water - Bbl.	Gas - Oil Ratio
Flow Tubing Press.	Casing Pressure	Calculated 24-Hour Rate	Oil - Bbl.	Gas - MCF	Water - Bbl.	Oil Gravity - API - (Corr.)	
29. Disposition of Gas (Sold, used for fuel, vented, etc.)						30. Test Witnessed By	
31. List Attachments							
32. If a temporary pit was used at the well, attach a plat with the location of the temporary pit.							
33. If an on-site burial was used at the well, report the exact location of the on-site burial:							
Latitude 36.343816N Longitude 107.645932W NAD 1927 1983X							
I hereby certify that the information shown on both sides of this form is true and complete to the best of my knowledge and belief							
Signature <i>Jamie Goodwin</i>		Printed Name <i>Jamie Goodwin</i>		Title <i>Regulatory Tech.</i>		Date <i>10/1/14</i>	
E-mail Address <i>JGoodwin@logosoperating.com</i>							



Pit Closure Form:

Date: 6/19/14

Well Name: ROADRUNNER 002X

Footages: 2340' FNL & 713' FEL Unit Letter: H

Section: 2, T-24N, R-8W, County: SAN JUAN State: NM

Contractor Closing Pit: JD

Construction Inspector: Wayne Ritter

Inspector Signature: Wayne Ritter

Date: 6/19/14

Jamie Goodwin

From: Tamra Sessions
Sent: Thursday, May 15, 2014 8:19 AM
To: Jonathan Kelly (jonathan.kelly@state.nm.us)
Cc: brandon.powell@state.nm.us; Wayne Ritter; Kristina Graham
Subject: Roadrunner 2X_Pit Closure 72hr Notice

Logos Operating is giving 72hr notice of plans to start temporary pit closure operations on Monday 05/19/2014 for the following well.

Please contact Wayne Ritter at 505-320-0436 for any questions or concerns. Thank you.

*Roadrunner 2X
API 30-45-35494
H – Sec 2 – T24N – R08W*

Tamra Sessions
Logos Resources, LLC
Operations Technician
tsessions@logosresourcesllc.com
(c) 505-330-9333
(o) 505-436-3790 ext 103



Reclamation Form:

Date: 8/23/14

Well Name: ROADRUNNER 002X

Footages: 2340' FNL & 713' FEL Unit Letter: H

Section: 2, T-24N, R-8W, County: SAN JUAN State: NM

Reclamation Contractor: JD

Reclamation Start Date: 7/8/14

Reclamation Complete Date: 8/22/14

Road Completion Date: 8/22/14

Seeding Date: Fall 2014

PIT MARKER STATUS

(When Required) Picture of Marker set needed

Date Marker Placed: 8/23/14


Latitude: 36.343816N


Longitude: 107.645932W

Date Pit Manifold Removed: N/A


Construction Inspector Signature: Wayne B...

Date Inspected: 8/23/14




WNR-11987
20-9

LOGOS OPERATING, LLC.
ROADRUNNER #2X
API #30-045-35494
2340' FNL 713' FEL
H-SEC. 2-T24N-R8W
SAN JUAN COUNTY, NM
OFFICE # 505-436-2627
AFTER HRS # 866-598-6220



Temporary Pit Weekly Inspection Form

WELL NAME:	ROADRUNNER 2X		API NO:	30-045-35494	
LEGALS:	Section:	2	Township:	24N	Range: 8W
Drilling RD Date:	12/092013				

Inspector's Name	Ramsey Hatalie	Ramsey Hatalie	Ramsey Hatalie									
WEEK #	13	14	15	16	17	18	19	20	21	22	23	24
DATE	05/13/14	05/19/14	06/11/014									
Well sign on location (Y/N)	Y	Y	Y									
Any liner breeches (Y/N)	N	N	N									
Any fluid seeps/spills (Y/N)	N	N	N									
HC's on top of temp. pit (Y/N)	N	N	N									
Temp pit free of misc. Solid												
Waste/Debris(Y/N)	Y	Y	Y									
Discharge Line												
Integrity Good (Y/N)	Y	N	Y									
Fence Integrity Good (Y/N)	Y	Y	Y									
Any Dead Wildlife/ Stock (Y/N)	N	N	N									
Freeboard to be 2' or > Est. (ft)	Y (10')	Y (10')	Y									
Was the OCD contacted (Y/N)	N	N	N									
Pictures taken (Y/N)	Y	Y	Y									
Comments:	10' CLEARANCE	10' CLEARANCE	STARTED FILLING PIT/CLOSED PIT									

Temporary Pit Weekly Inspection Form

WELL NAME:	ROADRUNNER 2X			API NO:	30-045-35494		
LEGAL:	Section:	2	Township:	24N	Range:	8W	
Drilling RD Date:	12/092013						

Inspector's Name	Ramsey Hatalie	Ramsey Hatalie	Ramsey Hatalie	Ramsey Hatalie	Ramsey Hatalie	Ramsey Hatalie	Ramsey Hatalie	Ramsey Hatalie	Ramsey Hatalie	Ramsey Hatalie	Ramsey Hatalie	Ramsey Hatalie
WEEK #	1	2	3	4	5	6	7	8	9	10	11	12
DATE	01/03/14	01/07/14	01/10/14	01/14/14	01/26/14	02/14/14	03/03/14	03/25/14	04/01/14	04/13/14	04/21/14	04/28/14
Well sign on location (Y/N)	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
Any liner breeches (Y/N)	N	N	N	N	N	N	N	N	N	N	N	N
Any fluid seeps/spills (Y/N)	N	N	N	N	N	N	N	N	N	N	N	N
HC's on top of temp. pit (Y/N)	N	N	N	N	N	N	N	N	N	N	N	N
Temp pit free of misc. Solid Waste/Debris(Y/N)	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
Discharge Line Integrity Good (Y/N)	Y	N	Y	N	Y	N	N	N	N	N	N	N
Fence Integrity Good (Y/N)	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
Any Dead Wildlife/ Stock (Y/N)	N	N	N	N	N	N	N	N	N	N	N	N
Freeboard to be 2' or > Est. (ft)	Y (4')	Y (8')	Y (6')	Y (6')	Y (6')	Y (8')	Y (8')	Y (6')	Y (6')	Y (6')	Y (13')	Y (8')
Was the OCD contacted (Y/N)	N	N	N	N	N	N	N	N	N	N	N	N
Pictures taken (Y/N)	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y

Comments:	4' CLEARANCE	8' CLEARANCE	6' CLEARANCE	6' CLEARANCE	6' CLEARANCE	8' CLEARANCE	8' CLEARANCE	6' CLEARANCE	6' CLEARANCE	6' CLEARANCE/ RESERVE PALLET FROM PIT	13' CLEARANCE	8' CLEARANCE
-----------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	-----------------	--	------------------	-----------------



4001 N. Butler Ave
Farmington, NM 87401
Phone: (505) 436-2627
Fax: (505) 832-3095

Date: October 23, 2014

OIL CONS. DIV DIST. 3

To: NMOCD

OCT 27 2014

Re: Closure Permit #12249
Roadrunner 2X
API 30-045-35494

Dear NMOCD,

Logos Operating, LLC (289408) has reviewed their information regarding your email request dated 10/20/14 for general issues encountered on our submitted closure report.

- No Copy of Pit Closure Extension was sent to the NMOCD for approval.
 - Please find explanation of pit closure delay on closure report.

Regards,

A handwritten signature in black ink that reads "Jamie Goodwin". The signature is written in a cursive, flowing style.

Jamie Goodwin
Regulatory Technician

Logos Operating, LLC
San Juan Basin
Closure Report

OIL CONS. DIV DIST. 3

OCT 27 2014

Lease Name: ROADRUNNER 2X
API NO: 30-045-35494

In accordance with Rule 19.15.17.12 NMAC the following information describes the closure requirements of temporary pits on Logos Operating, LLC (Logos) locations. This is Logos' standard procedure for all temporary pits. A Separate plan will be submitted for any temporary pit that does not conform to this plan.

All closure activities will include proper documentation and be available for review upon request and will be submitted to OCD within 60 days of the pit closure. Closure report will be filed on C-144 and incorporated the following:

- Detail on Capping and Covering, where applicable **(See report)**
- Plot Plan (Pit diagram) **(Included as an attachment)**
- Inspection reports **(Included as an attachment)**
- Sampling Results **(Included as an attachment)**
- C-105 **(Included as an attachment)**
- Copy of Deed Notice will be filed with County Clerk **(Not required on Federal, State or Tribal land as stated by FAQ dated October 30, 2008)**

General Plan

- 1 All free standing liquids will be removed at the start of the pit closure process from the pit and disposed of in a division-approved facility or recycle, reuse or reclaim the liquids in a manner that the appropriate division district office approves.

All recovered liquids were disposed of at Basin Disposal (permit #NM-01-005) and any sludge or soil required to be removed to facilitate closure was hauled to Envirotech Land Farm (Permit #NM-01-011) and JFJ Landfarm % IEI (Permit #NM-01-0010B).

- 2 The preferred method of closure for all temporary pits will be on-site burial, assuming that all criteria listed in sub-section (D) of 19.15.17.13 are met.

The pit was closed using onsite burial.

- 3 The surface owner shall be notified of Logos proposed closure plan using a means that provides proof of notice i.e., certified mail, return receipt requested.

The closure process notification to the landowner was sent via email. (See attached) (Well located on Federal Land/STATE LAND, certified mail is not required for Federal Land per BLM/OCD).

***Due to confusion on surface owner notification for State land, only the NMOCD was notified. In the future the State Land Office will be notified where the State is the surface owner.**

***Variance Explanation: Rule 19.15.17.13 E. If the surface owner is a public entity (BLM/State/Tribal) then an email notification will be sent, of plans to close the temporary pit at least 72 hours, but no more than 1 week, prior to any closure operation. The notice will include the well name, API number, and location.**

- 4 Within 6 months of the Rig Off status occurring Logos will ensure that temporary pits are closed, re-contoured, and reseeded.

The closure plan requirements were not met due to rig move off date as noted on C-105. (See attached).

Due to confusion at the time Logos did not submit a pit closure extension. In the future Logos will comply with NMOCD Ruling 19.15.17.13 (E) (2).

- 5 Notice of Closure will be given to the Aztec Division office between 72 hours and one week of closure via email, or verbally, The notification of closure will include the following:
 - i. Operator's name
 - ii. Location by Unit Letter, Section, Township, and Range. Well name and API Number

Notification is attached.

- 6 Pit contents shall be mixed with non-waste containing, earthen material in order to achieve the solidification process. The solidification process will be accomplished using a combination of natural drying and mechanically mixing. Pit contents will be mixed with non-waste, earthen material to a consistency that is deemed a safe and stable. The mixing ratio shall not exceed 3 parts clean soil to 1 part pit contents.

Logos mixed the pit contents with non-waste containing, earthen material in order to achieve the solidification process. The solidification process was accomplished by using a combination of natural drying and mechanically mixing. Pit contents were mixed with non-waste, earthen material to a consistency that is deemed as safe and stable. The mixing ratio consisted of not more than 3 parts clean soil to 1 part pit contents.

- 7 A five point composite sample will be taken of the pit using sampling tools and all samples tested per 19.15.17.13(D)(5). In the event that the criteria are not met, all contents will be handled per 9.15.17.13(D)(7) i.e., Dig and haul.

A five point composite sample was taken of the pit using sampling tools and all samples tested per 19.15.17.13(D)(5). (Sample results attached).

Components	Tests Method	Limit (mg/Kg)	Results (ppm)
Benzene	EPA SW-846 8021B or 8015M	10	SEE
BTEX	EPA SW-846 8021B or 8260B	50	ATTACHED
TPH	EPA SW-846 418.1	2500	
GRO/DRO	EPA SW-846 8015M	1000	
Chlorides	EPA 300.0	80000	

- 8 Upon completion of solidification and testing, Logos will fold the outer edges of the trench liner to overlap the waste material in the pit area, then install a geomembrane cover over the waste material in the pit to prevent collections of infiltration water after the soil cover is in place; geomembrane a 20-mil, string reinforced, LLDPE liner, or equivalent complying with EPA SW-846 method 9090A requirements.

The pit material passed solidification and testing standards. Logos folded the outer edges of the trench liner to overlap the waste material in the pit area, then installed a geomembrane cover over the waste material and folded liner as per 19.15.17.13(8)(a)(b).

- 9 The pit area will be backfilled with compacted, non-waste containing, earthen material. A minimum of four feet of cover shall be achieved and the cover shall include one foot of suitable material to establish vegetation at the site, or the background thickness of topsoil, whichever is greater.

The pit area was then backfilled with compacted, non-waste containing, earthen material. More than four feet of cover was achieved and the cover included one foot of suitable material to establish vegetation at the site.

- 10 Re-contouring of location will match fit, shape, line, form and texture of the surrounding area. Re-shaping will include drainage control, prevent ponding, and prevent erosion. Natural drainages will be unimpeded and water bars and/or silt traps will be placed in areas where needed to prevent erosion on a large scale. Final re-contour shall have a uniform appearance with smooth surface, fitting the natural landscape.

The pit area was re-contoured to match fit, shape, line, form and texture of the surrounding area. Reshaping included drainage control, to prevent ponding and erosion. Natural drainages were unimpeded and water bars and/or silt traps were placed in areas where needed to prevent erosion on a large scale. Final re-contour has a uniform appearance with smooth surface, fitting the natural landscape.

- 11 Notification will be sent to OCD when the reclaimed area is seeded.

Provision 11 was accomplished in accordance with NMOCD 19.15.17.13(5)(d) Notification will be sent to the OCD when re-vegetation is established.

- 12 Logos shall seed the distributed areas the first growing season after the operator closes the pit. Seeding will be accomplished via drilling on the contour whenever practical or by other division-approved methods. BLM or Forest Service stipulated seed mix will be used on federal lands. Vegetative cover will be established that will reflect a life-form ratio of plus or minus fifty percent (50%) of pre-disturbance levels and will equal

seventy (70%) of the native perennial vegetative cover (un-impacted) consisting of at least three native plant species, including at least one grass, but not including noxious weeds, and maintain that cover thorough two successive growing seasons. Repeat seeding or planting will be continued until successful vegetative growth occurs.

Provision 12 was accomplished in accordance with NMOCD 19.15.17.13(5)(d) Notification will be sent to the OCD when re-vegetation is established.

- 13 The temporary pit will be located with a steel marker, no less than four inches in diameter, cemented in a hole three feet deep in the center of the onsite burial. The marker will be flush with the ground to allow access of the active well pad and for safety concerns. The marker will include a threaded collar to be used for future abandonment. The top of the marker will contain a welded steel 12" square plate that indicates the onsite burial of the temporary pit. The plate will be easily removable and a four foot tall riser will be threaded into the top of the collar marker and welded around the base with the operator's information at the time of all wells on the pad are abandoned. The operator's information will include the following: Operator Name, Lease Name, Well Name and number, Unit Number, Section, Township, Range and an indicator that the marker is an onsite burial location.

Provision 13 was accomplished by installing a steel marker in the temporary pit, no less than four inches in diameter, cemented in a hole three feet deep in the center of the onsite burial. The marker is flush with the ground to allow access of the active well pad and for safety concerns. The top of the marker contains a welded steel 12" square plate that indicates the onsite burial of the temporary pit. The plate contains the following: Operator's name, Lease Name, Well Name and number, Unit Number, Section, Township, Range and an indicator that the marker is an onsite burial location.

The plate will be easily removable and a four foot tall riser will be threaded into the top of the collar marker and welded around the base with the following operator's information at the time of all wells on the pad are abandoned. The riser will also indicate that the marker is for an onsite burial location.

**Operator Name: LOGOS
Lease Name & Well Number: ROADRUNNER 2X
Unit Letter: H
Section: 2
Township: 24N
Range: 6W
API#: 30-039-31181
OBL**

- 14 Logos inspected and documented daily and weekly reports on the above Temporary Pit. Logos inspected any liner breaches, fluid seeps or spills, HC's on top of temporary pit, free of miscellaneous solid waste or debris, discharge line integrity, fence integrity, any dead wildlife or livestock and inspection of the freeboard. Logos will provide maintained documentation of inspections upon request.

Inspection Start Date: 11/27/13

Inspection End Date: 06/11/14

NOTE: During start and end dates of temporary pit inspections no issues found.