

State of New Mexico
Energy, Minerals and Natural Resources Department

Susana Martinez
Governor

David Martin
Cabinet Secretary

Brett F. Woods, Ph.D.
Deputy Cabinet Secretary

David R. Catanach Division Director
Oil Conservation Division



New Mexico Oil Conservation Division approval and conditions listed below are made in accordance with OCD Rule 19.15.7.11 and are in addition to the actions approved by BLM on the following 3160-3 APD form.

Operator Signature Date: 9-28-15

Well information;

Operator WIPX, Well Name and Number W. Alamo Unit #465H

API# 30-045-35718, Section 12, Township 22 N/S, Range 08 E/W

Conditions of Approval:

(See the below checked and handwritten conditions)

- ☒ Notify Aztec OCD 24hrs prior to casing & cement.
- ☒ Hold C-104 for directional survey & "As Drilled" Plat
- ☒ Hold C-104 for NSL, NSP, DHC
- ☐ Spacing rule violation. Operator must follow up with change of status notification on other well to be shut in or abandoned
- ☐ Regarding the use of a pit, closed loop system or below grade tank, the operator must comply with the following as applicable:
 - A pit requires a complete C-144 be submitted and approved prior to the construction or use of the pit, pursuant to 19.15.17.8.A
 - A closed loop system requires notification prior to use, pursuant to 19.15.17.9.A
 - A below grade tank requires a registration be filed prior to the construction or use of the below grade tank, pursuant to 19.15.17.8.C
- ☐ Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string
- ☒ Regarding Hydraulic Fracturing, review EPA Underground Injection Control Guidance 84
- ☒ Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.
- ☒ Well-bore communication is regulated under 19.15.29 NMAC. This requires well-bore Communication to be reported in accordance with 19.15.29.8.

Charles Per
NMOCD Approved by Signature

2-12-2016
Date KC

RECEIVED
SEP 28 2015

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FEB 02 2016

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NOG 1419-1984
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name W. Alamito Unit
2. Name of Operator WPX Energy Production, LLC		7. If Unit or CA Agreement, Name and No. W Alamito UT #465H
3a. Address P.O. Box 640 Aztec, NM 87410	3b. Phone No. (include area code) (505) 333-1849	8. Lease Name and Well No. W Alamito UT #465H
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface 2,089' FNL & 1,086' FEL, sec 12, T22N, R8W At proposed prod. zone 330' FSL & 1,800' FEL, sec 13, T22N, R8W		9. API Well No. 30-045-35718
14. Distance in miles and direction from nearest town or post office* approximately 7 miles southwest of Lybrook, New Mexico		10. Field and Pool, or Exploratory Alamito Mancos W
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 1,086'	16. No. of Acres in lease 160 acres	11. Sec., T., R., M., or Blk. and Survey or Area SHL: Sec 12, T22N, R8W BHL: Sec 13, T22N, R8W
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 40'	19. Proposed Depth 13,015' MD / 4,597' TVD	12. County or Parish San Juan County
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 6,803' GR	22. Approximate date work will start* October 30, 2015	13. State NM
17. Spacing Unit dedicated to this well 240.00 acres (W/2 SE/4 Section 12, T22N, R8W W/2 E/2 Section 13, T22N, R8W)		
20. BLM/BIA Bond No. on file B001576		
23. Estimated duration 1 month		

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification.
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature 	Name (Printed/Typed) Andrea Felix	Date 09/28/2015
Title Regulatory Specialist Sr.		
Approved by (Signature) 	Name (Printed/Typed) AFM	Date 1/29/16
Title AFM	Office FEO	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

WPX Energy Production, LLC, proposes to develop the Gallup formation at the above described location in accordance with the attached drilling and surface use plans.

The well pad surface is under jurisdiction of the BLM and is on lease and will be twinned with the W Alamito #464H.

This location has been archaeologically surveyed by La Plata Archeological Consultants. Copies of their report have been submitted directly to the BLM.

A new 7,715.7 foot on lease access road will be built to access the location.

A new 8,036.0 foot on lease pipeline will be built.

This action is subject to
technical and procedural review
pursuant to 43 CFR 3165.3 and
appeal pursuant to 43 CFR 3165.4

NMOCD AV

BLM'S APPROVAL OR ACCEPTANCE OF THIS
ACTION DOES NOT RELIEVE THE LESSEE AND
OPERATOR FROM OBTAINING ANY OTHER
AUTHORIZATION REQUIRED FOR OPERATIONS
ON FEDERAL AND INDIAN LANDS

DRILLING OPERATIONS AUTHORIZED
ARE SUBJECT TO COMPLIANCE WITH
ATTACHED "GENERAL REQUIREMENTS"

District II
B11 S. First Street, Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720

District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170

District IV
1220 S. St. Francis Drive, Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

OIL CONSERVATION DIVISION

1220 South St. Francis Drive
Santa Fe, NM 87505

Submit one copy to
Appropriate District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

*API Number 30-045-35718		*Pool Code 98143	*Pool Name ALAMITO MANCOS W
*Property Code 315082	*Property Name W ALAMITO UNIT		*Well Number 465H
*OGRID No. 120782	*Operator Name WPX ENERGY PRODUCTION, LLC		*Elevation 6803'

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
H	12	22N	8W		2089	NORTH	1086	EAST	SAN JUAN

¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
0	13	22N	8W		330	SOUTH	1800	EAST	SAN JUAN

¹² Dedicated Acres	W/2 SE/4 - Section 12 240.00 W/2 E/2 - Section 13	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No. R-14002 / 1,922.40 Acres
-------------------------------	--	-------------------------------	----------------------------------	---

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

SURFACE LOCATION
2089' FNL 1086' FEL
SECTION 12, T22N, RBW
LAT: 36.155694°N
LONG: 107.627696°W
DATUM: NAD1927


LAT: 36.155708 °N
LONG: 107.628305 °W
DATUM: NAD1983

POINT-OF-ENTRY
2302' FSL 1800' FEL
SECTION 12, T22N, R8W
LAT: 36.153229°N
LONG: 107.630137°W
DATUM: NAD1927

LAT: 36.153243 °N
LONG: 107.630746 °W
DATUM: NAD1983

END-OF-LATERAL
330' FSL 1800' FEL
SECTION 13, T22N, R8W
LAT: 36.133333° N
LONG: 107.630174° W
DATUM: NAD1927

LAT: 36.133348°N
LONG: 107.630783°W
DATUM: NAD1983



17 OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom-hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Signature [Signature] Date 9/28/2015

Andrea Felix
Printed Name
andrea.felix@wpxenergy.com
E-mail Address

¹⁸ SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

Date Revised: SEPTEMBER 23, 2015
Date of Survey: JUNE 16, 2015

Signature and Seal of Professional Surveyor



JASON C. EDWARDS
Certificate Number 15269



WPX Energy

Operations Plan

(Note: This procedure will be adjusted onsite based upon actual conditions)

DATE: September 15, 2015
WELL NAME: W Alamito UT #465H
SH Location: SENE Sec 12-22N-08W
BH Location: SWSE Sec 13-22N-08W

FIELD: Alamito Mancos W
SURFACE: Federal
ELEVATION: 6803' GR
MINERALS: Indian Allotted

MEASURED DEPTH: 13,014.82

I. GEOLOGY: SURFACE FORMATION - NACIMIENTO

A. FORMATION TOPS (KB)

NAME	MD	TVD	NAME	MD	TVD
OJO ALAMO	506	506	POINT LOOKOUT	3519	3465
KIRTLAND	673	673	MANCOS	3714	3656
PICTURED CLIFFS	1075	1071	GALLUP	4027	3962
LEWIS	1175	1169	KICKOFF POINT	4,067.90	4,002.42
CHACRA	1477	1465	TOP TARGET	5068	4723
CLIFF HOUSE	2584	2549	LANDING POINT	5303	4741
MENEFEE	2641	2605	BASE TARGET	5303	4741
			TD	13,014.82	4,597.00

B. MUD LOGGING PROGRAM: Mudlogger on location from surface csg to TD.

C. LOGGING PROGRAM: LWD GR from surface casing to TD.

D. NATURAL GAUGES: Gauge any noticeable increases in gas flow. Record all gauges in Tour book and on morning reports.

II. DRILLING

A. **MUD PROGRAM:** LSND mud (WBM) will be used to drill the 12-1/4" Surface hole, the 8 3/4" Directional Vertical hole, and the curve portion of the wellbore. A LSND (WBM) or (OBM) will be used to drill the lateral portion of well. Treat for lost circulation as necessary. Obtain 100% returns prior to cementing. Notify Engineering of any mud losses.

B. **BOP TESTING:** While drill pipe is in use, the pipe rams and the blind rams will be function tested once each trip. The anticipated reservoir is expected to be less than 1300 psi, so the BOPE will be tested to **250 psi (Low) for 5 minutes and 1500 psi (High) for 10 minutes**. Pressure test surface casing to **600 psi for 30 minutes** and intermediate casing to **1500 psi for 30 minutes**. Utilize a BOPE Testing Unit with a recording chart and appropriate test plug for testing. The drum brakes will be inspected and tested each tour. **All tests and inspections will be recorded in the tour book as to time and results.**

III. MATERIALS

A. CASING PROGRAM:

CASING TYPE	OH SIZE (IN)	DEPTH (MD)	CSG SIZE	WEIGHT	GRADE
SURFACE	12.25"	365'	9.625"	36 LBS	J-55
INTERMEDIATE	8.75"	5,213.34	7"	26 LBS	J-55
PRODUCTION	6.125"	13,014.82	4.5"	11.6 LBS	P-110
TIE BACK	6.125		4.5"	11.6 LBS	P-110

B. FLOAT EQUIPMENT:

1. SURFACE CASING: 9-5/8" notched regular pattern guide shoe. Run (1) standard centralizer on each of the bottom (4) joints of Surface Casing.
2. INTERMEDIATE CASING: 7" cement nose guide shoe with a self-fill insert float. Place float collar one joint above the shoe. Install (1) centralizer on each of the bottom (3) joints and one standard centralizer every (3) joints to 2,500 ft. Run (1) centralizer at 2,700 ft., 2,500 ft., 2,300ft., 2,000ft., 1,500 ft., and 1,000 ft.
3. PRODUCTION LINER: Run 4-1/2" Liner with cement nose guide Float Shoe + 2jts. of 4-1/2" casing + Landing Collar + 4-1/2" pup joint + 1 RSI (Sliding Sleeve) positioned inside the 330ft Hard line. Centralizer program will be determined by Wellbore condition and when Lateral is evaluated by Geoscientists and Reservoir Engineers. Set seals on Liner Hanger. Test TOL to 1500 psi for 15 minutes.

C. CEMENTING:

(Note: Volumes may be adjusted onsite due to actual conditions)

1. Surface 5 bbl Fresh Water Spacer, 100 sx (160 cu.ft.) of 14.5 ppg Type I-II (Neat G) + 20% Fly Ash cement w/ 7.41 gal/sack mix water ratio @ 1.61 cu ft/sx yield. Calculated @ volume + 50% excess. WOC 12 hours. Test csg to 600psi. Total Volume: (160 cu-ft/100 sx/ Bbls). TOC at Surface.
2. Intermediate 20 bbl (112 cu-ft) Mud Flush III spacer + Lead: +/- 700 sx Foamed 50/50 Poz Cement. 13.1 ppg + 0.1% Halad 766 + 0.2% Versaset + 1.5% Chem-Foamer 760 (Yield :1.43 cu-ft/ sk. / Vol: 1001 cu-ft / 178.3 Bbls.) + TAIL: 100 sx 13.5 #/gal. + 0.2% Versaset + 0.15% HALAD-766 (Yield: 1.28 cu-ft / sk / Vol: 128 cu-ft / 22.8 Bbls.). + Fresh Water Displacement (1,362 cu-ft / +/- 242 Bbls) + 100 sx Top-Out Cement Premium: Yield: (1.17 cu-ft/ sk / (Vol: 117 cu-ft / 20.8 Bbls). WOC 12 hrs. Test Casing to 1500 PSI for 30 minutes. Total Cement Volume: (900 sx / 1246 cu-ft / 222 bbls). Mix with +/- 84,000 SCF Nitrogen. TOC at surface.
3. PROD. LINER: Spacer #1:10 bbl (56.cu-ft) Water Spacer. Spacer #2: 40 bbl 9.5 ppg (224.6 cu-ft) Tuned Spacer III. Spacer #3: 10 bbl Water Spacer. Lead Cement: Extencem™ System. Yield 1.36 cuft/sk 13.3 ppg (745 sx /1014 cuft /181 bbls). Tail Spacer: 20 BBL of MMCR. Displacement: Displace w/ +/- 140 bbl Fr Water. Total Cement (745 sx /1014bbls).

I. COMPLETION

A. CBL

Run CCL for perforating

B. PRESSURE TEST

1. Pressure test 4-1/2" casing to 4500 psi max, hold at 1500 psi for 30 minutes. Increase pressure to Open RSI sleeves.

C. STIMULATION

1. Stimulate with approximately 2,805,000# 20/40 mesh sand and 340,000# 16/30 mesh sand in 619,113 gallons water with 42,696 mscf N₂ for 17 stages.
2. Isolate stages with flow through frac plug.
3. Drill out frac plugs and flowback lateral.

D. RUNNING TUBING

1. Production Tubing: Run 2-7/8", 6.5#, J-55, EUE tubing with a SN on top of bottom joint. Land tubing near Top of Liner.

- Although this horizontal well will be drilled past the applicable setbacks, an unorthodox location application is not required because the completed interval in this well, as defined by 19.15.16.7 B(1) NMAC, will be entirely within the applicable setbacks. This approach complies with all applicable rules, including 19.15.16.14 A(3) NMAC, 19.15.16.14 B(2) NMAC, 19.15.16.15 B(2) NMAC, and 19.15.16.15 B(4) NMAC.

NOTE:

Proposed Operations:

A 4-1/2" 11.6# N-80 Liner will be run to TD and landed +/- 150 ft. into the 7" 23# K-55 Intermediate casing with a Liner Hanger and pack-off assembly then cemented to top of liner hanger.

After cementing and TOL clean up operations are complete, the TOL will be tested to 1500 psi (per BLM).

No Tie back string will be ran in this well. All stimulation will be performed down the 7" casing.



WPX Energy

T22N R8W

W Alamito UT 12 H

W Alamito UT #465H - Slot A2

Wellbore #1

Plan: Design #1 1Sept15 sam

Standard Planning Report

01 September, 2015

WPX

Planning Report

Database: San Juan
Company: WPX Energy
Project: T22N R8W
Site: W Alamito UT 12 H
Well: W Alamito UT #465H
Wellbore: Wellbore #1
Design: Design #1 1Sept15 sam

Local Co-ordinate Reference: Well W Alamito UT #465H (A2) - Slot A2
TVD Reference: KB @ 6817.00usft (Aztec 920)
MD Reference: KB @ 6817.00usft (Aztec 920)
North Reference: True
Survey Calculation Method: Minimum Curvature

Project

Map System: US State Plane 1927 (Exact solution) **System Datum:** Mean Sea Level
Geo Datum: NAD 1927 (NADCON CONUS)
Map Zone: New Mexico West 3003

Site

Site Position: Northing: 1,875,976.76 usft Latitude: 36.1556910
From: Lat/Long Easting: 560,746.79 usft Longitude: -107.6275600
Position Uncertainty: 0.00 usft Slot Radius: 13.20 in Grid Convergence: 0.12 "

Well

Well Position **+N/-S** 1.09 usft **Northing:** 1,875,977.76 usft **Latitude:** 36.1556940
 +E/-W -40.15 usft **Easting:** 560,706.63 usft **Longitude:** -107.6276960
Position Uncertainty 0.00 usft **Wellhead Elevation:** 0.00 usft **Ground Level:** 6,803.00 usft

Wellbore

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	9/1/2015	9.25	62.89	49,999

Design

Audit Notes:
Version: **Phase:** PLAN **Tie On Depth:** 0.00
Vertical Section: **Depth From (TVD) (usft)** **+N/-S (usft)** **+E/-W (usft)** **Direction (°)**
 0.00 0.00 0.00 185.05

Plan Sections

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,082.41	11.65	302.81	1,078.41	31.97	-49.59	2.00	2.00	0.00	302.81	
4,067.90	11.65	302.81	4,002.42	358.59	-556.21	0.00	0.00	0.00	0.00	
4,808.60	60.00	180.46	4,621.81	41.82	-630.18	9.00	6.53	-16.52	-127.17	Start 60 tan #465H
4,868.60	60.00	180.46	4,651.81	-10.14	-630.60	0.00	0.00	0.00	0.00	End 60 tan #465H
5,013.41	73.04	180.36	4,709.38	-142.67	-631.54	9.01	9.00	-0.07	-0.45	
5,213.34	91.03	180.64	4,737.00	-339.85	-633.26	9.00	9.00	0.14	0.90	POE #465H
13,014.82	91.03	180.64	4,597.00	-8,139.59	-719.81	0.00	0.00	0.00	0.00	BHL #465H

WPX
Planning Report

Database: San Juan
Company: WPX Energy
Project: T22N R8W
Site: W Alamito UT 12 H
Well: W Alamito UT #465H
Wellbore: Wellbore #1
Design: Design #1 1Sept15 sam

Local Co-ordinate Reference: Well W Alamito UT #465H (A2) - Slot A2
TVD Reference: KB @ 6817.00usft (Aztec 920)
MD Reference: KB @ 6817.00usft (Aztec 920)
North Reference: True
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
320.00	0.00	0.00	320.00	0.00	0.00	0.00	0.00	0.00	0.00
9 5/8"									
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 2.00									
1,000.00	10.00	302.81	997.47	23.58	-36.58	-20.27	2.00	2.00	0.00
1,082.41	11.65	302.81	1,078.41	31.97	-49.59	-27.48	2.00	2.00	0.00
Hold 11.65 Inclination									
1,500.00	11.65	302.81	1,487.40	77.65	-120.45	-66.74	0.00	0.00	0.00
2,000.00	11.65	302.81	1,977.10	132.36	-205.30	-113.76	0.00	0.00	0.00
2,500.00	11.65	302.81	2,466.80	187.06	-290.14	-160.77	0.00	0.00	0.00
3,000.00	11.65	302.81	2,956.50	241.76	-374.99	-207.79	0.00	0.00	0.00
3,500.00	11.65	302.81	3,446.21	296.46	-459.84	-254.80	0.00	0.00	0.00
4,000.00	11.65	302.81	3,935.91	351.16	-544.68	-301.82	0.00	0.00	0.00
4,067.90	11.65	302.81	4,002.42	358.59	-556.21	-308.20	0.00	0.00	0.00
Start Build DLS 9.00 TFO -127.17									
4,500.00	32.97	189.61	4,411.07	262.58	-614.77	-207.40	9.00	4.94	-26.20
4,808.60	60.00	180.46	4,621.81	41.82	-630.18	13.85	9.00	8.76	-2.97
Hold 60.00 Inclination									
4,868.60	60.00	180.46	4,651.81	-10.14	-630.60	65.65	0.00	0.00	0.00
Start Build DLS 9.01 TFO -0.45									
5,000.00	71.83	180.37	4,705.34	-129.89	-631.46	185.01	9.01	9.00	-0.07
5,013.41	73.04	180.36	4,709.38	-142.67	-631.54	197.75	9.01	9.01	-0.07
Start DLS 9.00 TFO 0.90									
5,213.00	91.00	180.64	4,736.98	-339.51	-633.26	393.98	9.00	9.00	0.14
7"									
5,213.34	91.03	180.64	4,737.00	-339.85	-633.26	394.31	9.00	9.00	0.14
POE at 91.03 Inc 180.64 deg									
5,500.00	91.03	180.64	4,731.86	-626.44	-636.44	680.07	0.00	0.00	0.00
6,000.00	91.03	180.64	4,722.88	-1,126.33	-641.99	1,178.51	0.00	0.00	0.00
6,500.00	91.03	180.64	4,713.91	-1,626.22	-647.53	1,676.94	0.00	0.00	0.00
7,000.00	91.03	180.64	4,704.94	-2,126.11	-653.08	2,175.37	0.00	0.00	0.00
7,500.00	91.03	180.64	4,695.97	-2,626.00	-658.63	2,673.81	0.00	0.00	0.00
8,000.00	91.03	180.64	4,686.99	-3,125.89	-664.18	3,172.24	0.00	0.00	0.00
8,500.00	91.03	180.64	4,678.02	-3,625.78	-669.72	3,670.68	0.00	0.00	0.00
9,000.00	91.03	180.64	4,669.05	-4,125.67	-675.27	4,169.11	0.00	0.00	0.00
9,500.00	91.03	180.64	4,660.07	-4,625.55	-680.82	4,667.54	0.00	0.00	0.00
10,000.00	91.03	180.64	4,651.10	-5,125.44	-686.36	5,165.98	0.00	0.00	0.00
10,500.00	91.03	180.64	4,642.13	-5,625.33	-691.91	5,664.41	0.00	0.00	0.00
11,000.00	91.03	180.64	4,633.16	-6,125.22	-697.46	6,162.85	0.00	0.00	0.00
11,500.00	91.03	180.64	4,624.18	-6,625.11	-703.00	6,661.28	0.00	0.00	0.00
12,000.00	91.03	180.64	4,615.21	-7,125.00	-708.55	7,159.72	0.00	0.00	0.00
12,500.00	91.03	180.64	4,606.24	-7,624.89	-714.10	7,658.15	0.00	0.00	0.00
13,000.00	91.03	180.64	4,597.27	-8,124.77	-719.64	8,156.58	0.00	0.00	0.00
13,014.82	91.03	180.64	4,597.00	-8,139.59	-719.81	8,171.36	0.00	0.00	0.00
TD at 13014.82									

WPX
Planning Report

Database:	San Juan	Local Co-ordinate Reference:	Well W Alamito UT #465H (A2) - Slot A2
Company:	WPX Energy	TVD Reference:	KB @ 6817.00usft (Aztec 920)
Project:	T22N R8W	MD Reference:	KB @ 6817.00usft (Aztec 920)
Site:	W Alamito UT 12 H	North Reference:	True
Well:	W Alamito UT #465H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1 1Sept15 sam		


Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
BHL #465H - plan hits target center - Point	0.00	0.00	4,597.00	-8,139.59	-719.81	1,867,836.66	560,004.06	36.1333330	-107.6301336
Start 60 tan #465H - plan hits target center - Point	0.00	0.00	4,621.81	41.82	-630.18	1,876,018.25	560,076.37	36.1558088	-107.6298307
End 60 tan #465H - plan misses target center by 1.00usft at 4868.59usft MD (4651.81 TVD, -10.13 N, -630.60 E) - Point	0.00	0.00	4,651.81	-10.14	-629.60	1,875,966.29	560,077.06	36.1556661	-107.6298287
POE #465H - plan hits target center - Point	0.00	0.00	4,737.00	-339.85	-633.26	1,875,636.57	560,074.09	36.1547603	-107.6298411

Casing Points					
Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (in)	Hole Diameter (in)	
320.00	320.00	9 5/8"	9.62	12.25	
5,213.00	4,736.98	7"	7.00	8.75	

Plan Annotations				
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
500.00	500.00	0.00	0.00	Start Build 2.00
1,082.41	1,078.41	31.97	-49.59	Hold 11.65 Inclination
4,067.90	4,002.42	358.59	-556.21	Start Build DLS 9.00 TFO -127.17
4,808.60	4,621.81	41.82	-630.18	Hold 60.00 Inclination
4,868.60	4,651.81	-10.14	-630.60	Start Build DLS 9.01 TFO -0.45
5,013.41	4,709.38	-142.67	-631.54	Start DLS 9.00 TFO 0.90
5,213.34	4,737.00	-339.85	-633.26	POE at 91.03 Inc 180.64 deg
13,014.82	4,597.00	-8,139.59	-719.81	TD at 13014.82



Well Name: W Alamito UT #465H
 Surface Location: W Alamito UT 12 H
 NAD 1927 (NADCON CONUS) , US State Plane 1927 (Exact solution) New Mexico West 3003
 Ground Elevation: 6803.00
 +N/-S +E/-W Northing Easting Latitude Longitude Slot
 0.00 0.00 1875977.76 560706.63 36.1556940 -107.6276960 A2
 KB @ 6817.00usft (Aztec 920)



DESIGN TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Shape
BHL #465H	4597.00	-8139.59	-719.81	1867836.66	560004.06	36.1333330	-107.6301336	Point
Start 60 tan #465H	- plan hits target center	4621.81	41.82	-630.18	1876018.25	560076.36	36.1558089	-107.6298307 Point
End 60 tan #465H	- plan hits target center	4651.81	-10.14	-629.60	1875966.29	560077.05	36.1556661	-107.6298287 Point
POE #465H	- plan misses target center by 1.00usft at 4868.59usft MD (4651.81 TVD, -10.13 N, -630.80 E)	4737.00	-339.85	-633.26	1875636.57	560074.09	36.1547603	-107.6298411 Point




ANNOTATIONS

TVD	MD	Inc	Azi	+N/-S	+E/-W	Vsect	Departure	Annotation
500.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00	Start Build 2.00
1078.41	1082.41	11.65	302.81	31.97	-49.59	-27.48	59.00	Hold 11.65 Inclination
4002.42	4067.90	11.65	302.81	358.59	-556.21	-308.20	661.78	Start Build DLS 9.00 TFO -127.17
4621.81	4808.60	60.00	180.46	41.82	-630.18	13.85	1082.56	Hold 60.00 Inclination
4651.81	4868.60	60.00	180.46	-10.14	-630.60	65.65	1134.52	Start Build DLS 9.01 TFO -0.45
4709.38	5013.41	73.04	180.36	-142.67	-631.54	197.75	1267.05	Start DLS 9.00 TFO 0.90
4737.00	5213.34	91.03	180.64	-339.85	-633.26	394.31	1464.24	POE at 91.03 Inc 180.64 deg
4597.00	13014.82	91.03	180.64	-8139.59	-719.81	8171.36	9264.47	TD at 13014.82

Project: T22N R8W
 Site: W Alamito UT 12 H
 Well: W Alamito UT #465H
 Wellbore: Wellbore #1
 Design: Design #1 1Sept15 sam

SLOTS

Slot Name	+N/-S	+E/-W	Northing	Easting
A1	-1.09	40.15	1875976.76	560746.78
A2	0.00	0.00	1875977.76	560706.63



driving surface; the tear drop would be used to access the proposed wellheads and other facilities.

2. As practical, access will be a teardrop-shaped road through the production areas so that the center may be revegetated.
3. Within 90 days of installation, production facilities would be painted Juniper Green to blend with the natural color of the landscape and would be located, to the extent practical, to reasonably minimize visual impact.
4. Berms will be constructed around all storage facilities sufficient in size to contain the storage capacity of tanks. Berm walls will be compacted with appropriate equipment to assure containment.

After the completion phases and pipeline installation, portions of the project areas not needed for operation will be reclaimed. When the wells are plugged, final reclamation will occur within the remainder of the project areas. Reclamation is described in detail in the Reclamation Plan (Appendix A).

7.0 Methods for Handling Waste

A. Cuttings

1. Drilling operations will utilize a closed-loop system. Drilling of the horizontal laterals will be accomplished with water-based mud. All cuttings will be placed in roll-off bins and hauled to a commercial disposal facility or land farm. WPX will follow Onshore Oil and Gas Order No. 1 regarding the placement, operation, and removal of closed-loop systems. No blow pit will be used.
2. Closed-loop tanks will be adequately sized for containment of all fluids.

B. Drilling Fluids

1. Drilling fluids will be stored onsite in above-ground storage tanks. Upon termination of drilling operations, the drilling fluids will be recycled and transferred to other permitted closed-loop systems or returned to the vendor for reuse, as practical. All residual fluids will be hauled to a commercial disposal facility.

C. Spills

1. Any spills of non-freshwater fluids will be immediately cleaned up and removed to an approved disposal site.

D. Sewage

1. Portable toilets will be provided and maintained during construction, as needed (see Figure 4 in Appendix B for the location of toilets).

E. Garbage and other water material

1. All garbage and trash will be placed in a metal trash basket. The trash and garbage will be hauled off site and dumped in an approved landfill, as needed.

F. Hazardous Waste

1. No chemicals subject to reporting under Superfund Amendments and Reauthorization Act Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of these wells.
2. No extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of these wells.

Directions from the Intersection of US Hwy 550 & US Hwy 64

in Bloomfield, NM to WPX Energy Production, LLC W Alamito UT #465H

2089' FNL & 1086' FEL, Section 12, T22N, R8W, N.M.P.M., San Juan County, NM

Latitude: 36.155708°N Longitude: 107.628305°W Datum: NAD1983

From the intersection of US Hwy 550 & US Hwy 64 in Bloomfield, NM, travel Southerly on US Hwy 550 for 38.7 miles to Mile Marker 112.7:

Go Right (Southerly) on County Road #7900 for 4.9 miles to fork in road;

Go Straight (South-easterly) remaining on County Road #7900 for 0.2 miles to fork in road:

Go Left (Easterly) exiting County Road #7900 for 2.8 miles to new access on right-hand side of existing roadway which continues for 7715.7' to staked WPX W Alamito UT #465H location.

